

Copyrighted Material

Fourth Edition
Volume Six

Editor-in-Chief

Peter C. Neligan

Plastic Surgery

Hand and Upper Extremity

Volume Editor

James Chang

<https://t.me/MedicalBooksStore>

ELSEVIER

Copyrighted Material

Fourth Edition

Plastic Surgery

Hand and Upper Extremity

Volume Six

Content Strategist: Belinda Kuhn

Content Development Specialists: Louise Cook, Sam Crowe, Alexandra Mortimer

e-products, Content Development Specialist: Kim Benson

Project Managers: Anne Collett, Andrew Riley, Julie Taylor

Designer: Miles Hitchen


Illustration Managers: Karen Giacomucci, Amy Faith Heyden

Marketing Manager: Melissa Fogarty

Video Liaison: Will Schmitt

Fourth Edition

Plastic Surgery



Hand and Upper Extremity

Volume Six

Volume Editor

James Chang

MD

Johnson & Johnson Distinguished

Professor and Chief

Division of Plastic and Reconstructive Surgery

Stanford University Medical Center

Stanford, CA, USA

Editor-in-Chief

Peter C. Neligan

MB, FRCS(I), FRCS(C), FACS

Professor of Surgery

Department of Surgery, Division of Plastic Surgery

University of Washington

Seattle, WA, USA

Multimedia Editor

Daniel Z. Liu

MD

Plastic and Reconstructive Surgeon

Cancer Treatment Centers of America at

Midwestern Regional Medical Center

Zion, IL, USA

For additional online figures, videos and video lectures visit Expertconsult.com

ELSEVIER

© 2018, Elsevier Inc. All rights reserved.

First edition 1990

Second edition 2006

Third edition 2013

Fourth edition 2018

No part of this publication may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or any information storage and retrieval system, without permission in writing from the publisher. Details on how to seek permission, further information about the Publisher's permissions policies and our arrangements with organizations such as the Copyright Clearance Center and the Copyright Licensing Agency, can be found at our website: www.elsevier.com/permissions.

This book and the individual contributions contained in it are protected under copyright by the Publisher (other than as may be noted herein).

All photographs in Volume 6, Chapter 6 The fingertip, nail plate, and nail bed: Anatomy, repair, and reconstruction ©Southern Illinois University School of Medicine.

James Chang and Anais LeGrande retain copyright for their original photographs.

Notices

Knowledge and best practice in this field are constantly changing. As new research and experience broaden our understanding, changes in research methods, professional practices, or medical treatment may become necessary.

Practitioners and researchers must always rely on their own experience and knowledge in evaluating and using any information, methods, compounds, or experiments described herein. In using such information or methods they should be mindful of their own safety and the safety of others, including parties for whom they have a professional responsibility.

With respect to any drug or pharmaceutical products identified, readers are advised to check the most current information provided (i) on procedures featured or (ii) by the manufacturer of each product to be administered, to verify the recommended dose or formula, the method and duration of administration, and contraindications. It is the responsibility of practitioners, relying on their own experience and knowledge of their patients, to make diagnoses, to determine dosages and the best treatment for each individual patient, and to take all appropriate safety precautions.

To the fullest extent of the law, neither the Publisher nor the authors, contributors, or editors, assume any liability for any injury and/or damage to persons or property as a matter of products liability, negligence or otherwise, or from any use or operation of any methods, products, instructions, or ideas contained in the material herein.

Volume 6 ISBN: 978-0-323-35712-8

Volume 6 Ebook ISBN: 978-0-323-35713-5

6 volume set ISBN: 978-0-323-35630-5

ELSEVIER

your source for books,
journals and multimedia
in the health sciences

www.elsevierhealth.com



Working together
to grow libraries in
developing countries

www.elsevier.com • www.bookaid.org

The
publisher's
policy is to use
paper manufactured
from sustainable forests

Printed in Canada

Last digit is the print number: 9 8 7 6 5 4 3 2 1

Video Contents



Volume One:

Chapter 15: Skin graft

15.1: Harvesting a split-thickness skin graft

Dennis P. Orgill

Chapter 34: Robotics in plastic surgery

34.1: Robotic microsurgery

34.2: Robotic rectus abdominis muscle flap harvest

34.3: Trans-oral robotic surgery

34.4: Robotic latissimus dorsi muscle harvest

34.5: Robotic lymphovenous bypass

Jesse C. Selber

Volume Two:

Chapter 6.2: Facelift: Principles of and surgical approaches to facelift

6.2.1: Parotid masseteric fascia

6.2.2: Anterior incision

6.2.3: Posterior incision

6.2.4: Facelift skin flap

6.2.5: Facial fat injection

Richard J. Warren

6.2.6: Anthropometry, cephalometry, and orthognathic surgery

Jonathon S. Jacobs, Jordan M. S. Jacobs, and Daniel I. Taub

Chapter 6.3: Facelift: Platysma-SMAS plication

6.3.1: Platysma-SMAS plication

Dai M. Davies and Miles G. Berry

Chapter 6.4: Facelift: Facial rejuvenation with loop sutures – the MACS lift and its derivatives

6.4.1: Loop sutures MACS facelift

Patrick L. Tonnard

From Aston SJ, Steinbrech DS, Walden JL, eds. Aesthetic Plastic Surgery, Saunders Elsevier; 2009; with permission from Elsevier

Chapter 6.7: Facelift: SMAS with skin attached – the “high SMAS” technique

6.7.1: The high SMAS technique with septal reset

Fritz E. Barton Jr.

© Fritz E. Barton Jr.

Chapter 6.8: Facelift: Subperiosteal midface lift

6.8.1: Subperiosteal midface lift: Endoscopic temporo-midface

Oscar M. Ramirez

Chapter 9: Blepharoplasty

9.1: Periorbital rejuvenation

Julius Few Jr. and Marco Ellis

© Julius Few Jr.

Chapter 11: Asian facial cosmetic surgery

11.1: Medial epicanthoplasty

11.2: Eyelidplasty: Non-incisional method

11.3: Rhinoplasty

11.4: Subclinical ptosis correction (total)

11.5: Secondary rhinoplasty: Septal extension graft and costal cartilage strut fixed with K-wire

Kyung S. Koh, Jong Woo Choi, and Clyde H. Ishii

Chapter 12: Neck rejuvenation

12.1: Anterior lipectomy

James E. Zins, Colin M. Morrison, and C. J. Langevin

Chapter 13: Structural fat grafting

13.1: Structural fat grafting of the face

Sydney R. Coleman and Alesia P. Saboeiro

Chapter 14: Skeletal augmentation

14.1: Chin implant

Michael J. Yarumchuk

© Mesa J, Havlik R, Mackay D, Buchman S, Losee J, eds. *Atlas of Operative Craniofacial Surgery*, CRC Press, 2019.

14.2: Mandibular angle implant

14.3: Midface skeletal augmentation and rejuvenation

Michael J. Yarumchuk

© Michael J. Yaremchuk

Chapter 16: Open technique rhinoplasty

16.1: Open technique rhinoplasty

Allen L. Van Beek

Chapter 20: Otoplasty and ear reduction

20.1: Setback otoplasty

Leila Kasrai

Chapter 23: Abdominoplasty procedures

23.1: Abdominoplasty

Dirk F. Richter and Alexander Stoff

Chapter 24: Lipoabdominoplasty

24.1: Lipoabdominoplasty (including secondary lipo)

Oswaldo Saldanha, Sérgio Fernando Dantas de Azevedo, Oswaldo Ribeiro Saldanha Filho, Cristianna Bonnetto Saldanha, and Luis Humberto Uribe Morelli

Chapter 26.2: Buttock augmentation: Buttock augmentation with implants

26.2.1: Buttock augmentation

Terrence W. Bruner, Jose Abel De la Peña Salcedo, Constantino G. Mendieta, and Thomas L. Roberts III

Chapter 27: Upper limb contouring

27.1: Brachioplasty

27.2: Upper limb contouring

Joseph F. Capella, Matthew J. Trovato, and Scott Woehrl

Chapter 28: Post-bariatric reconstruction

28.1: Post-bariatric reconstruction – bodylift procedure

J. Peter Rubin and Jonathan W. Toy

© J. Peter Rubin

Volume Three:

Chapter 6: Aesthetic nasal reconstruction

6.1: The three-stage folded forehead flap for cover and lining

6.2: First-stage transfer and intermediate operation

Frederick J. Menick

Chapter 7: Auricular construction

7.1: Total auricular construction

Akira Yamada

Chapter 8: Acquired cranial and facial bone deformities

8.1: Removal of venous malformation enveloping intraconal optic nerve

Renee M. Burke, Robert J. Morin, and S. Anthony Wolfe

Chapter 13: Facial paralysis

13.1: Facial paralysis

Eyal Gur

13.2: Facial paralysis

13.3: Cross facial nerve graft

13.4: Gracilis harvest

Peter C. Neligan

Chapter 14: Pharyngeal and esophageal reconstruction

14.1: Reconstruction of pharyngoesophageal defects with the anterolateral thigh flap

Peirong Yu

Chapter 15: Tumors of the facial skeleton: Fibrous dysplasia

15.1: Surgical approaches to the facial skeleton

Yu-Ray Chen, You-Wei Cheong, and Alberto Córdova-Aguilar

Chapter 17: Local flaps for facial coverage

17.1: Facial artery perforator flap

17.2: Local flaps for facial coverage

Peter C. Neligan

Chapter 21.2: Rotation advancement cheiloplasty

21.2.1: Repair of unilateral cleft lip

Philip Kuo-Ting Chen, M. Samuel Noordhoff, Frank Chun-Shin, Chang, and Fuan Chiang Chan

21.2.2: Unilateral cleft lip repair – anatomic subunit approximation technique

David M. Fisher

Chapter 24: Alveolar clefts

24.1: Unilateral cleft alveolar bone graft

24.2: Mobilized premaxilla after vomer osteotomy prior to setback and splint application

Richard A. Hopper and Gerhard S. Munding

Chapter 26: Velopharyngeal dysfunction

26.1: Velopharyngeal incompetence – 1

26.2: Velopharyngeal incompetence – 2

26.3: Velopharyngeal incompetence – 3

Richard E. Kirschner and Adriane L. Baylis

Chapter 27: Secondary deformities of the cleft lip, nose, and palate

27.1: Abbé flap

27.2: Alveolar bone grafting

27.3: Complete takedown

27.4: Definitive rhinoplasty

Evan M. Feldman, John C. Koshy, Larry H. Hollier Jr., and Samuel Stal

27.5: Thick lip and buccal sulcus deformities

Evan M. Feldman and John C. Koshy

Chapter 36: Pierre Robin Sequence

36.1: Mandibular distraction

Arun K. Gosain and Chad A. Purnell

Chapter 39: Vascular anomalies

39.1: Lip hemangioma

Arin K. Greene

Chapter 43: Reconstruction of urogenital defects: Congenital

43.1: First-stage hypospadias repair with free inner preputial graft

43.2: Second-stage hypospadias repair with tunica vaginalis flap

Mohan S. Gundeti and Michael C. Large

Volume Four:

Chapter 2: Management of lower extremity trauma

2.1: Anterolateral thigh flap harvest

Michel Saint-Cyr

Chapter 3: Lymphatic reconstruction of the extremities

3.1: End-to-side lymphovenous bypass technique

© Cheng M-H, Chang D, Patel K. *Principles and Practice of Lymphedema Surgery*, Elsevier; 2015.

3.2: Recipient site preparation for vascularized lymph node transfer – axilla

© Cheng M-H, Chang D, Patel K. *Principles and Practice of Lymphedema Surgery*, Elsevier; 2015.

3.3: Indocyanine green lymphography

David W. Chang

3.4: Charles procedure

Peter C. Neligan

Chapter 6: Diagnosis and treatment of painful neuroma and nerve compression in the lower extremity

6.1: Diagnosis and treatment of painful neuroma and of nerve compression in the lower extremity 1

6.2: Diagnosis and treatment of painful neuroma and of nerve compression in the lower extremity 2

6.3: Diagnosis and treatment of painful neuroma and of nerve compression in the lower extremity 3

A. Lee Dellon

Chapter 7: Skeletal reconstruction

7.1: Medial femoral condyle/medial geniculate artery osteocutaneous free flap dissection for scaphoid nonunion

Stephen J. Kovach III and L. Scott Levin

Chapter 10: Reconstruction of the chest

10.1: Sternal rigid fixation

David H. Song and Michelle C. Roughton

Chapter 12: Abdominal wall reconstruction

12.1: Component separation innovation

Peter C. Neligan

Chapter 13: Reconstruction of male genital defects

13.1: Complete and partial penile reconstruction

Stan Monstrey, Peter Ceulemans, Nathalie Roche, Philippe Houtmeyers, Nicolas Lumen, and Piet Hoebeke

Volume Five:

Chapter 6: Mastopexy options and techniques

6.1: Circumareolar mastopexy

Kenneth C. Shestak

Chapter 7: One- and two-stage considerations for augmentation mastopexy

7.1: Preoperative markings for a single-stage augmentation mastopexy

W. Grant Stevens

Chapter 10: Reduction mammoplasty with short scar techniques

10.1: SPAIR technique

Dennis C. Hammond

Chapter 11: Gynecomastia surgery

11.1: Ultrasound-assisted liposuction

Charles M. Malata

Chapter 15: One- and two-stage prosthetic reconstruction in nipple-sparing mastectomy

15.1: Pectoralis muscle elevation

15.2: Acellular dermal matrix

15.3: Sizer

Amy S. Colwell

Chapter 16: Skin-sparing mastectomy: Planned two-stage and direct-to-implant breast reconstruction

16.1: Mastectomy and expander insertion: First stage

16.2: Mastectomy and expander insertion: Second stage

Maurizio B. Nava, Giuseppe Catanuto, Angela Pennati, Valentina Visintini Cividin, and Andrea Spano

Chapter 19: Latissimus dorsi flap breast reconstruction

19.1: Latissimus dorsi flap technique

Scott L. Spear[†]

19.2: Markings

19.3: Intraoperative skin paddles

19.4: Tendon division

19.5: Transposition and skin paddles

19.6: Inset and better skin paddle explanation

Neil A. Fine and Michael S. Gart

Chapter 20.2: The deep inferior epigastric artery perforator (DIEAP) flap

20.2.1: The Deep Inferior Epigastric Artery Perforator (DIEAP) flap breast reconstruction

Phillip N. Blondeel and Robert J. Allen, Sr

Chapter 21.2: Gluteal free flaps for breast reconstruction

21.2.1: Superior Gluteal Artery Perforator (SGAP) flap

21.2.2: Inferior Gluteal Artery Perforator (IGAP) flap

Peter C. Neligan

Chapter 21.3: Medial thigh flaps for breast reconstruction

21.3.1: Transverse Upper Gracilis (TUG) flap 1

Peter C. Neligan

21.3.2: Transverse Upper Gracilis (TUG) flap 2

Venkat V. Ramakrishnan

Chapter 23.2: Partial breast reconstruction using reduction and mastopexy techniques

23.2.1: Partial breast reconstruction using reduction mammoplasty

Maurice Y. Nahabedian

23.2.2: Partial breast reconstruction with a latissimus dorsi flap

Neil A. Fine

23.2.3: Partial breast reconstruction with a pedicle TRAM

Maurice Y. Nahabedian

Volume Six:

Chapter 1: Anatomy and biomechanics of the hand

1.1: The extensor tendon compartments

1.2: The contribution of the interosseous and lumbrical muscles to the lateral bands

1.3: Extrinsic flexors and surrounding vasculonervous elements, from superficial to deep

1.4: The lumbrical plus deformity

1.5: The sensory and motor branches of the median nerve in the hand

James Chang, Vincent R. Hentz, Robert A. Chase, and Anaïs Legrand

Chapter 2: Examination of the upper extremity

2.1: Flexor profundus test in a normal long finger

2.2: Flexor sublimis test in a normal long finger

2.3: Extensor pollicis longus test in a normal person

2.4: Test for the Extensor Digitorum Communis (EDC) muscle in a normal hand

2.5: Test for assessing thenar muscle function

2.6: The “cross fingers” sign

2.7: Static Two-Point Discrimination Test (s-2PD Test)

2.8: Moving 2PD Test (m-2PD Test) performed on the radial or ulnar aspect of the finger

2.9: Semmes–Weinstein monofilament test: The patient should sense the pressure produced by bending the filament

2.10: Allen's test in a normal person

2.11: Digital Allen's test

2.12: Scaphoid shift test

2.13: Dynamic tenodesis effect in a normal hand

2.14: The milking test of the fingers and thumb in a normal hand

2.15: Eichhoff test

2.16: Adson test

2.17: Roos test

Ryosuke Kakinoki

Chapter 3: Diagnostic imaging of the hand and wrist

3.1: Scaphoid lunate dislocation

Alphonsus K. Chong and David M. K. Tan

3.2: Right wrist positive midcarpal catch up clunk

Alphonsus K. Chong

Chapter 4: Anesthesia for upper extremity surgery

4.1: Supraclavicular block

Subhro K. Sen

Chapter 5: Principles of internal fixation as applied to the hand and wrist

5.1: Dynamic compression plating and lag screw technique

Christopher Cox

5.2: Headless compression screw

5.3: Locking vs. non-locking plates

Jeffrey Yao and Jason R. Kang

Chapter 7: Hand fractures and joint injuries

7.1: Bennett reduction

7.2: Hemi-Hamate arthroplasty

Warren C. Hammert

Chapter 9: Flexor tendon injury and reconstruction

9.1: Zone II flexor tendon repair

9.2: Incision and feed tendon forward

9.3: Distal tendon exposure

9.4: Six-strand M-tang repair

9.5: Extension–flexion test – wide awake

Jin Bo Tang

Chapter 10: Extensor tendon injuries

10.1: Sagittal band reconstruction

10.2: Setting the tension in extensor indicis transfer

Kai Megerle

Chapter 11: Replantation and revascularization

11.1: Hand replantation

James Chang

Chapter 12: Reconstructive surgery of the mutilated hand

12.1: Debridement technique

James Chang

Chapter 13: Thumb reconstruction: Non-microsurgical techniques

13.1: Osteoplastic thumb reconstruction

13.2: First Dorsal Metacarpal Artery (FDMA) flap

Jeffrey B. Friedrich

Chapter 14: Thumb reconstruction: Microsurgical techniques

14.1: Trimmed great toe

14.2: Second toe for index finger

14.3: Combined second and third toe for metacarpal hand

Nidal F. Al Deek

Chapter 19: Rheumatologic conditions of the hand and wrist

19.1: Extensor tendon rupture and end–side tendon transfer

James Chang

19.2: Silicone metacarpophalangeal arthroplasty

Kevin C. Chung and Evan Kowalski

Chapter 20: Osteoarthritis in the hand and wrist

20.1: Ligament reconstruction tendon interposition arthroplasty of the thumb carpometacarpal joint

James W. Fletcher

Chapter 21: The stiff hand and the spastic hand

21.1: Flexor pronator slide

David T. Netscher

Chapter 22: Ischemia of the hand

22.1: Radial artery sympathectomy

Hee Chang Ahn and Neil F. Jones

22.2: Interposition arterial graft and sympathectomy

Hee Chang Ahn

Chapter 24: Nerve entrapment syndromes

24.1: The manual muscle testing algorithm

24.2: Scratch collapse test – carpal tunnel

Elisabet Hagert

24.3: Injection technique for carpal tunnel surgery

24.4: Wide awake carpal tunnel surgery

Donald Lalonde

24.5: Clinical exam and surgical technique – lacertus syndrome

Elisabet Hagert

24.6: Injection technique for cubital tunnel surgery

24.7: Wide awake cubital tunnel surgery

Donald Lalonde

24.8: Clinical exam and surgical technique – radial tunnel syndrome

24.9: Clinical exam and surgical technique – lateral intermuscular syndrome

24.10: Clinical exam and surgical technique – axillary nerve entrapment

Elisabet Hagert

24.11: Carpal tunnel and cubital tunnel releases in the same patient in one procedure with field sterility: Part 1 – local anesthetic injection for carpal tunnel

24.12: Carpal tunnel and cubital tunnel releases in the same patient in one procedure with field sterility: Part 2 – local anesthetic injection for cubital tunnel

Donald Lalonde and Michael Bezuhyly

Chapter 25: Congenital hand I: Embryology, classification, and principles

25.1: Pediatric trigger thumb release

James Chang

Chapter 27: Congenital hand III: Thumb hypoplasia

27.1: Thumb hypoplasia*Joseph Upton III and Amir Taghinia*

Chapter 30: Growth considerations in pediatric upper extremity trauma and reconstruction

30.1: Epiphyseal transplant harvesting technique*Marco Innocenti and Carla Baldrighi*

Chapter 31: Vascular anomalies of the upper extremity

31.1: Excision of venous malformation*Joseph Upton III and Amir Taghinia*

Chapter 32: Peripheral nerve injuries of the upper extremity

32.1: Suture repair of the cut digital nerve**32.2: Suture repair of the median nerve***Simon Farnebo and Johan Thorfinn*

Chapter 35: Free-functioning muscle transfer in the upper extremity

35.1: Gracilis functional muscle harvest*Gregory H. Borschel*

Chapter 36: Brachial plexus injuries: Adult and pediatric

36.1: Pediatric: shoulder correct and biceps-to-triceps transfer with preserving intact brachialis**36.2: Adult: results of one-stage surgery for C5 rupture, C6–T1 root avulsion 10 years after****36.3: Nerve transfer results 1****36.4: Nerve transfer results 2****36.5: Nerve transfer results 3****36.6: Nerve transfer results 4****36.7: Nerve transfer results 5***David Chwei-Chin Chuang*

Chapter 37: Restoration of upper extremity function in tetraplegia

37.1: The single-stage grip and release procedure**37.2: Postoperative results after single-stage grip release procedure in OCu3–5 patients***Carina Reinholdt and Catherine Curtin*

Chapter 38: Upper extremity vascularized composite allotransplantation

38.1: Upper extremity composite tissue allotransplantation*W. P. Andrew Lee and Vijay S. Gorantla*

Chapter 39: Hand therapy

39.1: Goniometric measurement**39.2: Threshold testing***Christine B. Novak and Rebecca L. Neiduski*



Lecture Video Contents

Volume One:

Chapter 1: Plastic surgery and innovation in medicine

Plastic surgery and innovation in medicine

Peter C. Neligan

Chapter 7: Digital imaging in plastic surgery

Digital imaging in plastic surgery

Daniel Z. Liu

Chapter 15: Skin graft

Skin graft

Peter C. Neligan

Chapter 19: Repair and grafting of peripheral nerve

Nerve injury and repair

Kirsty Usher Boyd, Andrew Yee, and Susan E. Mackinnon

Chapter 20: Reconstructive fat grafting

Reconstructive fat grafting

J. Peter Rubin

Chapter 21: Vascular territories

Vascular territories

Steven F. Morris

Chapter 22: Flap classification and applications

Flap classification and applications

Joon Pio Hong

Chapter 23: Flap pathophysiology and pharmacology

Flap pathophysiology and pharmacology

Cho Y. Pang and Peter C. Neligan

Chapter 24: Principles and techniques of microvascular surgery

Principles and techniques of microvascular surgery

Fu-Chan Wei, Nidal F. Al Deek, and Sherilyn Keng Lin Tay

Chapter 25: Principles and applications of tissue expansion

Principles and applications of tissue expansion

Ivo Alexander Pestana, Louis C. Argenta, and Malcolm W. Marks

Chapter 26: Principles of radiation

Therapeutic radiation: principles, effects, and complications

Gabrielle M. Kane

Chapter 28: Benign and malignant nonmelanocytic tumors of the skin and soft tissue

Benign and malignant nonmelanocytic tumors of the skin and soft tissue

Rei Ogawa

Chapter 31: Facial prosthetics in plastic surgery

Facial prosthetics in plastic surgery

Gordon H. Wilkes

Volume Two:

Chapter 4: Skincare and nonsurgical skin rejuvenation

Skincare and nonsurgical skin rejuvenation

Leslie Baumann and Edmund Weisberg

Chapter 5.2: Injectables and resurfacing techniques: Soft-tissue fillers

Soft-tissue fillers

Trevor M. Born, Lisa E. Airan, and Daniel Suissa

Chapter 5.3: Injectables and resurfacing techniques: Botulinum toxin (BoNT-A)

Botulinum toxin

Michael A. C. Kane

Chapter 5.4: Injectables and resurfacing techniques: Laser resurfacing

Laser resurfacing

Steven R. Cohen, Ahmad N. Saad, Tracy Leong, and E. Victor Ross

Chapter 5.5: Injectables and resurfacing techniques: Chemical peels

Chemical peels

Suzan Obagi

Chapter 6.1: Facelift: Facial anatomy and aging

Anatomy of the aging face

Bryan Mendelson and Chin-Ho Wong

Chapter 6.2: Facelift: Principles of and surgical approaches to facelift

Principles of and surgical approaches to facelift

Richard J. Warren

Chapter 6.3: Facelift: Platysma-SMAS plication

Platysma-SMAS plication

Miles G. Berry

Chapter 6.4: Facelift: Facial rejuvenation with loop sutures – the MACS lift and its derivatives

Facial rejuvenation with loop sutures – the MACS lift and its derivatives

Mark Laurence Jewell

Chapter 6.5: Facelift: Lateral SMASectomy facelift

Lateral SMASectomy facelift

Daniel C. Baker and Steven M. Levine

Chapter 6.6: Facelift: The extended SMAS technique in facial rejuvenation

The extended SMAS technique in facelift

James M. Stuzin

Chapter 6.7: Facelift: SMAS with skin attached – the “high SMAS” technique

SMAS with skin attached – the high SMAS technique

Fritz E. Barton Jr.

Chapter 6.8: Facelift: Subperiosteal midface lift

Subperiosteal midface lift

Alan Yan and Michael J. Yaremchuk

Chapter 6.9: Facelift: Male facelift

Male facelift

Timothy J. Marten and Dino Elyassnia

Chapter 6.10: Facelift: Secondary deformities and the secondary facelift

Secondary deformities and the secondary facelift

Timothy J. Marten and Dino Elyassnia

Chapter 7: Forehead rejuvenation

Forehead rejuvenation

Richard J. Warren

Chapter 8: Endoscopic brow lifting

Endoscopic brow lift

Renato Saltz and Alyssa Lolofie

Chapter 9: Blepharoplasty

Blepharoplasty

Julius Few Jr. and Marco Ellis

Chapter 11: Asian facial cosmetic surgery

Asian facial cosmetic surgery

Clyde H. Ishii

Chapter 12: Neck rejuvenation

Neck rejuvenation

James E. Zins, Joshua T. Waltzman, and Rafael A. Couto

Chapter 13: Structural fat grafting

Structural fat grafting

Sydney R. Coleman and Alesia P. Saboeiro

Chapter 15: Nasal analysis and anatomy

Nasal analysis and anatomy

Rod J. Rohrich

Chapter 19: Secondary rhinoplasty

Secondary rhinoplasty

Ronald P. Gruber, Simeon H. Wall Jr., David L. Kaufman, and David M. Kahn

Chapter 21: Hair restoration

Hair restoration

Jack Fisher

Chapter 22.1: Liposuction: A comprehensive review of techniques and safety

Liposuction

Phillip J. Stephan, Phillip Dauwe, and Jeffrey Kenkel

Chapter 22.2: Correction of liposuction deformities with the SAFE liposuction technique

SAFE liposuction technique

Simeon H. Wall Jr. and Paul N. Afroz

Chapter 23: Abdominoplasty procedures

Abdominoplasty

Dirk F. Richter and Nina Schwaiger

Chapter 25.2: Circumferential approaches to truncal contouring: Belt lipectomy

Belt lipectomy

Al S. Aly, Khalid Al-Zahrani, and Albert Cram

Chapter 25.3: Circumferential approaches to truncal contouring: The lower lipo-bodylift

Circumferential lower bodylift

Dirk F. Richter and Nina Schwaiger

Chapter 25.4: Circumferential approaches to truncal contouring: Autologous buttocks augmentation with purse string gluteoplasty

Purse string gluteoplasty

Joseph P. Hunstad and Nicholas A. Flugstad

Chapter 25.5: Circumferential approaches to truncal contouring: Lower bodylift with autologous gluteal flaps for augmentation and preservation of gluteal contour

Lower bodylift with gluteal flaps

Robert F. Centeno and Jazmina M. Gonzalez

Chapter 26.3: Buttock augmentation: Buttock shaping with fat grafting and liposuction

Buttock shaping with fat grafting and liposuction

Constantino G. Mendieta, Thomas L. Roberts III, and Terrence W. Bruner

Chapter 27: Upper limb contouring

Upper limb contouring

Joseph F. Capella, Matthew J. Trovato, and Scott Woehrl

Chapter 30: Aesthetic genital surgery

Aesthetic genital surgery

Gary J. Alter

Volume Three:

Chapter 10.3: Midface reconstruction: The M. D. Anderson approach

Midfacial reconstruction: The M. D. Anderson approach

Matthew M. Hanasono and Roman Skoracki

Chapter 12: Lip reconstruction

Lip reconstruction

Peter C. Neligan and Lawrence J. Gottlieb

Chapter 14: Pharyngeal and esophageal reconstruction

Pharyngoesophageal reconstruction

Peirong Yu

Chapter 15: Tumors of the facial skeleton: Fibrous dysplasia

Fibrous dysplasia

Alberto Córdova-Aguilar and Yu-Ray Chen

Chapter 17: Local flaps for facial coverage

Local flaps for facial coverage

David W. Mathes

Chapter 19: Facial transplant

Facial transplant

Michael Sosin and Eduardo D. Rodriguez

Chapter 32: Nonsyndromic craniosynostosis

Nonsyndromic craniosynostosis

Patrick A. Gerety, Jesse A. Taylor, and Scott P. Bartlett

Chapter 36: Pierre Robin Sequence

Pierre Robin sequence

Chad A. Purnell and Arun K. Gosain

Chapter 39: Vascular anomalies

Vascular anomalies

Arin K. Greene and John B. Mulliken

Volume Four:

Chapter 2: Management of lower extremity trauma

Management of lower extremity trauma

Yoo Joon Sur, Shannon M. Colohan, and Michel Saint-Cyr

Chapter 15: Surgery for gender identity disorder

Surgery for gender identity disorder

Loren S. Schechter

Chapter 16: Pressure sores

Pressure sores

Robert Kwon, Juan L. Rendon, and Jeffrey E. Janis

Chapter 17: Perineal reconstruction

Perineal reconstruction

Hakim K. Said and Otway Louie

Volume Five:

Chapter 5: Breast augmentation with autologous fat grafting

Breast augmentation with autologous fat grafting

E. Delay

Chapter 6: Mastopexy options and techniques

Mastopexy

Robert Cohen

Chapter 9: Reduction mammoplasty with inverted-T techniques

Reduction mammoplasty with inverted-T techniques

Maurice Y. Nahabedian

Chapter 15: One- and two-stage prosthetic reconstruction in nipple-sparing mastectomy

Prosthetic reconstruction in nipple-sparing mastectomy

Amy S. Colwell

Chapter 20.1: Abdominally based free flaps: Introduction

Abdominally-based autologous breast reconstruction

Maurice Y. Nahabedian, Phillip N. Blondeel, and David H. Song

Chapter 20.2: The deep inferior epigastric artery perforator (DIEAP) flap

Abdominally-based autologous breast reconstruction

Maurice Y. Nahabedian, Phillip N. Blondeel, and David H. Song

Chapter 20.3: The superficial inferior epigastric artery (SIEA) flap

Abdominally-based autologous breast reconstruction

Maurice Y. Nahabedian, Phillip N. Blondeel, and David H. Song

Chapter 20.4: The free TRAM flap

Abdominally-based autologous breast reconstruction

Maurice Y. Nahabedian, Phillip N. Blondeel, and David H. Song

Chapter 25: Radiation therapy considerations in the setting of breast reconstruction

Radiation therapy in breast reconstruction

Steven Kronowitz

Volume Six:

Chapter 7: Hand fractures and joint injuries

Hand fractures and joint injuries

Joseph S. Khouri and Warren C. Hammert

Chapter 13: Thumb reconstruction: Non-microsurgical techniques

Thumb reconstruction

Nicholas B. Vedder and Jeffrey B. Friedrich

Chapter 21: The stiff hand and the spastic hand

The stiff hand

David T. Netscher, Kenneth W. Donohue, and Dang T. Pham

Chapter 24: Nerve entrapment syndromes

Tips and pearls on common nerve compressions*Elisabet Hagert and Donald Lalonde*

Chapter 30: Growth considerations in pediatric upper extremity trauma and reconstruction

Growth considerations in pediatric upper extremity trauma and reconstruction*Marco Innocenti and Carla Baldrighi*

Chapter 33: Nerve transfers

Nerve injury and repair*Kirsty Usher Boyd, Andrew Yee, and Susan E. Mackinnon*

Chapter 37: Restoration of upper extremity function in tetraplegia

Restoration of upper extremity function in tetraplegia*Carina Reinholdt and Catherine Curtin*



Preface to the Fourth Edition

When I wrote the preface to the 3rd edition of this book, I remarked how honored and unexpectedly surprised I was to be the Editor of this great series. This time 'round, I'm equally grateful to carry this series forward. When Elsevier called me and suggested it was time to prepare the 4th edition, my initial reaction was that this was way too soon. What could possibly have changed in Plastic Surgery since the 3rd edition was launched in 2012? As it transpires, there have been many developments and I hope we have captured them in this edition.

We have an extraordinary specialty. A recent article by Chadra, Agarwal and Agarwal entitled "Redefining Plastic Surgery" appeared in *Plastic and Reconstructive Surgery—Global Open*. In it they gave the following definition: "Plastic surgery is a specialized branch of surgery, which deals with deformities, defects and abnormalities of the organs of perception, organs of action and the organs guarding the external passages, besides innovation, implantation, replantation and transplantation of tissues, and aims at restoring and improving their form, function and the esthetic appearances." This is an all-encompassing but very apt definition and captures the enormous scope of the specialty.¹

In the 3rd edition, I introduced volume editors for each of the areas of the specialty because the truth is that one person can no longer be an expert in all areas of this diverse specialty, and I'm certainly not. I think this worked well because the volume editors not only had the expertise to present their area of subspecialty in the best light, but they were tuned in to what was new and who was doing it. We have continued this model in this new edition. Four of the seven volume editors from the previous edition have again helped to bring the latest and the best to this edition: Drs Gurtner, Song, Rodriguez, Losee, and Chang have revised and updated their respective volumes with some chapters remaining, some extensively revised, some added, and some deleted. Dr. Peter Rubin has replaced Dr. Rick Warren to compile the Aesthetic volume (Vol. 2). Dr. Warren did a wonderful job in corralling this somewhat disparate, yet vitally important, part of our specialty into the Aesthetic volume in the 3rd edition but felt that the task of doing it again, though a labor of love, was more than he wanted to take on. Similarly, Dr. Jim Grotting who did a masterful job in the last edition on the Breast volume, decided that doing a major revision should be undertaken by someone with a fresh perspective and Dr. Maurice Nahabedian stepped into that breach. I hope you will like the changes you see in both of these volumes.

Dr. Allen Van Beek was the video editor for the last edition and he compiled an impressive array of movies to complement the text. This time around, we wanted to go a step further and though we've considerably expanded the list of

videos accompanying the text (there are over 170), we also added the idea of lectures accompanying selected chapters. What we've done here is to take selected key chapters and include the images from that chapter, photos and artwork, and create a narrated presentation that is available online; there are annotations in the text to alert the reader that this is available. Dr. Daniel Liu, who has taken over from Dr. Van Beek as multimedia editor (rather than video editor) has done an amazing job in making all of this happen. There are over 70 presentations of various key chapters online, making it as easy as possible for you, the reader, to get as much knowledge as you can, in the easiest way possible from this edition. Many of these presentations have been done by the authors of the chapters; the rest have been compiled by Dr. Liu and myself from the content of the individual chapters. I hope you find them useful.

The reader may wonder how this all works. To plan this edition, the Elsevier team, headed by Belinda Kuhn, and I, convened a face-to-face meeting in San Francisco. The volume editors, as well as the London based editorial team, were present. We went through the 3rd edition, volume by volume, chapter by chapter, over an entire weekend. We decided what needed to stay, what needed to be added, what needed to be revised, and what needed to be changed. We also decided who should write the various chapters, keeping many existing authors, replacing others, and adding some new ones; we did this so as to really reflect the changes occurring within the specialty. We also decided on practical changes that needed to be made. As an example, you will notice that we have omitted the complete index for the 6 Volume set from Volumes 2-6 and highlighted only the table of contents for that particular volume. The complete index is of course available in Volume 1 and fully searchable online. This allowed us to save several hundred pages per volume, reducing production costs and diverting those dollars to the production of the enhanced online content.

In my travels around the world since the 3rd edition was published, I've been struck by what an impact this publication has had on the specialty and, more particularly, on training. Everywhere I go, I'm told how the text is an important part of didactic teaching and a font of knowledge. It is gratifying to see that the 3rd edition has been translated into Portuguese, Spanish, and Chinese. This is enormously encouraging. I hope this 4th edition continues to contribute to the specialty, remains a resource for practicing surgeons, and continues to prepare our trainees for their future careers in Plastic Surgery.

Peter C. Neligan
Seattle, WA
September, 2017

¹ Chandra R, Agarwal R, Agarwal D. Redefining Plastic Surgery. *Plast Reconstr Surg Glob Open*. 2016;4(5):e706.


List of Editors



Editor-in-Chief

Peter C. Neligan, MB, FRCS(I), FRCSC, FACS

Professor of Surgery
Department of Surgery, Division of Plastic Surgery
University of Washington
Seattle, WA, USA



Volume 4: Lower Extremity, Trunk, and Burns

David H. Song, MD, MBA, FACS

Regional Chief, MedStar Health
Plastic and Reconstructive Surgery
Professor and Chairman
Department of Plastic Surgery
Georgetown University School of Medicine
Washington, DC, USA



Volume 1: Principles

Geoffrey C. Gurtner, MD, FACS

Johnson and Johnson Distinguished Professor of
Surgery and Vice Chairman,
Department of Surgery (Plastic Surgery)
Stanford University
Stanford, CA, USA



Volume 5: Breast

Maurice Y. Nahabedian, MD, FACS

Professor and Chief
Section of Plastic Surgery
MedStar Washington Hospital Center
Washington, DC, USA;
Vice Chairman
Department of Plastic Surgery
MedStar Georgetown University Hospital
Washington, DC, USA



Volume 2: Aesthetic

J. Peter Rubin, MD, FACS

UPMC Professor of Plastic Surgery
Chair, Department of Plastic Surgery
Professor of Bioengineering
University of Pittsburgh
Pittsburgh, PA, USA



Volume 6: Hand and Upper Extremity

James Chang, MD

Johnson & Johnson Distinguished
Professor and Chief
Division of Plastic and Reconstructive Surgery
Stanford University Medical Center
Stanford, CA, USA



Volume 3: Craniofacial, Head and Neck Surgery

Eduardo D. Rodriguez, MD, DDS

Helen L. Kimmel Professor of Reconstructive
Plastic Surgery
Chair, Hansjörg Wyss Department of Plastic
Surgery
NYU School of Medicine
NYU Langone Medical Center
New York, NY, USA



Multimedia editor

Daniel Z. Liu, MD

Plastic and Reconstructive Surgeon
Cancer Treatment Centers of America at Midwest-
ern Regional Medical Center
Zion, IL, USA



Volume 3: Pediatric Plastic Surgery

Joseph E. Losee, MD

Ross H. Musgrave Professor of Pediatric Plastic
Surgery
Department of Plastic Surgery
University of Pittsburgh Medical Center;
Chief Division of Pediatric Plastic Surgery
Children's Hospital of Pittsburgh
Pittsburgh, PA, USA



List of Contributors

The editors would like to acknowledge and offer grateful thanks for the input of all previous editions' contributors, without whom this new edition would not have been possible.

VOLUME ONE

Hatem Abou-Sayed, MD, MBA

Vice President
Physician Engagement
Interpreta, Inc.
San Diego, CA, USA

Paul N. Afrooz, MD

Resident
Plastic and Reconstructive Surgery
University of Pittsburgh Medical Center
Pittsburgh, PA, USA

Claudia R. Albornoz, MD, MSc

Research Fellow
Plastic and Reconstructive Surgery
Memorial Sloan Kettering Cancer Center
New York, NY, USA

Nidal F. Al Deek, MD

Doctor of Plastic and Reconstructive Surgery
Chang Gung Memorial Hospital
Taipei, Taiwan

Amy K. Alderman, MD, MPH

Private Practice
Atlanta, GA, USA

Louis C. Argenta, MD

Professor of Plastic and Reconstructive Surgery
Department of Plastic Surgery
Wake Forest Medical Center
Winston Salem, NC, USA

Stephan Ariyan, MD, MBA

Emeritus Frank F. Kanthak Professor of Surgery,
Plastic Surgery, Surgical Oncology,
Otolaryngology
Yale University School of Medicine;
Associate Chief
Department of Surgery;
Founding Director, Melanoma Program
Smilow Cancer Hospital, Yale Cancer Center
New Haven, CT, USA

Tomer Avraham, MD

Attending Plastic Surgeon
Mount Sinai Health System
Tufts University School of Medicine
New York, NY, USA

Aaron Berger, MD, PhD

Clinical Assistant Professor
Division of Plastic Surgery
Florida International University School of
Medicine
Miami, FL, USA

Kirsty Usher Boyd, MD, FRCSC

Assistant Professor Surgery (Plastics)
Division of Plastic and Reconstructive Surgery
University of Ottawa
Ottawa, Ontario, Canada

Charles E. Butler, MD, FACS

Professor and Chairman
Department of Plastic Surgery
Charles B. Barker Endowed Chair in Surgery
The University of Texas MD Anderson Cancer
Center
Houston, TX, USA

Peter E. M. Butler, MD, FRCSI, FRCS, FRCS(Plast)

Professor
Plastic and Reconstructive Surgery
University College and Royal Free London
London, UK

Yilin Cao, MD, PhD

Professor
Shanghai Ninth People's Hospital
Shanghai Jiao Tong University School of
Medicine
Shanghai, China

Franklyn P. Cladis, MD, FAAP

Associate Professor of Anesthesiology
Department of Anesthesiology
The Children's Hospital of Pittsburgh of UPMC
Pittsburgh, PA, USA

Mark B. Constantian, MD

Private Practice
Surgery (Plastic Surgery)
St. Joseph Hospital
Nashua, NH, USA

Daniel A. Cuzzone, MD

Plastic Surgery Fellow
Hanjörg Wyss Department of Plastic Surgery
New York University Medical Center
New York, NY, USA

Gurleen Dhami, MD

Chief Resident
Department of Radiation Oncology
University of Washington
Seattle, WA, USA

Gayle Gordillo, MD

Associate Professor
Plastic Surgery
The Ohio State University
Columbus, OH, USA

Geoffrey C. Gurtner, MD, FACS

Johnson and Johnson Distinguished Professor
of Surgery and Vice Chairman,
Department of Surgery (Plastic Surgery)
Stanford University
Stanford, CA, USA

Phillip C. Haeck, MD

Surgeon
Plastic Surgery
The Polyclinic
Seattle, WA, USA

The late Bruce Halperin[†], MD

Formerly Adjunct Associate Professor of
Anesthesia
Department of Anesthesia
Stanford University
Stanford, CA, USA

Daniel E. Heath

Lecturer
School of Chemical and Biomedical Engineering
University of Melbourne
Parkville, Victoria, Australia

Joon Pio Hong, MD, PhD, MMM

Professor
Plastic Surgery
Asan Medical Center, University of Ulsan
Seoul, South Korea

Michael S. Hu, MD, MPH, MS

Postdoctoral Fellow
Division of Plastic Surgery
Department of Surgery
Stanford University School of Medicine
Stanford, CA, USA

C. Scott Hultman, MD, MBA

Professor and Chief
Division of Plastic and Reconstructive Surgery
University of North Carolina
Chapel Hill, NC, USA

Amir E. Ibrahim

Division of Plastic Surgery
Department of Surgery
American University of Beirut Medical Center
Beirut, Lebanon

Leila Jazayeri, MD

Microsurgery Fellow
Plastic and Reconstructive Surgery
Memorial Sloan Kettering Cancer Center
New York, NY, USA

Brian Jeffers

Student
Bioengineering
University of California Berkeley
Berkeley, CA USA

Lynn Jeffers, MD, FACS

Private Practice
Oxnard, CA, USA

Mohammed M. Al Kahtani, MD, FRCSC

Clinical Fellow
Division of Plastic Surgery
Department of Surgery
University of Alberta
Edmonton, Alberta, Canada

Gabrielle M. Kane, MB, BCh, EdD, FRCPC

Associate Professor
Radiation Oncology
University of Washington
Seattle, WA, USA

Raghu P. Kataru, PhD

Senior Research Scientist
Memorial Sloan-Kettering Cancer Center
New York, NY, USA

Carolyn L. Kerrigan, MD, MSc, MHCDS

Professor of Surgery
Surgery
Dartmouth-Hitchcock Medical Center
Lebanon, NH, USA

Timothy W. King, MD, PhD, FAAP, FACS

Associate Professor with Tenure
Departments of Surgery and Biomedical Engineering;
Director of Research, Division of Plastic Surgery
University of Alabama at Birmingham (UAB)
Craniofacial and Pediatric Plastic Surgery
Children's of Alabama – Plastic Surgery;
Chief, Plastic Surgery Section
Birmingham VA Hospital
Birmingham, AL, USA

Brian M. Kinney, MD, FACS, MSME

Clinical Assistant Professor of Plastic Surgery
University of Southern California
School of Medicine
Los Angeles, CA, USA

W. P. Andrew Lee, MD

The Milton T. Edgerton MD, Professor and Chairman
Department of Plastic and Reconstructive Surgery
Johns Hopkins University School of Medicine
Baltimore, MD, USA

Sherilyn Keng Lin Tay, MBChB, MSc, FRCS(Plast)

Consultant Plastic Surgeon
Canniesburn Plastic Surgery Unit
Glasgow Royal Infirmary
Glasgow, UK

Daniel Z. Liu, MD

Plastic and Reconstructive Surgeon
Cancer Treatment Centers of America at
Midwestern Regional Medical Center
Zion, IL, USA

Wei Liu, MD, PhD

Professor
Plastic and Reconstructive Surgery
Shanghai Ninth People's Hospital
Shanghai Jiao Tong University School of Medicine
Shanghai, China

Michael T. Longaker, MD, MBA, FACS

Deane P. and Louise Mitchell Professor and Vice Chair
Department of Surgery
Stanford University
Stanford, CA, USA

H. Peter Lorenz, MD

Service Chief and Professor, Plastic Surgery
Lucile Packard Children's Hospital
Stanford University School of Medicine
Stanford, CA, USA

Susan E. Mackinnon, MD

Sydney M. Shoenberg Jr. and Robert H. Shoenberg Professor
Department of Surgery, Division of Plastic and Reconstructive Surgery
Washington University School of Medicine
St. Louis, MO, USA

Malcolm W. Marks, MD

Professor and Chairman
Department of Plastic Surgery
Wake Forest University School of Medicine
Winston-Salem, NC, USA

Diego Marre, MD

Fellow
O'Brien Institute
Department of Plastic and Reconstructive Surgery
St. Vincent's Hospital
Melbourne, Australia

David W. Mathes, MD

Professor and Chief of the Division of Plastic and Reconstructive Surgery
University of Colorado
Aurora, CO, USA

Evan Matros MD, MMSc

Plastic Surgeon
Memorial Sloan-Kettering Cancer Center
New York, NY, USA

Isabella C. Mazzola, MD

Attending Plastic Surgeon
Klinik für Plastische und Ästhetische Chirurgie
Klinikum Landkreis Erding
Erding, Germany

Riccardo F. Mazzola, MD

Plastic Surgeon
Department of Specialistic Surgical Sciences
Fondazione Ospedale Maggiore Policlinico, Ca' Granda IRCCS
Milano, Italy

Lindsay D. McHutchion, MS, BSc

Anaplastologist
Institute for Reconstructive Sciences in Medicine
Edmonton, Alberta, Canada

Babak J. Mehrara, MD, FACS

Associate Member, Associate Professor of Surgery (Plastic)
Memorial Sloan Kettering Cancer Center
Weil Cornell University Medical Center
New York, NY, USA

Steven F. Morris, MD, MSc, FRCSC

Professor of Surgery
Department of Surgery
Dalhousie University
Halifax, Nova Scotia, Canada

Wayne A. Morrison, MBBS, MD, FRACS

Professorial Fellow
O'Brien Institute
Department of Surgery, University of Melbourne
Department of Plastic and Reconstructive Surgery, St. Vincent's Hospital
Melbourne, Australia

Peter C. Neligan, MB, FRCS(I), FRCSC, FACS

Professor of Surgery
Department of Surgery, Division of Plastic Surgery
University of Washington
Seattle, WA, USA

Andrea J. O'Connor, BE(Hons), PhD

Associate Professor
Department of Chemical and Biomolecular Engineering
University of Melbourne
Parkville, Victoria, Australia

Rei Ogawa, MD, PhD, FACS

Professor and Chief
Department of Plastic Reconstructive and Aesthetic Surgery
Nippon Medical School
Tokyo, Japan

Dennis P. Orgill, MD, PhD

Professor of Surgery
Harvard Medical School
Medical Director, Wound Care Center;
Vice Chairman for Quality Improvement
Department of Surgery
Brigham and Women's Hospital
Boston, MA, USA

Cho Y. Pang, PhD

Senior Scientist
Research Institute
The Hospital for Sick Children;
Professor
Departments of Surgery/Physiology
University of Toronto
Toronto, Ontario, Canada

Ivo Alexander Pestana, MD, FACS

Associate Professor
Plastic and Reconstructive Surgery
Wake Forest University
Winston Salem, NC, USA

Giorgio Pietramaggior, MD, PhD

Swiss Nerve Institute
Clinique de La Source
Lausanne, Switzerland

Andrea L. Pusic, MD, MHS, FACS

Associate Professor
Plastic and Reconstructive Surgery
Memorial Sloan Kettering Cancer Center
New York, NY, USA

Russell R. Reid, MD, PhD

Associate Professor
Surgery/Section of Plastic and Reconstructive Surgery
University of Chicago Medicine
Chicago, IL, USA

Neal R. Reisman, MD, JD

Chief
Plastic Surgery
Baylor St. Luke's Medical Center
Houston, TX, USA

Joseph M. Rosen, MD

Professor of Surgery
Plastic Surgery
Dartmouth-Hitchcock Medical Center
Lebanon, NH, USA

Sashwati Roy, MS, PhD

Associate Professor
Surgery, Center for Regenerative Medicine and Cell based Therapies
The Ohio State University
Columbus, OH, USA

J. Peter Rubin, MD, FACS

UPMC Professor of Plastic Surgery
Chair, Department of Plastic Surgery
Professor of Bioengineering
University of Pittsburgh
Pittsburgh, PA, USA

Karim A. Sarhane, MD

Department of Surgery
University of Toledo Medical Center
Toledo, OH, USA

David B. Sarwer, PhD

Associate Professor of Psychology
Departments of Psychiatry and Surgery
University of Pennsylvania School of Medicine
Philadelphia, PA, USA

Saja S. Scherer-Pietramaggiori, MD

Plastic and Reconstructive Surgeon
Plastic Surgery
University Hospital Lausanne
Lausanne, Vaud, Switzerland

Iris A. Seitz, MD, PhD

Director of Research and International Collaboration
University Plastic Surgery
Rosalind Franklin University;
Clinical Instructor of Surgery
Chicago Medical School
Chicago, IL, USA

Jesse C. Selber, MD, MPH, FACS

Associate Professor, Director of Clinical Research
Department of Plastic Surgery
MD Anderson Cancer Center
Houston, TX, USA

Chandan K. Sen, PhD

Professor and Director
Center for Regenerative Medicine and Cell-Based Therapies
The Ohio State University Wexner Medical Center
Columbus, OH, USA

Wesley N. Sivak, MD, PhD

Resident in Plastic Surgery
Department of Plastic Surgery
University of Pittsburgh
Pittsburgh, PA, USA

M. Lucy Sudekum

Research Assistant
Thayer School of Engineering at Dartmouth College
Hanover, NH, USA

G. Ian Taylor, AO, MBBS, MD, MD(Hon Bordeaux), FRACS, FRCS(Eng), FRCS(Hon Edinburgh), FRCSI(Hon), FRSC(Hon Canada), FACS(Hon)

Professor
Department of Plastic Surgery
Royal Melbourne Hospital;
Professor
Department of Anatomy
University of Melbourne
Melbourne, Victoria, Australia

Chad M. Teven, MD

Resident
Section of Plastic and Reconstructive Surgery
University of Chicago
Chicago, IL, USA

Ruth Tevlin, MB BAO BCh, MRCSI, MD

Resident in Surgery
Department of Plastic and Reconstructive Surgery
Stanford University School of Medicine
Stanford, CA, USA

E. Dale Collins Vidal, MD, MS

Chief
Section of Plastic Surgery
Dartmouth-Hitchcock Medical Center
Lebanon, NH, USA

Derrick C. Wan, MD

Associate Professor
Division of Plastic Surgery
Department of Surgery
Director of Maxillofacial Surgery
Lucile Packard Children's Hospital
Stanford University School of Medicine
Stanford, CA, USA

Renata V. Weber, MD

Assistant Professor Surgery (Plastics)
Division of Plastic and Reconstructive Surgery
Albert Einstein College of Medicine
Bronx, NY, USA

Fu-Chan Wei, MD

Professor
Department of Plastic Surgery
Chang Gung Memorial Hospital
Taoyuan, Taiwan

Gordon H. Wilkes, BScMed, MD

Clinical Professor of Surgery
Department of Surgery University of Alberta
Institute for Reconstructive Sciences in Medicine
Misericordia Hospital
Edmonton, Alberta, Canada

Johan F. Wolfaardt, BDS, MDent(Prosthodontics), PhD

Professor
Division of Otolaryngology – Head and Neck Surgery
Department of Surgery
Faculty of Medicine and Dentistry;
Director of Clinics and International Relations
Institute for Reconstructive Sciences in Medicine
University of Alberta
Covenant Health Group
Alberta Health Services
Alberta, Canada

Kiryu K. Yap, MBBS, BMedSc

Junior Surgical Trainee & PhD Candidate
O'Brien Institute
Department of Surgery, University of Melbourne
Department of Plastic and Reconstructive Surgery, St. Vincent's Hospital
Melbourne, Australia

Andrew Yee

Research Assistant
Division of Plastic and Reconstructive Surgery
Washington University School of Medicine
St. Louis, MO, USA

Elizabeth R. Zielins, MD

Postdoctoral Research Fellow
Surgery
Stanford University School of Medicine
Stanford, CA, USA

VOLUME TWO**Paul N. Afrooz, MD**

Resident
Plastic and Reconstructive Surgery
University of Pittsburgh Medical Center
Pittsburgh, PA, USA

Jamil Ahmad, MD, FRCSC

Director of Research and Education
The Plastic Surgery Clinic
Mississauga;
Assistant Professor
Surgery
University of Toronto
Toronto, Ontario, Canada

Lisa E. Airan, MD

Aesthetic Dermatologist NYC
Private Practice;
Associate Clinical Professor Department of
Dermatology
Mount Sinai School of Medicine
New York, NY, USA

Gary J. Alter, MD

Assistant Clinical Professor
Division of Plastic Surgery
University of California
Los Angeles, CA, USA

AI S. Aly, MD

Professor of Plastic Surgery
Aesthetic and Plastic Surgery Institute University
of California Irvine
Orange, CA, USA

Khalid Al-Zahrani, MD, SSC-PLAST

Assistant Professor
Consultant Plastic Surgeon
King Khalid University Hospital
King Saud University
Riyadh, Saudi Arabia

Bryan Armijo, MD

Plastic Surgery Chief Resident
Department of Plastic and Reconstructive
Surgery
Case Western Reserve/University Hospitals
Cleveland, OH, USA

Daniel C. Baker, MD

Professor of Surgery
Institute of Reconstructive Plastic Surgery
New York University Medical Center
Department of Plastic Surgery
New York, NY, USA

Fritz E. Barton Jr., MD

Clinical Professor
Department of Plastic Surgery
UT Southwestern Medical Center
Dallas, TX, USA

Leslie Baumann, MD

CEO
Baumann Cosmetic and Research Institute
Miami, FL, USA

Miles G. Berry, MS, FRCS(Plast)

Consultant Plastic and Aesthetic Surgeon
Institute of Cosmetic and Reconstructive
Surgery
London, UK

Trevor M. Born, MD

Division of Plastic Surgery
Lenox Hill/Manhattan Eye Ear and Throat
Hospital North Shore-LIJ Hospital
New York, NY, USA;
Clinical Lecturer
Division of Plastic Surgery
University of Toronto Western Division
Toronto, Ontario, Canada

Terrence W. Bruner, MD, MBA

Private Practice
Greenville, SC, USA

Andrés F. Cánclica, MD

Chief Resident of Plastic Surgery
Plastic Surgery Service Dr. Osvaldo Saldanha
São Paulo, Brazil

Joseph F. Capella, MD

Chief Post-bariatric Body Contouring
Division of Plastic Surgery
Hackensack University Medical Center
Hackensack, NJ, USA

Robert F. Centeno, MD, MBA

Medical Director
St. Croix Plastic Surgery and MediSpa;
Chief Medical Quality Officer
Governor Juan F. Luis Hospital and Medical
Center
Christiansted, Saint Croix, United States Virgin
Islands

Ernest S. Chiu, MD, FACS

Associate Professor of Plastic Surgery
Department of Plastic Surgery
New York University
New York, NY, USA

Jong Woo Choi, MD, PhD, MMM

Associate Professor
Department of Plastic and Reconstructive
Surgery
Seoul Asan Medical Center
Seoul, South Korea

Steven R. Cohen, MD

Senior Clinical Research Fellow, Clinical
Professor
Plastic Surgery
University of California
San Diego, CA;
Director
Craniofacial Surgery
Rady Children's Hospital, Private Practice,
FACES+ Plastic Surgery, Skin and Laser Center
La Jolla, CA, USA

Sydney R. Coleman, MD

Assistant Clinical Professor
Plastic Surgery
New York University Medical Center
New York;
Assistant Clinical Professor
Plastic Surgery
University of Pittsburgh Medical Center
Pittsburgh, PA, USA

Mark B. Constantian, MD

Private Practice
Surgery (Plastic Surgery)
St. Joseph Hospital
Nashua, NH, USA;
Adjunct Clinical Professor
Surgery (Plastic Surgery)
University of Wisconsin School of Medicine
Madison, WI, USA;
Visiting Professor
Plastic Surgery
University of Virginia Health System
Charlottesville, VA, USA

Rafael A. Couto, MD

Plastic Surgery Resident
Department of Plastic Surgery
Cleveland Clinic
Cleveland, OH, USA

Albert Cram, MD

Professor Emeritus
University of Iowa
Iowa City Plastic Surgery
Coralville, IO, USA

Phillip Dauwe, MD

Department of Plastic Surgery
University of Texas Southwestern Medical
School
Dallas, TX, USA

Dai M. Davies, FRCS

Consultant and Institute Director
Institute of Cosmetic and Reconstructive
Surgery
London, UK

Jose Abel De la Peña Salcedo, MD, FACS

Plastic Surgeon
Director
Instituto de Cirugia Plastica S.C.
Huixquilucan
Estado de Mexico, Mexico

Barry DiBernardo, MD, FACS

Clinical Associate Professor, Plastic Surgery
Rutgers, New Jersey Medical School
Director New Jersey Plastic Surgery
Montclair, NJ, USA

Felmont F. Eaves III, MD, FACS

Professor of Surgery, Emory University
Medical Director, Emory Aesthetic Center
Medical Director, EAC Ambulatory Surgery
Center
Atlanta, GA, USA

Marco Ellis, MD

Director of Craniofacial Surgery
Northwestern Specialists in Plastic Surgery;
Adjunct Assistant Professor
University of Illinois Chicago Medical Center
Chicago, IL, USA

Dino Elyassnia, MD

Associate Plastic Surgeon
Marten Clinic of Plastic Surgery
San Francisco, CA, USA

Julius Few Jr., MD

Director
The Few Institute for Aesthetic Plastic Surgery;
Clinical Professor
Plastic Surgery
University of Chicago Pritzker School of
Medicine
Chicago, IL, USA

Oswaldo Ribeiro Saldanha Filho, MD

Professor of Plastic Surgery
Plastic Surgery Service Dr. Oswaldo Saldanha
São Paulo, Brazil

Jack Fisher, MD

Associate Clinical Professor
Plastic Surgery
Vanderbilt University
Nashville, TN, USA

Nicholas A. Flugstad, MD

Flugstad Plastic Surgery
Bellevue, WA, USA

James D. Frame, MBBS, FRCS, FRCSEd, FRCS(Plast)

Professor of Aesthetic Plastic Surgery
Anglia Ruskin University
Chelmsford, UK

Jazmina M. Gonzalez, MD

Bitar Cosmetic Surgery Institute
Fairfax, VA, USA

Richard J. Greco, MD

CEO
The Georgia Institute For Plastic Surgery
Savannah, GA, USA

Ronald P. Gruber, MD

Adjunct Associate Clinical Professor
Division of Plastic and Reconstructive Surgery
Stanford University
Stanford, CA
Clinical Association Professor
Division of Plastic and Reconstructive Surgery
University of California San Francisco
San Francisco, CA, USA

Bahman Guyuron, MD, FCVS

Editor in Chief, Aesthetic Plastic Surgery Journal
Emeritus Professor of Plastic Surgery
Case School of Medicine
Cleveland, OH, USA

Joseph P. Hunstad, MD, FACS

Associate Consulting Professor
Division of Plastic Surgery
The University of North Carolina at Chapel Hill;
Private Practice
Huntersville/Charlotte, NC, USA

Clyde H. Ishii, MD, FACS

Assistant Clinical Professor of Surgery
John A. Burns School of Medicine;
Chief, Department of Plastic Surgery
Shriners Hospital
Honolulu Unit
Honolulu, HI, USA

Nicole J. Jarrett, MD

Department of Plastic Surgery
University of Pittsburgh
Pittsburgh, PA, USA

Elizabeth B. Jelks, MD

Private Practice
Jelks Medical
New York, NY, USA

Glenn W. Jelks, MD

Associate Professor
Department of Ophthalmology
Department of Plastic Surgery
New York University School of Medicine
New York, NY, USA

Mark Laurence Jewell, MD

Assistant Clinical Professor Plastic Surgery
Oregon Health Science University
Portland, OR, USA

David M. Kahn, MD

Clinical Associate Professor of Plastic Surgery
Department of Surgery
Stanford University School of Medicine
Stanford, CA, USA

Michael A. C. Kane, BS, MD

Attending Surgeon
Plastic Surgery
Manhattan Eye, Ear, and Throat Hospital
New York, NY, USA

David L. Kaufman, MD, FACS

Private Practice Plastic Surgery
Aesthetic Artistry Surgical and Medical Center
Folsom, CA, USA

Jeffrey Kenkel, MD

Professor and Chairman
Department of Plastic Surgery
UT Southwestern Medical Center
Dallas, TX, USA

Kyung S. Koh, MD, PhD

Professor of Plastic Surgery
Asan Medical Center, University of Ulsan School
of Medicine
Seoul, South Korea

Tracy Leong, MD

Dermatology
Rady Children's Hospital - San Diego;
Sharp Memorial Hospital;
University California San Diego Medical Center
San Diego;
Private Practice, FACES+ Plastic Surgery, Skin
and Laser Center
La Jolla, CA, USA

Steven M. Levine, MD

Assistant Professor of Surgery (Plastic)
Hofstra Medical School, Northwell Health,
New York, NY, USA

Michelle B. Locke, MBChB, MD

Senior Lecturer in Surgery
Department of Surgery
University of Auckland Faculty of Medicine and
Health Sciences;
South Auckland Clinical Campus
Middlemore Hospital
Auckland, New Zealand

Alyssa Lolofie

University of Utah
Salt Lake City, UT, USA

Timothy J. Marten, MD, FACS

Founder and Director
Marten Clinic of Plastic Surgery
San Francisco, CA, USA

Bryan Mendelson, FRCSE, FRACS, FACS

The Centre for Facial Plastic Surgery
Toorak, Victoria, Australia

Constantino G. Mendieta, MD, FACS

Private Practice
Miami, FL, USA

Drew B. Metcalfe, MD

Division of Plastic and Reconstructive Surgery
Emory University
Atlanta, GA, USA

Gabriele C. Miotto, MD

Emory School of Medicine
Atlanta, GA, USA

Foad Nahai, MD

Professor of Surgery
Division of Plastic and Reconstructive Surgery
Department of Surgery
Emory University School of Medicine
Emory Aesthetic Center at Paces
Atlanta, Georgia, USA

Suzan Obagi, MD

Associate Professor of Dermatology
Dermatology
University of Pittsburgh;
Associate Professor of Plastic Surgery
Plastic Surgery
University of Pittsburgh
Pittsburgh, PA, USA

Sabina Aparecida Alvarez de Paiva, MD

Resident of Plastic Surgery
Plastic Surgery Service Dr. Ewaldo Bolivar de
Souza Pinto
São Paulo, Brazil

Galen Perdikis, MD

Assistant Professor of Surgery
Division of Plastic Surgery
Emory University School of Medicine
Atlanta, GA, USA

Jason Posner, MD, FACS

Private Practice
Boca Raton, FL, USA

Dirk F. Richter, MD, PhD

Clinical Professor of Plastic Surgery
University of Bonn
Director and Chief
Dreifaltigkeits-Hospital
Wesseling, Germany

Thomas L. Roberts III, FACS

Plastic Surgery Center of the Carolinas
Spartanburg, SC, USA

Jocelyn Celeste Ledezma Rodriguez, MD

Private Practice
Guadalajara, Jalisco, Mexico

Rod J. Rohrich, MD

Clinical Professor and Founding Chair
Department of Plastic Surgery
Distinguished Teaching Professor
University of Texas Southwestern Medical Center
Founding Partner
Dallas Plastic Surgery Institute
Dallas, TX, USA

E. Victor Ross, MD

Director of Laser and Cosmetic Dermatology
Scripps Clinic
San Diego, CA, USA

J. Peter Rubin, MD, FACS

Chief
Plastic and Reconstructive Surgery
University of Pittsburgh Medical Center;
Associate Professor
Department of Surgery
University of Pittsburgh
Pittsburgh, PA, USA

Ahmad N. Saad, MD

Private Practice
FACES+ Plastic Surgery
Skin and Laser Center
La Jolla, CA, USA

Alesia P. Saboeiro, MD

Attending Physician
Private Practice
New York, NY, USA

Cristianna Bonnetto Saldanha, MD

Plastic Surgery Service Dr. Osvaldo Saldanha
São Paulo, Brazil

Osvaldo Saldanha, MD, PhD

Director of Plastic Surgery Service Dr. Osvaldo
Saldanha;
Professor of Plastic Surgery Department
Universidade Metropolitana de Santos
- UNIMES
São Paulo, Brazil

Renato Saltz, MD, FACS

Saltz Plastic Surgery
President
International Society of Aesthetic Plastic Surgery
Adjunct Professor of Surgery
University of Utah
Past-President, American Society for Aesthetic
Plastic Surgery
Salt Lake City and Park City, UT, USA

Paulo Rodamilans Sanjuan MD

Chief Resident of Plastic Surgery
Plastic Surgery Service Dr. Ewaldo Bolivar de
Souza Pinto
São Paulo, Brazil

Nina Schwaiger, MD

Senior Specialist in Plastic and Aesthetic
Surgery
Department of Plastic Surgery
Dreifaltigkeits-Hospital Wesseling
Wesseling, Germany

Douglas S. Steinbrech, MD, FACS

Gotham Plastic Surgery
New York, NY, USA

Phillip J. Stephan, MD

Clinical Faculty
Plastic Surgery
UT Southwestern Medical School;
Plastic Surgeon
Texoma Plastic Surgery
Wichita Falls, TX, USA

David Gonzalez Sosa, MD

Plastic and Reconstructive Surgery
Hospital Quirónsalud Torrevieja
Alicante, Spain

James M. Stuzin, MD

Associate Professor of Surgery
(Plastic) Voluntary
University of Miami Leonard M. Miller School of
Medicine
Miami, FL, USA

Daniel Suissa, MD, MSc

Clinical Instructor
Section of Plastic and Reconstructive Surgery
Yale University
New Haven, CT, USA

Charles H. Thorne, MD

Associate Professor of Plastic Surgery
Department of Plastic Surgery
NYU School of Medicine
New York, NY, USA

Ali Totonchi, MD

Assistant Professor
Plastic Surgery
Case Western Reserve University;
Medical Director Craniofacial Deformity Clinic
Plastic Surgery
MetroHealth Medical center
Cleveland, OH, USA

Jonathan W. Toy, MD, FRCSC

Program Director, Plastic Surgery Residency
Program Assistant Clinical Professor
University of Alberta
Edmonton, Alberta, Canada

Matthew J. Trovato, MD

Dallas Plastic Surgery Institute
Dallas, TX, USA

Simeon H. Wall Jr., MD, FACS

Director
The Wall Center for Plastic Surgery;
Assistant Clinical Professor
Plastic Surgery
LSU Health Sciences Center at Shreveport
Shreveport, LA, USA

Joshua T. Waltzman, MD, MBA

Private Practice
Waltzman Plastic and Reconstructive Surgery
Long Beach, CA, USA

Richard J. Warren, MD, FRCSC

Clinical Professor
Division of Plastic Surgery
University of British Columbia
Vancouver, British Columbia, Canada

Edmund Weisberg, MS, MBE

University of Pennsylvania
Philadelphia, PA, USA

Scott Woehrlie, MS BS

Physician Assistant
Department of Plastic Surgery
Joseph Capella Plastic Surgery
Ramsey, NJ, USA

Chin-Ho Wong, MBBS, MRCS, MMed(Surg), FAMS(Plast Surg)

W Aesthetic Plastic Surgery
Mt Elizabeth Novena Specialist Center
Singapore

Alan Yan, MD

Former Fellow
Adult Reconstructive and Aesthetic
Craniofacial Surgery
Division of Plastic and Reconstructive Surgery
Massachusetts General Hospital
Boston, MA, USA

Michael J. Yaremchuk, MD

Chief of Craniofacial Surgery
Massachusetts General Hospital;
Clinical Professor of Surgery
Harvard Medical School;
Program Director
Harvard Plastic Surgery Residency Program
Boston, MA, USA

James E. Zins, MD

Chairman
Department of Plastic Surgery
Dermatology and Plastic Surgery Institute
Cleveland Clinic
Cleveland, OH, USA

VOLUME THREE**Neta Adler, MD**

Senior Surgeon
Department of Plastic and Reconstructive
Surgery
Hadassah University Hospital
Jerusalem, Israel

Ahmed M. Afifi, MD

Assistant Professor of Plastic Surgery
Department of Surgery
University of Wisconsin
Madison, WI, USA;
Associate Professor
Department of Plastic Surgery
Cairo University
Cairo, Egypt

Marta Alvarado, DDS, MS

Department of Orthodontics
Facultad de Odontología
Universidad de San Carlos de Guatemala
Guatemala

Eric Arnaud, MD

Pediatric Neurosurgeon and Co-Director
Unité de Chirurgie Craniofaciale
Hôpital Necker Enfants Malades
Paris, France

Stephen B. Baker, MD, DDS

Associate Professor and Program Director
Co-Director Inova Hospital for Children
Craniofacial Clinic
Department of Plastic Surgery
Georgetown University Hospital
Georgetown, WA, USA

Scott P. Bartlett, MD

Professor of Surgery
Surgery
University of Pennsylvania;
Chief Division of Plastic Surgery
Surgery
Children's Hospital of Philadelphia
Philadelphia, PA, USA

Bruce S. Bauer, MD

Chief
Division of Plastic Surgery
NorthShore University HealthSystem
Highland Park;
Clinical Professor of Surgery
Department of Surgery
University of Chicago Pritzker School of
Medicine
Chicago, IL, USA

Adriane L. Baylis, PhD

Speech Scientist
Section of Plastic and Reconstructive Surgery
Nationwide Children's Hospital
Columbus, OH, USA

Mike Bentz, MD, FAAP, FACS

Interim Chairman
Department of Surgery
University of Wisconsin;
Chairman Division of Plastic Surgery
Department of Surgery
University of Wisconsin
Madison, WI, USA

Craig Birgfeld, MD, FACS

Associate Professor, Pediatric Plastic and
Craniofacial Surgery
Seattle Children's Hospital
Seattle, WA, USA

William R. Boysen, MD

Resident Physician, Urology
University of Chicago Medicine
Chicago, IL, USA

James P. Bradley, MD

Professor and Chief
Section of Plastic and Reconstructive Surgery
Temple University
Philadelphia, PA, USA

Edward P. Buchanan, MD

Division of Plastic Surgery
Baylor College of Medicine
Houston, TX, USA

Michael R. Bykowski, MD, MS

Plastic Surgery Resident
Plastic Surgery
University of Pittsburgh Medical Center
Pittsburgh, PA, USA

Edward J. Caterson, MD, PhD

Director of Craniofacial Surgery
Division of Plastic Surgery
Brigham and Women's Hospital
Boston, MA, USA

Rodney K. Chan, MD

Chief Plastic and Reconstructive Surgery
Clinical Division and Burn Center
United States Army Institute of Surgical
Research
Joint Base San Antonio, TX, USA

Edward I. Chang, MD

Assistant Professor
Department of Plastic Surgery
The University of Texas M. D. Anderson Cancer
Center
Houston, TX, USA

Constance M. Chen, MD, MPH

Director of Microsurgery
Plastic and Reconstructive Surgery
New York Eye and Ear Infirmary of Mt Sinai;
Clinical Assistant Professor
Plastic and Reconstructive Surgery
Weil Medical College of Cornell University;
Clinical Assistant Professor
Plastic and Reconstructive Surgery
Tulane University School of Medicine
New York, NY, USA

Yu-Ray Chen, MD

Professor of Surgery
Plastic and Reconstructive Surgery
Chang Gung Memorial Hospital
Taoyuan City, Taiwan

Philip Kuo-Ting Chen, MD

Professor
Craniofacial Center
Chang Gung Memorial Hospital
Taoyuan City, Taiwan

Ming-Huei Cheng, MD, MBA

Professor
Division of Reconstructive Microsurgery
Department of Plastic and Reconstructive
Surgery
Chang Gung Memorial Hospital
Taoyuan City, Taiwan

Gerson R. Chinchilla, DDS MS

Director
Department of Orthodontics
Facultad de Odontología
Universidad de San Carlos de Guatemala
Guatemala

Peter G. Cordeiro, MD

Chief
Plastic and Reconstructive Surgery
Memorial Sloan Kettering Cancer Center;
Professor of Surgery
Surgery
Weil Medical College of Cornell University
New York, NY, USA

Alberto Córdova-Aguilar, MD, MPH

Attending Plastic Surgeon
Surgery
Faculty of Medicine Ricardo Palma University
Lima, Peru

Edward H. Davidson, MA(Cantab), MBBS

Resident Plastic Surgeon
Department of Plastic Surgery
University of Pittsburgh
Pittsburgh, PA, USA

Sara R. Dickie, MD

Clinician Educator
Surgery
University of Chicago Hospital Pritzker School of Medicine;
Attending Surgeon
Section of Plastic and Reconstructive Surgery
NorthShore University HealthSystem
Northbrook, IL, USA

Risal S. Djohan, MD

Microsurgery Fellowship Program Director
Plastic Surgery
Cleveland Clinic;
Surgery ASC Quality Improvement Officer
Plastic Surgery
Cleveland Clinic
Cleveland, OH, USA

Amir H. Dorafshar, MBChB, FACS, FAAP

Associate Professor
Plastic and Reconstructive Surgery
Johns Hopkins Medical Institute;
Assistant Professor
Plastic Surgery
R Adams Cowley Shock Trauma Center
Baltimore, MD, USA

Jeffrey A. Fearon, MD

Director
The Craniofacial Center
Dallas, TX, USA

Alexander L. Figueroa, DMD

Craniofacial Orthodontist
Rush Craniofacial Center
Rush University Medical Center
Chicago, IL, USA

Alvaro A. Figueroa, DDS, MS

Co-Director
Rush Craniofacial Center
Rush University Medical Center
Chicago, IL, USA

David M. Fisher, MB, BCh, FRCS, FACS

Medical Director Cleft Lip and Palate Program
Plastic Surgery
Hospital for Sick Children;
Associate Professor
Surgery
University of Toronto
Toronto, Ontario, Canada

Roberto L. Flores, MD

Associate Professor of Plastic Surgery
Director of Cleft Lip and Palate
Hansjörg Wyss Department of Plastic Surgery
NYU Langone Medical Center
New York, NY, USA

Andrew Foreman, B. Physio, BMBS(Hons), PhD, FRACS

Consultant Surgeon, Department of
Otolaryngology - Head and Neck Surgery
University of Adelaide,
Royal Adelaide Hospital,
Adelaide, SA, Australia

Patrick A. Gerety, MD

Assistant Professor of Surgery
Division of Plastic and Reconstructive Surgery
Indiana University and Riley Hospital for Children
Philadelphia, PA, USA

Jesse A. Goldstein, MD

Chief Resident
Department of Plastic Surgery
Georgetown University Hospital
Washington, DC, USA

Arun K. Gosain, MD

Chief
Division of Plastic Surgery
Ann and Robert H. Lurie Children's Hospital of Chicago
Chicago, IL, USA

Lawrence J. Gottlieb, MD

Professor of Surgery
Department of Surgery
Section of Plastic and Reconstructive Surgery
University of Chicago
Chicago, IL, USA

Arin K. Greene, MD, MMSc

Department of Plastic and Oral Surgery
Boston Children's Hospital;
Associate Professor of Surgery
Harvard Medical School
Boston, MA, USA

Patrick J. Gullane, MD, FRCS

Wharton Chair in Head and Neck Surgery
Professor of Surgery, Department of
Otolaryngology - Head and Neck Surgery
University of Toronto
Toronto, Ontario, Canada

Mohan S. Gundeti, MB, MCh, FEBU, FRCS(Urol), FEAPU

Associate Professor of Urology in Surgery and Pediatrics, Director Pediatric Urology, Director Centre for Pediatric Robotics and Minimal Invasive Surgery
University of Chicago and Pritzker Medical School Comer Children's Hospital
Chicago, IL, USA

Eyal Gur, MD

Professor of Surgery, Chief
Department of Plastic and Reconstructive Surgery
The Tel Aviv Sourasky Medical Center
Tel Aviv, Israel

Bahman Guyuron, MD, FCVS

Editor in Chief, Aesthetic Plastic Surgery Journal;
Emeritus Professor of Plastic Surgery
Case School of Medicine
Cleveland, OH, USA

Matthew M. Hanasono, MD

Associate Professor
Department of Plastic Surgery
The University of Texas MD Anderson Cancer Center
Houston, TX, USA

Toshinobu Harada, PhD

Professor in Engineering
Department of Systems Engineering
Faculty of Systems Engineering
Wakayama University
Wakayama, Japan

Jill A. Helms, DDS, PhD

Professor
Surgery
Stanford University
Stanford, CA, USA

David L. Hirsch, MD, DDS

Director of Oral Oncology and Reconstruction
Lenox Hill Hospital/Northwell Health
New York, NY, USA

Jung-Ju Huang, MD

Associate Professor
Division of Microsurgery
Plastic and Reconstructive Surgery
Chang Gung Memorial Hospital
Taoyuan, Taiwan

William Y. Hoffman, MD

Professor and Chief
Division of Plastic and Reconstructive Surgery
UCSF
San Francisco, CA, USA

Larry H. Hollier Jr., MD

Division of Plastic Surgery
Baylor College of Medicine
Houston, TX, USA

Richard A. Hopper, MD, MS

Chief
Division of Craniofacial Plastic Surgery
Seattle Children's Hospital;
Surgical Director
Craniofacial Center
Seattle Children's Hospital;
Associate Professor
Department of Surgery
University of Washington
Seattle, WA, USA

Gazi Hussain, MBBS, FRACS

Clinical Senior Lecturer
Macquarie University
Sydney, Australia

Oksana Jackson, MD

Assistant Professor
Plastic Surgery
Perelman School of Medicine at the University of Pennsylvania;
Assistant Professor
Plastic Surgery
The Children's Hospital of Philadelphia
Philadelphia, PA, USA

Syrl James, MD

Clinic Marcel Sembat
Boulogne-Billancourt
Paris, France

Leila Jazayeri, MD

Microsurgery Fellow
Plastic and Reconstructive Surgery
Memorial Sloan Kettering Cancer Center
New York, NY, USA

Sahil Kapur, MD

Assistant Professor
Department of Plastic Surgery
University of Texas - MD Anderson Cancer Center
Houston, TX, USA

Henry K. Kawamoto Jr., MD, DDS

Clinical Professor
Surgery Division of Plastic Surgery
UCLA
Los Angeles, CA, USA

David Y. Khechoyan, MD

Division of Plastic Surgery
Baylor College of Medicine
Houston, TX, USA

Richard E. Kirschner, MD

Section Chief
Plastic and Reconstructive Surgery
Nationwide Children's Hospital;
Senior Vice Chair
Plastic Surgery
The Ohio State University Medical College
Columbus, OH, USA

John C. Koshy, MD

Division of Plastic Surgery
Baylor College of Medicine
Houston, TX, USA

Michael C. Large, MD

Urologic Oncologist
Urology of Indiana
Greenwood, IN, USA

Edward I. Lee, MD

Division of Plastic Surgery
Baylor College of Medicine
Houston, TX, USA

Jamie P. Levine, MD

Chief of Microsurgery
Associate Professor
Plastic Surgery
NYU Langone Medical Center
New York, NY, USA

Jingtao Li, DDS, PhD

Consultant Surgeon
Oral and Maxillofacial Surgery
West China Hospital of Stomatology
Chengdu, Sichuan, People's Republic of China

Lawrence Lin, MD

Division of Plastic Surgery
Baylor College of Medicine
Houston, TX, USA

Joseph E. Losee, MD

Ross H. Musgrave Professor of Pediatric Plastic Surgery
Department of Plastic Surgery
University of Pittsburgh Medical Center;
Chief, Division of Pediatric Plastic Surgery
Children's Hospital of Pittsburgh
Pittsburgh, PA, USA

David W. Low, MD

Professor of Surgery
Division of Plastic Surgery
Perelman School of Medicine at the University of Pennsylvania;
Clinical Associate
Department of Surgery
Children's Hospital of Philadelphia
Philadelphia, PA, USA

Ralph T. Manktelow, MD, FRCSC

Professor of Surgery,
The University of Toronto,
Toronto, Ontario, Canada

Paul N. Manson, MD

Distinguished Service Professor
Plastic Surgery
Johns Hopkins University
Baltimore, MD, USA

David W. Mathes, MD

Professor and Chief of the Division of Plastic and Reconstructive Surgery
Surgery Division of Plastic and Reconstructive Surgery
University of Colorado
Aurora, CO, USA

Frederick J. Menick, MD

Private Practitioner
Tucson, AZ, USA

Fernando Molina, MD

Director
Craniofacial Anomalies Foundation A.C.
Mexico City;
Professor of Plastic Reconstructive and Aesthetic Surgery
Medical School
Universidad La Salle
Mexico City, Distrito Federal, Mexico

Laura A. Monson, MD

Division of Plastic Surgery
Baylor College of Medicine
Houston, TX, USA

Reid V. Mueller, MD

Associate Professor
Plastic Surgery
Oregon Health and Science University
Portland, OR, USA

John B. Mulliken, MD

Professor
Department of Plastic and Oral Surgery
Boston Children's Hospital
Harvard Medical School
Boston, MA, USA

Gerhard S. Munding, MD

Assistant Professor
Craniofacial, Plastic, and Reconstructive Surgery
Louisiana State University Health Sciences Center
Children's Hospital of New Orleans
New Orleans, LA, USA

Blake D. Murphy, BSc, PhD, MD

Craniofacial Fellow
Plastic Surgery
Nicklaus Children's Hospital
Miami, FL, USA

Peter C. Neligan, MB, FRCS(I), FRCSC, FACS

Professor of Surgery
Department of Surgery, Division of Plastic Surgery
University of Washington
Seattle, WA, USA

M. Samuel Noordhoff, MD, FACS

Emeritus Professor in Surgery
Chang Gung University
Taoyuan City, Taiwan

Giovanna Paternoster, MD

Unité de chirurgie crânio-faciale du département de neurochirurgie
Hôpital Necker Enfants Malades
Paris, France

Jason Pomerantz, MD

Assistant Professor
Surgery
University of California San Francisco;
Surgical Director
Craniofacial Center
University of California San Francisco
San Francisco, CA, USA

Julian J. Pribaz, MD

Professor of Surgery
University of South Florida, Morsani College of Medicine
Tampa General Hospital
Tampa, FL, USA

Chad A. Purnell, MD

Division of Plastic Surgery
Lurie Children's Hospital of Northwestern
Feinberg School of Medicine
Chicago, IL, USA

Russell R. Reid, MD, PhD

Associate Professor
Surgery/Section of Plastic and Reconstructive Surgery
University of Chicago Medicine
Chicago, IL, USA

Eduardo D. Rodriguez, MD, DDS

Helen L. Kimmel Professor of Reconstructive Plastic Surgery
Chair, Hansjörg Wyss Department of Plastic Surgery
NYU School of Medicine
NYU Langone Medical Center
New York, NY, USA

Craig Rowin, MD

Craniofacial Fellow
Plastic Surgery
Nicklaus Children's Hospital
Miami, FL, USA

Ruston J. Sanchez, MD

Plastic and Reconstructive Surgery Resident
University of Wisconsin
Madison, WI, USA

Lindsay A. Schuster, DMD, MS

Director Cleft-Craniofacial Orthodontics
Pediatric Plastic Surgery
Children's Hospital of Pittsburgh of UPMC;
Clinical Assistant Professor of Plastic Surgery
Department of Plastic Surgery
University of Pittsburgh School of Medicine
Pittsburgh, PA, USA

Jeremiah Un Chang See, MD

Plastic Surgeon
Department of Plastic and Reconstructive
Surgery
Penang General Hospital
Georgetown, Penang, Malaysia

Pradip R. Shetye, DDS, BDS, MDS

Assistant Professor (Orthodontics)
Hansjörg Wyss Department of Plastic Surgery
NYU Langone Medical Center
New York, NY, USA

Roman Skoracki, MD

Plastic Surgery
The Ohio State University
Columbus, OH, USA

Mark B. Slidell, MD, MPH

Assistant Professor of Surgery
Department of Surgery
Section of Pediatric Surgery
University of Chicago Medicine Biological
Sciences
Chicago, IL, USA

Michael Sosin, MD

Research Fellow
Department of Plastic Surgery Institute of
Reconstructive Plastic Surgery
NYU Langone Medical Center
New York, NY, USA;
Research Fellow
Division of Plastic Reconstructive and
Maxillofacial Surgery
R Adams Cowley Shock Trauma Center
University of Maryland Medical Center
Baltimore, MD, USA;
Resident
Department of Surgery
Medstar Georgetown University Hospital
Washington, DC, USA

Youssef Tahiri, MD, MSc, FRCSC, FAAP, FACS

Associate Professor
Pediatric Plastic & Craniofacial Surgery
Cedars Sinai Medical Center
Los Angeles, CA, USA

Peter J. Taub, MD

Professor
Surgery Pediatrics Dentistry and Medical
Education
Surgery Division of Plastic and Reconstructive
Surgery
Icahn School of Medicine at Mount Sinai
New York, NY, USA

Jesse A. Taylor, MD

Mary Downs Endowed Chair of Pediatric
Craniofacial Treatment and Research;
Director, Penn Craniofacial Fellowship;
Co-Director, CHOP Cleft Team
Plastic, Reconstructive, and Craniofacial Surgery
The University of Pennsylvania and
Children's Hospital of Philadelphia
Philadelphia, PA, USA

Kathryn S. Torok, MD

Assistant Professor
Pediatric Rheumatology
University of Pittsburgh
Pittsburgh, PA, USA

Ali Totonchi, MD

Assistant Professor
Plastic Surgery
Case Western Reserve University;
Medical Director Craniofacial Deformity Clinic
Plastic Surgery
MetroHealth Medical Center
Cleveland, OH, USA

Kris Wilson, MD

Division of Plastic Surgery
Baylor College of Medicine
Houston, TX, USA

S. Anthony Wolfe, MD

Plastic Surgery
Miami Children's Hospital
Miami, FL, USA

Akira Yamada, MD, PhD

Professor of Plastic Surgery
World Craniofacial Foundation
Dallas, TX, USA;
Clinical Assistant Professor
Plastic Surgery
Case Western Reserve University
Cleveland, OH, USA

Peirong Yu, MD

Professor
Plastic Surgery
M. D. Anderson Cancer Center;
Adjunct Professor
Plastic Surgery
Baylor College of Medicine
Houston, TX, USA

Ronald M. Zuker, MD, FRCSC, FACS, FRCSEd(Hon)

Professor of Surgery
Department of Surgery
University of Toronto;
Staff Plastic and Reconstructive Surgeon
Department of Surgery
SickKids Hospital
Toronto, Ontario, Canada

VOLUME FOUR**Christopher E. Attinger, MD**

Professor, Interim Chairman
Department of Plastic Surgery
Center for Wound Healing
Medstar Georgetown University Hospital
Washington, DC, USA

Lorenzo Borghese, MD

Plastic Surgeon
Chief of International Missions
Ospedale Pediatrico Bambino Gesù
Rome, Italy

Charles E. Butler, MD, FACS

Professor and Chairman
Department of Plastic Surgery
Charles B. Barker Endowed Chair in Surgery
The University of Texas M. D. Anderson Cancer
Center
Houston, TX, USA

David W. Chang, MD

Professor of Surgery
University of Chicago
Chicago, IL, USA

Karel Claes, MD

Department of Plastic and Reconstructive
Surgery
Ghent University Hospital
Ghent, Belgium

Mark W. Clemens II, MD, FACS

Associate Professor
Plastic Surgery
MD Anderson Cancer Center,
Houston, TX, USA

Shannon M. Colohan, MD, MSc

Assistant Professor of Surgery
University of Washington
Seattle, WA, USA

Peter G. Cordeiro, MD

Chief
Plastic and Reconstructive Surgery
Memorial Sloan Kettering Cancer Center
New York, NY, USA

Salvatore D'Arpa, MD, PhD

Department of Plastic and Reconstructive
Surgery
Ghent University Hospital
Ghent, Belgium

Michael V. DeFazio, MD

Department Plastic Surgery
MedStar Georgetown University Hospital
Washington, DC, USA

A. Lee Dellon, MD, PhD

Professor of Plastic Surgery
Professor of Neurosurgery
Johns Hopkins University
Baltimore, MD, USA

Sara R. Dickie, MD

Clinical Associate of Surgery
University of Chicago Hospitals
Pritzker School of Medicine
Chicago, IL, USA

Ivica Ducic, MD, PhD

Clinical Professor of Surgery
GWU Washington Nerve Institute
McLean, VA, USA

Gregory A. Dumanian, MD

Stuteville Professor of Surgery
Division of Plastic Surgery
Northwestern Feinberg School of Medicine
Chicago, IL, USA

John M. Felder III, MD

Fellow in Hand Surgery
Plastic Surgery
Washington University in Saint Louis
St. Louis, MO, USA

Goetz A. Giessler, MD, PhD

Professor Director
Plastic-Reconstructive, Aesthetic and Hand
Surgery
Gesundheit Nordhessen
Kassel, Germany

Kevin D. Han, MD

Department of Plastic Surgery
MedStar Georgetown University Hospital
Washington, DC, USA

Piet Hoebeke

Department of Urology
Ghent University Hospital
Ghent, Belgium

Joon Pio Hong, MD, PhD, MMM

Professor of Plastic Surgery
Asan Medical Center, University of Ulsan
Seoul, South Korea

Michael A. Howard, MD

Clinical Assistant Professor of Surgery
Plastic Surgery
NorthShore University HealthSystem/University
of Chicago
Chicago, IL, USA

Jeffrey E. Janis, MD, FACS

Professor of Plastic Surgery, Neurosurgery,
Neurology, and Surgery;
Executive Vice Chairman, Department of Plastic
Surgery;
Chief of Plastic Surgery, University Hospitals
Ohio State University Wexner Medical Center
Columbus, OH, USA

Leila Jazayeri, MD

Microsurgery Fellow
Plastic and Reconstructive Surgery
Memorial Sloan Kettering Cancer Center
New York, NY, USA

Grant M. Kleiber, MD

Assistant Professor of Surgery
Division of Plastic and Reconstructive Surgery
Washington University School of Medicine
St. Louis, MO, USA

Stephen J. Kovach III, MD

Assistant Professor
Division of Plastic Surgery
University of Pennsylvania
Philadelphia, PA, USA

Robert Kwon, MD

Southwest Hand and Microsurgery
3108 Midway Road, Suite 103
Plano, TX, USA

Raphael C. Lee, MS, MD, ScD, FACS, FAIMBE

Paul and Allene Russell Professor
Plastic Surgery, Dermatology, Anatomy and
Organismal Biology, Molecular Medicine
University of Chicago
Chicago, IL, USA

L. Scott Levin, MD, FACS

Chairman of Orthopedic Surgery
Department of Orthopaedic Surgery
University of Pennsylvania School of Medicine
Philadelphia, PA, USA

Otway Louie, MD

Associate Professor
Surgery
University of Washington Medical Center
Seattle, WA, USA

Nicolas Lumen, MD, PhD

Head of Clinic
Urology
Ghent University Hospital
Ghent, Belgium

Alessandro Masellis, MD

Plastic Surgeon
Euro-Mediterranean Council for Burns and Fire
Disasters
Palermo, Italy

Michele Masellis, MD

Former Chief of Department of Plastic and
Reconstructive Surgery and Burn Therapy
Department of Plastic and Reconstructive
Surgery and Burn Therapy - ARNAS Ospedale
Civico e Benfratelli
Palermo, Italy

Stephen M. Milner, MB BS, BDS

Professor of Plastic Surgery
Surgery
Johns Hopkins School of Medicine
Baltimore, MD, USA

Arash Momeni, MD

Fellow, Reconstructive Microsurgery
Division of Plastic Surgery
University of Pennsylvania Health System
Philadelphia, PA, USA

Stan Monstrey, MD, PhD

Department of Plastic and Reconstructive
Surgery
Ghent University Hospital
Ghent, Belgium

Venkateshwaran N, MBBS, MS, DNB, MCh, MRCS(Intercollegiate)

Consultant Plastic Surgeon
Jupiter Hospital
Thane, India

Rajiv P. Parikh, MD, MPH

Resident Physician
Department of Surgery, Division of Plastic and
Reconstructive Surgery
Washington University School of Medicine
St. Louis, MO, USA

Mônica Sarto Piccolo, MD, MSc, PhD

Director
Pronto Socorro para Queimaduras
Goiânia, Goiás, Brazil

Nelson Sarto Piccolo, MD

Chief
Division of Plastic Surgery
Pronto Socorro para Queimaduras
Goiânia, Goiás, Brazil

Maria Thereza Sarto Piccolo, MD, PhD

Scientific Director
Pronto Socorro para Queimaduras
Goiânia, Goiás, Brazil

Vinita Puri, MS, MCh

Professor and Head
Department of Plastic, Reconstructive Surgery
and Burns
Seth G S Medical College and KEM Hospital
Mumbai, Maharashtra, India

Andrea L. Pusic, MD, MHS, FACS

Associate Professor
Plastic and Reconstructive Surgery
Memorial Sloan Kettering Cancer Center
New York, NY, USA

Vinay Rawlani, MD

Division of Plastic Surgery
Northwestern Feinberg School of Medicine
Chicago, IL, USA

Juan L. Rendon, MD, PhD

Clinical Instructor Housestaff
Department of Plastic Surgery
The Ohio State University Wexner Medical Center
Columbus, OH, USA

Michelle C. Roughton, MD

Assistant Professor
Division of Plastic and Reconstructive Surgery
University of North Carolina at Chapel Hill
Chapel Hill, NC, USA

Hakim K. Said, MD, FACS

Associate Professor
Division of Plastic surgery
University of Washington
Seattle, WA, USA

Michel Saint-Cyr, MD, FRSC(C)

Professor
Plastic Surgery
Mayo Clinic
Rochester, MN, USA

Michael Sauerbier, MD, PhD

Professor, Chair
Department for Plastic, Hand, and Reconstructive Surgery
Academic Hospital Goethe University Frankfurt am Main
Frankfurt am Main, Germany

Loren S. Schechter, MD

Associate Professor and Chief
Division of Plastic Surgery
Chicago Medical School
Morton Grove, IL, USA

David H. Song, MD, MBA, FACS

Regional Chief, MedStar Health
Plastic and Reconstructive Surgery
Professor and Chairman
Department of Plastic Surgery
Georgetown University School of Medicine
Washington, DC, USA

Yoo Joon Sur, MD, PhD

Associate Professor
Department of Orthopedic Surgery
The Catholic University of Korea, College of Medicine
Seoul, Korea

Chad M. Teven, MD

Resident
Section of Plastic and Reconstructive Surgery
University of Chicago
Chicago, IL, USA

VOLUME FIVE**Jamil Ahmad, MD, FRCSC**

Director of Research and Education
The Plastic Surgery Clinic
Mississauga, Ontario, Canada;
Assistant Professor of Surgery
University of Toronto
Toronto, Ontario, Canada

Robert J. Allen Sr., MD

Clinical Professor of Plastic Surgery
Department of Plastic Surgery
New York University Medical Center
Charleston, NC, USA

Ryan E. Austin, MD, FRCSC

Plastic Surgeon
The Plastic Surgery Clinic
Mississauga, ON, Canada

Brett Beber, BA, MD, FRCSC

Plastic and Reconstructive Surgeon
Lecturer, Department of Surgery
University of Toronto
Toronto, Ontario, Canada

Philip N. Blondeel, MD

Professor of Plastic Surgery
Department of Plastic Surgery
University Hospital Ghent
Ghent, Belgium

Benjamin J. Brown, MD

Gulf Coast Plastic Surgery
Pensacola, FL, USA

Mitchell H. Brown, MD, MEd, FRCSC

Plastic and Reconstructive Surgeon
Associate Professor, Department of Surgery
University of Toronto
Toronto, Ontario, Canada

M. Bradley Calobrace, MD, FACS

Plastic Surgeon
Calobrace and Mizuguchi Plastic Surgery Center
Departments of Surgery, Divisions of Plastic Surgery
Clinical Faculty, University of Louisville and University of Kentucky
Louisville, KY, USA

Grant W. Carlson, MD

Wadley R. Glenn Professor of Surgery
Emory University
Atlanta, GA, USA

Bernard W. Chang, MD

Chief of Plastic and Reconstructive Surgery
Mercy Medical Center
Baltimore, MD, USA

Mark W. Clemens II, MD, FACS

Assistant Professor Plastic Surgery
M. D. Anderson Cancer Center
Houston, TX, USA

Robert Cohen MD, FACS

Medical Director
Plastic Surgery
Scottsdale Center for Plastic Surgery
Paradise Valley, AZ and;
Santa Monica, CA, USA

Amy S. Colwell, MD

Associate Professor
Harvard Medical School
Massachusetts General Hospital
Boston, MA, USA

Edward H. Davidson, MA(Cantab), MB, BS

Resident Plastic Surgeon
Department of Plastic Surgery
University of Pittsburgh Medical Center
Pittsburgh, PA, USA

Emmanuel Delay, MD, PhD

Unité de Chirurgie Plastique et Reconstructrice
Centre Léon Bérard
Lyon, France

Francesco M. Egro, MB ChB, MSc, MRCS

Department of Plastic Surgery
University of Pittsburgh Medical Center
Pittsburgh, PA, USA

Neil A. Fine, MD

President
Northwestern Specialists in Plastic Surgery;
Associate Professor (Clinical) Surgery/Plastics
Northwestern University Feinberg School of Medicine
Chicago, IL, USA

Jaime Flores, MD

Plastic and Reconstructive Microvascular Surgeon
Miami, FL, USA

Joshua Fosnot, MD

Assistant Professor of Surgery
Division of Plastic Surgery
The Perelman School of Medicine
University of Pennsylvania Health System
Philadelphia, PA, USA

Allen Gabriel, MD

Clinical Associate Professor
Department of Plastic Surgery
Loma Linda University Medical Center
Loma Linda, CA, USA

Michael S. Gart, MD

Resident Physician
Division of Plastic Surgery
Northwestern University Feinberg School of Medicine
Chicago, IL, USA

Matthew D. Goodwin, MD

Plastic Surgeon
Plastic Reconstructive and Cosmetic Surgery
Boca Raton Regional Hospital
Boca Raton, FL, USA

Samia Guerid, MD

Cabinet
50 rue de la République
Lyon, France

Moustapha Hamdi, MD, PhD

Professor of Plastic and Reconstructive Surgery
Brussels University Hospital
Vrij Universitaire Brussels
Brussels, Belgium

Alexandra M. Hart, MD

Emory Division of Plastic and Reconstructive Surgery
Emory University School of Medicine
Atlanta, GA, USA

Emily C. Hartmann, MD, MS

Aesthetic Surgery Fellow
Plastic and Reconstructive Surgery
University of Southern California
Los Angeles, CA, USA

Nima Khavanin, MD

Resident Physician
Department of Plastic and Reconstructive Surgery
Johns Hopkins Hospital
Baltimore, MD, USA

John Y. S. Kim, MD

Professor and Clinical Director
Department of Surgery
Division of Plastic Surgery
Northwestern University Feinberg School of Medicine
Chicago, IL, USA

Steven Kronowitz, MD

Owner, Kronowitz Plastics
PLLC;
University of Texas, M. D. Anderson Medical Center
Houston, TX, USA

John V. Larson, MD

Resident Physician
Division of Plastic and Reconstructive Surgery
Keck School of Medicine of USC
University of Southern California
Los Angeles, CA, USA

Z-Hye Lee, MD

Resident
Department of Plastic Surgery
New York University Medical Center
New York, NY, USA

Frank Lista, MD, FRCS

Medical Director
The Plastic Surgery Clinic
Mississauga, Ontario, Canada;
Assistant Professor Surgery
University of Toronto
Toronto, Ontario, Canada

Albert Losken, MD, FACS

Professor of plastic surgery and Program Director
Emory Division of Plastic and Reconstructive Surgery
Emory University School of Medicine
Atlanta, GA, USA

Charles M. Malata, BSc(HB), MB ChB, LRCP, MRCS, FRCS(Glasg), FRCS(Plast)

Professor of Academic Plastic Surgery
Postgraduate Medical Institute
Faculty of Health Sciences
Anglia Ruskin University
Cambridge and Chelmsford, UK;
Consultant Plastic and Reconstructive Surgeon
Department of Plastic and Reconstructive Surgery
Cambridge Breast Unit at Addenbrooke's Hospital
Cambridge University Hospitals NHS Foundation Trust
Cambridge, UK

Jaume Masià, MD, PhD

Chief and Professor of Plastic Surgery
Sant Pau University Hospital
Barcelona, Spain

G. Patrick Maxwell, MD, FACS

Clinical Professor of Surgery
Department of Plastic Surgery
Loma Linda University Medical Center
Loma Linda, CA, USA

James L. Mayo, MD

Microsurgery Fellow
Plastic Surgery
New York University
New York, NY, USA

Roberto N. Miranda, MD

Professor
Department of Hematopathology
Division of Pathology and Laboratory Medicine
MD Anderson Cancer Center
Houston, TX, USA

Colin M. Morrison, MSc (Hons) FRCSI (Plast)

Consultant Plastic Surgeon
St. Vincent's University Hospital
Dublin, Ireland

Maurice Y. Nahabedian, MD, FACS

Professor and Chief
Section of Plastic Surgery
MedStar Washington Hospital Center
Washington DC, USA;
Vice Chairman
Department of Plastic Surgery
MedStar Georgetown University Hospital
Washington DC, USA

James D. Namnoum, MD

Clinical Professor of Plastic Surgery
Atlanta Plastic Surgery
Emory University School of Medicine
Atlanta, GA, USA

Maria E. Nelson, MD

Assistant Professor of Clinical Surgery
Department of Surgery, Division of Upper GI/
General Surgery, Section of Surgical Oncology
Keck School of Medicine
University of Southern California
Los Angeles, CA, USA

Julie Park, MD

Associate Professor of Surgery
Section of Plastic Surgery
University of Chicago
Chicago, IL, USA

Ketan M. Patel, MD

Assistant Professor of Surgery
Division of Plastic and Reconstructive Surgery
Keck Medical Center of USC
University of Southern California
Los Angeles, CA, USA

Nakul Gamanlal Patel, BSc(Hons), MBBS(Lond), FRCS(Plast)

Senior Microsurgery Fellow
St. Andrew's Centre for Plastic Surgery
Broomfield Hospital
Chelmsford, UK

Gemma Pons, MD, PhD

Head
Microsurgery Unit
Plastic Surgery
Hospital de Sant Pau
Barcelona, Spain

Julian J. Pribaz, MD

Professor of Surgery
Brigham and Women's Hospital
Harvard Medical School
Boston, MA, USA

Venkat V. Ramakrishnan, MS, FRCS, FRACS(Plast Surg)

Consultant Plastic Surgeon
St. Andrew's Centre for Plastic Surgery
Broomfield Hospital
Chelmsford, UK

Elena Rodríguez-Bauzá, MD

Plastic Surgery Department
Hospital Santa Creu i Sant Pau
Barcelona, Spain

Michael R. Schwartz, MD

Board Certified Plastic Surgeon
Private Practice
Westlake Village, CA, USA

Stephen F. Sener, MD

Professor of Surgery, Clinical Scholar
Chief of Breast, Endocrine, and Soft Tissue Surgery
Department of Surgery, Keck School of Medicine of USC
Chief of Surgery and Associate Medical Director
Perioperative Services
LAC+USC (LA County) Hospital
Los Angeles, CA, USA

Joseph M. Serletti, MD, FACS

The Henry Royster–William Maul Measey
Professor of Surgery and Chief
Division of Plastic Surgery
University of Pennsylvania Health System
Philadelphia, PA, USA

Deana S. Shenaq, MD

Chief Resident
Department of Surgery - Plastic Surgery
The University of Chicago Hospitals
Chicago, IL, USA

Kenneth C. Shestak, MD

Professor, Department of Plastic Surgery
University of Pittsburgh Medical Center
Pittsburgh, PA, USA

Ron B. Somogyi, MD MSc FRCSC

Plastic and Reconstructive Surgeon
Assistant Professor, Department of Surgery
University of Toronto
Toronto, ON, Canada

David H. Song, MD, MBA, FACS

Regional Chief, MedStar Health
Plastic and Reconstructive Surgery
Professor and Chairman
Department of Plastic Surgery
Georgetown University School of Medicine
Washington, DC, USA

The late Scott L. Spear[†], MD

Formerly Professor of Plastic Surgery
Division of Plastic Surgery
Georgetown University
Washington, MD, USA

Michelle A. Spring, MD, FACS

Program Director
Glacier View Plastic Surgery
Kalispell Regional Medical Center
Kalispell, MT, USA

W. Grant Stevens, MD, FACS

Clinical Professor of Surgery
Marina Plastic Surgery Associates;
Keck School of Medicine of USC
Los Angeles, CA, USA

Elizabeth Stirling Craig, MD

Plastic Surgeon and Assistant Professor
Department of Plastic Surgery
University of Texas
MD Anderson Cancer Center
Houston, TX, USA

Simon G. Talbot, MD

Assistant Professor of Surgery
Brigham and Women's Hospital
Harvard Medical School
Boston, MA, USA

Jana Van Thielen, MD

Plastic Surgery Department
Brussels University Hospital
Vrij Universitaire Brussel (VUB)
Brussels, Belgium

Henry Wilson, MD, FACS

Attending Plastic Surgeon
Private Practice
Plastic Surgery Associates
Lynchburg, VA, USA

Kai Yuen Wong, MA, MB BChir, MRCS, FHEA, FRSPH

Specialist Registrar in Plastic Surgery
Department of Plastic and Reconstructive
Surgery
Cambridge University Hospitals NHS
Foundation Trust
Cambridge, UK

VOLUME SIX**Hee Chang Ahn, MD, PhD**

Professor
Department of Plastic and Reconstructive
Surgery
Hanyang University Hospital School of Medicine
Seoul, South Korea

Nidal F. Al Deek, MD

Surgeon
Plastic and Reconstructive Surgery
Chang Gung Memorial Hospital
Taipei, Taiwan

Kodi K. Azari, MD, FACS

Reconstructive Transplantation Section Chief
Professor
Department of Orthopedic Surgery
UCLA Medical Center
Santa Monica, CA, USA

Carla Baldrighi, MD

Staff Surgeon
Pediatric Surgery Meyer Children's Hospital
Pediatric Hand and Reconstructive Microsurgery
Unit
Azienda Ospedaliera Universitaria Careggi
Florence, Italy

Gregory H. Borschel, MD, FAAP, FACS

Assistant Professor
University of Toronto Division of Plastic and
Reconstructive Surgery;
Assistant Professor
Institute of Biomaterials and Biomedical
Engineering;
Associate Scientist
The SickKids Research Institute
The Hospital for Sick Children
Toronto, Ontario, Canada

Kirsty Usher Boyd, MD, FRCSC

Assistant Professor
Division of Plastic Surgery, University of Ottawa
Ottawa, Ontario, Canada

Gerald Brandacher, MD

Scientific Director
Department of Plastic and Reconstructive
Surgery
Johns Hopkins University School of Medicine
Baltimore, MD, USA

Lesley Butler, MPH

Clinical Research Coordinator
Charles E. Seay, Jr. Hand Center
Texas Scottish Rite Hospital for Children
Dallas, TX, USA

Ryan P. Calfee, MD

Associate Professor
Department of Orthopedic Surgery
Washington University School of Medicine
St. Louis, MO, USA

Brian T. Carlsen, MD

Associate Professor
Departments of Plastic Surgery and Orthopedic
Surgery
Mayo Clinic
Rochester, MN, USA

David W. Chang, MD

Professor
Division of Plastic and Reconstructive Surgery
The University of Chicago Medicine
Chicago, IL, USA

James Chang, MD

Johnson & Johnson Distinguished Professor
and Chief
Division of Plastic and Reconstructive Surgery
Stanford University Medical Center
Stanford, CA, USA

Robert A. Chase, MD

Holman Professor of Surgery – Emeritus
Stanford University Medical Center
Stanford, CA, USA

Alphonsus K. S. Chong, MBBS, MRCS, MMed(Orth), FAMS (Hand Surg)

Senior Consultant
Department of Hand and Reconstructive
Microsurgery
National University Health System
Singapore;
Assistant Professor
Department of Orthopedic Surgery
Yong Loo Lin School of Medicine
National University of Singapore
Singapore

David Chwei-Chin Chuang, MD

Senior Consultant, Ex-President, Professor
Department of Plastic Surgery
Chang Gung University Hospital
Tao-Yuan, Taiwan

Kevin C. Chung, MD, MS

Chief of Hand Surgery
Michigan Medicine
Charles B G De Nancrede Professor, Assistant
Dean for Faculty Affairs
University of Michigan Medical School
Ann Arbor, Michigan, USA

Christopher Cox, MD

Attending Surgeon
Kaiser Permanente
Walnut Creek, CA, USA

Catherine Curtin, MD

Associate Professor
Department of Surgery Division of Plastic Surgery
Stanford University
Stanford, CA, USA

Lars B. Dahlin, MD, PhD

Professor and Consultant
Department of Clinical Sciences, Malmö – Hand Surgery
University of Lund
Malmö, Sweden

Kenneth W. Donohue, MD

Hand Surgery Fellow
Division of Plastic Surgery
Department of Orthopedic Surgery
Baylor College of Medicine
Houston, TX, USA

Gregory A. Dumanian, MD, FACS

Stuteville Professor of Surgery
Division of Plastic Surgery
Northwestern Feinberg School of Medicine
Chicago, IL, USA

William W. Dzwierzynski, MD

Professor and Program Director
Department of Plastic Surgery
Medical College of Wisconsin
Milwaukee, WI, USA

Simon Farnebo, MD, PhD

Associate Professor and Consultant Hand Surgeon
Department of Plastic Surgery, Hand Surgery and Burns
Institution of Clinical and Experimental Medicine, University of Linköping
Linköping, Sweden

Ida K. Fox, MD

Assistant Professor of Plastic Surgery
Department of Surgery
Division of Plastic and Reconstructive Surgery
Washington University School of Medicine
St. Louis, MO, USA

Paige M. Fox, MD, PhD

Assistant Professor
Department of Surgery, Division of Plastic and Reconstructive Surgery
Stanford University Medical Center
Stanford, CA, USA

Jeffrey B. Friedrich, MD

Professor of Surgery and Orthopedics
Department of Surgery, Division of Plastic Surgery
University of Washington
Seattle, WA, USA

Steven C. Haase, MD, FACS

Associate Professor
Department of Surgery, Section of Plastic Surgery
University of Michigan Health
Ann Arbor, MI, USA

Elisabet Hagert, MD, PhD

Associate Professor
Department of Clinical Science and Education
Karolinska Institute;
Chief Hand Surgeon
Hand Foot Surgery Center
Stockholm, Sweden

Warren C. Hammert, MD

Professor of Orthopedic and Plastic Surgery
Chief, Division of Hand Surgery
Department of Orthopedics and Rehabilitation
University of Rochester
Rochester, NY, USA

Isaac Harvey, MD

Clinical Fellow
Department of Pediatric Plastic and Reconstructive Surgery
Hospital for SickKids
Toronto, Ontario, Canada

Vincent R. Hentz, MD

Emeritus Professor of Surgery and Orthopedic Surgery (by courtesy)
Stanford University
Stanford, CA, USA

Jonay Hill, MD

Clinical Assistant Professor
Anesthesiology, Perioperative and Pain Medicine
Stanford University School of Medicine
Stanford, CA, USA

Steven E. R. Hovius, MD, PhD

Former Head, Department of Plastic, Reconstructive and Hand Surgery
Erasmus MC
University Medical Center
Rotterdam, the Netherlands;
Xpert Clinic, Hand and Wrist Center
The Netherlands

Jerry I. Huang, MD

Associate Professor
Department of Orthopedics and Sports Medicine
University of Washington;
Program Director
University of Washington Hand Fellowship
University of Washington
Seattle, WA, USA

Marco Innocenti, MD

Associate Professor of Plastic Surgery,
University of Florence;
Director, Reconstructive Microsurgery
Department of Oncology
Careggi University Hospital
Florence, Italy

Neil F. Jones, MD, FRCS

Professor and Chief of Hand Surgery
University of California Medical Center;
Professor of Orthopedic Surgery;
Professor of Plastic and Reconstructive Surgery
University of California Irvine
Irvine, CA, USA

Ryosuke Kakinoki, MD, PhD

Professor of Hand Surgery and Microsurgery, Reconstructive, and Orthopedic Surgery
Department of Orthopedic Surgery
Faculty of Medicine
Kindai University
Osakasayama, Osaka, Japan

Jason R. Kang, MD

Chief Resident
Department of Orthopedic Surgery
Stanford Hospital & Clinics
Redwood City, CA, USA

Joseph S. Khouri, MD

Resident
Division of Plastic Surgery, Department of Surgery
University of Rochester
Rochester, NY, USA

Todd Kuiken, MD, PhD

Professor
Departments of PM&R, BME, and Surgery
Northwestern University;
Director, Neural Engineering Center for Artificial Limbs
Rehabilitation Institute of Chicago
Chicago, IL, USA

Donald Lalonde, BSc, MD, MSc, FRCS

Professor of Surgery
Division of Plastic and Reconstructive Surgery
Saint John Campus of Dalhousie University
Saint John, New Brunswick, Canada

W. P. Andrew Lee, MD

The Milton T. Edgerton MD, Professor and Chairman
Department of Plastic and Reconstructive Surgery
Johns Hopkins University School of Medicine
Baltimore, MD, USA

Anais Legrand, MD

Postdoctoral Research Fellow
Plastic and Reconstructive Surgery
Stanford University Medical Center
Stanford, CA, USA

Terry Light, MD

Professor
Department of Orthopedic Surgery
Loyola University Medical Center
Maywood, IL, USA

Jin Xi Lim, MBBS, MRCS

Senior Resident
Department of Hand and Reconstructive Microsurgery
National University Health System
Singapore

Joseph Lopez, MD, MBA

Resident, Plastic and Reconstructive Surgery
Department of Plastic and Reconstructive Surgery
Johns Hopkins University School of Medicine
Baltimore, MD, USA

Susan E. Mackinnon, MD

Sydney M. Shoenberg, Jr. and Robert H. Shoenberg Professor
Department of Surgery, Division of Plastic and Reconstructive Surgery
Washington University School of Medicine
St. Louis, MO, USA

Brian Mailey, MD

Assistant Professor of Surgery
Institute for Plastic Surgery
Southern Illinois University
Springfield, IL, USA

Steven J. McCabe, MD, MSc, FRCS(C)

Director of Hand and Upper Extremity Program
University of Toronto
Toronto Western Hospital
Toronto, Ontario, Canada

Kai Megerle, MD, PhD

Assistant Professor
Clinic for Plastic Surgery and Hand Surgery
Technical University of Munich
Munich, Germany

Amy M. Moore, MD

Assistant Professor of Surgery
Division of Plastic and Reconstructive Surgery
Department of Surgery
Washington University School of Medicine
St. Louis, MO, USA

Steven L. Moran, MD

Professor and Chair of Plastic Surgery
Division of Plastic Surgery, Division of Hand and Microsurgery;
Professor of Orthopedics
Rochester, MN, USA

Rebecca L. Neiduski, PhD, OTR/L, CHT

Dean of the School of Health Sciences
Professor of Health Sciences
Elon University
Elon, NC, USA

David T. Netscher, MD

Program Director, Hand Surgery Fellowship;
Clinical Professor, Division of Plastic Surgery and Department of Orthopedic Surgery
Baylor College of Medicine;
Adjunct Professor of Clinical Surgery (Plastic Surgery)
Weill Medical College
Cornell University
Houston, TX, USA

Michael W. Neumeister, MD

Professor and Chairman
Division of Plastic Surgery
Springfield Illinois University School of Medicine
Springfield, IL, USA

Shelley Noland, MD

Assistant Professor
Division of Plastic Surgery
Mayo Clinic Arizona
Phoenix, AZ, USA

Christine B. Novak, PT, PhD

Associate Professor
Department of Surgery, Division of Plastic and Reconstructive Surgery
University of Toronto
Toronto, Ontario, Canada

Scott Oates, MD

Deputy Department Chair;
Professor
Department of Plastic Surgery, Division of Surgery
The University of Texas MD Anderson Cancer Center
Houston, TX, USA

Kerby Oberg, MD, PhD

Associate Professor
Department of Pathology and Human Anatomy
Loma Linda University School of Medicine
Loma Linda, CA, USA

Scott Oishi, MD

Director, Charles E. Seay, Jr. Hand Center
Texas Scottish Rite Hospital for Children;
Professor, Department of Plastic Surgery and Department of Orthopedic Surgery
University of Texas Southwestern Medical Center
Dallas, TX, USA

William C. Pederson, MD, FACS

President and Fellowship Director
The Hand Center of San Antonio;
Adjunct Professor of Surgery
The University of Texas Health Science Center at San Antonio
San Antonio, TX, USA

Dang T. Pham, MD

General Surgery Resident
Department of Surgery
Houston Methodist Hospital
Houston, TX, USA

Karl-Josef Prommersberger, MD, PhD

Chair, Professor of Orthopedic Surgery
Clinic for Hand Surgery
Bad Neustadt/Saale, Germany

Carina Reinholdt, MD, PhD

Senior Consultant in Hand Surgery
Center for Advanced Reconstruction of Extremities
Sahlgrenska University Hospital/ Mölndal Mölndal, Sweden;
Assistant Professor
Department of Orthopedics
Institute for Clinical Sciences
Sahlgrenska Academy
Goteborg, Sweden

Justin M. Sacks, MD, MBA, FACS

Director, Oncological Reconstruction;
Assistant Professor
Department of Plastic and Reconstructive Surgery
Johns Hopkins School of Medicine
Baltimore, MD, USA

Douglas M. Sammer, MD

Associate Professor of Plastic and Orthopedic Surgery
Chief of Plastic Surgery at Parkland Memorial Hospital
Program Director Hand Surgery Fellowship
University of Texas Southwestern Medical Center
Dallas, TX, USA

Subhro K. Sen, MD

Clinical Associate Professor
Plastic and Reconstructive Surgery
Robert A. Chase Hand and Upper Limb Center
Stanford University School of Medicine
Stanford, CA, USA

Pundrique R. Sharma, MBBS, PhD and FRCS (Plast)

Consultant Plastic Surgeon
Department for Plastic and Reconstructive Surgery
Alder Hey Children's Hospital
Liverpool, UK

Randolph Sherman, MD, FACS

Vice Chair
Department of Surgery
Cedars-Sinai Medical Center
Los Angeles, CA, USA

Jaimie T. Shores, MD

Clinical Director, Hand/Arm Transplant Program
Department of Plastic and Reconstructive Surgery
Johns Hopkins University School of Medicine
Baltimore, MD, USA

Vanila M. Singh, MD, MACM

Clinical Associate Professor
Anesthesiology, Perioperative and Pain Medicine
Stanford University School of Medicine
Stanford, CA, USA

Jason M. Souza, MD, LCDR, MC, USN

Staff Plastic Surgeon, United States Navy
Walter Reed National Military Medical Center
Bethesda, MD, USA

Amir Taghinia, MD, MPH

Attending Surgeon
Department of Plastic and Oral Surgery
Boston Children's Hospital;
Assistant Professor of Surgery
Harvard Medical School
Boston, MA, USA

David M. K. Tan, MBBS

Senior Consultant
Department of Hand and Reconstructive Microsurgery
National University Health System
Singapore;
Assistant Professor
Department of Orthopedic Surgery
Yong Loo Lin School of Medicine
National University Singapore
Singapore

Jin Bo Tang, MD

Professor and Chair
Department of Hand Surgery;
Chair, The Hand Surgery Research Center
Affiliated Hospital of Nantong University
Nantong, The People's Republic of China

Johan Thorfinn, MD, PhD

Senior Consultant of Plastic Surgery, Burn Unit;
Co-Director
Department of Plastic Surgery, Hand Surgery
and Burns
Linköping University Hospital
Linköping, Sweden

**Michael Tonkin, MBBS, MD, FRACS(Orth),
FRCS(Ed Orth)**

Professor of Hand Surgery
Department of Hand Surgery and Peripheral
Nerve Surgery
Royal North Shore Hospital
The Children's Hospital at Westmead
University of Sydney Medical School
Sydney, New South Wales, Australia

Joseph Upton III, MD

Staff Surgeon
Department of Plastic and Oral Surgery
Boston Children's Hospital;
Professor of Surgery
Harvard Medical School
Boston, MA, USA

Francisco Valero-Cuevas, PhD

Director
Brain-Body Dynamics Laboratory;
Professor of Biomedical Engineering;
Professor of Biokinesiology and Physical
Therapy;
(By courtesy) Professor of Computer Science
and Aerospace and Mechanical Engineering
The University of Southern California
Los Angeles, CA, USA

Christianne A. van Nieuwenhoven, MD, PhD

Plastic Surgeon/Hand Surgeon
Plastic and Reconstructive Surgery
Erasmus Medical Centre
Rotterdam, the Netherlands

Nicholas B. Vedder, MD

Professor of Surgery and Orthopedics
Chief of Plastic Surgery Vice Chair
Department of Surgery
University of Washington
Seattle, WA, USA

Andrew J. Watt, MD

Attending Hand and Microvascular Surgeon;
Associate Program Director, Buncke Clinic Hand
and Microsurgery Fellowship;
Adjunct Clinical Faculty, Stanford University
Division of Plastic and Reconstructive Surgery
The Buncke Clinic
San Francisco, CA, USA

Fu-Chan Wei, MD

Professor
Department of Plastic Surgery
Chang Gung Memorial Hospital
Taoyuan, Taiwan

Julie Colantoni Woodside, MD

Orthopedic Surgeon
OrthoCarolina
Gastonia, NC, USA

Jeffrey Yao, MD

Associate Professor
Department of Orthopedic Surgery
Stanford Hospital & Clinics
Redwood City, CA, USA

Acknowledgments



My wife, Gabrielle Kane, has always been my rock. She not only encourages me in my work but gives constructive criticism bolstered by her medical expertise as well as by her knowledge and training in education. I can never repay her. The editorial team at Elsevier have made this series possible. Belinda Kuhn leads the group of Alexandra Mortimer, Louise Cook, and the newest addition to the team, Sam Crowe. The Elsevier production team has also been vital in moving this project along. The volume editors, Geoff Gurtner, Peter Rubin, Ed Rodriguez, Joe Losee, David Song, Mo Nahabedian, Jim Chang, and Dan Liu have shaped and refined this edition, making vital changes to keep the series relevant and up-to-date. My colleagues in the University of Washington, headed by Nick Vedder, have provided continued encouragement and support. Finally, and most importantly, the residents and fellows who pass through our program keep us on our toes and ensure that we give them the best possible solutions to their questions.

Peter C. Neligan, MB, FRCS(I), FRCSC, FACS

This completely updated volume represents this generation's brightest minds in hand and microvascular surgery. I am indebted to my colleagues and friends from around the globe for their hard work and eloquent writing, and to our talented staff at Elsevier. It is our hope that this text will continue to serve as a guide for the optimal treatment of all our patients. I am fortunate to have two families to thank: the students, residents, fellows, and faculty at Stanford University who stimulate and enrich me intellectually; and my own loved ones, my wife Dr. Harriet Walker Roeder, and girls Julia, Kathleen, and Cecilia, who sustain me in every way.

James Chang, MD

*Dedicated to future plastic surgeons. Take up the torch
and lead us forward!*

Plastic surgery contributions to hand surgery

James Chang

Although references to surgery of the hand date back to Hippocrates in ancient Greece, the dedicated specialty of hand surgery is relatively young. The Second World War is thought to be the major driving event for the development of hand surgery as a separate surgical discipline. This modern specialty was founded by a combination of general surgeons, plastic surgeons, orthopedic surgeons, vascular surgeons, and neurosurgeons. Hand surgery has remained unique in that it is a regional specialty instead of a tissue specialty – its practitioners are ideally trained in managing problems affecting all component tissues of the hand. This introduction chronicles the role plastic surgery has played in the development of hand surgery as a surgical specialty. Furthermore, it predicts how plastic surgery will influence the future direction of hand surgery.

Origins of hand surgery

Henry C. Marble, in Flynn's classic textbook, *Hand Surgery*, found the earliest references to surgery of the hand by Hippocrates (460–377 BC) in ancient Greece.¹ In his writings, Hippocrates described methods to reduce wrist fractures and also highlighted the importance of well-fitting, clean dressings to the hand. A later Greek physician, Heliodorus, described his technique for amputation of a finger with specific reference to dissecting adequate skin flaps with which to cover the remaining bone. While Galen (131–201 AD) confused tendons with nerves and cautioned against suturing tendons for fear of “nervous spasms”,² Avicenna (981–1038 AD),³ an Arabian physician, wrote detailed descriptions of tendon repair in medieval times. Other references to hand surgery have been found in history, but comprehensive care of the hand was not truly developed until the 20th century.

An understanding of human anatomy has been critical to both plastic surgery and hand surgery, and therefore, the history of anatomy has paralleled the development of these two surgical disciplines. J. William Littler reviewed the

influence of famed anatomists on hand surgery.⁴ Perhaps these anatomists were drawn to the hand as the most intricate of body parts – the ultimate challenge to their craft. In the Renaissance period, Leonardo da Vinci (1452–1519) used his artistic genius to create extraordinarily accurate representations of the hand. His knowledge of anatomy was acquired from over 100 human dissections and ultimately resulted in a collection of 779 anatomical drawings.⁵

Andreas Vesalius (1514–1564) (Figs. 0.1 & 0.2) published his monumental work *De Corporis Humani Fabrica* in 1543 with many engravings dedicated to the hand.⁶ Like da Vinci, Vesalius relied on his own dissections of cadavers rather than accepting the dogma found in previous medical texts. His observations refuted the inaccuracies found in the earlier writings of Galen and his disciples. Modern-day hand surgeons J. William Littler and Robert A. Chase have both credited Sir Charles Bell (1774–1842) as the foremost anatomist of the hand.⁶ His *Fourth Bridgewater Treatise – The Hand: Its Mechanism and Vital Endowments as Evincing Design* (1834) remains a classic essay on the anatomic and functional aspects of the hand.⁷

In addition to anatomy, two more recent achievements allowed hand surgery to develop into a unique specialty in the modern era. On October 16, 1846 at the Massachusetts General Hospital, Dr. William Morton delivered sulfuric ether fumes to a patient undergoing excision of a neck mass by Dr. John Collins Warren.⁸ For the first time, adequate anesthesia was performed, thus allowing the possibility of more complex reconstructive procedures in both plastic surgery and hand surgery.

The second major achievement was an understanding of microbiology with resulting advances in sterile technique and antibiotics.⁹ In the 1860s, Louis Pasteur's work with fermentation introduced the field of bacteriology. Semmelweis, in Vienna, and Lister, in Britain, developed antiseptic surgery with the early use of carbolic acid as a disinfectant. In the 20th century, several Nobel Prizes marked the importance of the development of antibiotics. Paul Ehrlich a German



Fig. 0.1 Andreas Vesalius, master anatomist, at the age of 28. (Reproduced from Vesalius A. *De Humani Corporis Fabrica*. 1543. Reproduced with permission from the British Library.)




Fig. 0.2 An example of the anatomic illustrations of Stephan van Calcar in the monumental text of Vesalius, *De Humani Corporis Fabrica* (1543). (Reproduced from Vesalius A. *De Humani Corporis Fabrica*. 1543. Reproduced with permission from the British Library.)

bacteriologist, developed the principle of “antimicrobial chemotherapy” and received the Nobel Prize in 1908. Another German, Gerhard Domagk, received the Nobel Prize in 1939 for discovering the antibacterial effects of sulfa drugs. Finally, Alexander Fleming shared the Nobel Prize in 1945 for discovering the ability of a mold, *Penicillium notatum* to halt the growth of staphylococcus bacteria. With penicillin and later antibiotics, plastic surgeons and hand surgeons had an armamentarium of agents to control infections.

Over the course of this history, how has plastic surgery contributed to the development and progress of hand surgery? Like hand surgery, plastic surgery became a separate surgical specialty in the US only in the 20th century with the founding of the American Association of Oral and Plastic Surgeons (later shortened to the American Association of Plastic Surgeons) in 1921. The American Board of Plastic Surgery was not established until 1938. However, plastic surgery has profoundly influenced hand surgery, and this influence has predated formal associations and boards. In other words, surgeons throughout history have used plastic surgery principles before they were known as “plastic surgeons”. Therefore, early plastic surgery contributions to hand surgery are best chronicled by reviewing the development of plastic surgery principles and how they have been applied to hand surgery.

Principles of plastic surgery and their application to hand surgery

Sushruta, a Hindu surgeon in India around the first century AD, performed reconstruction of the nose using pedicled flaps from the face – either forehead or cheek. He described the operation as follows:

The physician should take the leaf of a tree the same size as the nose and apply it to the cheek in such a way that a stem is still adherent. Then he stitches the cheek with needle and thread, scarifies the stump of the nose and quickly but carefully places the flap in the nose. After the transplanted piece has grown, the stem is cut off. In like manner the flap might be turned up from the upper or lower arm and attached to the nose – with the arm over the head.¹

This description included the basic plastic surgery principles of precise patterning of the defect, preparation of the recipient bed, and the use of local and distant flaps, all which have had obvious applicability to soft-tissue reconstruction of the hand.

Another famed surgeon, Ambrose Paré (1510–1590), offered principles that allowed for optimal care of battlefield wounds, including the upper extremity: “to enlarge the wound for drainage; to remove bone splinters and foreign bodies from wounds; to control hemorrhage with ligatures; not to encourage suppuration; and to amputate through sound tissues.”¹ Paré’s use of ligatures during amputation controlled hemorrhage and saved countless lives on the battlefield (Figs. 0.3 & 0.4). His principles of wound care would later be applied directly to the enormous number of battlefield casualties of World War II. In addition, Paré popularized the anatomic drawings of Vesalius amongst surgeons, and even designed elaborate prostheses for upper extremity amputees, victims of the French wars of the 1500s. Paré was perhaps the quintessential upper extremity trauma surgeon.



Fig. 0.3 Ambrose Paré applying a ligature during battlefield amputation. Wood engraving by C. Maurand. (Reproduced with permission from The Wellcome Trust L0018530.)

Gaspare Tagliacozzi (1545–1599) did not invent the Italian method of nasal reconstruction, which has been generally attributed to Branca. However, Tagliacozzi, a professor of medicine and anatomy in Bologna, did popularize this technique of attaching a medial upper arm skin flap to the nasal defect. In addition, specialized leather band contraptions were devised to immobilize the patient during the period of flap revascularization (Fig. 0.5). His detailed textbook, *De Chirurgia Curtorum per Insitionem*, was published in 1597 and allowed later generations of surgeons to learn techniques for the transfer of distant pedicled flaps.⁵

As plastic surgeons became more adept at tissue transfer, these innovations were applied to reconstruction of the hand. Carl Nicoladoni (1849–1903) pioneered work on reconstruction of the thumb. Nicoladoni reported on a case of total skin avulsion of the thumb that he treated by a skin flap from the patient's left pectoral region – similar to the thoracoepigastric or random pattern chest flaps still used today.⁶ In 1903, his



Fig. 0.5 Tagliacozzi's immobilization device after arm-to-nose pedicled transfer. (Reproduced from Typ 525.97.820 with permission from Houghton Library, Harvard University.)

paper, "Further experience with thumb reconstruction", described the pedicled toe transfer to the thumb that continues to bear his name. Microsurgeons today have obviated the need for the uncomfortable positioning of this transfer; nevertheless, Nicoladoni deserves credit for the ingenuity behind the toe-to-hand transfer. Plastic surgeon George H. Monks (1853–1933) transferred a composite skin island flap from the forehead on the superficial temporal arteriovenous pedicle to a lower-eyelid defect.⁶ The use of island flaps would later be applied to the hand with the neurovascular island flaps of Littler, and, more recently, with the dorsal metacarpal artery flaps. Even Sir Harold Gillies (1882–1960) who, with Millard, codified the principles of plastic surgery and was one of history's most influential plastic surgeons, turned from the head and neck to the hand and devised a method to lengthen the stump of a thumb, the Gillies "cocked-hat" flap.¹⁰

Vilray P. Blair (1871–1955) was one of the founding fathers of American plastic surgery.¹¹ In addition to a large body of work in cleft lip repair and maxillofacial surgery, Blair made two significant contributions to plastic surgery that translated directly to hand surgery. Blair helped redefine the delay phenomenon of Tagliacozzi in a 1921 article, "The delayed transfer of long pedicled flaps in plastic surgery". Blair and his disciple, James Barrett Brown (1899–1971), described a new technique of harvesting skin for skin grafting in a paper published in *Surgery, Gynecology, and Obstetrics* entitled "The use and uses of large split skin grafts of intermediate thickness".¹² This simple and reproducible method of harvesting split-thickness skin improved on the previous techniques of Thiersch and would have a tremendous impact on the reconstruction of hand burns and other wounds in World War II.




Fig. 0.4 Examples of Paré's designs for prostheses. (Reproduced from *Les Oeuvres de M. Ambroise Paré*, 1575, p. 916–917.)

Origins of modern hand surgery

With this historical background in wound management, flap transfer, and skin grafting, plastic surgeons were poised to contribute to the founding of modern hand surgery. World War II was the crucible in which hand surgery became a separate specialty. Prior to the outbreak of this war, two surgeons were instrumental in hand surgery's early development. In 1939, Allen B. Kanavel published his *Infections of the Hand*,¹³ and for the first time, a comprehensive approach to the myriad of hand infections and treatments was described. Even at that early time, Kanavel stressed the importance of hospitalization for hand infections, intravenous hydration, and placing the hand at rest.

Sterling Bunnell (1882–1957) has been widely regarded as the father of hand surgery. The first edition of Bunnell's comprehensive textbook, *Surgery of the Hand*,¹⁴ was published in 1944, and remained the classic reference for many years. He was a general surgeon but believed in the importance of plastic surgery principles, and as the consummate hand surgeon, was able to apply plastic, orthopedic, and vascular principles equally to hand surgery. Marble recounted Bunnell's mastery:

He insisted on all of the teachings of the past masters, stressing particularly the gentle handling of the tissues. He called this atraumatic surgery. He exercised his skill also in plastic, bone, tendon, nerve, blood vessel, and muscle surgery to reconstruct crippled hands. He showed that tendons could be grafted to substitute for lost ones, and could be transferred to give function to useless digits or joints. He taught that nerves could be grafted and that whole fingers could be moved about for better function. Thus he opened the door for the complete reconstruction of the injured hand.¹

The specialty of hand surgery in the US really developed in the field hospitals and regional medical referral centers established during the Second World War. During those years, massive numbers of surviving casualties with upper extremity injuries, an organized resuscitation and transportation service, and increasing sophistication within the fields of general surgery, plastic surgery, orthopedic surgery, vascular surgery, and neurosurgery together formed the critical mass necessary for accelerated technical and educational development.

The high volume of hand injuries requiring care in World War II was unprecedented. Unlike the trench warfare of World War I when head and neck wounds were common, World War II involved open warfare with rapid movements and grenades, leading to a greater likelihood of upper extremity injuries. In the early years of the war, soldiers with injured hands and upper extremities were placed into individual hospitals and distributed somewhat arbitrarily on to orthopedic, general surgery, plastic surgery, and neurosurgery wards depending on the nature of the injury and the availability of beds. It became evident that specialized interdisciplinary care of the hand patient was necessary. In a masterpiece of organizational effort, regional hand referral centers were established in US military hospitals. Colonel J.J. Reddy and Colonel F.V. Kilgore together established the first ward designated for hand surgery at Cushing General Hospital in Framingham, Massachusetts.¹⁵ Plastic surgeon Captain (later Major) J. William Littler was assigned to this ward and supervised the first

service specifically dedicated to care of the injured hand. Joint conferences involving plastic surgery, orthopedic surgery, and neurosurgery were established and, within a short time, four complete wards dedicated to hand surgery were in operation.

Dr. Littler's unit was used as a model by Surgeon General Norman T. Kirk to establish nine military referral centers throughout the US.¹⁵ Sterling Bunnell served as civilian surgical consultant to the Secretary of War and visited each referral center to teach hand surgery.

Simultaneously, advances in plastic surgery had provided effective and reliable methods of wound coverage ranging from split- and full-thickness skin grafts to local and distant pedicled flaps. This ability to cover wounds was critical to the development of hand surgery. Because wound coverage was a priority, the regional hand centers established across the US were situated in hospitals that had been already designated as plastic surgery centers.

Plastic surgeons were instrumental in this early phase of development in American hand surgery because of their expertise in wound care and trauma reconstruction. In March 1945, Lieutenant Colonel Eugene M. Bricker outlined in an Army memorandum the principles of plastic surgery relevant to hand surgery:

1. Conservative, careful and thorough debridement of the primary wound is essential. Primary closure is not advised in an evacuation hospital, but skin flaps can be dressed back into place.
2. Splint purposefully, maintaining the palmar arch and flexion of the metacarpophalangeal joints.
3. Bring about delayed closure as early as possible, preferably on the third or fourth day, by simple closure, split graft or pedicle graft, according to the necessities of the case.
4. Use traction only when it is urgently indicated, and then for a minimum length of time.
5. Concentrate on maintenance of such function as remains following certain severe types of injury. Restoration of the injured part should not be attempted, and healing should be accomplished as rapidly as possible. Amputation of an irreparably damaged finger is justified.
6. Institute active motion as early as possible, and supplement by occupational therapy when healing has occurred.
7. Try to prevent edema and infection in open wounds. Proper debridement, proper dressings, proper splinting, and effective elevation of the hand will prevent this development.
8. Manage an open wound aseptically as long as it remains open. Aseptic management implies the use of masks and of instruments or gloves, whether or not the wound is infected.¹⁶ These principles served as the foundation for acute treatment of traumatic hand injuries.

Developments after World War II

Immediately after World War II, plastic surgeons continued to have a profound influence on hand surgery. In 1946, plastic

surgeon Darrel T. Shaw and general surgeon Robert Lee Payne published a landmark paper entitled, "One stage tubed abdominal flaps".¹⁷ This paper described an axial flap based on the superficial inferior epigastric vessels for composite tissue transfer to the hand. The development of reliable composite tissue transfer allowed early coverage of extensive hand and upper extremity defects. Sir Archibald McIndoe, a disciple of Gillies, established several burn facilities in England and refined techniques in burn excision and reconstruction of the hand.¹⁸

The patients wounded during the battles of World War II returned to the US for further reconstructive surgery by an increasingly better-trained cadre of hand surgeons. In order to coordinate this explosive growth in hand surgery, representatives from general surgery, plastic surgery, and orthopedic surgery combined to form the American Society for Surgery of the Hand in 1946.¹⁹ The first annual meeting was held on January 20, 1946 at the Blackstone Hotel in Chicago, Illinois, with Sterling Bunnell as the first president. Plastic surgeons figured prominently – of the 35 founding members, 13 (37%) came from plastic surgery backgrounds.²⁰

Hand surgery underwent another period of accelerated productivity during the Korean War. By that time, the US military had experience in organizing regional referral centers for reconstruction of the hand. Dr. J William Littler took on Bunnell's former role and was appointed as Hand Surgery Civilian Consultant to the Military.⁶ Littler's unrivaled experience from World War II and then the Korean conflict allowed him to become perhaps the most famous of plastic hand surgeons. His achievements have included the Littler digital neurovascular transfer and countless other surgical innovations bearing his name, in addition to his legendary anatomic sketches of the hand and long list of trainees who have become distinguished hand surgeons themselves. Other plastic surgeons who were involved in the Korean War effort included Robert A. Chase and Earle Peacock. Robert A. Chase returned from his military duty to embark on a lifelong effort of developing educational aids related to functional anatomy of the hand. Earle Peacock contributed original laboratory work on wound healing, particularly related to flexor tendon wound healing.

The era of microsurgery

Hand surgery underwent an intense period of laboratory and clinical activity in the 1960s and 1970s devoted to microsurgery and free tissue transfer. In 1963, Goldwyn *et al.* presented their work on abdominal free flaps in dogs, based on the inferior epigastric vessels.²¹ This investigative work was further developed by Krizek *et al.* in 1965.²² Together, these plastic surgeons, along with O'Brien,²³ Taylor *et al.*²⁴ and many others throughout the world, established the possibility of free tissue transfer that liberated the hand surgeon from the anatomic limitations of local tissue transfer.

Replantation of fingers and other body parts came into reality via an international effort of plastic surgeons, orthopedic surgeons, and general surgeons. The first successful replantation of an upper arm amputation by Malt and McKhann was carried out in 1962, and the first successful replantation of an amputated thumb was performed in 1968 by Komatsu and Tamai. Since then, replantation teams have

been organized in major hospitals, and microsurgical techniques have become an integral part of the training of hand surgeons. The techniques of replantation in the upper extremity have been extrapolated to successful replantation of other parts of the body, including the lower limb, the scalp, the ear, portions of the lip and nose, and the penis, and have led directly to the further evolution of elective microsurgical free tissue transfer. In addition, plastic surgeons have devised innovations to improve the success rates of replantation, including the use of Y-shaped interposition vein grafts in multiple-digit replantations²⁵ and replantation of fingers distal to the proximal interphalangeal joint.²⁶

Plastic surgeon Harry J. Buncke helped pioneer the toe-to-thumb transplant in animal models, and eventually in humans. His efforts in the past 40 years have made him one of the fathers of American microsurgery.²⁷ Beyond the earlier work of Littler on thumb reconstruction, plastic surgeons have continued to contribute greatly to the refinement of various operations, including the toe-to-hand transfer^{28,29} and the great-toe wraparound free flap of Morrison *et al.*³⁰

Critical to reconstruction of the hand with both pedicled flaps and free flaps has been a detailed knowledge of anatomy as it relates to vascular distributions to muscle and skin. McCraw *et al.* popularized the use of musculocutaneous flaps³¹ and Mathes and Nahai developed an atlas of these muscle and musculocutaneous flaps, which has been an invaluable reference for the reconstructive surgeon.³² Ian Taylor and his plastic surgery colleagues have described the vascular territories of skin flaps. Taylor's angiosome theory, where the body is divided into different vascular territories to the skin, originating from deeper source arteries, has allowed surgeons to design flaps with reliable perfusion. In addition, second-generation flaps, based on smaller vessels, may be possible with an understanding of this intricate anatomy.

Plastic surgeons have also continued to be involved in the political and educational development of hand surgery. In 1970, a second hand organization – the American Association for Hand Surgery (AAHS) – was founded.³³ By the fall of 1971, there were 65 full members. As in the American Society for Surgery of the Hand, plastic surgeons played an instrumental role. The first meeting in 1971 immediately preceded the annual American Society of Plastic and Reconstructive Surgeons meeting. This arrangement symbolized the influence and participation of plastic surgeons in the AAHS that continues today.

Recent developments

In recent years, significant contributions to hand surgery have been made by plastic surgeons. One area of intense study in the past several decades has been peripheral nerve repair and reconstruction. Millesi *et al.*³⁴ published a landmark paper in 1972 on interfascicular nerve grafting of median and ulnar nerves. Since then, nerve grafting, as well as autogenous vein grafting of nerve defects, has helped improve results of nerve reconstruction.^{35,36} Mackinnon and Hudson³⁷ have examined the possibility of immunosuppression for allograft nerve transplantation to bridge extensive defects where autogenous donor nerve may not be sufficient, and more recently pioneered the field of nerve transfers.³⁸ Several plastic

surgeons, including Terzis *et al.*³⁹ and Hentz and Narakas,⁴⁰ have published reports of their considerable experience on reconstruction of brachial palsy injury. Their dedication to the comprehensive reconstruction and rehabilitation of these devastating injuries has resulted in improved surgical outcomes.

Beyond replantation, more intricate microvascular operations have been undertaken by plastic hand surgeons to restore form and function to the hand. Although the indications are limited, microvascular transfer of a toe metatarsophalangeal joint to recreate a metacarpophalangeal joint has been shown to be possible.⁴¹ Further advances in microsurgical reconstruction of the hand include functional free muscle transfer. Manktelow and McKee's landmark paper in 1978 introduced the concept of a free gracilis or free pectoralis major muscle transfer with motor nerve coaptation to restore active finger flexion.⁴²

Plastic surgeons have also been at the forefront of congenital hand surgery.⁴³ Graham Lister published one of the first significant series of toe-to-hand microvascular transfers in children, ushering in a new era of complex reconstruction for congenital hand problems.⁴⁴ Other authors, including Gilbert⁴⁵ and Buck-Gramcko,⁴⁶ have also published their series. More recently, Neil Jones has added his work on pediatric toe-to-hand transfers to previous contributors, thus refining these technically challenging procedures.⁴⁷ In addition, Joseph Upton *et al.*⁴⁸ reported on their unrivalled experience with excision and reconstruction of vascular anomalies in the upper extremity.

The plastic surgery techniques of flap dissection have been used to develop newer flaps intrinsic to the hand and upper extremity such as vascularized bone flaps from the distal radius. There is much excitement in using these pedicled bone flaps for revascularization of the scaphoid in scaphoid non-union and avascular necrosis, or revascularization of the lunate in Kienbock's disease.⁴⁹ These second-generation flaps may lead to other intrinsic flaps that will also be useful for bone and ligament reconstruction.

Plastic surgeons know of their legacy of involvement in the field of organ transplantation. Much of the pioneering work on allograft rejection and homograft tolerance by Sir Peter Medawar and others was derived from experimentation with skin grafts in various animal models.⁹ Joe Murray, the only plastic surgeon ever to receive the Nobel Prize, received it for

his work on transplantation, including the first human kidney transplantation in 1954.⁹ With newer immunosuppressive agents and greater acceptance of the risks of transplantation, human hand allograft transplantation has now become a reality.⁵⁰ While the ultimate success of these early operations remains to be seen, reaching these new frontiers in hand reconstruction as well as in other forms of composite tissue allotransplantation is now possible.

Future directions

An accomplished hand and plastic surgeon once wrote:

I learned about hand surgery's battle against scar adherence and contraction and that the Z-plasty can be a major and intriguing weapon in that battle in other parts of the body as well as in the hand. I thought a lot about the Z-plasties that year and used them often, in multiple parts of the body, always trying to pick the optimum size and the best orientation, trying to decide which of the two parallel sides of the Z-plasty's diamond would be most advantageous for mimicking the wrinkle lines, and trying to avoid running into features not to be moved or, occasionally, to something on or in one of the flaps ... Ever since, I have looked upon the Z-plasty as a little bit of magic.⁵¹

That surgeon was Leonard T Furlow Jr, who took the Z-plasty from the scarred hand to the cleft palate. It is an excellent example of the intellectual interplay between plastic surgery and hand surgery.

Current plastic surgery research has focused on growth factor technology to inhibit scarring or to augment bone growth, wound healing,⁵² and angiogenesis. Tissue engineering may allow formation of ample supplies of bone, cartilage,⁵³ even muscle, skin, and nerve. Virtual reality surgery will help plastic surgeons model and practice complex reconstructive procedures prior to undertaking them. In the next decade, hand surgeons will acquire an armamentarium that includes bone substitutes, tissue-engineered bone, cartilage and nerve, and three-dimensional computer models for complex intracarpal abnormalities. Throughout the chapters of this hand volume, you will find new, pioneering translational work that shapes the future of hand and upper extremity surgery. As in microsurgery, plastic surgeons will lead the way for this new technical revolution in hand surgery.



Access the complete reference list online at

<http://www.expertconsult.com>

2. Kleinert HE, Spokevicius S, Papas NH. History of flexor tendon repair. *J Hand Surg Am.* 1995;20A:S46. *This paper by Kleinert et al. describes the evolution of flexor tendon repair over time from secondary repair of tendon laceration in zone II to the current techniques of primary repair.*
14. Bunnell S. *Surgery of the Hand.* Philadelphia: Lippincott; 1944. *This is the first edition of the first modern textbook in hand surgery, written by Sterling Bunnell, widely regarded as the father of American hand surgery.*
30. Morrison WA, O'Brien BM, Macleod AM. Thumb reconstruction with a free neurovascular wrap-around flap from the big toe. *J Hand Surg Am.* 1980;5A:575–583. *This original description of the great toe wrap-around flap represents a significant refinement of the great toe transfer, resulting in a narrower thumb and preservation of a portion of the length of the great toe donor site.*
38. Tung TH, Mackinnon SE. Nerve transfers: indications, techniques, and outcomes. *J Hand Surg Am.* 2010;35:332–341. *This review article describes current state of the art for new techniques in nerve transfers. Nerve transfers represent a developing field in hand surgery whereby fascicular dissection of nerves allows precise transfer of specific nerve branches to reinnervate other nerve-muscle units.*
47. Chang J, Jones NF. Radiographic analysis of growth in pediatric toe-to-hand transfer. *Plast Reconstr Surg.* 2002;109:576–582. *This article reviews a large clinical experience with pediatric toe-to-hand transfers. Radiographic analysis of the transferred toes was performed, with comparison to the opposite toe as a growth control. The authors showed that, with careful preservation of the growth plates, growth of these transferred toes is maintained over time.*

References

- Marble HC. History of hand surgery. In: Flynn JE, ed. *Hand Surgery*. Baltimore: Williams & Wilkins; 1966:1–10.
- Kleinert HE, Spokevicius S, Papas NH. History of flexor tendon repair. *J Hand Surg*. 1995;20A:S46. *This paper by Kleinert et al. describes the evolution of flexor tendon repair over time from secondary repair of tendon laceration in zone II to the current techniques of primary repair.*
- Haeger K. Medieval medicine. In: Haeger K, ed. *The Illustrated History of Surgery*. Gothenburg, Sweden: AB Nordbok; 1988:73.
- Littler JW. Plastic surgeons and the development of reparative surgery of the hand. In: Aston SA, Beasley RW, Thorne CHM, eds. *Grabb & Smith's Plastic Surgery*. 5th ed. Philadelphia: Lippincott-Raven; 1997:791.
- Haeger K. Surgery in the Renaissance. In: Haeger K, ed. *The Illustrated History of Surgery*. Gothenburg, Sweden: AB Nordbok; 1988:96.
- Littler JW. Plastic surgeons and the development of reparative surgery of the hand. In: Aston SA, Beasley RW, Thorne CHM, eds. *Grabb & Smith's Plastic Surgery*. 5th ed. Philadelphia: Lippincott-Raven; 1997:791.
- Bell C. *Fourth Bridgewater Treatise – The Hand: Its Mechanism and Vital Endowments as Evincing Design*. Philadelphia: Carey, Lea & Blanchard; 1833.
- Haeger K. Surgery in the age of revolutions. In: Haeger K, ed. *The Illustrated History of Surgery*. Gothenburg, Sweden: AB Nordbok; 1988:188–189.
- Haeger K. The world of modern surgery. In: Haeger K, ed. *The Illustrated History of Surgery*. Gothenburg, Sweden: AB Nordbok; 1988:267–270.
- Lister GD. Skin flaps. In: Green DG, ed. *Operative Hand Surgery*. Vol 2. 3rd ed. New York: Churchill Livingstone; 1993:1750–1751.
- Stelnicki EJ, Young VL, Francel T, et al. Vilray R. Blair, his surgical descendents, and their roles in plastic surgical development. *Plast Reconstr Surg*. 1999;103:1990–2009.
- Blair V, Brown JB. The use and uses of large split skin grafts of intermediate thickness. *Surg Gynecol Obstet*. 1929;49:82.
- Kanavel AB. *Infections of the Hand*. Philadelphia: Lea & Febiger; 1939.
- Bunnell S. *Surgery of the Hand*. Philadelphia: Lippincott; 1944. *This is the first edition of the first modern textbook in hand surgery, written by Sterling Bunnell, widely regarded as the father of American hand surgery.*
- Cutler CW. The overall picture in the zone of interior. In: Bunnell S, ed. *Surgery in World War II: Hand Surgery*. Washington D.C.: Office of the Surgeon General, Department of the Army; 1955:12–14.
- Cleveland M. Hand injuries in the European theater of operations. In: Bunnell S, ed. *Surgery in World War II: Hand Surgery*. Washington D.C.: Office of the Surgeon General, Department of the Army; 1955:161–162.
- Shaw D, Payne R. One stage tubed abdominal flaps. *Surg Gynecol Obstet*. 1946;83:205–209.
- Robson MC, Smith DJ. Thermal injuries. In: Jurkiewicz MJ, Krizek TJ, Mathes SJ, et al., eds. *Plastic Surgery: Principles and Practice*. St. Louis: C.V. Mosby; 1990:1359.
- Newmeyer WL. The second world war to 1971: the founding. In: Newmeyer WL, ed. *American Society for Surgery of the Hand: The First Fifty Years*. New York: Churchill Livingstone; 1995:3–4.
- Meals RA, ed. ASSH Video #127-90: 26. Conversations with the Founders.
- Goldwyn RM, Lamb DL, White WL. An experimental study of large island flaps in dogs. *Plast Reconstr Surg*. 1963;31:528–536.
- Krizek TJ, Tahi T, Desprez QO, et al. Experimental transplantation of composite grafts by microvascular anastomosis. *Plast Reconstr Surg*. 1965;36:358.
- O'Brien BM. *Microvascular Reconstructive Surgery*. Edinburgh: Churchill Livingstone; 1977.
- Taylor GI, Miller GD, Ham FJ. The free vascularized bone graft – a clinical extension of microvascular techniques. *Plast Reconstr Surg*. 1975;55:533–544.
- Jones NF, Jupiter JB. The use of Y-shaped interposition vein grafts in multiple digit replantations. *J Hand Surg*. 1985;10A:675–678.
- May JW, Toth BA, Gardner M. Digital replantation distal to the proximal interphalangeal joint. *J Hand Surg*. 1982;7A:161–166.
- Buncke HJ. Forty years of microsurgery: what's next? *J Hand Surg*. 1995;20A:S34.
- Lister GD, Kalisman M, Tsai TM. Reconstruction of the hand with free microneurovascular toe-to-hand transfer: experience with 54 toe transfers. *Plast Reconstr Surg*. 1983;71:372–386.
- May JW Jr, Bartlett SP. Great toe-to-hand free tissue transfer for thumb reconstruction. *Hand Clin*. 1985;1:271–284.
- Morrison WA, O'Brien BM, Macleod AM. Thumb reconstruction with a free neurovascular wrap-around flap from the big toe. *J Hand Surg*. 1980;5A:575–583. *This original description of the great toe wrap-around flap represents a significant refinement of the great toe transfer, resulting in a narrower thumb and preservation of a portion of the length of the great toe donor site.*
- McCraw JB, Dibbell DG, Carraway JH. Clinical definition of independent myocutaneous vascular territories. *Plast Reconstr Surg*. 1977;60:341–352.
- Mathes SJ, Nahai F, eds. *Clinical Application for Muscle and Musculocutaneous Flaps*. St. Louis: CV Mosby; 1982.
- Freeland AE. *The First Twenty-Five Years: History of the American Association for Hand Surgery*. Arlington Heights, Illinois: AAHS; 1995:1–3.
- Millesi H, Meissl G, Berger A. The interfascicular nerve grafting of the median and ulnar nerves. *J Bone Joint Surg*. 1972;54A:727–750.
- Terzis JK, Faibisoff BA, Williams HB. The nerve gap: suture under tension vs. graft. *Plast Reconstr Surg*. 1975;56:166–170.
- Chiu DTW, Janecka I, Krizek TJ, et al. Autogenous vein graft as a conduit for nerve regeneration. *Surgery*. 1982;91:226.
- Mackinnon SE, Hudson AR. Clinical application of peripheral nerve transplantation. *Plast Reconstr Surg*. 1992;90:695–699.
- Tung TH, Mackinnon SE. Nerve transfers: indications, techniques, and outcomes. *J Hand Surg*. 2010;35:332–341. *This review article describes current state of the art for new techniques in nerve transfers. Nerve transfers represent a developing field in hand surgery whereby fascicular dissection of nerves allows precise transfer of specific nerve branches to reinnervate other nerve-muscle units.*
- Terzis JK, Vekris MD, Soucacos PN. Outcomes of brachial plexus reconstruction in 204 patients with devastating paralysis. *Plast Reconstr Surg*. 1999;104:1221–1240.
- Hentz VR, Narakas A. The results of microneurosurgical reconstruction in complete brachial plexus palsy: assessing outcome and predicting results. *Orthop Clin North Am*. 1988;19:107–114.
- Mathes SJ, Buchannan R, Weeks PM. Microvascular joint transplantation with epiphyseal growth. *J Hand Surg*. 1980;5A:586–589.
- Manktelow RT, McKee NH. Free muscle transplantation to provide active finger flexion. *J Hand Surg*. 1978;3A:416–426.
- Upton J. Correction of constriction rings. *J Hand Surg*. 1991;16A:947–953.
- Lister G. Microsurgical transfer of the second toe for congenital deficiency of the thumb. *Plast Reconstr Surg*. 1988;82:658–665.
- Gilbert A. Reconstruction of congenital hand defects with microvascular toe transfers. *Hand Clin*. 1985;1:351–360.
- Buck-Gramcko D. Progress in the treatment of congenital malformations of the hand. *World J Surg*. 1990;14:715–724.
- Chang J, Jones NF. Radiographic analysis of growth in pediatric toe-to-hand transfer. *Plast Reconstr Surg*. 2002;109:576–582. *This article reviews a large clinical experience with pediatric toe-to-hand transfers. Radiographic analysis of the transferred toes was performed, with comparison to the opposite toe as a growth control. The authors showed that, with careful preservation of the growth plates, growth of these transferred toes is maintained over time.*

48. Upton J, Coombs CJ, Mulliken JB, et al. Vascular malformations of the upper limb: a review of 270 patients. *J Hand Surg.* 1999;24:1019–1035.
49. Zaidenberg C, Siebert JW, Agrigiani C. A new vascularized bone graft for scaphoid nonunion. *J Hand Surg.* 1991;16A:474–478.
50. Jones JW, Gruber SA, Barker JH, et al. Successful hand transplantation. *N Engl J Med.* 2000;343:468–473.
51. Furlow LT. Double opposing Z-plasties to repair a cleft palate: a personal account. *Adv Plast Reconstr Surg.* 1998;15:205.
52. Chang J, Siebert JW, Schendel SA, et al. Scarless wound healing: implications for the aesthetic surgeon. *Aesthetic Plast Surg.* 1995;19:237–341.
53. Ting V, Sims CD, Brecht LE, et al. *In vitro* prefabrication of human cartilage shapes using fibrin glue and human chondrocytes. *Ann Plast Surg.* 1998;40:413–420.

1

Anatomy and biomechanics of the hand

James Chang, Anais Legrand, Francisco Valero-Cuevas, Vincent R. Hentz, and Robert A. Chase

Access video content for this chapter online at expertconsult.com 

SYNOPSIS

- The hand is an incredibly designed structure with complex anatomy and precise biomechanics. The hand must be able to produce adequate force to allow performance of activities of daily living. Furthermore, it must ensure coordination of the fingers for precise prehension and fine motor tasks.
- In order to achieve an optimal functional and aesthetic outcome in patients requiring hand surgery, it is thus essential to fully understand the detailed bone, muscle–tendon, aponeurotic, vascular, nerve and lymphatic components.
- Additional challenges arise from the range of possible movements of various articular surfaces, assisted by muscle action and ligamentous support.
- In this chapter, we present the various elements that compose the hand as well as explanations of the biomechanical principles. These are updated according to the latest literature. Additionally, clinical examples will be used to illustrate anatomic principles.

Introduction

During the Renaissance, Vesalius corrected early misconceptions and brought gross anatomy into proper focus. Since that time, many investigators have embellished the basic structural studies with functional, physiologic, and philosophical observations. The forearm and hand have been prominently included in those observations. Sir Charles Bell (1834),¹ in his thought-provoking volume, *The Hand – Its Mechanism and Vital Endowments as Evincing Design*, presented a concept of hand anatomy that places it in proper context with the position of humans in the animal kingdom. Duchenne (1867) carried out detailed analysis of muscular function by isolated electrical stimulation, described in his classic volume, *Physiologie des Mouvements*.² Frederick Wood-Jones (1920) probed more extensively into comparative anatomy and anthropology in his excellent work, *The Principles of Anatomy as Seen in*

the Hand.³ Allen B. Kanavel (1925) published his monograph, *Infections of the Hand*, which reported detailed analysis of the spaces and synovial sheaths.⁴ *Surgery of the Hand* by Sterling Bunnell (1944) became an indispensable reference during World War II.⁵ Emanuel B. Kaplan (1953) produced the nicely illustrated, detailed volume, *Functional and Surgical Anatomy of the Hand*.⁶ Detailed studies of the integration of the intrinsic and extrinsic muscles operating the polyarticular digits may be found in the work of Landsmeer,^{7–10} Kaplan,¹¹ Eyler and Markee,¹² Stack,¹³ Tubiana and Valentin,¹⁴ and others. More recently, newer flaps intrinsic to the hand and upper extremity have been developed from more detailed investigation into vascular anatomy.^{15,16} Lastly, Berger,¹⁷ Viegas *et al.*,¹⁸ and others have expanded our knowledge of the ligamentous anatomy of the wrist.

As a functional puppet, the hand responds to human desires; its motor performance is initiated by the contralateral cerebral cortex. The conscious demands relayed to the hand and forearm from the central nervous controlling mechanism are sent as movement commands. At subconscious levels, such a movement command is broken down, regrouped, coordinated, and sent on as a signal for fixation, graded contraction, or relaxation of a specific muscular unit. The degree of contraction or relaxation is then modified by relayed evidence that the motion created is that desired by the person. The modifying factors arrive centrally from a multiplicity of sensory sources such as the eye, peripheral sensory end organs, and muscle or joint sensory endings.

The surgeon planning reconstructive surgery on the upper extremity must be aware not only of the complex anatomy of the hand and arm, but also of the physiologic interplay of balanced muscular functions under the influence of complex central nervous coordination. The maintenance of physiologic viability by the central and peripheral circulatory and lymphatic systems must also concern the reconstructive surgeon.

This chapter addresses the fundamentals of hand and upper extremity anatomy and highlights clinical pearls, new anatomic descriptions that may aid surgery of the hand, and

the fundamentals of biomechanics relevant to the hand surgeon. New pictures and dissection videos are now available for the reader to review important anatomic concepts.

Skin, subcutaneous tissue, and fascia

There is great disparity in the character of the skin and soft-tissue envelope covering the dorsum of the hand and that covering the palm. Dorsal skin is thin and pliable, anchored to the deep investing fascia by loose, areolar tissue. These characteristics, coupled with the fact that the major venous and lymphatic drainage in the hand courses dorsally, serve to explain why hand edema is first evident dorsally. The prominent, visible veins in the subcutaneous tissue make it the standard site in which to evaluate venous filling and limb venous pressure on physical examination. The same characteristics make the dorsum of the hand vulnerable to skin avulsion injuries.

Palmar skin, in contrast, is characterized by a thick dermal layer and a heavily cornified epithelial surface. The skin is not as pliable as dorsal skin, and it is held tightly to the thick fibrous palmar fascia by diffusely distributed vertical fibers between the fascia and dermis. Stability of palmar skin is critical to hand function. At the same time, if scar fixation or loss of elasticity occurs in palmar skin, contractures and functional loss result. The skin of the palm is laden with a high concentration of specialized sensory end organs and sweat glands. The surgeon must understand the relationship of the palmar skin creases and the underlying joints in order to plan precise placement of skin incisions for exposure of joints and their related structures (Box 1.1 & Fig. 1.1).

Examination of hand skin during normal ranges of motion in various planes is important in planning incisions or geometrically rearranging lacerations that might result in disabling scar contractures. Most loss of elasticity and some longitudinal shortening are compensated for adequately by mobility and elasticity of the uninjured dorsal skin. On the palmar aspect, however, scar shortening and inelasticity of the skin may result in contracture. The nature of palmar skin, its stabilizing fixation to the palmar fascia, and its position on the concave side of the hand are the bases for such contractures. Littler outlined the specific sites in the palm where a longitudinal scar would impede extension.²⁰ For example, in




Fig. 1.1 Kaplan's cardinal line, along with lines from the ulnar aspect of the middle finger and the ulnar aspect of the ring finger. Point A corresponds with the motor branch of the median nerve and point B with the motor branch of the ulnar nerve.

each digit the geometry has been worked out by noting each joint axis and the kissing surfaces of the palmar skin in full flexion. These diamond-shaped skin surfaces should not be shortened and rendered inelastic by longitudinal scars if limitation of extension is to be avoided (Fig. 1.2).

The palmar fascia consists of resistant fibrous tissue arranged in longitudinal, transverse, oblique, and vertical fibers (Fig. 1.3). The longitudinal fibers concentrate at the proximal origin of the palmar fascia at the wrist, taking origin from the palmaris longus when it is present (in about 80–85% of individuals). The fascia at this level is separable from the underlying flexor retinaculum/carpal ligament, being identified by the longitudinal orientation of its fibers in contrast to the transverse fibers of the retinaculum. The palmar fascia fibers fan out from this origin, concentrating in flat bundles to each of the digits. Generally, the fibers spread at the base of each digit and send minor fibers to the skin and the bulk of fibers distal into the fingers, where they attach to tissues making up the fibrous flexor sheath of the digits. There are attachments of the fascia to the volar plate and intermetacarpal ligaments at each side of the flexor tendon sheath at the level of the metacarpal heads.

Transverse fibers are concentrated in the midpalm and the web spaces. The midpalmar transverse fibers, although intimately associated with the longitudinal bundles, lie deep to them and are inseparable from the vertical fibers that concentrate into septa between the longitudinally oriented structures passing to the fingers. This system of palmar transverse fibers makes up what Skoog (1967) called the transverse palmar ligament.²¹ In fact, the transverse fibers form the roof of tunnels at this point that act as pulleys for the flexor tendons proximal to the level of the digital pulleys. Biomechanical evaluation of the palmar aponeurosis pulley has demonstrated that isolated sectioning did not change the work of flexor tendons or load efficiency.²² Nevertheless, this pulley has been implicated as contributing to the etiology of trigger finger.²³

BOX 1.1 Clinical pearl: Kaplan's cardinal line

Hand anatomist Emanuel Kaplan described specific surface lines that would aid surgeons in locating key structures in the palm of the hand. The cardinal line has often been misquoted; therefore we refer to Kaplan's classic hand text, *Functional and Surgical Anatomy of the Hand*.¹⁹ Kaplan's cardinal line is drawn from the apex of the first web space to the distal edge of the pisiform bone (see Fig. 1.1). Two longitudinal lines are drawn from the ulnar aspect of the middle finger and the ulnar aspect of the ring finger. These will cross the cardinal line. The intersection of the cardinal line and the longitudinal line from the ulnar side of the middle finger corresponds to the motor branch of the median nerve. The intersection of the cardinal line and the longitudinal line from the ulnar side of the ring finger corresponds to the hook of the hamate. The motor branch of the ulnar nerve is found on the cardinal line, equidistant between the hamate and pisiform. See Kaplan's original text for additional surface markings.




Fig. 1.2 (A,B) Schematic representation of the joint axes. The longitudinal dimensions in the midpalmar and mid-dorsal aspect of the digits change maximally. The midaxial line through the three joint axes does not change in length with flexion and extension. Palmar incisions placed longitudinally produce contracture if they pass across the palmar diamonds delineated by lines joining the joint axes (after Littler). Transverse incisions avoid the occurrence of flexion scar contractures. The same principle applies at the wrist. (Redrawn after Chase RA. *Atlas of Hand Surgery*, vol 1. Philadelphia: WB Saunders, 1973.)




Fig. 1.3 Superficial dissection of the palm, showing orientation of the palmar fascia. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.4 The palmar fascia with its longitudinal, transverse, and vertical fibers. The longitudinal fibers take origin in the palmaris longus (when present). Transverse fibers are concentrated in the distal palm supporting the web skin and in the midpalm as the transverse palmar ligament. Vertical fibers extend superficially as multiple, tiny tethering strands to stabilize the thick palmar skin. The deep vertical components concentrate in septa between the longitudinally oriented structures in the fingers. (Redrawn after McCarthy JG. Plastic Surgery. Philadelphia: WB Saunders, 1990.)

Longitudinal fibers pass toward the palmar surface of the thumb, but these fibers are generally less numerous and sometimes difficult to identify. The thumb fibers blend into the deep fascia overlying the thenar muscles. The ulnar extreme palmar fascia blends with the hypothenar fascia. The proximal one-third of this border is the attachment site of the palmaris brevis muscle. Laterally, the muscle attaches to the hypothenar skin and hypothenar fascia.

The vertical fibers of the palmar fascia, which lie superficially to the tough triangular membrane made up by the longitudinal and transverse fibers, consist of abundant vertical fibers to the palm dermis (Fig. 1.4). Deep to the palmar fascia, the vertical fibers coalesce into septa, or the “perforating fibers of Legueu and Juvara”,²⁴ forming compartments for flexor tendons to each digit and separate compartments for the neurovascular bundles together with the lumbrical muscles. There are eight such compartments, which extend proximally to about the midpalm. Proximal to this, there is a common central compartment.²⁵ The marginal septa extend more proximally than the seven intermediate septa closing the central compartment laterally and medially. The major septum between the index flexor tendons and the neurovascular and lumbrical space to the third interspace attaches to the third metacarpal, dividing the thenar or adductor space from the midpalmar space. Knowledge of these vertical compartments aids dissection and identification of structures in operations such as trigger-finger release and Dupuytren’s fasciectomy (Fig. 1.5).

In the fingers, two important bands of fascia are named Grayson’s ligaments and Cleland’s ligaments. Grayson’s ligaments are volar to the neurovascular bundles and are quite flimsy. The much stouter Cleland’s ligaments are dorsal to the neurovascular bundles. These two fascial sheets help contain and protect the ulnar and radial digital arteries and nerves (Fig. 1.6).

Bones and joints

Hand elements

The ability of the hand to resist and create powerful gross action, combined with its capacity to perform intricate fine

movements in multiple planes, reflects the masterful construction of its supporting architecture. Reducing the hand to its supporting skeleton and its restraining ligaments reveals the architectural basis for its varied function. A study of the range of joint motions in the hand and forearm with all motor elements removed discloses the full range and limitations that the skeleton imposes on hand function.

The hand skeleton is divisible into four elements:

1. The fixed unit of the hand, consisting of the second and third metacarpals and the distal carpal row.
2. The thumb and its metacarpal with a wide range of motion at the carpometacarpal joint. Five intrinsic muscles and four extrinsic muscles are specifically influential on thumb positioning and activity.
3. The index digit with independence of action within the range of motion allowed by its joints and ligaments. Three intrinsic and four extrinsic muscles allow such digital independence.
4. The third, fourth, and fifth digits with the fourth and fifth metacarpals. This unit functions as a stabilizing vise to grasp objects for manipulation by the thumb and index finger, or in concert with the other hand units in powerful grasp (Fig. 1.7).

The distal row of carpal bones forms a solid architectural arch with the capitate bone as a keystone. The articulations of the distal carpals with one another, the intercarpal ligaments, and the important transverse carpal ligament (flexor retinaculum) maintain a strong, fixed transverse carpal arch. Projecting distally from the central third of this arch are the fixed central metacarpals, the second and third. Littler called this the “the fixed unit of the hand”. It forms a fixed transverse arch of carpal bones and a fixed longitudinal arch created by the anatomic convexity of the metacarpals. As a stable foundation, this unit creates a supporting base for the three other mobile units. This central beam moves as a unit at the wrist under the influence of the prime wrist extensors (the extensor carpi radialis longus and brevis) and the prime wrist flexor, the flexor carpi radialis. These major wrist movers insert on the second and third metacarpals. Thus, the fixed central unit is positioned for activity of the adaptive elements of the hand around it.

The distal row of carpal bones constitutes a fixed transverse arch. At the level of the metacarpal heads, the transverse arch of the hand becomes mobile, which is possible because the first metacarpal moves through a wide range of motion at the saddle-like carpometacarpal joint. The loose capsular ligaments and the shallow saddle articulation between the first metacarpal and the trapezium allow circumduction of the mobile first metacarpal. Its range of motion is checked by these capsular ligaments, including the volar beak ligament, and by its attachment to the fixed hand axis through the adductor pollicis, the first dorsal interosseous, and the fascia and skin of the first web space. The mobile fourth and fifth metacarpal heads move dorsally and palmarly in relation to the central hand axis by limited mobility at the carpometacarpal joints. These metacarpal heads are tethered to the central metacarpals by the intermetacarpal ligaments. The latter unite adjacent metacarpophalangeal volar plates, which are an intimate part of the joint capsules.

When the head of the first metacarpal is palmar-abducted by thenar muscles innervated by the median nerve, and the




Fig. 1.5 These deep palmar and midpalmar axial views of the hand reinforce the concept of distinct anatomic compartments separated by fascia. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)

fourth and fifth metacarpals are palmar-abducted by the hypothenar muscles innervated by the ulnar nerve, a volar, concave, transverse metacarpal arch is created, approximating a semicircle. The mobile metacarpal heads are pulled dorsally by extrinsic extensor tendons when the thenar and hypothenar muscles relax. It is obvious that a flaccid paralysis of the intrinsic muscles of the hand in median and ulnar nerve palsy will produce a flattened or even reversed transverse metacarpal arch. The active production of a semicircular transverse arch by the thenar and hypothenar muscles creates the proper circumferential arrangement of the metacarpophalangeal joints for convergence of the fingers in flexion. In this position the fingers, flexing at the metacarpophalangeal joints only, converge, forming with the thumb a cone, the apex of which lies over the anatomic center of the hand (Fig. 1.8). A vertical line dropped from the apex of the cone to the center of its base will strike the third metacarpophalangeal joint. This point at the apex of the transverse metacarpal arch is the anatomic center of the hand. With the fingers fully abducted, the tips form radii of equal length from the anatomic center of the hand. The same radius projected proximally falls at the wrist joint.

The most important single motor operating the central hand beam at the wrist level is the extensor carpi radialis brevis, which works against gravity, positioning the pronated hand into extension. In the absence of any other motors it pulls the central third metacarpal into extension, making it the apex of the passively created transverse metacarpal arch.




Fig. 1.7 Exploded view of the functional elements of the hand: (1) the thumb and its metacarpal with a wide range of motion at the carpometacarpal joint; (2) the index digit with independence of action in several planes; (3) the third, fourth, and fifth digits with the fourth and fifth metacarpals; and (4) the fixed unit consisting of the carpal bones with the fixed transverse carpal arch and the second and third metacarpals forming a fixed longitudinal arch. (Redrawn after McCarthy JG. Plastic Surgery. Philadelphia: WB Saunders, 1990.)




Fig. 1.6 The components of the digital fascia that help to anchor the axial plane skin are Grayson's ligaments palmar to the neurovascular bundles and Cleland's ligaments dorsal to the bundles. (Redrawn after McCarthy JG. Plastic Surgery. Philadelphia: WB Saunders, 1990.)

The wrist

The wrist joint is the site for major postural change between the arm beam and the working hand end piece (Fig. 1.9). It has a multiarticulated architecture that creates a potentially wide range of motion in flexion, extension, radial deviation, ulnar deviation, and circumduction. The distal radioulnar joint allows pronation and supination of the hand as the radius rotates around the head of the ulna. The proximal row of carpal bones (scaphoid, lunate, triquetrum, pisiform) articulates with the distal radius and ulna, providing the ability to flex and extend the hand and perform radial and ulnar deviation. The distal carpal row (trapezium, trapezoid, capitate, and hamate), along with the second and third metacarpals, forms the "fixed unit" of the hand.

The radiocarpal joint includes the carpal bones and the distal radius (Fig. 1.10). The principal articulation of the carpus is with the distal surface of the radius. The articular surface of the radius slopes in several planes. In the radial-to-ulnar plane, the radius exhibits an average slope of 22°. In the dorsal-to-palmar plane, the articular surface of the radius slopes 12° with the dorsal surface more distal than the palmar surface. Fractures of the distal radius frequently result in a loss of the normal radiocarpal configuration in one or both planes. A loss




Fig. 1.8 When the adaptive arch is semicircular, the fingers converge in a cone over the anatomic center of the hand – the long-finger metacarpophalangeal joint. (From McCarthy JG. *Plastic Surgery*. Philadelphia: WB Saunders, 1990.)

of the normal dorsal-to-palmar tilt of the articular surface will result in a change in the biomechanical properties of the wrist joint, which may lead to degenerative arthritis.

The relationship of the length of the radius to the length of the ulna is fairly constant in individuals, and is termed ulnar variance. The distal ulna will complete the curve of the articular surface of the radius. If the end of the ulna falls short of this curvature, the condition is termed ulnar negative variance. If the ulna extends distal to this imaginary extension, the condition is termed ulnar positive variance. Either condition may lead to wrist problems. Ulnar negative variance is associated with a higher incidence of Kienbock's disease, avascular necrosis of the lunate. Ulnar positive variance greater than 2–3 mm is associated with ulnar impaction (Fig. 1.11).

Gilula and others have described several anatomic features that denote normal extracarpal and intracarpal architecture.²⁶ A line that follows the proximal articular contours of the proximal row of carpal bones circumscribes a smooth arc, termed the greater arc (Fig. 1.12). A disruption in the smooth appearance of this arc is one of the signs of carpal abnormality, such as abnormal rotation of one of the bones of the proximal carpal row, as would be seen with disruption of the scapholunate ligament. Similarly, the joint line between the proximal and distal row of carpal bones circumscribes another smooth arc, termed the lesser arc. The presence of abnormalities in either of these arcs may be an indication of carpal pathology, either acute or chronic.

The scaphoid and lunate bones of the proximal carpal row form the convex articular counterparts of the concave distal radius for the major wrist articulation. In fact, the articular surface of the radius is divided into scaphoid and lunate fossae (Box 1.2). The triquetrum articulates with the lunate in the proximal row, and with the hamate across the midcarpal






Fig. 1.9 Palmar (A) and dorsal (B) views of the bones of the wrist. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)

Right radius and ulna in supination: anterior view

Right radius and ulna in pronation: anterior view



Carpal articular surface



Coronal section of radius demonstrates how thickness of cortical bone of shaft diminishes to thin layer over cancellous bone at distal end

F. Netter M.D.

Fig. 1.10 Relationship of the radius and ulna at the proximal and distal radioulnar joints. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)



Fig. 1.11 X-ray of ulnar positive variance: this patient has ulnar-sided wrist pain due to ulnar impaction syndrome.

joint. The pisiform is essentially a floating bone, unimportant for carpal stability.

All four of the bones in the distal carpal row present articular surfaces for junction with the metacarpals. The distal carpal row forms a solid architectural arch with the central capitate as the keystone. The nature of the articulations of the distal carpals with one another, and of the carpal ligament




Fig. 1.12 Gilula's lines showing the greater arc and lesser arc of the carpal bones. (Reproduced from Hentz VR, Chase RA. *Hand Surgery: A Clinical Atlas*. Philadelphia: WB Saunders, 2001.)

BOX 1.2 Clinical pearl: blood supply to the scaphoid

Investigations by Gelberman and Menon have described two main vessel systems that perfuse the scaphoid via ligamentous attachments.²⁷ The superficial palmar branch of the radial artery contributes a volar blood supply that feeds the distal scaphoid. The dorsal carpal branch of the radial artery contributes a dorsal blood supply that also primarily feeds the distal scaphoid. Therefore, the proximal scaphoid is poorly vascularized and is susceptible to nonunion after proximal pole fracture.

(flexor retinaculum), is such that they make up a strong and fixed transverse carpal arch (Box 1.3).

The complex motions of the wrist are a product of the sums of the movements of the carpal bones in various planes and degrees of rotation relative to one another. The motion of any one carpal bone is a consequence of several factors. The first factor is the contour of the bone and the arrangements of its articular surfaces. The second is the degree of freedom afforded by intrinsic ligaments, which are ligaments originating from one carpal bone and inserting on another carpal bone, and by extrinsic ligaments, which are ligaments arising from the radius or ulna and attaching to a carpal bone or bones. This complex set of ligaments and the shape of the intercarpal and radiocarpal articulations control movement because no muscles arise or insert on any of the carpal bones except for the pisiform.

This unique adaptation of nature avoids the need for a thickly muscled wrist and hand unit. It permits great flexibility in positioning the hand in space without the need for sets of muscle agonists and antagonists to control the several degrees of freedom of movement.

The proximal row of carpal bones is anchored to the radius by a series of stout palmar ligaments arising primarily from the radius and by an additional set of stout ligaments arising from the ulna and the palmar portion of the triangular fibrocartilage complex. The triangular fibrocartilage complex separates the distal end of the ulna from the ulnar-sided carpal bones and serves to suspend the distal ulna to the radius at the distal radioulnar joint. These primary extrinsic palmar ligaments take the form of an inverted "V" with its apex pointed distally.

The three most predominant nerves innervating the triangular fibrocartilage complex are the dorsal cutaneous branch of the ulnar nerve (100%), the medial antebrachial cutaneous nerve (91%), and the volar branch of the ulnar nerve (73%). Other nerves play a minor role in the innervation of the triangular fibrocartilage complex: the anterior interosseous nerve, the posterior interosseous nerve and the palmar branch of the median nerve.²⁸

BOX 1.3 Clinical pearl: checking for malrotation

The tubercle of the scaphoid is found at the distal flexion crease of the wrist joint, lateral to the tendon of the flexor carpi radialis. It is an important skeletal landmark in evaluating digital malrotations. Normally, each finger points to the scaphoid tubercle when individually flexed. A finger that points away from the tubercle may do so because of destructive flattening of the carpal arch. More commonly, it may result from malrotation following a metacarpal or phalangeal fracture (Fig. 1.13).




Fig. 1.13 Each finger in correct alignment points to the tubercle of the scaphoid when flexed individually. (Redrawn after Chase RA. *Atlas of Hand Surgery*, vol. 1. Philadelphia: WB Saunders, 1973.)

Dorsally, the extrinsic radiocarpal ligament complex is thinner and is primarily a condensation of capsular tissues, except for two stout structures, the dorsal intercarpal ligament joining the distal pole of the scaphoid and the triquetrum, and the dorsal radiocarpal ligament. According to work by Viegas, these two dorsal ligaments form a unique lateral “V” configuration that allows variation in length by changing the angle of the “V” while maintaining a stabilizing force on the scaphoid during wrist range of motion.²⁹

The intrinsic ligaments are broad, stout structures that link one carpal bone to another, either within the proximal or distal row, or linking one carpal row to the other. The two most significant intrinsic ligaments are the scapholunate ligament and the lunotriquetral ligament. The scapholunate ligament anchors the scaphoid to the lunate to allow these two carpal bones to move in synchrony. Berger has subdivided this U-shaped structure into three regions: dorsal, proximal, and palmar.³⁰ The dorsal region is thick and controls scapholunate stability. The proximal portion, composed mainly of fibrocartilage, and the palmar region, with thin and obliquely oriented fibers, are less important for stability.³¹ The lunotriquetral

ligament is also composed of dorsal, proximal, and palmar portions. There is less motion between these two carpal bones. Disruption of either the scapholunate or lunotriquetral ligaments may lead to wrist instability as the normal restraints on synchronous motion are removed.

Joint motion

The bony anatomy of the hand is presented in Fig. 1.14. Normal metacarpophalangeal joint motion in the fingers ranges from 0 to 90°. Lateral activity in the metacarpophalangeal joints is limited by the rein-like collateral ligaments. These ligaments are loose and redundant when the metacarpophalangeal joints are in extension, allowing maximal medial and lateral deviation. As the metacarpophalangeal joint is flexed, the cam effect of the eccentrically placed ligaments and the epicondylar bowing of the collateral ligaments result in tightening and strict limitation of lateral mobility (Fig. 1.15). The fingers that have been fixed in extension during a period of healing have had the stage set for collateral ligament shrinkage and locking of the metacarpophalangeal joints in hyperextension.

The proximal interphalangeal joint can be pushed to 110° of flexion, but extension usually cannot be carried beyond 5° of hyperextension because of the ligamentous volar plate, which is an inseparable part of the joint capsule. The medial and lateral collateral ligaments are a part of the capsule. They are radially fixed in a manner that allows no medial or lateral deviation of the joint in any position. The shape of the articular joint surface also strongly contributes to this stability in lateral motion.

The distal interphalangeal joints of the fingers can be pushed into about 90° of flexion before they are limited by the dorsal joint capsule and extensor mechanism. The distal interphalangeal joints extend to 30° of hyperextension. There is no lateral mobility in these joints with the collateral ligaments intact. The collateral ligaments of the distal interphalangeal joints are simply thickened medial and lateral portions of the joint capsule.

Biomechanical concept: joint motion

Brand and Hollister, in their textbook, *Clinical Mechanics of the Hand*, discuss how joints move.³² An axis of rotation of a joint refers to a line fixed to the proximal bone about which the motion of the distal bone appears to be a pure rotation. For the simple (hinge type) interphalangeal joints of the fingers, the motion occurs only in flexion and extension; the axis of rotation is perpendicular to the sagittal plane and is located in the distal head of the phalanx proximal to the joint. A related concept is that of the degrees of freedom of a joint. The degrees of freedom of a joint are the minimum number of axes of rotation that can be used to describe completely the motion of the bone distal to the joint. The wrist as a whole, for example, has two degrees of freedom (flexion–extension and radial–ulnar deviation), represented by two nearly perpendicular axes of rotation.³³ The kinematics of more complex joints such as the thumb carpometacarpal joint³⁴ or the intercarpal joints³⁵ is still the subject of research and thought to have at least two degrees of freedom with nonintersecting, nonperpendicular axes of rotation.




Fig. 1.14 Bony anatomy of the wrist and hand. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.15 (A–D) The true collateral ligaments of the metacarpophalangeal joint are loose in extension but tight in flexion of the joint as a result of the cam effect of the metacarpal head in relationship to the proximal phalanx. This accounts for the lack of lateral mobility of the joint when it is flexed. (Redrawn after Chase RA. *Atlas of Hand Surgery*, vol. 1. Philadelphia: WB Saunders, 1973.)

In each finger, there is no difference between the radii of curvature of the ulnar and radial condyles of the middle phalanx head. Conversely, the radius of curvature of the distal phalanx ulnar groove is significantly greater than that of the radial groove. This asymmetry between the distal phalanx grooves and the middle phalanx results in a translational component during the flexion of the distal interphalangeal joint that may contribute to degenerative changes and development of arthritis.³⁶

The proximal and distal interphalangeal joints are hinge joints: any lateral motion is limited in all phases of flexion and extension by radially oriented collateral ligaments, which are tight at any angle. The metacarpophalangeal joints, in contrast, allow motion through several axes. The capsule, including the collateral ligaments and volar plate, is quite lax, allowing medial and lateral deviation, flexion, extension, and thereby circumduction and a small degree of distraction. In the absence of other sources of stabilization, upon cutting of the collateral ligaments the metacarpophalangeal joint becomes a flail, unstable mechanism. Nature, fortunately, has created another source of lateral stability – the interosseous muscles. By virtue of the selective variable pull, the interossei normally influence lateral motion in the metacarpophalangeal joint to the extent allowed by the unyielding collateral ligaments. If the collateral ligaments are sacrificed, the interossei remain the sole source of lateral stability. When there is intrinsic (ulnar) paralysis, if the collateral ligaments are sacrificed, all lateral stability is lost and disastrous ulnar deviation occurs. At the interphalangeal joints lateral stability is again dependent on the collateral ligaments, but at this level there is no second line of defense. The collateral ligaments of the

BOX 1.4 Clinical pearl: check rein ligaments

Check rein ligaments are, in fact, abnormal structures that are found only after fibrosis of the proximal interphalangeal joint occurs.³⁷ The volar lateral ridges of the proximal phalanx are termed “assembly lines” and represent a coalition of the flexor sheath and Cleland’s and Grayson’s ligaments. Normally, there is no connection between the volar plate and these assembly lines. However, in the proximal interphalangeal joint with a flexion contracture, fibrosis has occurred and stout check rein “ligaments” have formed from the volar plate that prevent full joint extension.

interphalangeal joints, therefore, cannot be sacrificed without creating a lateral instability that is curable only by fusion of the interphalangeal joints.

Palmar or volar plates are found in the metacarpophalangeal and interphalangeal joints where they reinforce the joint capsules, enhance joint stability, and limit hyperextension. The plates of the MCP and IP joints are structurally and functionally similar. The volar plates of the metacarpophalangeal joints are the sites of insertion of the intermetacarpal ligaments, which limit separation or fanning of the metacarpal heads. The volar plate is fixed to that portion of the capsule that originates from the proximal phalanx, and therefore the plate moves with the proximal phalanx in flexion and extension. Dorsal to this ligament on each side of the metacarpal heads are sagittal bands that connect the volar plates to the tendon of the extensor digitorum and to the extensor expansion. The volar plates to the proximal and distal interphalangeal joints are also stout structures that may become scarred in cases of fracture/dislocation and may ultimately lead to joint flexion contractures (Box 1.4).

The thumb

The thumb occupies the extreme radial position in the transverse arch of the hand. The column of bones making up the thumb architectural base comprises the two phalanges, the metacarpal, and the trapezium. Its formula differs from that of the remaining digits by virtue of its two named phalanges rather than three. From a functional point of view, however, the thumb metacarpal can be compared to a proximal phalanx and the trapezium to a grossly foreshortened metacarpal. This suggests that the thumb is a digit recessed by a short metacarpal (the trapezium) with the proximal phalanx loosely syndactylized to the second metacarpal. There is no clear evidence to support this point of view phylogenetically, but it seems sensible in understanding the gross anatomy of the thumb’s architecture. Like the finger metacarpophalangeal joints, the thumb’s metacarpotrapezial joint has the greatest degree of freedom of any in the digital rays. The metacarpotrapezial joint is a synovial joint separated and distinct from the general intercarpal joints of the wrist. The trapezium itself articulates with the trapezoid and scaphoid with ligamentous restraints that sharply limit trapezial motion in relationship to the carpus (Fig. 1.16).

The uniquely wide range of thumb motion as compared with that of the remaining digits is attributable largely to the joint between the base of the first metacarpal and the trapezium. In simplest terms, it is described as a biconcave double saddle joint with a permissively loose capsule. That




Fig. 1.16 The osteoarticular column of the thumb as compared with that of a finger. The trapezium in this comparison is the equivalent of a foreshortened metacarpal, and the metacarpotrapezial joint of the fingers. MC metacarpal; PP proximal phalanx; DP distal phalanx; ROM range of motion. (Redrawn after Chase RA. *Anatomy of the thumb*. In: Strickland J (ed.) *The Thumb*. Edinburgh: Churchill Livingstone, 1989.)

combination allows movements best described as flexion, extension, adduction, and abduction through infinite combinations that result in circumduction. The thumb rotates as a cone with its apex at a point where the axes of flexion-extension and abduction-adduction cross within the carpometacarpal joint.³⁸⁻⁴⁰

The first carpometacarpal joint is best described as a double saddle where one saddle sits atop another, allowing three degrees of motion: (1) flexion-extension; (2) abduction-adduction; and (3) medial rotation-lateral rotation.⁴¹ As the thumb rocks along the central ridge of the trapezoidal saddle in abduction and adduction, the metacarpal saddle's extensions over the trapezoidal saddle engage the trapezoidal saddle's medial or lateral condylar parts along the central axis. The axis line is curved in such a way that when the metacarpal is adducted, it locks into medial rotation, and when it is abducted, it locks into lateral rotation. This accounts for the sweep of the thumb in adduction to abduction along the transverse arch of the metacarpal heads. This mandatory rotation into medial rotation on adduction helps to position the thumb for pulp-to-pulp opposition of the thumb to the fingers. In neutral position the axis of the trapezium, represented by its central ridge, sits at about 60° from a line through the heads of the central stable second and third metacarpals. The base of the first metacarpal has a quadrilateral articular surface that is a complementary match to the articular surface of the trapezium. Its concavity is slightly exaggerated on the ulnar volar side by a protrusion

or "beak" for insertion of the important anterior oblique carpometacarpal ligament, commonly referred to as the "volar beak" ligament. As in some other joints in the body (e.g., the shoulder), stability and close coaptation of the joint surfaces between the trapezium and the first metacarpal are dependent on the presence of operational muscles and tendons. As noted above, there is a lot of slack in the joint capsule, allowing a wide range of motion, including joint distraction of up to 3 mm.⁴²

An important stabilizing capsular ligament for the first carpometacarpal joint is the anterior oblique carpometacarpal ligament or volar beak ligament referred to above. It extends like the leg of a person seated in the trapezoidal saddle extending from the "beak" of the first metacarpal to the anterior crest of the trapezium and adjacent intercarpal ligaments. It retains the fragment of bone fractured free from the base of the metacarpal as the metacarpal displaces radially in Bennett's fracture. In advanced metacarpotrapezial joint arthritis it weakens and attenuates, as also does the intermetacarpal ligament, allowing radial subluxation of the metacarpotrapezial joint.⁴³

The ligament at the radial border of the joint is like a radial collateral ligament and is referred to as the dorsoradial or anteroexternal ligament. Thus, the radial side of the joint support is the right anteroexternal ligament, which inserts close to but beneath the insertion of the abductor pollicis longus on the radial base of the first metacarpal. It forms part of the joint capsule and then attaches to the anterior crest of the trapezium. Dorsally, one sees the posterior oblique ligament crossing the dorsal joint capsule from the radially positioned posterolateral tubercle of the trapezium to attach to the ulnar base of the first metacarpal.

There is a stout intermetacarpal ligament between the base of the first metacarpal and the adjacent base of the second metacarpal, and good evidence that this ligament together with the anterior oblique ligament is a key to prevention of radial subluxation of the metacarpotrapezial joint, as seen in arthroses of the joint.⁴⁴ Function and range of motion within the limits imposed by these ligaments are influenced by the extrinsic and intrinsic muscles of the thumb and the external forces applied to the thumb. Bettinger and Berger have updated this ligamentous anatomy to include 16 different ligaments that are thought to stabilize the trapezium and trapeziometacarpal joint.⁴⁵

The first metacarpophalangeal joint differs from other metacarpophalangeal joints in several respects in both anatomic make-up and function. Generally, the first metacarpophalangeal joint range of motion in flexion and extension, as well as abduction and adduction, is less than that in the finger metacarpophalangeal joints. The metacarpal and proximal phalanx are more stout in order to accommodate to greater forces normally borne by the thumb in pinching and grasping. The head of the first metacarpal is different because the radial articular prominence is larger than the ulnar. The articular surface of the proximal phalanx is fashioned reciprocally to match. The collateral ligaments are similar to those of finger metacarpophalangeal joints. The metacarpophalangeal portion is taut in flexion and looser in extension. In extension, the portion of the fanlike collateral ligaments to the palmar plate is taut; thus, adduction and abduction are limited in both extension and flexion.⁴⁶ Some pronation but no supination is allowed at the metacarpophalangeal joint when it is in

extension. In supination, the joint locks into a stable position for secure grasping.

The sturdy fibrocartilaginous volar plate of the metacarpophalangeal joint extends from the palmar base of the proximal phalanx to the neck of the metacarpal. It regularly incorporates two sesamoid bones, one medial and one lateral to the flexor pollicis longus.

The nature of the condyle of the proximal phalanx of the interphalangeal joint to the thumb is such that, upon flexion of the joint, pronation of the distal phalanx occurs.

Muscles and tendons

Extrinsic extensors (Video 1.1 ►)

Extensor muscles lie on the dorsum of the forearm and hand and are innervated by the radial nerve (Figs. 1.17–1.19). The brachioradialis is a flexor of the elbow joint but is included with the extensor muscles because it is supplied by the radial nerve. The brachioradialis and the extensor carpi radialis longus originate from the lateral supracondylar ridge of the humerus. The four superficial extensors (extensor carpi radialis brevis, extensor digitorum communis, extensor digiti minimi, and extensor carpi ulnaris) originate from the common extensor tendon which is attached to the supracondylar ridge and the lateral epicondyle.

The extensors can be divided by function. The extensor carpi radialis longus and brevis and the extensor carpi ulnaris serve to extend the wrist. The extensor digitorum communis, extensor indicis proprius, and the extensor digiti minimi are finger extensors. Three extrinsic extensors assist in thumb motion: abductor pollicis longus, extensor pollicis brevis, and extensor pollicis longus.

Biomechanical concept: muscle structure

Muscles are composed of tissue that can actively contract under the influence of the brain and spinal cord to produce hand and finger motion and forces by pulling on bones via tendons.^{47,48} Muscle tissue is composed of parallel arrangements of muscle fibers that can actively shorten and passively resist stretching, but cannot actively lengthen. The muscles of the hand anchor to bone at either end, typically by a short tendon at their origin (proximal end) and a long tendon at their insertion (distal end). Muscle fibers run along the length of the muscle attaching to tendon at either end. The aponeurosis is the transitional region where the contractile fibers of the muscle interdigitate with the collagen fibers that form the tendon. Tendons are stout parallel bundles of collagen fibers that often cross multiple joints of the hand before inserting into bone. Some tendons of the hand are atypical as they bifurcate or combine before inserting into bone to form the extensor mechanism (or extensor hood) of the fingers. The lumbrical muscle is atypical as it both originates from and inserts on to tendon (the flexor profundus tendon and the extensor mechanism, respectively) and has no direct bony attachment.

Striated muscle fibers are themselves parallel assemblies of similarly long cells with multiple nuclei containing sarcomeres,

the fundamental contractile unit of muscle tissue. At the biochemical level, sarcomeres are interdigitated filaments of f-actin and myosin proteins. Muscle activation and contraction occur when a neural command causes the release of calcium ions inside the muscle cell to cause the free end of the myosin filaments to “ratchet” past the f-actin filaments to increase the overlap between them by metabolizing adenosine triphosphate, an important source of energy fueling cellular processes. The maximal force a muscle can produce is proportional to the number of parallel muscle fibers that compose it (physiological cross-sectional area), and the angle the fibers make with the line of action of the tendons (pennation angle). Mammalian muscle tissue is considered to produce a maximal stress of around 35 N/cm², which is a remarkable ratio of force per unit weight that is difficult to match artificially. In addition, the connective tissue that holds together the muscle fibers grants muscle tissue passive viscoelastic properties.


The extensor retinaculum prevents bowstringing of tendons across the wrist (Fig. 1.20). Six extensor compartments exist (Video 1.1 ► and Fig. 1.21): (1) abductor pollicis longus and extensor pollicis brevis; (2) extensor carpi radialis longus and extensor carpi radialis brevis; (3) extensor pollicis longus; (4) extensor digitorum communis and extensor indicis proprius; (5) extensor digiti minimi; and (6) extensor carpi ulnaris.

Extension of the phalanges of the fingers and thumb is dependent both on long extensors at the metacarpophalangeal joints and on an interplay between the long extensors and intrinsic muscles at the interphalangeal joints. The extensor digitorum is a series of tendons with a common muscle belly that enters into the central extensor of each of the fingers. There are intertendinous bridges between these separate tendons over the dorsum of the hand. Independent long extensor power is supplied to the index finger through the extensor indicis and to the little finger through the extensor digiti minimi. In each case the independent extensor lies on the ulnar side of the long extensor tendon to these two fingers from the extensor digitorum (Fig. 1.22).

Biomechanical concept: the extensor mechanism of the fingers (Fig. 1.23)

The extensor tendons are attached by dorsal expansions or dorsal hoods (Video 1.2 ►). These expansions are divided into three structures. (1) Lateral bands pass on either side of the proximal phalanx and extend all the way to the distal phalanx. The lumbrical and dorsal and palmar interossei muscles contribute to the lateral bands. (2) A single central slip passes down the middle of the finger, ending at the base of the middle phalanx. (3) The retinacular ligament runs obliquely along the middle phalanx, and connects the fibrous digital sheath on the volar side of the phalanges to the extensor expansion.

The extensor hood of the fingers is an example of tendons bifurcating and recombining in an intricate network that results in complex muscle actions. For example, extensor muscles can flex the proximal interphalangeal joints, and intrinsic



F. Netter M.D.

Fig. 1.17 The anatomy of the extensor muscles: superficial to deep. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.18 The anatomy of the extensor muscles: superficial to deep. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.19 (A,B) The anatomy of the extensor muscles: superficial to deep. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)



Posterior (dorsal) view**Cross section of most distal portion of forearm**

Fig. 1.20 The extensor retinaculum and extensor compartments. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.21 The extensor compartments. (Upper limb cadaver dissection, Stanford University Division of Plastic Surgery. © 2015 James Chang, Anaïs Legrand. All Rights Reserved.)

muscles can simultaneously flex the metacarpophalangeal joint and extend the interphalangeal joints.⁴⁹ The effect of each muscle at each joint, however, may depend on finger posture and the distribution of tendon tension. Detailed cadaver studies have shown that, although the change in length of the different components of the extensor hood is relatively small,^{50,51} their spatial orientation varies considerably from one finger configuration to another, and it has been suggested that the extensor mechanism may act as a floating net to amplify tendon forces^{52,53} or to coordinate joint motion.^{54,55} However, the anatomy of the insertion of the extrinsic and intrinsic muscles is quite complex and shows variations in the geometry of muscle bellies and insertion tendons.^{56,57}

Each of the three extrinsic muscles to the thumb on its extensor surface inserts on one of the thumb bones. The abductor pollicis longus inserts on the metacarpal where it primarily radially abducts the metacarpal, but since it bridges the wrist it secondarily radially deviates the wrist. The extensor pollicis brevis inserts on the proximal phalanx, so that it primarily acts as an extensor of the metacarpophalangeal joint but acts at the other joints with the abductor pollicis longus.




Fig. 1.22 Anatomic relations of the extensor digitorum, extensor indicis and extensor digiti minimi muscles. (Upper limb cadaver dissection, Stanford University Division of Plastic Surgery. © 2015 James Chang, Anaïs Legrand. All Rights Reserved.)

The extensor pollicis longus inserts on the distal phalanx and is the primary extensor of the interphalangeal joint. It secondarily acts to extend and dorsally abduct the other two thumb joints.

Pronators and supinators


The pronator teres originates from the common flexor origin and inserts at the midportion of the radius (Fig. 1.24). It is innervated by the median nerve and is a primary forearm pronator and a weak forearm flexor. The pronator quadratus is a short wide muscle that spans transversely across the distal radius and ulna. It is also innervated by the median nerve and is a forearm pronator. At the upper border of the pronator quadratus muscle, the anterior interosseous artery pierces the interosseous membrane and reaches the back of the forearm, where it anastomoses with the dorsal interosseous artery (Fig. 1.25). The supinator originates from the lateral epicondyle of the humerus and inserts on the proximal third of the radius. It is innervated by the deep branch of the radial nerve and is a primary supinator, assisted by the biceps brachii.

Extrinsic flexors (Video 1.3 ▶)

Flexion of the phalanges into the palm is a complicated motion representing the sum of actions of the long flexors (profundus and superficialis) and long extensors (extensor digitorum, extensor digiti minimi, and extensor indicis), modified and enhanced by the intrinsic muscles (interossei and lumbricals) (Figs. 1.26–1.31). The long flexors to the fingers are responsible for flexion of the interphalangeal joints and are supplements to active flexion of the metacarpophalangeal joints and the wrist joint.⁵⁸

Biomechanical concept: muscle force production

Muscles can produce force in different ways.⁵⁹ Concentric contractions occur when muscle fibers can shorten to induce tendon stretch, tendon excursion, and/or joint motion. Eccentric contractions occur when tendon forces overpower the passive and active force the muscle can produce and the muscle fibers lengthen during muscle activation. Isometric contractions occur when the muscle is not allowed to shorten (calling this state of the muscle a “contraction”, when in reality it remains the same length, is a historical artifact). The structural and biochemical properties of the sarcomere make the exact magnitude of muscle force for a given level of neural excitation a function of length of the fibers, velocity at which fibers shorten or lengthen, and its previous activation history. The force–length relationship of muscle (sometimes called the Blix curve) indicates that there is an optimal length of the fiber at which maximal force can be produced, and it drops at longer or shorter fiber lengths (Fig. 1.32). Thus, the length at which the muscle is placed in reconstructive surgeries or tendon transfers can greatly influence the force the muscle can produce postoperatively. *The force–velocity relationship of muscle indicates that muscle force drops greatly from its isometric level when muscle fibers shorten rapidly during concentric contractions, and rises to a plateau almost double its isometric level when muscle fibers lengthen rapidly during eccentric contractions* (Fig. 1.33).



C. Machado
— M.D.

Fig. 1.23 The extensor mechanism of the fingers. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)

Right forearm: anterior view




Fig. 1.24 The forearm pronators and supinators. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.25 Anatomic relations between the pronator quadratus muscle and the anterior interosseous artery. (Upper limb cadaver dissection, Stanford University Division of Plastic Surgery. © 2015 James Chang, Anaïs Legrand. All Rights Reserved.)

The flexors are located on the volar side of the forearm and wrist and are innervated by the median nerve, except the flexor carpi ulnaris, and the flexor digitorum profundus to the ring and small fingers, which are innervated by the ulnar nerve (see Figs. 1.26–1.31). The flexor carpi radialis, flexor carpi ulnaris, and palmaris longus provide wrist flexion. The digital flexors (flexor digitorum superficialis, flexor digitorum profundus, and flexor pollicis longus) pass through the carpal tunnel to provide dual flexion to the fingers and single flexion to the thumb (Video 1.3 ▶).

The flexor digitorum superficialis tendon lies palmar (superficial) to the profundus tendon in the palm.⁶⁰ It flattens, then splits at the level of the proximal phalanx, and its two tails surround the profundus, decussating behind the profundus to insert on the middle phalanx. The flexor digitorum profundus perforates the flexor digitorum superficialis to run superficially along the length of the proximal and middle phalanges to insert at the base of the distal phalanx. The superficialis and profundus flexors contribute most of the force for digital flexion. The flexor digitorum profundus of the index finger is unique in that it has an independent muscle belly. The flexor pollicis longus inserts at the distal phalanx of the thumb (Box 1.5).

In the finger and distal palm, the flexor tendons pass through a fitted fibrous flexor sheath that has thickened areas. The tendons at this level are surrounded by synovial sheaths. The flexor pollicis longus is the interphalangeal flexor of the thumb equivalent to the finger profundi. The flexor digitorum profundus is the only muscle that flexes the distal interphalangeal joint. Testing for profundus function requires observation of active flexion of the distal interphalangeal joint.

BOX 1.5 Clinical pearl: independent and common flexor muscles

The flexor profundi to the third, fourth, and fifth fingers work from a common muscle belly. Acting in unison, they fit the architectural concept of this unit as a stable vise for grasping objects. The independent function of the index profundus frees the index finger for use with the thumb to manipulate an object grasped by the viselike ulnar unit. Independence of action is well developed in the superficialis muscles and the intrinsic muscles.

Selected flexion of one or more of the metacarpophalangeal joints, or either the proximal or distal interphalangeal joint, depends on stabilizing fixation of the remainder by flexor–extensor interplay. Elimination of any single motor element reduces the selective adaptability of a finger.

As noted above, a muscle may positively influence any joint between its site of origin and its insertion. The flexor digitorum profundus muscle originates in the forearm, and its tendon therefore bridges the wrist joint, the metacarpophalangeal joint, the proximal interphalangeal joint, and the distal interphalangeal joint before it inserts on the distal phalanx. It may flex any of these joints, depending on the dynamic fixation of the others. Fixation of the distal interphalangeal joint converts the profundus tendon into a functional superficialis tendon by recessing its prime site of action to the proximal interphalangeal joint. By combined fixation of any of the joints, the profundus tendon may primarily flex any selected one.

Biomechanical concept: the shape of hand muscles

Many muscles of the hand depart from the simple fusiform (fish-like) shape seen in most textbooks. Many are flat, while others have multiple bellies. The interosseous muscles, for example, are bipennate. That is, a central common tendon is pulled on by fibers originating in different bones. The opposite arrangement is also found in muscles like the flexor superficialis of the fingers, which originate in a short belly that leads to a tendon that inserts in a second larger belly that then subdivides into four branches, each with a superficialis tendon to each finger. While it is possible to find muscle fibers that fire only when one finger is being flexed,^{61,62} the degree to which force production in each belly is independent of the others is still unknown. Moreover, most extrinsic flexor and extensor muscles have tendons that are connected by thin strands of collagen at the level of the metacarpals that prevent independent motions of the fingers (try to extend the ring finger with all other fingers flexed). Other muscles such as the adductor pollicis have a fan-shaped origin where the resultant force at the insertion tendon depends on the distribution of force among muscle fibers. Whether or not muscle fibers fire in synchrony to produce a consistent resultant force, or if the fibers can be subdivided in functional regions to produce different resultant forces, is still unknown.

It is intriguing to realize that under certain conditions the flexor profundus may accentuate extension of the proximal interphalangeal joint. The profundus pulling primarily at the distal interphalangeal joint may flex it acutely. In flexing the distal interphalangeal joint, the insertion of the extensor mechanism is advanced distally. This advancement, combined with either a contraction or fixation of the lateral bands, results in extension of the proximal interphalangeal joint. This effect is easily aborted by the intact flexor superficialis, whose prime flexion function is exerted on the proximal interphalangeal joint. Absence of the superficialis, whether occasioned by injury or by tendon graft replacement of the profundus only, results not infrequently in flexion of the distal interphalangeal




Fig. 1.26 The anatomy of the flexor muscles, from superficial to deep. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.27 The anatomy of flexor muscles in relation to surrounding neurovascular elements. (Upper limb cadaver dissection, Stanford University Division of Plastic Surgery. © 2015 James Chang, Anaïs Legrand. All Rights Reserved.)

joint with recurvatum deformity at the proximal interphalangeal joint. This can be corrected by fusion of the distal interphalangeal joint, making the profundus a functional superficialis, or by tenodesis or capsulodesis of the proximal interphalangeal joint in mild flexion. It is wise to keep in mind the innumerable functional circumstances that can be created by selective interplay of multiple motor forces exerted through a series of interdependent joints.⁶³

Biomechanical concept: moment arms

The moment arm of a tendon about an axis of rotation of a joint is defined as the shortest distance between the axis of rotation and the tendon as it crosses the joint (Fig. 1.34). This distance can vary with joint angle because of the suspension system of pulleys guiding flexor tendons, and/or the curved but not circular contour of the joint surfaces guiding extensor tendons.⁶³ The greater the moment arm, the greater the excursion of a tendon (and change in length of a muscle) that accompanies a given angle of rotation of the joint. Similarly, the moment of force (rotational action) of a tendon force about an axis of rotation increases with the magnitude of the moment arm of the tendon. These relationships between moment arm and tendon excursion/force assume hinge-type joints without sliding actions, which holds well for most finger joints. Note that a tendon that crosses a joint with multiple degrees of freedom (such as the thumb carpometacarpal joint) will have simultaneous and different actions about each axis of rotation.

The gross anatomic configuration and function of the extrinsic digital flexor tendons have been known since antiquity. The great growth in our knowledge and understanding of functional biomechanics, muscle physiology, tendon nutrition, and blood supply has influenced the management of problems involving these important flexor tendons. The long flexor tendons cross multiple joints. The tendon–muscle unit has an effect on each joint it crosses, which is altered by the positioning of the other joints in the linkage system. Thus, the influence of the long flexor tendon on one joint in the system is

augmented by the function of its antagonists at each of the other joints it crosses. For example, a digital flexor tendon aids in flexing the wrist, but its flexion capability within the digit at the metacarpophalangeal joints and interphalangeal joints is increased by wrist extension using wrist extensors, which in fact are antagonists to the digital flexors at the wrist. This is the simplified definition of synergistic function – finger flexion augmented by wrist extension, and vice versa.

Synergistic and antagonistic groups of muscles in hand function must be considered when functional substitution by tendon transfers is contemplated. Obviously, certain groups of muscles have developed functional synergism, which makes readjustment natural when one group is transferred to take on the function of the other. Examples of such natural synergism are the united functions of the wrist flexors and digital flexors or the wrist extensors and digital flexors.

In its course from forearm to fingers, the digital profundus flexor crosses the palmar aspect of the wrist joint, the metacarpophalangeal joint, and the interphalangeal joints. The relationship of the tendon to the joint axes is maintained by retinacular structures, or pulleys. This prevents the bowstringing effect, which would allow the tendon to move away from the joint axis, changing the moment arm and therefore the force exerted at that joint by the flexor tendon. The finely balanced relationship between the flexor muscle–tendon unit at each joint in the series may be disrupted by such a change. Such alterations can be compensated for, to some extent, by graded, proportional changes in the controlled power of antagonists, but the physiologic balance may be interfered with.

The retinacular system

The large, restraining pulley at the wrist, which serves all the long digital flexors, is the transverse carpal ligament (Fig. 1.35). It bridges the volar surface of the carpals from the pisiform and hook of the hamate medially to the scaphoid tubercle and trapezium laterally. It confines the nine extrinsic flexor tendons and the median nerve within the carpal tunnel, and prevents bowstringing of the flexor tendons at the wrist.

Three pulleys housing the flexor pollicis longus within the thumb are usually present. The proximal annular pulley is at the level of the metacarpophalangeal joint arising from the volar plate and base of the proximal phalanx. The distal annular pulley is located over the volar plate of the interphalangeal joint. Between the two is a single oblique pulley that originates proximally on the ulnar side of the middle phalanx, where it also gains fibers from the adductor pollicis before it extends to the middle one-third of the radial palmar surface of the middle phalanx. The oblique pulley must be preserved in order to prevent bowstringing of the flexor pollicis longus tendon.

Four or five discrete annular pulleys and three cruciate bands are ordinarily present in the fingers (Fig. 1.36). The most proximal pulley (A1) begins 0.5 cm proximal to the metacarpophalangeal joint. It is anchored to the volar plate and the proximal phalanx. Just distal to it is the second annular band (A2), which is the largest pulley, extending to nearly the proximal one-half of the proximal phalanx. The first cruciform band (C1) lies distal to A2 and well proximal to the proximal interphalangeal joint. The third annular pulley (A3) lies over the proximal interphalangeal joint arising from its volar plate.

Text continued on p. 32





Fig. 1.28 The anatomy of the flexor muscles, from superficial to deep. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)



**Right forearm:
anterior (palmar) view**

F. Netter M.D.

Fig. 1.29 The anatomy of the flexor muscles, from superficial to deep. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.30 The anatomy of the flexor muscles, from superficial to deep. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.31 The anatomy of the flexor muscles, from superficial to deep. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.32 The Blix curve. The maximal force is plotted on the vertical axis, and the muscle fiber length is plotted on the horizontal axis. There is an optimal length of the fiber at which maximal force can be produced, and this drops at longer or shorter fiber lengths.




Fig. 1.33 The force-velocity curve. The percentage of maximal isometric force is plotted on the vertical axis, and the relative shortening velocity is plotted on the horizontal axis. Therefore, muscle force drops from its isometric level when muscle fibers shorten rapidly during concentric contractions and rises to a plateau almost double its isometric level when muscle fibers lengthen rapidly during eccentric contractions.





Fig. 1.35 (A–D) The flexor tendon pulley system for fingers and thumb. (Redrawn after Chase RA. *Atlas of Hand Surgery, vol. II*. Philadelphia: WB Saunders, 1984.)








Fig. 1.34 The moment arm is defined as the shortest distance between the axis of rotation and the tendon as it crosses the joint.

Usual arrangement**Common variation****Lumbrical muscles: schema**

Note: Flexor digitorum superficialis and profundus tendons encased in synovial sheaths are bound to phalanges by fibrous digital sheaths made up of alternating strong annular (A) and weaker cruciform (C) parts (pulleys).



F. Netter M.D.

Fig. 1.36 Orientation of the flexor tendon sheaths, flexor tendons, and pulleys. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)

The second cruciate ligament (C2) is at the base of the middle phalanx. The fourth annular pulley (A4) lies over the middle one-third of the middle phalanx, and just distal to it is the third cruciate (C3). Often it is possible to identify thickening of the sheath over the distal interphalangeal joint, which, when present, is designated the fifth annular pulley (A5). The A2 and A4 pulleys insert directly into bone over the proximal and middle phalanges, respectively. In contrast, A1, A3 and A5 are narrower, more flexible, and insert mostly into the volar plate; additionally, with the cruciate pulleys, they permit compression without impingement and expansion during finger flexion and extension, respectively.

The pulleys are strategically placed to maintain the relationship of the flexor tendons to the axis of each finger joint, thus preventing the bowstring effect. The A2 and A4 pulleys are crucial to prevent bowstringing. The gaps between pulleys allow unrestrained flexion and extension of the joints by folding and pleating of the thin sheath between pulleys.

The synovial sheaths are closed sacs around the tendons composed of a visceral layer on the tendon surface and a parietal layer on the fibrous sheath surface. The thumb synovial sheath is continuous from the wrist to the distal extreme of the flexor pollicis longus. The digital synovial sheaths for the index, long, and ring fingers usually start at the level of the distal palmar crease and extend to the distal interphalangeal joints. Often the little-finger sheath extends more proximally to communicate with a common sheath around the finger flexors and then across the wrist to the distal forearm, where tendons pass through the carpal tunnel.

During embryonic development, synovial sacs form where the flexor tendons are subject to restraint by retacula. The tendon invaginates into the sac, creating a two-layered, closed synovial membrane around the tendon. The tendon carries its segmental nutrient vessels, and thus with invagination a mesentery-like mesotenon is formed. As time passes, and where the tendon has great excursion in relationship to adjacent bone, the mesentery refines itself to tiny, flexible bands, or vincula. At the sites of insertion, where differential motion between the bone and tendon is least, the mesenteric configuration persists, as it does for flexor tendons in the hand outside the confining tunnels. The vincula brevia form the residual mesotenon at the sites of insertion of the profundus and superficialis tendons on the phalanges (Fig. 1.37). The vincula longa are the flexible, vessel-carrying bands to each tendon




Fig. 1.38 The common configuration of the vincula. FDP, flexor digitorum profundus; FDS, flexor digitorum superficialis. (Redrawn after Chase RA. *Atlas of Hand Surgery*, vol. II. Philadelphia: WB Saunders, 1984.)

in the area where the complete mesotenon has disappeared (Fig. 1.38).

Because the cell population of tendons is sparse, metabolic demand is low and cells can survive with minimal nutritional support. The longitudinal blood supply to a tendon comes from its musculotendinous junction and its insertion site into bone. The segmental blood supply derives from the mesotenon where a mesotenon exists and from the vincula within the digital sheaths. It is now clear that synovial fluid within the sheath supplies nutrition to the tendon much as synovial fluid in a joint supports cartilage. This fact has altered thinking about the necessity for adhesion formation to ensure cell survival within a lacerated tendon stripped of blood supply or within tendon grafts.

On the basis of the anatomy of the flexor tendons and the associated synovial and fibrous sheaths, the area traversed by the tendons is divided into clinically important zones (Fig. 1.39).

- Zone 1 is the area traversed by the flexor digitorum profundus distal to the insertion of the flexor digitorum superficialis on the middle phalanx.
- Zone 2 extends from the proximal end of zone 1 to the proximal end of the digital fibrous sheath.
- Zone 3 is the area traversed by the flexor tendons in the palm and is free of fibrous pulleys. It extends, therefore, from the proximal end of the finger pulley system (A1) to the distal end of the wrist retinaculum, the transverse carpal ligament.
- Zone 4 is the carpal tunnel. It extends from the distal to the proximal borders of the transverse carpal ligament.
- Zone 5 extends from the proximal border of the transverse carpal ligament to the musculotendinous junctions of the flexor tendon (Box 1.6).




Fig. 1.37 Flexor digitorum superficialis and profundus; lateral view of the hand. (Upper limb cadaver dissection, Stanford University Division of Plastic Surgery. © 2015 James Chang, Anaïs Legrand. All Rights Reserved.)




Fig. 1.39 Flexor tendon zones are classified for their relevance to flexor tendon injuries. (Redrawn after Chase RA. *Atlas of Hand Surgery*, vol. II. Philadelphia: WB Saunders, 1984.)

A knowledge of the classical anatomy of the synovial sheaths and potential anatomic spaces in the hand is essential for proper diagnosis and treatment of serious hand infections. The flexor tendons are shrouded in synovial sheaths, particularly where there is flexion mobility in the longitudinal arch of each ray and at the wrist. The synovial sheath of the flexor pollicis longus generally extends from the flexor insertion to a point proximal to the wrist flexor retinaculum. The same is true of the synovial sheath around the little-finger flexors, but as the little-finger sheath approaches the proximal palm just distal to the carpal tunnel, it expands to encompass the flexors of the ring, long, and index fingers. At this point it is referred

to as the ulnar bursa. Each index, long, and ring finger has a flexor synovial sheath from the point of insertion of the profundus tendon to the level of the distal palmar crease in the palm. The deep space beneath the flexor tendons is divided into two compartments by the heavy vertical septum from the palmar fascia to the third metacarpal. Ulnar to the septum is the midpalmar space, and radial to it lies the thenar space. The thenar space straddles the adductor pollicis muscle like two legs extending between the adductor and deep flexors on the palmar side, and between the adductor and the first dorsal interosseous on the dorsal side. Infection starting in the digital synovial sheaths may extend proximally to the deep palmar spaces.

Intrinsic muscles (Video 1.2 ►)

Intrinsic muscles arise and insert within the hand (Figs. 1.40 & 1.41). They can be divided into four groups. The thenar muscles are a group of four muscles consisting of the abductor pollicis brevis, flexor pollicis brevis, opponens pollicis brevis, and the adductor pollicis brevis. The abductor pollicis brevis, opponens pollicis brevis, and superficial head of flexor pollicis brevis are median-innervated whereas the adductor pollicis brevis and the deep head of the flexor pollicis brevis are ulnar-innervated.


The hypothenar muscles are all innervated by the ulnar nerve. These four muscles include the palmaris brevis, abductor digiti minimi, flexor digiti minimi brevis, and opponens digiti minimi.

Lumbricals originate from flexor digitorum profundus tendons and insert on the radial aspect of the extensor mechanisms, distal to the metacarpophalangeal joint. They contribute to the flexion of metacarpophalangeal joints and the extension of the interphalangeal joints (Video 1.4 ►). The index and middle-finger lumbricals are innervated by the median nerve, whereas the ring and small-finger lumbricals are innervated by the ulnar nerve. The tiny lumbrical muscles harmonize function between the lateral band interphalangeal extensor mechanism and the flexor digitorum profundus. They have a moving site of origin from the profundus tendon. As the flexor profundus contracts, the lumbrical origin moves proximally. At the same time, the lumbrical insertion moves distally as the extensor is advanced by interphalangeal flexion. The separation of its insertion and origin makes the lumbrical more effective in flexing the metacarpophalangeal joint. Conversely, with a change in balance of power, the lumbrical tends to pull the profundus distally as it shortens the lateral bands. This combination of profundus relaxation and lateral band pull results in extension at the interphalangeal joints. Despite the fact that lumbricals have the smallest cross-sectional area in the upper extremity, they have the greatest number of muscle spindles, which are responsible for gathering proprioceptive input. They play an important role in the sensory feedback of the distal interphalangeal, proximal interphalangeal, and metacarpophalangeal joints of the fingers. Specifically, the lumbrical muscles may be important for forming a precision pinch comprised by the first three digits.⁶⁴

All interossei are ulnar-innervated. There are three volar muscles and four dorsal muscles. The interossei originate from the metacarpals and form the lateral bands with the lumbricals. The interosseous muscles function as ulnar and

BOX 1.6 Clinical pearl: examination of extrinsic flexors

The function of the flexor digitorum profundus can be confined by active flexion of the distal interphalangeal joint. It is the only flexor of this joint. Since a muscle-tendon unit affects every joint between its origin and insertion, the flexor digitorum profundus may also flex the proximal interphalangeal joint. This makes the diagnosis of superficialis nonfunction more difficult. Each superficialis flexor has its own muscle belly, and each acts independently of the others. The profundus flexors are not as independent, since there is a common muscle for the long, ring, and little finger profundus tendons, and a variable degree of interconnection between these and the index finger profundus. The diagnosis of disruption of flexor digitorum superficialis function is confirmed by check-reining the profundus by holding the other fingers in extension while the patient actively attempts to flex the finger whose superficialis is being tested. Flexion of the finger at the proximal interphalangeal joint while the distal interphalangeal joint remains loosely extended confirms the functional integrity of the flexor digitorum superficialis.



F. Netter M.D.
C. Machado M.D.

Fig. 1.40 Superficial and deep intrinsic muscles in the hand. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.41 Superficial and deep intrinsic muscles in the hand. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)

radial deviators of the fingers as well as flexors of the metacarpophalangeal joints and extensors of the interphalangeal joints. The dorsal interossei act as abductors from the axis of the hand, which falls in the middle of the long finger. The long finger moves both radially and ulnarly under the influence of the second and third dorsal interossei. The abductor digiti minimi is the dorsal interosseous equivalent of the little finger. The palmar interossei adduct the fingers to the hand axis.

The pull of all the interossei palmar to the axis of the metacarpophalangeal joints and dorsal to the interphalangeal joint axis acts to flex the metacarpophalangeal joints and extend the interphalangeal joints. The position assumed is called the “intrinsic plus” posture (Fig. 1.42 & Box 1.7).

With the hand axis or fixed unit in position, the metacarpal arch is adjusted primarily by the thenar and the hypothenar muscle groups. The median nerve generally innervates all the thenar muscles on the radial side of the flexor pollicis longus. These two and one-half muscles (the abductor pollicis brevis, opponens pollicis, and superficial head of the flexor pollicis brevis) are positioning muscles that act to bring the first metacarpal into palmar abduction, thus increasing the concavity of the transverse metacarpal arch. This in turn prepares the thumb for proper pulp-to-pulp opposition with the fingers.

The thumb is steadied in position by contraction of the antagonist muscles to the abductors and the thumb adductor.




Fig. 1.42 All interossei act as prime flexors of the metacarpophalangeal joints since they pass palmar to the joint axis. Extensions into the lateral bands result in extension of the interphalangeal joints. (Redrawn after Chase RA. *Atlas of Hand Surgery*, vol. 1. Philadelphia: WB Saunders, 1973.)

BOX 1.7 Clinical pearl: examination of intrinsic muscles

Examination of the hand for finger intrinsic function requires little more than an understanding of the anatomy described above and its related function. Function of the interossei may be assessed by asking the patient to adduct and abduct the fingers from the hand axis in the middle of the long finger. The ability to flex the metacarpophalangeal joints with the interphalangeal joints extended (“intrinsic plus” posture) confirms interosseous function. Paralysis is reflected by clawing of the fingers with hyperextension of the metacarpophalangeal joints and flexion of the interphalangeal joints on attempts actively to extend the fingers (“intrinsic minus”).

Lumbrical function is best reflected by having the patient fully flex the finger (extrinsic flexor function), then move the finger smoothly into extension at the interphalangeal joints while holding active flexion at the metacarpophalangeal joint.

Tightness or contracture of the interossei results in inability actively or passively to flex the interphalangeal joints while the metacarpophalangeal joint is extended. Inability to flex the interphalangeal joints may be a result of fixation of the extrinsic extensor tendons proximal to the metacarpophalangeal joint. Testing to differentiate these two possible etiologies is done by passively extending, then passively flexing, the metacarpophalangeal joint while assessing the degree of passive extension of the interphalangeal joints. If the interphalangeal joints passively extend when the metacarpophalangeal joint is extended, the interosseous muscle and tendon are short. If, by contrast, the interphalangeal joints extend when the metacarpophalangeal joint is passively flexed, the extrinsic extensor is adherent proximal to the metacarpophalangeal joint (Fig. 1.43).

Both the adductors and the abductors support flexion of the metacarpophalangeal joint to prevent recurvatum at this joint on pinching, which may occur with paralysis of either or both (Froment’s sign). With graded relaxation of the abductors, the adductor will dominate and pull the thumb against the side of the hand.

The carpometacarpal joint is a saddle joint with a lax capsule. This allows a wide range of circumduction motion and even a small degree of distraction of the joint on traction. Stability of the thumb root is heavily dependent on the muscles affecting it. The radial-innervated extensor pollicis longus and brevis and abductor pollicis longus secure the metacarpal dorsally. Opposing this to achieve stability are two groups of intrinsic muscles that, together with the extensor and dorsal abductor, triangulate the metacarpal. These two intrinsic groups are the median-innervated palmar abductors (the abductor pollicis brevis, opponens pollicis, and superficial head of the flexor pollicis brevis) and the ulnar-innervated adductors (the adductor pollicis, first dorsal interosseus, and deep head of the flexor pollicis brevis).

When there is paralysis of any of the three major motor nerves, thumb stability is compromised. In median nerve palsy, the positioning muscles of the thenar eminence are lost, resulting in inability to oppose the thumb for pulp-to-pulp opposition with other digits. Ulnar nerve palsy results in adduction weakness and imbalance of the structures influencing the metacarpophalangeal joint. Radial nerve palsy destroys extension and dorsal abduction function, with resultant adduction contracture that becomes fixed after an extended period of unopposed adduction. The ulnar nerve innervates the hypothenar muscle group, which serves further to develop the concavity of the transverse metacarpal arch (Box 1.8).




Fig. 1.43 (A,B) Testing for tightness or shortening of the interosseous muscles as a cause of passive extension contracture of the interphalangeal joint. The metacarpophalangeal joint is passively extended and the interphalangeal joints passively extend. If the cause of extensor tightness at the interphalangeal joint is a result of long extensor adhesions to the metacarpal, the interphalangeal joints will passively extend on passive flexion of the metacarpophalangeal joint. (Redrawn after Chase RA. *Atlas of Hand Surgery, vol. II. Philadelphia: WB Saunders, 1984.*)

Blood supply

The vascular inflow to the upper arm and hand is a continuation of the axillary artery to the brachial artery. The brachial artery is palpable just medial to the biceps tendon at the level of the elbow. The brachial artery branches into the radial and ulnar arteries at the bicipital aponeurosis of the elbow (Fig. 1.44). Supplementary arteries in the forearm include the anterior interosseous artery, the posterior interosseous artery, and the median artery.

The radial artery continues distally in the forearm between the brachioradialis and flexor carpi radialis muscles. At the wrist, the radial artery is located near the styloid process of the radius, and then travels dorsally, crossing the “anatomic snuffbox” deep to the tendons of the abductor pollicis longus, extensor pollicis brevis, and extensor pollicis longus

(Fig. 1.45). In the hand, it penetrates between the first and second metacarpal bones, through an arcade in the first dorsal interosseous muscle, to enter the palm and form the deep palmar arch. A superficial branch of the radial artery arises at the level of the distal radius before the artery enters the “snuffbox” and courses over or through the abductor pollicis brevis to contribute to the superficial palmar arch. This branch contributes blood supply to the skin over the thenar area and the underlying intrinsic muscles of the thumb.

The ulnar artery is the other major branch of the brachial artery. Soon after the takeoff of the ulnar artery, the common interosseous artery originates and itself branches into the anterior and posterior interosseous arteries. The ulnar artery continues in the forearm under the flexor carpi ulnaris muscle. At the wrist, it lies radial to the pisiform and ulnar to the hook of the hamate and travels into the hand through Guyon’s canal, deep to the palmaris brevis and the hypothenar fascia. Here it divides into a deep palmar branch and a superficial palmar branch. The superficial branch becomes the dominant contributor to the superficial palmar arch. The superficial arch crosses the palm at the level of the fully abducted thumb. The deep branch contributes to the deep palmar arch.

In general, the blood supply of the hand is conveniently divided into palmar vessels, which are subdivided into a superficial and a deep layer, and a single dorsal layer (Fig. 1.46).⁶⁵ For example, the superficial vascular arch and its branches constitute the superficial group, the deep arch and the palmar metacarpal branches make up the deep layer, and the dorsal arch with its dorsal metacarpal branches forms the dorsal distribution (Box 1.9).

The superficial palmar arch gives rise to three common digital arteries and multiple branches to intrinsic muscles and skin. The deep vascular arch lies at the proximal ends of the metacarpals deep to all the flexor tendons. It arises chiefly from the radial artery and becomes an arch by anastomosis with the deep branch of the ulnar artery. The deep arch is the major source of blood supply to the thumb and to the radial

BOX 1.8 Clinical pearl: dynamics of hand function

The central backbone of the hand is positioned in extension by the very important extensor carpi radialis brevis and longus. Flexion is affected by the flexor carpi radialis. All three muscles insert on the central two metacarpals (the second and third). These key motors are responsible for positioning the hand axis in preparation for operation of the adaptive hand elements around it. There are numerous other modifying motors to adjust the hand axis in the exact position desired, such as the flexor carpi ulnaris and extensor carpi ulnaris, which produce ulnar deviation. The fixed unit of the hand is extended from the radius at the radiocarpal joint. The entire complex is a beam attached to the ulna by the distal radioulnar joint, the interosseous membrane, and the proximal radioulnar articulation. Rotation around the fixed ulna in supination and pronation is largely under the influence of the median-innervated pronator teres and pronator quadratus and the radial-innervated supinator. The biceps and brachioradialis augment supination.

Anterior view




Fig. 1.44 Upper arm vascular anatomy and surrounding structures. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.45 The anatomic snuffbox. The superficial branch of the radial nerve can be palpated by stroking along the extensor pollicis longus. (*Upper limb cadaver dissection, Stanford University Division of Plastic Surgery. © 2015 James Chang, Anaïs Legrand. All Rights Reserved.*)

side of the index finger. This blood supply comes from the first of the four palmar metacarpal arteries. The first metacarpal artery is the prime source of blood supply to the radial and ulnar proper digital arteries of the thumb and the radial proper digital artery of the index finger. These digital arteries generally receive collateral branches from the superficial palmar arch as well. After giving its branch to the index finger, the first metacarpal artery becomes the primary source of blood supply to the thumb and is frequently called the princeps pollicis (Box 1.10).

The dorsal arteries originate proximally from the posterior interosseous artery and a dorsal perforating branch of the anterior interosseous artery. These arteries are joined by branches from the radial and ulnar arteries to form a dorsal carpal arch. Dorsal metacarpal arteries arise from this arch and extend distally to the margins of the fingers.^{66–70} These

BOX 1.9 Clinical pearl: the Allen's test

This test may be used to assess the competence of the major arterial contributors to blood supply in the hand and the functional efficiency of the vascular arches in the hand. Palpate the radial and ulnar pulses at the wrist and prepare to compress these arteries. Have the patient make a very tight fist. Compress the arteries and ask the patient to extend the digits. The hand will be blanched white. Release pressure on one of the arteries and observe the return of a red flush on the hand. Normally, the flush is immediate and progresses across the whole hand without delay. This confirms the patency of the artery and the competence of circulatory collaterals through the vascular arches. The test may be performed to confirm the competence of each of the two major arteries before surgery or to check their competence after repair, thrombectomy, manipulation, or injury.

The Allen's test principle may be used in clinically assessing the competence of the two proper digital arteries in the fingers. It may be done by observing return of color after compression of both arteries and release of one to the digit. Compress one artery, then the other, and then both to note the individual proper artery contribution to cutaneous blood supply. The technique may be useful when one is planning an island pedicle flap from a donor finger whose digital artery may have been damaged by an injury proximal to the finger.

BOX 1.10 Clinical pearl: the relative size of digital vessels

Although two digital arteries (radial and ulnar) usually perfuse each finger, there are differences in the diameter of the radial versus ulnar digital arteries.⁶⁶ In the thumb, the ulnar digital artery is usually much larger. The index finger is similarly ulnar-dominant whereas the small finger is radial-dominant. The arteries to the middle and ring fingers do not have appreciable size differences between radial and ulnar sides. This anatomic variation may be important in finding adequate vessels for microanastomosis during replantation or revascularization.

dorsal arteries are joined by a varying number of vessels perforating from the deep palmar metacarpal arteries. In fact, the dominant supply to the dorsal metacarpal arteries may come from these perforators. Dorsal arteries to the thumb come from branches of the radial artery before it plunges through the first dorsal interosseous arcade. Thus, the dorsal arterial blood supply of the thumb is similar to that of the fingers (Box 1.11).

Veins generally follow the arterial pattern in the deep system as venae comitantes. An abundant superficial system of venous drainage also exists (Fig. 1.47). Ultimately, these

BOX 1.11 Clinical pearl: dorsal metacarpal artery flaps

The dorsal arterial circulation of the hand is the source of multiple intrinsic hand flaps. The radial artery and the dorsal carpal arch give off the first and second metacarpal arteries which run in the intermetacarpal spaces between the thumb and index finger, and the index finger and middle finger, respectively. The third metacarpal artery is much smaller and is less reliable for flap transfer. Although multiple uses and variations have been described, the simplest method to catalogue these flaps is by artery and by direction of flow. Therefore, both the first and second dorsal metacarpal arteries may be used in an antegrade or retrograde fashion.

The first dorsal metacarpal artery (FDMA) has been found to originate from the dorsal radial artery, just distal to the extensor pollicis longus tendon. In a series of 30 hand dissections, 90% of hands had superficial or fascial FDMAs, 40% of hands had a deep intramuscular branch, and 30% had both vessels present.⁶⁷ The external diameter averaged 1.0–1.5 mm at the largest part. This vessel can be used to harvest a pedicled island flap of skin from the dorsum of the index proximal phalanx innervated by a branch of the radial sensory nerve.⁶⁸ In the antegrade fashion, this flap may reach about the dorsum of the radial two-thirds of the hand, and even to a portion of the volar hand. The reach of the FDMA flap can be extended distally if designed in a retrograde fashion.⁶⁹

The second dorsal metacarpal artery (SDMA) was found in 29 of 30 (97%) hands dissected. The origin of this vessel varied, including from the dorsal carpal arch, radial artery, FDMA, and the posterior interosseous artery. Once the SDMA reached the index finger extensor tendons, the vessel passed deep to the tendons and within the fascia of the second dorsal interosseous muscle. The SDMA branched and became superficial at the level of the metacarpophalangeal joints. The pedicle, being more central than the FDMA, can nearly reach the entire dorsum of the hand and can also be extended in a retrograde fashion, to reach the level of the proximal interphalangeal joints of the index and middle fingers.⁷⁰




Fig. 1.46 Hand vascular anatomy and surrounding structures. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)

Anterior (palmar) view

Posterior (dorsal) view




Fig. 1.47 The superficial and deep venous drainage system of the hand and arm. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)

superficial veins contribute to the cephalic and basilic veins of the upper extremities. Lymphatic drainage terminates in the axillary, supraclavicular, and subclavicular nodes.

Peripheral nerves

The peripheral nerves to the upper extremity have anatomic relationships of great importance to the surgeon. For example, one needs to know the anatomic availability for nerve block and sites where nerves are subject to compression or injury. Sites of particular susceptibility to injury coincide quite accurately with the sites chosen for anesthesia.

With the ability to perform fascicular and group fascicular repair of nerves in addition to epineurial repair, it is important for surgeons to understand the generic internal structure of peripheral nerves. The epineurium is the tubular fibrous support structure surrounding the entire nerve; it also courses between the fascicles. Subdivisions consisting of multiple fascicles within the nerve are covered by epineurium. Each fascicle is covered by perineurium. Within each fascicle are separate axons, some myelinated and some unmyelinated. Motor, sensory, and sympathetic fibers are present within each peripheral nerve. Blood vessels are found on the epineurial surface and in the internal supporting structure of the nerve. The internal topography is plexus-like, as described in detail in the classic monograph by Sunderland.⁷⁰

The radial nerve arises from the posterior cord of the brachial plexus (C6–8). As the nerve passes the distal humerus, muscular branches innervate the brachioradialis and extensor carpi radialis longus muscles (Fig. 1.48). The radial nerve divides into terminal deep and superficial branches at the proximal forearm (Fig. 1.49). The deep posterior interosseous nerve supplies the supinator as well as muscles in all the extensor compartments: extensor carpi radialis brevis, extensor digitorum communis, extensor digiti minimi, extensor carpi ulnaris, extensor indicis proprius, extensor pollicis longus, extensor pollicis brevis, and abductor pollicis longus muscles. Finally, the deep posterior interosseous nerve terminates to supply carpal joint sensation.

The dorsal or superficial branch of the radial nerve courses through the forearm in relationship to the brachioradialis muscle on the radial side of the arm. The superficial branch of the radial nerve crosses the “anatomic snuffbox” between the extensor pollicis brevis and the extensor pollicis longus in the loose subcutaneous tissue. Here it exchanges fibers with terminal branches of the lateral antebrachial cutaneous nerve. The area the superficial branch of the radial nerve supplies is the skin of the dorsum of the hand over the radial two-thirds, the dorsum of the thumb, and the index, long, and half of the ring finger proximal to the distal interphalangeal joint.

The median nerve arises from the lateral and medial cords of brachial plexus (C5–T1) (Fig. 1.50). In the forearm, muscular branches supply the pronator teres, flexor carpi radialis, palmaris longus, and flexor digitorum superficialis muscles. The anterior interosseous branch of the median nerve innervates the flexor pollicis longus, flexor digitorum profundus (index and middle finger), and pronator quadratus muscles, and provides wrist sensation. Proximal to the wrist and running between the flexor carpi radialis and palmaris longus tendons, the palmar cutaneous branch provides lateral

palmar sensation (Fig. 1.51). As the median nerve passes through the carpal tunnel, the recurrent motor branch innervates the thenar muscles (abductor pollicis brevis, opponens pollicis, and flexor pollicis brevis (superficial head)). Sensory branches supply digital nerves to the thumb, index, and middle fingers, as well as the radial aspect of the ring finger (Video 1.5 ).

Lastly, the ulnar nerve enters the upper extremity as a branch of the medial cord of the brachial plexus (C8–T1) (Fig. 1.52). Muscular branches innervate the flexor carpi ulnaris and flexor digitorum profundus muscles to the ring and small fingers. The palmar cutaneous branch of the ulnar nerve provides sensation to hypothenar eminence and medial portion of the palm. The dorsal branch of the ulnar nerve courses around the ulnar aspect of the forearm in its distal one-fourth after branching from the main trunk at a variable site in the distal one-third of the forearm. It passes from its position deep to the flexor carpi ulnaris out through the dorsal fascia to become subcutaneous (Fig. 1.53). This sensory nerve branches to innervate the ulnar portion of the dorsum of the hand, the dorsum of the little finger, and at least part of the dorsum of the ring finger. In contrast, the main sensory branch forms the ulnar digital nerve to the small finger and the common digital nerve which divides into the small-finger radial digital nerve and the ring-finger ulnar digital nerve. The deep motor branch of the ulnar nerve passes through the pisohamate and opponens tunnel in company with the deep branch of the ulnar artery. It courses with the deep vascular arch across the depths of the palm, giving off motor branches to the four hypothenar muscles (abductor digiti minimi, opponens digiti minimi, flexor digiti minimi brevis, and palmaris brevis), all the interossei, the two ulnar lumbricals, and the thumb intrinsic ulnar to the flexor pollicis longus – the adductor pollicis brevis and the flexor pollicis brevis (deep head).

Essentially the flexor pollicis longus divides the hand into a median and ulnar-innervated portion from the motor standpoint. The ulnar nerve is far less important from the standpoint of hand sensation but is very important for its motor innervation of all the hypothenar muscles and interossei. In addition, it innervates the thumb adductor, the deep head of the flexor pollicis brevis, and the two ulnar lumbricals. Classically, all the intrinsic muscles on the radial side of the flexor pollicis longus are median nerve-innervated (the abductor pollicis brevis, opponens, and superficial head of the flexor pollicis brevis). All other intrinsic muscles in the hand receive their innervation from the ulnar nerve. The two tiny radial lumbricals (median nerve innervated) are the only exceptions to this axiom (Boxes 1.12 & 1.13).

Conclusion

In the human hand, the complicated motor balance at each joint resulting from contraction, fixation, or relaxation of opposing muscle groups is worthless in the absence of the precisely fitted elements in the skeletal architecture. The skeletal framework with its restraining ligaments is beautifully designed but is useless without proper dynamic motor tension. The anatomic presence of both architecture and functioning muscles is only serviceable when there is integrity

Text continued on p. 48




Fig. 1.48 The proximal radial nerve wraps posteriorly around the humerus and then proceeds in a dorsal–radial direction distally. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)

Anterior view

Note: Only muscles innervated by median nerve shown




Fig. 1.50 The median nerve classically lends sensibility to the palmar aspect and the distal dorsum of the thumb, index, long, and radial half of the ring fingers. Intrinsic muscles radial to the flexor pollicis longus and the two radial lumbricals receive motor innervation from the median nerve. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.51 The palmar cutaneous branch of the median nerve travels superficial to the flexor retinaculum of the hand while the remaining portion of the median nerve travels deep. (*Upper limb cadaver dissection, Stanford University Division of Clinical Anatomy. © 2015 James Chang, Anaïs Legrand. All Rights Reserved.*)

BOX 1.12 Clinical pearl: median and ulnar nerve lacerations

The ulnar and median nerves are frequently injured just proximal to the wrist. The nerves are quite superficial and it is a region where injuries to all structures are frequent. Median palsy alone results in anesthesia over the important exploring and manipulating digits (the thumb, index, and long fingers, and part of the ring finger) on the palmar surface. The median positioning muscles of the thumb become paralyzed, resulting in an inability to position the thumb for pulp-to-pulp opposition with other digits. In addition, the two radial lumbricals are paralyzed, but this may be barely perceptible

functionally. There is a constant midvolar blood vessel on the median nerve that helps in its identity and in achieving very accurate axial rotation to perfect end-to-end opposition.

The ulnar nerve divides into a deep motor branch and a superficial sensory branch just beyond the pisiform. Occasionally, stab wounds of the hand result in transection of the motor branch with no sensory loss. A guide to proper fascicular orientation in the ulnar nerve is the fact that one can identify that portion destined to be the deep or superficial branches well above the wrist.

BOX 1.13 Clinical pearl: crowded areas with unyielding boundaries

Flexion and extension motions in the hand occur at two levels, the wrist and the finger joints. Flexion at these joints would surely create volar bowstringing at the long flexor tendons unless it were prevented by fixed retinacular conduits at these points. At the wrist the flexor retinaculum is the fixed roof of the carpal tunnel. The fibrous flexor sheath in the digits forms a fitted pulley system with condensed thickening in the areas of greatest fulcrum responsibility. At the wrist and in the digital fibrosynovial sheaths, anatomic structures create full occupancy. Any addition, whether it be more structures, postinjury or inflammatory swelling of the contents, or inflammatory tightening of the sheath, sets the stage for an inflammatory reaction and adhesion formation.

At the wrist, the median nerve passes beneath the flexor retinaculum and the transverse carpal ligament as the most superficial structure in this crowded space. It is subject to compression injury when swelling occurs within the carpal tunnel.

Just proximal to the wrist, the ulnar nerve passes from beneath the flexor carpi ulnaris along the radial side of the easily palpable pisiform. At this point the nerve enters a fibromusculofascial space that is tubular in configuration, crossing the entire length of the carpus. This is Guyon's tunnel, which is quite separate from the carpal tunnel, through which the median nerve and longitudinal structures to the digits pass. Guyon's tunnel starts at a hiatus formed by the distal edge of the volar carpal ligament superficially and the proximal edge of the transverse carpal ligament deeply. The

pisiform forms the ulnar side of the tunnel, and fibers from the volar carpal ligament that plunge down to join the underlying transverse carpal ligament form the radial wall. There is no fibrous roof on the proximal part of the tunnel until the pisohamate arcade fibers are encountered distally. The roof of the tunnel, therefore, consists of a thick layer of fascia continuous with the hypothenar fascia and generally a part of the palmaris brevis muscle. Through this rather soft hiatus, the superficial branch of the ulnar artery and the arterial branches to the palmaris brevis and overlying skin pass, together with the superficial branches of the ulnar nerve. Within Guyon's tunnel the ulnar nerve lies ulnar to the artery, and the division of the ulnar nerve into its deep motor branch and two superficial branches is evident. After the superficial branches of the artery and nerve emerge through the roof of the tunnel, the deep artery and deep branch of the ulnar nerve enter the pisohamate tunnel beneath the pisohamate arcade. Although the tunnel of Guyon is devoid of a thick, fibrous roof, it is nonetheless covered by palmaris brevis fascia, creating an unyielding space, and its contents are therefore subject to compression from a variety of causes. Repeated trauma, as when one uses the heel of the hand to pound objects, may result in swelling of the tissues and resultant hypertrophy and fibrosis or hemorrhage in the tunnel, which may squeeze the nerve or artery, or both. Ganglia, tumors, or displaced bone may cause compression in the ulnar tunnel, just as occurs with the median nerve in the carpal tunnel.

Ulnar Nerve

Anterior view

Note: Only muscles innervated by ulnar nerve shown




Fig. 1.52 The ulnar nerve classically gives sensory innervation to the little finger and the ulnar half of the ring finger. All hypothenar muscles, all interossei, the two ulnar lumbricals, the adductor pollicis, and the ulnar half of the flexor pollicis brevis are usually innervated by the ulnar nerve. (Reprinted with permission from www.netterimages.com © Elsevier Inc. All Rights Reserved.)




Fig. 1.53 The dorsal branch of the ulnar nerve. (Upper limb cadaver dissection, Stanford University Division of Plastic Surgery. © 2015 James Chang, Anaïs Legrand. All Rights Reserved.)

of the central nervous control mechanisms. As a unified inter-related melding of these elements emerges, hand function becomes the marvelous adaptable fact that it is in humans. Its function is modified and further refined by sensory integrity. Sensation is protective and influential on central motor function. Moreover, special sensation as it resides in the hand makes the hand a special sense organ with which human beings explore their environment. From a practical standpoint, surgeons need repeatedly to remind themselves of the anatomic basis for diagnosis and management of surgical problems in the hand.



Access the complete reference list online at

<http://www.expertconsult.com>

1. Bell C. *The Hand – Its Mechanism and Vital Endowments as Evincing Design*. London: William Pickering; 1834. This treatise by Sir Charles Bell is a literary classic that should be read by any student of hand surgery and anatomy.
5. Bunnell S. *Surgery of the Hand*. Philadelphia: J. B. Lippincott; 1944. This is the first edition of the first modern textbook in hand surgery, written by Sterling Bunnell, widely regarded as the father of American hand surgery.
17. Berger RA. The gross and histologic anatomy of the scapholunate interosseous ligament. *J Hand Surg*. 1996;21:170–178. In this journal article, Dr. Berger clearly describes the unique anatomy of the scapholunate interosseous ligament. He discusses clinical implications of the anatomy for injury patterns and repair/reconstruction.
24. Legueu F, Juvara E. Des aponèvrozes de la paume de la main. *Bull Mem Soc Anat Paris*. 1892;67:383. In this original manuscript, Legueu and Juvara perform anatomic dissections to outline the palmar aponeurosis of the hand. The vertical fibers that bear the authors' names are described. These vertical fibers separate the neurovascular and flexor tendon compartments within the palm.
27. Gelberman RH, Menon J. The vascularity of the scaphoid bone. *J Hand Surg*. 1980;5:508–513. The authors perform dye injection studies to determine the vascular anatomy to the scaphoid. The relative decreased blood flow to the proximal pole has implications for poor healing of scaphoid fractures in this region.

References

- Bell C. *The Hand – Its Mechanism and Vital Endowments as Evincing Design*. London: William Pickering; 1834. *This treatise by Sir Charles Bell is a literary classic that should be read by any student of hand surgery and anatomy.*
- Duchenne GB. *Physiologie des Mouvements*. Philadelphia: J. B. Lippincott; 1959 Paris, Baillière, 1867. Translation by Kaplan EB.
- Wood-Jones F. *The Principles of Anatomy as Seen in the Hand*. Philadelphia: Blakiston, Son; 1920.
- Kanavel AB. *Infections of the Hand*. Philadelphia: Lea and Febiger; 1925.
- Bunnell S. *Surgery of the Hand*. Philadelphia: J. B. Lippincott; 1944. *This is the first edition of the first modern textbook in hand surgery, written by Sterling Bunnell, widely regarded as the father of American hand surgery.*
- Kaplan EB. *Functional and Surgical Anatomy of the Hand*. Philadelphia: J. B. Lippincott; 1953.
- Landsmeer JM. Anatomy of the dorsal aponeurosis of the human finger and its functional significance. *Anat Rec*. 1949;104:31–44.
- Landsmeer JM. Anatomical and functional investigations on the articulation of the human fingers. *Acta Anat*. 1955;25:1–69.
- Landsmeer JM. A report on the coordination of the interphalangeal joints of the human finger and its disturbances. *Acta Morphol Neerl Scand*. 1958;2:59–84.
- Landsmeer JM. The coordination of finger joint motions. *J Bone Joint Surg*. 1963;45A:1654–1662.
- Kaplan EB. The participation of the metacarpophalangeal joint of the thumb in the act of opposition. *Bull Hosp Joint Dis*. 1966;27:39–45.
- Eyler DL, Markee JE. The anatomy of the intrinsic musculature of the fingers. *J Bone Joint Surg*. 1954;36A:1–9.
- Stack HG. A study of muscle function in the fingers. *Ann R Coll Surg Engl*. 1963;33:307–322.
- Tubiana R, Valentin P. L'extension des doigts. *Rev Chir Orthop*. 1963;49:543.
- Zancolli EA, Angrigiani C. Posterior interosseous island forearm flap. *J Hand Surg*. 1988;13B:130–135.
- Earley MJ, Milner RH. Dorsal metacarpal flaps. *Br J Plast Surg*. 1987;40:333–341.
- Berger RA. The gross and histologic anatomy of the scapholunate interosseous ligament. *J Hand Surg*. 1996;21:170–178. *In this journal article, Dr. Berger clearly describes the unique anatomy of the scapholunate interosseous ligament. He discusses clinical implications of the anatomy for injury patterns and repair/reconstruction.*
- Viegas SF, Yamaguchi S, Boyd NL, et al. The dorsal ligaments of the wrist: anatomy, mechanical properties, and function. *J Hand Surg*. 1999;24:456–468.
- Kaplan EB. *Functional and Surgical Anatomy of the Hand*. Philadelphia: J. B. Lippincott; 1953.
- Littler JW. Hand, wrist, and forearm incisions. In: Littler JW, Cramer LM, Smith JW, eds. *Symposium on Reconstructive Hand Surgery*. St. Louis: C.V. Mosby; 1974.
- Skoog T. The transverse elements of the palmar aponeurosis in Dupuytren's contracture. *Scand J Plast Reconstr Surg*. 1967;1: 51–63.
- Phillips C, Mass D. Mechanical analysis of the palmar aponeurosis pulley in human cadavers. *J Hand Surg Am*. 1996;21:240–244.
- Sherman PJ, Lane LB. The palmar aponeurosis pulley as a cause of trigger finger. A report of two cases. *J Bone Joint Surg Am*. 1996;78:1753–1754.
- Legueu F, Juvara E. Des aponévroses de la paume de la main. *Bull Mem Soc Anat Paris*. 1892;67:383. *In this original manuscript, Legueu and Juvara perform anatomic dissections to outline the palmar aponeurosis of the hand. The vertical fibers that bear the authors' names are described. These vertical fibers separate the neurovascular and flexor tendon compartments within the palm.*
- Bojsen-Moller F, Schmidt L. The palmar aponeurosis and the central spaces of the hand. *J Anat*. 1974;117:55–68.
- Gilula LA. Carpal injuries: analytic approach and case exercises. *Am J Radiol*. 1979;133:503–517.
- Gelberman RH, Menon J. The vascularity of the scaphoid bone. *J Hand Surg*. 1980;5:508–513. *The authors perform dye injection studies to determine the vascular anatomy to the scaphoid. The relative decreased blood flow to the proximal pole has implications for poor healing of scaphoid fractures in this region.*
- LaPorte DM, Shar Hashemi S, Lee Dellon A. Sensory innervation of the triangular fibrocartilage complex: a cadaveric study. *J Hand Surg Am*. 2014;39:1122–1124.
- Viegas SF. The dorsal ligaments of the wrist. *Hand Clin*. 2001;17: 65–75.
- Berger RA. The gross and histologic anatomy of the scapholunate interosseous ligament. *J Hand Surg*. 1996;21:170–178.
- Berger RA, Imeada T, Berglund L, et al. Constraint and material properties of the subregions of the scapholunate and interosseous ligament. *J Hand Surg*. 1999;24:953–962.
- Brand P, Hollister A. *Clinical Mechanics of the Hand*. St. Louis: Mosby-Year Book; 1999.
- Youm Y, McMurtry RY, Flatt AE, et al. Kinematics of the wrist – I. An experimental study of radial-ulnar deviation and flexion-extension. *J Bone Joint Surg*. 1978;A60:423–431.
- Hollister A, Giurintano DJ, Buford WL, et al. The axes of rotation of the thumb interphalangeal and metacarpophalangeal joints. *Clin Orthop Relat Res*. 1995;320:188–193.
- Wolfe SW, Neu C, Crisco JJ. *In vivo* scaphoid, lunate, and capitate kinematics in flexion and in extension. *J Hand Surg Am*. 2000;25: 860–869.
- Graham KS, Goitz RK, Kaufmann RA. Curvatures of the DIP joints of the hand. *Hand (NY)*. 2014;9:522–528.
- Watson HK, Light TR, Johnson TR. Checkrein resection for flexion contracture of the middle joint. *J Hand Surg*. 1979;4:67–71.
- Eaton RG, Littler JW. A study of the basal joint of the thumb. *J Bone Joint Surg*. 1969;51A:661–668.
- Dahhan P, Fischer L, Alliey Y. The trapeziometacarpal articulation. *Anat Clin*. 1980;2:43–56.
- Cooney WP, An KN, Daube JR, et al. Electromyographic analysis of the thumb: a study of isometric forces in pinch and grasp. *J Hand Surg*. 1985;10A:202–210.
- Kuczynski K. The thumb and the saddle. *Hand*. 1975;7:120–122.
- Kuczynski K. Carpometacarpal joint of the human thumb. *J Anat*. 1974;118:119–126.
- Tubiana R. *The Hand*. Vol. II. Philadelphia: W. B. Saunders; 1985.
- Pagalidis T, Kuczynski K, Lamb DW. Ligamentous stability of the base of the thumb. *Hand*. 1981;13:29–36.
- Bettinger PC, Berger RA. Functional ligamentous anatomy of the trapezium and trapeziometacarpal joint (gross and arthroscopic). *Hand Clin*. 2001;17:151–168.
- Aubriot JH. The metacarpophalangeal joint of the thumb. In: Tubiana R, ed. *The Hand*. Philadelphia: W. B. Saunders; 1981:184.
- Lieber RL. *Skeletal Muscle Structure and Function: Implications for Rehabilitation and Sports Medicine*. Baltimore: Williams and Wilkins; 1992.
- Enoka RM. *Neuromechanics of Human Movement*. Champaign, IL: Human Kinetics; 2001.
- Garcia-Elias M, An KN, Berglund L, et al. Extensor mechanism of the fingers: I. A quantitative geometric study. *J Hand Surg Am*. 1991;16:1130–1140.
- Hurlbut PT, Adams BD. Analysis of finger extensor mechanism strains. *J Hand Surg Am*. 1995;20:832–840.
- Garcia-Elias M, An KN, Berglund L, et al. Extensor mechanism of the fingers: II. Tensile properties of components. *J Hand Surg Am*. 1991;16:1130–1140.
- Valero-Cuevas FJ, Zajac FE, Bugar CG. Large index-fingertip forces are produced by subject-independent patterns of muscle excitation. *J Biomech*. 1998;31:693–703.
- Sancho-Bru JL, Perez-Gonzalez A, Vergara-Monedero M, et al. 3-D dynamic model of human finger for studying free movements. *J Biomech*. 2001;34:1491–1500.

54. Leijnse JN, Bonte JE, Landsmeer JM, et al. Biomechanics of the finger with anatomical restrictions – the significance for the exercising hand of the musician. *J Biomech.* 1992;25:1253–1264.
55. Leijnse JN, Snijders CJ, Bonte JE, et al. The hand of the musician: kinematics of the bidigital finger system with anatomical restrictions. *J Biomech.* 1993;26:1169–1179.
56. Ikebuchi Y, Murakami T, Ohtsuka A. The interosseous and lumbrical muscles in the human hand, with special reference to the insertions of the interosseous muscles. *Acta Med Okayama.* 1988;42:327–334.
57. Zancolli E, Cozzi EP. *Atlas of Surgical Anatomy of the Hand.* New York: Churchill Livingstone; 1992.
58. Chase RA. Surgical anatomy of the hand. *Surg Clin North Am.* 1964;44:1349.
59. Zajac FE. How musculotendon architecture and joint geometry affect the capacity of muscles to move and exert force on objects: a review with application to arm and forearm tendon transfer design. *J Hand Surg Am.* 1992;17:799–804.
60. Agee J, McCarroll HR, Hollister AM. The anatomy of the flexor digitorum superficialis relevant to tendon transfers. *J Hand Surg [Br].* 1991;16B:68–69.
61. Burgar CG, Valero-Cuevas FJ, Hentz VR. Fine-wire electromyographic recording during force generation. Application to index finger kinesiologic studies. *Am J Phys Med Rehabil.* 1997;76:494–501.
62. Stack HG. A study of muscle function in the fingers. *Ann R Coll Surg Engl.* 1963;33:307–322.
63. Tubiana R, ed. *The Hand.* Philadelphia: Saunders; 1981.
64. Wang K, McGlinn EP, Chung KC. A biomechanical and evolutionary perspective on the function of the lumbrical muscle. *J Hand Surg Am.* 2014;39:149–155.
65. McFadden JA, Gordon L. Arterial repair at the digital and palmar level. In: Blair WF, ed. *Techniques in Hand Surgery.* Baltimore: Williams and Wilkins; 1996:398–406.
66. Earley MJ, Milner RH. Dorsal metacarpal flaps. *Br J Plast Surg.* 1987;40:333–341.
67. Small JO, Brennan MD. The first dorsal metacarpal artery neurovascular island flap. *J Hand Surg.* 1987;13B:136–145.
68. Maruyama Y. The reverse dorsal metacarpal flap. *Br J Plast Surg.* 1990;43:24–27.
69. Hao J, Liu X, Ge B, et al. The second dorsal metacarpal flap with vascular pedicle composed of the second dorsal metacarpal artery and the dorsal carpal branch of radial artery. *Plast Reconstr Surg.* 1993;92:501–506.
70. Sunderland S. *Nerves and Nerve Injuries.* 2nd ed. New York: Churchill Livingstone; 1978.

2

Examination of the upper extremity

Ryosuke Kakinoki

Access video content for this chapter online at expertconsult.com 

SYNOPSIS

- Physical examination of the upper extremity starts with a detailed and accurate patient history.
- Physical examination of the upper extremity consists of inspection, palpation, measurement of length, girth, and ranges of motion, assessment of stability, and detailed assessment of the associated nerve and vascular systems.
- Thorough understanding of the anatomy, physiology, and biomechanics of the upper extremity is essential to perform a physical examination correctly and to make a correct diagnosis of pathologic conditions of the upper extremity.
- Examiners must master correct physical examination techniques based on the anatomy, physiology, and biomechanics.
- The entire upper extremity should be examined, even if the patient's complaint focuses only on the hand.
- It is essential to master correct techniques of physical examination to identify the pathologic conditions of patients.
- Examiners should have their own routine protocol of examination of the upper extremity so as not to leave a part unexamined.
- Comparison of the affected upper extremity with the contralateral unaffected one helps examiners identify pathologic conditions.
- Imaging modalities such as X-rays, CT or MRI should be used to confirm the diagnosis drawn from the physical examinations.

Obtaining a patient history

The patient history can be the most important tool in developing an accurate diagnosis. The history should not only detail the patient's current complaint, but should also document other elements of the patient's history which may be of great significance for interpreting the patient's current problem and choosing between treatment options. A patient history should include information on the patient's demographics, current complaint, medical history, allergies, medications, and

socioeconomic status. The time course of the patient history interview should also be documented.

Patient demographics

The patient's name, age, occupation, hand dominance, and hobbies should be documented. Information about previous injuries or diseases should be obtained regardless of whether they seem to be related to the patient's current complaint.

Current complaint

All information on the patient's current problem, including symptoms of pain, numbness, tingling (paresthesia), weakness, dislocation, coldness, clumsiness, or poor coordination and clicking or snapping should be documented. Each symptom should be characterized according to its location, intensity, duration, frequency, radiation and associated symptoms. The patient history should include information on activities or treatments that aggravate or ameliorate the symptoms. It is also important to record the time and place at which the initial injury occurred and the mechanism.

In trauma cases, the following data are especially important:

1. The time of the injury and the interval between the injury and the patient's presentation should be determined. The interval between an injury and revascularization of amputated fingers has a great effect on the outcome of replantation surgery.
2. The environment in which the injury occurred is important. Whether an injury occurred in a dirty or a clean environment may determine whether infection is likely to be present.
3. The mechanism of injury is also important. For example, information on the posture of the fingers and hand at the time of a tendon laceration is helpful for locating a transected tendon stump.
4. Any previous treatment associated with the injury is documented.

In non-trauma cases, the following data are especially significant:

1. The time at which symptoms such as pain, abnormal sensation, swelling or stiffness began and the subsequent progression of the symptoms is critical.
2. The effects of the symptoms on the patient's daily life, hobby or job are unique to that patient.
3. One must also ascertain whether or not the symptoms are limited to one part of the body.
4. Activities or postures that aggravate or ameliorate the symptoms are also discussed.
5. The association between time and the intensity of symptoms must be carefully documented (e.g., whether pain increases just after waking up in the morning or during the night).

Medical history

The patient's health status may influence diagnosis and treatment. Before starting treatment, it is essential to determine whether the patient has diabetes, or cardiac, pulmonary, and/or renal disease and whether the patient has a history of rheumatologic disease. Documentation of the family's medical history may be helpful for making an accurate diagnosis and for choosing an appropriate treatment if the disease is hereditary. Patients and their families should be questioned about previous problems associated with bleeding and anesthesia. It is also important to determine the course of any prior surgery.

Allergies and medications

The patient history should include data on any medications that the patient is taking. Previous allergic reactions to foods or medications should be noted. People who are allergic to shellfish are often allergic to contrast media that contain iodine.

Social history

The social history includes the patient's use of tobacco and alcohol. The amount of tobacco and alcohol used should be documented. Substance abuse and infection with hepatitis virus or HIV should also be noted. The patient's hobbies or sports should be documented because these activities often determine the most appropriate treatment.

Physical examination specific to the hand

Accurate diagnosis of hand problems depends on a systematic, careful physical examination. Physical examination should be performed routinely following a specific protocol. Even if the patient complains of a problem limited to the hand, the physical examination should start at the neck and shoulder region because the hand is suspended by the bones of the forearm, which connect proximally to the elbow joint, which in turn is stabilized by the humerus and the shoulder joint. In addition, numbness of the hand may be associated with cervical problems. These elements (inspection, palpation, measurement of range of motion, musculotendinous

assessment, stability assessment, nerve assessment, and vascular assessment) should be included in the examination procedure for patients with problems of the upper extremities. An understanding of the interrelationships among these elements is helpful for drawing accurate diagnostic conclusions. Repeated physical examinations reveal how symptoms change over time, which is important for assessing the effectiveness of the treatment.

Inspection

When inspecting the upper extremities, it is essential to compare the affected extremity with the contralateral extremity because the latter can be used as a normal reference if the injury is unilateral.

Discoloration

An abnormal skin color or a change in the color of the skin of the upper extremity is indicative of a wide variety of problems. Infections often cause swelling and patches of redness with proximal streaking. Vascular problems caused by arterial inflow insufficiency often present as pale colored and the distal part of the upper limb appears to have shrunk, whereas those caused by venous outflow insufficiency present as a purple or dark red discoloration and a swollen limb. The color of a hematoma can be used to estimate the interval since the trauma occurred. A fresh hematoma has purple or blue patches, which then become green and finally yellow.

Deformity

Fractures, tumors, arthritis, and some infectious conditions can cause deformities of the upper extremity. Fractures of the phalanges of the fingers frequently result in angular rotation or malrotation of the fingers. When the fingers are held up, the point at which the long axes of the fingers converge corresponds with the position of the scaphoid tubercle. However, the long axis of a malrotated finger deviates from the position of the scaphoid.

Muscular atrophy

It is important to determine whether atrophied muscles are innervated by specific peripheral nerves. If the atrophic muscles are innervated by a specific nerve, the atrophy may have been caused by a peripheral nerve disorder. Muscular atrophy may occur under systemic neural or muscular pathological conditions; in most of these cases, the atrophy is symmetrical in the bilateral extremities. Generally, neurogenic diseases involve muscles in the distal part of the extremity and muscular diseases involve the proximal part of the extremity. The girths of the arm (a portion measured should be noted, like the arm girth 20 cm distal to the acromion) and forearm (a portion with the maximum diameter of the forearm) of both upper extremities should be measured routinely because this often reveals a loss of muscle mass, which may not be obvious to the eye.

Trophic changes

Trophic changes are associated with an abnormality of the sympathetic nervous system. Increased hair growth or

abnormal perspiration of the hands is often observed in chronic regional pain syndrome.

Swelling

Swelling can be identified by comparison with the uninvolved extremity. Localized swelling indicates recent trauma or inflammation. Diffuse swelling is often caused by infection. General swelling may originate from a lymphatic or venous obstruction. Swelling of the dorsum of the hand is also common.

Skin creases

Disappearance of skin creases is indicative of loss of motion of the joint under the creases and can be helpful in determining the validity of a complaint of an inability to move the fingers or upper extremities. Clear finger creases over joints that a patient claims he or she is unable to flex or extend indicate that the patient moves the joint. In such cases, the patient may be malingering or may have a psychiatric condition in which he or she cannot recognize motion of the joint.

Palpation

Palpation is a powerful maneuver for identifying masses, abnormal skin temperature, areas of tenderness, crepitation, clicking or snapping and effusion. Masses in the deep layer can be detected by palpation before they emerge as masses under the skin. When performing palpation, special attention should be paid to differences in hardness or mobility relative to that of the surrounding tissue. For example, subtle palpation can identify a palmar bowstring of a flexor tendon in a patient who complains of lack of finger flexion after an injury of the flexor pulleys.

Assessment of musculotendinous function

The integrity of the tendon and the strength of the muscle should be considered when conducting a musculotendinous assessment.

Posture

When musculotendinous units are examined, it should be kept in mind that the muscle strength and ranges of motion of the hand and digits change depending on the posture of the wrist, forearm or digits. For example, the range of motion of the distal interphalangeal (DIP) joint of a finger is less when the proximal interphalangeal (PIP) joint is passively extended than when the PIP joint is flexed.

Motion

Both passive and active ranges of motion should be documented. The range of motion of both the contralateral healthy limb and the affected limb should be measured and compared. The range of motion may be affected by the posture of the adjacent joints. For example, active and passive distal interphalangeal (DIP) joint flexion is limited when the proximal interphalangeal (PIP) joint of the same finger is extended. When the wrist joint is flexed, the active range of finger flexion decreases. The range of motion of a joint should be measured in a posture that permits maximum motion.

The passive range of motion is measured by holding proximal and distal to the joint in question and then moving the joint from one limit of motion to the other in the absence of any muscular contraction by the patient. A limited range of passive motion is associated with joint stiffness and/or soft tissue contracture.

The active range of motion of a joint is that which occurs when the patient contracts his or her muscles. The active range of motion is affected by tendon excursion, the posture of the hand and fingers, nerve function, and muscular strength.

Power

Muscle power is classed according to the Medical Research Council scale, which ranges from zero to five (0–5) (Table 2.1).¹ Grip strength is a good indicator of the global muscle strength of the upper extremity. Grip strength is measured using a dynamometer with the shoulder and elbow joints stabilized. The patient grips the dynamometer with the elbow straightened beside the trunk in the standing position or flexed 90° in the sitting position. Measurement of pinch grip strengths includes the average of three grip strength trials on the affected and unaffected hands using a Jamar pinch gauge in two different postures. These include a lateral pinch grip measured between the thumb pulp and the radial aspect of the second digit, and a thumb–forefinger pinch grip measured between the tips of the thumb and forefinger. For both grips, the shoulder is adducted and neutrally rotated, and the forearm and wrist are in a closely neutral and comfortable position (Fig. 2.1).

Examination of the muscles of the hand

There are many muscles and tendons in the hand. Muscles, the origin and insertion of which are both distal to the wrist joint, are called intrinsic muscles. Muscles extending across the wrist joint are called extrinsic muscles. Other muscles often compensate for a nonfunctioning muscle, in which case the nonfunctioning muscle appears to function. To evaluate muscle function, each muscle should be evaluated in a posture or situation in which the cooperative muscles do not function. For example, the extensor pollicis longus (EPL) can compensate for impaired thumb adduction. Even when the thumb adductors do not function because of ulnar nerve palsy, patients may be able to adduct the thumb using a functional EPL.

Table 2.1 Medical research council scale

Grade	Physical examination findings
0	No contraction
1	Flicker or trace contraction
2	Active movement with gravity eliminated
3	Active movement against gravity
4	Active movement against gravity and resistance
5	Normal power

(Reproduced with permission from: Seddon HJ. *Peripheral Nerve Injuries*. Medical Research Council Special Report Series, 282. London: HMSO; 1954.)





Fig. 2.1 Lateral pinch (A) and thumb–forefinger tip pinch (B) grips.

The presence of abnormal muscles or an abnormal linkage of tendons should sometimes be considered. The flexion function of the PIP joint of a finger is generally accepted to be independent of that of the other fingers because the flexor digitorum superficialis (FDS) tendon of each finger has its own muscle belly. The motion of the FDS tendon of the small finger is often linked to that of the ring and/or the long finger and the PIP joint flexion of the small finger often coordinates with that of the ring and/or long fingers.² The extensor digitorum manus brevis is sometimes present in the middle finger and causes dorsal wrist pain.³

Examination of the extrinsic muscles

Flexor digitorum profundus muscle

The flexor digitorum profundus (FDP) tendons insert on the palmar surface of the distal phalanx of the fingers. Because the FDP muscles share a common origin, holding the DIP joint of a finger in full extension may prevent motion of all FDPs.

Flexor profundus test (Video 2.1 ▶)

Purpose: This test is used to assess the continuity, excursion, and muscle power of each of the FDP tendons.

Maneuver: The patient's hand is placed palm up on a table. The examiner presses down on the proximal and middle phalanges of the target finger to keep the metacarpophalangeal (MP) and PIP joints in extension and asks the patient to flex the DIP joint. The test should be performed on each finger.

Flexor digitorum superficialis muscle

The flexor digitorum superficialis (FDS) tendons insert on the proximal half of the palmar surface of the middle phalanx of the fingers. Because each FDS tendon has its own muscle belly, its function is independent of the FDS of the adjacent fingers.

Flexor sublimis test (Video 2.2 ▶)

Purpose: This test is used to assess the continuity, excursion, and muscle power of each of the flexor digitorum superficialis tendons.

Maneuver: The patient's hand is placed palm up on a table. The examiner presses down on the distal phalanges of all

fingers except that of the finger to be tested to keep the MP, PIP, and DIP joints of the other fingers in full extension. The patient is then asked to flex the finger to be tested. Each finger is tested individually. The FDS moves when the other fingers are kept fully extended.

Flexor pollicis longus muscle

The flexor pollicis longus (FPL) inserts on the palmar surface of the distal phalanx of the thumb and can be tested by asking the patient to flex the interphalangeal (IP) joint of the thumb.

Milking test of the finger and thumb flexor tendons (Video 2.14 ▶)

Purpose: To evaluate the continuity and excursion of the extrinsic flexors of the thumb and fingers. This test and the dynamic tenodesis test (Video 2.13 ▶) are useful for distinguishing nerve palsy from tendon rupture.

Maneuver: The patient is asked to place the dorsum of the forearm and the hand on a table and to relax. The examiner pushes down on the musculotendinous junctions of the flexor tendons around the palmar aspect of the mid-forearm. If the tendons have normal excursion and no adhesions, the fingers and thumb flex as the forearm is pushed down.

Extensor pollicis brevis and abductor pollicis longus muscles

The extensor pollicis brevis (EPB) inserts at the dorsal base of the proximal phalanx of the thumb. It is sometimes connected to the EPL. The abductor pollicis longus (APL) has several tendon slips and inserts at the dorsolateral base of the thumb metacarpal and trapezium. Both tendons pass through the first dorsal compartment at the wrist (the APL tendon lies radial to the EPB in the compartment). When the patient abducts the thumb maximally, the EPB and APL tendons as well as the EPL tendon merge under the skin over the radio-dorsal side of the wrist and create the snuffbox. The EPB and APL tendons are palpable as taut tendons in the radiopalmar border of the snuffbox. The tendinitis of the EPB and APL at the radial wrist level is known as de Quervain's tenosynovitis. There are two provocative tests for diagnosing de Quervain's tenosynovitis.

Finkelstein test

Purpose: To detect de Quervain's tenosynovitis.

Maneuver: The patient places the hand on a table with the thumb up. The examiner pushes down on the proximal phalanx of the thumb. A patient with de Quervain's tendinitis will experience pain or discomfort in the first extensor compartment of the wrist.

Eichhoff test (Video 2.15 ▶)

Purpose: To detect de Quervain's tenosynovitis.

Maneuver: The patient is asked to hold the thumb with the four flexed fingers of the affected hand. The hand is deviated ulnarly by the examiner. A patient with de Quervain's tenosynovitis will experience pain or discomfort in the first extensor compartment of the wrist.

Extensor carpi radialis longus and brevis muscles

The extensor carpi radialis longus (ECRL) and brevis (ECRB) tendons insert at the dorsal bases of the second and third metacarpal bones, respectively. The function of these muscles is to extend the wrist joint. Because the functional axis of the ECRL deviates radially, the ECRL extends the wrist dorsoradially. When the ECRB does not function, extension of the wrist deviates radially because of the intact ECRL tendon. The extensor digitorum communis (EDC) tendon also may function as a wrist extensor. To remove the EDC contribution to wrist extension, the patient is asked to make a fist and then extend the wrist. Making a fist eliminates EDC function.

Extensor pollicis longus muscle (Video 2.3 ▶)

The extensor pollicis longus (EPL) passes through the third dorsal compartment, turns radially at the Lister's tubercle and inserts at the dorsal base of the distal phalanx of the thumb. The EPL extends the IP joint of the thumb. The hand is placed palm down on a table with the thumb adducted. The patient is asked to lift only the thumb off the surface of the table, keeping the thumb adducted. The taut EPL tendon is palpable in the radiodorsal aspect of the wrist.

Clinical tip

The EPL tendon is often connected to the extensor pollicis brevis (EPB) tendon. Although the EPL tendon is not functioning, the thumb IP joint can be extended by means of the force of the EPB tendon. When examining EPL function, one must eliminate EPB function by stabilizing the thumb MCP joint.

Extensor digitorum communis muscles (Video 2.4 ▶)

The extensor digitorum communis (EDC) tendons pass through the fourth extensor compartment and insert at the dorsal base of the middle phalanges of the fingers. They mainly extend the MP joint, while the intrinsic extensors extend the PIP and DIP joints. EDC function is examined by asking the patient to lift the MP joints of four fingers (the index to the small finger) keeping the PIP and DIP joints flexed.

Extrinsic tightness test

The PIP joint is more easily flexed when the MP joint is kept extended than when it is flexed, signifying that tightness of the extrinsic muscles is present.⁴

Extensor indicis proprius muscle

The extensor indicis proprius (EIP) tendon passes through the fourth extensor compartment at the wrist deep to the EDC tendon and merges with the ulnar side of the index finger EDC tendon over the MP joint. The function of the EIP is to extend the MP joint of the index finger, which is isolated from the extension of the MP joints of the other fingers. The EIP is functional if the patient can straighten the index finger completely when the other fingers are flexed in a fist.

Extensor digiti minimi muscle

The extensor digiti minimi (EDM) tendon passes the fifth extensor compartment and merges with the ulnar side of the small finger EDC tendon at the MP joint level. Because the EDM tendon is usually divided into two tails distally, both tails of the tendon must be transected when the tendon is transferred. This tendon is evaluated by asking the patient to straighten the small finger when the other fingers are flexed into a fist.

Extensor carpi ulnaris muscle

The extensor carpi ulnaris (ECU) tendon passes through the sixth extensor compartment and inserts on the dorsal base of the fifth metacarpal bone. The function of this tendon is ulnar deviation of a wrist that is held extended. The wrist cannot be extended dorsally only by the ECU. This tendon is evaluated by asking the patient to make a fist and to lift and deviate the wrist ulnarly. The tendon is palpable radial to the ulnar styloid process.

Examination of the intrinsic muscles

Thenar muscles (Video 2.5 ▶)

The thenar muscles cover the thumb metacarpal and consist of three muscles: the abductor pollicis brevis, the flexor pollicis brevis and the opponens pollicis. The muscles move the thumb into opposition, enabling the thumb to touch the fingertips when the nails are parallel. These muscles are evaluated by asking the patient to place the dorsum of the hand flat on a table and to raise the thumb until it is perpendicular to the palm. The patient is then asked to resist a downward force by the examiner on the thumb.

Adductor pollicis muscle

The adductor pollicis (ADP) muscle arises from the third metacarpal and inserts to the ulnar base of the proximal phalanx of the thumb. Some fibers of the ADP extend dorsally to form an extensor apparatus for the thumb. Together with the first dorsal interosseous muscle, the ADP approximates the thumb to the second metacarpal.

Interosseous and lumbrical muscles (Video 2.6 ▶)

The interosseous and lumbrical muscles flex the MP joints and extend the PIP and DIP joints of the fingers. In addition, four dorsal interosseous muscles abduct the thumb and the radial three fingers and three palmar interosseous muscles adduct the fingers. The second and third dorsal interosseous muscles are evaluated by asking the patient to place the hand flat on a table and then to stretch the long finger upward (i.e., to hyperextend it) and to deviate it radially and ulnarly. Patients with ulnar nerve palsy cannot do this because of loss of power

in the interosseous muscles (the *Pitres–Testut sign*). The first palmar interosseous and the second dorsal interosseous muscles are tested by crossing the index and middle fingers (*crossing fingers sign*). The patient is asked to cross a flexed long finger over the index finger or to cross a flexed index finger over the long finger when the palm and the ring and little fingers are placed flat on a table. (Finger abduction refers to movement away from the long finger; finger adduction refers to movement toward the long finger.)

Intrinsic tightness test (Bunnell)

Purpose: This test assesses the contracture of the interosseous muscles.

Maneuver: The PIP joint is more easily flexed when the MP joint is flexed than when it is extended (0 degree extended position) if tightness of the interosseous muscles is present (Fig. 2.2).⁵ The test can be performed using radial and ulnar deviation of the finger to distinguish between tightness of the radial and ulnar lateral bands.

Lumbrical-plus test

The lumbrical muscle connects the flexor digitorum profundus tendon and the radial lateral band of each extensor tendon. The PIP and DIP joints are apt to be extended when a patient with lumbrical muscle tightness intends to flex a finger.⁶ The finger flexion is thus blocked (paradoxical movement of the finger) (Fig. 2.3). This movement is often seen in




Fig. 2.3 Lumbrical muscle tightness test. Because the lumbrical muscle connects the flexor digitorum profundus tendon and the radial lateral band of the extensor tendon, the PIP and DIP joint are apt to be extended when the patient intends to flex the finger (paradoxical movement). (A) Normal, (B) Abnormal, with lumbrical tightness causing extension of the finger.

the situation of FDP tendon repair using a tendon graft, which is longer than the appropriate length.

Hypothenar muscles

The hypothenar muscles (the abductor digiti minimi, the flexor digiti minimi, the opponens digiti minimi, and the palmaris brevis muscle) abduct the small finger, moving it away from the other fingers.

Assessment of stability

The tightness of the ligaments around a joint, morphology of the surface of a joint, and musculotendinous balance around a joint are useful indices of joint stability. The stability of ligaments is tested by holding the portions distal and proximal to the joint and gently moving the joint passively to stress the ligaments that stabilize the joint. When assessing joint stability, the biomechanical and physiological properties of the ligaments should be taken into consideration and the stress forces applied should be appropriate for the ligament in question. For example, the bilateral collateral ligaments of the finger metacarpal (MP) joints tighten when the joint is in the flexed position (Fig. 2.4), whereas those of the PIP joints tighten when the joints are in an extended position. The lateral instability of the MP joints is assessed at the fully flexed position, and the PIP joints should be checked at the neutral position. It is useful to measure the opening angle of the affected joint under stress using X-rays and to compare the opening angle of the affected joint with that of the corresponding healthy joint of the opposite hand (Fig. 2.5).

Assessment of the stability of wrist joints is complex and difficult. The stability of the wrist joint is determined by the stability of the radiocarpal, ulnocarpal, distal radioulnar, and midcarpal joints. Special tests for assessing the stability of specific ligaments or imaging tools such as X-rays, CT or MRI may be helpful in making a diagnosis.




Fig. 2.2 Intrinsic tightness test. If there is a tightness of the interosseous muscles, the PIP joint can be more easily flexed when the MP joint is held flexed than when the MP joint is extended. (A) The MP joint is extended. (B) The MP joint is flexed.

Clinical tip**Assessment of the lateral instability of the MP and PIP joints of fingers.**

The straight portions of the bilateral collateral ligaments of the finger metacarpal (MP) joints tighten when the joint is in the flexed position, whereas those of the PIP joints tighten when the joints are in an extended position. The lateral instability of the MP joints is assessed with the joint in full flexion, and the PIP joints should be checked with joint in the neutral position.





Fig. 2.4 The collateral ligament of the MP joint. The proper portion of the collateral ligament is relaxed when the joint is extended (top) and is tight when the MP joint is flexed (bottom). The smaller accessory portion has the opposite effect.

**Scaphoid shift test (Watson) (Video 2.12 🎥)**

Purpose: This test was originally developed to detect loosening or disruption of the scapholunate interosseous ligament. This test can also be used to detect a scaphoid fracture or scapholunate advanced collapse (SLAC) arthritis.

Maneuver: When the wrist deviates radially, the scaphoid rotates palmarly, and the palmar prominence of the tubercle of the scaphoid thus becomes evident. However, when the wrist deviates ulnarly, the scaphoid rotates dorsally and the bony prominence is less evident. The examiner holds the dorsum of the patient's hand with his or her fingers and places his or her thumb onto the radial palmar wrist to palpate the bony prominence of the scaphoid tubercle. When the examiner holds the patient's hand and deviates the wrist radially and ulnarly, he or she will feel the motion of the bony prominence under his or her thumb. When the examiner feels the palmar movement of the bony prominence of the scaphoid tubercle when moving the patient's wrist from the ulnar to the radial deviation, he or she pushes dorsally up on the tubercle against the force of the palmar movement. If scapholunate ligament insufficiency is present, the examiner will feel a clunk on the thumb over the distal tubercle.⁷

Finger extension test

Purpose: To detect the pre-dynamic rotary subluxation of the scaphoid (dorsal wrist syndrome).⁸

Maneuver: When being asked to extend the DIP and PIP joints of all fingers fully, keeping the wrist and the MP joints of all fingers in a full-flexed position, patients with overloaded scapholunate ligaments (pre-dynamic rotary subluxation of the scaphoid) experience pain around the scapholunate joint in the dorsal wrist.

Triquetrolunate ballottement test and the lunotriquetral shuck test

Purpose: To evaluate the stability of the lunotriquetral ligament.




Fig. 2.5 Rupture of the radial collateral ligament of the index finger PIP joint. Measure the opening angle of the affected joint under the radial and ulnar stress forces on X-ray films and compare the angle with that of the corresponding normal joint of the opposite hand. (A) Affected finger. (B) Normal opposite finger.



Fig. 2.6 (A,B) Triquetrolunate ballottement test.

Maneuver: The examiner places his or her thumb dorsally over the triquetrum and the index finger palmarly over the pisiform bone to keep the triquetrum–pisiform unit between the thumb and index finger. The examiner then places his or her opposite thumb on the dorsum of the lunate and pushes it palmarly down. If there is triquetrolunate ligament incompetence, the examiner will feel palmar movement of the lunate and the patient will complain of pain in the wrist (Fig. 2.6).⁹ The lunotriquetral shuck test is similar to the triquetrolunate ballottement test. The patient is asked to place the elbow on a table with the forearm in neutral rotation. The examiner's thumb is placed over the dorsal side of the lunate just beyond the radiolunate joint. The examiner's opposite thumb pushes the palmar side of the pisiform dorsally to load the pisotriquetral joint. In lunotriquetral ligament incompetence, the triquetrum–pisiform unit is moved dorsally and the patient will complain of pain in the lunotriquetral joint (Fig. 2.7).¹⁰

Distal radioulnar joint instability test

Purpose: To evaluate the integrity of the deep layer of the dorsal or palmar distal radioulnar ligaments.



Fig. 2.7 Lunotriquetral shuck test.

Maneuver: The deep layers of the dorsal and palmar ligaments of the distal radioulnar joint (DRUJ) comprise the triangular ligament of the triangular fibrocartilage complex (TFCC) and play a primary role to stabilize the DRUJ. The deep dorsal ligament becomes taut when the forearm is supinated and the deep palmar ligament is taut when the forearm is pronated. The deep layers of the palmar and dorsal ligaments thus restrict dorsal and palmar shift of the ulnar head, respectively. The examiner sits opposite the patient at a table. The patient's elbow is flexed 90° and placed on the table. The patient's forearm is fully pronated and the examiner places his or her thumb on the palmar aspect of the ulnar head and pushes dorsally upward. This maneuver should be repeated on the healthy wrist. If abnormal dorsal movement of the distal ulna is felt with the thumb, insufficiency of the deep layer of the palmar distal radioulnar ligament (palmar portion of the triangular ligament of the TFCC) is present. Next, the patient's forearm is fully supinated and the examiner places his or her thumb on the dorsum of the distal ulna and pushes palmarly down. If abnormal palmar movement of the distal ulna compared with that of the opposite wrist is felt with the thumb, insufficiency of the deep layer of the dorsal distal radioulnar ligament (dorsal portion of the triangular ligament of the TFCC) is present (Fig. 2.8).¹¹

Clinical tip

Dorsal instability of the ulna is assessed with the forearm fully pronated and palmar instability of the ulna is assessed with the forearm fully supinated.

Ulnocarpal abutment test

Purpose: To evaluate TFCC injuries and ulnar impaction syndrome.

Maneuver: The examiner places a thumb on the patient's distal ulna and holds the patient's hand with the remaining four fingers. The patient's forearm is stabilized by the examiner's opposite hand. The patient's wrist is fully deviated ulnarly and the forearm is pronated and supinated. A patient with a TFCC injury or ulnar impaction syndrome may complain of





Fig. 2.8 Distal radioulnar joint (DRUJ) instability test. **(A)** Examination for the palmar instability of the DRUJ. The examiner pushes the ulna head from the palmar side when the forearm is pronated to examine the deep palmar distal RU ligament. The deep palmar ligament is taut in the forearm pronated. **(B)** Examination for the dorsal instability of the DRUJ. The examiner pushes the ulna head from the dorsal side when the forearm is supinated to examine the deep dorsal distal RU ligament. The deep dorsal ligament is taut in the forearm supinated.

ulnar wrist pain and a click or pop may be felt when the examiner's thumb is placed on the ulnocarpal joint (Fig. 2.9).¹²

The ulnar fovea sign

Purpose: To evaluate the foveal disruption of the distal radio-ulnar ligaments and ulnotriquetral ligament injuries.

Maneuver: The ulnar fovea is a dynamic nucleus of the ulnar wrist. The ulnar collateral ligament complex composed of the deep layer of the radioulnar ligament, the ulnotriquetral ligament, the ulnolunate ligament, and the ulnocapitate ligament attaches to the ulnar fovea. The patient sits opposite the examiner with the patient's elbow on the table. The examiner supports the patient's hand to keep the elbow in 90° to 110° of flexion, forearm in neutral rotation, and wrist in neutral position with the patient's upper limb relaxed. The examiner's thumb tip is then pressed distally and deep into the interval "soft spot" between the ulnar styloid process, flexor carpi ulnaris tendon, volar surface of the ulnar head, and the pisiform. The ulnar fovea sign is positive when there is exquisite tenderness compared with the contralateral side. The positive ulnar fovea sign supports the foveal disruption of the distal

radioulnar ligaments and ulnotriquetral ligament injuries (Fig. 2.10).¹³

Pisiform gliding test

Purpose: To evaluate arthritis in the pisotriquetral joint.

Maneuver: The examiner palpates the pisiform and pushes it down against the triquetrum and applies shear force between the two bones. If there is arthritis in the pisotriquetral joint, the patient will feel pain in the joint during this maneuver (Fig. 2.11).

Midcarpal instability test

Purpose: To evaluate midcarpal stability.

Maneuver: The examiner places a thumb on the dorsal midcarpal joint and holds the patient's affected hand with the remaining four fingers. The patient's forearm is stabilized by the examiner's opposite hand. A patient with midcarpal instability will complain of pain in the midcarpal joint when the wrist is deviated ulnarly or radially. Patients with dorsal intercalary segmental instability (DISI) often complain of pain




Fig. 2.9 Ulnocarpal abutment test. The wrist is subjected to ulnar deviation and axial forces with the forearm fully supinated or pronated.




Fig. 2.10 The ulnar fovea sign. The tenderness over the ulnar fovea (positive ulnar fovea sign) strongly supports the foveal disruption of the TFCC. DPL, deep palmar ligament; UCLC, Ulnocarpal ligamentous complex; UT, ulnotriquetral ligament.




Fig. 2.11 Pisiform gliding test.

in the ulnodorsal portion of the midcarpal joint, and a click or pop may be felt when the wrist is deviated ulnarly.

Extensor carpi ulnaris synergy test

Extensor carpi ulnaris (ECU) tendinitis is a cause of ulnar-sided wrist pain. The ECU synergy test is a provocative test, indicating ECU tendinitis, which is often hard to distinguish from TFCC injuries.

Purpose: To detect ECU tendinitis.

Maneuver: The patient's forearm is held fully supinated. The examiner asks the patient to abduct all fingers and applies a counterforce to the index and small fingers sufficient to prevent abduction of the index and small fingers. A patient with ECU tendinitis will experience pain in the sixth extensor compartment (Fig. 2.12).¹⁴

Assessment of peripheral nerves

Evaluation of peripheral nerves should include both motor and sensory function.

To evaluate the motor function of the hand, it is necessary to understand not only the anatomy and biomechanics of the muscles of the upper extremity but also the peripheral innervation of the muscles. An understanding of the order in which branches of the nerves innervate muscles is important for assessing nerve recovery after a nerve injury or a compression neuropathy.

Sensibility testing also relies on knowledge of peripheral nerve anatomy. It is essential to understand which parts of the hand are innervated by which peripheral nerves. Peripheral nerve palsy should be diagnosed using motor and sensory evaluation. When the outcome of a motor assessment does not coincide with that of a sensory assessment, abnormal innervation of muscles or an unusual connection between peripheral

nerves should be considered. The Martin–Gruber connection is an abnormal innervation of the median nerve to the motor branch of the ulnar nerve. Patients with cubital tunnel syndrome and this nerve connection may have a sensory palsy of the ulnar nerve without motor palsy.

Comprehensive sensibility evaluation includes static and dynamic two-point discrimination (2PD) testing, Semmes–Weinstein monofilament testing, vibrotactile threshold testing, and cold-heat testing. The 2PD test evaluates the tactile sensation of the skin and assesses density of the perception receptors in the skin. Stimuli generated by the static 2PD test are mainly sensed by Merkel cells (slow-adapting mechanoreceptors), while the main receptors of stimuli generated by the moving 2PD test are Meissner corpuscles (quick-adapting receptors). In the static 2PD test, a caliper is applied longitudinally to the digit and the smallest distance between the tips of the caliper that the patient can distinguish is measured. The moving 2PD test is the smallest perceived distance between the tips of a caliper that is moved longitudinally along the ulnar or radial aspect of the finger.¹⁵ The normal distance is 3 mm for the moving 2PD test and 6 mm for the static 2PD test of the fingertips. The Semmes–Weinstein test evaluates the pressure perception of the skin of the fingers and assesses the threshold of the perception receptors in the skin. This test is conducted by touching the fingers with filaments of various diameters.¹⁵ The vibrotactile test also assesses the threshold of the perception receptors and is performed using two types of tuning forks with 30 cycles per second (cps) and 250 cps. The vibrating forks are touched on the area examined and whether patients can recognize the vibration is examined. Main receptors of stimuli generated by the tuning forks with 250 cps are Pacinian corpuscles, while those by the forks with 30 cps are Meissner corpuscles. In the cold–heat test, the perception of heat is evaluated by touching the skin with a test tube containing water at 40–45°C and the perception of cold is tested using a test tube containing water at 10°C. Stimuli of the cold–heat test are mainly sensed by free nerve endings of the skin (Table 2.2).



Fig. 2.12 Extensor carpi ulnaris synergy test. The patient is asked to abduct the fingers with the forearm fully supinated. The examiner applies counterforce to the index and little fingers.

Table 2.2 Specific sensory testing and main receptors

Test	Perception	Main receptor	Type of adaptation	Evaluation of innervation
Static 2PD	Tactile	Merkel cell	Slowly	Density
Moving 2PD	Tactile	Meissner corpuscle	Quickly	Density
Tune fork (250cps)	Vibration	Pacinian corpuscle	Quickly	Threshold
Tune fork (30 cps)	Vibration	Meissner corpuscle	Quickly	Threshold
S–W test	Pressure	Merkel cell	Slowly	Threshold

cps, Cycles per second.
(Reproduced with permission from Bell-Krotoski J, Tomancik E. The repeatability of testing with Semmes-Weinstein monofilaments. *J Hand Surg.* 1987;12A:155–161.)

Clinical tip

Ulnar nerve palsy occurring distal to the FDP muscle branches demonstrates more severe claw deformity than that occurring proximal to the branches. This is because the FDP tendons continue to flex the ring and little fingers, which accentuates the hyperextension of the MP joints and flexion of the PIP and DIP joints.

Signs and tests for peripheral nerves**Tinel's sign**

Purpose: To detect nerve regeneration.

Maneuver: When the examiner taps on a peripheral nerve distal to a nerve injury such as a compression neuropathy or a laceration, the patient will experience tingling that radiates distally along the course of the nerve. This phenomenon is called a *Tinel's sign*. The most distal point of the pain indicates the site at which axon sprouting has occurred. Peripheral nerve recovery after a nerve injury can be assessed by observing the advancement of *Tinel's sign* along the nerve (approximately 1 mm/day of advancement).

Phalen's test

Purpose: This test is used as a provocative test specific to carpal tunnel syndrome.

Maneuver: With the elbow in neutral position, the patient's wrist is held in maximum palmar flexion for up to 2 min. This increases pressure on the carpal tunnel and provokes paresthesia in the area innervated by the median nerve in patients with carpal tunnel syndrome (Fig. 2.13). Maximum extension of the wrist also increases pressure on the carpal tunnel. This is called the reverse Phalen's test.

Froment's test

Purpose: To assess motor function of the ulnar nerve.

Maneuver: The patient is asked to hold a piece of paper between the ulnar tip of the thumb and the radial tip of the index fingers. The examiner slowly pulls the paper away from the patient while encouraging the patient to hold on to it. Patients with normal strength of the first dorsal interosseous and adductor pollicis muscles keep the IP joint of the thumb extended. If the patient has weakness of thumb adduction caused by ulnar nerve palsy, the patient attempts to hold the paper by flexing the thumb IP joint using the flexor pollicis

longus and (hyper)extends the thumb MP joint to stabilize it (*Jeanne's sign*). Such patients also flex the PIP joint and hyperextend the DIP joint of the index finger to compensate for weakness of MP joint flexion of the index finger (Fig. 2.14).

Jeanne's sign

Purpose: To assess motor function of the ulnar nerve.

Maneuver: When patients with ulnar nerve dysfunction attempt a lateral or key pinch of the thumb, they hyperextend the thumb MP joint, which locks it to compensate for the lateral instability of the joint secondary to weakness of the thumb adductors.



Fig. 2.13 Phalen's test.



Fig. 2.14 Froment's sign. A patient with left ulnar nerve palsy attempts to hold the paper by flexing the thumb IP joint using the flexor pollicis longus and hyperextending the thumb MP joint to stabilize it. He also demonstrates flexion of the PIP joint and hyperextension of the DIP joint of the index finger to compensate for weakness of MP joint flexion of the finger (*Jeanne's sign*).



Fig. 2.15 Wartenberg's sign. A patient with left ulnar nerve palsy demonstrates inability to perform adduction of the left little finger when he attempts to adduct all fingers.

Wartenberg's sign

Purpose: To assess the motor function of the ulnar nerve.

Maneuver: The patient is asked to keep the fingers adducted with the MP, PIP, and DIP joints fully extended. If the patient has motor dysfunction of the ulnar nerve, the small finger deviates away from the ring finger because the third palmar interosseous muscle does not function and the extensor digiti minimi muscle abducts the small finger (Fig. 2.15).

Other signs associated with ulnar nerve palsy

Duchenne's sign: If the FDP muscles are functioning and the intrinsic muscles are paralyzed (low-level ulnar nerve palsy), the ring and little fingers show hyperextension of the MP joint and flexion of the PIP and DIP joints (claw finger deformity).

André-Thomas sign: A conscious effort to extend the fingers by tenodesing the extensor tendons with palmar flexion of the wrist only increases the claw deformity.

Bouvier maneuver: When hyperextension of the MP joint of the ring and little fingers is corrected, the flexion of the PIP and DIP joints of the fingers is reduced.

The Pitres–Testut sign: This maneuver reveals the function of the second and third interosseous muscles. The patient is asked to place the hand flat on a table and then to stretch the long finger upward (i.e., to hyperextend it) and to deviate it radially and ulnarly.

The “crossed fingers” sign (Video 2.6 ▶): The function of the first palmar interosseous and the second dorsal interosseous muscles is evaluated by this sign. The patient is asked to cross a flexed long finger over the index finger or to cross a flexed index finger over the long finger when the palm and the ring and little fingers are placed flat on a table.

Tests for evaluating sensory nerve function

Two-point discrimination (2PD) test (Video 2.7 ▶)

Purpose: To evaluate the tactile sensation of the skin and assess density of the perception receptors of the skin.

Maneuver: In the static 2PD test, a caliper is applied longitudinally to the digit and the smallest distance between the tips of the caliper that the patient is able to distinguish is measured. In the dynamic 2PD test, the distance between the tips of a caliper that is moved longitudinally along the ulnar or radial aspect of the finger is measured.¹⁴ The normal distance is 3 mm for the moving 2PD test and 6 mm for the static 2PD test. Although it is known that the main receptors for the static 2PD test are Merkel cells (slow-adapting mechanoreceptors) and those for the moving 2PD test are Meissner corpuscles (quick-adapting mechanoreceptors), the results of the 2PD test reflect the functions of multiple sensory receptors in the skin. This test is best for evaluation of nerve lacerations.

Semmes–Weinstein monofilament test (Video 2.9 ▶)

Purpose: To evaluate the pressure perception threshold of the skin. Stimuli generated by this test are mainly sensed by Merkel cells (slow-adapting mechanoreceptors).

Maneuver: Filaments of various diameters are used. The patient places a finger on a table with the palm up and closes his or her eyes. The tip of a filament is held vertically against the skin of the finger and sufficient force is applied to bend the filament before allowing it to return to the vertical position. The filament should remain in contact with the skin surface after the force is released. If the patient senses the pressure applied by the filament, other filaments of decreasing diameter are used until the patient no longer senses the pressure. The size of the smallest-diameter filament that can be sensed by the patient is recorded (Table 2.3).¹⁶

Table 2.3 Semmes–Weinstein test

Evaluator size	Pressure force (g)	Color	Interpretation
1.65–2.83	0.008–0.07	Green	Normal
3.32–3.61	0.16–0.4	Blue	Normal
3.84–4.31	0.6–2	Purple	Diminished light touch sensation
4.56–4.93	4–8	Red	Diminished protective sensation
5.07–6.45	10–180	Red	Loss of protective sensation
6.65	300	Red	Deep pressure sensation only

(Reproduced with permission from: Bell-Krotoski J, Tomancik E. The repeatability of testing with Semmes–Weinstein monofilaments. *J Hand Surg.* 1987; 12A:155–161.)

Clinical tip

Touching the tip of the filament on the skin should be so gentle that patients cannot recognize the touch of the filament tip on the skin. Patients have to recognize the bending pressure produced by the filaments. Some patients misunderstand that the test is whether they recognize the initial touch sensation of the filaments or not.

Moberg's pick-up test

Purpose: To generally evaluate the motor and sensory function of the hand. This test is applied to patients with median nerve injuries or injuries of both the ulnar and median nerves.

Maneuver: Small items such as a button, a key, and a paperclip are placed on a cloth mat. The patient is asked to pick up each item and put it into a small box as quickly as possible with their eyes open and again with their eyes closed. The times required to finish these tasks are measured (Fig. 2.16).¹⁷

Assessment of the vascular system

There are two types of vascular problems: arterial and venous insufficiency. Vascular problems are assessed according to the color, capillary refill, pressure (turgor) and temperature of the affected part.

Arterial interruption causes a pale white or grayish discoloration of the affected area. Venous blockage results in blood congestion, which causes a purple-blue discoloration.

Capillary refill is indicative of the circulation status of the digits. When the fingertip or nail bed is depressed, the area under pressure turns white. When the pressure is released, the area should turn pink within 2 seconds. A delay in refill is indicative of an arterial inflow problem. Prompt refilling may indicate venous congestion. A decrease in skin pressure or temperature may also indicate vascular problems.




Fig. 2.16 Moberg pick-up test. A patient with eyes open or closed picks up small items on a cloth mat and puts them into the box. The time required to finish the task is recorded.

The Allen's test (Videos 2.7–2.10 ►) is helpful for determining if there is an intact circulatory connection between the radial and ulnar arteries in the hand. If there is an intact circulatory path between the two arteries, the hand may be nourished by either of the arteries.¹⁷ This test is essential for assessing the vascularity of the hand before harvesting radial or ulnar forearm flaps. If both arteries are not patent, pedicled forearm flap elevation may compromise the vascularity of the hand.

To assess the circulatory connection between the radial and ulnar palmar digital arteries, the same maneuver is performed at the base of the fingers and thumb (digital Allen's test [Video 2.11 ►]). If there is no circulatory connection between the palmar digital arteries, pedicled island flap harvest should be avoided.

Allen's test (Video 2.10 ►)

Purpose: To assess the blood supply of the radial and ulnar arteries to the hand.

Maneuver: The patient places the dorsum of the hand on a table. The examiner compresses the patient's radial and ulnar arteries at the wrist to occlude both arteries. The patient is then asked to make and release a tight fist repeatedly to exsanguinate the hand, after which the fingers are held in a relaxed position. The examiner releases the pressure on the radial artery while keeping pressure on the ulnar artery. The time taken for blood to return to the hand and fingers is noted. A normal interval for this process is 2–5 seconds. The procedure is repeated for the ulnar artery.¹⁸

Digital Allen's test (Video 2.11 ►)

Purpose: To assess the blood supply of the radial and ulnar palmar digital arteries to the finger.

Maneuver: The patient is asked to place the dorsum of the finger to be tested flat on a table. The examiner compresses the ulnar and radial side of the patient's fingertip with his or her two fingers and moves them proximally to exsanguinate the finger to be tested. The examiner then releases the pressure on the radial palmar digital artery while maintaining pressure on the ulnar digital artery.

The time taken for blood to return to the finger is noted. A normal interval for this process is ≤ 3 seconds. The procedure is repeated for the palmar ulnar digital artery of the finger. A delay in the return of blood to the finger indicates that the blood flow of the radial or ulnar palmar digital arteries is impaired.

Physical examination specific to the forearm

The main functions of the forearm are to transmit force between the elbow and hand and to enable pronation and supination. According to a cadaveric study, 80% of an axial load applied to the wrist is transmitted to the radius and 20% is transmitted to the ulna. The axial force is distributed to the radiocapitellar and ulnohumeral joints in a 60:40 ratio, respectively. Some 20% of an axial force applied to the radius is therefore transferred to the ulna through the interosseous membrane (IOM).¹⁹ After resection of the radial head, 90% of an axial load applied to the forearm is transferred through the IOM.²⁰




Fig. 2.17 Interosseous membrane of the forearm. CB, Central band; (DL)AB, distal ligament of accessory band; DOB, dorsal oblique band; (PL)AB, proximal ligament of accessory band.

The interosseous membrane of the forearm (IOM)

The IOM is divided into three portions. Each portion contains several fibers that connect the radius and the ulna (Fig. 2.17).²¹

Distal membranous portion

Dorsal oblique band (DOB): This band functions as a stabilizer of the DRUJ, in particular by restricting a palmar shift of the ulna in the supination position.²²

Middle ligamentous portion

- Central band (CB): This is the strongest fiber of the IOM and extends from the proximal radius to the distal ulna. When the radial head removed, the CB carries 71% of the overall mechanical stiffness of the forearm.²⁰
- Distal ligament of accessory band (DLAB)
- Proximal ligament of accessory band (PLAB)

Proximal membranous portion

- Distal oblique accessory cord (DOAC)
- Proximal oblique cord (POC): a stabilizer of the proximal radioulnar joint

Among these fibers, the DOB and CB are isometric components and their lengths do not change during forearm rotation.²³ By contrast, the POC is shorter when the forearm is in a neutral or supination position than when it is in a pronation

position. The length of the DOAC shortens as the forearm is rotated from pronation to supination.

Measurement of forearm rotation

The patient should be seated on a chair with the elbow joints tucked in lateral to the abdomen. The patient is asked to grasp a pen in each hand and to rotate the forearm. The angle between the pen and a line perpendicular to the floor should be measured.

Measurement of the muscle strength of the forearm

Supination

The main supinators of the forearm are the supinator muscle and the biceps brachii muscle. The extensor carpi radialis longus (ECRL) and brachioradialis (BR) muscles act as the forearm supinators when the forearm is pronated.

Pronation

The main pronators are the pronator teres and pronator quadratus (PQ) muscles. The flexor carpi radialis and palmaris longus muscles also act as forearm pronators. The BR muscle is a forearm pronator when the forearm is in the supinated position. A recent study revealed that the PQ is responsible for 20% of forearm pronation, except when in the fully pronated position.²⁴ The muscle power of the PQ should be measured when the elbow joint is fully flexed to eliminate the effects of the other pronators.

Pronation or supination strength is evaluated with the elbow joint at 90° of flexion. Pronation strength is measured by grasping the wrist with the forearm in a neutral or supination position. To test supination strength, the forearm should be in a neutral or pronation position.

Physical examinations specific to the elbow

Bony landmarks of the elbow

The medial epicondyle, lateral epicondyle and the tip of the olecranon are located along a straight line (Hüter's line) when the elbow is extended and form an equilateral triangle (Hüter's triangle) when the elbow is flexed (Fig. 2.18). This feature is helpful for identifying a deformity of the distal humerus and elbow joint caused by fracture, malunion, dislocation or growth disturbances.

On the lateral aspect, the capitellum of the humerus and the radial head are easily palpable. The extensor muscles originate from the lateral epicondyle. The radial nerve is palpable in the interface between the BR muscle and the brachialis muscle.

On the anterior aspect, the cubital fossa is bordered by the BR muscle laterally and the pronator teres muscle medially. The musculocutaneous nerve is located deep to the brachioradialis muscle and medial to the biceps brachii tendon. The pulsation of the brachial artery is palpable, as it lies medial to the biceps brachii tendon and deep to the lacertus fibrosus.




Fig. 2.18 Bony landmarks of the elbow. The medial (M) epicondyle, (L) lateral epicondyle and the tip of the (O) olecranon locate on a straight line when the elbow is extended and form an equilateral triangle when the elbow is flexed.

The median nerve is located just medial to the brachial artery under the lacertus fibrosus, which can cause median nerve palsy (pronator teres syndrome).

In the medial aspect, the ulnar nerve groove is palpable between the medial epicondyle and the ulna. The ulnar nerve is sometimes palpated as a strand in the posterior aspect of the groove. In some patients with ulnar nerve palsy, a dislocated ulnar nerve is palpable over the epicondyle when the elbow is flexed.

On the posterior aspect, the olecranon and olecranon fossa of the humerus are easily palpated. The triceps brachii tendon is attached to the olecranon.

Ligaments of the elbow

Lateral ligament complex

The lateral ligament complex consists of the following four ligaments (Fig. 2.19).




Fig. 2.19 Lateral complex of the elbow.




Fig. 2.20 Medial complex of the elbow.

Lateral ulnar collateral ligament

The lateral ulnar collateral ligament originates from the lateral epicondyle, blends with the fibers of the annular ligament and terminates at the tubercle of the crest of the supinator. It functions as a primary stabilizer of the joint when a varus stress is applied.

Radial collateral ligament

This structure originates from the lateral epicondyle and terminates in the annular ligament. The ligament is located near the axis of the elbow joint and is uniformly taut during elbow motion.

Annular ligament

This ligament originates from the anterior margin of the sigmoid notch and inserts on the posterior notch of the sigmoid of the ulna to connect the radial head to the ulna.

Accessory collateral ligament

The ligament blends with the inferior margin of the annular ligament to support the annular ligament during varus stress.

Medial collateral ligament complex

The medial collateral ligament complex consists of three portions: the anterior bundle, the posterior bundle, and the transverse ligament. The transverse ligament is not considered functional. The posterior bundle is clinically insignificant with regard to the stability of the elbow joint. Contracture of the posterior bundle generates extension contracture of the elbow joint. The anterior bundle functions as the prime stabilizer of the elbow joint against valgus stress (Fig. 2.20).

Instability of the elbow joint

The elbow joint is stabilized by the medial collateral ligament (MCL) complex, the lateral collateral ligament (LCL) complex, the joint capsule, and the osteochondral articulation.

The MCL, joint capsule and osteochondral articulation contribute equally to restrain valgus displacement of the elbow joint when the joint is extended. The MCL contributes

more than the osteochondral articulation to restrain valgus displacement when the joint is flexed. The osteochondral articulation contributes more than the LCL to restrain varus displacement, especially in the flexed position.

When examining instability of the elbow joint, the elbow should be placed in a position in which other factors that affect its stability (articulation and tension of the joint capsule) are minimized. To assess collateral ligament integrity, the elbow should be flexed by about 15°. This position relaxes the anterior capsule and unlocks the olecranon from the fossa.

Varus instability of the elbow is therefore assessed with the humerus in full internal rotation and varus stress is applied to the slightly flexed joint. By contrast, valgus instability of the elbow is evaluated with the humerus in full external rotation while valgus stress is applied to the joint in slight flexion (Fig. 2.21).²⁵

Clinical tip

Collateral ligament integrity of the elbow should be assessed with the elbow in about 15° flexion, which relaxes the anterior capsule and unlocks the olecranon from the fossa. Varus instability of the elbow is assessed with the humerus in full internal rotation and varus stress is applied to the slightly flexed joint. Valgus instability of the elbow is evaluated with the humerus in full external rotation while valgus stress is applied to the joint in slight flexion.

Posterolateral rotatory instability

Insufficiency (loosening, rupture or laceration) of the lateral ulnar collateral ligament causes posterolateral instability of the elbow joint. Posterolateral rotatory instability (PLRI) is evaluated using the pivot shift test maneuver.²⁵

The pivot shift test

The patient is placed in a supine position with the shoulder and elbow flexed at 90°. The examiner stands cephalad to the patient. The examiner grasps the patient's forearm in a fully supinated position and extends the elbow slowly, applying valgus and axial compressions to the joint. If the patient has lateral collateral ligament insufficiency, these maneuvers cause rotatory subluxation in the ulnohumeral joint. The examiner continues to extend the elbow slowly. As the elbow joint approaches extension, the radial head is suddenly dislocated anteriorly. The prominence of the radial head disappears and a skin dimple appears. The dislocated radial head is repositioned by flexion of the elbow (Fig. 2.22).²⁶

Measurement of malrotation of the distal humerus

Patients in whom fractures of the distal humerus have not been treated correctly often demonstrate malrotation of the distal humerus, which restricts the functional arc of the shoulder joint. Malrotation of the distal humerus is easily assessed. The patient is asked to stand and flex the trunk more than 90° forward. The patient is then asked to extend both shoulder joints maximally with the elbow joints in 90° of flexion. The angles formed between the floor and the forearms




Fig. 2.21 Assessment of the lateral instability of the elbow. (A) Varus instability of the elbow is examined with the humerus in full internal rotation. (B) Valgus instability is assessed with the humerus in full external rotation.




Fig. 2.22 Pivotal shift test of the elbow. (A,B) Subluxation.

are measured. The malrotation angle of the affected distal humerus can be measured by comparing it with that of the contralateral normal side (Fig. 2.23).

Physical examination of thoracic outlet syndrome

Thoracic outlet syndrome (TOS) is a broad term that refers to compression of the neurovascular structures in the area just above the first rib and behind the clavicle resulting in upper extremity symptoms. It represents a constellation of symptoms.

Classification

TOS is usually classified into two groups: neurogenic and vascular. The neurogenic group is caused by compression or irritation of the brachial plexus trunks and comprises



Fig. 2.23 Assessment of malrotation of the humerus. The patient is asked to stand and flex the trunk more than 90° forward with the bilateral shoulder joints extended maximally and the elbow joints in 90° of flexion. The angles formed between the floor and the forearms are measured.

90% of the TOS. The neurogenic type can be divided into three types, depending on involvement of cervical nerve roots: the upper type (C5, C6, C7 spinal nerve involvement), lower type (C8, T1 spinal nerve involvement), and the combined type. The lower and combined types comprise 85–90% of all patients with TOS. Some 40–50% of TOS is associated with distal compression neuropathies, such as carpal tunnel, pronator teres, cubital tunnel, and radial tunnel syndromes.²⁴

The vascular group is subtyped into the venous type and arterial type. The venous type comprises 70–80% of the vascular group of TOS. The symptoms include pain, swelling, distended vein, and discoloration of the affected upper limb. Compression of the subclavian vein does not occur in the interscalene space because it passes anterior to the anterior scalene muscle, but usually occurs at the area between the anterior scalene insertion to the first rib and at the costocoracoid ligament and subclavius tendon insertion of the first rib. This type sometimes develops into thrombosis formation in the subclavian vein (Paget-Schroetter syndrome). The arterial type comprises only 20–30% of the vascular group and occurs with direct pressure of the cervical rib, or an abnormal middle scalene muscle to the first rib, or anomalous band-like structure under the subclavian artery.²⁷ Trauma to the neck, shoulder girdle, and upper extremity, particularly the lower trunk and C8–T1 spinal nerves, is thought to play an important role in developing the symptoms of thoracic outlet syndrome. The trauma can be a single blow or a repetitive, strenuous type.²⁷

Anatomy

The brachial plexus trunks and subclavian vessels are subject to compression or irritation in three spaces at the thoracic outlet region. The most important of these spaces is the interscalene space (triangle), which is also the most proximal. This space is bordered by the anterior scalene muscle anteriorly, the middle scalene muscle posteriorly, and the medial surface

of the first rib inferiorly. This area may be small at rest and may become even smaller in the posture with elevation or hyperabduction of the upper limb, which moves the scapula posteroinferiorly, resulting in the access of the clavicle to the first rib. The anomalous structures, such as fibrous bands, cervical ribs, and anomalous muscles, may constrict this space further. The second space is the costoclavicular space, which is bordered anteriorly by the middle third of the clavicle, posteromedially by the first rib, and posterolaterally by the upper border of the scapula. The last space is the subpectoralis minor space beneath the coracoid process just deep to the pectoralis minor tendon (Fig. 2.24).

Provocative maneuver

Adson test (Video 2.16 ►)

The patient is asked to inhale deeply with the chin up and tilt the neck toward the involved arm holding the breath. If the radial artery pulsation disappears or is diminished, the test is positive. This test is considered sensitive to compression in the interscalene space (Fig. 2.25).²⁸

The neck tilting

The patient is asked to inhale deeply and tilt the neck to the opposite direction of the involved arm holding the breath. In patients with TOS, this action produces arm heaviness, numbness, and tingling in the fingers or/and arm, with some pain.

The costoclavicular compression test

The patient is asked to inhale deeply and hold the breath. The examiner depresses the patient's shoulder of the involved limb. Patients with TOS complain of symptoms such as heaviness, pain, numbness or tingling in the limb, and the pulsation of the radial artery is often diminished. This maneuver calls attention to compression in the costoclavicular space (Fig. 2.26).

Wright test

The examiner holds the patient's arm in 90° abduction with the elbow 90° flexed, and rotates the arm externally. If the pulsation is diminished and the symptoms are provoked by this maneuver, the test is positive. Entrapment of the neurovascular bundle at the subpectoralis minor space or the costoclavicular space can make the test positive (Fig. 2.27).²⁹

Roos extended arm stress test (Video 2.17 ►)

The patient is asked to hold both arms with the shoulders in 90°-abduction and 90°-external rotation position and open and close the hands repetitively. If the patient develops any fatigue, pain, numbness or tingling in the hand or arm within three minutes, the test is positive.³⁰

Morley's test

The patient complains of pain, numbness, tingling or uncomfortable feelings when the examiner pushes the patient's brachial plexus in the supraclavicular fossa.

These provocative tests should be performed on the bilateral upper limbs and the outcomes of the involved limb




Fig. 2.24 The three spaces that potentially entrap the neurovascular bundle in patients with the thoracic outlet syndrome.

should be compared with those of the opposite one, because the tests can be positive in a normal person.

Physical examination of the upper extremity in children

Communication with very young children is often difficult or impossible and young children are not able to articulate their symptoms. A fatty subcutaneous tissue layer often prevents doctors from identifying a deformity or swelling. It is often difficult to locate the source of pain because children tend to complain that the pain is everywhere. Questioning of the parents and family of the patient is sometimes helpful for making a diagnosis. Physical examination should include

observing the child's activities when he or she is held by a parent or is playing. Valuable information in terms of the usage and dexterity of the upper extremity can be obtained by observing children playing with age-appropriate toys or props. The affected limb should be examined from the tip of fingers to the hemithorax, which should be compared with the contralateral limb to confirm the anomaly. The physical examination should include not only a musculoskeletal examination but also a nervous system examination. Primitive reflexes, including the Moro reflex, the systemic tonic neck response, the mouth lip reflex, and palmar grasp stimulation are used to assess neuromuscular function in newborns. As these patients age, gross movement patterns and integration of the affected hand into functional activities can be assessed.




Fig. 2.25 Adson test is sensitive to entrapment of the neurovascular bundle in the interscalene space (arrows) by Adson test.




Fig. 2.27 The neurovascular bundle can be potentially entrapped in the costoclavicular space (red arrow) and the subpectoralis minor space (black arrow) by Wright test.




Fig. 2.26 The costoclavicular compression test is considered to detect the entrapment in the costoclavicular space (arrow).



Access the complete reference list online at <http://www.expertconsult.com>

3. Ranade AV, Rai R, Prabhu LV, et al. Incidence of extensor digitorum brevis manus muscle. *Hand (N Y)*. 2008;3:320–323. *Small vestigial extensor tendons are sometimes found in the long and ring fingers beside the extensor digitorum communis tendons, which are called the extensor digitorum brevis manus. This muscle is often found as a soft tissue mass and sometimes causes pain in the dorsum of the hand.*
7. Watson HK, Ryu J, Akelman E. Limited triscaphoid intercarpal arthrodesis for rotatory subluxation of the scaphoid. *J Bone Joint Surg*. 1968;68:245–349. *Watson described his original maneuver of the so-called “scaphoid test” in this article. This maneuver has been modified by several authors and is now recognized as the “scaphoid shift test”, which is a useful physiological examination to identify the instability of the scapholunate ligament complex.*
11. Kleinman WB. Stability of the distal radioulnar joint: biomechanics, pathophysiology, physical diagnosis and restoration of function what we have learned in 25 years. *J Hand Surg Am*. 2007;32A:1086–1106. *The author describes detailed anatomy and biomechanics of the ulnar side of the wrist, including the TFCC. The deep layer of the distal radioulnar ligament plays an important role to stabilize the distal radioulnar joint. The dorsal deep layer of the ligament becomes tight in the supinated forearm and the palmar deep layer increases the strain in the pronated forearm.*
20. Hotchkiss RN, An KN, Sowa DT, et al. An anatomic and mechanical study of the interosseous membrane of the forearm: pathomechanics of proximal migration of the radius. *J Hand Surg Am*. 1989;14A:256–261. *When the radial head was resected, 90% of the axial load applied to the wrist joint was transmitted to the ulna through the interosseous membrane. The central band of the interosseous membrane provided 71% of the overall mechanical stiffness of the forearm.*
26. O'Driscoll SW, Bell DF, Morrey BF. Posterolateral rotatory instability of the elbow. *J Bone Joint Surg*. 1991;73A:440–446. *The authors addressed grades of dislocation of the joint caused by lateral ligament insufficiency (from instability of the joint to complete dislocation) and described a maneuver of the pivot shift test that was provocative of the elbow dislocation due to the lateral ligament instability.*

References

1. Seddon HJ. *Peripheral Nerve Injuries*. Medical Research Council Special Report Series. London: HMSO; 1954:282.
2. Tan JS, Oh L, Louis DS. Variations of the flexor digitorum superficialis as determined by an expanded clinical examination. *J Hand Surg Am*. 2009;34A:900–906.
3. Ranade AV, Rai R, Prabhu LV, et al. Incidence of extensor digitorum brevis manus muscle. *Hand (N Y)*. 2008;3:320–323. *Small vestigial extensor tendons are sometimes found in the long and ring fingers beside the extensor digitorum communis tendons, which are called the extensor digitorum brevis manus. This muscle is often found as a soft tissue mass and sometimes causes pain in the dorsum of the hand.*
4. Eaton RG. The extensor mechanism of the fingers. *Bull Hosp Joint Dis*. 1969;30:39–47.
5. Harris C Jr, Riordan DC. Intrinsic contracture in the hand and its surgical treatment. *J Bone Joint Surg*. 1954;36A:10–20.
6. Parkes A. The “lumbrical plus” finger. *J Bone Joint Surg*. 1971;53B:236–239.
7. Watson HK, Ryu J, Akelman E. Limited triscaphoid intercarpal arthrodesis for rotatory subluxation of the scaphoid. *J Bone Joint Surg*. 1968;68:245–349. *Watson described his original maneuver of the so-called “scaphoid test” in this article. This maneuver has been modified by several authors and is now recognized as the “scaphoid shift test”, which is a useful physiological examination to identify the instability of the scapholunate ligament complex.*
8. Yasuda M, Masada K, Takeuchi E. Dorsal wrist syndrome repair. *Hand Surg*. 2004;9:45–48.
9. Reagan DS, Linscheid RL, Dobyns JH. Lunotriquetral sprains. *J Hand Surg Am*. 1984;9A:502–514.
10. Kleinman WB. The lunotriquetral shuck test. *Am Soc Surg Hand Corr News*. 1985;51.
11. Kleinman WB. Stability of the distal radioulnar joint: biomechanics, pathophysiology, physical diagnosis and restoration of function what we have learned in 25 years. *J Hand Surg Am*. 2007;32A:1086–1106. *The author describes detailed anatomy and biomechanics of the ulnar side of the wrist, including the TFCC. The deep layer of the distal radioulnar ligament plays an important role to stabilize the distal radioulnar joint. The dorsal deep layer of the ligament becomes tight in the supinated forearm and the palmar deep layer increases the strain in the pronated forearm.*
12. Tay SC, Tomita K, Berger RA. The “ulnar fovea sign” for defining ulnar wrist pain: an analysis of sensitivity and specificity. *J Hand Surg Am*. 2007;32A:438–444.
13. Tatebe M, Nishizuka T, Hirata H, Nakamura R. Ulnar shortening osteotomy for ulnar-sided wrist pain. *J Wrist Surg*. 2014;3:77–84.
14. Ruland RT, Hogan CJ. The ECU synergy test: an aid to diagnose ECU tendonitis. *J Hand Surg Am*. 2008;33A:1777–1782.
15. Dellon AL. The moving two-point discrimination test; Clinical evaluation of the quickly-adapting fiber/receptor system. *J Hand Surg Am*. 1978;3:474–481.
16. Bell-Krotoski J, Tomancik E. The repeatability of testing with Semmes-Weinstein monofilaments. *J Hand Surg Am*. 1987;12A:155–161.
17. Moberg E. Objective methods for determining the function value of sensibility in the hand. *J Bone Joint Surg*. 1958;40B:476.
18. Allen EV. Thromboangitis obliterans: methods of diagnosis of chronic occlusive arterial lesions distal to the wrist with illustrative cases. *Am J Med Sci*. 1929;178:237–244.
19. Halls AA, Travill A. Transmission of pressures across the elbow joint. *Anat Rec*. 1960;150:243–248.
20. Hotchkiss RN, An KN, Sowa DT, et al. An anatomic and mechanical study of the interosseous membrane of the forearm: pathomechanics of proximal migration of the radius. *J Hand Surg Am*. 1989;14A:256–261. *When the radial head was resected, 90% of the axial load applied to the wrist joint was transmitted to the ulna through the interosseous membrane. The central band of the interosseous membrane provided 71% of the overall mechanical stiffness of the forearm.*
21. Noda K, Goto A, Murase T, et al. Interosseous membrane of the forearm: an anatomical study of ligament attachment locations. *J Hand Surg Am*. 2009;34A:415–422.
22. Stuart PR, Berger RA, Linscheid RL, et al. The dorsopalmar stability of the distal radioulnar joint. *J Hand Surg Am*. 2000;25A:689–699.
23. Moritomo H, Noda K, Goto A, et al. Interosseous membrane of the forearm: length change of ligaments during forearm rotation. *J Hand Surg Am*. 2009;34A:685–691.
24. McConkey MO, Schwab TD, Travlos A, et al. Quantification of pronator quadratus contribution to isometric pronation torque of the forearm. *J Hand Surg Am*. 2009;34A:1612–1617.
25. Morrey BF. *The Elbow and its Disorders*. 3rd ed. Philadelphia, US: WB Saunders Company; 2000.
26. O'Driscoll SW, Bell DE, Morrey BF. Posterolateral rotatory instability of the elbow. *J Bone Joint Surg*. 1991;73A:440–446. *The authors addressed grades of dislocation of the joint caused by lateral ligament insufficiency (from instability of the joint to complete dislocation) and described a maneuver of the pivot shift test that was provocative of the elbow dislocation due to the lateral ligament instability.*
27. Atasoy E. A Hand surgeon's experience with thoracic outlet compression syndrome. *J Hand Surg Am*. 2010;35A:1528–1538.
28. Adson AW. Surgical treatment for symptoms produced by cervical ribs and the scalenus anticus muscle. *Surg Gynecol Obstet*. 1947;85:687–700.
29. Wright CJS. The neurovascular syndrome produced by hyperabduction of the arms. *Am Heart J*. 1945;29:1–19.
30. Roos DB. New concepts of thoracic outlet syndrome that explain etiology, symptoms, diagnosis, and treatment. *Vasc Surg*. 1979;13:313–321.

3

Diagnostic imaging of the hand and wrist

Alphonsus K.S. Chong, Jin Xi Lim, and David M.K. Tan

Access video content for this chapter online at expertconsult.com 

SYNOPSIS

- Radiographs form the cornerstone of diagnostic imaging of the hand and wrist, and are usually the first imaging modalities performed following clinical evaluation.
- The keys to obtaining the most information from radiographs are ordering the correct radiographs for the situation, and ensuring the radiograph is appropriately taken.
- A systematic and careful examination of the radiograph is necessary to glean the often subtle findings in the hand and wrist.
- Clinical evaluation with plain radiographs often provides sufficient information for clinical decision-making.
- Computed tomography (CT) scans, ultrasound, magnetic resonance imaging (MRI), and other advanced imaging modalities can supplement information from plain radiographs in selected situations. On occasion, they may be the primary imaging study performed.
- These advanced imaging modalities allow today's clinician to visualize disorders that would previously have required open surgery or biopsy.
- The radiograph, despite its simplicity and age, still forms the foundation of imaging of hand and wrist conditions. In many clinical situations, an appropriately chosen and well-taken set of radiographs may be all the diagnostic imaging required.
- The key to obtaining the most information from a radiograph is to understand which radiographs are appropriate for each clinical situation, and how to obtain good-quality radiographs for evaluation.
- Advanced imaging modalities may then be ordered to provide additional information for decision-making.
- This chapter will equip the reader with practical information about the different imaging modalities available for the hand and wrist.
- It will start from the foundation of radiographs, covering the appropriate views, how they are taken, and how best to evaluate them. Following which, the advanced imaging techniques will be described in turn, emphasizing their applications in the hand and wrist.

Introduction

- A proper and directed history-taking followed by a careful examination of both hands and wrists forms the foundation of making a clinical differential diagnosis in hand conditions.
- Appropriate investigations are then ordered to help confirm the clinical diagnosis.
- Diagnostic imaging modalities are often the first-line investigations ordered, as many clinical conditions in the hand and wrist can be seen visually.
- Technological advances in many advanced imaging modalities like ultrasound, CT, and MRI, have led to them being applied for use in the hand and wrist. This increases clinician choices for diagnostic imaging of a suspected clinical condition.



Access the Historical Perspective section online at

<http://www.expertconsult.com>

Radiography

Radiography is the cornerstone in diagnostic imaging of the hand and wrist. It should be the first imaging modality for the diagnosis of most hand and wrist disorders.² The plain radiograph is inexpensive in relation to other imaging modalities, technically easy to perform, and widely available. The correct radiograph taken in an appropriate manner provides much imaging information to the attending clinician. In many hand and wrist conditions, radiography may also be the only imaging modality required for definitive diagnosis and assessment.

Historical perspective

The origins of diagnostic radiology are of particular significance to hand surgery. The first radiograph of human anatomy after the discovery of X-rays by Wilhelm Conrad Roentgen was that of his wife's hand in 1895. The medical community was quick to see the potential applications of this technology, and radiographs were rapidly adopted for clinical use. As a result, Roentgen is considered the father of diagnostic radiology, and his discovery led him to win the first Nobel Prize in Physics in 1901.

Plain X-ray radiographs are still the first-line imaging modality for the diagnosis of most hand and wrist disorders. Plain film radiography has progressed from a tedious process using an acetate-based film to one that applies digital technology. In newer facilities, widespread adoption of digital technology has led to radiographs that are not printed on film, but viewed on the computer screen. Beyond technology, the development of special views through positioning of the patient or machine, and stress application, has enabled improvements in imaging of specific disorders. The development of water-soluble contrast dyes allowed the use of X-rays to perform arthrography.

CT, MRI, and ultrasound are advanced imaging technologies that have become widely adopted for musculoskeletal

imaging, including the hand and wrist. Improvements in hardware technology, software, and imaging protocols have resulted in improved imaging of bone, joints, and soft tissue. These technologies have enabled detailed visualization and assessment of the musculoskeletal system and its disorders in a noninvasive manner. Prior to these technologies, many of these disorders would have required open surgery or biopsy for diagnosis.

Improvements in imaging modalities and technology are only part of the equation for the advances made in musculoskeletal imaging. Equally important has been the parallel development of musculoskeletal radiology as a distinct subspecialty.¹ The dedication of musculoskeletal radiologists has been instrumental in developing their field, and subspecialty training of future musculoskeletal radiologists. These radiologists can better appreciate the often subtle findings on imaging, leading to improved diagnosis. This has translated to earlier and more effective clinical care and improved outcomes.

Musculoskeletal radiology continues to progress at a rapid pace as both a clinical specialty and in technological advances. Building on its strong foundations, musculoskeletal imaging will continue to be a crucial pillar in the diagnosis and assessment of hand and wrist disorders.




Fig. 3.1 The posteroanterior (PA) radiograph of the hand and wrist is taken in the position shown. For the hand radiograph, the beam is centered over the midshaft of the third metacarpal. For the wrist radiograph, it is centered over the capitate.

Evaluation of the hand

The three basic radiographs to evaluate the hand are: postero-anterior (PA), oblique, and true lateral views. The radiographs should be performed in a standardized fashion to allow proper evaluation (Figs. 3.1 & 3.2). Specialized views are required to assess specific areas not well seen in the above views. The PA hand view provides a useful overview of the skeletal structure of the hand. Fractures, osseous tumors, and even soft-tissue masses (Fig. 3.3) can be seen on this view. The




Fig. 3.2 The oblique hand radiograph is taken with the hand positioned as shown. This position provides a good non-overlapping view of the metacarpals. The view is not adequate for assessment of the digits; separate lateral views of the digits should be performed if necessary.



Fig. 3.3 This female patient presented with a soft-tissue mass over the ulnar side of the middle finger. The radiograph shows the outline of the soft-tissue mass with scalloping of the ulnar border of the middle phalanx. Histology of the mass showed this to be a pigmented villonodular synovitis.

oblique view of the hand is useful to assess the metacarpals, as a true lateral view of the hand will lead to an overlapping of the second to fifth metacarpals. In the common boxer's or fifth metacarpal neck fracture, this view allows an assessment of the amount of angulation of the fracture.

In hand radiographs, begin by assessing the overall alignment of the metacarpals and phalanges. The individual bones should then be evaluated in terms of cortical shape and integrity, as well as bony quality. Fractures are usually easy to detect, although a careful review is necessary in the case of undisplaced or minimally displaced fractures. Osseous tumors are identified by an area of different lucency in the bone. There may be changes in the outline of the bone. Enchondromas are common benign bony tumors in the hand. They can result in pathological fractures, so an assessment of the bone for such pathology should be done, particularly if the trauma resulting in the injury is trivial (Fig. 3.4). Osteomyelitis typically occurs in the hand following open injuries (Fig. 3.5).

The joints should then be assessed, starting from the carpometacarpal joints (CMCJs) and working distally. The CMCJs may be dislocated following injury. These injuries are uncommon but are difficult to diagnose. In a normal hand X-ray the second to fifth CMCJs should be clearly visible on the PA view (Fig. 3.6).³ The loss of these features in the second to fifth CMCJs is usually due to a fracture dislocation of one or more of the CMCJs. However, an improperly performed hand radiograph can also give this impression. Fisher *et al.* described a systematic approach to evaluating the PA view of the hand for dislocations of the fourth and fifth CMCJs.³ In subluxation of the fifth CMCJ, the base of the fifth metacarpal is usually



Fig. 3.4 This nurse presented with pain at the base of her right ring finger after transferring a patient from his bed to a chair. The radiograph shows a partial articular fracture of the base of the proximal phalanx of the right ring finger. The area of lucency just at the fracture site and minor trauma were suspicious for a pathological fracture.



Fig. 3.6 In a normal hand radiograph, the second to fifth carpometacarpal joints should be well visualized, as shown. The articular surfaces should be profiled without overlap, parallel to each other, and have distinct cortical rims.



Fig. 3.5 This elderly man presented with increasing pain and redness in the finger. The radiograph shows a destructive lesion of the distal phalanx and head of the middle phalanx. This is consistent with osteomyelitis. A differential diagnosis would be that of a malignant bone tumor. These are much rarer, and usually due to metastatic disease in terminally ill patients.

offset ulnarly compared to the hamate (**Fig. 3.7**). Several views have been suggested to confirm this diagnosis. The true lateral of the hand provides a useful way to assess the CMCJ for any signs of dislocation and oblique views may also be helpful^{4,5}; if the diagnosis is still uncertain, a CT scan of the hand including the CMCJs will confirm the diagnosis.⁶ The more distal joints are then evaluated, from the metacarpophalangeal joints to the proximal interphalangeal joints and distal interphalangeal joints. A normal joint should be completely congruent with a visible joint space.

Osteoarthritis commonly affects the interphalangeal joints and thumb CMCJs. It is often demonstrable on radiographs by narrowing of the joint space, subchondral sclerosis, osteophytes, and deformity (**Fig. 3.8**).

Special views in the hand (**Box 3.1**)

A true lateral radiograph of the finger is needed to complete an assessment of the digit. Hand radiographs alone are insufficient for assessment. This is because the oblique view of the hand does not provide an adequate lateral profile of the digit and interphalangeal joint spaces to supplement the PA view. With only a PA view, subtle fractures, fracture displacement, or joint subluxation of the fingers may not be apparent. Metacarpal head fractures may also be difficult to assess and the Brewerton view⁷ will give additional information in addition to the standard hand radiographs.

To assess the thumb, specialized views are also necessary as the thumb lies in an oblique plane relative to the other digits in the usual hand radiograph. A true PA and lateral view of the thumb is obtained to allow proper radiographic



Fig. 3.7 This radiograph shows a dislocation of the fifth carpometacarpal joint. Note the ulnar offset of the fifth metacarpal with loss of the normal articular space.



Fig. 3.8 Osteoarthritis of the distal interphalangeal joints of middle and ring fingers. There is loss of joint space, and osteophytes are clearly seen on this lateral view.

assessment of the thumb. One common condition in the thumb for which radiographs are performed is that of basal joint or trapeziometacarpal joint (TMCJ) arthritis ([Fig. 3.9](#)). This condition is graded radiologically using the Eaton classification.⁸ The irregular saddle shape of the trapezium makes visualization of the bone difficult, and the Betts view will allow all four articulations of the trapezium to be visible without overlap ([Fig. 3.10](#)).

The ulnar collateral ligament of the thumb metacarpophalangeal joint is commonly injured in forceful thumb abduction.⁹ Less commonly the radial collateral ligament may also

BOX 3.1 Special hand and thumb views

Brewerton view

Purpose: To obtain tangential views of the metacarpal heads – for evaluation of metacarpal head fractures and erosive changes in rheumatoid arthritis

Positioning: With the palm facing up, the MCPJs are flexed 65° with the posterior aspect of the fingers in contact with the cassette, and beam angled at 15° from the ulnar side of the hand

Betts/Gedda view

Purpose: To obtain a true lateral view of the TMCJ, and see the trapezium in profile

Positioning: Palm of the hand must be placed flat on the cassette with the hand and forearm pronated, with the beam is then directed 5–10° distal to proximal

Robert's view

Purpose: To obtain a true AP view of the TMCJ

Positioning: The hand and forearm is hyperpronated such that the dorsum of the thumb lies on the cassette, with the beam angled 15° from the vertical



Fig. 3.9 The trapeziometacarpal joint shows narrowing of the joint space with osteophytes and joint subluxation.



Fig. 3.10 (A) Hand radiograph showing a trapezium fracture. (B) The Bett's view demonstrates the trapezial fracture and the step in the articular surface clearly.

Table 3.1 Appearance of ossification centers and fusion of epiphyses in children

	Females	Males
Appearance of capitate and hamate	3 months	3 months
Appearance of distal radius ossification center	10 months	1 year 3 months
Appearance of phalanges and metacarpal ossification center	10 months to 2 years	14 months to 3 years
Fusion of phalangeal and metacarpal epiphyses	13–15 years	14–16 years
Fusion of distal radius and ulna epiphyses	15–17 years	17–19 years

be injured. Lateral stress application during the posteroanterior thumb radiograph can be helpful to assess if the ligament injuries are complete or partial. Ultrasonography and MRI are alternatives to assess this injury.^{10,11}

Pediatric hand radiographs

Evaluation of the pediatric hand, especially after injury, is often more difficult than in adults. All carpal bones and epiphyses in the hand lack ossification in the newborn. The ossification centers then appear in a well-recognized sequence,¹² as detailed in Table 3.1. The staggered ossification of the various carpal bones (Fig. 3.11) and the presence of the growth plate may confuse the examiner as to whether a fracture is present or not.




Fig. 3.11 Commonest order of ossification: capitate, hamate, triquetrum, lunate, scaphoid, trapezium, trapezoid, and pisiform. Note the position of the growth plates on the proximal ends of the phalanges and first metacarpal. In the remaining ulnar four metacarpals, the growth plate is on the distal end of the bone.

A misdiagnosis rate of 8% for pediatric hand fractures was found in one study.¹³ There are several reasons for this. Clinical evaluation in children is more difficult, the more so the younger the child. It may not be possible to localize the site of the problem clearly, e.g., the site of injury following trauma. Proper standardized views may also be difficult to obtain. Other reasons for misdiagnosis include missing additional fractures and using an X-ray that was obscured by dressings.¹³ When the clinical suspicion remains high and the films obtained are inadequate, the radiograph should be repeated, either the same day or at another time when the patient is more cooperative. Similar views taken of the opposite uninjured limb are also helpful for evaluation.

Growth plate-related injuries are common in children. These injuries can be classified according to the system described by Salter and Harris (Fig. 3.12).¹⁴ The Salter–Harris type II fracture injury is the most common type of growth plate injury seen in the hand.

Wrist evaluation

A properly performed set of orthogonal wrist radiographs forms the basis of an effective evaluation of the wrist.^{15,16} This is especially important when indices are being measured. The wrist has numerous asymmetrically arranged bones, so a methodical assessment of the bones, joints, and overall alignment of the wrist is necessary.




Fig. 3.12 (A–E) The Salter–Harris classification of epiphyseal plate injuries. (Redrawn after Salter RB, Harris R. *Injuries involving the epiphyseal plate*. J Bone Joint Surg Am. 1963;45:587–621.)




Fig. 3.13 Normal wrist radiograph. **(A)** In the posteroanterior view, note the lateral position of the ulnar styloid and position of the extensor carpi ulnaris groove. It lies radial to the straight line that passes tangential to the radial edge of the ulnar styloid at the fovea. This indicates a good posteroanterior view. **(B)** On the lateral view, there is good radioulnar overlap.

Obtaining proper views for wrist radiographs (Figs. 3.1 & 3.13; see Fig. 3.18, below) requires careful positioning which may be difficult to achieve in patients with pain or limitations in motion of the affected upper limb (Box 3.2).

The wrist radiograph is first evaluated by checking the overall alignment of the bones of the wrist, starting with the distal radius and ulna, progressing to the carpal bones and metacarpal bases. Gilula described three smooth arcs made by the articular surfaces of the proximal and distal carpal row bones in a normal wrist PA radiograph (Fig. 3.14).¹⁷ A loss of the normal contour usually indicates a disruption in the normal arrangement of these carpal bones. A common cause of this is a perilunate dislocation (Fig. 3.15). Lunotriquetral (LT) dissociation is another cause of the loss of the normal Gilula's lines. Care must be taken when interpreting these findings in an asymptomatic patient as radial or ulnar deviation of the wrist can introduce a break in the arcs.¹⁸

The overall relationship between the different bones can also be assessed using two common parameters: the carpal height ratio and ulnar variance. These provide a quantitative assessment of the structural integrity of the carpal rows, and the relationship of the distal radius and ulna articular surfaces, respectively.

The carpal height ratio (Fig. 3.16)^{19,20} gives a measure of the distance between the distal articular surface of the radius to the proximal articular surface of the third metacarpal base. A

loss of this distance is seen in collapse of a carpal bone, for example Kienbock's disease (avascular necrosis (AVN) of the lunate) or in malrotation of the carpal bones, for example in rheumatoid arthritis or scapholunate (SL) dissociation. A ratio is used instead of actual dimensions to correct for variability in carpal bone sizes.

The ulnar variance provides a measure of the height difference between distal radius and ulnar articular surfaces. There are several ways to measure the ulnar variance.^{21,22} We prefer the technique of the perpendiculars (Fig. 3.17). It is easy to perform and has been shown to have higher intra- and interobserver reliability.²³




Fig. 3.14 In a normal posteroanterior wrist radiograph, three smooth curved non-overlapping lines can be drawn on the proximal and distal cortical surfaces of the proximal carpal bones (lines 1 and 2) and proximal surface of the distal carpal row (line 3). A disruption or step-off indicates a loss of the normal carpal bone relationships.

BOX 3.2 Assessing quality of wrist radiographs

There are criteria for acceptable wrist views. The PA view is assessed using the position of the ulnar styloid and extensor carpi ulnaris tendon groove.¹⁵ The lateral view is assessed using the radioulnar overlap and scaphoisocapitate relationships.¹⁶



Fig. 3.15 This radiograph shows a perilunate fracture dislocation with disruption of the normal smooth carpal arcs. There are associated radioulnar shaft fractures.

A proper PA and lateral radiograph of the wrist (Fig. 3.18; see Fig. 3.13) is the first necessary imaging for the evaluation of a suspected distal radioulnar joint (DRUJ) instability. Radiographic findings associated with this injury include widening of the DRUJ, a fracture of the ulnar styloid base, or a displaced fracture from the ulnar fovea. On the lateral view, there is loss of the normal radioulnar overlap. A comparison




Fig. 3.16 (1) Carpal height ratio = carpal height (L2)/third metacarpal length (L1). Normal is 0.54 ± 0.03 . (2) Revised carpal height ratio = carpal height (L2)/heights of capitate (rL1). (3) Capitate–radius index (CR). This is the shortest line between two eccentric arches of the carpal rows. The line is moved until the shortest distance is measured. Mean CR index 0.999 ± 0.034 . Values less than 0.92 are abnormal.




Fig. 3.17 Ulnar variance is measured on a true neutral posteroanterior view of the wrist. First a line along the longitudinal axis of the radius is drawn. Next a line perpendicular to this line through the volar ulnar sclerotic rim of the distal radius is drawn. Finally a line parallel to this second line at the level of the distal cortical rim of the ulna is drawn. The distance between these two parallel lines is the ulnar variance.




Fig. 3.18 A true lateral view of wrist is taken in the position shown.

radiograph of the contralateral normal wrist is helpful if the findings are unclear. The application of volar or dorsal-directed stress is also helpful in cases of suspected DRUJ instability (Fig. 3.19).

Scaphoid fractures are the commonest carpal fracture. The shape of the scaphoid bone does not lend itself well to evaluation by just two orthogonal views, so a “scaphoid series” of X-rays is usually done (Fig. 3.20 and Box 3.3).

Fractures of the hook of the hamate are uncommon but disabling. A carpal tunnel view is helpful to diagnose this injury (Fig. 3.21), although a CT scan can also provide the definitive diagnosis.

BOX 3.3 Scaphoid series

The scaphoid view of the wrist addresses the normal foreshortening of the scaphoid seen on the conventional PA wrist radiograph. The view is taken with the wrist ulnarly deviated and the X-ray tube angled $20\text{--}30^\circ$. Several other views are helpful for assessment of the scaphoid: a pronated oblique view (to view the distal third and tubercle of the scaphoid better), a supinated view (to assess the dorsoradial ridge of scaphoid and pisotriquetral articulation), and a lateral view to help assess a humpback deformity.



Fig. 3.19 Stress view: true lateral of the wrist. Notice the loss of radioulnar overlap due to the dorsal subluxation of the distal radioulnar joint. The pisiform lies between the volar aspect of the scaphoid and capitate, so the view is accurate.

Injuries to the wrist ligaments, for example the SL ligament, can lead to carpal instability. In severe cases, this can be seen on the usual wrist views as loss of the normal relationships between the carpal bones. In SL instability, this is typically seen as a dorsal intercalated segmental instability deformity (Fig. 3.22) with an increase in the SL angle, and dorsal tilt in the radiolunate angles (Fig. 3.23). However, in milder forms of instability, application of loads and/or positioning of the wrist are necessary to bring out these dynamic changes in carpal relationships. The clenched-fist PA series of the wrist is one technique used to diagnose dynamic carpal instability (Fig. 3.24).

Ulnar abutment syndrome is a common cause of ulnar-sided wrist pain. The use of a clenched-fist pronated view of the wrist enhances the ulnar variance and may demonstrate the abutment (Fig. 3.25).²⁴

Wrist evaluation in distal radius fractures

Distal radius fractures are the commonest fractures encountered in the emergency room.²⁵ Loss of the normal distal radius indices (Figs. 3.26 & 3.27) due to fracture displacement can affect final outcome. Unstable and displaced fractures are commonly treated with plates and screws. Screws placed subchondrally offer the greatest rigidity in fixation. However, conventional wrist views do not allow accurate assessment of screw position, especially when a distal fracture line compels the surgeon to place the screws in close proximity to the radiocarpal joint. This is because standard views do not compensate for the normal anatomic tilt of the radius. Radiographs angled 22 degree lateral and 11 degree posteroanterior

(Fig. 3.28) enable tangential X-ray exposure to the articular surface and facilitate this assessment after fixation. With increasing use of volar plates for treatment of distal radius fractures, extensor tendon rupture from screw protrusion dorsally is a concern. Detection of dorsal screw protrusion from a lateral X-ray has a sensitivity of only 56%²⁶ and on average, protrusion of the radial-most screw can only be detected at a minimum of 6.5 mm of protrusion.²⁷ Special X-ray views can be done to improve detection of screw protrusion (Box 3.4 and Fig. 3.29)

The availability of fluoroscopy in many clinics and operating rooms allows the dynamic assessment of many hand and wrist conditions. Smaller, lower cost, and radiation²⁸ mini c-arms have also lowered the barrier to acquiring such facilities. The clinician can operate the c-arm to obtain the best view and view changes in the relationships of the bones “live” with motion, loading, or application of stress. Fluoroscopy is helpful for assessing carpal instability, including SL injuries²⁹ (Video 3.1 ▶) and midcarpal instability (Video 3.2 ▶), guiding percutaneous insertion of implants, and assessing the position of implants.³⁰

Ultrasonography

Diagnostic ultrasound has advanced much recently. New ultra-high frequency probes and smaller probe sizes allow higher-quality images of the hand and wrist.³¹ Ultrasound’s safety, portability, and relatively low cost have led to wider use, especially by clinicians operating the machines themselves.³² One additional advantage over other forms of imaging, like CT scanning or MRI, is that it allows dynamic and real-time assessment. The addition of Doppler imaging enhances the information provided by the ultrasound study.³¹

Ultrasound uses the acoustic properties of generated sound waves to form images.³² The ultrasound transducer generates the sound waves in pulses. When the transducer is applied over the surface of the part to be examined, the sound waves pass through tissues. At the junction of two tissues, an acoustic interface occurs. When the sound waves meet an acoustic interface, some of the sound wave energy is reflected, while the rest continues to be transmitted deeper. The greater the differences in material properties of the adjacent tissues, the

BOX 3.4 Additional views for assessment of dorsal screw penetration from distal radius

Supinated

This view aligns the X-ray beam to the radial side of the dorsal cortex, allowing easier detection of prominent screws in the first and second dorsal compartment.

Pronated

This view aligns the X-ray beam to the dorsal-ulnar corner of the distal radius and allow easier detection of prominent screws in the fourth extensor compartment.

Dorsal horizon view

This view is done with the wrist hyperflexed and the X-ray beam aimed along the longitudinal axis of the radius.




Fig. 3.20 Scaphoid series to assess for a scaphoid fracture. Notice the fracture is best seen in the scaphoid view on the lower left corner of the series.

more energy is reflected. The reflected sound wave is received in the transducer. This is then converted to an electrical signal for processing. The greater the sound reflected, the larger the amplitude of the reflected wave, and consequently, the brighter the image.

Ultrasound has its disadvantages (Table 3.2). It only allows a small field of view, so is best used for a focused examination of a small area. Differentiation of different soft-tissue tumors of the hand and wrist, apart from ganglia, is also inadequate.³³ The problem of anisotropy can lead to reduced echogenicity when tendons are being imaged. Anisotropy is a phenomenon where the echogenicity of the tendon changes when the incidence of the sound beam changes. This can lead to the operator mistaking anisotropy for pathology like tendon degeneration. A careful complete assessment of suspected tendon lesions will detect this phenomenon.³⁴

One major advantage of musculoskeletal ultrasound is the ability to do real-time and dynamic assessments. An area in

the hand and wrist where this is particularly useful is in the assessment of tendons. For example, flexor tendon bowstringing due to pulley rupture can be dynamically demonstrated on ultrasound by the patient. Tendinopathies, partial and complete tendon tears, or lacerations can be demonstrated (Fig. 3.30). Ultrasound has also been shown to be able to detect changes in trigger finger³⁵ and DeQuervain’s tenosynovitis.³⁶

Table 3.2 Advantages and disadvantages of ultrasound	
Advantages	Disadvantages
• No ionizing radiation • Allows real-time and dynamic assessment by operator • Relatively cheap to acquire and operate	• Very limited field of view • Highly operator-dependent • Limited usefulness for assessment of soft-tissue masses




Fig. 3.21 (A) Carpal tunnel view of the wrist demonstrating several structures: trapezium (Tz), pisiform (P), and hook of hamate (HH). A fracture across the hook of the hamate is indicated by the black arrow. The trapezial ridge (indicated by white arrow) is an unusual site for fractures that is best seen on this projection. (B) Same patient with carpal tunnel view of the same wrist following open reduction and screw fixation. Notice that the fracture line is no longer visible.




Fig. 3.23 Carpal indices. Axes are drawn based on the true lateral wrist radiograph. (A) The scaphoid (S) is represented by a tangential line that connects the two palmar convexities of the bone. (B) The lunate (L) axis is perpendicular to a line that joins the two distal horns of the bone. (C) The capitate (C) axis is determined by the center of the two proximal and distal articular surfaces. (D) The axis of the radius (R) is obtained by tracing perpendicular lines to its distal third and connecting the center of these lines. (E) Normal scapholunate angles. (F) Normal capitolunate angles. (G) Normal radiolunate angles. DISI, dorsal intercalated segmental instability.



Fig. 3.22 DISI is the acronym for dorsal intercalated segmental instability. The term “intercalated segment” refers to the proximal carpal row bones. (A) This row has no direct musculotendinous insertions, hence it is “intercalated.” “Dorsal” refers to the dorsiflexion of the lunate seen in the radiograph. A scapholunate dissociation is the commonest cause of a DISI deformity, and will show an increased scapholunate angle as above. (B) On the posteroanterior view, the scaphoid will appear flexed and foreshortened with a positive cortical ring sign as seen.



Fig. 3.24 These radiographs show a patient with dynamic scapholunate instability. The scapholunate interval is normal on an unloaded wrist (**A**), but widens on clenching the fist (**B**).



Fig. 3.25 This patient presented with signs and symptoms of ulnar carpal abutment. The positive ulnar variance (**A**) is increased with the pronated clenched-fist view (**B**).




Fig. 3.26 Normal distal radius indices. PA, Posteroanterior.

In trigger finger, ultrasound has also been used to guide steroid injection and percutaneous release.^{37,38}

Diagnostic ultrasonography has also been applied to other wrist and hand disorders. Carpal ligament injuries and triangular fibrocartilage (TFCC) tears can be assessed using ultrasonography.³⁹ For TFCC tears, ultrasonography has been shown to have good correlation with MRI.⁴⁰ Ultrasonography of the carpal tunnel may be helpful to assess carpal tunnel syndrome. The median nerve is enlarged in carpal tunnel syndrome, with changes in the echogenicity of the nerve. The most consistent finding across the studies is the increase of the cross-sectional area of the median nerve at the level of the pisiform bone.⁴¹ Ultrasound is also useful for clinical




Fig. 3.28 Position of the limb and direction of X-ray beam for an anatomical tilt lateral view of the distal radius. This view is very helpful for assessing screw position when applying plates and screws close to the articular surface in distal radius fractures.

assessment if other causes of carpal tunnel syndrome are suspected (e.g., mass lesions in the carpal tunnel or tenosynovitis).

Computed tomography

CT is a key advanced imaging modality for the assessment of hand and wrist disorders, particularly those affecting the



Fig. 3.27 Distal radius fracture with loss of the normal radial height, inclination, and volar tilt.




Fig. 3.29 (A) Standard PA and lateral wrist X-rays showing a distal radius fracture post-fixation. (B) Supination and pronation views showing dorsal screw penetration. (C) Dorsal horizon view showing dorsal screw penetration.

bones and joints. Advances in CT scanning technology have resulted in shorter scanning times, and allow manipulation and reformatting of the CT data for image reconstruction in multiple planes and the development of three-dimensional images. The advantages and disadvantages of CT are shown in [Table 3.3](#).

Fractures and dislocations

CT is useful in evaluation of the hand and wrist for bony and joint injuries that are not well visualized or assessed using radiographs. Examples of these include scaphoid fractures, CMC joint injuries (see discussion in [radiography](#) section, above), and other articular fractures ([Fig. 3.31](#)).

Scaphoid fractures are often difficult to detect on plain radiology after an acute injury. A repeat radiograph several weeks later or other radiological investigations like CT scan, MRI, and bone scans are often employed to detect an occult scaphoid fracture.⁴² In one study, multidetector CT was shown to be as effective as MRI in the detection of such occult fractures.⁴³ In the management of scaphoid fractures, CT scan is useful in evaluating fracture union,⁴⁴ as plain radiography has been shown to have poor interobserver agreement for assessing scaphoid union.⁴⁵ CT scans along the long axis of the scaphoid⁴⁶ improve the ability to evaluate the scaphoid for fractures, and assess for any displacement or humpback deformity.⁴⁷ CT scan is also useful for the evaluation of other carpal fractures.⁴⁸




Fig. 3.30 This patient presented with difficulty in finger flexion after an injury. Ultrasonography showed a partial tear of flexor tendon at the level of the head of middle phalanx, more obvious on flexion against resistance (dark area, arrowed on longitudinal section image and between calipers on transverse section image). (Courtesy of Dr. Ian Tsou, Singapore.)

Wrist radiographs provide a first evaluation of the distal radius fractures. In an acute fracture, patient positioning is hindered by pain, and suboptimal radiographs are common. Radiography can over- and underestimate the articular step-off in 30% of intra-articular fractures.⁴⁹ CT scans of the wrist can improve assessment, which has an impact on clinical decision-making (Fig. 3.32). CT scanning and three-dimensional reconstruction are also helpful in complex fractures of the distal radius and ulna to help in surgical planning. In distal radius malunion, CT is recommended to assess the deformity⁵⁰ and as a basis for computer-assisted surgical techniques.^{51,52}

Table 3.3 Advantages and disadvantages of computed tomography (CT)

Advantages	Disadvantages
- Quick scanning with modern machines - Capacity to image in any anatomic plane (multiplanar imaging) and three-dimensional reconstruction - Excellent for assessing complex or poorly visualized fractures in the hand and wrist - CT angiography can be performed at the same sitting to assess the vascular tree	- Inferior to magnetic resonance imaging for imaging of soft tissue - Requires expose to ionizing radiation - Prone to artifacts from patient movement and implants

CT is also helpful in suspected DRUJ instability. A proper lateral view of the wrist is the key initial imaging. There are several pitfalls associated with this. Proper positioning of the wrist for a proper lateral wrist radiograph or stress views may not be possible because of pain or other factors. The instability may be subtle, manifesting only in certain wrist positions or under load. Bilateral axial cut CT scans of the wrists in the




Fig. 3.31 This displaced fracture of the radial condyle of the proximal phalanx (small finger) is well visualized on the computed tomography (A) and (B), but obscured on plain radiograph. There is a concomitant fracture of phalanx base, seen in (B).



Fig. 3.32 Coronal computed tomography (CT) image of distal radius fracture. Extension into the radiocarpal joint is seen here but not on the plain radiograph. CT is helpful for the assessment of intra-articular distal radius fractures with respect to articular involvement and incongruity, fragment number, and fragment orientation.

neutral, pronated, and supinated position provide critical information to allow better evaluation of these injuries (Fig. 3.33). For CT evaluation of DRUJ instability, different radiographic parameters have been described.^{53–56} Our institution uses the subluxation ratio method described by Park and Kim.⁵⁷

Other applications of CT

CT is also helpful for the evaluation of bony tumors in the hand. CT can help characterize the bony tumor and assess for bony destruction. In these situations, MRI is often complementary. Fine-cut CTs are the modality of choice for osteoid osteoma.⁵⁸

There are limitations to the use of CT. Soft-tissue resolution is limited, so it is less useful than MRI for imaging soft-tissue disorders. Artifacts from various sources, including patient movement and metal implants, hinder evaluation. Software techniques can be used to limit these artifacts, but often at the cost of resolution at the site of interest.⁵⁹




Fig. 3.33 Axial computed tomography cut of distal radioulnar joint in neutral position shows dorsal subluxation of the left joint (right image). This can be quantified by the use of indices.

The usefulness of CT is often enhanced when coupled with volume-rendering techniques. These allow clearer imaging of subtle fractures and complex injuries. They are also helpful in the evaluation of suspected infections or neoplastic disease. After operative fixation of fractures, volume rendering can improve the quality of imaging by eliminating streak artifacts.⁶⁰ Using intravenous contrast, CT angiography can be performed (see section on [vascular imaging techniques for the upper extremity](#), below).

Magnetic resonance imaging

MRI of the hand and wrist has come to the forefront in the last decade. It is the preferred modality for imaging soft tissue, particularly those associated with trauma and neoplastic conditions. Larger and more powerful magnets, improved gradient strength and speed, dedicated coils providing favorable signal-to-noise ratios, and the capability of supporting small fields of view enable visualization of pathology in exquisite anatomic detail. The advantages and disadvantages of MRI are shown in Table 3.4.

MRI basics

MRI employs magnetic fields and radiowaves rather than ionizing radiation. The magnetic field is generated by an electromagnetic coil with field strengths ranging from 1.5 to 3.0 Tesla (T) (15000–30000 gauss). Gradient (secondary) magnets fine-tune and focus the MRI on specific areas of interest. MRI coils send and receive radiofrequency pulses that are used to create images. In general, the smaller the coil and the more centrally located an anatomic structure is within the coil, the sharper the image and the higher the signal-to-noise ratio.

MR differentiates tissues such as fat, muscle, bone, blood, and water on the basis of their innate magnetic characteristics and the varying tissue concentration of hydrogen ions (protons). Each proton spins like a top, around an axis. In the absence of a magnetic field, their axes are randomly oriented and produce no net magnetic effect. In the MRI scanner, the magnetic field generated causes the axes of rotation of the protons to align themselves with the longitudinal axes of

Table 3.4 Advantages and disadvantages of magnetic resonance imaging (MRI)

Advantages	Disadvantages
- Capacity to image in any anatomic plane (multiplanar imaging) - High soft-tissue contrast with indication of tissue composition - No ionizing radiation - Acquisition of three-dimensional volume data using gradient echo sequences - Noninvasive imaging of blood vessels and other structures without the use of contrast (e.g., MR arthrography)	- The high cost of equipment - Image artifacts from motion and ferromagnetic objects - Inferior to computed tomography for imaging of cortical bone - Contraindicated in patients with cardiac pacemakers, aneurysm clips, metallic foreign body, claustrophobia

Table 3.5 Signal intensities of tissues on T₁- and T₂-weighted magnetic resonance images

Tissue	Signal T ₁ -weighted image	Signal T ₂ -weighted image
Fluid (free water)	Low	High
Fluid (proteinaceous)	Intermediate	High
Fat	High	High
Muscle	Intermediate	Intermediate
Cartilage	Intermediate	High
Cortical bone	Low	Low
Bone marrow (yellow)	High	Intermediate
Bone marrow (red)	Low	Intermediate

the magnet. Gradient magnets change the alignment of the rotating protons whilst radiofrequency pulses from the coils excite the protons to a higher energy level. Cessation of radiofrequency stimulation induces a tiny current within the surrounding coil which can be detected and amplified to give a signal. The time taken for a proton to become magnetized is known as the T₁ relaxation time and the time taken for the proton to be demagnetized is known as the T₂ relaxation time. The amount of energy released by a tissue is directly proportional to its concentration of protons. It is also the varying concentration of protons between different tissues that allows them to be magnetized and demagnetized differentially. This is the basis of differentiating the soft tissues. The relevant signals of different tissues on T₁- and T₂-weighted images are shown in Table 3.5.

Water can be categorized into free water and bound water. Free water is found mostly in extracellular fluid whilst bound water is mostly in intracellular fluid. Free water has long T₁ and T₂ relaxation times. Hence it typically shows low signal intensity on T₁-weighted images and high signal intensity on T₂-weighted images. Water that is not free is usually bound to proteins which inhibit motion. This preferentially shortens the T₁ relaxation time more than the T₂ relaxation time, hence the T₁ signal is usually of intermediate to high intensity. Examples of proteinaceous fluid include abscesses, synovial fluid, and purulent collections.

Clinical applications of MRI

MRI for soft-tissue masses

MRI is the preferred modality for imaging soft-tissue masses in the hand and wrist. The majority of soft-tissue masses in the hand and wrist are benign.⁶¹ MRI characteristics of the common tumors are well described in literature and references.^{62–64} MRI, with its multiplanar imaging capability, tissue characterization of lesions, and ability to define relationship of lesions to surrounding tissue and vessels (including tumor invasion), allows one in many circumstances to arrive at a specific diagnosis.

Ganglion cysts

Ganglia show low to intermediate signals on T₁-weighted images and high signals on T₂-weighted images. They may be

uniloculated or multiloculated and contain proteinaceous synovial fluid. This accounts for its isointense or slightly hypointense signal on T₁-weighted images compared to muscle (Fig. 3.34). Demonstration of a stalk can usually reveal its site of origin. Hemorrhage into a ganglion cyst can result in high signal intensity on T₁-weighted images. A ganglion




Fig. 3.34 This patient presented with a firm mass in the left thenar eminence that was difficult to characterize clinically. Radiographs were normal. **(A)** Magnetic resonance imaging shows a mass with typical high signal intensity during the T₂-weighted sequence. **(B)** A sagittal fat suppression short tau inversion recovery sequence shows the stalk of the ganglion connecting to the sheath of the flexor carpi radialis (indicative arrow) with the scaphoid (S) in close relation.

shows no enhancement on administration of intravenous gadolinium; however, its capsule and septa will usually show enhancement. Ganglion cysts occurring in “classic” locations such as the dorsum of the wrist can usually be diagnosed clinically and do not require MRI.

Giant cell tumors of the tendon sheath (GCTTS)

Synonymous with focal pigmented villonodular synovitis, these benign tumors of synovial origin typically occur in the digits over the volar aspect, and arise from the tendon sheath, joint capsule, fascia, or ligaments. They contain multinucleated giant cells and have intra- and extracellular hemosiderin deposition. On MRI, GCTTS appear as solid masses, hypointense on both T₁- and T₂-weighted images. The low signal is due to the paramagnetic effect of hemosiderin deposition. On T₁- and T₂-weighted images, these masses appear isointense with skeletal muscle. Uniform enhancement is seen following administration of intravenous gadolinium contrast (Fig. 3.35).

Lipomas

Lipomas are less common in the hand and wrist than in other parts of the body. In the hand, they usually occur over the palmar aspect, either in the thenar or hypothenar eminence or in the mid-palmar space. They show the same homogeneous high signal intensity as fat on T₁-weighted images and superficial lipomata can appear inconspicuous. They show low signals on short tau inversion recovery (STIR) and T₂-weighted sequences. The presence of distinct nodules or solid components may suggest a liposarcoma.

Hemangiomas

Hemangiomas are benign tumors classified into capillary, cavernous, and venous types. T₁-weighted signal intensity varies from low, to high, depending on the amount of fat contained. On T₂-weighted sequences, they tend to be lobulated with well-defined borders and very high signal intensity from pooled blood. A lace-like pattern of enhancement may be seen on T₁-weighted images due to fibrofatty elements. Signal voids may be present on all MR sequences as a consequence of phleboliths within the hemangiomas. The heterogeneous nature of hemangiomas thus makes preoperative diagnosis by MRI less certain.⁶¹

Enchondromas

Enchondromas are the most common benign tumors of bone that are found in the hand. Problems associated with enchondromas are pathological fractures and the rare occurrence of malignant transformation. Radiography demonstrates a lytic expansile lesion with a clear zone of transition and speckled calcifications. Cortical thinning is present and may be associated with a pathological fracture. On MRI, they appear as high-signal-intensity lobulated tumors on fat suppression (FS) STIR and T₂-weighted sequences. They show low to intermediate signal intensity on T₁-weighted sequences.

MRI for wrist and hand trauma

This application of MRI has become more widespread in the last two decades, in particular for ligamentous injuries. A further advantage of MRI is its superior imaging of bone




Fig. 3.35 This man presented with a firm painless enlarging mass over the dorsum of the left hand. Magnetic resonance imaging shows a low signal intensity mass over the third carpometacarpal junction, seen on (A) sagittal T₁-weighted sequence and (B) axial T₂-weighted sequence.

marrow and vascularity of bone with a wide range of applications, including diagnosing AVN, marrow edema, and inflammation, as well as infection.

Occult scaphoid and carpal fractures

MRI is the most sensitive and specific imaging modality for occult scaphoid fractures, although its cost may be greater or

equitable compared to the classic diagnostic algorithm.^{65,66} An area of a linear band of low signal intensity on T₁-weighted sequences, coupled with an area of high signal intensity on FS T₂-weighted sequences or STIR sequences, has the highest combined sensitivity and specificity. Cortical fracture lines are best seen on a STIR or gradient echo (GRE) sequence. Use of MRI for diagnosis of radiographically occult fractures is not limited to the scaphoid, but includes other carpal bone fractures which are difficult to image on radiography.⁶⁷ The added value of using MRI for detection of occult carpal bone fractures is that it also demonstrates ligament injuries which can clinically mimic carpal fractures (Fig. 3.36). Bone bruising, a term synonymous with bone contusion, exhibits exactly the same MRI findings as occult fractures do with the exception of a cortical break. This diagnosis is made in the setting of a positive history of preceding trauma and positive MRI findings, as described above.

Ligamentous injuries of the hand and wrist

Suspected ligamentous injuries of the hand and wrist are probably the most common indication for ordering an MRI. SL and LT ligament tears as well as tears of interphalangeal or metacarpophalangeal joint ligaments are frequent clinical problems. Another large group of wrist pathologies – ulnar-sided wrist pain, including but not limited to tears of the TFCC, ulnocarpal abutment, DRUJ and tendinitis – is considered separately in the next section.




Fig. 3.36 This patient presented with persistent dorsoradial-sided wrist pain after a fall. He had initially been seen by a general practitioner and diagnosed as having a sprain. Magnetic resonance imaging coronal fast spin echo proton density sequences with fat suppression showed two areas (white arrows) of high signal intensity in the scaphoid proximal pole and waist (associated with fracture). The signal enhancement in the proximal pole is due to an injury of the scapholunate ligament, noting a normal ligamentous structure of the lunotriquetral ligament (black arrow).

An intact ligament is shown as a homogeneous black signal or band on a proton density-weighted GRE sequence or a T₁-weighted spin echo sequence on coronal slices. An abnormal ligament shows increased signal intensity on T₂-weighted sequences or STIR sequences, segmental defect, increased length, thickening, thinning, and nonvisualization.⁶⁸ MR arthrography can be performed with saline or dilute gadolinium injected into the joint, enhancing the detection of ligaments and TFCC perforations.

Thumb ulnar collateral ligament injuries

A poorly treated complete tear of the ulnar collateral ligament of the thumb metacarpophalangeal joint can lead to painful and chronic instability. MRI is valuable in assessing for complete ligamentous disruption, a diagnosis that may be difficult to make in early or acute presentations (Fig. 3.37). Such imaging helps exclude a Stener lesion,⁶⁹ where the adductor aponeurosis becomes interposed between the two ends of the ruptured ligament, preventing ligament healing.

Scapholunate interosseous ligament injury

This is the most common intrinsic wrist ligament injury. Presentations vary from occult SL joint ganglions, dynamic SL instability, to static SL dissociation. SL dissociation is the commonest cause of carpal instability. Early recognition of SL instability allows treatment and prevention of late arthritis. Features which support a tear of the SL ligament include widening of the SL interval, fluid signal traversing the SL or LT ligaments on the fat-suppressed fast spin echo (FSE) T₁-weighted sequence, or STIR sequence (Fig. 3.38). Proton density sequences as well as T₂-weighted sequences with FS can also reveal morphological abnormalities and absence of the SL ligament. The same criteria also apply for evaluating the less common LT ligament injuries.

MRI for evaluating ulnar-sided wrist pain

Ulnar-sided wrist pain is a common and challenging problem. Causes of ulnar-sided wrist pain include injuries to the TFCC, LT ligament injuries, and ulnocarpal abutment syndrome. Other diagnoses include fractures and nonunion of fractures, especially of the ulnar styloid, DRUJ problems, and tendinopathies.

TFCC tears

TFCC injuries are classified into two groups: those occurring acutely and degenerative lesions. In the latter group, lesions occur in the central portion of the TFCC and the incidence increases with advancing age. Acute traumatic tears of the TFCC usually occur following a forced axial load of the wrist in an extended and ulnar-deviated position. Acute tears of the TFCC resulting in detachment from the fovea or detachment from its radial border can result in DRUJ instability. The gold standard for evaluation of TFCC injuries is arthroscopy. MRI has been increasingly used for imaging the TFCC. The sequence which best demonstrates the TFCC is the FS FSE T₁-weighted and GRE T₂ sequence.⁷⁰ GRE sequences which mimic FS FSE T₁-weighted sequences such as the proton density-weighted GRE sequence depicts TFCC disruptions even more distinctly (Fig. 3.39). With the advent of 3.0-T MRI




Fig. 3.37 This 15-year-old girl presented with pain at the ulnar aspect of the metacarpophalangeal joint of her right thumb after an abduction injury from a fall. Plain posteroanterior and lateral radiographs showed no abnormalities. Clinical assessment for joint instability was difficult because of her anxiety and pain and a magnetic resonance imaging scan was performed. The coronal fast spin echo proton density sequence, a variant form of gradient echo sequences, reveals a distal avulsion/rupture (**A**) of the ulnar collateral ligament (black arrow). The radial collateral ligament on the other hand is intact and smoothly inserts or joins the base of the proximal phalanx of the thumb. (**B**) The short tau inversion recovery sequence shows bright signal intensity at the site of rupture seen on the proton density sequence, correlating with an acute tear or rupture of the ligament.




Fig. 3.38 This patient presented with right-sided wrist pain. He had tenderness over the scapholunate junction over the dorsum of the wrist. Radiography showed a normal scapholunate angle on lateral wrist projections and no widening of the scapholunate interval on posteroanterior projections of the wrist. Magnetic resonance imaging coronal fast spin echo proton density sequences with fat suppression (**A**) showed widening of the scapholunate (SL) interval (star) with absence of the membranous portion of the ligament. The membranous portion of the lunotriquetral (LT) ligament is intact (white arrow). The next sequence shows a more dorsal section of the proximal carpal row with an intact LT ligament (black arrow) and disrupted SL ligament with abnormal fluid signal traversing it and a thickened and fibrillar morphology (white arrow) (**B**).




Fig. 3.39 This 27-year-old male presented with right ulnar-sided wrist pain of 1 year's duration. There was a preceding history of a fall during rollerblading. Magnetic resonance imaging proton density-weighted sequences show that the portion of the triangular fibrocartilage (small arrow) that inserts into the fovea (big arrow) has been avulsed off its insertion (**A**). In a different patient, the triangular fibrocartilage with its insertion into the fovea preserved (white arrow) is shown (**B**). This patient had instead a scapholunate ligament injury.

machines, the sensitivity and specificity of MRI for detection of TFCC lesions exceed that of 1.5-T machines.^{71,72}

Ulnocarpal abutment

This is a degenerative condition related to excessive load-bearing across the ulnar side of the wrist. An ulna positive

variance may be present. Radiography may be normal or may show subchondral cyst formation in the lunate and/or triquetrum. Stress films can demonstrate dynamic increase in ulnar length relative to the radius (pronated grip film of the wrist). MRI shows foci of low signal intensities in the lunate and triquetrum and occasionally in the ulnar head, reflecting chondromalacia. On FS STIR or FS T₂-weighted sequences, these same areas show bright signal intensities from bone marrow edema or secondary to the presence of cyst formation (Fig. 3.40).

DRUJ instability and tendinopathies

CT is the preferred imaging modality for DRUJ instability and subluxation. MRI however allows visualization of the ligaments and the insertion of the TFCC into the fovea, which contributes to stability of the DRUJ. Furthermore, high signal intensities on FS STIR sequence will suggest reactive marrow edema from persistent DRUJ instability and synovitis. The relationship of the ulnar head to the distal end of the radius and DRUJ subluxation is best assessed on an axial FSE T₁-weighted sequence. A halo of high signal enhancement can be seen in tendinopathies on axial slices during an FS STIR sequence or an FS T₂-weighted sequence. In addition, there may be thickening of the tendon and abnormal signal within the tendon itself on coronal slices.

MRI for evaluation of fracture nonunion

Scaphoid fractures are prone to nonunion. Radiography to assess for fracture healing lacks a high degree of sensitivity and specificity. The MRI criterion to assess union is the presence on T₁-weighted sequences of normal signal intensity crossing the previous fracture line.⁷³ Nonunion is shown by the presence of high signal intensity at the fracture line on FS STIR or FS T₂-weighted sequences or the GRE equivalents.

MRI for avascular necrosis (AVN) in scaphoid fracture nonunion

The proximal pole of the scaphoid is prone to AVN following a fracture due to its retrograde vascular axis pattern.⁷⁴ Radiographs can show changes associated with AVN, including sclerosis of the proximal fragment, osseous absorption, and cysts. MRI can detect AVN at an earlier stage. Knowing the vascularity of the proximal fragment guides clinical decision-making, including whether to use vascularized or nonvascularized grafts. Low signal intensity of the proximal fragment on T₁-weighted sequences indicates replacement of the normal marrow with fibrous tissue. High signal intensity of the proximal pole on gadolinium contrast-enhanced study suggests that vascularity is preserved. This finding has not been consistently proven in all studies, and the relative enhancement should be significantly greater than the surrounding carpal bones.⁷³

Kienbock's disease

Idiopathic AVN of the lunate is relatively uncommon when compared with post-traumatic AVN of the scaphoid. A negative ulnar variance has been shown to be associated with an increased risk of Kienbock's disease. MRI is of value in detecting early disease, prognosticating, and for monitoring




Fig. 3.40 This patient presented with persistent right ulnar-sided wrist pain of 6 months' duration and he complained of inability, in particular in hammering objects. He had tenderness over the ulnar fovea and a positive ulnocarpal grind. Plain film radiography (**A**) showed no fractures of the ulnar styloid. There was, however, a subchondral cyst seen in the proximal ulnar corner of the lunate (black arrow) and there was positive ulnar variance (white arrow). On magnetic resonance imaging, the fat suppression short tau inversion recovery sequence showed high signal intensity in the same corresponding area of the lunate (**B**). Note that the triangular fibrocartilage and the ulnar head (white arrows) show no signal enhancement which would typify more advanced involvement.

revascularization of the lunate following treatment.⁷⁵ AVN of the lunate is suggested by low signal intensity on T₁-weighted sequence as marrow is replaced by fibrous tissue. Areas of high signal intensity may be seen on FS T₂-weighted sequence or FSE FS STIR sequences, suggesting marrow edema or neovascularization (Fig. 3.41). Low signal intensity on such sequences likely indicates established ischemic necrosis without any further bone reactive changes.

Osteomyelitis

Osteomyelitis of the hand and wrist bones is relatively uncommon. It is usually a consequence of previous surgical intervention for fractures or other procedures. Traditionally, either scintigraphy or MRI has been used when plain film radiography has been negative in suspected osteomyelitis. MRI has the advantage of discriminating marrow abnormalities from joint and soft-tissue changes. Areas of marrow involvement will show low signal on T₁-weighted sequence and high signal intensity on T₂-weighted sequence.

Vascular imaging techniques for the upper extremity

Digital subtraction angiography (DSA) is the gold standard for vascular imaging of the extremities.^{76,77} Improvements in CT angiography and magnetic resonance angiography (MRA) make them increasingly viable alternatives in vascular imaging of the upper extremity. Arterial imaging of the upper limb is usually performed in two different clinical settings: the detection of extremity vascular injury following trauma to the limb, and assessment of vascular disorders involving the upper limb.

The indications for angiography following trauma are: decreased or absent pulse or blood pressure, cold limb, bruit or murmur, uncontrolled bleeding or increasing hematoma, neurologic deficit, and proximity of the injury to vascular structures.⁷⁸ When the clinical condition warrants immediate surgery, conventional angiography is contraindicated. Knife injuries (80%) and blunt trauma (67%) are more likely to be associated with vascular abnormalities, followed by gunshot wounds (44%).⁷⁸

DSA has a role in the assessment of the vascular tree in peripheral arteriosclerotic disease, connective tissue diseases, thoracic outlet syndrome, and Raynaud's phenomenon. It is also useful for assessing arteriovenous fistulae and vascular tumors and malformation of the upper limb.

CT angiography (CTA) is less invasive than DSA and can additionally assess vessel wall and extraluminal pathology. The data obtained allow reconstruction in three-dimensional and multiple planes. The advancements in CT technology, new protocols, and availability of CTs in proximity of many emergency departments have made CTA an increasingly attractive option for the assessment of the extremity vascular tree following trauma.^{79,80} In extremity trauma, CTA can identify arterial injuries, including pseudoaneurysm, active arterial hemorrhage, arteriovenous fistulae, occlusion, intimal injury, or vasospasm.⁸¹ Venous injury may also be assessed. CTA has also been shown to be useful in the evaluation of suspected extremity vascular trauma in pediatric patients.⁸² In




Fig. 3.41 A karate enthusiast presented with right wrist central dorsal pain of gradual onset that was associated with morning stiffness as well as weakness of grip over the passage of time. Radiography was normal aside from the suggestion of an area of faint linear sclerosis in the lunate. Magnetic resonance imaging fast spin echo T₁-weighted sequence showed loss of normal marrow signal affecting the radial corner of the lunate (**A**). Fast spin echo fat suppression short tau inversion recovery sequences showed diffuse marrow enhancement, sparing only the proximal ulnar tip of the lunate (**B**).

pediatric patients, CTA allows imaging of the vascular tree where DSA is often not possible.

The indications for CTA are similar to that of DSA. There are limitations with use of CTA for evaluation following trauma. For example, differentiation of a tapered contour deformity of CTA, which may variously represent dissection,

intimal injury, vasospasm, or adjacent hematoma, is difficult.⁷⁹ Imaging of the distal vascular tree is also difficult. DSA also offers an advantage where there is a possibility of endovascular treatment, for example in an arteriovenous fistula. The sensitivity and specificity of CT arteriography have been shown to be 95.1% and 98.7% in cases of suspected vascular injury following blunt or penetrating injury.⁸³

MRA offers advantages over conventional DSA for extremity vascular imaging. MRA is less invasive, does not require iodinated contrast, and can simultaneously demonstrate extraluminal disease.⁸⁴ The angiographic effect in MRA is created by various techniques with or without contrast enhancement with gadolinium chelate agent. The use of contrast-enhanced MRA with a dedicated surface coil enables quick and high-quality examination of the hand vascular tree.⁸⁵

MRA of the wrist and hand has a potential number of indications for its use and has been employed successfully in imaging of vascular malformations, vascular trauma, and vascular occlusion.⁸⁶ MRA is performed making use of a coronal volume three-dimensional spoiled GRE time-of-flight sequence and dynamic administration of intravenous gadolinium contrast with image acquisition using a wrist coil. The inherent contrast from protons in flowing blood relative to the saturated protons in the stationary soft tissue produces the image which is formulated based on an MR algorithm which deletes the signal from the soft tissue. MRA has the potential to depict pathologic change in vessels of up to 1 mm in diameter and can reliably show the superficial and deep palmar arches of the hand (Fig. 3.42). Some of the disadvantages of MRA include the inferior resolution of vasculature at 1 mm diameter or less, susceptibility to motion artifacts, as well as flow artifacts at sites of severe stenosis or thrombosis where a high signal intensity may be mistaken for flowing blood. MRA is useful in patients with renal impairment where intravascular ionic contrast could cause further nephrotoxic damage, as well as in pediatric patients.

Radionuclide imaging

Radionuclide imaging is a highly sensitive imaging modality⁸⁷ with applications in hand and wrist conditions. It can be positive even when conventional imaging techniques are unable to visualize the condition. The main limitation of radionuclide imaging is its lack of specificity. This is because the tracers used reflect function.⁸⁸ The imaging detail required to differentiate physiological and pathological processes is often lacking in these scans. Therefore it is most useful as a screening tool. The most common radionuclide musculoskeletal imaging is bone scintigraphy with technetium-99m-labelled diphosphonates. The three-phase bone scan is highly sensitive for osteomyelitis. However, similar findings can be mimicked by conditions such as tumors, fractures, and joint neuropathy. The use of indium-111-labeled autologous leukocytes can improve its specificity.⁸⁹ Bone scintigraphy is also useful for diagnosis of complex regional pain syndrome (reflex sympathetic dystrophy),⁹⁰ occult fractures of the scaphoid,⁹¹ and metastatic disease.⁹² Newer modalities, such as the combination of scintigraphy with morphologic information, e.g., single-photon emission CT/CT can improve diagnostic yields in the extremity.⁹³




Fig. 3.42 This 23-year-old female had a previous excision of arteriovenous malformation more than 5 years ago and now presents with skin changes suggestive of recurrence. Magnetic resonance angiography delineates the palmar arch well and in addition shows blushes of bright signal intensity over the thumb pulp, the first web area, and over the index finger (**A**). This correlated well with the pigmented changes seen on the clinical photo (**B**).

Future directions – safety in fluoroscopy

Fluoroscopy is a powerful imaging tool allowing operative and dynamic assessment of the bones and joints of the hand. As the surgeon is often the operator of the machine, this causes exposure to both direct and scattered radiation. Such

radiation exposure is an occupational risk, with potential serious effects. There was a report suggesting an increased cancer risk in orthopedic surgeons working in an institution with poor compliance to use of radiation protective measures when working with standard c-arm devices.⁹⁴ Another study found a 1.9-fold increased prevalence of cancer and 2.9-fold increased prevalence of breast cancer in female orthopedic surgeons when compared with the women of similar age and race.⁹⁵

Radiation exposure is directly related to the distance from the X-ray source. This relationship is described by the inverse square law. In practical terms, a doubling of the distance from the source reduces the exposure 4 times. Conversely, a halving of the distance results in a four-fold increase in radiation exposure. Some basic knowledge and precautions will minimize radiation to the worker during its operation (**Box 3.5**).

The choice of fluoroscopy affects the potential radiation exposure. Compared to conventional fluoroscopy, mini c-arm fluoroscopy has been shown to emit about half the radiation exposure.⁹⁶ However, if the surgeon places his or her hand in the path of the X-ray beam during intraoperative use of the mini c-arm, there is a decreased source-to-skin distance resulting in higher radiation exposure to the hand than when using the standard c-arm.^{97,98} While the mini c-arm fluoroscopy has been widely adopted in hand surgery, we need to exercise caution during its use to ensure safety of both the surgeon and the patient. Technological advances will improve the resolution and utility of these devices, while aiming to mitigate radiation risks. In tandem, there should be more research into the long-term risks of exposure during use of such devices.

BOX 3.5 Methods to reduce radiation exposure

Increasing the distance between the personnel and the source of radiation is key, as it has been shown that the rate of radiation exposure drops significantly beyond the path of the radiation beam and is minimal beyond 15 cm from the point of focus on the image intensifier.⁹⁹

1. Increasing distance from radiation source
 - Placement of the limb directly on the image intensifier (when using mini C-arms)
 - Uninvolved personnel to position themselves away from the radiation source
2. Shielding
 - Lead gowns
 - Lead-lined operating rooms
 - Protective goggles
 - Radiation attenuation gloves for operators placing their hands near radiation source
 - Shielding for anaesthetists and patients
3. Minimizing radiation use
 - Increasing accuracy of fluoroscopy by using laser beams
 - Collimation
 - Avoiding long exposure time



Access the complete reference list online at <http://www.expertconsult.com>

3. Fisher MR, Rogers LF, Hendrix RW. Systematic approach to identifying fourth and fifth carpometacarpal joint dislocations. *AJR Am J Roentgenol.* 1983;140:319–324.
14. Salter RB, Harris R. Injuries involving the epiphyseal plate. *J Bone Joint Surg Am.* 1963;45:587–621. *This classic instructional lecture course provides an excellent overview of the growth plate, its injury patterns, mechanisms and prognosis, as well as radiographic features.*
17. Gilula LA. Carpal injuries: analytic approach and case exercises. *AJR Am J Roentgenol.* 1979;133:503–517.
32. Smith J, Finnoff JT. Diagnostic and interventional musculoskeletal ultrasound: part 1. Fundamentals. *PM R.* 2009;1:64–75. *The principles of medical ultrasonography as applied to the musculoskeletal system are covered in this first part of a two-part comprehensive review. Part 2 covers clinical applications of ultrasonography.*
48. Kaewlai R, Avery LL, Asrani AV, et al. Multidetector CT of carpal injuries: anatomy, fractures, and fracture-dislocations1. *Radiographics.* 2008;28:1771–1784.
57. Park MJ, Kim JP. Reliability and normal values of various computed tomography methods for quantifying distal radioulnar joint translation. *J Bone Joint Surg Am.* 2008;90:145–153.
64. Ergun T, Lakadamyali H, Derincek A, et al. Magnetic resonance imaging in the visualization of benign tumors and tumor-like lesions of hand and wrist. *Curr Probl Diagn Radiol.* 2010;39:1–16. *This review provides a practical approach to MR evaluation of benign tumors of the hand and wrist. A comprehensive list of conditions is covered, with descriptions and images of the MRI findings.*
70. Nakamura T, Yabe Y, Horiuchi Y. Fat suppression magnetic resonance imaging of the triangular fibrocartilage complex. Comparison with spin echo, gradient echo pulse sequences and histology. *J Hand Surg [Br].* 1999;24:22–26.
84. Stepansky F, Hecht EM, Rivera R, et al. Dynamic MR angiography of upper extremity vascular disease: pictorial review. *Radiographics.* 2008;28:e28. *MRA is rapidly becoming a viable alternative to digital subtraction angiography. This article reviews MRA techniques and protocols, and shows examples of upper extremity pathology diagnosed with MRA.*
87. Love C, Din AS, Tomas MB, et al. Radionuclide bone imaging: an illustrative review. *Radiographics.* 2003;23:341–358. *Bone scintigraphy is one of the most frequently performed radionuclide procedures. This article reviews the basic principles, protocols, normal findings, and applications of bone scintigraphy.*

References

- Sofka CM, Pavlov H. The history of clinical musculoskeletal radiology. *Radiol Clin North Am.* 2009;47:349–356.
- Peh WC. Modern imaging of the musculoskeletal system: is there still a role for radiography? *Singapore Med J.* 2002;43:385–386.
- Fisher MR, Rogers LF, Hendrix RW. Systematic approach to identifying fourth and fifth carpometacarpal joint dislocations. *AJR Am J Roentgenol.* 1983;140:319–324.
- Parkinson RW, Paton RW. Carpometacarpal dislocation: an aid to diagnosis. *Injury.* 1992;23:187–188.
- Gurland M. Carpometacarpal joint injuries of the fingers. *Hand Clin.* 1992;8:733–744.
- Chong AK, Chew WY. An isolated ring finger metacarpal shaft fracture? Beware an associated little finger carpometacarpal joint dislocation. *J Hand Surg [Br].* 2004;29:629–631.
- Lane CS. Detecting occult fractures of the metacarpal head: the Brewerton view. *J Hand Surg Am.* 1977;2:131–133.
- Eaton RG, Littler JW. Ligament reconstruction for the painful thumb carpometacarpal joint. *J Bone Joint Surg Am.* 1973;55:1655–1666.
- Heim D. The skier's thumb. *Acta Orthop Belg.* 1999;65:440–446.
- Ebrahim FS, De Maeseneer M, Jager T, et al. US Diagnosis of UCL tears of the thumb and Stener lesions: technique, pattern-based approach, and differential diagnosis. *Radiographics.* 2006;26:1007–1020.
- Hergan K, Mittler C, Oser W. Ulnar collateral ligament: differentiation of displaced and nondisplaced tears with US and MR imaging. *Radiology.* 1995;194:65–71.
- Gilsanz V, Ratib O. Indicators of skeletal maturity in children and adolescents. In: *Hand Bone Age.* New York: Springer-Verlag; 2005:9–16.
- Chew EM, Chong AKS. Hand fractures in children: epidemiology and misdiagnosis in a tertiary referral hospital. *J Hand Surg Am.* 2012;37A:1684–1688.
- Salter RB, Harris R. Injuries involving the epiphyseal plate. *J Bone Joint Surg Am.* 1963;45:587–621. *This classic instructional lecture course provides an excellent overview of the growth plate, its injury patterns, mechanisms and prognosis, as well as radiographic features.*
- Levis CM, Yang Z, Gilula LA. Validation of the extensor carpi ulnaris groove as a predictor for the recognition of standard posteroanterior radiographs of the wrist. *J Hand Surg Am.* 2002;27:252–257.
- Yang Z, Mann FA, Gilula LA, et al. Scaphopisocapitate alignment: criterion to establish a neutral lateral view of the wrist. *Radiology.* 1997;205:865–869.
- Gilula LA. Carpal injuries: analytic approach and case exercises. *AJR Am J Roentgenol.* 1979;133:503–517.
- Peh WC, Gilula LA. Normal disruption of carpal arcs. *J Hand Surg Am.* 1996;21:561–566.
- Bouman HW, Messer E, Sennwald G. Measurement of ulnar translation and carpal height. *J Hand Surg [Br].* 1994;19:325–329.
- McMurtry RY, Youm Y, Flatt AE, et al. Kinematics of the wrist. II. Clinical applications. *J Bone Joint Surg Am.* 1978;60:955–961.
- Kristensen SS, Thomassen E, Christensen F. Ulnar variance determination. *J Hand Surg [Br].* 1986;11:255–257.
- Palmer AK, Glisson RR, Werner FW. Ulnar variance determination. *J Hand Surg Am.* 1982;7:376–379.
- Steyers CM, Blair WF. Measuring ulnar variance: a comparison of techniques. *J Hand Surg Am.* 1989;14:607–612.
- Shin AY, Deitch MA, Sachar K, et al. Ulnar-sided wrist pain. Diagnosis and treatment. *J Bone Joint Surg Am.* 2004;86:1560–1574.
- Chung KC, Spilson SV. The frequency and epidemiology of hand and forearm fractures in the United States. *J Hand Surg Am.* 2001;26:908–915.
- Thomas AD, Greenberg JA. Use of fluoroscopy in determining screw overshoot in dorsal distal radius: a cadaveric study. *J Hand Surg Am.* 2009;34A:258–261.
- Maschke SD, Evans PJ, Schub D, et al. Radiographic evaluation of dorsal screw penetration after volar fixed-angle plating of the distal radius: a cadaveric study. *Hand.* 2007;2:144–150.
- Badman BL, Rill L, Butkovich B, et al. Radiation exposure with use of the mini-C-arm for routine orthopaedic imaging procedures. *J Bone Joint Surg Am.* 2005;87:13–17.
- Kwon BC, Baek GH. Fluoroscopic diagnosis of scapholunate interosseous ligament injuries in distal radius fractures. *Clin Orthop Relat Res.* 2008;466:969–976.
- Bain GL, Hunt J, Mehta JA. Operative fluoroscopy in hand and upper limb surgery. One hundred cases. *J Hand Surg [Br].* 1997;22:656–658.
- Wong DC, Wansaicheong GK, Tsou IY. Ultrasonography of the hand and wrist. *Singapore Med J.* 2009;50:219–225, quiz 226.
- Smith J, Finnoff JT. Diagnostic and interventional musculoskeletal ultrasound: part 1. Fundamentals. *PM R.* 2009;1:64–75. *The principles of medical ultrasonography as applied to the musculoskeletal system are covered in this first part of a two-part comprehensive review. Part 2 covers clinical applications of ultrasonography.*
- Smith J, Finnoff JT. Diagnostic and interventional musculoskeletal ultrasound: part 2. Clinical applications. *PM R.* 2009;1:162–177.
- Connolly DJA, Berman L, McNally EG. The use of beam angulation to overcome anisotropy when viewing human tendon with high frequency linear array ultrasound. *Br J Radiol.* 2001;74:183–185.
- Guerini H, Pessis E, Theumann N, et al. Sonographic appearance of trigger fingers. *J Ultrasound Med.* 2008;27:1407–1413.
- Diop AN, Ba-Diop S, Sane JC, et al. [Role of US in the management of de Quervain's tenosynovitis: review of 22 cases.]. *J Radiol.* 2008;89:1081–1084.
- Bodor M, Flossman T. Ultrasound-guided first annular pulley injection for trigger finger. *J Ultrasound Med.* 2009;28:737–743.
- Kuo LC, Su FC, Tung WL, et al. Kinematical and functional improvements of trigger digits after sonographically assisted percutaneous release of the A1 pulley. *J Orthop Res.* 2009;27:891–896.
- Renoux J, Zeitoun-Eiss D, Brasseur J-L. Ultrasonographic study of wrist ligaments: review and new perspectives. *Semin Musculoskelet Radiol.* 2009;13:55–65.
- Keogh CF, Wong AD, Wells NJ, et al. High-resolution sonography of the triangular fibrocartilage: initial experience and correlation with MRI and arthroscopic findings. *AJR Am J Roentgenol.* 2004;182:333–336.
- Beekman R, Visser LH. Sonography in the diagnosis of carpal tunnel syndrome: a critical review of the literature. *Muscle Nerve.* 2003;27:26–33.
- Brookes-Fazakerley S, Kumar A, Oakley J. Survey of the initial management and imaging protocols for occult scaphoid fractures in UK hospitals. *Skeletal Radiol.* 2009;38:1045–1048.
- Memarsadeghi M, Breitenseher MJ, Schaefer-Prokop C, et al. Occult scaphoid fractures: comparison of multidetector ct and mr imaging: initial experience. *Radiology.* 2006;240:169–176.
- Dias JJ. Definition of union after acute fracture and surgery for fracture nonunion of the scaphoid. *J Hand Surg Br.* 2001;26:321–325.
- Dias J, Taylor M, Thompson J, et al. Radiographic signs of union of scaphoid fractures. An analysis of inter-observer agreement and reproducibility. *J Bone Joint Surg Br.* 1988;70-B:299–301.
- Sanders WE. Evaluation of the humpback scaphoid by computed tomography in the longitudinal axial plane of the scaphoid. *J Hand Surg Am.* 1988;13:182–187.
- Lozano-Calderon S, Blazar P, Zurakowski D, et al. Diagnosis of scaphoid fracture displacement with radiography and computed tomography. *J Bone Joint Surg Am.* 2006;88:2695–2703.
- Kaewlai R, Avery LL, Asrani AV, et al. Multidetector CT of carpal injuries: anatomy, fractures, and fracture-dislocations. *Radiographics.* 2008;28:1771–1784.
- Cole RJ, Bindra RR, Evanoff BA, et al. Radiographic evaluation of osseous displacement following intra-articular fractures of the distal radius: reliability of plain radiography versus computed tomography. *J Hand Surg Am.* 1997;22:792–800.

50. Slagel BE, Luenam S, Pichora DR. Management of post-traumatic malunion of fractures of the distal radius. *Hand Clin.* 2010;26:71–84.
51. Athwal GS, Ellis RE, Small CF, et al. Computer-assisted distal radius osteotomy. *J Hand Surg Am.* 2003;28:951–958.
52. Murase T, Oka K, Moritomo H, et al. Three-dimensional corrective osteotomy of malunited fractures of the upper extremity with use of a computer simulation system. *J Bone Joint Surg Am.* 2008;90:2375–2389.
53. Mino DE, Palmer AK, Levinsohn EM. The role of radiography and computerized tomography in the diagnosis of subluxation and dislocation of the distal radioulnar joint. *J Hand Surg Am.* 1983;8:23–31.
54. Mino DE, Palmer AK, Levinsohn EM. Radiography and computerized tomography in the diagnosis of incongruity of the distal radio-ulnar joint. A prospective study. *J Bone Joint Surg Am.* 1985;67:247–252.
55. Wechsler RJ, Wehbe MA, Rifkin MD, et al. Computed tomography diagnosis of distal radioulnar subluxation. *Skeletal Radiol.* 1987;16:1–5.
56. Lo IK, MacDermid JC, Bennett JD, et al. The radioulnar ratio: a new method of quantifying distal radioulnar joint subluxation. *J Hand Surg Am.* 2001;26:236–243.
57. Park MJ, Kim JP. Reliability and normal values of various computed tomography methods for quantifying distal radioulnar joint translation. *J Bone Joint Surg Am.* 2008;90:145–153.
58. Assoun J, Richardi G, Railhac JJ, et al. Osteoid osteoma: MR imaging versus CT. *Radiology.* 1994;191:217–223.
59. Barrett JF, Keat N. Artifacts in CT: recognition and avoidance. *Radiographics.* 2004;24:1679–1691.
60. Pretorius ES, Fishman EK. Volume-rendered Three-dimensional spiral CT: musculoskeletal applications. *Radiographics.* 1999;19:1143–1160.
61. Capelastegui A, Astigarraga E, Fernandez-Canton G, et al. Masses and pseudomasses of the hand and wrist: MR findings in 134 cases. *Skeletal Radiol.* 1999;28:498–507.
62. Peh WC, Truong NP, Totty WG, et al. Pictorial review: magnetic resonance imaging of benign soft tissue masses of the hand and wrist. *Clin Radiol.* 1995;50:519–525.
63. Teh J, Whiteley G. MRI of soft tissue masses of the hand and wrist. *Br J Radiol.* 2007;80:47–63.
64. Ergun T, Lakadamyali H, Derincek A, et al. Magnetic resonance imaging in the visualization of benign tumors and tumor-like lesions of hand and wrist. *Curr Probl Diagn Radiol.* 2010;39:1–16. *This review provides a practical approach to MR evaluation of benign tumors of the hand and wrist. A comprehensive list of conditions is covered, with descriptions and images of the MRI findings.*
65. Amrami KK. Radiology corner: diagnosing radiographically occult scaphoid fractures – what's the best second test? *J Am Soc Surg Hand.* 2005;5:134–138.
66. Jenkins PJ, Slade K, Huntley JS, et al. A comparative analysis of the accuracy, diagnostic uncertainty and cost of imaging modalities in suspected scaphoid fractures. *Injury.* 2008;39:768–774.
67. Peh WC, Gilula LA, Wilson AJ. Detection of occult wrist fractures by magnetic resonance imaging. *Clin Radiol.* 1996;51:285–292.
68. Steinbach LS, Smith DK. MRI of the wrist. *Clin Imaging.* 2000;24:298–322.
69. Stener B. Displacement of the ruptured ulnar collateral ligament of the metacarpo-phalangeal joint of the thumb. *J Bone Joint Surg Br.* 1962;44-B:869–879.
70. Nakamura T, Yabe Y, Horiuchi Y. Fat suppression magnetic resonance imaging of the triangular fibrocartilage complex. Comparison with spin echo, gradient echo pulse sequences and histology. *J Hand Surg [Br].* 1999;24:22–26.
71. Anderson ML, Skinner JA, Felmlee JP, et al. Diagnostic comparison of 1.5 Tesla and 3.0 Tesla preoperative MRI of the wrist in patients with ulnar-sided wrist pain. *J Hand Surg Am.* 2008;33:1153–1159.
72. Magee T. Comparison of 3-T MRI and arthroscopy of intrinsic wrist ligament and TFCC tears. *AJR Am J Roentgenol.* 2009;192:80–85.
73. Karantanis A, Dailiana Z, Malizos K. The role of MR imaging in scaphoid disorders. *Eur Radiol.* 2007;17:2860–2871.
74. Gelberman RH, Gross MS. The vascularity of the wrist. Identification of arterial patterns at risk. *Clin Orthop Relat Res.* 1986;202:40–49.
75. Sowa DT, Holder LE, Patt PG, et al. Application of magnetic resonance imaging to ischemic necrosis of the lunate. *J Hand Surg Am.* 1989;14:1008–1016.
76. McDonald EJ Jr, Goodman PC, Winestock DP. The clinical indications for arteriography in trauma to the extremity. A review of 114 cases. *Radiology.* 1975;116:45–47.
77. Rieger M, Mallouhi A, Tauscher T, et al. Traumatic arterial injuries of the extremities: initial evaluation with MDCT angiography. *AJR Am J Roentgenol.* 2006;186:656–664.
78. McCorkell S, Harley J, Morishima M, et al. Indications for angiography in extremity trauma. *AJR Am J Roentgenol.* 1985;145:1245–1247.
79. Shah N, Anderson SW, Vu M, et al. Extremity CT angiography: application to trauma using 64-MDCT. *Emerg Radiol.* 2009;16:425–432.
80. Fishman EK, Horton KM, Johnson PT. Multidetector CT and Three-dimensional CT Angiography for Suspected Vascular Trauma of the Extremities. *Radiographics.* 2008;28:653–665.
81. Miller-Thomas MM, West OC, Cohen AM. Diagnosing traumatic arterial injury in the extremities with CT angiography: pearls and pitfalls. *Radiographics.* 2005;25(suppl 1):S133–S142.
82. Hsu CS, Hellinger JC, Rubin GD, et al. CT angiography in pediatric extremity trauma: preoperative evaluation prior to reconstructive surgery. *Hand (N Y).* 2008;3:139–145.
83. Soto JA, Mañera F, Morales C, et al. Focal arterial injuries of the proximal extremities: helical CT arteriography as the initial method of diagnosis. *Radiology.* 2001;218:188–194.
84. Stepansky F, Hecht EM, Rivera R, et al. Dynamic MR angiography of upper extremity vascular disease: pictorial review. *Radiographics.* 2008;28:e28. *MRA is rapidly becoming a viable alternative to digital subtraction angiography. This article reviews MRA techniques and protocols, and shows examples of upper extremity pathology diagnosed with MRA.*
85. Connell DA, Koulouris G, Thorn DA, et al. Contrast-enhanced MR angiography of the hand. *Radiographics.* 2002;22:583–599.
86. Epstein RE, Dalinka MK. Magnetic resonance imaging of the hand and wrist. *Operative Techniques Sports Med.* 1997;5:37–49.
87. Love C, Din AS, Tomas MB, et al. Radionuclide bone imaging: an illustrative review. *Radiographics.* 2003;23:341–358. *Bone scintigraphy is one of the most frequently performed radionuclide procedures. This article reviews the basic principles, protocols, normal findings, and applications of bone scintigraphy.*
88. Palestro CJ, Love C, Schneider R. The evolution of nuclear medicine and the musculoskeletal system. *Radiol Clin North Am.* 2009;47:505–532.
89. Palestro CJ, Torres MA. Radionuclide imaging in orthopedic infections. *Semin Nucl Med.* 1997;27:334–345.
90. Wuppenhorst N, Maier C, Frettlow J, et al. Sensitivity and specificity of 3-phase bone scintigraphy in the diagnosis of complex regional pain syndrome of the upper extremity. *Clin J Pain.* 2010;26:182–189.
91. Beeres FJ, Rhemrev SJ, den Hollander P, et al. Early magnetic resonance imaging compared with bone scintigraphy in suspected scaphoid fractures. *J Bone Joint Surg Br.* 2008;90:1205–1209.
92. Hage WD, Aboulafia AJ, Aboulafia DM. Incidence, location, and diagnostic evaluation of metastatic bone disease. *Orthop Clin North Am.* 2000;31:515–528, vii.
93. Linke R, Kuwert T, Uder M, et al. Skeletal SPECT/CT of the peripheral extremities. *AJR Am J Roentgenol.* 2010;194:W329–W335.
94. Mastrangelo G, Fedeli U, Fadda E, et al. Increased cancer risk among surgeons in an orthopaedic hospital. *Occup Med.* 2005;55:498–500.
95. Chou LB, Cox CA, Tung JJ, et al. Prevalence of cancer in female orthopaedic surgeons in the United States. *J Bone Joint Surg Am.* 2010;92:240–244.

96. Athwal GS, Bueno RA Jr, Wolfe SW. Radiation exposure in hand surgery: mini versus standard C-arm. *J Hand Surg Am.* 2005;30:1310–1316.
97. Vosbikian MM, Ilyas AM, Watson DD, Leinberry CF. Radiation exposure to hand surgeons' hands: a practical comparison of large and mini C-arm fluoroscopy. *J Hand Surg Am.* 2014;39:1805–1809.
98. Singer G, Herron B, Herron D. Exposure from the large C-arm versus the mini C-arm using hand/wrist and elbow phantoms. *J Hand Surg Am.* 2011;36:628–631.
99. Giordana BD, Ryder S, Baumhauer JF, DiGiovanni BF. Exposure to direct and scatter radiation with use of mini c-arm fluoroscopy. *J Bone Joint Surg Am.* 2007;89:948–952.

4

Anesthesia for upper extremity surgery

Jonay Hill, Vanila M. Singh, and Subhro K. Sen

 Access video content for this chapter online at expertconsult.com

SYNOPSIS

- Optimal perioperative anesthetic outcomes are achieved by a thorough understanding of anatomy, pharmacology, techniques, and potential complications.
- Local anesthetics (LA) make regional anesthesia possible by preventing the propagation of nerve conduction and by inhibiting or relieving pain.
- Ultrasound guidance in the use of regional anesthesia has decreased the need for high volumes of anesthetic.

Introduction

The goal of anesthesia for hand and upper extremity procedures is to provide a comfortable and safe experience for the patient during surgery. Many options are available for anesthesia, with respective benefits and risks. The decision regarding which anesthetic technique is chosen depends on various factors, including the extent, site, and expected duration of surgery; need for sedation; general medical health of the patient, and personal preference.

General anesthesia techniques can be applied for hand and upper extremity procedures the same as for procedures elsewhere. In addition, regional anesthesia techniques can be applied for procedures involving the upper extremity when used in the proper setting and patient population. Adjunctive measures are used to augment local anesthetics to provide longer duration of action, lower risk of adverse systemic effects, and less bleeding at the surgical site.

Optimal perioperative anesthetic outcomes are achieved by a thorough understanding of anatomy, pharmacology, techniques, potential complications, and general pain management.

Anatomy

The brachial plexus arises from the ventral rami of nerves C5–8 and T1, with variable contributions from C4 and T2 (Fig. 4.1). These rami unite and diverge forming the roots,

trunks, divisions, cords, and terminal nerves of the brachial plexus. C5 and C6 roots form the superior trunk, C7 becomes the middle trunk, and C8 and T1 form the inferior trunk between the anterior and middle scalene muscles. The three trunks then divide into anterior and posterior divisions, coursing over the first rib and lateral to the subclavian artery. The divisions then reunite to form cords. The anterior divisions of the superior and middle trunk form the lateral cord, while the anterior division of the inferior trunk forms the medial cord. The posterior divisions of all three trunks form the posterior cord. The cords are named according to their anatomic relationship with the axillary artery. The cords then divide once again to become the terminal branches of the brachial plexus. The lateral cord gives rise to the musculocutaneous nerve and contributes to the median nerve. The medial cord also contributes to the median nerve and gives rise to the ulnar nerve and the medial brachial and antebrachial cutaneous nerves. The posterior cord becomes the axillary and radial nerves.¹

Additional nerves outside the brachial plexus can be important for complete anesthesia of the upper extremity. The supraclavicular nerve (C3–4) provides sensory innervation to the “cape” of the shoulder, and the intercostobrachial nerve (T2) innervates the skin of the medial upper arm and axilla.

Knowledge of brachial plexus anatomy and the dermatomes supplied (Figs. 4.2 & 4.3) enables selective regional anesthesia.

Perineurial environment

The axillary sheath is the connective tissue surrounding the neurovascular structures of the brachial plexus. It originates as a continuation of the prevertebral fascia and joins the fascia of the biceps and brachialis muscles distally. This connective tissue extends inward, forming septa between components of the plexus and creating fascial compartments for each nerve.² Controversy exists regarding the ability of the septa to limit the spread of local anesthetics within the sheath. Some investigators report that these fascial compartments limit the




Fig. 4.1 Brachial plexus anatomy.




Fig. 4.2 Upper extremity nerve innervation (arm pronated).




Fig. 4.3 Upper extremity nerve innervation (arm supinated).

circumferential spread of local anesthetics and that injected solutions spread longitudinally up and down the nerve and remain compartmentalized. This concept provides a rational explanation for the occurrence of a rapid and profound block of one nerve, yet partial or absent block in other nerves during brachial plexus blockade.³ Other investigators propose that these septa are incomplete and form small bubble-like pockets when solution is injected. They found that single injections of dye solutions into the axillary sheath resulted in immediate staining of median, radial, and ulnar nerves, despite the presence of septa. These data demonstrate that there are connections between compartments within the sheath, and may explain why single injection techniques have success rates comparable with multiple injection techniques during blockade of the brachial plexus.⁴

Microneuroanatomy

Peripheral nerves are composed of fascicles of individual nerve fibers surrounded by endoneurium. Groups of fascicles are contained within the epineurium. As the nerve travels away from the spinal cord, fascicle numbers increase, while fascicle size decreases.⁵ The nerve roots contain large fascicles, demonstrating a monofascicular or oligofascicular pattern, while a multifascicular pattern is found more distally.^{6,7} While the amount of neural tissue remains constant, the amount of non-neural connective tissue increases from proximal to distal. The ratio of neural to non-neural tissue changes from 1:1 in the proximal plexus to 1:2 in the more distal plexus.^{2,7} The presence of non-neural tissue may explain why injections within the epineurium rarely result in neural injury.⁶

Sonoanatomy

The shape and echogenicity of a nerve determine its ultrasound appearance. Structures that strongly reflect ultrasound waves generate large signal intensities and appear white or hyperechoic. In contrast, hypoechoic structures weakly reflect ultrasound waves and appear darker.⁸ Peripheral nerves show a mixture of hypoechoic and hyperechoic structures constituting a typical “honeycomb” structure.⁹ Hypoechoic structures seen with ultrasound correspond to neural tissue, while hyperechoic areas correlate with connective tissue.¹⁰ Ultrasound imaging of the proximal brachial plexus usually shows hypoechoic structures reflecting an oligofascicular pattern. Distal brachial plexus structures display a more hyperechoic, honeycomb appearance, reflecting a multifascicular pattern.⁷

Pharmacology of local anesthetics

Local anesthetics (LA) make regional anesthesia possible by preventing the propagation of nerve conduction and inhibiting or relieving pain.¹¹ LA are primarily weak bases that attach to sites of the sodium channel in nerves and prevent the movement of the sodium ion through the nerve pores, which temporarily halts nerve conduction.¹²

Local anesthetics are classified as amides or esters, based on the chemical structure. Most local anesthetics used in regional anesthesia are amides (e.g., “-caines”). The structure of a typical local anesthetic consists of a lipophilic head, a

hydrophilic tail, and a chain linking the head and tail which is either an amide or ester and determines the classification of the type of LA. Alteration of the structure of the LA affects the various actions of the LA itself and is important when making the choice of which LA to use. For example, increasing the alkyl substitution on the aromatic ring increases its lipid solubility, thereby increasing its potency. Allergic reactions to local anesthetics are more common with esters and rare with amides.

Pharmacokinetics

Local anesthetics differ from other drugs because they are directly delivered at their site of action. Efficacy depends on the amount of LA that reaches the nerve and proximity to the nerve. Diffusion of local anesthetic is dependent on the amount of connective tissue and adipose tissue that is present in the area of the block.

Toxicity

Local anesthetic toxicity has been a concern since its first use in nerve blockade. Regardless of which local anesthetic is injected, traditional methods have required large volumes for successful regional anesthesia such as with brachial plexus blockade or Bier blocks. Frequent aspiration and incremental dosing are imperative, as is communication with the patient to detect early signs of potential intravenous injection before progression to signs and symptoms of toxicity. Factors such as drug dose, rate of absorption, biotransformation, and elimination of the drug from the circulation are determinants of the plasma concentration of local anesthetics. Fortunately, one of the benefits of ultrasound guidance in the use of regional anesthesia has been the decreased need for large volumes.¹³

High plasma levels may be a consequence of direct intravascular injection, plasma absorption, and/or certain underlying medical conditions of the patient (i.e., hypoproteinemia in renal or hepatic disease). Elevated intravascular levels of LA may result in minor CNS symptoms such as dizziness, ringing in the ears, and may proceed to more intense symptoms of loss of consciousness, and seizures. At even higher levels, cardiac arrhythmias ensue, including complete cardiovascular collapse. Use of LA in regional anesthesia demands an appreciation of these toxicities. Understanding agent-specific toxic levels is vital – as much as the preparation for these unintended events.

Adjuncts such as epinephrine affect absorption and elimination. The use of epinephrine as a marker of intravascular injection is warranted in almost all situations. Exceptions include those cases where the vasoconstriction resulting from epinephrine may in fact compromise the blood flow to the area.

Physicians must be prepared with monitors, emergency drugs, and airway supplies to facilitate treatment of LA-related toxicity. Toxicity related to LA can include but is not limited to oxygen desaturation, hypotension, bradycardia, and seizures. The extent of toxicity is determined by the specific drug's intrinsic properties as well as the plasma level of the LA. The safety of LA is an essential aspect of regional anesthesia and is dependent on the skill of the physician, placement of the needle, the drug utilized, and patient health. All

of these factors must be considered when determining the appropriate procedure and LA dose.¹⁴

Bupivacaine has been in use for many years and has the highest cardiotoxicity potential due to its intrinsic properties. Although the cardiac system is generally resistant to the effects of LA, bupivacaine is the notable exception. An overdose is more likely to result in cardiovascular collapse compared with other LA. This cardiac collapse is difficult to treat traditionally with ACLS/CPR alone. Recent case studies have demonstrated that IV infusion of Intralipid, an emulsified fat, may be successful in ameliorating cardiotoxicity associated with local anesthetics by acting as a “sink”.

Vasoconstrictors

With the addition of vasoconstrictors such as epinephrine or phenylephrine to the LA anesthetic solution, the systemic absorption rate of an LA can be decreased.¹⁴ The dose of bupivacaine increases from 3.5 to 4.0 mg/kg. This action of epinephrine is more significant with lidocaine as the upper limit increases from 3.0 to 7.0 mg/kg. Vasoconstrictors allow the physician to identify an intravascular injection sooner rather than later, due to the development of tachycardia with an intravascular injection.¹⁵ The block can be halted immediately, possibly preventing a more serious intravascular complication. Vasoconstrictors result in decreased plasma uptake and increased duration of local anesthetic effect.¹⁶

LA selection

The choice of a LA depends on toxicity (as discussed previously), duration of effect, and time to onset (Table 4.1).

Duration is important when considering surgical times when the block is the primary anesthetic. In such instances, the longer-acting agents such as ropivacaine or bupivacaine

have the distinct advantage as they often can outlast the surgery and offer the greater benefits of postoperative pain management.

Time to onset is also an important factor. Most of the time, regional anesthesia is done prior to the surgery and a fast time to onset is highly desirable. Each LA has its own time to onset or latency. Various factors can shorten this latency, including the addition of bicarbonate, higher dose, and needle location. The recent use of ultrasound allows for a more precise needle placement, which in turn allows for quicker onset.

The choice of local anesthetic affects the quality of the block, time to onset, and duration of action (Table 4.2).¹⁵ Quicker onset generally leads to quicker clearance. Lidocaine and mepivacaine, agents with intermediate duration, have a short latency period which is further shortened by the addition of bicarbonate as mentioned above. In comparison, bupivacaine and ropivacaine, two long-acting agents used commonly in regional anesthesia, have a longer latency period, and are not able to mix with bicarbonate due to precipitation concerns. Some may consider mixing two agents together to achieve the quicker onset effect and the longer duration of anesthesia/analgesia. These mixtures can be about 50:50; however, it can vary depending on the experience and training of the anesthesiologist. The toxicity of mixtures are additive and the mixture does not lower the overall toxicity.¹⁷

Another consideration is the differential blockade, as nerves are blocked unequally and at different rates. Nerve blockade proceeds in the following order: sympathetic nerves, pin-prick sensation, touch, temperature, and finally motor.¹⁸ This is an important attribute of bupivacaine, as one can provide improved analgesia without much motor blockade in the postoperative period if an infusion is run at analgesic doses. Optimally, an LA with sensory selectivity is desired.

Table 4.1 Commonly used agents in upper extremity regional anesthesia

Lidocaine	Most widely used local anesthetic Prototype amide Can be used in almost any peripheral block 1.5% or 2% with or without epinephrine is most commonly used for surgical anesthesia
Mepivacaine	Intermediate duration Similar to lidocaine Less vasodilation Ineffective as topical agent 1.5% mepivacaine is the most commonly used agent in regional anesthesia
Bupivacaine	One of the most commonly used local anesthetics in regional and infiltration anesthesia Long-acting High quality sensory anesthesia relative to motor blockade Most commonly used for epidural and spinal Refractory cardiac arrest with 0.75% concentration. Interaction with cardiac Na ⁺ channels “fast in, slow out” Disruption of atrioventricular nodal conduction Depression of myocardial contractility Indirect effects mediated by CNS Limitations on total dose of bupivacaine given
Ropivacaine	Developed due to cardiotoxicity related to bupivacaine Long-acting Slightly less potent than bupivacaine Higher concentrations fastens its onset and density of block Reduced CNS/CV toxicity compared to bupivacaine

Table 4.2 Comparative pharmacology and current use of local anesthetics

Classification and compounds	pKa	Non-ionized (%) at pH 7.4	Potency ^a	Max. dose (mg) for infiltration ^b	Duration after infiltration (min)	Topical	Infiltration	Intravenous regional	Peripheral block	Epidural	Spinal ^c
Esters											
Procaine	8.9	3	1	500	45–60	No	Yes	No	Yes	No	Yes
Chlorprocaine	8.7	5	2	600	30–60	No	Yes	No	Yes	Yes	Yes (?)
Tetracaine	8.5	7	8	–	–	Yes	No	No	No	No	Yes
Amides											
Lidocaine	7.9	24	2	300	60–120	Yes	Yes	Yes	Yes	Yes	Yes (?)
Mepivacaine	7.6	39	2	300	90–180	No	Yes	No	Yes	Yes	Yes (?)
Prilocaine	7.9	24	2	400	60–120	No	Yes	Yes	Yes	Yes	Yes (?)
Bupivacaine, levobupivacaine	8.1	17	8	150	240–480	No	Yes	No	Yes	Yes	Yes
Ropivacaine	8.1	17	6	200	240–480	No	Yes	No	Yes	Yes	Yes

^aRelative potencies vary based on experimental model or route of administration.^bDosage should take into account the site of injection, use of a vasoconstrictor, and patient-related factors.^cUse of lidocaine, mepivacaine, prilocaine, and chlorprocaine for spinal anesthesia is controversial and evolving (see text).

Regional anesthesia techniques

Regional anesthesia has been shown to be an excellent anesthetic modality for upper extremity surgery. This relates to long-lasting pain relief, reduced opioid-related side effects during the first 24 hours after surgery, and expedited hospital discharge.^{2,19} Despite this, many patients still receive other types of anesthesia for a variety of reasons. Alternatives to regional anesthesia include general anesthesia, monitored anesthetic care (MAC), Bier block or simple local anesthetic infiltration without blockade of the brachial plexus. The factors involved in determining suitability of an anesthetic include patient preference, surgeon preference, relative and absolute contraindications to regional anesthesia, as well as type of surgery. General anesthesia has been utilized for many years with a safety record that has improved significantly over the past decades.²⁰ Due to respiratory depression, general anesthesia requires airway management not routine in regional anesthesia, local anesthesia or in monitored anesthetic care. Additionally, patients who undergo general anesthesia may experience hemodynamic variations that may be significant in those with cardiac disease. All patients who will undergo any type of anesthesia need to have standard ASA monitors, which include pulse oximetry, blood pressure monitoring, and electrocardiogram monitoring as well as intravascular access established in the non-operative limb.

The use of ultrasound-guided blocks has gained significant momentum in the last decade. The benefits of ultrasound include shortened time to onset, enhanced visualization of the nerve target and surrounding structures such as arteries, veins, muscle, and other soft tissues, needle visualization, visualization of the local anesthetic and its spread, anomalies of anatomy.²¹ Combining the traditional technique of peripheral nerve stimulation with ultrasound has not demonstrated notable benefits, although that has been a common practice, particularly for difficult cases. Surprisingly, there have been no studies that demonstrate improved safety with ultrasound over the technique of peripheral nerve stimulation.^{22,23}

Digital block

Digital nerve blockade is easy to perform and provides useful anesthesia for a variety of surgical procedures or injuries isolated to a digit. Many techniques for performing digital nerve blocks have been described. These techniques rely on anesthesia of the volar common digital nerves derived from the median and ulnar nerves as well as the dorsal digital branches of the radial nerve.

The authors' preferred technique for digital blockade involves volar and dorsal injections. The hand is placed palm up and the skin is cleansed. Using a small needle, 5 mL of local anesthetic such as 1% lidocaine or 0.25% bupivacaine is injected into the subdermal space directly overlying the A1 pulley of the involved finger. A wheal is slowly raised. The hand is then turned palm down and an additional 2–3 mL of local anesthetic is injected into the subcutaneous tissue over the dorsum of the finger, just distal to the metacarpophalangeal joint.

The use of epinephrine in digital blocks was, in the past, a controversial subject. Despite the admonition against

epinephrine use in numerous medical textbooks, no case of digital gangrene has been reported in the literature resulting solely from the use of epinephrine with a local anesthetic. A number of studies have demonstrated epinephrine can be safely used as an adjunct for digital block anesthesia. A randomized, prospective, blinded study with over 3000 consecutive cases showed no cases of infarction, necrosis or tissue loss.²⁴ Epinephrine can be added to local anesthetics to lengthen the duration of action, lessen bleeding, reduce the need for a tourniquet, and reduce the risk of adverse systemic effects.²⁵

Clinical tip: injection technique

Use a small needle such as 27- or 30-gauge and a slow injection technique to deliver the local anesthetic. Smaller needle size with gentle insertion have been shown to result in less painful injections.²⁶

Wrist block

When the entire hand requires anesthesia, a wrist block is appropriate. A wrist block is the technique of blocking the median, ulnar and radial nerves at the level of the wrist. Similar to the digital block, it is easy to perform, has minimal complications, and is highly effective.

The patient should be supine with the arm abducted and wrist in slight dorsiflexion. The median nerve is located between the tendons of the palmaris longus (PL) and the flexor carpi radialis (FCR). The palmaris longus tendon is usually the more prominent of the two; the median nerve passes just radial to it. The ulnar nerve passes between the ulnar artery and tendon of the flexor carpi ulnaris (FCU). The tendon of the flexor carpi ulnaris is superficial to the ulnar nerve. The superficial branch of the radial nerve runs along the medial aspect of the brachioradialis muscle. It then passes between the tendon of the brachioradialis and radius to pierce the fascia on the dorsal aspect. Just above the radial styloid process, it gives digital branches for the dorsal skin of the thumb, index finger, and lateral half of the middle finger.

The median nerve is blocked by inserting a 25-gauge needle between the tendons of the palmaris longus and flexor carpi radialis at a 30° angle. The needle is inserted until it pierces the deep fascia. Piercing of the deep fascia may be appreciated with a fascial "click". Local anesthetic, 3–5 mL, is injected. There should be no resistance to the injection as the local anesthetic travels up and down the carpal tunnel.

The ulnar nerve is anesthetized by transversely inserting the needle under the tendon of the FCU muscle close to its distal attachment proximal to the ulnar styloid. The needle is advanced 5–10 mm past the FCU tendon. The syringe is aspirated to confirm that it is not intravascular in the ulnar artery. Local anesthetic solution, 3–5 mL, is then injected. A subcutaneous injection of 2–3 mL of local anesthesia just above the tendon of the FCU is also advisable in blocking the cutaneous branches of the ulnar nerve.

The radial nerve is essentially anesthetized with a field block. This blockade requires a more extensive infiltration because of the less predictable anatomic location and division into multiple, smaller, cutaneous branches. Local anesthetic, 5 mL, is injected subcutaneously just above the radial styloid,

aiming medially. The infiltration is then extended laterally, using an additional 5 mL of local anesthetic.

Intravenous regional anesthesia (Bier block)

A Bier block is indicated for brief surgery of the hand or forearm (up to 1 h). This technique relies on diffusion of local anesthetic from the venous system to nearby nerves. The operative extremity is exsanguinated using an Esmarch bandage. A double tourniquet is inflated sequentially from distal to proximal. The distal tourniquet is then deflated to allow local anesthetic to penetrate that area. Local anesthetic solution is then injected through a small IV catheter placed in the hand of the arm to be anesthetized. A total of 50 mL of 0.5% lidocaine is commonly used. Of note, the patient should have a separate IV on the nonoperative limb to be available for sedation and/or emergency access. Anesthesia onset is within minutes. Patients may complain of tourniquet pain after 30 min, at which time the distal cuff is inflated and the proximal cuff is released. At the conclusion of surgery, the tourniquet is deflated, and there is a rapid resolution of anesthesia. To prevent local anesthetic toxicity, the tourniquet should not be deflated before 30 min have elapsed after drug infusion. Advantages of a Bier block include its safety profile, simplicity and reliability. However, its use is limited to short procedures due to tourniquet discomfort, and it offers no postoperative analgesia.

Interscalene block

Indications for an interscalene block include surgery of the shoulder, distal clavicle, acromioclavicular joint, and proximal humerus. The block is performed at the level of C5–C7 nerve roots, providing anesthesia to the shoulder and upper arm. Proximal spread of local anesthetic to C3–4 will also anesthetize the cape of the shoulder. Ulnar nerve distribution is usually spared with this technique. The nerve roots lie in a groove between the anterior and middle scalene muscles, posterolateral to the sternocleidomastoid muscle and phrenic nerve.

To perform the block, the patient is placed in a semi-recumbent position. When using the nerve stimulation technique, the interscalene groove is palpated at the level of C6 and the needle is advanced in a slight posterocaudal direction. A twitch of the bicep, tricep, or distal muscle is sought. When using ultrasound, the C5–7 roots form a characteristic “stoplight” appearance as they lie sequentially between the scalene muscles. The nerves are identified, and local anesthetic is deposited circumferentially around the nerves (Fig. 4.4).

Complications and side effects specific to this block are ipsilateral phrenic nerve palsy, Horner’s syndrome, hoarseness from blockade of the recurrent laryngeal nerve, and vascular puncture or injection; the carotid artery, internal and external jugular veins, and vertebral artery are in close proximity to the nerves of interest.

Supraclavicular block

The supraclavicular approach to the brachial plexus provides more reliable and effective regional anesthesia to the upper extremity than other approaches.²⁷ Indications for the supraclavicular approach include surgery of the upper extremity including the arm, elbow, and hand. Though the

supraclavicular block can also be used for shoulder surgery, it may require some supplementation of the supraclavicular nerve (C3–C4).²

With ultrasound assistance, it is easy to appreciate the continuum that exists within the brachial plexus. Moving the ultrasound probe up or down, the brachial plexus will change a block from an interscalene block to a supraclavicular block. With the gain in popularity with ultrasound, there has been a resurgence in the supraclavicular block as the concerns of pneumothorax have diminished. In a recent study of 510 patients who underwent ultrasound-guided supraclavicular blocks, none were found to have a pneumothorax.²⁸

The supraclavicular block is performed with the probe placed in the supraclavicular fossa (Video 4.1 ). The sonoanatomy includes the subclavian artery, which is the primary landmark in this block. The brachial plexus (trunks and/or divisions of the plexus) lies superior (posterior) and lateral to the artery in a majority of patients and appears as a “bunch of grapes” or several round structures with a dark interior (hypoechoic) and a bright outline (hyperechoic outer circle). Once an adequate view is identified, the area is prepped and draped in a sterile fashion. The needle is then aligned with the probe in what is referred to as an “in-plane” technique. The needle appears on screen to move in a lateral to medial fashion. Once the needle is seen, placement should be carefully done with frequent aspiration. It may take 2–3 needle placements to ensure adequate coverage of the brachial plexus (Fig. 4.5).

The most common side effects include hemi-diaphragmatic paresis secondary to phrenic nerve block, ipsilateral Horner’s syndrome, and ipsilateral nasal congestion. Other risks include infection, bleeding, nerve injury, and pneumothorax.

Nerve stimulation technique of the supraclavicular block is less frequently performed due to the concerns and risk of pneumothorax. There are other suitable alternatives if the ultrasound view is difficult to obtain.

Infraclavicular block

Indications for an infraclavicular block are the same as for the supraclavicular approach. The main difference is that the infraclavicular approach generally preserves pulmonary function by avoiding a block of the diaphragm, which is possible with the supraclavicular approach. The infraclavicular approach is a block of the brachial plexus at the level of the lateral, medial and posterior cords. These cords are named for their relationship to the axillary artery, although this relationship can have many variations.²⁹ In the United States, the most common approach for the infraclavicular block is using the coracoid process as a landmark, both with ultrasound guidance, as well as with peripheral nerve stimulation. Ultrasound-guided infraclavicular blocks are performed with the probe placed just medial to the coracoid process and below the clavicle. Important sonoanatomy includes the axillary artery with the three cords surrounding the artery in a U-shaped fashion. The approach includes an in-plane technique with the needle aligned with the probe in a 45° angle aiming in a cephalad to caudad direction. The needle is placed just posterior to the axillary artery, which, when the LA is injected, provides coverage to all three cords in a U-shaped spread (Fig. 4.6).




Fig. 4.4 (A,B) Interscalene block, functional anatomy and (C) technique.




Fig. 4.5 Functional anatomy of supraclavicular block.

Use of the nerve stimulator with the infraclavicular approach is quite common and may be considered to be less difficult by some than ultrasound-guided infraclavicular block. In order to perform the infraclavicular block, the coracoid process is identified and marked. Once this is achieved, the physician will measure 2 cm medial and 2 cm inferior – this marks the nerve stimulator needle entry point. The nerve stimulator is turned to 1.0 mA. The needle is advanced in a direction that is perpendicular to the floor. It is important to note, as with other blocks, that there should be frequent aspiration throughout the block in order to minimize the risk of intravascular injection. As the needle is advanced, stimulation of the posterior cord is sought (extension of the elbow, wrist or fingers) and maintained at 0.5 mA. If the correct stimulation of muscle groups is not achieved, the needle's direction should be redirected by 5° at a time. Some anesthesiologists may seek both the medial and lateral cord if the posterior cord is difficult to find in order to improve success rates. The risks of the infraclavicular block include infection, bleeding, nerve injury, and pneumothorax.

Axillary block

An axillary block is indicated for surgery of the hand and forearm. It is performed at the level of the terminal branches of the brachial plexus. The radial, median, and ulnar nerves are positioned around the axillary artery, and the musculocutaneous nerve resides in the coracobrachialis muscle, lateral to the neurovascular bundle. The distribution of anesthesia includes the entire arm, except for the medial strip of skin in




Fig. 4.6 Functional anatomy of infraclavicular block.




Fig. 4.7 (A,B) Functional anatomy and (C) technique of axillary block.

the upper arm, which is supplied by the intercostobrachial nerve from T2 (Fig. 4.7).

For this block, the arm is abducted and the elbow flexed. When using the nerve stimulation technique, the axillary artery is palpated high in the axilla and the needle is directed lateral, medial, and posterior to the artery to stimulate the median, ulnar, and radial nerves, respectively. Obtaining two or more separate twitches, and therefore injecting local anesthetic near two or more nerves, improves block success.³⁰ The musculocutaneous nerve is then blocked by directing the needle laterally into the coracobrachialis muscle, obtaining a twitch of the bicep muscle, and depositing additional local anesthetic. When using ultrasound, the probe is placed transversely on the upper arm near the axilla, perpendicular to the axillary artery. The artery and nerves of interest are

visualized. The needle is advanced in a lateral to medial direction, and local anesthetic is deposited around each nerve.

The axillary approach to the brachial plexus has potential benefits for certain patient populations, such as patients with pulmonary disease, because the phrenic nerve will not be affected. This block may also be superior in patients with coagulopathies, since the area is superficial and easily compressible if vascular puncture occurs. One disadvantage of this block is that the needle must be repositioned multiple times to adequately block all of the nerves, potentially increasing the risk of vascular puncture or causing more patient discomfort. Additionally, the arm must be abducted in order to have adequate access to the upper arm and axilla, which may be difficult in some patients such as those with injuries.

Complications

Complications associated with regional anesthesia present a rare but significant risk to patients undergoing surgery of the upper extremity. Serious complications include neurologic injury, seizures, and cardiac arrest. Other risks associated with regional anesthesia are hematoma, infection, and block-specific complications such as pneumothorax. A large French prospective study reported an incidence of severe complications related to peripheral nerve blocks to be <5/10000 and an incidence of serious neurologic injury to be 2.4/10000.³¹

Neurologic complications

Peripheral nerve injury can present as pain, sensory disturbances, or motor deficits. Most of these are transient, with 95% resolving within 4–6 weeks and over 99% resolving within 1 year.^{2,30} The pathophysiology and mechanisms of peripheral nerve injury are mechanical, injection, ischemic, and neurotoxic. Recovery and prognosis are related to the location of injury. If the axon is damaged, recovery is slow and often incomplete, relying on collateral reinnervation or axonal regrowth. Damage to the myelin sheath disrupts the nerve action potential and tends to have faster recovery and a better prognosis. Mechanical injury from needles or catheters can disrupt the axon, although nerves tend to move away from approaching needles.³² Needle to nerve contact or intraneural injection can result in ischemia and neurotoxicity if the perineurium is disrupted. Local anesthetics can cause acute inflammatory reactions and be neurotoxic to exposed axons via cellular cytotoxic effects, dependent on the concentration and duration of exposure.³¹ Finally, ischemic injury may be caused by vascular injury, prolonged tourniquet use, or the use of vasoconstrictors. Intraneural injection can result in elevated pressure leading to ischemia. Ischemia causes metabolic stress and is associated with axonal damage and a poorer prognosis.

Peripheral nerve injury

A suspected peripheral nerve injury warrants an immediate evaluation, including a complete history and physical examination to screen for any pre-existing problems and to determine the location of the lesion. The 2008 American Society of Regional Anesthesia and Pain Medicine (ASRA) Practice Advisory on Neurologic Complications recommends that a complete or progressive deficit should be evaluated immediately by a neurologist or peripheral nerve surgeon. Mild or resolving symptoms without evidence of a neural deficit can be monitored and may only require patient reassurance. However, if symptoms fail to improve, a neurological consultation is recommended. Incomplete lesions with evidence of a neural deficit should initially be evaluated by a neurologist and may require referral to a peripheral nerve surgeon if symptoms persist or worsen.³² Neurologic tests such as nerve conduction studies, electromyography, and MRI may be helpful in establishing the degree of nerve damage, location, and prognosis.

The Second ASRA Practice Advisory on Neurologic Complications Associated with Regional Anesthesia and Pain Medicine provides updates to the 2008 advisory. Similar to

reports from the first advisory, the incidence of peripheral nerve injury has remained stable regardless of the localization technique used. The reported range of long-term injury is 2–4 per 10000 blocks. Long-term injury is rare, but transient postoperative neurologic symptoms are common in the first days to month following peripheral nerve blocks and decrease over time. The current advisory continues to advise against placing blocks in deeply sedated or anesthetized adults, as paresthesias reported by patients are considered a valuable warning sign for potential nerve injury.³³

Local anesthetic toxicity

Local anesthetics used for peripheral nerve blocks have the potential to cause serious harm. Systemic absorption of local anesthetic from an appropriately placed and dosed nerve block may result in mild symptoms, while an unintentional intravascular injection can lead to severe neurologic or cardiac toxicity causing major disability or even death. Risk factors that increase the potential for local anesthetic systemic toxicity (LAST) include local anesthetic potency and dose, peripheral nerve block location and technique, and patient risk factors such as age, pre-existing disease, and medications. Methods to prevent LAST revolve around avoiding intravascular injection and limiting the total dose of local anesthetic. Intravascular injection can be limited or avoided by incrementally injecting local anesthetic to monitor for symptoms of systemic absorption, aspirating prior to injection, and using an intravascular marker such as epinephrine. If systemic toxicity does occur, the classic symptoms present as auditory changes, circumoral numbness, metallic taste, and agitation. Symptoms may then progress to seizures, CNS depression and, finally, cardiac excitation followed by depression. However, cardiac toxicity may occur simultaneously or even before neurological symptoms. The treatment of LAST is circulatory and airway support to minimize hypoxia and acidosis. Seizures can be controlled with benzodiazepines, although succinylcholine may be necessary for persistent seizures. Cardiac arrest requires rapid restoration of cardiac output and oxygen delivery. If standard ACLS measures such as epinephrine or amiodarone fail to provide an adequate response, lipid emulsion therapy should be administered. Cardiac arrest refractory to vasopressor and lipid emulsion therapy should prompt institution of cardiopulmonary bypass.³⁴

Vascular injury

Vascular complications include hematomas, vasospasm from arterial puncture or local anesthetic-induced vasoconstriction, and arterial dissection from intramural injection. Hematomas have the potential to cause ischemic injury to nearby neural structures from compression, although they are usually small and inconsequential.³⁵ The severity of symptoms and progression are related to the rate and duration of hematoma formation. Risk factors include the extent of arterial injury (number of needle punctures), intrinsic vascular elasticity, and presence of diabetes, hypertension, or anticoagulation.³⁶ The presence of a hematoma should prompt evaluation of neurological function. Surgical decompression and evacuation may be necessary for severe cases, although conservative management is often appropriate.

When considering peripheral nerve blocks in the anticoagulated patient, significant blood loss, rather than neural deficits, may be the most serious complication. The expansile nature of the neurovascular sheath may decrease the chance of irreversible neural ischemia. Although neuraxial regional anesthesia presents significant risk to the anticoagulated patient, the risk after peripheral techniques remains undefined. Published case reports of clinically significant bleeding after peripheral regional anesthesia techniques demonstrate that all patients presenting with neurodeficits had complete recovery within 6 months to 1 year.³⁷ The 2010 ASRA Guidelines on Regional Anesthesia in the Anticoagulated Patient suggest that brachial plexus blockade in this patient population is not contraindicated, but should be evaluated on a case-by-case basis with increased caution.²

Infection

Infectious complications associated with regional anesthesia of the upper extremity are rare. Localized infection and bacteremia have been reported after both single-shot and continuous catheter techniques. One study reported catheter tip colonization in 29% of peripheral catheters, with 3% resulting in local inflammation.^{38,39} Patient risk factors for infectious complications include underlying sepsis, diabetes, immunocompromised status, steroid therapy, localized bacterial infection, chronic catheter maintenance (>48 h), and ICU admission.^{40,41} A careful evaluation of the risk-to-benefit ratio should be made prior to placing nerve blocks in infected or immunocompromised patients.^{2,39}

Outcomes

Upper extremity surgery can be performed successfully under both general anesthesia (GA) and regional anesthesia (RA). The potential benefits of RA techniques in outpatient surgery include improved clinical outcomes, patient satisfaction, efficiency, and reduced cost.⁴² However, GA is still widely used for outpatient surgery, and many of the newer anesthetic agents are short-acting with fewer side effects and better recovery profiles as compared with older agents. Additionally, many anesthesiologists are more familiar and comfortable with providing GA compared with RA.^{43,44}

Clinical outcomes and patient satisfaction

Several studies comparing regional anesthesia to general anesthesia for upper extremity surgery have demonstrated more favorable clinical outcomes with regional anesthesia, in terms of improved pain control, less nausea and vomiting, and fewer opioid-related side effects. Other benefits include patients feeling more alert, tolerating oral intake sooner, and ambulating sooner.^{42,43}

While improved clinical outcomes have been shown for RA in the immediate postoperative period, long-term benefits are still undefined. In a study comparing RA to GA in patients undergoing outpatient hand and wrist surgery, patients having RA had better initial analgesia and faster recovery but both groups had a similar degree of pain and need for oral analgesics 48 h postoperatively.⁴² In another study comparing RA to GA in ambulatory hand surgery, patients in the RA

group had significantly less postoperative pain before hospital discharge, but on postoperative days 1, 7, and 14, there were no differences in pain, opioid consumption, adverse effects, pain–disability index, or satisfaction.⁴³ Improved functional capacity has been demonstrated in patients having lower extremity surgery with continuous RA techniques. A study of patients undergoing outpatient shoulder and foot surgery under RA with continuous outpatient perineural infusions of local anesthetics demonstrated optimized functional recovery, analgesia, and patient satisfaction for 3 days postoperatively.⁴⁵ Further studies are necessary to determine if RA for upper extremity surgery has a benefit after the immediate postoperative period in terms of pain control, adverse effects, and functional capacity.

Patient satisfaction, although difficult to define, is usually high, with both regional and general anesthesia. Improved patient satisfaction with RA techniques may be a result of improved analgesia and fewer side effects.⁴⁶ Studies showing lower patient satisfaction with RA techniques often cite tourniquet pain and discomfort during the nerve block placement as causes of dissatisfaction.⁴⁷

Clinical tip: benefits of a regional anesthesia service and outpatient clinic

A 24-hour regional anesthesia service can expand care to patients who present during off-hours with traumatic injuries. Blocks are placed in the emergency department for patients with fractures, traumatic amputations, and other injuries hours prior to their scheduled surgery. This offers the benefit of decreased opioid use during admission and decreased side effects such as delirium.

A regional anesthesia outpatient clinic permits walk-ins from home or from their surgeon's office to be evaluated for postoperative neuropathies, catheter management, or other related concerns. The benefits of a regional anesthesia clinic include reduced emergency department admissions, early diagnosis and management of neuropathies, and improved patient satisfaction.

Operating room cost and efficiency

Several investigators have sought to determine if regional anesthesia is superior to general anesthesia in terms of operating room (OR) efficiency and costs. Some potential areas to improve efficiency and reduce costs are OR utilization time and recovery room time.

Some studies suggest that in order to save OR time through the use of regional anesthesia techniques, nerve blocks must be performed outside the operating room. In this case, the cost of valuable OR time is spared and efficiency is maximized because patients are ready for surgery as soon as they enter the operating room.⁴³ Others have reported similar OR times for RA versus GA techniques even when the blocks were performed in the operating room. This was attributed to the combination of fast-acting local anesthetics, the ability for surgeons to prepare the patients while the nerve blocks took full effect, and faster emergence time compared to GA.⁴²

Clinical tip: benefits of an out-of-OR regional team

Having a separate, out-of-OR regional anesthesia team offers several benefits. Efficiency is improved when blocks are placed in the preoperative holding area rather than the operating room. An out-of-OR team has the freedom and availability to place rescue blocks in the recovery room and bolus, reposition, or replace catheters placed preoperatively. Additionally, blocks can be placed in the emergency department, hospital ward, or intensive care unit for patients with acute pain such as dressing changes and other non-operative pain.

The addition of a block nurse to the regional anesthesia service improves efficiency. The block nurse assists the team by placing IVs, applying monitors to the patients, preparing drugs and supplies, and directing the pre-procedure “time-out”. Other responsibilities include assisting with documentation and patient follow-ups.

Patients having RA for upper extremity surgery who experience superior pain control and fewer side effects may potentially have a shorter PACU stay. A meta-analysis of RA versus GA for ambulatory anesthesia showed that patients receiving RA had an increased ability to bypass the PACU and/or a decreased PACU time.⁴⁶

To date, studies demonstrating an overall cost reduction for intraoperative and postoperative care during upper extremity surgery have compared GA to intravenous regional anesthesia (Bier block). The IVRA group had significant cost-savings attributed to lower anesthetic drug and equipment costs, shorter OR times, shorter PACU times, and shorter nursing times.^{48,49} In contrast, a retrospective comparison of costs for RA and GA techniques demonstrated a cost disadvantage for brachial plexus regional anesthesia, although recovery room costs were not included in this analysis.⁵⁰ More research is needed to determine if RA techniques for upper extremity surgery show a significant cost reduction when compared with other anesthetic techniques.

Special considerations

Cardiac patients

Patients with cardiac disease, including those with cardiac dysfunction and low ejection fractions, conduction abnormalities or ongoing ischemia, should be given consideration for regional anesthesia for upper extremity cases when indicated. Regional anesthesia allows patients the usual advantages of perioperative analgesia and possibly avoidance of general anesthesia.²⁰ General anesthesia, while very safe, can cause hemodynamic variations during the induction of anesthesia, intubation, emergence from anesthesia and possibly during surgical stimulation or bleeding. In this patient population, variations in blood pressure and heart rate can have significant consequences. The prospect of regional anesthesia and analgesia allows the patient to avoid hemodynamic fluctuations, thus minimizing risk.

Patients with cardiac disease may be anticoagulated for a variety of reasons. In these patients, the risks and benefits of

the block must take into consideration the possibility of an increased likelihood of bleeding during a nerve block with a resultant hematoma and nerve compression.

Pediatric patients

The pediatric population warrants special considerations when considering the type of anesthetic for surgery. These include anatomic and physiologic differences when compared with adult counterparts. Regional anesthesia offers the advantage of intraoperative and postoperative analgesia for the pediatric population. While still receiving a general anesthesia in most cases, the pediatric patient may benefit from a regional anesthetic as a result of decreased requirements for inhalational agents, leading to improved respiratory status.⁵¹ Improved respiratory status decreases the chance of laryngospasm on emergence. There are additional benefits of comfort for the patient’s family, observing a more comfortable and pain-free child in the recovery room. Overall, there is less stress for all involved.⁵²

The types of blocks performed on pediatric patients are generally performed with the patient under GA. It is not until the child is older and demonstrating a level of maturity that the block can be performed on the awake patient. When a block is performed on an asleep patient, there is an elevated risk of nerve injury as the patient cannot relay the sensation of paresthesias and pain from the rare event of neural trauma. Overall, regional anesthetic techniques are considered safe with an extremely low incidence of complications.⁵³

Ultrasound guidance is strongly recommended when considering regional anesthesia as part of the anesthetic in infants and children. The increased assistance provided in locating sonographic landmarks and nerve targets are of great benefit.^{54–56}

Perioperative pain management

For upper extremity surgery, the use of regional anesthesia with local anesthetics is primarily motivated by the desire to avoid general anesthesia. It has resulted in lower postoperative opiate usage and therefore alleviation of opiate-related side effects.⁵⁷ This approach has become, in many ways, the standard of care in upper extremity cases.

Peripheral catheters

Peripheral nerve blockade is safe and provides postoperative analgesia through the use of long-acting local anesthetics and/or continuous infusions through peripheral nerve catheters.⁵⁸ Outpatient catheters have become very common. Catheters provide longer acting pain relief over single shot techniques and benefit patients who undergo more painful surgical procedures, patients with chronic pain, and patients who are unable to tolerate opioids for various reasons. Peripheral nerve catheters are usually placed preoperatively by the anesthesiologist when the initial nerve block is performed. Alternatively, a catheter may be placed in the postoperative period if the patient experiences severe pain. Continuous catheters do not delay discharge in outpatient surgery as they can be managed at home by the patient.

Clinical tip: use and protocols for ambulatory catheters and pain pumps

For upper extremity procedures, the infraclavicular approach is preferred over the supraclavicular approach because there is less catheter migration at this location, possibly due to the anchoring of the catheter by the pectoralis muscles or the decreased amount of skin movement with activity. Patients are sent home with a catheter and an elastomeric pain pump with an on-demand button function. The pumps are set at a basal rate at 6 mL/hour (on average) with a bolus option of 5 mL every 30 minutes. The pumps are filled to 550 mL and usually last roughly three days, depending on the number of boluses activated by the patient. Patients remove the catheters themselves at home. The patients are instructed on the use and care of the catheter and pump prior to discharge and are sent home with an instruction pamphlet and a 24-hour number to call for any questions or concerns.

Preemptive analgesia

Preemptive analgesia is a pain management technique initiated prior to incision, which continues during the surgical procedure to reduce ongoing changes that occur in the body as a result of surgical incision and stimulation.⁵⁹ The rationale is that by preemptively blocking the nociceptive transmission onslaught that occurs with surgical incision, there will be less pain in the postoperative period and thus less need for consumption of opiates with fewer side effects. The duration of treatment includes the entire time that the noxious stimulation of surgery and its inflammatory injuries occur (intraoperative and early postoperative period).⁵⁹

Opiate-related side effects of sedation, nausea, respiratory depression, ileus and urinary retention can impact patient safety and satisfaction, discharge or patient admission, particularly in the outpatient setting, thereby affecting cost issues. Multimodal analgesic regimens have been developed featuring the peripheral nerve block in order to improve perioperative outcomes for minimally invasive procedures.

There has been much controversy surrounding the relevance and effectiveness of preemptive analgesia. Although the benefits have been established to some degree in animal studies, it has had questionable effect in human studies to date.⁶⁰ Many physicians practice with the belief that there is some preemptive analgesic effect. Some suggest that there is greater complexity in pain pathways than our understanding, and that studies are too simplistic. However, there is little doubt that excellent pain management in the pre- and post-surgical area contributes to an overall improved pain experience. A meta-analysis demonstrated that analgesia in the preoperative period lowered opiate consumption when the preemptive treatment was epidural analgesia, local infiltration, and systemic non-steroidal anti-inflammatory drugs (NSAIDs).⁶¹ The findings were equivocal with opioids and NMDA receptors alone. Certain studies go further to demonstrate that the preemptive analgesia associated with ketamine or a cox-2 analgesic gives additional benefit pre-incision.

One such study looked at patients about to undergo upper limb surgery under axillary brachial plexus blockade.⁶² The study examined the addition of a long-acting NSAID, ampiroxicam, versus placebo given 3 h prior to surgery. A

significant improvement occurred in patients who received the NSAID when compared to those in the placebo group. The treated patients consumed significantly less opiates and therefore were less likely to develop narcotic side effects such as sedation, nausea, constipation, or urinary retention. Nociceptive afferent transmission is known to be sensitive to inflammation and NSAIDs are postulated to have this effect via their anti-inflammatory action. Another study retrospectively reviewed a multimodal, preemptive pathway for patients undergoing major knee or hip surgery featuring peripheral nerve blocks, and found that patients were better able to participate in postoperative rehabilitation, were eligible for hospital discharge sooner, initiated earlier ambulation, experienced lower perioperative pain scores, and experienced reduced postoperative nausea and vomiting when compared with more traditional PCA measures.⁶³ These findings advocate for the preemptive multimodal analgesic regimen.

Inflammatory neuropathies

Since the 2008 ASRA advisory, new knowledge has emerged regarding postsurgical inflammatory neuropathies.³³ These neuropathies appear to be immune-mediated and precipitated by stressors such as infection or surgery. The clinical presentation may be delayed, usually within the first month after surgery, followed by a period of normal recovery. Patients complain of intense pain that is out of proportion to that expected from surgery, which resolves, and is then followed by weakness. Symptoms are outside of the expected location of the anesthetic block or surgery. The neurologic deficits may be focal, multifocal, or diffuse. Patients presenting with this combination of symptoms should be promptly referred for neurologic consultation, as many neurologists recommend treatment with steroids or immunoglobulin, and most postsurgical inflammatory neuropathies improve with early diagnosis and treatment.

Patients with persistent postsurgical pain may suffer from perioperative nerve injury related to their nerve block or surgical procedure. Patients with persistent pain, pain out of proportion to that expected from surgery, pain limiting function, or signs and symptoms concerning for chronic regional pain syndrome should be referred to a pain specialist. The pain physician plays an important role in providing symptomatic treatment and coordinating patient care, education and therapy.

Chronic postoperative pain

The development of postoperative pain after surgery is due to complex pathways – endocrine, metabolic, and inflammatory – that trigger a prolonged state of excitation of the spinal cord.⁶⁴ Various chemicals released during and soon after surgical incision may induce conversion of high threshold nociceptors into low threshold receptors, via a process called peripheral sensitization. This complex process eventually leads to release of cellular mediators in the recuperative period resulting in central sensitization and chronic pain.⁶⁵ Chronic pain is, among other factors, linked to patients with severe postoperative pain.^{15,66} While the development of chronic pain following surgery has lacked a spotlight in the medical literature, it is a reality that needs to be considered particularly in patients who may be at higher risk of

Table 4.3 Risk factors for severe postoperative pain

Preoperative pain
Prior use of opiates
Female gender
Nonlaparoscopic surgery
Knee and shoulder surgery
Psychosocial vulnerability
Repeat surgery
Intensity of early postoperative pain
Surgical approach with risk of nerve damage

developing chronic pain.⁶⁷ Inadequately treated postoperative pain is a major source of patients' dissatisfaction with their overall surgical experience.⁶⁸ Severe pain in the postoperative period correlates to a greater likelihood of developing chronic pain.⁶⁹ There are a number of risk factors⁷⁰ for developing severe postoperative pain (Table 4.3).

It is imperative that postoperative pain be treated effectively, possibly with a multimodal approach which considers preemptive analgesia and its potential benefits. It is crucial to identify those patients that have a greater likelihood of developing severe postoperative pain, not only to minimize the likelihood of developing chronic pain, but also to improve the patient's experience in the perioperative period.

Future directions

Wide awake upper extremity surgery

Most upper extremity surgery is performed with the use of a tourniquet, which allows improved visibility offered by a

bloodless field. Mitigation of tourniquet discomfort is usually achieved with the use of sedation, regional anesthetic blocks or general anesthesia. An alternative to this traditional approach is the wide awake local anesthesia no tourniquet (WALANT) technique, under which hand surgery is performed only with lidocaine for anesthesia combined with epinephrine for hemostasis.

The use of epinephrine permits adequate hemostasis and visibility; it effectively eliminates the need for a tourniquet in most types of hand surgery. Epinephrine is now considered to be safe for use in the upper extremity, specifically the hand and fingers.⁷¹ There have been no reported cases of digital infarction directly attributable to the use of epinephrine.

There are multiple recognized benefits of wide awake hand surgery. The risks of sedation or general anesthesia can be avoided, particularly in patients with complicated medical histories. Wide awake surgery has been shown to be cost effective as the charges related to the anesthesiologist, preoperative testing and postanesthesia recovery monitoring can be avoided.⁷² In the absence of sedation, patients can actively demonstrate intraoperative range of motion during tenolysis and flexor tendon repair surgery. Gapping in tendon repairs can be assessed and corrected immediately. During tendon transfer surgery, patients can activate transfers and demonstrate tensioning; transfers that are too tight or loose can be adjusted prior to skin closure.⁷³ For these reasons, wide awake surgery can improve results after hand surgery, particularly with respect to tendon repairs and tendon transfers. Wide awake hand surgery is gaining traction and is expected to be increasingly utilized as more surgeons are trained in the technique.



Access the complete reference list online at <http://www.expertconsult.com>

- Neal JM, Gerancher JC, Hebl JR, et al. Upper extremity regional anesthesia: essentials of our current understanding. 2008. *Reg Anesth Pain Med*. 2009;34:134–170. This article provides a comprehensive review of upper extremity regional anesthesia, including relevant anatomy, pharmacology, techniques, and complications. This review also summarizes the essential scholarly works available on upper extremity regional anesthesia and identifies informational gaps where further study is warranted.
- Moayeri N, Bigeleisen PE, Groen GJ. Quantitative architecture of the brachial plexus and surrounding compartments, and their possible significance for plexus blocks. *Anesthesiology*. 2008;108:299–304.
- Sites BD, Brull R, Chan VW, et al. Artifacts and pitfall errors associated with ultrasound-guided regional anesthesia. Part I: understanding the basic principles of ultrasound physics and machine operations. *Reg Anesth Pain Med*. 2007;32:412–418. This article presents the basics of ultrasound used for regional anesthesia. By understanding basic ultrasound physics most relevant to regional anesthesia and recognizing brachial plexus ultrasound anatomy, physicians can improve their ability to visualize target nerves, position of needles, and real-time spread of local anesthetic, thus improving nerve block efficiency, success, and safety.
- Bridenbaugh PO, Cousins MJ. *Neural Blockade in Clinical Anesthesia and Management of Pain*. 3rd ed. Philadelphia: Lippincott-Raven; 1998:xxii, 1177. This book chapter presents a review of the clinical pharmacology of local anesthetics, including factors that influence their usefulness and toxicity. Additionally, the various local anesthetics are reviewed for their specific activity, physiochemical structure, and applicability in clinical practice. These drugs, integral to the practice of regional anesthesia, are presented in a totality essential to the understanding of their role in practice.
- Raj PP. *Textbook of Regional Anesthesia*. New York: Churchill Livingstone; 2002:xix, 1083.
- Klein SM, Evans H, Nielsen KC, et al. Peripheral nerve block techniques for ambulatory surgery. *Anesth Analg*. 2005;101:1663–1676.
- Neal JG, Cox MJ, Drake DB, et al. The ASRA evidence-based medicine assessment of ultrasound-guided regional anesthesia and pain medicine: Executive summary. *Reg Anesth Pain Med*. 2010;35:S1–S9.
- Sorenson EJ. Neurological injuries associated with regional anesthesia. *Reg Anesth Pain Med*. 2008;33:442–448. This article provides a concise review of neurological injuries associated with regional anesthesia, including mechanisms, diagnosis, and management. Although neurologic injury is rare, every anesthesiologist and surgeon employing regional anesthesia techniques for their patients must be able to recognize a potential injury and institute treatment if necessary.
- Liu SS, Strodtbeck WM, Richman JM, et al. Comparison of regional versus general anesthesia for ambulatory anesthesia: a meta-analysis of randomized controlled trials. *Anesth Analg*. 2005;101:1634–1642.
- Hebl JR, Dilger JA, Byer DE, et al. A pre-emptive multimodal pathway featuring peripheral nerve block improves perioperative outcomes after major orthopedic surgery. *Reg Anesth Pain Med*. 2008;33:510–517.

References

- Brown DL. *Atlas of Regional Anesthesia*. 3rd ed. Philadelphia: Saunders; 2006.
- Neal JM, Gerancher JC, Hebl JR, et al. Upper extremity regional anesthesia: essentials of our current understanding, 2008. *Reg Anesth Pain Med*. 2009;34:134–170. This article provides a comprehensive review of upper extremity regional anesthesia, including relevant anatomy, pharmacology, techniques, and complications. This review also summarizes the essential scholarly works available on upper extremity regional anesthesia and identifies informational gaps where further study is warranted.
- Thompson GE, Rorie DK. Functional anatomy of the brachial plexus sheaths. *Anesthesiology*. 1983;59:117–122.
- Partridge BL, Katz J, Benirschke K. Functional anatomy of the brachial plexus sheath: implications for anesthesia. *Anesthesiology*. 1987;66:743–747.
- Kawai H, Kawabata H. *Brachial Plexus Palsy*. Singapore: World Scientific; 2000.
- Moayeri N, Bigeleisen PE, Groen GJ. Quantitative architecture of the brachial plexus and surrounding compartments, and their possible significance for plexus blocks. *Anesthesiology*. 2008;108:299–304.
- van Geffen GJ, Moayeri N, Bruhn J, et al. Correlation between ultrasound imaging, cross-sectional anatomy, and histology of the brachial plexus: a review. *Reg Anesth Pain Med*. 2009;34:490–497.
- Sites BD, Brull R, Chan VW, et al. Artifacts and pitfall errors associated with ultrasound-guided regional anesthesia. Part I: understanding the basic principles of ultrasound physics and machine operations. *Reg Anesth Pain Med*. 2007;32:412–418. This article presents the basics of ultrasound used for regional anesthesia. By understanding basic ultrasound physics most relevant to regional anesthesia and recognizing brachial plexus ultrasound anatomy, physicians can improve their ability to visualize target nerves, position of needles, and real-time spread of local anesthetic, thus improving nerve block efficiency, success, and safety.
- Schafhalter-Zoppoth I, Gray AT. The musculocutaneous nerve: ultrasound appearance for peripheral nerve block. *Reg Anesth Pain Med*. 2005;30:385–390.
- Thoirs K, Scutter S, Wilkinson M. The ulnar nerve at the elbow: an anatomic, sonographic, and histology comparison. *J Diagn Med Sonogr*. 2003;19:16–23.
- Hadzic A, Vloka JD. *New York School of Regional Anesthesia. Peripheral Nerve Blocks*. 1st ed. New York: McGraw-Hill Health Professions Division; 2004.
- Covino BG, Scott DB. *Handbook of Epidural Anaesthesia and Analgesia*. Orlando: Grune & Stratton; 1985:175.
- Ponrouch M, Bouic N, Bringuier S, et al. Estimation and pharmacodynamic consequences of the minimum effective anesthetic volumes for median and ulnar nerve blocks: a randomized, double-blind, controlled comparison between ultrasound and nerve stimulation guidance. *Anesth Analg*. 2010;111:1059–1064.
- Gerancher J, Weller R. Plastic surgery. In: Hentz VR, Mathes SJ, eds. *Plastic Surgery*. Philadelphia: Saunders Elsevier; 2006.
- Bridenbaugh PO, Cousins MJ. *Neural Blockade in Clinical Anesthesia and Management of Pain*. 3rd ed. Philadelphia: Lippincott-Raven; 1998:xxii, 1177. This book chapter presents a review of the clinical pharmacology of local anesthetics, including factors that influence their usefulness and toxicity. Additionally, the various local anesthetics are reviewed for their specific activity, physiochemical structure, and applicability in clinical practice. These drugs, integral to the practice of regional anesthesia, are presented in a totality essential to the understanding of their role in practice.
- Bernards CM, Kopacz DJ. Effect of epinephrine on lidocaine clearance in vivo: a microdialysis study in humans. *Anesthesiology*. 1999;91:962–968.
- Spiegel DA, Dexter F, Warner DS, et al. Central nervous system toxicity of local anesthetic mixtures in the rat. *Anesth Analg*. 1992;75:922–928.
- Raj PP. *Textbook of Regional Anesthesia*. New York: Churchill Livingstone; 2002:xix, 1083.
- Klein SM, Evans H, Nielsen KC, et al. Peripheral nerve block techniques for ambulatory surgery. *Anesth Analg*. 2005;101:1663–1676.
- Pierce EC Jr. The 34th Rovenstine Lecture. 40 years behind the mask: safety revisited. *Anesthesiology*. 1996;84:965–975.
- Neal JG, Cox MJ, Drake DB, et al. The ASRA evidence-based medicine assessment of ultrasound-guided regional anesthesia and pain medicine: Executive summary. *Reg Anesth Pain Med*. 2010;35:S1–S9.
- Koff MD, Cohen JA, McIntyre JJ, et al. Severe brachial plexopathy after an ultrasound-guided single-injection nerve block for total shoulder arthroplasty in a patient with multiple sclerosis. *Anesthesiology*. 2008;108:325–328.
- Zetlaoui PJ, Labbe JP, Benhamou D. Ultrasound guidance for axillary plexus block does not prevent intravascular injection. *Anesthesiology*. 2008;108:761.
- Lalonde D, Bell M, Benoit P, et al. Multicenter prospective study of 3,110 consecutive cases of elective epinephrine use in the fingers and hand: the Dalhousie Project clinical phase A. *J Hand Surg Am*. 2005;30:1061–1067.
- Wilhelmi BJ, Blackwell SJ, Miller JH, et al. Do not use epinephrine in digital blocks: myth or truth? *Plast Reconstr Surg*. 2001;107:393–397.
- Gill HS, Prausnitz MR. Does needle size matter? *J Diabetes Sci Technol*. 2007;1:725–729.
- Winnie AP, Collins VJ. The subclavian perivascular technique of brachial plexus anesthesia. *Anesthesiology*. 1964;25:353–363.
- Perlas A, Lobo G, Lo N, Brull R, et al. Ultrasound-guided supraclavicular block: outcome of 510 consecutive cases. *Reg Anesth Pain Med*. 2009;34:171–176.
- Sauter AR, Smith HJ, Stubhaug A, et al. Use of magnetic resonance imaging to define the anatomical location closest to all three cords of the infraclavicular brachial plexus. *Anesth Analg*. 2006;103:1574–1576.
- Sorenson EJ. Neurological injuries associated with regional anesthesia. *Reg Anesth Pain Med*. 2008;33:442–448. This article provides a concise review of neurological injuries associated with regional anesthesia, including mechanisms, diagnosis, and management. Although neurologic injury is rare, every anesthesiologist and surgeon employing regional anesthesia techniques for their patients must be able to recognize a potential injury and institute treatment if necessary.
- Auroy Y, Benhamou D, Bagues L, et al. Major complications of regional anesthesia in France: The SOS Regional Anesthesia Hotline Service. *Anesthesiology*. 2002;97:1274–1280.
- Neal JM, Bernards CM, Hadzic A, et al. Practice advisory on neurologic complications in regional anesthesia and pain medicine ASRA. *Reg Anesth Pain Med*. 2008;33:404–415.
- Neal JM, et al. The Second ASRA Practice Advisory on Neurologic Complications Associated with Regional Anesthesia and Pain Medicine, Executive Summary 2015. *Reg Anesth Pain Med*. 2015;40:401–430.
- Neal JM, Bernards CM, Butterworth JF 4th, et al. Practice advisory on local anesthetic systemic toxicity ASRA. *Reg Anesth Pain Med*. 2010;35:152–161.
- Ben-David B, Stahl S. Axillary block complicated by hematoma and radial nerve injury. *Reg Anesth Pain Med*. 1999;24:264–266.
- Zipkin M, Backus WW, Scott B, et al. False aneurysm of the axillary artery following brachial plexus block. *J Clin Anesth*. 1991;3:143–145.
- Horlocker TT, Wedel DJ, Rowlingson JC, et al. Regional anesthesia in the patient receiving antithrombotic or thrombolytic therapy: American Society of Regional Anesthesia and Pain Medicine Evidence-Based Guidelines, 3rd edn. *Reg Anesth Pain Med*. 2010;35:64–101.
- Capdevila X, Pirat P, Bringuier S, et al. Continuous peripheral nerve blocks in hospital wards after orthopedic surgery: a multicenter prospective analysis of the quality of postoperative analgesia and complications in 1,416 patients. *Anesthesiology*. 2005;103:1035–1045.

39. Hebl JR, Neal JM. Infectious complications: a new practice advisory. *Reg Anesth Pain Med.* 2006;31:289–290.
40. Horlocker TT, Wedel DJ. Regional anesthesia in the immunocompromised patient. *Reg Anesth Pain Med.* 2006;31:334–345.
41. Wedel DJ, Horlocker TT. Regional anesthesia in the febrile or infected patient. *Reg Anesth Pain Med.* 2006;31:324–333.
42. Hadzic A, Arliss J, Kerimoglu B, et al. Comparison of infraclavicular nerve block versus general anesthesia for hand and wrist day-case surgeries A. *Anesthesiology.* 2004;101:127–132.
43. McCartney CJ, Brull R, Chan VW, et al. Early but no long-term benefit of regional compared with general anesthesia for ambulatory hand surgery. *Anesthesiology.* 2004;101:461–467.
44. Eppe J, Kubitz J, Schmidt H, et al. Comparative analysis of costs of total intravenous anaesthesia with propofol and remifentanyl vs. balanced anaesthesia with isoflurane and fentanyl. *Eur J Anaesthesiol.* 2001;18:20–28.
45. Capdevila X, Dadure C, Bringuier S, et al. Effect of patient-controlled perineural analgesia on rehabilitation and pain after ambulatory orthopedic surgery: a multicenter randomized trial. *Anesthesiology.* 2006;105:566–573.
46. Liu SS, Strodtbeck WM, Richman JM, et al. Comparison of regional versus general anesthesia for ambulatory anesthesia: a meta-analysis of randomized controlled trials A. *Anesth Analg.* 2005;101:1634–1642.
47. De Andrés J, Valía JC, Gil A, et al. Predictors of patient satisfaction with regional anesthesia. *Reg Anesth.* 1995;20:498–505.
48. Chan VW, Peng PW, Kaszas Z, et al. Comparative study of general anesthesia A, intravenous regional anesthesia, and axillary block for outpatient hand surgery: clinical outcome and cost analysis. *Anesth Analg.* 2001;93:1181–1184.
49. Chilvers CR, Kinahan A, Vaghadia H, et al. Pharmacoeconomics of intravenous regional anaesthesia vs general anaesthesia for outpatient hand surgery. *Can J Anaesth.* 1997;44:1152–1156.
50. Schuster M, Gottschalk A, Berger J, et al. retrospective comparison of costs for regional and general anesthesia techniques A. *Anesth Analg.* 2005;100:786–794.
51. Shandling B, Steward DJ. Regional analgesia for postoperative pain in pediatric outpatient surgery. *J Pediatr Surg.* 1980;15:477–480.
52. Leak WD, Winchell SW. Regional anesthesia in pediatric patients: review of clinical experience. *Reg Anesth Pain Med.* 1982;7:64–65.
53. Giaufre E, Dalens B, Gombert A. Epidemiology and morbidity of regional anesthesia in children: a one-year prospective survey of the French-Language Society of Pediatric Anesthesiologists. *Anesth Analg.* 1996;83:904–912.
54. Lönqvist PA. Is ultrasound guidance mandatory when performing paediatric regional anaesthesia? *Curr Opin Anesthesiol.* 2010;23:337–341.
55. Marhofer P, Chan VW. Ultrasound-guided regional anesthesia: current concepts and future trends. *Anesth Analg.* 2007;104:1265–1269.
56. Marhofer P, Frickey N. Ultrasonographic guidance in pediatric regional anesthesia Part 1: Theoretical background. *Paediatr Anaesth.* 2006;16:1008–1018.
57. Richman JM, Liu SS, Courpas G, et al. Does continuous peripheral nerve block provide superior pain control to opioids? A meta-analysis. *Anesth Analg.* 2006;102:248–257.
58. Jin F, Chung F. Multimodal analgesia for postoperative pain control. *J Clin Anesth.* 2001;13:524–539.
59. Kissin I. Preemptive analgesia at the crossroad. *Anesth Analg.* 2005;100:754–756.
60. Moiniche S, Kehlet H, Dahl JB. A qualitative and quantitative systematic review of preemptive analgesia for postoperative pain relief: the role of timing of analgesia. *Anesthesiology.* 2002;96:725–741.
61. Ong CK, Lirk P, Seymour RA, et al. The efficacy of preemptive analgesia for acute postoperative pain management: a meta-analysis. *Anesth Analg.* 2005;100:757–773.
62. Hebl JR, Dilger JA, Byer DE, et al. A pre-emptive multimodal pathway featuring peripheral nerve block improves perioperative outcomes after major orthopedic surgery. *Reg Anesth Pain Med.* 2008;33:510–517.
63. Sai S, Fujii K, Hiranuma K, et al. Preoperative ampiroxicam reduces postoperative pain after hand surgery. *J Hand Surg [Br].* 2001;26:377–379.
64. Joshi GP, Ogunnaike BO. Consequences of inadequate postoperative pain relief and chronic persistent postoperative pain. *Anesthesiol Clin North America.* 2005;23:21–36.
65. Warfield CA, Bajwa ZH. *Principles and Practice of Pain Medicine.* 2nd ed. New York: McGraw-Hill; 2004:xxiii, 938.
66. Gerbershagen HJ, Dagtekin O, Rothe T, et al. Risk factors for acute and chronic postoperative pain in patients with benign and malignant renal disease after nephrectomy. *Eur J Pain.* 2009;13:853–860.
67. Asokumar B. Regional anesthesia and analgesia: prevention of chronic pain. *Anesth Analg.* 2008;12:199–202.
68. Tong D, Chung F, Wong D. Predictive factors in global and anesthesia satisfaction in ambulatory surgical patients. *Anesthesiology.* 1997;87:856–864.
69. Yarnitsky D, Crispel Y, Eisenberg E, et al. Prediction of chronic post-operative pain: pre-operative DNIC testing identifies patients at risk. *Pain.* 2008;138:22–28.
70. Perkins FM, Kehlet H. Chronic pain as an outcome of surgery: a review of predictive factors. *Anesthesiology.* 2000;93:1123–1133.
71. Thomson CJ, Lalonde DH, Denkler KA, et al. A critical look at the evidence for and against elective epinephrine use in the finger. *Plast Reconstr Surg.* 2007;119:260–266.
72. Lalonde D, Martin A. Tumescence local anesthesia for hand surgery: improved results, cost effectiveness, and wide-awake patient satisfaction. *Arch Plast Surg.* 2014;41:312–316.
73. Bezuhly M, Sparkes GL, Higgins A, et al. Immediate thumb extension following extensor indicis proprius-to-extensor pollicis longus tendon transfer using the wide-awake approach. *Plast Reconstr Surg.* 2007;119:1507–1512.

5

Principles of internal fixation as applied to the hand and wrist

Jason R. Kang, Christopher Cox, and Jeffrey Yao

Access video content for this chapter online at expertconsult.com 

SYNOPSIS

- Careful preoperative planning facilitates safe and expeditious surgery.
- Ligamentotaxis relies on the application of linear traction to indirectly reduce fragments via the intact periosteum, ligaments and soft tissues.
- The most appropriate method of fracture fixation depends on a careful assessment of the fracture characteristics and patient-related factors.
- Postoperative care should generally allow for early mobilization if fixation permits.

Introduction

Fracture care was significantly advanced in the twentieth century with the introduction of new techniques and instrumentation for internal and external fixation.¹ Today's capable hand surgeon must be well versed in the spectrum of available techniques of fracture fixation to provide optimum care for the myriad of bony injuries that occur within the purview of a hand surgery practice. Fixation of fractures in the hand is notoriously difficult given the relatively small size of the osseous structures and complexity of the surrounding anatomy.² The aim of this chapter is not to review every possible technique of fracture fixation in the hand, but rather, to present basic concepts and general techniques useful in routine fracture care.

Much of the credit for these advances in fracture management should go to the Arbeitsgemeinschaft für Osteosynthesefragen (AO), who devised a set of principles (Table 5.1) that, in its modified form, provides the basic tenets that underlie appropriate fracture care.³

Patient selection

Fracture assessment

Any consideration of fracture fixation must begin with a careful, complete history and physical examination. Was the

mechanism of injury high or low energy trauma? How much time has elapsed since the fracture and the current presentation? Does the patient require early return to functional activities or are their daily demands limited? Does the patient have multiple injuries, or is this an isolated injury? Are there open wounds or soft tissue damage? Is there angular or rotational displacement? The vast majority of fractures that are non- or minimally displaced are amenable to treatment with immobilization and non-operative methods.

Patient-specific considerations

The treatment of fractures requires a commitment from the patient to observe potential activity restrictions and to participate in appropriate rehabilitation. Failure to comply with immobilization, follow-up care, therapy recommendations, or weight-bearing restrictions may result in compromised outcomes.

Certain host factors can increase susceptibility to fracture and/or surgical wound healing problems. Systemic risk factors for poor healing potential include: diabetes mellitus,⁴ an immunocompromised state, advanced age, and smoking. Local risk factors include: skin quality, volume/quality of soft tissues available for closure, type of hardware utilized, and tension across the wound. Failure to recognize and address these factors may result in poor outcomes. Patients with an elevated risk for wound problems should be counseled accordingly and managed with alternative strategies where appropriate. Non-modifiable risk factors should be recognized and taken into consideration during treatment decision-making. Modifiable risk factors should be addressed and optimized before, during, and after fracture treatment.

Preoperative imaging

Proper radiographic assessment requires a minimum of 2 orthogonal views with the X-ray beam centered near the

Table 5.1 AO principles

1. Anatomical fracture reduction
2. Appropriate stability of the fixation construct
3. Preservation of blood supply and soft-tissue attachments to fracture fragments
4. Early and safe mobilization

fracture to minimize distortion. Factors to carefully evaluate include:

1. Location of fracture (articular, metaphyseal, diaphyseal)
2. Pattern (transverse, oblique, spiral)
3. Presence of comminution
4. Displacement
5. Angulation (sagittal, coronal, and axial/rotational planes)
6. Potential deforming forces acting across the fracture site

Occasionally, advanced imaging with computed tomography (CT) scans or magnetic resonance imaging (MRI) may be indicated to further characterize complex fracture patterns or to evaluate for occult injuries to the bones or soft tissue. After careful consideration of the fracture pattern in the context of the injured patient, a decision must be made regarding non-operative versus operative treatment.

Treatment/surgical technique

Preoperative planning

Once a decision has been made to treat a fracture operatively, the surgeon begins the planning phase. Similar to the “reconstructive ladder” concept for management of soft-tissue defects, the surgeon should, in general, use the simplest method that will reliably produce excellent clinical results. Planning should include every detail of the proposed operation. This includes patient positioning, operating room setup, type of imaging (fluoroscopy) desired, implants needed, surgical approach, fracture fixation constructs, and consideration of backup plans. Time spent planning will save operative time, decrease staff frustration, and ensure that the appropriate tools are present for the safest, most successful and most efficient surgery possible.

Fracture reduction

Fracture reduction may be obtained by closed or open means. For closed reductions, pulling linear traction across the fracture site is usually required. This utilizes the phenomenon of ligamentotaxis,^{5,6} whereby intact periosteum, soft tissue attachments, and ligaments help realign bony fragments as they are stretched. For open reductions, the fracture site is exposed and reduction is obtained through a combination of external manipulation and instruments placed within the fracture site. The reduction can be provisionally held with reduction forceps or Kirschner wires. The concept of reducing the number of fragments by temporary or final fixation of fragments to other fragments is critical in achieving a satisfactory reduction in the face of comminution. Forceps or wires used for temporary fixation should be carefully thought out so as to not interfere with the planned definitive fixation.

Reduction hints and tips: reduction forceps

Reduction forceps may be useful to attain and maintain fracture reduction in fixation of larger fragments. One tine of the forceps is introduced firmly onto a fragment and the other tine is used to tease another fragment into the appropriately reduced position. Careful pronation and supination movements while applying the forceps may allow for the restoration of length to difficult fractures. One has to take care not to crush or shatter the fragments with excessive compression of the clamps.

Reduction hints and tips: Kirschner wires (K-wires)

These are discussed in a separate section below in detail. In fracture reduction, K-wires can be used to temporarily secure fractures that are already reduced. Alternatively, they may be applied in a unicortical fashion and utilized as “joysticks” or “handles” to manipulate pieces into the appropriate position. After attaining this position, they are often advanced across the fracture to transition them from a reduction aid into a tool of temporary or definitive fixation.

Reduction hints and tips: Kapandji (intrafocal) pinning⁷⁻¹¹

This is a special type of application of a K-wire utilized commonly in distal radius fractures. The wire is introduced through the fracture site (intrafocally). The pin is then tilted in the desired direction of the reduction, then advanced through the far cortex. This has particular applicability to the restoration of volar tilt and radial inclination in distal radial fracture. This may be employed as either temporary or definitive fixation.

Reduction hints and tips: temporary/supplemental external fixation

For select, extremely difficult fractures, an external fixator may be utilized to hold traction, neutralize shortening and apply ligamentotaxis to assist with fracture reduction.

Intraoperative imaging

Fluoroscopy provides a valuable adjunct to many fracture fixation surgeries. A complete review of the physics and principles of fluoroscopy is beyond the scope of this chapter, but a few points are worth mentioning. For upper extremity surgery, either an image intensifier or a “mini” fluoroscopic unit may be employed. For the vast majority of hand surgery cases a “mini” fluoro provides adequate visualization with greater mobility and less radiation.¹²⁻¹⁵

Many different operating room setups may be employed, but patient positioning should be confirmed preoperatively to




Fig. 5.1 Compressed osteotomy site. Note the migration of osteocytes across the fracture line, an example of contact healing. (Hematoxylin and eosin: magnification $\times 100$.)

allow for adequate fluoroscopic visualization during surgery. We typically position the mini fluoroscopic unit parallel to the bed, oriented from the foot toward the axilla, so that the patient's arm can be adducted off of the hand table to provide unobstructed views.

The region being examined should always be centered on the detector of the fluoroscopic unit to minimize the distortion from the "parallax" effect. Multiple views are helpful to determine fracture reduction or hardware position in all planes. It may also be helpful to orient the beam directly down a placed K-wire or screw to precisely visualize its placement. Specific knowledge of certain anatomic regions may also be helpful. For instance, when imaging the distal radius, inclining the wrist approximately 20–30 degrees from a true lateral can provide better visualization of the cortex of the lunate facet to evaluate for screw penetration into the radiocarpal joint.¹⁶ Live, dynamic fluoroscopy may be useful to examine for stability across a fracture site with controlled motion or to evaluate for intra-articular screw penetration.

Fixation principles

Absolute stability and interfragmentary compression

Absolute stability is employed when fracture fragments are reduced anatomically and secured with rigid fixation. Interfragmentary compression is a critical component of fixation when the surgeon attempts to achieve absolute stability.^{17,18} This compression, when combined with anatomic reduction, leads to microscopic interdigitation of fracture ends, thus minimizing the distance required for cells to travel from one side of the fracture to the other. The fracture heals by **primary bone healing** and histologically with "cutting cones" that facilitate direct healing of one fragment to another (Fig. 5.1). Minimal to no fracture callus is observed. This may be achieved via a variety of methods discussed below, including lag screws, compression plates, and tension bands. Interfragmentary compression should be avoided in highly comminuted fractures, as overzealous compression may lead to excessive shortening.

Relative stability

Relative stability is important when treating comminuted fractures where anatomical reduction is not possible or in cases where closed reduction is elected. With relative stability, the primary focus is on restoring the anatomic relationship of the neighboring articular surfaces in length, alignment and rotation. Some micromotion occurs at the fracture site, and, in fact, is conducive to this type of healing (**secondary bone healing**). Stability, however, must be adequate to maintain alignment and prevent excessive motion at the fracture sites. In contrast to primary bone healing via absolute stability, secondary bone healing occurs via progression through cartilaginous intermediaries and fracture callus is typically observed. Relative stability is typically achieved with external fixation, bridge plating, or intramedullary fixation. This concept, in general, is not commonly applied to articular fractures.

Methods of fixation

Kirschner wires

Kirschner wires (K-wires) are inexpensive and simple, yet versatile tools to assist with fracture fixation. They may be inserted in either a percutaneous or open fashion and appropriate insertion causes minimal tissue trauma. They may be implemented either as provisional or definitive fixation (Fig. 5.2).¹⁹ When used for definitive fixation, relative stability is generally obtained and healing occurs with callus formation. Insertion of K-wires may be either directly across a fracture site or in an intramedullary fashion. The main limitation of K-wires is that they do not allow for interfragmentary compression and may loosen over time, leading to implant migration.

Sizes of Kirschner wires are usually reported either in terms of inches or millimeters. For instance, a 0.062-inch K-wire is the same caliber as a 1.6-mm K-wire. Sizes typically utilized in hand surgery range from 0.035 inches (0.9 mm) to 0.079 inches (2.0 mm), although larger wires may be used for select indications. Most wires are available in either smooth or threaded varieties. Smooth wires allow for easy removal in a clinic setting, but are also more prone to unintended migration. Threaded wires have a tendency to follow prior tracts within bone; advancing them with the drill on reverse somewhat negates this tendency.

Tension band constructs

When bone is subjected to eccentric axial forces, one side of the bone is subjected to compression forces and the opposite side to tensile forces. A tension band,^{20–23} either in the form of a wire construct or a plate, aims to convert this eccentric tensile force into compression to assist with fracture compression and healing (Fig. 5.3). This concept is most applicable to simple, transverse fractures in the diaphyseal region and requires an intact cortex (no comminution) on the compression side.

To accomplish this conversion of eccentric forces into compression, the tension band must be placed on the tension surface. Fortunately, in the hand, this is on the dorsal side of the metacarpals and the phalanges, allowing easier surgical access. As the patient actively flexes the fingers, the force of



Fig. 5.2 This 75-year-old had multiple injuries after being run over by a truck. He sustained fractures of all metacarpals. Relative stability through usage of multiple K-wires was elected to minimize further soft-tissue disruption.

flexion on the annular pulleys is transmitted directly to the attached bone, and the vectors of force are through the volar cortex toward one another. Because the tension band fixes the dorsal cortex stably, the effect is to force the volar cortices against each other and, by this process, produce further compression of the fragments, thus attaining absolute stability.

The exact configuration of the wires may vary with the individual fracture, but most commonly consists of a “figure-of-8” construct with dorsally crossed wires (**Fig. 5.4**). Typically, this is employed by passing the wire either through a drill hole or under a tendinous origin/insertion on each side of the fracture. The wire can then be twisted to reduce and compress the fracture. Depending on the specific situation, one may use a twist on either side of the bone, combine K-wires with the intraosseous wires, or many other techniques.

In the hand, 28-gauge wire is adequate for a tension band in small phalanges; 26-gauge wire serves in larger phalanges and metacarpals. Rotation may be controlled and stability augmented by accurately interdigitating the jagged edges of fracture fragments together (**Table 5.2**).




Fig. 5.3 Tension band technique. (A) Transverse midshaft proximal phalangeal fracture with volar angulation and displacement. (B) Reduction without fixation allows compression of the volar cortex during digital flexion but unacceptable dorsal cortical instability, causing an unacceptable gap. (C) A figure-of-eight tension band wire is applied dorsal to the central axis of the proximal phalanx. (D) The loops on either side of the tension band are tightened simultaneously to achieve symmetric tension on both sides of the fracture. After the tension band wire is applied, the compressive forces created during digital flexion are evenly distributed across the entire fracture site. The tension band wire absorbs an amount of tension equal to the compression at the fracture site. (E) Dorsal view of the tightened tension band wire. Holes may be drilled in the bone, and the ends of the wire loops may be inserted into these holes to minimize soft-tissue irritation. (After Freeland AE. *Hand Fractures: Repair, Reconstruction and Rehabilitation*. Philadelphia: Churchill Livingstone; 2000:42.)



Fig. 5.4 (A) A displaced transverse fracture of the mid-diaphysis of the middle phalanx resulting from a glancing blow to the dorsum of the long finger. (B) Application of a tension band wire resulting in good interdigitation of the fracture so that it was held securely against rotational forces. (From Freeland AE, Jabaley ME, Hughes JL. *Stable Fixation of the Hand and Wrist*. New York: Springer-Verlag; 1985:89.)

A specific form of intraosseous wiring,²⁴ the 90-90 technique (Fig. 5.5), is useful, especially for arthrodesis, replantation, and transverse fractures. Although not a tension band strictly speaking, it is a rigid enough construct that it will permit immediate motion.

External fixation

External fixation provides a useful, versatile option for fracture stabilization. This typically consists of pins placed on either side of the fracture with the pins connected to each other through an external apparatus. This may be employed as either temporary or definitive fixation. Reduction is achieved through ligamentotaxis.^{5,25,26} While this may be used with any fracture, it serves a particular purpose when there is severe fracture comminution (Fig. 5.6) and/or an element of soft tissue loss requiring reconstruction, thus increasing the risk of infection with internal implants. External fixators can typically be inserted through small incisions away from the

fracture site and zone of injury, thus avoiding violation of the fracture hematoma. Knowledge of local anatomy together with proper techniques of pin insertion should be used to avoid damage to neurovascular structures. For instance, when placing an external fixator for a distal radius fracture, great care should be used to avoid damage to the radial sensory nerve. Most authors advocate using an open approach and identifying the radial sensory nerve in this instance although others have advocated percutaneous placement of the pins in a more dorsal position.²⁷

Two main categories of external fixators exist: non-bridging and bridging. Non-bridging fixators²⁸ only span the fracture site, while bridging fixators also span a joint. Bridging fixators are more often used with metaphyseal fractures. Bridging fixators may also be combined with limited K-wire or internal fixation for comminuted articular fractures.^{11,29} When bridging joints, care must be taken to avoid unwanted overdistraction.³⁰ Some specialized bridging fixators are hinged to allow mobilization of the spanned joint.³¹ Relative stability is achieved with any method of external fixation and healing occurs with abundant callus via secondary bone healing.

Interfragmentary lag screws

Lag screws (Figs. 5.7 & 5.8) provide compression between two fragments to achieve absolute stability. These may be used alone, in combination with another method of fixation, or through a plate. Lag screws are most useful in simple oblique or spiral fractures,³² but also may be used to piece together comminuted fractures. The utility of lag screws is very limited in the fixation of transverse fractures as proper orientation perpendicular to the fracture is difficult. If the trajectory of the lag screw is not perpendicular to the plane of the fracture, a shear force is introduced.

Key concepts: lagging by technique vs lagging by design

Insertion of a lag screw can be accomplished in two ways.

Lagging by technique relies on screw placement technique to achieve interfragmentary compression, whereas **lagging by design** applies the design features of the screw to achieve compression.

When placing a lag screw by technique, a proper site of insertion is selected first (see Fig. 5.7 and Video 5.1 ►). Ideally, lag screws should be positioned perpendicular to the plane of the fracture. Long spiral fractures may be fixed with lag screws

Table 5.2 Techniques for internal fixation

	Interosseous wire (gauge)	Kirschner wire (diameter inches)	Interosseous (lag) screw (mm)	Plate (mm)
Distal phalanx	28	0.028/0.035	1.3/1.5	N/A
Middle phalanx	28	0.035	1.3/1.5	1.3/1.5
Proximal phalanx	26/28	0.045	1.5/2.0	1.5/2.0
Metacarpal	26	0.045/0.062	1.5/2.0	2.0
Carpal	24/26	0.045/0.062	1.5/2.0/2.4	2.0/2.4



Fig. 5.5 This 37-year-old male had a saw injury to the palm of the hand. In addition to multiple tendon injuries, he sustained a severe injury to the cartilage of the thumb metacarpophalangeal joint. A primary fusion was elected with usage of 90-90 interosseous wires and a supplemental K-wire.

in different planes, but perpendicular to the fracture at each position. Screws placed too close to fracture edges may lead to fracture propagation.

Second, the near cortex is overdrilled with a drill size equivalent to or slightly larger than the outer thread diameter of the planned screw. This allows the screw to “glide” through the near cortex as the screw is tightened.

Next, the far cortex is drilled with a smaller drill size equivalent to the core diameter of the planned screw. Tapping may be done at this stage. However, most modern screws are self-tapping.

Next, the near cortex is countersunk. This increases the contact area of the screw head on the near cortex, thus

distributing the forces more evenly and avoiding the high contact pressure that may lead to fracture propagation from the drill site into the fracture site. Countersinking also decreases the prominence of the screw head, decreasing irritation of the overlying soft tissues.

Finally, the screw length is measured with a depth gauge and the appropriate length screw is inserted. Visible compression across the fracture site is frequently observed. Care should be taken to avoid overcompression.

Lagging by design may be achieved by utilizing specially designed implants. Two types of screws commonly employed are partially threaded screws (Fig. 5.9) and headless compression screws. Partially threaded screws have threads at the




Fig. 5.6 A spanning external fixator has been applied to this highly comminuted 5th metacarpal shaft fracture.




Fig. 5.7 Lag screw technique. A long oblique metacarpal fracture (A) is reduced and secured with a pointed reduction forceps. (B) A glide hole is drilled perpendicular to the fracture in the near cortex with a 2.4 mm drill bit. A drill guide is used to protect adjacent soft tissue and to prevent skating of the drill bit on the bone. (C) The opposite end of this double-ended drill guide inserts into the 2.4 mm gliding hole. It has an internal diameter of 1.8 mm. A concentric 1.8 mm core hole is drilled in the opposite cortex (D). A countersink fashions an area in the proximal half of the dorsal cortex to correspond to and seat the screw head (E). A depth gauge determines the appropriate screw length (F). A 2.4 mm tap threads the core hole of the opposite cortex (G). A tap sleeve is used to protect the adjacent soft tissues. (This step may be omitted for self-tapping screws.) A 2.4 mm screw is inserted. As the screw glides through the proximal hole, its head engages the proximal cortex (H). A second screw is applied in a manner similar to the first but in a plane perpendicular to the long metacarpal axis, thus satisfying the need for a neutralization screw (I). (Redrawn after Freeland AE. *Hand Fractures: Repair, Reconstruction and Rehabilitation*. Philadelphia: Churchill Livingstone; 2000:42.)

tip of the screw but no threads below the screw head that allows the screw to glide through the near cortex. They may be placed after drilling bicortically with the core-diameter drill and then placing the screw, which saves time intraoperatively. The utility of partially threaded screws may be limited by the relatively large size of the implant in many regions of the hand and wrist. Another type of compression screw is the headless compression screw (Fig. 5.10 and Video 5.2 ►). This screw has threads of varying pitches. The threads with greater pitch within one fragment lead to more travel per turn within that fragment compared to the finer pitch threads in the other fragment (Fig. 5.11). Thus, compression is achieved as the screw is advanced (Fig. 5.10 and see Video 5.2 ►).

Compression plating

Compression plating is a method of obtaining absolute stability and interfragmentary compression through a specific method of plate application. This particular plating method is typically employed for oblique or transverse fractures.

For transverse fractures (Fig. 5.12), the fracture is provisionally reduced and the plate is affixed to one side of the fracture in a neutralization fashion (holes drilled centrally within the screw holes of the plate). Next, a hole is drilled eccentrically (the portion of screw hole farthest away from the fracture) on the opposite side of the fracture. As the screw head engages the plate, it slides down the incline of the screw hole in the plate, thus causing the screw/plate interface to




Fig. 5.8 This 34-year-old woman sustained an oblique fracture of the ring finger proximal phalanx. Absolute stability was achieved through usage of multiple lag screws. Note that the screws are placed in different planes, but perpendicular to the fracture at each site.

translate toward the fracture site, leading to interfragmentary compression.

In oblique fractures (Fig. 5.13), the plate should be affixed first to the side of the fracture that allows for an acute angle (or axilla) to be created between the undersurface of the plate and the fragment. This allows for the second fragment to be compressed into the axilla, thus entrapping the fragment and assisting with reduction and compression. If the opposite sequence was done and an obtuse angle was created, further compression would lead to shortening and displacement of the fracture. An angled lag screw through the plate placed perpendicular to the fracture may be added to provide further interfragmentary compression.

Bridge plating

Bridge plating (Fig. 5.14) is a useful method of relative stability for stabilization of comminuted metaphyseal and




Fig. 5.9 Anatomy of a partially threaded screw.




Fig. 5.10 A 20-year-old woman fell onto her wrist and sustained a left scaphoid fracture. A headless compression screw is used for fixation. This device allows for interfragmentary compression while avoiding screw-head prominence when treating intra-articular fractures.




Fig. 5.11 Headless compression screw. Headless compression screws have threads with variable pitch so that the screw advances at a different rate in the proximal and distal bone fragments as the screw is advanced. This achieves compression at the fracture site without the prominence of a screw head at an articular surface.




Fig. 5.12 Compression plate. This illustration demonstrates the application of a mini compression plate to a reduced transverse fracture of the mid-metacarpal shaft. The straight miniplate has a graduated bend of about 5 degrees centered at the middle of the plate. (A) Two neutral (centered) screws secure the plate to the left (distal) of the fracture. (B) A drill hole is placed eccentrically away from the fracture site in the first plate hole to the right of the fracture. (C) A screw is inserted in the eccentric drill hole. (D) As the screw is tightened and the screw head engages the plate, translation of the plate and bone in opposite directions causes compression at the fracture site. (E) After compression is obtained, a neutral drill hole is centered in the remaining plate holes. If further compression is desired a second offset hole may be used instead. (F) A neutral screw is inserted, completing the fixation. (Redrawn from Freeland AE. *Hand Fractures: Repair, Reconstruction and Rehabilitation*. Philadelphia: Churchill Livingstone; 2000:53).




Fig. 5.13 Compression plate – compression screw (CS) within the plate. (A) Lateral view of a short oblique mid-diaphyseal metacarpal fracture in the coronal plane. (B) The fracture is reduced and a tension band plate is applied, compressing the fracture. It is essential to place the offset mini compression screw (OS) eccentrically away from the triangle of bone that is compressed into the “axilla” of the miniplate. (C) A large screw is placed across the fracture site, adding compression and stability. (Redrawn from Freeland AE. *Hand Fractures: Repair, Reconstruction and Rehabilitation*. Philadelphia: Churchill Livingstone; 2000:55).




Fig. 5.14 Bridge plate. A complicated fracture in the first metacarpal with comminution and bone loss has been excised and filled with an autogenous graft. This plate provides a modicum of compression and screws through it further stabilize the graft. (Reproduced with permission from Freeland AE, Jabaley ME, Hughes JL. *Stable Fixation of the Hand and Wrist*. New York: Springer-Verlag; 1986:248.)

diaphyseal fractures where anatomic reduction is either not possible or would require extensive dissection.³³ Ideally, the fracture site should not be opened with this technique to avoid unnecessary surgical trauma to the surrounding soft tissues and allow for the preservation of vascularity to the comminuted fragments. Bridge plates are used in a similar manner to that of an external fixator. The principal goal is to restore length, alignment, and rotation of the proximal and distal articular surfaces. Healing is indirect via callus formation. Alternatively, if inadequate bone is thought to be present to allow healing, this technique may be supplemented with a staged bone grafting procedure to stimulate healing.

Locked plating

Locking plates allow for the creation of angular stable constructs to share load across a healing fracture (see Video 5.3 ). Special threads on the screw heads themselves allow for interdigitation with threads located within the screw hole of the plate. The resultant angular stable construct is no longer reliant on screw thread purchase within bone and may present an advantage in osteoporotic bone or in low-density metaphyseal bone. Failure of this construct is not at the screw/plate interface, but rather would represent catastrophic failure of the entire construct from the bone. Furthermore, because purchase within the far cortex is not mandatory, screws may be used in a unicortical fashion, thus avoiding soft-tissue irritation in the tissues overlying the far side of the fracture.

Locked plates may be applied in a variety of methods, depending on the particular fracture pattern. Compression, if desired, may be achieved through lag screws (either outside or through the plate) or usage of non-locked eccentrically placed compression screws (depending on plate selected).

Postoperative care

Immobilization following fracture fixation may be done for several reasons including: need to protect the soft tissues during initial wound healing, desire to mitigate the possibility of secondary loss of reduction, and as treatment for associated injuries in the polytrauma patient. Immobilization, however, is not without risks. Certain joints, such as the proximal interphalangeal joints of the fingers and the elbow, are notoriously prone to problematic stiffness following immobilization.

Joint immobilization following fracture fixation may result in increased stiffness due to either tendon adhesions or capsular contraction. In the setting of articular fractures, unwanted alterations in cartilage physiology occur with immobilization. Several studies have showed a protective effect of early motion on cartilage following articular injury.^{34,35} Furthermore, some degree of micromotion across the fracture site may be beneficial for fracture healing, as illustrated in the examples of bridge plating and external fixation. This micromotion facilitates callous formation through the secondary bone healing pathway.

Where possible, fixation should be stable enough to allow for early postoperative motion without allowing unintended motion across the fracture site. The decision whether to add supplemental splint or cast immobilization following fracture fixation should consider the need for soft-tissue protection, level of stability achieved, and presence of associated injuries.

Summary

The hand surgeon must be familiar with various aspects of proper fracture care and fixation. Decisions regarding optimal treatment rely heavily on careful consideration of patient related factors and on a detailed analysis of fracture morphology. Once operative management is chosen, a myriad of options are available. Comprehensive preoperative planning should be done to shorten operative times and ensure that adequate instrumentation is available. The type of stability desired, planned operative sequence, and desired implants should all be included in the preoperative plan. A thorough understanding of the key concepts underlying proper operative fracture care aids the hand surgeon in optimizing surgical outcomes.



Access the complete reference list online at <http://www.expertconsult.com>

2. Henry MH. Fractures of the proximal phalanx and metacarpals in the hand: preferred methods of stabilization. *J Am Acad Orthop Surg*. 2008;16:586–595. *This is a concise, recent review article which summarizes many options for fracture fixation in the proximal phalanx and metacarpals with case examples.*
5. Agee JM. Distal radius fractures. Multiplanar ligamentotaxis. *Hand Clin*. 1993;9:577–585. *This classic article describes the use of ligamentotaxis in multiple planes to achieve optimal reduction of distal radius fractures. The author has developed innovative external fixators that use the concepts described in this article.*
9. Kapandji A. [Intra-focal pinning of fractures of the distal end of the radius 10 years later]. *Ann Chir Main*. 1987;6:57–63. *This is a report of some refinements to the author's originally published technique of intrafocal pinning for distal radius fractures. This is a useful technique to understand, even in this era of volar plate fixation of the distal radius.*
32. Horton TC, Hatton M, Davis TR. A prospective randomized controlled study of fixation of long oblique and spiral shaft fractures of the proximal phalanx: closed reduction and percutaneous Kirschner wiring versus open reduction and lag screw fixation. *J Hand Surg [Br]*. 2003;28:5–9. *In this prospective, randomized clinical trial, K-wiring and lag screw fixation of proximal phalangeal fractures were compared. The series is limited by the uniqueness of each fracture, nevertheless, worthwhile conclusions may be drawn from this study.*
33. Hanel DP, Lu TS, Weil WM. Bridge plating of distal radius fractures: the Harborview method. *Clin Orthop Relat Res*. 2006;445:91–99. *In this retrospective study, the authors describe their method of bridge plating of the distal radius including a summary of indications for this technique. Their experience is derived from patients in an extremely busy trauma center.*

References

- Meals RA, Meuli HC. Carpenter's nails, phonograph needles, piano wires, and safety pins: the history of operative fixation of metacarpal and phalangeal fractures. *J Hand Surg Am.* 1985;10:144–150.
- Henry MH. Fractures of the proximal phalanx and metacarpals in the hand: preferred methods of stabilization. *J Am Acad Orthop Surg.* 2008;16:586–595. *This is a concise, recent review article which summarizes many options for fracture fixation in the proximal phalanx and metacarpals with case examples.*
- Helfet DL, Haas NP, Schatzker J, et al. AO philosophy and principles of fracture management-its evolution and evaluation. *J Bone Joint Surg Am.* 2003;85-A:1156–1160.
- Wukich DK, Lowery NJ, McMillen RL, Frykberg RG. Postoperative infection rates in foot and ankle surgery: a comparison of patients with and without diabetes mellitus. *J Bone Joint Surg Am.* 2010;92:287–295.
- Agee JM. Distal radius fractures. Multiplanar ligamentotaxis. *Hand Clin.* 1993;9:577–585. *This classic article describes the use of ligamentotaxis in multiple planes to achieve optimal reduction of distal radius fractures. The author has developed innovative external fixators that use the concepts described in this article.*
- Dee W, Klein W, Rieger H. Reduction techniques in distal radius fractures. *Injury.* 2000;31:48–55.
- Dowdy PA, Patterson SD, King GJ, et al. Intrafocal (Kapandji) pinning of unstable distal radius fractures: a preliminary report. *J Trauma.* 1996;40:194–198.
- Kapandji A. [Internal fixation by double intrafocal plate. Functional treatment of non articular fractures of the lower end of the radius (author's transl)]. *Ann Chir.* 1976;30:903–908.
- Kapandji A. [Intra-focal pinning of fractures of the distal end of the radius 10 years later]. *Ann Chir Main.* 1987;6:57–63. *This is a report of some refinements to the author's originally published technique of intrafocal pinning for distal radius fractures. This is a useful technique to understand, even in this era of volar plate fixation of the distal radius.*
- Silverman AT, Paksima N. Biplanar Kapandji intrafocal pinning of distal radial fractures. *Am J Orthop (Belle Mead NJ).* 2004;33:40–41.
- Trumble TE, Wagner W, Hanel DP, et al. Intrafocal (Kapandji) pinning of distal radius fractures with and without external fixation. *J Hand Surg Am.* 1998;23:381–394.
- Athwal GS, Bueno RA Jr, Wolfe SW. Radiation exposure in hand surgery: mini versus standard C-arm. *J Hand Surg Am.* 2005;30:1310–1316.
- Giordano BD, Baumhauer JF, Morgan TL, Rechtine GR 2nd. Patient and surgeon radiation exposure: comparison of standard and mini-C-arm fluoroscopy. *J Bone Joint Surg Am.* 2009;91:297–304.
- Giordano BD, Ryder S, Baumhauer JF, DiGiovanni BF. Exposure to direct and scatter radiation with use of mini-c-arm fluoroscopy. *J Bone Joint Surg Am.* 2007;89:948–952.
- Sinha S, Evans SJ, Arundell MK, Burke FD. Radiation protection issues with the use of mini C-arm image intensifiers in surgery in the upper limb. Optimisation of practice and the impact of new regulations. *J Bone Joint Surg Br.* 2004;86:333–336.
- Soong M, Got C, Katarincic J, Akelman E. Fluoroscopic evaluation of intra-articular screw placement during locked volar plating of the distal radius: a cadaveric study. *J Hand Surg Am.* 2008;33:1720–1723.
- Bagby GW, Janes JM. The effect of compression on the rate of fracture healing using a special plate. *Am J Surg.* 1958;95:761–771.
- Perren SM, Huggler A, Russenberger M, et al. The reaction of cortical bone to compression. *Acta Orthop Scand Suppl.* 1969;125:19–29.
- Belsky MR, Eaton RG, Lane LB. Closed reduction and internal fixation of proximal phalangeal fractures. *J Hand Surg Am.* 1984;9:725–729.
- Allende BT, Engelem JC. Tension-band arthrodesis in the finger joints. *J Hand Surg Am.* 1980;5:269–271.
- Jupiter JB, Sheppard JE. Tension wire fixation of avulsion fractures in the hand. *Clin Orthop Relat Res.* 1987;113–120.
- Safoury Y. Treatment of phalangeal fractures by tension band wiring. *J Hand Surg [Br].* 2001;26:50–52.
- Pehlivian O, Kiral A, Solakoglu C, et al. Tension band wiring of unstable transverse fractures of the proximal and middle phalanges of the hand. *J Hand Surg [Br].* 2004;29:130–134.
- Lister G. Intraosseous wiring of the digital skeleton. *J Hand Surg Am.* 1978;3:427–435.
- Agee JM. External fixation. Technical advances based upon multiplanar ligamentotaxis. *Orthop Clin North Am.* 1993;24:265–274.
- Agee JM. Application of multiplanar ligamentotaxis to external fixation of distal radius fractures. *Iowa Orthop J.* 1994;14:31–37.
- Emami A, Mjoberg B. A safer pin position for external fixation of distal radial fractures. *Injury.* 2000;31:749–750.
- Eichenbaum MD, Shin EK. Nonbridging external fixation of distal radius fractures. *Hand Clin.* 2010;26:381–390, vi–vii.
- Weil WM, Trumble TE. Treatment of distal radius fractures with intrafocal (kapandji) pinning and supplemental skeletal stabilization. *Hand Clin.* 2005;21:317–328.
- Loebig TG, Badia A, Anderson DD, Baratz ME. Correlation of wrist ligamentotaxis with carpal distraction: implications for external fixation. *J Hand Surg Am.* 1997;22:1052–1056.
- Hove LM, Krukhaug Y, Revheim K, et al. Dynamic compared with static external fixation of unstable fractures of the distal part of the radius: a prospective, randomized multicenter study. *J Bone Joint Surg Am.* 2010;92:1687–1696.
- Horton TC, Hatton M, Davis TR. A prospective randomized controlled study of fixation of long oblique and spiral shaft fractures of the proximal phalanx: closed reduction and percutaneous Kirschner wiring versus open reduction and lag screw fixation. *J Hand Surg [Br].* 2003;28:5–9. *In this prospective, randomized clinical trial, K-wiring and lag screw fixation of proximal phalangeal fractures were compared. The series is limited by the uniqueness of each fracture, nevertheless, worthwhile conclusions may be drawn from this study.*
- Hanel DP, Lu TS, Weil WM. Bridge plating of distal radius fractures: the Harborview method. *Clin Orthop Relat Res.* 2006;445:91–99. *In this retrospective study, the authors describe their method of bridge plating of the distal radius including a summary of indications for this technique. Their experience is derived from patients in an extremely busy trauma center.*
- Salter RB, Simmonds DF, Malcolm BW, et al. The biological effect of continuous passive motion on the healing of full-thickness defects in articular cartilage. An experimental investigation in the rabbit. *J Bone Joint Surg Am.* 1980;62:1232–1251.
- Salter RB. The physiologic basis of continuous passive motion for articular cartilage healing and regeneration. *Hand Clin.* 1994;10:211–219.

6

The fingertip, nail plate and nail bed: Anatomy, repair, and reconstruction

Brian Mailey and Michael W. Neumeister

SYNOPSIS

- Fingertip and nail bed injuries are the most common injuries of the hand.
- Large subungual hematomas should be drained to relieve pressure and pain; small and asymptomatic hematomas (<50%) can be observed; trephination of a subungual hematoma is performed to relieve the throbbing pain associated with this injury.
- When the nail plate is intact, not all nail bed lacerations need to be repaired.
- Common secondary nail deformities seen after nail bed injury include nail ridging, splitting, nonadherence, absence, cornified nail bed, hook nails and spikes, or nail cysts.
- Knowledge of the anatomic arterial branching patterns of the fingertip allows creation of flaps to preserve length after distal fingertip amputation injuries, including the volar and lateral V-Y advancement flaps.
- In the appropriate patient, subungual melanoma *in situ* can be safely treated without amputation.
- The purpose of the current chapter is to provide the reader with a comprehensive review of the pathophysiology, diagnosis, and treatment of nail and fingertip injuries and their management.

Introduction

The fingertip serves many functions in our everyday interactions with the world. The sensation provided by the complex unit of the highly specialized immobile, glabrous skin and soft tissue pulp with the rigidity and counter pressure created by the distal phalanx, nail plate and nail bed produces tactile feedback allowing detailed sensation, proprioception, and fine object manipulation. The perionychium consists of the nail bed, nail fold, eponychium, paronychium and hyponychium. Embryologically, these structures develop near the end of the first trimester¹ as a thickened area of epidermis on the dorsal distal phalanx of each finger and toe that proximally

invades the underlying dermis to form the nail groove. The deep layer of epidermal cells proliferates to form the nail matrix. Cells within the superficial layer of the nail matrix differentiate into hard keratin, forming the nail. At approximately 14 weeks, proliferation of the deeper layers of the nail matrix pushes the nail distally across the nail bed while firm attachment is maintained between the nail and nail bed.² Folds of epidermis lateral and proximal to the developing nail form the nail folds. Nails reach the tips of the fingers and toes at about 32 and 36 weeks of intrauterine life, respectively.³

Anatomy

Surface anatomy

The topography of the nail was first described by Zaias in 1963.⁴ In this landmark study, fingers and toes of human embryos from 9-weeks to full term were sectioned and examined; and the development of the human nail was detailed. This paper began to clarify terminology of nail structures and embryology with a glossary of various fingernail structures. Later, in 1980, a standardized nomenclature for the anatomy of the nail was proposed by Zook *et al.*⁵ to improve communication between physicians regarding nail pathology, injury, and treatment (Fig. 6.1A,B). The entire nail structure, including the nail fold, paronychium, hyponychium, nail bed (germinal and sterile matrices), and nail, is referred to as the perionychium. The paronychium refers to the lateral skin surrounding the nail bed and nail. The skin over the dorsum of the nail fold is referred to as the nail wall. Extension of the nail wall distally onto the dorsum of the nail forms the eponychium. The eponychium is attached to the nail by a cornified material known as the nail vest, or cuticle. The white, convex opacity extending distally from beneath the eponychium is the lunula, which is the distal visible extent of the germinal matrix. The white color remains after removal of the nail and is thought to be secondary to retention of nuclei of the germinal cells to this level in the nail. The mass of




Fig. 6.1 (A) The nail, the sterile and germinal matrices, and the surrounding tissue marked in blue compose the perionychium. (B) A lateral view of the nail bed showing the ventral floor (germinal matrix), the nail bed (sterile matrix), and the dorsal roof of the nail fold. (C) Histologic section of the keratinous plug at the hyponychium. (© Southern Illinois University School of Medicine.)

keratin beneath the distal aspect of the nail and at the distal edge of the nail bed is the hyponychium (Fig. 6.1C), which forms from a thickening of stratum intermedium known in the embryo as the distal ridge.

The nail bed consists of the germinal and sterile matrices. The germinal matrix makes up the ventral floor of the proximal nail fold. The sterile matrix consists of the soft tissue immediately beneath the nail distal to the germinal matrix.

Vascularity

The nail unit is supplied by branches of the common volar digital arteries. As described by Flint,⁶ the digital arteries form three arterial anastomoses over the dorsal surface of the distal phalanx. A superficial arcade supplies the nail fold, and proximal and distal arcades wrap around the waist of the distal phalanx to supply the sterile matrix and the pulp space. On dissection of 10 amputated digits, Zook *et al.*⁵ found two consistent dorsal arterial branches of the digital arteries. The first branch was seen at the base of the nail fold and the second branch at the level of the lunula. Venous drainage of the perionychium coalesces laterally and dorsally, proximal to

the nail fold, drains in a random fashion over the dorsum of the digit, and becomes large enough for vessel anastomosis at the level of the distal interphalangeal joint.⁷

Lymphatics roughly parallel the veins and are most numerous at the free edge of the nail (hyponychium). The density of hyponychial lymphatics is greater than in any other dermal area of the body.⁸ This explains the low subungual infection rate, considering the heavy exposure of the hyponychial region to pathogenic organisms with use of the nails and fingertips to scratch frequently contaminated areas.

Knowledge of the anatomic arterial branching patterns allows creation of fingertip flaps to preserve length after distal fingertip amputation injuries. These local flaps will be discussed in detail later in the chapter.

Nerve supply

The common volar digital nerves branch dorsally, just distal to the distal interphalangeal joint, to supply the perionychium. Zook *et al.*⁵ reported the most common distribution of branching (70%) to be a proximal fascicle into the deep nail bed at the level of the lunula and a distal branch to the hyponychial area. Wilgis and Maxwell⁹ reported innervation by three nerve

branches including two dorsal branches, as well as a branch to the pulp.

Physiology

The hard and elastic structure of the nail plate is produced continuously by the nail matrix. The nail is transparent, however appears pink due to the presence of vessels of the underlying nail bed. Keratinization of nail matrix cells occurs along an oblique axis. As a result, the proximal part of nail matrix produces the dorsal portion of the nail plate and, when damaged, gives rise to the development of nail plate surface abnormalities, whereas the distal part of nail matrix produces the ventral portion of the nail plate.⁹ The nail plate is firmly attached to the nail bed and it detaches at the hyponychium, where its color becomes white due to the presence of air underneath.

Nail growth continues throughout life. The speed of growth increases with age until 10–14 years, at which point it becomes similar to adults, which averages about 0.1 mm a day,^{4,10} and is a rate 4× faster than toenails.¹¹ The rate of growth changes by season, with growth increased during summer months and by age. Nail growth is twice as rapid before the age of 30 years than after 80 years.¹¹ Nail growth is also affected by comorbid conditions of the individual, including endocrine, vascular, infectious, and nutritional disorders.¹² The rate of complete nail progression from the nail fold to the free margin has been reported to be between 70 and 140 days.⁴ Baden¹⁰ described a 21-day delay in growth after injury, during which time the nail thickens proximally but does not grow distally. Distal growth of a thicker than normal nail proceeds for the next 50 days; followed by growth of a thinner than normal nail for 30 days. Therefore, it is normal for an injury-induced lump to be present on the growing nail. Nail growth is not normal for approximately 100 days after injury. The nail is fixed to underlying tissues by virtue of being a continuous chain of cells from the germinal layer into the nail, each cell attached to the one in front, behind, and beside it.

The nail is produced by cells from three areas of the perionychium: the germinal matrix, the sterile matrix, and the dorsal roof of the nail fold (Fig. 6.2). The germinal matrix produces the majority of the nail volume (90%) by gradient parakeratosis.⁴ The sterile matrix and the dorsal roof of the proximal nail fold produce the remaining nail cells. The sterile matrix adds cells to the volar surface of the nail, accounting for the attachment of the nail to the matrix. The addition of ventral nail during distal growth usually results in a thicker nail distally and compensates for the dorsal wear.^{13,14} There are longitudinal ridges in the sterile matrix increasing the surface for attachment and accompany the rich, longitudinally oriented vascularized capillary network. The dorsal roof of the nail fold adds flattened cells to the dorsal surface of the nail, producing the shine of the nail.¹⁵ Loss of the dorsal roof causes a dull-appearing nail. Proximally and laterally, the nail plate is surrounded by the nail folds that are responsible for the protection of the nail matrix.

Fig. 6.2 appears online only.

Function

The function of nails was described in 1724 as “weapons to defend us from trouble ... from small creatures, that often make

their habitation upon our bodies and to allay the uneasy titillation by scratching”.¹³ Accordingly, fingernails are used for scratching and in defense. The nail protects the fingertip and contributes to tactile sensation.¹⁶ Counterforce between the nail and the volar skin and pulp aids in delicate and precise touch. Picking up small objects is difficult if the nail is absent. Two-point discrimination will frequently double when the nail is lost. However, incompletely attached or split nails are often painful, especially in individuals who work with their hands and may be worthy of removal in select situations.

Acute injury

Epidemiology

Injury to the fingertip and nail bed is the most common injury of the hand because of its prominent position.¹⁷ The long finger is most commonly injured, followed by the ring, index, small finger and the thumb, with equal frequency bilaterally. The majority of injuries occur between the ages of 4 and 30 years, with 75% occurring in males.¹⁷ Fractures of the distal phalanx are present in 50% of nail bed injuries, and most injuries occur to the middle or distal third of the nail bed.

The mechanism of injury generally constitutes a deforming force, which compresses the nail bed between the nail and the distal phalanx. A subungual hematoma results from injury to the nail bed, causing bleeding beneath the nail. Most commonly injury to the nail bed is a simple laceration (Fig. 6.3A), especially¹⁷ when the object causing the injury is small or sharp. A stellate laceration (Fig. 6.3B) occurs after compression with larger objects causing a bursting injury. Severe crush of the nail bed (Fig. 6.3C) is commonly caused by a wider, greater force of compression. Avulsion injuries (Fig. 6.3D) are the least common.¹⁷

Fig. 6.3 appears online only.

Subungual hematoma

Subungual hematoma formation causes separation of the nail from the nail bed. The pressure of bleeding in this closed space frequently results in throbbing pain. Hematoma drainage is thus indicated for pain relief.

Treatment

Drainage is performed with a heated (red-hot), sterile paper clip, battery-operated cautery, 18-gauge needle,¹⁸ or 2-mm punch biopsy^{19,20} or in children, an insulin-syringe needle may be used.²¹ The heated object burns a hole through the nail and is cooled by the underlying hematoma. The hole is made large enough to ensure prolonged drainage of the hematoma. A small hematoma will be incorporated into the nail and travel distally with nail growth. The decision to perform trephination is made by the size of hematoma and symptoms; not all hematomas require drainage.

The extent of underlying nail bed injury is difficult to assess with a subungual hematoma. Some advocate the use of ultrasound to detect nail bed injuries.²² If there is minimal disruption of the nail bed, normal nail growth is expected. However, if a significant disruption of the nail bed is present, there is higher risk of nail deformity if the nail bed is not repaired.




Fig. 6.2 Components of the nail are produced in three areas. (© Southern Illinois University School of Medicine.)




Fig. 6.3 Of nail bed injuries: (A) 36% are classified as simple lacerations; (B) 27% as stellate lacerations; (C) 22% as crushing injuries of the nail bed; (D) 15% as avulsions of the germinal or sterile matrix. (© Southern Illinois University School of Medicine.)



Fig. 6.4 11-year-old male crushed his left index finger in a fence and suffered (A) an avulsion injury of the nail plate with a stellate laceration of the nail bed in the sterile matrix with an intact germinal matrix. (B) The nail was taken off with a Freer elevator, the nail bed and hyponychium were repaired and the nail plate replaced. (C) 4 months after injury and repair (left index finger) compared to the uninjured right index fingernail.

Therefore, whether a subungual hematoma should be drained with the nail left intact or the nail removed and the nail bed repaired is debatable. In the past, removal of the nail for inspection of the nail bed with repair, as needed, was advocated for hematomas undermining more than 25% of the nail. Simon and Wolgin²³ examined the nail beds of 47 patients presenting to the emergency department with a subungual hematoma and found that a hematoma >50% had a 60% incidence of laceration requiring repair. Repair of the nail bed was advocated with a hematoma >50% and an associated distal phalanx fracture. At the University of Pittsburgh, a 2-year prospective, observational study was designed to examine the outcome of 48 patients with subungual hematomas treated with drainage alone. No complications of nail deformity were found with this treatment, regardless of the size of hematoma or presence of fracture.²⁴ Roser and Gellman²⁵ compared three treatment groups in a prospective study of 52 children with subungual hematomas. A total of 26 fingers were treated with nail removal and repair of the nail bed. Drainage only was performed in 11 fingers, and 16 of 27 fingers were observed. No notable difference in outcome was found between the groups, regardless of hematoma size. It was concluded that nail removal and nail bed exploration are not justified in children with subungual hematoma with an intact nail and nail margin. A systemic review in 2012 evaluated four articles comparing nail bed repair with simple decompression and concluded the outcome of nail cosmesis did not differ by the mode of treatment.²⁶ Leaving the nail in place is recommended for most subungual hematomas with an intact nail. Exceptions may include children or patients with concern for an optimally aesthetic nail. If the nail is broken or the edge disrupted, removal of the nail and exploration of the nail bed are advised (Fig. 6.4). The acutely painful subungual hematoma should be decompressed, whether done by trephination or nail removal.

Hints and tips

Nail bed repair

The nail bed handles like wet tissue paper; each suture should be thrown with two bites. Be conservative with the placement of sutures. The goal is simple – re-approximation. Tension on the nail bed suture line will lead to excessive scarring.

Lacerations

Avulsion of the nail, or nonadherence of the nail to the nail bed, is an indication for nail removal. Any loose nail should be trimmed and only enough of the nail that allows adequate exposure and repair of the nail bed laceration should be removed. Complete removal of the nail is not always necessary. With middle to distal nail bed injuries, it may be possible to leave the proximal nail undisturbed within the nail fold.

Treatment

Exploration of the nail bed is performed with digital block, anesthesia, and tourniquet (e.g., a half-inch Penrose drain or cut-out from a sterile glove). The nail plate is gently removed from the nail bed with a small periosteal elevator or iris scissors. Careful removal of the nail is important to avoid further injury to the nail bed. Once removed, the nail is scraped to remove residual soft tissue, then soaked in povidone-iodine (Betadine) solution. The nail bed is examined with loupe magnification. It is better to leave ragged edges and allow the replaced nail to mold the edges than to debride and cause tension on closure. Careful undermining of the edges may assist in reducing tension on closure. A double-armed 7-0 chromic suture on an ophthalmic needle is recommended.




Fig. 6.5 (A) When the proximal nail is flipped out of the nail fold and is lying on top of it, one must remove the nail and explore the nail bed. (B) There is almost always a nail bed laceration with stripping of the germinal matrix up with the nail or a Salter fracture of the distal phalanx. (C) The laceration must be replaced and repaired. (D) Radial incisions are made in the eponychium to access the nail fold. It is almost impossible to replace the nail in the nail fold without its total removal and then sliding it back. (© Southern Illinois University School of Medicine.)

The suture is cut in half to provide a second stitch because the small needle is commonly bent during the repair.

Re-approximation of the more complex stellate laceration and crush injury is more difficult. In these types of injuries, it may appear to be missing fragments. However, they are often present, attached to the undersurface of the nail. Small fragments should be gently removed with a periosteal elevator and used as a nail bed graft. A split- or full-thickness nail bed graft up to 1 cm in diameter will usually survive, even when it is placed directly on the distal phalanx cortex.⁶ Blood supply to the graft is established by inosculation and vascular ingrowth from the periphery.

The scenario with nail bed fragments attached to the nail commonly occurs in avulsion type of injuries. To avoid further insult to the nail bed, leaving the large nail bed fragment on the nail is recommended. The edges of the nail are trimmed a few millimeters to expose the nail bed for suturing into the defect.

Avulsion of the bed often occurs at the level of the germinal matrix and proximal nail fold, leaving a distally based nail bed flap of germinal or sterile matrix (Fig. 6.5A). The nail bed remains attached to the nail, avulsing the germinal matrix off the bone and out of the nail fold (Fig. 6.5B). The nail and germinal matrix must be separated and the germinal matrix replaced and sutured back into the nail fold (Fig. 6.5C). The nail fold is exposed with unilateral or bilateral incisions perpendicular to the lateral corners of the eponychium. The incisions should be made at a 90° angle to the eponychium to prevent a notch deformity (Fig. 6.5D). If the laceration occurs at the junction of the ventral and dorsal roof of the nail fold, suture approximation may not be possible. In this case, a horizontal mattress stitch is placed through the proximal end of the avulsed nail bed and brought out through the nail wall.

This will secure the nail bed within the nail fold. The eponychial incisions are then re-approximated with 5-0 or 6-0 nylon after nail bed repair.

Loss of small areas of nail bed may be replaced with split-thickness nail bed grafts from adjacent uninjured nail bed, harvested carefully with a No. 15 scalpel blade (Fig. 6.6A,B). A split-thickness nail bed graft may be harvested from an adjacent noninjured finger (risky) or an amputated finger. A split toenail bed graft may also be used acutely and avoids the possible deformity of an adjacent nail (Fig. 6.6C–H).²⁷ With exception of the great toe, the nail bed from the other toes are not large enough to supply enough graft for an entire finger nail bed.

On completion of the nail bed repair, the nail is removed from the povidone-iodine solution and a hole made in the nail away from the site of injury. The hole allows drainage of the subungual space after reinsertion of the nail into the nail fold. The nail is placed within the nail fold to mold the edges of the repair, to act as a splint for tuft or phalangeal fractures, to prevent formation of synechiae between the nail fold and the injured nail bed, and to protect the tender fingertip. The nail is held in place with a 5-0 nylon suture placed distally through the nail and hyponychial region. On rare occasions with severe injury to the fingertip, a mattress suture may be placed proximally through the nail fold. If the nail is not available or is in small fragments, a piece of silicone sheeting (reinforced 0.020-inch-thickness silastic) may be shaped to fit beneath the nail fold and secured proximally through the nail fold (Fig. 6.7). Unlike the nail, the silastic sheet is soft and easily slips from beneath the nail fold if it is secured only distally. Non-adherent gauze may also be placed within the nail fold if no nail or silicone sheet is available.

Fig. 6.7 appears online only.



Fig. 6.7 An example of a stitch in the silicone sheeting to hold it in place.
(© Southern Illinois University School of Medicine.)




Fig. 6.6 (A) A crushing injury to the tip of the finger with laceration of the surrounding skin. (B) After the skin is sutured, an area of cortex is seen. (C) A split-thickness sterile matrix graft is removed from an adjoining area on the finger or toe. Back-and-forth sawing with a scalpel blade will remove a small fragment of nail bed, which is slightly curved after the nail has been removed. The white line of the sharp edge of the blade should always be able to be seen so that the graft is not taken too thick with a resultant deformity. (D) The fragment of nail bed taken. (E) If a larger piece of nail bed graft is needed, it may be taken from proximal to distal; the tip of the knife blade is used to dissect up the split-thickness layer of nail bed. (F) The large toe after removal of the split-thickness nail bed graft. (G) A split-thickness nail bed graft is sutured into place over the periosteum without any manipulation of the cortex. (H) One year later, good regrowth of the nail and adherence are shown. (© Southern Illinois University School of Medicine.)

Hints and tips

Nail plate replacement

Trim the nail plate of sharp contours. Place the nail plate under the eponychial fold for a distance of 2–3 mm. An absorbable suture can be used to hold the nail plate in place as an alternative to nylon. This will avoid painful suture removal.

Postoperative care

The fingertip is dressed with nonadherent gauze, 2-inch roll gauze, and a four-prong splint to protect the repair. At 3–7 days after repair, the holding suture is removed, especially if it is in the proximal nail fold position. The authors have observed stitch track formation in the nail fold if the stitch is

left in place longer than 7–10 days. If not disturbed, the nail will frequently adhere to the nail bed for 1–3 months as the new nail forms beneath. Fingertip tenderness is usually less with the nail replaced.

Distal phalanx fractures

Initial evaluation

Distal phalanx fractures are found in approximately 50% of nail bed injuries and result in a higher incidence of secondary nail deformities.¹⁷ Therefore, multiple-view radiographs of the distal phalanx are recommended. A Seymour fracture presents in children with the appearance of an elongated nail. The fracture occurs through the physis with interposed soft tissue, usually consisting of nail bed matrix but can include other tissues, like eponychial fold.

Treatment

Treatment of nondisplaced distal fractures consists of nail bed repair and replacement of the nail. The nail acts as an excellent splint for the fracture. Small, displaced tuft fractures and most stable distal fractures can be reduced with reapproximation of the nail bed and replacement of the nail. Larger displaced fractures or unstable fractures require longitudinal or cross K-wire fixation. Care must be taken to put the pin in the medullary cavity of the bone. K-wires traversing the nail bed can cause a painful ridging deformity.

Secondary procedures

Reconstruction

The painful non-adherent, split, or hooked nail, may hinder work productivity in the laborer. For others, nail deformities, such as nail ridges, grooves, or absence of the nail may create self-consciousness or an unsightly appearance. Goals for reconstruction should be based on concerns and wishes of the individual patient. Surgical measures often improve function and appearance but often do not produce a normal nail. The best chance for restoring a normal nail is at time of the initial repair.

Most nail deformities are secondary to scarring of the nail bed with subsequent disruption of nail growth. Similar to other scars, it is recommended to wait at least 8–12 months after injury before consideration of reconstruction. With scar remodeling, small nail deformities may resolve significantly or completely. Common secondary nail deformities seen after nail bed injury include nail ridging, splitting, non-adherence, absence, cornified nail bed, hook and spikes, or cysts.

Nail ridge

Nail ridges are secondary to an irregularly healed distal phalanx fracture or scar within the nail bed. Nail ridges may also occur secondary to a K-wire placed between the sterile matrix and the periosteum on reduction of a phalanx fracture (Fig. 6.8). Longitudinal irregularities result in longitudinal ridges or grooves. Transverse irregularities beneath the nail bed result in corresponding transverse grooves or ridges or distal nonadherence. Correction of this deformity requires excision of the scar or irregular bone edge to form a flat, smooth nail bed surface.^{6,16} A defect that cannot be reapproximated primarily requires use of a nail bed graft.

Fig. 6.8 appears online only.

Transverse nail ridges may develop secondary to hypoxia from ischemic injury or tourniquet hemostasis. The ridges resolve with correction of the inciting factor and subsequent new nail growth.

Split nail

A split nail is often secondary to longitudinal scarring of the germinal or sterile matrix. Unlike the germinal and sterile matrices, the scar does not produce nail cells, resulting in splitting of the nail. Scar within the germinal matrix can split the nail from its most proximal aspect. Scar within the sterile matrix disrupts the progressive addition of nail cells to the volar nail, leading to detachment of the nail plate (Fig. 6.9). Other causes of split nails include bone spurs beneath the nail bed, eponychial pterygium resulting from failure

of the dorsal roof matrix to detach from the nail, and scar formation between the dorsal roof and ventral floor of the nail fold. Although longitudinal splits are most common, a horizontal split has been reported; it caused a diagonal scar in the matrix and formation of a portion of the nail on each side (Fig. 6.10). The nail was produced within both folds, forming a horizontally split nail.

Figs. 6.9 and 6.10 appear online only.

Treatment

Scar must be minimized to allow normal nail production. Scar within the sterile matrix can occasionally be treated with excision and primary closure. The excised defect is frequently too wide to be approximated without tension and requires repair with a split-thickness sterile nail bed graft from the same digit or a toe. In germinal matrix injuries, Johnson²⁸ recommended releasing incisions in the lateral paronychia folds with bilateral central advancement of the germinal matrix, but our experience with this technique has been disappointing in traumatic deformities. Replacement of germinal matrix with sterile matrix will not be successful because sterile matrix grafts do not produce a nail. Split-thickness germinal matrix grafts also do not produce hard nail growth. The germinal matrix defect requires repair with a full-thickness germinal matrix nail bed graft.^{27,29} The second-toe germinal matrix is a good option with its similar shape and size; the large toe is a second choice (Fig. 6.11). The patient is warned that use of the toenail germinal matrix will eliminate hard nail growth on the toe. This second-toe nail defect is frequently more acceptable to patients than a defect of the great toenail. In the case of an existing bone spur, the nail bed is lifted free and the spur is removed with rongeurs to produce a flat surface, and the nail bed is replaced.

Pterygium

Splitting of the nail may also be caused by a pterygium. A pterygium of the eponychium results from adherence of the eponychium or dorsal roof of the nail fold to the nail plate or nail bed during healing. A web between the eponychium and nail bed will result in splitting of the nail as it grows distally from the nail fold (Fig. 6.12).

Fig. 6.12 appears online only.

Treatment

Simple pterygia are amenable to warm water soaks until the eponychium can be bluntly separated from the nail. Sharp dissection of the eponychium from the dorsal nail is performed if blunt dissection is unsuccessful. Separation between the dorsal roof and nail is then maintained with nonadherent gauze or a silastic sheet. This allows epithelialization of the undersurface of the nail fold. If adherence persists between the dorsal roof and the ventral floor (matrix) of the nail fold, it must be divided surgically. Once the nail fold has been redesigned, maintenance of the separation must be achieved with nail, silicone sheet, or gauze until healing occurs. If a large raw surface is present after freeing, a split-thickness sterile matrix graft can be placed on the raw surface of the dorsal roof. If the scar has completely replaced the normal germinal matrix, a full-thickness germinal matrix graft is necessary.



Fig. 6.8 A longitudinal pin was placed to maintain fracture reduction but was between the periosteum and sterile matrix, causing scarring in the ridge.
(© Southern Illinois University School of Medicine.)



Fig. 6.9 (A) A split nail may occur within the sterile matrix with minimal problems. **(B)** An injury to the germinal matrix can cause a split in the entire nail, causing significant pain secondary to trauma and disfigurement. (© Southern Illinois University School of Medicine.)




Fig. 6.10 (A) A horizontal laceration in the sterile matrix with a resultant transverse scar can cause a separation so that two nails grow out. If the volar nail is adequate, surgical removal of the dorsal nail-producing matrix will correct the problem. (B) The patient's index finger postoperatively. (© Southern Illinois University School of Medicine.)




Fig. 6.12 (A) A split of the nail due to scarring between the dorsal roof and the ventral floor of the nail fold. (B) End-on view of the nail deformity. (C) With the two portions of nail removed, the cicatrix between the dorsal roof and the ventral floor of the nail fold can be seen. (D) The cicatrix is divided with the resultant defect on the dorsal roof. (E) A split-thickness sterile matrix graft is removed from the sterile matrix and sutured in place on the dorsal roof of the nail fold. (F) One-year follow-up with an improved appearance and reduced functional problems. (G) An end-on view of the nail demonstrating the improved contour. (© Southern Illinois University School of Medicine.)




Fig. 6.11 (A) Avulsion of a portion of the germinal matrix with a split nail. (B) The sterile matrix has been reapproximated after resection of the scar, and a toe germinal matrix graft is shown before insertion in the germinal matrix. (C) Insertion of the germinal matrix graft as a free graft into the sterile matrix. (D) At 6 months, the graft of germinal matrix is shown to be growing nail. (© Southern Illinois University School of Medicine.)

Nonadherence (onycholysis)

Nonadherence of the nail is the most common post-traumatic nail deformity. This occurs secondary to nail bed scarring and is often found immediately distal to transverse or diagonally oriented nail bed scars or bone irregularities. The scar interrupts the progressive addition of nail cells from the sterile matrix to the volar nail plate, causing detachment of the nail. The nail is unable to reattach to the nail bed distally.³⁰

Distal nonadherence may lead to problems with subungual hygiene, an unstable nail when picking up small objects, pain from repeated avulsions when catching the nail on objects, or may simply be an aesthetic concern.

Treatment

Nonadherence secondary to a nail bed scar is corrected with scar excision and primary closure or closure with a split-thickness sterile matrix graft from the adjacent nail bed or toenail bed.^{30–32}

Malalignment of distal phalanx fractures may cause nonadherence. Prevention begins with accurate alignment of the fracture at initial repair. Secondary deformities caused by bone exostosis, bone angulation, or nonunion will require revision. The exostosis should be removed to form a flat surface for the sterile matrix and subsequent nail adherence. Bone angulation may require osteotomy of the distal phalanx to re-form a flat surface.

Nail absence (anonychia)

Any process, including trauma, infection, and burn, which destroys the nail matrix will lead to an absent nail. Frequently, small nail remnants will remain that can cause other secondary deformities. Nail absence is also rarely seen as a congenital deformity known as *anonychia*.

Treatment

Free partial and composite nonvascularized nail grafts have been described by McCash³³ and Lille *et al.*³⁴ for

reconstruction of absent nails. Both germinal and sterile matrices are needed for total reconstruction of a nail bed. Zook recommended a full-thickness second-toe germinal and sterile matrix graft to approximate the width of the fingernail. To match the length of the fingernail, a split-thickness sterile matrix graft from another toe is placed distal to the free composite graft. The large toenail is used for thumbnail reconstruction. Results can be unpredictable and at times unsuccessful secondary to nontake or shrinkage of the graft. Patients should be informed of the risk of toenail deformity and a possible suboptimal outcome.

The most reliable and normal-appearing nail is constructed with a free vascularized dorsal tip of the toe.^{35–38} This procedure can be technically difficult, requiring microsurgical expertise, and produces scarring of the foot from harvest of the vascular pedicle.

Skin grafts, as opposed to nail bed grafts, have been used with some success to mimic the nail. This method has been advocated for treatment of traumatic nail absence and congenital nail absence in which multiple digits are involved (Fig. 6.13). The scar is excised from the fingertip in the shape of a larger than normal nail (10% larger), and replaced with a similarly shaped split- or full-thickness skin graft. Full-thickness grafts can be placed proximally and distally to simulate a white lunula and hyponychia, respectively. An artificial nail can then be fixed to the healed skin with glue, but patients may have difficulties maintaining the nail in place with glue alone. To aid in nail adherence, Bunke and Gonzales³⁹ reconstructed the proximal fold using a prosthesis wrapped in split-thickness skin graft and buried it under the dorsal finger skin. Artificial nails were then secured beneath the new fold. Unfortunately, the fold was only temporary and slowly disappeared with time. Baruchin *et al.*⁴⁰ described an osseointegrated anchorage device to secure the artificial nail.

Cornified nail bed

With ablation of the germinal matrix, nail production ceases. However, an intact sterile matrix will continue to produce



Fig. 6.13 A nail-shaped split-thickness skin graft is placed on the dorsum of the finger to mimic a nail. (© Southern Illinois University School of Medicine.)

varying amounts of keratinous material, resulting in a cornified nail bed.

Treatment

Treatment for a cornified nail bed includes excision of the sterile matrix and replacement with a split-thickness skin graft. Overproduction of keratinous material from the sterile matrix can also occur beneath a nail from chronic repetitive partial avulsion, allowing build-up beneath the distal nail, leading to nonadherence. Treatment includes removal of the nail to a point just proximal to this area of overproduction. The keratinous material is scraped from the nail bed with a scalpel blade. The nail is then able to adhere to the nail bed during distal growth. The process may need to be repeated if overproduction on the exposed nail bed occurs more quickly than nail growth (Fig. 6.14). Sterile matrix grafts may be necessary if scraping is unsuccessful (Fig. 6.15).

Figs. 6.14 and 6.15 appear online only.

Nail spikes and cysts

On elimination of the nail bed or amputation of the distal phalanx, care must be taken to excise the germinal matrix completely. Any residual matrix allows continued production of nail cells. These cells produced within a closed space form nail cysts and the cells that are able to grow distally form nail spikes.

Treatment

Treatment consists of complete surgical removal of the cyst or spike along with the residual matrix. These deformities are

seen more commonly after revision amputations performed in the emergency department.

Hooked nail

The hooked nail is a nail that hooks volarly during distal growth. This deformity is commonly seen after tight closure of tip amputations. On closure, the nail bed is pulled around the tip of the finger. Healing of a distal amputation site by secondary intention may also pull the nail bed volarly over the tip. Because the growing nail follows the direction of the nail bed, the nail grows in a hooked fashion, curving around the fingertip.

Treatment

This deformity can be avoided during repair of the acute injury by following two rules. The nail bed should never be pulled over the tip of the distal phalanx. If bone support beneath the nail bed is missing, it must be replaced or the nail bed shortened to match the length of the remaining distal phalanx.

Correction of the hooked nail secondary to the distal nail being pulled over the tip comprises release of contracted soft tissue, return of the nail bed to its normal position, and replacement of fingertip soft tissue. A full-thickness skin graft, V-Y advancement flap, cross-finger flap, or proximal thenar crease flap can be used to augment the tip and reposition the nail bed on the dorsum of the distal phalanx.⁴¹ When bony support is missing, the options are either to shorten the nail bed or add bony support to maintain length. Non-vascularized bone grafts have been placed distally with successful initial support of the nail bed. However, they often resorb with time, and the correction is lost.⁶ Osteotomy and distraction of the distal phalanx with placement of a bone graft between the distracted segments has been proposed to decrease the incidence of graft resorption but may be technically difficult.

Bubak *et al.*⁴² described a repair of a hooked nail deformity using a composite second-toe graft for tip support. A fish-mouth incision is made in the hyponychium and carried proximally on the lateral aspects of the digit until the nail bed is released. An elliptical, transverse wedge of skin and pulp is excised from the second toe and placed beneath the released nail bed. Good results were reported with a 2-year follow-up.

Free vascularized second-toe tip (bone, soft tissue, and nail bed) transfer has been presented as a more permanent yet more complex option.³⁶

Eponychial deformities

Eponychial deformities occur as sequelae after trauma, burns, tumor, infection or any process causing direct destruction of the nail fold tissue. As the tissues heal, scar contractures create the final deformity. Loss of eponychium causes more of an aesthetic defect than a functional one. Notching or loss of the eponychium exposes more of the proximal nail and results in loss of nail shine. Despite this change in appearance, there is no effect on nail growth.

Treatment

The three-dimensional structure of the nail fold makes reconstruction difficult. Multiple local rotation flaps have been




Fig. 6.14 (A) Nonadherence of nail to the sterile matrix thought to be due to an episode of pulling the nail free from the nail bed traumatically and then repeated attempts to clean under the nail. The area of nonadherence is marked on the nail. (B) That area of nail is removed, showing the hyperkeratinous sterile matrix. The hypertrophic keratinous material is scraped off with a scalpel blade to bare the vascular sterile matrix. (C) The patient 1 year later with improved adherence of the nail. (© Southern Illinois University School of Medicine.)




Fig. 6.15 (A) Nonadherence of the nails to the nail bed after a crushing injury and then application of artificial nails. The cause of the detachment could be either of these. (B) A split-thickness sterile matrix graft from the large toe donor site is placed over the defect. (C) The patient 1 year later with much improved attachment. (© Southern Illinois University School of Medicine.)



Fig. 6.16 (A) Loss of eponychium secondary to trauma with resultant irregularity and roughness of the nail. (B) One year after a full-thickness composite graft of second-toe dorsal roof transfer to the finger. Note the improvement in the contour and shine of the dorsum of the nail. (C) The eponychial graft was taken from the second toe and here shows essentially no deformity. (© Southern Illinois University School of Medicine.)

described. Reconstruction of a nail fold with both inner and outer surfaces has been described with use of rotation flaps lined with split-thickness skin grafts.¹⁶ Hayes⁴³ used distally based ulnar finger flaps for creation of the nail fold without reconstruction of the inner surface. Kasai and Ogawa⁴⁴ modified Hayes' technique of distally based ulnar finger flaps by using the local tissue to reconstruct the inner surface. The scarred eponychial tissue is incised proximally and turned over distally to form the nail roof. An ulnar, dorsal flap is then raised on a distal base and placed on top of the new roof to form the new eponychium, with split-thickness skin grafting of the donor site. Achauer and Welk⁴⁵ described a one-stage reconstruction of the burn-scarred eponychium with dorsal transposition of bilateral proximally based lateral digit flaps.

A composite eponychial graft of skin and dorsal roof from the first or second toe to the eponychial defect is recommended. This eponychial graft has been found to improve appearance and restore the shine to the nail (Fig. 6.16).

The eponychial flap is a technique used for fingertip injuries when the eponychium is intact. This flap lengthens the appearance of the visible nail. It was first presented in 1998 by Bakhach⁴⁶ and is indicated for fingertip injuries with a resultant small stump of intact nail and nail bed. The procedure consists of incising the dorsal eponychium with two radial incisions, elevating the dorsal eponychium as a flap and suturing it down in a more proximal location. This can be done at the time of acute injury or as a later reconstructive procedure.⁴⁷

Hyponychial defects

The keratinous plug of the hyponychium may hypertrophy secondary to acute or chronic trauma to the distal nail and hyponychium. When this occurs, it may protrude beyond the nail and cause pain when it is bent or pressed with use of the finger. It may also produce an unsightly protrusion from under the nail (Fig. 6.17). Loss of the hyponychium results in lack of support of the nail and a hook nail deformity. To prevent hygiene and cosmetic issues, patients must keep their

nails trimmed. Alternatively, further shortening of the digit or nail bed ablation would be required.

Fig. 6.17 appears online only.

Treatment

Treatment for the hypertrophic hyponychium requires determination of the inciting activity, which is often something that causes acute or chronic irritation. Initial management consists of avoidance of process producing the pathology. If irritation cannot be avoided or if symptoms persist despite avoidance, excision of the hypertrophic hyponychium and coverage with a split-thickness sterile matrix graft have resulted in a high incidence of symptom relief. The split-thickness sterile matrix graft is carried out in the same manner as with replacement for avulsion of a portion of the sterile matrix or scar excision.

Pigmented lesions

The differential diagnosis for pigmentation of the nail bed is complex; it includes subungual hematoma, foreign body, onychomycosis nigricans, junctional nevi, pyogenic granuloma, paronychia, vascular lesion, melanonychia striata, melanoma *in situ*, and malignant melanoma.⁴⁸ Although most pigmented lesions of the nail are benign, they should be evaluated carefully to rule out malignancy.

Patient presentation

The history of the pigmentation is generally the most valuable aspect to making the diagnosis. Trauma may cause bands of pigment, especially in darkly pigmented individuals. Development of pigment in adults, even without a known history of trauma, is often secondary to a subungual hematoma, but the differential diagnosis of malignant melanoma must be considered. These suspicious areas can be monitored by scratching the nail at the proximal and distal edges of the pigment with a scalpel blade or 18-gauge needle (Fig. 6.18).




Fig. 6.17 (A) A hypertrophic hyponychium (arrowhead) causing pain and discomfort with upper traction on the nail. (B) Dorsal view of the same patient. (C) Same patient with relief of pain after resection of the hypertrophic hyponychium and a split-thickness sterile matrix graft in its place. (D) Same patient, dorsal view with hyponychial attachment. (© Southern Illinois University School of Medicine.)




Fig. 6.18 (A) A swollen, inflamed paronychia known as a paronychia. (B) The side of the nail, which is undermined by the infection, is separated from the nail bed and the lateral aspect of the dorsal roof of the nail fold. (C) This fragment of nail is removed, giving adequate drainage to the infection. (D) A piece of water-soluble gauze is placed as a drain. (© Southern Illinois University School of Medicine.)

Distal migration of pigmentation over 3–4 weeks, together with the scratch marks suggests a hematoma. However, if the scratch marks move distally, away from the pigment, this suggests foreign body, nevus, or melanoma. The evaluation of nail clippings can also provide some diagnostic value.⁴⁹ To do this, a sample at least 4 mm in length is required and can be used to diagnose a number of conditions, including melanonychia, subungual hematoma, onychomycosis and others.⁴⁹

Melanonychia striata is defined as any linear tan–brown–black pigment of the nail bed that is carried into the nail as growth occurs. This pigmentation is caused by focal increase in the number or function of melanocytes. Melanonychia striata is common in individuals with darkly pigmented skin but uncommon in those with fair skin (Fig. 6.19).

Subungual nevi produce pigmentation within the nail bed and the ventral nail (Fig. 6.20). These pigmented nevus cells are derived from neural crest cells and are frequently present at birth or shortly thereafter. The nail is frequently pigmented with elevation and ridging (Fig. 6.21).

Fleegler and Zeinowicz⁵⁰ recommended nail bed biopsy of dark streaks present at or shortly after birth because of the danger of malignant degeneration at puberty. Melanocytic hyperplasia without atypia can be observed. However, complete excision with reconstruction of the nail bed is advised if atypical cells are found.

Subungual melanoma

Nail melanoma is an infrequent cause of brown–black nail color compared to other melanocytic and nonmelanocytic pigmentations. More common causes of nail discoloration are subungual hematoma, exogenous pigmentations and melanonychia, which are all benign. In a review of 100 patients seen at a dermatology clinic for nail discoloration, 25 required additional evaluation, but only one had a melanocytic pigmentation that required a surgical evaluation.⁵¹ Most lesions can be diagnosed by history alone. The first determination is to decide if the pigment is due to melanin within the nail. This step can help exclude exogenous pigmentations, fungal melanonychia and subungual hematoma. Examining the other digits can reveal racial melanonychia, effects of systemic

drugs or pregnancy, endocrine disorders and frictional melanonychia. Next, the appearance of the nail itself can provide diagnostic information, including trauma, psoriasis and nail tumors (onychopapilloma, onychomatricoma, Bowen's disease). Nail clippings can also be used to assist in the diagnosis. Finally, if the diagnosis has not been determined then removal of the nail plate and a histopathologic evaluation of tissue is required.⁵¹

Subungual melanoma represents only 1–2% of all cutaneous melanoma and usually affects the thumb or big toe.⁵² An




Fig. 6.19 Scratching of the nail proximal and distal to the pigment to determine whether the pigment is in the nail or in the nail bed. (© Southern Illinois University School of Medicine.)



Fig. 6.20 The melanocytic streaks in an African American patient after trauma to the perionychium (arrowhead). (© Southern Illinois University School of Medicine.)

important clinical clue to subungual melanoma is characterized by extension of brown or black pigment from the nail bed, matrix and nail plate to the adjacent cuticle and proximal or lateral nail folds; this is known as Hutchinson's nail sign. There are two stages to melanoma growth. The first stage is



Fig. 6.21 A newly occurring pigmented streak that originates in the germinal matrix or proximal to the observable pigment. (© Southern Illinois University School of Medicine.)

superficial, radial growth under the nail plate, followed by a vertical growth. At this stage, the lesion begins to develop a more dramatic change in appearance.

Treatment

The historic standard treatment recommendation for subungual melanoma has been *en bloc* partial or complete digit amputation. This strategy was considered the safest means of obtaining clear margins, preventing recurrence and metastasis. This rationale, however, was not based on clear scientific evidence, but rather the principles of wide excision for what was thought to be an aggressive malignancy. Current evidence suggests this disease is not more aggressive than their more common cutaneous counterpart of similar depth.^{53,54} The original evidence to support these recommendations came from Das Gupta *et al.* in 1965.⁵⁵ They presented 34 patients with subungual melanoma treated with amputation at different levels. Three patients who underwent a less aggressive form of amputation recurred and subsequently died from their disease. On the basis of these findings, it was determined that local amputation was not an adequate resection. However, it should be noted that they did not present the depth of these lesions and half of the patients in the study were being treated for recurrent melanoma or already had regional lymph node metastases at time of treatment. Therefore, the conclusions derived from Hutchinson's and Das Gupta's findings regarding aggressive amputation are not appropriately supported by their evidence.

Today, interphalangeal joint amputations are the most commonly performed treatments for this disease. However, digit sparing procedures in appropriately selected cases have also been successfully performed. The precedent for digit sparing came from a study in 1992 by Park *et al.*⁵⁶ In this manuscript, the authors treated subungual melanoma *in situ* without amputation. This was followed by a number of series in the literature presenting similar experiences with variable results, but not infrequent recurrence. Today, it seems wide excision can be an option for patients with melanoma *in situ*. However, they should be followed closely for signs or disease recurrence. For a complete discussion and further in-depth review of available literature, a manuscript presented by Cochran *et al.* in the August 2014 issue of *Plastic and Reconstructive Surgery* is available for the reader.⁵⁷

Pincer nail

Pincer nail deformity is described as lateral hooking or excessive transverse curvature of the nail plate, unilaterally or bilaterally (Fig. 6.22). The progressive tubing of the nail eventually pinches off the nail bed and hyponychium, resulting in an unaesthetic, painful nail. Pincer nail is most commonly seen in middle-aged to elderly women. The cause of the pincer nail is not known.

Treatment

Previous treatments have included resection of a wedge of the phalanx to flatten the nail edges and release of the nail bed with a medial longitudinal nail bed incision and split-thickness skin graft coverage of the resultant triangular defect.⁵⁸ They have been largely unsuccessful. Brown *et al.*⁵⁹ have advocated the use of dermal graft strips between the lateral nail bed and




Fig. 6.22 (A) Unilateral pincer nail deformity. (B) The perionychium is freed from the bone, and a graft of dermis or dermal substitute is placed into the tunnel to flatten the nail bed. (C) One year after correction. (© Southern Illinois University School of Medicine.)

the distal phalanx periosteum for elevation of the lateral borders of the nail bed. The nail is removed, and incisions are made at the tip of the digit to allow freeing and elevation of the paronychia folds from the periosteum. The dermal grafts are placed within this space to maintain the elevation and to flatten the nail bed. Our preferred technique is a modification of this, using human acellular dermal matrix in place of autologous dermal strips. We have achieved equally good correction of pincer nail without the addition of an additional donor defect.

In more severe cases, the pain from a pincer nail deformity may be severe enough to warrant surgical ablation of the nail bed, especially if other forms of reconstruction are unsuccessful.

Reconstruction of fingertip injuries

Reconstructing defects on the fingers requires thorough knowledge of a variety of coverage options. Treatment possibilities range from simple, including an occlusive dressing to allow healing by secondary intention, to extremely complex, including free pulp transfer. As the surgeon considers each possibility to obtain definitive closure, one must also integrate the priorities of function, contour, stability, and the anticipation for further reconstructive surgery. The reconstructive decision is based on characteristics of the defect, including

size, shape, location and availability of donor sites. Age, occupation and individual attributes of the patient ultimately play the largest role in appropriate selection of the reconstructive plan. The final decision is made by the patient, however the surgeon may affect this choice. A recent survey sent out to American Association for Hand Surgery members revealed US and private practice physicians were less likely to perform replantations than academic or international centers.⁶⁰ For soft-tissue fingertip injuries, local flaps were preferred over secondary intention or skin grafts more commonly in surgeons with a plastic surgery background or with more than 30 years of experience.⁶⁰ Younger surgeons were also more likely to perform skeletal shortening than those with more than 5 years' experience.⁶⁰

The Allen classification⁶¹ is commonly used to describe the level of fingertip injury, as thought of in a transverse amputation. Type 1 injuries involve the pulp only. A type 2 injury also involves the nailbed. Concomitant distal phalangeal fractures with associated pulp and nail represents a type 3 injury and the type 4 injury occurs more proximal with involvement at the level of the lunula.

Reconstructive principles

The principles of wound management in the traumatized digit or hand are the same basic guidelines that apply to the rest of the body and include irrigation, debridement, and

restoration of vascularity. Stabilization of fractures and repair of specialized tissues such as nerve and tendon become the second priority, followed by the definitive soft-tissue coverage. The skin of the hand and the fingers varies from palmar to dorsal sides. The palmar aspect is covered with glabrous skin notable for its limited sheer, high friction coefficient and papillary ridges, which create the characteristic fingerprint. Numerous fibrous septae compartmentalize subcutaneous tissue of the palm with fibers from the underlying dermis to the musculoskeletal structures below. The midaxial line of each digit is formed by connecting the lateral volar finger crease at the distal interphalangeal joint (DIP), proximal interphalangeal joint (PIP) and metacarpal phalangeal (MCP) joint. It is at this line that the transition from the glabrous to non-glabrous skin of the hand occurs. The midaxial line corresponds to the midline of the phalanx. Whereas the true midlateral line of the finger corresponds to the location of the neurovascular bundle. The dorsal skin is relatively soft, pliable, and thin. It is devoid of the fibrous septae observed in the volar skin.¹³ The importance of understanding the difference of glabrous and non-glabrous skin comes to light when one observes one of the dictums of reconstructive surgeons to replace “like with like”. Local flaps that include glabrous skin should be considered first for glabrous defects. The relative limited and inelastic quality of glabrous skin on the body prevents reconstruction of large glabrous defects with similar tissue. In such cases, alternative strategies must be employed, including using spare parts in a multi-digit injury, use of multiple grafts for a single defect, allow wounds with non-vital structures exposed to heal by secondary intention or coverage with non-glabrous skin. Dorsal skin more closely resembles skin on the anterior trunk and defects of the dorsal hand and fingers can readily be closed with other similar quality skin.

Flap selection

A multitude of available flaps can produce good outcomes for both the recipient and donor site. Each flap has inherent advantages and drawbacks. Ultimately, flap selection is dependent upon variables such as size, shape, location of the defect, and the characteristics of the tissue lost. The hand surgeon must select the most ideal flap to restore as many of the native skin characteristics present prior to the defect, and to provide the quickest means of wound closure. Efficient wound closure becomes a higher priority to prevent finger stiffness and maximize hand function.

Fingertip injuries should be thoroughly irrigated and debrided of foreign material and nonviable tissue before closure is attempted. If the entire defect cannot be closed primarily, the wound can be partially closed and the remainder allowed to heal by secondary intention. Suture selection varies by surgeon preference. If possible, the wound should be closed with a chromic or other resorbable suture. Nylon sutures in the fingertip are not usually necessary; they are uncomfortable to remove in the early follow-up periods. The wound is covered with a non-stick dressing like Xeroform or other minimal adherence dressing. Daily dressing changes permits rapid wound healing. Early motion is encouraged to prevent stiffness at the DIP or PIP joints. Larger wounds can heal by secondary intention if bone, tendon or neurovascular structures are not exposed. Wounds up to 2–3 cm may be allowed to heal by re-epithelialization, but both surgeon and patient must be aware that closure may take 4–6 weeks (Fig. 6.23). Previously, authors advocated that defects >1 cm should be closed with local flaps.⁶² However, secondary intention offers many advantages over flap closure, including improved contour, sensation, and lack of donor site morbidity.⁶³




Fig. 6.23 (A) Large soft tissue defect of the volar aspect of the thumb allowed to heal by secondary intent. (B) 4-year follow-up of healed thumb showing good contour.

Skin grafting

Patient selection

When the extent of the defect is limited to skin, a split- or full-thickness skin graft may be used for coverage of a well-vascularized bed. Graft contraction is expected. Although re-innervation is poor with split-thickness grafts, protective sensation may be possible if full-thickness grafts are used.^{62,64} Dermal substitutes (Integra, Intera LifeSciences Co., Plainsboro, NJ) over tendons can provide an interface that accepts a skin graft and prevents scar adhesion formation that prevents motion (Fig. 6.24). Distal fingertip amputations often comprise skin, subcutaneous fat and a portion of the nail bed. The amputated part may be replaced as a composite graft after defatting, called a cap graft.⁶⁵ The overall success rate of composite grafts is poor in the adult population and better in children <10 years of age. A recent review of pediatric patients treated with cap grafts revealed a relatively poor rate of complete take (7.7%).⁶⁶ The majority of patients had a partial take (38.5%) and 33% had total loss of the graft. Despite this seemingly poor overall success of composite grafts, only 10% of patients went on to require a secondary procedure.⁶⁶ It can be concluded that a composite graft placed on a fingertip that does not revascularize should be left as a biologic dressing to allow healing from below the eschar. This often leads to an adequately contoured fingertip. These injuries do, however, take many weeks to months to completely heal and in the adult laborer needing to return to work, a revision amputation may be a preferred method for treatment of these types of injuries.

An evaluation by Allen level concluded that cap grafts are most successful for Zone I and II sharp or blunt-cut injuries, but Zone III or IV injuries regardless of mechanism should be treated by another method (e.g., revision amputation, local flap, micro-anastomosis, etc.).⁶⁷

Treatment: Local flaps

Volar V–Y advancement (Atasoy, Kleinert)

Fingertip defects less than one centimeter and oriented in a dorsal oblique or transverse fashion may be closed with a volar V–Y advancement flap.⁶⁴ Originally described by Atasoy *et al.* in 1970, this flap is oriented as a triangle and closed in a V–Y fashion. The base of the triangle sits at the wound edge and the apex at the DIP crease (Fig. 6.25).^{68,69} This skin is incised down through the dermis and then scissor dissection is used to release fibrous septae that anchor glabrous skin to the deeper musculoskeletal structures.⁶⁴ The most distal corners of the flap must be freed by 2–3 mm in order to allow adequate release of the flap distally. Similarly, the apex of the flap at the DIP joint must be released significantly to permit distal migration of the flap.⁷⁰ The flap is elevated with its neurovascular pedicles on either side of the flap in the plane of flexor tendon sheath; 0.75–1 cm of length can be obtained with a volar V–Y advancement flap. Functional and cosmetic results are extremely good as this flap remains one of the most important tools in treatment of fingertip injury closure.^{62,64,68,69}

Lateral V–Y advancement flaps (Kutler)

Transverse and lateral oblique defects can be covered with sensate vascularized skin using V–Y advancement flaps on the

lateral aspect of the digits (Fig. 6.26).⁶⁴ Often bilateral flaps are required to get sufficient closure of the of the fingertip defect. The lateral V–Y flaps are elevated in a similar fashion as to the volar V–Y flap; however, they are based laterally and medially instead of volar. Unlike the Atasoy counterpart, this flap's advancement has limited mobility and can only reliably close defects of 0.5 cm, but no more than 1 cm. The flap is elevated in the plane of the deeper musculoskeletal structures.⁷⁰

Visor flap

Described by Neumeister *et al.*, the visor flap is indicated for closure of transverse distal fingertip amputations with exposed bone.^{70,71} This flap utilizes skin on the dorsal aspect of the finger to preserve length and close defects on the most distal aspect of the finger amputation site. The visor flap is a bipediced rectangular-shaped flap from the dorsal aspect of the finger. It is raised at the level of the paratenon immediately proximal to the defect (Fig. 6.27). The width of the flap is approximately that of the fingertip defect. The flap is sensate and vascularized by branches of the volar lateral and medial digital arteries and nerves, respectively.⁷¹ Back cuts in the dorsal aspect of the skin may be required for transposition of the flap. The donor site requires a skin graft. If dog ears are present, they are left in place and should flatten over a period of months. The visor flap provides acceptable sensation, good cosmetic appearance and preservation of length of the digit without violating adjacent normal digits or creating volar scars.

Homodigital flaps

Reverse homodigital flap

The reverse homodigital flap, originally described by Lai *et al.*,⁷² takes advantage of the dual vascularity of the digit, as the finger can remain viable on a single digital artery. The other artery can provide blood supply for an axial flap that can be based proximally or distally (Fig. 6.28). The digital nerve remains *in situ* to preserve sensation to the finger, however small nerve branches can be used for coaptation to improve sensation of the transferred flap. These arterial perforator flaps involve small perforators arising from the digital artery. The skin island can be isolated on the perforator while the remaining aspect of the artery provides length to the pedicle, ultimately creating an arc of rotation of up to 180° (Fig. 6.29A–D).^{73,74} The donor site may be closed with a skin graft if primary closure is not possible. Distally based homodigital flaps take advantage of the communication with the contralateral digital artery.⁷⁵ These flaps may be somewhat precarious as they require retrograde venous flow and may have limited communication with the contralateral vessels. This reverse homodigital flap can also be taken as an adipofascial flap.⁷⁶ This technique can provide a slightly broader and larger flap and reduces donor site morbidity.⁷⁶

Fig. 6.29 appears online only.

Alternative modifications described islandize a dorsal-lateral skin paddle on a volar perforating branch from the digital vessel. This digital artery perforator propeller flap is innervated and can be used to reconstruct lateral oblique fingertip defects and prevent further skeletal shortening.⁷⁷






Fig. 6.29 (A) Homodigital flaps are based on the nondominant digital artery to the fingers and used to transpose either in a retrograde or an antegrade fashion. (B) Exposed PIP joint necessitates closure, the homodigital flap is elevated, care is taken to incorporate the digital artery proper into the flap. (C,D) The flap is transposed and the donor site closed with a full-thickness skin graft. The flap can be elevated without transecting the skin paddle proximally. This improves the venous outflow of the flap. (E) Healed flap, dorsal aspect of finger.



Fig. 6.24 54-year-old male suffered occupational avulsion injury as an elevator repairman. **(A)** The neurovascular bundles were intact, but there was exposed flexor tendon sheath. **(B)** The wound was debrided and Integra (indicated by the scissor tips) was placed over the tendon sheath and **(C)** immediately covered with a full-thickness skin graft from the volar forearm. **(D)** Some areas of purplish discoloration are seen during the immediate postoperative period. **(E)** At 4 weeks postoperative, he healed completely and with good motion.






Fig. 6.27 (A) The visor flap is designed over the dorsum of the digit. The height of the defect (A to B) is equal to the height of the flap (A to C). The proximal incision is carried down to the midaxial line on either side of the dorsum of the finger. A back cut to D1 can be made but only through the dermis in order to protect the neurovascular structures supplying the flap. (B) Clinical picture of the design of the visor flap. (C) The flap was transposed over the distal aspect of the amputated stump. The donor defect is closed with a split thickness skin graft or a full thickness graft. (D,E) Lateral and AP view of the visor flap after it is transposed and healed.

Moberg flap

The homodigital volar advancement flap, also known as a Moberg flap, can be used to reconstruct defects on the thumb (Fig. 6.30A–C). A volar oblique injury to the tip of the thumb is the classic indication for this flap. However, this flap's uses have expanded to include a wider range of defects. The unique dorsal and volar blood supplies to the thumb allow creation of a volar skin paddle with both neurovascular bundles. Flap elevation is performed in a plane just volar to the tendon sheath. The flap can be completely islandized on the neurovascular structures, with a variety of proximal incisions used to close the defect in the palm, including a V–Y design (Fig. 6.30D) or transverse incisions at the base with excision of Burow's triangles. The Dellon modification of the flap allows closure of defects up to 3 cm. This requires dissection of the flap into the palm past the base of the thumb.

Heterodigital flaps

The cross-finger flap

The cross-finger flap utilizes skin from the dorsal aspect of the adjacent finger as part of a two-stage technique. The inner cross-finger flap is most applicable for volar defects of the distal aspect of an adjacent finger. The flap is normally taken from the dorsal radial surface over the middle phalanx of the adjacent digits.^{62,64,70,77} The flap is designed slightly larger than the defect to ensure complete coverage. Vascularity of the flap arises from the digital artery and vena comitantes that send branches dorsally beyond the PIP joint. The flap is elevated superficial to the extensor paratenon and flipped over like a page in a book to cover the volar defect of the adjacent finger (Fig. 6.31). The base of the flap remains intact with the donor finger while the donor defect on the dorsal aspect of the middle phalanx is covered with a full-thickness or



Fig. 6.28 (A) Dorsal defects of the fingers with exposed bone or flap closure. (B) A homodigital island flap is designed involving the nondominant side of the right ring finger. (C) The healed flap over the dorsal aspect of the fingers. The flap was based on the ulnar digital artery.

split-thickness skin graft. The flap is sutured in with chromic sutures and the fingers are immobilized for 2–3 weeks. The flap is then divided and inset. The dorsal cutaneous branches of the digital nerve can be incorporated into the flap and coapted to the recipient digital nerve to improve re-innervation potential.⁷⁰

The reverse cross-finger flap is utilized to cover dorsal defects of the adjacent digit. In the reverse cross-finger flap, the dorsal skin is elevated but left with an intact base at the lateral border away from the defect. The subcutaneous tissue is then elevated at the level of the paratenon and turned over 180° like a page of a book to cover the dorsal defect of the involved finger (Fig. 6.32). The elevated full-thickness skin flap on the opposite side of the donor finger is then replaced in its original position.⁶² A skin graft is still required at the recipient site to cover the adipofascial flap that overlies the dorsal defect. Both cross-finger and reverse cross-finger flaps provide tissue with reliable blood supply to defects measuring up to 3 cm in size. Following division and inset of the flaps, mobilization and aggressive therapy may be warranted to prevent stiffness or contractures.

Thenar crease flap

Smaller fingertip defects with exposed bone may be closed with a thenar crease flap. The flap itself is designed based on the radial aspect of the palmar thenar crease. It is most often utilized for the index and long fingers because of their proximity to the thumb.^{62,64} The thenar crease flap is designed in a two-stage fashion. At the initial phase, the flap can be elevated measuring up to 1½×1 cm (Fig. 6.33). Care must be taken not to injure the neurovascular bundles that lie immediately beneath the fasciocutaneous thenar crease flap. The injured finger must be flexed at the PIP and often the DIP joint in order to allow flap inset with chromic sutures and the donor site closed primarily (Fig. 6.34). After 2 weeks, the flap is divided.⁷⁸ Sensation is reported to be better than skin grafting to the affected digit or with cross-finger flaps.⁷⁹ Care must be taken when utilizing this flap in the elderly, as permanent stiffness or PIP joint contractures may arise. Aggressive therapy is required following the flap division and inset.

Fig. 6.34 appears online only.



Fig. 6.34 (A) Distal fingertips with exposed bone of the index and long fingers in a 23-year-old female. (B) A thenar crease flap is elevated based on the radial aspect of the MP joint of the thumb. The index finger is flexed at the PIP joint and the flap is inset onto the defect of the fingertip. A heterodigital flap is elevated on the index finger and transposed to cover the tip of the long finger. (C) Flaps are divided and definitively inset after 2–3 weeks per time to provide appropriate coverage for the distal fingertips of the index and long fingers.




Fig. 6.30 52-year-old male suffered (A) volar oblique injury to his left thumb during an industrial accident with (B) exposed bone. (C) A Moberg volar advancement flap was performed to prevent skeletal shortening. Many modifications have been made to increase the flap advancement including (D) the V-Y proximal incision (different patient pictured). This technique islandizes the flap on the volar neurovascular bundles.



Fig. 6.31 (A) Mutilated fingertip with exposed bone requiring soft-tissue coverage. (B) Cross-finger flap from the adjacent digit is used to cover the volar defect of the index finger. The flap is elevated at the level of the paratenon and the donor site is then closed with a full-thickness skin graft. (C) 2–3 weeks later the flap is divided and inset. (D) Long-term outcome after soft-tissue healing and nail regrowth.




Fig. 6.32 (A) A finger injury with tip amputation and soft-tissue avulsion from the dorsal aspect of the index finger with exposed tendon. A reverse cross finger flap is designed. The dorsal skin of the long finger is de-epithelialized. (B) The flap is elevated at the level of the paratenon and transposed like a page in a book over the dorsal aspect of the index finger. (C) Both digits are covered with a full-thickness skin graft and the flaps are then divided and are inset 2–3 weeks later. (D,E) Final outcome of the reverse cross-finger flap and donor site is shown.



Fig. 6.33 (A) The long finger has a distal amputation with exposed bone. To preserve length, the defect will be closed with a thenar crease flap. (B) The flap was designed with approximately 1 cm width and based radially. The recipient finger was flexed at the PIP joint for flap inset.

Little neurovascular island flap

This neurovascular island flap utilizes the donor skin from the ulnar aspect of the long or ring finger to provide sensate vascularized tissue to a given recipient site (Fig. 6.35).⁶⁴ However, donor site compromise may be significant resulting in stiff fingers with contractures making this flap less desirable than others for fingertip or thumb pulp reconstruction. Arteriograms and digital Allen's tests have been advocated prior to performing this flap to confirm an adequate co-dominant arterial supply to the donor and adjacent finger because the dissection of the flap requires extension beyond the bifurcation of the common digital artery. The contralateral branch will need to be ligated and divided. Dividing this contralateral branch in a finger that does not have another means of circulation can result in significant digital ischemia. Therefore, before ligating and dividing the contralateral branch, a temporary clip should be applied, the tourniquet released, and the viability of the finger verified.⁸⁰

Fig. 6.35 appears online only.

The flap may be tunneled through a subcutaneous plane to the defect on the volar aspect of the thumb or, alternatively, through a zig-zag Brunner type incision to allow easy transposition of the flap without fear of compression or compromise to the pedicle. The donor site is closed with a split-thickness skin graft. Creating chevron incisions lateral to the DIP and PIP creases is important to prevent contractures at these joints following healing of the skin graft. Protective sensation has been observed with two-point discrimination averaging 6–7 mm.⁶⁸ Although there is a potential for cortical relearning or plasticity, most patients perceive the sensation as that of the donor site and not the recipient site. Cortical relearning may only be present in 25–40% of individuals.^{64,81}

Dorsal metacarpal artery flaps

Foucher described the first dorsal metacarpal artery flap for reconstruction of thumb defects involving the volar thumb pulp (Fig. 6.36A). This is also known as a kite flap because of its distinct appearance of a distal skin paddle pedicled on a tail of neurovascular structures. This flap utilizes the skin and subcutaneous tissue of the proximal phalanx of the index finger and is based on the neurovascular bundle that rests within or under the fascia of the first dorsal interosseous muscle (Fig. 6.36B–F).⁸² The first dorsal metacarpal artery supplies vascularity in the vena comitantes and some superficial veins supply the venous outflow of the flow. Branches of the superficial radial nerve provide sensibility to this flap. The flap is elevated at the plane above the paratenon so that the donor site can accept the skin graft for closure. The rest of the pedicle is dissected and the flap can either be transposed through a tunnel or through a zig-zag incision into the volar thumb defect.⁷⁰ Although this flap provides protective sensation, cortical relearning is required. The morbidity from harvesting tissue from an undamaged digit must also be considered.

Fig. 6.36 appears online only.

A reverse dorsal metacarpal artery flap based on perforators from the palmar digital arteries (Fig. 6.37) can be used as an adipofascial flap or with a skin paddle.⁷⁰ These perforators arise between the metacarpophalangeal joints and at the neck of each metacarpal. This flap is a reverse-flow island flap where the skin paddle is taken from the dorsum of the hand closer to the wrist. It is elevated off the fascia of the interosseous muscles and transposed to resurface distal finger defects. In order to get adequate pedicle length to cover the distal finger, the pedicle should be dissected down into the web space. This flap is not typically used for distal fingertips but for dorsal defects of the finger as the dissection is somewhat tedious between the digits.

Fig. 6.37 appears online only.

Hints and tips

Reverse dorsal metacarpal artery flap

To gain pedicle length, continue the dissection between the proximal phalanges on either side. The pedicle is easily mobilized to reach the volar or dorsal fingertip area.



Fig. 6.35 (A) The Littler neurovascular island flap utilizes the skin subcutaneous tissue and neurovascular bundle from the nondominant side of the long or ring fingers. The dissection is carried down into the palm and the flap is transposed to the defect on the thumb. (B) This flap was elevated on the neurovascular bundle involving the nondominant side of the long finger. (C) The donor defect closed with a full-thickness graft and then the flap transposed onto the dorsum of the thumb. (D) The healed defect on the thumb with the neurovascular island flap well inset. The donor finger that may result in a contracture if the flap is harvested in a more volar aspect of the finger.




Fig. 6.36 (A) Significant defect of the volar pulp of the thumb with exposed bone and tendon. (B) First dorsal metacarpal artery flap is designed over the dorsal aspect of the index finger. The first dorsal metacarpal artery lies within the fascia of the first dorsal interosseous muscle. (C) The pedicle is elevated with the fascia and care is taken to keep the superficial veins to allow appropriate drainage of the flap. (D) Final appearance of the defect on the thumb as well as the donor site.




Fig. 6.37 (A) Dorsal defects of the finger with a designed reversed dorsal metacarpal artery flap. (B) The flap is based between the metacarpal heads as perforators from the palmar side communicate with the dorsal metacarpal arteries. The venous drainage is retrograde. (C) The flap is tunneled and inset into place to the dorsal aspect of the finger. This flap can be carried out to the distal aspect of the finger if further dissection is carried down within the web space.

Conclusions

The choice of treatment for fingertip injuries relies heavily on the patient's primary outcome goal, namely speed to recovery *vs.* skeletal preservation. Revision amputation returns a laborer to work faster and minimizes chances for complications, including wound breakdown, joint stiffness and flap failure. Women or patients interested in preservation of anatomic normalcy may prefer a potentially longer and possibly multi-stage procedure to return the fingertip as closely as possible to its normal state. The classic flaps described for reconstructing the fingertip, including the Moberg, Atasoy, Foucher and others, remain excellent viable options. Additional developments have included use of adipofascial reverse-flow turnover flaps, use of volar perforating branches from the digital arteries to design custom homodigital flaps and otherwise considered randomly based flaps (i.e. keystone design). These allow creation of variable skin paddle designs to cover defects and speed healing. Additional modalities include use of negative-pressure dressings and neodermis (e.g., Integra) to promote granulation and prevent tendon desiccation.

Recent experiences have demonstrated that many simple nail bed injuries with an intact nail plate can be observed with a comparable or potentially superior long-term aesthetic outcome. More complex injuries or extensive subungual hematomas still require repair and drainage, however; if possible the proximal nail plate can be left *in situ*. A good understanding of fingertip anatomy and treatment options remains important, as these types of injuries continue to be some of the most commonly seen presenting complaints in emergency and urgent care settings. Avoiding complications and preventing delayed return of function remains the continued challenge for practitioners treating these injuries.

Future directions

Managing joint stiffness, hyperesthesia and nerve injuries remain the most difficult and unpredictable issues to resolve after fingertip injuries. The mainstays of treatment include early range-of-motion therapy to improve gliding and prevent internal scarring from limiting motion. For patients with hypersensitivity of the fingertip, desensitization therapy, smoking cessation, and neurologic medications including gabalin and pregabalin along with the tincture of time are the best methods currently available. The use of neuromodulators, including botulinum toxin, may prove to have an added benefit for these patients. Use of vitamin C has proven useful for preventing complex regional pain syndrome (CRPS) after repair of distal radius fractures and may have a benefit for preventing CRPS in fingertip injuries, too. Regaining full sensation in transected nerves in the digit also remains an incompletely solved issue. The current gold standard in order of preference includes a tension-free primary repair, followed by autograft, allograft and lastly a nerve conduit. However, evidence in the literature can be found to support a wide range of reconstructive strategies. Future directions will need to be directed towards solving the ongoing unsolved problem of restoring normal nervous function after injury, preventing

hypersensitivity of the injured fingertip and restoring normal range of motion.



Bonus images for this chapter can be found online at

<http://www.expertconsult.com>

Fig. 6.2 Components of the nail are produced in three areas.

Fig. 6.3 Of nail bed injuries: **(A)** 36% are classified as simple lacerations; **(B)** 27% as stellate lacerations; **(C)** 22% as crushing injuries of the nail bed; **(D)** 15% as avulsions of the germinal or sterile matrix.

Fig. 6.7 An example of a stitch in the silicone sheeting to hold it in place.

Fig. 6.8 A longitudinal pin was placed to maintain fracture reduction but was between the periosteum and sterile matrix, causing scarring in the ridge.

Fig. 6.9 **(A)** A split nail may occur within the sterile matrix with minimal problems. **(B)** An injury to the germinal matrix can cause a split in the entire nail, causing significant pain secondary to trauma and disfigurement.

Fig. 6.10 **(A)** A horizontal laceration in the sterile matrix with a resultant transverse scar can cause a separation so that two nails grow out. If the volar nail is adequate, surgical removal of the dorsal nail-producing matrix will correct the problem. **(B)** The patient's index finger postoperatively.

Fig. 6.12 **(A)** A split of the nail due to scarring between the dorsal roof and the ventral floor of the nail fold. **(B)** End-on view of the nail deformity. **(C)** With the two portions of nail removed, the cicatrix between the dorsal roof and the ventral floor of the nail fold can be seen. **(D)** The cicatrix is divided with the resultant defect on the dorsal roof. **(E)** A split-thickness sterile matrix graft is removed from the sterile matrix and sutured in place on the dorsal roof of the nail fold.

(F) One-year follow-up with an improved appearance and reduced functional problems. **(G)** An end-on view of the nail demonstrating the improved contour.

Fig. 6.14 **(A)** Nonadherence of nail to the sterile matrix thought to be due to an episode of pulling the nail free from the nail bed traumatically and then repeated attempts to clean under the nail. The area of nonadherence is marked on the nail. **(B)** That area of nail is removed, showing the hyperkeratinous sterile matrix. The hypertrophic keratinous material is scraped off with a scalpel blade to bare the vascular sterile matrix. **(C)** The patient 1 year later with improved adherence of the nail.

Fig. 6.15 **(A)** Nonadherence of the nails to the nail bed after a crushing injury and then application of artificial nails. The cause of the detachment could be either of these. **(B)** A split-thickness sterile matrix graft from the large toe donor site is placed over the defect. **(C)** The patient 1 year later with much improved attachment.

Fig. 6.17 **(A)** A hypertrophic hyponychium (arrowhead) causing pain and discomfort with upper traction on the nail. **(B)** Dorsal view of the same patient. **(C)** Same patient with relief of pain after resection of the hypertrophic hyponychium and a split-thickness sterile matrix graft in its place. **(D)** Same patient, dorsal view with hyponychial attachment.

Fig. 6.29 **(A)** Homodigital flaps are based on the nondominant digital artery to the fingers and used to transpose either in a retrograde or an antegrade fashion. **(B)** Exposed PIP joint necessitates closure, the homodigital flap is elevated, care is taken to incorporate the digital artery proper into the flap. **(C,D)** The flap is transposed and the donor site closed with a full-thickness skin graft. The flap can be elevated without transecting the skin paddle proximally. This improves the venous outflow of the flap. **(E)** Healed flap, dorsal aspect of finger.

Fig. 6.34 **(A)** Distal fingertips with exposed bone of the index and long fingers in a 23-year-old female. **(B)** A thenar crease flap is elevated based on the radial aspect of the MP joint of the thumb. The index finger is flexed at the PIP joint and the flap is inset onto the defect of the fingertip. A heterodigital flap is elevated on the index finger and transposed to cover the tip of the long finger. **(C)** Flaps are divided and definitively inset after 2–3 weeks per time to provide appropriate coverage for the distal fingertips of the index and long fingers.

Fig. 6.35 **(A)** The Littler neurovascular island flap utilizes the skin subcutaneous tissue and neurovascular bundle from the nondominant side of the long or ring fingers. The dissection is carried down into the palm and the flap is transposed to the defect on the thumb. **(B)** This flap was elevated on the neurovascular bundle involving the nondominant side of the long finger. **(C)** The donor defect closed with a full-thickness graft and then the flap transposed onto the dorsum of the thumb. **(D)** The healed defect on the thumb with the neurovascular island flap well inset. The donor finger that may result in a contracture if the flap is harvested in a more volar aspect of the finger.

Fig. 6.36 (A) Significant defect of the volar pulp of the thumb with exposed bone and tendon. **(B)** First dorsal metacarpal artery flap is designed over the dorsal aspect of the index finger. The first dorsal metacarpal artery lies within the fascia of the first dorsal interosseous muscle. **(C)** The pedicle is elevated with the fascia and care is taken to keep the superficial veins to allow appropriate drainage of the flap. **(D)** Final appearance of the defect on the thumb as well as the donor site.

Fig. 6.37 (A) Dorsal defects of the finger with a designed reversed dorsal metacarpal artery flap. **(B)** The flap is based between the metacarpal heads as perforators from the palmar side communicate with the dorsal metacarpal arteries. The venous drainage is retrograde. **(C)** The flap is tunneled and inset into place to the dorsal aspect of the finger. This flap can be carried out to the distal aspect of the finger if further dissection is carried down within the web space.



Access the complete reference list online at

<http://www.expertconsult.com>

5. Zook EG, Van Beek AL, Russell RC, Beatty ME. Anatomy and physiology of the perionychium: a review of the literature and anatomic study. *J Hand Surg Am.* 1980;5:528–536. *This article offers complete analysis of the normal architecture of the nail bed unit. They compile a literature review with their own cadaveric dissection for the purpose of applied anatomy in nail bed repair and reconstruction.*
8. Zook EG, Brown RE. Injuries of the fingernail. In: Green DP, Hotchkiss RN, Pederson WC, eds. *Operative Hand Surgery*. 4th ed. New York: Churchill Livingstone; 1999:1353–1380.
16. Ashbell TS, Kleinert HE, Putcha SM, Kutz JE. The deformed finger nail, a frequent result of failure to repair nail bed injuries. *J Trauma.* 1967;7:177–190.
17. Zook EG, Guy RJ, Russell RC. A study of nail bed injuries: causes, treatment, and prognosis. *J Hand Surg Am.* 1984;9:247–252.
30. Zook EG, Russell RC. Reconstruction of a functional and esthetic nail. *Hand Clin.* 1990;6:59–68. *This article is an extensive review of the options to correct a variety of nail deformities. All pictures are clinical photographs, with excellent long-term follow-up.*
31. Yong FC, Teoh LC. Nail bed reconstruction with split-thickness nail bed grafts. *J Hand Surg Am.* 1992;17:193–197.
32. Pessa JE, Tsai TM, Li Y, Kleinert HE. The repair of nail deformities with the nonvascularized nail bed graft: indications and results. *J Hand Surg Am.* 1990;15:466–470.
39. Buncke HJ Jr, Gonzalez RI. Fingernail reconstruction. *Plast Reconstr Surg Transplant Bull.* 1962;30:452–461.
45. Achauer BM, Welk RA. One-stage reconstruction of the postburn nailfold contracture. *Plast Reconstr Surg.* 1990;85:937–940, discussion 941. *This article describes reconstruction of the eponychium for burn reconstruction. Various local flaps are described with indications and outcomes.*
63. Russell R. Fingertip injuries. In: May JW Jr, Littler JW, eds. *The Hand*. Philadelphia: WB Saunders; 1990:4477.
64. Ganchi PALW. Fingertip reconstruction. In: Mathes SJ, ed. *Plastic Surgery*. Vol. 7. Philadelphia: Elsevier; 2006:153.
70. Neumeister M. Intrinsic flaps of the hand. In: Guyuron B, ed. *Plastic Surgery, Indications and Practice*. Philadelphia: WB Saunders; 2009:1001. *A review of the vast variety of flaps used for closure of the finger. Technical details and indications are provided.*
82. Omokawa S, Tanaka Y, Ryu J, Kish VL. The anatomical basis for reverse first to fifth dorsal metacarpal arterial flaps. *J Hand Surg Am.* 2005;30:40–44. *Many local or regional flaps require flexion of the PIP joint to permit tension-free coverage. The article describes the practical anatomy and defining features of the reverse dorsal artery metacarpal arterial flaps.*

References

1. AW Ham DC. *Histology*. 8th ed. Philadelphia: JB Lippincott; 1979.
2. Gonzalez-Serva A. *Structure and Function*. 2nd ed. Philadelphia: WB Saunders; 1997.
3. Moore K. *The Developing Human*. 3rd ed. Philadelphia: WB Saunders; 1982.
4. Zaias N. Embryology of the human nail. *Arch Dermatol*. 1963;87:37–53.
5. Zook EG, Van Beek AL, Russell RC, Beatty ME. Anatomy and physiology of the perionychium: a review of the literature and anatomic study. *J Hand Surg Am*. 1980;5:528–536. *This article offers complete analysis of the normal architecture of the nail bed unit. They compile a literature review with their own cadaveric dissection for the purpose of applied anatomy in nail bed repair and reconstruction.*
6. Flint MH. Some observations on the vascular supply of the nail bed and terminal segments of the finger. *Br J Plast Surg*. 1955;8:186–195.
7. Zook EG. Anatomy and physiology of the perionychium. *Hand Clin*. 2002;18:553–559, v.
8. Zook EG, Brown RE. Injuries of the fingernail. In: Green DP, Hotchkiss RN, Pederson WC, eds. *Operative Hand Surgery*. 4th ed. New York: Churchill Livingstone; 1999:1353–1380.
9. Piraccini BM, Starace M. Nail disorders in infants and children. *Curr Opin Pediatr*. 2014;26:440–445.
10. Baden HP. Regeneration of the nail. *Arch Dermatol*. 1965;91:619–620.
11. Jones F. *The Principles of Anatomy as Seen in the Hand*. 2nd ed. London: Baillière, Tindall & Cox; 1941.
12. Fleckman P. *Basic Science of the Nail Unit*. 2nd ed. Philadelphia: WB Saunders; 1997.
13. Barron JN. The structure and function of the skin of the hand. *Hand*. 1970;2:93–96.
14. De Berker D, Mawhinney B, Sviland L. Quantification of regional matrix nail production. *Br J Dermatol*. 1996;134:1083–1086.
15. Lewis BL. Microscopic studies of fetal and mature nail and surrounding soft tissue. *AMA Arch Derm Syphilol*. 1954;70:733–747.
16. Ashbell TS, Kleinert HE, Putcha SM, Kutz JE. The deformed finger nail, a frequent result of failure to repair nail bed injuries. *J Trauma*. 1967;7:177–190.
17. Zook EG, Guy RJ, Russell RC. A study of nail bed injuries: causes, treatment, and prognosis. *J Hand Surg Am*. 1984;9:247–252.
18. Tzeng YS. Use of an 18-gauge needle to evacuate subungual hematomas. *J Emerg Med*. 2013;44:196–197.
19. Khan MA, West E, Tyler M. Two millimetre biopsy punch: a painless and practical instrument for evacuation of subungual haematomas in adults and children. *J Hand Surg Eur Vol*. 2011;36:615–617.
20. Kain N, Koshy O. Evacuation of subungual haematomas using punch biopsy. *J Plast Reconstr Aesthet Surg*. 2010;63:1932–1933.
21. Horn B. Treatment of subungual hematoma in office and outdoor conditions]. *Ther Umsch*. 2015;72:58.
22. Soyuncu S, Bektas F. Nail bed injury detected by ultrasonography. *Am J Emerg Med*. 2012;30:1323.e5–1323.e6.
23. Simon RR, Wolgin M. Subungual hematoma: association with occult laceration requiring repair. *Am J Emerg Med*. 1987;5:302–304.
24. Seaberg DC, Angelos WJ, Paris PM. Treatment of subungual hematomas with nail trephination: a prospective study. *Am J Emerg Med*. 1991;9:209–210.
25. Roser SE, Gellman H. Comparison of nail bed repair versus nail trephination for subungual hematomas in children. *J Hand Surg Am*. 1999;24:1166–1170.
26. Dean B, Becker G, Little C. The management of the acute traumatic subungual haematoma: a systematic review. *Hand Surg*. 2012;17:151–154.
27. Shepard GH. Management of acute nail bed avulsions. *Hand Clin*. 1990;6:39–56, discussion 57–58.
28. Johnson RK. Nailplasty. *Plast Reconstr Surg*. 1971;47:275–276.
29. Shepard GH. Nail grafts for reconstruction. *Hand Clin*. 1990;6:79–102, discussion 103.
30. Zook EG, Russell RC. Reconstruction of a functional and esthetic nail. *Hand Clin*. 1990;6:59–68. *This article is an extensive review of the options to correct a variety of nail deformities. All pictures are clinical photographs, with excellent long-term follow-up.*
31. Yong FC, Teoh LC. Nail bed reconstruction with split-thickness nail bed grafts. *J Hand Surg Am*. 1992;17:193–197.
32. Pessa JE, Tsai TM, Li Y, Kleinert HE. The repair of nail deformities with the nonvascularized nail bed graft: indications and results. *J Hand Surg Am*. 1990;15:466–470.
33. McCash C. Free nail grafting. *Br J Plast Surg*. 1955;8:19–33.
34. Lille S, Brown RE, Zook EE, Russell RC. Free nonvascularized composite nail grafts: an institutional experience. *Plast Reconstr Surg*. 2000;105:2412–2415.
35. Koshima I, Soeda S, Takase T, Yamasaki M. Free vascularized nail grafts. *J Hand Surg Am*. 1988;13:29–32.
36. Shibata M, Seki T, Yoshizu T, et al. Microsurgical toenail transfer to the hand. *Plast Reconstr Surg*. 1991;88:102–109, discussion 110.
37. Nakayama Y, Iino T, Uchida A, et al. Vascularized free nail grafts nourished by arterial inflow from the venous system. *Plast Reconstr Surg*. 1990;85:239–245, discussion 246–247.
38. Endo T, Nakayama Y. Short-pedicle vascularized nail flap. *Plast Reconstr Surg*. 1996;97:656–661.
39. Buncke HJ Jr, Gonzalez RI. Fingernail reconstruction. *Plast Reconstr Surg Transplant Bull*. 1962;30:452–461.
40. Baruchin AM, Nahlieli O, Vizethum F, Sela M. Utilizing the osseointegration principle for fixation of nail prostheses. *Plast Reconstr Surg*. 1995;96:1665–1671.
41. Kumar VP, Satku K. Treatment and prevention of “hook nail” deformity with anatomic correlation. *J Hand Surg Am*. 1993;18:617–620.
42. Bubak PJ, Richey MD, Engrav LH. Hook nail deformity repaired using a composite toe graft. *Plast Reconstr Surg*. 1992;90:1079–1082.
43. Hayes CW. One-stage nail fold reconstruction. *Hand*. 1974;6:74–75.
44. Kasai K, Ogawa Y. Nailplasty using a distally based ulnar finger dorsum flap. *Aesthetic Plast Surg*. 1989;13:125–128.
45. Achauer BM, Welk RA. One-stage reconstruction of the postburn nailfold contracture. *Plast Reconstr Surg*. 1990;85:937–940, discussion 941. *This article describes reconstruction of the eponychium for burn reconstruction. Various local flaps are described with indications and outcomes.*
46. Bakhach J. [Eponychial flap]. *Ann Chir Plast Esthet*. 1998;43:259–263.
47. Chen HY, Hsu CC, Lin YT, et al. Functional and aesthetic outcomes of the fingertips after nail lengthening using the eponychial flap. *J Plast Reconstr Aesthet Surg*. 2015;68:1438–1446.
48. Baran RHE. *Tumours of the Nail Apparatus and Adjacent Tissues*. Oxford: Blackwell Scientific; 1984.
49. Stephen S, Tosti A, Rubin AI. Diagnostic applications of nail clippings. *Dermatol Clin*. 2015;33:289–301.
50. Fleegler EJ, Zeinowicz RJ. Tumors of the perionychium. *Hand Clin*. 1990;6:113–133, discussion 135–116.
51. Piraccini BM, Dika E, Fanti PA. Tips for diagnosis and treatment of nail pigmentation with practical algorithm. *Dermatol Clin*. 2015;33:185–195.
52. Phan A, Touzet S, Dalle S, et al. Acral lentiginous melanoma: a clinicoprognostic study of 126 cases. *Br J Dermatol*. 2006;155:561–569.
53. Krementz ET, Feed RJ, Coleman WP 3rd, et al. Acral lentiginous melanoma. A clinicopathologic entity. *Ann Surg*. 1982;195:632–645.
54. Patterson RH, Helwig EB. Subungual malignant melanoma: a clinical-pathologic study. *Cancer*. 1980;46:2074–2087.
55. Das Gupta T, Brasfield R. Subungual melanoma: 25-year review of cases. *Ann Surg*. 1965;161:545–552.
56. Park KG, Blessing K, Kernohan NM. Surgical aspects of subungual malignant melanomas. The Scottish Melanoma Group. *Ann Surg*. 1992;216:692–695.

57. Cochran AM, Buchanan PJ, Bueno RA Jr, Neumeister MW. Subungual melanoma: a review of current treatment. *Plast Reconstr Surg*. 2014;134:259–273.
58. Suzuki K, Yagi I, Kondo M. Surgical treatment of pincer nail syndrome. *Plast Reconstr Surg*. 1979;63:570–573.
59. Brown RE, Zook EG, Williams J. Correction of pincer-nail deformity using dermal grafting. *Plast Reconstr Surg*. 2000;105:1658–1661.
60. Miller AJ, Rivlin M, Kirkpatrick W, et al. Fingertip amputation treatment: a survey study. *Am J Orthop (Belle Mead NJ)*. 2015;44:E331–E339.
61. Allen MJ. Conservative management of finger tip injuries in adults. *Hand*. 1980;12:257–265.
62. Browne EZ, Pederson WC. Skin grafts and skin flaps. In: Green DP, Hotchkiss RN, Pederson WC, et al., eds. *Green's Operative Hand Surgery*. 5th ed. Philadelphia: Elsevier; 2005:1629.
63. Russell R. Fingertip injuries. In: May JW Jr, Littler JW, eds. *The Hand*. Philadelphia: WB Saunders; 1990:4477.
64. Ganchi PALW. Fingertip reconstruction. In: Mathes SJ, ed. *Plastic Surgery*. Vol. 7. Philadelphia: Elsevier; 2006:153.
65. Moiemien NS, Elliot D. Composite graft replacement of digital tips. 2. A study in children. *J Hand Surg Am*. 1997;22:346–352.
66. Eberlin KR, Busa K, Bae DS, et al. Composite grafting for pediatric fingertip injuries. *Hand (N Y)*. 2015;10:28–33.
67. Kiuchi T, Shimizu Y, Nagasao T, et al. Composite grafting for distal digital amputation with respect to injury type and amputation level. *J Plast Surg Hand Surg*. 2015;49:224–228.
68. Atasoy E, Ioakimidis E, Kasdan ML, et al. Reconstruction of the amputated finger tip with a triangular volar flap. A new surgical procedure. *J Bone Joint Surg Am*. 1970;52:921–926.
69. Gharb BB, Rampazzo A, Armijo BS, et al. Tranquilli-Leali or Atasoy flap: an anatomical cadaveric study. *J Plast Reconstr Aesthet Surg*. 2010;63:681–685.
70. Neumeister M. Intrinsic flaps of the hand. In: Guyuron B, ed. *Plastic Surgery, Indications and Practice*. Philadelphia: WB Saunders; 2009:1001. A review of the vast variety of flaps used for closure of the finger. Technical details and indications are provided.
71. Karamursel S, Kayikcioglu A, Aksoy HM, et al. Dorsal visor flap in fingertip reconstruction. *Plast Reconstr Surg*. 2001;108:1014–1018.
72. Lai CS, Lin SD, Yang CC. The reverse digital artery flap for fingertip reconstruction. *Ann Plast Surg*. 1989;22:495–500.
73. Koshima I, Urushibara K, Fukuda N, et al. Digital artery perforator flaps for fingertip reconstructions. *Plast Reconstr Surg*. 2006;118:1579–1584.
74. Mitsunaga N, Mihara M, Koshima I, et al. Digital artery perforator (DAP) flaps: modifications for fingertip and finger stump reconstruction. *J Plast Reconstr Aesthet Surg*. 2010;63:1312–1317.
75. Kawakatsu M, Ishikawa K. Dorsal digital perforator flap for reconstruction of distal dorsal finger defects. *J Plast Reconstr Aesthet Surg*. 2010;63:e46–e50.
76. Karamese M, Akatekin A, Abac M, et al. Fingertip Reconstruction With Reverse Adipofascial Homodigital Flap. *Ann Plast Surg*. 2015;75:158–162.
77. Shen XF, Xue MY, Mi JY, et al. Innervated digital artery perforator propeller flap for reconstruction of lateral oblique fingertip defects. *J Hand Surg Am*. 2015;40:1382–1388.
78. Melone CP Jr, Beasley RW, Carstens JH Jr. The thenar flap—An analysis of its use in 150 cases. *J Hand Surg Am*. 1982;7:291–297.
79. Porter RW. Functional assessment of transplanted skin in volar defects of the digits. A comparison between free grafts and flaps. *J Bone Joint Surg Am*. 1968;50:955–963.
80. Lee YH, Baek GH, Gong HS, et al. Innervated lateral middle phalangeal finger flap for a large pulp defect by bilateral neurotomy. *Plast Reconstr Surg*. 2006;118:1185–1193, discussion 1194.
81. Henderson HP, Reid DA. Long term follow up of neurovascular island flaps. *Hand*. 1980;12:113–122.
82. Omokawa S, Tanaka Y, Ryu J, Kish VL. The anatomical basis for reverse first to fifth dorsal metacarpal arterial flaps. *J Hand Surg Am*. 2005;30:40–44. Many local or regional flaps require flexion of the PIP joint to permit tension-free coverage. The article describes the practical anatomy and defining features of the reverse dorsal artery metacarpal arterial flaps.

7

Hand fractures and joint injuries

Joseph S. Khouri and Warren C. Hammert

▶ Access video and video lecture content for this chapter online at expertconsult.com

SYNOPSIS

- Diagnosis of hand fractures and joint injuries requires history, examination, and adequate imaging studies.
- Treatment decisions are based on fracture geometry, stability, and individual patient needs.
- Non-operative principles include reduction, maintenance of reduction through casting or splinting, followed by protected motion.
- Operative treatment includes closed reduction with or without percutaneous pinning, external fixation, and open reduction and internal fixation.
- Rehabilitation is an important aspect of caring for patients with hand fractures and joint injuries and involves splinting and restoring motion.
- Secondary procedures may be considered when the desired outcome is not achieved. These include correction of malunion, tenolysis, and capsulotomy.

Introduction

Phalangeal and metacarpal fractures are estimated to account for 16.2 and 12.5 fractures per 10000 persons, respectively.¹ Appropriate diagnosis and treatment can minimize deformity and maximize function. Although many of these fractures can be managed non-operatively, appropriate follow-up is crucial for a good outcome. These injuries can result in time away from work and activities and can be complicated by stiffness and weakness. The goal of the treating physician should be to minimize deformity and maximize function. The decision to operate depends on multiple factors, including stability, location, geometry, configuration, and associated injuries, but ultimately is chosen when the anticipated outcome is better than non-operative management.²

The goal of treatment of fractures in the hand is to reduce and stabilize the fracture, maintain the reduction and begin rehabilitation to restore function. The treating physician must take into account the vocation and avocation of the injured patient, as this may affect the treatment.

Anatomy

The metacarpals and proximal and middle phalanges are anatomically divided into the head, neck, shaft, and base. The distal phalanx is divided into the tuft, shaft, and base. The carpometacarpal (CMC) joints of the index and middle fingers have little mobility, while the ring and small fingers have some motion to allow for grasp and power grip. The metacarpophalangeal (MCP) joints are stabilized by the volar plate and the collateral ligaments: the proper collateral ligaments are thicker and run between the head of the metacarpal and the base of the proximal phalanx, while the accessory collateral ligaments are thinner and have a more vertical direction, running from the metacarpal head to the volar plate. The cam shape of the metacarpal head contributes to the tightening of the collateral ligaments when the joint is flexed, stabilizing the joint and decreasing abduction and adduction, whereas in extension, the collateral ligaments are lax and allow some radial-ulnar motion. The thick intermetacarpal ligaments stabilize the second through fifth metacarpals distally, often providing stability with fractures of the metacarpal shaft. The MCP joint articulations of the thumb are hinged, allowing flexion and extension whereas MCP joints of the index through little fingers are condyloid in nature and allow flexion/extension, abduction/adduction, and circumduction.³

The proximal phalanx acts as an intercalated segment, with tendons running on all sides, but nothing inserting on this bone. The collateral ligaments of the proximal interphalangeal (PIP) joint contain a proper and accessory component, with insertions into the base of the middle phalanx and the volar plate, respectively. They function to provide lateral stability. The head is bicondylar in shape (as opposed to the cam shape of the metacarpal head) and the collateral ligaments of the PIP joint are tightest with the joint in extension. The middle phalanx has insertions of the extensor mechanism (central slip) and flexor tendon (flexor digitorum superficialis – FDS). The distal interphalangeal (DIP) joint is anatomically similar to the PIP joint and the distal phalanx contains the insertion

of the terminal portion of the extensor mechanism and the flexor digitorum profundus (FDP).

The volar plates of the MCP joints differ from the IP joints in that the MCP joint volar plate has more of an accordion-like structure, allowing for the volar plate to be compressed with flexion and expanded with extension. The volar plates of the IP joints have stout proximal extensions known as checkrein ligaments. When contracted, these can contribute to PIP flexion contractures.

The thumb has a greater degree of motion at the CMC joint, allowing for opposition to the fingers. The CMC joint of the thumb is classified as a saddle joint allowing flexion/extension, abduction/adduction as well as circumduction. The shape of the metacarpal head (radial condyle has greater dorsal–volar dimension) allows for pronation of the thumb to assist with opposition.

Classification of fractures and dislocations

Fractures of the phalanges and metacarpals may occur through the joints (articular) or along the shaft (extra-articular).

Articular fractures are more common in the PIP and DIP joints than the MCP joints. They may occur through the head or the base. Fractures through the head of the phalanges are classified as unicondylar or bicondylar and can occur in the sagittal and/or coronal plane. Fractures through the shaft can occur as transverse, oblique, or spiral planes. In addition, fractures can be classified as comminuted when there are multiple fragments.

The angular deformity of the fracture is dependent upon the forces acting on the distal bones. The deformity is classified according to the position of the distal fracture segment relative to the proximal segment. Metacarpal fractures most commonly have an apex dorsal angulation while fractures of the proximal phalanx tend to have apex volar angulation secondary to the pull of the interosseous muscles. Fractures of the middle phalanx have a variable deformity, depending on the location of the fracture. Those proximal to the insertion of the FDS have dorsal angulation due to flexion of the distal portion of the bone from the FDS, while fractures distal to the FDS insertion have apex volar angulation due to flexion of the proximal fragment (Fig. 7.1).

For a dislocation to occur, the stabilizing structures (collateral ligaments, volar plate, dorsal capsule) must be




Fig. 7.1 Angular deformity associated with fractures of the metacarpal and phalanges. **(A)** Metacarpal fractures typically have apex dorsal angulation secondary to the location of the interosseous muscles, while the proximal phalanx fractures **(B)** have an apex volar angulation. The angulation of middle phalanx fractures is dependent on the location of the fracture, relative to the insertion of the FDS tendon: fractures proximal to the insertion **(C)** will have apex dorsal angulation while those distal **(D)** will have apex volar angulation.

disrupted. Dislocations are similarly described by the location of the distal bone and are classified as dorsal, volar, radial, or ulnar.

Fracture dislocations commonly occur at the PIP joints of the fingers, and the base of the thumb and ring/small metacarpals. PIP joint and ulnar sided CMC joint fracture dislocations are most commonly dorsal. Thumb CMC joint fracture dislocations are referred as Bennett or Rolando, depending on the configuration and size of the fractured segments.

Fracture stabilization/fixation and return to function

The goal of fracture treatment in the hand is to reduce the fracture and maintain the reduction while restoring motion. Prolonged immobilization will lead to stiffness and should be avoided. Open reduction requires exposure of the fracture sites and stripping of the periosteum. This will induce scarring that impedes motion, so when open reduction is performed, it is important that fixation be stable enough to allow early motion.

For non-displaced fractures, often protection with buddy straps and active motion without resistance is adequate. For displaced or unstable fractures, reduction and fixation is necessary. Rigid internal fixation with plates and/or screws can provide an anatomic reduction, and the fractures can heal by primary bone healing, but this is not always necessary for hand fractures. This can be particularly problematic for proximal and middle phalanx fractures as there are tendons on all sides that must glide for full motion. The presence of plates and screws in this area will produce scarring and often require removal to maximize motion and ultimately function.

Functionally stable fixation implies the fracture is stable enough to begin motion. This can often be accomplished by closed reduction with percutaneous Kirschner wire (K-wire) insertion. The K-wires can be removed, leaving no internal hardware and minimizing additional scarring.

Pediatric fractures

Pediatric fractures, or fractures in patients with open growth plates require special attention. The physes are located in the metacarpal neck regions in the index, long, ring, and small fingers and at the metacarpal base in the thumb. The physes of the phalanges are located at the base. Growth plate fractures are described by the Salter–Harris classification (Fig. 7.2 and Table 7.1), with type II being the most common. An extra-articular fracture of the proximal phalanx is the most common pediatric fracture of the proximal phalanx. This is a Salter–Harris type II fracture with angulation distal to the physis. The physeal fracture is secondary to the proximal attachment of the collateral ligament.

General principles include early reduction and stabilization. An initial reduction attempt should be completed for displaced fractures, but remanipulating a fracture involving the growth plate should be minimized as this can lead to physeal arrest and premature closure of the growth plate. Generally, the use of plates and screws is avoided and hardware is removed when the fracture is healed. Stabilization of fractures can be accomplished with smooth K-wires and if




Fig. 7.2 Classification of Salter–Harris fractures. Type 1 is through the physis. Type 2 extends from the physis toward the shaft. Type 3 extends from the physis toward the joint. Type 4 starts in the shaft and extends through the physis and into the joint. Type 5 is a crush injury of the physis.

necessary to cross the physis, effort should be made to minimize the number of passes and thus further injury to the growth plate.

Open fractures

Open fractures of the distal phalanx are treated with irrigation and debridement. If the circulation is intact and the patient is

Table 7.1 Classification of Salter–Harris fractures	
Type 1	Fracture is confined to the physis, often with normal radiographs
Type 2	Fracture starts in the physis and extends through the shaft (away from the joint)
Type 3	Fracture starts in the physis and extends into the joint
Type 4	Fracture starts in the shaft and extends through the physis and into the joint
Type 5	The physis is crushed, and there may be sheering through the physis

immunocompetent, antibiotics are not necessary. Fractures of other bones in the hand are treated with antibiotics in addition to irrigation and debridement. Cephalosporins are generally used and with crush injuries or heavy contamination, an aminoglycoside is added. Bite wounds (human or animal) should have penicillin added to cover anaerobes (*Eikenella* in human bites) and *Pasteurella* in animal bites (see Chapter 16, Infections of the hand).

Bone gaps

In high-energy injuries such as gunshot wounds, the hand surgeon may be faced with a bone defect. These defects are divided into non-critical (less than 6–8 cm) and critical (greater than 6–8 cm). In a non-critical bone deficit of the hand, reconstruction with autologous bone graft allows rigid fixation to promote optimal healing.⁴ Free vascularized bone flaps are necessary when treating critical bone gap (greater than 6–8 cm), but require microsurgical expertise. Osteoconductive substrates such as calcium phosphate cement and demineralized bone are contraindicated in infected or potentially infected wounds; they also require a previously stabilized defect, as they will add no structural support.⁵

Diagnosis

The diagnosis of hand injuries begins with a history, including hand dominance and occupation as well as the mechanism of injury. The appearance of the hand should be evaluated with the fingers extended as well as flexed. The alignment of the digits may appear normal in extension, but the patient should be asked to flex the fingers as a rotational deformity may become apparent, even with limited flexion (Fig. 7.3).

Specific areas of edema, ecchymosis or tenderness are noted as well as any wounds that may be present. While general screening radiographs of the hand may be beneficial for initial evaluation, specific X-rays provide better detail and should be used once the diagnosis is made (radiographs of the injured finger are preferred over radiographs of the hand

for phalangeal fractures). Three views of the injured part are required to adequately evaluate a fracture in the hand.

Occasionally, additional studies will be necessary for diagnosis or to further define the injury. For example, a collateral ligament injury at the metacarpophalangeal (MCP) of the thumb may not be apparent with plain radiographs, but will become apparent with stress views when the joint space is increased. Magnetic resonance imaging (MRI) can also be used to evaluate collateral ligament injuries and determine if a Stener lesion is present, guiding treatment. Computerized tomography (CT) scans can be used to determine bony alignment/fracture configuration and may be helpful in some joint injuries.

Treatment: fingers

Once the diagnosis of a fracture has been made, a decision must be made regarding the best treatment. Options include protection with early motion, immobilization alone or reduction by closed or open techniques. The goal should be to reduce the fracture, maintain the reduction and return the patient to function with early motion, while minimizing stiffness.

Phalangeal fractures and dislocations

Fractures of the *distal phalanx* are among the most common fractures encountered.⁶ They can involve the tuft, shaft, or base, often extending into the articular surface of the DIP joint. Tuft fractures are often associated with nail bed injuries and repair of the nail bed often reduces and stabilizes the fracture. Shaft fractures are often stable and patients may function well after healing with a fibrous union. For those cases where the fibrous union is symptomatic, correction of the non-union/fibrous union can be performed.

DIP joint

Bony mallet fractures involve the dorsal aspect of the base of the distal phalanx. The dorsal aspect contains the terminal extensor tendon and the goal of treatment should be to allow healing of a congruent joint without an extension lag. Most of these can be treated with a splint, maintaining the alignment of the joint.^{7,8} These fractures tend to have palpable and sometimes visible prominence along the dorsal aspect of the finger following healing, even when the radiographic alignment is anatomical, but this typically does not adversely affect their function. Fractures with volar subluxation of the distal phalanx should be reduced and often require pinning of the joint to maintain the reduction.⁹ Several techniques have been described, but all involve reduction of the joint surface.^{10–12} Attempted screw placement into the fragment is difficult, even when the fragment appears large on radiograph, and often results in fragmentation of the dorsal bone. Surgical treatment of stable fractures without subluxation is generally reserved for patients who cannot wear the splint continuously during the healing process, as complications such as pin breakage, pin tract infections and subsequent osteomyelitis can occur, and the risks must be carefully considered.

DIP joint dislocations are typically in a dorsal direction (distal phalanx is dorsal to the middle phalanx) (Fig. 7.4). Acute dislocations can often be managed by closed reduction.




Fig. 7.3 Clinical example of malrotation of the middle finger secondary to a metacarpal fracture.




Fig. 7.4 Radiograph of DIP dorsal dislocation of index finger.

Flexing the wrist and MCP joints to take the tension off the flexor tendons, and applying distal pressure to the base of the distal phalanx will often reduce the joint. If this is unsuccessful, it is often due to tissue interposed in the joint – most commonly the volar plate – and an open reduction is necessary.¹³ This can be completed through a volar zig-zag incision or midlateral incisions. The joint is exposed and any intervening tissue is removed, taking care to avoid damaging the articular cartilage, and the joint is reduced. Late presentation of DIP joint dislocations will usually require open reduction, using the same technique. Following reduction, these injuries are typically stable and immediate motion can be started using a dorsal blocking splint.

Fractures involving the proximal aspect of the DIP joint can occur as isolated middle phalanx articular fractures, involving one or both condyles and may extend proximally into the shaft (diaphysis). Stable fractures can be managed with protective splinting and followed closely with radiographs. If alignment is maintained, buddy taping and range-of-motion (ROM) exercises can begin around 3 weeks and can be continued for an additional 3 weeks or until radiographic healing is present. Unstable or displaced fractures should be reduced and stabilized either with K-wires or screws.

Middle phalanx shaft fractures

Treatment of middle phalanx shaft fractures depends on stability and fracture pattern (transverse versus oblique/spiral). Stable, non-displaced fractures can be managed with a short period of immobilization (typically 2–3 weeks) followed by protected motion with buddy taping. They should be followed closely, checking for displacement and clinical signs of malrotation. This should be checked with the fingers in flexion. Any evidence of malrotation is an indication for reduction and stabilization.

Oblique fractures tend to be unstable, even following closed reduction, and often result in shortening, which is poorly tolerated by the extensor mechanism. Spiral fractures shorten and rotate. Therefore, these fractures are usually best treated with stabilization. Stiffness is common following these

injuries, making postoperative rehabilitation important to optimize the outcome. Plate and screw fixation can provide good stability and allow early motion, but hardware tends to irritate extensor tendons, often resulting in adhesions, necessitating removal and tenolysis to improve tendon gliding. Lag screws are better tolerated than plates, but still require soft tissue dissection, which can result in adhesions and limit postoperative motion. K-wire fixation can often be accomplished with minimal soft-tissue stripping and can easily be removed following healing, but the fixation is not rigid, so the rehabilitation program cannot be as aggressive. These fractures take a longer to heal due to the higher ratio of cortical to cancellous bone (in comparison to the proximal phalanx and metacarpal), but are usually stable enough to remove the K-wires between 4 and 6 weeks. Radiographic healing may take up to 4 months. A removable splint for protection and protected motion with buddy strapping is instituted to maximize motion.

PIP joint injuries

Injuries around the PIP joint are challenging to treat and good outcomes can be difficult to obtain. Stiffness is common and causes difficulty with gripping and grasping activities, as well as fine dexterity. The small size of the articular fracture fragments can make it difficult to maintain reduction. The goal in treating injuries of the PIP joint is to create a congruent joint and begin a rehabilitation program aimed at restoring motion.

The PIP joint functions as a hinge joint with approximately 100° of motion in the sagittal plane (flexion/extension) and minimal motion in the coronal or axial planes. The base of the middle phalanx is a biconcave surface with a central ridge. The volar lateral aspects of the bone are the sites of insertion of the proper collateral ligaments. The volar plate is a fibrocartilaginous structure, which provides additional stability to the joint. It has thicker fibers that insert laterally and thinner fibers, which insert centrally, to the base of the middle phalanx and proximal extensions (checkrein ligaments), which attach to the periosteum on the proximal phalanx. The volar base of the middle phalanx and its curvature play an important role in stability, preventing dorsal subluxation of the middle phalanx.

The head of the proximal phalanx contains two condyles, separated by a groove or sulcus. There is a slight difference on the size of each condyle, allowing the fingers to converge in flexion. The index and middle have a slightly larger radial condyle while the small finger has a slightly larger ulnar condyle.

Injuries involving the PIP joint can involve fracture of the base of the middle phalanx, the head of the proximal phalanx, a pure dislocation, or any combination of these. Fractures involving the base of the middle phalanx include dorsal base fractures (involving the insertion of the central slip of the extensor mechanism), the volar base, resulting dorsal subluxation of the middle phalanx, avulsion of the collateral ligaments, or pilon type of fracture involving the dorsal and volar margins, with a depressed central articular fragment (Fig. 7.5). Fractures involving the proximal phalanx head can involve one or both condyles and can occur with or without proximal extension.

Pure dislocations result from hyperextension and an axial load. They are often dorsal dislocations and are managed




Fig. 7.5 Classification of PIP joint fracture dislocations. (A) Volar base fracture resulting in dorsal subluxation of the middle phalanx. (B) Dorsal base fracture resulting in volar subluxation of the middle phalanx. (C) Pilon type fracture with dorsal and volar base fractures and comminuted, depressed central articular surface.

similar to the DIP joint, with an initial trial of closed reduction (with the wrist and fingers flexed and distal pressure on the base of the middle phalanx). When successful, a dorsal blocking splint and early active flexion can produce good results. When reduction cannot be completed by closed means, open reduction is indicated, either through a volar or midlateral approach.¹⁴

Volar dislocations are less common, but can lead to late deformities if not recognized and treated.¹⁵ The central slip is often injured and can result in late boutonniere deformities. Following reduction, splinting the PIP joint in extension and active flexion of the DIP joint will allow gliding of the lateral bands. Active flexion can be started following three weeks, as further immobilization of the PIP joint may result in permanent stiffness. Irreducible dislocations are due to an interposed central slip or collateral ligament and require open reduction through a dorsal approach, allowing direct inspection of the central slip.

Middle phalanx base articular fractures

Fracture dislocations of the PIP joint result from an axial load in a dorsal direction or longitudinal direction when the finger




Fig. 7.6 Stability of PIP fracture dislocations. Fractures involving <30% of the articular surface are typically stable. Those involving 30–50% are tenuous and those involving >50% are unstable and have resultant dorsal subluxation.

is slightly flexed. These injuries are classified according to the amount of the articular surface involved. Fractures involving <30% of the articular surface of the base of the middle phalanx are typically stable and can be managed non-operatively. Fractures involving 30–50% of the articular surface are tenuous and often are unstable. Fractures involving >50% are unstable and result in dorsal subluxation of the middle phalanx (Fig. 7.6).¹⁶

Lateral radiographs should be carefully evaluated for the “V sign”, indicative of dorsal subluxation (Fig. 7.7). The two condyles of the proximal phalanx should be superimposed and the base of the middle phalanx should be collinear with the head of the proximal phalanx. There should be a smooth curvature of the joint surface, with a consistent space between the proximal and middle phalanx. If there is convergence of the joint space creating a dorsal “V”, the patient may be able to flex the digit at the PIP joint, but this occurs through a hinge process rather than rotation, and the joint surface will degenerate.

Treatment is directed at recreating a congruent joint surface and restoring motion. Stable fractures and those which are classified as tenuous but maintain stable reduction and a congruent joint with no more than 30° of flexion can be managed non-operatively with a dorsal extension block splint. Active flexion is initiated and extension is allowed short of the point of subluxation. These patients should be followed closely to ensure that subluxation of the joint does not develop. Unstable fractures, or those which a congruent joint




Fig. 7.7 The lateral “V” sign indicating dorsal subluxation of the middle phalanx and associated hinging with flexion.

cannot be established with $<30^\circ$ of flexion, require operative treatment.

A variety of techniques have been described, including extension block pinning,^{17,18} open reduction and internal fixation,¹⁷ volar plate arthroplasty,^{18,19} replacement arthroplasty,^{20,21} and external fixation. All of these techniques have case reports or small series illustrating good outcomes, but there are no prospective studies indicating one technique is better than others for a particular injury.²²⁻²⁴

Hints and tips

- Fluoroscopy can be helpful to determine stability of PIP dorsal fracture dislocations.
- The patient can actively flex and extend the digit and the point of subluxation can be determined.
- If this is $<30^\circ$, an extension blocking splint with active flexion can be used.
- If this is $>30^\circ$, operative treatment is indicated.

External fixation

A variety of devices have been described for management of PIP joint fracture dislocations.²²⁻²⁵ The common principle is to produce distraction across the joint, allowing alignment to be maintained through ligamentotaxis. In addition, some devices provide a volar directed force on the middle phalanx to assist in maintaining alignment. They all allow immediate PIP joint motion. Careful attention should be paid to the fragments along the volar base of the middle phalanx as dorsal subluxation can recur if these do not heal in proper position (the volar lip of the base of the middle phalanx is a restraint to dorsal subluxation, so healing of the fracture fragments must recreate the normal curvature).

External fixation systems can be fabricated from K-wires with or without the use of rubber bands, or commercially available devices can be used. Fig. 7.8 illustrates an example of a PIP joint fracture dislocation in the small finger managed with an external fixator fabricated from K-wires.

Technique of external fixation

A 0.045-inch K-wire is inserted through the head of the proximal phalanx, perpendicular to the joint surface (Fig. 7.8). A second 0.045-inch K-wire is inserted through the distal shaft of the middle phalanx, parallel to the DIP joint surface. The proximal wire is bent distally along the radial and ulnar aspects, paralleling the digit. Distal to the second wire, a dorsal proximal bend is created, followed by a dorsal distal bend. The bends should be at the same level on both the radial and ulnar sides. This creates a groove in the proximal wire for the distal wire to be positioned, allowing slight distraction across the joint, which will aid the reduction via ligamentotaxis. Increasing or decreasing the first bend on the proximal wire can adjust the distraction across the joint. This can be performed under local anesthesia and immediate motion is initiated. The fixator is left in place for approximately six weeks and rehabilitation focuses on motion of the PIP and DIP joints. The joint surface will remodel over time.

Internal fixation

Internal fixation of middle phalanx base fractures can be demanding, but good results can be obtained. Postoperative rehabilitation is critical to a good outcome, so the patient must be compliant or the result can be a good radiograph with a stiff non-functional finger. Larger fragments can often be stabilized with small screws, reconstructing the volar base of the middle phalanx (Fig. 7.9). Dorsal fragments can be stabilized with screws or K-wires to reinsert the central slip. Comminution at the base of the middle phalanx creates a greater challenge and the surgeon should be prepared for this as often what appears as a large piece on X-ray is found to be multiple smaller pieces. If the articular surface can be reduced, a cerclage wire may be used to hold the bone fragments in place (Fig. 7.10).²⁶ This may provide adequate stability to allow early motion.

If the remaining fragments are too small to stabilize, they can be excised and the joint surface is reconstructed. The two most common methods to accomplish this are by advancing the volar plate (volar plate arthroplasty) or replacement of the volar base of the middle phalanx. This can be accomplished by using a portion of the hamate (hemi-hamate graft/replacement arthroplasty, HHRA).

The volar plate arthroplasty was described by Eaton and Malerich in 1980¹⁹ and involves excision of the collateral ligaments, removing the comminuted portion of bone along the volar aspect of the base of the middle phalanx, creating a trough parallel to the dorsal surface of the middle phalanx, and advancing the volar plate to resurface the joint. The volar plate is attached to the bone, either through drill holes or with a permanent suture at the lateral aspect. The joint is temporarily pinned in slight flexion. At 3 weeks, the pin is removed and motion is begun.¹⁸ The volar plate serves to prevent dorsal subluxation of the middle phalanx. The results with this technique can be unpredictable as stiffness and recurrent dorsal subluxation can occur. Long-term follow-up of Dr. Eaton's patients have been published with good results,²⁷ but there are few recent reports of this procedure.

More recently, the hemi-hamate replacement arthroplasty has been described (Hastings *et al.*, ASSH annual meeting, 1999) and subsequently published. The dorsal distal portion of the hamate has similar anatomy to the volar base of the middle phalanx. Osseous cuts must be precise and the curvature of the volar base of the middle phalanx must be reproduced or persistent dorsal subluxation will occur. This can be rigidly fixed and early motion can be instituted. Published series have shown promising results.^{21,28}

Technique of HHRA (Video 7.2)

The finger is approached from the volar aspect with a Bruner incision from the palmodigital crease to the DIP flexion crease (Fig. 7.11). Skin flaps are elevated and retracted. The digital neurovascular bundles are freed so they are not under tension when the joint is exposed. A radial or ulnar based flap of the flexor sheath is created between the A2 and A4 pulleys. The collateral ligaments are released from the middle phalanx, leaving a small stump for later repair, and the volar plate is released from fragments at the base of the middle phalanx. The neurovascular bundles are inspected to make sure they will not tether as the joint is exposed. The flexor tendons are




Fig. 7.9 (A) Preoperative and (B) postoperative radiographs of patient with middle phalanx base fracture treated with ORIF. (C) Clinical photograph in flexion following rehabilitation.



Fig. 7.10 Postoperative radiograph of cerclage wire (and K-wire) used to repair middle phalanx base articular fracture. Radiographically, the wire does not appear secure dorsally because this is secured around the articular cartilage (not seen on radiograph) and cannot be placed further distally due to the central slip insertion.




Fig. 7.8 (A) Fabrication of external fixator from K-wires. (B) Preoperative radiograph of PIP fracture dislocation involving the small finger. (C) Radiograph with external fixator in place, allowing motion. (D) Postoperative results in flexion.

retracted and the joint is shot gunned open exposing the joint. If resistance is encountered, it is usually due to the collateral ligaments; these are inspected, ensuring complete release from the middle phalanx.

Once the joint is exposed, the loose fragments are removed and a smooth surface is created along the joint surface and along the volar margin of the middle phalanx. This will be the site of insertion of the hemi-hamate graft. Care must be taken to preserve as much of the dorsal cortex as possible as this becomes prone to fracture if insufficient bone remains. The defect for the graft should be large enough to allow fixation of the graft with at least two screws. The dimensions of the defect are measured so an appropriate size graft can be obtained.

Next, a dorsal transverse incision is outlined proximal to the base of the ring and small metacarpals to expose the distal aspect of the hamate. Fluoroscopy can be used to confirm the

correct location of the incision. Care is taken to preserve the dorsal sensory branch of the ulnar nerve and a transverse capsulotomy is performed exposing the joint CMC joint of the 4th and 5th metacarpals. The dimensions of the graft are outlined and the graft is harvested slightly larger than necessary, so it can be trimmed to the appropriate dimensions. The axial and sagittal cuts are made using a small saw. A portion of the dorsal hamate can be removed proximal to the axial cut to facilitate the coronal cut from proximal to distal. Alternatively, a portion of the dorsal fourth and fifth metacarpal base can be removed to allow better visualization and access for the osteotomy from distal to proximal. This can be completed with a curved osteotome. The graft is removed and the donor site is closed. The graft is placed along the base of the middle phalanx and provisionally fixed with small K-wires. This step is crucial as proper positioning is necessary for a good outcome. The graft must be placed so the normal curvature




Fig. 7.11 Technique of hemi-hamate replacement arthroplasty. Preoperative PA (A) and lateral (B) radiographs and clinical photographs in extension (C) and flexion (D). Diagram (E) of configuration of hemi-hamate graft. Intraoperative photograph (F) of graft secured (note articular wear on the head of the proximal phalanx due to delay in presentation).



Fig. 7.11, cont'd Postoperative clinical photograph (G) and lateral radiograph (H).

of the middle phalanx base is recreated. If the graft is positioned too vertically, dorsal subluxation of the middle phalanx will occur. The joint is reduced and visualized with fluoroscopy. The joint should now appear congruent, with appropriate curvature of the middle phalanx base and without evidence of the dorsal “V”. The cartilage on the graft is typically thicker than the middle phalanx, so images may appear as if the graft is not in proper position. This can be ignored since direct visualization will ensure alignment of the joint surface. The joint is opened and the K-wires are replaced with small screws (1.0–1.5 mm), rigidly securing the graft to the middle phalanx. The joint is reduced and fluoroscopy is used to confirm appropriate length of the screws and position of the graft.

The volar plate is repositioned and can be repaired to the collateral ligament stumps or to the graft. K wires can be used to create small holes in the graft to secure the volar plate. The stability of the reconstructed PIP joint (and prevention of dorsal subluxation) is created by the shape and position of the hemi-hamate graft. The flexor sheath can be placed dorsal to the flexor tendons and secured to the opposite side. The skin is closed, the tourniquet is deflated and perfusion of the digit is evaluated. Occasionally, the vessels are in spasm, but the perfusion should be restored within a few minutes. A volar splint is placed from the forearm to the fingertips.^{20,29} Rehabilitation is begun around day five with attention to edema control and motion. A figure-of-eight splint is used to prevent the final 10–15° of extension. A removable wrist orthosis is used for comfort to support the donor site.

The average arc of motion at the PIP joint has been reported between 65° and 100° (average 85°) with return to light activities at one month and return to manual labor at 2 months.^{21,28}

If the entire base of the middle phalanx is involved, replacement arthroplasty can be considered, but there are only a few case reports of this technique. Hemiarthroplasty has been reported, but currently, the use of the PyroCarbon and surface replacement arthroplasty requires special approval and is not available for routine use in the PIP joint.

Hints and tips

- When positioning the hemi-hamate graft, ensure the graft is positioned to recreate the concavity and volar buttress to prevent dorsal subluxation.
- Postoperative therapy and a motivated patient are critical to obtain a good result following PIP joint fracture dislocations.
- The patient should be informed that the goal is to create a stable joint with motion, but the return of motion to the pre-injury level is rare.
- Some degree of post-traumatic PIP joint arthritis is inevitable, but this does not always correlate with functional outcomes.

Proximal phalanx head fractures

Fractures involving the head of the proximal phalanx are intra-articular and anatomic reduction and early motion of these injuries is the goal. Fractures can involve one or both condyles and classification systems have been described.³⁰ These fractures are often unstable and require treatment. Stable, non-displaced fractures can be treated with a short period of immobilization with frequent radiographic evaluation. Motion is typically started at three weeks and the finger is protected with buddy taping to an adjacent digit. Displaced or unstable fractures require reduction and stabilization.³⁰ Fixation is dependent on the size of the fragment and the ability to reduce the joint with closed manipulation. If anatomic alignment can be obtained with closed reduction and the fragment can be stabilized with K-wires, these can be treated as a stable non-displaced fracture. Often, anatomic reduction requires open exposure. The fragments are often large enough to hold at least one small (1.0 mm) screw and a K-wire or two screws. This provides enough stability to begin early motion and minimizes adhesions to the extensor tendons. When both condyles are involved, initial alignment and stabilization of the articular surface is preferred. Then, the

articular surface can be secured to the shaft either with K-wires or plates and screws. Although plates and screws provide good stability, they require more dissection, and adhesions to the extensor tendons are likely to occur, often requiring a secondary procedure to remove the hardware and perform a tenolysis.

Technique of open reduction and internal fixation (ORIF) of unicondylar fractures

A straight or curvilinear dorsal approach is used from the middle of the proximal phalanx to the middle of the middle phalanx. Skin flaps are elevated to expose the extensor tendon distal to the insertion of the central slip on the middle phalanx. The joint can be exposed by splitting the extensor tendons or an incision to the side of the central slip with release of the lateral band. Better visualization is obtained through exposure along the side of the central slip on the side with the fracture. The tendon is elevated off the proximal phalanx, taking care to preserve the insertion of the central slip. A capsulotomy is performed, exposing the head of the proximal phalanx. The fragments are reduced under direct visualization and temporarily stabilized with small K-wires. Fluoroscopy is used to confirm alignment and the K-wires are replaced with screws. The capsule can be repositioned, but does not need to be closed with sutures. If the tendons were split, they are repaired with a non-absorbable suture. The central slip insertion is inspected to confirm it has not been disrupted. The skin is closed and a splint is applied. Rehabilitation begins around the fifth postoperative day with edema control and a figure-of-eight splint, allowing flexion and blocking the final 10° of extension (Fig. 7.12).

Proximal phalanx shaft and base fractures

Fractures of the shaft of the proximal phalanx can be transverse or oblique. Transverse fractures typically have apex volar angulation and are unstable. Fractures of the base are typically transverse. If not reduced and stabilized, the extensor mechanism will shorten, creating an extensor lag at the PIP joint. Percutaneous fixation has the advantage of stabilizing the fracture and allowing early motion while minimizing soft-tissue injury.³¹ Two crossed K-wires typically provide enough stability to allow early motion. The wires can be inserted proximally through the base with one on each side of the metacarpal head or distally, with one entering along the head or neck. Alternatively, the K-wires can be placed through the MCP joint in flexion (Fig. 7.13). The disadvantage is the K-wire is passed through the articular surface, but in cases with substantial soft-tissue edema, this may help prevent MCP joint extension contractures. By 3–4 weeks, the fracture is usually stable enough for removal of the K-wires. Protected motion should occur until complete fracture healing. Radiographic healing lags behind clinical healing, which typically occurs around 6 weeks. ORIF with plates and screws can allow immediate motion, but adherence of the tendon to the hardware can be problematic, often resulting in stiffness and need for secondary procedures.³²

Oblique or spiral fractures should be evaluated in flexion as well as extension. These often shorten obliquely, resulting in a rotational deformity. Fixation can be accomplished with either K-wires or interfragmentary screws if the length of the fracture is two times the length of the diameter of the bone. ORIF with interfragmentary screws allows enough stability to proceed with early active motion and when anatomically




Fig. 7.12 Preoperative lateral radiograph (A) of displaced unicondylar fracture. Postoperative lateral (B) radiograph in flexion.



Fig. 7.13 Preoperative and postoperative PA radiograph of proximal phalanx shaft (**A,B**) and base (**C,D**) fractures treated with K-wires.



Fig. 7.14 Preoperative (A) and postoperative (B) radiographs of proximal phalanx fracture treated with interfragmentary screws.

reduced, primary bone healing ([Fig. 7.14](#)). Adhesions between the screws and tendons are less when plates are not used, and although removal is sometimes necessary, often the screws can be left in place.

MCP joint fractures and dislocations

Fractures extending into the articular surface of the MCP joint should be reduced anatomically and stabilized, in an effort to minimize the development of post-traumatic arthritis.

Dislocations of the MCP joint can occur in any direction, with dorsal being the most common. The border digits (index and small finger) are most commonly involved ([Fig. 7.15](#)).³² The volar plate ruptures from the proximal phalanx, allowing it to sublux dorsally, with the proximal phalanx extended in relation to the metacarpal. If the volar plate does not become interposed in the joint, these can be treated with closed reduction. The wrist is flexed to relax the flexor tendons and distal pressure is applied to the base of the proximal phalanx. A snap or pop is often felt, which is the reduction of the joint. Radiographs are obtained to confirm the reduction. The joint is typically stable following reduction, but an extension block splint can be used if instability exists.

When the volar plate becomes interposed in the joint, the dislocation is complex and closed reduction attempts are unsuccessful. Dimpling of the skin is seen over the dislocation. Radiographs will show the proximal phalanx and metacarpal collinear (as opposed to the convergence seen with simple dislocations). In the index finger, the lumbrical displaces around the radial side and the flexor tendons around the ulnar side. Distal pressure on the proximal phalanx base tightens the lumbrical and flexor tendons around the metacarpal neck, creating a noose effect and preventing reduction.

In the small finger, the flexor tendons and lumbrical displace radially while the flexor digiti minimi displaces ulnarly, creating the same noose-like effect when closed reduction is attempted.



Fig. 7.15 Radiographs of MCP dorsal dislocation.

Open reduction through a dorsal or volar approach is necessary.³³ The volar approach is more direct, but the metacarpal head pushes the digital nerves closer to the skin and care must be taken to avoid injuring them with the skin incision. The A-1 pulley is released, exposing the metacarpal head, and the volar plate is removed from the joint. The flexor tendons are pulled over the metacarpal, allowing reduction. The dorsal approach does not allow direct visualization, but avoids the risk of injuring the digital nerves with the incision. The extensor tendons are split longitudinally. If the volar plate cannot be easily removed from the joint, it can be split longitudinally, allowing each side to be pushed out of the joint. The joint can then be reduced with distal pressure on the proximal phalanx base while pushing the flexor tendons around the metacarpal head. The joint is typically stable following reduction, but extension block splinting can be used if instability exists.

Hints and tips

- For MCP joint dislocations, attempt closed reduction with the wrist maximally flexed; if unsuccessful, proceed to open reduction.
- The volar open approach is more direct, but it places the digital nerves at risk during the skin incision as they will be tented beneath the skin.
- The dorsal open approach often requires splitting the volar plate to allow complete reduction.

Volar dislocations of the MCP joint are rare. Interposed structures can include the dorsal capsule, extensor tendon junctura, collateral ligament or the volar plate.^{33,34} When closed reduction is unsuccessful, open reduction is performed through a dorsal approach.

Metacarpal fractures

Relative to phalangeal anatomy, the metacarpals have more soft tissue between bone and tendons, making them less susceptible to adhesion formation. As such, stiffness following recovery is less common. Metacarpal fractures commonly occur as a result of a direct blow. They can occur through the head, neck, shaft, or base.³⁵ Fracture configuration is usually transverse, oblique, or spiral. Transverse fractures occur as a result of an axial load with bending and result in apex dorsal deformity. Oblique or spiral patterns occur with torsional stress when an axial load is received.

Indications for operative treatment of metacarpal fractures

A rotational deformity is an indication for operative treatment. Malrotation of 1° at the metacarpal translates to 5° rotation at the fingertip, furthermore malrotation of 5° in the metacarpal can result in 1.5 cm of overlap at the fingertips and thus, evaluation of the fingers in flexion is imperative. Other indications include: shortening of 2–3 mm, articular step-off greater than 1 mm, greater than 25% articular involvement, and multiple fractures. As the amount of energy increases, the amount of comminution increases and stability decreases, and the incidence of multiple fractures increases.

An open wound over the MCP joint region should be treated as a “fight bite”, with irrigation of the wound and inspection of the extensor tendon and joint capsule. Alignment of the fingers is evaluated with the fingers in flexion to check for rotation. Three views of the hand (posterior–anterior, lateral, and oblique) are often adequate for diagnosis of metacarpal fractures. Additional images include a Brewerton view to improve visualization of the metacarpal heads. This is an A-P view with the phalanges flexed to 45–60° and in contact with the film (the metacarpals are elevated at a 45–60° angle and the beam is directed 15° from ulnar to radial). A 30° pronated oblique view improves visualization of the ring and small finger CMC joints, while a 30° supinated view helps visualize the index and middle finger CMC joints. CT scans can be used when plain radiographs are inconclusive, multiple CMC fracture dislocations are present, or for complex metacarpal head fractures.

Many metacarpal fractures are stable and can be treated non-operatively. Boxer’s fractures (fifth metacarpal neck) are impaction fractures and although there is angulation of the metacarpal neck, they are stable. This term is a misnomer as professional boxers rarely sustain this injury; this injury commonly occurs when a firm object, such as a wall, is struck. The intermetacarpal ligaments stabilize fractures involving the middle and ring metacarpals and often alignment is maintained with minimal shortening.

Forces on the metacarpal bases result in proximal displacement and shortening, due to deforming forces that act on each digit, including the adductor pollicis longus (on the first metacarpal), the extensor carpi radialis longus and brevis (on the second and third metacarpal), and the extensor carpi ulnaris (on the fifth metacarpal). More distal metacarpal shaft or neck fractures result in apex dorsal angulation due to the pull of the intrinsic muscles of the hand.

Metacarpal head fractures

Treatment of fractures involving the metacarpal head involves anatomic reduction and stabilization. A dorsal approach is used and the extensor tendon is split or the sagittal band incised to expose the metacarpal head and MCP joint. Rigid fixation is preferred when possible, so use of small screws placed through the collateral recess or headless screws are preferred, with the goal of early motion. Severely comminuted fractures are problematic as stiffness and arthritis often result. Hemi-arthroplasty, replacing the metacarpal head, has been described, but there is no long-term data to support its routine use.

Metacarpal neck fractures

Metacarpal neck fractures are the most common metacarpal fracture and are more common on the ulnar side of the hand (fifth metacarpal, Boxer’s fracture), but can occur in any of the fingers. The amount of apex dorsal angulation that is acceptable varies between patients depending on vocation and avocations, but increases from radial to ulnar. Due to the mobility at the ring and little finger CMC joints, allowing 20°–30° mobility in the sagittal plane. The lack of mobility at the index and middle fingers makes angulation of greater than 15° unacceptable. Acceptable angulation for the ring finger is between 20° and 40°, and the small finger up to 60°.³⁶ This deformity will result in loss of prominence of the




Fig. 7.16 The Jahss maneuver for reduction of a metacarpal neck fracture. The DIP and PIP joints are flexed and dorsal pressure is applied to the PIP joint while counter pressure is applied to the metacarpal shaft proximal to the fracture.

“knuckle” (metacarpal head) with a proximal prominence along the metacarpal neck and occasionally noticeable prominence in the palm; the flexed metacarpal head. This is unlikely to cause functional limitations. Occasionally, pseudo-clawing will develop secondary to the flexed position of the metacarpal head, MCP hyperextension, and PIP joint flexion.

Treatment is dependent on the existing deformity. Closed reduction and immobilization often provides adequate alignment and can be used for definitive management.³⁷ Flexing the MCP joint to 90°, which relaxes the deforming intrinsic muscles and simultaneously tightens the collateral ligaments, allows for control of the distal metacarpal fragment. The Jahss maneuver involves flexion of the distal interphalangeal, proximal interphalangeal, and metacarpophalangeal joints followed by dorsally directed pressure over the flexed PIP while applying a volar directed force over the apex of the fracture.³⁸ This maneuver delivers the three-point fixation needed for fracture immobilization and ensures reduction with appropriate angulation and rotation. After the Jahss maneuver has been performed, the hand can be immobilized, either in intrinsic plus position or with MCP and PIP joints extended, as outcomes are similar.³⁹ A cast or splint is not always successful in maintaining reduction, especially with the swelling associated with the fracture (Fig. 7.16).

Indications for operative treatment include malrotation or unacceptable alignment following closed reduction. Surgical options include closed reduction and percutaneous pinning

(CRPP), intramedullary (IM) wires, and open reduction internal fixation (ORIF). The distal location of metacarpal neck fractures makes stabilization with plates difficult.

The MCP joint is flexed and alignment is evaluated, correcting any malrotation. Percutaneous K-wires can be placed from distal, through the collateral recess, or proximal through the metacarpal base. Alternatively, the wires can be placed transverse, stabilizing the fifth metacarpal to the fourth metacarpal, or multiple wires as intramedullary nails (bouquet pinning). This is completed through an incision proximally near the metacarpal base. After exposing the bone, an awl or similar instrument is used to creating an opening in the bone and wires are placed into the shaft. The reduction is confirmed with fluoroscopy and the wires are advanced across the fracture site and into the bone distally. These wires are typically left out of the bone proximally to allow removal following healing, but can be cut and left within the bone. Depending on stability, postoperative immobilization is often required for 4–6 weeks, followed by therapy to regain motion.

ORIF is performed when reduction cannot be attained by closed means or when there is a desire to minimize postoperative immobilization. It is completed through a dorsal approach, either splitting the extensor tendons (small or index finger) or along the side. If adequate stability is achieved, the patient can be transitioned to a removable splint and begin active motion within the first week.

Metacarpal shaft fractures

Isolated metacarpal shaft fractures are often stable and amenable to non-operative management. The intermetacarpal ligaments stabilize the distal metacarpal and maintain alignment. Similar to metacarpal neck fractures, the amount of acceptable apex dorsal angulation is debated, but increases ulnarly and distally. The amount of acceptable angulation is less in the shaft than in the neck, with <10° in the index and middle fingers and approximately 20° in the ring and 30° in the small finger.

Non-operative treatment includes immobilization for about 4 weeks, with the MCP joints flexed and the IP joints free. Operative indications include open fractures, malrotation and unacceptable angulation (Fig. 7.17). Similar to metacarpal neck fractures, closed reduction and pinning can be completed from distal or proximal, transversely into the adjacent metacarpal⁴⁰ or with IM wires.⁴¹

ORIF can be completed with interfragmentary screws for spiral or oblique fractures or with plates and screws for transverse fractures.⁴² Coverage of the plate with periosteum, when possible, will decrease tendon irritation and need for later removal. Early motion should be initiated following ORIF to prevent tendon adhesions.

Severely comminuted fractures, those with segmental bone or soft tissue loss can be treated with external fixation, either temporarily until adequate soft-tissue healing for internal fixation, or in some cases definitively.^{43–45}

Multiple metacarpal fractures

Multiple metacarpal fractures are often the result of higher energy and result in greater soft-tissue disruption. In addition, the stability provided by the transverse intermetacarpal ligament is lost and stabilization is often necessary.




Fig. 7.17 Radiographs of metacarpal shaft fracture treated with ORIF due to malrotation (A,B). (See the preoperative clinical picture in Fig. 7.3.)

Technique of ORIF of multiple metacarpal fractures

For two metacarpal fractures, the skin incision can be placed between them. The incision can be curved proximally or distally as necessary as the locations of the fractures are often different in each bone. When three or four fractures are present, more than one incision will be necessary. Dissection is carried to the level of the extensor tendons, taking care to protect sensory branches of the ulnar (fourth and fifth metacarpals) and the radial (second and third metacarpals) nerves. The extensor tendons are retracted and the metacarpal is visualized. There is often hematoma and disruption of the periosteum around the fracture site. A longitudinal incision is made off axis of the metacarpal and the fracture is exposed.

The adjacent metacarpal is exposed in a similar manner. Beginning with the most radial fractured metacarpal, any interposed tissue is removed from the fracture site. The fracture is reduced and provisionally stabilized (either with a fracture reduction forceps or K-wires), while alignment of the fingers is checked, making sure there is no malrotation. Interfragmentary screws or plate and screws are applied; fluoroscopy is used to confirm positioning of the hardware and the adjacent metacarpal is addressed. After all fractures are stabilized, the periosteum is closed, creating a layer of tissue between the hardware and the extensor tendons. A splint is applied for comfort and motion can begin as the swelling subsides, typically between 3 and 5 days postoperatively.

CMC dislocations/fracture dislocations

Fractures of the metacarpal base, fracture dislocations of the CMC joint and dislocations involving the CMC joint usually involve the ring and small fingers. Fracture dislocations may involve the capitate and hamate in addition to the metacarpal base.^{46,47} These patients will have a prominence along the ulnar side of the hand in the region of the CMC joints. Diagnosis is confirmed in the pronated oblique view, observing the relationship between the carpus and base of the metacarpal. The dorsal aspect should be collinear and when subluxation is present, the metacarpal will be positioned dorsal to the carpus. CT scan can be used when the diagnosis is not clear on plain radiographs or to define fracture geometry. These injuries are often unstable and require operative treatment. Closed reduction and percutaneous pinning is usually successful when performed within the first several days (Fig. 7.18). Delayed presentation usually requires open reduction. Stabilization is obtained using K-wires across the CMC joints. The K-wires are removed at four to six weeks and motion is resumed with protective splinting for comfort. Alternatively, a plate can be applied across the CMC joints with planned removal once soft-tissue healing has occurred.

Treatment: thumb

Injuries to the thumb distal and proximal phalanges can be managed similarly to the fingers. Metacarpal shaft fractures can tolerate more rotation and angulation due to the greater degree of freedom in three planes (flexion/extension, radial/ulnar deviation, pronation/supination) of the CMC joint. Injuries involving the MCP joint, specifically collateral ligament injuries and those involving the CMC joints require special consideration.

MCP joint injuries

The primary motion of the MCP joint is flexion/extension. The radial condyle of the metacarpal head has a greater height (dorsal/volar dimension), allowing rotation (pronation) with increasing flexion. Stability of this joint is provided by the collateral ligaments, the dorsal capsule and the volar plate, the thenar muscles and the adductor pollicis.

Injuries involving the ulnar collateral ligament are more common than the radial collateral ligament (RCL) and have been reported to occur at a 10:1 ratio.^{48,49} This typically results from forced abduction (radial directed stress), such as falling with an object, such as a ski pole, in the first web space. The




Fig. 7.18 Preoperative radiograph (A) and intraoperative fluoroscopic image (B) of fourth and fifth CMC dislocations.

dorsal capsule tears along the ulnar aspect of the joint and the proximal phalanx supinates around the intact RCL, creating a prominence of the ulnar aspect of the metacarpal head. Although commonly used to describe this injury, the term “gamekeeper’s thumb” more accurately defines a chronic injury from repetitive radial directed stress resulting in attenuation of the ligament. This occurred in Scottish gamekeepers while breaking the necks of rabbits between their thumb and index fingers. The term “skier’s thumb” is more accurate and the preferred term when referring to acute injuries.

Injuries typically involve disruption of the ligament from the base of the proximal phalanx. This can occur as a bony avulsion or pure ligamentous injury. Larger fractures (those >2 mm), those involving >10% of the articular surface, or

those with articular incongruity are best treated with open reduction and stabilization.^{49,50}

Isolated ligamentous injuries can be more challenging to diagnose. Avulsion from the proximal phalanx is five times more common than midsubstance tears or avulsion from the metacarpal.⁵¹

Stener lesion

In 1962, Stener described the injury where the complete ulnar collateral ligament tear retracted proximally and the adductor aponeurosis was interposed between the ligament and the site of avulsion along the base of the proximal phalanx (Fig. 7.19). Without contact between the ligament and bone, healing




Fig. 7.19 Stener lesion of the MCP joint of the thumb. (A) Normal relationship of the adductor aponeurosis. With a radial directed stress (B), the ligament is avulsed from the bone and retracts proximal to the adductor aponeurosis (C). When the joint is reduced, the adductor is interposed between the ligament and bone (D), preventing healing.

cannot occur and chronic instability will result.⁵² A complete rupture and retraction of the ligament is necessary for the Stener lesion to occur and therefore it is important to differentiate between partial or complete tears without retraction and those where the ligament has retracted proximal to the adductor aponeurosis. Unfortunately, there is not an absolute clinical criterion for making this diagnosis. The MCP joint is observed for swelling and tenderness along the ulnar side. A palpable mass at the level of the metacarpal neck may be consistent with the retracted ulnar collateral ligament (UCL). The joint should be tested in both flexion and extension, checking for a definite endpoint and comparing to the opposite thumb. Multiple reports exist in the literature, all using different clinical criteria for diagnosis of a complete tear.^{53–56} Stress radiographs may assist in making the diagnosis. In addition, MRI and ultrasound can be used in cases of uncertainty following clinical exam and plain radiographs.

When a Stener lesion is present, operative treatment is required. Open ligament repair is the most common procedure performed, but arthroscopic repositioning of the ligament has been described, placing the ligament deep to the adductor aponeurosis and allowing it to heal to the bone.^{57,58} Delayed presentation may make it difficult to repair the ligament primarily and reconstruction may be indicated. With late presentation, radiographs should be evaluated for presence of arthritis and when present, arthrodesis should be considered. Reconstruction techniques produce dynamic (tendon transfers and adductor advancement) and static reconstructions (creation of a static restraint to radial directed stress with a graft).

Dynamic reconstructions typically involve transfer of a tendon to stabilize the MCP joint. Procedures include transfer of the extensor indicis proprius (EIP) to the extensor mechanism, transfer of the extensor pollicis brevis (EPB) to the ulnar side of the proximal phalanx^{59,60} and advancement of the adductor.⁶¹ The adductor is transferred from its insertion on the sesamoid to the proximal phalanx. Static reconstructions involve replacement of the ligament with a graft, such as palmaris longus tendon, through holes created in the metacarpal and proximal phalanx.^{49,62}

Primary repair can be completed as long as there is adequate ligament to repair. When the procedure is greater than 6 weeks following the injury, the surgeon should be prepared to proceed with reconstruction in the event the ligament is not amenable to primary repair. Repair or reattachment too distal or volar will result in loss of flexion and placement too dorsal may result in persistent instability. With an acute injury, it is often possible to determine the site of avulsion and reattach it to the site of avulsion. The ligament runs from dorsal to volar in a proximal to distal direction. The origin of the proper collateral ligament is 7 mm proximal to the joint and 3 mm from the dorsal cortex. The insertion of the base of the proximal phalanx is located 3 mm distal to the joint and 3 mm from the volar cortex (Fig. 7.20).⁶³ Reattachment can be completed using suture anchors or a pull-out suture exiting the opposite side tied over a button or directly over the bone.

Radial collateral ligament injuries are much less common than their ulnar counterparts. On the radial side of the thumb, the abductor aponeurosis is broad, covering a larger percentage of the joint and there is no interposition of the aponeurosis between the ligament and the bone (Stener lesion). Tear of the RCL typically results from forced adduction on a flexed joint. The dorsal capsule tears along the radial aspect and the




Fig. 7.20 Location of thumb MCP joint UCL on metacarpal and proximal phalanx. The ligament runs from dorsal to volar in a proximal to distal direction. The origin of the proper collateral ligament is 7 mm proximal to the joint and 3 mm from the dorsal cortex. The insertion of the base of the proximal phalanx is located 3 mm distal to the joint and 3 mm from the volar cortex.

proximal phalanx pronates around the intact UCL, creating a prominence of the radial aspect of the metacarpal head. The location of the tear is more variable than the UCL counterpart, with equal frequency between proximal and distal avulsions⁴⁸ and mid-substance tears.⁴⁹

Surgical repair of an acute UCL tear

The skin incision is outlined in a straight or lazy “S” configuration from the ulnar base of the proximal phalanx to the dorsal aspect of the metacarpal head/neck region (Fig. 7.21). After the skin incision is completed, spreading to the level of the adductor aponeurosis is carefully performed. Care should be taken to identify the cutaneous branch of the radial nerve, as injury to this structure can cause a painful neuroma, compromising the final outcome. When a Stener lesion is present, the ligament will be identified proximal to the adductor aponeurosis. The adductor aponeurosis is incised, splitting the fibers until the base of the proximal phalanx can be identified. The ligament is debrided of hematoma and fibrous tissue in preparation for repair. The joint can be opened and irrigated to remove hematoma and the site of attachment is identified. When a larger fragment of bone is present, this can be reduced and secured with a screw or K-wires. When the fragment is small, it can be excised and the ligament repaired to the site of avulsion with a suture anchor. The adductor aponeurosis is repaired and the skin is closed. If there is a concern about the stability of the repair, a K-wire can be placed across the joint, but this is generally not necessary.

A plaster thumb spica splint is applied, leaving the IP joint free and converted to a short arm cast at 1 week. Motion of the IP joint is encouraged to prevent adhesions of the extensor tendons. At 4 weeks, the cast is removed and a therapy program is instituted to regain motion. A thermoplastic orthosis is used between exercises with avoidance of radial directed stress. Pinch strengthening is begun at 10 weeks and unrestricted activities are allowed at 12 weeks. Final motion is typically 80% of the non-injured side with grip and pinch strength approximately 90% of the contralateral side.





Fig. 7.21 Surgical repair of thumb MCP joint UCL. (A) Preoperative clinical photograph illustrating laxity at MCP joint. (B) Intraoperative photograph illustrating suture anchor in base of proximal phalanx with suture through the UCL.

Reconstruction of chronic UCL tear with tendon graft

This creates a static restraint to radial directed stress and although not the same as the ligament prior to the injury, can provide a stable thumb MCP joint. The approach to the joint is the same as for acute repairs. After exposing the joint, the remaining collateral ligament is excised. The site of origin and insertion of the graft is identified (Fig. 7.22). A tendon graft is harvested using palmaris longus when present or a strip of flexor carpi radialis (FCR) in the event the palmaris longus is not present. The graft can be attached either through drill holes or with tenodesis screws (alternatively, the collateral ligament can be left attached to the metacarpal and the graft secured to the native ligament). The tendon is attached to the metacarpal head just dorsal to the dorsal volar axis, approximately 8 mm from the joint surface. The proximal phalanx insertion site is 3 mm from the volar cortex and 3 mm distal to the joint. The tendon can be attached to the bone with suture anchors, biotenodesis screws or transosseous sutures. The joint is pinned in slight flexion and ulnar deviation. The

adductor aponeurosis and skin incisions are closed and a thumb spica splint is applied. Postoperative rehabilitation is similar to acute repairs except the joint is immobilized for 6 weeks and pinching is avoided for 3 months. Unrestricted activities are allowed at 4–5 months. Motion tends to be less following reconstructions than acute repairs, but 70% of the flexion/extension and 80% grip and pinch strength can often be obtained. The goal of the reconstruction is to produce a stable painless thumb and the slight loss of motion is compensated for at the CMC joint.

Thumb metacarpal fractures

Fractures of the thumb metacarpal are more tolerant of displacement and rotation due to the motion in three planes (flexion/extension, abduction/adduction, pronation/supination). Fractures can occur through the shaft or the base at the metaphyseal–diaphyseal junction. Angulation $<20^\circ$ can be tolerated, but greater than this may result in compensatory MCP joint hyperextension, compromising the function of the thumb. The distal fragment tends to supinate, so closed reduction is performed by applying longitudinal traction, downward pressure of the apex of the thumb, and pronation and





Fig. 7.22 Technique of thumb MCP joint UCL reconstruction with palmaris longus tendon graft. (A) Intraoperative exposure of the joint following resection of scar and remnants of UCL. (B) Tendon graft secured to the proximal phalanx in preparation for securing to metacarpal.

extension of the distal fragment. K-wires can be used to stabilize the fracture or, alternatively, plates and screws.

Thumb CMC joint injuries

The anatomy of the thumb CMC joint resembles two interlocking saddles (thumb metacarpal and trapezium), which allow motion parallel (abduction and adduction) and perpendicular (pronation and supination). Joint stability is maintained through multiple ligaments, with the anterior oblique, posterior oblique, anterior and posterior intermetacarpal and dorsal radial ligaments being the major stabilizers.⁶⁴ Compressive forces are 12 times greater at the CMC joint than the tip of the thumb, so arthritis may develop if incongruence is present at the CMC joint.^{65,66}

Isolated dislocations occur much less frequently than CMC fracture dislocations (Bennett and Rolando fractures). When pure dislocations occur, they are dorsal and result from an axial compression of a flexed thumb. There are 16 ligaments that stabilize the thumb CMC joint, with some considered major and other considered minor stabilizers. The anterior oblique (volar beak ligament) and the dorsal radial ligament are disrupted to allow dorsal dislocation of the metacarpal. Partial ligament tears may result in subluxation and may be treated with reduction and immobilization, typically with K-wires. Complete ligament tears result in dorsal dislocation and are unstable. Because these injuries are rare, most reports in the literature are case reports or small series.^{67,68} For acute and chronic dislocations, ligament reconstruction with a portion of the FCR, as described by Eaton and Littler^{69,70} should provide reasonable results.

Fracture dislocations are much more common. The *Bennett fracture* (Video 7.1 ►) is a fracture subluxation, which occurs when a flexed metacarpal receives an axial load (Fig. 7.23).⁷¹ The Bennett fragment is maintained due to the attachment of the anterior oblique ligament, while the remainder of the metacarpal subluxes radially, dorsally, and proximally, due to the abductor pollicis longus and adductor pollicis muscles. The goals of treatment of this injury are to restore stability to the joint by allowing the displaced metacarpal to heal to the Bennett fragment and restoration of articular congruity to the base of the thumb. Bennett fractures can be treated with closed reduction and pinning. Indications for ORIF include inability to reduce the fracture by closed means. Some surgeons advocate ORIF when the Bennett fragment involves a substantial amount of the joint.⁷²

The reduction is performed with longitudinal traction on the thumb, pressure at the metacarpal base, and pronation. It is not necessary to secure the Bennett fragment as long as alignment is maintained and K-wires can be placed in a variety of configurations, most commonly, either through the metacarpal base and into the trapezium or trapezoid, or through the thumb metacarpal and into the index metacarpal. The hand is immobilized in a thumb spica cast, with the fingers and IP joint of the thumb free, for 4–5 weeks, followed by a protective orthosis for an additional 4 weeks.

When ORIF is performed, a Wagner incision is used, along the junction of the glabrous and non-glabrous skin, extending from the mid-metacarpal to the region of the FCR tendon. The thenar muscles are reflected subperiosteally, and the capsule is incised to expose the joint. Hematoma is removed from the joint, and then the fracture is reduced and stabilized with

small screws or K-wires. If screw fixation is used, a removable orthosis and motion can be initiated at one week.

The *Rolando fracture*, as originally described, is a metacarpal base fracture with a “T”- or “Y”-shaped intra-articular pattern.⁷³ Currently, the term is used to describe any comminuted intra-articular fracture of the base of the thumb metacarpal. The treatment goals are the same as for the Bennett fracture, but may be more difficult to obtain, as the comminution often makes it difficult to align the articular surface. The true Rolando fracture can be treated with closed reduction, using the same technique as for the Bennett fracture. Comminuted fractures are more difficult to treat and open reduction can lead to devascularization of the small fracture segments. Bone grafting can be used if there is extensive comminution or a void in the metaphysis, to assist with healing. Stabilization is best accomplished with K-wires from the thumb to index metacarpal or an external fixator. Various designs have been described, including stabilization to the trapezium, or multiple rods securing the thumb to the index metacarpal⁷⁴ or in a triangular configuration, securing the thumb and index metacarpals to the radius.⁷⁵

Hints and tips

- Metacarpal base articular fractures are often more comminuted than the appearance on radiographs, and the thumb does not develop stiffness following immobilization, so the authors prefer K-wire fixation for these fractures.
- Reduction of thumb metacarpal base articular fractures requires distraction, pronation and abduction of the metacarpal base.
- K-wires can be placed in the metacarpal, the fracture reduced and the K-wires advanced into the trapezium.

Pediatric fractures

Classification of pediatric fractures has been described in Fig. 7.2, Salter–Harris classification of fractures, but fractures of the distal phalanx and the proximal phalanx head deserve special mention. Generally, pediatric fractures are stabilized with smooth K-wires. Effort should be made to minimize the number of passes through the physis and remanipulation of the fracture.

The Seymour fracture is a fracture involving the epiphyseal region of the distal phalanx (Fig. 7.24).⁷⁶ This injury appears as an open mallet fracture, with extension of the proximal segment with the attachment of the extensor tendon and flexion of the distal fragment with the FDP attached. There is a transverse laceration of the nail matrix, which is often interposed in the physeal fracture site. The nail plate is displaced proximally out of the eponychial fold. Treatment is irrigation and debridement with reduction of the fracture and repair of the nail matrix. The nail plate is used as a stent on the proximal nail fold to help maintain reduction. A splint of longitudinal K-wire is used to maintain the reduction.^{77–79}

Proximal phalanx neck fractures

Fractures of the proximal phalanx neck and occasionally the middle phalanx neck are common in children and result from withdrawal of a finger when caught in a door. These are visualized on a lateral X-ray and are classified according to




Fig. 7.23 (A) Comparison of Bennett and Rolando fracture (Bennett fracture has one articular segment while Rolando fracture has at least two articular segments, commonly in “Y” or “T” configuration). **(B)** Reduction (distraction, pronation, and dorsal pressure) and pinning of thumb CMC fracture dislocation (Bennett fracture and Rolando fracture).

the amount of displacement (Fig. 7.25).^{80–82} The distal fragment can rotate 90°, so the head is directed dorsally and the fracture surface is volar. These should be reduced anatomically and stabilized with K-wires. If alignment is not restored, a bony block may occur in the retrocondylar fossa resulting in decreased flexion. If this occurs, an osteotomy of the volar spike can be performed to remove the bony block and restore flexion.

Complications

Many patients with phalangeal fractures have some residual stiffness following treatment. This is not a complication, but

a result of the need for tendons to glide along all sides of the proximal and middle phalanx and the adhesions that form between the bone and the tendon.³²

True complications include infection, loosening of K-wires, malunion, non-union and compartment syndrome. Infections should be managed with antibiotics. If K-wires have been used, a course of antibiotics will often allow enough healing prior to removal of the implant that the fracture is stable.⁸³ Malunions can be extra-articular or intra-articular and can occur in any bone in the hand and may cause cosmetic or functional problems. Angular and rotational malunions often cause dysfunction, which must be corrected. Non-unions are uncommon and typically occur with infection, substantial bone loss or associated severe soft tissue injuries. They can be




Fig. 7.24 (A) Seymour fracture with nail bed interposed into physis and nail plate dorsal to eponychial fold and (B) following repair of nail matrix.

atrophic or hypertrophic and are managed with resolution of the infection, providing a stable soft tissue environment and reconstruction with stable fixation and, in some instances, bone grafting (atrophic non-unions).

Compartment syndromes are not common in the hand, but may occur with crush injuries. Notable pain following a crush injury to the hand, which is exacerbated by passive stretching of the digit, should raise the suspicion for compartment syndrome. In the unresponsive patient with substantial swelling, compartment pressures can be measured. Pressures >30 mmHg or within 30 mm of diastolic pressure should be treated with urgent fasciotomies, thereby releasing the interosseous, thenar, hypothenar, adductor pollicis muscles and transverse carpal ligament.

Secondary procedures

Secondary procedures can be performed to correct a problem, such as malunion or non-union, or in an attempt to improve motion for stiff digits. All wounds should be healed and soft tissues supple before secondary procedures are performed.

Malunion correction

Malunion typically occurs as angular or rotational deformities. Correction of an angular malunion involves an opening or closing wedge osteotomy with internal fixation.⁸⁴ Closing wedge osteotomies are easier to perform and are stable, while opening wedge osteotomies often require bone graft. These are best treated at the site of the malunion. Rotational malunions are treated with derotational osteotomies. These can be performed as transverse^{85,86} or step-cut osteotomies⁸⁷⁻⁸⁹ and rigid




Fig. 7.25 Pediatric proximal phalanx neck fractures. Type I is a stable, non-displaced fracture. Type II is a fracture with dorsal displacement of the condyles, but contact between the bony surfaces. Type III fractures are defined by dorsal displacement of the condyles with rotation of 90°, so the fracture surface is perpendicular to the dorsal aspect of the proximal phalanx.

fixation is used to provide stability and early motion (Fig. 7.26). Intra-articular malunions can be corrected with an intra-articular⁹⁰ (Fig. 7.27) or extra-articular⁹¹ osteotomy.

Figs. 7.26 & 7.27 appear online only.

Non-union correction

Non-unions are rare in the hand, but can be managed by following principles of non-union reconstruction in long bones.⁹² Any underlying infection should be treated and a good soft-tissue envelope should be present prior to reconstruction. Hypertrophic non-unions demonstrate bone formation around the fracture without bridging bone at the non-union site. These will typically heal if stability and compression are provided at the non-union site. Atrophic non-unions require bone grafting in addition to internal fixation. Metabolic conditions, such as vitamin D deficiency, should be evaluated with blood tests and corrected if necessary, as low vitamin D levels will prevent ossification.

Hardware removal, tenolysis, capsulotomy

Patients with residual stiffness may benefit from secondary procedures to improve motion. When internal fixation with plates and screws has been used for initial treatment of the fracture, adhesions between the plate and the extensor tendons often occur. Removal of the hardware and extensor tenolysis will often improve flexion. Indications include a motivated patient who will be compliant with the postoperative therapy program, complete osseous healing and supple soft tissues with passive motion that is greater than active motion. When joints become stiff, the results are much less predictable and outcomes not as good. Results following release of MCP extension contractures are better than PIP flexion or extension contracture release.

Hints and tips

- Tenolysis can be performed as a wide-awake procedure, using local anesthesia with epinephrine, avoiding the use of a tourniquet.
- Tenolysis knives are specifically designed to free adhesions between tendon and bone, flexor sheath and the tendons themselves.
- Active motion after releasing adhesions will often allow rupture of additional adhesions, illustrating when adequate release has been completed.
- Begin therapy, focusing on active motion, immediately following the release. This can be demonstrated in the OR when done wide-awake.

Future directions

There have not been substantial advances in management of hand fractures over the last decade. K-wires are still commonly used and provide functionally stable fixation. Ideally, something to minimize adhesions, whether something used locally or systemically, or increase the rate of bony healing could improve motion and ultimate outcome. Comparative studies including randomized trials comparing fixation methods may help surgeons determine better treatments.



Bonus images for this chapter can be found online at

<http://www.expertconsult.com>

Fig. 7.9 (A) Preoperative and **(B)** postoperative radiographs of patient with middle phalanx base fracture treated with ORIF. **(C)** Clinical photograph in flexion following rehabilitation.

Fig. 7.10 Postoperative radiograph of cerclage wire (and K-wire) used to repair middle phalanx base articular fracture. Radiographically, the wire does not appear secure dorsally because this is secured around the articular cartilage (not seen on radiograph) and cannot be placed further distally due to the central slip insertion.

Fig. 7.26 (A–C) Step-cut osteotomy for correction of malunion. This can be used in the metacarpal or phalanx. The distal transverse cut is in the direction of malrotation, so the dorsal surface closes as the malrotation is corrected.

Fig. 7.27 Technique for correction of intra-articular malunion of the proximal phalanx head with condylar advancement osteotomy. **(A)** A longitudinal osteotomy is created into the site of the intra-articular malunion, the condyle is advanced and rotated into proper alignment and secured with screws, leaving the proximal shaft defect to heal secondarily. Clinical example **(B)** preoperative radiograph; **(C)** intraoperative photograph of articular malunion prior to osteotomy. **(D)** Intraoperative photograph following condylar advance osteotomy and fixation. Postoperative PA **(E)** and lateral **(F)** radiographs and clinical example in flexion **(G)**.



Access the complete reference list online at

<http://www.expertconsult.com>

10. Leinberry C. Mallet finger injuries. *J Hand Surg Am.* 2009;34:1715–1717. An evidence-based review, discussing the literature of operative and nonoperative (splinting) for the treatment of mallet finger injuries.
16. Kiefhaber TR, Stern PJ. Fracture dislocations of the proximal interphalangeal joint. *J Hand Surg Am.* 1998;23:368–380. This article provides excellent overview of the diagnosis of injuries of the base of the middle phalanx and indications for operative treatment. This article was

written prior to hemi-hamate arthroplasty, so this technique is not covered.

21. Williams RM, Kiefhaber TR, Sommerkamp TG, et al. Treatment of unstable dorsal proximal interphalangeal fracture/dislocations using a hemi-hamate autograft. *J Hand Surg Am.* 2003;28:856–865.
22. Badia A, Riano F, Ravikoff J, et al. Dynamic intradigital external fixation for proximal interphalangeal joint fracture dislocations. *J Hand Surg Am.* 2005;30:154–160.




Fig. 7.26 (A–C) Step-cut osteotomy for correction of malunion. This can be used in the metacarpal or phalanx. The distal transverse cut is in the direction of malrotation, so the dorsal surface closes as the malrotation is corrected.




Fig. 7.27 Technique for correction of intra-articular malunion of the proximal phalanx head with condylar advancement osteotomy. **(A)** A longitudinal osteotomy is created into the site of the intra-articular malunion, the condyle is advanced and rotated into proper alignment and secured with screws, leaving the proximal shaft defect to heal secondarily. Clinical example **(B)** preoperative radiograph; **(C)** intraoperative photograph of articular malunion prior to osteotomy. **(D)** Intraoperative photograph following condylar advance osteotomy and fixation.



Fig. 7.27, cont'd Postoperative PA (E) and lateral (F) radiographs and clinical example in flexion (G).

References

- Karl JW, Olson PR, Rosenwasser MP. The epidemiology of upper extremity fractures in the United States, 2009. *J Orthop Trauma*. 2015;29:e242–e244.
- Kozin SH, Thoder JJ, Lieberman G. Operative treatment of metacarpal and phalangeal shaft fractures. *J Am Acad Orthop Surg*. 2000;8:111–121.
- Leversedge FJ. Anatomy and pathomechanics of the thumb. *Hand Clin*. 2008;24:219–229, v.
- Seitz WH, Shimko P, Patterson RW. Long-term results of callus distraction-lengthening in the hand and upper extremity for traumatic and congenital skeletal deficiencies. *J Bone Joint Surg Am*. 2010;92:47–58.
- Marino JT, Ziran BH. Use of solid and cancellous autologous bone graft for fractures and nonunions. *Orthop Clin North Am*. 2010;41:15–26.
- Schneider LH. Fractures of the distal phalanx. *Hand Clin*. 1988;4:537–547.
- Wehbe MA, Schneider LH. Mallet fractures. *J Bone Joint Surg Am*. 1984;66:658–669.
- Kalainov DM, Hoepfner PE, Hartigan BJ, et al. Nonsurgical treatment of closed mallet finger fractures. *J Hand Surg Am*. 2005;30:580–586.
- Hamas RS, Horrell ED, Pierret GP. Treatment of mallet finger due to intra-articular fracture of the distal phalanx. *J Hand Surg Am*. 1978;3:361–363.
- Leinberry C. Mallet finger injuries. *J Hand Surg Am*. 2009;34:1715–1717. *An evidence-based review, discussing the literature of operative and nonoperative (splinting) for the treatment of mallet finger injuries.*
- Rocchi L, Genitiempo M, Fanfani F. Percutaneous fixation of mallet fractures by the “umbrella handle” technique. *J Hand Surg Br*. 2006;31:407–412.
- Schneider LH. A simple fixation method for unstable bony mallet finger. *J Hand Surg Am*. 2005;30:626–627, author reply 627.
- Palmer AK, Linscheid RL. Irreducible dorsal dislocation of the distal interphalangeal joint of the finger. *J Hand Surg Am*. 1977;2:406–408.
- Green SM, Posner MA. Irreducible dorsal dislocations of the proximal interphalangeal joint. *J Hand Surg Am*. 1985;10:85–87.
- Peimer CA, Sullivan DJ, Wild DR. Palmar dislocation of the proximal interphalangeal joint. *J Hand Surg Am*. 1984;9A:39–48.
- Kieffhaber TR, Stern PJ. Fracture dislocations of the proximal interphalangeal joint. *J Hand Surg Am*. 1998;23:368–380. *This article provides excellent overview of the diagnosis of injuries of the base of the middle phalanx and indications for operative treatment. This article was written prior to hemi-hamate arthroplasty, so this technique is not covered.*
- Hamilton SC, Stern PJ, Fassler PR, Kieffhaber TR. Mini-screw fixation for the treatment of proximal interphalangeal joint dorsal fracture-dislocations. *J Hand Surg Am*. 2006;31:1349–1354.
- Blazar PE, Robbe R, Lawton JN. Treatment of dorsal fracture/dislocations of the proximal interphalangeal joint by volar plate arthroplasty. *Tech Hand Up Extrem Surg*. 2001;5:148–152.
- Eaton RG, Malerich MM. Volar plate arthroplasty of the proximal interphalangeal joint: a review of ten years' experience. *J Hand Surg Am*. 1980;5:260–268.
- Williams RMM, Hastings H, Kieffhaber TR. PIP Fracture/dislocation treatment technique: use of a hemi-hamate resurfacing arthroplasty. *Tech Hand Up Extrem Surg*. 2002;6:185–192.
- Williams RM, Kieffhaber TR, Sommerkamp TG, et al. Treatment of unstable dorsal proximal interphalangeal fracture/dislocations using a hemi-hamate autograft. *J Hand Surg Am*. 2003;28:856–865.
- Badia A, Riano F, Ravikoff J, et al. Dynamic intradigital external fixation for proximal interphalangeal joint fracture dislocations. *J Hand Surg Am*. 2005;30:154–160.
- Ellis SJ, Cheng R, Prokoppis P, et al. Treatment of proximal interphalangeal dorsal fracture-dislocation injuries with dynamic external fixation: a pins and rubber band system. *J Hand Surg Am*. 2007;32:1242–1250.
- Ruland RT, Hogan CJ, Cannon DL, Slade JF. Use of dynamic distraction external fixation for unstable fracture-dislocations of the proximal interphalangeal joint. *J Hand Surg Am*. 2008;33:19–25.
- Agee JM. Unstable fracture dislocations of the proximal interphalangeal joint. Treatment with the force couple splint. *Clin Orthop*. 1987;214:101–112.
- Weiss AP. Cerclage fixation for fracture dislocation of the proximal interphalangeal joint. *Clin Orthop*. 1996;327:21–28.
- Dionysian E, Eaton RG. The long-term outcome of volar plate arthroplasty of the proximal interphalangeal joint. *J Hand Surg Am*. 2000;25:429–437.
- Calfee RP, Kieffhaber TR, Sommerkamp TG, Stern PJ. Hemi-hamate arthroplasty provides functional reconstruction of acute and chronic proximal interphalangeal fracture-dislocations. *J Hand Surg Am*. 2009;34:1232–1241.
- McAuliffe JA. Hemi-hamate autograft for the treatment of unstable dorsal fracture dislocation of the proximal interphalangeal joint. *J Hand Surg Am*. 2009;34:1890–1894.
- Weiss AP, Hastings H. Distal unicondylar fractures of the proximal phalanx. *J Hand Surg Am*. 1993;18:594–599.
- Belsky MR, Eaton RG, Lane LB. Closed reduction and internal fixation of proximal phalangeal fractures. *J Hand Surg Am*. 1984;9:725–729.
- Page SM, Stern PJ. Complications and range of motion following plate fixation of metacarpal and phalangeal fractures. *J Hand Surg Am*. 1998;23:827–832. *This paper illustrates the challenges associated with plate and screw fixation of fractures in the hand and although often necessary due to open fractures and other conditions, complications, including stiffness, plate prominence, infection and tendon rupture can occur.*
- Patel MR, Bassini L. Irreducible palmar metacarpophalangeal joint dislocation due to junctura tendinum interposition: a case report and review of the literature. *J Hand Surg Am*. 2000;25:166–172.
- Betz RR, Browne EZ, Perry GB, Resnick EJ. The complex volar metacarpophalangeal-joint dislocation. A case report and review of the literature. *J Bone Joint Surg Am*. 1982;64:1374–1375.
- Chin SH, Vedder NB. MOC-PSSM CME article: Metacarpal fractures. *Plast Reconstr Surg*. 2008;121:1–13.
- Kuokkanen HO, Mulari-Keränen SK, Niskanen RO, et al. Treatment of subcapital fractures of the fifth metacarpal bone: a prospective randomised comparison between functional treatment and reposition and splinting. *Scand J Plast Reconstr Surg Hand Surg*. 1999;33:315–317.
- Hunter JM, Cowen NJ. Fifth metacarpal fractures in a compensation clinic population. A report on one hundred and thirty-three cases. *J Bone Joint Surg Am*. 1970;52:1159–1165.
- Jahss S. Fractures of the metacarpals: A new method of reduction and immobilization. *J Bone Jt Surg Am*. 1938;20:726–731.
- Hofmeister EP, Kim J, Shin AY. Comparison of 2 methods of immobilization of fifth metacarpal neck fractures: a prospective randomized study. *J Hand Surg Am*. 2008;33:1362–1368.
- Brown PW. The management of phalangeal and metacarpal fractures. *Surg Clin North Am*. 1973;53:1393–1437.
- Foucher G. Bouquet” osteosynthesis in metacarpal neck fractures: a series of 66 patients. *J Hand Surg Am*. 1995;20:S86–S90.
- Hastings H. Unstable metacarpal and phalangeal fracture treatment with screws and plates. *Clin Orthop*. 1987;214:37–52.
- Seitz WH, Gomez W, Putnam MD, Rosenwasser MP. Management of severe hand trauma with a mini external fixateur. *Orthopedics*. 1987;10:601–610.
- Drenth DJ, Klasen HJ. External fixation for phalangeal and metacarpal fractures. *J Bone Joint Surg Br*. 1998;80:227–230.
- Ashmead D, Rothkopf DM, Walton RL, Jupiter JB. Treatment of hand injuries by external fixation. *J Hand Surg Am*. 1992;17:954–964.
- Garcia-Elias M, Bishop AT, Dobyns JH, et al. Transcarpal carpometacarpal dislocations, excluding the thumb. *J Hand Surg Am*. 1990;15:531–540.

47. Gurland M. Carpometacarpal joint injuries of the fingers. *Hand Clin.* 1992;8:733–744.
48. Camp RA, Weatherwax RJ, Miller EB. Chronic posttraumatic radial instability of the thumb metacarpophalangeal joint. *J Hand Surg Am.* 1980;5:221–225.
49. Smith RJ. Post-traumatic instability of the metacarpophalangeal joint of the thumb. *J Bone Joint Surg Am.* 1977;59:14–21.
50. Husband JB, McPherson SA. Bony skier's thumb injuries. *Clin Orthop.* 1996;327:79–84.
51. Bowers WH, Hurst LC. Gamekeeper's thumb. Evaluation by arthrography and stress roentgenography. *J Bone Joint Surg Am.* 1977;59:519–524.
52. Stener B. Skeletal injuries associated with rupture of the ulnar collateral ligament of the metacarpophalangeal joint of the thumb. A clinical and anatomical study. *Acta Chir Scand.* 1963;125:583–586.
53. Smith RJ, Peimer CA. Injuries to the metacarpal bones and joints. *Adv Surg.* 1977;11:341–374.
54. Palmer AK, Louis DS. Assessing ulnar instability of the metacarpophalangeal joint of the thumb. *J Hand Surg Am.* 1978;3:542–546.
55. Heyman P, Gelberman RH, Duncan K, Hipp JA. Injuries of the ulnar collateral ligament of the thumb metacarpophalangeal joint. Biomechanical and prospective clinical studies on the usefulness of valgus stress testing. *Clin Orthop.* 1993;292:165–171.
56. Heyman P. Injuries to the ulnar collateral ligament of the thumb metacarpophalangeal joint. *J Am Acad Orthop Surg.* 1997;5:224–229.
57. Ryu J, Fagan R. Arthroscopic treatment of acute complete thumb metacarpophalangeal ulnar collateral ligament tears. *J Hand Surg Am.* 1995;20:1037–1042.
58. Slade JE, Gutow AP. Arthroscopy of the metacarpophalangeal joint. *Hand Clin.* 1999;15:501–527.
59. Sakellarides HT, DeWeese JW. Instability of the metacarpophalangeal joint of the thumb. Reconstruction of the collateral ligaments using the extensor pollicis brevis tendon. *J Bone Joint Surg Am.* 1976;58:106–112.
60. Ahmad I, DePalma AF. Treatment of game-keeper's thumb by a new operation. *Clin Orthop.* 1974;103:167–169.
61. Neviaser RJ, Wilson JN, Lievano A. Rupture of the ulnar collateral ligament of the thumb (gamekeeper's thumb). Correction by dynamic repair. *J Bone Joint Surg Am.* 1971;53:1357–1364.
62. Mitsionis GI, Varitimidis SE, Sotereanos GG. Treatment of chronic injuries of the ulnar collateral ligament of the thumb using a free tendon graft and bone suture anchors. *J Hand Surg Br.* 2000;25:208–211.
63. Bean CH, Tencer AF, Trumble TE. The effect of thumb metacarpophalangeal ulnar collateral ligament attachment site on joint range of motion: an in vitro study. *J Hand Surg Am.* 1999;24:283–287. *This paper is an excellent study reviewing the precise anatomical location to optimize motion and function following repair/reconstruction of the MCP joint UCL.*
64. Imaeda T, An KN, Cooney WP, Linscheid R. Anatomy of trapeziometacarpal ligaments. *J Hand Surg Am.* 1993;18:226–231.
65. Cooney WP, Chao EY. Biomechanical analysis of static forces in the thumb during hand function. *J Bone Joint Surg Am.* 1977;59:27–36.
66. Cooney WP, Lucca MJ, Chao EY, Linscheid RL. The kinesiology of the thumb trapeziometacarpal joint. *J Bone Joint Surg Am.* 1981;63:1371–1381.
67. Jakobsen CW, Elberg JJ. Isolated carpometacarpal dislocation of the thumb. Case report. *Scand J Plast Reconstr Surg Hand Surg.* 1988;22:185–186.
68. Watt N, Hooper G. Dislocation of the trapezio-metacarpal joint. *J Hand Surg Br.* 1987;12:242–245.
69. Eaton RG, Littler JW. Ligament reconstruction for the painful thumb carpometacarpal joint. *J Bone Joint Surg Am.* 1973;55:1655–1666.
70. Simonian PT, Trumble TE. Traumatic dislocation of the thumb carpometacarpal joint: early ligamentous reconstruction versus closed reduction and pinning. *J Hand Surg Am.* 1996;21:802–806.
71. Pellegrini VD. Fractures at the base of the thumb. *Hand Clin.* 1988;4:87–102.
72. Foster RJ, Hastings H. Treatment of Bennett, Rolando, and vertical intraarticular trapezial fractures. *Clin Orthop.* 1987;214:121–129.
73. Langhaff O, Andersen K, Kjaer-Petersen K. Rolando's fracture. *J Hand Surg Br.* 1991;16:454–459.
74. Buchler U, McCollam SM, Oppikofer C. Comminuted fractures of the basilar joint of the thumb: combined treatment by external fixation, limited internal fixation, and bone grafting. *J Hand Surg Am.* 1991;16:556–560.
75. Schuind F, Noorbergen M, Andrianne Y, Burny F. Comminuted fractures of the base of the first metacarpal treated by distraction-external fixation. *J Orthop Trauma.* 1988;2:314–321.
76. Abzug JM, Kozin SH. Seymour fractures. *J Hand Surg Am.* 2013;38:2267–2270, quiz 2270.
77. Al-Qattan MM. Extra-articular transverse fractures of the base of the distal phalanx (Seymour's fracture) in children and adults. *J Hand Surg [Br].* 2001;26:201–206.
78. Banerjee A. Irreducible distal phalangeal epiphyseal injuries. *J Hand Surg Br.* 1992;17:337–338.
79. Seymour N. Juxta-epiphyseal fracture of the terminal phalanx of the finger. *J Bone Joint Surg Br.* 1966;48:347–349.
80. Al-Qattan MM. Phalangeal neck fractures in children: classification and outcome in 66 cases. *J Hand Surg Br.* 2001;26:112–121.
81. Al-Qattan MM. Juxta-epiphyseal fractures of the base of the proximal phalanx of the fingers in children and adolescents. *J Hand Surg Br.* 2002;27:24–30.
82. Al-Qattan MM, Hashem FK, Rasool MN, et al. A unique fracture pattern of the proximal phalanx in children: fractures through the phalangeal neck with an attached dorsal bony flange. *Injury.* 2004;35:1185–1191.
83. Botte MJ, Davis JL, Rose BA, et al. Complications of smooth pin fixation of fractures and dislocations in the hand and wrist. *Clin Orthop Relat Res.* 1992;276:194–201.
84. Freeland AE, Lindley SG. Malunions of the finger metacarpals and phalanges. *Hand Clin.* 2006;22:341–355. *This paper provides an algorithm for managing malunions in the hand, including the various different osteotomies and concomitant procedures, such as tenolysis and capsulotomy, to improve motion.*
85. Büchler U, Gupta A, Ruf S. Corrective osteotomy for post-traumatic malunion of the phalanges in the hand. *J Hand Surg Br.* 1996;21:33–42.
86. Trumble T, Gilbert M. In situ osteotomy for extra-articular malunion of the proximal phalanx. *J Hand Surg Am.* 1998;23:821–826.
87. Jawa A, Zucchini M, Lauri G, Jupiter J. Modified step-cut osteotomy for metacarpal and phalangeal rotational deformity. *J Hand Surg Am.* 2009;34:335–340.
88. Lucas GL. Rotational step-cut osteotomy for treatment of metacarpal and phalangeal malunion. *J Hand Surg Am.* 1992;17:583.
89. Manktelow RT, Mahoney JL. Step osteotomy: a precise rotation osteotomy to correct scissoring deformities of the fingers. *Plast Reconstr Surg.* 1981;68:571–576.
90. Teoh LC, Yong FC, Chong KC. Condylar advancement osteotomy for correcting condylar malunion of the finger. *J Hand Surg [Br].* 2002;27:31–35.
91. Harness NG, Chen A, Jupiter JB. Extra-articular osteotomy for malunited unicondylar fractures of the proximal phalanx. *J Hand Surg Am.* 2005;30:566–572.
92. Jupiter JB, Koniuch MP, Smith RJ. The management of delayed union and nonunion of the metacarpals and phalanges. *J Hand Surg Am.* 1985;10:457–466.

32. Page SM, Stern PJ. Complications and range of motion following plate fixation of metacarpal and phalangeal fractures. *J Hand Surg Am.* 1998;23:827–832. *This paper illustrates the challenges associated with plate and screw fixation of fractures in the hand and although often necessary due to open fractures and other conditions, complications, including stiffness, plate prominence, infection and tendon rupture can occur.*
56. Heyman P. Injuries to the ulnar collateral ligament of the thumb metacarpophalangeal joint. *J Am Acad Orthop Surg.* 1997;5:224–229.
63. Bean CH, Tencer AF, Trumble TE. The effect of thumb metacarpophalangeal ulnar collateral ligament attachment site on joint range of motion: an in vitro study. *J Hand Surg Am.* 1999;24:283–287. *This paper is an excellent study reviewing the precise anatomical location to optimize motion and function following repair/reconstruction of the MCP joint UCL.*
77. Al-Qattan MM. Extra-articular transverse fractures of the base of the distal phalanx (Seymour's fracture) in children and adults. *J Hand Surg [Br].* 2001;26:201–206.
83. Botte MJ, Davis JL, Rose BA, et al. Complications of smooth pin fixation of fractures and dislocations in the hand and wrist. *Clin Orthop Relat Res.* 1992;276:194–201.
84. Freeland AE, Lindley SG. Malunions of the finger metacarpals and phalanges. *Hand Clin.* 2006;22:341–355. *This paper provides an algorithm for managing malunions in the hand, including the various different osteotomies and concomitant procedures, such as tenolysis and capsulotomy, to improve motion.*
90. Teoh LC, Yong FC, Chong KC. Condylar advancement osteotomy for correcting condylar malunion of the finger. *J Hand Surg [Br].* 2002;27:31–35.

8

Fractures and dislocations of the wrist and distal radius

Steven C. Haase and Kevin C. Chung

SYNOPSIS

- Wrist injuries are common, and proper management relies on an understanding of normal anatomy, alignment, and kinematics.
- Scaphoid fractures can be subtle, and due to the precarious blood supply to this bone, may go on to nonunion if not properly managed.
- Indications for scapholunate ligament repair and/or reconstruction depend on the patient's symptoms and on the chronicity of the injury.
- For distal radius fractures requiring stabilization, external fixation and dorsal plating have largely been supplanted by volar fixed-angle locking plates, which provide the necessary stability for fracture healing, even in osteoporotic individuals.
- Ulnar styloid fractures only require fixation in the setting of distal radioulnar joint instability.

Introduction

The wrist is a complex articulation that connects the hand to the forearm. Entire textbooks have been devoted to detailed discussions of the anatomy, physiology, and pathology of this important joint. This chapter will review some of the more common injury patterns seen in the wrist, including fractures of the carpal bones, ligamentous injuries of the wrist, and fractures of the distal radius and ulna.

The epidemiology of wrist fractures has been investigated in detail. Each year, nearly 1.5 million hand and wrist fractures are estimated to occur in the United States, accounting for 1.5% of all emergency department visits.¹ Of these, approximately 208 000 are carpal fractures.

The scaphoid is the carpal bone most commonly fractured; it accounts for 60–80% of all carpal fractures.^{2,3} Incidence estimates range from 2.9/10 000 person-years in the United Kingdom⁴ to 12.1/10 000 person-years in the US military population.⁵ The highest incidence is found in the 20–24-year-old age group, and there is a clear male predominance.^{4,5}

Distal radius fractures are the most common upper extremity fracture; the annual incidence is estimated at 643 000

fractures per year in the United States.¹ When the incidence is examined by age, there are two distinct peaks identified (Fig. 8.1), representing the 5–14-year-old group (55.7/10 000 person-years) and the 75–84-year-old group (35.2/10 000 person-years).

Although a common injury, these fractures should never be treated casually. There is significant potential for patient disability if these injuries are not managed with great care and expertise. Khan and Giddins' review of hand and wrist surgery negligence claims in the UK from 1995–2001 revealed that wrist fracture was the most common condition in which negligence was alleged, comprising 48% of claims.⁶



Access the Historical Perspective section and Figs. 8.2 & 8.3 online at

<http://www.expertconsult.com>

Basic science/disease process

Anatomy

Normal anatomy of the wrist is covered in detail in Chapter 1 of this textbook. However, there are a few points that merit emphasis in this chapter with regard to these injuries.

The vascularity of the scaphoid bone bears particular consideration. The scaphoid bone has a single dominant vascular pedicle that enters from the distal pole of the bone. Therefore, the proximal pole relies wholly on the intramedullary blood supply for survival. It is for this reason that proximal pole fractures typically take longer to heal and have increased incidence of nonunion. Furthermore, in cases of nonunion, the proximal pole is susceptible to avascular necrosis, which further complicates these injuries.¹¹

Detection of ligamentous injuries of the wrist is made easier by attention to the Gilula arcs (Fig. 8.4). Dr. Gilula, a radiologist, described three arcs that can be noted on the posteroanterior radiograph of the wrist, formed by the

Historical perspective

The carpus was not well described until the 1500s, when Andreas Vesalius first identified the eight carpal bones. Before then, drawings of the hand connected the metacarpals directly to the distal radius, with no mention of wrist anatomy. Carpal bones are generally named for their shapes. For example, the scaphoid resembles a boat, whereas the lunate resembles the crescent moon. The names of the carpal bones were not solidified until 1955 when *Nomina Anatomica* established the official nomenclature for the carpal bones that we use today (Fig. 8.2).⁷

Historically, the carpal bones have been grouped together in various ways, based on function and kinematics. The earliest classification separates the wrist joint into two rows, consisting of the distal carpal row (trapezium, trapezoid, capitate, hamate) and the proximal carpal row (scaphoid, lunate, triquetrum). The carpus can also be divided into columns: a radial column (scaphoid, trapezoid, trapezium), a central column (lunate, capitate), and an ulnar column (triquetrum, hamate). The pisiform bone is not involved in wrist motion, so it is not typically included in these groupings.

Abraham Colles (1773–1843) is credited with the first clinical description of fractures of the distal radius. His 1814 manuscript provides an eloquent description of closed reduction and splinting, in an era before the development of radiographs, anesthesia, and plaster of Paris. On the results of treatment, he proclaimed, “The cases treated on this plan have all recovered without the smallest defect or deformity of the limb, in the ordinary time for the cure of fractures.”⁸

More than 200 years later, closed reduction and immobilization is still the predominant method of treatment for distal radius fractures, though internal fixation has been steadily gaining in popularity.⁹ It is now commonly believed that restoration of anatomic alignment of the distal radius leads to

better outcomes, although the age and activity level of the patient certainly contribute to this equation. To achieve these ends, technology has advanced to allow for precise fracture fixation with a variety of techniques. Over the past several decades, pins-and-plaster and external fixation systems have largely given way to internal fixation methods, heavily encouraged by AO (Arbeitsgemeinschaft für Osteosynthesefragen). AO is a Swiss organization started in the late 1950s for promoting more consistent fracture care, chiefly using rigid internal fixation. Despite the development of hundreds of fixators, plates, rods, and other devices, there is little high-level evidence to support the use of one technique over another. In some ways, Colles’ conservative approach was probably correct – many patients, especially the low-demand elderly population, achieve excellent outcomes even in the presence of significant malunion or malalignment.¹⁰

Many textbooks discourage the use of eponyms, believing them to be of historical interest only. However, the various eponyms for distal radius fractures often convey precise information regarding the fracture pattern and the type of injury sustained. The major eponyms for distal radius fractures are: Colles fracture (extra-articular fracture with dorsal displacement of distal fragment) (Fig. 8.3A); Smith fracture (also called reverse Colles fracture; extra-articular with volar displacement of distal fragment) (Fig. 8.3B); Barton fracture (intra-articular shear fracture of the radiocarpal joint, may be dorsal or volar) (Fig. 8.3C,D); and Chauffeur fracture (intra-articular fracture involving the radial styloid) (Fig. 8.3E). For some cases, these eponyms may help in selecting a treatment modality.




Fig. 8.2 Posteroanterior radiograph of the wrist, with carpal bones identified.



Fig. 8.3 Examples of common distal radius fracture eponyms: (A) Colles fracture, (B) Smith fracture, (C) dorsal Barton fracture, (D) volar Barton fracture, and (E) Chauffeur fracture.




Fig. 8.1 Age-related variation in radius/ulna fracture incidence. (Data from Chung KC, Spilson SV. The frequency and epidemiology of hand and forearm fractures in the United States. *J Hand Surg Am.* 2001;26:908–915.)

proximal and distal articular surfaces of the proximal row, and the proximal articular surface of the distal row. Increased joint space or deviation of carpal bones from these lines is indicative of wrist instability.¹²

The bones of the wrist are linked by a complex system of intrinsic and extrinsic ligaments (Fig. 8.5). The strength of these wrist ligaments helps determine the injury patterns observed. For example, the very strong short radiolunate ligament tends to resist lunate dislocation, retaining the lunate in its fossa on the distal radius in all but the most severe traumas. Instead, the surrounding carpal bones typically dislocate away from the lunate. This perilunate pattern of injury (Fig. 8.6) involves: rupture of the scapholunate interosseous ligament; capsular disruption through the space of Poirier, an area of inherent weakness of the volar capsule between the lunate

and capitate, and rupture of the lunotriquetral interosseous ligament. If the dislocated carpus rebounds, then the capitate will settle into the lunate fossa, and the lunate rotates volarly, hinged on the short radiolunate ligament (Fig. 8.7).^{13,14}

Injury patterns are also influenced by the details of bony anatomy and structure. For example, both the diaphysis and the articular surface of the distal radius have thicker cortical bone than is found at the metaphysis. The thinner cortical bone at the metaphysis is what makes it vulnerable to fracture, especially in the osteoporotic population. Furthermore, within the metaphysis, there is a distinct difference between the dorsal and volar cortices. The dorsal cortex is much thinner, resulting in extensive comminution in most cases of distal radius fracture from falls on outstretched hands, where the force is directed in a volar-to-dorsal direction.

The extensor pollicis longus (EPL) is the tendon most likely to rupture after a distal radius fracture. Of note, rupture is more common with non-displaced fractures, and has been reported in cases of wrist injury without fracture. The etiology of this appears to be related to interruption of the tendon's nutritional supply, leading to attritional rupture. This most commonly occurs at the Lister tubercle, where there is a natural watershed area of this tendon's intrinsic blood supply. If the extrinsic (diffusion-mediated) nutritional supply is also interrupted by fracture callus, fracture displacement, or swelling from edema or hematoma, rupture of the EPL can occur.¹⁵

Biomechanics

The biomechanics of the hand and wrist were reviewed in Chapter 1, but there are a few points to revisit here.

Disruption of the normal linkages between the bones of the wrist – whether due to ligamentous rupture or fracture – can lead to carpal instability. The concept of carpal instability has evolved rapidly over the past 50 years as we have learned more about the ways in which the wrist bones move (kinematics) and transfer a load (kinetics). Specifically, a wrist is unstable if it is unable to transfer functional loads without sudden changes in stress on the articular cartilage, and if it is unable to maintain motion throughout its range without sudden alterations of intercarpal alignment.¹⁶

Carpal instability has been thoughtfully classified into four major patterns (Table 8.1). Carpal instability dissociative (CID) occurs when there is a disruption within or between the




Fig. 8.4 The Gilula arcs are used to detect alterations in carpal alignment and stability. The lines are defined by (1) the proximal and (2) the distal articular surface of the proximal row, as well as (3) the proximal articular surface of the distal row.




Fig. 8.5 (A) Dorsal extrinsic wrist ligaments. (B) Volar extrinsic wrist ligaments. (C) Intrinsic wrist ligaments. C, Capitate; L, lunate; P, pisiform; R, radius; S, scaphoid; Td, trapezoid; Tm, trapezium; U, ulna.




Fig. 8.6 Mayfield stages of perilunate instability: (I) scapholunate ligament rupture; (II) volar capsule tear at the space of Poirer; (III) lunotriquetral ligament rupture; (IV) lunate dislocation.

bones of the same carpal row. Carpal instability non-dissociative (CIND) refers to a disruption between the distal radius and the proximal carpal row, or between the proximal and distal carpal rows. When a combination of elements of both CID and CIND exist, it is referred to as carpal instability complex (CIC). Finally, when the instability is an adaptive response to a problem proximal or distal to the wrist itself, it is called carpal instability adaptive (CIA).¹⁷

Carpal kinematics has perhaps the biggest clinical impact on scaphoid fractures and scapholunate ligament injuries. The proximal carpal row is “pre-tensioned”, with the scaphoid subject to a flexion moment, and the triquetrum tending to follow an extension moment. Any breakage of the connections within this row, whether intracarpal (e.g., scaphoid fracture) or intercarpal (e.g., scapholunate ligament rupture), will result in carpal instability because the disconnected carpal bones rotate in opposite directions. This natural tendency for the components in this row to fall away from each other is in part responsible for the high rate of complications after these types of injury.

Two particular instability patterns that result from CID within the proximal row are dorsal intercalated segment instability (DISI) and volar intercalated segment instability (VISI) (Fig. 8.8). DISI deformity is commonly associated with scapholunate ligament disruption or displaced scaphoid fractures; whereas VISI deformity is associated with lunotriquetral ligament disruption.




Fig. 8.7 Lateral radiograph examples of (A) perilunate dislocation and (B) lunate dislocation injury patterns.

Table 8.1 Patterns of carpal instability

Pattern	Definition	Example(s)
Carpal instability dissociative (CID)	Disruption within or between bones of the same carpal row	Scapholunate dissociation; Scaphoid nonunion
Carpal instability non-dissociative (CIND)	Disruption at the radiocarpal or midcarpal joints, with intact proximal and distal rows	Midcarpal instability
Carpal instability complex (CIC)	Derangement both within and between carpal rows (CID plus CIND)	Perilunate dislocation with ulnar translation
Carpal instability adaptive (CIA)	Instability due to injury proximal or distal to wrist	Distal radius malunion

(Data from International Wrist Investigators' Workshop Terminology Committee. Wrist: terminology and definitions. *J Bone Joint Surg Am.* 2002;84-A(Suppl 1):1-73.)

Because of the scaphoid's natural tendency to flex when loaded, delayed treatment of comminuted fractures of the scaphoid waist tend to result in the so-called "humpback deformity" (Fig. 8.9). This term describes the shape of the scaphoid as seen on lateral tomograms, reflecting malunion of the bone with an abnormally acute angle between the proximal and distal poles of the scaphoid.¹⁸

Mechanisms of injury

In elderly osteoporotic patients, wrist injuries are commonly seen after falls from a standing height. Very often, this is an extra-articular fracture with apex volar angulation, the so-called "Colles fracture" (see Fig. 8.3). The younger population typically experiences fractures caused by higher energy




Fig. 8.8 (A) Lunate position in DISI and VISI deformities of the wrist. X-rays of (B) DISI and (C) VISI deformities.



Fig. 8.9 Fracture at the waist of the scaphoid, resulting in a humpback deformity.

injuries, such as motor vehicle collisions or sports-related trauma, resulting in more complex fracture patterns. With increasing force of injury, the chance of associated carpal fracture, intercarpal ligament injury, or triangular fibrocartilage complex injury increases.

Diagnosis/patient presentation

History

A detailed history begins with careful documentation of the circumstances or mechanism of the injury. Patients involved in high-energy falls or collisions should be evaluated for associated injuries by an emergency medicine physician or trauma specialist. The patient's handedness, occupation, important hobbies or recreational activities, medical and surgical history, and social history should be recorded. It is important to ask about numbness and/or tingling in the hand, because these patients are prone to acute carpal tunnel syndrome which may need to be addressed at the time of operation.

Physical examination

The examination of the patient's upper extremity should be thorough and systematic. Although the focus of this chapter is on the wrist, both the elbow and the hand should be included in the scope of examination, to avoid missing associated injuries. Examination begins with inspection. The signs of acute trauma should be noted: wounds, ecchymosis, bleeding, swelling, etc. Subacute or chronic changes may be more subtle, and comparison to the patient's contralateral uninjured extremity can be helpful in detecting slight differences in swelling, alignment, and skin characteristics.

Palpation of the extremity can help localize the site of injury. The examining surgeon should be familiar with the

topography of the wrist, and be able to identify injury to specific structures by careful, systematic palpation. For instance, focal tenderness just distal to the Lister tubercle could indicate injury to the scapholunate interosseous ligament, whereas pain with palpation of the floor of the anatomic snuffbox may signify a scaphoid waist fracture.

Before assessing the range of motion or performing any provocative testing, it is important to review the radiographs of the extremity to rule out any unstable fractures that might be displaced or otherwise worsened by vigorous physical examination. While assessing the patient's active and passive range of motion, palpation over the joints being moved can yield other useful information about crepitus, clicks, or clunks in the wrist. A complete examination should also include assessment of grip strength, pinch strength, and sensibility. It is particularly important to detect median neuropathy in wrist injury patients, because acute carpal tunnel syndrome may require treatment. Provocative testing of specific intrinsic ligaments of the wrist can be valuable in reaching a diagnosis, but should be conducted with caution when unstable fractures are present to avoid unwanted fracture displacement.

The Watson scaphoid shift test stresses the scapholunate ligament to detect injury or instability (**Fig. 8.10**). The examiner applies pressure (typically with the thumb) over the distal scaphoid tubercle, while moving the patient's wrist from ulnar to radial deviation.¹⁹ In ulnar deviation, the scaphoid is extended, whereas in radial deviation it is flexed. Thus, in the intact wrist, the scaphoid's ligamentous attachments resist subluxation during this maneuver. However, in cases of scapholunate dissociation, the scaphoid may be forced dorsally out of the scaphoid fossa into a painful position for the patient. Upon releasing pressure, a clunk may be detected, indicating the self-reduction of the scaphoid back over the dorsal rim of the radius. A painful Watson test in the absence




Fig. 8.10 Watson scaphoid shift test.

of an obvious clunk may be a sign of scapholunate ligament damage without complete disruption of the ligament.

The lunotriquetral interosseous ligament can be assessed by the Kleinman shear test (Fig. 8.11). The examiner grasps the patient's wrist in one hand, specifically applying stabilizing pressure over the lunate, which is palpable dorsally just beneath the fourth extensor compartment tendons. With the other hand, the examiner applies dorsally directed pressure over the pisiform, which applies a shear force directed across the lunotriquetral articulation.²⁰ Laxity can be assessed by further grasping the pisiform and triquetrum "unit" and moving it both palmarly and dorsally in a "shucking"-type maneuver. This latter is referred to as the lunotriquetral ballottement test.²¹ Pain and/or instability may indicate injury or disruption of the lunotriquetral ligament.

Diagnostic tests

At a minimum, assessment of wrist injuries should include four radiographs: posteroanterior (PA), oblique, lateral, and PA ulnar deviation. The ulnar deviation view is particularly important in detecting scaphoid injuries. The lateral view can evaluate the relationship between scaphoid and lunate; the normal scapholunate angle is between 30–60° (Fig. 8.12). Another helpful view for detecting dynamic instability of the scapholunate ligament is the clenched fist view. When making a tight fist, load is placed across the wrist, and the capitate is driven toward the scapholunate articulation, which will make scapholunate ligament laxity or rupture more evident. To increase the accuracy of the diagnosis, both anteroposterior (AP) and PA stress views should be considered.²²

With regard to distal radius fractures, there are a few key metrics that help guide management, and plain radiographs are generally sufficient to determine these measurements. Changes in radial height (normal = 10–13 mm), radial inclination (normal = 21–25°), and volar tilt (range 2–20°,




Fig. 8.11 Kleinman shear test.




Fig. 8.12 The normal angle between the mid-axis of the scaphoid to the lunate ranges from 30–60° (average 47°).

average = 11°) help define the extent of fracture displacement (Fig. 8.13).²³

Cross-sectional imaging modalities, such as computed tomography (CT) and magnetic resonance imaging (MRI), are also used routinely to investigate wrist injuries. CT is an X-ray-based modality, and as such it is best for assessing complex fracture-dislocation patterns. In particular, CT can help assess joint congruity and/or depressed articular fragments. CT is also better than MRI at determining osseous healing across a fracture site. On the other hand, MRI is the preferred modality for assessing nonosseous structures, and has the added benefit of providing some information about vascularity of parts of the carpus. MRI technology continues to evolve, and modern machines can detect very small ligamentous injuries. When the modalities of MRI and arthrography are combined, even small perforations in the interosseous ligaments can be detected.

Clinical tip

CT scans are better at showing fracture details and bony bridging/healing. MRIs are better at showing soft tissue injury, occult (non-displaced) fractures, and bony edema.

The use of bone scans has decreased substantially over the years because of the effectiveness of MRIs. Nevertheless, bone scans are still helpful in identifying "hot areas" of the wrist in difficult cases when the etiology of the patient's wrist pain




Fig. 8.13 (A) Radial height measured as the distance between two lines, the first line perpendicular to the longitudinal axis of the radius and intersecting the distal surface of the ulnar head, and the second line that passes through the distal tip of the radial styloid. (B) Radial inclination represented by the angle between the line perpendicular to the longitudinal axis of the radius and a second line connecting the ulnar aspect of the distal radius and the tip of the radial styloid. (C) Volar tilt is the angle between the line perpendicular to the longitudinal axis of the radius and a line along the distal articular surface of the radius.

is uncertain. However, the nonspecific nature of the bone scan limits its usefulness in the evaluation of most injuries.

Diagnostic wrist arthroscopy, while more invasive than the tests mentioned above, must still be considered the “gold standard” for detecting intra-articular wrist injuries. In a recent systematic review comparing MRI results with findings at arthroscopy, the negative predictive value of MRI for scapholunate injury ranged from 72–94%.²⁴ In other words, MRI can never completely rule out ligamentous injury in the wrist.

One pitfall associated with the increasingly widespread use of MRI is the inevitable detection of “false positive” findings in the wrist. It is not uncommon to find multiple minor abnormalities on high-resolution wrist MRI, many of which have nothing to do with the patient’s complaints. Therefore, it is important for the treating physician to use MRI wisely, in cases where there is reasonable suspicion of injury or occult pathology, rather than use it indiscriminately.

Patient selection

Indications for fixation of scaphoid fractures are fairly well established. Because displaced scaphoid fractures cannot be reduced in a closed fashion, open reduction and internal fixation (ORIF) is required to restore anatomic alignment. This is important to facilitate healing in the scaphoid, due to its tenuous blood supply, and to restore normal scaphoid shape and alignment, which is important for carpal kinematics.²⁵ Other relative indications are listed in [Table 8.2](#).

Operative fixation of non-displaced scaphoid fractures has been debated. Advocates cite many advantages, including earlier return to active military duty and increased quality-adjusted life-years.^{26,27} Despite some evidence of improved functional outcomes and less time off work, surgical treatment does present some risk of complications and should not be considered lightly, since the majority of these fractures will heal nicely with immobilization alone.^{28,29}

Acute scapholunate ligament injuries require operative repair to maintain carpal alignment and avoid collapse which can lead to predictable patterns of wrist arthritis.³⁰ However, unlike bone fixation, which reliably leads to union in most cases, techniques for repair of interosseous ligaments are not as predictable. Furthermore, the healing capacity of intercarpal ligaments seems to deteriorate over time, so patients presenting more than 6 weeks after injury may not have any suitable ligament remnants to attempt an operative repair.

Table 8.2 Relative indications for scaphoid fracture fixation

Displaced fractures
Proximal pole fractures (regardless of displacement)
Fractures associated with perilunate injuries
Open fractures
Fractures in multiply injured patients
Fractures not healing after a trial of immobilization (3–4 months)

The evidence favoring acute repair of lunotriquetral tears is less convincing. Many authors believe a trial of non-operative treatment with immobilization is indicated prior to considering operative repair.^{21,31}

The American Academy of Orthopaedic Surgeons has published guidelines regarding treatment of distal radius fractures.³² Non-displaced distal radius fractures typically heal with immobilization alone and do not require surgical intervention. Displaced distal radius fractures should undergo a reduction maneuver before deciding if surgery is needed. Stable fractures that remain reduced will not require an operation, but should be followed weekly for 2–3 weeks to be sure the fracture does not collapse or re-displace. Although the available evidence does not lend itself to many definitive recommendations, there is moderate evidence to support operative fixation of fractures with post-reduction radial shortening >3 mm, dorsal tilt >10°, and/or intra-articular displacement or step-off >2 mm.³²

Despite the existence of these guidelines, patient selection does not depend on X-ray findings alone. A patient's overall health, comorbidities, pre-injury activity level, job requirements, and expectations all play a role in the decision for surgery. This concept is exemplified in the ongoing investigation of the optimal treatment of distal radius fractures in the elderly.

With the development of volar fixed-angle plates with locking screws, fixation of distal radius fractures quickly became easier and more predictable, especially for fragility fractures in older adults.^{33,34} This has led to an increase in the operative management of these fractures in the elderly, increasing from 3% in 1996 to 16% in 2005.⁹ Without surgery, these fractures predictably result in malunion, with the majority having less-than-excellent radiographic results.³⁵ However, patient-reported outcome studies have shown that older adults tolerate greater degrees of malalignment without difficulty.³⁶ Therefore, an independent, active retiree might do better with surgical fixation, whereas a low-demand, infirm patient of the same age might do better with nonoperative treatment.

Treatment and surgical techniques

Scaphoid fractures

The scaphoid appears to be in the shape of a cashew nut, and can be divided into three segments: distal pole (tubercle), waist, and proximal pole. Due to the distally-located blood supply, fractures of the distal pole or tubercle heal reliably with 6–8 weeks of immobilization, and rarely need surgical fixation unless significantly displaced. However, as the location of the fracture line moves more proximally, the incidence of nonunion increases, and any measurable displacement increases this risk. Even non-displaced proximal pole fractures will take considerable time to heal if treated nonoperatively; cast treatment can last as long as 6–9 months before healing is confirmed.

Internal fixation of scaphoid fractures is most commonly accomplished with a headless compression screw. Placement of the screw can be challenging, as complete visualization of the scaphoid is difficult, and the screw should be placed down the long axis of the bone for best bony purchase with least risk of extrusion. We advocate a dorsal approach for proximal

pole fractures; waist fractures can be repaired through a volar or dorsal approach. Although minimally invasive (percutaneous) techniques have been developed for scaphoid fractures, these are not for the novice hand surgeon.

The dorsal approach for ORIF of a scaphoid fracture (Fig. 8.14A) begins with a longitudinal incision just distal and ulnar to the Lister tubercle, extending over the dorsal wrist (Fig. 8.14B). The third compartment is identified through this incision, and EPL is partially released, without completely opening the compartment. With EPL protected, the wrist capsule is opened longitudinally to expose the scaphoid, identify the fracture, and examine the nearby scapholunate ligament. The fracture is then reduced; this can be aided by bone reduction forceps, or another similar instrument.³⁷ The wrist is then flexed to fully expose the proximal pole, and the guidewire for the cannulated headless compression screw is placed down the long axis of the bone. Ideally, a second wire should be added to prevent displacement of the fracture during drilling and screw placement (Fig. 8.14C). This stabilizing wire should be placed across the fracture into the trapezium for maximum stability, but it must not interfere with screw placement. Multiplanar mini C-arm fluoroscopy is used to confirm that the guidewire is through the central axis of the scaphoid and that the fracture is reduced. Most screw sets utilize a measuring tool at this point to select a screw length, based on the length of guidewire that is protruding from the bone.

Clinical tip

When basing the scaphoid screw measurement on the guidewire, one must take into account the position of the wire relative to the distal cortex. If the wire abuts the distal cortex, at least 2 mm should be subtracted from the given measurement to ensure the screw does not penetrate into the scaphotrapezial joint. Generally, screw measurements are around 22–24 mm for men and 18–20 mm for women.

A cannulated drill or reamer is then used to gently drill the hole by hand, frequently checking progress using fluoroscopy. Consider advancing the guidewire into the trapezium to stabilize it further before drilling. It is important to maintain a straight trajectory with the drill and avoid bending the guidewire, so as to avoid damaging or breaking the wire. The cannulated screw is then placed on the guidewire and advanced across the fracture line (Fig. 8.14D). The K-wires are then removed, final position of the screw is verified with fluoroscopy, and the incision closed (Fig. 8.14E).

Scaphoid nonunion

Scaphoid nonunion is not an uncommon occurrence, both because scaphoid fractures can be missed upon initial examination, and because the scaphoid's precarious blood supply puts it at risk. Many of those who suffer from a scaphoid nonunion are active young adults who are involved in athletic activities, and their fracture was either misdiagnosed as a sprain, or not diagnosed at all. The natural history of scaphoid nonunion is not precisely known. It is clear that there is an increased risk of post-traumatic arthritis – the scaphoid nonunion advanced collapse (SNAC) wrist – due to the disruption of the proximal row biomechanics. What is not known is the incidence of symptoms, since many asymptomatic patients




Fig. 8.14 (A) Scaphoid fracture to be treated with ORIF using a screw. (B) The incision is made ulnar to the Lister tubercle. (C) Two K-wires are passed into the scaphoid, one of which is the guidewire for the cannulated screw. (D) Finally, a compression screw is inserted into the bone. (E) Final fracture reduction showing the screw placement.

never present for treatment of their nonunion.³⁸ Asymptomatic patients do not need surgical intervention, but should probably be followed periodically to monitor for the development of symptoms and/or radiographic signs of arthritis.

Patients with symptomatic scaphoid nonunion may be candidates for operative treatment.³⁹ Advanced imaging is indicated to determine the exact deformity present in the scaphoid, and may also provide clues as to the vascularity of the proximal fragment. Correction of a “humpback” deformity (see Fig. 8.9) is easiest from the volar approach, as it requires the fracture site to be opened and a structural graft from either the iliac crest or from the distal radius inserted to restore the height of the scaphoid. This approach can also be used to treat established malunion of the scaphoid with similar deformity.

If there is concern for avascular necrosis, vascularized bone grafting should be considered to increase the blood flow to the scaphoid. Typically, this situation arises in proximal pole fractures, and dorsal approach is preferred. Pedicled grafts from the dorsal distal radius, such as those based on the 1,2-intercompartmental supraretinacular artery, reach the

scaphoid easily.⁴⁰ Although more technically demanding, a free vascularized bone graft from the medial femoral condyle is another option (Fig. 8.15).⁴¹

Scapholunate ligament injury

Scapholunate ligament injury is the most common form of carpal instability. It is critical to establish the chronicity of the injury before developing a treatment plan.

Acute scapholunate injuries present with localized pain and swelling, but rarely have dramatic findings on radiographs. The diastasis between scaphoid and lunate and the DISI deformity that characterize this injury often develop over time as secondary supporting structures attenuate and degenerate (Fig. 8.16). If radiographs are normal, identification of these injuries demands a high degree of clinical suspicion, and may require confirmation with MRI arthrography or arthroscopy.

Acute partial tears will not have any gross instability and should heal with 4–6 weeks of immobilization alone. Acute




Fig. 8.15 (A) The medial femoral condyle flap is taken from the leg and (B,C) grafted into the wrist.

complete tears should be treated with open repair of the ligament using suture anchors or other suitable method. The repair should be protected with scapholunate and scapho-capitate (midcarpal) pinning for 8 weeks to allow the ligament to heal. Many surgeons reinforce such acute repairs with

additional capsulodesis, especially in subacute repairs.⁴² Repairs delayed greater than several weeks may be difficult, as the ligament remnants tend to deteriorate over time.³⁰

For patients with chronic tears, the treatment becomes more complex. Patients with a reducible scapholunate diastasis without arthritic changes may benefit from reconstruction. Arthroscopy is often utilized to determine the status of the cartilaginous surfaces and the reducibility of the carpals, but sometimes a final decision can only be made after open exploration of the joint. It is important to discuss all potential options with the patient prior to surgery.

Reconstruction of chronic scapholunate dissociation can take many forms. For an easily reducible diastasis with some ligament remnants present, repair with capsulodesis can be performed, much like in a more acute injury. Our preference is to perform a dorsal capsulodesis by inserting a mini-bone anchor into the distal pole of the scaphoid (Fig. 8.17) to anchor this part of the scaphoid to the dorsal wrist capsule, thereby preventing volar flexion of the scaphoid and subsequent impingement on the radial styloid.

Clinical tip

A good indicator of the “reducibility” of chronic scapholunate dissociation is the ease with which the diastasis can be corrected using K-wire “joysticks” in the bones to manipulate them. If the scapholunate articulation can be reduced without permanently deforming 0.062-inch K-wire joysticks, then reconstruction can be considered.



Fig. 8.16 A widened interval between scaphoid and lunate as a result of a scapholunate ligament tear.

If the ligament is not repairable, there have been many strategies developed to restore the scapholunate linkage, usually relying on tendon grafts to perform some variety of tenodesis between the unstable bones. Our preferred technique uses a slip of the flexor carpi radialis (FCR) tendon passed through a drill hole in the scaphoid, woven through the



Fig. 8.17 A mini-bone anchor used to anchor the distal pole of the scaphoid to prevent its flexion, which can cause arthritis change at the radial styloid.

dorsal radiocarpal ligament, and secured to the lunate, which has been referred to as a three-ligament tenodesis (Fig. 8.18).⁴³

If uncorrected, scapholunate dissociation can lead to wrist arthritis. Depending on the stage of arthritis at presentation, various salvage procedures may be indicated. These are addressed more fully in Chapter 20 of this textbook.

Lunotriquetral ligament injury

Lunotriquetral ligament injuries are more subtle than scapholunate ligament tears. A true lunotriquetral diastasis is rarely seen on radiographs, although a mild VISI deformity or minor disruption in the first Gilula arc may help identify the injury (Fig. 8.19). Because of this subtlety, these injuries are rarely diagnosed acutely.

If no collapse (VISI deformity) is present, both acute and chronic injuries can be treated initially with immobilization and other conservative measures. Operative intervention is reserved for those wrists that progress to VISI deformity, or otherwise fail nonoperative management. Surgical treatment options include ligament repair, ligament reconstruction, arthrodesis, and ulnar-shortening osteotomy.

Lunotriquetral ligament repair is technically challenging, typically requiring both dorsal and volar approaches. The ligament tends to be short and is not amenable to repair in chronic injuries. Reconstruction with a slip of the extensor carpi ulnaris tendon passed through drill holes in these bones has been used with some success to recreate the lunotriquetral linkage, and is superior to repair in chronic cases.^{31,44} Ulnar shortening osteotomy can be useful in unloading a painful ulnocarpal joint, as in cases of ulnocarpal abutment leading to lunotriquetral injury, and may help to re-tension secondary stabilizers in these cases.⁴⁵

Perilunate dislocation

Perilunate injuries are usually diagnosed immediately, as these patients present with a major wrist injury and often have acute median neuropathy (Fig. 8.20A). Reduction should be performed immediately to alleviate this pressure on the nerve and restore carpal alignment. This maneuver typically requires sedation, analgesia, and distraction. With careful manipulation of the wrist into extension, while applying traction, the capitate can be re-located onto the lunate in most cases. If the lunate is completely dislocated into the carpal tunnel, gentle volar pressure should be used to relocate it back into its place between capitate and radius. Patients presenting in a delayed fashion will be more difficult to reduce. If reduction is not possible, consideration should be given to a more urgent operative intervention, especially in patients with ongoing nerve impingement.

For definitive repair, we believe both dorsal and volar approaches are required.¹³ Volarly, an extended carpal tunnel incision is performed, crossing the wrist crease (Fig. 8.20B). After reducing the lunate, the volar capsule tear is closed using permanent sutures. This repair often incorporates closure of the space of Poirier as well as repair of the volar lunotriquetral ligament, if sutures are placed deep enough. Proponents of a dorsal-only approach to this injury argue that these ligaments are nicely opposed after reduction, and sutures are unnecessary.¹⁴ However, given the need for carpal tunnel decompression in the vast majority of these patients, we perform the capsular repair through this incision as well.

A dorsal wrist exposure (Fig. 8.20C) is then used to confirm accurate carpal alignment, pin the reduced carpus, and repair the dorsal scapholunate ligament, typically with suture anchors. A capsulodesis can be added to reinforce the repair. The pins are cut below the surface of the skin, to remain in place for 8 weeks (Fig. 8.20D). We prefer burying the pins to reduce the risk of postoperative pin track infection. Interestingly, although the lunate is often stripped of all its attachments in this type of injury, avascular necrosis of the lunate is rare in these patients.

Clinical tip

In perilunate dislocations, it is important to make sure the carpus is “rebuilt” with the lunate in neutral position (no DISI or VISI). We begin by placing a temporary pin across the radiolunate joint, with the lunate in neutral position, verified with lateral fluoroscopy. The scaphoid and triquetrum are then reduced to the lunate, and pinned in the appropriate reduced position. After repairing the dorsal ligaments, the radiolunate pin is removed.

Distal radius fractures

Most distal radius fractures present as closed injuries; those that fail conservative treatment can be electively fixed on an outpatient basis, preferably within 1 week. If fixed within this time frame, we find that most fragments are easily reducible, and the deposition of healing callus that can obscure an accurate reduction is minimized. However, there are a couple of situations where more urgent intervention might be needed.

Open fractures of the distal radius are a surgical emergency, especially if there is gross contamination of the fracture site.




Fig. 8.18 (A) PA X-ray showing mild scapholunate diastasis and cortical ring sign. (B) Intraoperative view of chronic scapholunate dissociation. L, Lunate; S, scaphoid. (C) Three-ligament tenodesis. DRC, dorsal radiocarpal ligament; FCR, flexor carpi radialis tendon. (D) Postoperative X-ray showing properly extended scaphoid, bone anchors, and protective K-wires.




Fig. 8.19 Disruption of the first Gilula arc as a result of a lunotriquetral ligament injury.

Any fracture-related wound more than a tiny puncture should probably be washed out formally in the operating room to reduce the risk of osteomyelitis.

Patients with median nerve symptoms that do *not* improve after reduction of the fracture should be considered for an acute carpal tunnel release. It is our experience that these patients typically have a prolonged recovery due to their nerve contusion/crush injury, so relieving any ongoing compression of the nerve can be important to their ultimate recovery. If median nerve symptoms *do* improve with fracture reduction, the carpal tunnel should still be released at the time of surgical fixation.

Operative treatments for distal radius fractures include percutaneous K-wire fixation, external fixation, internal fixation, or combinations of these techniques. Internal fixation can be further subdivided into dorsal plating, volar plating, and fragment-specific plating configurations.

The introduction of volar fixed-angle plates with locking screws has revolutionized the treatment of these fractures.³³ Historically, the dorsal approach was thought to be safer, as it avoided the important neurovascular structures found at the volar wrist. Furthermore, dorsal buttress plates seemed more logical, since these fractures tend to displace dorsally. However, dorsal plating was soon found to be associated with many complications, especially extensor tendon ruptures, due

to the difficulty of protecting these soft tissues from the hardware in this location.

The modern volar approach is intended to overcome the problems of dorsal plating. The advantage of the volar plating technique is the ability to place the plate under the pronator quadratus muscle, which can shield the plate from injuring the overlying tendons and nerves. In addition, the introduction of locking screws made rigid fixation from the volar side possible irrespective of the amount of comminution of the dorsal metaphysis (Fig. 8.21). Traditional non-locking screws must adequately engage both cortices in order to secure the plate to bone using friction. While locking screws do engage the bone to some extent, they also have threads on the screw head to engage the plate itself. This prevents the screw from “toggling” due to pressure across the fixed fracture. Furthermore, each screw can be firmly positioned in space to lend three-dimensional support beneath the articular surface of the radius. This construct is rigid enough in most cases to allow for early gentle motion of the wrist in routine cases.

Volar plating does have several nuances that one must pay attention to during exposure to prevent unnecessary complications.⁴⁶ First, the volar incision must be made radial to the FCR tendon to protect the palmar cutaneous branch of the median nerve, which is found immediately ulnar to the FCR at the wrist. Next, instead of incising the pronator quadratus down the middle, the muscle should be elevated as an ulnarly based flap by dividing its insertion on the radius. This makes coverage of the plate easier at the conclusion of the case. For the distal locking screws, the lengths should be measured very carefully. We advocate using screws 1–2 mm shorter than the depth gauge measurement to prevent screw-tip related injuries to the extensor tendons. Finally, once the plate has been completely installed, fluoroscopy should be performed in multiple planes to ensure correct implant and screw position. Specifically, an offset lateral view should be used to examine the radiocarpal joint. By angling the wrist about 30° (equal to the radial inclination of the joint), one can get a view down the articular surface to make sure no distal screws penetrate the joint (Fig. 8.22). Adhering to these guidelines will allow for effective plating, with minimal complications.

Ulnar styloid fractures

The distal radioulnar ligaments connect the distal radius to the ulna, inserting via the triangular fibrocartilage complex (TFCC) to both the fovea and the styloid of the ulna. Because of this mechanical connection, the ulnar styloid often sustains some degree of an avulsion fracture when distal radius fractures displace (see Fig. 8.21). Even in cases where the ulnar styloid is not fractured, avulsion injuries of the TFCC can lead to instability of the distal radioulnar joint (DRUJ). For this reason, the stability of this joint should be tested in every case of distal radius fracture. When instability is detected, it should be addressed by performing fixation of the styloid fracture, or by repair of the TFCC attachment in cases without styloid fracture. In some ways, the ulnar styloid fracture is analogous to the volar lip avulsion fracture seen in PIP joint hyperextension injury: it serves as a marker of injury severity, but does not need to be treated unless instability is present.

Despite evidence of nonunion in many cases, patients without DRUJ instability do very well without ulnar styloid fixation.⁴⁷ Biomechanical studies have shown that DRUJ




Fig. 8.20 (A) Lateral X-ray showing perilunate dislocation. (B) Extended carpal tunnel release, showing lunate in the carpal tunnel. L, lunate. (C) Dorsal wrist exposure, after lunate has been reduced. Note the complete disruption of the scapholunate ligament. C, Capitate; DR, distal radius; H, hamate; L, lunate; S, scaphoid; Tq: triquetrum. (D) Postoperative X-ray showing bone anchors and protective K-wires across scapholunate, scaphocapitate, and lunotriquetral articulations.



Fig. 8.21 (A) A complex distal radius fracture that has been (B) reduced using a volar locking plate. Note the displacement of the ulnar styloid fracture, which does not need to be fixated because the distal radioulnar joint is stable with manual testing.



Fig. 8.22 Fluoroscopic 30° offset lateral view, showing that each of the distal screws is outside the radiocarpal joint.

stability in these cases can be maintained by the distal oblique bundle of the interosseous membrane.⁴⁸ This makes it all the more important to obtain anatomic distal radius reductions, so that the appropriate tension on the interosseous membrane is maintained.⁴⁹

In cases where the DRUJ is unstable, the ulnar styloid can be fixed with tension-band constructs or small “hook plates”, which have recently been developed (Fig. 8.23). Hardware in this location is not particularly dangerous to the nearby tendons, but is often symptomatic to the patient, since it is on the subcutaneous border of the wrist and forearm, without much soft tissue padding to cover the hardware.

Future directions

The problem of scaphoid nonunion with avascular necrosis of the proximal pole has led to tremendous amounts of research and innovation over the years. The latest development in this field is a further refinement of the medial femoral condyle flap. While the traditional flap was described as an osteoperiosteal flap, Drs. Higgins and Burger have developed a version of the flap that is an osteocartilaginous construct, termed the *medial femoral trochlear flap*.⁵⁰ This free flap can be used to replace the entire proximal pole of the scaphoid, as long as one takes the time to precisely “carpenter” the graft to the correct shape. Although logic dictates that there must be some




Fig. 8.23 Options for ulnar styloid fixation include (A) K-wires, with or without a tension band, and (B) ulnar hook plate, which works well for larger styloid or ulnar head fractures.

disadvantage to the loss of the scapholunate ligament, it does not appear that these patients develop automatic instability. In fact, Dr. Higgins has shown that scapholunate stability can be effectively restored by “overstuffing” the scaphoid dimensions using a larger-than-anatomic graft to reconstruct this troublesome carpal bone.⁵¹

Treatment of distal radius fractures in the elderly, as mentioned before, is still an area where we would like better outcomes data to guide treatment decisions. It is clear that the elderly perhaps adapt more easily to malunion, or are somehow more tolerant of wrist malalignment. Furthermore, it is not clear which method of fixation (K-wires, external fixation, or internal fixation) will lead to the most acceptable

result. A large, 21-center, international trial is underway (Wrist and Radius Injury Surgical Trial, or “WRIST”) to help answer the question of which is the best treatment for this patient population.⁵²



Bonus images for this chapter can be found online at

<http://www.expertconsult.com>

Fig. 8.2 Posteroanterior radiograph of the wrist, with carpal bones identified.
Fig. 8.3 Examples of common distal radius fracture eponyms: (A) Colles fracture, (B) Smith fracture, (C) dorsal Barton fracture, (D) volar Barton fracture, and (E) Chauffeur fracture.



Access the complete reference list online at

<http://www.expertconsult.com>

9. Chung KC, Shauver MJ, Birkmeyer JD. Trends in the United States in the treatment of distal radial fractures in the elderly. *J Bone Joint Surg Am.* 2009;91:1868–1873. *This Medicare database study examines the recent trends in treatment of distal radius fractures in elderly patients. As internal fixation has become more reliable, we have seen an increase in its use in this population, though the majority of fractures are still treated nonoperatively.*
13. Kozin SH. Perilunate injuries: diagnosis and treatment. *J Am Acad Orthop Surg.* 1998;6:114–120.
26. Davis EN, Chung KC, Kotsis SV, et al. A cost/utility analysis of open reduction and internal fixation versus cast immobilization for

acute nondisplaced mid-waist scaphoid fractures. *Plast Reconstr Surg.* 2006;117:1223–1235, discussion 1236–1238.

28. Buijze GA, Doornberg JN, Ham JS, et al. Surgical compared with conservative treatment for acute nondisplaced or minimally displaced scaphoid fractures: a systematic review and meta-analysis of randomized controlled trials. *J Bone Joint Surg Am.* 2010;92:1534–1544. *This meta-analysis combined data from several randomized controlled trials to evaluate surgical versus non-surgical treatment of acute, non-displaced or minimally displaced scaphoid fractures. The findings suggest that surgical treatment is favorable with regard to functional outcome and time off work, but this approach does lead to more complications than non-operative treatment.*

30. Kuo CE, Wolfe SW. Scapholunate instability: current concepts in diagnosis and management. *J Hand Surg Am.* 2008;33:998–1013.
31. Shin AY, Battaglia MJ, Bishop AT. Lunotriquetral instability: diagnosis and treatment. *J Am Acad Orthop Surg.* 2000;8:170–179. *This article presents a series of patients with lunotriquetral instability treated with a variety of reconstructive techniques. It is one of the largest series on this topic, and the treatment algorithm is thoughtfully presented.*
33. Chung KC, Petruska EA. Treatment of unstable distal radial fractures with the volar locking plating system. *J Bone Joint Surg Am.* 2006;88:2687–2694.
40. Sheetz KK, Bishop AT, Berger RA. The arterial blood supply of the distal radius and ulna and its potential use in vascularized pedicled bone grafts. *J Hand Surg Am.* 1995;20:902–914. *This anatomic study presents a detailed, thorough look at the blood supply to the distal radius, and proposes reliable, pedicled bone flaps based on this data. For many surgeons, these flaps have become workhorses for carpal reconstruction.*
43. Garcia-Elias M, Lluch AL, Stanley JK. Three-ligament tenodesis for the treatment of scapholunate dissociation: indications and surgical technique. *J Hand Surg Am.* 2006;31:125–134. *Dr. Garcia-Elias has enormous experience treating carpal instability, and his approach is constantly evolving. This article presents a logical, reliable technique as well as a thoughtful treatment algorithm for these patients.*
47. Sammer DM, Shah HM, Shauver MJ, Chung KC. The effect of ulnar styloid fractures on patient-rated outcomes after volar locking plating of distal radius fractures. *J Hand Surg Am.* 2009;34:1595–1602.

References

- Chung KC, Spilson SV. The frequency and epidemiology of hand and forearm fractures in the United States. *J Hand Surg Am*. 2001;26:908–915.
- Hove LM. Fractures of the hand. Distribution and relative incidence. *Scand J Plast Reconstr Surg Hand Surg*. 1993;27:317–319.
- Dunn AW. Fractures and dislocations of the carpus. *Surg Clin North Am*. 1972;52:1513–1538.
- Duckworth AD, Jenkins PJ, Aitken SA, et al. Scaphoid fracture epidemiology. *J Trauma Acute Care Surg*. 2012;72:E41–E45.
- Wolf JM, Dawson L, Mountcastle SB, Owens BD. The incidence of scaphoid fracture in a military population. *Injury*. 2009;40:1316–1319.
- Khan IH, Giddins G. Analysis of NHS LA claims in hand and wrist surgery. *J Hand Surg Eur Vol*. 2010;35:61–64.
- Johnson RP. The evolution of carpal nomenclature: a short review. *J Hand Surg Am*. 1990;15:834–838.
- Colles A. On the fracture of the carpal extremity of the radius. *Edinb Med Surg J*. 1814;10:182–186.
- Chung KC, Shauver MJ, Birkmeyer JD. Trends in the United States in the treatment of distal radial fractures in the elderly. *J Bone Joint Surg Am*. 2009;91:1868–1873.
- Gehrmann SV, Windolf J, Kaufmann RA. Distal radius fracture management in elderly patients: a literature review. *J Hand Surg Am*. 2008;33:421–429.
- Panagis JS, Gelberman RH, Taleisnik J, Baumgaertner M. The arterial anatomy of the human carpus. Part II: the intraosseous vascularity. *J Hand Surg Am*. 1983;8:375–382.
- Nagle DJ. Evaluation of chronic wrist pain. *J Am Acad Orthop Surg*. 2000;8:45–55.
- Kozin SH. Perilunate injuries: diagnosis and treatment. *J Am Acad Orthop Surg*. 1998;6:114–120.
- Budoff JE. Treatment of acute lunate and perilunate dislocations. *J Hand Surg Am*. 2008;33:1424–1432.
- Kozin SH, Wood MB. Early soft-tissue complications after fractures of the distal part of the radius. *J Bone Joint Surg Am*. 1993;75:144–153.
- Definition of carpal instability. The Anatomy and Biomechanics Committee of the International Federation of Societies for Surgery of the Hand. *J Hand Surg Am*. 1999;24:866–867.
- International Wrist Investigators' Workshop Terminology Committee. Wrist: terminology and definitions. *J Bone Joint Surg Am*. 2002;84(suppl 1):1–73.
- Amadio PC, et al. Scaphoid malunion. *J Hand Surg Am*. 1989;14:679–687.
- Watson HK, Ashmead DT, Makhlof MV. Examination of the scaphoid. *J Hand Surg Am*. 1988;13:657–660.
- Kleinman WB. Physical examination of the wrist: useful provocative maneuvers. *J Hand Surg Am*. 2015;40:1486–1500.
- Reagan DS, Linscheid RL, Dobyns JH. Lunotriquetral sprains. *J Hand Surg Am*. 1984;9:502–514.
- Schreibman KL, Freeland A, Gilula LA, Yin Y. Imaging of the hand and wrist. *Orthop Clin North Am*. 1997;28:537–582.
- Goldfarb CA, Yin Y, Gilula LA, et al. Wrist fractures: what the clinician wants to know. *Radiology*. 2001;219:11–28.
- Andersson JK, Andersnord D, Karlsson J, Fridén J. Efficacy of magnetic resonance imaging and clinical tests in diagnostics of wrist ligament injuries: a systematic review. *Arthroscopy*. 2015;31:2014–2020.e2.
- Haisman JM, Rohde RS, Weiland AJ. Acute fractures of the scaphoid. *J Bone Joint Surg Am*. 2006;88:2750–2758.
- Davis EN, Chung KC, Kotsis SV, et al. A cost/utility analysis of open reduction and internal fixation versus cast immobilization for acute nondisplaced mid-waist scaphoid fractures. *Plast Reconstr Surg*. 2006;117:1223–1235, discussion 1236–1238.
- Bond CD, Shin AY, McBride MT, Dao KD. Percutaneous screw fixation or cast immobilization for nondisplaced scaphoid fractures. *J Bone Joint Surg Am*. 2001;83-A:483–488.
- Buijze GA, Doornberg JN, Ham JS, et al. Surgical compared with conservative treatment for acute nondisplaced or minimally displaced scaphoid fractures: a systematic review and meta-analysis of randomized controlled trials. *J Bone Joint Surg Am*. 2010;92:1534–1544.
- Dias JJ, Wildin CJ, Bhowal B, Thompson JR. Should acute scaphoid fractures be fixed? A randomized controlled trial. *J Bone Joint Surg Am*. 2005;87:2160–2168.
- Kuo CE, Wolfe SW. Scapholunate instability: current concepts in diagnosis and management. *J Hand Surg Am*. 2008;33:998–1013.
- Shin AY, Battaglia MJ, Bishop AT. Lunotriquetral instability: diagnosis and treatment. *J Am Acad Orthop Surg*. 2000;8:170–179.
- Lichtman DM, Bindra RR, Boyer MI, et al. Treatment of distal radius fractures. *J Am Acad Orthop Surg*. 2010;18:180–189.
- Chung KC, Petruska EA. Treatment of unstable distal radial fractures with the volar locking plating system. *J Bone Joint Surg Am*. 2006;88:2687–2694.
- Orbay JL, Fernandez DL. Volar fixed-angle plate fixation for unstable distal radius fractures in the elderly patient. *J Hand Surg Am*. 2004;29:96–102.
- Young BT, Rayan GM. Outcome following nonoperative treatment of displaced distal radius fractures in low-demand patients older than 60 years. *J Hand Surg Am*. 2000;25:19–28.
- Grewal R, MacDermid JC. The risk of adverse outcomes in extra-articular distal radius fractures is increased with malalignment in patients of all ages but mitigated in older patients. *J Hand Surg Am*. 2007;32:962–970.
- Chung KC. A simplified approach for unstable scaphoid fracture fixation using the Acutrak screw. *Plast Reconstr Surg*. 2002;110:1697–1703.
- Kozin SH. Incidence, mechanism, and natural history of scaphoid fractures. *Hand Clin*. 2001;17:515–524.
- Kawamura K, Chung KC. Treatment of scaphoid fractures and nonunions. *J Hand Surg Am*. 2008;33:988–997.
- Sheetz KK, Bishop AT, Berger RA. The arterial blood supply of the distal radius and ulna and its potential use in vascularized pedicled bone grafts. *J Hand Surg Am*. 1995;20:902–914.
- Jones DB Jr, Moran SL, Bishop AT, Shin AY. Free-vascularized medial femoral condyle bone transfer in the treatment of scaphoid nonunions. *Plast Reconstr Surg*. 2010;125:1176–1184.
- Szabo RM. Scapholunate ligament repair with capsulodesis reinforcement. *J Hand Surg Am*. 2008;33:1645–1654.
- Garcia-Elias M, Lluch AL, Stanley JK. Three-ligament tenodesis for the treatment of scapholunate dissociation: indications and surgical technique. *J Hand Surg Am*. 2006;31:125–134.
- Wagner ER, Elhassan BT, Rizzo M. Diagnosis and treatment of chronic lunotriquetral ligament injuries. *Hand Clin*. 2015;31:477–486.
- Mirza A, Mirza JB, Shin AY, et al. Isolated lunotriquetral ligament tears treated with ulnar shortening osteotomy. *J Hand Surg Am*. 2013;38:1492–1497.
- Chung KC, Petruska EA. Treatment of unstable distal radial fractures with the volar locking plating system. Surgical technique. *J Bone Joint Surg Am*. 2007;89(suppl 2 Pt. 2):256–266.
- Sammer DM, Shah HM, Shauver MJ, Chung KC. The effect of ulnar styloid fractures on patient-rated outcomes after volar locking plating of distal radius fractures. *J Hand Surg Am*. 2009;34:1595–1602.
- Moritomo H. The distal interosseous membrane: current concepts in wrist anatomy and biomechanics. *J Hand Surg Am*. 2012;37:1501–1507.
- Ross M, Di Mascio L, Peters S, et al. Defining residual radial translation of distal radius fractures: a potential cause of distal radioulnar joint instability. *J Wrist Surg*. 2014;3:22–29.
- Higgins JP, Burger HK. Proximal scaphoid arthroplasty using the medial femoral trochlea flap. *J Wrist Surg*. 2013;2:228–233.
- Capito AE, Higgins JP. Scaphoid overstuffing: the effects of the dimensions of scaphoid reconstruction on scapholunate alignment. *J Hand Surg Am*. 2013;38:2419–2425.
- Wrist and Radius Injury Surgical Trial (WRIST) Study Group. Reflections 1 year into the 21-Center National Institutes of Health-funded WRIST study: a primer on conducting a multicenter clinical trial. *J Hand Surg Am*. 2013;38:1194–1201.

9

Flexor tendon injuries and reconstruction

Jin Bo Tang

 Access video content for this chapter online at expertconsult.com

SYNOPSIS

- Tendons transmit forces generated by muscles to move joints or to create action power. Flexor tendon injuries are common, but recovery of satisfactory function, particularly after injuries within the digital sheath, is sometimes difficult. Lacerated flexor tendons should be treated by primary surgical repair whenever possible.
- The current trend of end-to-end surgical tendon repairs is to use multistrand core sutures (four-strand repairs such as cruciate, double Tsuge, Strickland, modified Savage, or six-strand repairs such as modified Savage, Tang, or triple Kessler).
- In tendon repairs in the digital sheath area, a number of surgeons advocate that the A2 pulley can be released up to two-thirds of its length, and the A4 pulley can be entirely released when necessary and tendon repair is in the proximity of the pulley, given the integrity of the other pulleys. The release may reduce the resistance to tendon motion and the chance of repair ruptures. This technique is somewhat controversial.
- Postoperatively, early tendon mobilization should always be employed, except in children or in some rare instances; motion protocols vary greatly among different treatment centers.
- Repair rupture, adhesion formation, and joint stiffness are major complications of primary surgery.
- Combined use of multistrand core repairs, release of constricting pulley parts, and well-designed postoperative combined passive and active motion protocols – that do not overload, but sufficiently move the tendon – can help minimize adhesions, avoid repair ruptures, and restore optimal function. Full extension and flexion of the operated digit should be tested right after repair, ideally in a wide-awake setting, to ascertain no gapping of the repair and smooth tendon gliding.
- Secondary surgeries include tenolysis, free tendon grafting, and staged tendon reconstruction. Tenolysis is indicated when restricting adhesions hamper tendon gliding and soft tissues and joint conditions of the hand are favorable. Free tendon grafting is a salvage operation for failed primary repairs, delayed treatment (>1 month) of an acute cut, or lengthy tendon defects. Staged reconstruction is indicated in case of extensive scar formation or multiple failed surgeries. Preservation or reconstruction of major annular pulleys is vital to restoring function of the digits during these secondary surgeries.

- Closed rupture of flexor tendons usually requires surgical repair.
- Success of flexor tendon surgery is very expertise-dependent. A thorough mastery of anatomy and meticulous surgical technique are requirements for satisfactory restoration of function.

Introduction

Tendons are composed of dense connective tissues that transmit forces generated by muscles to move the joints or to create action power. Functionally, the hand is dependent upon the integrity and ample gliding of the tendons. Among all the tendons in the body, those in the hand are most frequently injured, due to their length and the varied nature of the activities of the hand. The pursuit of ideal repair techniques has drawn the attention of surgeons ever since hand surgery became a subspecialty. For over a century, flexor tendon repairs have presented challenges to hand surgeons.

Difficulties in restoration of function of digital flexor tendons relate chiefly to the intricate anatomy of flexor tendon systems: the coexistence of superficialis and profundus tendons within a tight fibro-osseous tunnel. Peritendinous adhesions jeopardize tendon gliding. Tendons within the synovial sheath (intrasynovial tendons) were once considered to lack self-reparative capacity; therefore, ingrowth of adhesions from peritendinous tissues was believed to be a prerequisite in the tendon healing process.¹⁻⁴ As the concepts regarding tendon healing biology evolved, tendon cells have been proven capable of proliferating and of producing collagen to heal tendons.⁵⁻¹⁰ However, the tendon is innately low in cell density and growth factor activity, limiting its early healing strength.

In the early and middle 20th century, secondary tendon grafting dominated the repair of digital flexor tendons. During this period, tendon implants were developed for staged tendon reconstruction. However, as the practice of primary repair prevailed in recent decades, the number of cases indicated for secondary tendon grafting or staged reconstruction

BOX 9.1 General tips for surgeons of flexor tendon repairs

1. Repairing flexor tendons is based on a thorough mastery of anatomy and biomechanics. The surgeon should know the anatomy in detail, including the lengths of major pulleys, characteristic changes in the diameter of the sheath, and tendon gliding amplitude.
2. Primary repairs should be performed by experienced surgeons whenever possible.
3. Mastery of atraumatic techniques is essential for the operator. The outcomes of the repairs are very expertise-dependent; repair of tendons by an inexperienced surgeon is a frequent cause of tendon adhesions and poor function, and thus should be avoided.
4. Conventional two-strand repairs are weak; stronger surgical repairs are preferable.
5. Complete closure of the tendon sheath is not necessary. Venting of a part of sheath (<2.0 cm), including a critical portion of the pulleys, provides easy access to the injured tendons, and may decrease resistance to tendon gliding after surgery; this procedure does not lead to loss of digital function when other sheath parts are intact.
6. Surgeons should emphasize strong suture techniques and decreasing compression to the tendons, which will aid in achieving improved outcomes with hand therapy.

decreased drastically. Primary repair of injured digital flexor tendons was pioneered by Verdan¹¹ and Kleinert *et al.*¹² in the 1960s and is the essential approach underlying current practice. Current primary repair and early tendon motion are based on the recognition of intrinsic healing capacity of the tendon in the 1970s and 1980s by Lundborg, Manske *et al.*, and Gelberman *et al.*^{5–10}

Nevertheless, despite the widespread use of primary repairs, surgical outcomes remained unpredictable, and sometimes even disappointing. In the last two to three decades, major efforts were thus devoted to tackling this problem, with the goal of achieving consistently optimal outcomes and minimizing repair ruptures and adhesions. In this regard, a number of multistrand core surgical repairs – such as Savage, Strickland, cruciate, Lim–Tsai, or Tang techniques^{13–19} – have been developed to replace weaker, conventional two-strand repairs. Subdivisions of zones 1 and 2 of digital flexor tendon systems were proposed by Moiemien and Elliot²⁰ and Tang,²¹ which offer precise nomenclature in recording the locations of tendon cuts, discussing treatments, and comparing outcomes. Surgical procedures to release critical parts of the pulleys have been advocated by Tang²² and Kwai Ben and Elliot²³ to decompress the tendon and “free” tendon motion. In the past few years, we have witnessed reports in which repair ruptures have been minimized, with recovery of excellent or good function in the majority of cases.^{19,24,25} These recent reports represent some remarkable steps towards satisfactory flexor tendon repairs and highlight the promise of predictable tendon repairs (Box 9.1).

Basic science**Anatomy**

There are 12 flexor tendons in the hand and forearm region. They include finger and thumb flexors and wrist flexors. Finger flexor tendons are the flexor digitorum superficialis (FDS) and the flexor digitorum profundus (FDP), and the tendon in the thumb is the flexor pollicis longus (FPL). They originate from muscles at about the mid forearm. The tendons of the FDP, except the index finger, come from a common muscle belly. The tendons of the FDS originate from the separate muscle bellies, which allow more independent finger flexion. The FPL tendon arises from the volar aspect of the midportion of the radial shaft and from its adjacent interosseous membrane. Three wrist flexors are flexor carpi radialis (FCR) and ulnaris (FCU), and palmaris longus. Palmaris longus is absent in about 15–20% of the normal population. Wrist flexion power is not affected by absence of this muscle.

Within the carpal tunnel, nine tendons exist – four FDS, four FDP, and one FPL. The relationship of these tendons within the carpal tunnel is fairly constant. The FDS tendons to the ring and middle fingers lie superficially, deeper are the FDS tendons to the index and small fingers, and deeper still are the FDP tendons. The FPL tendon is located deep and radially adjacent to the scaphoid and the trapezium. After emerging from the carpal tunnel, the tendons enter the palm. At about the level of the superficial palmar artery arch, the lumbrical tendons originate from the FDP tendons.

The most intricate portions of the flexor tendons are within the fingers, where the tendons glide within a closed fibro-osseous sheath with segmental, semirigid, constrictive dense connective tissue bands present. The digital sheath forms a closed synovial compartment extending from the distal palm to the middle of the distal phalanx. Proximally, the synovial sheath ends just proximal to the neck of the metacarpus, forming the proximal reflection of the digital flexor sheath. The FDS tendons lie superficial to the FDP tendons up to the bifurcation of the FDS tendon at the midportion of the proximal phalanx. Then, FDS tendons become two slips coursing laterally and then deeper to the FDP tendons. This FDS bifurcation is in the A2 pulley area. This part of the FDS tendon also serves to constrain the FDP tendon; the FDS segment at bifurcation may be viewed as a structure functioning similarly to a pulley. Deep to the FDP tendon, the FDS slips rejoin to form Camper's chiasm (a fibrous interweaved connection between two FDS slips), and distally insert on the proximal and middle parts of the middle phalanx as two separate slips. The FDP tendon inserts into the volar aspect of the distal phalanx. The FPL tendon is the only tendon inside the flexor sheath of the thumb and inserts at the distal phalanx.

The digital flexor sheath consists of synovial sheath and interwoven condensed fibrous bands (“pulleys”). Synovial sheath is a thin layer of continuous smooth paratenon covering the inner surface of the fibrous sheath, providing a smooth surface for tendon gliding and nutrition to the tendons. The pulley system of the digital flexor tendon is unique; it consists of annular pulleys (condensed, rigid, and heavier annular bands) and cruciate pulleys (filmy cruciform bands) (Fig. 9.1).¹⁵¹ There are five annular pulleys (A1–A5), three cruciate pulleys (C1–C3), and one palmar aponeurosis



Access the Historical Perspective section online at

<http://www.expertconsult.com>

Historical perspective

Documentation and treatment of tendon injuries dates back to antiquity. Hippocrates and other ancient physicians observed a white slender tubular structure entering skeletal muscle, and considered it as a nerve. Galen, who lived in the Roman Empire in the second century, advised physicians not to repair tendons because it was believed to result in pain, twitching, and convulsions of the limb. Over the following 15 centuries, surgeons were largely influenced by the teaching of Galen. The seminal challenge to Galen's assertion did not occur until the mid-eighteenth century when Von Haller showed that the placement of a suture in canine Achilles tendons did not have detrimental effects.²⁶

The first experimental investigation of the tendon healing process was performed in 1767 by John Hunter, who recorded that the canine Achilles tendon healed by the formation of callus, similar to that seen in healing bone.^{26,27} However, specific studies of the flexor tendon healing within digital sheath were not started until about 150 years later, in the early twentieth century. Around 1920, Bier and Saloman observed poor tendon healing of sutured canine flexor tendons.²⁸ Saloman thus advocated to leave a defect in the tendon sheath which allowed contact between the repaired tendon and the subcutaneous tissue. Bunnell and Garlock observed frequent occurrence of restrictive adhesions at the flexor tendon laceration site.²⁹⁻³² Bunnell coined the term "no man's land" to describe the region where the flexor tendons passed through the digital sheath and advised surgeons to be cautious when repairing tendons within this region. In 1940, Mason advised some specific conditions for repairing lacerated digital flexor tendons, which included never repairing both tendons, wide excision of the overlying sheath, and adequately eliminating contaminants from the wound.³³ Because of the generally unsatisfactory results of primary flexor tendon repairs, many surgeons preferred tendon grafting, despite the fact that a few surgeons had demonstrated that primary surgeries were practicable at that time.

In the early half of the 20th century, repairing the lacerated tendons within the digital sheath was predominantly by means of secondary tendon grafting. The first series of flexor tendon grafts in the hand was reported by Lexer in 1912.³⁴ He used grafts to repair flexor tendons after rupture, old lacerations, infections and cases with ischemic contracture. In 1916, Mayer published articles that have served as the basis of the present day concepts of free tendon grafting.³⁵⁻³⁷ He emphasized the need for existing surgical techniques, direct juncture of the tendon to bone, the use of adequate muscle as a motor, and preserving peritenon around a graft to lessen adhesions. In 1918, Bunnell published a classic article on tendon grafting in which atraumatic technique, a bloodless field, perfect asepsis, and preservation of pulleys were emphasized.³⁰ The surgical techniques of tendon grafting were subsequently modified by various leaders in the field, including Pulvertaft, Graham, Littler, Boyes and Stark.³⁸⁻⁴²

In an effort to combat serious scarring in the tendon gliding bed in which conventional one-stage free tendon graft likely failed to restore tendon function, various materials have been implanted into the fingers to stimulate formation of a smoother tendon gliding bed. In 1936, Mayer inserted a celloidin tube into seriously scarred tendon gliding bed, and after 4 to 6

weeks of implantation he then introduced a tendon graft.⁴³ Mayer brought forth the pseudosheath concept. In the 1950s, Bassett and Carroll began working with flexible silicone rubber rods to build pseudosheaths in badly scarred fingers, adding passive motion into this procedure.⁴⁴ This method was later refined into a two-stage tendon reconstruction by Hunter *et al.* in the 1960s.⁴⁵ Hunter *et al.* also developed the active tendon implant.⁴⁶ These implants and two-stage reconstruction procedures are still used currently, effective for those patients with badly scarred digits and serving as a salvage procedure after other surgery attempts failed.

It was not until the 1960s that reports of surgical techniques and outcomes of primary repair from Verdan,¹¹ and Kleinert *et al.*¹² became the turning point in establishing the practice of primary repair of digital flexor tendons. The emerging popularity of primary tendon repair stimulated experimental studies to elucidate mechanisms of the healing process. In the 1970s and 1980s, Manske *et al.* demonstrated diffusion of nutrients through synovial fluid to be an effective source of nutrition of intrasynovial tendon, thus obviating the need of vascularization in the healing process.⁴⁷⁻⁵⁰ Matthews and Richards observed healing of lacerated rabbit flexor tendons within the intact digital sheath in the absence of adhesions.^{5,51-54} Lindsay *et al.* noted that both epitenon and endotenon cells proliferate and migrate to the laceration site, subsequently bridging it.^{5,55-57} Lundborg *et al.* demonstrated healing of lacerated flexor tendon segments when placed within the synovial environment of the knee joint or in a synthetic membrane pouch placed in a subcutaneous pocket of the back of the rabbit.^{6,7} In the 1980s, Manske, Lesker, Gelberman, and Mass *et al.* demonstrated healing of lacerated flexor tendon segments of different animals when placed in tissue culture in the complete absence of extrinsic cells.^{9,10,58-61}

In the last three decades, major advancements in the field of flexor tendon repairs were made with respect to the development of novel surgical repair techniques, accumulation of biomechanical information regarding tendon repairs or gliding mechanisms, modifications of postsurgical rehabilitation methods, and an emerging trend of exploring biological approaches to enhance tendon healing. In 1985, Savage¹³ published an influential experimental study that later stimulated a widespread interest in developing multistrand suture techniques to repair the tendon.⁶²⁻⁷⁴ The cruciate repair, a simple yet strong four-strand repair developed by McLaren *et al.*¹⁶ in the late 1990s, is used in many hand centers. In the same period, multistrand repair using Tsuge's looped suture lines, as developed by Lim and Tsai, Tang (and its modification, M-Tang method),^{17-19,68} were used by surgeons in hand centers in Asia, Europe, and North America. In 1995 and 1998, Tang²² and Elliot²³ presented an anatomical study and clinical results of the release of a major flexor pulley (A2) to accommodate gliding of the repaired tendons, respectively. Elliot and Tang also proposed to vent the A4 pulley when the tendon repairs are in the areas.^{19,23}

The flexor tendons were divided into five zones by Verdan in the 1960s. In the 1990s, subdivisions of zone 1 by Moiemmen and Elliot²⁰ and zone 2 by Tang²¹ were added into the existing zoning system, in order to describe the location of injuries and repairs more specifically. These zoning and sub-zoning systems provide hand surgeons with the nomenclature to document the tendon injuries and outcomes, and discuss the principles of treatment.

In the past 30 years, biomechanics of the flexor tendon system has become a subject of intense interest for both surgeons and basic scientists. A large volume of information regarding tendon gliding and repair biomechanics has been obtained,^{74–122} including surgical repair techniques (mainly from labs of Gelberman, Manske, Mass, McGrouther, Tang, Trumble, and Wolfe), gliding resistance of tendons within the sheath or against annular pulleys (Amadio and Tang), mechanics of the pulleys (Amadio, Mass, and Tang), postsurgical rehabilitation (Amadio and Boyer), and edema formation (Tang). In recent years, as advocated by Lalonde,^{123,124} flexor tendon repair and tenolysis are popularly performed in some centers around the globe under wide-awake settings (without tourniquet) with local anesthesia plus epinephrine. This approach allows the tendon to move actively during surgery to ascertain good quality of tendon repair or tenolysis.

In the past two decades, investigations exploring molecular events in the tendon healing process, tendon tissue engineering, and biological approaches to enhance the healing came into the center stage of basic science investigations. Chang *et al.* reported a series of investigations exploring function of growth factors in tendon healing, molecular methods to prevent adhesions, and tendon tissue engineering.^{125–135} Tang and colleagues performed a series of studies of molecular events in tendon healing and gene therapy approaches to enhance the strength or to limit adhesions.^{136–145}

Comprehensive history and development of flexor tendon repairs were covered in more detail in the reviews written by Verdan (1972),¹⁴⁶ Manske (1989),¹⁴⁷ Strickland (1995),¹⁴⁸ Elliot (2003),¹⁴⁹ Manske (2005),²⁶ and Tang (2007)¹⁹ and Tang *et al* (2014).¹⁵⁰




Fig. 9.1 Annular pulleys (condensed, rigid, and heavier annular bands) and cruciate pulleys (filmy cruciform bands) are present in the fingers. There are five annular pulleys (A1–A5), three cruciate pulleys (C1–C3), and one palmar aponeurosis (PA) pulley.

pulley.^{151,152} The A1, A3, and A5 pulleys originate from the palmar plates of the metacarpophalangeal (MCP), proximal interphalangeal (PIP) and distal interphalangeal (DIP) joints, and the A2 and A4 pulleys originate from the middle portion of the proximal and middle phalanges, respectively. The broadest annular pulley is the A2 pulley, which covers the proximal two-thirds of the proximal phalanx and encompasses the bifurcation of the FDS tendon at its middle part. The A4 pulley is located at the middle third of the middle phalanx. The A2 and A4 pulleys are the largest among five annular pulleys and have the most important function. The annular pulleys maintain the anatomical paths of tendons close to bones and phalangeal joints, thus optimizing the mechanical efficiency of digital flexion. The more compressible cruciate pulleys allow for digital flexion to occur with condensation of the fibro-osseous sheath at the inner part of flexed fingers. This is called the “concertina effect”.

The length of the A2 pulley is about 1.5–1.7 cm in the middle finger of an average adult, and the length of the A4 pulley is about 0.5–0.7 cm. The diameter of the flexor sheath is at its narrowest at the level of the A4 pulley and in the

middle and distal parts of the A2 pulley. The A2 and A4 pulleys are easily recognizable, because both are remarkably denser and more rigid than their adjacent flexor sheath. The A1 pulley, with a length of about 1.0 cm, is located proximal to the A2 pulley; in some instances, both A1 and A2 pulleys merge to form an especially lengthy pulley complex. The A3 pulley is located palmar to the PIP joint, but it is very short (0.3 cm) and may be difficult to distinguish from the synovial sheath.

In the thumb, there are three pulleys (A1, oblique, and A2) with no cruciate pulleys (Fig. 9.2). The A1 and oblique pulleys are functionally important. The A1 pulley, 0.7–0.9 cm long, is located palmar to the MCP joint. The oblique pulley, 0.9–1.1 cm long, spans the middle and distal parts of the proximal phalanx. The A2 pulley is near the site of insertion of the FPL tendon, which is thin and 0.8–1.0 cm long.

The FDP tendon has two vincula: a fan-like short vinculum and a cord-like long vinculum. The short vinculum is located at the insertion of the FDP tendon (Fig. 9.3). The long vinculum connects the FDP tendon through the short vinculum of the FDS tendon to the floor of the palmar surface of the phalanges. The FDS tendon also has two vincula; one connecting to the proximal phalanx, and another at the insertion of the FDS tendon. Vincula carry blood vessels to the dorsum of these tendons, providing limited nutrition. Tendon insertion sites to bones also carry vessels into tendons over a very short distance.

According to anatomical features, the flexor tendons in the hand and forearm are divided into five zones, which offers




Fig. 9.2 Locations of flexor pulleys of the thumb. There are three pulleys in the thumb: A1, oblique, and A2 pulley, from distal to proximal.





Fig. 9.3 Insertions and relative positions of the flexor digitorum superficialis (FDS) and flexor digitorum profundus (FDP) tendons and vincula. Each of the FDS and FDP tendon has two vincula, one short and one long. The relation of the FDS and FDP tendons are complex in the middle part of the proximal phalanx under the A2 pulley (zone 2C).

the fundamental nomenclature for flexor tendon anatomy and surgical repairs.¹⁵³ In the 1990s, the most complex areas – flexor tendons in the digital sheath – were subdivided by Moiemmen and Elliot,²⁰ and by Tang.²¹ The zoning is described below, and its relation to the locations of pulleys is shown in Figs. 9.4 and 9.5:

- Zone 1: from the insertion of the FDS tendon to the terminal insertion of the FDP tendon
- Zone 2: from the proximal reflection of the digital synovial sheath to the FDS insertion
- Zone 3: from the distal margin of the transverse carpal ligament to the digital synovial sheath




Fig. 9.4 Divisions of the flexor tendons into five zones according to anatomical structures of the flexor tendons, presence of the synovial sheath, and the transverse carpal ligament.

- Zone 4: Area covered by the transverse carpal ligament
- Zone 5: Proximal to the transverse carpal ligament

In the thumb, zone 1 is distal to the interphalangeal (IP) joint, zone 2 is from the IP joint to the A1 pulley, and zone 3 is the area of the thenar eminence.

The subdivisions of zone 1 by Moiemmen and Elliot are:

- 1A: the very distal FDP tendon (usually <1 cm)
- 1B: from zone 1A to distal margin of the A4 pulley
- 1C: the FDP tendon within the A4 pulley

The subdivisions of zone 2 by Tang are:

- 2A: the area of the FDS tendon insertion
- 2B: from the proximal margin of the FDS insertion to the distal margin of the A2 pulley
- 2C: the area covered by the A2 pulley




Fig. 9.5 Subdivisions of zones 1 and 2 of flexor tendons in the fingers and their relations to the flexor pulleys.

- 2D: from the proximal margin of the A2 pulley to the proximal reflection of the digital sheath

Flexor tendon healing

Flexor tendons derive nutrition from both synovial and vascular sources. Flexor tendons outside the synovial sheath are supplied with a segmental vascular network through the paratenon, and the vascular supply plays an important role in nutrition of these tendons. However, the tendons within the synovial sheath are mostly deprived of a vascular network. Only limited dorsal regions around vincular insertions are vascularized. A series of experiments by Manske *et al.* showed that intrasynovial flexor tendons are nourished by synovial fluid and that nutrition through vascular supplies is insignificant.^{47–50} While the general healing process of the tendon has long been recognized as having early inflammatory, middle collagen production, and late remodeling phases, the healing potential of the intrasynovial flexor tendon was a subject of intense investigations and debate over several decades in late 20th century.^{1–10,52–61}

Before the 1970s, it was widely accepted that the digital flexor tendon lacked intrinsic healing capacity.^{1–4} However, in subsequent decades, the intrinsic healing capacity of the tendon came to light in a series of elegant experimental studies. These experiments by Matthews, Lundborg, Manske, Gelberman, and Mass and others, included observation of the repair process in lacerated flexor tendons within the synovial sheath, investigation of cellular activity in the lacerated tendon within the knee joint, detection of cellular activity, and the ability to produce matrix by *in vitro* tendon cultures.^{5–10,51–61} The work led to the well-supported conclusion that cells in the intrasynovial tendon can proliferate and participate in the healing process, making the tendon itself capable of healing without forming adhesions. This became the scientific basis of early postoperative tendon mobilization.

It is now agreed that intrasynovial flexor tendons can heal through two mechanisms – intrinsic and extrinsic. Intrinsic healing takes place through the proliferation of tenocytes and production of extracellular matrix by intrinsic cells. Growth of tissues or cell seeding from outside the tendon is extrinsic healing. The tendon's intrinsic healing capacity is innately weak; extrinsic healing becomes dominant when intrinsic healing capacity is disabled (such as in the case of severe trauma to the tendon or peritendinous tissues) or under conditions (such as postsurgical immobilization) favoring extrinsic healing. Tendon healing exclusively through the intrinsic healing mechanism occurs only under a few experimental conditions.^{7–9} Clinically, the lacerated tendon heals through a combination of both intrinsic and extrinsic mechanisms, whose balance depends upon the condition of the tendon and surrounding tissues. Extrinsic healing may act on the tendon healing process through either forming adhesions or seeding of the extrinsic cells without adhesions to laceration site. On the other hand, adhesions do not necessarily consist of extrinsic cells. Tenocytes may migrate out of the laceration site for a very limited distance to become part of adhesions. Conceptually, extrinsic healing does not equal adhesion formation. However, it is extrinsic healing in the form of restrictive adhesions that hampers tendon function.

The following five variants (grades) of adhesions are seen clinically: (1) no adhesions; (2) filmy adhesions: formation of

visible, filmy, and membranous tissue from tendon to outside tissues; (3) loose adhesions: loose and largely movable; (4) moderately dense adhesions: of limited mobility; and (5) dense adhesions: dense, almost immovable, and invading deep into the tendon.

The first two grades do not affect tendon motion; the third affects motion mildly. Because the fourth and fifth affect motion dramatically, those are the adhesions that surgeons seek to prevent. The density of adhesions relates to the tissues from which they arise. The adhesions arising from bones, periosteum, or major annular pulleys are dense. The density of adhesions can be altered to some extent by tendon motion. Some adhesion fibers can be disrupted as well. Surgeons should do their utmost to preclude or minimize the formation of adhesions that will restrict tendon gliding.

Many strategies have been attempted or suggested to prevent adhesion formations, including medications, use of artificial or biological barriers, and chemical or molecular approaches, with varied results. However, few medications or barriers have become clinically routine. So far, the most effective methods to prevent adhesions in clinic are meticulous surgery and early postoperative motion; the prime cause of adhesions is tendon repair by inexperienced surgeons.

Biomechanics of tendon repairs and gliding

Forces generated during normal hand action range from 1 to 35N, except tip pinch, according to *in vivo* measurements.¹⁵⁴ Therefore, a surgically repaired tendon should be able to withstand a tension of at least 40N during motion, with power sufficient to resist gap formation. The repair should be able to withstand cyclic loads under both linear and curvilinear load conditions. Laboratory tests have shown that conventional two-strand core repairs plus running peripheral sutures yield a maximal strength from 20 to 30N;⁹³ this is lower than forces generated during normal hand actions and explains why some repairs are disrupted during postoperative motion exercise. Studies showed that failure forces of four-strand repairs are around or beyond 40N;^{16,65,94} six-strand repairs fail with loads over 50–60N.^{13,71,85}

Many factors affect the strength of a surgical repair (Fig. 9.6): (1) the number of suture strands across the repair sites – strength is roughly proportional to the number of core sutures;^{74–76,81–83,85,94–97} (2) the tension of repairs – most relevant to gap formation and stiffness of repairs;^{19,98} (3) the core suture purchase;^{84,86,88,94} (4) the types of tendon–suture junction – locking or grasping;^{79,88,95,97} (5) the diameter of suture locks in the tendons – a small-diameter lock diminishes anchor power;^{80,91} (6) the suture calibers (diameter);^{82,116,117} (7) the material properties of suture materials;^{95,155} (8) the peripheral sutures;^{156,157} (9) the curvature of tendon gliding paths – the repair strength decreases as tendon curvature increases;^{89,90} and (10) above all, the holding capacity of a tendon, affected by varying degrees of trauma and post-traumatic tissue softening, plays a vital role in repair strength.

To achieve an optimal surgical repair, the above-outlined factors must be considered and incorporated into repair design. A core suture purchase of at least 0.7 to 1.0 cm is necessary to generate maximal holding power, as recommended by Tang *et al.*^{86,93} and Cao *et al.*⁹⁴ Slight tension in the core sutures is necessary to resist gapping at the repair site.⁹⁸ A locking tendon–suture junction is generally better than a grasping

Factors affecting surgical repair strength




Fig. 9.6 Factors affecting the surgical repair strength of the tendon.

junction in terms of holding power. Diameter of the suture locks must reach or exceed 2 mm, according to Xie *et al.*⁹¹ Tan and Tang recommend a greater core suture purchase (>1.2 cm) and locking repairs for an obliquely cut tendon.^{86–88} Barrie *et al.*¹¹⁶ and Taras *et al.*¹¹⁷ greatly improved repair strength by increasing suture calibers. Clinically, the caliber of suture used in adults is either 3-0 or 4-0; sutures of 2-0 or greater are too large and rigid in the hand.

Tendon–suture junctions in surgical repairs are either grasping or locking; locking junctions vary greatly (Fig. 9.7). Grasping repairs are generally weaker than locking repairs. Among locking junctions, cross-locks provide identical strength to circle-locks.⁹⁴ Exposed and embedded cross-locks create the same strength.⁹² With an identical number of suture strands across the tendon, different locking junctions result in minor differences in the strength. Nevertheless, repairs with cross- or circle-locks appear slightly stronger than

Kessler-type repairs with Pennington locks. Pennington locks provide a looser junction than cross- or circle-locks.

Peripheral sutures serve to “tidy up” the approximated tendon stumps; they may add strength to repairs as well. Deep-bite peripheral sutures increase repair strength.¹⁵⁶ Increases in suture purchase or complex peripheral sutures, as typified by the Silfverskiöld method,⁶⁴ increase overall strength. However, most surgeons choose to insert only simple peripheral stitches. Some surgeons even do not supplement peripheral stitches when multistrand core sutures have been used.²⁵ In the presence of a strong multistrand core repair, peripheral sutures contribute little in terms of strength. In fact, to simplify repair maneuvers, multistrand core sutures (with or without a few peripheral sutures) may be sufficient.

In addition to surgical factors, tendon curvature affects strength as well. Surgical repair in a tendon under a curvilinear load is weaker than that under a linear load; the repair strength decreases as the curvature increases.^{89,90} Mechanically, a tendon under linear tension is pulled without being bent, whereas a tendon under curvilinear tension is subjected to both linear pulling and bending forces. Therefore, the repair fails more easily in the flexed finger under curvilinear loads. When the finger moves to approach full flexion, a strongly bent tendon is particularly prone to fail (Fig. 9.8).

Annular pulleys are critical to the function of the digital flexor tendons. The pulleys keep the tendons’ course close to the phalanges for optimal mechanical efficiency of tendon excursion. Lengthy loss of the sheath and pulleys causes anterior displacement – bowstringing – of the flexor tendon during finger flexion. In fingers, the A2 and A4 pulleys are most critically located and functionally important. Preservation or reconstruction of the two pulleys is necessary in the absence of other pulleys or sheath. Nevertheless, given the presence of other pulleys and sheath, loss of any individual pulleys – including the A2 or A4 pulley – appears to result in few detrimental consequences. Both Tang²² and Tomiano *et al.*^{111,112} showed that incision of the A2 pulley up to one-half or two-thirds of its length or of the entire A4 pulley results in no tendon bowstringing and little loss of digital flexion. In *in vivo* settings, incision of the A2 pulley decreases resistance to




Fig. 9.7 Different tendon–suture junctions in tendon repairs: locking and grasping junctions




Fig. 9.8 The forces acting on the tendon are different when the tendon is subjected to linear pulling (A) or a curvilinear tension (B,C). (A) The tendon subjected to linear pulling is loaded by only a linear pulling force. (B,C) The tendon subjected to a curvilinear tension is loaded by both linear and bending forces. The repaired tendon fails more easily while being linearly pulled and bent. From (B) to (C), as the curvature of the gliding path increases, the bending force on the tendon is increased ($F_2 > F_1$). Under greater gliding curvature, the tendon fails with a smaller linear pulling force. From (B) to (C), as the finger flexes progressively, the tendon fails with an increasingly smaller linear tension. (C) The tendon is particularly prone to fail when the finger approaches full flexion. The tendon is easier to disrupt in (C) when gliding over joints (1' and 2') with greater curvature than in (B) with smaller curvature.

tendon motion and lessens the chance of repair failure.^{109,110} Loss of the A3 pulley alone has few consequences as well, but a lengthy sheath cut adjacent to the A3 pulley, containing the C1 or C2, causes tendon bowstringing.¹⁰⁷ Therefore, significant loss of sheath should be avoided to maintain tendon function; however, loss of a small portion (<2 cm in length) of the sheath–pulley, even including a part of the most critically located A2 pulley, has no substantial mechanical consequence.

Flexor tendons in the digits glide in a fairly resistance-free synovial environment. Resistance to tendon motion is increased when the tendons are injured and repaired. The following create resistance to tendon gliding: (1) rough tendon gliding surface; (2) biological reactions of the wound, e.g., subcutaneous and tendon edema; (3) friction caused by

exposure of suture materials; (4) increases in tendon bulkiness due to placement of sutures; (5) tight closure of sheath or pulleys that narrows the tendon gliding tunnel; (6) tendon-catching at pulley or sheath edges; (7) postsurgical extensor tethering and joint stiffness that burden the movement of the flexor tendon; and (8) adhesions that restrict tendon gliding.

Following trauma and surgery, tendons undergo inflammation, healing, and edema. The volume of the tendons is increased, which increases the resistance within the narrow sheath tunnel. Subcutaneous edema outside the sheath also impedes tendon motion. These factors affecting the resistance to tendon gliding should be considered in deciding how rigorous the postoperative motion program should be. The safety margin can be enhanced by a strong surgical tendon repair or appropriately decompressing the tendon to avoid repair ruptures.

Biological healing strength is a central issue underlying all tendon repairs. Urbaniak *et al.*,⁷⁶ Aoki *et al.*,⁷⁷ Kubota *et al.*⁷⁸ and Boyer *et al.*¹¹⁴ have characterized the strengths of the healing flexor tendon using animal models. They found that strength either remained consistent or actually decreased somewhat over the initial few weeks after surgery.^{76–78} Decreases in strength, typically those in the second postsurgical week, are thought to be caused by softening of the tendon stumps, which lower the suture's holding power. Our investigations using a chicken model indicated that the strength of a healing tendon is steady during the initial 4 weeks, followed by a substantial increase (greater than threefold) in the fifth and sixth weeks; thereafter, the tendon heals strongly and is difficult to disrupt. The fifth and sixth weeks after surgery appear very crucial to regaining strength. Accelerating the healing, aiming to move this critical “strength gain” period to earlier weeks, is a current focus of research into molecular modulation of tendon healing.

Diagnosis

Flexor tendon injuries are open in most cases, resulting from a sharp cut or a crush, but they can also present as closed injuries. Open injuries due to extensive trauma are frequently associated with neurovascular deficits. Closed injuries often relate to forced extension during active flexion of the finger. Flexor tendon rupture can also occur as a result of chronic attrition in rheumatoid disease, Kienböck disease, scaphoid nonunion, a hamate or a distal radius fracture.

Careful attention to the patient's history and the mechanism of injury can alert the surgeon to the extent of the tendon trauma and associated injuries. The natural resting posture of the wounded digits is important for evaluation. Complete lacerations of both FDP and FDS tendons are easily diagnosed when the affected fingers are seen in a relatively extended position with loss of active finger flexion at PIP and DIP joints. If the patient can actively flex the DIP joint while the motion of the PIP joint is blocked, no injuries or only partial injuries to the FDP tendon can be diagnosed (Fig. 9.9). To assess the continuity of the FDS tendon, the adjacent fingers are held in full extension by the examiner. If the patient cannot actively flex the PIP joint, the FDS tendon is severed completely (Fig. 9.10). Variations of the FDS tendons in the little finger are frequent. The FDS in 30–35% of the little fingers has a connection with the FDS in the ring or middle fingers. Some little



Fig. 9.9 Examination of flexor digitorum profundus (FDP) tendon continuity and function. When the proximal interphalangeal joint flexion is blocked, flexion of the distal interphalangeal joint indicates continuity and function of the FDP tendon.




Fig. 9.10 Examination of flexor digitorum superficialis (FDS) tendon continuity and function. If the patient is unable to flex the proximal interphalangeal joint of the examined finger while flexion of the other fingers is blocked, this indicates loss of function of the FDS tendon. Complete flexion of the proximal interphalangeal joint indicates function and continuity of the FDS tendon.

fingers (10–15%) are missing an FDS tendon. These patients have limited or no PIP flexion of the little finger during testing. Weakness during resisted finger flexion indicates a possible partial tendon cut. To test the FPL tendon, the thumb MCP joint is stabilized in neutral position. The patient is asked to flex the IP joint. Loss of active flexion at the joint indicates complete severance of the FPL tendon.

Nerve and vascular function should be assessed routinely, because accompanying injuries in the neurovascular bundles in one or both sides of the fingers or median and ulnar nerves at carpal tunnel or distal forearm are common. Loss of sensation in the finger pulps or loss of function of some intrinsic muscles in the hand are indicative of such accompanying injuries; treatment of neurovascular injuries must be included when planning surgical strategies. If fingers or hands are found to be hypovascular or avascular due to vascular lacerations, vascular anastomosis should be a surgical emergency. Otherwise, after wound debridement, either the lacerated flexor tendons can be repaired (when experienced surgeons are readily available) or the skin can be closed to allow for delayed primary repairs within days by experienced surgeons.

Radiographs should always be taken. Associated fractures are not infrequent and require treatment. Computed tomography (CT) scan or magnetic resonance imaging (MRI) are usually not necessary to diagnose open tendon injuries. However, for diagnosis of closed tendon ruptures or suspected ruptures of the primary end-to-end surgical repair, these tools are of particular value. MRI should be utilized if there is a suspicion of closed tendon rupture. Ultrasonographic examination may also reveal rupture of the tendons.

Treatment/surgical techniques

Primary and delayed primary repairs

Whenever possible, acutely lacerated flexor tendons in the hand and forearm should be treated primarily or at the delayed primary stage. Primary tendon repair is the end-to-end repair performed immediately after wound cleaning and debridement, usually within 24 hours after trauma. Delayed primary repair is defined as the repair performed within 3 or even 4 weeks after tendon lacerations. No clinical investigations actually validated the best time for primary repair. The ideal situation is that of a patient with digital flexor tendon lacerations brought into the clinic soon after injury; surgery begins within a few hours, and an experienced surgeon is readily available. The tendon injured in critical areas (such as zone 2) should not be repaired by an inexperienced surgeon. Rather, the tendon repair can be delayed until an experienced surgeon is available. My preferred period of deliberate delay is 4–7 days, when the risk of infection can be properly addressed and edema has reduced substantially. Delay of the repair beyond 3–4 weeks may cause myostatic shortening of the muscle–tendon unit; for these late cases, lengthening the tendon within the muscles in the forearm can ease the tension (Fig. 9.11).

Rupture of the repaired flexor tendons after surgery can be re-repaired if the rupture occurs within a few weeks up to a month after surgery; secondary tendon grafts may be the only choice for ruptured cases in the presence of obvious retraction




Fig. 9.11 A decision-making flow chart of primary and delayed primary flexor tendon repairs.

of the tendon end or extensive scarring in the intact FDS tendon when the FDP tendon ruptures.

Indications and contraindications

Primary or delayed primary end-to-end tendon repairs are indicated mainly in clean-cut tendon injuries with limited damage to peritendinous tissues. Neurovascular injury is not a contraindication for primary repairs. Loss of soft-tissue coverage over the tendon and the presence of fractures are borderline indications. Local defects in skin and subcutaneous tissues can be covered by flap transfer. A simple fracture limited to the phalangeal or metacarpal shaft can be securely fixed with screws, wires, or intramedullarily placed headless screws, and then tendons can be repaired. However, serious crush injuries, severe wound contamination, loss of extensive soft tissues, or extensive destruction of pulleys and tendon structures are contraindications for primary tendon repairs. Severe injuries to multiple joint components and fractures involving bones at different levels or not yielding stable internal fixation are contraindications for primary tendon repairs (Box 9.2).

Anesthesia

Brachial plexus block is usually sufficient; general anesthesia can also be used when associated injuries are severe. A tourniquet is placed on the upper arm. Nevertheless, local anesthesia without tourniquet with the patient being wide awake during entire surgery can be more beneficial, called “wide-awake” flexor tendon repair as advocated by Lalonde.^{123,124} This approach allows the patient to actively flex and extend the operated digits, enabling the surgeons to confirm that the motion is smooth, does not lead to gapping in the repair site, and the repair strength is sufficient for early active motion on the operating table. The anesthetic mixture of 1% lidocaine with 1:100,000 epinephrine is given in the surgical waiting room 20 to 30 minutes before making surgical incisions (Box 9.3). Epinephrine acts to stop bleeding from capillaries and produces maximal capillary constriction about 25 minutes after infiltration to the surgical field.

BOX 9.2 Primary flexor tendon repairs

Indications

1. Clean-cut tendon injuries
2. Tendon cut with limited peritendinous damage, no defects in soft-tissue coverage
3. Regional loss of soft-tissue coverage or fractures of phalangeal shafts are borderline indications
4. Within several days or at most 3 or 4 weeks after tendon laceration

Contraindications

1. Severe wound contamination
2. Bony injuries involving multiple joint components or extensive soft-tissue loss
3. Destruction of a series of annular pulleys and lengthy tendon defects
4. Experienced surgeons are not available

Surgical techniques

The hand and arm are scrubbed and draped. The wounds should be thoroughly debrided, devitalized tissues excised, and the wounds washed with antibiotic solution. Position of the fingers or hand is determined by levels of cuts in the tendons in relation to their superficial tissues. The hand is usually held by an assistant, so that it can be adjusted during surgery. Loupe magnification is advised for surgery. The tendons are exposed through zigzag skin incisions on the volar side of the fingers, e.g., Bruner’s incision, or a lateral incision. When the wounds are in the palm or forearm, incision by extending the opening of wounds is often necessary (Fig. 9.12).

BOX 9.3 How to perform local anesthesia for a wide-awake repair

1. Primary or delayed primary repair of the flexor tendons can be performed under local anesthesia, without tourniquet, while the patient is wide awake during entire operation.
2. For the repair in zones 1–3, the method of local anesthesia is to inject 1% lidocaine premixed with 1:100,000 epinephrine. The surgeon should prepare 10 ml of such an anesthetic for each finger with tendon repair. The local anesthetic is injected 20–30 min before beginning the surgical repair.
3. For zone 1 and 2 injuries, the point of first injection is at the midpalm level, just proximal to the MCP joint; a total of 5 ml of anesthetic is injected. The needle should be perpendicular to the skin to minimize pain, and injection is into the subcutaneous tissue.
4. After waiting 5–10 minutes, the second injection (2 ml) is given to the middle part of the proximal phalanx at the volar midline. Immediately after that, the third and fourth injections (2 ml and 1 ml, respectively) are administered to the middle parts of the middle and distal phalanx along the palmar midline.
5. 15 minutes after completing the above four injections, surgery can begin.
6. For repair in the forearm (zone 5), 20–50 ml of 1% lidocaine with 1:200,000 epinephrine is injected to the multiple sites where surgical incisions will be made 15 minutes before surgery.




Fig. 9.12 Skin incisions utilized to approach the tendons in the digits and palm.

Zone 1 injuries

In this area, only the FDP tendon is located. When the tendon laceration is in the distal part of this zone (zone 1A and 1B), because the vincula connects to the proximal tendon to prevent retraction, both the proximal and distal ends can be easily found not far from the skin wound in many cases. When cut in zone 1C and some distal tendon cuts, the tendon may retract more proximally. Often it is necessary to make an incision to find the retracted proximal stump. Using a forceps the surgeon can feed the proximal tendon forward from the incision in the palm, bit by bit, to the distal incision in the finger (Fig. 9.13). This maneuver does not traumatize the sheath tunnel or the end of the proximal tendon. Then, a 25-gauge needle is inserted at the base or middle of the finger through the proximal tendon to hold the tendon temporarily.

For zone 1A injuries, the distal stump is very short. The proximal tendon end can be sutured with Bunnell or modified Becker suture with 3-0 polypropylene, and an osteoperiosteal flap is raised at the base of the distal phalanx (Fig. 9.14). The suture is led through an oblique drill-hole, brought out through the nail, and tied over a button above the nail. To avoid passing the suture through the nail, the proximal tendons can be sutured to a fish-mouth opening in the distal tendon stump using reinforced suture repairs or mini-anchors (see Fig. 9.14).^{157,158} Another method is to drill a transverse hole through the distal phalanx. After the tendon stump is




Fig. 9.13 A separate incision in the distal palm is often necessary to find retracted flexor digitorum profundus tendon and advance it distally. (A) An incision in the distal palm to find the proximal stump. (B) Feeding the retracted proximal tendon forward to the surgical field in zone 1 bit by bit using forceps without traumatizing the tendon stump, which the author often uses. (C) A needle was inserted transversely through the sheath and proximal tendon to temporarily fix the proximal tendon to ease tension during repair.




Fig. 9.14 Methods of making a tendon-to-bone junction in zone 1. **(A)** A conventional method to anchor the flexor digitorum profundus (FDP) tendon to the bone by pull-out sutures through the nail and tied over a button. Alternative ways to anchor the distal tendon stump to the bone by: **(B)** directly suturing the stump to residual FDP tendon; **(C)** looping the tendon through the bone; **(D)** pull-out suture over the fingertip; **(E)** mini-anchors; **(F)** looping the sutures through a transverse hole in the bone; and **(G)** a set of 10 or more strands of robust repairs from the proximal stump to the distal stump, nearby periosteum, and distal insertion site of the volar plate of the distal interphalangeal joint.




Fig. 9.15 A tendon-to-bone junction made through splitting the short distal stump and reinforced suture repair to the proximal stump or a graft using a 4-0 suture.

sutured, the suture is led through the hole and tied to the other end, through an open approach or percutaneously.¹⁵⁹

Other methods include: (1) reinforced suture repair of the proximal FDP tendon stump to the distal stump with 4-0 or 3-0 sutures, after the distal stump is split along the midline and the proximal stump is placed between the two slips of the split distal stump;¹⁶⁰ and (2) an extremely robust end-to-end repair, with 10 or 12 strands with 4-0 sutures to connect the proximal tendon to the distal stump, periosteum of the distal phalanx, and the distal anchoring part of the volar plate of the DIP joint (see Fig. 9.14). The author uses both methods (Figs. 9.15 & 9.16) and finds that they have sufficient strength.

Injuries in zones 1B and 1C usually create tendon stumps of sufficient lengths for a more common end-to-end repair, which can be treated by methods similar to treatment in zone







Fig. 9.16 A case of direct suture repair of the proximal stump to the short distal stump with a set of robust 12-strand core sutures made with 4-0 suture. **(A)** In making the first set of repairs: two-strand Kessler, the first bit is in the proximal stump; **(B)** the suture was placed to both stumps; **(C)** after completion of all 12-strand core sutures the repair consists of a Kessler repair in the tendon and a few two-strand repairs with rectangle configuration of different lengths extending to other tissues as shown in **(D)**; and **(D)** drawing depicting this robust direct attachment. The sutures placed after the first Kessler were extended to the periosteum and the other adjacent tissues to help anchor the sutures.

2. Core tendon sutures, such as the cruciate, modified Becker, Strickland, double Kessler repairs, six-strand triple Kessler, or M-Tang, can be placed to the proximal end through a window opening in the proximal sheath. The proximal end is brought underneath the intact sheath between the wound and the proximal opening to approximate the distal end.

Zone 2 injuries (Videos 9.1–9.5 ▶)

Tendon injuries in this area are often exposed through a Bruner skin incision and a window opening in the synovial sheath, a release, or local excision of a short part of the annular pulleys. If the tendon ends have not retracted far proximally, flexion of the MCP or PIP joint can effectively bring the proximal end into sight. Sometimes the proximal tendon end is found retracted even to the middle of the palm. In this instance, an additional incision of 1–1.5 cm is made in the distal or middle of the palm around the MCP joint level to expose the tendons. By loosely suturing the proximal tendon end to a catheter, the proximal tendon end is then pulled distally within the synovial sheath, or the proximal tendon is advanced underneath the intact sheath tunnel by alternately feeding the tendon with two pairs of forceps from the palm

incision (see Fig. 9.13). The end is brought out of the distal opening in the sheath to approximate the distal end. While the finger is held in slight flexion, a 25-gauge needle is then inserted at the base of the finger through the proximal tendon to hold the tendon temporarily and to release the tension at the surgical suture site.

During surgery, tendons should be handled atraumatically, and ragged tendon tissue at the cut ends should be removed with a scalpel or fine scissors. Stronger suture materials are preferred; 3-0 or 4-0 sutures (nylon or coated nylon) are common choices. Basic requirements of a tendon repair are: (1) sufficient strength; (2) smooth tendon gliding surface, with minimal suture (and knot) exposure; (3) no gapping of the repair site under tension; and (4) ease to perform.

Surgical suture techniques used vary among surgeons. Some of core suture methods are shown in Fig. 9.17. The modified Kessler and cruciate techniques are further detailed in Fig. 9.18. The Bunnell method is no longer popular for end-to-end repair. The two-strand modified Kessler method and Tsuge method are among the most widely used over the past 40 years. In the last 25 years, a number of multistrand repair techniques have emerged,^{14–19,65–69} which include four-strand repairs such as cruciate, modified Savage, Strickland,




Fig. 9.17 Summary of some methods used to make core sutures in flexor tendon repairs.




Fig. 9.18 Two common techniques in flexor tendon repairs. **(A)** Modified Kessler method. **(B)** Cruciate method.

and double Kessler; six-strand repairs such as Savage, Lim-Tsai, Tang, and M-Tang; and eight-strand Winters-Gelberman methods. Most surgeons now prefer a multistrand repair. The author uses multistrand methods, typically a six-strand repair method, in repairing lacerated FDP tendons in zone 2.

In the author's practice, the double Tsuge method or six-strand methods have been used in the past 25 years. In the past 15 years, the author and colleagues have used modifications of the original methods to repair tendons using fewer looped lines and knots, but maintaining suture strands and repair strength across the repair site identical to those of the original methods (Fig. 9.19). These methods are relatively easy, and surgical repair strength is very reliable (Figs. 9.20–9.26).

Surgeons use many variants of multistrand repairs in an FDP tendon repair: a variant of the Strickland method is used at Stanford University, a locking cruciate repair at the Hospital for Special Surgery in New York (Fig. 9.27), and an eight-strand core suture is used at Washington University in St. Louis, Missouri. The six-strand Lim-Tsai method is used at the University of Bern, Switzerland and a six-strand Tang method at Broomfield Hospital in Chelmsford, England. The author has also used an asymmetric six-strand Kessler repair, a method of three groups of two-strand Kessler repair made with different purchase lengths in two tendon stumps to better resist gapping (see Fig. 9.27). For FDS tendon cut proximal to bifurcation, I also used a four-strand repair carrying a looped suture or two separate suture lines (see Fig. 9.27).⁷² To make a successful repair, surgeons should follow some universal principles, such as ensuring strong core suture repair, sufficient suture purchase, secure anchor of the suture to the tendon and knot security, and creating tighter tension over the repair site. Once such principles are followed, suture configuration itself is not vital. The multistrand methods described – preferred in different centers – may be likewise reliable.

Epitendinous stitches smooth the approximation of the tendon ends and resist gapping during tendon movement. Simple running peripheral, locking running peripheral, cross-stitch peripheral, and Halsted horizontal mattress sutures are

among those most often used, with the first two more popular (Fig. 9.28). Some surgeons prefer “deep-bite” peripheral stitches to add strength to repairs.¹⁵⁶ An epitendinous suture is usually added after completion of core sutures, but it can also be added first.¹⁶¹ Peripheral stitches can be unnecessary given a strong multistrand core suture.²⁵ Clinically, peripheral repairs vary from complex stitches to none. The author's preference is to use a simple running peripheral suture with 6-0 nylon after completion of a four- or six-strand core suture repair.

Technically, to make an optimal surgical repair, the length of core suture purchase in each tendon end should be at least 7 mm to 1.0 cm. Surgical repair strength decreases as the length of the suture purchase decreases (Fig. 9.29). In addition, a certain tension across the repair site is beneficial to resist gapping. In the author's experience, a certain tension (that results in about 10% shortening of the encompassed tendon, when the proximal tendon is temporarily fixed during surgery) appears beneficial, because a small amount of baseline tension in the repair would counteract the tension of the locomotor system during resting or active motion. When locking suture-junction in the tendon is incorporated in the core sutures, the locking circles of the suture in the tendon should be of a sufficient diameter (approximately 2 mm). After completing the repair, the cut tendon ends should align well, and no gapping between the tendon ends should be observed (Box 9.4).

In the past 15 years, novel repair concepts have emerged and novel materials have been used. For example, of potential clinical merit are techniques involving a single passage of the needle carrying double or even triple strands into the tendon,^{69,155,161–163} FiberWire also offers a strong suture material for tendon repairs.^{95,155} These methods are effective in enhancing strength with a minimal suture passage in the tendon.

Closure of the synovial sheath is no longer considered essential for tendon repairs after hot debate in the 1980s and early 1990s.^{164–171} Closure may be attempted in clean-cut injury when sheath defects or abrasions are absent. It is now agreed that avoiding compression or constriction to the edematous




Fig. 9.19 The technique for making a six-strand M-Tang tendon repair. Two separated looped sutures are used to make an M-shaped repair within the tendon. **(A–C)** A U-shaped four-strand repair is completed, which can be used alone for tendon repair. **(D,E)** An additional looped repair is added at the center, to complete the six-strand repair. In tendon cross-sections, three suture groups are placed at points of a triangle to avoid interference to the dorsal center of the tendon where the vascular networks converge. The dorsolateral sutures may act as tension bands to resist gapping of the tendon.

tendons by the sheath or annular pulleys after surgery is very important to tendon healing. With major pulleys and a majority of the sheath intact, leaving a part of the synovial sheath open has no significant adverse effect on tendon function and healing. On the other hand, incision of one single annular pulley (A1, A3, or A4) or a critical part (up to two-thirds of its length) of the A2 pulley does not significantly affect tendon gliding when all other pulleys or the synovial sheath are intact. Such a release can in fact be beneficial to tendon healing and gliding: as healing responses and adhesions arise, it releases constrictions on edematous tendons.

Clinically, the A4 or A2 pulley sometimes constitutes an obstacle for the edematous tendon to glide through, which




Fig. 9.20 A case with complete laceration of the flexor digitorum profundus tendon and partial flexor digitorum superficialis tendon laceration in zone 2B. The surgery was performed 10 days after injury. The wound was exposed through a Bruner incision, and the distal half of the A2 pulley was incised through the volar midline.




Fig. 9.21 The lacerated flexor digitorum profundus tendon was found through a separate incision in the palm and was led underneath the sheath and pulleys to the operation field distal to the A2 pulley, to approximate the distal stump.




Fig. 9.22 Completion of inserting a four-strand repair using one looped suture line.




Fig. 9.23 Completion of the six-strand M-Tang repair.



Fig. 9.24 Addition of a simple running peripheral repair.



Fig. 9.25 Follow-up at 10 months after surgery, full flexion of the repaired finger, without tendon bowstringing.




Fig. 9.26 Full extension of the repaired finger.




Fig. 9.27 Other designs of four-, six-, eight-, or ten-strand repairs used in different centers. **(A)** A variant of the Strickland repair (Stanford University, USA). **(B)** An eight-strand repair (Washington University in St. Louis, USA). **(C)** A six-strand asymmetric Kessler repair (Nantong University, China). **(D)** A ten-strand repair that the author use for late direct repairs.




Fig. 9.28 Two simple, common methods of peripheral suture. **(A)** Simple running peripheral suture. **(B)** Running locking peripheral suture.

may cause repair rupture during tendon motion exercise. The perceived need for complete preservation of the A4 and A2 pulleys during primary repairs is “borrowed” from the surgery pertaining to secondary tendon reconstructions, and does not hold true when the tendons are cut through a single wound and other sheaths or pulleys are intact. Contrary to the practice of 10 or 20 years ago, releasing the A4 pulley entirely and releasing a part of the A2 have become accepted clinical practice in recent years.^{19,23,150,172,173} In the author’s clinic, when the repaired FDP tendons are found tightly entrapped by the A4 pulley after testing during surgery, the A4 pulley is completely released (Figs. 9.30–9.32) (Box 9.5). A




Fig. 9.29 Two bad repairs decrease the strength: **(A)** a repair with short core suture purchase and **(B)** a loose repair. Sufficient core suture purchase and a certain pre-tension favor resisting gapping and decrease the chance of repair failure during tendon motion after surgery.

BOX 9.4 Recommended surgical tendon repair requirements

- More than 2 strands as the core repair – four- or six-strands recommended.
- Certain tension across the repair site – 10% shortening of tendon segment after repair.
- Core suture purchase: 7–10 cm.
- Locking tendon-suture junctions in core suture.
- Diameter of the locks: 2 mm or over.
- Suture calibers: 3-0 or 4-0 for core suture.
- A variety of nylon sutures, or a FiberWire suture.
- A simple running or locking peripheral suture.
- Minimal separate stitches of peripheral suture if core repair is extremely strong.
- Avoid extensive exposure of sutures over the tendon surface.




Fig. 9.30 The constricting A4 pulley sometimes presents an obstacle for the passage of the flexor digitorum profundus tendon.




Fig. 9.31 The A4 pulley and a part of its adjacent sheath were vented to allow tendon passage in this patient. Other parts of the sheath were not violated. In this case, the flexor digitorum profundus tendon was repaired with a six-strand original Tang repair with three groups of looped sutures.




Fig. 9.32 A case of delayed primary repair. **(A)** An intact A4 pulley was seen. **(B)** The A4 pulley was cut open entirely to allow tendon repair. The flexor digitorum profundus tendon was repaired with a six-strand asymmetric Kessler repair (see Fig. 9.27C). **(C)** Methods of venting a pulley: midline cut, lateral cut, or shortening.

part of the A2 pulley, either proximal or distal (about one-half to two-thirds length of the A2 pulley; see Figs. 9.20–9.24), is cut when both the FDS and FDP tendons are repaired in the area of or distal to the A2 pulley. When the repair is considerably delayed (3 weeks after injury), the A2 pulley usually collapses or is even embedded within scars. A portion of the A2 pulley is excised to shorten this pulley (Figs. 9.33–9.37).

The release usually needs to include a part of adjacent synovial sheath. The total length of the sheath–pulley release is about 2 cm in adults, which amply decompresses tendon gliding, but does not lead to functional disturbance. The areas of the release are shown in Fig. 9.38.

Over the years, release of the pulleys has been achieved differently: (1) incision of the entire or a critical part of the major pulley;^{19,22,23,150} (2) excision of a part of the major pulley;¹⁹ (3) Omega pulley plasty;¹⁷⁴ and (4) sheath enlargement plasty.^{175,176} My current pulley release is a simple procedure: incising the A4 or a portion of the A2 pulley, or partially excising the A2 pulley, while obviating complicated sheath- or pulley-plasty surgeries.

Whether or how to repair the FDS tendon when both flexor tendons are injured is a subject of diverse opinions, particularly in the areas covered by the A2 pulley or distal to it. A few reports have discussed it specifically.^{21,177,178} Repair of one

BOX 9.5 When and how to vent the A4 pulley for tendon repair

1. The A4 pulley is located at the middle part of the middle phalanx, about 5 mm long.
2. The A4 pulley is rigid, constrictive, and narrow.
3. When this pulley prevents smooth passage of the retracted FDP tendon underneath, or when the pulley is found to prevent smooth gliding of the repaired FDP tendon during digital extension–flexion test (see [Box 9.6](#) for method detail), this pulley can be entirely vented after the surgeon confirms that all other annular pulleys are intact.
4. The A3 pulley should usually be preserved. In the rare case when the A3 pulley has to be vented, any synovial sheath proximal to the A3 should be entirely preserved.
5. The entire length of the sheath–pulley venting should be less than 1.5–2 cm over the middle phalanx area.
6. The method of venting is (1) direct cut along the palmar midline of the pulley, or (2) direct cut along the lateral side of the pulley, or (3) resection of this pulley if it has been embedded inside adhesions and fibrosis.



Fig. 9.35 The proximal tendon stump was passed underneath the preserved portion of the A2 pulley. The tendon was repaired with the six-strand M-Tang technique.




Fig. 9.33 A case of ruptured primary repair referred to the author. Direct repair of the ruptured flexor digitorum profundus tendon was performed 3 weeks after the first tendon repair. The flexor tendons and the A2 pulley were found embedded within scars.



Fig. 9.34 The A2 pulley was partially excised and the intact part of the A2 pulley was released from the scar. The ragged tendon ends were trimmed to fresh tendon surfaces.

slip of the FDS is also feasible.^{100,108} In the area of the A2 pulley (zone 2C), the author prefers to locally excise the FDS in cases with severe peritendinous injuries, when the tendons appear edematous, and in cases with delayed primary repairs. In performing the delayed repair, the author finds it almost impossible to repair the FDS tendon in zone 2C, because some degree of collapse or narrowing of the A2 pulley is inevitable, and the tendons are often edematous. In zone 2B, where the FDS tendon is bifurcated into two slips, the author uses two Tsuge repairs separately in each tendon slip; when the laceration is close to the insertion, the tendon slips are anchored to the phalanx. Treatment of the FDS tendon in zone 2D is straightforward, similar to the FDP tendon except that the FDS is flatter and four or fewer strands are used.



Fig. 9.36 Follow-up 6 months after surgery. Full flexion of the finger, with no loss of digital flexion and no tendon bowstringing.



Fig. 9.37 Full extension of the fingers, without extension deficits of the finger joints.

In deciding surgical options relating to both the FDS and the pulleys, the author generally seeks to appropriately decrease the gliding contents (by not repairing or excising the FDS tendon) or enlarge the sheath (when both tendons are repaired primarily or only the FDP tendon is repaired at the delayed stage). The underlying idea is that the fibro-osseous digital flexor sheath tunnel is comparable to a tight fascia compartment of extremities; the edematous and healing tendons are compromised easily. Release of compression of the tendon to avoid overloading it during motion can be more vital to the success of treatment than providing it with sufficient surgical strength.

Surgical options currently advised to deal with the tendons and pulleys in the most complex areas of finger flexor tendons are summarized in [Table 9.1](#).

Once surgeons have completed surgical repair of the tendon, and vented the pulleys in case of need, an intra-operative test – “digital extension–flexion test” – should be performed before closure of surgical incisions.¹⁴⁹ Detailed in [Box 9.6](#), this test consists of three parts: full extension of the operated digit, flexion of the digit from full extension to flexion, and finally maximal digital flexion ([Fig. 9.39](#)). If the repair fails this test, the repair should be either redone or enhanced, or the annular pulley proximal to the repair vented further, depending on the circumstance. If the repair is a wide-awake surgery, the patient should move the digit actively on




Fig. 9.38 Drawings depicting the length and areas of release of the pulley–sheath complex to decompress the repaired tendons, without bowstringing or loss of tendon function. **(A)** Release of the entire A4 pulley when the flexor digitorum profundus tendon has been cut around the A4 pulley and the tendon cannot pass easily beneath this pulley during surgery. **(B)** Release of a part of the sheath distal to the A2 pulley and the distal half of the A2 pulley, when the tendons are cut a little distal to the A2 pulley. **(C)** Release of a short part of the sheath distal to the A2 pulley and the distal two-thirds of the A2 pulley when repairing tendons cut at the edge of, or in the distal part of, the A2 pulley. **(D)** Release of the proximal two-thirds of the A2 pulley when repairing a cut in the middle, or proximal part of, the A2 pulley.

Table 9.1 Summary of mechanical basis and surgical options advised to deal with the flexor digitorum superficialis (FDS) tendon and pulleys in zone 2 of the finger

Investigations	Area of FDS insertion (2A)	Distal to A2 pulley (2B)	Beneath A2 pulley (2C)	Proximal to A2 pulley (2D)
Anatomic				
FDS tendon	Insertion	2 slips, dorsal to FDP, with vincula	Bifurcation	One single band, flattened palmar to FDP
Pulleys	A4, C2, narrow	A3, C1	A2, narrow	A1, PA
Biomechanical				
FDS tendon	No gliding	Not constricting FDP	Constricting FDP, as a moving and second “pulley”	Little constriction
Pulleys	A4 release is feasible ¹¹²	May incise one pulley ¹⁰⁷	Partial release is feasible ^{22,111,112}	
Clinical options				
FDS tendon		Repair ^{174,214}	Resection or do not repair ^{21,23,150} Resect one slip ¹⁰¹	Repair both tendons when possible
Pulleys	A4 venting ^{19,23,172}		Partial release ^{19,23,150,172} Pulley shortening or plasty ^{100,175}	
FDP, Flexor digitorum profundus; PA, palmar aponeurosis.				

the operating table, which offers the most objective measure of quality of the repair (Fig. 9.40). If a repair fails the test intraoperatively, this poor repair is bound to gapping or disruption in later early active motion; therefore it should be revised before leaving the operating table.

Zone 3, 4, and 5 injuries

The repair techniques for injured flexor tendons proximal to zone 2 are almost identical to those used in zone 2. These zones have a better prognosis because of richer vascularity around the tendon and lack of constricting pulleys over the tendons. Adhesions in these areas are less likely to impede tendon motion. Zone 4 tendon injuries are frequently accompanied

by lacerations to the median nerve. The transverse carpal ligament may be partly or entirely opened to facilitate repairs and left partly open after tendon repairs. Zone 5 tendon injuries usually present as multiple tendon lacerations with neurovascular injuries. A wrist with transection of a majority of tendons, vessels, and nerves (at least 10 out of 15 of these structures, excluding palmaris longus) is called a “spaghetti” wrist.^{179–183} A “spaghetti” wrist was reported to have an adverse effect on the recovery of the independent FDS action but not on the recovery of digital range of motion.¹⁸³ In zone 5, repair of the FDS tendon is preferred, and early postoperative tendon motion is advised,^{183–185} which favors independent movement of the superficialis. However, the FDS tendon to the little finger may be absent or too slender to repair.

BOX 9.6 When and how to perform an extension–flexion test

- This test should be performed after any kind of primary repair of flexor tendons in the digital and palm area, to make sure the repair is strong and that tendon gliding is smooth before closure of surgical incisions.
- There are three parts to this test. *Part 1*: Full passive extension of the digit that has undergone surgery by the operator, to confirm that the tendon repair site has no gapping.
- *Part 2*: From the fully extended position, the operated digit is passively flexed to moderate degrees, to confirm that the tendon and the repair site can glide smoothly.
- *Part 3*: Further pushing the digit to full or almost full flexion, to confirm that the tendon repair site does not impinge against rigid annular pulleys.
- If tendon gapping is found with digital extension, the repair should be reinforced, or if annular pulleys block tendon gliding with digital flexion, the pulleys should be vented, according to guidelines for treatment of pulleys.
- The results of the above tests are included in the operative notes and the therapists are informed.

FPL injuries

Repair of the injured FPL tendon in the thumb usually follows the same principles and methods of repairs of the FDP tendon in fingers. Multistrand repairs are advised, and one or two pulleys can be vented to free tendon motion. Reports have shown that conventional two-strand repairs have a risk of rupture as high as 17%.^{25,172} In a report from David Elliot’s hand center, Giesen *et al.*²⁵ reported no ruptures and good function after use of a six-strand Tang method without peripheral sutures in repairing 50 FPL tendons. In this case series, which reported the best outcomes of FPL tendon repairs thus far, the pulleys were vented and the sheath was not closed. The authors found that this six-strand repair was safe for early active mobilization and easier to perform than Kessler core sutures and elaborate Silfverskiöld sutures.

In repairing the FPL tendon, the proximal cut end of the tendon frequently retracts into the thenar muscles. This end can be retrieved with the techniques described for retracted FDS and FDP tendons (Figs. 9.41 & 9.42). If the proximal stump of the FPL tendon has retracted proximal to the thenar




Fig. 9.39 Extension–flexion test of the repaired tendon before closure of surgical incision. **(A)** Full extension of the digit. **(B)** Motion from full extension to flexion. **(C)** Completing the maximal flexion. In wide-awake surgical settings, the digital motion is active, providing the best measure of quality of surgical repair.

muscles, a separate incision in the forearm is required to locate the stump. The FPL stump usually lies deep to the FCR tendon and the radial artery.

Injuries in children

Flexor tendon repairs in children have a better prognosis than those in adults.^{186–190} As children may be less compliant with instructions to limit movement, the repaired digits are usually immobilized for 3–3.5 weeks after surgery. Either a two-strand or a four-strand repair can be used. In practice, many surgeons use a two-strand repair and achieve good return of function. The outcomes appear unaffected by whether a two- or four-strand repair is used or whether the tendon is moved or immobilized early after surgery.^{188,189} Navali and Rouhani¹⁸⁸ reported that both a two-strand and four-strand repair achieved good functional return, with no difference in range

of active digital motion between the two methods. Elhassan *et al.*¹⁸⁹ reported that early postoperative motion and immobilization did not affect outcomes in children aged 2–14 years with injuries in zones 1 and 2.

Partial tendon lacerations

Laceration through less than 60% of the diameter of the tendon does not necessitate a repair by core sutures. An increased risk of triggering, entrapment, or ruptures is associated with partial laceration over 60%.^{191–195} For lacerations less than 60%, the tendon wound can be trimmed to lessen the chance of entrapment by pulley edges and friction against the sheath. Alternatively, the cut portion of the tendon can be repaired with epitendinous stitches to smooth the tendon surface and to strengthen the tendon. Laceration of 60–80% requires at least an epitendinous repair^{196–199} and is better repaired using a two-strand core suture through the cut portion. Laceration of 80–90% is treated identically to a complete laceration.

Closed rupture of the flexor tendons and pulleys

Traumatic FDP tendon avulsion from the tendon–bone junction accounts for a major portion of closed rupture cases.^{200–203} The injury mechanism is hyperextension of the DIP joint, which subjects the FDP tendon to excessive load. The tendon disrupts at its insertion to the distal phalanx. Athletic injuries can lead to this type of injury. In football, wrestling, or rugby, when one player grabs another's jersey, a finger gets caught and pulled, resulting in disruption of flexor tendons. This injury ("jersey finger") is seen most commonly in the ring finger. Closed tendon ruptures at the wrist can be associated with fractures in carpal bones.²⁰³ Flexor pulleys are prone to sprains and ruptures during climbing. Rupture of the pulleys occurs in up to 20% of climbers.²⁰⁴ The A2 pulley of the ring finger is the most often injured. Closed pulley ruptures are treated conservatively or by surgical reconstruction.

Leddy and Packer²⁰⁰ classified close tendon ruptures into following types:

- I. The FDP tendon is avulsed from the phalanx and retracts into the palm. The vincula of the FDP tendon are disrupted. There is no active flexion of the DIP joint. A tender mass is present in the palm. The tendon should be reinserted within 7–10 days before the sheath collapses, which may prevent advancing the tendon distally. Muscle contracture may also prevent tendon advancement.
- II. The FDP tendon retracts to the level of the PIP joint. This is the most common type. The sheath is not compromised, and muscle contracture does not develop easily. Repair may be attempted 1 month after injury.
- III. A large bone fragment is attached to the FDP tendon. This bone fragment frequently prevents the tendon from retraction proximal to the A4 pulley. Bony fixation using a K-wire or a screw usually suffices.
- IV. The FDP tendon avulses from the bony fragment. This type was added by Smith.²⁰⁰ The avulsed tendon retracts beyond the middle phalanx and even into the palm. In treating type IV injuries, the bony fragment is attached into the distal phalanx first; then the avulsed tendon is




Fig. 9.40 Primary tendon repair of the tendon in the A2 pulley area (zone 2C) under a wide-awake setting. **(A)** The first injection of 5 ml of the 1% lidocaine with 1:100 000 to the palm 30 minutes before surgery. **(B)** The second injection was given 15 minutes later, to the proximal part of the digit, followed immediately by injection to the middle and distal parts of the digit **(C,D)**. **(E)** A close-up view of making the first anchor of the looped suture to the tendon in the six-strand M-Tang repair. Note that the site of needle entry is 1 cm away from the cut end and the size of the lock is large. **(F)** The U-shaped repair with the first looped suture was completed. Two strands of centrally placed looped sutures were added later to complete the 6-strand core repair.



Fig. 9.40, cont'd (D) After completion of the six-strand repair and simple peripheral suture, the patient actively extended (G) and actively flexed (H) the digit to check quality of the repair. (I) Pictures taken 5 months later showing full recovery.





Fig. 9.41 A 9-year-old boy with a complete flexor pollicis longus tendon cut. The retracted proximal tendon end was found and was temporarily fixed with a needle to accommodate tendon repair (A). The FPL tendon was repaired with the six-strand M-Tang technique (B).




Fig. 9.42 Follow-up 8 months after surgery. (A) Full flexion of the repaired thumb. (B) Full extension of the thumb.

advanced. Postoperatively, the DIP joint is immobilized for 4–5 weeks, or a gentle motion regime is prescribed.

Early recognition of closed tendon ruptures is of paramount importance. In the cases of late diagnosis, primary repair is difficult or even impossible. Chronic cases require free tendon grafting.

Postoperative care

With the exception of a few instances – such as tendon repairs in children, adults who are unable to follow through the protocol, or associated with complex fractures – motion of repaired tendons should be initiated from the early postsurgical period. From the 1970s to 1990s, the Kleinert and Duran–Houser protocols were most popular. In recent years, a variety of combined passive–active flexion protocols have been developed, replacing passive flexion protocols. The protocols have evolved and the methods presently used in many clinics are combined passive–active digital flexion regimes.

In the 1960s, Kleinert and associates introduced a controlled active extension–passive flexion protocol, which was a conceptual breakthrough.²⁰⁵ They placed the wrist in palmar flexion of 30° to 40° and 60–70° MCP joint flexion with a dorsal protective splint. Rubber bands were attached to the volar forearm and to the tip of the finger. The patients were allowed to actively extend the fingers and the fingers were brought back to flexion passively by the tensed rubber bands. This traction was found to lead to flexion contractures of the finger, with the original protocol as well as after a pulley for the rubber band added at the MCP joint level in 1990s.^{206,207} Therefore, the rubber band traction has mostly been abandoned.

Duran–Houser method


This was a controlled passive finger flexion protocol introduced by Duran and Houser in the 1970s.²⁰⁸ A dorsal splint

was applied with the wrist in 20° flexion, the MCP joint in 50° flexion, and the IP joints were allowed full extension (Fig. 9.43). Within the first 4.5 weeks, the patients performed 10 passive DIP joint extensions with PIP and MCP joint flexions, and 10 passive PIP joint extensions with MCP and DIP joint flexions hourly within the splint (see Fig. 9.43).


Strickland and Gettle modified this protocol by adopting a Duran-like protocol for a four-strand tendon repair,²⁰⁹ later known as the “Indianapolis method”. This protocol consisted of two splints, the dorsal-blocking splint (used during periods of rest and passive motion, with the wrist at 20–30° of flexion, MCP joints in 50° of flexion, and IP joints in neutral position) and a tenodesis splint (used when performing place and hold exercise). The latter hinged wrist splint permitted the wrist position to be varied between flexion and extension. With the tenodesis splint, the patient passively flexed the digits while actively extending the wrist. The patients passively pushed their fingers into a passive composite fist with the wrist extended and hold for 5 seconds. The patients relaxed the wrist and let it descend into flexion. Patients were instructed to exercise 25 times per waking hour. Four weeks after surgery, active digital flexion and extension was instituted with the dorsal blocking splint still on and the tenodesis splint was discontinued. One week later, active composite fist followed by active extension of the wrist and digits was added to the program. When both flexor tendons are repaired in the digital sheath, differential motion of the two tendons could be practiced. Shifting the finger postures from straight, hook, and fist positions generated differential gliding of the two tendons.

Early active motion


In the late 1980s and early 1990s, protocols containing early active tendon motion components emerged. One requirement is that the tendon repairs be strong enough to tolerate the tension during the motion. In 1989, Belfast surgeons devised an active motion protocol,²¹⁰ which was later known as



(A) Duran and Houser passive motion regime



(B)



(C)



(D)

Fig. 9.43 (A) Duran passive tendon motion protocols. (B) Nantong regime. Passive flexion of the fingers over 20–40 times, followed by partial active digital motion to one- or two-thirds of the entire arc of finger flexion.

“Belfast method”. Postoperatively, a splint is applied from the elbow to the fingertips with the wrist in mid-flexion, the MCP joint at slightly less than 90° flexion, and the IP joints straight. The light dressing is removed from the digits and exercises commences 48 hours after surgery. Under supervision, the exercises consist of two passive movements followed by two active movements and are performed at 2-hour intervals. The hand is rested in elevation overnight. During the first week, the PIP joint is actively flexed through about 30° and the DIP joint through 5–10°. In subsequent weeks, the range of active motion is gradually increased. The splint is removed by the 6th week and blocking exercises of the IP joints are initiated when necessary. Variants of the Belfast method have been reported. In one of the variants, the “Billericay regimen”, the wrist and the MCP joint are kept in a splint at 30° flexion, respectively, and the splint is removed by the fifth week. The patient is instructed to perform 10 repetitions of exercise hourly.²¹¹

Author’s preferred combined passive–active method (Nantong regimen)

After surgery, the hand is protected in a dorsal thermoplastic splint, with the wrist at 20–30° flexion, MCP joint at slight flexion, and the IP joints in extension for the initial 2.5 weeks (3 weeks or slightly longer when the trauma is severe or digital edema is remarkable) (see Fig. 9.43).¹⁹ The wrist can be placed at neutral position instead. We do not encourage the patients to move the finger in the initial postoperative days; exercise starts at 3–5 days after surgery. The patient is instructed to perform at least 4–6 sessions of combined passive–active motion daily across the morning, noon, evening, and before sleep. More sessions can be implemented as needed, while hourly exercises are not required. At beginning of each exercise session, the finger is passively flexed 10–30 times to lessen the overall resistance of finger joints and soft tissues during subsequent active flexion. The passive motion is followed by actively flexing the finger with gentle force 20–30 times up to the range the patients feel comfortable with (usually from full extension to one-third or one-half of entire flexion range, and may even increase to two-thirds if achieved with ease). Active flexion over full range is not encouraged, unless it can be achieved very easily. In this 2.5-week period, full active extension is particularly encouraged, and prevention of extension deficits rather than achieving full range active flexion is emphasized.

After 2.5 weeks (or 3 weeks, or slightly later), a new thermoplastic splint is made, and the wrist is splinted at 30° extension (Fig. 9.44). Exercise of finger flexion, both passively and actively, is emphasized in this period. Active motion up to the midrange is required, and can proceed up to two-thirds (or full range). However, digital flexion from the mid-range to full range, in particular over the final one-third of the flexion range, usually is achieved passively. In this period, we ensure passive flexion over a full range to prevent joint contracture and active flexion over an increasingly greater range gradually approaching full flexion range, but discourage active forceful flexion of the finger over the final range where the tendon is subjected to the greatest load and is more vulnerable to rupture (see Figs. 9.8 & 9.43). Differential FDS and FDP motion exercise is encouraged throughout the first 5 weeks. From the sixth week, full active finger flexion is

encouraged (which can be started earlier when the flexion is judged to have less resistance). From 6 or 8 weeks, the splint is removed or used only at night or when going out.

Delayed motion exercises

Delaying motion exercises, i.e., immobilization over the first 2 weeks, can be a right choice for some patients. A patient with distal zone 1 direct end-to-end repair, the terminal part of the FDP tendon has little need of gliding and adhesions have almost no impact on digital motion. The author immobilizes the wrist in 20–30° of flexion and the MCP joint in slight flexion for 2 weeks with a short dorsal splint. From the third week, the digit is passively moved within the splint. From the fifth week, the patient performs active digital flexion with the splint removed; the splint is not discarded until week 7.

A severely traumatized hand after repair of multiple structures also merits from such delayed exercises. The above-described protocols represent several distinct categories of exercise. While the key points of the passive–active motion regime are respected currently (Box 9.7), upon applying to individual patients, surgeons or therapists should incorporate refinements. In patients with severe edema of the hand or trauma to multiple digits, motion exercise can be delayed for a few days, and more sessions of passive digital motion should be integrated. Table 9.2 is the straightforward scale that I use to record the severity of digital edema for setting timing and intensity of exercise. Other factors such as joint stiffness, soft-tissue conditions, and extensor tethering should also be considered in adjusting the regime.²¹²

Strong surgical repairs together with necessary venting of the pulleys have bestowed greater freedom in wrist positions after surgery. Often the wrist is put in a neutral position and a shorter splint is used (to about 10 cm above the wrist)

BOX 9.7 When to begin and how to perform early active motion

- Early active motion of the surgically repaired digit is a component of an early passive–active motion regime, which should be performed together with passive motion in each exercise session with the protection of a dorsal splint (or out-of-splint exercise in very compliant patients).
- Early active motion should be initiated on day 3, 4, or 5 after surgery, not necessarily starting on day 1. Delaying the early motion for a few days decreases pain and avoids peak digital edema.
- Early active motion can be delayed to around the end of week 1 if remarkable digital edema is drastic and wound conditions do not allow earlier motion. However, passive hand motion should be implemented earlier to decrease the risk of joint stiffness and edema.
- At least 4–6 sessions of exercise are necessary, distributed across the day and evening. More exercise sessions should be added if possible.
- In each session, passive motion always precedes active digital flexion. The finger should be flexed passively and extended 20–30 times (or more) before starting active finger flexion.
- In performing active finger flexion, the patient should be instructed to perform partial range active flexion in the first 2.5 or 3 weeks, i.e., active flexion over the first one-half or two-third parts of the entire flexion arc, avoiding the final part of active flexion or making a fist.
- Full range of active flexion is allowed 3–4 weeks after surgery.



Fig. 9.44 The author's combined passive-active tendon motion protocol. This protocol is divided into two 2.5-week periods, or into two 3-week periods when trauma to the digit is severe or edema of the hand is remarkable. In the first 2.5 weeks, with wrist in slight flexion, finger extension is emphasized. Only partial active digital flexion is allowed, but full range of passive motion is implemented. In the second 2.5 weeks, with wrist in extension, full active finger flexion is encouraged. This protocol incorporates the concept of synergistic wrist and finger motion. When the wrist is flexed, finger extension is less tensed; when the wrist is extended, finger flexion is less tensed.

to protect zone 1 and 2 repairs (Fig. 9.45). Because tendon repairs are strong, out-of-splint active motion is performed regularly.

From communications with many hand surgeons and therapists, the author has found that hand centers around

the globe actually use some kinds of variants of these protocols.^{149,213} Motion regimes for zone 4 and 5 repairs are generally not as complex as those described above. There is not yet universal agreement regarding the timing of initiating rehabilitation and frequency of motion. Theoretically, tendon adhesions develop from 10 days to 2 weeks after surgery. No studies have yet proven the necessity of starting exercise on the first day. It seems equally reasonable to commence exercise slightly later, though still within one week after surgery. Likewise, no studies have identified the optimal frequency of motion in each exercise episode.

Experimental evidence supporting later commencement of tendon motion were offered by Zhao *et al.*¹¹⁸ of the Amadio group, and the author's colleagues Xie *et al.*¹¹⁹ and Cao *et al.*¹²² Digital edema increases resistance to motion, which peaks at 3 to 5 days.¹²⁰⁻¹²² Both Zhao *et al.*¹¹⁸ and Cao *et al.*¹²² suggest that motion be commenced later (5 days after surgery).

Table 9.2 Severity of digital edema

Grades	Descriptions
0 (none)	Swelling is absent
1 (slight)	Swelling is minimal or mild
2 (moderate)	Swelling is prominent, with increase in digital diameter
3 (severe)	Swelling with openings in skin incisions



Fig. 9.45 The postoperative protection and motion. **(A)** Neutral wrist position with a short forearm splint. **(B)** Out-of-splint motion exercise is allowed. **(C)** In later weeks, specific motion exercise of the distal interphalangeal joint is often necessary to correct mild to moderate stiffness, which develops 3 to 4 weeks after surgery.

Outcomes, prognosis, and complications

Review of outcomes reported over 25 years showed excellent or good active range of finger motion in more than three-quarters of primary tendon repairs.^{14,17,19–21,25,210,211,213–232} Nevertheless, repair ruptures were documented in a majority of the reports. In the earlier part of this period, the rupture rates ranged from 4 to 10% in the finger flexors and from 3 to 17% in the FPL tendon of thumbs.^{14,17,214–228} Adhesions remained the most common complication, preventing satisfactory return of active joint motion. Finger joint stiffness was reported fairly frequently as well. It is worth noting that most of these reports came from the finest hand centers in the world, and each team was supervised by at least one surgeon with expertise in treating tendon injuries. The outcomes in a general hospital setting may actually reflect a lower level of success. Flexor tendon repairs might have been unsuccessful in a larger proportion of patients, with a greater incidence of repair ruptures, adhesion formations, or digital joint contracture.

Nevertheless, the past 25 years have seen impressive improvements in outcomes of flexor tendon repairs. In the late 1980s and early 1990s, Small *et al.*²¹⁰ and Cullen *et al.*²¹³ used a two-strand repair and postoperative active motion and had repair ruptures in 6–9% of the repairs, with overall good or excellent results in 78% of the digits. Elliot *et al.*²¹¹ reported a series of 233 patients with complete division of the digital flexor tendons, treated with a two-strand core repair with a controlled active motion regimen. Thirteen (5.8%) fingers and five (16.6%) thumbs suffered tendon ruptures during the mobilization. In the same period, multistrand core repairs were reported by Savage and Risitano,¹⁴ and Tang *et al.*^{17,214} together with active or passive-active motion therapies.

Trumble *et al.*²²⁹ used a four-strand Strickland core suture and a running epitendinous suture to repair zone 2 flexor tendon lacerations in 119 digits (103 patients) and examined postoperative therapies in a multicenter prospective randomized trial. They documented significantly greater range of digital motion, smaller digital flexion contractures, and greater patient satisfaction in the active motion group than in the passive motion group. Associated nerve injury, multiple digit injuries, and smoking were factors leading to poorer outcomes. Patients treated by a certified hand therapist had better motion

BOX 9.8 Methods to optimize outcomes

1. Master tendon anatomy in detail and use atraumatic techniques throughout surgery.
2. To expose the tendons, open a window in the synovial sheath, or open the A2 partially or the entire A4 pulley if the repair site overlaps or is located just distal to these structures.
3. May release the distal two-third parts of the A2 pulley, where it is the most narrow and most constrictive to the tendons, when the FDP tendon is cut just distal or under the pulley.
4. Adopt a stronger and more secure core suture method.
5. Add peripheral sutures to smooth the repair and to prevent gap formation.
6. Properly combine passive and active finger motion into postoperative motion protocols. Fully extend and flex the finger passively, followed by active finger flexion over a certain range. Active motion over the final one-half or one-third is discouraged in the initial weeks to avoid tendon overload (rupture). Postoperatively, apply motion therapy for at least 5–6 weeks.
7. Passive finger motion before active motion substantially decreases the overall resistance to digital motion, lessening the chance of repair ruptures during active motion.
8. Surgical tendon repairs are performed by experienced surgeons, and the unit should have established postsurgical rehabilitation guidelines.

and less severe contractures. Two digits had tendon ruptures in each group. The study supports the combination of multi-strand tendon repair and early active motion after zone 2 repairs. Reports over the recent years give further support to early active digital motion.^{230–232} Rupture rates do not increase in tendons with strong surgical repair and early active flexion.^{230–232} The wrist can be placed in a neutral position or may simply use a hand-based splint after tendon repairs in the digits. Robust tendon repairs and venting the narrow part of the annular pulleys actually result in greater freedom of hand position and motion, and minimize the risk of repair ruptures.

Of note, reports of multistrand core sutures in recent years documented minimal or zero repair ruptures. A stronger surgical repair combined with release of the pulleys offered great safety to the postoperative active motion exercise. After combined use of multistrand repairs and pulley releases, the majority of the cases had good to excellent active range of digital motion with zero tendon ruptures.^{19,24,25} The author's own clinical outcomes also indicate that good-to-excellent return of function can be achieved fairly consistently by means of multistrand tendon repairs, venting of pulleys, and well-designed combined passive and active motion protocols (Boxes 9.8 & 9.9). Strickland and Glogovac criteria (Table 9.3) are the most commonly used methods in assessment of outcomes.¹⁵ The Moiemmen and Elliot criteria (Table 9.3),²⁰ which specifically evaluate the active range of flexion of the DIP joint, are favored by surgeons who record outcomes of zone 1 repair. The TAM (total active range of motion) method proposed by the American Society for Surgery of the Hand is also used, and the Buck-Gramcko method is used often by German-speaking hand societies.¹⁵³ Among the less popular methods currently used are White, Tubiana, and tip-to-palm distance methods. The author currently uses a criterion that implements a more stringent measure of range of active finger

BOX 9.9 What are the most important factors during surgery?

1. Two essential goals must be achieved: maintaining sufficient purchase length (> 0.7–1.0 cm) of the core suture – most vital for the suture's anchor in the tendon, and maintaining tension in the sutures placed in the tendon – critical to prevent gapping between stumps.
2. The suture's holding – a grasp or a lock – in the tendon should be at least 2 mm or greater. Small grasps or locks are pulled out easily.
3. Increasing the diameter of suture from 4-0 to 3-0 can increase the core suture strength; but with sutures of either caliber, at least four strands are needed for any zone 1–3 repairs.
4. Even a robust repair may fail if the tendon impinges against a pulley or is tightly constricted by narrow pulleys. Therefore, properly venting pulleys when necessary is just as important as employment of a robust repair.

motion, as well as grip strength and quality of motion, into the grading system (see Table 9.3).¹⁹

Outcomes of flexor tendon repairs are affected by patient age, extent and zones of injuries, timing of the repairs, postoperative exercise, and the expertise of the surgeon. Results of tendon repairs in children are generally better than those in adults. Tendon repairs associated with extended soft-tissue damage or accompanied by phalangeal fractures are likely to have worse outcomes.

Secondary procedures

Secondary tendon repairs are achieved by free tendon grafting or staged reconstruction. These procedures are reserved for tendons that could not be repaired primarily or for lengthy tendon defects (Box 9.10). These techniques, developed by the early masters of hand surgery,^{38–42,233–243} remain largely unchanged today despite refinements in tendon junction methods, use of novel suture materials, and widespread adoption of postsurgical rehabilitation in recent decades.^{244–248}

BOX 9.10 Secondary surgery: grafting and staged reconstruction**Indications**

1. Tendon injuries not treated within 1 month after injury
2. Rupture of the tendon repairs at primary or delayed primary stages
3. Tendon injuries not indicated for primary repair
4. Badly scarred digits

Essential requirements

1. Supply passive motion of the hand
2. Good soft-tissue condition
3. Sufficient time after initial tendon injury: at least 3 months

Contraindications

1. Limited joint motion
2. Presence of soft tissue wounds or defects, and fractures not well-healed

Table 9.3 Criteria of assessment of functional outcomes of flexor tendon repairs

% Return of motion*	Grip strength†	Quality of motion‡	Function grade
Strickland criteria (1980)			
85–100 (>150°)			Excellent
70–84 (125–149°)			Good
50–69 (90–124°)			Fair
0–49 (<90°)			Poor
Moimen–Elliot criteria (2000) for zone 1 injuries, the distal interphalangeal (DIP) joint only			
85–100 (>62°)			Excellent
70–84 (51–61°)			Good
50–69 (37–50°)			Fair
0–49 (<36°)			Poor
Tang criteria (2007)			
90–100	+	Excellent or good	Excellent +
	–	Poor	Excellent –
70–89	+	Excellent or good	Good +
	–	Poor	Good –
50–69			Fair
30–49			Poor
0–29			Failure

Function is graded as excellent or good when either the grip strength is – or quality of motion is “poor”.
 *Percentage return of the normal (contralateral) hand. Strickland and Tang criteria use sum of active range of motion of the DIP and proximal interphalangeal joints. Moimen–Elliot criteria use motion of the DIP joint only.
 †Grip strength is recorded as + when it is greater than that of the contralateral hand (the nondominant hand), or over 70% of that of the contralateral hand (dominant hand). Otherwise, grip strength is considered abnormal and recorded as –.
 ‡Quality of motion is rated on the basis of direct observation of finger motion by surgeons. It is recorded as “excellent” when all three aspects – motion arc, coordination, and speed – are normal; as “good” when any two are normal; and as “poor” when only one, or none, is normal.

Free tendon grafting

Indications and contraindications

Most traumatic lacerations of the digital flexor tendons are now treated with end-to-end tenorrhaphy primarily. Only some cases require secondary repairs by means of free tendon grafting. Tendon grafting is indicated (1) when the lacerated tendons are not treated during primary or delayed primary stage, (2) when the primary repairs have ruptured and cannot be re-repaired directly, and (3) in the cases with severe contamination, infection, lengthy loss of tendon substance, extensive destruction of the pulleys, or accompanying injuries. Patients who have serious scarring in the tendon bed or failed previous efforts at secondary flexor tendon procedures are appropriate for a staged tendon reconstruction, rather than one-stage tendon grafting. Surgeons sometimes need to decide according to intraoperative findings.

Before surgery is attempted, the soft tissue wound should be well-healed, with supple passive motion of the hand. Physical therapy is prescribed to improve the range of motion of the digits if passive joint motion is limited substantially. Boyes⁴² classified the conditions associated with the cases of tendon grafts and surgical prognosis is worsened by poor hand condition. Lack of passive range of joint motion is contraindicated for one-stage tendon grafting, but may be suitable for staged tendon reconstruction. The timing of tendon grafting is usually 3 months after injury.

Donor tendons

The donors are palmaris longus, plantaris, long toe extensors, or in rare instances the FDS tendon from a normal finger (Figs. 9.46 & 9.47). The palmaris longus tendon (about 15 cm) from the ipsilateral limb is a frequently used donor and is appropriate for a palm-to-fingertip graft. It can be easily harvested through a short transverse incision over the tendon just




Fig. 9.46 Harvesting a tendon graft through a small skin incision, using a tendon stripper.




Fig. 9.47 Three common donors of tendon grafts: (A) palmaris longus tendon; (B) plantaris; and (C) toe extensors.

proximal to the flexion crease of the wrist. The tendon is divided and grasped with a hemostat, while a tendon stripper is advanced slowly into the proximal forearm. Care must be taken to protect the median nerve trunk lying beneath the tendon and its cutaneous branch of the median nerve.²⁴⁹ Because this tendon is absent in about 15% of all hands,²⁵⁰ examination to confirm its presence is essential before surgery. The plantaris tendon is equally satisfactory for a graft, which is obtained by an incision medial to the Achilles tendon and use of a tendon stripper. The length of this tendon (25 cm) is well-suited for a long distal forearm–fingertip graft. However, this tendon is absent in 7–20% of limbs, and its presence cannot be predicted preoperatively.^{251,252} Extensor digitorum longus tendons to the second, third, and fourth toes, the extensor indicis proprius, the extensor digiti quinti proprius, and the FDS tendon to the fifth finger can be used as well. In my clinic, I use the palmaris longus tendon most frequently and place the proximal junction in the palm.

Operative techniques

The flexor tendon is exposed through a volar Bruner's incision or the midaxial approach.^{253–257} Integrity of the major annular pulleys is important to the function of the graft. At

least the A2 and A4 pulleys should be preserved. If possible, other annular pulleys such as A1 or A3 and a part of the synovial sheath are preserved to foster better gliding of the grafted tendon. If a series of annular pulleys are found to be destroyed, reconstruction of pulleys is necessary. Most cases requiring the reconstruction need to be preceded by staged tendon reconstruction.

The distal junction of the graft is placed at the fingertip. The common method is to suture the graft directly to the residual FDP stump or to bury it under an osteoperiosteal flap in the volar phalanx (see Fig. 9.14).^{257–259} In the latter case, straight Keith needles are passed through the distal phalangeal drill hole and exit over the proximal portion of the nail. After emerging from the nail surface, the needles are passed through a gauze pad or a sponge, and through the holes of an overlaying button. The sutures are tied over the button to anchor the graft. Additional sutures are used to secure the FDP tendon stump to the graft. Alternative methods are available, as shown in zone 1 repair (see Fig. 9.14).^{157,159,160,243} In children, because drill-holes in the distal phalanx may damage the open epiphyses, the graft is sutured directly to the stump of the profundus instead. Either at the palm or in the forearm, the proximal junction of the graft is achieved by a Pulvertaft weave suture to the proximal stump of the flexor tendon (Fig. 9.48). Placement of the junction at the palm requires a shorter graft and preserves the function of lumbrical muscles. Care is taken to avoid suturing the tendon to the lumbrical muscle, because this tends to increase the tension in the muscle. Placement of the junction distal to the wrist allows easy adjustment of the tension of the graft, and the scar may be less severe. In the author's experience, a Pulvertaft weave suture is appropriate for the proximal junction in both areas (Fig. 9.49), and the finger is held in slightly greater flexion than in the resting position when the proximal stump is sutured (Fig. 9.50).

Postoperatively, the wrist is held in a position of 30–40° flexion, the MCP joints flexed to 60–70°, and the IP joints at rest in almost full extension. The traditional recommendation is 3 weeks of immobilization within a dorsal splint applied from the fingertip to below the elbow, followed by active exercise of the digits with the protection of a dorsal blocking splint. Some surgeons advocate passive or active finger motion under cautious supervision from a few days after surgery if the graft junctions are strong. Most surgeons still prefer to immobilize the grafted digits for at least 3 weeks to avoid tension on the tendon and to allow some revascularization of the graft. More vigorous exercise can be instituted at 6 weeks after surgery.

The need for tendon graft or reconstruction is controversial when the superficialis tendon is fully functional, but the FDP tendon is cut and has not been repaired directly within 3 to 4 weeks after trauma.^{260–266} There is a risk of losing function if a profundus graft fails. However, such operations are worth the risk in selected cases, such as in young people with a reasonable need for active DIP joint flexion. The procedures are similar to those described above. A thinner donor tendon is preferable and the A2 pulley can be shortened, but a series of pulleys are preserved (Fig. 9.51). Alternatively, one slip of the FDS tendon can be removed to favor passage of the graft. During the procedure, while passing the graft through the FDS tendon, injury may occur that results in formation of adhesions and a loss of finger function. Overall, caution must be exercised with patient selection. Patients with intact




Fig. 9.48 Skin incision and the method of free tendon grafting to reconstruct the function of digital flexion. As many annular pulleys as possible are preserved. **(A)** The tendon junctions are placed outside of the flexor sheath region. To make a proximal junction of the graft with the end of a digital flexor tendon, the Pulvertaft weave technique is commonly used (shown in detail in **B**). The junction is placed at either palm or distal forearm. The graft was woven with the digital flexor through holes in the tendons created by a knife (**B** – top to bottom).

superficialis tendon may adapt nicely and require no treatment. Surgeons should fully inform patients about expected gain of function versus risks of this operation.

When the superficialis tendon is intact and the DIP joint is not stable, the DIP joint can be fused or tenodesed in slight flexion. In the presence of a functional FDS tendon, the combination of MCP and PIP joint motion produces approximately 85% of the arc covered by the finger in flexion.

Staged tendon reconstruction

Indications

This operation is indicated in cases with badly scarred digits, as a result of injury or multiple failed attempts to restore tendon continuity and gliding. The techniques were developed in the middle of the 20th century by Bassett and Carroll, Hunter, Paneva-Holevich, Schneider, *et al.*^{44,267–278} This operation consists of procedures in two stages. In the first stage, the tendon and scar from the tendon bed are excised, but the pulleys are preserved or reconstructed. A Dacron-reinforced silicone tendon implant is inserted into the tendon bed to maintain the tunnel and to stimulate the formation of a mesothelium-lined pseudosheath. Following maturation of the sheath, a tendon is grafted in lieu of the implant in the second stage.

Techniques

The first stage

The involved finger is exposed through a volar zigzag incision and the incision is continued to the lumbrical origin level of the palm (Fig. 9.52). The tendons and sheath (pulleys) are usually found embedded within scars. The tendons are excised with a 1-cm stump of the profundus tendon retained at its distal insertion. The critically located annular pulleys are carefully dissected out of scars. All potential useful pulley materials are preserved. When a series of pulleys are damaged, critically located pulleys (A2 and A4) should be reconstructed, which is an important part of the reconstruction. One method is to use a tendon graft, either a portion of an excised flexor tendon or the palmaris longus tendon, and wrap it around the phalanx twice to obtain sufficient width, but place it deeper than the extensor mechanism in the proximal phalanx or superficial to the extensors in the middle phalanx (Fig. 9.53). Another method is to make use of one rim of a residual pulley, and a tendon graft or a part of the extensor retinaculum is woven back and forth to form a volar part of the residual pulley. A slip of the FDS tendon can be used to make a pulley as well. In the presence of flexion contracture of the finger joint, check-rein extensions of the palmar plate and the accessory collateral ligaments are divided to release the contracture. The profundus tendon is transected at the midpalm.

A set of tendon implants is then tried to determine the appropriate size of the implant, which is judged by the tightness of the digital pulleys and the expected size of the tendon graft in the second stage. In adults, 4-mm implants are often used, which are close in size to the tendon graft. After insertion of the implant underneath the pulleys, the implant should be movable in the tendon bed with minimal resistance. The distal anchor of the implant can be created in several ways (Fig. 9.54). A second incision is made in the distal forearm.






Fig. 9.49 A case of free tendon grafting with a Pulvertaft weave junction of the graft with a digital flexor tendon in the palm. **(A)** The graft was woven into the digital flexor tendon. **(B,C)** Two sutures were added in either side of the graft and the digital flexor. **(D)** Completion of the weave tendon repair.




Fig. 9.50 Tension status of the fingers at the time of suturing the proximal tendon junction of a graft. With the wrist in neutral position, the fingers are slightly more flexed than at the resting position, with each finger falling into slightly more flexion than its radial neighboring fingers.




Fig. 9.51 A case of reconstruction of the flexor digitorum profundus tendon in the presence of an intact flexor digitorum superficialis (FDS) tendon. A palmaris longus tendon was harvested as a graft. A series of pulleys (A4, a part of the A2, and A1) were preserved. The thin palmaris longus tendon fits well within the pulleys and intact bifurcating FDS tendon in the finger.




Fig. 9.52 (A) In stage 1, extensive scars are found after exposure. The scar and the tendon are excised. The annular pulleys were preserved. **(B)** A tendon implant is placed into the scarred tendon bed. Proximal end of the tendon implant is not sutured and left free.

The implant then is passed from the proximal palm to the distal forearm using a tendon passer. After the implant is seated, traction is placed on the proximal end of the implant to make sure that it glides freely. A tunnel is created with blunt dissection proximally over the profundus muscle in the proximal forearm. The implant is laid into this tunnel and a space proximal to the implant is ensured for implant migration during exercise.

Postoperatively, the wrist is held with a short arm posterior splint in slight flexion (30°) and the MCP joint in marked flexion. Passive wrist and digital motion can be started one week later. By 8 weeks, full activity is permitted, except powerful grip until 12 weeks. In cases with pulley reconstruction, the fingers must be protected by circumferential taping or orthoplast rings.

The second stage

The second stage operation is planned approximately 3 months later. A small incision is made adjacent to the distal implant-tendon junction (Fig. 9.55). A portion of the previous incision can be used. After disconnecting the implant from the tendon, the implant is tagged. A free tendon graft is harvested and inserted into the pseudosheath tunnel. Care is taken not to open the pseudosheath proximal to the DIP joint and to avoid injury to any pulleys. The appropriate motor tendon is then selected. The profundus mass is chosen for grafts to the

middle, ring, and small fingers. For index finger reconstruction, the profundus tendon to the index finger is chosen as a motor. For thumb reconstruction, the FPL or one of the FDS muscles is used. The proximal junction can be placed in the palm, but in most cases, it is located in the distal forearm. The tendon graft is attached to one end of the implant. The implant is pulled out through the pseudosheath from one end. The distal tendon junction is secured as previously described for **free tendon grafting**. Placement of the proximal juncture in the forearm offers the graft a favorable environment for tendon gliding. Proper tension on the graft is essential for function.

Paneva-Holevich²⁶⁷ advocated that the FDS tendon should be used proximal to the injury from the same finger as the graft source. This procedure evolved to include placement of a tendon implant together with suturing the proximal FDS to the proximal FDP tendon end at the first stage, and implant removed, grafting the FDS into the finger at the second stage, which yielded favorable results.^{244,279}

Postoperatively, the wrist is held in a position identical to that for a tendon graft.

Some surgeons immobilize the hand for 3–4 weeks; others favor an early protected motion program initiated days after surgery. Therapy proceeds carefully through passive and light active motion until at least 6 weeks, when the tensile strength of the tendon and its junctures are sufficiently strong to tolerate more vigorous motion.

Tenolysis

Indications

Tenolysis is indicated when the passive range of digital motion greatly exceeds the range of active flexion several months after direct end-to-end tendon repair or tendon grafting.^{234,280–286} Tendon trauma with severe damage to peritendinous tissues or compound injuries (such as digital or palm replantation) have greater chances of adhesion formation, thus are more likely to require tenolysis as a later surgery.²⁸² Children can also be candidates for this surgery.²⁸² The prerequisites for this operation are: (1) all fractures are healed; (2) wounds have reached equilibrium with soft, pliable skin and subcutaneous tissues, and minimal reactions around the incision scars; and (3) joint contractures must have been corrected and a normal or near-normal passive range of digital motion has been achieved. The optimal timing of tenolysis remains controversial.^{233,284–287} It is reasonable to consider tenolysis if the desired range of motion is not achieved after 3 months of therapy. At least 3 months should have passed since the direct repair or graft, to allow necessary healing and revascularization of tendons, so as to avoid endangering tendon strength. To assess the patient's final function reliably, 4–6 months are usually required. However, there is no absolute criteria for how poor the range of motion must be to indicate tenolysis. Surgeons should consider the patient's age, occupational requirements, and functionality of the hand in making a decision. Preoperatively, the patients should be informed that intraoperative findings may be incompatible with tenolysis; thus the surgeons need to proceed to the first step of staged reconstruction on finding serious destruction of pulleys or a lengthily lysed tendon segment.




Fig. 9.53 Methods of flexor pulley reconstruction. **(A)** Reconstruction of the A4 and A2 pulleys using flexor tendon grafts passed circumferentially around proximal and middle phalanges. The tendon graft passes deeper to the extensor apparatus at the proximal phalangeal level and superficial to the extensors at the middle phalangeal level. **(B)** A tendon graft is woven through remnant of the A2 pulley to reconstruct the A2 pulley. **(C)** Use of a slip of flexor digitorum superficialis (FDS) tendon for middle digital pulley reconstruction. **(D)** An operative picture showing the FDS tendon slip as a source of graft for reconstructing multiple pulleys. The FDS was sutured to the remnants of the pulleys and periosteum.

Anesthesia

Active involvement of the patient in assessing tendon mobility and adequacy of release is a key step of surgery. This is achieved by using sedative anesthesia, combined with local anesthesia at the operation area,^{234,288} or only local anesthesia (no sedation) with the patient awake during the entire surgical period.^{123,124} The author uses 2% lidocaine infiltrated locally in the subcutaneous tissues or as a digital nerve block at the metacarpal level if the patient does not want to be awake. To perform wide-awake tenolysis, the author injects 10 ml of 1% lidocaine with 1:100,000 epinephrine to the surgical field in each digit and the palm. Axillary block or general anesthesia are used if the surgeon expects an extensive operation, such as tenolysis in more than 2–3 digits, a staged reconstruction procedure, or if the patient is unlikely to tolerate surgery with local anesthesia.

Operative techniques

Through either a Bruner or midlateral incision, dissection proceeds from the unaffected area to the affected area. Tenolysis requires wider surgical exposure. All limiting adhesions are meticulously divided and care is taken to define the borders of the flexor tendons. During dissection, some surgeons advise preservation of the sheath as much as possible, but others prefer to excise the synovial sheath. Regardless, the

major pulleys should be maintained, and the synovial sheath imbedded within the scar is removed. It is necessary to maintain the A2 and A4 pulleys at a minimum. If possible, the A3 pulley and its adjacent sheath are also preserved. A variety of instruments may aid in dissection of the scarred tendons from inner surfaces of the major pulleys.^{289–291} Whenever possible, the FDS and FDP tendons are separated from one another. In some cases with severe adhesions, the FDS tendon has to be resected locally. Dissection is continued until normal tissues are revealed and no scar around the tendon is visible. Adequacy of the release is then checked by active digital flexion if the patient is wide-awake, or by a gentle proximal traction on the proximal part of the tendon. A separate proximal incision in the palm can be created to pull the tendon. The quality of the tendon and integrity of the pulleys are checked. If tendon continuity is maintained only by scar or greater than one-third of the tendon width is lost, the tendon is unlikely to function properly and the case should proceed to staged tendon reconstruction. If the critical pulleys are destroyed, it is appropriate to proceed to pulley reconstruction (Box 9.11).

Over the years, many attempts have been made to develop strategies to block or limit adhesion formation.^{292–302} Thus far, few of these attempts have reliably reduced adhesions clinically and are used routinely. Some surgeons favor use of steroids.²⁸⁶ One multicenter clinical trial indicated benefits of using a hyaluronan gel in reducing adhesions after tenolysis.³⁰³




Fig. 9.54 Distal junction of the tendon implant in stage 1. **(A)** The distal junction wire method. A figure-of-eight suture of a monofilament wire (no. 32) is placed in the implant and sutured to the FDP stump. Additional sutures are supplemented on each side of the implant. **(B)** Screw-plate fixation method. A self-taping Woodruff screw (2-mm) is used, which is inserted into a drill hole in the phalanx using a K-wire (0.035-inch).

Postoperative treatment

Oral analgesics usually alleviate pain during the postoperative period. Transcutaneous placement of local anesthetic catheters may be considered for patients with low pain thresholds or those undergoing extensive operations. Repeated digital nerve block can also be used.³⁰⁴ Active motion of the fingers can begin on the first day after surgery. Some surgeons advocate waiting for several days or until soft-tissue inflammation and pain subside to start motion.

Postoperative tendon movement is critical to the success of tenolysis and remains the most effective method to prevent recurrence of adhesions.^{305–309} The amplitude, frequency, and forces of motion should be decided based on intraoperative findings. The surgeons should directly discuss with the therapists to consolidate a therapy program. A tendon appearing nearly normal in a minimally scarred bed with a strong pulley system is appropriate for a more vigorous motion protocol. When a tendon is of poor quality – with a dense scar, a lysed segment, or a decrease in tendon caliber – or if pulleys have been reconstructed, gentle active motion or delayed initiation of the finger motion are indicated.²³⁴ In this instance, a “place and hold” maneuver after passive digital motion into full flexion is useful to reduce tension and the likelihood of tendon disruption. Passive motion of the fingers is helpful in preventing finger joint contractures and in decreasing the resistance to active finger movement. The motion program usually is continued for 4–6 weeks.

Future directions

Though most hand surgeons are performing a stronger primary flexor tendon repair than previously, postoperative motion regimes have not been updated and active flexion exercises have yet to be used in some regions or units. The most efficient rehabilitation protocols for the hand with various injury conditions remain to be determined. Some surgeons or therapists advocate early hand and wrist mobilization with short splints from fingertip to the wrist. Though this appears to have merits and is reasonable, we are awaiting for validation with the scope of its application being defined. Currently, traditional tendon-to-bone junction repairs have been questioned and alternatives are sought, but it remains to be determined mechanically and clinically what methods can reliably replace traditional pullout repairs. Wide-awake flexor tendon repair has become a favorite practice of some surgeons (including the author); we anticipate greater popularity. Reducing adhesion formation in severely jeopardized tendons, a long tendon defect, or loss of multiple tendons (which are often seen in complex or extensive hand or forearm injuries) continue to present major clinical challenges and are unsolved problems. We expect that advancements in basic science – in biological modulation of tendon healing and adhesion formation, development of engineered tendon grafts or tendon allografts – will help provide solutions to these very difficult conditions associated with tendon injuries.

BOX 9.11 Tenolysis

1. Local anesthesia is advised, to allow active finger flexion when needed during surgery.
2. Adequate surgical exposure is required to expose all adhesions.
3. Preserve the critically located annular pulleys (A2 and A4 as a minimal).
4. Check mobility of the released tendon to confirm adequacy of surgery.
5. Postoperative motion is paramount to the success of this procedure.
6. Rigor of motion regimes is decided according to intraoperative findings of the released tendons. Motion exercise should always be applied and continued for 4–6 weeks.





Fig. 9.55 In stage 2, the tendon implant is replaced by a tendon graft. **(A)** The implant is exposed through a small incision at the distal part of the finger. After being disconnected from the flexor digitorum profundus tendon stump, the implant is sutured to the tendon graft. The implant is pulled proximally through the newly formed sheath to lead the grafted tendon. **(B)** The graft has been tunneled in the hand. The distal tendon junction is completed in a way similar to tendon grafting either through a pullout suture or a robust direct suture repair. The proximal junction of the graft is made at either the distal forearm or the palm as shown. **(C)** An intraoperative view of pulling the implant out of the finger. Note the proximal end of the implant was sutured to the grafted tendon. Therefore, after the implant was pulled out, the grafted tendon was inside the sheath. **(D)** The distal end of the graft was securely sutured directly to the distal stump of the FDP tendon, which is my preferred method in recent years.



Access the complete reference list online at <http://www.expertconsult.com>

19. Tang JB. Indications, methods, postoperative motion and outcome evaluation of primary flexor tendon repairs in Zone 2. *J Hand Surg (Eur)*. 2007;32:118–129. This article provides a comprehensive and updated review of the current indications for primary tendon repairs in zone 2. The author's techniques of multi-strand repairs and rehabilitation are detailed. Most importantly, the author defines the needs, mechanical basis, and areas of releasing the critical parts of the major digital annular pulleys to facilitate tendon repairs. The author highlights the importance of releasing the critical pulley parts and strong surgical repairs in achieving predictable primary flexor tendon repairs in this most difficult area. Subdivision of zone 2 and novel criteria for outcome evaluation are also presented in this article.
25. Giesen T, Sirotakova M, Copsey AJ, Elliot D. Flexor pollicis longus primary repair: further experience with the Tang technique and controlled active mobilisation. *J Hand Surg (Eur)*. 2009;34:758–761. This clinical study reported the most up-to-date clinical outcomes of repairs of lacerated flexor pollicis longus (FPL) tendons from a renowned center dealing with flexor tendon injuries. These authors have made a series of reports of their results in treating FPL injuries over the past two decades; this most recent report documents their outcomes in 50 FPL injuries. With a six-strand core tendon repair alone (without peripheral repairs), they achieved good or excellent functional recovery in 80% of thumbs, with zero tendon rupture with an active motion regime. These are the best clinical results of FPL tendon repairs reported thus far. It is worth noting that the authors did not elaborate peripheral sutures in these FPL tendon repairs, and the oblique pulley in the thumb was vented to accommodate tendon repairs.
42. Boyes JH, Stark HH. Flexor-tendon grafts in the fingers and thumb. A study of factors influencing results in 1000 cases. *J Bone Joint Surg Am*. 1971;53:1332–1342. This classic article reported perhaps the largest case series of free tendon grafting in the fingers and thumbs. The authors analyzed the factors influencing the prognosis for free tendon grafting and showed that the tendon grafting procedure used can produce clinically acceptable function. However, hand conditions are extremely important. Prognostic factors include conditions of the soft tissues and joints. Extensively scarred tendon bed and joint damage led to the worst prognosis after tendon graft surgeries.
46. Hunter JM, Salisbury RE. Flexor-tendon reconstruction in severely damaged hands. A two-stage procedure using a silicone Dacron reinforced gliding prosthesis prior to tendon grafting. *J Bone Joint Surg Am*. 1971;53:829–858.
123. Lalonde DH, Martin AL. Wide-awake flexor tendon repair and early tendon mobilization in zones 1 and 2. *Hand Clin*. 2013;29:207–213. This article provides details on how surgeons can repair flexor tendon under local anesthesia with tourniquet control and how the patient can actively move the repaired digit during surgery to ascertain the repair is strong and appropriate for early active motion. Early active motion protocols used by the authors are also illustrated in details.

149. Elliot D, Giesen T. Primary flexor tendon surgery: the search for a perfect result. *Hand Clin.* 2013;29:191–206.
150. Tang JB, Chang J, Elliot D, et al. IFSSH Flexor Tendon Committee report 2014: from the IFSSH Flexor Tendon Committee. *J Hand Surg (Eur)*. 2014;39:107–115.
173. Tang JB. Release of the A4 pulley to facilitate zone II flexor tendon repair. *J Hand Surg Am.* 2014;39:2300–2307.
213. Tang JB, Amadio PC, Boyer MI, et al. Current practice of primary flexor tendon repair: a global view. *Hand Clin.* 2013;29:179–189.
233. Strickland JW. Delayed treatment of flexor tendon injuries including grafting. *Hand Clin.* 2005;21:219–243. *This is an extensive review of secondary tendon surgeries, covering indications, techniques, and postoperative care of free tendon grafting, staged tendon reconstruction, and tenolysis. This article is the most recent in an array of reviews about techniques for flexor tendon surgeries written by an experienced hand surgeon. This article provides an update on historical developments of surgical techniques, the author's personal approaches, and current practice of these secondary repair procedures, which are generally considered classic operations, little changed over recent decades.*

References

- Potenza AD. Tendon healing within the flexor digital sheath in the dog. *J Bone Joint Surg Am.* 1962;44:49–64.
- Peacock EE. Fundamental aspect of wound healing relating to the restoration of gliding function after tendon repair. *Surg Gynecol Obstet.* 1964;119:241–250.
- Peacock EE. Biological principles in the healing of long tendons. *Surg Clin North Am.* 1965;45:461–476.
- Potenza AD. Mechanisms of healing of digital flexor tendons. *Hand.* 1969;1:40–41.
- Matthews P, Richards H. The repair potential of digital flexor tendons. *J Bone Joint Surg Br.* 1974;56:618–625.
- Lundborg G. Experimental flexor tendon healing without adhesion formation—a new concept of tendon nutrition and intrinsic healing mechanisms. *Hand.* 1976;8:235–238.
- Lundborg G, Rank F, Heinau B. Intrinsic tendon healing. A new experimental model. *Scand J Plast Reconstr Surg.* 1985;19:113–117.
- Katsumi M, Tajima T. Experimental investigation of healing process of tendons with or without synovial coverage in or outside of synovial cavity. *J Niigata Med Assoc.* 1981;95:532–567.
- Manske PR, Gelberman RH, Vande Berg J, Lesker PA. Flexor tendon repair: morphological evidence of intrinsic healing in vitro. *J Bone Joint Surg Am.* 1984;66:385–396.
- Gelberman RH, Manske PR, Vande Berg JS, Lesker PA, Akeson WH. Flexor tendon healing in vitro: comparative histologic study of rabbit, chicken, dog and monkey. *J Orthop Res.* 1984;2:39–48.
- Verdan CE. Primary repair of flexor tendons. *J Bone Joint Surg Am.* 1960;42:647–657.
- Kleinert HE, Kutz JE, Ashbell TS, Martinez E. Primary repair of lacerated flexor tendons in “No Man’s Land”. [abstract]. *J Bone Joint Surg Am.* 1967;49:577.
- Savage R. In vitro studies of a new method of flexor tendon repair. *J Hand Surg [Br].* 1985;10:135–141.
- Savage R, Risitano G. Flexor tendon repair using a “six strand” method of repair and early active mobilization. *J Hand Surg [Br].* 1989;14:396–399.
- Strickland JW, Glogovac SV. Digital function following flexor tendon repair in zone II: a comparison of immobilization and controlled passive motion techniques. *J Hand Surg Am.* 1980;5:537–543.
- McLarney E, Hoffman H, Wolfe SW. Biomechanical analysis of the cruciate four-strand flexor tendon repair. *J Hand Surg [Br].* 1999;24:295–301.
- Tang JB, Shi D, Gu YQ, Chen JC, Zhou B. Double and multiple looped suture tendon repair. *J Hand Surg [Br].* 1994;19:699–703.
- Tang JB, Wang B, Chen F, Pan CZ, Xie RG. Biomechanical evaluation of flexor tendon repair techniques. *Clin Orthop Relat Res.* 2001;386:252–259.
- Tang JB. Indications, methods, postoperative motion and outcome evaluation of primary flexor tendon repairs in Zone 2. *J Hand Surg (Eur).* 2007;32:118–129. *This article provides a comprehensive and updated review of the current indications for primary tendon repairs in zone 2. The author’s techniques of multistrand repairs and rehabilitation are detailed. Most importantly, the author defines the needs, mechanical basis, and areas of releasing the critical parts of the major digital annular pulleys to facilitate tendon repairs. The author highlights the importance of releasing the critical pulley parts and strong surgical repairs in achieving predictable primary flexor tendon repairs in this most difficult area.*
- Moiemen NS, Elliot D. Early active mobilization of primary flexor tendon repairs in zone 1. *J Hand Surg [Br].* 2000;25:78–84.
- Tang JB. Flexor tendon repairs in zone IIC. *J Hand Surg [Br].* 1994;19:72–75.
- Tang JB. The double sheath system and tendon gliding in zone IIC. *J Hand Surg [Br].* 1995;20:281–285.
- Kwai Ben I, Elliot D. Venting or partial release of the A2 and A4 pulleys after repair of zone II flexor tendon injuries. *J Hand Surg [Br].* 1998;23:649–654.
- Al-Qattan MM, Al-Turaiki TM. Flexor tendon repair in zone 2 using a six-strand ‘figure of eight’ suture. *J Hand Surg (Eur).* 2009;34:322–328.
- Giesen T, Sirotakova M, Copsey AJ, Elliot D. Flexor pollicis longus primary repair: further experience with the Tang technique and controlled active mobilisation. *J Hand Surg (Eur).* 2009;34:758–761. *This clinical study reported the most up-to-date clinical outcomes of repairs of lacerated flexor pollicis longus (FPL) tendons from a renowned center dealing with flexor tendon injuries. These authors have made a series of reports of their results in treating FPL injuries over the past two decades; this most recent report documents their outcomes in 50 FPL injuries. With a six-strand core tendon repair alone (without peripheral repairs), they achieved good or excellent functional recovery in 80% of thumbs, with zero tendon rupture with an active motion regime. These are the best clinical results of FPL tendon repairs reported thus far. It is worth noting that the authors did not elaborate peripheral sutures in these FPL tendon repairs, and the oblique pulley in the thumb was vented to accommodate tendon repairs.*
- Manske PR. History of flexor tendon repair. *Hand Clin.* 2005;21:123–127.
- Mason ML, Shearon CG. The process of tendon repair. An experimental study of tendon suture and tendon graft. *Arch Surg.* 1932;25:615–692.
- Salomon A. Klinische und experimentelle Untersuchungen über Heilung von Schnenverletzungen insbesondere innerhalb der Sehnenscheiden. *Arch Klin Chir.* 1924;129:397.
- Salomon A. Ueber den Ersatz grosser Sehnendefekte durch Regeneration. *Arch Klin Chir.* 1919;113:30.
- Bunnell S. Repair of tendons in the fingers and description of two new instruments. *Surg Gynecol Obstet.* 1918;26:103–110.
- Bunnell S. Repair of tendons in the fingers. *Surg Gynecol Obstet.* 1922;35:88–97.
- Garlock JH. Repair of wounds of the flexor tendons of the hand. *Ann Surg.* 1926;83:111–122.
- Mason ML. Primary and secondary tendon suture. A discussion of the significance of technique in tendon surgery. *Surg Gyn Obstet.* 1940;70:392–402.
- Lexer E. Did Verwehtung der freien Schnenstransplantation. *Arch Klin Chir.* 1912;98:818–825.
- Mayer L. The physiological method of tendon transplantation. I. Historical, anatomy, and physiology of tendons. *Surg Gynecol Obstet.* 1916;22:182–197.
- Mayer L. The physiological method of tendon transplantation. II. Operative technique. *Surg Gynecol Obstet.* 1916;22:298–306.
- Mayer L. The physiological method of tendon transplantation. III. Experimental and clinical experiences. *Surg Gynecol Obstet.* 1916;22:472–481.
- Pulvertaft RG. Repair of tendon injuries in the hand. *Ann R Coll Surg Engl.* 1948;3:3–14.
- Graham WC. Flexor tendon grafts to the finger and thumb. *J Bone Joint Surg Am.* 1947;29:553–559.
- Littler JW. Free tendon grafts in secondary flexor tendon repair. *Am J Surg.* 1947;74:315–321.
- Boyes JH. Why tendon repair? *J Bone Joint Surg Am.* 1959;41:577–579.
- Boyes JH, Stark HH. Flexor-tendon grafts in the fingers and thumb. A study of factors influencing results in 1000 cases. *J Bone Joint Surg Am.* 1971;53:1332–1342. *This classic article reported perhaps the largest case series of free tendon grafting in the fingers and thumbs. The authors analyzed the factors influencing the prognosis for free tendon grafting and showed that the tendon grafting procedure used can produce clinically acceptable function. However, hand conditions are extremely important. Prognostic factors include conditions of the soft tissues and joints.*
- Mayer L. Celloidin tube reconstruction of extensor communis sheath. *Bull Hosp Joint Dis Orthop Inst.* 1940;1:39.
- Bassett CAL, Carroll RE. Formation of tendon sheaths by silicone rod implants. Proceedings of American Society for Surgery of the Hand. *J Bone Joint Surg Am.* 1963;45:884.

45. Hunter JM. Artificial tendons. Early development and application. *Am J Surg*. 1965;109:325.
46. Hunter JM, Salisbury RE. Flexor-tendon reconstruction in severely damaged hands. A two-stage procedure using a silicone Dacron reinforced gliding prosthesis prior to tendon grafting. *J Bone Joint Surg Am*. 1971;53:829–858.
47. Manske PR, Bridwell K, Lesker PA. Nutrient pathways to flexor tendons of chickens using tritiated proline. *J Hand Surg Am*. 1978;3:352–357.
48. Manske PR, Bridwell K, Whiteside LA, Lesker PA. Nutrition of flexor tendon in monkeys. *Clin Orthop Relat Res*. 1978;136:294–298.
49. Manske PR, Lesker PA. Nutrient pathways of flexor tendons in primates. *J Hand Surg*. 1982;7A:436–447.
50. Manske PR, Lesker PA. Comparative nutrient pathways to the flexor profundus tendons in zone II of various experimental animals. *J Surg Res*. 1983;34:83–93.
51. Matthew P. The fate of isolated segments of flexor tendons within the digital sheath. *Br J Plast Surg*. 1976;28:216–224.
52. Matthews P, Richards H. The repair reaction of flexor tendon within the digital sheath. *Hand*. 1975;7:27–29.
53. Matthews P, Richards H. Factors in the adherence of flexor tendons after repair. *J Bone Joint Surg*. 1976;58B:230–236.
54. Matthew P. The fate of isolated segments of flexor tendons within the digital sheath. *Br J Plast Surg*. 1976;28:216–224.
55. Lindsay WK, Thomson HG. Digital flexor tendons: an experimental study (part I). The significance of each compartment of the flexor mechanism in tendon healing. *Br J Plast Surg*. 1959;12:289–316.
56. Lindsay WK, Thomson HG, Walker FG. Digital flexor tendon: an experimental study (part II). The significance of a gap occurring at the line of suture. *Br J Plast Surg*. 1960;13:1–9.
57. Lindsay WK, McDougall EP. Digital flexor tendons: an experimental study (part III). The fate of autogenous digital flexor tendon grafts. *Br J Plast Surg*. 1961;13:293–304.
58. Manske PR, Lesker PA. Histological evidence of flexor tendon repair in various experimental animals. An in vitro study. *Clin Orthop*. 1984;182:353–360.
59. Manske PR, Lesker PA. Biochemical evidence of flexor tendon participation in the repair process—an in vitro study. *J Hand Surg [Br]*. 1984;9:117–120.
60. Gelberman RH, Manske PR, Vande Berg JS, et al. Flexor tendon healing in vitro: comparative histologic study of rabbit, chicken, dog and monkey. *J Orthop Res*. 1984;2:39–48.
61. Mass DP, Tuel R. Human flexor tendon participation in the in vitro repair process. *J Hand Surg Am*. 1989;14:64–71.
62. Pribaz JJ, Morrison WA, Macleod AM. Primary repair of flexor tendons in no man's land using the Becker repair. *J Hand Surg [Br]*. 1989;14:400–405.
63. Lee H. Double loop locking suture: a technique of tendon repair for early active mobilization. Part I: Evolution of technique and experimental study. *J Hand Surg Am*. 1990;15:945–952.
64. Silfverskiöld KL, May EJ, Törnvall AH. Gap formation during controlled motion after flexor tendon repair in zone II: a prospective clinical study. *J Hand Surg Am*. 1992;17:539–546.
65. Greenwald DP, Randolph MA, Hong HZ, May JW Jr. Augmented Becker versus modified Kessler tenorrhaphy in monkeys: dynamic mechanical analysis. *J Hand Surg Am*. 1995;20:267–272.
66. Taras JS, Skahen JR, Raphael JS, et al. The double-grasping and cross-stitch for acute flexor tendon repair. *Atlas Hand Clin*. 1996;1:13–28.
67. Sandow MJ, McMahon MM. Single-cross grasp six-strand repair for acute flexor tendon tenorrhaphy. *Atlas Hand Clin*. 1996;1:41–64.
68. Lim BH, Tsai TM. The six-strand techniques for flexor tendon repair. *Atlas Hand Clin*. 1996;1:65–76.
69. Winters SC, Gelberman RH, Woo SL, et al. The effects of multiple-strand suture methods on the strength and excursion of repaired intrasynovial flexor tendons: A biomechanical study in dogs. *J Hand Surg Am*. 1998;23:97–104.
70. Sirotakova M, Elliot D. Early active mobilization of primary repairs of the flexor pollicis longus tendon with two Kessler two-strand core sutures and a strengthened circumferential suture. *J Hand Surg [Br]*. 2004;29:531–535.
71. Wang B, Xie RG, Tang JB. Biomechanical analysis of a modification of Tang method of tendon repair. *J Hand Surg [Br]*. 2003;28:347–350.
72. Cao Y, Tang JB. Biomechanical evaluation of a four-strand modification of the Tang method of tendon repair. *J Hand Surg [Br]*. 2005;30:374–378.
73. Manchio JV, Shashikant MP, Shrivastava A, et al. Evaluation of a new 4-strand flexor tendon repair in a cadaveric porcine model. *J Hand Surg Am*. 2009;34:102–107.
74. Gelberman RH, Boyer MI, Brodt MD, et al. The effect of gap formation at the repair site on the strength and excursion of intrasynovial flexor tendons. An experimental study on the early stages of tendon-healing in dogs. *J Bone Joint Surg Am*. 1999;81:975–982.
75. Gelberman RH, Siegel DB, Woo SL, et al. Healing of digital flexor tendons: importance of the interval from injury to repair. A biomechanical, biochemical, and morphological study in dogs. *J Bone Joint Surg Am*. 1991;73:66–75.
76. Urbaniak JR, Cahill JD, Mortenson RA. Tendon suturing methods: analysis of tensile strengths. In: *AAOS Symposium on Tendon Surgery in the Hand*. St. Louis: CV Mosby Co.; 1975:70–80.
77. Kubota H, Manske PR, Aoki M, et al. Effect of motion and tension on injured flexor tendons in chickens. *J Hand Surg Am*. 1996;21:456–463.
78. Aoki M, Kubota H, Pruitt DL, Manske PR. Biomechanical and histologic characteristics of canine flexor tendon repair using early postoperative mobilization. *J Hand Surg Am*. 1997;22:107–114.
79. Hotokezaka S, Manske PR. Differences between locking loops and grasping loops: effects on 2-strand core suture. *J Hand Surg Am*. 1997;22:995–1003.
80. Hatanaka H, Manske PR. Effect of suture size on locking and grasping flexor tendon repair techniques. *Clin Orthop Relat Res*. 2000;375:267–274.
81. Komanduri M, Phillips CS, Mass DP. Tensile strength of flexor tendon repairs in a dynamic cadaver model. *J Hand Surg Am*. 1996;21:605–611.
82. Alavanja G, Dailey E, Mass DP. Repair of zone II flexor digitorum profundus lacerations using varying suture sizes: a comparative biomechanical study. *J Hand Surg Am*. 2005;30:448–454.
83. Walbeehm ET, De Wit T, Hovius SE, McGrouther DA. Influence of core suture geometry on tendon deformation and gap formation in porcine flexor tendons. *J Hand Surg [Br]*. 2009;34:190–195.
84. Kim JB, de Wit T, Hovius SE, et al. What is the significance of tendon suture purchase? *J Hand Surg (Eur)*. 2009;34:497–502.
85. Xie RG, Zhang S, Tang JB, Chen F. Biomechanical studies of 3 different 6-strand flexor tendon repair techniques. *J Hand Surg Am*. 2002;27:621–627.
86. Tang JB, Tan J, Xu Y. Lengthening and locking: 2 ways to improve repair strength of obliquely lacerated tendons. *J Hand Surg Am*. 2003;28:832–837.
87. Tan J, Wang B, Xu Y, Tang JB. Effects of direction of tendon lacerations on strength of tendon repairs. *J Hand Surg Am*. 2003;28:237–242.
88. Tan J, Tang JB. Locking repairs for obliquely cut tendons: Effects of suture purchase and directions of locking circles. *J Hand Surg Am*. 2004;29:891–897.
89. Tang JB, Xu Y, Wang B. Repair strength of tendons of varying gliding curvature: a study in a curvilinear model. *J Hand Surg Am*. 2003;28:243–249.
90. Tang JB, Cao Y, Xie RG. Effects of tension direction on strength of tendon repair. *J Hand Surg Am*. 2001;26:1105–1110.
91. Xie RG, Xue HG, Gu JH, et al. Effects of locking area on strength of 2- and 4-strand locking tendon repairs. *J Hand Surg Am*. 2005;30:455–460.
92. Xie RG, Tang JB. Investigation of locking configurations for tendon repair. *J Hand Surg Am*. 2005;30:461–465.

93. Tang JB, Zhang Y, Cao Y, Xie RG. Core suture purchase affects strength of tendon repairs. *J Hand Surg Am.* 2005;30:1262–1266.
94. Cao Y, Zhu B, Xie RG, Tang JB. Influence of core suture purchase length on strength of four-strand tendon repairs. *J Hand Surg Am.* 2006;31:107–112.
95. Miller B, Dodds SD, deMars A, et al. Flexor tendon repairs: the impact of fiberwire on grasping and locking core sutures. *J Hand Surg Am.* 2007;32:591–596.
96. Thurman RT, Trumble TE, Hanel DP, et al. Two-, four-, and six-strand zone II flexor tendon repairs: an in situ biomechanical comparison using a cadaver model. *J Hand Surg Am.* 1998;23:261–265.
97. Barrie KA, Tomak SL, Cholewicki J, Wolfe SW. The role of multiple strands and locking sutures on gap formation of flexor tendon repairs during cyclical loading. *J Hand Surg Am.* 2000;25:714–720.
98. Wu YF, Tang JB. Effects of tension across the tendon repair site on tendon gap and ultimate strength. *J Hand Surg Am.* 2012;37:906–912.
99. Uchiyama S, Amadio PC, Coert JH, et al. Gliding resistance of extrasynovial and intrasynovial tendons through the A2 pulley. *J Bone Joint Surg Am.* 1997;79:219–224.
100. Paillard PJ, Amadio PC, Zhao C, et al. Pulley plasty versus resection of one slip of the flexor digitorum superficialis after repair of both flexor tendons in zone II: a biomechanical study. *J Bone Joint Surg Am.* 2002;84:2039–2045.
101. Zhao C, Amadio PC, Zobitz ME, An KN. Resection of the flexor digitorum superficialis reduces gliding resistance after zone II flexor digitorum profundus repair in vitro. *J Hand Surg Am.* 2002;27:316–321.
102. Silva JM, Zhao C, An KN, et al. Gliding resistance and strength of composite sutures in human flexor digitorum profundus tendon repair: an in vitro biomechanical study. *J Hand Surg Am.* 2009;34:87–92.
103. Zhao CF, Amadio PC, Berglund L, An KN. The A3 pulley. *J Hand Surg Am.* 2000;25:270–276.
104. Tang JB, Shi D, Zhang QG. Biomechanical and histologic evaluation of tendon sheath management. *J Hand Surg Am.* 1996;21:900–908.
105. Xu Y, Tang JB. Effects of superficialis tendon repairs on lacerated profundus tendons within or proximal to the A2 pulley: an *in vivo* study in chickens. *J Hand Surg Am.* 2003;28:994–1001.
106. Tang JB, Wang YH, Gu YT, Chen F. Effect of pulley integrity on excursions and work of flexion in healing flexor tendons. *J Hand Surg Am.* 2001;26:347–353.
107. Tang JB, Xie RG. Effect of A3 pulley and adjacent sheath integrity on tendon excursion and bowstringing. *J Hand Surg Am.* 2001;26:855–861.
108. Tang JB, Xie RG, Cao Y, et al. A2 pulley incision or one slip of the superficialis improves flexor tendon repairs. *Clin Orthop Relat Res.* 2007;456:121–127.
109. Tang JB, Cao Y, Wu YF, Wang GH. Effect of A2 pulley release on repaired tendon gliding resistance and rupture in a chicken model. *J Hand Surg Am.* 2009;34:1080–1087.
110. Cao Y, Tang JB. Strength of tendon repair decreases in the presence of an intact A2 pulley: biomechanical study in a chicken model. *J Hand Surg Am.* 2009;34:1763–1770.
111. Mitsionis G, Bastidas JA, Grewal R, et al. Feasibility of partial A2 and A4 pulley excision: effect on finger flexor tendon biomechanics. *J Hand Surg Am.* 1999;24:310–314.
112. Tomaino M, Mitsionis G, Bastidas J, et al. The effect of partial excision of the A2 and A4 pulleys on the biomechanics of finger flexion. *J Hand Surg [Br].* 1998;23:50–52.
113. Boyer MI, Ditsios K, Gelberman RH, et al. Repair of flexor digitorum profundus tendon avulsions from bone: an ex vivo biomechanical analysis. *J Hand Surg Am.* 2002;27:594–598.
114. Boyer MI, Gelberman RH, Burns ME, et al. Intrasynovial flexor tendon repair. An experimental study comparing low and high levels of in vivo force during rehabilitation in canines. *J Bone Joint Surg Am.* 2001;83:891–899.
115. Boyer MI, Ditsios K, Gelberman RH, et al. Repair of flexor digitorum profundus tendon avulsions from bone: an ex vivo biomechanical analysis. *J Hand Surg Am.* 2002;27:594–598.
116. Barrie KA, Tomak SL, Cholewicki J, et al. Effect of suture locking and suture caliber on fatigue strength of flexor tendon repairs. *J Hand Surg Am.* 2001;26:340–346.
117. Taras JS, Raphael JS, Marczyk SC, Bauerle WB. Evaluation of suture caliber in flexor tendon repair. *J Hand Surg Am.* 2001;26:1100–1104.
118. Zhao C, Amadio PC, Paillard P, et al. Digital resistance and tendon strength during the first week after flexor digitorum profundus tendon repair in a canine model in vivo. *J Bone Joint Surg Am.* 2004;86:320–327.
119. Xie RG, Cao Y, Xu XF, Zhu B. The gliding force and work of flexion in the early days after primary repair of lacerated flexor tendons: an experimental study. *J Hand Surg (Eur).* 2008;33:192–196.
120. Cao Y, Tang JB. Investigation of resistance of digital subcutaneous edema to gliding of the flexor tendon: an in vitro study. *J Hand Surg Am.* 2005;30:1248–1254.
121. Cao Y, Tang JB. Resistance to motion of flexor tendons and digital edema: An in vivo study in a chicken model. *J Hand Surg Am.* 2006;31:1645–1651.
122. Cao Y, Chen CH, Wu YF, et al. Digital oedema, adhesion formation and resistance to digital motion after primary flexor tendon repair. *J Hand Surg (Eur).* 2008;33:745–752.
123. Lalonde DH, Martin AL. Wide-awake flexor tendon repair and early tendon mobilization in zones 1 and 2. *Hand Clin.* 2013;29:207–213. *This article provides details on how surgeons can repair flexor tendon under local anesthesia with tourniquet control and how the patient can actively move the repaired digit during surgery to ascertain the repair is strong and appropriate for early active motion.*
124. Lalonde DH. Wide-awake flexor tendon repair. *Plast Reconstr Surg.* 2009;123:623–625.
125. Chang J, Most D, Thunder R, et al. Molecular studies in flexor tendon wound healing: the role of basic fibroblast growth factor gene expression. *J Hand Surg Am.* 1998;23:1052–1058.
126. Chang J, Thunder R, Most D, et al. Studies in flexor tendon wound healing: neutralizing antibody to TGF-beta1 increases postoperative range of motion. *Plast Reconstr Surg.* 2000;105:148–155.
127. Ngo M, Pham H, Longaker MT, Chang J. Differential expression of transforming growth factor-beta receptors in a rabbit zone II flexor tendon wound healing model. *Plast Reconstr Surg.* 2001;108:1260–1267.
128. Klein MB, Yalamanchi N, Pham H, et al. Flexor tendon healing in vitro: effects of TGF-beta on tendon cell collagen production. *J Hand Surg Am.* 2002;27:615–620.
129. Hsu C, Chang J. Clinical implications of growth factors in flexor tendon wound healing. *J Hand Surg Am.* 2004;29:551–563.
130. Zhang AY, Pham H, Ho F, et al. Inhibition of TGF-beta-induced collagen production in rabbit flexor tendons. *J Hand Surg Am.* 2004;29:230–235.
131. Yalamanchi N, Klein MB, Pham HM, et al. Flexor tendon wound healing in vitro: lactate up-regulation of TGF-beta expression and functional activity. *Plast Reconstr Surg.* 2004;113:625–632.
132. Bates SJ, Morrow E, Zhang AY, et al. Mannose-6-phosphate, an inhibitor of transforming growth factor-beta, improves range of motion after flexor tendon repair. *J Bone Joint Surg Am.* 2006;88:2465–2472.
133. Costa MA, Wu C, Pham BV, et al. Tissue engineering of flexor tendons: optimization of tenocyte proliferation using growth factor supplementation. *Tissue Eng.* 2006;12:1937–1943.
134. Chong AK, Riboh J, Smith RL, et al. Flexor tendon tissue engineering: acellularized and reseeded tendon constructs. *Plast Reconstr Surg.* 2009;123:1759–1766.
135. Chang J. Studies in flexor tendon reconstruction: biomolecular modulation of tendon repair and tissue engineering. *J Hand Surg Am.* 2012;37:552–561.

136. Galvez MG, Crowe C, Farnebo S, Chang J. Tissue engineering in flexor tendon surgery: current state and future advances. *J Hand Surg (Eur)*. 2014;39:71–78.
137. Tang JB, Xu Y, Ding F, Wang XT. Tendon healing *in vitro*: promotion of collagen gene expression by bFGF with NF- κ B gene activation. *J Hand Surg Am*. 2003;28:215–220.
138. Tang JB, Xu Y, Wang XT. Tendon healing *in vitro*: activation of NIK, IKK α , IKK β , and NF- κ B genes in signal pathway and proliferation of tenocytes. *Plast Reconstr Surg*. 2004;113:1703–1711.
139. Wang XT, Liu PY, Tang JB. Tendon healing *in vitro*: genetic modification of tenocytes with exogenous PDGF gene and promotion of collagen gene expression. *J Hand Surg Am*. 2004;29:884–890.
140. Wang XT, Liu PY, Xin KQ, Tang JB. Tendon healing *in vitro*: bFGF gene transfer to tenocytes by adeno-associated viral vectors promotes expression of collagen genes. *J Hand Surg Am*. 2005;30:1255–1261.
141. Wang XT, Liu PY, Tang JB, et al. Tendon healing *in vitro*: adeno-associated virus-2 effectively transduces intrasynovial tenocytes with persistent expression of the transgene, but other serotypes do not. *Plast Reconstr Surg*. 2007;119:227–234.
142. Tang JB, Cao Y, Zhu B, et al. Adeno-associated virus-2-mediated bFGF gene transfer to digital flexor tendons significantly increases healing strength: an *in vivo* study. *J Bone Joint Surg Am*. 2008;90:1078–1089.
143. Chen CH, Cao Y, Wu YF, et al. Tendon healing *in vivo*: gene expression and production of multiple growth factors in early tendon healing period. *J Hand Surg Am*. 2008;33:1834–1842.
144. Chen CH, Zhou YL, Wu YF, et al. Effectiveness of microRNA in down-regulation of TGF- β gene expression in digital flexor tendons of chickens: *in vitro* and *in vivo* study. *J Hand Surg Am*. 2009;34:1777–1784.
145. Wu YF, Chen CH, Cao Y, et al. Molecular events of cellular apoptosis and proliferation in the early tendon healing period. *J Hand Surg Am*. 2010;35:2–10.
146. Verdan CE. Half a century of flexor tendon surgery. *J Bone Joint Surg Am*. 1972;54:472–491.
147. Manske PR. Flexor tendon healing. *J Hand Surg [Br]*. 1988;13:237–245.
148. Strickland JW. Development of flexor tendon surgery: twenty-five years of progress. *J Hand Surg Am*. 2000;25:214–235.
149. Elliot D, Giesen T. Primary flexor tendon surgery: the search for a perfect result. *Hand Clin*. 2013;29:191–206.
150. Tang JB, Chang J, Elliot D, et al. IFSSH Flexor Tendon Committee report 2014: from the IFSSH Flexor Tendon Committee. *J Hand Surg (Eur)*. 2014;39:107–115.
151. Doyle JR. Anatomy of the flexor tendon sheath and pulley system. *J Hand Surg Am*. 1988;13:473–483.
152. Manske PR, Lesker PA. Palmar aponeurosis pulley. *J Hand Surg Am*. 1983;8:259–263.
153. Kleinert HE, Verdan C. Report of the Committee on Tendon Injuries. *J Hand Surg Am*. 1983;8:794–798.
154. Schuind F, Garcia-Elias M, Cooney WP 3rd, An KN. Flexor tendon forces: *in vivo* measurements. *J Hand Surg Am*. 1992;17:291–298.
155. Brockardt CJ, Sullivan LG, Watkins BE, Wongworawat MD. Evaluation of simple and looped suture and new material for flexor tendon repair. *J Hand Surg (Eur)*. 2009;34:329–332.
156. Diao E, Hariharan JS, Soejima O, Lotz JC. Effect of peripheral suture depth on strength of tendon repairs. *J Hand Surg Am*. 1996;21:234–239.
157. Sood MK, Elliot D. A new technique of attachment of flexor tendons without a button tie over. *J Hand Surg [Br]*. 1996;21:629–632.
158. McCallister WV, Ambrose HC, Katolik LI, Trumble TE. Comparison of pullout button versus suture anchor for zone I flexor tendon repair. *J Hand Surg Am*. 2006;31:246–251.
159. Tripathi AK, Mee SNJ, Martin DL, Katsarma E. The transverse intraosseous loop technique (TILT) to re-insert flexor tendons in zone I. *J Hand Surg (Eur)*. 2009;34:85–89.
160. Tang JB. Uncommon methods of flexor tendon and tendon-bone repairs and grafting. *Hand Clin*. 2013;29:215–221.
161. Papandrea R, Seitz WH Jr, Shapiro P, Borden B. Biomechanical and clinical evaluation of the epitendon-first technique of flexor tendon repair. *J Hand Surg Am*. 1995;20:261–266.
162. Wu YF, Tang JB. Recent developments in flexor tendon repair techniques and factors influencing strength of the tendon repair. *J Hand Surg (Eur)*. 2014;39:6–19.
163. Viinikainen A, Göransson H, Huovinen K, et al. The strength of the 6-strand modified Kessler repair performed with triple-stranded or triple-stranded bound suture in a porcine extensor tendon model: an *ex vivo* study. *J Hand Surg Am*. 2007;32:510–517.
164. Eiken O, Rank F. Experimental restoration of the digital synovial sheath. *Scand J Plast Reconstr Surg*. 1977;11:213–218.
165. Lister G. Indications and techniques for repair of the flexor tendon sheath. *Hand Clin*. 1985;1:85–95.
166. Peterson WW, Manske PR, Kain CC, Lesker PA. Effect of flexor sheath integrity on tendon gliding: a biomechanical and histologic study. *J Orthop Res*. 1986;4:458–465.
167. Saldana MJ, Ho PK, Lichtman DM, et al. Flexor tendon repair and rehabilitation in zone II open sheath technique versus closed sheath technique. *J Hand Surg Am*. 1987;12:1110–1114.
168. Peterson WW, Manske PR, Dunlap J, et al. Effect of various methods of restoring flexor sheath integrity on the formation of adhesions after tendon injury. *J Hand Surg Am*. 1990;15:48–56.
169. Gelberman RH, Woo SL, Amiel D, et al. Influences of flexor sheath continuity and early motion on tendon healing in dogs. *J Hand Surg Am*. 1990;15:69–77.
170. Tang JB, Ishii S, Usui M. Surgical management of the tendon sheath at different repair stages. Biomechanical and morphological evaluations of direct sheath closure, partial sheath excision, and interposing sheath grafting. *Chin Med J*. 1990;103:295–303.
171. Tang JB, Ishii S, Usui M, Yamamura T. Flexor sheath closure during delayed primary tendon repair. *J Hand Surg Am*. 1994;19:636–640.
172. Tang JB. Clinical outcomes associated with flexor tendon repair. *Hand Clin*. 2005;21:199–210.
173. Tang JB. Release of the A4 pulley to facilitate zone II flexor tendon repair. *J Hand Surg Am*. 2014;39:2300–2307.
174. Bakhach J, Sentucq-Rigal J, Mouton P, et al. The Omega “Omega” pulley plasty. A new technique to increase the diameter of the annular flexor digital pulleys. *Ann Chir Plast Esthet*. 2005;50:705–714.
175. Bunata RE, Kosmopoulos V, Simmons S, et al. Primary tendonsheath enlargement and reconstruction in zone 2: An *in vitro* biomechanical study on tendon gliding resistance. *J Hand Surg Am*. 2009;34:1436–1443.
176. Tang JB, Zhang QG, Ishii S. Autogenous free sheath grafts in reconstruction of injured digital flexor tendon sheath at the delayed primary stage. *J Hand Surg [Br]*. 1993;18:31–32.
177. Boulas HJ, Strickland JW. Strength and functional recovery following repair of flexor digitorum superficialis in zone 2. *J Hand Surg [Br]*. 1993;18:22–25.
178. Britto JA, Ragoowansi R, Flemming AF. A novel method for repair of flexor digitorum superficialis lacerations in zone 2. *Plast Reconstr Surg*. 2001;108:456–459.
179. Puckett CL, Meyer VH. Results of treatment of extensive volar wrist lacerations: the spaghetti wrist. *Plast Reconstr Surg*. 1985;75:714–719.
180. Katz RG. Discussion. Results of treatment of extensive volar wrist lacerations: the spaghetti wrist. *Plast Reconstr Surg*. 1985;75:720–721.
181. Roger GD, Henshell AL, Sach RP, Wallis KA. Simultaneous laceration of the median and ulnar nerves with flexor tendons at the wrist. *J Hand Surg Am*. 1990;15:990–995.
182. Stefanich RJ, Putnam MD, Peimer CA, Sherwin FS. Flexor tendon lacerations in zone V. *J Hand Surg Am*. 1992;17:284–291.

183. Hudson DA, de Jager LT. The spaghetti wrist. Simultaneous laceration of the median and ulnar nerves with flexor tendons at the wrist. *J Hand Surg [Br]*. 1993;18:171–173.
184. Yii NW, Urban M, Elliot D. Zone 5 A prospective study of flexor tendon repair in zone 5. *J Hand Surg [Br]*. 1998;23:642–648.
185. Wilhelmi BJ, Kang RH, Wages DJ, et al. Optimizing independent finger flexion with zone V flexor repairs using the Massachusetts General Hospital flexor tenorrhaphy and early protected active motion. *J Hand Surg Am*. 2005;30:230–236.
186. O'Connell SJ, Moore MM, Strickland JW, et al. Results of zone I and zone II flexor tendon repairs in children. *J Hand Surg Am*. 1994;19:48–52.
187. Kato H, Minami A, Suenaga N, et al. Long-term results after primary repairs of zone 2 flexor tendon lacerations in children younger than age 6 years. *J Pediatr Orthop*. 2002;22:732–735.
188. Navali AM, Rouhani A. Zone 2 flexor tendon repair in young children: a comparative study of four-strand versus two-strand repair. *J Hand Surg (Eur)*. 2008;33:424–429.
189. Elhassan B, Moran SL, Bravo C, Amadio P. Factors that influence the outcome of zone I and zone II flexor tendon repairs in children. *J Hand Surg Am*. 2006;31:1661–1666.
190. Moehrlen U, Mazzone L, Bieli C, Weber DM. Early mobilization after flexor tendon repair in children. *Eur J Pediatr Surg*. 2009;19:83–86.
191. Stahl S, Kaufman T, Bialik V. Partial laceration of flexor tendons in children. Primary repair versus conservative treatment. *J Hand Surg [Br]*. 1997;22:377–380.
192. McGeorge DD, Stilwell JH. Partial flexor tendon injuries: to repair or not. *J Hand Surg [Br]*. 1992;17:176–177.
193. Wray RC, Weeks PM. Treatment of partial tendon lacerations. *Hand*. 1980;12:163–166.
194. Wray RC, Holtman B, Weeks PM. Clinical treatment of partial tendon lacerations without suturing and with early motion. *Plast Reconstr Surg*. 1977;59:231–234.
195. Schlenker JD, Lister GD, Kleinert HE. Three complications of untreated partial laceration of flexor tendon—entrapment, rupture, and triggering. *J Hand Surg Am*. 1981;6:392–398.
196. Bishop AT, Cooney WP, Wood MB. Treatment of partial tendon lacerations: the effect of tenorrhaphy and early protected mobilization. *J Trauma*. 1986;26:301–312.
197. Boardman ND, Morifusa S, Saw SS, et al. Effects of tenorrhaphy on the gliding function and tensile properties of partially lacerated canine digital flexor tendons. *J Hand Surg Am*. 1999;24:302–309.
198. Hariharan JS, Diao E, Soejima O, Lotz JC. Partial lacerations of human digital flexor tendons: a biomechanical analysis. *J Hand Surg Am*. 1997;22:1011–1015.
199. Tan J, Wang B, Tan B, et al. Changes in tendon strength after partial cut and effects of running peripheral sutures. *J Hand Surg [Br]*. 2003;28:478–482.
200. Leddy JP, Packer JW. Avulsion of the profundus insertion in athletes. *J Hand Surg Am*. 1977;2:66–69.
201. Smith JH. Avulsion of a profundus tendon with simultaneous intraarticular fracture of the distal phalanx—case report. *J Hand Surg Am*. 1981;6:600–601.
202. Gaston A, Allavena C, Mansat P, et al. Traumatic avulsion of the flexor digitorum profundus tendon. Report of 20 cases. *Chir Main*. 2009;28:288–293.
203. Yamazaki H, Kato H, Hata Y, et al. Closed rupture of the flexor tendons caused by carpal bone and joint disorders. *J Hand Surg (Eur)*. 2007;32:649–653.
204. Kubiak EN, Klugman JA, Bosco JA. Hand injuries in rock climbers. *Bull NYU Hosp Jt Dis*. 2006;64:172–177.
205. Kleinert HE, Schepel S, Gill T. Flexor tendon injuries. *Surg Clin North Am*. 1981;61:267–286.
206. Slattery PG, McGrouther DA. A modified Kleinert controlled mobilization sSplint following flexor tendon repair. *J Hand Surg [Br]*. 1984;9:217–218.
207. Chow JA, Thomes LJ, Dovel S, et al. A combined regimen of controlled motion following flexor tendon repair in “no man’s land. *Plast Reconstr Surg*. 1987;70:447–453.
208. Duran RJ, Houser RG. Controlled passive motion following flexor tendon repairs in zones 2 and 3. In: *American Academy of Orthopedic Surgeons: Symposium on Tendon Surgery of the Hand*. St. Louis: CV Mosby Co.; 1975:105–114.
209. Strickland JW, Gettle KH. Flexor tendon repair: the Indianapolis method. In: Hunter JM, Schneider LH, Mackin EJ, eds. *Tendon and Nerve Surgery in the Hand: A Third Decade*. St. Louis: CV Mosby Co.; 1997:353–361.
210. Small JO, Brennen MD, Colville J. Early active mobilization following flexor tendon repair in zone 2. *J Hand Surg [Br]*. 1989;14:383–391.
211. Elliot D, Moiemmen NS, Flemming AFS, et al. The rupture rate of acute flexor tendon repairs mobilized by the controlled active motion regimen. *J Hand Surg [Br]*. 1994;19:607–612.
212. Wu YF, Tang JB. Tendon healing, edema, and resistance to flexor tendon gliding: clinical implications. *Hand Clin*. 2013;29:167–178.
213. Tang JB, Amadio PC, Boyer MI, et al. Current practice of primary flexor tendon repair: a global view. *Hand Clin*. 2013;29:179–189.
214. Cullen KW, Tolhurst P, Lang D, Page RE. Flexor tendon repair in zone II followed by controlled active mobilization. *J Hand Surg [Br]*. 1989;14:392–395.
215. Tang JB, Shi D. Subdivision of flexor tendon “no man’s land” and different treatment methods in each sub-zone. A preliminary report. *Chin Med J*. 1992;105:60–68.
216. O'Connell SJ, Moore MM, Strickland JW, et al. Results of zone I and zone II flexor tendon repairs in children. *J Hand Surg Am*. 1994;19:48–52.
217. Silfverskiöld KL, May EJ. Flexor tendon repair in zone II with a new suture technique and an early mobilization program combining passive and active flexion. *J Hand Surg Am*. 1994;19:53–60.
218. Grobelaar AO, Hudson DA. Flexor tendon injuries in children. *J Hand Surg [Br]*. 1994;19:696–698.
219. Berndtsson L, Ejekær A, Zone II. flexor tendon repair in children. A retrospective long term study. *Scand J Plast Reconstr Hand Surg*. 1995;29:59–64.
220. Baiktir A, Turk CY, Kabak S, et al. Flexor tendon repair in zone II followed by early active mobilization. *J Hand Surg [Br]*. 1996;21:624–628.
221. Kitis CK, Wade PJF, Krikler SJ, et al. Controlled active motion following primary flexor tendon repair: a prospective study over 9 years. *J Hand Surg [Br]*. 1998;23:344–349.
222. Harris SB, Harris D, Foster AJ, Elliot D. The aetiology of acute rupture of flexor tendon repairs in zones 1 and 2 of the fingers during early mobilization. *J Hand Surg [Br]*. 1999;24:275–280.
223. Percival NJ, Sykes PJ. Flexor pollicis longus tendon repair: a comparison between dynamic and static splintage. *J Hand Surg [Br]*. 1989;14:412–415.
224. Noonan KJ, Blair WF. Long-term follow-up of primary flexor pollicis longus tenorrhaphies. *J Hand Surg Am*. 1991;16:651–662.
225. Sirotakova M, Elliot D. Early active mobilization of primary repairs of the flexor pollicis longus tendon. *J Hand Surg [Br]*. 1999;24:647–653.
226. Fitoussi F, Mazda K, Frajman JM, et al. Repair of the flexor pollicis longus tendon in children. *J Bone Joint Surg Br*. 2000;82:1177–1180.
227. Kasashima T, Kato H, Minami A. Factors influencing prognosis after direct repair of the flexor pollicis longus tendon: multivariate regression model analysis. *Hand Surg*. 2002;7:171–176.
228. Sirotakova M, Elliot D. Early active mobilization of primary repairs of the flexor pollicis longus tendon with two Kessler two-strand core sutures and a strengthened circumferential suture. *J Hand Surg [Br]*. 2004;29:531–535.
229. Trumble TE, Vedder NB, Seiler JG 3rd, et al. Zone-II flexor tendon repair: a randomized prospective trial of active place-and-hold therapy compared with passive motion therapy. *J Bone Joint Surg Am*. 2010;92:1381–1389.

230. Sandow MJ, McMahon M. Active mobilisation following single cross grasp four-strand flexor tenorrhaphy (Adelaide repair). *J Hand Surg (Eur)*. 2011;36:467–475.
231. Frueh FS, Kunz VS, Gravestock IJ, et al. Primary flexor tendon repair in zones 1 and 2: early passive mobilization versus controlled active motion. *J Hand Surg Am*. 2014;39:1344–1350.
232. Moriya K, Yoshizu T, Maki Y, et al. Clinical outcomes of early active mobilization following flexor tendon repair using the six-strand technique: short- and long-term evaluations. *J Hand Surg (Eur)*. 2015;40:250–258.
233. Strickland JW. Delayed treatment of flexor tendon injuries including grafting. *Hand Clin*. 2005;21:219–243. *This is an extensive review of secondary tendon surgeries, covering indications, techniques, and postoperative care of free tendon grafting, staged tendon reconstruction, and tenolysis. This article is the most recent in an array of reviews about techniques for flexor tendon surgeries written by an experienced hand surgeon.*
234. Azari KK, Meals RA. Flexor tenolysis. *Hand Clin*. 2005;21:211–217.
235. Adamson JE, Wilson JN. The history of flexor tendon grafting. *J Bone Joint Surg Am*. 1961;43:709–716.
236. Pulvertaft RG. Tendon grafts for flexor tendon injuries in the fingers and thumb. A study of technique and results. *J Bone Joint Surg Br*. 1954;38:175–194.
237. Pulvertaft RG. Indications for tendon grafting. In: *AAOS Symposium on Tendon Surgery in the Hand*. Philadelphia: CV Mosby Co; 1975:123–131.
238. White WL. Secondary restoration of finger flexion by digital tendon grafts: an evaluation of seventy-six cases. *Am J Surg*. 1956;91:662–668.
239. White WL. Tendon grafts: a consideration of their source, procurement and suitability. *Surg Clin North Am*. 1960;40:403–413.
240. Tubiana R. Technique of flexor tendon grafts. *Hand*. 1969;1:108–114.
241. McClinton MA, Curtis RM, Wilgis EF. One hundred tendon grafts for isolated flexor digitorum profundus injuries. *J Hand Surg Am*. 1982;7:224–229.
242. Moberg E. Experiences with Bunnell's pull-out wire sutures. *Br J Plast Surg*. 1951;3:249–251.
243. Skoff HD, Hecker AT, Hayes WC, et al. Bone suture anchors in hand surgery. *J Hand Surg [Br]*. 1995;20:245–248.
244. Beris AE, Darlis NA, Korompilias AV, et al. Two-stage flexor tendon reconstruction in zone II using a silicone rod and a pedicled intrasynovial graft. *J Hand Surg Am*. 2003;28:652–660.
245. Ipsen T, Barfred T. Early mobilization after flexor tendon grafting for isolated profundus tendon lesions. *Scand J Plast Reconstr Surg Hand Surg*. 1988;22:163–167.
246. Tanaka T, Zhao C, Ettema AM, et al. Tensile strength of a new suture for fixation of tendon grafts when using a weave technique. *J Hand Surg Am*. 2006;31:982–986.
247. Matsuzaki H, Zaegel MA, Gelberman RH, Silva MJ. Effect of suture material and bone quality on the mechanical properties of zone I flexor tendon-bone reattachment with bone anchors. *J Hand Surg Am*. 2008;33:709–717.
248. Khan K, Riaz M, Murison MS, Brennen MD. Early active mobilization after second stage flexor tendon grafts. *J Hand Surg [Br]*. 1997;22:32–34.
249. Dowdy P, Richard RS, McFarlane RM. Palmar cutaneous branch of the median nerve passing through the Palmaris longus tendon: cadaveric study. *J Hand Surg Am*. 1994;19:199–202.
250. Reimann AF, Daseler E, Anson BJ, Beaton LE. The palmaris longus muscle and tendon: a study of 1,600 extremities. *Anat Rec*. 1944;89:495–505.
251. Daseler MS, Anson BJ. The plantaris muscle. *J Bone Joint Surg*. 1943;25:822–827.
252. Harvey FJ, Chu G, Morrison WA. The plantaris tendon as a tendooosseous graft. Part I. An anatomic study. *J Hand Surg [Br]*. 1992;17:467–470.
253. Wilson RL. Flexor tendon grafting. *Hand Clin*. 1985;1:97–107.
254. Bruner JM. The zig-zag volar-digital incision for flexor tendon surgery. *Plast Reconstr Surg*. 1967;40:571–574.
255. Bunnell S. Repair of tendons in the fingers. *Surg Gynecol Obstet*. 1922;35:88–97.
256. Bunnell S. *Surgery of the Hand*. 2nd ed. Philadelphia: JB Lippincott; 1948:381–466.
257. Peacock EE. Some technical aspects and results of flexor tendon repair. *Surgery*. 1965;58:330–342.
258. Pulvertaft RG. Suture materials and tendon junctures. *Am J Surg*. 1965;109:346–352.
259. Tubiana R. Incisions and techniques in tendon grafting. *Am J Surg*. 1965;109:339–345.
260. Nichols HM. The dilemma of the intact superficialis tendon. *Hand*. 1975;7:85–86.
261. Reid DAC. The isolated flexor digitorum profundus lesion. *Hand*. 1969;1:115–117.
262. Wakefield AR. The management of flexor tendon injuries. *Surg Clin N Am*. 1960;40:267–273.
263. Bora FW. Profundus tendon grafting with unimpaired sublimis function in children. *Clin Orthop Relat Res*. 1970;71:118–123.
264. Chan W, Thomas OJ, White WL. Avulsion injury of the long flexor tendons. *Plast Reconstr Surg*. 1972;50:260–264.
265. Goldner JL, Coonrad RW. Tendon grafting of flexor profundus in the presence of a completely or partially intact flexor sublimis. *J Bone Joint Surg Am*. 1969;51:527–532.
266. Jaffe S, Weckesser E. Profundus tendon grafting with the sublimis intact. An end result of thirty patients. *J Bone Joint Surg Am*. 1967;49:1298–1308.
267. Paneva-Holevich E. Two-stage tenoplasty in injury of the flexor tendons of the hand. *J Bone Joint Surg Am*. 1969;51:21–32.
268. Kesler FB. Use of a pedicled tendon transfer with a silicone rod in complicated secondary flexor tendon repairs. *Plast Reconstr Surg*. 1972;49:439–443.
269. Hunter JM. Artificial tendons. Early development and application. *Am J Surg*. 1965;109:325–338.
270. Hunter JM. Staged flexor tendon reconstruction. *J Hand Surg Am*. 1983;8:789–793.
271. Schneider LH. Treatment of isolated flexor digitorum profundus injuries by tendon grafting. In: Hunter JM, Schneider LH, Mackin EJ, eds. *Tendon Surgery in the Hand*. St. Louis: CV Mosby; 1987:303–311.
272. Chuinard RG, Dabezies EJ, Matthews RE. Two stage superficialis reconstruction in severely damaged fingers. *J Hand Surg Am*. 1980;5:135–143.
273. Hunter JM, Singer DI, Jaeger SH, Mackin EJ. Active tendon implants in flexor tendon reconstruction. *J Hand Surg Am*. 1988;13:849–859.
274. Schneider LH. Staged tendon reconstruction. *Hand Clin*. 1985;1:109–120.
275. LaSalle WB, Strickland JW. An evaluation of the two-stage tendon reconstruction technique. *J Hand Surg Am*. 1983;8:263–267.
276. Hunter JM, Jaeger SH. Flexor tendon reconstruction and rehabilitation using active tendon implants. In: Green DP, ed. *Operative Hand Surgery*. 3rd ed. New York: Churchill Livingstone; 1993:1900–1914.
277. Hunter JM, Singer DI, Mackin EJ. Staged flexor tendon reconstruction using passive and active tendon implants. In: Hunter JM, Schneider LH, Mackin EJ, Callahan AD, eds. *Rehabilitation of the Hand: Surgery and Therapy*. 3rd ed. St. Louis: CV Mosby; 1990:427–457.
278. Amadio PC, Wood MB, Cooney WP, Bogard SD. Staged flexor tendon reconstruction in the fingers and hand. *J Hand Surg Am*. 1988;13:559–562.
279. O'Shea K, Wolfe SW. Two-stage reconstruction with the modified Paneva-Holevich technique. *Hand Clin*. 2013;29:223–233.
280. Fetrow KO. Tenolysis in the hand and wrist: a clinical evaluation of 220 flexor and extensor tenolyses. *J Bone Joint Surg Am*. 1967;49:667–685.
281. James JIP. The value of tenolysis. *Hand*. 1969;1:118–119.

282. Jupiter JB, Pess GM, Bour CJ. Results of flexor tendon tenolysis after replantation in the hand. *J Hand Surg Am.* 1989;14:35–44.
283. Birnie RH, Idler RS. Flexor tenolysis in children. *J Hand Surg Am.* 1995;20:254–257.
284. Strickland JW. Flexor tendon surgery. Part 2. Free tendon grafts and tenolysis. *J Hand Surg [Br].* 1989;14:368–382.
285. Strickland JW. Flexor tenolysis. *Hand Clin.* 1985;1:121–132.
286. Whitaker JH, Strickland JW, Ellis RG. The role of tenolysis in the palm and digit. *J Hand Surg Am.* 1977;2:462–470.
287. Wray RC, Moucharafieh B, Weeks PM. Experimental study of the optimal time for tenolysis. *Plast Reconstr Surg.* 1978;61:184–189.
288. Hunter JM, Schneider LH, Dumont J, Erickson JC. A dynamic approach to problems of hand function using local anesthesia supplemented by intravenous fentanyl-droperidol. *Clin Orthop Relat Res.* 1974;104:112–115.
289. McDonough JJ, Stern PJ. Modified 69 blade for tenolysis. *J Hand Surg Am.* 1983;8:610–611.
290. Schreiber DR. Arthroscopic blades in flexor tenolysis of the hand. *J Hand Surg Am.* 1986;11:144–145.
291. Constantinescu MA, Greenwald DP, Amarante MT, et al. Effects of laser versus scalpel tenolysis in the rabbit flexor tendon. *Plast Reconstr Surg.* 1996;97:595–601.
292. Bora F, Lane JM, Prockop DJ. Inhibitors of collagen biosynthesis as a means of controlling scar formation in tendon injury. *J Bone Joint Surg Am.* 1972;54:1501–1508.
293. Wrenn RL, Goldner JL, Markee JL. An experimental study of the effect of cortisone on the healing process and tensile strength of tendons. *J Bone Joint Surg Am.* 1954;36:588–601.
294. Carstam N. The effects of cortisone on the formation of tendon adhesions and on tendon healing: an experimental investigation in the rabbit. *Acta Chir Scand.* 1953;182:1–111.
295. James JIP. The use of cortisone in tenolysis. *J Bone Joint Surg Br.* 1959;41:209–210.
296. Pinkerton M. Amnioplastin for adherent digital flexor tendons. *Lancet.* 1942;1:70–72.
297. Nichols H. Discussion of tendon repair with clinical and experimental data on the use of gelatin sponge. *Ann Surg.* 1949;129:223–234.
298. Ketchum LD. The effects of triamcinolone on tendon healing and function. *Plast Reconstr Surg.* 1971;47:471–482.
299. Stark HH, Boyes JH, Johnson L, Ashworth CR. The use of paratenon, polyethylene film, or silastic sheeting to prevent restricting adhesions to tendons in the hand. *J Bone Joint Surg Am.* 1977;59:908–913.
300. Karakurum G, Buyukbeci O, Kalender M, Gulec A. Seprafilm interposition for preventing adhesion formation after tenolysis. An experimental study on the chicken flexor tendons. *J Surg Res.* 2003;113:195–200.
301. Ferguson RE, Rinker B. The use of a hydrogel sealant on flexor tendon repairs to prevent adhesion formation. *Ann Plast Surg.* 2006;56:54–58.
302. Khanna A, Gougoulas N, Maffulli N. Modalities in prevention of flexor tendon adhesion in the hand: what have we achieved so far? *Acta Orthop Belg.* 2009;75:433–444.
303. Riccio M, Battiston B, Pajardi G, et al. Efficiency of hyaloglides(R) in the prevention of the recurrence of adhesions after tenolysis of flexor tendons in zone II: a randomised, controlled, multicentre clinical trial. *J Hand Surg (Eur).* 2010;35:130–138.
304. Kirchhoff R, Jensen PB, Nielsen NS, Boeckstyns ME. Repeated digital nerve block for pain control after tenolysis. *Scand J Plast Reconstr Surg Hand Surg.* 2000;34:257–258.
305. Cannon NM, Strickland JW. Therapy following flexor tendon surgery. *Hand Clin.* 1985;1:147–165.
306. Foucher G, Lenoble E, Ben Youssef K, Sammut D. A postoperative regime after digital flexor tenolysis. A series of 72 patients. *J Hand Surg [Br].* 1993;18:35–40.
307. Ketchum LD, Martin NL, Kappel DA. Experimental evaluation of factors affecting the strength of tendon repairs. *Plast Reconstr Surg.* 1977;59:708–719.
308. McCarthy JA, Lesker PA, Peterson WW, Manske PR. Continuous passive motion as an adjunct therapy for tenolysis. *J Hand Surg [Br].* 1986;11:88–90.
309. Goloborod'ko SA. Postoperative management of flexor tenolysis. *J Hand Ther.* 1999;12:330–332.

10

Extensor tendon injuries

Kai Megerle and Karl-Josef Prommersberger

Access video content for this chapter online at expertconsult.com 

SYNOPSIS

- A thorough understanding of the complex anatomy is crucial for successful treatment of extensor tendon injuries.
- Injuries are classified into nine anatomic zones. Treatment strategies vary considerably according to the location of the lesion, ranging from splinting to tendon grafting.
- Minimal variations in tendon length may result in considerable alteration in range of motion.
- As in flexor tendon injuries, postoperative care is an essential part of the treatment concept.
- Closed ruptures of the extensor tendon at the level of the distal interphalangeal (DIP) and proximal interphalangeal (PIP) joints are typically treated conservatively.
- Lacerations at the level of the metacarpophalangeal (MP) joint (zone V) are not infrequently caused by human bites and are prone to infection unless thoroughly debrided.
- Ruptures of the sagittal bands may result in subluxation of the extensor tendon at the level of the MP joint.
- The swan-neck deformity is characterized by DIP joint flexion and PIP joint hyperextension. It can be caused by an untreated mallet injury or palmar plate laxity.
- The boutonnière deformity is characterized by hyperextension of the DIP joint and PIP joint flexion. It can be caused by rupture of the central slip of the extensor tendon or palmar subluxation of the lateral bands.
- Complex injuries to the dorsum of the hand can involve skin, tendon, and bone. Adequate debridement is of paramount importance. Before reconstructing tendons, fractures must be stabilized and soft-tissue coverage must be provided.

Introduction

Injuries to the extensor tendons are frequently underestimated. Several reasons might contribute to this phenomenon, including easy access to the tendons due to the thin soft-tissue envelope, their extrasynovial nature, and limited retraction.

However, in contrast to common belief, injuries to the extensor tendon apparatus are often more difficult to treat than those of flexor tendons. First of all, a thorough understanding of the complex interactions between the long extensor tendons and the intrinsic muscles of the hand is necessary to achieve good postoperative results. Second, the extensor apparatus consists of superficial, thin structures that are very close to the underlying bones, which makes them prone to develop severe adhesions. Moreover, their excursion amplitude is limited, so that even subtle lengthening or shortening will result in severe restrictions of range of motion. Postoperative regimes vary considerably in respect to the exact location of the lesion and have to be selected carefully.

However, not only the tendon itself but also the surrounding soft tissues have to be taken into consideration when establishing a treatment concept. Extensor tendons are easily exposed on the dorsum of the fingers and hand even after minor trauma due to the thin tissue envelope. Additional procedures are frequently necessary. Shortcomings in adequate soft-tissue coverage will inevitably result in poor overall results, even if the tendons themselves were addressed properly.



Access the Historical perspective section online at

<http://www.expertconsult.com>

Basic science/disease process

The anatomy of the extensor mechanism is complex and some functional details are still subject to discussion. However, in order to be able to provide the best possible treatment in a given pathologic situation, fundamental knowledge about the functional anatomy of this complex system is paramount.

Anatomy of the extensor tendons

The extensor mechanism consists of extrinsic muscles, which are located on the forearm (extensor digitorum, extensor

Historical perspective

The history of tendon surgery reaches back to about AD 200. Galen (130–201) mistook the tendons for nerves and suggested in his *Ars Parva* that no sutures should be placed within the tendons in order not to cause pain and convulsion. The error was not corrected until the 10th century, when Avicenna of Boukhara (980–1037), in Persia, advocated surgical suturing of tendons. However, this new concept did not reach the west until much later – Galen's dogma was not refuted until the 18th century. The basic structure of the extensor tendon mechanism was illustrated by Albinus in 1734. The next step forward was the concept of tendon transplantation, which was introduced in the late 19th century. In the beginning of the 20th century extensive clinical and experimental research was conducted, especially in Germany. Lexer published the results of 10 flexor tendon grafts in 1912. During the first half of the 20th century, Bunnell developed basic principles of flexor tendon surgery which were published in his masterly book *Surgery of the Hand* in 1944.¹ Fowler and Landsmeer advanced the concept of the balanced forces and dynamics between the flexor and extensor apparatus in the 1940s. During the 1960s operating techniques were introduced that are still in use today.




Fig. 10.1 Extensor compartments: I, APL and EPB; II, ECRL and ECRB; III, EPL; IV, ED and EI; V, EDM; VI, ECU. APL, Abductor pollicis longus; ECU, extensor carpi ulnaris; ECRB, extensor carpi radialis brevis; ECRL, extensor carpi radialis longus; ED, extensor digitorum; EDM, extensor digiti minimi; EI, extensor indicis; EPB, extensor pollicis brevis; EPL, extensor pollicis longus.

indicis, extensor digiti minimi (EDM)), intrinsic muscles, which are located at the level of the metacarpals (interosseous and lumbrical muscles), and fibrous structures.

Extrinsic muscles

All extrinsic tendons pass through the six compartments of the extensor retinaculum on the back of the wrist (**Fig. 10.1**). The first compartment is attached to the outer rim of the radius and contains the tendons of the abductor pollicis longus (APL) and extensor pollicis brevis (EPB) muscles. In 34% of patients the compartment is further divided by an additional septum, which has implications for the etiology and treatment of de Quervain's disease.² The extensor carpi radialis longus (ECRL) and extensor carpi radialis brevis (ECRB) tendons run through the second compartment, which is bordered by Lister's tubercle on the ulnar side. The third compartment crosses the wrist in a diagonal fashion above the second compartment, while Lister's tubercle acts as a pivot point for the extensor pollicis longus (EPL) tendon. While passing through the compartment, the tendon is quite vulnerable to ruptures, e.g., in fractures of the distal radius. The fourth compartment contains both the extensor digitorum (ED) and extensor indicis (EI) tendons. The EDM and extensor

carpi ulnaris (ECU) tendons run through the fifth and sixth extensor compartments, respectively. The ECU not only functions as an extensor for the wrist, but is also part of the triangular fibrocartilage complex (TFCC) and thus a major stabilizer for the distal radioulnar joint.

The two extensor proprii tendons of the index and the little finger are located on the ulnar sides of the corresponding communis tendons and allow for individual movements of the peripheral fingers. On the dorsum of the hand, the ED tendons are interconnected by the juncturae tendinum which facilitate combined extension of the fingers. Lacerations of the extensor tendons which are located proximal to the juncturae may be masked by the function of these bands. The patterns of the intertendinous connections are highly variable and have been classified into three types: filamentous, fibrous, and tendinous bands.³ At the level of the proximal phalanges, the extensor tendons split up into three parts: the central band and two lateral bands (**Fig. 10.2**). These merge with the intrinsic extensor system to form the complex extensor apparatus of the digits.

The extrinsic extensor tendons themselves have three insertion sites on the phalanges. Proximally, the tendon is fixed at the level of the metacarpal heads to the palmar plate by the sagittal bands. This attachment centers the tendon of the MP joint and prevents hyperextension. The most important insertion is located at the base of the middle phalanx. Distally, the terminal tendon is attached to the distal phalanx. In addition to these three sites, there is a variable degree of attachment of the tendon to the proximal phalanx.

Intrinsic muscles

The intrinsic muscular system of the hand consists of seven interosseous and four lumbrical muscles. The three palmar interosseous muscles arise from the medial sides of the second, fourth, and fifth metacarpal bones and join the extensor




Fig. 10.2 Extensor apparatus.




Fig. 10.3 The distribution of intrinsic muscles in the fingers. Roman numbers indicate finger numbers. ADM, Abductor digiti minimi; DA, dorsal aponeurosis; ED, extensor digitorum; EDM, extensor digiti minimi; EI, extensor indicis; ID, dorsal interosseous muscles; IP, palmar interosseous muscles, numbered from radial to ulnar; L, lumbrical muscles, numbered from radial to ulnar; La, accessory lumbrical muscle (variation).

apparatus of the digits at the level of the proximal phalanx after crossing palmar to the axis of the MP joint. The four dorsal interosseous muscles originate with two heads each from the adjacent sides of the five metacarpal bones. The first two interosseous muscles approach the index and middle finger from the radial side; the third and fourth approach the middle and ring finger from the ulnar side. They have insertions at the proximal phalanges and the interosseous hood of the extensor apparatus before joining the lateral bands.


The lumbrical muscles are considered some of the most variable muscles of the human body, while the degree of variation increases from the radial to ulnar muscles. In general, they arise from the radial sides of the flexor digitorum profundus tendons at the level of the metacarpals and join the extensor apparatus from the radial side.

With this arrangement, all four digits have three intrinsic muscles contributing to the extensor apparatus, with the missing ulnar interosseous muscle for the little finger being equivalent to the abductor digiti minimi muscle (Fig. 10.3). The thumb also has three short muscles that join the extensor apparatus: the flexor pollicis brevis (FPB) and abductor pollicis brevis (APB) muscles on the radial side and the adductor pollicis (ADP) muscle on the ulnar side.

Functional anatomy

Linked chains

The movement of the fingers is a highly complex mechanism. It is dependent upon a delicate equilibrium between the extrinsic extensor and flexor muscles and the intrinsic muscles. Biomechanically, the finger can be compared to a multiarticular chain comprised of the three phalangeal bones (Fig. 10.4).



Landsmeer was able to show that at least three muscles are necessary to control two joints in such a multiarticular chain.⁴ For the proximal phalanx, these are the extrinsic extensor and flexor muscles and the diagonal intrinsic system (lumbrical and interosseous muscles). In the middle phalanx there is no diagonal muscle system; instead the third component is made up of the oblique retinacular ligament (Landsmeer's ligament) which has its origin at the flexor pulley and inserts distally into the extensor apparatus. Both of these diagonal systems run palmar to the joint axis proximally and dorsal to the joint axis distally. They play a crucial role in the coordination of extension and flexion movements of the fingers by linking the extrinsic flexor and extensor muscles.

Functions of the intrinsic muscles

It is generally believed that the intrinsic muscles of the hand act as flexors at the MP joints and extensors at the interphalangeal joints. However, this is not always true for the interosseous muscles. They approach the extensor apparatus at a much smaller angle (less steep) than the lumbrical muscles. Due to this little anatomical difference, the function of the interosseous muscles is highly dependent on the position of the interosseous hood and therefore as well of the position of the MP joint. When the MP joints are in extension, the interosseous muscles cover the articular space and the oblique fibers of the interossei are put into tension, which translates into extension of the interphalangeal joints. However, when the MP joints are in flexion, the interosseous muscles slide distally on the proximal phalanx. During contraction of the muscles, the interosseous hood is pulled towards the hand and the flexion movement of the MP joint is enforced. In this position, the interossei lose the extensor function on the distal joints.

Fig. 10.4 Linked chains. ED & EI, Extensor digitorum and extensor indicis; FCR, flexor carpi radialis; L, lumbrical muscle; Obliq. R. lig., oblique retinacular ligament (Landsmeer's ligament).

The lumbricals join the extrinsic tendon at a much greater angle than the interossei and are therefore not depending in their function on MP joint position. They act as extensors at the proximal and DIP joint in both extension and flexion of the MP joint.

Extrinsic muscle function

It has been shown biomechanically that both the extrinsic flexor and extensor muscles have a component that acts as an extensor on the proximal phalanx. Under physiologic conditions this force is counteracted by the intrinsic muscles. Paralysis of these muscles (as in ulnar nerve palsy) therefore results in hyperextension of the MP joints. Without intrinsic muscle function the long extensors exhaust their potential at the level of the proximal phalanx. Anatomical studies have demonstrated that isolated contraction of the extrinsic extensors results in hyperextended, clawlike position of the MP joints, but not complete finger extension.³ For complete extension of the interphalangeal joints intrinsic muscle function is therefore mandatory.

Mechanisms of joint extension

The MP joint is extended by the extrinsic extensor tendon. However, there have been debates about how tendon force is transmitted to the joint. The variable direct attachment of the tendon to the proximal phalanx has been shown to have no significant contribution to MP joint extension.⁵ It has been postulated that instead the fibrous connections of the extensor tendon to the flexor sheath are the primary transmitters for extension of the joint.

Extension of the PIP joint is mediated by the central slip of the extensor tendon. However, as stated above, intrinsic muscle function is necessary in order to enable the extrinsic extensor tendon to act on the PIP joint. At the level of the PIP joint, the extensor tendon is centered by the transverse retinacular ligaments. Harris and Rutledge have stressed the importance of the correct position and balance between the central slip and the lateral bands in order to maintain normal PIP extension.⁵

Until the late 1940s, extension of the DIP joint was thought only to be mediated by the terminal part of the extensor mechanism. In 1949 Landsmeer defined the function of the oblique retinacular ligament, which had been unclear since its identification in the 1800s.⁶ He described the extension of the DIP joint as a combination of the terminal lateral bands and a tenodesis effect mediated by these ligaments. Later these findings were questioned.⁵ However, dissection of the ligament results in lack of extension of the DIP joint.

Diagnosis/patient presentation

The diagnosis of extensor tendon injuries is often evident. However, partial lesions can be missed if the remaining tendon is strong enough to create some extension force. As a general rule, open lesions should therefore be surgically explored to identify the extent of the injury and prevent secondary ruptures. The function of the ED tendon should be assessed by extension of the MP joint of the affected digit against resistance.

Clinical tips

Always obtain a focused history, including the exact mechanism of injury. Expect concomitant osseous involvement in crush injuries. Long-term outcomes should be kept in mind and communicated with the patient when formulating a treatment plan.

Clinical tips

Intrinsic muscle function may obscure complete lacerations of the ED tendons by extension of the PIP and DIP joints. Always check extension of the MP joints to rule out ED injuries.



Fig. 10.5 Test of the extensor pollicis longus tendon.

The EPB tendon inserts into the extensor tendon apparatus of the thumb at varying levels and may be able to extend the IP joint of the thumb. If there is a questionable rupture of the EPL tendon, it should therefore not be tested by extension of the IP joint. Instead, the patient should be asked to lift the thumb off the table, which will be impossible without an intact EPL tendon (Fig. 10.5).

Kleinert and Verdan proposed a system to classify lesions of the extensor tendon apparatus into eight zones according to the level of the lesion.⁷ Doyle has added a ninth zone by dividing the forearm into the distal (zone 8) and proximal forearm (zone 9).⁸ This classification is presented in Fig. 10.6.

Patient selection

The repair of simple lacerations of the extensor tendon can be safely performed in the emergency room. However, as the lesions are generally underestimated and require sufficient exposure of the tendon, a thorough knowledge of the surgical anatomy and treatment regimes is mandatory. Lesions proximal to zone VI should be treated in the operating room. The use of loupe magnification should be considered. The patient should be aware that, despite the often short duration of




Fig. 10.6 The zones of extensor tendon injuries.

operations, postoperative treatment protocols can be complicated and may last for several months.

Wide-awake surgery is a concept that is becoming increasingly accepted. In this approach, procedures are performed with no sedation and no tourniquet with the use of tumescent lidocaine and epinephrine. This technique has been proven to be safe and cost-effective.⁹⁻¹² Most importantly, however, with the patient able to move the fingers during the operation, the surgeon can verify the success of tenolysis or tendon repair procedures immediately.¹³ Not only tendon repairs and tenolysis, but also tendon transfers can be most effectively performed in this approach.¹⁴

Treatment/surgical technique

Suturing techniques

The size of the extensor tendon varies considerably during its course from the distal forearm to its terminal insertion at the distal phalanx. While the tendon is round and thick proximally, it becomes thin and flat more distally. Suturing techniques therefore have to be adapted specifically to the location of the lesion. Whatever technique is chosen, it should provide the best stability with the least shortening possible.

In zones II to IV, extensor tendons are thin and flat and, thus, less amenable to suture techniques involving multiple core sutures. For lacerations in these areas, epitendinous suture techniques have demonstrated favorable results.¹⁵ In

zones VI and proximally, the extensor tendon resembles a flexor tendon and as such can be repaired with a core suture and an epitendinous running suture. Commonly used suture strengths include 3-0 and 4-0 for core sutures and 5-0 for epitendinous sutures. For neither flexor nor extensor tendons is there any scientific evidence for an advantage of using resorbable or nonresorbable suture materials. Fig. 10.7 gives an overview of common types of core suture. In order to achieve maximum core suture strength, locking stitches should be preferred over grasping stitches in order to prevent suture pull-out and reduce gapping.¹⁶ However, grasping suture techniques have a higher tensile strength and less gap formation in extensor tendon repair than mattress or figure-of-eight stitches.¹⁷ For flexor tendons, it has been shown that at least four core strands should be applied in order to enable early active motion¹⁸ and the same is probably true for extensor tendon repair.

In the more distal zones of injury, locking or grasping core stitches become increasingly difficult due to flattening of the tendon. Newport *et al.* report that grasping stitches in zone IV injuries are strong enough to enable postoperative early active motion.¹⁹ More recently, Chung *et al.* have demonstrated that a single cross-stitch may even be superior to multiple cross-stitches in a modified Becker repair of the extensor tendon in zone IV.²⁰ Simple running stitches should be avoided due to the low pull-out strength in favor of more complex locking suture techniques.

Clinical tips

Always check the stability of the sutured tendon intraoperatively by gentle movements of the finger. If possible, use locking core stitches in preference to other techniques. Soft-tissue coverage can be very thin in fingers, so patients may be able to make out dyed suture material through the skin.

Zone I

The mallet finger

The mallet finger is characterized by persistent flexion of the distal phalanx due to a lesion of the extensor apparatus at the level of the DIP joint. It represents a classic closed injury that




Fig. 10.7 Different types of core sutures.

is usually treated conservatively, although open injuries may occur as well.

The flat terminal extensor tendon inserts at the base of the distal phalanx where it blends with the joint capsule. Since its excursion is only about 4 mm, even small gaps may result in a considerable lack of extension. It should be kept in mind that the full extension of the distal phalanx is also dependent on an intact oblique retinacular ligament.

Mallet fingers can be classified by the degree of osseous involvement. Isolated tendinous ruptures are differentiated from injuries that involve bony avulsions. The latter have been classified into avulsions of small triangular fragments, large fragments that result in palmar subluxation of the phalanx, and epiphyseal detachments in children.

Most surgeons prefer conservative treatment with splints over operative therapy for uncomplicated injuries, although the scientific evidence is limited.^{21,22}

Niechajev reviewed 135 patients who had been treated for various types of mallet finger with a minimal follow-up of 12 months.²³ The author concludes that operative treatment should only be performed in cases with subluxation of the distal phalanx or avulsed fragments that are more than one-third of the joint surface and with a diastasis of more than 3 mm. Stern and Kastrup reviewed 123 mallet injuries retrospectively.²⁴ Thirty-nine patients were treated surgically, resulting in a complication rate of 53%, including infection, nail deformities, joint incongruities, fixation failure, and bony prominence. The authors conclude that splinting is the preferred treatment option in nearly all mallet fingers. Handoll and Vaghela included four trials in a systematic review.^{25–29} They concluded that there is insufficient evidence from randomized trials to establish the effectiveness of custom-made or off-the-shelf finger splints, the advantage of surgical treatment over splinting, or even the advantage of splinting over no treatment at all.

The best available evidence therefore supports conservative treatment by splinting for the majority of cases. Conservative treatment usually implies immobilization of the DIP joint in extension while sparing the PIP joint. By extension or slight hyperextension of the joint the two ruptured ends of the tendon are approximated (Figs. 10.8 & 10.9). The fibrous tissue of the resulting scar is thought to be strong enough to restore extension of the joint. The type of splint is not nearly as important as patient compliance. Prefabricated stack splints have been shown to be equally effective as simple aluminum splints or custom sandwich splints (Figs. 10.10 & 10.11). Most authors recommend full-time splinting for at least 6–8 weeks followed by a period of 2–6 weeks of splinting at night to enable further shrinking of the immature scar. All patients should be thoroughly instructed to avoid ineffective use of the splints. The splints should only be removed when flexion of the DIP joint by the strong pull of the FDP tendon is counteracted, e.g., through resting the finger flat on a table. By thorough splinting, a residual lack of extension of 10° or less can be expected.³⁰

Surgical treatment for closed injuries should only be considered in fragment sizes greater than one-third of the joint surface. Transfixation of the DIP joint with a Kirschner wire has been suggested for sole treatment of the mallet injury in addition to other surgical interventions.^{31,32} To avoid scarring of the finger pulp, Tubiana has suggested an oblique angle when crossing the DIP joint.³³



Fig. 10.8 Acute mallet injury, reduced by stack splint: posteroanterior view.



Fig. 10.9 Acute mallet injury, reduced by stack splint: lateral view.



Fig. 10.10 Aluminum splint.




Fig. 10.11 Stack splint.

When surgical intervention is indicated, the size of the avulsed fragment should be carefully evaluated for direct fixation. This can be very difficult to achieve and may result in further fragmentation of the avulsed bone. In case of a rather small fragment, indirect reduction by extension block pin fixation should be preferred (“doorstop osteosynthesis”). In this technique the distal phalanx is maximally flexed and a 1.0-mm Kirschner wire is advanced into the middle phalanx dorsal to the avulsed fragment at a 45° angle, creating the extension block against which the fragment is reduced. The joint is then extended, reducing the fragment. This position is secured by a second Kirschner wire inserted longitudinally across the DIP joint for transfixation. The wires are cut and a splint is applied for at least 6 weeks (Figs. 10.12–10.15).

If the avulsed fragment seems large enough, it may either be pinned directly percutaneously or reduced in an open fashion through a zigzag incision of the distal and middle phalanges. In case of open reduction, screw fixation seems



Fig. 10.13 Mallet injury: lateral view. Despite the stack splint, the fragment is not properly reduced.

preferable. Alternatively, a pull-out suture may be applied, as described by Doyle.⁸

Open injuries

Most authors agree to operative treatment for open injuries. In some cases, suturing of the skin alone and supporting the joint in extension or slight hyperextension is enough to



Fig. 10.12 Mallet injury: posteroanterior view.



Fig. 10.14 Postoperative doorstep: posteroanterior view.



Fig. 10.15 Postoperative doorstop: lateral view 6 weeks after doorstop osteosynthesis.

approximate the ends of the ruptured tendon and allow direct healing. When sutures are needed to approximate the tendon ends, a suture that incorporates both skin and tendon may be superior to individual suturing of the tendon, because further tendon dissection may decrease the blood supply and compromise healing.

Chronic injuries

If tendinous ruptures over the DIP joint are not or insufficiently treated, gapping of the tendon ends will result in the incorporation of fibrous tissue and lack of extension. A swan-neck deformity may occur. The approach to these conditions is described below (under secondary procedures).

Zone II

Injuries to the extensor tendon over the middle phalanx usually result from sharp, direct lacerations or crush injuries. Acute lacerations should be explored to determine the extent of the tendon injury. If less than 50% of the tendon substance are injured, the tendon is considered stable and no further treatment is necessary. If more than half of the tendon is involved, additional suturing is necessary. When evaluating these injuries, phalangeal extension should always be tested against resistance. Doyle recommended a running stitch combined with a Silfverskiöld cross-stitch⁸ (Fig. 10.16). Care should be taken to avoid considerable shortening of the tendon which will result in lack of flexion of the DIP joint.

Zone III

Injuries to the extensor tendon at the level of the PIP joint (zone III) occur as both closed and open injuries, ranging from minor strains to complete ruptures or lacerations. Injuries at

this level can give rise to the characteristic boutonnière deformity when the proximal phalanx herniates through the central slip defect. However, the deformity will not develop immediately after the injury. Disruption of the tendon first leads to an inability to extend the PIP joint actively while passive extension is possible. Only after the lateral bands migrate palmarly and retraction of the central slip occurs will hyperextension of the DIP joint develop.

Closed injuries

A closed avulsion injury of the central slip may not be immediately evident and extension may be retained by means of the lateral bands. If in doubt, extension of the PIP joint should therefore always be tested against resistance.

The central slip may be restored without surgical intervention by extension splinting. As flexion of the DIP joint stretches the extensor mechanism and facilitates dorsal relocation of the lateral bands, the DIP joint should not be included in immobilization. Instead patients should be encouraged to move the DIP joint actively and passively while wearing the PIP splint (Fig. 10.17). Several authors have proposed pinning the PIP joint in extension by a Kirschner wire.^{34–36} Most authors suggest keeping the joint in extension for 5–6 weeks.^{35–37}

Surgical treatment has been suggested for avulsion injuries with large bony fragments or unstable transarticular fractures.³³ If the fragment is too small to be pinned directly, it may be excised and the tendon reinserted into the middle fragment with a bone anchor.

Open lacerations

Open injuries should always be thoroughly explored. Care should be taken specifically to include the lateral bands and the triangular ligament in the inspection.

Clinical tips

Because of the excursion of the tendon at the time of injury, the full extent of tendon involvement may not be visible at first sight. It is therefore mandatory to carefully inspect the tendon proximally and distally to the skin lesion.




Fig. 10.16 (A,B) Silfverskiöld cross-stitch for sutures in zone II injuries.




Fig. 10.17 (A,B) Splinting for closed extensor tendon ruptures in zone III.

The mechanism of injury is of special importance in open zone III injuries with regard to the extent of injury to both the tendinous structures and the surrounding soft tissues. In clean and sharp lacerations, the wound can be easily enlarged and the injured tendon should be sutured directly or reinserted into the middle phalanx. A Silfverskiöld cross-stitch may be used where appropriate to enforce the suture. In contrast, contaminated defect wounds, e.g., after saw injuries, are a lot more difficult to deal with. If there is considerable loss of tendon, an immediate reconstruction should be attempted. Snow described a retrograde tendinous flap created from the proximal tendon that is flipped over to bridge the defect over the joint (Fig. 10.18).³⁸ Aiache *et al.* proposed a longitudinal split of the two lateral bands that are joined in the midline to reconstruct the tendinous insertion and to cover the joint (Fig. 10.19).³⁹ Any loss of covering skin should be replaced immediately as well; options include local random pattern flaps, reversed cross-finger flaps, or flaps from the dorsal metacarpal artery system.

Postoperatively, a Kirschner wire may be used to reinforce splinting of the PIP joint, which should be kept for 4–6 weeks. Tenolyses or joint releases are frequently necessary, but should be delayed until 3–6 months after the injury.

Zone IV

As the extensor becomes very broad over the proximal phalanx, partial lacerations are more commonly observed than complete injuries of the tendons. Therefore extension should be examined against resistance. Surgical inspection is necessary to assess the exact extent of the injury. Newport *et al.* have demonstrated that modified Kessler sutures do not result in significant shortening of the tendon and allow 30° of flexion in the PIP joint without gapping.¹⁹

Extensor tendon injuries in zone IV are often associated with fractures of the proximal phalanx.⁴⁰ Due to the close




Fig. 10.18 (A,B) Snow's technique of reconstructing the central slip. MP, Metacarpophalangeal; PIP, proximal interphalangeal.

relationship between tendon and bone, adhesions frequently occur and tenolysis is often necessary. Some form of a post-operative early active motion regimen is therefore advisable to reduce loss of range of motion. Maintenance of the wrist in an extended position will “unload” the tendon and allow early range of motion of the finger.




Fig. 10.19 (A,B) Reconstruction of the central slip involving splitting of the lateral bands (Aiache's technique).

Zone V

At the level of the MP joints, the extensor tendon consists of the central extensor tendon and the sagittal bands. Due to the broad width of the extensor apparatus complete lacerations are uncommon. On the other hand, partial lacerations can be easily missed because the remaining tendon may be sufficient to maintain extension function. Surgical exploration is therefore warranted. It should be taken into account that the injury to the tendon may be located more proximally than the skin laceration if the tendon was injured in flexion and the exploration is performed with the digit in extension. If possible, a core suture with an epitendinous running stitch should be performed. In the rare cases of complete lacerations, the tendon will not significantly retract proximally, as it is restrained by the sagittal bands and the juncturae.

Human bite injuries

A common mechanism of injuries to the extensor tendon in zone V is a human bite injury caused by a punch to the opponent's face (fight bites; Fig. 10.20). Bite wounds are heavily contaminated and prone to serious infection. As skin damage is often minimal, these injuries are frequently underestimated by the patient and treatment is delayed until infection has developed. Primary inspection is mandatory in fresh injuries, as are X-ray studies to detect avulsed bony fragments or teeth. During exploration, the tendon should be split longitudinally and the MCP joint irrigated with antibiotic solution.⁴¹ Partial lacerations of the tendon often do not require suturing; a number of authors suggest delayed primary treatment after the occurrence of infection has been ruled out.⁴²

Sagittal band injuries

The central tendon is centered over the MP joint by the lateral bands which attach to the palmar plate of the joint. Open or closed injuries to the sagittal bands may result in subluxation of the tendon to the unaffected side during flexion. Partial lacerations will not result in subluxation unless two-thirds of the sagittal band is affected.⁴³ Stable lacerations can be treated by buddy-taping of the affected finger to an adjacent finger

for 3 weeks. In case of an unstable tendon, the laceration should be sutured.

Closed ruptures of the sagittal bands are much more common than open injuries and usually occur in the course of a primary disease of the joints such as rheumatoid arthritis. Ishizuki describes two layers of the sagittal bands, a superficial and a deep layer.⁴⁴ He postulated that degenerative ruptures affect only the superficial layer, while traumatic ruptures affect both layers. Traumatic and spontaneous ruptures of the sagittal bands may be treated by splinting within 10–14 days.^{45,46} In older injuries, direct suturing of the bands should be attempted. Reconstruction of the sagittal bands in chronic subluxation is discussed in the section on secondary surgery, below.

Zone VI

Extensor tendon lesions at the level of the metacarpal bones have a better prognosis than in more distal zones.⁴⁰ This is due to several reasons. First, the tendons are very broad and can usually be sutured by a 3-0 core stitch and an epitendinous running suture. Moreover, they are extrasynovial and are not associated with any joints. At the same time, tendon excursion is greater than in more distal locations and imbalances between extensor and flexor systems are less likely to occur. Soft-tissue coverage is better than in distal zones, but still quite thin compared to flexor tendons.

At this level, the function of the extrinsic extensor tendon is to extend the MP joint. Therefore MP joint extension should be tested against resistance. However, the extrinsic tendons are linked by the juncturae tendinum and patients may still be able to extend the joints by means of the adjacent tendons.

Postoperatively, early mobilization with a dynamic splinting regime is indicated to reduce tendon adhesions. Loss of flexion has been reported to be more common than loss of extension.⁴⁰

Zone VII

Injuries to the extensor tendons at the level of the extensor retinaculum are due to either open lacerations that often affect multiple tendons or closed ruptures, most often after distal radius fractures.

In order to repair open lacerations at this level, at least a part of the retinaculum has to be opened. There has been an ongoing debate whether or not to reconstruct the retinaculum over the affected tendon. Some surgeons advocate excising the retinaculum in order to avoid postoperative adhesions. Others suggest reconstructing at least parts of the retinaculum to prevent subluxation or bowstringing of the tendons. Although adhesions between the tendons and the retinaculum seem more likely, Newport *et al.* found no differences between the outcomes of zone VII lesions in comparison to lesions in adjacent zones.⁴⁰ The tendon repair itself should be performed with a stable core suture and an epitendinous running stitch. Special attention should also be paid to concomitant injuries of sensory branches of the radial and ulnar nerves. Primary coaptation of the nerve ends should be performed in order to prevent the development of painful and difficult-to-manage neuromas.

As the tendons are arranged very close to each other, injuries of multiple tendons through one laceration occur



Fig. 10.20 Fight bite in the ring-finger metacarpal. The extensor tendon is split longitudinally.

frequently. Identification of the tendons can be quite difficult, because they tend to retract into the forearm. A thorough knowledge of the surgical anatomy is therefore mandatory. Botte *et al.* described a useful technique of labeling the retrieved tendons by placing sterile labels on hemostats that are clamped to sutures placed in the proximal ends of the tendon.⁴⁷

Ruptures of the EPL tendon are most often associated with fractures of the distal radius or rheumatoid arthritis. Two main causes for EPL ruptures after distal radius fractures have been hypothesized.⁴⁸ On the one hand, the tendon may be injured while drilling the holes for palmar plate fixation or by choosing screws that are too long and protrude into the extensor compartments. On the other hand, dislocated dorsal fragments of the fracture may harm the tendon. Because of the degenerative nature of the process, an end-to-end repair of the tendon is usually not possible without unacceptable shortening of the tendon. Instead, reconstruction of the tendon can be performed by EI to EPL tendon transfers or interposing tendon grafts. Both techniques are discussed in the section on secondary surgery, below.

Zones VIII/IX

Lesions of the extensor tendons at levels VIII and IX include injuries of the musculotendinous junctions and muscle bellies. As in zone VII injuries, the recovery and identification of retracted tendons can be quite challenging. Combined injuries to muscles and/or nerves are possible. Knowledge of the sequence of motor innervation helps to distinguish a motor nerve injury from a tendon injury. The motor branches of the wrist and fingers have been divided into two groups, a proximal superficial group and a distal deep group.⁴² The proximal superficial group consists of the ECRL, ECRB, ED, EDM, and ECU muscles. The entry of nerve fibers into the muscles is near the lateral epicondyle. When exposing the posterior interosseous nerve, the interval between the wrist ECRB and ECRL tendon (proximal to the supinator muscle) and the ED, EDM, and ECU (distal to the supinator) should be chosen to avoid injury to motor branches. The distal deep group consists of the APL, EPB, EPL, and EI. They originate in the distal half of the forearm, close to the skeletal plane.

Adequate repair of muscles and tendons can be very difficult in this area. Sutures of muscle fibers alone have virtually no tensile strength. Therefore an effort should be made to suture tendons or fascial layers instead of muscle fibers alone. Nevertheless, these sutures are usually not strong enough for dynamic postoperative treatment protocols and immobilization for 3–4 weeks should be initiated postoperatively.

Postoperative care

As with flexor tendon injuries, the importance of an adequate postoperative treatment cannot be overestimated. Extensor tendon healing itself does not differ very much from flexor tendon healing. However, it has to be considered that the treatment protocol needs to address the powerful antagonist force of the opposing flexor tendons. Initially, static postoperative treatment regimes were considered sufficient for all injuries, as in theory tendon adhesion is limited due to the mostly extrasynovial nature of extensor tendons. In reality,

however, while prolonged immobilization allows healing of the tendon without disturbances, it still promotes loss of motion due to the formation of adhesions. The problem can be addressed by early active or passive motion which in turn increases the risk of gap formation and ruptures of the sutured tendons. As for flexor tendon injuries, in recent years, dynamic postoperative treatment protocols have been developed that reduce postoperative adhesion formation without jeopardizing the stability of the sutured tendon.

Nevertheless, strict immobilization is the treatment of choice for some indications. Mallet injuries should be treated by full-time static splinting for 8 weeks. The same is true for closed ruptures of the central slip (zone III injuries). Immobilization should also be considered for injuries proximal to the extensor retinaculum (zones VIII and IX) because it may not be possible to achieve adequate tensile strength by suturing fascial layers around the muscle.

Postoperative immobilization of open injuries in zones III–V will inevitably result in severe adhesions, because the tendon is very broad and in close relationship to the adjacent bone in this area. To overcome this problem, Evans described a postoperative treatment protocol that reduces adhesions by limited early active motion (“short arc motion”).⁴⁹ The regime is based on biomechanical studies that examined the extensor tendon excursions necessary to prevent adhesion formation. Duran *et al.*⁵⁰ found that 3–5 mm of passive tendon glide is sufficient to achieve this goal. Evans⁵¹ compared intraoperative measurements of tendon excursions in zone IV and V with previous measurements of Brand and Hollister,⁵² and estimated that 60° of PIP joint flexion translates into 5 mm of tendon glide at Lister’s tubercle.

For the protocol, three finger splints are required. The affected digit is immobilized between training sessions in an extension split in 0° extension of the DIP and PIP joints. At every waking hour, the splint is removed and a controlled active motion protocol is followed. First a splint is put on to block flexion of the PIP joint at 30° and flexion of the DIP at 20–25°. After 20 repetitions of active and passive motion within the defined limits, a third splint is put on that stabilizes the PIP joint in 0° extension while sparing the DIP joint. The patient then actively extends and flexes the DIP joint 20 times. During the second and third week of the protocol, flexion of the PIP joint is increased to 40° and 50°. In a retrospective study, Evans reported on significant improvement of clinical results with the dynamic protocol when compared to a group of patients who were immobilized postoperatively.⁵⁰

Dynamic mobilization for injuries in zones V–VII can be achieved by passive extension with a rubber band system combined with active flexion of the affected digit (Fig. 10.21). This protocol has also been termed the “reversed Washington” or “reversed Kleinert” regimen. The patient is encouraged to perform active flexion and passive extension exercises 10 times every hour for 3 weeks, starting on the second postoperative day. The range of motion for flexion of the MP joint is restricted at 30° in the beginning and gradually increased to 60° until the end of the third week. Active motion is initiated after 3 weeks and the splint is removed after 6 weeks. The load of the tendon is gradually increased over 6 weeks. In a prospective, randomized study, better total active motion was achieved in zone V and VI lesions after 4, 6, and 8 weeks after a dynamic splinting protocol when compared to static splinting.⁵³



Fig. 10.21 Dynamic extension splint.

Early dynamic motion is also superior to immobilization after transfer of the EI tendon for EPL reconstruction.⁵⁴ After performing a Pulvertaft weave, the tendon is more stable and splinting can be discontinued after 3 weeks. However, active extension of the thumb has no advantage over dynamic splinting after transfer of the EI tendon.⁵⁵

A different concept for lacerations in zones IV to VII is the immediate controlled active motion (ICAM) splinting protocol.⁵⁶ This protocol, also referred to as relative motion splinting, encourages active motion of the affected digit which is kept in 15° to 20° less relative motion than the adjacent joints by a simple splint for 6 weeks. The rationale for this concept is that placing the finger in a slightly more extended position than the neighboring digits results in a reduction of force, regardless of the position of the MP joint.⁵⁷ Recently, ICAM has also been applied for postoperative care after correction of boutonnière deformities, sagittal band ruptures and side-to-side tendon-transfers in caput ulnae syndrome.⁵⁸

Outcomes, prognosis, and complications

Outcomes

Outcomes vary considerably with the location of the lesion, the extent of concomitant injuries to the bone or surrounding soft tissues, timing of the repair, and adequate postoperative care. Clinical results are most often assessed by total active motion.⁵⁹ Hung *et al.* established 270° of total active motion in a digit as a normal value.⁶⁰ Some authors have adapted evaluation systems for flexor tendon injuries.^{7,61} Alternatively, results can be compared by total lag of extension or flexion, as proposed by Miller in 1942.⁶²

Lesions distal to the MP joints lead to less favorable results than more proximal lesions. Newport *et al.* report the results of a retrospective analysis of 101 patients, most of whom were treated with static splinting.⁴⁰ Good or excellent results with an average total active motion of 230° were achieved in 64% of patients without an associated injury. However, lesions in zones I through IV resulted in good or excellent results in only 50% of patients. Evans found a total active motion of 147° 6 weeks after repair of lacerations in zone III and an early active motion regimen.⁴⁹

Hung *et al.* reported on 38 patients with an average of 229° of total active motion after postoperative dynamic splinting.⁶⁰ Patients with lesions in zones II–IV showed the worst results, with an average of 188° total active motion. For lesions at the level of the MP joint, several studies reported superior results after postoperative dynamic splinting protocols when compared with immobilization, ranging from 237° to 254° of total active motion.^{60,63,64}

Complications

The most common complication after extensor tendon injuries is the formation of adhesions between the tendon and surrounding tissues. Under these circumstances, a tenodesis restraint may occur, limiting PIP joint flexion when the MP joint is also flexed. Adhesion formation should be addressed first by hand therapy and splinting of the affected joints in order to improve tendon gliding. If there is not adequate improvement in range of motion after 4–6 months, extensor tendon tenolysis can be considered. A stable skin envelope is a prerequisite before performing any additional procedures. Tenolysis can be elegantly performed utilizing the wide-awake technique with no sedation and no tourniquet with the use of tumescent lidocaine and epinephrine (see patient selection, above).

Tenolysis alone may not be sufficient to achieve an improvement in range of motion. An additional capsulotomy, collateral ligament release, or even flexor tendon tenolysis may be necessary.⁶⁵ Creighton and Steichen reported the results of extensor tenolysis after phalangeal and metacarpal fracture repair.⁶⁶ Total active range of motion was improved by 31% on average, but only 21% when an additional capsulotomy was necessary.

Secondary procedures

Clinical tips

Secondary correction of established finger deformities is exceedingly difficult. Patients should be aware that restoration of “normal” finger movement is rare.

The hanging fingertip

Even a minimal increase in tendon length will result in an extensor lag after a mallet injury. In many patients, therefore, some residual deformity will occur. However, this deformity is rarely of any relevance in terms of long-term prognosis.⁶⁷ With the extension lag exceeding 40–50°, however, a considerable number of patients will desire correction. In this case, additional immobilization should be considered for up to 6 months after the injury, especially if there is any doubt about the adequacy of the primary treatment.

If conservative treatment fails, surgical treatment should be discussed with the patient. Due to the delicate equilibrium between the extensor and the flexor tendon system, results are not always satisfactory after secondary surgery. None of the procedures available will invariably provide reliable results. Correction of the deformity may be incomplete, there may be some loss of flexion in the DIP joint, and pain reduction cannot



Fig. 10.22 Hanging fingertip.



Fig. 10.23 Resection of skin and tendon.

be reliably predicted. Any accompanying arthritis of the joint should be ruled out; in case of cartilaginous deterioration, DIP joint fusion should be considered.

If surgical correction is indicated, a simple combined excision of callus and skin may be the procedure of choice. This dermatotenodesis has also been referred to as the Brooks–Garner procedure. In this procedure, an elliptical wedge of skin and underlying soft tissues, including the scarred extensor tendon, is excised from the dorsum of the involved DIP joint (Figs. 10.22–24). The wound edges are closed by en bloc sutures, resulting in a slight hyperextension of the joint. The DIP joint is then transfixed with a Kirschner wire to keep the joint in the desired position for 6 weeks.

Alternatively, a Fowler release (central slip tenotomy) or even a reconstruction of the spiral oblique retinacular ligament may be performed. Both procedures are primarily used to correct swan-neck deformities and require a supple PIP joint. They are therefore discussed in the following section.

The swan-neck deformity

The swan-neck deformity is a classic finger deformity that can be caused by many reasons, including congenital PIP palmar plate laxity and intrinsic tightness. Often it is associated with some form of arthritis; however, it can also result from a

mallet injury. A thorough history-taking and physical examination will distinguish the mallet etiology from other causes. In this case, the disrupted extensor tendon results in a concentration of extensor force at the PIP joint (Fig. 10.25). If the palmar plate of the joint is lax, the swan-neck deformity will occur immediately. However, even if it is not lax to begin with, it will stretch over time due to increased extensor pull. If hyperextension of the PIP joint exceeds a critical point, snapping of the joint will occur. This may be often more disconcerting to the patient than the postural deformity.

A tenotomy of the central slip has been used to address the swan-neck deformity in patients with a chronic mallet deformity in which the terminal extensor tendon cannot be repaired.⁶⁸ This procedure has also been referred to as the Fowler release. By transection of the central slip, rebalancing of the extensor mechanism should occur in order to increase the extension force on the DIP joint. Grundberg and Reagan reported on a series of 20 patients with an average reduction of PIP joint extension of 10° to less than 2°.⁶⁹ A biomechanical study demonstrated the ability to correct an extensor lag of



Fig. 10.24 Transfixation of the distal interphalangeal joint.




Fig. 10.25 (A,B) Pathophysiology of the swan-neck deformity. The deformity persists when the tendon heals with lengthening.




Fig. 10.26 (A–C) Spiral oblique retinacular ligament. A palmaris longus tendon graft is passed between the flexor tendon and the palmar plate and fixed to the distal phalanx by a pull-out suture.

up to 46° .⁷⁰ The authors noted that extensor lags greater than 36° may not achieve full correction of the deformity. Increasing the extent of the release will potentially increase the risk of a secondary extensor lag of the PIP joint, but there was no clear relationship between the occurrence of a lag and the amount of release in a recent biomechanical study.⁷¹ It should be noted that there is some confusion in the literature about the operation that is referred to as a “Fowler release”. Fowler also described a procedure to address the boutonnière deformity by rebalancing the extensor tendon (see below). However, in this operation the extensor tendon is divided distal to the insertion of the central slip and thus even increasing extension forces at the level of the PIP joint.

Alternatively, the extensor tendon may be reconstructed by a tendon graft (spiral oblique retinacular ligament or SORL reconstruction: Fig. 10.26). Thompson *et al.* described a procedure using a palmaris tendon to restrain PIP extension and to extend the DIP.⁷² In this technically demanding operation, the tendon graft is fixed to the distal phalanx by a pull-out suture. It is then passed between the flexor tendon and the palmar plate of the PIP joint into an osseous tunnel in the proximal phalanx (see Fig. 10.26). Although Girot *et al.* reported a 95% success rate to correct PIP hyperextension, experience with this procedure seems to be limited.⁷³

Swan-neck deformities which are not primarily related to injuries of the distal extensor tendon should be approached differently. Frequently, these deformities are caused by

hyperlax palmar plates at the level of the PIP joint. In these cases, correction of the laxity can be indicated, e.g., by a tenodesis of the flexor digitorum superficialis tendon.

The boutonnière deformity

Acute injury to the central band of the extensor tendon will result in an acute boutonnière deformity as both lateral bands shift palmarly due to the accompanied disruption of the triangular ligament. In the acute phase, the deformity should be easily reducible and may be treated as described above. However, if left untreated, a chronic contracture results from shortening of the oblique retinacular ligament (Fig. 10.27). This condition has long been recognized as one of the most challenging problems in hand surgery.⁷⁴

Preoperative considerations

Any surgical correction of the deformity should only be performed if the PIP joint can be extended passively. This can sometimes be achieved conservatively by a physical therapy program in combination with static and dynamic splinting. In severe cases, an additional operative tenoarthrolysis may be necessary. This procedure can sometimes be combined with revision of the extensor tendon from a dorsal approach. However, in severe cases a first-stage palmar approach to release the joint contracture is combined with a staged secondary procedure from dorsally. If combined with a splinting regimen, the tenoarthrolysis may be sufficient to achieve functional improvement, so that further operations can be avoided.

Burton and Melchior have listed several more aspects that should be considered before attempting a surgical correction of the deformity.⁷⁵ Patients should be aware that postoperative splinting is an essential part of the treatment strategy and may




Fig. 10.27 (A,B) Pathophysiology of the boutonnière deformity. Subluxation of the lateral bands results in redistribution of forces and an extensor lag in the proximal interphalangeal joint. Retraction of the oblique retinacular ligament prohibits reduction in chronic deformities.

be necessary for months after surgery. Any attempt to reconstruct the soft tissues around the PIP joint should be avoided if the joint shows any signs of arthritis. In this case, joint fusion or arthroplasty should be considered. The boutonnière deformity does not necessarily compromise the extent of flexion in the PIP joint or grip strength. An increase in extension of the joint should not be traded for a stiff finger or loss of grip strength.

There are two main categories of procedure to address the boutonnière deformity: tenotomy or reconstruction of the extensor tendon by tendon relocation or tendon grafting.

Tenotomy

Tenotomy of the extensor tendon on the middle phalanx is referred to as the Dolphin or Fowler procedure.^{76,77} It may be the procedure of choice when patients mainly complain about hyperextension of the DIP joint. The incision should be performed just distally to the insertion of the central slip. In Dolphin's description, the tendon is divided more proximally in order to preserve the distal insertions of the oblique retinacular ligament (Fig. 10.28). The lateral bands should be able to slide proximally in order to increase the tone on the PIP joint to allow improved extension and reduce tension on the DIP joint. Postoperatively, the PIP joint should be splinted in extension, allowing free range of motion of the DIP joint. It has been recommended to apply splinting for 6–8 weeks.⁷⁵

Secondary reconstruction of the extensor tendon

If the main patient complaint is the lack of extensor function, secondary reconstruction of the extensor should be considered. This goal can be achieved by either tendon relocation or tendon grafting. Intraoperative transfixation of the PIP joint with a Kirschner wire has been subject to controversial discussion for any type of reconstruction. In severe flexion contractures of the joint, it may be beneficial.

The central slip can be reconstructed as described by Snow (see Fig. 10.18). The end of the reconstructed tendon is either sutured to the remaining insertion on the middle phalanx or reinserted directly into the phalanx.

A large number of techniques have been described to reconstruct the central slip using the lateral bands. By relocation of the lateral bands the tension of the terminal tendon on the DIP joint is reduced while increasing the extension force on the PIP joint. Littler and Eaton described the resection of both lateral bands in order to relocate them dorsally and suture them on to the insertion of the central slip, thus




Fig. 10.28 Treatment of the boutonnière deformity by tenotomy as described by Dolphin and Fowler. Dolphin's tenotomy preserves the insertions of the oblique retinacular ligament.




Fig. 10.29 Littler operation. The lateral bands are resected and relocated to the central tendon.

combining a tenotomy and tendon relocation (Fig. 10.29).⁷⁸ In Matev's technique, the lateral bands are incised at different levels (Fig. 10.30). The distal end of the longer slip is sutured to the proximal end of the other slip, resulting in an increase in length of the terminal tendon in order to reduce tension on the DIP joint. The free slip is then relocated medially to restore the central slip.⁷⁹

In extensive defects of the central slip, the lateral bands may be insufficient for reconstruction. In these cases, free tendon grafts may be indicated. Littler described a figure-of-eight weave through the base of the middle phalanx and the lateral bands.⁸⁰ Several other variations of fixation of the graft have been proposed.^{32,77,81}

Delayed sagittal band reconstruction (Video 10.1)

The function of the sagittal bands is to align the tendon centrally on the MP joint. If the sagittal band is ruptured, the tendon may subluxate to the unaffected side. The lesion most often involves a longitudinal or oblique tear on the radial side of the tendon which leads to an ulnar dislocation at the level of the MP joint.⁸² Tendon dislocation rarely occurs in patients not suffering from rheumatoid arthritis. If conservative treatment fails, surgical reconstruction of the sagittal band is indicated. In addition to the reconstruction, a release of the contracted contralateral sagittal band may be necessary in long-standing cases.⁴³ Several techniques have been described for reconstruction, if direct repair is not possible because of missing soft tissue or severe scarring^{82–85} (Fig. 10.31).




Fig. 10.30 (A,B) Matev's technique for reconstruction of the central slip. Both lateral bands are cut at different heights and relocated to reconstruct the central slip.




Fig. 10.31 Different techniques for reconstruction of the sagittal band. **(A)** Disruption of the radial sagittal band results in ulnar subluxation of the extensor tendon. **(B)** Primary suturing. **(C)** Wheeldon's technique: the ulnar junctura tendinum is relocated to the deep intercarpal ligament. **(D)** McCoy's technique: the tendon is split distally and wrapped around the lumbricalis muscle. **(E)** Carroll's technique: an ulnarly distal-based slip of the extensor digitorum tendon is wrapped around the radial collateral ligament (RCL).

Wheeldon described an anchoring of the ulnar-sided junctura tendinum to the radial side of the extensor hood.⁸⁵ Elson passed a retrograde tendon slip beneath the deep transverse metacarpal ligament and sutured it to the joint capsule.⁸⁶ McCoy and Winsky described another reconstructive procedure that used a proximally based tendon slip.⁸⁴ In their "lumbrical loop operation" the tendon was wrapped around the lumbrical muscle and then sutured to itself. Kilgore *et al.*⁸⁷ and Carroll *et al.*⁸³ both described techniques that utilized distally or ulnarly based tendon slips that were passed around the radial collateral ligament and then sutured to themselves. In Watson's technique, a distally based central tendon slip is looped through the deep transverse metacarpal ligament.⁸²

Clinical tips

Regardless of the preferred technique for sagittal band reconstruction, make sure the tendon is stabilized while maintaining full finger flexion. A dynamic postoperative protocol is advisable.

Carroll *et al.* reported the results of three patients who were operated on with their technique in five fingers.⁸¹ No recurrent subluxation was noted. Watson *et al.* found no recurrent subluxation in 21 sagittal band reconstructions in 16 patients after a mean of 16 months.⁸²

The missing tendon: tendon transfers versus tendon grafting (Video 10.2 ►)

In cases of degenerative rupture of an extensor tendon, direct suturing is not usually possible because of an existing gap or extensive degeneration of the tendon ends. In the absence of rheumatoid arthritis, the EPL tendon is most often affected. To reconstruct extensor function two options exist. First, the tendon can be reconstructed with the use of a tendon graft, e.g., derived from the palmaris longus tendon (Fig. 10.32A–D). Second, reconstruction is possible by transfer of another tendon. In case of an EPL rupture, the EI tendon is most frequently used (Fig. 10.33A–D).

Good results have been reported for both techniques.^{88–91} In general, both show similar results.⁹² However, each technique has specific advantages and disadvantages. For reconstructions with tendon grafts two weaving sutures are performed, which increases the risk of insufficiencies and ruptures. Harvesting of a tendon graft is necessary, but donor site morbidity should be minimal with the use of a palmaris longus graft. In contrast to tendon transfers no cortical rearrangement and adaption are needed. However, clinical results after tendon grafting are worse in long-standing ruptures because of atrophy and contracture of the affected muscles.⁹³

Cortical adaptation is necessary after tendon transfers, but this is usually not a problem even in older patients. The operative technique is usually easier and faster. Because only one weaving suture is performed, the risk of tendon ruptures may be lower than in tendon transfers. After transfer of the EI tendon isolated extension of the index finger is maintained in most patients.⁹⁴ However, it has to be considered that the strength of isolated index finger extension is weakened.^{95,96} This is not a problem for daily life activities, but may be a problem in specific patients, such as musicians.

Soft-tissue management and staged reconstruction in combined injuries

Clinical tips

Soft tissue coverage of the fingers must allow for full flexion of the finger joints. After debridement of skin on the dorsum of the fingers, local flaps are often necessary to avoid exposure of the extensor tendon postoperatively.




Fig. 10.32 Reconstruction of a ruptured extensor pollicis longus (EPL) tendon with the use of a palmaris longus tendon graft. **(A)** Degenerative rupture of the extensor pollicis longus tendon. Direct suture is not possible. **(B)** Harvest of the ipsilateral palmaris longus tendon as a graft. **(C)** Weaving suture of the graft to the proximal stump of the tendon. **(D)** Weaving suture of the graft to the distal stump. Notice full extension of the thumb in wrist flexion.

Lesions of the extensor tendons are often complicated by lesions of the bones and joints and by loss of skin. The treatment of these combined defects poses a difficult problem for the treating surgeon. Extensive scarring can be expected and must be taken into consideration when formulating a treatment plan. As in other mutilating injuries, basic reconstructive principles apply. Before attempting reconstruction of the tendons, several requirements must be fulfilled. First of all, radical debridement of all devitalized tissue is mandatory. Before closure, the wound should not contain any contamination or tissue of compromised blood supply in order to prevent infection. Primary radical debridement has been shown to be superior to several serial debridement steps, because of the formation of edema and infected granulation tissue, which is only poorly penetrated by antibiotic treatment.⁹⁷⁻¹⁰⁰

Clinical tips

Extensive undermining of the skin should be avoided at the back of the hand. Soft tissue coverage is thin and breaks down easily, leading to complex defects.

Second, osseous structures must be stabilized before turning to soft tissues. This can be achieved by internal or external fixation as appropriate. Third, a stable soft-tissue coverage for tendons and bony structures must be provided. In case of combined lesions of the dorsum of the hand, often pedicled or free tissue transfer is necessary. While the dorsal side of the hand is frequently used as a donor side to harvest soft-tissue flaps for coverage of palmar defects, the opposite is not true. Instead, flaps are usually harvested from adjacent proximal or distal regions on the hand and forearm. The pedicled radial forearm flap is a classic pedicled workhorse flap for coverage of the dorsum of the hand. However, due to sacrifice of the radial artery and the conspicuous donor site, variations of the original technique such as perforator-based flaps or fascial flaps should be considered.¹⁰¹ Another classic pedicled flap is the posterior interosseous artery flap (Figs. 10.34–10.38). With the advancement of microsurgical techniques, free tissue transfers are now more frequently performed.¹⁰²

The timing of combined reconstructive procedures has been subject to discussions. Traditionally, these injuries have been addressed by multistage procedures.¹⁰³ However, since Godina's classic work on the value of early debridement and



Fig. 10.33 Reconstruction of a ruptured extensor pollicis longus (EPL) tendon by transfer of the extensor indicis (EI) tendon. **(A)** Distal stump of the ruptured extensor pollicis longus tendon. **(B)** Harvest of the extensor indicis tendon at the base of the index finger. **(C)** The EI tendon is reflected to the level of the wrist and a subcutaneous tunnel is created. **(D)** Weaving suture of the tendons.



Fig. 10.34 Postinfectious defect of the dorsum of the hand with exposed extensor tendons.



Fig. 10.35 Defect after debridement of the extensor tendons. The metacarpal bones are exposed.



Fig. 10.36 Soft-tissue reconstruction by a posterior interosseus artery flap. The missing tendons have been reconstructed by transfer of the extensor indicis tendon.



Fig. 10.37 Recovery of extensor function.

free tissue transfer for lower-extremity defects, today probably most surgeons apply the same principles in upper-extremity reconstruction with the aim of achieving soft-tissue coverage within 72 hours.¹⁰⁴ Several authors have reported excellent results after one-stage procedures for defects involving the dorsum of the hand with the use of emergency free flaps.^{105–107} Reconstruction of missing tendons is usually performed at the time of soft-tissue coverage by primary grafting or tendon transfers. Because the creation of a secondary tendon sheath is not necessary, staged reconstruction of extensor tendons utilizing silicone rods is rare.^{108–110} Adams reported on six patients who were treated by two-staged reconstructions of complex defects of the extensor tendon at the level of the PIP joint.¹¹⁰ Active extension of the PIP joint could be achieved in all patients with an average extensor lag of 15°. In contrast, Quaba *et al.* presented good clinical results in nine patients



Fig. 10.38 Flexor function 12 weeks after reconstruction.

with complex defects in zones VI and VII who received soft-tissue coverage only without reconstruction of tendon defects.¹¹¹

Conclusion

Extensor tendon injuries are frequently underestimated. However, even slight disturbances in the delicate balance between the flexor and the extensor tendon systems will result in significant loss of finger function. Therefore, a clear understanding of the pertinent anatomy is essential to achieve good treatment results. Acute injuries require early diagnosis and treatment, which should always take the surrounding soft-tissue structures into consideration. Chronic injuries and subsequent finger deformities such as swan-neck and boutonnière deformities are very difficult to correct and require a thorough analysis of the underlying tendon imbalance. As is true for other tendon injuries, good results cannot be achieved without the choice of the right postoperative treatment protocol.

Future directions

The functional anatomy of the extensor mechanism is complex and certain aspects less clear than some publications might suggest. Therefore, biomechanical research will hopefully improve the treatment of injuries to the extensor apparatus and especially their sequelae. However, most research today is probably directed towards other aspects, namely suture techniques and postoperative treatment protocols. These two are connected, as stronger suture techniques allow earlier and more extensive motion exercises. These developments are reflected in the latest revision of this chapter and will hopefully continue to improve clinical results for our patients.



Access the complete reference list online at

<http://www.expertconsult.com>

5. Harris CJ, Rutledge GLJ. The functional anatomy of the extensor mechanism of the finger. *J Bone Joint Surg Am.* 1972;54:713–726.
6. Landsmeer JM. The anatomy of the dorsal aponeurosis of the human finger and its functional significance. *Anat Rec.* 1949;104:31–44. Classic description of the function of the oblique retinacular ligaments

which is the anatomical foundation for numerous reconstructive procedures of the distal extensor tendon.

17. Newport ML, Williams CD. Biomechanical characteristics of extensor tendon suture techniques. *J Hand Surg Am.* 1992;17:1117–1123.

25. Handoll HH, Vaghela MV. Interventions for treating mallet finger injuries. *Cochrane Database Syst Rev*. 2004;(3):CD004574.
38. Snow JW. Use of a retrograde tendon flap in repairing a severed extensor in the pip joint area. *Plast Reconstr Surg*. 1973;51:555–558. *Although only 6 cases in 3 years are reported, this is the classic description of one of the most commonly used techniques to reconstruct defects of the central slip.*
49. Evans RB. Early active short arc motion for the repaired central slip. *J Hand Surg Am*. 1994;19:991–997. *Based on several anatomical studies, Evans introduces a new early active motion protocol for extensor tendon injuries in zones III and IV. Sixty-four digits in 55 patients were investigated. Patients who were treated by early active motion demonstrated better functional results than those who were treated by immobilization.*
50. Duran RJ, Houser RG, Stover MG. Management of flexor tendon lacerations in Zone 2 using controlled passive motion postoperatively. In: Hunter JM, Schneider LH, Mackin EJ, et al., eds. *Rehabilitation of the Hand*. St. Louis: CV Mosby; 1978:217–224.
53. Mowlavi A, Burns M, Brown RE. Dynamic versus static splinting of simple zone V and zone VI extensor tendon repairs: a prospective, randomized, controlled study. *Plast Reconstr Surg*. 2005;115:482–487.
68. Bowers WH, Hurst LC. Chronic mallet finger: The use of Fowler's central slip release. *J Hand Surg Am*. 1978;3:373–376.
76. Dolphin JA. Extensor tenotomy for chronic boutonnière deformity of the finger; report of two cases. *J Bone Joint Surg Am*. 1965;47:161–164. *Description of the classic technique to address the problem of the boutonnière deformity.*
78. Littler JW, Eaton RG. Redistribution of forces in the correction of boutonnière deformity. *J Bone Joint Surg Am*. 1967;49:1267–1274. *Littler and Eaton describe the pathophysiology of the boutonnière deformity and the results of 8 patients who were treated by detachment and proximal reinsertion of the lateral bands.*

References

- Bunnell SB. *Surgery of the Hand*. Philadelphia: JB Lippincott; 1944.
- Leslie BM, Ericson WBJ, Morehead JR. Incidence of a septum within the first dorsal compartment of the wrist. *J Hand Surg Am*. 1990;15:88–91.
- von Schroeder HP, Botte MJ. The functional significance of the long extensors and juncturae tendinum in finger extension. *J Hand Surg Am*. 1993;18:641–647.
- Landsmeer JM. Anatomical and functional investigations on the articulation of the human fingers. *Acta Anat Suppl (Basel)*. 1955;25:1–69.
- Harris CJ, Rutledge GLJ. The functional anatomy of the extensor mechanism of the finger. *J Bone Joint Surg Am*. 1972;54:713–726.
- Landsmeer JM. The anatomy of the dorsal aponeurosis of the human finger and its functional significance. *Anat Rec*. 1949;104:31–44. *Classic description of the function of the oblique retinacular ligaments which is the anatomical foundation for numerous reconstructive procedures of the distal extensor tendon*.
- Kleinert HE, Verdan C. Report of the Committee on Tendon Injuries (International Federation of Societies for Surgery of the Hand). *J Hand Surg Am*. 1983;8:794–798.
- Doyle JR. Extensor tendons – acute injuries. In: Green DP, ed. *Operative Hand Surgery*. New York: Churchill Livingstone; 1999:1950–1987.
- Denkler K. A comprehensive review of epinephrine in the finger: to do or not to do. *Plast Reconstr Surg*. 2001;108:114–124.
- Krunic AL, Wang LC, Soltani K, et al. Digital anesthesia with epinephrine: an old myth revisited. *J Am Acad Dermatol*. 2004;51:755–759.
- Lalonde D, Bell M, Benoit P, et al. A multicenter prospective study of 3110 consecutive cases of elective epinephrine use in the fingers and hand: the Dalhousie Project clinical phase. *J Hand Surg Am*. 2005;30:1061–1067.
- Leblanc MR, Lalonde J, Lalonde DH. A detailed cost and efficiency analysis of performing carpal tunnel surgery in the main operating room versus the ambulatory setting in Canada. *Hand (N Y)*. 2007;2:173–178.
- Lalonde DH. Wide-awake flexor tendon repair. *Plast Reconstr Surg*. 2009;123:623–625.
- Bezuhly M, Sparkes GL, Higgins A, et al. Immediate thumb extension following extensor indicis proprius-to-extensor pollicis longus tendon transfer using the wide-awake approach. *Plast Reconstr Surg*. 2007;119:1507–1512.
- Henderson J, Sutcliffe M, Gillespie P. The tension band principle and angular testing of extensor tendon repairs. *J Hand Surg Eur Vol*. 2011;36:297–302.
- Miller B, Dodds SD, deMars A, et al. Flexor tendon repairs: the impact of fiberwire on grasping and locking core sutures. *J Hand Surg Am*. 2007;32:591–596.
- Newport ML, Williams CD. Biomechanical characteristics of extensor tendon suture techniques. *J Hand Surg Am*. 1992;17:1117–1123.
- Strickland JW. Development of flexor tendon surgery: twenty-five years of progress. *J Hand Surg Am*. 2000;25:214–235.
- Newport ML, Pollack GR, Williams CD. Biomechanical characteristics of suture techniques in extensor zone IV. *J Hand Surg Am*. 1995;20:650–656.
- Chung KC, Jun BJ, McGarry MH, Lee TQ. The effect of the number of cross-stitches on the biomechanical properties of the modified becker extensor tendon repair. *J Hand Surg Am*. 2012;37:231–236.
- Jablecki J, Syrko M. Zone 1 extensor tendon lesions: current treatment methods and a review of literature. *Ortop Traumatol Rehabil*. 2007;9:52–62.
- Leinberry C. Mallet finger injuries. *J Hand Surg Am*. 2009;34:1715–1717.
- Niechajev IA. Conservative and operative treatment of mallet finger. *Plast Reconstr Surg*. 1985;76:580–585.
- Stern PJ, Kastrop JJ. Complications and prognosis of treatment of mallet finger. *J Hand Surg Am*. 1988;13:329–334.
- Handoll HH, Vaghela MV. Interventions for treating mallet finger injuries. *Cochrane Database Syst Rev*. 2004;(3):CD004574.
- Auchincloss JM. Mallet-finger injuries: a prospective, controlled trial of internal and external splintage. *Hand*. 1982;14:168–173.
- Kinninmonth AW, Holburn F. A comparative controlled trial of a new perforated splint and a traditional splint in the treatment of mallet finger. *J Hand Surg [Br]*. 1986;11:261–262.
- Maitra A, Dorani B. The conservative treatment of mallet finger with a simple splint: a case report. *Arch Emerg Med*. 1993;10:244–248.
- Warren RA, Norris SH, Ferguson DG. Mallet finger: a trial of two splints. *J Hand Surg [Br]*. 1988;13:151–153.
- Abouna JM, Brown H. The treatment of mallet finger. The results in a series of 148 consecutive cases and a review of the literature. *Br J Surg*. 1968;55:653–667.
- Casscells SW, Strange TB. Intramedullary wire fixation of mallet-finger. *J Bone Joint Surg Am*. 1957;39-A:521–526.
- Weeks PM. The chronic boutonniere deformity: a method of repair. *Plast Reconstr Surg*. 1967;40:248–251.
- Tubiana R. Surgical repair of the extensor apparatus of the fingers. *Surg Clin North Am*. 1968;48:1015–1031.
- McFarlane RM, Hampole MK. Treatment of extensor tendon injuries of the hand. *Can J Surg*. 1973;16:366–375.
- Elliott RAJ. Injuries to the extensor mechanism of the hand. *Orthop Clin North Am*. 1970;1:335–354.
- Sakellarides HT. The extensor tendon injuries and the treatment. *R I Med J*. 1978;61:307–313.
- Stewart IM. Boutonniere finger. *Clin Orthop*. 1962;23:220–226.
- Snow JW. Use of a retrograde tendon flap in repairing a severed extensor in the pip joint area. *Plast Reconstr Surg*. 1973;51:555–558. *Although only 6 cases in 3 years are reported, this is the classic description of one of the most commonly used techniques to reconstruct defects of the central slip*.
- Aiache A, Barsky AJ, Weiner DL. Prevention of the boutonniere deformity. *Plast Reconstr Surg*. 1970;46:164–167.
- Newport ML, Blair WF, Steyers CMJ. Long-term results of extensor tendon repair. *J Hand Surg Am*. 1990;15:961–966.
- Dreyfuss UY, Singer M. Human bites of the hand: a study of one hundred six patients. *J Hand Surg Am*. 1985;10:884–889.
- Nolan WB. Extensor tendon injuries and reconstruction. In: Mathes SJ, Hentz V, eds. *Plastic Surgery*. Philadelphia: Saunders; 2005:401–421.
- Koniuch MP, Peimer CA, VanGorder T, et al. Closed crush injury of the metacarpophalangeal joint. *J Hand Surg Am*. 1987;12:750–757.
- Ishizuki M. Traumatic and spontaneous dislocation of extensor tendon of the long finger. *J Hand Surg Am*. 1990;15:967–972.
- Araki S, Ohtani T, Tanaka T. Acute dislocation of the extensor digitorum communis tendon at the metacarpophalangeal joint. A report of five cases. *J Bone Joint Surg Am*. 1987;69:616–619.
- Inoue G, Tamura Y. Dislocation of the extensor tendons over the metacarpophalangeal joints. *J Hand Surg Am*. 1996;21:464–469.
- Botte MJ, Cohen MS, von Schroeder HP. Method of tendon labeling in forearm injuries. *J Hand Surg Am*. 1991;16:763–764.
- Benson EC, DeCarvalho A, Mikola EA, et al. Two potential causes of EPL rupture after distal radius volar plate fixation. *Clin Orthop Relat Res*. 2006;451:218–222.
- Evans RB. Early active short arc motion for the repaired central slip. *J Hand Surg Am*. 1994;19:991–997. *Based on several anatomical studies, Evans introduces a new early active motion protocol for extensor tendon injuries in zones III and IV. Sixty-four digits in 55 patients were investigated. Patients who were treated by early active motion demonstrated better functional results than those who were treated by immobilization*.
- Duran RJ, Houser RG, Stover MG. Management of flexor tendon lacerations in Zone 2 using controlled passive motion postoperatively. In: Hunter JM, Schneider LH, Mackin EJ, et al., eds. *Rehabilitation of the Hand*. St. Louis: CV Mosby; 1978:217–224.

51. Evans RB. Therapeutic management of extensor tendon injuries. *Hand Clin.* 1986;2:157–169.
52. Brand PW, Hollister AM. *Clinical Mechanics of the Hand*. St. Louis: CV Mosby; 1999.
53. Mowlavi A, Burns M, Brown RE. Dynamic versus static splinting of simple zone V and zone VI extensor tendon repairs: a prospective, randomized, controlled study. *Plast Reconstr Surg.* 2005;115:482–487.
54. Germann G, Wagner H, Blome-Eberwein S, et al. Early dynamic motion versus postoperative immobilization in patients with extensor indicis proprius transfer to restore thumb extension: a prospective randomized study. *J Hand Surg Am.* 2001;26:1111–1115.
55. Giessler GA, Przybiski M, Germann G, et al. Early free active versus dynamic extension splinting after extensor indicis proprius tendon transfer to restore thumb extension: a prospective randomized study. *J Hand Surg Am.* 2008;33:864–868.
56. Howell JW, Merritt WH, Robinson SJ. Immediate controlled active motion following zone 4-7 extensor tendon repair. *J Hand Ther.* 2005;18:182–190.
57. Sharma JV, Liang NJ, Owen JR, et al. Analysis of relative motion splint in the treatment of zone VI extensor tendon injuries. *J Hand Surg Am.* 2006;31:1118–1122.
58. Merritt WH. Relative motion splint: active motion after extensor tendon injury and repair. *J Hand Surg Am.* 2014;39:1187–1194.
59. Soni P, Stern CA, Foreman KB, et al. Advances in extensor tendon diagnosis and therapy. *Plast Reconstr Surg.* 2009;123:52e–57e.
60. Hung LK, Chan A, Chang J, et al. Early controlled active mobilization with dynamic splintage for treatment of extensor tendon injuries. *J Hand Surg Am.* 1990;15:251–257.
61. Khandwala AR, Blair J, Harris SB, et al. Immediate repair and early mobilization of the extensor pollicis longus tendon in zones 1 to 4. *J Hand Surg [Br].* 2004;29:250–258.
62. Miller H. Repair of severed tendons of the hand and wrist. *Surg Gynecol Obstet.* 1942;75:693–698.
63. Ip WY, Chow SP. Results of dynamic splintage following extensor tendon repair. *J Hand Surg [Br].* 1997;22:283–287.
64. Kerr CD, Burczak JR. Dynamic traction after extensor tendon repair in zones 6, 7, and 8: a retrospective study. *J Hand Surg [Br].* 1989;14:21–22.
65. Uhl RL. Salvage of extensor tendon function with tenolysis and joint release. *Hand Clin.* 1995;11:461–470.
66. Creighton JJJ, Steichen JB. Complications in phalangeal and metacarpal fracture management. Results of extensor tenolysis. *Hand Clin.* 1994;10:111–116.
67. Moss JG, Steingold RF. The long term results of mallet finger injury. A retrospective study of one hundred cases. *Hand.* 1983;15:151–154.
68. Bowers WH, Hurst LC. Chronic mallet finger: The use of Fowler's central slip release. *J Hand Surg Am.* 1978;3:373–376.
69. Grundberg AB, Reagan DS. Central slip tenotomy for chronic mallet finger deformity. *J Hand Surg Am.* 1987;12:545–547.
70. Chao JD, Sarwahi V, Da Silva YS, et al. Central slip tenotomy for the treatment of chronic mallet finger: an anatomic study. *J Hand Surg Am.* 2004;29:216–219.
71. Hiwatari R, Kuniyoshi K, Aoki M, et al. Fractional Fowler tenotomy for chronic mallet finger: a cadaveric biomechanical study. *J Hand Surg Am.* 2012;37:2263–2268.
72. Thompson JS, Littler JW, Upton J. The spiral oblique retinacular ligament (SORL). *J Hand Surg Am.* 1978;3:482–487.
73. Girot J, Marin-Braun F, Amend P, et al. [Littler's operation (SORL = spiral oblique retinacular ligament) in the treatment of swan neck]. *Ann Chir Main.* 1988;7:85–89.
74. Massengill JB. The boutonnière deformity. *Hand Clin.* 1992;8:787–801.
75. Burton RI, Melchior JA. Extensor tendons – late reconstruction. In: Hotchkiss RN, Pederson WC, Kozin SH, et al., eds. *Operative Hand Surgery*. New York: Churchill Livingstone; 1999:1988–2021.
76. Dolphin JA. Extensor tenotomy for chronic boutonnière deformity of the finger; report of two cases. *J Bone Joint Surg Am.* 1965;47:161–164. *Description of the classic technique to address the problem of the boutonnière deformity.*
77. Fowler SB. The management of tendon injuries. *J Bone Joint Surg Am.* 1959;41-A:579–580.
78. Littler JW, Eaton RG. Redistribution of forces in the correction of boutonnière deformity. *J Bone Joint Surg Am.* 1967;49:1267–1274. *Littler and Eaton describe the pathophysiology of the boutonnière deformity and the results of 8 patients who were treated by detachment and proximal reinsertion of the lateral bands.*
79. Matev I. Transposition of the lateral slips of the aponeurosis in treatment of long-standing boutonnière deformity of the fingers. *Br J Plast Surg.* 1964;17:281–286.
80. Littler RW. The digital extensor-flexor system. In: Converse JM, ed. *Reconstructive Plastic Surgery*. Philadelphia: WB Saunders; 1977:3166–3183.
81. Suzuki K. Reconstruction of post-traumatic boutonnière deformity. *Hand.* 1973;5:145–148.
82. Watson HK, Weinzwieg J, Guidera PM. Sagittal band reconstruction. *J Hand Surg Am.* 1997;22:452–456.
83. Carroll CT, Moore JR, Weiland AJ. Posttraumatic ulnar subluxation of the extensor tendons: a reconstructive technique. *J Hand Surg Am.* 1987;12:227–231.
84. McCoy FJ, Winsky AJ. Lumbrical loop operation for luxation of the extensor tendons of the hand. *Plast Reconstr Surg.* 1969;44:142–146.
85. Wheelton FT. Recurrent dislocation of extensor tendons in the hand. *J Bone Joint Surg Br.* 1954;36-B:612–617.
86. Elson RA. Dislocation of the extensor tendons of the hand. Report of a case. *J Bone Joint Surg Br.* 1967;49:324–326.
87. Kilgore ES, Graham WP, Newmeyer WL, et al. Correction of ulnar subluxation of the extensor communis. *Hand.* 1975;7:272–274.
88. Bora FWJ, Osterman AL, Thomas VJ, et al. The treatment of ruptures of multiple extensor tendons at wrist level by a free tendon graft in the rheumatoid patient. *J Hand Surg Am.* 1987;12:1038–1040.
89. Moore JR, Weiland AJ, Valdata L. Tendon ruptures in the rheumatoid hand: analysis of treatment and functional results in 60 patients. *J Hand Surg Am.* 1987;12:9–14.
90. Williamson SC, Feldon P. Extensor tendon ruptures in rheumatoid arthritis. *Hand Clin.* 1995;11:449–459.
91. Wilson RL, DeVito MC. Extensor tendon problems in rheumatoid arthritis. *Hand Clin.* 1996;12:551–559.
92. Chung US, Kim JH, Seo WS, et al. Tendon transfer or tendon graft for ruptured finger extensor tendons in rheumatoid hands. *J Hand Surg Eur Vol.* 2010;35:279–282.
93. Nakamura S, Katsuki M. Tendon grafting for multiple extensor tendon ruptures of fingers in rheumatoid hands. *J Hand Surg [Br].* 2002;27:326–328.
94. Moore JR, Weiland AJ, Valdata L. Independent index extension after extensor indicis proprius transfer. *J Hand Surg Am.* 1987;12:232–236.
95. Magnussen PA, Harvey FJ, Tonkin MA. Extensor indicis proprius transfer for rupture of the extensor pollicis longus tendon. *J Bone Joint Surg Br.* 1990;72:881–883.
96. Noorda RJ, Hage JJ, de Groot PJ, et al. Index finger extension and strength after extensor indicis proprius transfer. *J Hand Surg Am.* 1994;19:844–849.
97. Haury B, Rodeheaver G, Vensko J, et al. Debridement: an essential component of traumatic wound care. *Am J Surg.* 1978;135:238–242.
98. Burke JF. Effects of inflammation on wound repair. *J Dent Res.* 1971;50:296–303.
99. Robson MC, Edstrom LE, Krizek TJ, et al. The efficacy of systemic antibiotics in the treatment of granulating wounds. *J Surg Res.* 1974;16:299–306.
100. Lister G, Scheker L. Emergency free flaps to the upper extremity. *J Hand Surg Am.* 1988;13:22–28.
101. Page R, Chang J. Reconstruction of hand soft-tissue defects: alternatives to the radial forearm fasciocutaneous flap. *J Hand Surg Am.* 2006;31:847–856.
102. Megerle K, Sauerbier M, Germann G. The Evolution of the Pedicled Radial Forearm Flap. *Hand (N Y).* 2010;5:37–42.

103. Reid DA. Hand injuries requiring skin replacement and restoration of tendon function. *Br J Plast Surg*. 1974;27:5–18.
104. Godina M. Early microsurgical reconstruction of complex trauma of the extremities. *Plast Reconstr Surg*. 1986;78:285–292.
105. Scheker LR, Langley SJ, Martin DL, et al. Primary extensor tendon reconstruction in dorsal hand defects requiring free flaps. *J Hand Surg [Br]*. 1993;18:568–575.
106. Sundine M, Scheker LR. A comparison of immediate and staged reconstruction of the dorsum of the hand. *J Hand Surg [Br]*. 1996;21:216–221.
107. Ulusal BG, Lin YT, Ulusal AE, et al. Free lateral arm flap for 1-stage reconstruction of soft tissue and composite defects of the hand: A retrospective analysis of 118 cases. *Ann Plast Surg*. 2007;58:173–178.
108. Bevin AG, Hothem AL. The use of silicone rods under split-thickness skin grafts for reconstruction of extensor tendon injuries. *Hand*. 1978;10:254–258.
109. Cautilli D, Schneider LH. Extensor tendon grafting on the dorsum of the hand in massive tendon loss. *Hand Clin*. 1995;11:423–429.
110. Adams BD. Staged extensor tendon reconstruction in the finger. *J Hand Surg Am*. 1997;22:833–837.
111. Quaba AA, Elliot D, Sommerlad BC. Long term hand function without long finger extensors: a clinical study. *J Hand Surg [Br]*. 1988;13:66–71.

11

Replantation and revascularization

William W. Dzwierzynski

Access video content for this chapter online at expertconsult.com



SYNOPSIS

- Replantation should be considered for all amputated parts; the only absolute contraindication to replantation is a patient too sick to tolerate surgery.
- A “string sign” or “ribbon sign” in the amputated part suggests the digital vessels are not suitable for replantation.
- Skeletal shortening should be considered. Bone shortening also facilitates a primary nerve and vessel repair.
- Rigid bone fixation is desired for early mobilization. Interosseous wires offer an excellent option for rigid fixation.
- Revascularization of amputations proximal to the wrist should be performed before 12 hours of cold ischemia (6 hours of warm ischemia). If ischemia time is over 4 hours, consideration should be given to temporary arterial shunting prior to bone fixation.
- Pharmacological management of replantation and revascularization remains controversial. Our current protocol includes heparin irrigation at a dilution of 100 units/mL during surgery and a heparin bolus of 50–100 units/kg before release of microvascular clamps.
- The psychological implications of amputation and replantation must be considered. The hand plays a significant role in a patient's identity and psyche.

Introduction

Restoring life has always been a dream. From the mythological resurrection of the phoenix to the rising of Lazarus from the dead, returning life to the dead remains a miracle. Replantation restores life to the lifeless extremity: a miracle of modern surgery.

Basic science/disease process

Pathophysiology of ischemia and reperfusion

Tissue tolerance to ischemia varies significantly. In normal ambient temperature, irreversible changes can occur in muscle with only 2 hours of ischemia; skin properly cooled and stored in a nutrient media can be viable for over a month.⁴ Ischemia causes tissue hypoxia and the conversion from aerobic to anaerobic metabolism. Adenosine triphosphate (ATP) is produced by glycolysis which leads to the buildup of lactic acid in the tissue and the resultant reduction of intercellular pH.⁵ As the supply of ATP is diminished, intracellular Na^+ and Ca^{2+} concentrations are increased. Chemical mediators and enzymes are triggered by ischemia, resulting in the production of phospholipase A_2 and lysozymes. If continued beyond the critical point, these processes lead to eventual cell necrosis.

Revascularization is essential before these processes become irreversible, but revascularization can lead to its own problems. Reperfusion injury can cause problems as severe as the initial ischemic insult. When ischemic tissue is suddenly reperfused, reactive oxygen species (ROS) are produced. These include superoxide (O_2^-), hydrogen peroxide (H_2O_2), and hydroxyl radical ($\text{OH}^\cdot$).⁶ The ROS react with the cell membranes, especially in the endothelial cells. They cause direct cell damage and produce inflammatory mediators, complement activation, and leukocyte adhesion. This cascade increases vascular permeability and can cause cell death despite revascularization. Reperfusion-generated mediators may have systemic effects when vessels are unclamped and the inflammatory mediators are released to the circulation. This can lead to a decreased level of consciousness, jaundice, cardiac arrhythmia, metabolic acidosis, myoglobinuria, and multisystem organ failure.⁷ Methods to prevent or reduce ischemia–reperfusion injury include hypothermia, interarterial flushing, ischemic preconditioning, antithrombotic agents,



Access the Historical Perspective section online at

<http://www.expertconsult.com>

Historical perspective

Malt performed the first replantation on May 23, 1962 at the Massachusetts General Hospital on a 12-year-old boy who had his arm amputated in a train accident.¹ The first digital replantation was performed in Japan on January 7, 1965 by Komatsu and Tamai.² Subsequent to these historical events, replantation surgery took off with a flourish. China was the epicenter of early replantation surgery. The American Replantation Mission to China report in 1974 highlighted the replantation efforts in China to an astonished American surgical audience.³ The boundaries of replantation surgery continue to expand, now reaching into the realm of extremity transplantation.²

free-radical scavengers, and leukocyte inhibitors.^{4,5} While many of these techniques show promise experimentally or in elective free flap surgery, pretreatment is not an option in traumatic replantation and revascularization. In major limb replantation, once arterial flow is established, the vein should be allowed to bleed to eliminate ROS, prior to establishing flow to the systemic circulation.

Diagnosis/patient presentation

Transportation

The most critical factors in replantation and revascularization surgery are management of the patient and the amputated part. Proper handling of the amputation is essential to revascularization and replantation success. The part is wrapped in moist saline gauze and placed in a waterproof plastic bag. The plastic bag is placed in a container of ice (Fig. 11.1). The part should not come into direct contact with the ice. Freezing the severed extremity can cause direct irreversible damage to the microvascular system. Timely, efficient transportation of the patient and the amputated part to the replantation center is critical for survival and function. Muscle undergoes

Table 11.1 Replantation center criteria

1. An efficient ground and air transportation system to transfer the patient from the injury site or referring hospital to the replant center
2. Experienced microsurgical teams, able to work in shifts
3. A well-prepared emergency room staff to stabilize and quickly evaluate the patient with physical examination, X-rays, and laboratory tests
4. Experienced anesthesiologists, operating room, and microsurgical staff available 24 hours/day, 7 days/week
5. Proper microscopes, instruments, and sutures
6. A carefully trained nursing staff for postoperative care and monitoring
7. Physical and occupational therapists trained in post replantation rehabilitation
8. Psychologists and social workers to help the patient cope with his or her injuries and continue an active and useful life

irreversible damage with ischemia times greater than 6–9 hours. Digits can tolerate longer periods of ischemia. Successful replantation can be achieved even after prolonged ischemia. VanderWilde *et al.* reported a successful hand replantation after 54 hours of cold ischemia.⁸ Wei *et al.* reported a series of three successful digital replants with 84, 86, and 94 hours of cold ischemia.⁹ All patients had satisfactory functional results and no vascular compromise. Lin *et al.* reviewed their experience with 31 replantations (two thumb, 21 finger, and two hand amputations), all with over 24 hours of either cold or warm ischemia. The overall success rate was 64%. Only one of the hands was successfully replanted; 15 of the 23 digits were salvaged.¹⁰

Replantation center

A replantation center, usually a trauma center, with a dedicated team is optimal for success of replantations. The replantation center should include an emergency room and paramedic system familiar with the transportation of the injured patient and the amputated part (Table 11.1). This often includes a medical air transportation system to facilitate rapid transportation from the accident scene. At the replantation center, the operating room should be large enough to allow two independent surgical teams to operate, one on the patient and the second on the amputated part (Fig. 11.2). Chung *et al.* reviewed the database from the Agency for Healthcare Policy and Research, evaluating 304 cases of finger replantation. Over 906 hospitals were represented in the database but only 15% performed a finger replantation in the year reviewed; 60% of these hospitals performed only one replant. Only 2% of the hospitals in the database performed 10 or more cases. He postulated that replantations should be best performed at high-volume centers.¹¹ Chen and Narayan reviewed the economic trends of upper extremity replantations over a 10-year period and found an increasing tendency for these surgeries to be performed at large teaching institutions.¹² A survey of members of the American Society of Surgery of the Hand found that only 56% of its members perform replantation surgery, despite 94% of the responders describing their microsurgical training as good or excellent.¹³




Fig. 11.1 The amputated part should be wrapped in moist gauze placed in a plastic bag which is chilled in an ice–water mixture. Direct contact of the part with the ice must be avoided.



Fig. 11.2 Replantation operation room set-up. The pressure pump is situated at the patient's head. The fluid cooler/warmer (far right) is used for icing the amputated part.

Patient selection

Indications and contraindications

Needless to say, the critical patient selection criterion for replantation is a patient with an amputation. The amputated part must be both available and in satisfactory condition for the replantation (Table 11.2). Digits recovered from the stomach of an attacking animal or extracted from industrial grinders generally do not meet this criterion. Outside these obvious examples, replantation should at least be considered for all amputated parts. Generally accepted indications for replantations in the upper extremities are thumb amputations, multidigit amputations and any amputation in a child.¹⁴ Often adult patients with single-digit amputations, especially the index finger, are generally not considered candidates for replantation.¹⁵ Replantation of a single digit is generally indicated in children. This is partly due to improved healing in children but also because of the future potential of the child. Lower-extremity and upper arm replantations also are indicated in a child.

Table 11.2 Indications for replantation

Strong indications

- Multiple digital amputations
- Thumb amputations
- Whole hand
- Transmetacarpal and partial hand amputations
- Any amputated part in a child
- Single digit amputation distal to flexor digitorum superficialis insertion

Relative indications

- Sharp injuries at elbow or proximal forearm
- Humeral-level amputations

Thumb amputations also deserve special emphasis. While thumb reconstruction can be achieved with methods such as pollicization or toe transfer, these reconstructions have a significant donor site cost. Thumb replantation should be considered even if shortening or arthrodesis is necessary. The thumb primarily functions as a post for opposition. Decreased motion in a thumb is generally well accepted, and even a stiff thumb contributes to the overall function of the hand.

Patients who have lost multiple digits also deserve an extra consideration in replantation. Where a single digit loss may be well tolerated, patients who have lost multiple digits have a significantly greater disability. Salvaging one or two fingers in a mutilated hand may preserve essential function of the hand. In multiple-digit amputations consideration should also be made for "spare-parts surgery". If an amputation is through the metacarpophalangeal (MCP) joint of the long finger and more proximal on the index finger, replantation of the index finger to the long finger ray, preserving the joint, may increase the patient's overall function. Replantation above the elbow is advocated for preservation of elbow function but generally distal function in the hand is poor.¹⁶ Fingertip replantations, once considered not indicated, are now seen as an excellent level of replantation. Replantation of a digit distal to the flexor digitorum superficialis (FDS) insertion generally has excellent function because only one flexor tendon requires repair, and should be strongly considered.

The only absolute contraindication to replantation is preserving life over limb. A patient with life-threatening injuries or multiple medical problems who cannot withstand prolonged surgery should not undergo replantation. An uncooperative patient is also a contraindication for replantation.¹⁴ In a patient with acute major life-threatening injuries, an amputated hand or digit may be kept in cold storage and the patient reassessed in 24 hours. If the patient is stable enough to undergo surgery, delayed replantation may be considered.

There are several relative contraindications to digital replantation¹⁷ (Table 11.3). These contraindications are related both to the microvascular success rate and ultimate hand function compared to an amputation revision. All patients must be evaluated individually to determine if they are a candidate for digital replantation. While age is not an absolute contraindication for replantation, older patients carry a greater risk of arteriosclerosis of the vessel, joint stiffness, and generally decreased function secondary to less recovery of sensation. Okada *et al.* reviewed eight replantations in patients over

Table 11.3 Relative contraindications to replantation

- Concomitant life-threatening injury
- Systemic illness (e.g., small-vessel disease)
- Poor anesthesia risk
- Mentally unstable patients
- Single finger proximal to flexor digitorum superficialis insertion in adults
- Multiple segmental injuries in the amputated part
- Severe crushing or avulsion of the tissues
- Extreme contamination
- Prior surgery or trauma to the amputated part
- Prolonged warm ischemia time
- Ribbon sign, red line sign
- Most index finger amputations

65 years old. Function of these digits was generally classified as poor, although all patients were satisfied with their results. Expectations in the elderly patient may be less than those of a younger patient.¹⁸

Treatment/surgical technique (Video 11.1 ▶)

Operative sequence

Replantation surgery is an exacting and strenuous operation. It should proceed in an organized and deliberate fashion. When replantation is considered feasible, the amputated part is brought to the operating room and explored to identify the neurovascular structures. This may even be performed while the patient is still in the emergency room being evaluated and stabilized.

If two surgical teams are available, both the amputated part and the patient can undergo simultaneous surgery. The amputated part is brought to the operating room first. Using loupe magnification, all structures are examined. The blood vessels and nerves are usually examined at high magnification with the operating microscope before committing to perform a replantation. Under the operating microscope, the part is examined for suitability of replantation. Tissue loss is evaluated, along with the level of amputation. Multiple levels of injury may be found which were not apparent during the emergency room examination. The neurovascular structures should be evaluated for evidence of avulsion injuries. A string sign or ribbon sign means the digit is not suitable for replantation. These signs are indicated by a red streaking of blood along the path of the artery, usually implying an avulsion injury. The artery and nerves should be identified and tagged with a 7-0 polypropylene suture or microclips. If the digital vessels cannot be readily identified through the wound, the digital vessels can be exposed through a midaxial incision (Fig. 11.3). Dorsal veins are identified and tagged in a similar fashion. The location of the veins is more variable, and they may not be readily visible. Two or three veins should be identified. Preliminary bone fixation and methods of tendon repair are considered at this time. The digital tendon suture may be placed while the amputated digit is on the back table. The distal aspect of the bony fixation can also be secured, whether this is with K-wires, interosseous wires, or a mini fixation plate.

Once the patient is under anesthesia, the proximal level of the injury is explored. Replantation surgery is usually performed under general anesthesia. Regional anesthesia may be considered for a cooperative patient. Regional anesthesia offers the added benefit of decreased postoperative pain and possible vasodilatation. A Foley catheter is inserted and proper body warming is assured by utilizing a warming blanket and warming the operating room. All pressure points should be well padded to avoid pressure injuries; this includes the occiput to avoid scalp alopecia.

The sequence of the repair in digital replantation varies among surgeons, with some advocating arterial repair after bony fixation and flexor tendon repair while others advocate repair of the dorsal structures, including the extensor tendon, dorsal veins, and skin prior to repairing any volar structures.¹⁷ The author favors repairing the volar structures first, and then




Fig. 11.3 (A,B) A midlateral exposure of the amputated part offers greater access to the neurovascular structures.

proceeding to the dorsal structures. Repair of the extensor tendons is performed prior to releasing the tourniquet. Dorsal veins are repaired either before or after tourniquet release, depending on their visualization.

Bone fixation

The time spent in achieving rigid digital fixation is well worth the additional effort required (Fig. 11.4). Adequate fixation of the replanted digit is essential not only for short-term healing but also for long-term function. Rigid fixation of the bony fracture can reduce pain, allow early mobilization of the hand, and improve long-term function. The final outcome of the replantation lies in the ultimate function of the hand. Function is linked to motion, and motion is optimized by early mobilization. Rigid bone fixation is desired for early mobilization. Skeletal shortening should be considered in all replantations; this can allow more secure bone fixation and lessen the need for vessel and nerve grafting¹⁴ (Fig. 11.5). In a thumb, shortening of the digit should be performed judiciously.¹⁹

A variety of methods are available for bone fixation. The simplest method is K-wire fixation. K-wires are universally available and can be easily and rapidly inserted. The simplest fixation is a longitudinally placed K-wire. While easily performed, longitudinal K-wires have many disadvantages.




Fig. 11.4 Techniques of bony fixation include: (A) crossed K-wires; (B) single longitudinal K-wire; (C) I-O wire and K-wire; (D) 90-90 I-O wires; (E) intermedullary fixation; (F) compression plate; (G) H-plate; and (H) lag screw.



Fig. 11.5 (A) 46-year-old with distal forearm amputation. (B) Bone shortening and dynamic compression plating allowed primary repair of the neurovascular structures. (C) Hand after replantation and fasciotomies.

K-wires do not offer rigid fixation, longitudinal K-wires do not control against rotation and, almost by necessity, must go through the joint. Longitudinal K-wires are best utilized in distal replants and revascularizations where other fixation methods may not be technically feasible.

Cross K-wires offer more advantages than longitudinal K-wire fixation, most notably the control of rotation. Cross K-wires can be difficult for the novice to perform in simple fracture fixation and devascularization injuries, but complete amputation simplifies the process of cross K-wire placement. While the amputated digit is on the back table, the K-wires can be inserted in a retrograde fashion. The neurovascular structures need to be meticulously protected and the amputated part securely held to avoid spinning the part uncontrollably.

Kirschner wires offer control of rotational deformity but greater care must be taken with early digital motion. Cross K-wires give an acceptable result although rigid fixation is not achieved. Late digital stiffness and fracture malunion may occur. Kirschner wires should be reserved for cases where rapid fixation is necessary and in children.¹⁹

Interosseous (I-O) wires offer an excellent option for rigid fixation in amputations. I-O wires can be technically demanding to perform, but offer the advantage of rigid fixation and the ability to correct for any rotational deformity prior to final tightening of the wires. Three sets of wires, two longitudinal and one radial ulnar, give as much rigidity as a fixation plate. The exposure granted by the amputation allows easier access to the bone for I-O wire placement. The ends of the wires should be turned in to the fracture site to add additional strength to the configuration and to avoid impingement on the tendons.²⁰ Ninety-ninety-wire bone fixation has a low nonunion rate and provides secure compression of the fractures.^{17,19,21,22} Bioabsorbable poly-DL lactic acid rods have been introduced for rapid intermedullary fixation of phalangeal replantations. A series of 9 replanted digits show initial strength to tolerated early motion protocols and good to excellent results in all cases.²³

Clinical tips

Interosseous wire fixation is a quick and secure method of bony fixation for digital replantations. While the amputated part is on the back table, two tunnels – one radial to ulnar and one dorsal to volar – are made with a 21-gauge hollow needle or K-wire. The 21-gauge needle allows a 26-gauge wire to pass through the tunnel easily.

Plate fixation offers secure fixation for fractures. Standard miniplates, while offering secure fixation and compression, have the disadvantage of requiring significant periosteal stripping and more extensive soft-tissue exposure. Small “H” plates offer similar fixation strength with less exposure and periosteal stripping. One disadvantage of plates is the lack of adjustability. If distinct registration points are not present on the bone, improper fixation can lead to rotational deformities. The increased dissection and periosteal stripping may lead to increased scarring and tendon adhesions. Generally plate fixation is more time-consuming than other methods of fixation. A low-profile H-plate may allow less dissection; however, this

application is technically demanding and angulation and malunions can occur.¹⁹

Tendon repair

Secure tendon repair is necessary for early-motion protocols. Inexperienced surgeons may desire to fix the tendons quickly in order to move on to the revascularization of the fingers. In properly cooled digital amputations, ischemia time can be safely prolonged without any deleterious effects on success rates and overall function. The extra 20–30 minutes required to obtain a good tendon repair is time well spent. We prefer to use a modified Kessler repair along with an epitendinous suture. The Kessler repair is easy and quick to perform. The use of a looped 4-0 braided polyethylene fiber suture allows a strong four-strand repair without significant bulk. The epitendinous suture supplies increased strength, facilitates tendon gliding, and allows proper tendon tensioning of the core suture. The pulleys should always be preserved. The distal core suture may be first performed and then the tendon is glided under the pulley for the final repair.

The distal core tendon suture is usually performed on the back table. The proximal tendon is identified and secured with a 25-gauge needle to the underlying tissue to prevent retraction. Utilizing a 6-0 polypropylene suture, the epitendinous repair is started on the dorsal aspect of the tendon, with a locked, running suture. After completion of the dorsal epitendinous repair, the core suture repair is woven through the proximal portion of the tendon. The knot is tied in the substance of the tendon. Finally the volar epitendinous repair is performed with a running locking stitch, utilizing the remaining portion of the 6-0 polypropylene suture. This four-strand repair is strong enough to initiate early active motion protocols.

Clinical tips


In tendon repair, performing the back wall of the epitendinous suture first allows better approximation of the core suture. The tendon is held securely with a 25-gauge needle to the soft tissue, and then a running locking 6-0 polypropylene suture is used for the back wall. The core suture is placed without any tendon “bunching”. The running polypropylene suture is then continued on the volar aspect of the tendon.

Controversy exists among surgeons as to whether both the FDS and FDP tendons should be repaired in zone 2 replantations.²⁴ Waikakul *et al.*, in their series of 1018 replantations, found patients who had a sharp guillotine zone 2 amputation had good to acceptable results in terms of range of motion with repair of both tendons. In crush, degloving, or avulsion injuries, repairing only the FDP tendon or both tendons gave poor results. Repairing the FDP stump to the proximal superficialis tendon gave the best result, which was statistically significant.²⁵ Ross *et al.* prospectively evaluated tendon function after replantation using a modified Kessler repair with 4-0 polyester suture. The average total active motion was 129°. Patients with zone 1 and 5 injuries had a significantly better active range of motion. Replantation after avulsion injury resulted in lower range of motion compared to sharp injuries. When they evaluated patients who had one tendon

repaired versus those with a repair of both tendons, the average motion for fingers with both tendons repaired was 136° compared to 111° for fingers with only the FDP tendon repaired. This was statistically significant. Of all factors in the surgeon's control, the most important was initiating early therapy. Early therapy increased both active and passive range of motion and did not significantly increase the incidence of tendon rupture.²⁴

Artery repair

A patent arterial repair is essential to successful replantation. The red line sign, or ribbon sign, is an indication of torsion or stretch of the vessel and suggests a relative contraindication to replantation.²⁶ Arteries should be debrided to beyond the zone of injury. The lumen of the artery should be explored to make certain there are no intimal flaps which can cause thrombosis. The arteries should be examined and cut back, as necessary, prior to inflation of the tourniquet. The vessel is flushed with a dilute heparin solution at a concentration of 100 units/mL. The heparinized saline solution can be placed in a pressure bag to assure a constant, accurate irrigation pressure (Fig. 11.6). Manual irrigation with a standard 3-cc syringe may produce excessive irrigation pressure. Yan *et al.* found that irrigation pressures under 80 mmHg are as effective as higher pressures at removing clots and did not damage the vessel endothelium.²⁷ After irrigation, the vascular clamp is released to visualize the arterial flow. If the artery does




Dorsal venous arch of foot

Fig. 11.7 The dorsum of the foot provides a source of potential vein grafts. The branching pattern allows revascularization of several vessels.



(A)



(B)

Fig. 11.6 (A) Pressure bag irrigation with pharmacy-prepared heparin irrigation solution. (B) Irrigation hand control.

not have a strong pulsatile flow, the vessel is cut back and irrigated until pulsatile flow is obtained. It is preferable to repair both digital arteries, if possible. Zumtotti *et al.* found that when two arteries and more than one vein were anastomosed, the success rate was highest.²⁸ In the index finger, long finger, and thumb, the ulnar digital artery is usually larger and should be preferentially repaired. In the small finger, the radial digital artery is usually of larger diameter. Adequate exposure to the blood vessels is essential. Skin hooks attached to rubber bands may facilitate artery exposure. If this is not adequate, additional incisions should be made to aid exposure. In the proximal and middle phalanx, zigzag incisions are preferable, while in distal replantations a midaxial incision is preferred.¹⁴

If after proper debridement the gap precludes primary repair, a vein graft should be used. Theoretically an increased potential of thrombosis exists when vein grafts are used since there are two microvascular anastomoses. However, clinical studies do not support an increased incidence of thrombosis. When vein grafts are utilized, venous discrepancies may be managed by a variety of techniques, including fish mouth incisions, sleeve anastomosis, or end-to-side coupling or step-down vein grafts.²⁹ Vein grafts can be harvested from the palmar side of the thenar eminence of the hand, the distal volar forearm, or the dorsal foot (Fig. 11.7). For arterial reconstruction in the finger, the author prefers the dorsal foot veins because they are thicker-walled and better match the digital artery. For more proximal amputations the greater or lesser saphenous veins can be harvested. When there is a large discrepancy between the distal and proximal vessels, an

arterial graft should be considered. Sources of grafts include the superficial or deep inferior epigastric arteries, the descending branch of the lateral femoral circumflex artery and the subscapular artery system. Shuck and Masden reviewed the use of arterial grafts; no long term outcome studies have been published but intermediate outcome studies show patencies up to 100%.³⁰

Lee *et al.* prospectively followed 75 finger replantations with Doppler examinations for 60 days postoperatively. In 37% of successful replantations Doppler signals, which were initially present, were not heard on postoperative day 15. This rate was five times greater for crush injuries than for guillotine amputation. Their replantation center now routinely administers anticoagulants for 2 weeks in all replantations, regardless of the degree of tissue damage. They postulate that by continuing anticoagulation, reduced morbidity such as cold intolerance and sensory abnormalities may be achieved.³¹

Vein repair

Repair of the veins is one of the most crucial steps in replantation. The number of veins repaired correlates well with success in digital replantation.^{32,33} In a devascularized extremity or digit, a small skin bridge of only a few millimeters can allow adequate venous outflow. Dorsal veins can be found by identifying bruising or small hematomas just under the skin (Fig. 11.8). The veins are usually repaired after repair of one or both of the digital arteries. If ischemia time is prolonged, the vein can be repaired after the first digital artery and then the hand supinated to repair a second digital artery. Vein grafts to bridge segments of venous loss are used as required. Additional length on dorsal veins may be achieved by dividing the interconnecting branches between the veins. At least one vein should be repaired prior to release of the arterial clamp. If a vein could not be identified on the initial




Fig. 11.8 Ligation of branches of the dorsal subcutaneous veins can provide additional length for primary venous repair.

exploration of the amputated part, release of the arterial clamp will allow visualization of the dorsal veins as they fill with blood; but the resulting bleeding may obscure the clean microvascular field.

A functional venous anastomoses is important to overall success rate in replantation; however, the more distal the amputation, the less this factor comes into play. Distal amputations can be successfully replanted even without a venous anastomosis as long as some method of venous egress is assured.^{34–37} In a series of 120 replantations distal to the FDS insertion, a 91.7% success rate was achieved when two veins were repaired. This success rate dropped to 84.4% when only one vein was repaired, but with no vein anastomosis, a 40% success rate was still achieved.³⁸ The Chang Gung hospital group from Taiwan reviewed 30 fingertip amputations performed without a venous anastomosis. 90% of the digits survived, however the average transfusion rate was 4.0 units of blood; and the average length of time needed to maintain external bleeding was 6.8 days.³⁹ Various methods of venous outflow other than direct vein coaptation have been described. These include use of leeches (*Hirudo medicinalis*), arterial venous anastomoses, nail plate removal, heparin rubs, subcutaneous heparin instillation, nail ablation, and dermal implantation.^{34,35,39–41}

Nerve repair

Sensibility is even more important than range of motion.¹⁴ Primary repair of the nerve can be performed in most clean guillotine-type injuries. Bone shortening facilitates a primary nerve repair.⁴² Patient factors influencing nerve recovery are age, level of injury, and mechanism of injury. Surgeon-controllable factors include digital blood flow and postoperative sensory re-education. Repair of more than one artery improves nerve recovery.⁴³ If there is any question of the quality of the nerve it should be debrided to identify a good fascicular pattern. Nerve grafts or conduits can be used for small nerve defects. Conduits are constructed utilizing a variety of materials, including segments of vein, collagen, silicone, Gore-Tex, polyester, and polyglycolide.⁴⁴ Conduits are best limited to defects of less than 2 cm in length.⁴⁵ Some conduits are extremely rigid and may impede motion if placed over a joint or are at risk for erosion of overlying skin. Conduits are best used for sensory nerve defects; for motor nerves standard nerve autografts are preferred. Nerve grafts can be harvested from a variety of donor sites. In the upper extremity these include the posterior interosseous or median antebrachial cutaneous nerves. The sural nerve is the standard donor graft in the lower extremity. The fascicles of the sural nerve match the digital nerve topology well. After successful nerve repair, replanted fingers typically achieve protective sensation with a two-point discrimination under 15 mm, and the majority will achieve static two-point discrimination less than 12 mm.⁴⁶

Skin closure

Skin closure should be performed with special precautions not to constrict arterial inflow or venous outflow. If there is any concern a skin graft should be utilized. A small graft over the midlateral incision covering the vascular pedicle is far safer than a tight closure. If there is a deficit of skin and an

arterial defect requiring a vein graft, consideration should be given to using a venous flow-through flap (vascularized by the digital artery).⁴⁷ The flap is harvested from the distal ipsilateral volar wrist or forearm. A vein of sufficient size is identified and a skin flap slightly larger than the skin defect is designed, centered over the vein. The flap should not extend more than 1.5 cm from the vein. The vein is reversed and used to bridge the arterial defect and the skin island covers the skin defect.

Special circumstances

Thumb replantation

Thumb replantation and revascularization deserve special consideration (Fig. 11.9). The ulnar digital artery of the thumb is usually of larger caliber and is preferentially repaired. The ulnar digital artery of the thumb, however, is difficult to access under the microscope. Even with the use of a lead hand, exposure is a challenge. It is the rare revascularization where a direct arterial repair is possible. The use of an interpositional vein graft from the radial artery to the snuff box simplifies revascularization in thumb replantation^{17,19} (Fig. 11.10). An 8–10-cm vein graft is harvested, usually from the dorsal foot or saphenous vein. The graft is reversed and irrigated. The distal anastomosis of the vein graft is performed on the back table before bone and tendon fixation. Performing the anastomosis on the back table allows easy positioning of the amputated thumb. The distal aspect of bone fixation should be performed prior to the distal revascularization. Care should be taken when doing the proximal bone fixation, as the vein graft can easily become wrapped up in the power equipment. In the thumb pulp sizable palmar veins can usually be identified superficial to the arteries and these should be identified.⁴⁸

Rosson *et al.* compared the functional outcome of thumb replantation versus great toe transplantation. In 384 thumb amputations over a 20-year period, an 85% success rate was obtained in thumb replantations. Complications occurred in 29% of cases. The average replant patient underwent four additional operations. Patients achieved 30% diminished protective sensation and light touch as compared to the normal contralateral thumb. In great toe to thumb transplantations the surgical success rate was 93%, but 43% of patients had complications. The motion in the interphalangeal joint was better in toe transplants than in the replanted thumb; sensation was comparable in both groups.⁴⁹

Multiple digits

Multiple digit replantations are a significant surgical challenge and should be performed in a replantation center with significant experience in this type of surgery (Fig. 11.11). The time commitment is considerable: 3–4 hours should be allowed for each amputated finger. There may be a time-saving benefit from performing all the bony and tendon work first, then bringing in the microscope to do the microvascular repairs. Although total surgical time may be reduced, the warm ischemia time for each digit is increased. As many digits as possible are replanted. The finger with the best chance of function is repaired first. An exception to this rule is the index finger. If the index finger is stiff or has decreased sensation,

the patient often avoids use of this finger.¹⁹ Replantation of the distal amputation of the ring and little finger is strongly advocated because of their need for full length in order to get optimal hand closure and good grip function, especially when torque needs to be applied.¹⁴

A functional hand can be achieved with an opposable thumb, a satisfactory first webspace, a stable wrist, and at least two fingers. Heterotrophic replantation can maximize hand function. If the thumb and index finger are amputated and the distal thumb is not replantable, replantation of the index finger to the thumb position, a microvascular pollicization, should be performed.⁵⁰ Forty to 50% of hand function is accounted for by the thumb. Restoration of at least two fingers is most important in achieving hook grasp, power grasp, and precision handling.⁵¹ The value of the ulnar digits to hand function, especially power grip, is underappreciated. Priority should be given to restoration of the ulnar digits after salvage of the thumb.

A functional MCP joint is a significant priority for determining digital reconstruction. Digits with injuries through the MCP joint should be considered for heterotrophic transfer to another ray with a functional MCP joint. "Spare-parts surgery" should be considered in any multidigit amputation. If a digit is non-replantable, skin can be harvested for use as a skin graft. Tendon, nerves, and vessels can also be used for grafts.

Proximal amputations

Amputations at the level of the palm and proximal forearm offer unique challenges and opportunities. The functional deficit of amputations at this level is devastating and replantation and revascularization offer the opportunity for meaningful function of the hand. At this level, the vessels are larger and the procedure is technically easier. Because of the presence of muscle in the amputated part, timing of revascularization is critical. Revascularization of wrist and more proximal amputations should be performed before 12 hours of cold ischemia or 6 hours of warm ischemia.³ Rapid revascularization is necessary to preserve muscle viability and prevent myoglobinuria. For injuries at the level of the distal forearm and hand, preservation of the intrinsic muscles is important to hand function but unlikely to result in myoglobinuria if critical ischemia time is exceeded. The risk of reperfusion injury is low due to their small mass; if function of the muscle is to be preserved, revascularization should be expediently performed (Fig. 11.12). If the injury is at the level of the palmar arch or distal, an arterial graft or reversed "Y" vein graft, usually from the dorsal foot, can be harvested to revascularize multiple common digital arteries (Fig. 11.13).

Injuries in the distal forearm and wrist have excellent functional results after replantation and every effort should be made to salvage these injuries.⁵² Bone fixation should be performed first, shortening of the bones at this level provides quicker fixation and decreased need for vein and nerve grafts, and yields almost no functional loss. If ischemia time is over 4 hours, consideration should be given to temporary arterial shunting prior to bone fixation. A carotid shunt or an intervascular catheter is used (Fig. 11.14). Only one artery and one vein is required to revascularize the extremity successfully. After opening the arterial clamp, bleeding from multiple distal veins will require ligation or clamping with microvascular clamps. The risk of exsanguination with arterial and





Fig. 11.9 (A) A 22-year-old college student with a thumb avulsion amputation. The arteries were avulsed at the level of the interphalangeal joint. The digital nerves were avulsed in the carpal tunnel. (B) The amputated thumb with avulsion of the flexors and extensor tendons from the muscle origin. (C) Radiograph of hand. (D) The subscapular arterial tree provides an accessible source for a stepdown arterial graft. (E) Early postoperative photo of successful replantation. The patient developed protective sensation and useful opposition function of the thumb.




Fig. 11.10 If a primary anastomosis cannot be performed, the gap can be bridged with a reversed vein graft or transposition from an adjacent proper digital artery.

venous shunts is significant. Considerable bleeding can occur and the patient should have matched blood available. If shunting is utilized, the vein should be allowed to drain prior to connecting it to the proximal circulation.⁵³

In patients with a multiple-level mangled extremity, the goal of treatment is to restore prehension and sensibility. A sensate partial hand is quite often better than a prosthesis¹⁶ (Fig. 11.15). However patients with crush or avulsion injuries may be poor candidates for replantation. Adequate debridement is the critical first step in reconstruction.⁵⁴ Vein grafts should be liberally used to avoid injured segments of artery and vein.²⁹ With major limb replantation, fasciotomies are usually required. Godina emphasized that, upon completion of aggressive debridement, the wound should resemble a tumor resection.⁵⁵ Nonviable tissue with bacterial contamination is associated with loss of salvaged limb. The sequence of repairs for forearm replantation is bony fixation followed by arterial and venous repair. The vena comitantes should be repaired primarily; if this is not successful, then dorsal or antecubital veins are utilized. Nerves should be repaired after the arteries with the possible exception of the ulnar nerve, which lies deep to the ulnar artery.⁵⁴

Amputations at the proximal forearm present a difficult clinical decision process. Functional results are generally worse at this level than in more distal amputations. Because of the loss of muscle tissue, poor motor nerve recovery, loss of intrinsic function and postoperative scarring, results after replantation at this level are disappointing.

Amputations proximal to the elbow should be considered, if only to salvage a functional elbow joint. Recovery of distal function is poor. The greater muscle mass in a proximal limb




Fig. 11.11 (A) Four-finger amputation in a 26-year-old smoker. (B) Radiographs demonstrate amputation distal to the flexor digitorum superficialis insertion. (C) Radiographs of the amputated digits. (D) Immediately postoperative, after four-finger replantation. Small skin grafts were harvested to cover dorsal veins. (E) Radiographs demonstrate secure fixation with 90-90 I-O wire technique. (F) Six months postoperatively. The replantation was lost on the small finger despite salvage attempts. (G) Excellent function of the hand was achieved despite minimum motion at the distal interphalangeal joints.




Fig. 11.12 (A) Miter saw injury in a 26-year-old carpenter; all fingers were avascular. (B) Preoperative radiograph. (C) Radiograph demonstrating fixation with I-O wires and crossed K-wires. (D) Postoperative extension. (E) Postoperative flexion.

amputation is more susceptible to ischemia time. Metabolic breakdown products from the muscles entering the systemic circulation after revascularization can result in reperfusion syndrome. Death may occur in patients with above-elbow replants who develop reperfusion syndrome.⁵⁶ A functional elbow and below-elbow prosthesis may offer the patient the best result, but many patients are reluctant to undergo a revision amputation after a successful replantation despite having poor function.

Distal amputations

Replantation distal to the distal interphalangeal (DIP) joint was once considered as folly. Patients with amputation revisions at this level generally did very well functionally. Recent experience with distal replantations now shows both excellent

success and functional and aesthetic results with replantations (Fig. 11.16). These distal anastomoses can challenge the surgeon's microvascular skills (Fig. 11.17). In distal crush injuries it is often difficult to get the proper size match of the distal artery. Transfer of a digital artery from an adjacent digit may be utilized, especially in children where the size match is critical.⁵⁷ A step-down arterial graft should be utilized if a vein graft is required and the reversed vein segment has too great of a size mismatch. A method of temporary intravascular stenting using 4-0 to 6-0 (0.199–0.07 mm) nylon monofilament stents for very-small-vessel anastomoses has been advocated for distal fingertip amputations; 11-0 or 12-0 sutures are placed in the vessel around the stent, which is removed prior to the last two sutures being placed. Vessels as small as 0.15 mm have been anastomosed using this technique. Microvascular survival of 85% has been reported.⁵⁸




Fig. 11.13 Branches of the subscapular artery are utilized for revascularization of multiple distal vessels.

While arteries in very distal replants can be difficult to repair, veins may be a nightmare. The surgeon should be familiar with the venous anatomy of the digits and the thumb. Repairing volar veins may be preferable in these distal injuries, since they are easier to dissect than the dorsal veins, which lie in a dense fibrous tissue.⁵⁹ Occasionally suitable veins for repair are not available; a successful outcome can still be obtained in these cases if there is an effective means of ensuring temporary venous outflow while the collateral circulation develops. The primary method of temporary venous

outflow is medicinal leeches. Leeches effectively remove congested blood and detach when engorged. Additionally, they inject hirudin, a potent anticoagulant which results in bleeding long after the leech detaches.

The leech is applied to the congested part and allowed to attach. If the arterial blood supply is poor, the leech may detach prematurely and attempt to wander to another site, this usually implies that the initial diagnosis of venous congestion was wrong. The patient's dressing should be fabricated to allow the leech to attach only to the congested part. Leeches




Fig. 11.14 Silicone temporary vascular stent is used in major limb replantation prior to bone fixation if ischemia time is prolonged.





Fig. 11.15 (A) A 39-year-old farmer with corn harvester injury to his left hand. All fingers were avascular. The dorsal skin bridge was severely crushed with no veins identifiable. The avulsed thumb was unable to be located. (B) Segmental bone loss was present over the metacarpals and proximal phalanges. Because of the extensive damage with no viable skin bridge the distal part was separated and cooled in an ice bath. (C) The ring finger was replanted ectopically to replace the missing thumb. The long finger was ectopically replanted to the ring finger to preserve metacarpophalangeal joint motion. The small finger was replanted. (D) The small-finger replantation failed despite multiple take-back attempts. The first webspace was recreated and a lateral arm free flap was used for soft-tissue coverage. (E) A tissue expander was used to remove the adherent dorsal skin graft. (F) Postoperative extension and (G) flexion demonstrate adequate function for opposition. The patient resumed his preinjury occupation.



Fig. 11.16 (A) Single-digit amputation of the index finger at the level of the distal interphalangeal joint. The patient desired replantation. The surgery was performed as an outpatient, with the patient discharged home on oral aspirin. (B) Postoperative view of the hand. (C) Volar view of replanted finger.

feed usually for 10–40 minutes, after which they detach or should be removed. Absorbent dressing is utilized to avoid further constriction from the continued oozing, which may last for up to 6 hours. A new leech is applied if the finger appears congested again, usually no sooner than 4 hours.

Leech therapy is slowly weaned at approximately 5 days. At this point venous circulation should be re-established. *Aeromonas* species bacteria in the leech gut are essential for digestion of blood.³⁴ *Aeromonas hydrophila* is not normally a pathogen, but precautions should be utilized. Prophylactic antibiotics to cover *Aeromonas* should be considered. These are mainly third-generation cephalosporins or aminoglycosides. Leeches may not always be available and other methods of venous outflow can be utilized. Removing the distal nail plate and mechanical rubbing of the sterile matrix followed by application of a dressing with a 1000 unit/mL heparin solution may achieve active oozing in the congested finger. This technique is repeated hourly until congestion is improved.^{35,59} Another option is the injection of heparin subcutaneously. In this technique, a fish mouth incision is made in the distal digit

to allow venous outflow. A solution of 1000 units of heparin in 0.1 mL saline is injected subcutaneously into the tip of the congested replanted finger. Heparin subcutaneous injections are reported to be more cost-effective than medical leeches and simpler to administer, and heparin action can last for over 6 hours.³⁶

Another technique which should be considered is subcutaneously pocketing of the distal replantation. This technique was initially described using a subdermal pocket on the chest wall³⁶ to prevent the awkward immobilization of a chest flap; the subdermal pocket has been described on the palm.⁶⁰ An arterial repair is performed if possible. If there are no veins to repair or the finger appears congested, the pulp of the amputated finger is de-epithelialized and a subdermal pocket is made in the palm or thenar crease. The finger is secured in a flexed position attached to the palm for 7 days. After 7 days the patient is brought to the operating room and the finger is detached. Retrospective reviews have found this method to be reliably successful in saving the nailbed, and preserving length even in adult patients without an artery or vein repair.^{61,62} With distal phalanx amputation, replantation can achieve a success rate of over 90% when venous anastomosis is performed. Even without venous anastomosis, success rates over 75% can be achieved.^{38,41,43,44} Given these success rates, distal fingertip replantation is justifiable and these fingers should be aggressively treated.⁶³ The aesthetic and psychological benefit of distal fingertip replantation should not be ignored.

Ring avulsion injuries

Ring avulsions are some of the most difficult injuries to treat. The classification scheme popularized by Urbaniak *et al.*⁶⁴ and modified by Kay *et al.*⁶⁵ is commonly used (Table 11.4). Injuries of class 2 and above require microvascular repair; class 3 ring avulsions are the most challenging, due to their degloving, avulsion, and amputation (Fig. 11.18). Under the operating microscope a midlateral incision is made on the ulnar aspect of the amputated digit. Nonviable tissue should be debrided. Damaged arteries should be bypassed. Inadequate debridement leads to poor outcome. Vein grafts are almost universally required due to the significant extent of the vascular damage. Because of difficulty in arterial size matching, a second step-down vein graft can be harvested; alternatively, an arterial pedicle from the adjacent digit may be used.⁶⁶

A minimum of two veins should be repaired. Vein grafts should be utilized if needed. If the amputation occurs at the DIP joint, primary arthrodesis of the joint should be




Fig. 11.17 Ishikawa and Tamai classification for distal replantation.

Table 11.4 Ring avulsion injuries classification

I	Circulation adequate
II	Circulation inadequate, no skeletal injury
a	Arterial circulation inadequate only
v	Venous circulation inadequate only
av	Arterial and venous circulation inadequate
III	Circulation inadequate, skeletal injury
a	Arterial circulation inadequate only
v	Venous circulation inadequate only
av	Arterial and venous circulation inadequate
IV	Complete amputation

considered. Following replantation at this level, motion at the DIP joint is poor and fusion may permit bony shortening, which may aid in nerve repair and skin closure. The skin should not be pulled taut in order to close the skin defect or to attempt to get a primary skin closure. Skin grafts should be utilized to avoid a tight closure. A venous flap should be considered for coverage of the skin defect. A retrospective review of venous flaps used for ring avulsion injuries showed 100% survival of all flaps and fingers. The venous flaps produced a supple skin envelope and made subsequent surgeries such as tenolysis or capsulotomy easier to perform. Venous flaps should be vascularized only by the arterial inflow, as




Fig. 11.18 (A) Child with a type IV ring avulsion injury. (B) Immediately postoperative after replantation. (C) Crossed K-wire fixation. (D) Fourteen months after injury, extension of finger. (E) Flexion of fingers. (F) Radiographs demonstrate bone union but premature closure of growth plate. (Courtesy of James R. Sanger, MD.)




Fig. 11.19 (A) Venous flap designed on the volar forearm. (B) Harvested flap *in situ* with venous network diagram. (C) Vein matches size of digital vessels.

flaps vascularized with venous outflow have had poor survival rates.⁴⁷ (Fig. 11.19).

Survival rates for ring avulsion injuries requiring revascularization range from 60% to 81%. Adani *et al.* achieved an 88% success rate in 33 patients, with an average total arc of motion (TAM) of 185°. They concluded the most important factor for success was resection of the avulsed digital artery and vein.⁶⁷ The factor most significantly associated with revascularization failure is repair of fewer than two veins. Cigarette smoking and level of bone injury have not been found to affect survival. The most commonly occurring complications are flexion contracture, cold intolerance, and malunion. A majority of patients can expect two-point discrimination greater than 8 mm. In patients with ring avulsion injuries, finger reconstruction generally gives a better result than amputation, although in patients with ring avulsion amputation proximal to the insertion of the flexor superficialis tendon, amputation or ray amputation should be considered, since these patients are likely to have poor hand function.⁶⁸ Sears and Chung performed a systematic review of avulsion injuries and found the results are much better than historically cited and challenged the practice of performing amputations for these injuries.⁶⁹

Clinical tips

In type III and IV ring avulsion injuries, fusion of the distal interphalangeal (DIP) joint can allow easier bony fixation and sufficient shortening to allow primary approximation of the dorsal veins, skin, and nerves. Range of motion of the DIP joint is generally poor even after attempts to preserve the joint.

Ectopic transplantation secondary at replantation

Godina *et al.* performed the first ectopic replantation in 1983 when they transferred an amputated hand to the axilla after a contaminated multilevel farm injury.⁷⁰ Sixty-five days later the hand was successfully replanted to the forearm. This technique has subsequently been utilized for a variety of amputated parts, including fingers, thumbs, ears, penises, and scalps.^{71–74} The recipient sites best used are the thoracodorsal, the deep inferior epigastric, the superficial inferior epigastric, the radial and the dorsalis pedal vessels. These vascular pedicles are familiar to most microsurgeons. The choice of recipient vessel for ectopic replant depends on the




Fig. 11.20 (A) Avulsion injury of the radial aspect of the forearm and wrist. (B) Thumb ectopically transplanted to the wrist via the radial artery. (C) Thumb replantation after staged reconstruction with second toe second metatarsophalangeal joint and dorsalis pedis free flap. (D) Opposition of the thumb and toe transfer. (Courtesy of N. John Yousif, MD.)

length of the expected pedicle as well as donor site morbidity (Fig. 11.20). Adequate surgical debridement is essential prior to replantation of the digit. Often a staged local or free flap is needed for soft-tissue coverage prior to second-stage transplantation. The ectopic site must be outside the zone of injury.

Complications were significant in all series of ectopic replantations.⁷² These occurred mostly after the second stage of transplantation. Nazerani and Motamedi⁷⁴ reported a series of 24 staged distal finger ectopic replantations, initially transplanting the digit to the ipsilateral groin, anastomosing an artery and a vein. After 8–12 weeks, the finger was transferred to the hand as a pedicle groin flap. A success rate of 75% was achieved by this method with few complications. This technique may be of clinical use in thumb amputation where there is need for flap coverage along with salvage of bony length and the cosmetic appearance of the thumb.

Pediatric replantation

In children, less stringent criteria for replantation and revascularization are generally employed. Replantation should be considered for all amputated parts, including amputations of the lower extremity. Success rate in replantation is lower in children than in adults, but this may be due to the fact that surgeons are more aggressive in salvaging and attempting to replant parts in children. Disparities have been found to exist in the management of children with amputations in the US. Whites and children with private health insurance are more likely to receive replantation than Blacks, Hispanics and children without insurance.⁷⁵ Clean guillotine amputations generally have the greatest success; however, crush and avulsion injuries from bicycle and mechanical sports equipment with spokes or chains are the most common form of injury in

children. The operative procedure in children is similar to that in adults, and the sequence of the procedure is identical. Surgery may be more challenging because of the size of the vessels and a greater tendency for spasm in the pediatric age group.⁵⁷ Replantation of multiple digits should begin with the thumb, then with the most ulnar amputated digits. An opposable thumb and two ulnar digits provide essential power grip. In finger replantation, K-wire fixation is preferred over plate fixation to avoid growth disturbances.⁷⁶ The replanted part can be expected to grow to 90% compared to normal unless there is significant damage directly to the growth plate.⁷⁷

Recovery of nerve and muscle function is generally better in pediatric patients. After a mutilating hand injury, children tend to rebound more quickly from both functional and psychological aspects. Parents add a level of complexity to the care of the child, often because of guilt issues. Family psychological counseling may be beneficial. A long-term follow-up of 14 children with digital replantation shows an 88% success rate. Satisfactory sensory recovery was obtained in all fingers. The growth rate of the digit was 86% compared to the contralateral, non-injured extremity. Twelve of the 14 cases were judged to have excellent results.⁷⁸

Postoperative care

Anticoagulation

Pharmacological management of replantation and revascularization remains a controversial topic. Platelet aggregation is the most prevalent underlying cause of arterial thrombosis. Venous thrombosis is generally caused by fibrin clotting. The

risk of thrombosis is highest in the first two postoperative days, with 80% of thromboses being seen in this time period. Various schemes of pharmacological management have been utilized. No consensus exists on the use of anticoagulation therapy after microsurgery. The most commonly utilized agents are heparin, low-molecular-weight dextran, and aspirin, but little evidence is available on the efficacy of any of these regimens. A survey of microsurgeons showed that 90% used anticoagulation in free flap and microvascular surgery.⁷⁹

Heparin has been used for over 50 years. Heparin binds to antithrombin III, enhancing its antiprotease activity. Various factors, including thrombin and factor Xa, are rendered inactive.⁸⁰ Heparin also has a vasodilatory effect. Heparin can be administered systemically by intravenous methods, by subcutaneous injection, or by direct irrigation. When given intravenously or subcutaneously, heparin needs to be monitored by measuring activated partial thromboplastin time levels. Side-effects of heparin include hematoma formation and heparin-induced thrombocytopenia. Low-molecular-weight heparin (LMWH) is a derivative of standard unfractionated heparin with the same activity against factor X but weaker antithrombotic factor II activity. LMWH is as effective as heparin in its antithrombogenic effects but has fewer adverse reactions. The advantage of LMWH is that there is no need for monitoring and it can be used on an outpatient basis. Chen *et al.* examined topical effects of LMWH compared to unfractionated heparin in a crush injury model and found the thrombosis rates were significantly reduced with both treatments.⁸¹ A Cochrane review of LMWH found no difference in microvascular success rate compared to unfractionated heparin but few postoperative bleeds and hypocoagulability.⁸² Dextran 40 is a group of polysaccharides synthesized by *Leuconostoc mesenteroides* streptococcus. The exact mechanism by which Dextran 40 works is unclear. The antithrombotic effect of dextran is thought to be due to binding to erythrocytes, platelets, and the vascular endothelium. It is mostly thought to interfere with the formation of fibrin clot and to prevent the aggregation of red thrombi. This effect is thought to be significantly greater than any effect on platelets. Dextran has a low risk of postoperative bleeding and hematoma formation. It has some rare, but serious, consequences, including that of pulmonary edema due to fluid overload.⁸³

The use of Dextran 40 has been shown to be beneficial in animal studies. There has been no trial to date that demonstrates any significant beneficial effect in humans with the use of dextran. There is no generally accepted regimen for the administration of dextran. Jallali in his review on the use of dextran advocates initiation of Dextran 40 at a rate of 0.4 cc/kg per hour for 2 days, then reducing the rate to 0.2 cc/kg per hour on day 3 and 4, and weaning on day 5.⁸³ Ridha *et al.*⁸⁴ surveyed the practice of 161 microsurgeons and found 45% routinely used dextran postoperatively with 17% combining it with aspirin or heparin. Forty percent of surgeons using dextran used it for less than 72 hours; 52% used it for 5 days. Eight percent used it for greater than 5 days. There was no difference of survival in the patients who used dextran versus those who did not use dextran. A single institutional study from Memorial Sloan Kettering compiled data from 505 free flap surgeries. One group treated by surgeons who routinely used only aspirin was compared to a group treated by a

surgeon who routinely used low-molecular-weight dextran. There was no significant difference between the two groups in regard to microvascular thrombosis, flap loss, hematoma, or bleeding.⁸⁵ Disa *et al.*⁸⁶ prospectively analyzed 100 consecutive patients undergoing microvascular free flap surgery. All patients were randomized into one of three anticoagulation groups, which included low-molecular-weight dextran (20 cc/h for 48 hours), low-molecular-weight dextran (20 cc/h for 120 hours), or aspirin (325 mg for 120 hours). There were no total flap losses, three flaps were re-explored, and systemic complications were greatest at 51% in patients with 120 hours of dextran, 29% in patients who had 48 hours of dextran, and only 7% in patients receiving aspirin. Based on this prospective study, the surgeons at this institution eliminated the use of dextran for microvascular surgery at their institution.⁸⁶

Aspirin (acetylsalicylic acid) inhibits platelet enzyme cyclooxygenase and impedes arachidonic acid breakdown through thromboxane and prostacyclin. Preoperative aspirin has been shown to decrease microvascular thrombosis formation; however, the administration is very time-dependent. Rat studies suggest aspirin needs to be given 10 hours before surgery.⁸⁰

Many animal studies have suggested that anticoagulation may be useful, especially in the crush or avascular injury, yet prospective studies in humans are limited. Khouri and the International Microvascular Research Group prospectively studied the use of anticoagulation in microvascular surgery. This was a 6-month study of 23 free flap surgeons analyzing data for 493 free flaps. While the study was prospective in nature, it was not randomized, and all of the surgeons performed their standard anticoagulation therapy, including the use of heparin, aspirin, and Dextran 40. This study was on elective free flap surgeries and not replantation. They found the overall rate of thrombosis was 9.9% with a 60% salvage rate after re-exploration of thrombosed vessels. There was no increased risk of thrombosis in young or old patients, smokers, or diabetics. The use of intraoperative anticoagulation therapy did not reduce the risk of thrombosis. They concluded that only subcutaneous heparin given postoperatively may have decreased the rate for thrombosis, but the use of heparin irrigation intraluminally had no beneficial effect on preventing thrombosis.⁸⁷

Conrad and Adams reviewed the use of anticoagulation in microsurgery. They conceded that most of the better studies have been performed in animals and very few studies with a high level of evidence have been performed in humans. Irrespective of these limitations, they recommended in replantation surgery using a loading dose of aspirin, 1.4 mg/kg (100 mg aspirin in a 70-kg adult) followed by aspirin 1.4 mg/kg/day for 2 days. They advocate the use of heparin irrigation at a dilution of 100 units/mL during surgery and a heparin bolus of 50–100 units/kg before release of a microvascular clamp.⁸⁸

Continuous brachial plexus blockade may be beneficial in preventing microvascular thrombosis and for early continuous pain relief. Sixteen patients were evaluated after replantation or revascularization surgery. One group received continuous brachial plexus blockade; the second received conventional management. The group undergoing conventional treatment had two microvascular thromboses, which were explored and salvaged. Pain control was adequate in both groups, although

Table 11.5 Circulation

	Normal circulation	Venous occlusion	Arterial occlusion
Color	Pink	Blue/purple hue, cyanotic	Pale, mottled
Capillary refill time	1–2 seconds	Increased, <1 second	Decreased, >2 seconds
Temperature	Warm	Warm–cool	Cold
Turgor	Full	Distended, swollen	Hollow
Dermal bleeding	Bright red blood	Dark red or bluish Bleeds briskly	Minimal bleeding only serum

those in the conventional anesthesia group required more intravenous pain medication.⁸⁹

For revascularizations and sharp guillotine-type injuries, the author uses heparin irrigation intraoperatively (100 units/mL) and aspirin. Aspirin 325 mg is given in the recovery room and daily for 1 month. In patients with crush or avulsion injuries, LMWH at a deep-vein thrombosis prophylaxis dose is utilized. The first dose is given in the operating room, and it is continued for 2 weeks postoperatively. The patient and family are instructed on home injection prior to discharge. The LMWH regimen is based on animal studies on the efficacy of heparins in crush injuries.⁹⁰ The advantage of the LMWH regime is that patients can be discharged home while still on therapy.

Postoperative monitoring

Careful postoperative monitoring is essential in replantation surgery. Eighty percent of vascular occlusions occur within the first 48 hours after surgery. The salvage rate in a failing replantation explored early ranges from 66% to 80%.⁹¹ A dedicated replantation team is essential for monitoring the patient. The best monitor is a conscientious nursing staff. When the patient arrives on the floor, the physician should examine the replant with the nurse, judging its color, capillary refill, and turgor. The finger is examined every hour by the nursing staff. If there is any change from the baseline level, the physician should be notified (Table 11.5). Proper handoff between nursing shifts is essential: at the bedside the clinical parameters are assessed with both nursing teams at each shift change. Venous occlusion is more insidious and harder to assess than acute arterial thrombosis. Venous occlusion will eventually lead to arterial thrombosis. If there is any doubt regarding the clinical assessment of the digit, the pulp of the finger can be pricked with a 25-gauge needle. If the blood is blue, has brisk bleeding, delayed bleeding or serous fluid exudate; exploration of the digit should be performed.

Technology cannot replace a dedicated, experienced nurse, but can aid in the postoperative assessment of viability. The most commonly used devices are pulse oximetry, ultrasonic Doppler, digital thermometry, and the laser Doppler.⁹¹ Each of these devices can help identify an early vascular occlusion, but each has its shortcomings. While temperature measurements are inexpensive, variations such as room temperature can affect the accuracy. Laser Dopplers have a high sensitivity and specificity. When compared to thermometry, the sensitivity of the Doppler is 93% while that of thermometry is 84%. Specificity is 94% with the laser Doppler and 86% with thermometry.⁹²

Clinical tips

The best monitor of the replanted digit is a well-trained nursing staff. The surgeon should examine the replantation with the nursing staff and ask to be called at any change in appearance. Shift change handoffs should be made at the bedside, so that all care members know the physical appearance of the replantation.

Postoperative therapy

Therapy is essential to regaining function. During the first few days after surgery the therapist fabricates splints, and initiates gentle range of motion to the non-affected joints. At postoperative days 5–7, a formal therapy program is initiated; this includes dressing changes, passive splinting, and instruction regarding activities of daily living. Blood vessel and nerve repairs are protected for 3–4 weeks. Tendon therapy initially involves immobilization to prevent injury, but early active and passive mobilization can be initiated if there is rigid bone fixation and a solid multistrand tendon repair. After 6–8 weeks, the therapy program is increased to include strengthening and full range-of-motion programs. Sensory re-education is initiated after any nerve injuries. Desensitization programs start using fabric textures and progress to vibratory sensory re-education.⁹³ Patients who started therapy before day 14 postoperatively have better recovery of motion than those who start therapy later.²⁴

Psychosocial aspects of replantation

The surgeon treating a patient with an amputation must not only treat the amputation, but the whole patient, and the family. The psychological implications of amputation and replantation must not be overlooked when caring for these patients. The hand has a significant role in a patient's identity and psyche. The hands are an individual's second most visually prominent structure, second only to the face. Most individuals view their hands far more than they view their own faces. The hands are not only a source of contact with the world, but a means of communication and an instrument of sexuality. Injury or disfigurement to the hands can be a source of tremendous psychological difficulty. The psychological consequences of amputation may not correlate with the degree of injury.⁹⁴ The consequences of a distal single-digit injury in one patient may be more severe than that of a major limb amputation in another individual. Despite

common misconceptions, the presence or absence of worker's compensation or litigation does not seem to correlate with the patient's psychological reaction after injury.⁹⁵

The psychological response to amputation may take various forms, including anxiety, depression, anger, guilt, fear, frustration, and sadness. All of these emotions are normal after an injury, but their prolonged manifestation may be pathological and lead to full acute stress disorder and post-traumatic stress disorder (PTSD). PTSD symptoms may include flashbacks, nightmares, sleep disturbances, avoidance, and detachment.

The physician should convey hope but also give the patient realistic expectations prior to surgery. Patients need to be reassured that everything possible will be done to make them whole again.

Nightmares and flashbacks are commonly seen after traumatic injuries. Flashbacks are an almost universal component of the traumatic hand injury. These can be "replay flashbacks" where an individual replays the entire traumatic event, or an "appraisal flashback" where the patient sees a snapshot of the injured hand. Patients may also have "projection flashbacks" where the injury is seen as more severe than it actually is. The type and persistence of flashbacks are strong prognostic factors in predicting PTSD and the eventual return to work and function. Psychological care of the patient with a traumatic hand amputation begins immediately in the emergency room. The patient is asked two questions: how did this accident occur, and what do you perceive was responsible for the injury? Whether patients take responsibility for the injury or attribute it to something out of their control is an important prognostic sign. Patients who see the accident as under their control, e.g., I knew I should not have removed the blade guard, do significantly better than those who believe they lack control, e.g., the machine intermittently malfunctions.

Patients are also asked how the injury appears to them and their emotional reaction. Finally they are asked about flashbacks. After discharge from the hospital, patients should be followed up with psychological treatment. Patients who are experiencing signs of PTSD are begun on a course of desensitization and systematic exposure training. Grunert *et al.*⁹⁵ were able to achieve over 90% return to work with a graded return-to-work exposure program in patients with PTSD.

Children with traumatic injuries are a special challenge to the surgeon. Rusch *et al.* found that 98% of children with traumatic injuries had symptoms of PTSD, depression, or anxiety 1 month after injury. Twelve months after injury, 21% still met the criteria for PTSD.⁹⁶

Outcome, prognosis, and complications

Outcome after replantation and revascularization surgery can be measured in many ways. The simplest of these is survival of the replanted part. Overall survival can be expected in over 90% of digits. The largest single-institution study found a success rate of 92.9%.²⁵ Several factors are associated with worse prognosis. The most significant of these is mechanism of injury. Crush and avulsion injuries have a poorer anastomotic success rate than clean amputations. The anastomotic success after a clean amputation approaches 100%.^{25,97}

Other factors associated with poorer success rates include the total number of anastomosed vessels. The more vessels anastomosed (whether arteries or veins) improved survival. Even in very distal replantation where anastomosis of a vein is not possible, a high success rate of over 60% can still be obtained.²⁸ A positive correlation exists between the number of vessels anastomosed and the mechanism of injury; crush injuries generally reduce the number of anastomosed vessels and veins.³³ The use of vein grafts is not associated with a poorer outcome. Cigarette smoking leads to a poorer outcome, but alcohol consumption does not affect survival.

A better indicator of outcome is objective measurement of hand function. Standard measurements include range of motion, grip strength, and sensation. These measurements can be compared to non-injured hands or to hands with amputations. Long-term follow-up of 59 successfully replanted digits showed that average active range of motion was 44–56% of the normal contralateral hand. Grip strength was 67% of the contralateral hand. Only three digits had normal two-point discrimination. Over one-half achieve 10 mm or less two-point discrimination.⁹⁸

The best measurement of outcome is the use and function of the hand. A variety of tests are available to judge outcome, including the short-form 36 (SF36), upper extremity functional test (UEFT), and the Disability of the Arm, Shoulders and Hand (DASH). Outcome assessment after major upper extremity replantation is difficult.^{99,100} Outcome of replantation can be compared to amputation, the normal hand, or other surgical reconstructions.⁵⁸ Various scales have been devised to try to assess and predict functional recovery after mutilating hand injuries and replantations; these include the Tamai scale, the Chen scale (Table 11.6), and the Campbell hand injury severity scale (HISS).^{56,101–103} The HISS performed at the time of injury can be predictive in assessing return to work and functional recovery of the patient. The more proximal level of injury and the more injured fingers predicted poorer functional outcome.¹⁰⁴ A comparison of four commonly

Table 11.6 Chen classification of functional results after replantation/revascularization

Grade	Return to work	AROM (%)	Sensation	Cold intolerance	Grip strength (five-grade scale)
I	Same profession	>60	Normal	–	4–5
II	Other profession	40–60	Satisfactory	–	3–4
III	Not returned to work	30–40	Protective	Yes	Slight
IV	The limb survived, but is functionally severely disabled				

AROM, Active range of motion.

used scales, the Tamai, Ipsen, Chen, and DASH, found a high correlation between the Ipsen, Tamai and DASH. The Chen had a moderate correlation with the others.¹⁰⁵ Despite results of functional outcome, patient satisfaction after replantation is high; long-term follow-up in successfully replanted digits shows good satisfaction by a majority of the patients.

Replantation distal to the FDS insertion offers excellent functional results. Hattori *et al.* compared the functional results of single fingertip amputations versus replantation in regard to symptoms of pain, paresthesias, cold intolerance, and DASH scores. Grip strength did not differ between the amputation group and the replantation group. Range of motion of the proximal interphalangeal joint was better in the replantation group. Replantation patients had significantly improved DASH scores. Ninety-six percent of patients obtained protective sensation. Less than 10% of replantation patients complained of pain, 60% of patients with amputation complained of pain, half of these patients rarely or never use their affected fingers for activities of daily living. All patients with successful replantations were highly or very satisfied. Only 60% of patients in the amputation group were highly or very satisfied.⁹⁷ Patients with primary amputation revisions have a higher incidence of painful and uncomfortable sensation in their amputation stumps. Patients with replanted index and middle fingers have improved use and function of these fingers compared with patients with amputation revision. When cost was compared, a successful replantation cost 20% more than unsuccessful replantation and 300 times more than primary amputation revision.¹⁰⁶ The level of injury had a significant influence on the final function, with the worse function in amputations in flexor tendon zone II. In this area, repairing the profundus stump to the superficialis had improved outcome.²⁵

The surgical success rate for major limb replantation ranges from 36% to 100% depending on the level of amputation, etiology of amputation, and age of the patient.⁹⁸ Using the Carroll Quantitative Test of Upper Extremity Function, the Louisville group compared the outcomes of replantation to prosthesis in adults with amputations proximal to the wrist. In injuries between the wrist and elbow, good to excellent outcomes were achieved in 50% of replantation patients. No patients in the prosthetic group had good or excellent function.¹⁰⁶ Better outcomes were seen in younger patients and those with more distal injuries. Outcomes for injuries proximal to the elbow were significantly worse in both groups.

Replantation, even after significant mangling injuries, is still worthwhile. Avulsion amputations in the forearm were evaluated based on the patient's overall satisfaction, recovery of motion, and ability to perform daily activities: 100% success rate of replantation was achieved. Postoperative function was rated as excellent to good in 40%, but poor in 30% of patients.¹⁰⁷

Amputation at the transmetacarpal level is an intermediary between the digital amputation and major limb replantation. A review of 10 patients with transmetacarpal-level replantations showed 90% salvage of the replanted hands. Intrinsic muscle function was weak or absent in all patients. Only one patient was able to resume his prior occupation. Despite this fact, all patients were satisfied with their replantation.¹⁰⁸

Complications

The most devastating complication after replantation and revascularization is anastomotic failure. Re-exploration to

correct arterial insufficiency can be successful in over 50% of patients with a failing replantation.^{103,109} Close observation of the patient postoperatively for signs of thrombosis and urgent re-exploration of the vessel is the essential first step in successful re-exploration. In the patient's room, the dressing should be removed and if skin sutures appear to be constricting venous outflow, they should also be removed. The patient is given a bolus of intravenous heparin and the operating room is readied. The anastomosis is opened and clots are atraumatically evacuated. The use of a Fogarty catheter may be considered; however, a catheter can cause significant intimal damage. If white thrombus or intimal injury is present, a vein graft should be utilized. Intravascular tissue plasminogen activator is considered; however, there is very limited clinical data and outcome of its effectiveness. After establishing flow, prophylactic therapy with aspirin or heparin should be strongly considered.^{85,110}

Cold intolerance is common in varying degrees in almost all replanted digits; it usually resolve in 1–2 years but may be permanent.⁹⁸ Eighty-one adults from Norway were evaluated for cold sensitivity after successful replantation or revascularization. Twenty percent were severely or extremely cold-hypersensitive. Cold-hypersensitivity is significantly higher in replantations as compared to revascularizations.¹¹¹ Only 40% of children with replanted digits reported cold intolerance.⁵⁰

Secondary procedures

The incidence of secondary procedures after digital replantation ranges from 15% to 80%.^{108,109} Most series report an approximate 50% rate of reoperative surgery. Procedures include those performed immediately, mostly related to vascular anastomosis and skin closure, and late secondary procedures relating mainly to bony nonunion, or tendon adhesions.¹¹² Yu *et al.* reviewed a series of 102 secondary procedures in 55 patients with injuries in 79 digits. Ninety-two percent of the early procedures were for soft-tissue coverage and 67% of later procedures were for tendon function. Significant factors related to the need for secondary surgeries are avulsion or degloving injuries, and proximal replantations in zones 3–5.¹¹³ In digital replantations proximal to the superficialis insertion, a high rate of secondary procedures can be expected. Many of these secondary surgeries have a poor outcome.¹¹⁴ Tenolysis after finger replantation and revascularization is technically demanding, but the results can be rewarding (Fig. 11.21). Tenolysis in these digits may produce a modest total improvement in motion, but this functional improvement can be substantial. The risk of tendon rupture in these patients is significant.¹¹⁵

Revascularization and replantation remains one of the most challenging procedures in hand surgery. The surgeon must have a meticulous plan and exacting surgical technique. The postoperative management may be as complicated as the surgical procedure itself. Yet the rewards of a successful replantation for the patient and the surgeon are immeasurable.

Future directions

Replantation remains one of the most challenging surgeries performed. Microsurgery and “supermicrosurgery” is




Fig. 11.21 (A,B) A 24-year-old status post five-finger amputation and replantation with stiff fingers. **(C)** Exploration at time of tenolysis shows severe scarring and attenuation of the digital pulleys. **(D)** Hunter rod inserted, and A2 and A4 pulley reconstruction.

allowing reattachment of more distal amputations. Newer procedures such as palmar pocketing allow successful reattachment of very distal amputations even without a venous anastomosis. Outcomes analyses generally show good to excellent satisfaction with replantation and revascularization surgery, yet there are few studies which compare functional

and psychological results of replantation with that of amputation revision.¹¹⁶ In this changing healthcare environment, economic and cost effectiveness studies of replantation are still lacking and are needed to establish the benefit of these procedures.¹¹⁷



Access the complete reference list online at <http://www.expertconsult.com>

3. Buncke HJ Jr. Microvascular hand surgery transplants and replants over the past 25 years. *J Hand Surg Am.* 2000;25:415–428. The pioneer of US microsurgery discusses the history of microsurgery and replantation. Tips and techniques from a lifetime of experience are included.
11. Chung KC, Kowalski CP, Walters MR. Finger replantation in the United States: rates and resource use from the 1996 Healthcare Cost and Utilization Project. *J Hand Surg Am.* 2000;25A:1038–1042. The database from the Agency for Healthcare Policy and Research was reviewed to obtain data on the frequency and cost of digital replantation. Only 60% of the 906 hospitals performed any replantation. Only 2% of hospitals performed 10 or more cases of replantation.
25. Waikakul S, Sakkarnkosol S, Vanadurongwan V, et al. Results of 1018 digital replantations in 552 patients. *Injury.* 2000;31:33–40. The largest series of digital replantation published from Bangkok, Thailand with at least 2-year follow-up. A 92.9% success rate in digits. Risk factors and outcome are discussed.
33. Chaivanichsiri P, Rattanasrithong P. Type of injury and number of anastomosed vessels: impact on digital replantation. *Microsurgery.* 2006;26:151–154. A retrospective review of 130 digital replantations was performed. The type of injury and the number of vessel anastomoses were the most significant predictors of successful outcome. Crush injuries had significantly worse outcome than sharp injuries. In distal replantations, an arterial repair even without repair of a vein can achieve a high success rate.
37. Zhang X, Wen S, Wang B, et al. Reconstruction of circulation in the fingertip without vein repair in zone 1 replantation. *J Hand Surg Am.* 2008;33A:1597–1601.
49. Rosson GD, Buncke GM, Buncke HJ. Great toe transplant versus thumb replant for isolated thumb amputation: critical analysis of functional outcome. *Microsurgery.* 2008;598–600.
59. Li J, Guo Z, Zhu Q, et al. Finger replantation: determinants of survival. *Plast Reconstr Surg.* 2008;122:833–839. A retrospective review of 211 finger amputations was performed over a 16-year period. An 81.5%

- success rate was achieved. Injury mechanism, platelet count, smoking, and the use of vein grafting were found to be the main predictors for the survival of the replanted fingertip.
68. Sanmartin M, Fernandes F, Lajoie AS, et al. Analysis of prognostic factors in ring avulsion injuries. *J Hand Surg Am.* 2004;29a:1028–1037.
76. Buncke GM, Buntic RF, Romeo O. Pediatric mutilating hand injuries. In: Dellapena D, ed. *Hand Clinics*. Philadelphia: WB Saunders; 2003:121–131.
91. Bakri K, Moran SL. Monitoring for upper extremity free flaps and replantations. *J Hand Surg Am.* 2008;33A:1905–1908.

References

- Malt RA, McKhann C. Replantation of several arms. *JAMA*. 1964;189:716–722.
- Tamai S. History of microsurgery. *Plast Reconstr Surg*. 2009;124:e282–e294.
- Buncke HJ Jr. Microvascular hand surgery transplants and replants over the past 25 years. *J Hand Surg Am*. 2000;25:415–428. *The pioneer of US microsurgery discusses the history of microsurgery and replantation. Tips and techniques from a lifetime of experience are included.*
- Khalil AA, Aziz FA, Hall JC. Reperfusion injury. *Plast Reconstr Surg*. 2006;117:1024–1033.
- Wang WZ. Investigation of reperfusion injury and ischemic preconditioning in microsurgery. *Microsurgery*. 2009;29:72–79.
- al-Qattan MM. Ischaemia-reperfusion injury. Implications for the hand surgeon. *J Hand Surg [Br]*. 1998;23:570–573.
- Beyersdorf F, Schlensak C. Controlled reperfusion after acute and persistent limb ischemia. *Semin Vasc Surg*. 2009;22:52–57.
- VanderWilde RS, Wood MB, Zu ZG. Hand replantation after 54 hours of cold ischemia: a case report. *J Hand Surg Am*. 1992;17:217–220.
- Wei FC, Chang YL, Chen HC, et al. Three successful digital replantations in a patient after 84, 86, and 94 hours of cold ischemia time. *Plast Reconstr Surg*. 1988;82:346–350.
- Lin CH, Aydyn N, Lin YT, et al. Hand and finger replantation after protracted ischemia (more than 24 hours). *Ann Plast Surg*. 2010;64:286–290.
- Chung KC, Kowalski CP, Walters MR. Finger replantation in the United States: rates and resource use from the 1996 Healthcare Cost and Utilization Project. *J Hand Surg Am*. 2000;25A:1038–1042. *The database from the Agency for Healthcare Policy and Research was reviewed to obtain data on the frequency and cost of digital replantation. Only 60% of the 906 hospitals performed any replantation. Only 2% of hospitals performed 10 or more cases of replantation.*
- Chen MW, Narayan D. Economics of upper extremity replantation: national and local trends. *Plast Reconstr Surg*. 2009;136:2003–2011.
- Payatakes AH, Zagoreos NP, Fredorick GG. Current practice of microsurgery by members of the American Society for Surgery of the Hand. *J Hand Surg Am*. 2007;32A:541–547.
- Morrison WA, McCombe D. Digital replantation. In: Dellapena D, ed. *Hand Clinics*. Vol. 23. Philadelphia: WB Saunders; 2007:1–12.
- White WL. Why I hate the index finger. *Orthop Rev*. 1980;6:23.
- Wilhelmi BJ, Lee WPA, Pagensteert GI, et al. Replantation in the mutilated hand. In: Dellapena D, ed. *Hand Clinics*. Vol. 19. Philadelphia: WB Saunders; 2003:89–120.
- Chang J. Twelve simple maneuvers to optimize digital replantation and revascularization. *Tech Hand Up Extrem Surg*. 2004;8:161–166.
- Okada T, Ishikura N, Tsukada S. Digital replantation in the aged patient. *J Reconstr Microsurg*. 1988;5:351–357.
- Freeland AE, Lineaweaver WC, Lindley SG. Fracture fixation in the mutilated hand. In: Dellapena D, ed. *Hand Clinics*. Vol. 19. Philadelphia: WB Saunders; 2003:51–61.
- Green RA, Zins JE. The “Knot Twist”: a new method of securing wire loops – An assessment of mechanical properties. *Plast Reconstr Surg*. 1988;81:956–958.
- Vanik RK, Weber RC, Matloub HS, et al. The comparative strengths of internal fixation techniques. *J Hand Surg Am*. 1982;9:216–221.
- Al-Qattan MM. Metacarpal shaft fractures of the fingers: treatment with interosseous loop wire fixation and immediate postoperative finger mobilization in a wrist splint. *J Hand Surg [Br]*. 2006;31:377–382.
- Peiji W, Qirong D, Jianzhong Q, et al. Intramedullary fixation in digital replantation using bioabsorbable poly-DL-lactic acid rods. *J Hand Surg Am*. 2012;37:2547–2552.
- Ross DC, Manktelow RT, Wells MT. Boyd Tendon function after replantation: prognostic factors and strategies to enhance total active motion. *Ann Plast Surg*. 2003;51:141–146.
- Waikakul S, Sakkarnkosol S, Vanadurongwan V, et al. Results of 1018 digital replantations in 552 patients. *Injury*. 2000;31:33–40. *The largest series of digital replantation published from Bangkok, Thailand with at least 2-year follow-up. A 92.9% success rate in digits. Risk factors and outcome are discussed.*
- Li J, Guo Z, Zhu Q, et al. Fingertip replantation: determinants of survival. *Plast Reconstr Surg*. 2008;122:833–839.
- Yan JG, Yousif NJ, Dzwierzynski WW, et al. Irrigation pressure and vessel injury during microsurgery: a qualitative study. *J Reconstr Microsurg*. 2004;20:399–403.
- Zumiotti A, Ferreira MC. Replantation of digits: factors influencing survival and functional results. *Microsurgery*. 1994;15:18–21.
- Suri MP, Ahmad QG, Yadav PS. Managing venous discrepancy: simple method. *J Reconstr Microsurg*. 2009;25:497–499.
- Shuck J, Masden DL. Options for revascularization: artery versus vein: technical considerations. *Hand Clin*. 2015;31:85–92.
- Lee CH, Han SK, Dhong ES, et al. The fate of microanastomosed digital arteries after successful replantation. *Plast Reconstr Surg*. 2005;116:805–810.
- Urbaniak JR, Roth JH, Nunley JA, et al. The results of replantation after amputation of a single finger. *J Bone Joint Surg Am*. 1985;67:611–619.
- Chaivanichsiri P, Rattanasrithong P. Type of injury and number of anastomosed vessels: impact on digital replantation. *Microsurgery*. 2006;26:151–154. *A retrospective review of 130 digital replantations was performed. The type of injury and the number of vessel anastomoses were the most significant predictors of successful outcome. Crush injuries had significantly worse outcome than sharp injuries. In distal replantations, an arterial repair even without repair of a vein can achieve a high success rate.*
- Daane S, Zamora S, Rockwell WB. Clinical use of leeches in reconstructive surgery. *Am J Orthop (Belle Mead NJ)*. 1997;26:528–532.
- Han SK, Lee BI, Kim WK. Topical and systemic anticoagulation in the treatment of absent or compromised venous outflow in replanted fingertips. *J Hand Surg Am*. 2000;25A:659–667.
- Lin TS, Jeng SF, Chiang YC. Fingertip replantation using the subdermal pocket procedure. *Plast Reconstr Surg*. 2004;113:247–253.
- Zhang X, Wen S, Wang B, et al. Reconstruction of circulation in the fingertip without vein repair in zone 1 replantation. *J Hand Surg Am*. 2008;33A:1597–1601.
- Yamano Y. Replantation of the amputated distal part of the fingers. *J Hand Surg Am*. 1985;10A:211–218.
- Chen YC, Chan FC, Hsu CC, et al. Fingertip replantation without venous anastomosis. *Ann Plast Surg*. 2013;70:284–288.
- Barnett GR, Taylor GI, Mutimer KL. The “chemical leech”: intra-replant subcutaneous heparin as an alternative to venous anastomosis. Report of three cases. *Br J Plast Surg*. 1989;42:556–558.
- Chen KT, Chen YC, Mardini S, et al. Salvage of an avulsion amputated thumb at the interphalangeal joint level using afferent arteriovenous shunting. *Br J Plast Surg*. 2005;58:869–872.
- Gelberman RH, Urbaniak JR, Bright DS, et al. Digital sensibility following replantation. *J Hand Surg Am*. 1978;3:313–319.
- Glickman LT, Mackinnon SE. Sensory recovery following digital replantation. *Microsurgery*. 1990;11:236–242.
- Siemionow M, Brzezicki G. Current techniques and concepts in peripheral nerve repair. *Int Rev Neurobiol*. 2009;87:141–172.
- Agnew SP, Dumanian GA. Technical use of synthetic conduits for nerve repair. *J Hand Surg Am*. 2010;35:838–841.
- Dellon AL. Sensory recovery in replanted digits and transplanted toes: a review. *J Reconstr Microsurg*. 1986;2:123–129.
- Brooks D, Buntic RF, Taylor C. Use of the venous flap for salvage of difficult ring avulsion injuries. *Microsurgery*. 2008;6:397–402.
- Matloub HS, Strathy KM, Sanger JR, et al. Venous anatomy of the thumb. *J Hand Surg Am*. 1991;16:1063–1069.
- Rosson GD, Buncke GM, Buncke HJ. Great toe transplant versus thumb replant for isolated thumb amputation: critical analysis of functional outcome. *Microsurgery*. 2008;598–600.

50. Allen DM, Levin LS. Digital replantation including postoperative care. *Tech Hand Up Extrem Surg.* 2002;6:171–177.
51. An PC, Kuo YR, Lin TS, et al. Heterotopic replantation in mutilating hand injury. *Ann Plast Surg.* 2003;50:113–119.
52. Waikakul S, Vanadurongwan V, Unnanuntana A. Prognostic factors for major limb re-implantation at both immediate and long-term follow-up. *J Bone Joint Surg Br.* 1998;80:1024–1030.
53. Atzei A, Pignatti M, Maria Baldrighi C, et al. Long-term results of replantation of the proximal forearm following avulsion amputation. *Microsurgery.* 2005;25:293–298.
54. Hanel DP, Chin SH. Wrist level and proximal-upper extremity replantation. In: Dellapena D, ed. *Hand Clinics.* Philadelphia: WB Saunders; 2007:13–21.
55. Godina M. Early microsurgical reconstruction of complex trauma of the extremities. *Plast Reconstr Surg.* 1986;78:285–292.
56. Bueno RA, Neumeister MW. Outcomes after mutilating hand injuries: review of the literature and recommendations for assessment. In: Dellapena D, ed. *Hand Clinics.* Philadelphia: WB Saunders; 2003:193–204.
57. Xu JH, Gao ZJ, Yao JM, et al. Foster replantation of fingertip using neighbouring digital artery in a young child. *J Plast Reconstr Aesthet Surg.* 2009;62:38–41.
58. Narushima M, Mihara M, Koshima I, et al. Intravascular stenting (IVaS) method for fingertip replantation. *Ann Plast Surg.* 2009;62:38–41.
59. Li J, Guo Z, Zhu Q, et al. Finger replantation: determinants of survival. *Plast Reconstr Surg.* 2008;122:833–839. *A retrospective review of 211 finger amputations was performed over a 16-year period. An 81.5% success rate was achieved. Injury mechanism, platelet count, smoking, and the use of vein grafting were found to be the main predictors for the survival of the replanted fingertip.*
60. Puhaindran ME, Paavilainen P, Tan DMK, et al. Dermal pocketing following distal finger replantation. *J Plast Reconstr Aesthet Surg.* 2009;113:247–253.
61. Jung MS, Lim YK, Hong YT, Kim HN. Treatment of fingertip amputation in adults by palmar pocketing of the amputated part. *Arch Plast Surg.* 2012;39:404–410.
62. Lin TS, Yang JC. Secondary subdermal pocket procedure for venous insufficiency after digital replantation/revascularization. *Ann Plast Surg.* 2014;73:662–667.
63. Patadul A, Ngarmukos C, Parkpian V. Distal digital replantations and revascularizations 237 digits in 192 patients. *J Hand Surg [Br].* 1998;5:578–582.
64. Urbaniak JR, Evans JP, Bright DS. Microvascular management of ring avulsion injuries. *J Hand Surg Am.* 1981;6:25–30.
65. Kay S, Werntz J, Wolff TW. Ring avulsion injuries: classification and prognosis. *J Hand Surg Am.* 1989;14:204–213.
66. Akyurek M, Safak T, Kecik A. Ring avulsion replantation by extended debridement of the avulsed digital artery and interposition with long venous grafts. *Ann Plast Surg.* 2002;48:574–581.
67. Adani R, Pataia E, Tarallo L, Mugnai R. Results of replantation of 33 ring avulsion amputations. *J Hand Surg Am.* 2013;38:947–956.
68. Sanmartin M, Fernandes F, Lajoie AS, et al. Analysis of prognostic factors in ring avulsion injuries. *J Hand Surg Am.* 2004;29a:1028–1037.
69. Sears ED, Chung KC. Replantation of finger avulsion injuries: a systematic review of survival and functional outcomes. *J Hand Surg Am.* 2011;36:686–694.
70. Godina M, Bajec J, Baraga A. Salvage of the mutilated upper extremity with temporary ectopic implantation of the undamaged part. *Plast Reconstr Surg.* 1986;78:295–299.
71. Matloub HS, Yousif NJ, Sanger JR. Temporary ectopic implantation of an amputated penis. *Plast Reconstr Surg.* 1994;93:408–412.
72. Yousif NJ, Dzwierzynski WW, Anderson RC, et al. Complications and salvage of an ectopically replanted thumb. *Plast Reconstr Surg.* 1996;97:637–640.
73. Bakhach J, Katrana F, Panconi B, et al. Temporary ectopic digital implantation: a clinical series of eight digits. *J Hand Surg Eur Vol.* 2008;33E:717–722.
74. Nazerani S, Motamedi MH. Ectopic single-finger transplantation, a novel technique for nonreplantable digits: assessment of 24 cases – presenting the “piggyback” method. *Tech Hand Up Extrem Surg.* 2009;13:65–74.
75. Squitieri L, Reichert H, Kim HM, et al. Patterns of surgical care and health disparities of treating pediatric finger amputation injuries in the United States. *J Am Coll Surg.* 2011;213:475–485.
76. Buncke GM, Buntic RF, Romeo O. Pediatric mutilating hand injuries. In: Dellapena D, ed. *Hand Clinics.* Philadelphia: WB Saunders; 2003:121–131.
77. Michalko KB, Bentz ML. Digital replantation in children. *Crit Care Med.* 2002;30:S444–S447.
78. Ikeda K, Yamauchi S, Hashimoto F, et al. Digital replantation in children: a long-term follow-up study. *Microsurgery.* 1990;11:261–264.
79. Askari M, Fisher C, Weniger FG, et al. Anticoagulation therapy in microsurgery: a review. *J Hand Surg Am.* 2006;31A:836–846.
80. Levin LS, Cooper EO. Clinical use of anticoagulants following replantation. *J Hand Surg Am.* 2008;33A:1437–1439.
81. Chen LE, Seaber AV, Korompilias AV, et al. Effects of enoxaparin, standard heparin, and streptokinase on the patency of anastomoses in severely crushed arteries. *Microsurgery.* 1995;16:661–665.
82. Chen YC, Chi CC, Chan FC, Wen YW. Low molecular weight heparin for prevention of microvascular occlusion in digital replantation. *Cochrane Database Syst Rev.* 2013;(7):CD009894.
83. Jallali N. Dextran in microsurgery: a review. *Microsurgery.* 2003;23:78–80.
84. Ridha H, Jallali N, Butler PE. The use of dextran post free tissue transfer. *J Plast Reconstr Aesthet Surg.* 2006;59:951–954.
85. Ashjian P, Chen CM, Pusic A, et al. The effect of postoperative anticoagulation on microvascular thrombosis. *Ann Plast Surg.* 2007;59:36–40.
86. Disa JJ, Polvora VP, Pusic AL, et al. Dextran-related complications in head and neck Microsurgery: do the benefits outweigh the risks? A prospective randomized analysis. *Plast Reconstr Surg.* 2003;112:1534–1539.
87. Khouri RK, Cooley BC, Kunselman AR, et al. A prospective study of microvascular free-flap surgery and outcome. *Plast Reconstr Surg.* 1998;102:711–721.
88. Conrad MH, Adams WP. Pharmacologic optimization of microsurgery in the new millennium. *Plast Reconstr Surg.* 2001;108:2088–2096.
89. Kurt E, Ozturk S, Isik S, et al. Continuous brachial plexus blockade for digital replantations and toe-to-hand transfers. *Ann Plast Surg.* 2005;54:24–27.
90. Yan JG, Rowe DJ, Dzwierzynski WW, et al. Pathophysiological process of traumatic vascular spasm in multiple crush injury. *J Reconstr Microsurg.* 2007;23:237–242.
91. Bakri K, Moran SL. Monitoring for upper extremity free flaps and replantations. *J Hand Surg Am.* 2008;33A:1905–1908.
92. Hovius SER, van Adrichem LNA, Mulder HD, et al. Comparison of laser Doppler flowmetry and thermometry in the postoperative monitoring of replantations. *J Hand Surg Am.* 1995;20A:88–93.
93. Shieh SJ, Chiu HY, Lee JW, et al. Evaluation of the effectiveness of sensory reeducation following digital replantation and revascularization. *Microsurgery.* 1995;16:578–582.
94. Meyer TM. Psychological aspects of mutilating hand injuries. In: Dellapena D, ed. *Hand Clinics.* Vol. 19. Philadelphia: WB Saunders; 2003:41–49.
95. Grunert BK, Dzwierzynski WW. Prognostic factors for return to work following severe hand injuries. *Tech Hand Up Extrem Surg.* 1997;1:213–218.
96. Rusch MD, Grunert BK, Sanger JR, et al. Psychological adjustment in children after traumatic disfiguring injuries: a 12-month follow-up. *Plast Reconstr Surg.* 2000;106:1451–1458.
97. Hattori Y, Doi K, Ikeda K, et al. A retrospective study of functional outcomes after successful replantation versus amputation closure

- for single fingertip amputations. *J Hand Surg Am.* 2006;31A:811–818.
98. Walaszek I, Zyluk A. Long term follow-up after finger replantation. *J Hand Surg Eur Vol.* 2008;33E:59–64.
 99. Syrko M, Jablęcki J. Quality of life-oriented evaluation of late functional results of hand replantation. *Ortop Traumatol Rehabil.* 2010;12:19–27.
 100. Sugun TS, Ozaksar K, Ada S, et al. Long-term results of major upper extremity replantations. *Acta Orthop Traumatol Turc.* 2009;43:206–213.
 101. Chen CW. Extremity replantation. *World J Surg.* 1978;2:513.
 102. Tamai S. Twenty years' experience of limb replantation. Review of 293 upper extremity replants. *J Hand Surg Am.* 1982;7:549–556.
 103. Matasuzaki H, Narisawa H, Miwa H, et al. Predicting functional recovery and return to work after mutilating hand injuries: usefulness of Campbell's hand injury severity score. *J Hand Surg Am.* 2009;34A:880–885.
 104. Elliot D, Sood MK, Flemming AFS, et al. A comparison of replantation and terminalization after distal finger amputation. *Br J Hand Surg.* 1997;22B:523–529.
 105. Kamburoğlu HO, Aksu AE, Sönmez E, et al. Which instrument should we use to assess hand function after digital replantation? *J Hand Surg Eur Vol.* 2011;36:392–395.
 106. Graham B, Adkins P, Tsai TM, et al. Major replantation versus revision amputation and prosthetic fitting in the upper extremity: a late functional outcomes study. *J Hand Surg Am.* 1998;23:783–791.
 107. Hoang NT, Hai LH, Staudenmaier R, et al. Complete middle forearm amputations after avulsion injuries – microsurgical replantation results in Vietnamese patients. *J Trauma.* 2009;66:1167–1172.
 108. Weinzweig N, Sharzer LA, Starker I, et al. Replantation and revascularization at the transmetacarpal level: long-term functional results. *J Hand Surg Am.* 1996;21A:877–883.
 109. Yu JC, Shieh SJ, Lee JW, et al. Secondary procedures following digital replantation and revascularization. *Br J Plast Surg.* 2003;56:125–128.
 110. Hanasono MM, Butler CE. Prevention and treatment of thrombosis in microvascular surgery. *J Reconstr Microsurg.* 2008;24:305–314.
 111. Vaksvik T, Hetland K, Rokkum M, et al. Cold hypersensitivity 6 to 10 years after replantation or revascularization of fingers: consequences for work and leisure activities. *J Hand Surg Eur Vol.* 2009;34E:12–17.
 112. Matsuzaki H, Kouda H, Maniwa K. Secondary surgeries after digital replantations: a case series. *Hand Surg.* 2012;17:351–357.
 113. Yu JC, Shieh SJ, Lee JW, et al. Secondary procedures following digital replantation and revascularization. *Br J Plast Surg.* 2003;56:125–128.
 114. Pitzler D, Buck-Gramcko D. Secondary operations after replantation. *Ann Chir Gynaecol.* 1982;71:19–27.
 115. Jupiter JB, Pess GM, Bour CJ. Results of flexor tendon tenolysis after replantation in the hand. *J Hand Surg Am.* 1989;14:35–44.
 116. Sebastin SJ, Chung KC. A systematic review of the outcomes of replantation of distal digital amputation. *Plast Reconstr Surg.* 2011;128:723–737.
 117. Sears ED, Shin R, Prosser LA, Chung KC. Economic analysis of revision amputation and replantation treatment of finger amputation injuries. *Plast Reconstr Surg.* 2014;133:827–840.

12

Reconstructive surgery of the mutilated hand

William C. Pederson and Randolph Sherman

Access video content for this chapter online at expertconsult.com 

SYNOPSIS

- Thorough debridement is essential in the management of these patients to decrease risk of infection and scarring.
- In cases of arterial insufficiency, provisional revascularization via a shunt or temporary vein graft should be considered.
- Adequate skeletal stabilization should be performed early and preferentially is done with internal fixation to allow definitive repairs of neurovascular structures and soft-tissue coverage.
- Definitive vascular reconstruction is usually delayed until after skeletal stabilization is achieved.
- Musculotendinous reconstruction should be done early if possible, to the point of performing early tendon transfers.
- Nerve repair is also best performed early, to allow proper alignment of nerves and to avoid having to dissect the nerve out of scar at a secondary procedure.
- Proper management of the soft-tissue envelope is essential to allow all of the other structures to be repaired as noted above. Proper flap selection allows early rehabilitation and facilitates secondary surgery when necessary.
- Postoperative management revolves around proper planning at the first stage of reconstruction. Every surgery should be performed with an eye to what will need to be done in the future.

Introduction

General

Management of the mangled upper extremity is complex, demands special skills and expertise, and is facilitated by a team approach with participation of all those dedicated to upper extremity surgery. When adequate facilities, equipment, and surgical expertise are not available to manage the patient's degree of injury, the patient should be transferred with the extremity splinted. If the limb is ischemic, or if part of the limb is amputated, the extremity should be cooled. The

ischemic limb should be carefully covered in ice, with a protective barrier to prevent frostbite injury. The amputated part should be wrapped in a saline-soaked gauze, placed on ice, and sent with the patient. The ideal temperature is +4°C. Dry ice or alcohol should not be used to aid in cooling during transport of the part as this can cause actual freezing of the tissues.

Resuscitation of the patient is a priority over addressing the extremity injury. However, in the event of a coexisting life-threatening injury, the extremity injury must not be neglected. Assessment of vascularity, realignment, and splinting are not time-consuming and should be done as soon as possible. Provisional revascularization through shunting may be an option to quickly restore circulation to the extremity while the trauma team simultaneously addresses the coexisting injuries. Consent of the patient should initially be obtained for wide debridement of the wound; internal versus external fixation; repair or reconstruction as indicated of nerves, vessels, tendons, and muscles; use of vein grafts for arterial and venous reconstruction; possible donor sites for flap coverage; and primary amputation. The selected treatment is based on the intraoperative findings.

The initial treatment includes meticulous debridement, wound irrigation, wound culture, antibiotic administration, and tetanus prophylaxis. Copious irrigation of the wound coupled with debridement is important because it removes foreign bodies and decreases the bacterial load. High-pressure and/or pulsed lavage of the soft tissues is to be avoided in these types of injuries, as it may force debris and bacteria into the tissues and has a tendency to force fluid into the tissues, potentially creating more edema in the postoperative period. The cultures most predictive of later infecting organisms are the post-irrigation cultures. Antibiotics will help reduce infection and should be administered in the emergency department and continued intravenously for at least 72 hours. Antibiotic coverage should be effective against both gram-positive and gram-negative organisms. The authors currently prefer to use a first-generation cephalosporin and an aminoglycoside in combination. In cases of soil contamination, as in farm injuries,




Fig. 12.1 43-year-old patient who suffered a crush injury to his hand when an airplane fell on it while under repair. This hand will require extensive debridement to delineate which tissues are viable and which are not.

coverage against anaerobic organisms should always be added. High-dose penicillin provides excellent anaerobic coverage. The possibility of gas gangrene should also be considered in these cases. The antibiotic regimen should subsequently be modified depending on the culture results. Tetanus prophylaxis should be administered in accordance with the status of previous immunization.

Debridement (Video 12.1)

Radical debridement with elimination of all nonviable tissue is *the crucial step* in the management of these injuries. This is performed under tourniquet control to provide the best visualization of the extent of injury and to prevent iatrogenic injury to intact structures. Once nerves and vessels are identified, the tourniquet may be released to better assess the viability of the remaining tissue (Fig. 12.1).

Skin and subcutaneous tissues are sharply debrided to bleeding edges. Muscle is debrided until bright red blood is seen. Color and twitch are used to assess muscle tissue; however, these characteristics are not totally reliable in determining viability. If the muscle does not bleed, it is dead and should be debrided. Small bone fragments devoid of soft-tissue attachments are avascular and should be discarded unless they constitute part of an articular surface. Contused or contaminated nerves are left in continuity. Superficial dissection above the epineurium can be carefully done to remove foreign material if it is present. Cut nerves are debrided to healthy-appearing fascicles. At the time of reconstruction, this is done under microscopic visualization because a primary repair or nerve graft will fail if the entirety of the injured segment is not resected.

The wound is copiously irrigated. Tissue margins are re-evaluated, and further debridement is performed as necessary. Hemostasis should be done cautiously. Do not cauterize vessels that may be needed for arterial or venous reconstruction. Side branches may be controlled with small sutures or vascular clips. Arterial debridement is performed for cut or thrombosed vessels. Definitive debridement of arteries that

are to be reconstructed is done with the tourniquet released. At the completion of debridement, assess and record what structures remain intact and what the functional losses are. Some of the remaining intact muscles may be suitable for immediate tendon transfer to replace important functional losses.

Provisional revascularization

When the extremity is amputated or ischemic and the delay to surgery or anticipated length of time for debridement and definitive skeletal stabilization exceeds 6 hours, provisional revascularization can be done with use of a shunt, such as a Javid, Ishihara, or comparable segment of plastic tubing (Fig. 12.2). Another option is to rapidly perform reversed vein grafting between the arterial ends to re-establish arterial inflow. After definitive skeletal stabilization, the length of the vein graft can be adjusted and the anastomosis revised.

Skeletal stabilization

Definitive stable internal fixation should be done immediately when possible to allow therapeutic access to the extremity for wound care and early joint range of motion when applicable. In general, the use of external fixation is to be avoided. These





Fig. 12.2 (A) 24-year-old patient after mid-forearm amputation. Shunt placed from radial artery to radial artery to perfuse limb while debridement and bony fixation is performed. (B) View of shunt perfusing limb while debridement is performed.

devices carry the risk of neurovascular injury during pin placement, restrict circumferential access to the extremity, and may limit rehabilitation. They may be useful as a temporary solution for severely contaminated wounds with extensive soft-tissue injury, however. External fixation should not be used for the reason to avoid exposed hardware. Potentially exposed hardware should be addressed with appropriate soft-tissue coverage.

Diaphyseal fractures of the arm and forearm are usually amenable to plate fixation. If the fracture is segmental or comminuted over a large segment, a flexible interlocking intramedullary nail can be used. Fractures should be reduced anatomically with respect to rotational alignment. One must carefully check pronation and supination prior to final fixation to avoid placing the hand in a poor position. Comminuted bone fragments without soft tissue attachments should be removed. Shortening of the humerus up to 5 cm and of the radius and ulna up to 4 cm is acceptable. Indications for shortening include significant comminution over a segment with bone and soft-tissue loss and bony shortening has the advantage of allowing primary repair of vessels and, more important, of nerves.

Complex diaphyseal fractures include Galeazzi fractures (radial diaphyseal fracture with disruption of the distal radioulnar joint), Monteggia fractures (proximal ulna fractures with radial head dislocation or radial head or neck fracture), and Essex-Lopresti injuries (radial head fracture with associated rupture of the interosseous membrane to the level of the wrist). These fractures must be restored to anatomic length to restore joint congruity and alignment.

Diaphyseal fractures of the hand are fixed with Kirschner wires, with attention to maintaining rotational alignment. Shortening of the metacarpals or phalanges between 5 and 6 mm may be necessary in replantation. For other injuries, length can be restored or maintained with internal or external fixation and primary or delayed bone grafting. In general, initial use of plate fixation is not recommended in the hand, particularly in the phalanges. This requires more stripping of the periosteum and later has an adverse effect on functional outcome because of potential tendon adhesions around the plate.

In contrast to lower extremity injuries, primary bone grafting is acceptable and recommended in the upper extremity. Primary iliac crest bone graft or bone allograft may be used for defects up to 4 cm. For larger defects, vascularized bone grafts, in particular a vascularized segment of free fibula, should be considered (see below). With massive bone loss, creation of a one-bone forearm can be considered as a salvage procedure when other options are not available. The results of this procedure in trauma are not as good as in limb salvage surgeries for tumor reconstruction.

Intra-articular fractures should be anatomically reduced. Stable fixation is imperative to allow early range of motion. Fixation can be done with plates, screws, K-wires, or tension band wiring as dictated by the fracture pattern and location. Articular fragments free of soft-tissue attachments should be preserved to reconstruct the joint surface. Primary bone grafting should be done to address bone defects, to enhance the stability of the fixation, and to promote bone healing. If there is complex injury to the distal radius and/or wrist, spanning plates across the wrist may be used to provide excellent fixation and allow healing of complex bony and ligamentous

injuries.¹ These have been shown to be an excellent option in the face of severe injury and soft-tissue dissection can be minimal, without the disadvantages of external fixation² (Fig. 12.3). When the joint surface cannot be reconstructed owing to severe comminution or bone loss, other reconstructive options are available. At the shoulder and elbow, a primary allograft or a prosthesis can be used. At the wrist joint, primary fusion should be the first treatment option. If wrist motion is critical to the patient, vascularized free fibula, retaining the proximal articular cartilage, can be used to reconstruct the joint surface. Prosthetic devices for total wrist arthroplasty are poor at present, and historically do not do well in post-traumatic wrists regardless.

In summary, the goal of skeletal stabilization is to achieve stable anatomic fixation to allow early range of motion and rehabilitation. Soft-tissue stripping of bone is limited to only that which is necessary for fixation. Comminuted fragments with attached soft tissue are retained. Bone defects are treated primarily whenever possible. The potential of exposed hardware should not limit the choice of fixation. Exposed bone, hardware, or joints are addressed with appropriate soft-tissue coverage, whether it be pedicled or free.

Vascular reconstruction

Definitive revascularization is done once skeletal stabilization is completed. Lacerated vessels are resected to healthy-appearing vessel wall both proximally and distally. Contusion along the adventitia suggests injury within the intimal layer as well. A "ribbon sign" (convoluted or tortuous course of the digital vessels) indicates injury to the media layer of the vessel and requires resection of the length of the involved area and reversed vein grafting (Fig. 12.4). Inflow is assessed, and if it is not adequate, the vessel should be resected more proximally until excellent pulsatile flow is achieved.

When possible, primary repair is preferred. However, it is better to resect appropriately and to use a reversed vein graft than to perform a primary repair under tension. Reversed vein grafts are available from several sites. The most commonly used for long segments in the upper extremity is the saphenous vein. For reconstruction in the hand, local grafts from the dorsal or volar forearm can be used.

Reconstruction of the superficial palmar arch and its multiple common digital arteries may be difficult. Branched vein grafts from the dorsum of the foot and use of the subscapular artery and its branches have been described for this. The descending branch of the lateral femoral circumflex artery may also be utilized as a smaller arterial graft to make use of its branches to reconstruct the arch. The conventional method is to harvest two Y vein segments from the volar forearm and to perform end-to-end or end-to-side anastomoses as necessary. Vein grafts should be routinely used to reconstruct venous outflow if primary repair cannot be achieved. There is almost no role for artificial grafts for vascular reconstruction in the upper extremity distal to the axillary artery, particularly in contaminated wounds.

When the need for coverage and vascular repair present themselves simultaneously, one can consider "flow-through" free flaps to both bridge the arterial defect and obtain coverage at the same time. The radial forearm free flap is very useful in this regard, as the radial artery offers an excellent choice for a long bypass.³ Due to trauma to the



Fig. 12.3 (A,B) Preoperative X-rays of patient suffering crushing injury to the wrist. Note midcarpal capitate fracture/dislocation and radial styloid fracture. **(C,D)** After reduction and fixation with spanning plate. (Courtesy of Dr. Ramesh Srinivasan, the Hand Center of San Antonio.)

forearm, however, this may not be an appropriate choice of flap. In this case, the anterolateral thigh flap with its long segment of the descending branch of the lateral femoral circumflex can be utilized.^{4,5} Small venous free flaps with arterialized segments of vein can be utilized to great utility for revascularization of fingers in the face of a soft-tissue loss volarly.⁶

Musculotendinous reconstruction

Primary tendon repair is preferred when permitted by the injury. There is often a crush or avulsive component to the injury, which may preclude primary repair. In these cases, treatment options include primary or delayed reconstruction

with tendon grafts or Silastic tendon rods. Immediate reconstruction is favored with use of available donor tendons (palmaris, plantaris, local tendons that cannot be reconstructed, and toe extensors).

In flexor tendon injuries in the hand, priority is usually given to reconstruction of the profundus tendons. If there is trauma to the distal interphalangeal joint requiring fusion, priority is rather given to the superficialis tendon. The lesser priority tendon can be used for reconstruction of the other when necessary. It can be used as a donor tendon for other sites or for pulley reconstruction as necessary. One should pay close attention to the status of the pulleys in the fingers, and the A2 and A4 should be reconstructed with portions of tendon grafts when necessary.




Fig. 12.4 “Ribbon” sign in an avulsed finger. Note corkscrewing of vessel which indicates severe avulsion damage to the adventitial layer.

Functional reconstruction of muscle deficits and tendon injuries should be done immediately whenever possible.⁷ Unrecoverable muscle function can be treated with tendon transfer, and it is preferable to perform this as a primary procedure. However, this can also be performed at a later stage of reconstruction. Delayed transfers are generally more difficult because they have to be performed through a scarred tissue bed, and this requires additional surgical procedures and further delays the patient’s rehabilitation and recovery. When no donor tendons are available for transfer muscle function can be restored with functional free muscle transfer. The gracilis is the most commonly used muscle for functional reconstruction and can actually provide both coverage and restoration of muscle function to the fingers. Again, this can be done either primarily or at a later stage of reconstruction, however primary reconstruction is favored as available nerves and vessels are easier to locate and one is not operating through a scarred bed of tissue. This procedure will be discussed in more length below and in Chapter 35.

Nerves

Nerves may have internal derangement without loss of anatomic continuity and they can be partially or completely disrupted. Severe contusion to the nerve with internal hemorrhage without actual division may mitigate against functional return, however contused or attenuated nerves are usually left intact. If lacerated, the nerve ends should be debrided serially under magnification until healthy-appearing fascicles appear. Do not compromise the resection to preserve length, as nerve regeneration will not occur through scarred nerve tissue, and nerves repaired under tension also do not recover well.

Mobilizing the proximal and distal stumps to achieve primary repair is not recommended because this results in devascularization of large segments of the nerve. Mobilization can be done over a 1- to 2-cm distance to allow repair, but to avoid repair under tension, nerve grafting is preferable. If a staged repair is planned, nerve ends are tagged with 6-0 polypropylene suture for later identification. Primary nerve grafting is recommended, however, as the orientation is much

clearer at the time of injury rather than later and dissecting a nerve out of a scarred bed is technically challenging (Fig. 12.5). Common donor nerves include the sural or saphenous nerves, sensory branch of the radial nerve (if lacerated from the injury), medial or lateral antebrachial cutaneous nerves, and the posterior interosseous nerve. In multiple nerve injuries, primary nerve transfers can be performed.⁸ These include transfer of the anterior interosseous nerve (distal to the branch to the flexor pollicis longus) to the motor branch of the ulnar nerve and transfer of the sensory branch of the radial nerve to the digital nerves of the thumb and index finger.⁹ When a nerve defect is greater than 15 cm, an end-to-side neurorrhaphy of the distal stump of the injured nerve to a neighboring intact major nerve can be done, although functional outcomes of this procedure are generally poor.

Skin and soft-tissue reconstruction

Appropriate soft-tissue coverage is of paramount importance for coverage of bone, joint, tendons, neurovascular structures, and hardware. The selection of coverage should provide a gliding surface for mobile structures and enhance vascularity in the injured area.

Extensive skin and soft-tissue loss is one of the major problems in the mangled upper extremity. Isolated skin loss may be managed by split-thickness skin grafting (if not over a bony prominence, hardware, or exposed tendons). Local random skin flaps have limited utility even in superficial soft tissue defects owing to their restricted mobility, precarious blood supply, and frequent involvement in the injury.

Soft-tissue loss can be managed in a variety of ways. A simple approach is to leave the wound open and let it heal by secondary intention with granulation tissue. However, exposed tissues sensitive to desiccation, such as nerves and tendons, will become necrotic, scarring will be promoted, and function will be compromised. Local muscle flaps are usually not suitable because of their proximity to the zone of injury, the limited amount of coverage that they provide, and the resulting functional deficit. Two-stage distant pedicled flap procedures are avoided when possible; immobilization of the reconstructed area will lead to stiffness and swelling. If this means of coverage is required, the most common sources are the pedicled groin flap, cross-arm flap, thoracoacromial flap, and abdominal flap. In mangling injuries, the need for extensive coverage, reliable vascularity of the flap, and early mobilization usually necessitates use of axial flaps (local or regional), one-stage distant pedicled flaps, or free flaps. The type of coverage depends on site and extent of the defect. This is particularly important for bone, tendon, nerve, and hardware coverage, as well as for facilitation of future reconstructive procedures in planning a staged reconstruction. As discussed above, one should think one or two steps ahead in terms of what reconstructive procedures are potentially going to be performed later under or through the chosen flap.

Fasciocutaneous flaps or cutaneous flaps with subcutaneous tissue are recommended when tendons are exposed as this tissue facilitates tendon gliding. However, many fasciocutaneous flaps over time do not have a good cosmetic appearance (color match can be poor and they can be too bulky). The primary fasciocutaneous flaps used with acceptable cosmetic appearance include the radial forearm flap, as either a free or rotational flap; the lateral arm flap; and the




Fig. 12.5 (A) View of upper arm in patient suffering avulsive injury and global nerve palsy in the hand. (B) Close-up view of nerves. Median and ulnar over background in front and radial behind. (C) Nerves after debridement to healthy fascicles and sural nerve grafting.

groin flap. These can all be utilized as free flaps, but the groin flap is generally utilized today as a pedicled flap due to the small size and short available vascular pedicle. An alternative to the fasciocutaneous flap is a fascial flap. Donors for this include the temporoparietal fascia, the parascapular fascia, and the radial forearm fascia. The free fascial flap is placed on the defect and then covered with an unmeshed split-thickness skin graft. It has been our experience, though, that it can be difficult to lift a fascial flap later for tenolysis or other procedures.

Muscle flaps are used when a moderate to large soft-tissue defect is present. Although muscle flaps may be harvested with a skin component, harvesting of muscle alone is preferred. This is then covered with a split-thickness skin graft. In the arm and elbow, the latissimus dorsi can be used as a one-stage distal pedicled rotational flap. Most other reconstructions are done with a free muscle transfer using the gracilis, rectus abdominis, latissimus dorsi, or serratus anterior. When a functional deficit is present, consideration should be given to use of a functional free muscle transfer to provide both functional restoration and soft-tissue coverage. The

gracilis is most commonly used for this transfer in the forearm as noted above.

Postoperative management

In the immediate postoperative period, the extremity is splinted in an appropriate position to prevent capsuloligamentous shortening and tension on repaired structures. Elevation is necessary to reduce edema and help control pain. The patient's pain and anxiety should be adequately controlled. The ambient temperature should be at least 25°C and adjusted to the patient's body temperature. Hydration should be sufficient to maintain urine output between 80 and 100 mL/hr. Anticoagulant therapy is used by many surgeons. However, the authors are selective in using heparin; aspirin is used daily for 4 to 6 days after surgery. Appropriate antibiotic therapy is continued in the postoperative period and later modified as necessary according to culture results.

Extremity and flap monitoring is critical. Early recognition of arterial hypoperfusion or venous congestion will occur only in a well-monitored environment with trained nursing

staff. If there is a question about tissue viability, the dressings are released and the entirety of the revascularized tissue is exposed for further assessment of perfusion, congestion, temperature, turgor, and color with Doppler examination. Release of the dressings alone may be sufficient to alter the vascular issue. If viability is still in question after 30 minutes, immediate re-exploration and further assessment may prevent failure of the revascularized tissue, whether it be the extremity or a free flap.

Early and motivated rehabilitation of the extremity is an important factor in achieving a successful outcome. Early motion reduces edema, adhesions, and scarring. It prevents muscle atrophy and facilitates healing of the soft tissues by remodeling of collagen fibers. The details of the rehabilitation program are determined by the existing injuries and the reconstruction procedure.

Basic science/disease process

Upper extremity function and facial appearance and expression are the two centrally defining features of our humanity. Movement of the hand through space along with precise grasp, pinch, and positioning allows us to perform the most rudimentary to the most highly complex tasks to actualize the entire range of our wishes, dreams, and ambitions. Man without hands is akin to a plane without wings. Nearly all tasks combine positioning of the hand with shoulder, elbow, and wrist motion followed by intricate manipulation of finger joint position with both intrinsic and extrinsic muscle force modulation.

Injuries to any part of the upper extremity, no matter how minor, may immediately compromise and chronically debilitate the user's ability to perform. Witness the enormously negative impact of work-related injuries on our economy. Productivity is reduced, medical costs are escalated, and the work environment is disrupted, not to mention the enormous personal and family suffering caused by pain and loss of function. Some have estimated the cost to our economy from upper extremity trauma to run in the hundreds of billions of dollars. In light of the significantly problematic consequences that result from extensive upper extremity injuries, it is paramount that early diagnosis and, more important, strategically sound treatment be instituted from the outset.

Extensive skin and soft-tissue trauma along with composite injuries involving multiple structures must be managed actively, there being few circumstances in the hand in which open wound management and healing by secondary intention play a role. Maximum preservation of motion and sensibility should be ever present in the mind of the reconstructive surgeon from the moment of first evaluation, with prompt wound closure given high priority.

The term *mangled* is commonly used to describe the hand and upper extremity after major trauma. Gregory *et al.* used the term *mangled* to describe a severe injury to at least three of the four organ and tissue systems of skin, bone, vessel, and nerve.¹⁰ According to the *Oxford English Dictionary*, to mangle is "to reduce by cutting, tearing or crushing to a more or less unrecognizable condition". Each of these definitions implies a severe, high-energy injury that involves multiple anatomic structures, usually over an extended topography.




Fig. 12.6 View of hand after it was caught in a 9-ton press. This is the definition of mangled, however it was also unfortunately unsalvageable.

Mangling injuries are produced by high-energy forces. High-power equipment – agricultural (corn picker, grain auger), industrial (punch press, power saw), or household (lawn mower, snow blower) – may cause such an injury (Fig. 12.6). In addition, gunshot wounds, explosives, and motor vehicle accidents (especially with the arm of the patient being outside the car window¹¹) account for many cases. The injury may have a combination of sharp, crushing, avulsive, and thermal components. The wound may be severely contaminated, depending on the location and mechanism of injury.

Types of injury

Amputation involves complete severing of a part from the body. This is common in the upper extremities, and ranges from fingertip amputation (an extremely common injury and one of the most common ones seen in emergency departments) to amputation of the entire upper extremity at the shoulder. While fingertip amputations may be managed in any number of ways (most by benign neglect) with excellent outcomes, management of major limb amputations can lead to significant functional and cosmetic deformity and present significant local and systemic problems in management. Replantation of amputated parts requires microsurgical skills and may necessitate other procedures to lead to final restoration of function.

Crush injuries may and may not lead to amputation, but involve significantly more damage to the involved structures than straightforward and sharp amputations. These injuries often lead to major loss of bony and soft-tissue structures and have much poorer results both in terms of survival (if replantation is required) and function. Familiarity with various options for bony and soft-tissue reconstruction, as well as nerve and musculotendinous reconstruction, is often required.

Avulsion injuries primarily involve the soft tissues of the upper extremity. The etiology of these injuries is often due to industrial accidents in roller press machines which cause both bone dislocations in the hand and can lead to loss of the entire soft-tissue envelope to the hand (Fig. 12.7). These injuries predictably lead to severe scarring and often poor function despite the type of reconstruction performed. Early motion is essential for reasonable outcomes in these injuries.




Fig. 12.7 Hand of 25-year-old male with avulsion injury of entire skin of hand and distal portions of phalanges. This is a devastating injury and will require a number of procedures for adequate reconstruction.

Roller injuries occur when the hand is caught between two rollers whose function is usually to compress sheets of metal. This can result in an array of injuries including degloving of the skin of the hand, fractures, and potentially crushing of all the tissues of the hand and forearm. These are devastating injuries and call on the entire armamentarium of the surgeon to manage the bony fractures, dislocations, and coverage and functional issues from soft-tissue damage (Fig. 12.8).

Careful evaluation of both the patient and the injury, formulation of a treatment plan, meticulous operative treatment

by an experienced team, and early, motivated rehabilitation reduce the morbidity associated with these injuries.

Diagnosis/patient presentation

Evaluation of the patient in the emergency room

Evaluation of the patient with a high-energy injury includes a thorough trauma work-up, beginning with the basics of airway, breathing, and circulation. Whereas the mangled extremity is often the most apparent injury, careful evaluation of the entire patient for potential life-threatening or other associated injuries is critical to formulation of a treatment plan.

The patient's history focuses on the time and mechanism of injury and any associated chemical, electrical, or thermal components of the injury. The mechanism of and the time from injury, which is especially crucial when ischemia is present, are the most important factors in determining the zone of injury and predicting the ability to salvage the extremity. A medical history is taken to determine the patient's ability to tolerate a prolonged anesthetic with the potential for significant blood loss, fluid shifts, and release of metabolic byproducts after revascularization of ischemic tissue. Medical conditions such as diabetes, hypertension, vasculitis or other inflammatory diseases, and smoking history can adversely affect outcome and should be considered in developing a treatment plan. Similarly, the occupational history and social




Fig. 12.8 (A) 27-year-old male who got his hand caught in a roller press. Note avulsion of muscles and position of hand. (B) AP X-ray of hand and wrist. Patient has a longitudinal dislocation between the 3rd and 4th rays (a “peri-hamate peri-pisiform” injury) which is typical of crushing injuries to the hand. (C) Lateral X-ray of the hand and wrist. Note the carpometacarpal dislocation of the thumb in this view, also fairly typical of crushing injuries to the hand.

history are important in determining postoperative compliance and in addressing the reconstructive goals. The presence of one or several adverse factors is not an absolute contraindication to salvage of an extremity or to microvascular repair and/or reconstruction. However, these factors should be considered in selecting the type of reconstruction to be used and in better predicting outcome.

Examination of the mangled extremity should be systematic and address vascular status, skeletal stability, motor and sensory function, and soft-tissue loss. The vascular status is evaluated by assessment of peripheral pulses, color, temperature, and capillary refill time in the distal extremity. Pulse oximetry is generally readily available in the emergency department and is helpful in assessing ischemia in the fingers. Doppler examination and angiography can also be used. Arteriographic exam in the mangled extremity may simply delay revascularization, however, and should be utilized very selectively. Skeletal injury is assessed clinically by the presence of deformity, crepitance, or bone tenderness. Radiographs should be taken of the entire extremity – particularly to evaluate the joints above and below the level of injury. A motor and sensory examination should be documented. The examiner should be aware that motor or sensory loss can result from muscle, tendon, or nerve injury as well as from ischemia. The ultimate assessment of the mangled extremity occurs in the operating room, however, after the debridement of nonviable tissue.

In the case of limb-threatening ischemia in a mangling injury, evaluation of the status of the vessels is generally performed in the operating room without the delay necessary for an arteriogram. An intraoperative angiogram may aid in determining the level and extent of arterial injuries, however. Radiographs taken in the operating room are usually of better quality than those taken in the emergency department because the extremity can be positioned without causing the patient discomfort. Traction radiographs allow better delineation of the fracture pattern and number of fragments, especially in evaluating intra-articular fractures about the wrist and elbow. Photographic documentation of the injury should be done throughout the course of treatment from initial evaluation to conclusion of treatment.¹²

Clinical tips

Initial management

- Debridement of all nonvital tissue is essential
 - Save intact vessels, nerves, and tendons
 - May need to return in 24–48 hours to reassess
- Fixation is important in management
 - Internal fixation is superior
 - Consider “spanning” plates across joints
- As you clean up, consider timing and type of coverage
 - May need a flap early to cover neurovascular structures
 - Can re-debride under flap
- Consider single-stage reconstruction when appropriate
 - Reconstruct tendons with grafts
 - Reconstruct nerves with grafts
 - Consider delayed bony reconstruction or vascularized bone transfer

Emergency room to operating room – making a plan

Planning in patient management starts when the patient is first seen in the emergency room. As a general rule, however, multiple examinations of the extremity by multiple physicians (emergency physician, intern, resident, fellow, etc.) is to be avoided. In the unanesthetized patient this is painful and leads to further anxiety which can lead to vasospasm and further problems. The quality of circulation in the extremity must be assessed, and a rough idea of the soft-tissue deficit should be obtained in a single examination. X-ray studies of the extremity (and of the distal portion in cases of amputation) done in the emergency room can also give an idea of what might be necessary in terms of bony fixation. Consent must be obtained for whatever might be necessary to include bony fixation, revascularization (including potential vascular graft donor sites), and coverage. While an emergency free flap is rarely indicated, the patient should be informed of potential soft-tissue flap donor sites as well. The patient and family should also be informed of the need for further surgery, including second looks/wash-outs which should be performed in the first several days.

Planning for reconstruction

In deciding how best to treat the mangled extremity, a variety of factors are considered. They can be broadly classified as patient and extremity factors. Pertinent *patient factors* include the general condition, age, handedness, occupation, functional requirements, and socioeconomic background of the patient. Associated injuries resulting in cardiopulmonary or hemodynamic compromise as well as pre-existing medical problems will mitigate against a lengthy salvage procedure, especially in a patient of advanced age. Conditions adversely affecting the blood vessels, such as diabetes mellitus, vasculitis, or smoking, will increase the risk of anastomotic failure and should be taken into consideration. Psychiatric disorders may be a contraindication to reconstruction because of possible repeated suicide attempts or anticipated noncompliance with the rehabilitation program. A morose patient may be temporarily incompetent to participate in determining treatment. Because time is a critical factor in treatment, it may be better to err in attempting to salvage an extremity than to perform a primary amputation.

Important *extremity factors* include the time since the injury, the severity of the injury, and the previous functional status of the extremity. Warm ischemia time longer than 6 hours results in progressively irreversible changes in cellular structure of muscle. Even if vascularity is re-established, tissue necrosis will not be avoided. Systemic risks of revascularizing a limb with prolonged ischemia must also be considered and addressed. These include acidosis, hyperkalemia, and rhabdomyolysis. In amputations of digits, where no muscle is present, the delay until reperfusion with use of cold ischemia may be extended to 20 hours. Finally, the previous condition of the extremity is considered. A history of major trauma, neurologic disease, or congenital deformity resulting in impaired function may not justify a salvage attempt.

The multitude of factors and the complex interrelations among them make reaching a decision a difficult task, even for experienced surgeons. Specialized scoring systems have

been developed on the basis of lower extremity injuries. These may offer valuable guidelines for evaluating the lower extremity but cannot be applied well to the upper extremity.¹³ Each case is unique, however, and the final decision should be an individualized one based on assessment of the patient and extremity parameters as well as sound judgment. The patient's knowledge of the potential risks and benefits of surgery and the possibility of early or later amputation is important.

A third factor which is rarely discussed is the surgeon factor. The skill and experience of the surgeon managing the patient is extremely important in determining the outcome.¹⁴ While obviously the experienced surgeon is more likely to have a more favorable outcome, reasonable results can be obtained by others if they follow basic principles and stick to what they are comfortable doing. The surgeon who only occasionally performs microsurgical tissue transfer may better serve his patient by performing a pedicled flap for initial coverage than attempting an esoteric and complex microsurgical procedure that he read about once. It is always better to perform an initial reconstruction using a technique that you are familiar with rather than attempting to perform a procedure that has a high potential for failure. In any case, it is preferable to refer a patient with a complex extremity injury to a center which routinely deals with these problems rather than attempt reconstruction if one is not familiar with these types of problems.

The single most important factor in planning reconstruction of a mangled extremity is to in fact have a plan and to know what you are going to need to do next. While the merits of early reconstruction and primary vs. delayed reconstruction will be discussed below, the surgeon must have a plan and be ready to alter this depending on the findings at surgery and potential problems as they arise. The reconstructive surgeon must always think at least one or two steps ahead of where he is today in order to maximize his reconstructive efforts. *Anticipation of what will need to be done in the future is the primary determinant of what needs to be accomplished today.* If one decides to delay bone grafting but proceed with soft-tissue coverage (which is often applicable) the soft-tissue reconstruction should be done in such a manner to make the secondary bony reconstruction both feasible and easy. If there is a large bony defect which may potentially require vascularized bone grafting, the soft-tissue flap should be performed in such a manner as to facilitate performance of the vascularized fibula transfer later. This may mean that a pedicled soft-tissue flap is a superior choice to a free flap (to save recipient vessels for the later bone transfer), but if this type of coverage is not feasible, then the anastomosis for the soft-tissue transfer should be performed in a location and to a vessel which will not make a second microsurgical bone transfer technically more challenging than it already is. The same philosophy applies when one anticipates later toe transfer(s) for thumb or digital reconstruction. Another example is the potential need for later tenolysis or tendon grafting under a soft-tissue flap which is placed at the initial surgery. There is no question that it is much easier to re-operate through a soft-tissue flap than it is under a muscle flap. Muscle flaps scar rather severely underneath when placed on a wound, while soft-tissue flaps do not. Tendons also glide much easier under a fascia or fatty tissue flap than they do under a muscle flap, thus it is preferable to cover exposed

tendons (or wounds with gaps in tendons) with some type of fascial or fasciocutaneous flap.

Timing of reconstruction

Definitive reconstruction of the mangled extremity may be undertaken either early or late. In both reconstructive plans, the initial treatment includes aggressive debridement, skeletal stabilization, revascularization, and soft-tissue coverage. Early soft-tissue coverage is of paramount importance to limb salvage.¹⁵ This improves the vascularity to the traumatized area, limits exposure to hospital pathogens, and reduces the risk of infection. Coverage is technically easier to perform early; with delay, edema obscures tissue planes, vessels become friable, and vascular grafts may be needed to perform microanastomoses out of the zone of injury.¹⁶

Reconstruction of bone, tendons, and nerves can be performed either early or late. Early reconstruction implies repair or reconstruction of all injured structures during the initial phase of treatment, up to 10 days from the initial injury. Delayed reconstruction implies staged repair of bone, tendon, nerve, and soft tissue at different periods in the course of treatment. The choice of the reconstructive approach depends on the characteristics of the injury and the preference and expertise of the treating surgeon.

Early reconstruction (single-stage)

This approach requires debridement of the wound followed by reconstruction of all structures: bone, tendon, and nerve. This is done ideally within 24 to 72 hours. Primary corticocancellous bone graft or vascularized bone grafts, nerve grafts, tendon transfers, tendon grafting, and free functional muscle transfer are performed at the time of soft-tissue coverage. Reconstruction can be delayed up to 10 days in the event of a severely contaminated wound, which requires several debridements to reduce the contaminant load.

Primary reconstruction of all structures is technically easier to perform when the tissue bed is fresh rather than later through a scarred soft-tissue bed. It decreases the number of subsequent procedures, total hospitalization time, and cost. Also, rehabilitation can begin earlier. The development of adhesions is decreased, and the functional outcome is improved.^{17,18} This type of reconstruction by its nature, however, usually mandates experience and skill with microsurgical repair (nerves) and tissue transfer (for complex and composite tissue loss).⁷ If one lacks experience in this type of reconstruction, it is usually best to get primary soft-tissue coverage by whatever means is best and delay the reconstruction of the other structures until a stable soft-tissue bed is obtained.

Delayed reconstruction (multiple stage)

In the past, delayed, staged reconstruction was the primary method of treatment of severe injuries with multiple structural defects. In this treatment plan, vascularity is established, and the soft-tissue injuries are treated with serial debridements performed at 24- to 72-hour intervals. Appropriate wound coverage is performed when the wound is clean and all necrotic tissue has been debrided. This should be within the first 10 days from injury, regardless of the technique chosen. Bone, tendon, and nerve reconstruction is delayed until "soft




Fig. 12.9 (A) Hand of 38-year-old male after saw injury with amputation of index and middle fingers with mangling injury to thumb. Thumb is not replantable. (B) View of index finger after debridement and identification of structures for replantation. (C) Hand after replantation of index finger in thumb position.

tissue equilibrium” is achieved. This is when the tissues have healed and are free of infection, edema has resolved, scar tissue has matured, and the joints are supple and have achieved their maximum passive range of motion. Delayed reconstruction is a good option when the patient’s comorbidities or a severely contaminated or infected wound prevents early definitive treatment.

Salvage versus amputation

The surgeon may be confronted with the decision to attempt salvage or to amputate a mangled, nonviable upper extremity. The appropriate decision is difficult because recovery of function in a salvaged extremity may be limited or absent.¹⁹ Thus, multiple reconstructive procedures with associated morbidity, prolonged hospitalization, disability time, psychological distress, and financial demands may be too expensive a price to pay for the end result of a useless and painful limb. In contrast to prostheses for the leg, prostheses for the hand and forearm offer limited restoration of function. Even with the most advanced prosthetic devices available today, there is no sensory feedback from the prosthesis, and for most purposes, this makes a prosthesis less functional than a sensate yet injured hand. Thus, most mangled upper extremities should be considered for salvage. Nevertheless, serious associated injuries or diseases, ischemia time longer than 6 hours, and parts that are severely crushed, avulsed, contaminated, or injured at multiple levels constitute unfavorable conditions

for a replantation or revascularization attempt. In this setting, amputation is not a failure but rather a step toward stabilization of the patient and rehabilitation of the extremity.

Spare-parts utilization

In some instances in severe injury to the upper extremity, there may be uninjured tissues, which while not salvageable in their native position, may be utilized for coverage and/or reconstruction of the defect. This is certainly the case in multiple digital amputations when the thumb is severely damaged and another finger can be placed in the thumb position to reconstruct this important function (Fig. 12.9). Likewise, the tissue from an amputated finger or forearm can be utilized for coverage of another defect, or even an amputation stump, to salvage length and preclude the necessity for another flap. One should remember to salvage whatever may be useable for reconstruction from parts not deemed suitable for replantation, and this can include skin (grafts or flaps), bone graft, joints (vascularized or not), nerves and tendons.

Treatment/surgical technique

Options for bony reconstruction

Mangling injuries to the hand and upper extremity usually involve the bone structure as well as the soft tissue. This can



Fig. 12.10 X-ray of patient shown in Fig. 12.7 after reduction and pinning of dislocations using Kirschner wires.

range from dislocations to significant bone loss. Each of these must be managed primarily to allow stabilization for vascular and soft-tissue repairs. Dislocations are generally managed with relocation and pinning with Kirschner wires, which usually require 6–8 weeks in place to allow for healing of ligamentous structures. Crushing and roller press injuries commonly lead to longitudinal dislocations in the metacarpal and carpal bones, most frequently between the 3rd and 4th rays (axial loading dislocations or “meat cleaver” injuries). One may also see the thumb ray dislocated with the trapezium on the radial side of the hand. Ligament repair is rarely possible in these injuries, and the bony injury can be missed due to the fact that the soft-tissue issues are often quite dramatic (see Fig. 12.8B,C). Management of these injuries is appropriate reduction of the dislocations and/or fractures and pinning (Fig. 12.10). Immobilization is needed for 6–8 weeks. Other wrist dislocations are usually managed in a similar manner.

Fractures of the hand are often best managed with simple K-wire fixation, as this is a rapid and reliable technique. Taking a great deal of time to perform plate fixation in the case of severe injuries in the hand is often counter-productive, especially if the distal extremity is ischemic. This type of fixation usually will not allow early motion, but this is frequently difficult to do in any case in mangle injuries. On the other hand, fractures of the radius and ulna are best managed by internal plate fixation. This can be performed relatively rapidly, and gives very stable fixation. We prefer to utilize stainless steel locking plate fixation, and ideally there should be three screws placed on either side of the fracture. The state of the soft tissues should not be a deterrent to plate fixation, as providing good soft-tissue coverage (with an appropriate flap) should be part of the initial plan. The bone must be thoroughly debrided and contaminated fragments with no blood supply should be discarded, however. In the case of

severe contamination, a second wash-out at 48–72 hours should be planned with elevation of the soft tissues, further debridement, and irrigation.

Bone loss may or may not present a problem. Small segments may not preclude healing, but large segments may need reconstruction. Bones should still usually be placed in proper relationship with internal fixation whenever possible, and as noted above, with the ends in anatomic alignment around the gap. In heavily contaminated wounds, primary bone grafting (with non-vascularized grafts) is not indicated, as the bone graft could be lost to infection. Soft-tissue coverage should be obtained first and the gap dealt with by either standard bone graft (if the defect is less than 6 cm) or vascularized bone grafting (usually a free fibula transfer in the upper extremity). In cases where a significant amount of bone has been lost in both bones of the forearm, an external fixator may be required until adequate soft-tissue reconstruction can be performed and internal bony stabilization applied.

Options for vascular reconstruction

Ideally, primary repair of vascular injury will be possible, but if there is any doubt about potential injury to the ends of the vessels, one should rapidly perform a bypass graft. For most purposes in the upper extremity, this is going to involve the use of vein grafts. Artificial conduits smaller than 6 mm (primarily expanded PTFE or Gore-Tex) have extremely poor patency rates, and are not indicated for bypass grafting. That leaves primarily venous grafts and in some instances arterial grafts. For long segments in the upper arm or forearm, the preferred vein graft is the saphenous from the medial thigh or lower leg (Fig. 12.11). The lesser saphenous, located on the posterior-lateral portion of the ankle and running up the midline of the calf, presents another option if the saphenous is absent or severely varicose. Arm veins (the basilica or cephalic) can be utilized for bypass in the arm, but in the face of severe injury, these may not be available and in fact may be needed for venous outflow (particularly in the face of replantation).

For reconstruction of injuries distal to the wrist, small vein grafts from the volar forearm or dorsal foot may be used. The use of arterial grafts in reconstruction of the ulnar artery and arch has some advocates, and donor sites for this include the subscapular–thoracodorsal axis from the axilla and the descending branch of the lateral femoral circumflex artery in the lateral thigh.⁴ Both of these give a reasonable size match for the vessels of the arch, and may offer multiple side branches to anastomose to the common digital vessels as they come off of the reconstructed arch. In cases of traumatic injury with ischemic distal tissue, however, the time it takes to dissect these arterial grafts out (as compared to subcutaneous veins) is probably not worth it. To date, we are not aware that there is any proven benefit to utilizing arterial grafts over venous grafts.

Another option in the face of a moderately large wound with the need for arterial bypass grafting is the use of “flow-through” flaps. As noted above, several flaps are available for this, and the radial forearm free flap, anterolateral thigh, temporoparietal fascia,²⁰ and omentum have all be utilized as arterial flow-through free flaps. One can also utilize arterialized venous flaps, which have a great deal of utility in digital revascularization to cover small volar defects and provide




Fig. 12.11 (A) Arm of patient after vehicle roll-over with crush-avulsion injury. There were no palpable pulses in the wrist and the hand was cool. Surgeons at an outlying hospital planned to amputate the limb. (B) View of brachial artery after excision. Note severe intimal avulsion injury in mid-portion. (C) Portion of saphenous vein harvested for revascularization. Note branch taken with graft, which is to be utilized for anastomosis to free muscle transfer for coverage. (D) Vein graft distended with blood after removal of vascular clamps.

arterial inflow at the same time, while larger flaps based on the saphenous vein with large skin paddles have been successfully utilized.²¹ Another option in the case of large segments of amputated tissue is to provide both coverage and salvage of length utilizing all or a portion of the amputated tissue as a flow-through flap. The use of all of these flaps for both coverage and bypass is unusual, but the surgeon dealing with severe extremity injuries should be familiar with the options.

Nerve reconstruction

The ideal time for nerve reconstruction is usually at the time of injury, because it is easiest to determine level of damage (by observing bruising of the nerve), and dissection and orientation of the nerve are obvious prior to the onset of scarring. Nonetheless, the goal should be repair of nerve damage at the time of initial treatment with the caveat that nerve repairs

and/or grafts should be surrounded with well-vascularized tissue. This may require the use of vascularized flap transfer to maximize nerve recovery, however a flap may be needed regardless. Nerve repairs and nerve grafts should not be done if there is inadequate soft tissue surrounding the repair and should certainly not be placed under skin grafts.

Primary repair of damaged nerves is the ideal, but if this cannot be achieved, the nerve should be grafted. Small gaps of smaller, sensory nerves may be treated with any of the number of "tubes" available,²² however their utility in larger nerves and in longer gaps remains unproven.^{23,24} The recently approved nerve allograft has shown some possible application in nerve gaps, but the results in larger nerves have not proven to be the equal of autologous nerve grafts.²⁵ Autologous nerve grafts remain the gold standard, and a number of donor sites are available. The most commonly utilized is the sural nerve running from the posterior knee to the lateral ankle, but other peripheral sensory nerves can be utilized as

well. These include the saphenous nerve, the medial and lateral antebrachial cutaneous nerve, the radial sensory branch, and the medial brachial cutaneous nerve. These secondary sources of nerve graft are all limited by their diameter and available length compared to the sural. When nerves are grafted, an attempt must be made to line up similar areas of fascicular bundles on the nerves to maximize functional recovery.

As noted above, nerve transfers may be the best option when multiple nerves have been injured.^{8,9} The reader is referred to Chapters 32 and 33 in this text for more information on these subjects.

Muscle and tendon repair and reconstruction

As with other structures, primary repair of muscles and tendons is desirable. Tendons and tendon repair will also require good, vascular soft-tissue coverage in order to both survive and have maximal function. Flexor tendons in the hand and fingers should be repaired with a double core suture whenever possible, with the addition of an epitendon stitch of fine monofilament suture to aid in gliding.²⁶ In the case of injury to both the flexor digitorum superficialis and profundus tendons in the finger, one may opt to simply repair only the profundus, particularly if the cut ends are untidy. If the ends cannot be brought together, one must consider either primary tendon grafting or the possibility of tendon transfer to provide the missing function if it is essential. Primary tendon grafting should not be performed in a bad wound bed, as the odds of success are small. In these cases, one might also consider placing silastic tendon rods along the course of the tendon requiring reconstruction. Grafts can then be placed in the tracts of the rods. This scenario would most commonly accompany flap coverage, however, and in general cutaneous flaps are a much better bed than muscle for placing tendon grafts. Direct injury to muscles can often be sutured, but with severe injury the damaged muscle will often require debridement. Loss of function from removing muscle can be reconstructed with tendon transfers on occasion but may require free innervated muscle transfer to repair the loss.

Soft-tissue reconstruction

The approach to wounds of the upper extremity should follow the usual parameters of soft-tissue reconstruction, the so-called reconstructive ladder. In complex wounds, however, this concept is being replaced by that of the “reconstructive elevator”, which proposes bypassing simple reconstructions and providing the best functional coverage available (despite the fact that a wound might “get by” with a skin graft.) Many wounds nonetheless can be covered with a split-thickness skin graft or with regional flaps, particularly in the hand. The ultimate morbidity of any local or regional flap must be considered, however, especially in relation to later hand function. Because the hand is highly visible, the cosmetic aspect of certain local and regional flaps must be considered as well. Although certain wounds may be adequately covered with a flap from the same extremity, one should consider what offers the best coverage in terms of the overall reconstruction.²⁷ This will often lead to use of a free flap for many hand and upper limb wounds. The selection of flap coverage for a clean wound allows use of composite tissue in many cases.^{28–30} Whereas

many smaller wounds in the upper extremity are amenable to small local or regional flaps, this discussion centers on the use of major axial-based pedicle or free flaps for the management of larger wounds.

Wounds should be definitively closed as soon as the wound bed is clean. This applies equally to flap coverage as well as simple primary closure. As discussed above, wound debridement is essential to provide control of tissue necrosis and infection. If the status of the tissue is in doubt, serial debridements should be performed to avoid removal of viable tissue and yet assure a well-vascularized wound with minimal bacterial contamination. In patients with vital structures exposed, it is often best to place a muscle flap (usually a free muscle flap), with the plan to return to the operating room every 48 hours. The flap is not definitively sutured down, and is lifted at each subsequent procedure and debridement and irrigation is carried out. Once the muscle flap starts becoming adherent to the underlying tissue and there is a decrease in cloudy fluid under the flap, it is ready for definite inset and coverage with a skin graft (Fig. 12.12). Vacuum-assisted wound closure provides an excellent temporizing measure between debridements,^{31,32} and may be utilized in the upper part of the arm to optimize a wound bed prior to skin grafting. This wound management technique has the advantage of removing edema and exudates from the wound and tends to keep swelling down in our experience. It should be utilized with caution in the hand, however, as extended use can lead to increased scar (in the form of granulations) and a great deal of stiffness. When utilized for a relatively short period of time, however, it can be advantageous.

Types of flaps – cutaneous vs. muscle

Wounds of the hand and upper extremity can be covered by either cutaneous flaps or muscle flaps. Myocutaneous flaps are not utilized as much today as in the past, because surprisingly they are not generally as cosmetic as a simple muscle flap covered with a split-thickness skin graft. Muscle flaps have always been thought of as superior for coverage of untidy and/or infected wounds,²⁹ however fasciocutaneous flaps (at least with inclusion of the well-vascularized fascia) are actually equally applicable to these wounds in terms of the ability to manage infection.³⁰ For hand coverage, we prefer cutaneous flaps whenever possible, as it is usually easier to re-operate through skin and subcutaneous fat than muscle. While the muscle has the advantage that it atrophies over time, there tends to be a fairly severe amount of scarring under a muscle flap, which makes it more difficult to raise for secondary procedures and mitigates against tendon gliding. Thus, in general, we prefer to utilize any of the number of fasciocutaneous flaps when covering the hand. In severe injuries and in the face of a large dead-space needing to be filled, however, muscle is probably superior. There has been a great deal of interest in the so-called “perforator flap” based on septal perforators supplying the skin.³³ In the case of a severe injury to the hand most perforator flaps available in the upper extremity are probably too small to provide adequate coverage. The severity of injury would also likely render many of these flaps unavailable. While the hand and upper extremity affords a large number of local and regional flaps, this chapter will deal primarily with larger flaps and emphasize free tissue transfer for coverage of the hand.





Fig. 12.12 (A) Forearm of young patient 48 hours after replantation at proximal forearm level. Note necrotic-appearing muscle in forearm. (B) View of forearm after debridement. Note exposed vein bypass grafts. (Patient and family refused amputation at this point.) (C) Patient at same surgery after placement of rectus abdominis muscle free flap to cover vessels and bone. (D) View of forearm at time of re-exploration 48 hours after last debridement and flap cover. (E) Nonviable muscle debrided at this surgery. Note rectus muscle flap flipped back to allow debridement and wash-out and nonviable muscle in basin. (F) Forearm at third wash-out, 6 days after injury. There was no further muscle necrosis noted on this exploration, and the muscle flap was becoming adherent to the underlying tissues. (G) Forearm at fourth wash-out, 9 days after injury. The wounds were very clean and the muscle flap was sutured down and a split-thickness skin graft was placed. This patient never developed evidence of sepsis and no infection developed in either the soft tissues or bone, despite severe contamination at the time of injury.

Pedicated flaps – the groin flap

The pedicled groin flap remains one of the workhorses for hand coverage. It provides a very large portion of soft tissue which can cover many large defects in the hand and forearm. This flap was the first axial-pattern flap described, and was the first flap transferred microsurgically. Its use as a free flap has been supplanted by many flaps with better vasculature, but it should be a part of the armamentarium of every hand surgeon. The blood supply is based on the superficial circumflex iliac vessels, which exit the femoral vessels in the groin and run approximately two centimeters below and parallel to the inguinal ligament (Fig. 12.13). This artery can be located with a pencil Doppler and can be mapped out roughly to the level of the anterior superior iliac spine (ASIS). This flap can (and should be) taken out beyond the ASIS to allow the proximal portion to be tubed to allow some shoulder and elbow motion. It can be radically defatted, especially the more distal portion (which will be placed on the hand), and contours very well on the hand. It can be utilized for coverage of the dorsal hand, forearm, first webspace, and has great utility as a first step prior to toe transfer for thumb or digital reconstruction.

The flap is first marked out with the vessel in the center axis of the flap (which we prefer to locate with a Doppler) (Fig. 12.14). Dissection proceeds from lateral to medial. Care should be taken to avoid leaving a great deal of the fat from



Fig. 12.14 Locating the groin flap pedicle (superficial circumflex iliac artery) with a pencil Doppler.




Fig. 12.13 Anatomy of groin flap and superficial inferior epigastric artery (SIEA) flap. Note that superficial circumflex iliac artery runs approximately 2 cm (or two fingerbreadths) below the inguinal ligament. These two flaps can provide coverage of very large wounds of the hand.

the iliac area on the deep surface of the flap, as this will have to be removed regardless. The landmark to look for as dissection proceeds medially is the sartorius, as the artery pierces the fascia of the sartorius at its medial edge. We prefer to incise the fascia at the lateral edge of the muscle and stop the dissection short of the space medial to the muscle, which obviates damage to the vascular pedicle. Once the flap has been dissected up, the donor site is closed. The edges of the donor site *should not be undermined*, as this simply makes the wound larger. Closure is facilitated by bending the hip and placing a pillow under the knee. Once the donor site is closed, the proximal portion of the flap is usually sewn into a tube. The distal flap to be placed on the hand is defatted centripetally, avoiding defatting the central portion too much to avoid damage to the pedicle. Once this is done, the flap is sewn in place in the defect on the hand (Fig. 12.15).

We have not seen a patient pull the flap off the hand once they are fully awake, but it is prudent to either strap the arm down to the torso or put a very large suture between the wrist and the body until the patient is fully awake and on the ward. If the arm is strapped, this should be removed once the patient is cogent as it can lead to swelling and congestion in the hand. In the postoperative period, the patient is instructed how to move the shoulder and elbow through their available range based on the tubed portion of the pedicle. The flap can usually safely be divided at around three weeks, but this is dependent on how well the flap is healed on the hand. If healing has been delayed or there has been a partial dehiscence, division may need to be delayed. The flap can also be “delayed” prior to division, which is accomplished by either making a small incision in the tubed portion and dividing all the deep tissues (i.e., the pedicle) or conversely by incising the tube




Fig. 12.15 (A) Markings on groin of patient for pedicled groin flap. Patient had failed replantation of thumb and flap is to prepare for later toe transfer for thumb reconstruction. (B) Flap elevated. Note size of donor defect after elevation. Be aware that undermining these edges simply makes this defect more difficult to close. (C) Donor site has been closed primarily and flap has been tubed. (D) Flap after placement on hand. (E) Final view after three and a half weeks at time of division and inset of flap.

circumferentially to interrupt the subdermal plexus. Once this has been done, the flap can usually be safely divided in 5–7 days.

At the time of division, the donor site is closed and the flap is gently inset on the hand. Some advocate leaving the tubed portion dangling on the hand to allow for potential demarcation of the flap into viable and nonviable portions. Our experience has been that if the flap is well healed on the hand, the flap can usually be safely trimmed and inset. The patient is begun on a rigorous physical therapy program to regain shoulder and elbow motion, as well as motion in the hand. The pedicled groin flap can usually be contoured (defatted) adequately when first placed on the hand, but on occasion will require secondary procedures to inset and decrease the bulk later. The primary advantage of the pedicled groin flap is that it does not require microsurgical expertise, while the primary disadvantage of this flap is that the hand is placed in a dependent position and may lead to stiffness in the shoulder. One caveat concerning the donor site is that if this area gets infected, is it unwise to remove all the sutures. This will lead to a gigantic wound which can be quite difficult to manage (Fig. 12.16). It is much better to treat this by removing a few



Fig. 12.16 Patient who suffered infection and dehiscence of groin flap donor site after 3 weeks of wound care, prior to placement of split-thickness skin graft. This can be avoided by treating the wound carefully in the postoperative period and avoiding leaving it open.

sutures and irrigating the area under the sutures daily which will rid the area of infection without the morbidity of a massive wound on the hip.

Free flaps – fasciocutaneous flaps

The radial forearm flap

This flap offers almost ideal characteristics for hand reconstruction.³ Its primary application is as a pedicled flap, based on reversed flow through the distal radial artery and venae comitantes.³⁴ It may be elevated on a proximal vascular pedicle to cover wounds in the forearm or about the elbow. Nonetheless, it may be used as a free flap in certain instances and affords excellent hand coverage. This flap can be raised anywhere along the course of the radial artery, and a skin island from very small to quite large may be taken (Fig. 12.17).




Fig. 12.17 Anatomy of radial forearm flap. This flap can be taken anywhere over the radial artery in the forearm, and can include skin, fascia, tendon, and bone.

The radial artery provides a large-caliber vessel for anastomosis and may be used for revascularization of the distal limb if necessary as a “flow-through” free flap. The venous drainage is through the dual concomitant veins of the radial artery; larger flaps can be drained by cutaneous veins. There has been some controversy as to the primary venous drainage of these flaps, but the venae comitantes offer reliable drainage even in the absence of superficial veins. This flap may be innervated by anastomosis of the lateral antebrachial cutaneous nerve, part of which is invariably in the flap. The quality of sensation in such reinnervated flaps is not great, but it may be useful. If the patient has a palmaris longus tendon, it may be taken in the flap as well and offers an excellent option for tendon reconstruction, especially on the dorsal hand. Because the tendon is taken with its surrounding tissue, it has excellent gliding when transferred as part of the flap. A portion of the volar radius may be harvested with the flap as well and is particularly useful in reconstruction of missing segments of metacarpal^{35,36} (Fig. 12.18). The radial artery can be taken with the fascia only, which offers a thin flap that is particularly useful in reconstruction of the palm.

The advantages of this flap as a free flap are its thinness, its reliability (based on the radial artery), and the multitude of other tissues that may be harvested with it. The main disadvantage of this flap is the resulting donor site, which must usually be covered with a skin graft. The donor site is usually aesthetically unpleasing but causes few functional problems. Another relative contraindication to this flap is the loss of the radial artery, but studies have shown that significant problems are unusual. Cold sensitivity is seen but may be related to other factors. Whereas the radial forearm flap is an excellent free flap, it can usually be used as a distally pedicled island flap for hand reconstruction (Fig. 12.19). If this flap is not available for some reason as a pedicled flap, a skin flap is usually selected from another area, and a radial forearm flap is not taken from the contralateral uninjured arm.

Lateral arm free flap

This fasciocutaneous flap from the lateral distal upper arm is based on the posterior radial collateral artery, a branch of the profundus brachii.³⁷ This vessel runs with the radial nerve in the spiral groove and comes to lie in the posterior intermuscular septum between the brachialis and lateral head of the triceps (Fig. 12.20). It gives arterial supply to the skin overlying the septum as well as the underlying humerus (Fig. 12.21). Distal to the intermuscular septum, the posterior radial collateral artery has a rich system of anastomoses with vessels in the proximal lateral forearm, which will allow extension of the flap onto the proximal forearm. This flap can also be based distally for coverage of small to moderate defects of the elbow (Fig. 12.22). The pedicle for this flap is relatively short (5 to 7 cm), and the proximal artery has a small diameter (1.5 to 2 mm) compared with the flaps previously discussed. The length of the pedicle is limited by the fact that it exits the spiral groove with the radial nerve, and damage to this nerve must be avoided in the dissection. Acland and Shatford, in unpublished video demonstrations, have demonstrated a safe and effective method to significantly lengthen the pedicle through an alternative proximal dissection. The skin paddle can be based directly over the intermuscular septum for a smaller flap or extended distally for a larger one. Donor sites up to




Fig. 12.18 Cross-section anatomy of the forearm. The radial forearm flap is based on the radial artery as it runs between the flexor carpi radialis muscle and the brachioradialis muscle. Muscle and/or bone may be harvested with this flap.

7 cm in width can be closed primarily, but larger ones require a skin graft.³⁸ When closed primarily, the donor site can be cosmetic, but the scar will widen significantly in some patients. The posterior cutaneous nerve to the arm may be taken to innervate the flap; the posterior cutaneous nerve to the forearm may be used as a flow-through vascularized nerve graft.³⁹ A portion of the lateral humerus can be taken with the flap for bone reconstruction, based on its vascular supply from the overlying pedicle.⁴⁰ The lateral arm flap is purported to be a “thin” flap, but because of the tissue in the intermuscular septum, it is a bit bulky when placed on a flat recipient site (i.e., the back of the hand). This problem can be avoided by using the fascia only, which also decreases donor site problems.^{38,41} The primary advantages of this flap are that it can be taken from the ipsilateral arm (of injury) (Fig. 12.23), it avoids the sacrifice of a major vessel, it has the potential to serve as a multicomponent composite transplant, and the donor site can often be closed primarily. The primary disadvantages of the lateral arm free flap are its somewhat limited size, the short and small-diameter pedicle, the resultant contour deformity in the arm, and forearm dysesthesias. It is useful in coverage of small defects of the hand and works well in the first webspace (Fig. 12.24). In thin patients, it can be used to cover a degloving injury of the thumb with the added benefit of reinnervation through the cutaneous nerve. It has served nicely as a composite osteocutaneous flap to reconstruct multicomponent defects about the antecubital fossa and elbow.

Scapular flap

The scapular and parascapular flaps offer a versatile large skin flap for coverage of defects in the upper extremity.⁴² The vascular supply is based on the circumflex scapular vessels that branch from the subscapular system.⁴³ The pedicle for this flap is long (4 to 6 cm) because the subscapular vessels can be taken if necessary, and this provides vessels of large diameter at the takeoff from the axillary artery. The vessels lie in the fascia with branches to the overlying skin. There are

two primary branches, giving rise to the “transverse” scapular flap, which is sited transversely across the back, and the “parascapular” flap, which is sited obliquely down the back (Fig. 12.25). Based on this vascular supply, a large skin flap can be designed that will cover most defects of the forearm and arm.⁴⁴ Although a number of cutaneous nerves enter the skin, there is not a dominant nerve to this area, and thus this flap has poor potential for innervations. Branches from the primary pedicle feed the lateral surface of the scapula, and a portion of this bone can be taken to repair bone defects. This bone is flat, however, and its primary indication is reconstruction of smaller defects in the hand. Donor sites in the 8 cm range can usually be closed primarily, but this is usually limited to the parascapular design of the flap.

The primary advantages of this flap are the length and diameter of its pedicle along with its potential large size. The primary disadvantage of this flap is the need for turning the patient to harvest it. The scapular flap is an excellent choice for coverage of large wounds of the forearm and can be used in place of a pedicled groin flap for hand coverage (Fig. 12.26). It can be combined with the latissimus dorsi and serratus anterior muscle flaps on a single pedicle to provide a huge amount of tissue and for coverage of different surfaces of the hand and arm.⁴⁴ Fascia alone can be harvested if back skin and subcutaneous tissue is deemed too bulky for an effective transfer.

Temporoparietal fascia flap

The temporoparietal fascia offers a flap of specialized tissue that has great utility in reconstruction of the hand.²⁰ This flap is supplied by the superficial temporal artery and vein and has a pedicle in the 2- to 3-cm range, which is about 1.5 to 2.5 mm in diameter⁴⁵ (Fig. 12.27). The temporal fascia lies on the temporal region of the skull, beginning on the zygoma and running superiorly. There is a larger superficial layer as well as a deep temporal fascial layer, and both may be taken with this flap. The use of both layers of fascia has been promoted for wrapping adherent tendons on the dorsum of the hand




Fig. 12.19 (A) Degloving injury in 13-year-old boy after automobile roll-over injury. Patient and family refused pedicled groin flap coverage. (B) Outline of distally-based pedicled radial forearm flap for coverage of wound. (C) Flap elevated. Note that the palmaris longus tendon has been harvested in the flap for extensor tendon reconstruction. (D) Flap placed on hand. Note that flap and pedicle will be placed through a subcutaneous tunnel to reach the dorsal hand. (E) Healed flap on dorsal hand. Note color and texture match of flap with hand. (F) Donor site on volar forearm after healing of split-thickness skin graft.




Fig. 12.20 Anatomical depiction of anatomy of lateral arm free flap.




Fig. 12.21 Dissection of lateral arm free flap.

after tenolysis in a scarred bed. The deep fascia can provide tissue for reconstruction of small tendons on the dorsal hand as well. A flap of moderate dimensions may be taken, in the 8- to 10-cm range. The potential for harvesting vascularized bone with this flap exists, but the thin, outer table bone available has little indication in the hand. Although the donor scar is one of the best in terms of cosmesis, the problem of alopecia exists because the superficial fascia must be dissected from just beneath the hair follicles of the scalp.

The primary advantages of this flap include the potential to provide a gliding surface and a donor site that is one of the best in terms of cosmesis. The primary disadvantage of this flap is that it is thin and must be covered with a skin graft. The frontal branch of the facial nerve can be injured in its dissection. Temporoparietal fascia offers nice coverage for defects of the fingers and hand, but the size of the flap is limited.⁴⁶ This tissue does seem to improve the gliding ability of tendons, particularly on the dorsum. When covered with a split-thickness skin graft, the temporoparietal fascia flap offers the thinnest coverage available (excluding other fascial flaps) (Fig. 12.28).

Anterolateral thigh flap

The anterolateral thigh flap is a more recently popularized flap which has application in reconstruction of wounds in the hand. It is based on the descending branch of the lateral femoral circumflex artery in the thigh, and can be taken with a large skin paddle, fascia, and potentially muscle (Fig. 12.29). This flap was originally thought to be a septal perforator type of flap, but it is well-recognized now that most of these flaps are supplied by intramuscular perforators through the vastus lateralis muscle.⁴⁷ Donor sites in the 6–7 cm width range can be closed primarily, but larger flaps will require a skin graft for the donor site. This flap can supply a large amount of tissue for coverage, and the fascia may be useful in reconstruction of tendons (i.e., the distal triceps tendon). It can also be utilized to revascularize the distal extremity as a flow-through flap via the descending branch which also supplies the flap.⁴⁸ When placed on the hand, the flap can be thinned rather radically to obviate a too-bulky piece of tissue.⁵

The flap is designed by marking a line from the anterior superior iliac spine to the lateral border of the patella. This should roughly follow the septum between the rectus femoris and the vastus lateralis. The primary perforators are located roughly half the way down this line. While some design the flap without identifying the perforators,⁴⁹ we prefer to utilize a pencil Doppler to locate the primary perforators along the medial border of the vastus lateralis. Once the central axis of the flap is laid out, the dissection begins by raising the medial aspect of the flap. This is raised over to the intermuscular septum between the rectus femoris and vastus lateralis, which is inspected to see if there are any perforators present. The dissection then proceeds from medial to laterally over the vastus, and great care must be taken to lift the flap very carefully and identify and preserve any and all perforators coming through the muscle and fascia lata into the skin paddle. Once these perforators are identified, the lateral edge of the flap can be incised and the remainder of the flap lifted. The perforators are then carefully dissected out of the muscle down to the level of the descending branch of the lateral femoral circumflex vessels. Once these




Fig. 12.22 (A) Recurrent wound of elbow in paraplegic patient. (B) Markings for distally pedicled lateral arm flap for coverage. Note that distal extent of recurrent radial artery has been located with a pencil Doppler and marked. (C) Flap after elevation. Note distal pedicle at elbow. Vascular clamp is on proximal vessel, note excellent perfusion of flap without evidence of venous congestion. (D) Flap sutured in place. (E) Donor site closed primarily. (F) Flap healed at three months with good coverage.




Fig. 12.23 (A) Avulsion injury on dorsum of 24-year-old patient's hand. (B) Lateral arm flap raised. Note position of pedicle between triceps and brachialis and pedicle on deep surface of fascia of flap. (C) Free flap after being inset on hand. Anastomosis was to radial artery in anatomic snuffbox.

are dissected out, the flap pedicle can be ligated and the flap moved.

The primary indication for the anterolateral thigh flap is in large defects of the forearm and/or hand (Fig. 12.30). As noted above, it can be utilized for distal revascularization as well. The donor site is generally well-tolerated, even if it has to be grafted.⁵⁰ The primary downside of this flap is that it tends to be bulky, particularly in obese patients.

Free flaps – muscle flaps

Latissimus dorsi

The latissimus dorsi muscle is a large muscle of the back and shoulder, and its vascular supply for free transfer is based on the subscapular–thoracodorsal system^{51,52} (see Fig. 12.25). The pedicle is lengthy (8–11 cm) and has a relatively large diameter proximally (up to 6 mm). This is the largest single muscle available for transfer, and its area of coverage can be expanded by including a portion of the serratus anterior muscle by its nourishing branch that arises from the thoracodorsal artery.⁵³ It can be used as an innervated muscle because of the single

thoracodorsal nerve,⁵⁴ but the latissimus is generally used in the upper limb for coverage of large, degloving-type wounds (Fig. 12.31).

The advantages of this muscle are that it has a totally reliable vascular supply and is very large. Its primary disadvantage is that the patient must be turned in the lateral decubitus position for harvest of the muscle. If the contralateral muscle is taken, the patient can be turned on the side and the injured arm can be prepared simultaneously with muscle harvest (assuming that appropriate surgical assistance is available). It can be taken as a musculocutaneous flap or harvested with the entire subscapular axis to include up to two muscles (latissimus and a portion of the serratus anterior), a fasciocutaneous paddle, and vascularized bone; but for most indications in the upper extremity, the muscle only is taken and covered with a split-thickness skin graft. The donor site is easily closed, but seroma formation is a common sequela of this donor site. The functional morbidity from the loss of muscle is minimal in most patients, but its use should be avoided in patients who must adduct the arm strongly (crutch-walkers and paraplegics).





Fig. 12.24 (A) Patient with severe first webspace contracture after crush injury. (B) Flap being raised from posteriorly. Underside of flap showing pedicle at base of septum, note triceps muscle posterior to flap. (C) Flap raised on its pedicle. Arrow points to radial nerve in septum. (D) Flap after suturing in place.




Fig. 12.25 Anatomy of the thoracodorsal/subscapular vascular tree with the flaps (scapular/parascapular/latissimus/serratus anterior) that can be raised on this pedicle.



Fig. 12.26 (A) Patient with amputation and degloving of dorsal hand from rope injury. (B,C) Parascapular free flap utilized for coverage.




Fig. 12.27 Anatomy of the temporoparietal fascia.

Rectus abdominis

The rectus abdominis is a muscle widely used in microsurgery, primarily today as the transverse rectus abdominis muscle flap and perforator variants for breast reconstruction. This muscle is on the anterior abdominal wall and runs from the medial lower ribs to the pubis. It lies in a sheath composed anteriorly of continuations of the external and internal oblique muscle layers. The posterior sheath is a continuation of the transversus abdominis but is quite thin in the lower abdomen (below the linea semicircularis). It is a fairly large muscle and has a reliable vascular pedicle based on the deep inferior epigastric system. The pedicle is fairly long (5 to 7 cm) and the diameter fairly large (2.5 to 3 mm).

The rectus abdominis muscle will cover most defects of the hand and/or forearm,^{55,56} and it will cover large defects of the forearm if most of the muscle is harvested and placed "barber pole" fashion around the arm.⁵⁷ The advantages of this muscle are that it has a reliable vascular pedicle and may be taken with the patient supine. The disadvantage of this muscle is that a hernia can result from its harvest if fascia is taken (for a myocutaneous flap) or if the anterior sheath is weak. For coverage of the upper extremity, this muscle is usually harvested without a skin paddle and covered with a split-thickness skin graft. The muscle can actually be harvested as a pedicled flap and placed on the forearm in rare situations where microsurgery might be difficult or pose other problems (Fig. 12.32).





Fig. 12.28 (A) Degloving injury of dorsal hand. (B) View of temporal vessels within temporal fascia on side of head. Temporal artery is tortuous, vein is anterior and straighter. (C) Healed dorsal hand after flap covered with meshed split-thickness skin graft.

Serratus anterior

This muscle is useful for coverage of smaller hand defects.^{53,58} It consists of nine slips of muscle that connect from ribs at the anterior axillary line to the tip of the scapula. The lower slips are vascularized by a branch coming off the thoracodorsal artery; the upper slips are vascularized by a branch of the lateral thoracic artery. The lower three slips may be taken individually or together as a free muscle flap based on the thoracodorsal pedicle. This dissection is tedious because branches of the long thoracic nerve may be intertwined with the vessels, and damage to the nerve supplying the remaining slips of muscle can lead to winging of the scapula.⁵⁹ The branch to the serratus is usually taken with the proximal thoracodorsal vessels, both for lengthening the pedicle and because of the larger diameter of the proximal vessel. This can give a lengthy pedicle (15 to 17 cm) with a large diameter (3 to 6 mm) (see Fig. 12.25).

The primary advantage of this muscle is its small size and lengthy vascular pedicle. The disadvantages of this muscle are the potential for long thoracic nerve injury and the decubitus position necessary for harvest. This flap can be used for coverage of the dorsal or palmar hand and first web space. It has the potential for innervation through a branch of the long thoracic nerve, but this application would be limited in the upper extremity.

Clinical tips

Flap selection

- Wound factors
 - Is the wound clean or relatively dirty?
 - Will you need to perform further surgery through or under flap?
- Patient factors
 - What donor site morbidity is acceptable to the patient?
 - Soft-tissue reconstruction only vs. composite tissue transfer
- Surgeon factors
 - Which flap(s) are you comfortable with and can you transfer reliably?

Postoperative care

In the immediate postoperative period, the extremity is splinted in an appropriate position to prevent capsuloligamentous shortening and tension on repaired structures.




Fig. 12.29 Anatomy of descending branch of lateral femoral circumflex artery and anterolateral thigh flap. This flap offers one of the largest cutaneous free flaps available, and can be taken with vascularized muscle and/or fascia.

Elevation is necessary to reduce edema and help control pain. The patient's pain and anxiety should be adequately controlled. The ambient temperature should be at least 25°C and adjusted to the patient's body temperature. Hydration should be sufficient to maintain urine output between 80 and 100 mL/hr. Anticoagulant therapy is used by many surgeons. However, the authors are selective in using either heparin or dextran;⁶⁰ aspirin is used daily for 4 to 6 days after surgery. Appropriate antibiotic therapy is continued and later modified according to the culture results.

Flap monitoring is critical. Early recognition of arterial hypoperfusion or venous congestion will occur only in a well-monitored environment, with trained nursing staff. If there is a question about tissue viability, the dressings are released and the entirety of the revascularized tissue is exposed for further assessment of perfusion, congestion, temperature, turgor, and color and Doppler examination. Release of the dressings alone may be sufficient. If viability is still in question after 30 minutes, immediate re-exploration and further assessment may prevent failure of the revascularized tissue.

Early and motivated rehabilitation of the extremity is an important factor in achieving a successful outcome. Early motion reduces edema, adhesions, and scarring. It prevents muscle atrophy and facilitates healing of the soft tissues by remodeling of collagen fibers. The details of the rehabilitation program are determined by the existing injuries and the reconstruction procedure.

Outcomes, prognosis, and complications

Reconstruction of complex hand injuries remains a challenge. The ultimate desired outcome is "normal" function of the hand and upper limb, but this can rarely be obtained. Actual outcome studies in terms of the management of these injuries are very limited, however. Based on the few studies available, the primary determinants of the quality of eventual function are the severity of nerve injury and the need for emergency fasciotomy (which may lead to functional muscle loss).⁶¹ Likewise, it is not surprising that outcomes have been shown to be better in younger patients, both from their ability to recover function and to adapt.⁶² del Pinal has suggested that the initial goal in reconstruction of mutilating hand injuries should be the "acceptable hand", which he defines as a hand with three fingers, near normal length, near normal sensation, and a functional thumb.¹⁴ This would seem to be a reasonable approach in these severe injuries, however it is not always obtainable.

There are many complications that can arise in the management of these injuries, with the early problems centering around infection. As noted above, this can be largely mitigated by early and thorough debridement, with return to the operating room frequently in the early period to re-assess the wound and to perform more debridement of nonviable tissues as necessary.^{63,64} Appropriate antibiotic coverage is helpful, but is not a substitute for debridement. While the principle of "early" coverage in the first days after injury was proposed by Godina and has been the gold standard for nearly 25 years,¹⁷ recent experience with the management of war wounds in the conflicts in the Middle East has proven that wounds can be safely and properly managed in a delayed fashion. These studies have shown that early debridement, followed by wound management with negative pressure therapy can temporize and decrease the infection rate in heavily contaminated wounds. The results of management of patients in this fashion is equivalent to that with early coverage in most instances.⁶⁵⁻⁶⁷ These patients also suffer from the complications (or more properly labeled "sequelae") found in any injury to the hand or upper extremity, including tendon adhesions, poor nerve recovery, bony problems (malunion and/or nonunion), etc. These are managed by the surgeon in standard fashion, but particular problems will be addressed below.

Secondary procedures

Free fibula transfer

Most bone defects in the upper extremity can be managed with standard bone grafts; however, long defects (>6 cm) and



Fig. 12.30 (A) Forearm of patient who suffered severe electrical burn with loss of all volar musculature. Plan is for coverage with free anterolateral thigh flap and placement of tendon rods followed by innervated muscle transfer and tendon grafting. (B) Markings on leg for flap. Hip is to the right and knee to the left in this view. (C) Forearm and hand after placement of tendon rods and pulley reconstruction. (D) View after vascular anastomosis and inset of flap. (E) Hand and forearm after three months prior to innervated gracilis transfer.



Fig. 12.31 (A) View of patient's elbow with wound breakdown after total elbow replacement for traumatic fracture/dislocation. (B) Patient after wound debridement, and pedicled latissimus dorsi for coverage. (C) Close-up of muscle in wound. Note that there is plenty of length to reach beyond the elbow proper.

those associated with recurrent nonunions may be candidates for microvascular bone transfer.⁶⁸ Whereas several flaps are available that can include a portion of vascularized bone (iliac crest, scapula, lateral arm, radial forearm, dorsalis pedis), the fibula osseocutaneous flap offers the best piece of bone for reconstruction of significant defects of the long bones of the upper extremity.^{69,70} Smaller defects, such as those in the hand, can be managed by one of the previously discussed flaps with inclusion of a segment of bone. Larger defects of the radius, ulna, or humerus will usually require a piece of bone such as the fibula^{71,72} (Fig. 12.33). The vascular supply of the free fibula is based on the peroneal vessels of the leg. These vessels run along the deep surface of the fibula from just below the tibio-peroneal trunk to the level of the ankle. Whereas the peroneal vessels provide an endosteal nutrient artery to the medullary canal of the fibula, they also provide rich periosteal blood supply to the cortical surface. The proximal portion of the fibula can be taken for reconstruction of the radiocarpal joint, but this segment of bone gets its primary blood supply from a branch of the anterior tibial artery,⁷¹ which must be taken to ensure viability of this segment. The proximal portion can be

taken with the vascularized epiphysis in children to promote later growth,⁷³ and this application will be discussed further in Chapter 30.

A portion of the skin overlying the fibula can be taken with the bone, and thus compound defects can be managed with this flap. The perforators to the skin run around the posterior aspect of the bone, and thus it is best to include a cuff of muscle along the posterior surface of the bone if a skin paddle is to be included. If a skin paddle is taken, most donor sites will require a skin graft on the overlying muscles. The primary advantage of this donor site is the large amount of bone that can be taken. In adults, a total of up to 24 to 26 cm of bone may be harvested. The fibular head should be left in place at the knee level, and 6 cm of the distal fibula should remain to avoid problems with the ankle. In children, a screw should be placed across the distal fibular-tibial joint to avoid proximal migration of the fibula. The disadvantages of this donor site are few; the pedicle is relatively short (2 to 4 cm) and there is some morbidity from harvesting, but this usually does not present functional problems.



Fig. 12.32 (A) 33-year-old patient after forearm amputation and coverage with latissimus dorsi muscle flap. Hand is supplied by vein grafts as is latissimus flap. (B) View of rectus abdominis muscle being raised proximally as a pedicled flap. (C) Flap after inset on arm. (D) Flap healed at four weeks. (E) View of flap at three months after division.




Fig. 12.33 (A) X-ray of forearm of 15-year-old male after automobile accident with loss of majority of radius through open fracture. (B) X-ray view of arm after external fixation to align bones. (C) X-ray after vascularized free fibula transfer to reconstruct defect of radius. (D) View of X-ray at six months. Note interface between fibula and distal radial remnant. (Patient developed osteomyelitis of distal ulna and required long-term intravenous antibiotics, but functionally had no problems from this.)

Digital reconstruction with toe transfer

Microvascular toe transfer represents one of the pinnacles of reconstructive surgery. The ability to replace in kind a missing digit with a mobile, sensate toe offers the best type of reconstruction available. Although this is a complex microsurgical procedure that should not be undertaken without experience,⁷⁴ it remains the benchmark for thumb and most digital reconstructions (Fig. 12.34). There are a number of variations of toe transfer, and almost any tissue needed for digital reconstruction can be transferred. These range from pulp-only transfers to double second- and third-toe transfers to

reconstruct the metacarpal hand.^{75,76} All great- and second-toe transfers ideally have their vascular basis on the dorsalis pedis–first dorsal metatarsal system. This anatomy is highly variable, however, and a thorough knowledge of this is the basis for safe harvesting of these flaps. The venous drainage is based on dorsal superficial veins of the foot; the deep system that accompanies the arterial supply is usually very small.⁷⁷ The flaps can be innervated by the proper plantar digital nerves to the toe as well as by the deep peroneal nerve that accompanies the dorsalis pedis–dorsal metatarsal vessels. The actual details of all the complexities of digital reconstruction with toe transfer is beyond the scope of this chapter, but




Fig. 12.34 (A) Hand of fireman, who lost fingers due to burn injury, after two second toe transfers for digital reconstruction. (B) Flexion of toes. Note good motion at native metacarpophalangeal joints but rather poor motion of interphalangeal joints of toes.

the reader is referred to several excellent review articles on this subject.⁷⁵⁻⁷⁷ Toe transfer for thumb reconstruction is discussed in detail in Chapter 14.

Innervated muscle transfer

In the case of loss of functional muscle in the forearm, the options for reconstruction of this function are either tendon transfer or innervated microvascular muscle transfer. Although many losses can be adequately reconstructed with standard tendon transfers, patients with significant loss of muscle substance (such as those with Volkmann ischemic contracture) may benefit from reconstruction of function with a microvascular muscle transfer.⁷⁸ The muscles available for this include the gracilis, latissimus dorsi, and rectus femoris. The latissimus dorsi can be used in the forearm as a free functional transfer,⁷⁹ but it is not ideal. It is better suited as a replacement for elbow flexion when biceps function is lost. In this case, a pedicle transfer is perfectly adequate. The rectus femoris has been used for this in the past, but again, it is not the optimal muscle due to its short excursion. The gracilis muscle, on the other hand, is nearly ideal for reconstruction of the muscles of the forearm. It has adequate excursion to provide finger flexion or extension, it is of appropriate size (both length and width), and it has an excellent neurovascular pedicle. The reader is referred to Chapter 35 for the details of this procedure.

Future directions

Reconstruction of severe mangling hand injuries can be very frustrating, particularly if complications are encountered. Loss of replanted or transplanted tissues can lead to increased infection rates, fibrosis, and stiffness. These are all the enemies of the hand surgeon, but there are times when they cannot be avoided and/or adequately treated. Prevention of these

injuries is undoubtedly the best approach, but this goal remains elusive. This is especially true when one considers that despite all of our technology, many industries (drilling for oil and heavy manufacturing come to mind) still rely on the versatility of the human hand to guide the machines. These hands are put in harm's way on a daily basis, and until such activities can be truly completely automated, mangling hand injuries will unfortunately be with us.

Probably the most promising development in the last several years has been the successful transplantation of hands and arms in patients. Most of these individuals have had bilateral amputations or injuries, and some have suffered the loss of their lower limbs as well. Despite early enthusiasm, this area has not grown particularly, and while many centers have set up "hand transplant" programs, few have proceeded. This is undoubtedly due to the relative lack of appropriate donor hands and ongoing concerns about immunosuppression. Despite the protestations of those who have performed hand transplants, the issues involving rejection, infections, and other systemic metabolic conditions related to the immunosuppression remain problematic. Barring a major breakthrough in immunosuppressive regimens to make these drugs less likely to cause side effects, the authors do not see hand transplantation as currently offering the best solution in *most* cases of mangling hand injuries.

Fortunately prosthetic options in the hand are improving, and with approaches including targeted muscle reinnervation and the work being done on allowing prosthetics to have sensory feedback, these may offer better solutions for missing digits and hands in the future. The primary issue with these advanced prosthetics is their cost, and the fact that the more sophisticated the prosthetic, the less able it is to withstand the wear and tear of daily use.

Tissue engineering may hold hope for the future, but engineering all or a portion of a hand (bones, tendons, nerves, soft tissue) from a scaffold of collagen or a 3D printer remains, the authors believe, a far distant hope.



Access the complete reference list online at

<http://www.expertconsult.com>

17. Godina M. Early microsurgical reconstruction of complex trauma of the extremities. *Plast Reconstr Surg*. 1986;78:285-292. *This is the classic paper by Godina on early coverage of severe trauma with free flaps. In this paper he proves the rationale for early coverage.*
18. Gupta A, Shatford RA, Wolff TW, et al. Treatment of the severely injured upper extremity. *J Bone Joint Surg Am*. 2000;81:1628-1651. *This paper from an AAOS instructional course lecture gives a very organized and well-structured overview of the subject from the orthopedic standpoint.*
61. Topel I, Pfister K, Moser A, et al. Clinical outcome and quality of life after upper extremity arterial trauma. *Ann Vasc Surg*. 2009;23:317-323. *This paper from Germany looked at 33 patients with*

arterial trauma with DASH scores at the time of final follow-up. Not surprisingly, they found that nerve and orthopedic trauma had more long-term impact than vascular injury (short of those patients with muscle damage from ischemia).

65. Kumar AR, Grewal NS, Chung TL, Bradley JP. Lessons from the modern battlefield: successful upper extremity injury reconstruction in the subacute period. *J Trauma*. 2009;67:752-757. *This recent paper dealing with injuries in US soldiers from the Middle East wars notes that successful flap reconstruction can be performed in a delayed fashion (contradicting the long-held notions of Godina). Their average time to flap reconstruction was 31 days, with a 4% flap loss rate and 8% infection rate, which are both very acceptable.*

References

- Mithani SK, Srinivasan RC, Kamal R, et al. Salvage of distal radius nonunion with a dorsal spanning distraction plate. *J Hand Surg Am.* 2014;39:981–984.
- Wolf JC, Weil WM, Hanel DP, Trumble TE. A biomechanical comparison of an internal radiocarpal-spanning 2.4-mm locking plate and external fixation in a model of distal radius fractures. *J Hand Surg Am.* 2006;31:1578–1586.
- Soutar DS, Tanner NSB. The radial forearm flap in the management of soft tissue injuries of the hand. *Br J Plast Surg.* 1984;37:18.
- Wang HT, Fletcher JW, Erdmann D, Levin LS. Use of the anterolateral thigh free flap for upper-extremity reconstruction. *J Hand Surg Am.* 2005;30:859–864.
- Adani R, Tarallo L, Marcoccio I, et al. Hand reconstruction using the thin anterolateral thigh flap. *Plast Reconstr Surg.* 2005;116:467–473.
- Rounds K, Buntic R, Brooks D. Artery-vein-artery venous flap for simultaneous soft-tissue repair and radial artery reconstruction: case report. *J Hand Surg Am.* 2011;36:1339–1342.
- Bumbasirevic M, Stevanovic M, Lesic A, Atkinson HD. Current management of the mangled upper extremity. *Int Orthop.* 2012;36:2189–2195.
- Tung TH, Mackinnon SE. Nerve transfers: indications, techniques, and outcomes. *J Hand Surg Am.* 2010;35:332–341.
- Brown JM, Tung TH, Mackinnon SE. Median to radial nerve transfer to restore wrist and finger extension: technical nuances. *Neurosurgery.* 2010;66:75–83.
- Ring D, Jupiter JB. Mangling upper limb injuries in industry. *Injury.* 1999;30:B5–B13.
- Bakker A, Moseley J, Friedrich J. Vehicle factors and outcomes associated with hand-out-window motor vehicle collisions. *J Trauma Acute Care Surg.* 2013;74:687–691.
- Levin LS, Goldner RD, Urbaniak JR, et al. Management of severe musculoskeletal injuries in the upper extremity. *J Orthop Trauma.* 1990;4:432–440.
- Togawa S, Yamami N, Nakayama H, et al. The validity of the mangled extremity severity score in the assessment of upper limb injuries. *J Bone Joint Surg Br.* 2005;87:1516–1519.
- del Piñal F. Severe mutilating injuries to the hand: guidelines for organizing the chaos. *J Plast Reconstr Aesthet Surg.* 2007;60:816–827.
- Chim H, Ng ZY, Carlsen BT, et al. Soft tissue coverage of the upper extremity: an overview. *Hand Clin.* 2014;30:459–473, vi.
- Ninkovic M, Deetjen H, Ohler K, Anderl H. Emergency free tissue transfer for severe upper extremity injuries. *J Hand Surg [Br].* 1995;20:53–58.
- Godina M. Early microsurgical reconstruction of complex trauma of the extremities. *Plast Reconstr Surg.* 1986;78:285–292. *This is the classic paper by Godina on early coverage of severe trauma with free flaps. In this paper he proves the rationale for early coverage.*
- Gupta A, Shatford RA, Wolff TW, et al. Treatment of the severely injured upper extremity. *J Bone Joint Surg Am.* 2000;81:1628–1651. *This paper from an AAOS instructional course lecture gives a very organized and well-structured overview of the subject from the orthopedic standpoint.*
- Tos P, Artiac S, Titolo P, et al. Limits of reconstruction in mangled hands. *Chir Main.* 2010;29:280–282.
- Upton J, Rogers C, Durham-Smith G, Swartz WM. Clinical applications of free temporoparietal flaps in hand reconstruction. *J Hand Surg.* 1986;11:475–483.
- Rozen WM, Ting JW, Gilmour RF, Leong J. The arterialized saphenous venous flow-through flap with dual venous drainage. *Microsurgery.* 2012;32:281–288.
- Bushnell BD, McWilliams AD, Whitener GB, Messer TM. Early clinical experience with collagen nerve tubes in digital nerve repair. *J Hand Surg Am.* 2008;33:1081–1087.
- Wangensteen KJ, Kalliainen LK. Collagen tube conduits in peripheral nerve repair: a retrospective analysis. *Hand (N Y).* 2010;5:273–277.
- Moore AM, Kasukurthi R, Magill CK, et al. Limitations of conduits in peripheral nerve repairs. *Hand (N Y).* 2009;4:180–186.
- Karabekmez FE, Duymaz A, Moran SL. Early clinical outcomes with the use of decellularized nerve allograft for repair of sensory defects within the hand. *Hand (N Y).* 2009;4:245–249.
- Viinikainen A, Goransson H, Ryhanen J. Primary flexor tendon repair techniques. *Scand J Surg.* 2008;97:333–340.
- Upton J, Havlik RJ, Khouri RK. Refinements in hand coverage with microvascular free flaps. *Clin Plast Surg.* 1992;19:841–857.
- Asaadi M, Murray KA, Russell RC, Zook EG. Experimental evaluation of free-tissue transfer to promote healing of infected wounds in dogs. *Ann Plast Surg.* 1986;17:6–12.
- Chang N, Mathes SJ. Comparison of the effect of bacterial inoculation in musculocutaneous and random-pattern flaps. *Plast Reconstr Surg.* 1982;70:1–10.
- Calderon W, Chang N, Mathes SJ. Comparison of the effect of bacterial inoculation in musculocutaneous and fasciocutaneous flaps. *Plast Reconstr Surg.* 1986;77:785–794.
- Hinck D, Franke A, Gatzka F. Use of vacuum-assisted closure negative pressure wound therapy in combat-related injuries—literature review. *Mil Med.* 2010;175:173–181.
- Hunter JE, Teot L, Horch R, Banwell PE. Evidence-based medicine: vacuum-assisted closure in wound care management. *Int Wound J.* 2007;4:256–269.
- Mateev MA, Kuokkanen HO. Reconstruction of soft tissue defects in the extremities with a pedicled perforator flap: series of 25 patients. *J Plast Surg Hand Surg.* 2012;46:32–36.
- Braun FM, Hoang P, Merle M. Technique and indications of the forearm flap in hand surgery. A report of thirty-three cases. *Ann Chir Main.* 1985;4:85–97.
- Yajima H, Tamai S, Yamauchi T, Mizumoto S. Osteocutaneous radial forearm flap for hand reconstruction. *J Hand Surg.* 1999;24:594–603.
- Foucher G, VanGenechten F, Merle M, Michon J. A compound radial artery forearm flap in hand surgery: an original modification of the Chinese forearm flap. *Br J Plast Surg.* 1984;37:139.
- Chen HC, el-Gammal TA. The lateral arm fascial free flap for resurfacing of the hand and fingers. *Plast Reconstr Surg.* 1997;99:454–459.
- Harpf C, Papp C, Ninkovic M, et al. The lateral arm flap: A review of 72 cases and technical refinements. *J Reconstr Microsurg.* 1998;14:39–48.
- Arnez ZM, Kersnic M, Smith RW, Godina M. Free lateral arm osteocutaneous neurosensory flap for thumb reconstruction. *J Hand Surg [Br].* 1991;16:395–399.
- Yousif NJ, Warren R, Matloub HS, Sanger JR. The lateral arm fascial free flap: Its anatomy and use in reconstruction. *Plast Reconstr Surg.* 1990;86:1138–1145.
- Scheke LR, Kleinert HE, Hanel DP. Lateral arm composite tissue transfer to ipsilateral hand defects. *J Hand Surg.* 1987;12:665–672.
- Barwick WJ, Goodking DJ, Serafin D. The free scapular flap. *Plast Reconstr Surg.* 1982;69:779–787.
- Thoma A, Heddle S. The extended free scapular flap. *Br J Plast Surg.* 1990;43:709–712.
- Germann G, Bickert B, Steinau HU, et al. Versatility and reliability of combined flaps of the subscapular system. *Plast Reconstr Surg.* 1999;103:1386–1399.
- Abul-Hassan HS, von Drasek Ascher G, Acland RD. Surgical anatomy and blood supply of the fascial layers of the temporal region. *Plast Reconstr Surg.* 1985;77:17.
- Hing DN, Buncke HJ, Alpert BS. Use of the temporo-parietal fascial free flap. *Plast Reconstr Surg.* 1988;81:534.
- Luo S, Raffoul W, Luo J, et al. Anterolateral thigh flap: A review of 168 cases. *Microsurgery.* 1999;19:232–238.
- Yildirim S, Taylan G, Eker G, Akoz T. Free flap choice for soft tissue reconstruction of the severely damaged upper extremity. *J Reconstr Microsurg.* 2006;22:599–609.
- Lin SJ, Rabie A, Yu P. Designing the anterolateral thigh flap without preoperative Doppler or imaging. *J Reconstr Microsurg.* 2010;26:67–72.

50. Hanasono MM, Skoracki RJ, Yu P. A prospective study of donor-site morbidity after anterolateral thigh fasciocutaneous and myocutaneous free flap harvest in 220 patients. *Plast Reconstr Surg.* 2010;125:209–214.
51. Bailey BN, Godina M. Latissimus dorsi muscle free flaps. *Br J Plast Surg.* 1982;35:47–52.
52. Jones NF, Lister GD. Free skin and composite flaps. In: Green DP, Hotchkiss RN, Pederson WC, eds. *Green's Operative Hand Surgery.* 4th ed. Philadelphia: Churchill Livingstone; 1999:1159–1200.
53. Whitney TM, Buncke HJ, Alpert BS, et al. The serratus anterior free-muscle flap: Experience with 100 consecutive cases. *Plast Reconstr Surg.* 1990;86:481–490.
54. Favero KJ, Wood MB, Meland NB. Transfer of innervated latissimus dorsi free musculocutaneous flap for the restoration of finger flexion. *J Hand Surg.* 1993;18:535–540.
55. Horch RE, Stark GB. The rectus abdominis free flap as an emergency procedure in extensive upper extremity soft-tissue defects. *Plast Reconstr Surg.* 1999;103:1421–1427.
56. Rao VK, Baertsch A. Microvascular reconstruction of the upper extremity with the rectus abdominis muscle. *Microsurgery.* 1994;15:746–750.
57. Press BH, Chiu DT, Cunningham BL. The rectus abdominis muscle in difficult problems of hand soft tissue reconstruction. *Br J Plast Surg.* 1990;43:419–425.
58. Gordon L, Levinsohn DG, Finkemeire C, et al. The serratus anterior free-muscle transplant for reconstruction of the injured hand: An analysis of the donor and recipient sites. *Plast Reconstr Surg.* 1993;92:97–101.
59. Derby LD, Bartlett SP, Low DW. Serratus anterior free-tissue transfer: Harvest-related morbidity in 34 consecutive cases and a review of the literature. *J Reconstr Microsurg.* 1997;13:397–403.
60. Pederson WC. Clinical use of anticoagulants following free tissue transfer surgery. *J Hand Surg Am.* 2008;33:1435–1436.
61. Topel I, Pfister K, Moser A, et al. Clinical outcome and quality of life after upper extremity arterial trauma. *Ann Vasc Surg.* 2009;23:317–323. *This paper from Germany looked at 33 patients with arterial trauma with DASH scores at the time of final follow-up. Not surprisingly, they found that nerve and orthopedic trauma had more long-term impact than vascular injury (short of those patients with muscle damage from ischemia).*
62. Ignatiadis IA, Yiannakopoulos CK, Mavrogenis AF, et al. Severe upper limb injuries with or without neurovascular compromise in children and adolescents—analysis of 32 cases. *Microsurgery.* 2008;28:131–137.
63. Bernstein ML, Chung KC. Early management of the mangled upper extremity. *Injury.* 2007;38:S3–S7.
64. Bowyer G. Debridement of extremity war wounds. *J Am Acad Orthop Surg.* 2006;14:S52–S56.
65. Kumar AR, Grewal NS, Chung TL, Bradley JP. Lessons from the modern battlefield: successful upper extremity injury reconstruction in the subacute period. *J Trauma.* 2009;67:752–757. *This recent paper dealing with injuries in US soldiers from the Middle East wars notes that successful flap reconstruction can be performed in a delayed fashion (contradicting the long-held notions of Godina). Their average time to flap reconstruction was 31 days, with a 4% flap loss rate and 8% infection rate, which are both very acceptable.*
66. Steiert AE, Gohritz A, Schreiber TC, et al. Delayed flap coverage of open extremity fractures after previous vacuum-assisted closure (VAC) therapy – worse or worth? *J Plast Reconstr Aesthet Surg.* 2009;62:675–683.
67. Ficke JR, Pollak AN. Extremity war injuries: development of clinical treatment principles. *J Am Acad Orthop Surg.* 2007;15:590–595.
68. Pederson WC, Person DW. Long bone reconstruction with vascularized bone grafts. *Orthop Clin North Am.* 2007;38:23–35, v.
69. Yajima H, Tamai S, Ono H, et al. Free vascularized fibula grafts in surgery of the upper limb. *J Reconstr Microsurg.* 1999;15:515–521.
70. Gerwin M, Weiland AJ. Vascularized bone grafts to the upper extremity. *Hand Clin.* 1992;8:509–523.
71. Tang CH. Reconstruction of the bones and joints of the upper extremity by vascularized free fibular graft: Report of 46 cases. *J Reconstr Microsurg.* 1992;8:285–292.
72. Chhabra AB, Golish SR, Pannunzio ME, et al. Treatment of chronic nonunions of the humerus with free vascularized fibula transfer: a report of thirteen cases. *J Reconstr Microsurg.* 2009;25:117–124.
73. Innocenti M, Delcroix L, Romano GF, Capanna R. Vascularized epiphyseal transplant. *Orthop Clin North Am.* 2007;38:95–101, vii.
74. Lister GD. Reconstruction of the hand with free microvascular toe-to-hand transfer: experience with 54 toe transfers. *Plast Reconstr Surg.* 1983;71:372.
75. Lutz BS, Wei FC, Chen SH, Lin CH. Functional reconstruction of the metacarpal hand with multiple toe transplantations. *Tech Hand Up Extrem Surg.* 1999;3:37–43.
76. Mardini S, Wei FC. Unilateral and bilateral metacarpal hand injuries: classification and treatment guidelines. *Plast Reconstr Surg.* 2004;113:1756–1759.
77. Wallace CG, Wei FC. Posttraumatic finger reconstruction with microsurgical transplantation of toes. *Hand Clin.* 2007;23:117–128.
78. Manktelow RT, Anastakis DJ. Functioning free muscle transfers. In: Green DP, Hotchkiss RN, Pederson WC, eds. *Operative Hand Surgery.* 4th ed. Philadelphia: Churchill Livingstone; 1999:1201–1220.
79. Park C, Shin KS. Functioning free latissimus dorsi muscle transplantation: Anterogradely positioned usage in reconstruction of extensive forearm defect. *Ann Plast Surg.* 1991;27:87–91.

13

Thumb reconstruction: Non-microsurgical techniques

Nicholas B. Vedder and Jeffrey B. Friedrich

Access video and video lecture content for this chapter online at expertconsult.com



SYNOPSIS

- Thumb reconstruction should aim to restore the cardinal thumb actions: mobility, stability, sensibility, length, and appearance.
- Level of thumb loss is divided into thirds: distal (tip to interphalangeal joint), middle (interphalangeal joint to metacarpal neck), and proximal (metacarpal neck to carpometacarpal joint).
- Distal third reconstruction typically requires only soft-tissue restoration.
- Numerous options exist for middle-third reconstruction, including increasing thumb ray length (metacarpal lengthening, osteoplastic reconstruction) and increasing relative length (phalangization).
- Proximal third reconstruction may be accomplished with pollicization or on-top plasty (pollicization of a damaged index finger). However, microsurgical reconstruction (discussed in Chapter 14) is preferred at this level.

Introduction

- When thumb loss occurs due to trauma, replantation is the best method of reconstruction for many patients. When replantation is not possible, thumb reconstruction is warranted.
- The level of thumb amputation guides the type of reconstruction. Determination of level of loss is based on physical examination and radiographs.
- Any thumb reconstruction method requires input and acceptance by the patient. The reconstruction should be tailored to the patient's personal and professional needs. Because significant rehabilitation may be required, the patient must be a willing participant in both the reconstruction and rehabilitation.
- Functional compensation following distal-third thumb loss is easily achieved; therefore, reconstruction at this level is chiefly soft tissue alone. Techniques such as the neurovascular advancement (Moberg) flap and the

cross-finger flap remain reliable methods for reconstruction at this level.

- For losses in the middle third of the thumb, restoration of length is a priority. This can be done via absolute length restoration with metacarpal lengthening or osteoplastic reconstruction, or via relative length restoration using phalangization of the thumb.
- Proximal third thumb losses are best treated with microsurgical reconstruction. However, in some cases this may not be possible. In these situations, transfer of another finger can provide an excellent thumb replacement. A normal finger (typically the index) can be pollicized to become a thumb. A damaged index finger can also be transferred (on-top plasty) to become a stable post for opposition, pinch, and grip.
- Hand rehabilitation after reconstruction is absolutely necessary, especially following middle- and proximal-third reconstructions. Rehabilitation can last months, but allows the patient to regain motion and strength. For some procedures, such as neurovascular island flaps and digit transfer, sensory re-education is an important part of the rehabilitation.
- This chapter will provide a comprehensive description of non-microsurgical thumb reconstruction, including reconstruction decision-making, technical approaches, and post-reconstruction management.



Access the Historical perspective section online at

<http://www.expertconsult.com>

Basic science/disease process

By far, the most common “disease process” necessitating thumb reconstruction is traumatic injury. The majority of these patients are working-age males. Within the larger trauma classification, thumb injury can be the result of a

Historical perspective

Littler extensively reviewed the history of thumb reconstruction, a field in which he has been a major contributor.¹ Nicoladoni introduced two techniques, namely, osteoplastic reconstruction and toe transfer through the pedicle method.² Guermontprez was among the first to pollicize a finger, a technique subsequently refined by the island principle, attributed to Littler and Gosset.³⁻⁷ A mobile and sensate thumb was obtained, but at the price of sacrificing a finger. Matev originated the technique of progressive lengthening through distraction, maintaining good sensibility and improving length.^{8,9} A major advance was the introduction of microvascular techniques, which led to microvascular free toe-to-hand transfer. First- and second-toe transfers were initially described, followed by refined techniques allowing the surgeon to improve the appearance of the reconstructed thumb while at the same time minimizing donor site morbidity.

variety of different mechanisms. These include sharp cut, avulsion, and crush. There are some mechanisms that have characteristics of more than one injury type. This phenomenon is best illustrated by saw and lawn mower injuries, which have both cutting and crushing components, resulting in a larger zone of injury.

Other insults that can result in thumb loss requiring reconstruction are infections and neoplasms. Because tumors are not acute events, thumb reconstruction planning can be more deliberate, and can even be performed at the time of tumor extirpation.¹⁰

Diagnosis/patient presentation

The diagnosis of thumb trauma is relatively straightforward, as there will be, in most cases, open wounds. It is important to obtain history regarding the mechanism and other details of the traumatic insult, time from injury to presentation, handedness, occupation, pertinent social issues (such as tobacco use), and pertinent medical problems (including problems that can compromise peripheral circulation and/or wound healing). If feasible, replantation of the amputated thumb will generally yield a thumb that is superior in appearance and function to any other type of thumb reconstruction. However, this is sometimes not possible, in which case, other reconstruction methods are employed.

Evaluation of the traumatically injured thumb requires complete evaluation of all tissues of the thumb including integumentary, neural, vascular, and musculoskeletal. The wound(s) on the thumb should be carefully inspected. The integrity of the sensory nerves supplying the thumb is assessed. Assessing any compromise in the circulation to the thumb is crucial, as is assessing the feasibility of arterial and venous reconstruction. Finally, assessment of the integrity of the thumb tendons and skeletal structures is performed. Radiographs are necessary to evaluate thumb skeletal structure.

Evaluation of the thumb following infection is similar to that following trauma. All tissues must be assessed, making particular note of the cutaneous defect requiring reconstruction.

Evaluation of a thumb affected by a tumor will be guided by the tumor itself. Specifically, tumor type and grade will determine the extent of extirpation that will need to be determined prior to reconstruction. This will also determine which procedures will be needed either intraoperatively (sentinel lymph node biopsy, lymphadenectomy) or perioperatively (radiation, chemotherapy).

Patient selection

Because there are many ways to reconstruct a deficient thumb, patients must be educated about the various options so that they may make an informed decision as to which type of reconstruction will serve them best in both the personal and professional settings.

Many thumb injuries occur in the workplace, and these patients will be affected by the injury because their work involves significant hand use. In these patients especially, it is essential to work toward a thumb that has adequate length




Fig. 13.1 Thumb loss classification, divided into thirds. Distal third is from thumb tip to interphalangeal joint. Middle third is interphalangeal joint to metacarpal neck. Proximal third is metacarpal neck to carpometacarpal joint.

for both gripping and pinching, is stable during activities, has reasonable motion, and, importantly, is sensate in order to give tactile feedback during these actions and to prevent recurrent ulceration or injury. That said, adequate length, stability, motion, and sensibility are the end-goals for any patient requiring thumb reconstruction, regardless of profession or vocation.¹¹

In addition to patient input regarding reconstructive methods, the patient must also commit to the reconstructive process. Most of the reconstructive options will result in edema, stiffness, and pain in the near term; therefore, adherence to a supervised hand therapy program is critical to reconstruction success.

As with any type of reconstructive surgery, medical optimization prior to procedure(s) allows superior outcomes. This includes, but is not limited to, tobacco cessation, cardiopulmonary stabilization, and good diabetes control. If the thumb is being reconstructed following cancer extirpation, the physician must ensure adequate local disease control prior to reconstruction, and coordination of the patient's reconstruction with any systemic adjuvant therapies that will be required. Similarly, in patients for whom a thumb is deficient due to infection, infection control prior to reconstruction is paramount.

The most important factor in patient selection is the amount and nature of tissue loss that must be reconstructed. The level of amputation is the easiest way to classify thumb deficiencies, and is listed in thirds¹² (Fig. 13.1). The distal third extends from the interphalangeal joint to the thumb tip. The middle third is the portion between interphalangeal joint and the metacarpal neck, and the proximal third is from metacarpal neck to the carpometacarpal joint. Each amputation level presents unique challenges for patient and physician, and each level can be reconstructed with multiple modalities.

Treatment/surgical technique

Distal third

Thumb distal-third amputations rarely, if ever, require restoration of length, as a thumb amputated through the interphalangeal joint remains very functional.¹² Therefore, the chief goals of thumb tip reconstruction are soft-tissue coverage of

bone and length preservation. When there is no bone exposed at the tip of the thumb, closure can be achieved with either healing by secondary intention or skin grafting. Secondary healing of tip amputations has been shown to result in a stable scar and good two-point discrimination, and is therefore a relatively easy (and usually the preferred) method of achieving coverage.¹³ Secondary healing by wound contracture has the advantage of bringing stable, sensate skin together to close the defect, as opposed to skin grafts, which remain insensate. Defects up to 1.5 cm in diameter with no bone exposure can be effectively treated with dressing changes. Daily dressing changes with petroleum or bismuth-impregnated gauze are relatively easy for patients. Larger defects with a stable base, however, require skin grafting. Full-thickness grafts are usually preferred, as they are more durable and stable, especially in the contact areas subject to pressure and shear. Small full- or split-thickness skin grafts can be harvested from the hypothenar eminence or the volar wrist crease. Larger skin grafts, however, are best harvested from the upper inner arm or groin crease.

When phalangeal bone is exposed at the thumb tip, vascularized coverage is required to preserve length, and there are several flaps that can accomplish these goals. The main criteria for flap selection are defect size and location of soft-tissue loss, specifically if it is volar, dorsal, or at the tip. The V-Y advancement flap described by Atasoy *et al.* provides good coverage of the tip of the distal phalanx when only a very small amount of bone is exposed¹⁴ (Fig. 13.2). The technique involves incising the volar pulp of the thumb in a V shape. Scissors are then used to spread the subcutaneous tissue carefully. The subcutaneous attachments deep to the flap, which provide the neurovascular supply to the flap, are left intact. The flap is then advanced distally to close the defect and the proximal aspect of the V is closed side to side, thereby creating the Y shape of the final scar. In practice, there is limited application for this flap due to the limited advancement that is possible without devascularizing the flap.

The neurovascular volar advancement flap, which goes by the eponym of the Moberg flap, is well suited to cover volar and tip defects of the thumb.¹¹ It is often described as an advancement flap, but in reality, the amount of advancement achieved with the conventional rectangular Moberg flap is limited. Instead, the elevation of the flap allows flexion of the interphalangeal joint of the thumb, thereby allowing the flap to appear to “advance” distally (Fig. 13.3). To elevate the flap,




Fig. 13.2 Thumb tip closure via volar V-Y advancement flap. The flap is perfused by small vessels traversing the subcutaneous tissues immediately deep to the flap.




Fig. 13.3 Moberg thumb volar advancement flap. It is a sensate flap by virtue of the digital nerves remaining in the flap, and is perfused by the digital vessels.

one incises the mid-lateral lines on either side of the thumb, down to the base of the proximal phalanx. The flap is then elevated from the deeper tissues, directly off the flexor retinaculum, with sharp dissection. The flap includes both neurovascular bundles and all of the subcutaneous tissue down to the flexor tendon sheath. The interphalangeal joint is flexed, and the flap is inset at the tip. If necessary, a Kirschner wire can be placed across the interphalangeal joint to stabilize it, though this is seldom required. This flap can easily cover a defect of 1–2 cm² (Fig. 13.4). A variation of the Moberg flap is an island flap in which the flap is incised transversely across the proximal base, and the only remaining attachments are the two neurovascular bundles. The proximal gap at the base of the flap will then require a small skin graft. Alternatively, the proximal incision can be in the shape of a V, and following advancement, this can be closed in a Y, obviating the need for a donor site skin graft. Unlike the conventional Moberg flap, this method will allow a small amount of actual advancement, thereby covering more distal defects.^{15,16}

The cross-finger flap from the index finger is an excellent reconstructive technique for larger volar and tip defects of the thumb, up to 2–3 cm².¹⁷ The tissue transferred is reliable and durable.¹⁸ The chief disadvantages to this technique are iatrogenic syndactyly for 2–3 weeks, and the need for a skin graft on the index donor site. A radially based rectangular flap is marked on the dorsum of the index proximal phalanx that extends from the ulnar to the radial mid-lateral lines (Fig. 13.5). The flap is incised and elevated from ulnar to radial in the plane between the subcutaneous tissues and the extensor mechanism. It is critically important to leave the paratenon on the extensor to allow skin grafting. Upon reaching the radial aspect of the flap, one must release Cleland's ligaments along the length of the base of the flap to prevent kinking at the flap “hinge”. The flap is then sutured to the thumb – this may require some trial and error to find the best flap orientation (Fig. 13.6). A full-thickness skin graft is then sutured to the dorsum of the index finger. A bulky thumb splint is



Fig. 13.4 Thumb reconstructed with a Moberg flap for a distal amputation. Note the flexed posture of the interphalangeal joint.



Fig. 13.6 Thumb tip defect resurfaced with a cross-finger flap from the index finger.




Fig. 13.5 Diagrammatic representation of the cross-finger flap to the thumb. The flap is elevated from the dorsum of the index finger proximal phalanx and inset to the thumb volar defect. Once elevated, Cleland's ligament of the index radial neurovascular bundle can restrain and kink the flap, therefore release of this ligament allows greater flap freedom.

applied. At 2 or 3 weeks, the flap is divided and the inset to the thumb is completed (**Fig. 13.7**). After division, aggressive range-of-motion therapy for both the thumb and index finger should begin.

The neurovascular island flap attributed to Littler is a valuable tool in thumb reconstruction.¹⁹ It is rarely used as a primary coverage flap, although it is certainly possible to use it in that manner. Rather, its most common use is for the restoration of sensation to the thumb pulp following reconstruction.^{19,20} The flap is based on the ulnar neurovascular bundle of either the middle or ring finger (**Fig. 13.8**). The ulnar side of the digit is chosen because its loss will have minimal effect on grip and pinch activities. The dimensions of the flap



Fig. 13.7 Reconstructed thumb following division of the cross-finger flap seen in **Fig. 13.6**.




Fig. 13.8 Depiction of neurovascular island flap taken from ulnar side of ring finger. The flap will then be tunneled through the palm to the thumb to provide sensate reconstruction of volar thumb.

needed are marked on the ulnar pulp of the chosen donor finger. Often, the flap will require harvesting of skin over the distal and middle phalanges of the donor finger. The flap is incised, and a mid-lateral incision proceeding from the proximal aspect of the flap is made. The flap is elevated from distal to proximal, and the entire ulnar neurovascular bundle is elevated in continuity with the flap. It is critical to raise the neurovascular bundle with a fairly thick cuff of surrounding fatty tissue containing the vasa vasorum of the artery, as that is the only source of venous outflow for the flap. Failure to do this will result in flap congestion. One must dissect fairly proximally in the palm to allow adequate transposition to the thumb, and the other branch of the common digital artery (i.e., the radial digital artery to the ring or small finger) must be divided. The common digital nerve can be split along the fascicles to allow adequate flap mobility. The flap can then be transposed to the thumb either via subcutaneous tunnel, or a connecting incision from the donor site to the thumb can be made (Fig. 13.9). The flap is then inset into the volar defect of the thumb. The donor site is grafted with full-thickness skin. In addition to postoperative restoration of motion, patients must work with a hand therapist on sensory re-education of the thumb.

The proximally based first dorsal metacarpal artery (FDMA) flap is an excellent tool to achieve thumb coverage, although it is better suited for dorsal or lateral thumb defects than palmar defects^{21,22} (Figs. 13.10–13.12 and Video 13.2 ►). Its harvest causes virtually no donor site functional loss. The FDMA is found using a conventional Doppler device, beginning proximally with the radial artery at the anatomic snuff-box. The radial artery then branches into the princeps pollicis



Fig. 13.9 Neurovascular island flap following dissection.

artery radially and the FDMA ulnarly. At approximately the metacarpal head level, the artery then becomes difficult to trace further distal. The flap is then centered over the FDMA (Fig. 13.13). The flap is incised and dissected from distal to proximal, leaving paratenon over the extensor mechanism for later skin grafting. To ensure inclusion of the FDMA with the flap, it is imperative to incise the thin fascia over the first dorsal interosseous muscle and include it with the flap. Once the flap is elevated and the proximal vascular leash fully mobilized, it can then be tunneled to the thumb in the subcutaneous plane, or a connecting incision can be made. The donor defect is then closed with a skin graft. It is critical to raise the vascular pedicle of the FDMA flap with a fairly thick pedicle of surrounding fatty tissue containing the venae comitantes of the artery, as that is the only source of venous outflow for the flap. It is possible to innervate the FDMA flap by suturing a branch of the radial sensory nerve in the flap to a digital or radial sensory nerve in the thumb (Box 13.1).

Middle third

Loss in the middle third of the thumb is more functionally limiting than that of the distal third. Therefore, the priorities are both soft-tissue coverage and functional restoration.

BOX 13.1 Clinical tips: distal-third reconstruction

Loss of the distal third of the thumb is minimal in terms of functional loss.¹² Therefore, the chief priority is soft-tissue coverage. The choice of soft-tissue reconstruction is determined by the location of loss. Volar defects can be reconstructed with secondary healing (wound contraction), full-thickness skin grafts, Moberg flaps, cross-finger flaps, and neurovascular island flaps, while dorsal defects may be dealt with using skin grafts or first dorsal metacarpal artery flaps.



Fig. 13.10 Dorsal ulnar thumb squamous cell carcinoma. The neoplasm was resected and reconstructed in one stage.

Commonly, the soft-tissue coverage of amputations at this level will have been achieved acutely by revision amputation in which the skeletal components are shortened to allow primary closure. Reconstruction then occurs weeks or months after the initial insult.

Phalangization is a set of reconstruction techniques that increases the effective, rather than the absolute, length of the thumb. The chief component of phalangization is first webspace deepening.¹² The webspace may be injured or not injured during the initial injury to the thumb. Webspace deepening allows better thumb excursion, specifically both palmar and radial abduction, thereby improving the thumb's oppositional function. First webspaces with mild or moderate tightness can be deepened with skin grafts or local tissue rearrangement (commonly Z-plasties). The main assessment of the webspace is whether the contracture is broad or is a discrete linear band. If it is broad, then scar contracture incision, followed by skin grafting, is warranted, whereas if the contracture is linear, Z-plasties are the preferred treatment. Full-thickness skin grafts are usually used for the first web, although a thick split-thickness skin graft can be used (Figs. 13.14 & 13.15). A single Z-plasty can be used for a linear scar

band, although two combined Z-plasties are uniquely suited to this anatomic area. The four-flap Z-plasty (which is essentially two superimposed Z-plasties) (Fig. 13.16) and the double-opposing Z-plasty ("jumping man" flap) (Fig. 13.17) have been commonly used for the first web. In both cases, the scar band itself is the middle limb of both Zs, and the triangular flaps then are mobilized from the dorsal and volar sides of the scar contracture. When using either skin graft or Z-plasty for the first webspace, the adductor muscle is often tight due to scarring. A portion of it can be released to allow further thumb abduction prior to skin closure.

More significant first webspace contractures can require transposition of vascularized tissue into the space, rather than the less-complex local tissue rearrangement. Along with soft-tissue expansion of the first web, one should consider application of a first webspace external fixator or pinning of the thumb carpometacarpal joint in order to maintain the width of the first webspace while the reconstruction is healing.

The dorsal hand flap provides a good option for webspace deepening. This flap is proximally based on the dorsum of the hand and is vascularized by the metacarpal artery system (Fig. 13.18). Unlike the FDMA flap, it is not an island flap, and can include more than one metacarpal artery. The flap's distal extent is at the level of the metacarpal heads and is elevated in the plane between subcutaneous tissue and extensor tendon paratenon. The flap is then transposed radially into the first



Fig. 13.11 Thumb defect from Fig. 13.10, and the first dorsal metacarpal artery flap raised on its pedicle. Note that all tissues down to and including the first dorsal interosseous fascia are taken with the flap pedicle.




Fig. 13.12 (A,B) Healed thumb from Figs. 13.10 and 13.11 following reconstruction with proximally-based FDMA flap.

webspace, following release of all constraining structures in the space. The donor site is then skin-grafted.

If the dorsal hand skin has been injured, or if a larger amount of vascularized tissue is required to resurface both the first web and the thumb itself, then regional flaps will be necessary. The radial forearm flap and the posterior interosseous artery flap are good choices. The utility of the radial forearm flap has been repeatedly demonstrated

in a variety of hand reconstruction settings, including the thumb. The major drawback to use of a reverse-flow radial forearm flap is that its use may compromise future thumb reconstruction. Specifically, if a microvascular toe transfer is being considered for thumb reconstruction, the radial artery is the preferred recipient vessel, and the transposition of a pedicled radial forearm flap will make later microvascular transfer difficult, if not impossible. It is, however, possible to




Fig. 13.13 Diagram of dorsal metacarpal artery flap ("kite flap") from index-finger dorsum. It is important to include subcutaneous fat and interosseous muscle fascia with the pedicle.

harvest a radial artery perforator flap, leaving the radial artery intact.^{23,24}

The radial forearm flap is extremity versatile, and can be harvested as a fascia-alone flap, fasciocutaneous flap, or a suprafascial skin flap. For thumb reconstruction, the use of the fascia-alone flap with skin grafts applied directly to the flap allows maintenance of the normal contour of the thumb²⁵ (Figs. 13.19 & 13.20). An Allen's test is always performed to ensure the digits will remain perfused by the ulnar artery. The pivot point of the flap pedicle is approximately at the radial styloid, although it can be more proximal than this. The flap should then be drawn on the forearm such that the pivot point



Fig. 13.15 First webspace from Fig. 13.14 that has been deepened with a full-thickness skin graft. Note improved thumb abduction.



Fig. 13.14 Severe wood chipper injury that later resulted in a first webspace contracture that prevented radial and palmar thumb abduction.

is midway between the distal end of the thumb or first web defect and the proximal end of the radial forearm flap. The flap is elevated on the radial and ulnar sides. Upon reaching the ulnar edge of the brachioradialis muscle on the radial side of the flap, and the radial edge of the flexor carpi radialis tendon on the ulnar side of the flap, dissection then proceeds directly down toward the radius. The dissection then proceeds




Fig. 13.16 Depiction of four-flap Z-plasty used for deepening the first webspace and/or releasing a first webspace contracture.




Fig. 13.17 Diagram of the double-opposing Z-plasty (known as the “jumping man” flap). This Z-plasty and the four-flap Z-plasty provide similar substantial amounts of first webspace release.



Fig. 13.19 Severe dorsal thumb injury from a router. The fractures were stabilized, and the extensor pollicis longus tendon was reconstructed with a transferred extensor indicis proprius tendon.




Fig. 13.18 (A,B) Diagram of the dorsal hand flap. This flap can provide a substantial amount of coverage for first webspace deepening.

under the deep aspect of the radial vascular bundle. Prior to dividing the proximal end of the radial artery, a microvascular clamp can be placed on the artery just proximal to the flap, and the tourniquet released. After several seconds, if both the flap and all the digits are well perfused, the proximal radial artery can then be divided. The flap is then transposed distally to the first webspace and/or thumb. Depending on the type of flap used, the donor site is primarily closed (fascia-alone flap) or skin-grafted (fasciocutaneous or suprafascial). Because venous outflow from the reverse radial artery flap is retrograde through the venae comitantes against the venous valves, venous congestion can occur. It is imperative to include the venae comitantes and surrounding fatty tissue with the arterial pedicle when raising the flap. Performing an ante-grade venous microvascular anastomosis to a vein in the hand can reduce venous congestion and flap swelling.

The vascular supply to the posterior interosseous artery flap is both an advantage and a disadvantage: the flap is perfused by reverse flow-through in the posterior interosseous artery via anastomotic connections with the anterior interosseous artery just proximal to the distal radioulnar joint²⁶ (Figs. 13.21–13.23). This allows preservation of the radial and ulnar arteries to the hand, but the vascular supply can be compromised if the zone of injury is anywhere near the wrist. The posterior interosseous artery is found with a Doppler and the flap centered over it. The vessel is along a line drawn between the lateral epicondyle of the elbow and the ulnar head. The pedicle of the flap runs in the diminutive septum between the extensor carpi ulnaris and extensor digiti minimi (quinti) tendons. Dissection is performed from distal to proximal so as first to locate the anastomotic connection with the anterior interosseous artery and then include the



Fig. 13.20 Thumb from [Fig. 13.19](#) satisfactorily reconstructed with a pedicled radial forearm fascia flap. The flap was skin-grafted and the donor site closed primarily as no skin was harvested from the forearm.

posterior interosseous artery with the flap as one dissects proximally. Once fully dissected, the flap is transposed to the first webspace, and the donor site is closed primarily or skin grafted. Another disadvantage of the flap is the appearance of the donor site, which is on the easily visible dorsal forearm.

Metacarpal lengthening allows increase in the absolute length of the thumb ray. This is usually performed for more proximal losses in the middle third of the thumb, and was popularized by Matev.^{8,9} Matev reported that the only absolute contraindication to the procedure is less than 3 cm of remaining thumb metacarpal.²⁷ One should note that this reconstruction technique requires a long period of time with external fixation, and multiple outpatient visits, therefore patient acceptance of the technique should be established prior to reconstruction. The pins for the distraction device are placed




Fig. 13.21 Large first webspace defect following firework blast injury. An external fixator holds the space open.

distally and proximally prior to osteotomy ([Fig. 13.24](#)). Through a dorsal incision over the metacarpal, the distraction device is applied first, and the bone is then cut at the diaphysis and the skin closed. Distraction is initiated at 1 mm/day until the desired length is achieved. While some patients, especially children, will spontaneously ossify the bony gap of the metacarpal, many patients will require bone grafting at a second surgery. This bone can be harvested from the iliac crest, or with small defects, from the distal radius. While the bone graft is consolidating, the original frame may be left in place, or one may change to internal fixation. In Matev's experience, a number of patients had first webspace creep due to the distraction drawing the first web skin distally.²⁷ If this occurs, one of the first web deepening techniques described previously may be used ([Box 13.2](#)).



Fig. 13.22 Posterior interosseous artery flap elevated and attached only to the pedicle proximally and distally. Note the anastomotic vessels distally curving radially to join the anterior interosseous vessels.



Fig. 13.23 Healed first webspace of patient from Figs. 13.21 and 13.22.

Osteoplastic thumb reconstruction allows restoration of good thumb length, and when combined with a neurovascular island flap, can result in fairly good thumb pulp sensation. While not absolute prerequisites, the osteoplastic thumb reconstruction method works best when there is intact and functioning thenar musculature and a working thumb carpometacarpal joint. It is generally accepted that osteoplastic thumb reconstruction is performed in three stages: (1) skeletal reconstruction with iliac crest bone graft wrapped with a flap (typically a groin flap); (2) groin flap division and serial thinning; and (3) pulp reconstruction with a neurovascular island flap.

The groin flap is a versatile and reliable flap.²⁸ It is an axial flap, perfused by the superficial circumflex iliac artery, which runs parallel to and 2 cm below the inguinal ligament. The flap is centered over this line. It is incised and elevated from lateral to medial just superficial to the muscle fascia. Upon reaching the lateral border of the sartorius, the sartorius




Fig. 13.24 Thumb metacarpal lengthening as described by Matev.

BOX 13.2 Clinical tips: thumb metacarpal lengthening

Metacarpal lengthening of the thumb is a good procedure and can achieve meaningful restoration of thumb length in patients who are not able or willing to undergo a toe transfer. However, it is an arduous process, most importantly for the patient.

1. Patient education is paramount. They must understand that the process involves at least two surgeries, multiple clinic visits, and a real potential for complications such as pin infection or distractor loosening.
2. Pain is not a trivial issue with this procedure. Patients are in near-constant pain from the stretching of the soft tissues. Practitioners must be prepared to manage pain for a number of weeks.
3. Younger patients may ossify the bone gap, but older adults may require iliac crest bone grafting. This bone grafting procedure is a good time to place internal fixation. The internal fixation should be strong enough to prevent flexion of the lengthened metacarpal that often happens with these cases.

muscle fascia is incised and elevated with the flap to prevent kinking of the pedicle. Typically, dissection to the medial border of the sartorius is sufficient length for a thumb groin flap. The proximal end of the flap is tubed upon itself. At this point, an iliac crest tricortical bone graft may be harvested from the lateral aspect of the groin flap incision. An oscillating saw allows rapid and neat harvest of the bone graft. The bone graft is then fixed to the distal end of the thumb stump (either proximal phalanx base or distal metacarpal). Fixation can be provided in a variety of ways; however, plate and screw fixation allows early motion (Fig. 13.25). Following bone graft fixation, the groin flap is then wrapped around the graft and inset to the thumb. The groin flap is usually divided 2–3 weeks after inset. Several stages of flap thinning are usually




Fig. 13.25 Iliac crest bone graft used for osteoplastic reconstruction of a thumb. The fixation of the bone graft is in progress, and will be covered by a groin flap.




Fig. 13.26 Osteoplastic reconstruction from Fig. 13.25 following thinning of the groin flap.

required (Fig. 13.26 and Video 13.1). At approximately 3–6 months after skeletal and soft-tissue reconstruction, sensibility is achieved by transfer of the neurovascular island flap. The chief disadvantages of the osteoplastic reconstruction technique for the thumb are possible bone graft resorption, the multiple stages required, and the bulky appearance of the reconstructed thumb.

Osteoplastic thumb reconstruction is not necessarily performed only with the groin flap.²⁹ There are other flaps that can be used to cover a bone graft, most notably the reversed radial forearm flap. The other option with this type of reconstruction is to utilize an osteocutaneous radial forearm flap, rather than an iliac crest bone graft for the skeletal restoration. The flap may also be innervated by harvesting the lateral antebrachial cutaneous nerve with it, and then coapting it to the ulnar digital nerve of the thumb. While some authors tout this as a one-stage osteoplastic reconstruction, the flap often requires at least some debulking as it can be somewhat bulbous on the thumb.

Quite often, thumb amputations do not happen in isolation – there is often damage to other finger(s), especially the index finger. In the ultimate example of “spare-parts” surgery, the damaged/amputated index finger stump can be transferred on to the thumb amputation stump. This is an excellent reconstructive option for patients with a middle-third amputation of the thumb, especially at the proximal end of that zone.^{12,30} The index transfer procedure has been variably referred to as “pollicization” and “on-top plasty”. On-top plasty is probably more accurate as pollicization is most often used to denote transfer of a normally functioning index to the thumb. On-top plasty does not necessarily need to be accomplished with the index stump – the middle- or ring-finger stump may instead be used.

On-top plasty may be accomplished with a variety of skin incisions; however “racket”-type incisions at the base of the

index and the end of the thumb stump are usually made. Perhaps the most important part of the surgery is the dissection of the dorsal veins. At least one vein must be preserved, but when possible, it is recommended that the majority of the dorsal vein arcade be taken with the digit. Volarly, both neurovascular bundles to the index are carefully dissected. Either before or after index dissection, the thumb is prepared for receipt of the transferred digit. This consists of soft-tissue elevation and metacarpal exposure for bone fixation. Internal fixation is preferred because it does not need to be removed, and early motion can be performed. At this time, a microvascular clamp is placed on the ulnar digital artery to the index, and the tourniquet released. If the index stump is perfused, then the ulnar digital artery is divided. Alternatively, the radial digital artery to the middle finger can be divided, and the common digital artery taken with the index. The ulnar digital nerve will need to be separated from the common digital nerve to allow transposition. As this is a damaged index stump, the flexor and extensor mechanisms are not usually transferred (in contrast to pollicization), and can be divided. The second metacarpal is cut at the appropriate length for the thumb reconstruction. The remainder of the second metacarpal (down to proximal metaphyseal flare) is removed to allow a full first webspace. Fixation of the index metacarpal neck to the thumb metacarpal shaft or base is then performed. In order to gain webspace closure and ensure an adequately deep webspace, a dorsal hand flap may need to be transferred to the webspace (Box 13.3).

Proximal third

Loss of the thumb at the level of the proximal third is a challenge for reconstruction, as this is essentially total thumb loss. While the divisions between middle-third and proximal-third loss are somewhat arbitrary, one chief difference is that loss at the proximal third can include loss of some or the entire cuff of thenar musculature. This muscle loss then precludes use of previously mentioned techniques such as osteoplastic reconstruction, distraction osteogenesis, and perhaps on-top plasty. Because of the paucity of local reconstruction options,

BOX 13.3 Clinical tips: middle-third reconstruction

For thumb losses in the middle third, length restoration becomes a primary goal. This is done by extending either the absolute length or the relative length of the thumb:

- Relative length (“phalangization”): restoring or deepening the first webspace. This may be accomplished as follows:
 - Small webspace deepening: either skin grafting or Z-plasties. If the patient has a linear scar band, Z-plasties; skin grafting is required for broader scar contractures
 - Large webspace deepening: vascularized tissue imported from another location, achieved by the dorsal hand flap, radial forearm flap, or posterior interosseous artery flap
- Absolute length: several techniques can increase absolute length of the thumb:
 - Metacarpal lengthening
 - Osteoplastic reconstruction: bone graft wrapped with a flap, most commonly the groin flap
 - On-top plasty: transposition of a damaged index finger on to the remaining thumb ray

microvascular techniques play a primary role in thumb reconstruction at this level. This primarily is performed with various types of toe transfer, and these techniques are detailed in a separate chapter.

There are some instances of proximal-third loss in which on-top plasty may be appropriate. As stated, if some or all of the thenar musculature is missing, mobility of the transferred index will be limited, and may need to be augmented by an opposition transfer at a later time. In the adult, this opposition transfer can be accomplished with either the ring-finger flexor digitorum superficialis tendon, or the extensor indicis proprius tendon. The technique of on-top plasty is performed the same way as discussed in the section on middle-third loss.

Short of microvascular techniques, index-finger pollicization is the only other viable technique for proximal-third thumb reconstruction (Figs. 13.27 & 13.28). The procedure's utility in children with thumb hypoplasia or aplasia is undisputed. Its use in adults is also fairly reliable, although it may be more difficult for adults than children to adapt to the new finger position. In Brunelli and Brunelli's description of pollicization in adults, the authors highlight one of the chief differences in pollicization between children and adults: in children, the thenar musculature and the adductor pollicis are entirely missing, whereas in adults, there may be at least a remnant.³¹ This then slightly changes what is done with the index palmar interosseous (becomes the adductor pollicis) and the dorsal interosseous (becomes the thenar muscles). In children, these muscles are transferred with the index, whereas in adults, the muscles themselves are eliminated and their tendons sutured to the thenar and adductor remnants.

A variety of skin incision patterns can be used. Once the skin is incised, the dorsal veins are carefully dissected. Vein preservation is critically important, and is often the most tedious portion of the pollicization surgery. Next, the neurovascular bundles to the index are dissected. The palmar and dorsal



Fig. 13.28 Pollicization from Fig. 13.27 demonstrating good opposition of the pollicized finger and good tip pinch.

interosseous tendons are divided from the muscles. The flexor and extensor tendons are dissected after opening the first and second annular pulleys. The thumb is then prepared by dissection of the soft tissue and exposure of the metacarpal remnant. The thenar and adductor pollicis muscles or their remnants are also prepared. At this point, the tourniquet is released. There are two possibilities for the ulnar digital artery of the index finger: it can be divided if the radial digital artery adequately perfuses the finger, or the radial digital artery to the middle finger can be divided and the common digital artery to the second webspace can be taken with the index finger. The second metacarpal is then cut at the neck. The remainder of the second metacarpal down to the metaphyseal flare is removed to open the new webspace. The index is transferred and rotated.

In general, the pulp of the new thumb should be facing the ring finger when bony fixation is completed. The tendon of the first dorsal interosseous muscle is sutured to the thenar muscle remnant (opponens pollicis if possible) and the tendon of the palmar interosseous muscle is sutured to the adductor pollicis muscle or its remnant. Some authors recommend no shortening of the extrinsic extensor and flexor tendons, whereas others advocate tendon plication.^{12,31} The metacarpophalangeal joint is pinned for 6 weeks in slight flexion to counteract the tendency of the index metacarpophalangeal joint to hyperextend. The skin is then closed. If any of the skin closure appears tight, one should have a low threshold for placement of skin grafts to complete the closure. As with on-top plasty, the thenar musculature may be later found to be inadequate for functional opposition, and in these cases, opposition transfer (ring-finger flexor digitorum superficialis or extensor indicis proprius) can be performed at a later time (Box 13.4). Some authors have reported using a digit other than the index finger for pollicization, including one group who has studied transposition of the small finger into the thumb position.³²

Prosthetics

Prosthetics for thumb loss are a viable option for patients who do not wish to undergo reconstruction. Prosthetics are generally aesthetic in nature, which is to say they have minimal or no function. Pillet has the largest experience with upper extremity prosthetics, and his aesthetic results are impressive.³³ There are scattered reports of osseointegrated digital



Fig. 13.27 Completed index-finger pollicization following traumatic thumb loss at the base of the thumb ray.

BOX 13.4 Clinical tips: proximal-third reconstruction

Losses in the proximal third of the thumb are not adaptable, and are challenging reconstructions for patient and surgeon. The entire thumb ray requires restoration. Microsurgical methods are now the standard for losses at this level. However, there remains a role for pollicization of the index finger, which can still be very functional. In cases where there is a concomitant damaged index finger, one can transpose the remaining index on to the thumb ray (on-top plasty) to restore a stable, mobile, and perhaps sensate thumb ray.

and thumb prosthetics, which would render them slightly more functional and durable.³⁴ In general, there must be at least a remnant of thumb proximal phalanx for an aesthetic prosthetic to remain on the thumb.¹² Otherwise, a hand-based extension may be required for prosthesis stabilization.

Postoperative care

Immobilization is the cornerstone of any hand postoperative care, and the thumb is no exception. Generally, distal-third thumb reconstruction is soft tissue alone and, therefore, immobilization in a postoperative plaster splint is only done for approximately a week. After that, the thumb can be supported with a removable splint, and normal showering and hand washing can begin. Sutures are removed at 2 weeks postoperatively.

More proximal reconstructions can involve skeletal reconstruction, in addition to soft tissue. Plate and screw fixation allows early mobilization, typically initiated at 1–2 weeks postoperatively. Kirschner wire fixation can be slightly less rigid; however, at least some passive gliding exercises can still be initiated at 2 weeks. Again, removable splinting allows hand washing and bathing.

At approximately 6 weeks, bony consolidation will have proceeded to the point that some resistive exercises can be started (provided that on radiographs the fixation has remained stable and there is at least some evidence of consolidation). It is also at this point that scar modification techniques can usually begin in earnest.

Outcomes, prognosis, and complications

Unfortunately, there is a scarcity of well-controlled outcomes studies related to the various types of thumb reconstruction.³⁵ There are, however, a number of large retrospective series for each of the above-listed reconstruction methods that, in general, demonstrate good results.^{11,14–16,19,27,29}

There are five goals when reconstructing a thumb: restoration of (1) functional length; (2) stability; (3) mobility (especially opposition); (4) sensibility; and (5) aesthetic appearance. The treating physician should help the patient choose the technique that will allow restoration of (hopefully) all five of these aspects to the thumb. If all five are restored, then the prognosis for a functional thumb and a satisfied patient is

good. If all five cannot be restored, then, at the least, restoration of a stable thumb with adequate length will allow some grip and pinch activities.

Secondary procedures

First webspace deepening is frequently required after thumb trauma and possibly after prior reconstructive procedures. This can be done with skin grafts or local tissue rearrangement, as discussed previously. Other scar contractures that are functionally limiting or aesthetically displeasing can be treated with a variety of releases and transpositions, including Z-plasties and Y-V-plasties.

Tendon adhesions are also common after thumb reconstruction. The primary method of treatment of this problem is early and aggressive hand therapy to minimize their impact. If therapy cannot overcome the adhesions, then flexor and/or extensor tenolysis may be required. Following tenolysis, therapy should resume within 24–48 hours.

As mentioned in the section on metacarpal lengthening, bone grafting is often required. Nonunions in the hand are rare but may require later bone grafting. Malunions of the thumb ray are extremely well tolerated and compensated; however, severe malunions may require osteotomy and fixation.

Joint contractures in the non-thumb digits can be particularly detrimental, especially the proximal interphalangeal joint. However, in the thumb, these are less an issue, and in fact can help with thumb stability. If there is a severe flexion contracture of the metacarpophalangeal joint, this may need joint release.

Distal-third thumb loss may result in painful neuromas that require later excision. However, this can largely be mitigated by traction neurectomy of the digital nerve(s) at the time of initial reconstruction.

Future directions

One exciting development in the last several years is the development of perforator flap surgery. This has enabled soft-tissue reconstruction using local tissue that in the past may have necessitated use of a free flap. Some authors have dubbed this “microsurgery without the microscope”. One group has described use of a princeps pollicis perforator flap for local thumb ray reconstruction, and it is likely that more hand-based perforator flaps will be described in the future.³⁶

It was mentioned at the beginning of the chapter that perhaps the best thumb reconstruction is actually replantation of the amputated thumb when possible. The advent of super-microsurgery in the last decade has enabled replantation of more distal amputations, even at the nail bed level. Better replantation techniques will potentially allow salvage of more native thumb tissue.

Finally, advances in prosthetics for the upper extremity are occurring at an astounding pace. It is possible that more durable osseointegrated thumb prosthetics will allow more function without autologous tissue reconstruction, and one day, these prosthetics may even enable sensation.



Access the complete reference list online at <http://www.expertconsult.com>

1. Littler JW. On making a thumb: one hundred years of surgical effort. *J Hand Surg Am.* 1976;1:35–51. Authored by one of the pioneers of hand surgery, this manuscript is a detailed and richly illustrated history of thumb reconstruction up to 1976. Many of the techniques described in this article remain common today. These include digit transfer, toe transfer, osteoplastic reconstruction, and phalangization.
12. Muzaffar AR, Chao JJ, Friedrich JB, et al. Posttraumatic thumb reconstruction. *Plast Reconstr Surg.* 2005;116:103e–122e. The authors present a comprehensive review of the classification of thumb loss in thirds, as well as reconstructive options for each level of amputation. This article includes both microsurgical and non-microsurgical reconstructive techniques. The focus of the article is reconstruction of the traumatically injured thumb, but the principles contained within are applicable to other thumb loss etiologies.
27. Matev I. Thumb metacarpal lengthening. *Tech Hand Up Extrem Surg.* 2003;7:157–163. This paper by Dr. Matev describes his experience with thumb metacarpal lengthening over a 40-year period. It is both a historical reference as well as an excellent technical guide to the procedure. While most of his patients required bone grafting following distraction, he describes situations in which the gap spontaneously ossified. Finally, Dr. Matev addresses other considerations such as the effects of distraction on the first webspace and the thumb carpometacarpal joint.
30. Bravo CJ, Horton T, Moran SL, et al. Traumatized index finger pollicization for thumb reconstruction. *J Hand Surg Am.* 2008;33:257–262. This article is one of a very few that analyze the on-top plasty (pollicization of a damaged index finger). The authors review 7 patients who underwent this reconstruction method, including pinch strength and sensibility. They find that, in general, this is a sound method of thumb reconstruction, and most patients reported favorably on their postoperative functionality. The article also includes a valuable list of technical points necessary to accomplish the procedure.
31. Brunelli GA, Brunelli GR. Reconstruction of traumatic absence of the thumb in the adult by pollicization. *Hand Clin.* 1992;8:41–55. This is a technique manuscript describing index finger pollicization which can be used for proximal third thumb loss. The authors present in detail the steps required to accomplish pollicization. Additionally, they address important considerations including management of the dorsal and palmar interosseous muscles of the index finger, as well as management of the transferred metacarpophalangeal joint. They also briefly describe pollicization of other digits if the index finger is unavailable.

References

1. Littler JW. On making a thumb: one hundred years of surgical effort. *J Hand Surg Am.* 1976;1:35–51. Authored by one of the pioneers of hand surgery, this manuscript is a detailed and richly illustrated history of thumb reconstruction up to 1976. Many of the techniques described in this article remain common today. These include digit transfer, toe transfer, osteoplastic reconstruction, and phalangization.
2. Nicoladoni C. Daumenplastik und organischer Ersatz der Fingerspitze (Anticheiroplastik und Daktyloplastik). *Arch Klin Chir.* 1900;61:606–628.
3. Guermontprez F. *Notes sur Quelques Resections et Restaurations du Pouce.* Paris: Asselin; 1887.
4. Littler JW. Subtotal reconstruction of the thumb. *Plast Reconstr Surg.* 1952;10:215–226.
5. Littler JW. The neurovascular pedicle method of digital transposition for reconstruction of the thumb. *Plast Reconstr Surg.* 1953;12:303–319.
6. Gosset J. La pollicisation de l'index (technique chirurgicale). *J Chir (Paris).* 1949;65:403–411.
7. Gosset J, Sels M. Technique, indications et resultats de la pollicisation du quatrieme doigt. *Ann Chir.* 1964;48:1005–1014.
8. Matev IB. Thumb reconstruction through metacarpal bone lengthening. *J Hand Surg Am.* 1980;5:482–487.
9. Matev IB. Thumb reconstruction in children through metacarpal lengthening. *Plast Reconstr Surg.* 1979;64:665–669.
10. Mehrra BJ, Abood AA, Disa JJ, et al. Thumb reconstruction following resection for malignant tumors. *Plast Reconstr Surg.* 2008;121:1279–1287.
11. Heitmann C, Levin LS. Alternatives to thumb replantation. *Plast Reconstr Surg.* 2002;110:1492–1503, quiz 1504–1505.
12. Muzaffar AR, Chao JJ, Friedrich JB, et al. Posttraumatic thumb reconstruction. *Plast Reconstr Surg.* 2005;116:103e–122e. The authors present a comprehensive review of the classification of thumb loss in thirds, as well as reconstructive options for each level of amputation. This article includes both microsurgical and non-microsurgical reconstructive techniques. The focus of the article is reconstruction of the traumatically injured thumb, but the principles contained within are applicable to other thumb loss etiologies.
13. Bickel KD, Dosanjh A. Fingertip reconstruction. *J Hand Surg Am.* 2008;33:1417–1419.
14. Atasoy E, Ioakimidis E, Kasdan ML, et al. Reconstruction of the amputated finger tip with a triangular volar flap. A new surgical procedure. *J Bone Joint Surg Am.* 1970;52:921–926.
15. Pet MA, Ko JH, Vedder NB. Reconstruction of the traumatized thumb. *Plast Reconstr Surg.* 2014;134:1235–1245.
16. Thibaudeau S, Tremblay DM, Tardif M, Chollet A. Moberg modification using the first web space: thumb reconstruction following distal amputation. *Hand (N Y).* 2012;7:210–213.
17. Hynes DE. Neurovascular pedicle and advancement flaps for palmar thumb defects. *Hand Clin.* 1997;13:207–216.
18. Woon CY-L, Lee JY-L, Teoh L-C. Resurfacing hemipulp losses of the thumb: the cross finger flap revisited: indications, technical refinements, outcomes, and long-term neurosensory recovery. *Ann Plast Surg.* 2008;61:385–391.
19. O'Brien B. Neurovascular island pedicle flaps for terminal amputations and digital scars. *Br J Plast Surg.* 1968;21:258–261.
20. Thompson JS. Reconstruction of the insensate thumb by neurovascular island transfer. *Hand Clin.* 1992;8:99–105.
21. Muyldermans T, Hierner R. First dorsal metacarpal artery flap for thumb reconstruction: a retrospective clinical study. *Strategies Trauma Limb Reconstr.* 2009;4:27–33.
22. Gregory H, Heitmann C, Germann G. The evolution and refinements of the distally based dorsal metacarpal artery (DMCA) flaps. *J Plast Reconstr Aesthet Surg.* 2007;60:731–739.
23. Page R, Chang J. Reconstruction of hand soft-tissue defects: alternatives to the radial forearm fasciocutaneous flap. *J Hand Surg Am.* 2006;31:847–856.
24. Hansen AJ, Duncan SFM, Smith AA, et al. Reverse radial forearm fascial flap with radial artery preservation. *Hand (N Y).* 2007;2:159–163.
25. Friedrich JB, Katolik LI, Vedder NB. Soft tissue reconstruction of the hand. *J Hand Surg Am.* 2009;34:1148–1155.
26. Agir H, Sen C, Alagöz S, et al. Distally based posterior interosseous flap: primary role in soft-tissue reconstruction of the hand. *Ann Plast Surg.* 2007;59:291–296.
27. Matev I. Thumb metacarpal lengthening. *Tech Hand Up Extrem Surg.* 2003;7:157–163. This paper by Dr. Matev describes his experience with thumb metacarpal lengthening over a 40-year period. It is both a historical reference as well as an excellent technical guide to the procedure. While most of his patients required bone grafting following distraction, he describes situations in which the gap spontaneously ossified. Finally, Dr. Matev addresses other considerations such as the effects of distraction on the first webspace and the thumb carpometacarpal joint.
28. Friedrich J, Vedder N. Groin flap coverage of the hand and wrist. In: Cooney W, Moran S, eds. *Soft Tissue: Master Techniques in Orthopaedic Surgery Series.* Baltimore, MD: Lippincott, Williams & Wilkins; 2008:233–244.
29. Cheema TA, Miller S. One-stage osteoplastic reconstruction of the thumb. *Tech Hand Up Extrem Surg.* 2009;13:130–133.
30. Bravo CJ, Horton T, Moran SL, et al. Traumatized index finger pollicization for thumb reconstruction. *J Hand Surg Am.* 2008;33:257–262. This article is one of a very few that analyze the on-top plasty (pollicization of a damaged index finger). The authors review 7 patients who underwent this reconstruction method, including pinch strength and sensibility. They find that, in general, this is a sound method of thumb reconstruction, and most patients reported favorably on their postoperative functionality. The article also includes a valuable list of technical points necessary to accomplish the procedure.
31. Brunelli GA, Brunelli GR. Reconstruction of traumatic absence of the thumb in the adult by pollicization. *Hand Clin.* 1992;8:41–55. This is a technique manuscript describing index finger pollicization which can be used for proximal third thumb loss. The authors present in detail the steps required to accomplish pollicization. Additionally, they address important considerations including management of the dorsal and palmar interosseous muscles of the index finger, as well as management of the transferred metacarpophalangeal joint. They also briefly describe pollicization of other digits if the index finger is unavailable.
32. Ince B, Gundeslioglu AO, Cicekcibasi AE, et al. Transfer of the fifth finger to replace an amputated thumb: a preliminary study. *Surg Innov.* 2015;22:462–468.
33. Pillet J, Didierjean-Pillet A. Aesthetic hand prosthesis: gadget or therapy? Presentation of a new classification. *J Hand Surg Am.* 2001;26:523–528.
34. Manurangsee P, Isariyawut C, Chatuthong V, et al. Osseointegrated finger prosthesis: An alternative method for finger reconstruction. *J Hand Surg Am.* 2000;25:86–92.
35. Parvizi D, Koch H, Friedl H, et al. Analysis of functional outcome after posttraumatic thumb reconstruction in comparison to nonreconstructed amputated thumbs at the proximal phalanx of the thumb ray: a mid-term follow-up with special attention to the Manchester-modified M2 DASH questionnaire and effect size of Cohen's d. *J Trauma Acute Care Surg.* 2012;72:E33–E40.
36. Al-Dhamin A, Cox J, Bissell MB, et al. Anatomical study of the princeps pollicis artery perforator flap. *Ann Plast Surg.* 2016;76:564–568.

14

Thumb reconstruction: Microsurgical techniques

Nidal F. Al Deek and Fu-Chan Wei

▶ Access video content for this chapter online at expertconsult.com

SYNOPSIS

- Microsurgical toe-to-hand transplantation allows “like-with-like” reconstruction, achieving the best functional and aesthetic results in the hand that is missing digits.
- Preservation of neurovascular bundles, flexor and extensor tendons, mobile joints, and viable skin with minimal bone shortening in the amputation stump ensures optimal functional results and less morbidity at the foot donor site.
- Retrograde dissection of the vascular pedicle at the first webspace during toe harvest is a key technique to alleviate concerns regarding variations in the vascular anatomy of the donor vessels.
- A missing thumb, traumatic or congenital, can be successfully reconstructed with the second toe, great toe or modifications of the great toe including trimmed great toe, partial great toe, and great-toe wrap-around flaps.
- Missing fingers, traumatic or congenital, can also be successfully reconstructed with various configurations from the lesser toes, achieving good outcomes, especially in those distal to the insertion of flexor digitorum superficialis. Timing of toe-to-hand surgery does not have an effect on flap survival, complications, and secondary procedures.
- The “metacarpal hand” refers to a hand with amputations of all fingers proximal to their functional length with or without accompanying thumb amputations. Toe-to-hand transplantation can help restore maximal hand function to this once crippling condition, even for bilateral defects.
- The “metacarpal-like hand” is an ill-defined term and entity of debilitating condition that also benefits from toe-to-hand surgery.
- Our extensive experience of over 2200 cases of various toe-to-hand transplantations allows pioneering of new concepts and refinements of existing techniques, classification systems and strategic management algorithms, and patient-reported outcomes, which all shall improve how we think and perform toe-to-hand surgery.

Introduction

Microsurgical toe-to-hand transplantation is one of the earliest free tissue transfers dating back to 1966.^{1–3} The technique

was first developed to overcome functional deficits following fingers traumatic injury then congenital deformities but evolved to address even aesthetic concerns. Over 40 years of history, toe-to-hand transfer has already reached its zenith.

When confronted with digit amputations, replantation remains the standard of care.^{4–6} However, in unreplantable cases or after failed replantation, toe-to-hand transplantation is the next best option superior to the use of prosthesis or other non-microsurgical techniques, fulfilling the “like-with-like” reconstruction principle without the need for immunosuppression.^{7–13}

For replacing a mutilated or unreplantable thumb, microsurgical toe-to-thumb transfer is the gold standard; a surgery well-justified based on the fact that the thumb constitutes 40–50% of hand function.^{14–17}

For multiple finger amputations, although the resultant disability is comparable to the loss of the thumb and drastically alters the appearance of the hand, indications for microsurgical toe-to-finger transplantation remain controversial.^{8,18–21} It worth noting that toe transfer to the missing finger distal to the insertion of the flexor digitorum superficialis generally yields superior functional and aesthetic results compared with other techniques.^{22–26}

Single finger amputation is not an exception to multiple finger amputation in controversy; although toe-to-finger transplantation could be indicated to help certain patients keep their jobs.^{22–26}

The metacarpal hand, a more severe and extensive type of injury,^{12,27,28} is a strong indication for toe-to-hand transfer, especially in bilateral injuries,^{29,30} and in the era of hand allotransplantation its indication is more justified for amputations distal to the wrist given the good results at the price of prolonged immunosuppression.³¹

A critical look at the literature on toe-to-hand surgery may not reveal significant changes since the middle of the 1980s, but it does show slightly increased interest in toe-to-finger transplantation; a sign of change in surgeons’ attitudes.³² It also shows a growing interest in refining the appearance of the transplanted toe^{33–40} and camouflaging the donor site.^{41–43}




Fig. 14.1 Number of cases performed at Chang Gung University Medical College Hospital from 1985 to 2015.

Long-term outcomes have also been studied that shall further establish the safety and efficacy of the procedure.^{44,45} This chapter outlines the current experience of toe-to-hand transplantations, drawing from the authors' experience of more than 2200 cases over a 30-year period at Chang Gung Memorial Hospital and Medical College (Fig. 14.1).



Access the Historical Perspective section online at

<http://www.expertconsult.com>

Diagnosis/patient presentation

The initial management of the potential toe-to-hand transplantation patient is similar to any other trauma or patient requiring digital replantation, with resuscitation and management of concomitant life-threatening injuries if necessary, and appropriate preservation of the amputated digits. Initial assessment of the injured hand allows preemptive discussion of toe-to-hand transplantation with the patient, especially when the possibility of a successful replantation is in doubt, such as in severely avulsed, crushed, or multiple amputations. In particular, patients whose occupation requires a high-demand use of their hands or those with special needs and hobbies requiring a fine degree of dexterity and ten fingers, e.g., musicians or athletes, should be given all information available concerning different reconstructive options. If there is significant tissue damage, or anticipated tissue lack following debridement, the use of pedicled groin flap with or without iliac bone graft to replace missing soft tissue and bone should be considered at the time of the initial operation and discussed with the patient (Fig. 14.2).

The initial operation

Anticipation of either primary or secondary toe-to-hand operations ensures careful preservation of all viable structures at the initial debridement or following failed replantation.^{55,56}

Excessive shortening of structures in order to achieve direct wound closure or the use of local and regional flaps should be avoided¹⁰ and electively replaced by distant pedicled flaps such as the groin flap that allows for: (1) maintenance of all important structures in the amputation stump; (2) primary closure at the foot donor site; (3) enough soft tissue to create adequate webspaces and avoid skin grafts in the hand improving overall cosmetic appearance; and (4) preservation of potential recipient vessels in the hand for microsurgical toe transplantation. Although some reports have suggested other methods of additional soft-tissue harvest with the toe transplantation, either as a single-stage microvascular procedure with combined free flaps,⁵⁷ or the use of native foot tissue,^{33,58} we still recommend the groin flap for the majority of cases; it is simple and reliable and leaves an almost negligible donor scar. In some severe cases of extensive soft-tissue loss, a pedicled anterolateral thigh (ALT) flap in sandwich technique fashion could be an alternative.

As the use of intraosseous wires is an effective method of osteosynthesis⁵⁹ and only requires 0.5 cm of bone for wire placement, as much remnant bone should be preserved as possible. In transjoint amputations, any intact articular cartilage and accompanying ligaments should be preserved to facilitate joint reconstruction with disarticulated toe joints.⁶⁰ Amputations at the level of the thumb metacarpals can be augmented with the use of bone blocks, thus avoiding the



Fig. 14.2 (A,B) Coverage of an injured hand with a pedicled groin flap before toe transplantation.

Historical perspective

The first ever report on toe-to-hand transfer was performed in a staged, pedicled manner on a 5-year-old child over a four-week period of time by Carl Nicoladoni in 1897. Unfortunately, the resultant transfer was stiff due to prolonged immobilization but still superior to the tubed pedicled flaps popular at that time.⁴⁶ Davis was the first to combine staged transfer with microanastomosis of the dorsalis pedis artery, opening the door for many innovations to follow.⁴⁷ But, it was not until 1967 that the first microvascular toe-to-thumb transplantation was performed by Yang and Gu² who transplanted the second toe to the thumb.² Notably, Buncke and Schulz's experimental work on monkeys⁴⁸ preceded Yang's operation by one year and probably inspired Cobbett, who successfully transplanted the great toe to the thumb in 1969.³ Recent follow-up of Cobbett's first patient at 30 years showed good subjective sensation and no evidence of osteoarthritis.⁴⁹

Partial toe transfer, another frontier in toe-to-hand surgery, was deemed feasible in 1979 after Buncke and Rose performed the first neurosensory pulp flap for finger tip reconstruction.⁵⁰ Koshima further pushed the limits of microsurgery by performing, for the first time, a free vascularized nail graft in 1988.⁵¹

The success of toe-to-hand transfer in adults encouraged pediatric toe-to-hand transfer with O'Brien first reporting the procedure for congenital absence of the thumb⁵² and Gilbert⁵³ and Cooney and Wood⁵⁴ for the replacement of congenitally missing fingers.

The long and incredible history of toe-to-hand transfer has yielded it the current "state of the art" with the focus now on refinements of the functional and aesthetic results, long-term and patient-reported outcomes, and strategic guidelines. Toe-to-hand transplantations for traumatic and congenital hand defects will remain an important tool in the armamentarium of the reconstructive microsurgeon.

need for a transmetatarsal osteotomy in great-toe harvest, as preservation of the metatarsophalangeal joint is important for foot function and appearance.^{12,61}

Avulsed or shredded extensor and flexor tendons should be debrided but never sacrificed for the sole purpose of obtaining wound closure. In fingers, preserving the native intrinsic extensor apparatus as far as possible, especially over the proximal interphalangeal joint, allows preservation of the arrangement of the intrinsic and extrinsic extensor systems⁶² following reconstruction. Similarly, preserving the insertion of the flexor digitorum superficialis, wherever possible, has proved useful in achieving better functional results.^{56,63}

Excessive shortening and the use of cauterization of arterial and venous ends are to be avoided in order to minimize intimal damage and preserve length, avoiding more extensive foot dissection and the need for vein grafts which prolong the operation and increase complications.⁶⁴ The same applies to nerves. Traditional teaching of the “pull and cut” method for prevention of neuromas in amputated stumps is to be avoided, as sensory recovery is much faster when nerve length is preserved and neurorrhaphy performed nearer to the transferred toe.⁶⁵ All neurovascular bundles should be tagged carefully with 10/0 sutures to ensure easier identification at the subsequent reconstruction.

Patient selection

Patient factors

Careful patient selection is the key to success. Age in itself is not a contraindication for microsurgical toe-to-hand surgery.⁶⁶ Instead, it may impact sensory recovery and range of motion with the best results achieved in younger patients.⁶⁷ Ideal patients should be highly motivated, clear about their needs with realistic goals and in good health. Decision-making for each patient is individualized not simply for the injury status but also to take into account the hand dominance and occupation as well as socioeconomic status.

Timing: primary versus secondary reconstruction

The time window once advocated by Godina for microsurgical reconstruction of lower extremity is not applicable in toe-to-hand surgery.⁶⁸ Acute, subacute, and chronic reconstructions cause confusion and have no significant impact on the result and, therefore, are better to be avoided; primary and secondary reconstructions should be used, instead. Primary refers to microsurgical reconstruction done at any time as long as the wound has not healed yet, while secondary refers to transplantation after the wound has healed. With that understanding, secondary toe-to-hand procedures may ensure better wound control and definition of the injury zone, while primary reconstruction allows one-stage procedure, earlier rehabilitation, and subsequent return to work, as advocated by several authors.^{24,69–71} In our study of 26 primary cases versus 96 secondary cases, there was no significant difference in terms of flap survival rates, vascular re-exploration rates, recipient site complications including infection, or requirement for secondary revision.⁷¹ In a well-informed and motivated patient without extensive soft-tissue loss or other

significant injuries of the ipsilateral upper limb, primary toe-to-hand transplantation offers the ideal method of replacing digit loss. It is worth noting though that earlier transfer may also result in better sensory recovery than delayed transfer. On the other hand, the procedure should be postponed or not even performed in patients who are unsure about their decisions and who cannot undergo rehabilitation as expected.

Injury factors

Decision-making for the thumb

The functional thumb depends on adequate length, sensibility, stability, and the function of the thenar muscle group to perform opposition. Microvascular toe-to-thumb transplantations allow these four objectives to be achieved in a single stage with a superior aesthetic result. The function of the thumb decreases by 50% once the amputation level is proximal to the proximal interphalangeal joint and reaches 100% once it crosses the metacarpophalangeal joint.⁷² Amputations distal to the interphalangeal joint are generally well tolerated but, in certain patients, the additional length, stability, and sensibility from a transplanted distal toe transfer should always be offered as an option.^{65,73}

Various classifications and reconstructive algorithms exist for thumb defects,^{74–76} although the underlying principles relate mainly to the types of tissue and the length of thumb missing.⁷⁷ Toe-to-thumb transplantations can be successfully reconstructed with various modifications of the great toe, including whole great toe,⁷³ trimmed great toe,⁷⁸ great-toe wrap-around flaps,⁷⁹ pulp flaps,⁸⁰ and the second toe.^{29,58} The decision to use which toe or its variation should be individualized not only to the thumb defect and the patient's needs, but also with careful consideration of the donor site. In general, thumb reconstruction using the great toe or its variants provides better functional outcomes in terms of tripod pinch, side-to-side and pulp-to-side pinch, as well as appearance than the lesser toes do, although augmentation procedures for second toes to improve bulk have been described.⁵⁸ If the great toe is used, at least 1 cm of the proximal phalanx should be preserved in the foot to ensure better push-off and preservation of foot appearance; the great toe is therefore an ideal option for thumb amputation levels distal to the mid-metacarpal shaft. In a more proximal amputation, additional challenges are inadequate bone stump length and thenar muscle function. The first can be overcome by a transmetatarsal transfer of the second toe or preliminary distraction lengthening of the existing metacarpal ray or interpositional bone grafting between the transferred toe and the metacarpal without sacrificing the base of proximal phalanx or the metatarsophalangeal joint of the great toe.^{12,30,65} The destruction of the thenar musculature and the subsequent loss of opposition, however, may necessitate pronation osteosynthesis, but is better corrected by primary opposition transfer in the authors' experience.⁸¹

Decision-making for fingers

Classification of finger defects is similar to the thumb and pertains to the type of tissue and length of finger missing, with the additional consideration of which finger is involved and whether there are single or multiple amputations. The

definition of proximal or distal amputations is determined by its relation to the insertion of the flexor digitorum superficialis tendon.^{55,65,82} Toe transplantation to more distal finger amputations can be achieved by a wide variety of options, including the use of vascularized nail grafts,^{51,83,84} pulp flaps,⁸⁵ wrap-around flaps,³⁵ and partial second toes,²³ depending on what tissues are missing. These operations are rewarding due to the restoration of high-density pulp sensation, fine pinch, and cosmetic appearance of the nail.^{82,83,86} A partial second-toe flap which includes the distal interphalangeal joint or both the proximal and distal interphalangeal joints is indicated in amputations distal to the flexor digitorum superficialis insertion.^{22,82,87,88} In contrast, a whole second-toe flap is indicated in carefully selected patients with more proximal amputations;⁶⁵ the ideal level, however, is distal to the middle of the proximal phalanx as reconstructions for more proximal amputations usually result in a slightly shorter finger.⁸⁹

Decision-making for patients with multiple finger amputations are largely guided by the specific occupational and cosmetic needs of the patient. In general, two adjacent fingers should be reconstructed wherever possible to allow a stable tripod pinch or hook grip.^{12,21,88} Preferential reconstruction of the radial two fingers should be recommended for patients who require fine pinch and the ulnar two digits for manual workers who require a strong grip.^{19,90} However, multiple finger amputation could be too complicated to be addressed with toe-transfer alone, and additional procedures such as lengthening and ray amputation could be necessary, as well.⁸⁶

Decision-making for the metacarpal hand

The term “metacarpal hand” refers to a hand injury with multiple finger amputations at the level of the metacarpophalangeal joint, or immediately proximal or distal to it. Delitala was perhaps the first to coin this term⁹¹ and, since then, various classification systems have been proposed,^{92–95} with varying levels of clinical usefulness. A classification system based on reconstructive options and different stages of injury has proved useful in our experience^{12,61,91} (Tables 14.1 & 14.2). This takes into account the level of finger amputations and thumb involvement, and provides guidelines for the reconstructive technique as well as prediction of the functional outcome after reconstruction. Type I refers to four-finger proximal amputations without the thumb or only distal-thumb involvement (no thumb reconstruction necessary). In type IA where the amputation level is distal to the

Table 14.1 Metacarpal hand classification for type I defects

Subtype	Thumb amputation levels	Finger amputation levels
IA	Amputation distal to the interphalangeal joint	Distal to the level of metacarpophalangeal joint
IB		At the level of the metacarpophalangeal joint
IC		Proximal to the level of the metacarpophalangeal joint

metacarpophalangeal joint, the focus is on the selection of two separate toes or combined second and third, or third and fourth toe transplantations depending on the presence of webspace (Fig. 14.3). To ensure that the different digits curve around an object more evenly in grasp prehension, the length of the remaining amputation stumps should not be longer than that of a normal little finger when considering a combined second- and third-toe transfer.⁹⁰ For type IB, where the amputation level is through the joints with intact articular surfaces, combined second and third toes are harvested as composite joint transfers. For type (IC) where the amputation level is proximal to the metacarpophalangeal joints, combined second and third toes as transmetatarsal transfers is indicated. Reconstruction of two adjacent fingers allows for a stable tripod pinch, although reconstruction of all four fingers is possible in certain selected patients with acceptable donor site morbidity (Fig. 14.4).¹²

Type II injuries refer similarly to four-finger proximal amputations but with various levels of thumb involvement proximal to the base of proximal phalanx. The reconstruction of fingers with toe transplantations follows a similar decision-making process as for type I defects, but reconstruction of the thumb is determined by the presence or absence of a functional thenar musculature. If the thenar muscles are intact or possess adequate function (types IIA and IIB), a one-stage procedure to reconstruct the thumb and two adjacent fingers is recommended. If the thenar muscles are missing or have inadequate function (IIC), the thumb reconstruction should follow finger reconstructions in a second stage and only after the thumb position is determined by the aid of prosthesis while the fingers assume their final positions (Fig. 14.5). Either

Table 14.2 Metacarpal hand type II defects and proposed reconstruction algorithm

Subtype	Thumb amputation level	Reconstructive options	Stage
IIA	Distal to the metacarpal neck	Whole or trimmed great toe	Simultaneous
IIB	Proximal to the metacarpal neck with adequate thenar muscle function	Whole or trimmed great toe ± lengthening or bone augmentation Transmetatarsal second-toe transfer	Simultaneous
IIC	Any level with inadequate thenar musculature	Same as in IIA or IIB Opponensplasty	Staged
IID	Any level with damaged carpometacarpal joint	Same as in IIA or IIB Immobile thumb post	Staged




Fig. 14.3 Indications for combined second- and third-toe harvest versus bilateral toe harvest. A combined second- and third-toe transplantation is preferred for: **(A)** amputations proximal to the webspace (indicative of a level at or proximal to the metacarpophalangeal joints); or **(B)** when the remaining fingers are at the level of, or shorter than, the little finger. Using this technique when the remaining finger is longer than the little finger will produce a hand with gross unequal finger lengths and an uneven digital arcade **(C)**. **(D)** Bilateral second toes are best suited when the webspaces are preserved, indicative of amputations distal to the metacarpophalangeal joints with adequate bone for osteosynthesis.

pronation osteosynthesis or an opposition transfer can be performed to provide better pinch.^{81,96}

Decision-making in bilateral metacarpal hand injuries requires a careful balance of the severity of injury (type I or II), patient's needs, and donor site morbidity. Other options should also be discussed with the patient. Type II injuries are much more difficult than type I, requiring up to but not exceeding five toes to achieve a functional level of

prehension.³⁰ In general, the use of a great toe, usually from the left foot, is sacrificed for dominant thumb reconstruction together with a combined two-toe reconstruction from the opposite foot to achieve a tripod pinch. In the non-dominant hand, single-digit pulp-to-pulp pinch is considered adequate with the use of a lesser toe for thumb reconstruction.³⁰ Although the option of sacrificing both great toes or more



Fig. 14.4 The reconstructed tripod pinch of a type I metacarpal hand, showing stability of grip and good opposition with the thumb.



Fig. 14.5 Use of a prosthetic thumb for a type IIC metacarpal hand after combined second- and third-toe transplantation for middle- and ring-finger reconstruction. This is useful for determining the exact position of the future transplanted thumb and for planning additional procedures (e.g., opponensplasties).




Fig. 14.6 (A,B) Appearance of bilateral metacarpal hands and donor sites after toe-to-hand transplantations. Up to a total of five toes can be harvested for the most severe defects of bilateral type II metacarpal hands requiring reconstruction of opposing digits in both hands.

lesser toes for hand reconstruction may seem attractive, we have found that the donor morbidity reaches a level that is incompatible with activities of daily living. In instances where multiple toes are needed, the patient needs to participate fully in the decision-making with regard to the foot morbidity, especially in certain populations where patients are far less tolerant of sacrificing their toes to reconstruct their hands (Fig. 14.6).²⁹

Treatment/surgical technique

Despite the many configurations and combinations of toe-to-hand transplantations available, a few important principles exist for all cases which, when adhered to, allow easier dissection, reduced foot morbidity, and improved overall functional and aesthetic outcomes.

General principles in vascular dissection

The venous drainage system should be identified and selected before the arterial system. One sizeable vein located in the intermediate layer and drained by the great saphenous vein is usually enough, but should not be confused with the arterial system.

As for the arterial blood supply, we recommend the vascular pedicle dissection starts at the first webspace and proceeds in retrograde manner. This method alleviates concerns regarding vascular anatomy and allows early detection of system dominance pattern (dorsal *vs.* plantar) which shall guide the rest of surgery minimizing damage and reducing time.^{97,98} In our experience, the first dorsal metatarsal artery (FDMA) is usually dominant (70%) and identified by its dorsal relation to the intermetatarsal ligament (Fig. 14.7).^{65,99} Once this is confirmed, it permits early ligation of the plantar system,

minimizing tedious and destructive dissection in the foot. In the 20% of cases where a first plantar metatarsal arterial (FPMA) system is dominant, as identified by its plantar relations to the deep intermetatarsal ligament (see Fig. 14.7), the FDMA is then ligated, reducing time spent on dorsal dissection, and the plantar dissection continued together with the harvest of the digital nerves. The length of the arterial pedicle harvested should be able to reach the chosen recipient artery. However, in a dominant FPMA system, dissection should be limited to the non-weight-bearing zones, with the use of vein grafts if necessary to increase pedicle length. In cases where both the FDMA and FPMA appear equally dominant (10%; see Fig. 14.7), the dorsal system is always selected due to its easier harvest and less donor morbidity. Following toe harvests, at least 20 minutes should be allowed for observation of adequate perfusion before detaching the flap.

Clinical hints and tips

- Always start the vascular pedicle dissection from the first webspace and identify the trifurcation (two branches to two adjacent toes and one communicating branch to the plantar artery) then trace the arterial pedicle in a retrograde fashion. In 70–80% of cases, the first dorsal metatarsal artery can be used as the arterial pedicle.
- To avoid “cobra-head” disfigurement, create four mobile flaps through a cruciate incision, and interpose these with the V-shaped flaps of the transplanted toe.
- The neurovascular bundles are skeletonized during the dissection to avoid difficult inset and bulky appearance at the junction of transplanted toe and amputated stump.




Fig. 14.7 (A) Retrograde dissection of the arterial pedicle begins in the first webspace and allows early confirmation of a dominant dorsal or plantar system. (B) In 70% of cases, a dominant first dorsal metatarsal artery is present (MAKE DORSAL VESSEL THREE TIMES LARGER THAN PLANTAR VESSEL), whereas in 20% of cases, a dominant first plantar metatarsal artery is present (C) (MAKE PLANTAR VESSEL THREE TIMES LARGER THAN DORSAL VESSEL). In 10% of cases, both systems are equally dominant, in which case the dorsal system is selected (D).

General principles in recipient preparation

A two-team approach greatly reduces the overall operating time, surgeon fatigue, and risks of anesthesia.⁵⁵ Proper preparation of the recipient site allows a smooth transition from flap harvest to inset without any delays. Preservation of all viable lengths of bone, joints, neurovascular bundles, and tendons should have been performed at the initial operation by a surgeon who has working knowledge of toe-to-hand transplantations.⁵⁶ A cruciate incision allows the creation of four equal triangular flaps for smooth interdigitation with the V-shaped flap of the transplanted toe and prevents the ugly “cobra” appearance that features prominently at the toe–digit junction (Fig. 14.8). Following preliminary inset, excess fatty tissues are trimmed by skeletonizing the neurovascular bundles of the recipient flaps. All these maneuvers allow the creation of a finger or thumb with a more natural-looking appearance.

Clinical hints and tips

To reduce foot morbidity and avoid the use of skin grafts, pay careful attention to the placement of incisions on the foot. Webspace incisions should not cross the midline on to the territory of the contralateral toes, and all proximal incisions should converge to a V proximal to the osteotomy sites. In addition, scars should be kept away from all weight-bearing sites.

General guidelines in donor closure

Careful placement of incision lines in the donor foot minimizes weight-bearing pain and scar tenderness and permits earlier mobility. V-shaped flaps are placed proximal to the osteotomy site whereas distally, the incisions are situated midway between the webspaces to permit tension-free closure, even with combined second–third or third–fourth-toe



Fig. 14.8 A cruciate incision at the recipient site allows the creation of four equal triangular flaps and prevents a bulbous appearance at the subsequent toe-to-finger junction.



Fig. 14.9 A prepared recipient site with interosseous wires inserted, ready for inset of the toe flap.

transplantations. Incisions on weight-bearing areas as well as extensive foot dissection should be avoided. Skin grafts are generally discouraged due to difficulties in replacing glabrous skin, wound breakdown due to repeated pressure from weight-bearing and footwear, and also because it prevents early ambulation. When skin grafts are required, for example, after pulp flap, webspace flap, and wrap-around flap harvests, they should be carried out meticulously with strict prevention of ambulation until the grafts are healed.

General principles in flap inset

Intraosseous wires provide a stable, not rigid, method of fixation, achieving a union rate of 98.5%.⁵⁹ They are also advantageous for the following reasons: a shorter segment of recipient bone is required for osteosynthesis; and the semirigid fixation allows early postoperative correction if the transplanted toe is found to be malaligned or malrotated (Fig. 14.9).

Clinical hints and tips

- To preserve maximum bone length in the amputation stump, use parallel intraosseous wires as the preferred method of osteosynthesis, as this requires only 0.5 cm of available bone, achieves a good union rate, and allows postoperative correction of any malalignment or malrotation.
- Careful attention to tendon repairs increases range of motion and also corrects the natural tendency of the toe to claw. The extensor tendons are always reconstructed first. Preserving the extensor tendon apparatus over the proximal interphalangeal joint, wherever possible, allows the intact intrinsic system of the hand to work synergistically with the reconstructed extrinsic system. Release of the extensor digitorum longus attachment from the metacarpophalangeal joint capsule, suturing of the extensor digitorum brevis to the dorsal expansion or to the interosseous musculotendinous structure, and a tight extensor repair in full extension are different ways of overcoming the naturally flexed position of the toe.³⁶ In addition, a K-wire is also inserted at the end of the procedure, transfixing the distal

interphalangeal joint and the proximal interphalangeal joint in full extension.

- The flexor tendon repair is carried out against the tension of the extensor repair to restore a normal digital cascade. In proximal amputations, the flexor tendon of the transplanted toe should be pulled through proximally into zone III for repair to prevent an increased risk of tendon adhesions in “no man’s land” (zone II).

Clinical hints and tips

- To achieve the best functional outcome of the reconstructed tendons, preserve all extensor apparatus as far as possible to allow synergistic action of the native intrinsic system with the reconstructed extrinsic system. To correct the natural tendency of the toe to claw, perform a tight extensor tendon repair and insert a K-wire with the distal and proximal interphalangeal joints in extension for 6 weeks followed by splinting for up to a year.
- To achieve maximal stability of the interphalangeal joint following a trimmed great-toe harvest, ensure that the periarticular flap consisting of the periosteum, medial collateral ligament, and joint capsule is redraped and closed in a tight manner around the trimmed interphalangeal joint of the great toe.

Nerve repair is carried out next. The proper digital nerves are selected for end-to-end anastomosis with recipient digital nerves that have been trimmed back to reveal healthy nerve stumps. If additional dorsal recipient nerves are available, these can be sutured to any harvested branches of the superficial and deep peroneal nerves. Following nerve repair, the skin flaps are closed temporarily to allow for final skin adjustments if necessary. Care must be taken to prevent a tight closure which may eventually compress the pedicles. If in doubt, a skin graft should be used rather than try to force primary closure. A single arterial anastomosis is then performed and perfusion of the toe checked before the venous anastomosis. If it is judged to be inadequate, the entire pedicle should be assessed for any kinking, twisting, or compression with further stripping of the adventitia if necessary. If required, further shortening or a vein graft should be used to ensure healthy inflow.

Clinical hints and tips

- To ensure maximal success and reduce vascular complications, harvest the combined second- and third-toe flap with the first dorsal metatarsal artery as the dominant pedicle, and the second and third common digital artery as a backup in case of inadequate perfusion.
- To reduce donor site morbidity, close the donor site primarily in all cases. It is not necessary to reconstruct the transmetatarsal arch even when disturbed, for example, in transmetatarsal osteotomies, as this does not affect gait and walking ability in the long term.




Fig. 14.10 Trimmed great-toe harvest technique.

(A) Markings of the thumb are made at three positions on the thumb and transposed to the toe: nail eponychium, widest point (interphalangeal joint), and middle of proximal phalanx. (B, C) The discrepancies are marked on the medial side as an area to be excised. (D) The skin flap is elevated superficial to the collateral ligament and joint capsule. (E) The periarticular flap is created by raising the periosteum, medial collateral ligament, and joint capsule as a single flap, exposing the phalanges. The medial joint prominence and 2–4 mm of the proximal and distal phalanges are removed by an oscillating saw. (F) Following tight redraping of the periarticular flap, the skin is closed to create a toe of smaller circumference, ready for transfer.

In a combined second- and third-toe transplantation, two anastomoses should be prepared as a higher rate of arterial spasm, and re-exploration rates of up to 20%¹⁰⁰ have been found when using a single dominant artery. A second anastomosis using the second and third common plantar artery should be carried out when the perfusion to the third toe is uncertain. Once perfusion is established, the hand is then turned around, and the venous outflow checked for healthy back-bleeding. Venous anastomosis is carried out through a separate incision on the dorsum of the hand. A recipient vein of suitable caliber is selected and mobilized from the adjacent fingers if necessary. The skin incisions are then loosely closed definitively over small silastic drains placed in the dorsum of the hand and fingers, and finally the K-wire is inserted across the distal and proximal interphalangeal joints in full extension. The hand is then wrapped in a non-circumferential, non-compressive dressing with the transplanted toe largely exposed to monitor perfusion.

Specific operations

Trimmed great toe (Video 14.1 ►)

Harvest of the trimmed great toe begins with measurements taken and compared at three locations on the normal contralateral thumb and the great toe to reconstruct a new thumb with matching proportions: the nail eponychium, the interphalangeal joint, and the middle of the proximal phalanx (Fig. 14.10). The size discrepancies are marked on the medial aspect of the great toe as an area of tissue to be excised, with an excess of 2–3 mm on each side and tapering of both the proximal and distal ends to facilitate closure.

Elevation of the trimmed great toe begins in the first web-space to identify the dominant blood supply and carry out retrograde dissection, as previously described. Following identification of the flexor and extensor tendons and also after careful preservation of the deep peroneal nerves, the

trimming of the great toe commences. The marked area of redundancy is excised with incisions down to and superficial to the medial collateral ligament of the interphalangeal joint. The next step is removal of bony excess. To facilitate access to the phalanges, a plantar-based periarticular flap composed of periosteum, joint capsule, and medial collateral ligament is raised. About 4–6 mm of the joint prominence and 2–4 mm of the phalanges are removed with an oscillating saw and the remaining bones smoothed with a burr. The periarticular flap is then redraped with the excess tissue excised and sutured in a tight manner to ensure the stability of the joint. Finally, the medial skin incisions are approximated and the overall appearance checked before carrying out the transverse osteotomy at the level of the proximal phalanx and the flap islanded, ready for inset (see Fig. 14.10).

Second toe: total and partial (Video 14.2 ►)

Transplantation of a partial second toe is used for distal digit amputations whereas a transplantation of total second toe is used for the reconstruction of more proximal finger amputations.

For either, the skin markings encircle the base of the second toe and cross the midpoints of the first and third webspaces, finally converging as a V proximally and extending at least 5–10 mm beyond the osteotomy site (Fig. 14.11). The toe harvest commences by identifying the dominant arterial supply in a retrograde fashion and one sizeable vein, as previously described. Both the extensor digitorum longus and brevis tendons are identified and traced proximally for adequate length. Branches of the peroneal nerves are usually not

harvested in preference of the plantar digital nerves. The dissection is then continued on the plantar aspect of the foot, similarly with a V extending from the base of the toe and further extension with avoidance of any weight-bearing areas. The flexor sheaths are opened and the flexor tendons pulled out and cut at a proximal level to ensure adequate length. The plantar nerves are traced proximally to the bifurcation of the common digital nerves and internal neurolyses carried out if necessary to obtain adequate length before dividing them. The removal of excess fibro-fatty tissues by skeletonization of each neurovascular component is routinely carried out, as this greatly facilitates wound closure and improves the aesthetic appearance of the transplanted toe. This is especially so for partial toe transfers, due to the relative lack of space for flap inset at the level of the middle phalanx.

The bone length required for a complete second-toe transfer is achieved by an osteotomy at the proximal phalanx, the metatarsal shaft, or via a metatarsophalangeal joint disarticulation preferably. In a partial toe transfer, the neurovascular bundles are freed distal to the osteotomy sites at the middle or proximal phalanges or the disarticulated joint. Metatarsophalangeal joint disarticulation is usually necessary to permit direct skin closure, even following partial toe transfers.

Partial second-toe transfer has further evolved into specific-structure partial transfer such as vascularized nail, pulp or joint with preservation of the second toe. The donor site of such a specialized partial second-toe flap can be covered with a full-thickness skin graft.¹⁰¹

The second-toe flap can also be modified to improve the appearance of the reconstructed new thumb. Although the second toe can be transferred to create a functionally




Fig. 14.11 Second-toe harvest technique. (A,B) A dorsal S incision is made on the dorsum of the foot to expose the donor veins, extensor mechanism, and arterial pedicle, although dissection begins in the first webspace to allow a retrograde dissection (C). Plantar dissection begins with a midline incision, avoiding the weight-bearing areas of the foot, to expose the digital nerves and to harvest the flexor tendon (D).

acceptable thumb, the appearance falls short due to narrow neck, bulbous appearance, and short nail. The lateral pulp flap from the great toe can be harvested with the second toe based on the same vascular pedicle and used to augment the volar aspect of the second toe to give more bulk and correct the narrow neck and the eponychium of the nail complex of the second toe can be excised to lengthen the nail and mimic the thumb nail.¹⁰²

Third toe

The third toe can also be transferred to reconstruct missing digits. Indications are: (1) the second toe is not available or is not suitable for transfer because of previous injury, surgery, or deformity; (2) the second toe is on the same foot from which the great toe has been harvested for thumb reconstruction and therefore the second toe is spared for gait; and (3) the third toe provides a better size match for finger reconstruction than the second toe.¹⁰³

For reliable harvest of the third-toe flap, the key principles used in great and second toe dissection apply. However, since the majority of the patients undergoing transplantation of the third toe have already had transplantation of either the great or the second toe or will have it, the second metatarsal pedicle is either not available or must be preserved for subsequent transfer of the great or second toe. Therefore, the third toe is preferably transferred based on the third plantar metatarsal artery, which is usually bigger in caliber than the second or third dorsal metatarsal arteries. As the pedicle of choice for the third toe is the plantar pedicle, it will be simpler and quicker to proceed directly to the dissection of the plantar vascular pedicle, and if found short, a vein graft is used for the vascular anastomosis.¹⁰³ In most cases, however, the pedicle is long enough to reach the proper digital artery at the level of the proximal phalanx in the hand.

The donor site is closed in the same way as described for the second toe.

Wrap-around flaps: great and second toes

The great-toe wrap-around flap was originally used in conjunction with a non-vascularized iliac bone graft for reconstructing thumb loss distal to the metacarpophalangeal joint,⁷⁹ although reconstructions at more proximal levels have been described.¹⁰⁴ The use of these flaps can be extended to the replacement of skin and nail loss in the thumb and ring avulsion finger injuries with an intact skeleton, tendon, and proximal interphalangeal joints. Reconstruction of the latter is better achieved with a second-toe wrap-around flap which provides an excellent contour and nail match and also avoids using the great toe as a donor.³⁵

Harvest of the great-toe wrap-around flap follows similar principles as the trimmed great-toe technique, previously described. Preoperative markings are made with measurements taken from the contralateral thumb and transposed on to the great toe (see Fig. 14.10A). The flap utilizes the dorsal, lateral, and plantar skin, leaving behind a cuff of skin and subcutaneous tissue on the medial aspect for donor closure. Disarticulating the remaining interphalangeal joint and closing the medial skin flap over the proximal phalanx is preferred rather than using a cross-toe flap from the second toe. The second-toe wrap-around flap begins in exactly the



Fig. 14.12 Pulp flap harvested from the great toe.

same manner as the partial or complete second-toe flap (see above). The flap is then carefully degloved from the underlying skeleton, except for the distal phalanx, which is always included in the flap to maintain distal stability and prevent bone resorption. Careful consideration is also given to the placement of scars during flap harvest for their subsequent positioning on the “trailing” edges of the fingers. Disarticulation at the metatarsophalangeal joint in the remnant toe provides a donor defect amenable to primary closure and improved appearance.

Neurosensory pulp flaps

The size of the defect is outlined and marked on the selected toe (Fig. 14.12). The lateral aspect of the great toe is preferred for its richer nerve supply, more abundant tissues, and therefore increased likelihood of primary closure.⁶⁵ Principles for flap harvest are similar to those previously described, but important considerations are keys to achieving success: (1) identifying and including both the branches of the deep peroneal nerve and proper digital nerve to provide the best sensory outcome; (2) dissection and inclusion of the proper digital artery by tracing its origin from the first dorsal or plantar metatarsal artery in the first webspace; (3) skeletonizing the neurovascular bundle to allow tunneling of the vessels during flap inset.

First-web neurosensory flap

This is a useful flap due to its rich sensory innervations, pliability, and size, with dimensions of 14 × 7 cm achievable¹⁰⁵ for resurfacing of bigger defects in one or multiple fingers, and the potential to replace glabrous skin for palm defects.^{104,106,107} After outlining the defect in the first webspace, the vein is first identified, as previously described. The location of the intermetatarsal ligament is identified next as this structure points to the first dorsal or plantar metatarsal artery and the distal communicating artery that supplies this flap. Once the dominant blood supply is confirmed, retrograde dissection continues in a straightforward manner, continuing with either the dorsal or plantar approach. Branches of the proper digital arteries must be traced and included if the flap dimensions extend to the pulps of the great or second toes.




Fig. 14.13 (A–D) First-web neurosensory flap harvest from the left foot for reconstruction of the first webspace of the right hand.

Likewise, in this situation, the proper digital nerves are harvested in conjunction with the deep peroneal nerve branches to provide adequate sensation. The donor defect is readily reconstructed with a split-thickness skin graft and tie-over dressings. Careful attention to detail and strict non-weight-bearing reduce the incidence of wound-healing complications and the need for prolonged foot care (Fig. 14.13).

Combined second- and third-toe transplantation (Video 14.3 ►)

Combined second- and third-toe transplantations carry the advantages of only needing potentially one set of microvascular anastomoses, less operative time, and confining donor morbidity to one foot.⁹⁰ Its popularity has been limited, however, by the length of digits achievable following reconstruction and probably concerns regarding the donor morbidity, especially in certain populations.²⁹ If carried out carefully, however, this procedure is extremely useful in replacing two adjacent finger amputations at a level proximal to the web space, especially when the other remaining fingers are shorter than the little finger. It is especially useful in the metacarpal hand deformity to provide tripod pinch function, hook grip capability, and lateral stability.

Skin incisions in the first and third webspaces should not cross the midline to allow primary closure of the donor site, and converge to a V 1 cm proximal to the level of osteotomy. In proximal phalanx amputations with at least 5 mm of bone remaining, the toe is disarticulated from the metatarsophalangeal joint and then subsequently shortened to the required length and osteosynthesized to the finger skeleton. Through metacarpophalangeal joint amputations are reconstructed with the corresponding metatarsophalangeal joints of the toes with their joint capsules intact. Even more proximal amputations require harvest of the respective metatarsals (Fig. 14.14).

Retrograde dissection of the dominant arterial supply is performed in the first webspace, as previously described. The second and third plantar arteries should be dissected and preserved as a backup in case a second set of anastomosis is required. The common digital nerve to the second and third toe, together with their respective proper digital nerves, is also isolated and preserved for transfer during the plantar dissection. Direct closure of the donor site in a tension-free manner should be achievable without the need for a skin graft. In cases where the metatarsals have been osteotomized, the authors' present policy is to not replace the foot defect with a bone graft as previous analysis of patients has demonstrated no difference in walking and gait performance.⁶⁵

For situations when one neighboring second toe needs to be preserved for specific reasons and the amputation level at the recipient site is distal to the webspace, a bilateral third-toe transplantation provides an alternative solution. A split combined second and third toe from the other foot can be also performed and, in this case, two sets of pedicle vessels from the dorsal or plantar system are prepared and the best selected. Separation of second and third toes can be done after the adjacent toes were taken down or before.¹⁰⁸

Postoperative care

Immediate postoperative period

The immediate postoperative care is critical to ensure the success of the microsurgical procedure. Patients ideally should be kept for close monitoring of the flap in a microsurgical intensive care unit for a minimum of 5 days. If this facility is not available, they should be kept in a warm room and nursed by experienced staff trained in the routine monitoring of free



Fig. 14.14 Combined second- and third-toe harvest as a transmetatarsal transfer for reconstruction of a metacarpal hand. (A) Surface markings on the donor foot before harvest showing the position of the first dorsal metatarsal artery and a suitable vein. (B) Harvested toe with artery, veins, nerves, and tendons. (C,D) Reconstructed hand following inset showing primary closure of all wounds without tension.

flaps. Although both internal devices such as implantable Doppler¹⁰⁹ and external devices such as infrared temperature assessment and pulse oximetry may be useful modalities,¹¹⁰ the most reliable method of flap monitoring is still clinical observation. At the first sign of vascular compromise, rapid action should be taken to avoid further flap deterioration.¹¹¹ Infection should also be identified and controlled early as it has been found to be the single greatest factor contributing to vascular compromise and re-exploration in toe-to-hand surgery.¹¹² Beside flap monitoring and infection control, all patients are carefully monitored to ensure they are warm, well-hydrated, and pain-free. The hand is kept slightly elevated above the level of the heart, but not higher. Non-constricting, non-bulky dressings should be used as this prevents clot formation which could induce vasospasm during dressing change and also prevents early mobilization. A routine intraoperative bolus of dextran is given, followed by continuous infusion over the next 5 days. In addition, a 2-week course of oral aspirin is administered to reduce the incidence of platelet aggregation.

Motor rehabilitation

Toe-to-hand transplantations require a close collaboration between surgeons, nurses, physiotherapists, occupational therapists, and prosthetists to provide the necessary postoperative rehabilitation program and maximize the functional outcome. Individual patient motivation and employment needs also have to be considered. A five-stage rehabilitation program⁶⁵ ensures that these objectives are met:

1. Protective stage (days 1 to 3): Psychological support is provided while the patient is still in the microsurgical intensive care unit through interaction with the hand therapist.
2. Early mobilization stage (day 4 to week 4): The goal is to prevent excessive swelling and joint stiffness. On day 4, controlled gentle passive range of motion for about 15° is performed on the less involved joints. In the subsequent weeks the passive movement involves all joints both proximal and distal to the osteosynthesis site and is gradually increased in range but not to interfere

with bone union or to induce stress on the repaired tendons and the neurovascular structures. A protective splint is provided between exercises.

3. Active motion stage (weeks 5 to 6): While the passive exercises are still maintained, gentle active exercises under supervision begin, and the splint is changed to a dynamic one. Once tendon healing is no longer a concern, blocking flexion and extension exercises are started. At this stage, more care can be directed towards softening the scar and improving appearance, and to avoiding adhesion by providing compression bandages, ultrasound, and scar massage.
4. Activities of daily living training stage (weeks 7 to 8): Depending on patient capabilities, different manual jobs that simulate daily manual activities are designed to increase muscle power and range of motion.
5. Pre-vocational training stage (week 8 and beyond): The goal is to further improve muscle strength, hand dexterity and coordination. Vocational activities are encouraged, and a night-time extension splint to prevent claw deformity is recommended for 1 year at least. Group sessions with other patients who have also received toe-to-hand transplants can be helpful to encourage integrating the reconstructed hand into the patient's normal life.

Sensory rehabilitation

The finger and thumb pulps are unique in that they contain a higher density of sensory nerve endings than other body areas, packed within a relatively small area of skin that is tightly adhered to the underlying bone via fibrous septa.¹¹³ Although toe transfers allow the replacement of this specialized glabrous skin, targeted sensory rehabilitation plays an important role in producing an optimal functional result. Several studies have demonstrated the importance of sensory re-education in maximizing both subjective and objective sensory recovery following nerve repair in digits;^{67,114–116} this is of even greater importance in toe-to-hand transplantations due to the fewer number of sensory endings in the toe as compared to the fingertip.¹¹⁷ Two types of sensory re-education program are used in the authors' unit: early and delayed.

Early re-education focuses on improving the local adaptation to the submodalities of light touch, pinprick, and pressure with correct localization, according to Dellon.⁶⁷ Static and moving two-point discrimination tests are usually chosen to measure local sensory recovery^{70,87,107,118} following early re-education, although our unit has shown that there is very little correlation between this method of assessment and sensory threshold testing using the Semmes–Weinstein monofilament kit.¹¹⁹ These results suggest that subjective recovery of functional sensibility may not always reflect the actual recovery of nerve function at the microscopic level. In fact, from our earlier study, the actual number of Meissner corpuscles was found to be decreased after transplantation, even though good functional sensibility was restored,¹²⁰ stressing again the importance of delayed sensory education which emphasized the retraining of central cortical functions like concentration, memory, and relearning.

Delayed sensory re-education consists of touching objects, both blinded and non-blinded, to appreciate further

the differences in texture, size, shape, and consistency from different surfaces. The significant improvement that can be seen following this re-education can probably be explained by the increased cortical reorganization caused by increased neural activity in the postcentral gyrus that compensates effectively for the decreased local neural activity.^{121–123}

Outcomes, prognosis, and complications

Outcomes and prognosis

The success rates of microsurgical toe-to-hand transplantations are around 96–98%.^{53,112,124–126} Therefore, the goal of this surgery should no longer be flap survival but improved aesthetic and functional outcomes. In a series of 2200 procedures carried out by the authors over 30 years (1985–2015) at Chang Gung Memorial Hospital and Medical College, a success rate of 97% was achieved (see Fig. 14.1).

Range of motion

In terms of range of motion, an average of 25° and 29° following thumb reconstruction using the great toe should be achievable at the metacarpophalangeal joint and interphalangeal joint, respectively.¹²⁵ The trimmed great-toe technique generally results in an anticipated reduction of movement at the interphalangeal joint of 18°, although this did not seem to affect pulp-to-pulp pinch prehension.⁷⁸ In toe-to-finger transplantations, an average total range of motion of 50–60° is usually achievable for the proximal and distal interphalangeal joints.^{60,127} If a metatarsophalangeal joint has been transferred to reconstruct the metacarpophalangeal joint, the expected range of movement should average 50°, or 52° if a composite joint reconstruction has been carried out via a metatarsophalangeal joint disarticulation during harvest.^{12,90}

Strength assessment

In general, an average of more than 75–80% approximation to the opposite thumb has been reported for both grip and pinch strength following thumb reconstruction, in many instances exceeding the strength of its counterpart.^{25,125,128} Independent strength assessment in finger reconstructions is more difficult to measure and is often dependent on an intact thumb function to produce a stable tripod or pulp-to-pulp pinch. The reconstructed finger is also often shorter and may not be accurately assessed using conventional methods of assessment like the traditional dynamometer or pinch meter. These instruments may need to be specially modified to conform to the length and profile of transplanted toes. Furthermore, restoring the prehensile patterns of the hand may be a much more valid measure of outcome and has been achieved in most series, especially following reconstructions for multiple-finger amputations and the metacarpal hand deformity.^{8,20,82,129,130} In addition, from the authors' series of toe transfers for isolated finger amputations, we have also found restoring the digital arcade and storage function of the hand to be useful both functionally and psychologically.^{26,103}



Fig. 14.15 Donor site after combined second- and third-toe harvest in the left foot and second-toe harvest in the right foot.

Appearance and sensory outcomes

A major advantage of toe-to-hand transplantations is the replacement of tissue that bears a near-normal resemblance of what was lost. Both Chung and Wei¹²⁸ and Poppen *et al.*¹²⁵ found a much higher use of the reconstructed hand following toe-to-thumb transplantation as compared to its use before thumb reconstruction. With improved sensory recovery comes an enhanced appreciation of the reconstructed digits and also a better overall integration into the body. These improvements are largely dependent on a comprehensive sensory re-education program as described. Performing the toe-to-hand transplantation surgery within a month of the injury has also been shown to lead to better sensory results.¹²³ Overall, the average recovered two-point discrimination should not be expected to exceed approximately 7–8 mm.^{49,76,107,120}

Donor site outcome evaluation

An evidence-based recommendation of the superiority of a specific type of toe-to-hand transfer is difficult to draw from the perspective of donor site morbidity.¹³¹ Generally, the morbidity is well accepted after isolated second-toe transfer^{34,35,89} (Fig. 14.15). On the other hand, great-toe harvest followed by combined second- and third-toe dissection appear to have more donor site morbidity, but it remains largely acceptable especially when the gain in hand function is taken into consideration.^{132,133} And, in spite of increased dynamic and static loading on the first metatarsal head and heel, this seldom translates into significant complaints regarding gait or appearance⁶⁵ (see Fig. 14.15). Even after 16 years median follow-up, 92% of patients reported no or only minor complaints.⁴⁵

The practice of using non-vascularized bone blocks to replace harvested metatarsal bones and the repair of the metatarsal ligament after toe transfer have been abandoned for a long time, as no problems when walk or take-off have been documented. However, every measure should be taken to ensure additional potential complications such as skin necrosis, hypertrophic scarring, or painful neuroma¹³⁴ are minimized. The potential donor defect should always be discussed in detail with the needs of each patient individualized with regard to lifestyle, hobbies, and concerns regarding appearance.

Complications

The most common complication in the immediate postoperative period is vascular compromise due to vasospasm followed by arterial, and less commonly, venous thrombosis. In our earlier experience, the re-exploration rate was 17.6% with an 89% salvage rate.¹¹² Emergency re-exploration of the anastomosis is warranted following failed bedside measures such as lowering the hand, release of sutures, topical application of warm saline and 2–4% lidocaine, and fluid optimization. In re-exploration, the hematoma is evacuated, the adventitia is sharply excised with free use of warm saline and 2–4% lidocaine if there is vasospasm, and the anastomosis is revised once lumen occlusion is confirmed. Additional anastomoses using another arterial pedicle may be required in certain cases, for example, combined toe units. In some cases of intractable spasm, excision of the spasmodic segment, like that done in thrombotic vessels, and replacing it with vein graft or flow-through venous flap for tension-free closure may become necessary.

Venous compromise is usually treated in the same manner, but it is less critical and does often lead to total toe loss. Despite careful preoperative planning and early recognition of problems, around 3–5% still fail, possibly due to irreparable damage or inherent problems with the suitability of the vessels.^{135,136} Once the cause of the problem is identified, a repeat toe transfer may be indicated with the use of an interim groin flap.¹³⁷ Other complications, including skin flap necrosis or wound-healing problems with resultant exposed structures, must be remedied as soon as possible to prevent desiccation of tendons or neurovascular bundles, which result in further complications from the injury. Longer-term complications may be directly related to the original injury or indirectly as a result of suboptimal reconstruction, often correctable by secondary procedures.

Secondary procedures

Despite meticulous planning and optimization of the technique, secondary procedures are still required in a percentage of cases (14–20%) to improve the functional and aesthetic outcome of the hand and foot following toe-to-hand transplantations.^{40,138,139} Revision procedures for functional improvement such as tenolysis, arthrodesis, and webspace deepening usually yield good results.⁴⁰ Flexor tenolysis is one of the most common secondary procedures described for most series and may be related to the methods of bone osteosynthesis or the severity of the original injury requiring a period of immobilization.^{40,140}

Revision procedures for aesthetic improvement are usually minor, and aim to increase resemblance of the toe to the finger or thumb.^{36,38,141} The most common procedure is a pulp plasty carried out under local anesthesia to reduce the bulbous appearance of the toe, although other procedures including scar revision and flap thinning may be required (Fig. 14.16).

Future directions

Microsurgical toe-to-hand transfer had its principles and techniques well established by the end of 1990s. And, what can be expected from the surgery has become well-known to




Fig. 14.16 (A,B) Pulp plasty technique.

the working reconstructive surgeon today. Nevertheless, there is still room for improvement.

Patient-reported outcomes and evidence-based studies are largely missing; the need for these publications will further determine which toe-to-hand transplantation techniques can provide the highest reward with the least morbidity. Furthermore, preoperative planning for complicated toe-to-hand reconstructions may benefit from 3D printing and computer-aided design and modeling to increase surgical precision and to enhance aesthetics and function.^{142,143}

Robotic surgery could be another potential, and with the advantages of physiological tremor suppression, user-friendly ergonomics, and ultraprecise control of the instruments, ultra partial toe transfer may become feasible with reduction of surgical time and complications.¹⁴⁴



Access the complete reference list online at

<http://www.expertconsult.com>

12. Wei FC, el-Gammal TA, Lin CH, et al. Metacarpal hand: classification and guidelines for microsurgical reconstruction with toe transfers. *Plast Reconstr Surg.* 1997;99:122–128. Metacarpal hand refers to the hand that has lost its prehensile ability through amputation of all fingers with or without amputation of the thumb. Functional restoration can be achieved by a wide variety of microvascular toe transfer techniques. When deciding which procedure should be used, careful consideration must be given to the level of amputation of the fingers as well as the functional status of the remaining thumb. In this article, a classification is proposed for the various patterns of the metacarpal hand along with guidelines for selection of the proper toe transfer procedure.
26. Demirkan F, Wei FC, Jeng SF, et al. Toe transplantation for isolated index finger amputations distal to the proximal interphalangeal joint. *Plast Reconstr Surg.* 1999;103:499–507.
30. Wei FC, Lutz BS, Cheng SL, et al. Reconstruction of bilateral metacarpal hands with multiple-toe transplantations. *Plast Reconstr Surg.* 1999;104:1698–1704.
38. Wei FC, Yim KK. Pulp plasty after toe-to-hand transplantation. *Plast Reconstr Surg.* 1995;96:661–666.
56. Wei FC. Tissue preservation in hand injury: the first step to toe-to-hand transplantation. *Plast Reconstr Surg.* 1998;102:2497–2501. This article gives useful guidelines in the initial management of amputated digits, especially if a preemptive view of future toe-to-hand transplantation is to be considered and discussed with patients. The main recommendations outlined in this editorial emphasize tissue preservation, facilitating future toe-to-hand transplantation in terms of reconstructive options, functional and aesthetic outcomes in the hand, and donor site morbidity in the foot. Although tissue conservation is the main goal at this stage of treatment, this should not be at the expense of tissue viability. If in doubt about management issues, advice should be sought from the reconstructive microsurgery unit.
77. Wei FC, Chen HC, Chuang CC, et al. Microsurgical thumb reconstruction with toe transfer: selection of various techniques. *Plast Reconstr Surg.* 1994;93:345–351, discussion 52–57. This review looked at the established method of thumb reconstruction using different options. Selection of technique requires balancing the patient's functional needs, appearance of the reconstructed thumb, and donor site cosmesis.
- Based on their experience with 103 toe-to-thumb transfers performed over the previous 9 years, this paper attempts to provide guidelines for appropriate selection among the four most commonly employed toe transfer techniques (second toe, total great toe, great toe wrap-around, trimmed great toe) so that both optimal results and patient acceptance can be achieved.
90. Wei FC, Colony LH, Chen HC, et al. Combined second and third toe transfer. *Plast Reconstr Surg.* 1989;84:651–661. This study reported a 4-year experience with 26 consecutive combined second- and third-toe transfers to replace missing adjacent fingers in order to delineate the indications and technical considerations and to emphasize prevention of donor site complications. The surgical technique is described in detail. Combined second- and third-toe transfer is reserved for adjacent finger amputations proximal to the digital webspace with remaining fingers no longer than the small finger. Radial amputations are replaced with contralateral combined toe units, while ipsilateral toes are more ideal for ulnar amputations. When properly applied in selected patients, this single-stage microsurgical procedure can restore prehensile function, improve the appearance of the hand with multiple digital amputations, and preserve near-normal donor foot function.
99. Wei FC, Silverman RT, Hsu WM. Retrograde dissection of the vascular pedicle in toe harvest. *Plast Reconstr Surg.* 1995;96:1211–1214. A retrograde approach to dissection of the vascular pedicle in toe-to-hand transfer is presented, along with a simplified view of the vascular anatomy of the first webspace. This paper described the several advantages of this approach. First, the dominant vascular supply to the toe is elucidated early in the procedure, allowing for less unnecessary dissection of an inadequate pedicle. This also eliminates the need for preoperative arteriography. Furthermore, in cases where a lengthy pedicle is not required, retrograde dissection dispenses with harvest of a proximal vessel, which will not be needed for the transfer, thus minimizing donor morbidity.
119. Lin CH, Lin YT, Sassu P, et al. Functional assessment of the reconstructed fingertips after free toe pulp transfer. *Plast Reconstr Surg.* 2007;120:1315–1321.
121. Wei FC, Ma HS. Delayed sensory reeducation after toe-to-hand transfer. *Microsurgery.* 1995;16:583–585.

References

- Daniel ME, Kleinert H, Lange W, et al. Replantation surgery in China. *Plast Reconstr Surg*. 1973;52:476–489.
- Yang DY, Gu Y. The report of free second toe transfer for thumb reconstruction in 4 cases. *Chin J Surg*. 1977;15:1–3.
- Cobbett JR. Free digital transfer. Report of a case of transfer of a great toe to replace an amputated thumb. *J Bone Joint Surg Br*. 1969;51:677–679.
- Foucher G. Distal replantation. *J Hand Surg Am*. 1986;11:456–457.
- Jaeger SH, Tsai TM, Kleinert HE. Upper extremity replantation in children. *Orthop Clin North Am*. 1981;12:897–907.
- Kleinert HE, Jablon M, Tsai TM. An overview of replantation and results of 347 replants in 245 patients. *J Trauma*. 1980;20:390–398.
- Michon J, Merle M, Bouchon Y, et al. Thumb reconstruction pollicisation or toe-to-hand transfers. A comparative study of functional results. *Ann Chir Main*. 1985;4:98–110.
- Foucher G, ed. *Indications for Reconstruction in Finger Mutilations*. London: Martin Dunitz; 1997.
- Chung KC, Tong L. Use of three free flaps based on a single vascular pedicle for complex hand reconstruction in an electrical burn injury: a case report. *J Hand Surg Am*. 2001;26:956–961.
- Morrison WA. Thumb and fingertip reconstruction by composite microvascular tissue from the toes. *Hand Clin*. 1992;8:537–550.
- Tsubokawa N, Yoshizu T, Maki Y. Long-term results of free vascularized second toe joint transfers to finger proximal interphalangeal joints. *J Hand Surg Am*. 2003;28:443–447.
- Wei FC, el-Gammal TA, Lin CH, et al. Metacarpal hand: classification and guidelines for microsurgical reconstruction with toe transfers. *Plast Reconstr Surg*. 1997;99:122–128. *Metacarpal hand refers to the hand that has lost its prehensile ability through amputation of all fingers with or without amputation of the thumb. Functional restoration can be achieved by a wide variety of microvascular toe transfer techniques. When deciding which procedure should be used, careful consideration must be given to the level of amputation of the fingers as well as the functional status of the remaining thumb. In this article, a classification is proposed for the various patterns of the metacarpal hand along with guidelines for selection of the proper toe transfer procedure.*
- Wei FC, Jain V, Chen SH. Toe-to-hand transplantation. *Hand Clin*. 2003;19:165–175.
- Lee CK, Buncke GM. Great toe-to-thumb microvascular transplantation. *Clin Plast Surg*. 2007;34:223–231, ix.
- May JW Jr, Bartlett SP. Great toe-to-hand free tissue transfer for thumb reconstruction. *Hand Clin*. 1985;1:271–284.
- McCauley RL. Reconstruction of the pediatric burned hand. *Hand Clin*. 2000;16:249–259.
- Whitworth IH, Pickford MA. The first toe-to-hand transfer: a thirty-year follow-up. *J Hand Surg [Br]*. 2000;25:608–610.
- Morrison WA, MacLeod AM, O'Brien BM. Digital reconstruction in the mutilated hand. *Ann Plast Surg*. 1982;9:392–399.
- Wei FC, Chen HC, Chuang CC, et al. Simultaneous multiple toe transfers in hand reconstruction. *Plast Reconstr Surg*. 1988;81:366–377.
- Wei FC, Coessens B, Ganos D. Multiple microsurgical toe-to-hand transfer in the reconstruction of the severely mutilated hand. A series of fifty-nine cases. *Ann Chir Main Memb Supr*. 1992;11:177–187.
- Wei FC, Strauch RJ, Chen HC, et al. Reconstruction of four damaged or destroyed ipsilateral fingers with free toe-to-hand transplantations. *Plast Reconstr Surg*. 1994;93:608–614.
- el-Gammal TA, Wei FC. Microvascular reconstruction of the distal digits by partial toe transfer. *Clin Plast Surg*. 1997;24:49–55.
- Woo SH, Lee GJ, Kim KC, et al. Cosmetic reconstruction of distal finger absence with partial second toe transfer. *J Plast Reconstr Aesthet Surg*. 2006;59:317–324.
- del Pinal F. The indications for toe transfer after “minor” finger injuries. *J Hand Surg [Br]*. 2004;29:120–129.
- Wei FC, el-Gammal TA. Toe-to-hand transfer. Current concepts, techniques, and research. *Clin Plast Surg*. 1996;23:103–116.
- Demirkan F, Wei FC, Jeng SF, et al. Toe transplantation for isolated index finger amputations distal to the proximal interphalangeal joint. *Plast Reconstr Surg*. 1999;103:499–507.
- Iselin M. La main metacarpienne. *Ann Chir Plast*. 1961;6:247–258.
- Foucher G, ed. *Reconstruction in the Mutilated Hand*. London: Martin Dunitz; 1997.
- Kotkansalo T. The functional results of post-traumatic metacarpal reconstructions with microvascular toe transfers. *J Hand Surg Eur Vol*. 2009;34:730–742.
- Wei FC, Lutz BS, Cheng SL, et al. Reconstruction of bilateral metacarpal hands with multiple-toe transplantations. *Plast Reconstr Surg*. 1999;104:1698–1704.
- Shores JT, Brandacher G, Lee WP. Hand and upper extremity transplantation: an update of outcomes in the worldwide experience. *Plast Reconstr Surg*. 2015;135:351e–360e.
- Waljee JF, Chung KC. Toe-to-hand transfer: evolving indications and relevant outcomes. *J Hand Surg Am*. 2013;38:1431–1434.
- del Pinal F, Garcia-Bernal FJ, Delgado J, et al. Overcoming soft-tissue deficiency in toe-to-hand transfer using a dorsalis pedis fasciosubcutaneous toe free flap: surgical technique. *J Hand Surg Am*. 2005;30:111–119.
- Lee DC, Kim JS, Ki SH, et al. Partial second toe pulp free flap for fingertip reconstruction. *Plast Reconstr Surg*. 2008;121:899–907.
- Wei FC, Chen HC, Chuang DC, et al. Second toe wrap-around flap. *Plast Reconstr Surg*. 1991;88:837–843.
- Wei FC, Chen HC, Chuang DC, et al. Aesthetic refinements in toe-to-hand transfer surgery. *Plast Reconstr Surg*. 1996;98:485–490.
- Wei FC, Mardini S. Reevaluation of the technique of toe-to-hand transfer for traumatic digital amputations in children and adolescents. *Plast Reconstr Surg*. 2003;112:1870–1874.
- Wei FC, Yim KK. Pulp plasty after toe-to-hand transplantation. *Plast Reconstr Surg*. 1995;96:661–666.
- Yang JY. The first dorsal metacarpal flap in first webspace and thumb reconstruction. *Ann Plast Surg*. 1991;27:258–264.
- Yim KK, Wei FC. Secondary procedures to improve function after toe-to-hand transfers. *Br J Plast Surg*. 1995;48:487–491.
- del Pinal F, Garcia-Bernal FJ, Regalado J, et al. A technique to improve foot appearance after trimmed toe or hallux harvesting. *J Hand Surg Am*. 2007;32:409–413.
- Schenker M, Kelley SP, Kay SP. Free hand-to-toe transfer: a method to minimise donor-site morbidity in free joint transfers. *Br J Plast Surg*. 2003;56:57–59.
- Bourke G, Kay SP. Free phalangeal transfer: donor-site outcome. *Br J Plast Surg*. 2002;55:307–311.
- Kvernmo HD, Tsai TM. Posttraumatic reconstruction of the hand—a retrospective review of 87 toe-to-hand transfers compared with an earlier report. *J Hand Surg Am*. 2011;36:1176–1181.
- Kotkansalo T, Elo P, Luukkaala T, Vilkkilä SK. Long-term effects of toe transfers on the donor feet. *J Hand Surg Eur Vol*. 2014;39:966–976.
- Nicolandi C. Daumenplastik. *Wien Klin Wochenschr*. 1897;10:663.
- Davis J. Toe to hand transfers: pedochyrodactyloplasty. *Plast Reconstr Surg*. 1964;33:422–436.
- Buncke H, Schulz W. Immediate Nicoladoni procedure in the Rhesus monkey, or hallux-to-hand transplantation, utilising microminiature vascular anastomoses. *J Bone Joint Surg Br*. 1966;19:332–337.
- Whitworth IH, Pickford MA. The first toe-to-hand transfer: a thirty-year follow-up. *J Hand Surg [Br]*. 2000;25:608–610.
- Buncke HJ, Rose EH. Free toe-to-fingertip neurovascular flaps. *Plast Reconstr Surg*. 1979;63:607–612.
- Koshima I, Soeda S, Takase T, et al. Free vascularized nail grafts. *J Hand Surg Am*. 1988;13:29–32.
- O'Brien B, Brennen MD, MacLeod AM. Microvascular free toe transfer. *Clin Plast Surg*. 1978;5:223–237.
- Gilbert A. Toe transfers for congenital hand defects. *J Hand Surg Am*. 1982;7:118–124.

54. Cooney WP 3rd, Wood MB. Microvascular reconstruction of congenital anomalies and post-traumatic lesions in children. *Hand Clin.* 1992;8:131–146.
55. Wallace CG, Wei FC. Posttraumatic finger reconstruction with microsurgical transplantation of toes. *Hand Clin.* 2007;23:117–128.
56. Wei FC. Tissue preservation in hand injury: the first step to toe-to-hand transplantation. *Plast Reconstr Surg.* 1998;102:2497–2501. *This article gives useful guidelines in the initial management of amputated digits, especially if a preemptive view of future toe-to-hand transplantation is to be considered and discussed with patients. The main recommendations outlined in this editorial emphasize tissue preservation, facilitating future toe-to-hand transplantation in terms of reconstructive options, functional and aesthetic outcomes in the hand, and donor site morbidity in the foot. Although tissue conservation is the main goal at this stage of treatment, this should not be at the expense of tissue viability. If in doubt about management issues, advice should be sought from the reconstructive microsurgery unit.*
57. Fan CY, Jiang J, Zeng BF, et al. Reconstruction of thumb loss complicated by skin defects in the thumb-index webspace by combined transplantation of free tissues. *J Hand Surg Am.* 2006;31:236–241.
58. Zhang J, Xie Z, Lei Y, et al. Free second toe one-stage-plasty and transfer for thumb or finger reconstruction. *Microsurgery.* 2008;28:25–31.
59. Yim KK, Wei FC. Intraosseous wiring in toe-to-hand transplantation. *Ann Plast Surg.* 1995;35:66–69.
60. Strauch RJ, Wei FC, Chen SH. Composite finger metacarpophalangeal joint reconstruction in combined second and third free toe-to-hand transfers. *J Hand Surg Am.* 1993;18:972–977.
61. Mardini S, Wei FC. Unilateral and bilateral metacarpal hand injuries: classification and treatment guidelines. *Plast Reconstr Surg.* 2004;113:1756–1759.
62. Harris C Jr, Rutledge GL Jr. The functional anatomy of the extensor mechanism of the finger. *J Bone Joint Surg Am.* 1972;54:713–726.
63. Wei F, ed. *Toe to Hand Transplantations.* Philadelphia: Churchill Livingstone; 2007.
64. Piza-Katzer H. Analysis of complications in digital vein grafts. *Chir Plastica (Berl).* 1979;5:23–32.
65. Wei F, ed. *Toe to Hand Transplantations.* Philadelphia: Churchill Livingstone; 2005.
66. Bhama PK, Patel SA, Khan U, et al. Head and neck free flap reconstruction in patients older than 80 years. *J Reconstr Microsurg.* 2014;30:523–530.
67. Dellon AL. Sensory recovery in replanted digits and transplanted toes: a review. *J Reconstr Microsurg.* 1986;2:123–129.
68. Godina M. Early microsurgical reconstruction of complex trauma of the extremities. *Plast Reconstr Surg.* 1986;78:285–292.
69. Woo SH, Kim JS, Seul JH. Immediate toe-to-hand transfer in acute hand injuries: overall results, compared with results for elective cases. *Plast Reconstr Surg.* 2004;113:882–892.
70. Woo SH, Lee GJ, Kim KC, et al. Immediate partial great toe transfer for the reconstruction of composite defects of the distal thumb. *Plast Reconstr Surg.* 2006;117:1906–1915.
71. Yim KK, Wei FC, Lin CH. A comparison between primary and secondary toe-to-hand transplantation. *Plast Reconstr Surg.* 2004;114:107–112.
72. American Medical Association. *Guides to the Evaluation of Permanent Impairment.* Chicago: American Medical Association; 1990:14–55.
73. Morrison WA. Thumb reconstruction: a review and philosophy of management. *J Hand Surg [Br].* 1992;17:383–390.
74. Strickland W, ed. *Thumb Reconstruction.* Philadelphia: Churchill Livingstone; 2005.
75. Leung PC. Thumb reconstruction using second-toe transfer. *Hand Clin.* 1985;1:285–295.
76. Morrison WA, O'Brien BM, MacLeod AM. Experience with thumb reconstruction. *J Hand Surg [Br].* 1984;9:223–233.
77. Wei FC, Chen HC, Chuang CC, et al. Microsurgical thumb reconstruction with toe transfer: selection of various techniques. *Plast Reconstr Surg.* 1994;93:345–351, discussion 52–57. *This review looked at the established method of thumb reconstruction using different options. Selection of technique requires balancing the patient's functional needs, appearance of the reconstructed thumb, and donor site cosmesis. Based on their experience with 103 toe-to-thumb transfers performed over the previous 9 years, this paper attempts to provide guidelines for appropriate selection among the four most commonly employed toe transfer techniques (second toe, total great toe, great toe wrap-around, trimmed great toe) so that both optimal results and patient acceptance can be achieved.*
78. Wei FC, Chen HC, Chuang CC, et al. Reconstruction of the thumb with a trimmed-toe transfer technique. *Plast Reconstr Surg.* 1988;82:506–515.
79. Morrison WA, O'Brien BM, MacLeod AM. Thumb reconstruction with a free neurovascular wrap-around flap from the big toe. *J Hand Surg Am.* 1980;5:575–583.
80. Ratcliffe RJ, McGrouther DA. Free toe pulp transfer in thumb reconstruction. Experience in the West of Scotland Regional Plastic Surgery Unit. *J Hand Surg [Br].* 1991;16:165–168.
81. Lin CH, Lo S, Lin CH, Lin YT. Opponensplasty provides predictable opposable tripod pinch in toe transfer for proximal thumb ray defect reconstruction. *Plast Reconstr Surg.* 2012;130:810e–818e.
82. Wei FC, Epstein MD, Chen HC, et al. Microsurgical reconstruction of distal digits following mutilating hand injuries: results in 121 patients. *Br J Plast Surg.* 1993;46:181–186.
83. Brown RE, Zook EG, Russell RC. Fingertip reconstruction with flaps and nail bed grafts. *J Hand Surg Am.* 1999;24:345–351.
84. Cheng G, Fang G, Hou S, et al. Aesthetic reconstruction of thumb or finger partial defect with trimmed toe-flap transfer. *Microsurgery.* 2007;27:74–83.
85. Logan A, Elliot D, Foucher G. Free toe pulp transfer to restore traumatic digital pulp loss. *Br J Plast Surg.* 1985;38:497–500.
86. del Pinal F, Herrero F, Garcia-Bernal FJ, et al. Minimizing impairment in laborers with finger losses distal to the proximal interphalangeal joint by second toe transfer. *Plast Reconstr Surg.* 2003;112:1000–1011.
87. Foucher G, Merle M, Maneaud M, et al. Microsurgical free partial toe transfer in hand reconstruction: a report of 12 cases. *Plast Reconstr Surg.* 1980;65:616–627.
88. Wei FC, Colony LH. Microsurgical reconstruction of opposable digits in mutilating hand injuries. *Clin Plast Surg.* 1989;16:491–504.
89. Buncke G, ed. *Lengthening by Toe Transfer.* London: Martin Dunitz; 1997.
90. Wei FC, Colony LH, Chen HC, et al. Combined second and third toe transfer. *Plast Reconstr Surg.* 1989;84:651–661. *This study reported a 4-year experience with 26 consecutive combined second- and third-toe transfers to replace missing adjacent fingers in order to delineate the indications and technical considerations and to emphasize prevention of donor site complications. The surgical technique is described in detail. Combined second- and third-toe transfer is reserved for adjacent finger amputations proximal to the digital webspace with remaining fingers no longer than the small finger. Radial amputations are replaced with contralateral combined toe units, while ipsilateral toes are more ideal for ulnar amputations. When properly applied in selected patients, this single-stage microsurgical procedure can restore prehensile function, improve the appearance of the hand with multiple digital amputations, and preserve near-normal donor foot function.*
91. Buck-Gramcko D, ed. *The Metacarpal Hand.* London: Martin Dunitz; 1997.
92. Pulvertaft RG. Reconstruction of the mutilated hand. Erik Moberg Lecture 1977. *Scand J Plast Reconstr Surg.* 1977;11:219–224.
93. Pulvertaft RG. Reconstruction of the severely mutilated hand. *Rheumatol Phys Med.* 1971;11:90.
94. Leung PC. Double toe transfers. *J Hand Surg [Br].* 1987;12:162–165.
95. Leung PC. Pincer reconstruction using second toe transplantation. *J Hand Surg [Br].* 1987;12:159–161.
96. Lin CH, Mardini S, Lin YT, et al. Osteoplastic thumb ray restoration with or without secondary toe transfer for

- reconstruction of opposable basic hand function. *Plast Reconstr Surg*. 2008;121:1288–1297.
97. Leung PC, Wong WL. The vessels of the first metatarsal webspace. An operative and radiographic study. *J Bone Joint Surg Am*. 1983;65:235–238.
 98. Gu YD, Zhang GM, Chen DS, et al. Vascular anatomic variations in second toe transfers. *J Hand Surg Am*. 2000;25:277–281.
 99. Wei FC, Silverman RT, Hsu WM. Retrograde dissection of the vascular pedicle in toe harvest. *Plast Reconstr Surg*. 1995;96:1211–1214. A retrograde approach to dissection of the vascular pedicle in toe-to-hand transfer is presented, along with a simplified view of the vascular anatomy of the first webspace. This paper described the several advantages of this approach. First, the dominant vascular supply to the toe is elucidated early in the procedure, allowing for less unnecessary dissection of an inadequate pedicle. This also eliminates the need for preoperative arteriography. Furthermore, in cases where a lengthy pedicle is not required, retrograde dissection dispenses with harvest of a proximal vessel, which will not be needed for the transfer, thus minimizing donor morbidity.
 100. Cheng MH, Wei FC, Santamaria E, et al. Single versus double arterial anastomoses in combined second- and third-toe transplantation. *Plast Reconstr Surg*. 1998;102:2408–2412, discussion 13.
 101. Zhang G, Ju J, Zhao Q, et al. Combined ipsilateral and contralateral second toe flaps for repair of finger degloving injury. *Microsurgery*. 2014;34:540–546.
 102. Zhao J, Tien HY, Abdullah S, Zhang Z. Aesthetic refinements in second toe-to-thumb transfer surgery. *Plast Reconstr Surg*. 2010;126:2052–2059.
 103. Wei FC, Coskunfirat OK, Lin CH, et al. Isolated third-toe transfer: indications, technique, and reliability. *Plast Reconstr Surg*. 2005;115:1314–1321, discussion 22–24.
 104. Lee KS, Chae JJ, Hahn SB. Thumb reconstruction with a free neurovascular wrap-around flap from the big toe: long-term follow-up of thirty cases. *Microsurgery*. 1995;16:692–697.
 105. Strauch B, Tsur H. Restoration of sensation to the hand by a free neurovascular flap from the first webspace of the foot. *Plast Reconstr Surg*. 1978;62:361–367.
 106. Halbert CF, Wei FC. Neurosensory free flaps. Digits and hand. *Hand Clin*. 1997;13:251–262.
 107. Kato H, Ogino T, Minami A, et al. Restoration of sensibility in fingers repaired with free sensory flaps from the toe. *J Hand Surg Am*. 1989;14:49–54.
 108. Lin CH, Hu TL, Lin CH. Split second- and third-toe transplantation in mutilating-hand-injury reconstruction. *Ann Plast Surg*. 2008;60:267–271.
 109. Swartz WM, Izquierdo R, Miller MJ. Implantable venous Doppler microvascular monitoring: laboratory investigation and clinical results. *Plast Reconstr Surg*. 1994;93:152–163.
 110. Jones NF, Gupta R. Postoperative monitoring of pediatric toe-to-hand transfers with differential pulse oximetry. *J Hand Surg Am*. 2001;26:525–529.
 111. Chen KT, Mardini S, Chuang DC, et al. Timing of presentation of the first signs of vascular compromise dictates the salvage outcome of free flap transfers. *Plast Reconstr Surg*. 2007;120:187–195.
 112. Lin YT, Su ST, Lo S, et al. Risk factors for reexploration in toe-to-hand transfer: a multivariate analysis of 363 cases. *Plast Reconstr Surg*. 2015;135:501–506.
 113. Hauck RM, Camp L, Ehrlich HP, et al. Pulp nonfiction: microscopic anatomy of the digital pulp space. *Plast Reconstr Surg*. 2004;113:536–539.
 114. Efsthathopoulos D, Gerostathopoulos N, Misitzis D, et al. Clinical assessment of primary digital nerve repair. *Acta Orthop Scand Suppl*. 1995;264:45–47.
 115. Rosen B, Lundborg G. Sensory re-education after nerve repair: aspects of timing. *Handchir Mikrochir Plast Chir*. 2004;36:8–12.
 116. Lundborg G, Rosen B. Sensory relearning after nerve repair. *Lancet*. 2001;358:809–810.
 117. Ma HS, Abdalla el-Gammal T, Wei FC. Current concepts of toe-to-hand transfer: surgery and rehabilitation. *J Hand Ther*. 1996;9:41–46.
 118. Deglise B, Botta Y. Microsurgical free toe pulp transfer for digital reconstruction. *Ann Plast Surg*. 1991;26:341–346.
 119. Lin CH, Lin YT, Sassu P, et al. Functional assessment of the reconstructed fingertips after free toe pulp transfer. *Plast Reconstr Surg*. 2007;120:1315–1321.
 120. Wei FC, Carver N, Lee YH, et al. Sensory recovery and Meissner corpuscle number after toe-to-hand transplantation. *Plast Reconstr Surg*. 2000;105:2405–2411.
 121. Wei FC, Ma HS. Delayed sensory reeducation after toe-to-hand transfer. *Microsurgery*. 1995;16:583–585.
 122. Chen CJ, Liu HL, Wei FC, et al. Functional MR imaging of the human sensorimotor cortex after toe-to-finger transplantation. *AJNR Am J Neuroradiol*. 2006;27:1617–1621.
 123. Chu NS, Wei FC. Recovery of sensation and somatosensory evoked potentials following toe-to-digit transplantation in man. *Muscle Nerve*. 1995;18:859–866.
 124. Foucher G, Medina J, Navarro R, et al. Toe transfer in congenital hand malformations. *J Reconstr Microsurg*. 2001;17:1–7.
 125. Poppen NK, Norris TR, Buncke HJ Jr. Evaluation of sensibility and function with microsurgical free tissue transfer of the great toe to the hand for thumb reconstruction. *J Hand Surg Am*. 1983;8:516–531.
 126. Gu YD, Zhang GM, Cheng DS, et al. Free toe transfer for thumb and finger reconstruction in 300 cases. *Plast Reconstr Surg*. 1993;91:693–700, discussion 1–2.
 127. Wei FC, Yim KK. Single third-toe transfer in hand reconstruction. *J Hand Surg Am*. 1995;20:388–394, discussion 95–96.
 128. Chung KC, Wei FC. An outcome study of thumb reconstruction using microvascular toe transfer. *J Hand Surg Am*. 2000;25:651–658.
 129. Fumiaki S, Wei FC, Sassu P, et al. Multiple toe transplantations to reconstruct three amputated neighbouring distal fingers by heat press injury – a case report. *J Plast Reconstr Aesthet Surg*. 2009;62:e309–e313.
 130. Coskunfirat OK, Wei FC, Lin CH, et al. Simultaneous double second toe transfer for reconstruction of adjacent fingers. *Plast Reconstr Surg*. 2005;115:1064–1069.
 131. Lin PY, Sebastin SJ, Ono S, et al. A systematic review of outcomes of toe-to-thumb transfers for isolated traumatic thumb amputation. *Hand (N Y)*. 2011;6:235–243.
 132. Stupka JV, Hya P, Molitor M, et al. Long-term results of digital reconstruction using toe-to-finger transfers. *Eur J Plast Surg*. 2004;27:271–282.
 133. Gülgönen A, Gudemez E. Toe-to-hand transfers: more than 20 years follow-up of five post-traumatic cases. *J Hand Surg [Br]*. 2005;31:2–8.
 134. Maloney CT Jr, DeJesus R, Dellon AL. Painful foot neuromas after toe-to-thumb transfer. *J Hand Surg Am*. 2005;30:105–110.
 135. Del Pinal F, Garcia-Bernal FJ, Ayala H, et al. Ischemic toe encountered during harvesting: report of 6 cases. *J Hand Surg Am*. 2008;33:1820–1825.
 136. Gu YD, Zhang GM, Chen DS, et al. Toe-to-hand transfer: an analysis of 14 failed cases. *J Hand Surg Am*. 1993;18:823–827.
 137. Ozkan O, Chen HC, Mardini S, et al. Principles for the management of toe-to-hand transfer in reexploration: toe salvage with a tubed groin flap in the last step. *Microsurgery*. 2006;26:100–105.
 138. Jones NF, Hansen SL, Bates SJ. Toe-to-hand transfers for congenital anomalies of the hand. *Hand Clin*. 2007;23:129–136.
 139. Foucher G, Moss AL. Microvascular second toe to finger transfer: a statistical analysis of 55 transfers. *Br J Plast Surg*. 1991;44:87–90.
 140. Lister GD, Kalisman M, Tsai TM. Reconstruction of the hand with free microvascular toe-to-hand transfer: experience with 54 toe transfers. *Plast Reconstr Surg*. 1983;71:372–386.
 141. Wallace CG, Wei FC. Further aesthetic refinement for great toe transfers. *J Plast Reconstr Aesthet Surg*. 2010;63:e109–e110.

142. Tan H, Yang K, Wei P, et al. A novel preoperative planning technique using a combination of CT angiography and three-dimensional printing for complex toe-to-hand reconstruction. *J Reconstr Microsurg*. 2015;31:369–377.
143. Wang L, Tian G, Wang M, Yang G. Analysis of the morphologic differences of the second toe and digits of the hand, and evaluation of potential surgical intervention to minimize the differences using computer-aided design technology. *Plast Reconstr Surg*. 2014;134:902e–912e.
144. Maire N, Naito K, Lequint T, et al. Robot-assisted free toe pulp transfer: feasibility study. *J Reconstr Microsurg*. 2012;28:481–484.

15

Benign and malignant tumors of the hand

Justin M. Sacks, Kodi K. Azari, Scott Oates, and David W. Chang

SYNOPSIS

- Benign and malignant tumors of the hand arise from distinct tissue types.
- The majority of these tumors are benign.
- Accurate assessment, diagnosis, and treatment will optimize clinical outcomes.
- Reconstructive procedures of the hand and upper extremity should be performed only after the diagnosis is confirmed and appropriate surgical margins are achieved.

Introduction

- Most tumors of the hand are benign, recognized early, and treated by excision.
- Ninety-five percent of hand tumors that do not involve the skin are benign.
- Malignant tumors of the hand can be divided into two categories: primary and metastatic. Primary tumors can arise from the skin (e.g., melanoma, basal and squamous cell carcinoma), soft tissues (e.g., sarcoma), or bone (e.g., osteosarcoma). Metastatic disease originates most commonly from cancers of the breast, kidney, thyroid, lung, and colon.
- Appropriate evaluation, diagnosis, and treatment for tumors of the hand are required for optimal patient care. A careful history and physical examination will rapidly focus the investigation of a suspicious mass found in the hand.
- Magnetic resonance imaging (MRI) has become the “gold standard” to evaluate soft-tissue masses for malignancy. Computed tomography (CT) is preferred for osseous lesions.
- Incisional or excisional biopsy is required for definitive diagnosis in many cases.

- Surgical incisions must be planned carefully with definitive surgery in mind, utilizing a longitudinal incision in line with or parallel to a potential limb salvage procedure.
- Reconstructive procedures, in the setting of a neoplasm of the hand, are performed only after the final pathological diagnosis and clear resection margins are established.
- An understanding of both oncologic and reconstructive principles is required in order to achieve an optimal clinical outcome.

Clinical tips

Most hand tumors:

- arise from any cell type
- are benign
- are treated with a favorable prognosis

When in doubt:

- excisional biopsy
- plan incisions carefully
- definitive surgery in mind

Basic science/disease process

Tumors of the hand can arise from the skin, adipose tissue, synovium, tendons, cartilage, bones, muscles, fibrous tissue, nerves, and blood vessels. The majority of hand tumors are benign, most are recognized early, and the prognosis is typically good.^{1,2} Malignant tumors also occur in the hand and can be divided into two categories: primary and metastatic. In addition, premalignant lesions such as actinic keratoses and atypical nevi can occur on the hands.

In this chapter, benign and malignant tumors are classified and discussed by their tissues of origin. Understanding the origin of hand lesions will assist in accurate diagnosis and appropriate therapeutic interventions.³

The management of hand tumors requires the hand surgeon to function as both oncologic surgeon and reconstructive surgeon. A complete understanding of both oncologic and reconstructive principles is therefore required to achieve an optimal outcome. The role of the oncologic surgeon is to eradicate the tumor completely, which can compromise both aesthetics and function. In contrast, the role of the reconstructive surgeon is to optimize hand function. Balancing these sometimes competing goals can be challenging.⁴

An effective strategy to evaluate, diagnose, and treat tumors of the hand and associated upper extremity is required for optimal patient care. A careful analysis of the history and physical examination will rapidly focus the investigation of a newly evident hand lesion. The use of radiography (X-rays), CT, and MRI will strengthen the apparent diagnosis.⁵ However, incisional or excisional biopsy will, in most instances, be the final determinant of diagnosis.

Diagnosis/patient presentation

Patient history

A thorough history and physical examination remain the foundation of proper initial diagnosis. Questions concerning the history of the tumor are solicited. These include duration, changes in size or color, associated pain, and occurrence of ulceration. Pain can signify a malignancy or a mass that has encroached on neurologic structures. The sensitivity of the mass to cold or heat needs to be clarified, as the former typifies a subungual glomus tumor.⁶

Inquiring about risk factors for tumors of the hand will strengthen eventual diagnostic conclusions. The patient should be questioned about a history of cutaneous malignancies, extensive sun exposure or sunburns as a child, chemical and ionizing radiation exposure, and trauma or infections. The patient should also be questioned about rheumatologic conditions, such as gout, psoriasis, and rheumatoid arthritis.

The age of the patient needs to be considered when evaluating a mass in the hand. Certain masses are specific to certain age groups. For instance, bone cysts are typically seen in adolescents and young adults, whereas metastatic tumors in the hand are rare under the age of 50 years.⁷

Questions about previous biopsies or excisions will complete a thorough historical evaluation of the patient with a hand tumor. Pathology reports for previous biopsies or excisions will need to be obtained and reviewed. Prior operative reports will help clarify the diagnosis and optimize future surgical interventions in instances in which the current pathology is unknown.

Clinical tips

History

Past medical history:

- rheumatoid arthritis – rheumatoid nodule
- gout – tophus

Pain: suggestive of malignancy

Cold sensitivity: subungual lesion – glomus tumor

Pain relieved by NSAIDs: osteoid osteoma

Infections

Trauma

Physical examination

The physical examination of the hand involves a complete examination of the skin, tendons, muscles, ligaments, bones, and neurovascular structures. An evaluation of the regional lymph nodes for adenopathy is the cornerstone for assessing the malignant potential of a hand mass. For example, adenopathy can be observed in epithelioid or clear cell sarcomas.^{8,9}

An inspection of the lesion begins in the examination room. An adequate light source is essential to visualize the lesion's characteristics. Color and texture changes are noted, and an examination for ulcerations, erythema, and edema is performed. Transillumination of the mass can be helpful in distinguishing between solid and cystic etiologies. The lesion is palpated, and the mass size is appreciated along with its shape and contour. The mobility of the mass is assessed to determine whether it is fixed to underlying anatomic structures. Having the patient flex and extend the fingers and wrist will further delineate whether the lesion is associated with tendons or deeper structures within the joints. A complete vascular examination with palpation of pulses is required. If pulses are not palpable, Doppler ultrasonography can be used to define the vascular status of the hand and upper extremity. Allen's test is mandatory. Neurologic testing of fine and gross motor and sensory function is also performed.

When benign lesions are to be followed clinically, photographic documentation is an essential tool to judge the rate of growth over time. Photographs are also recommended for patients with multiple and subtle lesions.

Laboratory studies

Laboratory studies are helpful in determining the etiology of some hand tumors. A hematology profile can determine an infectious etiology. Serum calcium, phosphorus, and alkaline phosphatase levels are often increased in patients with metastatic tumors, and alkaline phosphatase is also increased in patients with osteosarcoma. An erythrocyte sedimentation rate assesses for inflammation; the rate is often increased in Ewing's sarcoma, lymphoma, and myeloma. An extremely elevated prostate-specific antigen level is specific for metastatic prostate cancer. In male patients older than 50 years with evidence of blastic hand lesions on X-rays, a serum prostate-specific antigen test should be performed. Although these laboratory findings are not specific for hand tumors, they can help focus the search for a diagnosis.

Clinical tips

Laboratory tests

- Increased ESR: Ewing's sarcoma, lymphoma, myeloma
- Increased Ca^{++} : metastatic tumors
- Increased alkaline phosphatase: osteosarcoma
- Males, age >50, and blastic bone lesions: check PSA

Imaging

Multiple radiologic modalities are available for imaging benign and malignant hand lesions and masses. Radiographs are not essential for most skin lesions. However, radiographs are required for very large skin lesions and for those apparently

fixed to underlying anatomic structures based upon physical examination.

The plain X-ray is one of the most important studies for evaluating lesions and masses of the hand. X-rays are easily obtained and can evaluate a mass from multiple angles. The size of the mass can be inferred from X-rays. In the hand, a mass >3 cm in diameter should be considered potentially malignant. The architecture of the mass as it relates to the cortex of the associated bone can be determined rapidly by X-ray. Sharp cortical margins indicate a benign process, while a “moth-eaten” or destroyed cortex indicates a malignant process. Erosions and periosteal elevation on X-rays can signify a potential malignancy or an infectious process. Soft-tissue calcifications may signify a malignancy (Fig. 15.1). Rounded calcifications with central lucencies can portend a vascular etiology.

Ultrasonography can be helpful in assessing soft-tissue masses. This technique is non-invasive and inexpensive. Ultrasonography can determine if a tumor is solid or cystic and differentiate between a discrete mass and diffuse edema. In many instances, ultrasonography can be used to guide needle biopsy.

Scintigraphy or bone scanning is beneficial in screening for skeletal masses. This technique is sensitive in isolating abnormalities, but the findings are not very specific for malignancy. For example, there is intense uptake with osteoid osteoma, a benign bone tumor. Bone scans are very helpful when searching for sources of metastasis in the workup of hand and upper extremity primary malignancies.



Fig. 15.1 In this proximal phalanx lesion of the thumb a destroyed cortex potentially indicates a malignant process.

CT is extremely useful for the assessment of bones and cortical destruction. CT scans have markedly greater bony resolution than standard radiographs. If bone involvement by the mass is equivocal on X-rays, CT is the next appropriate radiographic modality. CT also distinguishes calcification patterns from ossification and is superior in assessing periosteal versus endosteal reactions.

MRI is superior to CT for the evaluation of soft-tissue masses. MRI is better able to assess the intra- and extraosseous extent of soft-tissue masses. It has become the gold standard to evaluate soft-tissue masses for malignancy.¹⁰ The MRI study should include T1-weighted, fat-suppressed T2-weighted, and short tau inversion recovery images. The contrast agent gadolinium can further enhance the visualization of soft-tissue tumors. An MRI study obtained with various views can clearly delineate the extent of soft-tissue involvement prior to operative intervention. A drawback of MRI is that it cannot reliably distinguish between benign and malignant processes. In addition, for MRI of hand masses, a dedicated hand coil is required.

The next logical progression in the workup of a skin, soft-tissue, or bony lesion is a biopsy. The accuracy of pathologic assessment is dependent on the type of specimen obtained. A frozen-section analysis can be performed to assess the adequacy of the tissue sample. However, the accuracy of frozen-section diagnosis is only 80%, whereas permanent-section diagnosis is accurate 96% of the time. The accuracy of core needle biopsy is intermediate between the two, at 83–93%.²

A biopsy can be closed or open. In a closed biopsy, a needle or trephine is used to obtain samples. Closed biopsy is useful for metastatic workup. However, tissue samples from closed biopsy are often inadequate for initial diagnosis.¹¹

Open biopsies can take many forms: the type of open biopsy performed is determined by the patient's history, physical findings, and imaging findings. For all open biopsies, longitudinal incisions should be in line with or parallel to incisions that would be used in a later limb salvage procedure if the tumor proves to be malignant. If a tourniquet is used, the upper extremity must not be exsanguinated because doing so may cause spread of malignant cells into the lymphatics. Proper hemostasis should be maintained, and adjacent anatomic compartments should not be violated unless a radical excision is required. An important tenet is to biopsy all infections and culture all masses.^{3,12} Chronic infections can masquerade as malignancies, and masses can result from subclinical infections.

In an incisional biopsy, only a piece of the lesion is removed. A longitudinal incision is made; if soft-tissue masses invade adjacent compartments, muscle fibers are split longitudinally. A piece of the lesion is then excised for pathological diagnosis.

An excisional biopsy removes the entire lesion and is potentially a single-stage cure for a benign lesion. Excisional biopsy is limited to lesions ≤1 cm.

Enneking developed a method for musculoskeletal tumor dissection based on the histologic grade, location, and extent of the mass. An intralesional dissection is through the plane of the tumor, whereas a marginal dissection is through the tumor “reactive zone”. A wide dissection involves removal of the mass plus a margin of normal tissue but remains within a single compartment.¹² A wide dissection is performed when there is a suspicion of malignancy. A radical dissection involves extracompartmental resection.

Clinical tips

Imaging studies

X-ray

- Most important study
- Margin appearance
 - Sharp margins: benign
 - “Moth-eaten”: malignant
- Size
 - Size >6 cm: malignant

Patient selection

All patients with a lesion or a mass of the hand must be appropriately evaluated. A history and physical examination are critical to determining what further workup is needed. Once the process needed to investigate the lesion or mass is determined, it is then the physician's responsibility to determine the appropriate diagnosis and plan the treatment.

Treatment/surgical treatment by tissue of origin

Skin tumors

Neoplasms of the skin can be benign, premalignant, or malignant. In addition, there are masses such as sebaceous cysts and cutaneous horns that can masquerade as tumors but are not true neoplasms and thus are considered pseudotumors.¹³ For the majority of benign neoplasms or tumors, an excisional biopsy will completely eradicate the mass. For malignant skin neoplasms, such as melanoma, complete excision with clear margins does not always correlate with complete eradication of the skin tumor because of the potential for metastatic spread.¹

Clinical box

Incisional biopsy

- Longitudinal incision
- Tourniquet, do not exsanguinate
- Avoid violating adjacent compartments
- Split muscle fibers longitudinally
- Frozen section to assess adequacy of sample
- Cultures
- “Biopsy all infections. Culture all masses.”

Cutaneous horn

A cutaneous horn is an exophytic lesion that originates from the skin and is composed of keratotic material (Fig. 15.2).¹³ Cutaneous horns are located on sun-exposed areas of the body such as the dorsum of the hands and forearms. These unsightly lesions can interfere with function. They can occur



Fig. 15.2 Cutaneous horn. The lesion typically presents on the palmar surface of the hand. This lesion represents the typical keratin horn.

in association with a variety of tumors, including epidermal inclusion cysts, epidermal nevi, fibromas, and pyogenic granulomas. In addition, cutaneous horns can be associated with both premalignant and malignant neoplasms such as actinic keratoses and squamous cell carcinomas. In fact, 10% of cutaneous horns are found in association with squamous cell carcinoma.

Cutaneous horns are treated by excisional biopsy with 1–2-mm margins. Incisional biopsy is not recommended for this lesion because of the potential for sampling errors.²

Epidermal inclusion cyst

Epidermal inclusion cysts are the third most common hand tumors (Fig. 15.3). These masses, which originate from an



Fig. 15.3 Epidermal inclusion cyst. These masses, which originate from an invagination of epithelium, can follow trauma, injection, or an incision. The epithelium is internalized, resulting in subcutaneous keratin deposition.

invagination of epithelium, can follow a trauma, injection, or incision.^{2,14} The epithelium is internalized, resulting in subcutaneous keratin deposition. Epithelial cysts are typically painless and most commonly occur in the digits.

Treatment of an epidermal inclusion cyst involves a complete marginal excision of the cyst and its wall. The risk of recurrence of this lesion following complete excisional biopsy is extremely low.

Sebaceous cyst

A sebaceous cyst is another lesion originating from the skin and is similar in appearance to an epidermal inclusion cyst (Fig. 15.4). Sebaceous cysts arise from an obstructed apocrine gland, which produces sebum as opposed to keratin.² When they occur in the hand, sebaceous cysts are found on the dorsal aspect. Palmar skin does not contain sebaceous glands, so sebaceous cysts do not appear there. Treatment is similar to that of an inclusion cyst, and the risk of recurrence is low.

Verruca vulgaris

The human papillomavirus causes verruca vulgaris or common warts (Fig. 15.5). Types 1–4, 7, and 10 have been implicated in the etiology of skin lesions involving keratinized epithelium. Verruca vulgaris presents as a rough raised surface anywhere on the hand and is 20 times more common than the verruca plana or flat wart, which is found commonly on the dorsum of the hand. Verrucae vulgaris are often found at sites of trauma in the periungual region (such as from habitual nail biting). The typical course of these benign neoplasms is self-limited, with spontaneous resolution in 1–2 years. However, there have been reports of malignant transformation of verrucae vulgaris, most commonly when they occur on the mucosa.¹⁵

Treatment is instituted if the lesions become cosmetically unacceptable or if they interfere with hand function. The first-line therapy is topical agents such as salicylic acid, which results in cure rates of 70–80%. Cryotherapy is considered the



Fig. 15.5 Verruca vulgaris. This lesion presents as a rough raised surface commonly on the dorsum of the hand.

second-line therapy for lesions unresponsive to topical agents and offers cure rates of 60–80%. Third-line treatments include immunomodulatory agents, lasers such as carbon dioxide and pulsed dye, and photodynamic therapy. It is critical to be highly suspicious of lesions that do not respond to therapy, as they may be malignant. Excision is therefore recommended for treatment-refractory verrucae or to rule out malignancy.

Nevi

A melanocytic nevus or benign pigmented nevus is a benign proliferation of melanocytes (Fig. 15.6). Nevi can be either acquired or congenital. The acquired form typically begins to appear 6 months after birth, and acquired nevi increase in both number and size throughout childhood and adolescence. Congenital nevi require surveillance because of the potential for malignant transformation. Nevi are classified by size as small (<1.5 cm), medium (1.5 cm to <20 cm), and large or giant (>20 cm). The lifetime risk for malignant transformation of giant congenital nevi is 10%.¹⁶

Common acquired nevi are defined by their anatomic location within the epidermis and dermis. Junctional nevi are found at the dermal–epidermal junction. These lesions transform into compound nevi when their growth extends into the dermis. Nevi found completely within the dermis are termed intradermal nevi. Acral nevi are typically found on the palmar or plantar surfaces. Longitudinal melanonychia refers to streaking of the nail secondary to melanin deposits in the nail plate; these lesions can result from acral nevi involving the nail matrix.

Nevi of the hand and upper extremity should be evaluated for any clinically suspicious changes. These include asymmetry, border irregularities, color changes, diameter >6 mm, or elevation of the lesion. A useful mnemonic for these changes is “ABCDE”. When there is any doubt about diagnosis, excisional biopsy is recommended.¹⁷

Keratoacanthoma

Keratoacanthoma is thought to be derived from the epithelium of hair follicles (Fig. 15.7). This skin lesion closely resembles



Fig. 15.4 Sebaceous cyst. These pseudotumors arise from an obstructed apocrine gland, which produces sebum as opposed to keratin.



Fig. 15.6 Nevus. A benign proliferation of melanocytes, either acquired or congenital.

squamous cell carcinoma. However, keratoacanthoma growth is more rapid and central necrosis is more dominant. These lesions are typically found on hair-bearing regions. A keratoacanthoma begins as a small red papule and progresses to a large ulcerated mass. This mass is “volcano”-shaped, with a



Fig. 15.7 Keratoacanthoma. In appearance, this skin lesion closely resembles squamous cell carcinoma. The lesion begins as a red papule progressing to a large ulcerated mass.

large central crater. The natural course of the lesion involves regression after a latent phase of 6 months to several years.¹⁸

Excisional biopsy is necessary to rule out a malignant neoplasm, most commonly squamous cell carcinoma. Treatment can include curettage if a benign nature is considered likely. Because the natural history of these lesions is to involute, classically they have been treated conservatively. However, poor cosmetic outcomes can result from this approach.

Muir-Torre syndrome is an autosomal-dominant disorder associated with multiple keratoacanthomas. This clinical entity is also associated with visceral malignancy, and the workup of patients with multiple keratoacanthomas should include colonoscopy and CT.^{19,20}

Dermatofibroma

A dermatofibroma is a fibrous tumor involving the dermis (Fig. 15.8). This neoplasm contains fibroblasts, collagen, and histiocytes. The clinical presentation is that of a firm, solitary mass of varying color. Dermatofibromas usually form in young adulthood and are found more typically in females. Excisional biopsy is performed to rule out a malignant lesion such as a sarcoma, squamous cell carcinoma, or melanoma.²¹

The malignant form of this lesion is a dermatofibrosarcoma protuberans, which is occasionally found in the hand.²² While the metastatic potential is low, there is a potential for recurrence after excision. A wide excision with 3-cm margins is recommended and should include underlying fascia and muscle. The likelihood of local control associated with this procedure exceeds 90%, with the probability of regional or distant metastases being less than or equal to 5%. Adjuvant radiotherapy is indicated in the event that a patient has unresectable macroscopic disease.²³



Fig. 15.8 A dermatofibroma is a fibrous tumor involving the dermis. These lesions form in young adulthood and are found more typically in females.



Fig. 15.9 Seborrheic keratosis. A benign neoplasm originating from keratinocytes, common in middle-aged and older patients and distributed widely over the body.

Seborrheic keratosis

A seborrheic keratosis is a benign neoplasm that originates from keratinocytes (Fig. 15.9). Seborrheic keratoses are very common, typically present in middle-aged and older patients, and can be distributed widely over the body. Initially, they appear as a hyperpigmented lesion but later coalesce into a characteristic waxy, “stuck-on” appearance. The clinical conundrum with these lesions is that, although they are benign in nature, they may mimic melanoma. These lesions require a biopsy to rule out a malignancy. If a malignancy is not suspected, these lesions can be treated with cryotherapy, curettage, or excision.

Actinic keratosis

Actinic keratoses are premalignant lesions and in fact are the most common precancerous skin condition (Fig. 15.10). An actinic keratosis presents as a rough, scaly, erythematous plaque found in an area of chronic sun exposure. The lesion is commonly tender to palpation. Histologically, this lesion shows dysplastic keratinocytes confined to the lower third of the epidermis. Actinic keratoses are the direct result of chronic sun exposure and are more common in fair-skinned persons. The potential for malignant conversion to squamous cell



Fig. 15.10 Actinic keratosis. A premalignant skin lesion found on the upper extremity. It presents as a rough, scaly, and erythematous plaque found in areas of chronic sun exposure.




Fig. 15.11 Basal cell carcinoma. These lesions are malignant neoplasms of the basal epithelium forming insidiously but rarely metastasizing.

carcinoma ranges from 0.25% to 1.00% per year. Regression can be spontaneous if sun exposure after diagnosis is limited.

Treatment ranges from continued clinical observation to ablation. Cryotherapy can be used for isolated lesions. For more dispersed lesions, topical 5-fluorouracil, dermabrasion, and cutaneous peels such as trichloroacetic acid peel can be used. Newer reports have shown positive benefits using photodynamic therapy with porphyrin derivatives acting as a photosensitizer. Cure rates with this new modality have been reported as similar to those with topical 5-fluorouracil.²⁴

Basal cell carcinoma

Basal cell carcinoma is the second most common skin malignancy on the hand and is the most common form of skin cancer (Fig. 15.11). Basal cell carcinomas are malignant neoplasms of the basal epithelium. Five major types of basal cell carcinoma exist: fibroepithelioma, morpheaform, nodulo-ulcerative, pigmented, and superficial. The nodulo-ulcerative is the most common form, and the morpheaform variant is the most aggressive form of the tumor. The lesions form insidiously and rarely metastasize.^{1,2,25}

Basal cell carcinomas present in sun-damaged areas. The middle to older age group is commonly afflicted. Clinically, the lesion is observed as ulcerated skin with pearly elevated edges. Treatment consists of excisional biopsy with 2-mm margins. The key is surgical resection until only normal tissue remains. Regular follow-up is indicated to identify recurrences and new lesions. Since there is a low likelihood of metastasis, no further workup is required.

Squamous cell carcinoma

Squamous cell carcinoma is the most common malignant tumor in the hand (Fig. 15.12).²⁶ The tumor typically presents in late middle age or later. Usually, squamous cell carcinoma is found on the dorsum of the hand secondary to chronic sun exposure. Squamous cell carcinomas are pink or skin-colored and can present as firm hyperkeratotic lesions. Since there is a potential for malignant spread, it is critical to evaluate lymph node status by physical examination.

Etiologies of squamous cell carcinoma, in addition to sun exposure, include a history of therapeutic radiation, chronic



Fig. 15.12 Squamous cell carcinoma. The most common malignant tumor in the hand, typically found on the dorsum of the hand secondary to chronic sun exposure. It is critical to evaluate lymph node status upon physical exam.

inflammation, chronic sinus sites secondary to osteomyelitis, and immunosuppression. A Marjolin's ulcer is a squamous cell carcinoma present in a chronic burn ulcer. It is important to beware of non-responsive subungual lesions mimicking fungal infections. It is essential to biopsy all chronic infections to rule out malignancy.

Treatment of squamous cell carcinomas ranges from electrodesiccation and curettage for low-risk tumors to excisional biopsy for high-risk lesions. Excision with 5-mm margins of normal tissue results in complete clearance of 95% of tumors.²⁷ Other studies have shown that wide local excision with 4-mm margins has a clearance rate of 96% and that 6-mm margins clear 99% of tumors. Metastasis is found within the first 5 years in 5% of patients with squamous cell carcinoma. This is in contrast to basal cell carcinoma, which typically does not metastasize. Long-term follow-up after treatment of these lesions is therefore critical to assess for recurrence or metastatic spread.

A recent study of patients with squamous cell carcinoma of the fingertips using Mohs technique was performed in 43 cases. Microinvasive disease was diagnosed in 5 cases, *in situ* disease in 7 cases, and invasive disease in 45 patients. Recurrences were observed in 2 patients (3.5%). No tumor recurrences were observed in 4 to 5 years of follow-up. Mohs surgery provides the highest cure rate for the treatment of nail squamous cell carcinoma.²⁸

Melanoma

Melanoma is a highly malignant tumor of melanocytes (Fig. 15.13). Although melanomas represent only 5% of all skin cancers, they are responsible for 75% of the deaths from skin cancer.^{2,29} Based on these percentages, the prompt, accurate diagnosis and treatment of these tumors are critical for the well-being of all patients who present with a suspicious skin lesion on the upper extremity. The typical presentation of melanoma is a pigmented mass with appearance changes (ABCDE; see above). Melanomas may arise from atypical moles, but half of these tumors develop *de novo* and are unrelated to a pre-existing nevus (Fig. 15.14).¹ Acral lentiginous




Fig. 15.13 Melanoma. A highly malignant tumor of melanocytes, melanoma may arise from atypical moles. One-half of these tumors develop *de novo* and are unrelated to pre-existing nevus.

melanoma is a variant that occurs on the palmar, plantar, and nail plate surfaces.^{30,31}

Diagnosis is established by incisional or excisional biopsy. Determination of the depth of invasion is a critical component of pathologic analysis. The Breslow system, which is most commonly used, reports the depth of invasion in millimeters and correlates with rates of lymphatic spread and distant metastasis. The Clark system reports invasion based on anatomic levels.

Treatment of melanoma *in situ* is excision with a 0.5-cm tissue margin. For invasive lesions <1.0 mm thick, a 1-cm



Fig. 15.14 Subungual melanoma. These lesions must be differentiated from hematoma and onychomycosis. Evaluation of lymph node basins must be determined clinically and pathologically in lesions of intermediate thickness.

margin is used. For lesions that are 1–4 mm thick, a 2-cm margin is used; and for lesions >4 mm thick, a 2–4-cm margin is used. The risk of metastasis is only 2% for thin (<1 mm) lesions but higher for lesions that are 1–4 mm thick (addressed below). It is important to examine clinically the lymph nodes that drain melanomas.

Lymphatic metastases from melanoma are believed to occur in an orderly, anatomic progression. The first node to which a melanoma metastasizes is considered the sentinel lymph node (SLN) and can be predicted by the lymphatic drainage pattern of the skin area where the tumor is located. By performing a biopsy of the SLN in patients with intermediate-thickness melanomas, the potential for metastasis to other nodes can be predicted. The SLN is identified at the time of tumor resection by lymphoscintigraphy and the use of dye.³² Technetium-99m is given the morning of the operation, with surgery being performed 4 hours later after Lymphazurin blue is injected intradermally around the lesion. Next, the “hot” lymph node is searched for using a radioactive sensor and by visualizing the path of the blue dye. This lymph node, the SLN, is then sent for frozen-section pathologic assessment. If the SLN is positive, a full dissection of the draining lymph node basin(s) is performed. Consideration should then be given to adjuvant chemotherapy. No further treatment is given if the SLN is negative.

For thick melanomas (>4 mm), the risk of nodal metastasis is high (60–80%). Any clinically identified positive nodes are resected along with the primary lesion. If the clinical node examination is negative, SLN biopsy is not routinely indicated because this group will probably not benefit from loco-regional disease control.

Subungual melanomas may masquerade as a subungual hematoma or onychomycosis. Typically, treatment of subungual melanoma is an amputation at the distal interphalangeal joint.³⁰

Synovial lesions

Ganglion cysts

Ganglion cysts are the most common soft-tissue tumors of the hand and upper extremity (Fig. 15.15). Ganglion cysts are



Fig. 15.15 Ganglion cysts. The cyst is a mucinous-filled structure associated with joint capsules, tendons, and tendon sheaths. The etiology of these cystic structures is presumed to be secondary to synovial herniation and trauma.



Fig. 15.16 Mucous cyst. (A) Ganglions found on the dorsal proximal interphalangeal joint associated with osteoarthritis are termed mucous cysts. (B) Excision of the cyst along with excision of osteophytes must be performed to treat this clinical entity completely.

mucin-filled structures associated with joint capsules, tendons, or tendon sheaths. The etiology of these cystic structures is presumed to be secondary to synovial herniation and trauma but remains unclear.³³

In the hand, ganglion cysts typically occur in the dorsal carpal region (60–70%) and originate from the scapholunate interosseous ligament. The volar carpal region is the next most commonly involved region, with 20% of ganglion cysts originating from the scapho-trapezio-trapezoid ligament. Ganglion cysts are also found on the volar retinaculum (10–20%). Ganglion cysts found on the dorsal proximal interphalangeal joint associated with osteoarthritis are termed mucous cysts (Fig. 15.16). These are treated by excision of the cyst along with associated osteophytes. If atypical presentations occur or if clinical examination does not clarify a potential ganglion cyst, then ultrasonography or MRI can be helpful in determining a diagnosis.

A key point in the treatment of ganglion cysts is to clarify their benign nature for the patient. Patients often seek reassurance when confronted with this lesion. The natural course of volar retinaculum ganglion lesions is spontaneous resolution in almost two-thirds of patients. Aspiration of these masses results in complete resolution in the same proportion of patients. Aspiration of volar and dorsal ganglions in other locations with fenestration techniques has improved results. However, recurrence is still observed.³³

The definitive management of ganglion cysts is surgical excision with a cuff of retinaculum. For larger ganglions in the volar and dorsal regions of the hand, removal of the ganglion with its stalk and a portion of the cuff of the joint capsule is required. The capsule is not repaired so as not to limit motion. Arthroscopic removal of ganglion cysts in the dorsal region of the wrist is currently being performed. Success rates have been favorable, although long-term follow-up data are currently lacking.

Giant cell tumor (pigmented villonodular synovitis)

Giant cell tumors are the second most common soft-tissue masses in the hand (Fig. 15.17). A giant cell tumor is a benign tumor containing multinucleated giant cells and xanthoma cells. Giant cell tumors are found in synovial fluid-producing sites such as joints, capsular ligaments, and tendon sheaths.^{34,35} They are slow-growing and can have a mass effect on adjacent structures, at times indenting cortical bone. They are firm,



Fig. 15.17 Giant cell tumor (pigmented villonodular synovitis). A benign tumor containing multinucleated giant cells and xanthoma cells found in synovial fluid-producing sites such as joints, capsular ligaments, and tendon sheaths.

nodular, and non-tender. Most commonly, they are found over the volar aspect of the hand.

The treatment for this tumor is careful, complete excision. When dissecting these tumors out of the hand, the surgeon must beware of nerve displacement. The main problem with these masses is the potential for recurrence; the recurrence rate has been reported to be 5–50%. A malignant form of this tumor has been described but is extremely rare.

Nerve tumors

Schwannoma/neurilemoma

Schwannomas, the most common benign nerve tumors of the hand, arise from Schwann cells (Fig. 15.18). The presentation of schwannoma is one of a slow-growing, well-circumscribed, eccentric, and essentially painless mass.³⁶ However, there may be a neurologic deficit or pain if the lesion is in the distribution of motor or sensory nerves. Schwannomas are mobile transversely, not longitudinally. They are typically found on the volar surface of the hand and forearm in the fourth to sixth decades of life.

The treatment for schwannoma is to “shell it out” from surrounding intact nerve fascicles, under magnification. The risk of a postoperative neurologic deficit is 4%. There are very rare reports of malignant transformation.

Neurofibroma

Neurofibromas are benign, slow-growing tumors arising within nerve fascicles (Fig. 15.19).




Fig. 15.18 Schwannoma/neurilemoma. This soft-tissue mass arises from Schwann cells and is typically found on the volar surface of the hand and forearm.

The lesions appear histologically as diffuse growths of Schwann cells, fibrous tissue, and axons. When groups of these lesions are encountered, von Recklinghausen’s disease or neurofibromatosis should be considered as a diagnosis.

The treatment for neurofibromas is excision; however, this is likely to require segmental nerve resection and nerve grafting based on the anatomy of the tumor in that normal nerve fascicles are incorporated into the tumor.



Fig. 15.19 Neurofibroma, a benign slow-growing tumor arising within nerve fascicles. When encountered in groups, von Recklinghausen’s disease or neurofibromatosis should be considered as a diagnosis.



Fig. 15.20 Lipofibromatous hamartoma. This mass is a fibrofatty infiltration of the nerves, most commonly found in the median nerve. In a child who presents with carpal tunnel syndrome, this should be considered part of the differential diagnosis.

Malignant transformation of neurofibroma is possible, and rapid enlargement may indicate malignant transformation.² In patients with neurofibromatosis, malignant degeneration into plexiform neurofibromas can occur. A pseudoarthrosis, which is a rare condition frequently associated with neurofibromatosis, can occur in the upper extremity. This appears as “sucked candy” on radiographs.

Lipofibromatous hamartoma

Lipofibromatous hamartoma represents a fibrofatty infiltration of the nerves (Fig. 15.20). This tumor is most commonly found in the median nerve. In a child who presents with carpal tunnel syndrome, lipofibromatous hamartoma should be considered part of the differential diagnosis.³⁷ Exploration of the mass reveals fusiform swelling of the nerve without invasion into perineural tissue.

Interfascicular resection is not possible and in fact is contraindicated for the treatment of this lesion. Instead, simple decompression is recommended. Gradual deterioration of nerve function can occur; only then should resection and nerve grafting be considered.

Fat tumor: lipoma

A lipoma is a benign tumor composed of adipose tissue (Fig. 15.21). Lipomas can be located subcutaneously or intramuscularly. If present in the carpal tunnel or Guyon’s canal, lipoma can lead to nerve compression. Lipomas typically have a longstanding history with very slow growth. Physical examination and history will invariably lead to the diagnosis. If imaging is warranted, X-rays will reveal lucent soft-tissue shadows, and MRI will show a signal intensity consistent with adipose tissue.

The treatment of lipoma is simple excisional biopsy consisting of a marginal resection. The well-defined margins of the tumor make excision not technically challenging. The primary indication for excision is size increase and mass effect (nerve compression).

The malignant form of this mass, liposarcoma, has rarely been reported in the hand. However, liposarcoma can be confused with a lipoma if encountered.

Fibrous tissue lesions

Benign lesions

The majority of the lesions of fibrous tissue found in the hand are benign. These include simple scars, hypertrophic scars, and keloid tissue. Hypertrophic scars are confined within the original wound margins, whereas keloids grow beyond these margins. Both exhibit increased cellularity and vascularity. Other benign fibrous tumors found in the hand include juvenile aponeurotic fibroma, desmoid tumors, fibrous histiocytoma, and Dupuytren’s disease. The last of these constitutes fibrosis of the palmar fascia that leads to subsequent contractures of the fingers involving the metacarpophalangeal, proximal interphalangeal, and distal interphalangeal joints.

Sarcomas

Malignant fibrous histiocytoma is the most common soft-tissue sarcoma in adults (Fig. 15.22).^{37,38} It develops in the sixth to eighth decades of life. This tumor presents as a painless enlarging mass that is most common in the forearm. Treatment is wide excision or amputation. Neoadjuvant therapy can be administered to reduce tumor bulk and avoid amputation of the limb. A metastatic workup is required, with the most common site of metastasis being the lungs.

Synovial sarcoma is among the more common sarcomas in the hand and wrist. This malignant soft-tissue tumor occurs near tendons and joints and may invade bone. Its most common presentation in the upper extremity is that of a firm, indolent, painless mass on the dorsum of the hand.⁸ It typically presents in young adults to middle-aged patients. Synovial sarcoma is a very aggressive tumor. Treatment is wide or radical surgical excision. Nodal status must be evaluated because of the high rates (50%) of metastasis from this mass. Adjuvant radiotherapy or chemotherapy is recommended.

Epithelioid sarcoma is the most common malignant soft-tissue tumor of the upper extremity (Fig. 15.23). It most commonly appears on the hand and forearm in adolescents and young adults as a firm, slow-growing mass.⁸ Epithelioid



Fig. 15.21 Lipoma. This lesion is a benign tumor composed of adipose tissue. Commonly they are located subcutaneously or intramuscularly in the upper extremity.

sarcoma can affect the digits and palm with proximal spread along tendon sheaths. It can be misdiagnosed as a wart or an ulcer. Treatment of epithelioid sarcoma is wide or radical excision. Nodal status needs to be evaluated as metastasis is typically to regional lymph nodes.

Chemotherapy and limb salvage surgery with reconstruction has become the standard treatment for sarcomas of the extremities, including the hand. Local flaps are often inadequate for repairing extensive defects resulting from tumor resection. Such defects may require free tissue transfer. The use of free flaps in reconstructing oncologic defects has enabled reconstructive surgeons to effect a paradigm shift in limb salvage. Complex free flap reconstructions are now routinely being used to preserve limbs that, due to locally advanced disease, would have been previously amputated.

This has redefined the surgical management of sarcomas of the extremities. This shift toward limb preservation has prompted surgeons to re-evaluate the indications for amputation and thus improved patients' quality of life. In addition, tremendous advances in the multidisciplinary management of sarcoma have been made. Neoadjuvant chemotherapy and radiotherapy are now used to reduce tumor size to enable neurovascular-sparing resections that preserve limb function.

Vascular lesions

Hemangioma

Hemangiomas are benign capillary malformations. They can present as superficial, cutaneous lesions; as deep, cavernous




Fig. 15.22 Malignant fibrous histiocytoma. This sarcoma presents as a painless enlarging mass commonly found on the upper extremity. Treatment for this tumor is wide excision with mandatory metastatic evaluation. (A) Dorsal hand lesion. (B) Specimen revealing composite resection involving extensor tendons. (C) Wide local excision with proximal and distal extensor tendons tagged for reconstruction. (D) Dorsalis pedis flap elevation, including dorsal foot extensors. (E) Postoperative flap.



Fig. 15.23 Epithelioid sarcoma. The most common malignant soft-tissue tumor of the upper extremity. (A) Recurrent epithelioid sarcoma following wide local excision. (B) Composite resection involving both distal radius and ulna. (C) Bone allograft with internal fixation. Soft-tissue coverage supplied by a reverse radial forearm flap. (D) Intraoperative flap inset. (E) Postoperative result.

lesions; or as a mixture of the two forms (Fig. 15.24). Hemangiomas typically are not present at birth but appear in the first month of life. They are characterized by a rapid growth phase during the first year. The rate of involution is 50% by 5 years of age and 70% by 7 years of age.³⁹

Treatment is typically observation, as most will involute. However, laser therapy, systemic steroids, intralesional steroids, and interferon have all been shown to have beneficial effects. When hemangiomas become symptomatic in adults, they require a marginal resection. Even after resection, these lesions can recur.



Fig. 15.24 Hemangiomas present as: (1) superficial in the cutaneous form; (2) deep, which represents cavernous lesions; or (3) a mixture of both. Not present at birth, they are characterized by a rapid growth phase during the first year. Expected involution is 50% by 5 years of age and 70% by 7 years of age.

Infantile hemangiomas can be associated with Kasabach–Merritt syndrome (Fig. 15.25). This aggressive hemangioendothelioma leads to a consumptive coagulopathy secondary to platelet trapping. High-dose steroids and vincristine have been used to treat this syndrome.⁴⁰

Maffucci's syndrome is a condition characterized by multiple hemangiomas and enchondromas.⁴¹ The digits in patients with this condition are short and angulated. There is a risk of malignant transformation of the enchondromas and hemangiomas into chondrosarcomas and angiosarcomas.

Vascular malformations

Vascular malformations are typically present at birth, in contrast to hemangiomas, and represent malformed vascular channels. Malformations are described by their location as capillary, venous, lymphatic, or mixed venous–lymphatic malformations (Fig. 15.26). These are considered “low-flow” tumors. Treatment can be observation, laser therapy, sclerosing agents, or excision.⁴²

“High-flow” vascular malformations have arterial or arteriovenous components. These masses represent a “time bomb” with the potential for rapid expansion. Treatment of these tumors involves preoperative embolization followed by excision.



Fig. 15.25 Kasabach–Merritt syndrome. This aggressive hemangioendothelioma leads to a consumptive coagulopathy secondary to platelet trapping.




Fig. 15.26 Vascular malformations are typically present at birth, in contrast to hemangiomas, and represent malformed vascular channels. Treatment can be observation, laser therapy, sclerosing agents, or excision.

Other vascular malformations seen in the hand are aneurysms and pseudoaneurysms (Fig. 15.27). The former can originate from the radial, ulnar, or digital artery. Aneurysms involve all three layers of the vessel wall – the intima, the media and adventitia. In contrast, pseudoaneurysms represent a defect in the arterial wall contained by fibrous tissue.

Glomus tumor

A glomus tumor is a benign tumor of the neuromyoarterial apparatus, which is responsible for controlling circulation to



Fig. 15.27 Pseudoaneurysm. This represents a defect in the arterial wall contained by fibrous tissue as opposed to an aneurysm, which involves all three vessel wall layers (intima, media, and adventitia). (A) Radial artery pseudoaneurysm. (B) Radial artery pseudoaneurysm exposed.




Fig. 15.28 Glomus tumor. A benign tumor of the neuromyoarterial apparatus responsible for controlling skin circulation presenting in a subungual location. (A) Glomus tumor *in situ*. (B) Glomus tumor excised. (C) Magnetic resonance imaging scan of glomus tumor distal phalanx.

the skin. Glomus tumors frequently present subungually (Fig. 15.28). The classic triad of symptoms is cold hypersensitivity, intermittent severe pain, and point tenderness.^{6,43}

Diagnostic workup for a suspected glomus tumor should include radiography and MRI. Radiographs reveal a “scalloped” osteolytic defect. MRI will commonly reveal a high-signal-intensity lesion. Excisional biopsy is curative.

Pyogenic granuloma

Pyogenic granuloma is a rapidly progressing vascular lesion (Fig. 15.29). Pyogenic granulomas of the hands are commonly found on the fingers. The lesion begins as a solitary “red” nodule and progresses to a chronically inflamed vascular lesion. The exact etiology is unknown.⁴² Current beliefs are that the lesion begins with trauma followed by a subsequent subclinical infection. Treatment modalities range from excision with 1-mm margins, to curettage, to topical silver nitrate; however, all are associated with some incidence of recurrence.

Muscle lesions

Myositis ossificans

In myositis ossificans, benign ossification occurs in muscles and other soft tissues (Fig. 15.30). The etiology can be traumatic. In the upper extremity, the deltoid and brachialis muscles are involved most frequently. Over time, the volume of heterotopic bone will diminish.

Leiomyoma

Leiomyoma is a benign, smooth-muscle neoplasm (Fig. 15.31). Leiomyomas are rare in the hand. Treatment is excisional



Fig. 15.29 Pyogenic granuloma. Rapidly progressing benign vascular lesion commonly found in the finger. Etiology is unknown.

biopsy. If a lesion is clinically suspicious, biopsy is necessary to differentiate leiomyoma from leiomyosarcoma.²¹

Rhabdomyosarcoma

Rhabdomyosarcoma is a malignant tumor of muscle stem cells. Presentation is typically before 15 years of age. In the hand, rhabdomyosarcoma presents as a slowly developing, deep, painless mass. Rhabdomyosarcomas have been observed in the thenar eminence and between the metacarpals.

The treatment for rhabdomyosarcoma is wide resection or amputation. Regional lymph node dissection is usually necessary. Adjuvant radiotherapy and chemotherapy are recommended.³⁸

Cartilage and bone tumors

Enchondroma

Enchondroma is the most common primary tumor in the bones of the hand. Essentially, it is a benign cartilage lesion within the bone. The tumor most commonly presents in the fourth decade of life. Typically, it arises in a proximal phalanx or metacarpal. The common clinical presentation is pain and edema secondary to pathologic fracture. The diagnosis is strengthened by radiographic patterns showing a radiolucent lesion with cortical thinning and “popcorn” calcification (Fig. 15.32).^{44,45}

Treatment can begin with observation. However, solitary lesions have a potential for malignant transformation to chondrosarcoma (<5% risk).⁴⁵ A healing fracture resembles a chondrosarcoma, so it is important to follow up these lesions radiographically. If a pathologic fracture occurs, it is recommended that the fracture be treated first, followed by curettage of the tumor. A bone graft or allograft is placed into the bone cavity.

Ollier’s disease is a non-hereditary condition characterized by multiple enchondromas.⁴⁵ The tumors occur mainly unilaterally. Pain is uncommon unless there is a fracture. There is a 30–50% risk of malignant transformation, so it is critical to follow patients with Ollier’s disease closely.

Osteoid osteoma

Osteoid osteoma represents a benign bone-forming lesion typically affecting the distal radius, carpus, and phalanges





Fig. 15.30 Myositis ossificans. Extraskeletal ossification seen here in the upper extremity. **(A)** Computed tomographic scan showing extraosseous lesion in distal upper extremity. **(B)** *In situ* lesion. **(C)** Excised specimen.

(Fig. 15.33). These bone tumors rarely form in the hand (<1%). They present during the first two decades of life, and patients may complain of persistent pain relieved only by nonsteroidal anti-inflammatory agents. Radiographs reveal sclerosis around a central lucency.^{46,47} Treatment can be either curettage or resection. There is a potential for recurrence if a lesion is incompletely removed.

Osteochondroma

Osteochondroma represents the most common benign bone tumor (Fig. 15.34). It develops during adolescence and enlarges during puberty. Osteochondroma is a benign bone prominence with a cartilage cap. Osteochondroma can present in the hand as multiple enchondromas or as an asymptomatic hard lump, which can cause a growth deformity (e.g., short deformed ulna or radius displacement). Osteochondroma can also cause a mechanical block to flexion from the angular growth disturbance.⁴⁴

The treatment of this lesion is observation initially, with excision if there is pain or deformity. Bone grafting is performed for the correction of angular deformity. There is a 10–25% chance of malignant degeneration when multiple osteochondromas are present.

Solitary unicameral bone cyst

Solitary unicameral bone cysts are rare in the hand and usually present in the forearm. The cyst usually becomes clinically evident because of a pathologic fracture causing pain and edema. Radiographs show radiolucency in the affected metaphysis with a thin cortical wall (Fig. 15.35). Treatment is curettage and bone graft.

Aneurysmal bone cyst

Aneurysmal bone cyst is a benign vascular tumor of bone, rare in the hand and usually found in the forearm (Fig. 15.36).




Fig. 15.31 Leiomyoma. A benign smooth-muscle neoplasm seen here on the volar aspect of the hand in close proximity to neurovascular structures.

Growth is rapid and can be locally invasive. Radiographs reveal a large radiolucency with a “blown-out” cortex. Treatment of this mass is curettage and bone or strut grafting. Amputation has been used for destructive distal phalanx lesions. There is a high recurrence rate (60%) following curettage. Ray section will treat recurrences.⁴⁸

Giant cell tumor of bone

Giant cell tumor of the bone is a distinct entity from a giant cell tumor of the tendon (Fig. 15.37). The tumor may present



Fig. 15.33 Osteoid osteoma. A benign bone-forming lesion found here in the phalanges. Radiographs reveal sclerosis around a central lucency.



Fig. 15.32 Enchondroma. A benign cartilage lesion within the bone presenting here in the proximal phalanx.

with joint pain and swelling. Pathological fracture is commonly seen as the presenting diagnosis in up to 10% of the affected population.⁴⁹ The neoplasm is multicentric, with a potential for metastatic spread, most often to the lungs (<2% of cases). The tumor appears in the distal radius up to 10% of the time, with other sites more commonly the proximal tibia and distal femur.⁴⁹ Metastatic workup is appropriate for this tumor secondary to the potential for metastatic spread.

Surgical treatment can include extended curettage, wide excision, or amputation.^{50,51} Recurrence rates for extended curettage are significant.⁵² However, when extended curettage



Fig. 15.34 Osteochondroma. The most common benign bone tumor. Seen here in the distal phalanx of the thumb, it is a benign bone prominence with cartilage cap.




Fig. 15.35 (A,B) Solitary unicameral bone cyst: a benign cyst of the bone usually presenting in the forearm. This lesion, seen here in the small-finger metacarpal, shows radiolucency in the metaphysis with a thin cortical wall.



Fig. 15.36 Aneurysmal bone cyst. A benign vascular tumor of bone seen here in the metacarpal bone. Radiographs reveal a large radiolucency with a "blown-out" cortex.



Fig. 15.37 Giant cell tumor of bone. A multicentric neoplasm with a potential for metastatic spread. Treatment of this mass is wide excision or amputation.

is performed the cavity can be packed with either cancellous bone graft or methylmethacrylate cement.⁵² In cases of wide local excision reconstruction where the bone is made unstable, such as the distal radius, reconstruction is required typically with an autograft or allograft.

Reconstruction of the distal radius is performed to optimize the function of the wrist, specifically the radiocarpal joint. Surgical reconstruction can be performed with either an arthroplasty or arthrodesis involving the use of non-vascularized (tibia, fibula, iliac crest, or distal part of ulna) or vascularized (fibula and distal portion of the ulna) bones.^{53–56} Reconstruction with vascularized and non-vascularized fibular grafting has been shown to give the patient improved function over arthrodesis.^{53,57} However, distal radius resection managed with a radiocarpal arthrodesis through use of an intercalary bone graft stabilized with a long plate also has shown proven functional benefits.⁵⁸

Healing complications related to the use of a bone allograft or autograft may involve malunion and nonunion of bone. In addition the graft can fracture, necessitating further surgical intervention.⁵⁴ In reference to distal radius reconstruction potential subluxation of the carpus, and degenerative osteoarthritis can lead to limited wrist movement and pain. Donor site complications related to autograft harvest involving the

fibula, such as ankle instability, pain, footdrop, and paresthesia, might develop.⁵⁹

Osteosarcoma

Osteosarcoma is the most common primary malignant bone-forming tumor. Presentation is a firm, rapidly enlarging, painful mass. Although rarely found in the hand, osteosarcoma can occur in the metacarpals and proximal phalanges.

Treatment starts with incisional biopsy. Local and systemic staging is then performed. This is followed by wide excision, or possibly finger or ray amputation for osteosarcoma in the hand. Neoadjuvant chemotherapy and postoperative adjuvant chemotherapy are recommended for high-grade lesions of the hand.^{60–62}

Chondrosarcoma

Chondrosarcoma is a malignant cartilaginous tumor and the most common primary malignant tumor of the hand, although this site is rare. This mass presents typically in patients >40 years old. In the metacarpals and proximal phalanges, chondrosarcoma is firm, insidious, and painful. Radiographically, the presence of lytic lesions with cortical destruction and soft-tissue destruction differentiates chondrosarcoma from enchondroma.^{44,63}

Treatment for hand tumors is incisional biopsy to establish the diagnosis and then wide excision or ray amputation. Local and systemic staging is critical.

Staging and treatment of musculoskeletal sarcomas

A sarcoma, as previously discussed, is described as a malignant neoplasm arising from transformed connective tissue cells originating from embryonic mesoderm.⁶⁴ These cells can include adipose tissue, bone, cartilage, muscle, and bone. Commonly they can present as an asymptomatic mass originating in an extremity. However, this neoplasm can occur anywhere in the body such as the trunk, retroperitoneum, or the head and neck.⁶⁴

Enneking *et al.* developed a classification system for the staging of musculoskeletal tumors.⁶⁵ This three-stage classification system is based on grade (G), site (T), and metastasis (M), using histological, radiologic, and clinical criteria. Grade 0 refers to benign lesions, G1 to low-grade, and G2 to high-grade lesions. Low or G1 lesions have a low risk of metastases (<25%). They are well differentiated, and have fewer mitoses and moderate cellular atypia. G2 lesions, high-grade lesions, are characterized by an increased rate of metastasis.³ T0 represents a benign intracapsular and intracompartmental lesion, whereas T1 is an intracapsular and T2 an intracompartmental lesion. M0 represents no regional or distant metastasis and M1 represents regional and distant metastasis. Stage I represents a low-grade lesion without metastasis, stage II represents a high-grade lesion without metastasis, and stage III represents a metastatic lesion regardless of tumor grade (Table 15.1). The Enneking classification correlates the tumor stage with the recommended excision margins depending on whether it is a benign or malignant mass. Based on the stage, the appropriate surgical margin is chosen to obtain appropriate local control.

Four types of surgical margin are typically described when removing tumors of the hand. An intralesional resection is

Table 15.1 Enneking's classification system of musculoskeletal sarcomas

Stage	Grade	Site	Metastases
IA	G1	T1	M0
IB	G2	T2	M0
IIA	G1	T1	M0
IIB	G2	T2	M0
IIIA	G1–G2	T1	M1
IIIB	G1–G2	T2	M1

Grade: G1, low; G2, high.
 Site: T1, intracompartmental; T2, extracompartmental.
 Metastases: M0, no regional or distant metastases; M1, regional or distant metastases.

through the plane of the tumor, leaving gross or macroscopic tumor behind. A marginal resection is performed through the tumor pseudocapsule or “reactive zone”, potentially leaving “satellite” or “skip” lesions. A wide resection plane involves removal of the mass with normal tissue but remains within the relative tissue compartment. This resection can potentially leave “skip” lesions. Finally, a radical resection of tumor involves removing the entire intracompartment and extracompartment of involved and uninvolved tissue. An example of this would be a soft-tissue sarcoma of the hand requiring a radiocarpal disarticulation.

Oncological treatment for upper extremity sarcoma emphasizes limb salvage as an alternative to amputation and is determined mainly by the stage of the disease.³ Treatment options for musculoskeletal sarcomas include chemotherapy, radiation therapy, and surgery. Since neither radiation nor chemotherapy alone or in combination has been shown to attain long-term local control of disease, surgical ablation is a critical step in the management of these neoplasms.^{64,66,67} A multidisciplinary team involving the medical and surgical oncologist along with an integrated hand surgeon adept at reconstructive surgery best handles the overall treatment of a sarcoma of the upper extremity.

Metastases

In the hand, metastases from tumors at other sites are rare. However, the most common sources of metastatic spread to the hand are primary breast, kidney, thyroid, lung, and colon cancers. The distal phalanges are the most common site of metastasis in the hand (Fig. 15.38).⁷ The symptoms and signs reported are pain, edema, and erythema. Radiography can reveal destructive lytic lesions. The diagnosis is confirmed by incisional biopsy.

Treatment of metastatic lesions in the hand begins by identifying the primary tumor. Once a primary tumor is identified, a systematic workup is undertaken that takes into consideration other metastatic lesions in the body. Treatment of hand lesions may include local radiotherapy for tumors that are radiosensitive, such as metastases from breast, prostate, and thyroid cancers. A digit or ray amputation can be performed to reduce the tumor load or effect a cure. However, metastasis to the hand is an ominous sign. Life expectancy in these patients is usually <6 months.^{1,7}



Fig. 15.38 Metastasis. Sources of metastatic spread to the upper extremity most commonly are from primary breast, kidney, thyroid, lung, or colon cancer. The distal phalanx, as seen here, is the most common site.

Postoperative care

For most lesions of the hand, simple excision and closure will suffice for treatment. In these instances, a sterile bulky dressing with or without a splint will be required. For larger

soft-tissue resections with concomitant reconstruction, appropriate volar or dorsal splinting is required. The patient is instructed to elevate the extremity for the first several days to alleviate postoperative swelling. If bone reconstruction is performed, appropriate postoperative radiographs must be obtained during the first week to determine if there is displacement of fixated structures.

The success of upper extremity reconstruction is quantified by limb function, sensation, cosmesis, and stable wound coverage. Appropriate postoperative splinting and aggressive rehabilitation to maximize long-term upper extremity function are critical to complete postoperative care.⁶⁸ The role of the upper extremity reconstructive surgeon is critical as the team-leader to obtain optimal clinical outcomes.

Outcomes, prognosis, and complications

Tumors of the hand are typically recognized early. They may originate from any cell type, and most are benign. Malignancy is uncommon but must be ruled out. A careful history and physical examination followed by an appropriate diagnostic workup will typically lead the hand surgeon to the correct diagnosis. When the tumor type remains in question, excisional biopsy will very often lead to both diagnosis and cure. The critical element when dealing with tumors of the hand is to follow a careful surgical plan that preserves function as much as possible while simultaneously removing the neoplastic process completely.⁶⁹

Future directions

The majority of tumors of the hand and upper extremity are benign. Variations in care, that cannot be accounted for by differences in pathophysiology or other objective evidence may represent opportunities for process improvement. Future research will define the role of patient algorithms and decision aids for managing suspected benign tumors of the upper extremity.⁶⁹



Access the complete reference list online at <http://www.expertconsult.com>

1. Plate AM, Steiner G, Posner MA. Malignant tumors of the hand and wrist. *J Am Acad Orthop Surg.* 2006;14:680–692. Malignant tumors in the hand and wrist compose a wide variety of lesions involving skin, soft tissues, and bone. Squamous cell carcinomas are described as the most common, followed by basal cell carcinomas and malignant melanomas. Other soft-tissue malignancies are defined as less common and can present diagnostic problems. These lesions often remain clinically indolent for some time prior to diagnosis. Delay in diagnosis of these tumors can have morbid and fatal consequences. Bone malignancies involve both primary lesions, with chondrosarcomas being the most common, and metastatic lesions. Treatment of malignant tumors in the hand and wrist requires special considerations because of the critical function role in the upper extremity. It is critical for upper extremity surgeons to be familiar with the wide clinical array of these tumors, the appropriate evaluation necessary to arrive at a precise diagnosis, and the treatment plan that will achieve the most favorable outcomes, oftentimes requiring a multidisciplinary approach.
2. Chakrabarti I, Watson JD, Dorrance H. Skin tumours of the hand. A 10-year review. *J Hand Surg [Br].* 1993;18:484–486. This was a retrospective study performed over 10 years. The incidence, histological type, and clinical progression of skin tumors of the hand that were referred to a regional plastic surgery unit were evaluated. Eighty-five patients were studied with 98 malignant or premalignant lesions identified. The majority of skin lesions were squamous cell carcinoma. Recurrence after excision was seen in lesions greater than 1.5 cm in diameter. The overall incidence of squamous cell carcinoma of the hand was seen to be five cases per million per year. Other skin lesions and tumors were noted to be rare.
4. Upton J, Kocher MS, Wolford FG. Reconstruction following resection of malignancies of the upper extremity. *Surg Oncol Clin North Am.* 1996;5:847–892. A multidisciplinary approach using diagnosis, staging, adjuvant therapy, surgical resection, and reconstruction is described as the standard of care for upper extremity neoplasms. The reconstructive surgeon's involvement with preoperative planning is crucial for optimal functional and aesthetic outcome. Varied techniques currently available for both salvage and restoration of function, including local soft-tissue flaps, regional pedicled and vascular island flaps, and free tissue transfers, bone autografts, and allografts, were described. This article reviews both new and well-established reconstructive options after resection of upper extremity malignancies in children and adults.
7. Kerin R. The hand in metastatic disease. *J Hand Surg Am.* 1987;12:77–83.

8. Murray PM. Soft tissue sarcoma of the upper extremity. *Hand Clin.* 2004;20:325–333, vii. *Soft-tissue sarcomas of the upper extremities are rare. It is critical for the physician to review the characteristics of these tumors and understand their biology. These lesions typically are misdiagnosed and treatment is often delayed. The most common soft-tissue sarcomas of the upper extremity are the epithelioid sarcoma, synovial cell sarcoma, and malignant fibrous histiocytoma. Limb salvage surgery is the standard of care for soft-tissue sarcomas in order to preserve upper extremity function. Following wide tumor resection, adjuvant therapies such as chemotherapy, external beam radiation therapy, and brachytherapy may lessen local recurrence rates, but their effect on overall survival remains unclear.*
12. Enneking WF, Spanier SS, Goodman MA. A system for the surgical staging of musculoskeletal sarcoma. 1980. *Clin Orthop Relat Res.* 2003;415:4–18. *A surgical staging system for musculoskeletal sarcomas is presented which stratifies bone and soft-tissue lesions of varied histological type and by the grade of biologic activity, anatomic setting, and the presence of metastasis. Three stages – I, low grade; II, high grade; and III, presence of metastases – were subdivided by whether the lesion is anatomically confined within surgical compartments or beyond such compartments. Operative margins are defined as intralesional, marginal, wide, and radical relating to the surgical margin of the lesions, its reactive zone, and anatomic compartment. The system defines prognostically significant progressive stages of risk with their surgical implications and probability of survival.*
28. Dika E, Fanti PA, Patrizi A, et al. Mohs surgery for squamous cell carcinoma of the nail unit: 10 years of experience. *Dermatol Surg.* 2015;41:1015–1019.
31. Goydos JS, Shoen SL. Acral lentiginous melanoma. *Cancer Treat Res.* 2016;167:321–329.
33. Thornburg LE. Ganglions of the hand and wrist. *J Am Acad Orthop Surg.* 1999;7:231–238.
44. O'Connor MI, Bancroft LW. Benign and malignant cartilage tumors of the hand. *Hand Clin.* 2004;20:317–323, vi.
60. Daecke W, Bielack S, Martini AK, et al. Osteosarcoma of the hand and forearm: experience of the Cooperative Osteosarcoma Study Group. *Ann Surg Oncol.* 2005;12:322–331.
67. Thomas BP, Sasi K, Pallapati S, et al. Malignant tumors of the hand and wrist. *Indian J Plast Surg.* 2011;44:337–347.
68. Saint-Cyr M, Langstein HN. Reconstruction of the hand and upper extremity after tumor resection. *J Surg Oncol.* 2006;94:490–503.
69. Sluijmer HCE, Becker SJE, Ring DC. Benign upper extremity tumors: factors associated with operative treatment. *Hand (N Y).* 2013;8:274–281.

References

1. Plate AM, Steiner G, Posner MA. Malignant tumors of the hand and wrist. *J Am Acad Orthop Surg*. 2006;14:680–692. Malignant tumors in the hand and wrist compose a wide variety of lesions involving skin, soft tissues, and bone. Squamous cell carcinomas are described as the most common, followed by basal cell carcinomas and malignant melanomas. Other soft-tissue malignancies are defined as less common and can present diagnostic problems. These lesions often remain clinically indolent for some time prior to diagnosis. Delay in diagnosis of these tumors can have morbid and fatal consequences. Bone malignancies involve both primary lesions, with chondrosarcomas being the most common, and metastatic lesions. Treatment of malignant tumors in the hand and wrist requires special considerations because of the critical function role in the upper extremity. It is critical for upper extremity surgeons to be familiar with the wide clinical array of these tumors, the appropriate evaluation necessary to arrive at a precise diagnosis, and the treatment plan that will achieve the most favorable outcomes, oftentimes requiring a multidisciplinary approach.
2. Chakrabarti I, Watson JD, Dorrance H. Skin tumours of the hand. A 10-year review. *J Hand Surg [Br]*. 1993;18:484–486. This was a retrospective study performed over 10 years. The incidence, histological type, and clinical progression of skin tumors of the hand that were referred to a regional plastic surgery unit were evaluated. Eighty-five patients were studied with 98 malignant or premalignant lesions identified. The majority of skin lesions were squamous cell carcinoma. Recurrence after excision was seen in lesions greater than 1.5 cm in diameter. The overall incidence of squamous cell carcinoma of the hand was seen to be five cases per million per year. Other skin lesions and tumors were noted to be rare.
3. Enneking WF, Spanier SS, Goodman MA. Current concepts review. The surgical staging of musculoskeletal sarcoma. *J Bone Joint Surg Am*. 1980;62:1027–1030.
4. Upton J, Kocher MS, Wolford FG. Reconstruction following resection of malignancies of the upper extremity. *Surg Oncol Clin North Am*. 1996;5:847–892. A multidisciplinary approach using diagnosis, staging, adjuvant therapy, surgical resection, and reconstruction is described as the standard of care for upper extremity neoplasms. The reconstructive surgeon's involvement with preoperative planning is crucial for optimal functional and aesthetic outcome. Varied techniques currently available for both salvage and restoration of function, including local soft-tissue flaps, regional pedicled and vascular island flaps, and free tissue transfers, bone autografts, and allografts, were described. This article reviews both new and well-established reconstructive options after resection of upper extremity malignancies in children and adults.
5. Shankman S, Kolla S, Beltran J. MR imaging of tumors and tumor-like lesions of the upper extremity. *Magn Reson Imaging Clin North Am*. 2004;12:349–359.
6. Abou Jaoude JF, Roula Farah A, Sargi Z, et al. Glomus tumors: report on eleven cases and a review of the literature. *Chir Main*. 2000;19:243–252.
7. Kerin R. The hand in metastatic disease. *J Hand Surg Am*. 1987;12:77–83.
8. Murray PM. Soft tissue sarcoma of the upper extremity. *Hand Clin*. 2004;20:325–333, vii. Soft-tissue sarcomas of the upper extremities are rare. It is critical for the physician to review the characteristics of these tumors and understand their biology. These lesions typically are misdiagnosed and treatment is often delayed. The most common soft-tissue sarcomas of the upper extremity are the epithelioid sarcoma, synovial cell sarcoma, and malignant fibrous histiocytoma. Limb salvage surgery is the standard of care for soft-tissue sarcomas in order to preserve upper extremity function. Following wide tumor resection, adjuvant therapies such as chemotherapy, external beam radiation therapy, and brachytherapy may lessen local recurrence rates, but their effect on overall survival remains unclear.
9. McPhee M, McGrath BE, Zhang P, et al. Soft tissue sarcoma of the hand. *J Hand Surg Am*. 1999;24:1001–1007.
10. Capelastegui A, Astigarraga E, Fernandez-Canton G, et al. Masses and pseudomasses of the hand and wrist: MR findings in 134 cases. *Skeletal Radiol*. 1999;28:498–507.
11. Toomayan GA, Robertson F, Major NM, et al. Upper extremity compartmental anatomy: clinical relevance to radiologists. *Skeletal Radiol*. 2006;35:195–201.
12. Enneking WF, Spanier SS, Goodman MA. A system for the surgical staging of musculoskeletal sarcoma. 1980. *Clin Orthop Relat Res*. 2003;415:4–18. A surgical staging system for musculoskeletal sarcomas is presented which stratifies bone and soft-tissue lesions of varied histological type and by the grade of biologic activity, anatomic setting, and the presence of metastasis. Three stages – I, low grade; II, high grade; and III, presence of metastases – were subdivided by whether the lesion is anatomically confined within surgical compartments or beyond such compartments. Operative margins are defined as intralesional, marginal, wide, and radical relating to the surgical margin of the lesions, its reactive zone, and anatomic compartment. The system defines prognostically significant progressive stages of risk with their surgical implications and probability of survival.
13. Gould JW, Brodell RT. Giant cutaneous horn associated with verruca vulgaris. *Cutis*. 1999;64:111–112.
14. Lucas GL. Epidermoid inclusion cysts of the hand. *J South Orthop Assoc*. 1999;8:188–192.
15. Leman JA, Benton EC. Verrucas. Guidelines for management. *Am J Clin Dermatol*. 2000;1:143–149.
16. Gosain AK, Santoro TD, Larson DL, et al. Giant congenital nevi: a 20-year experience and an algorithm for their management. *Plast Reconstr Surg*. 2001;108:622–636.
17. Tucker MA, Halpern A, Holly EA, et al. Clinically recognized dysplastic nevi. A central risk factor for cutaneous melanoma. *JAMA*. 1997;277:1439–1444.
18. Carroll RE, Bowers WH. Keratoacanthoma: an unusual hand tumor. *Clin Orthop Relat Res*. 1976;118:173–179.
19. Ponti G, Losi L, Di Gregorio C, et al. Identification of Muir–Torre syndrome among patients with sebaceous tumors and keratoacanthomas: role of clinical features, microsatellite instability, and immunohistochemistry. *Cancer*. 2005;103:1018–1025.
20. Ponti G, Ponz de Leon M. Muir–Torre syndrome. *Lancet Oncol*. 2005;6:980–987.
21. Brien EW, Terek RM, Geer RJ, et al. Treatment of soft-tissue sarcomas of the hand. *J Bone Joint Surg Am*. 1995;77:564–571.
22. Coles M, Smith M, Rankin EA. An unusual case of dermatofibrosarcoma protuberans. *J Hand Surg Am*. 1989;14:135–138.
23. Mendenhall WM, Zlotecki RA, Scarborough MT. Dermatofibrosarcoma protuberans. *Cancer*. 2004;101:2503–2508.
24. Drake LA, Ceilley RI, Cornelison RL, et al. Guidelines of care for actinic keratoses. Committee on Guidelines of Care. *J Am Acad Dermatol*. 1995;32:95–98.
25. Wolf DJ, Zitelli JA. Surgical margins for basal cell carcinoma. *Arch Dermatol*. 1987;123:340–344.
26. Schiavon M, Mazzoleni F, Chiarelli A, et al. Squamous cell carcinoma of the hand: fifty-five case reports. *J Hand Surg Am*. 1988;13:401–404.
27. Brodland DG, Zitelli JA. Surgical margins for excision of primary cutaneous squamous cell carcinoma. *J Am Acad Dermatol*. 1992;27:241–248.
28. Dika E, Fanti PA, Patrizi A, et al. Mohs surgery for squamous cell carcinoma of the nail unit: 10 years of experience. *Dermatol Surg*. 2015;41:1015–1019.
29. Essner R, Belhocine T, Scott AM, et al. Novel imaging techniques in melanoma. *Surg Oncol Clin North Am*. 2006;15:253–283.
30. Ridgeway CA, Hieken TJ, Ronan SG, et al. Acral lentiginous melanoma. *Arch Surg*. 1995;130:88–92.
31. Goydos JS, Shoen SL. Acral lentiginous melanoma. *Cancer Treat Res*. 2016;167:321–329.
32. Joseph E, Brobeil A, Cruse CW, et al. Lymphatic mapping for melanomas of the upper extremity. *J Hand Surg Am*. 1999;24:675–681.
33. Thornburg LE. Ganglions of the hand and wrist. *J Am Acad Orthop Surg*. 1999;7:231–238.
34. Wittig JC, Simpson BM, Bickels J, et al. Giant cell tumor of the hand: superior results with curettage, cryosurgery, and cementation. *J Hand Surg Am*. 2001;26:546–555.
35. Walsh EF, Mechrefe A, Akelman E, et al. Giant cell tumor of tendon sheath. *Am J Orthop*. 2005;34:116–121.

36. Kang HJ, Shin SJ, Kang ES. Schwannomas of the upper extremity. *J Hand Surg [Br]*. 2000;25:604–607.
37. Al-Qattan MM. Lipofibromatous hamartoma of the median nerve and its associated conditions. *J Hand Surg [Br]*. 2001;26:368–372.
38. Gustafson P, Arner M. Soft tissue sarcoma of the upper extremity: descriptive data and outcome in a population-based series of 108 adult patients. *J Hand Surg Am*. 1999;24:668–674.
39. Achauer BM, Chang CJ, Vander Kam VM. Management of hemangioma of infancy: review of 245 patients. *Plast Reconstr Surg*. 1997;99:1301–1308.
40. Maguiness S, Guenther L. Kasabach–Merritt syndrome. *J Cutan Med Surg*. 2002;6:335–339.
41. Schwartz HS, Zimmerman NB, Simon MA, et al. The malignant potential of enchondromatosis. *J Bone Joint Surg Am*. 1987;69:269–274.
42. Fleming AN, Smith PJ. Vascular cell tumors of the hand in children. *Hand Clin*. 2000;16:609–624.
43. McDermott EM, Weiss AP. Glomus tumors. *J Hand Surg Am*. 2006;31:1397–1400.
44. O'Connor MI, Bancroft LW. Benign and malignant cartilage tumors of the hand. *Hand Clin*. 2004;20:317–323, vi.
45. Ablove RH, Moy OJ, Peimer CA, et al. Early versus delayed treatment of enchondroma. *Am J Orthop*. 2000;29:771–772.
46. Ilyas I, Younge DA. Medical management of osteoid osteoma. *Can J Surg*. 2002;45:435–437.
47. Marcuzzi A, Acciaro AL, Landi A. Osteoid osteoma of the hand and wrist. *J Hand Surg [Br]*. 2002;27:440–443.
48. Athanasian EA, McCormack RR. Recurrent aneurysmal bone cyst of the proximal phalanx treated with cryosurgery: a case report. *J Hand Surg Am*. 1999;24:405–412.
49. McDonald DJ, Sim FH, McLeod RA, et al. Giant-cell tumor of bone. *J Bone Joint Surg Am*. 1986;68:235–242.
50. Athanasian EA, Wold LE, Amadio PC. Giant cell tumors of the bones of the hand. *J Hand Surg Am*. 1997;22:91–98.
51. Cheng CY, Shih HN, Hsu KY, Hsu RW. Treatment of giant cell tumor of the distal radius. *Clin Orthop Relat Res*. 2001;383:221–228.
52. Sheth DS, Healey JH, Sobel M, et al. Giant cell tumor of the distal radius. *J Hand Surg Am*. 1995;20:432–440.
53. Lackman RD, McDonald DJ, Beckenbaugh RD, et al. Fibular reconstruction for giant cell tumor of the distal radius. *Clin Orthop Relat Res*. 1987;218:232–238.
54. Murray JA, Schlafly B. Giant-cell tumors in the distal end of the radius. Treatment by resection and fibular autograft interpositional arthrodesis. *J Bone Joint Surg Am*. 1986;68:687–694.
55. Campbell CJ, Akbarnia BA. Giant-cell tumor of the radius treated by massive resection and tibial bone graft. *J Bone Joint Surg Am*. 1975;57:982–986.
56. Seradge H. Distal ulnar translocation in the treatment of giant-cell tumors of the distal end of the radius. *J Bone Joint Surg Am*. 1982;64:67–73.
57. Pho RW, Patterson MH, Kour AK, et al. Free vascularised epiphyseal transplantation in upper extremity reconstruction. *J Hand Surg [Br]*. 1988;13:440–447.
58. Vander Griend RA, Funderburk CH. The treatment of giant-cell tumors of the distal part of the radius. *J Bone Joint Surg Am*. 1993;75:899–908.
59. Nassr A, Khan MH, Ali MH, et al. Donor-site complications of autogenous nonvascularized fibula strut graft harvest for anterior cervical corpectomy and fusion surgery: experience with 163 consecutive cases. *Spine J*. 2009;9:893–898.
60. Daecke W, Bielack S, Martini AK, et al. Osteosarcoma of the hand and forearm: experience of the Cooperative Osteosarcoma Study Group. *Ann Surg Oncol*. 2005;12:322–331.
61. Okada K, Wold LE, Beabout JW, et al. Osteosarcoma of the hand. A clinicopathologic study of 12 cases. *Cancer*. 1993;72:719–725.
62. Wittig JC, Bickels J, Kellar-Graney KL, et al. Osteosarcoma of the proximal humerus: long-term results with limb-sparing surgery. *Clin Orthop Relat Res*. 2002;397:156–176.
63. Bovee JV, van der Heul RO, Taminiau AH, et al. Chondrosarcoma of the phalanx: a locally aggressive lesion with minimal metastatic potential: a report of 35 cases and a review of the literature. *Cancer*. 1999;86:1724–1732.
64. Cormier JN, Pollock RE. Soft tissue sarcomas. *CA Cancer J Clin*. 2004;54:94–109.
65. Enneking WF, Spanier SS, Goodman MA. A system for the surgical staging of musculoskeletal sarcoma. *Clin Orthop Relat Res*. 1980;153:106–120.
66. Cormier JN, Huang X, Xing Y, et al. Cohort analysis of patients with localized, high-risk, extremity soft tissue sarcoma treated at two cancer centers: chemotherapy-associated outcomes. *J Clin Oncol*. 2004;22:4567–4574.
67. Thomas BP, Sasi K, Pallapati S, et al. Malignant tumors of the hand and wrist. *Indian J Plast Surg*. 2011;44:337–347.
68. Saint-Cyr M, Langstein HN. Reconstruction of the hand and upper extremity after tumor resection. *J Surg Oncol*. 2006;94:490–503.
69. Sluijmer HCE, Becker SJE, Ring DC. Benign upper extremity tumors: factors associated with operative treatment. *Hand (N Y)*. 2013;8:274–281.

16

Infections of the hand

Amy M. Moore and Ryan P. Calfee

SYNOPSIS

- Hand infections are common with diverse etiologies. It is important to have a high index of suspicion to diagnose and treat hand infections expeditiously in order to prevent morbidity and maximize outcomes.
- A thorough understanding of hand anatomy and the pathophysiology of hand infections is necessary to adequately provide treatment and improved functional outcomes.
- The treatment of hand infections includes the combination of early diagnosis, empiric broad-spectrum antibiotics – later tailored to culture data, and operative intervention.
- Patients should be followed closely as hand infections can rapidly progress or spread to deeper tissues. If no clinical response is noted within 24–48 hours of initial intervention, the treatment plan should be reassessed.
- A multidisciplinary team including physicians from the emergency department, radiology, infectious diseases and hand surgery as well as hand therapists are important for global care of the patient with a hand infection.

Introduction

Hand infections encompass a diverse array of diagnoses from paronychia involving the fingertip to necrotizing fasciitis of the hand and forearm. The etiology of infections is equally diverse; however, most are the result of direct inoculation of bacteria from penetrating trauma and lacerations. If not identified and treated expeditiously, these infections can result in significant morbidity.

The purpose of this chapter is to review the basic principles, evaluation, and management of patients presenting with infections based on anatomic location (fingertip, finger, hand, wrist, joints and bone). We will also briefly discuss infection mimickers such as gout and pyoderma gangrenosum. A multidisciplinary team, including specialists from infectious disease, radiology, emergency medicine, primary care and

hand surgery, is necessary to effectively diagnose and manage infections of the hand.



Access the Historical perspective section online at

<http://www.expertconsult.com>

Basic science/disease process

Skin and soft-tissue infections account for 1.7% of all emergency department visits in the United States.⁶ Further, hand infections remain one of the few surgical emergencies for hand surgeons and account for up to 35% of patients admitted to hand surgery services.⁷ The fingertip is the most common site for hand infections followed by the subcutaneous tissue of the dorsum and palm, tendon, joint and bone.^{8–10} The most frequent cause of major hand infections is a neglected wound with either a delayed presentation and/or appropriate initial treatment.⁹

Numerous factors influence the development and severity of hand infections. The body is capable of preventing an infection with contamination of less than 10^5 bacterial organisms per gram of tissue.¹¹ Higher concentrations of bacteria overwhelm phagocytic cells (polymorphonuclear cells and macrophages) and acute phase antibacterial proteins (lysozyme, C-reactive protein, interferon and complement) to produce infection.¹² Factors that impact the severity of infection include the anatomic location, virulence of the organism, viability and vascularity of the surrounding soft tissue, timing of intervention, and health status of the patient.

Immunocompromised patients are more vulnerable to, and suffer increased morbidity from infection. Malnutrition, immunosuppression, immunodeficiency, alcohol or intravenous drug abuse, autoimmune disorders, systemic steroid use and diabetes impair the immune response and increase risk of infection.^{13–15} These compromised hosts also have increased polymicrobial infections and opportunistic infections.^{8,9} Patients with weakened immunity may have

Historical perspective

The treatment for hand infections dates back to the Golden Age of Greece and there have been many contributions to our understanding of and ability to treat infections over time. Hippocrates, a Greek physician, is often referred to as the “true father of hand surgery”. He was born in 460 BC and authored works that described the treatment of wound infections in addition to the treatment of fractures, joints and dislocations.¹ His treatment principles were practiced and popularized in Greece and continue to hold true today. For example, in the treatment of infections, Hippocrates is quoted as saying that the dressing should be kept loose “so as not to intercept the pus but allow it to flow away freely”.²

Although not clearly delineated in the literature with regards to hand surgery, a few important steps in the evolution of medicine and surgery have certainly impacted our current understanding and treatment of hand infections. In 1846, the first surgical procedure was performed using sulfur ether inhalational anesthesia at Massachusetts General Hospital. The development of “painless” surgery could then be used for the treatment of hand infections with surgical drainage. Contributing to the understanding of the basis of infection and its treatment in the mid-1800s, Louis Pasteur used heat to remove undesirable microorganisms, which was later

termed “pasteurization”. This concept was recognized and utilized in the surgical arenas thereafter.¹

A momentous leap in the treatment of hand infections occurred when the relationship between hand anatomy and infection was established. In 1905, Allen Kanavel published his work on fascial and synovial spaces of the hand. Kanavel used injection studies to define the fascial spaces of the hand and described their patterns of communication.³ Based on his findings, he identified the appropriate location of surgical incisions which are still utilized today. A few years later, Kanavel also characterized infections as to their findings on exam. For example, he described the classic signs of flexor tenosynovitis, now referred to as Kanavel’s cardinal signs, as well as advocated for thorough surgical debridement and drainage of established infections.⁴

Finally, the introduction of antibiotics revolutionized the treatment of all infections. In 1929, Alexander Fleming identified a contaminant on a culture plate that inhibited growth of *Staphylococcus*. Years later this substance was purified and produced as the drug penicillin. Penicillin use became widespread in the 1940s and its positive impact on clinical results were evident.⁵ Although penicillin resistance was found early, alternative antibiotics have continued to be discovered and their importance in our current treatment algorithm for hand infections has not wavered.

attenuated clinical signs and symptoms which can lead to delayed recognition of infection and increased severity at presentation. Thus, it is important to have a high index of suspicion for infection when evaluating an immunocompromised patient with “hand pain”.

Causative organisms

Staphylococcus and *Streptococcus* species are the most common organisms to cause hand infection. *S. aureus* is particularly virulent, producing leukocidin, a neutrophil toxin. *S. aureus* has been reported to cause up to 80% of hand infections.^{7,16,17} Although Gram-positive organisms are most common, Gram-negative, fungal, mycobacterial organisms and viruses are also culprits especially in polymicrobial infections. Methicillin-resistant *S. aureus* (MRSA) infections, both nosocomial and community acquired, have increased in prevalence over the past few decades. In the United States, community-acquired MRSA is now responsible for the majority of hand infections.^{8,18,19} Risk factors for community-acquired MRSA include crowded living conditions such as day care, the homeless, inmates, athletes with shared clothing or sporting equipment, and military personnel. Empiric antibiotic coverage for presumptive MRSA infection is recommended based on the local prevalence of MRSA.¹⁹

Although *S. aureus* is the most common culprit of hand infections, it is helpful to consider the etiology of the infection and associate it with the possible offending microbial organism. Human bites, or “fight bites”, are notorious sources of hand infections. Although *S. aureus* and alpha-hemolytic *Streptococcus* are usually isolated from these wounds, *Eikenella corrodens* is also found. *Neisseria gonorrhea*, a Gram-negative diplococcus, should be considered in the young, sexually active patient with a hand infection without a clear nidus of infection. Domestic animal bites are usually polymicrobial, but are often associated with *Pasteurella multocida*. Fungal or mycobacterial organisms should be suspected in the presence of chronic, indolent infections. Atypical mycobacteria such as *Mycobacterium marinum* is associated with injuries from fishing, fish tanks and swimming pools. *Sporothrix schenckii* and *Enterobacter agglomerans* infections occur following contamination with soil or plant material such as rose thorns.^{12,20}

Appropriate antibiotic coverage should be chosen based on the severity of infection and the exposure history. Ideally, they would be initiated after Gram stain and cultures are obtained. In cases of severe infections, a multidisciplinary approach including an infection specialist is recommended to adequately treat the patient and optimize outcomes. Current antibiotic recommendations for common organisms are listed in Table 16.1.

- Obtain baseline lab work, X-rays, and blood cultures.
- Obtain wound cultures and start empiric antibiotics. Cover for MRSA if local prevalence is high.
- Once an area of fluctuance and/or abscess is identified, surgical intervention with incision, drainage, irrigation and debridement should be performed.
- Plan for multiple washouts (every 24–48 hours) until infection is controlled.
- Immobilize the extremity for tissue rest and elevation.
- Once tolerable, begin aggressive hand therapy to maximize return of function.

Pain, erythema, edema, fluctuance and tenderness are prominent features of an existing hand infection. Systemic signs are often rare. Early recognition and intervention can greatly improve outcomes.

When evaluating a patient with a possible hand infection, it is important to perform a thorough medical history to identify risk factors. Handedness, occupation, immunization history (e.g. tetanus), smoking, drug or alcohol abuse history and previous surgeries or trauma are important details to obtain. Prior personal or family history of MRSA infections is suggestive of another MRSA infection. On physical exam, it is important to assess the entire extremity for lymphangitic spread, indicating clinically advanced infection. A head to toe examination should also be performed to identify other sources or concomitant sites of infection.

Routine laboratory studies such as the white blood cell count (WBC) and the erythrocyte sedimentation rate (ESR) are often normal in the evaluation of a hand infection. When elevations do occur, they are usually associated with more severe cases.²¹ Measurement of the acute-phase reactant C-reactive protein (CRP) can be helpful when monitoring treatment response, especially in patients with osteomyelitis. The CRP level can elevate in response to a variety of stressors or clinical conditions such as surgery or trauma. Thus it is sensitive, but nonspecific. In cases requiring long-term parenteral antibiotics, i.e. osteomyelitis, flexor tenosynovitis, or necrotizing fasciitis, blood cultures should be obtained. These should be negative prior to any long-term indwelling line being placed.

Radiographic imaging is important in the assessment of hand infections. Plain radiographs should be taken with any presenting hand infection to rule out the presence of a foreign body or subcutaneous emphysema. They will also allow for assessment of the underlying bone and joints, providing either diagnostic information or a baseline for which to compare in the future as radiographic evidence of osteomyelitis occurs 2–3 weeks after the onset of infection.²² Ultrasound (US) and magnetic resonance imaging (MRI) are also useful tools for the diagnosis and treatment of musculoskeletal infections. US can diagnose early suppurative flexor tenosynovitis, localize foreign bodies and/or focal fluid collections. MRI is useful for early detection of osteomyelitis and can be used for evaluation of cellulitis, abscess formation and necrotizing fasciitis.²² For the diagnosis of osteomyelitis in the presence of hardware, a tagged ^{99m}Tc-labeled white blood cell radionuclide scan with bone marrow imaging can be performed. This study avoids the confounder of artifact or scatter seen on CT or MRI.²³

Diagnosis/patient presentation

Clinical tips

Global treatment of the patient with a hand infection

- Early recognition and intervention improve outcomes.
- Identify risk factors: Immunocompromised? Diabetes? Steroid use?

Table 16.1 Antibiotic recommendations for common organisms.

Organism	Antibiotic	Additional information
Methicillin-sensitive <i>Staphylococcus aureus</i>	Cephalexin, amoxicillin clavulanate (orally)	
Methicillin-resistant <i>Staphylococcus aureus</i>	Trimethoprim/sulfamethoxazole (orally), linezolid (orally or IV) If sulfa allergy, clindamycin or doxycycline Vancomycin (IV), daptomycin (IV) Quinupristin/dalfopristin (IV) Tigecycline (IV) Ceftaroline (IV)	Linezolid: expensive, avoid in endocarditis or meningitis, weekly complete blood cell monitoring Dapto: weekly creatinine phosphokinase monitoring
Vancomycin-resistant enterococci	Daptomycin, linezolid (orally or IV), tigecycline (IV), quinupristin/dalfopristin (IV)	
Gram negative	Piperacillin/tazobactam Ceftriaxone Ertapenem Quinolones/ciprofloxacin	
<i>Pseudomonas</i>	Piperacillin/tazobactam Cefepime Meropenem	
Anaerobic infections	Ampicillin/sulbactam, Piperacillin/tazobactam, ertapenem, meropenem Metronidazole Clindamycin Tigecycline	
<i>Vibrio vulnificus</i>	Ceftriaxone and doxycycline Imipenem and doxycycline	
Nocardia	Trimethoprim/sulfamethoxazole If sulfa allergy: imipenem, ceftriaxone, amikacin	6 months of treatment in immune-suppressed patients
<i>Sporothrix schenckii</i>	Itraconazole Fluconazole and voriconazole	
<i>Mycobacterium marinum</i>	Clarithromycin/azithromycin Trimethoprim/sulfamethoxazole minocycline Ethambutol	
<i>Aeromonas hydrophilia</i>	Ciprofloxacin Imipenem Trimethoprim/sulfamethoxazole	
Cutaneous anthrax	Ciprofloxacin Doxycycline	Treatment for 60 days to treat any remaining spores
Tularemia	Gentamicin and doxycycline	

(Reproduced with permission from Osterman M, Draeger R, Stern P. Acute hand infections. *J Hand Surg.* 2014;39:1628–35.)

Early or superficial infections, including cellulitis may respond to nonsurgical intervention. Antibiotics, immobilization and elevation should be initiated. Patients should be followed closely as the infection can rapidly progress or spread to deeper tissues necessitating operative management. Further, if no clinical response is noted following non-operative treatment, deeper involvement should be suspected. Once an area of fluctuance and/or abscess is identified, surgical intervention with incision, drainage, irrigation and debridement should be performed. Ideally, cultures would be obtained prior to the administration of antibiotics. Fluid should be sent for Gram stain, aerobic and anaerobic cultures, and sensitivities. Fungal stains, fungal cultures and mycobacterial cultures should be sent if suspicion is high or if the patient is immunocompromised.

In the following section we review the basic principles, evaluation, and management of specific upper extremity infections according to anatomic location. A comprehensive understanding of hand anatomy including the intricate synovial connections and spaces are essential for adequate treatment and improved surgical outcomes.

Fingertip

Paronychia

Paronychia accounts for 30% of all hand infections making it the single most common infection in the hand. This infection is most commonly caused by *Staphylococcus aureus* followed by *Streptococcus* and *Pseudomonas*.²⁴ Paronychias originate



Fig. 16.1 Acute paronychia involving the paronychium with inflammation extending towards the eponychial fold.

from either the proximal nail fold or the paronychium (skin fold on either lateral side of the nail plate). The infection typically begins unilaterally or just proximal to the nail. Untreated, the paronychia can expand around the nail, which is termed the “runaround” infection. The infection may also spread deep between the nail plate and the nail bed. Acute bacterial infection follows disruption of the barrier between the nail plate and the surrounding nail folds such as may occur with manicures, hangnails, or nail biting.

Early paronychia presents with pain, redness, and swelling (Fig. 16.1). As the infection progresses, gross purulence may collect around, or deep to, the nail plate. Extension toward the palmar fingertip may result in a felon. Before developing an associated abscess, the developing paronychia is treated with oral antibiotics and warm soapy soaks.²⁵

After developing an abscess, drainage is required. Small abscesses with thin skin coverings can be unroofed and cultured. However, in many of the cases referred for hand specialty care, formal surgical decompression is required. This decompression is performed with a digital block and a small elastic digit tourniquet. The authors recommend first elevating the involved proximal or lateral nail fold from the nail plate. If purulence has accumulated deep to the nail plate, then at least part of the nail is removed. Skin incisions are made parallel to the lateral nail folds if required. Paronychia involving the proximal nail fold may be incised transversely over the most superficial portion of the abscess or decompressed with incisions extending proximally from the corners of the nail fold (Fig. 16.2). In cases in which skin incisions are required, we leave a thin plastic drain or cotton gauze wick to allow passive egress of fluid. Patients are allowed to remove the drain/wick and dressing 1–2 days after surgery and continue soapy water soaks twice a day until all wounds are sealed and dry.

Chronic paronychia is a distinct entity most commonly found in patients with prolonged exposure of the fingertips to a wet environment. By definition, a paronychia is chronic after being present for at least 6 weeks. *Candida albicans* is the primary pathogen responsible for chronic paronychia. Patients with chronic paronychia present with thickened, indurated, and erythematous tissue proximal to the nail plate (Fig. 16.3). Nail plates may become thickened and discolored. The eponychial fold may retract. The pain associated with chronic paronychia is less impressive than that reported during acute paronychia infection. Chronic paronychia may involve multiple fingertips.




Fig. 16.2 Incisions for drainage of paronychia. (A) The nail plate and eponychial fold are elevated with a Freer elevator. (B) A skin incision is placed parallel to the lateral nail fold to drain the paronychia. (C) If proximal extension is needed, the incision can be carried from the corner of the nail fold and extended laterally at an angle. (D) A second skin incision can be performed to adequately drain the paronychia. (E) Wicking the incision site with gauze is recommended to prevent premature closure and re-collection of pus.



Fig. 16.3 Chronic paronychia involving thumb. (A) Dorsal view showing thickened, indurated and erythematous tissue proximal to the nail plate. The nail plate is also thickened and discolored. (B) Lateral view demonstrates retraction of the eponychial fold.

Treatment for chronic paronychia is frequently surgical but a trial of topical antifungal cream (2% ketoconazole or 2% miconazole) or oral antifungal medication (itraconazole or fluconazole) may be attempted. In the authors' experience, this may take months to obtain results and these medications are prescribed by a dermatologist. Eponychial marsupialization is the surgical treatment for chronic paronychia (Fig. 16.4). Performed with a digital block and tourniquet at the base of the finger, a 3–5 mm wide crescent-shaped portion of skin is removed starting 1 mm proximal to the eponychial fold. Although marsupialization has been described to various depths, the authors have removed the entire dermal layer but left the roof of the germinal matrix intact. Removing the deformed nail plate has reduced recurrence of chronic paronychia.²⁶ The wounds are left open for healing via secondary intention. Soft gauze dressings are changed once or twice a day until the wounds have healed. In our experience, marsupialization has been effective but changing the patient's occupational or leisure activities to minimize prolonged exposure of the fingertips to liquids is important to prevent recurrence.

Paronychia must be differentiated from herpetic whitlow at the time of presentation. Herpetic whitlow is a viral infection caused by herpes simplex type 1 (60% of cases) or 2 (40% of cases). It is caused from a viral inoculation of the host via infected body fluids. The virus invades the dermis and subcutaneous tissue and symptoms begin 2–14 days after exposure. Symptoms of this infection include a painful, burning or tingling sensation of the affected digit followed by erythema, edema and the development of 1–3 mm grouped vesicles over the next 7–10 days (Fig. 16.5). The infection is usually self-limiting with resolution within 3 weeks. Herpetic whitlow is characterized by a primary infection followed by a latent period in which the virus enters the cutaneous nerve endings and migrates to the peripheral ganglia. Recurrences can be induced with physiologic or psychological stress, fever, and sun exposure. Unroofing the vesicles may allow for a definitive diagnosis, usually with culture and Tzanck smear, but deeper debridement risks secondary bacterial infection or more disseminated herpetic infection.^{17,27}

Felon

A felon is an infection in the subcutaneous pulp space of the fingertip. *Staphylococcus aureus* remains the most common




Fig. 16.5 Herpetic whitlow. Clinical signs include 1–3 mm grouped vesicles present along the digital neurovascular bundles.

causative organism. Felon infections have been demonstrated to be increasingly secondary to community acquired MRSA.¹⁸

A felon behaves like a deep space infection forming an abscess because it is confined within the matrix of vertical fibrous septa in the pulp space. Felons most commonly follow penetrating trauma to the fingertip. Patients present with painful swollen fingertips that are exquisitely tender over the pulp space (Fig. 16.6). The swelling and pain should be confined to the pulp space distal to the distal interphalangeal flexion crease. When not treated, the felon may progress to cause tissue necrosis in the pulp space or seed infection into the distal phalanx (osteomyelitis) or the flexor tendon sheath (tenosynovitis).¹⁷

With the exception of the rare pulp space infection presenting prior to abscess formation, felons require surgical decompression. Similar to paronychia, various surgical approaches are described (Fig. 16.7). A longitudinal incision in the pulp space is an approach that minimizes risk to the digital neurovascular structures. Alternatively, a midaxial incision may be used (typically radial side of small and thumb, ulnar side of index, long, and ring fingers to minimize the chance of painful pinch or resting the hand on a painful scar). Regardless of the skin incision, blunt dissection with a tenotomy scissor or hemostat is required to disrupt the fascial bands in the pulp space to ensure complete decompression. Nonviable tissue is debrided and the wound is irrigated. A small plastic drain or cotton gauze wick is left in the wound and dressing changes with soapy water soaks and drain/wick removal commence the following day.

Finger

Pyogenic flexor tenosynovitis

Clinical tips

Pyogenic flexor tenosynovitis

- Kanavel's signs on exam include:
 - fusiform digit
 - flexed resting posture of digit
 - tenderness over the flexor tendon sheath
 - pain with passive extension of the digit.
- Pyogenic flexor tenosynovitis warrants urgent surgical intervention.




Fig. 16.4 Eponychial marsupialization for chronic paronychia. (A,B) A 3 mm wide crescent-shaped excision of skin is performed to the depth of the germinal matrix. The germinal matrix is maintained and unharmed.



Fig. 16.6 Severe paronychia with felon. **(A)** Dorsal view of purulent paronychia with felon. **(B)** Volar view of midline incision. **(C)** Dorsal view of debrided finger with nail plate removed.

- Open the tendon sheath proximally over A1 pulley and expose sheath distally either through midaxial or volar zigzag incision.
- Use 5 French pediatric feeding tube to irrigate tendon sheath copiously from proximal to distal.
- Plan for multiple washouts (every 24–48 hours) until infection is controlled.

The flexor tendon sheath is a double-walled structure with a visceral and parietal layer. The visceral layer is closely adhered to the tendon forming the epitendon. The outer parietal layer is in contact with the pulley system. A closed system is created between these two mesothelium-lined layers. This synovial sheath envelops the flexor tendons from the level of the insertion of the flexor digitorum profundus at the distal interphalangeal joint to the metacarpal neck proximal to the A1 pulley

(Fig. 16.8). The flexor tendon sheaths of the thumb and small finger communicate with the radial and ulnar bursae, respectively, and extend into the carpal tunnel and space of Parona.²⁸ In up to 80% of individuals the radial and ulnar bursae communicate. The nutrient supply to the flexor tendons is from direct vascular inflow via the vincula in addition to diffusion from the synovial fluid.

Pyogenic flexor tenosynovitis occurs when bacteria is inoculated into the synovial sheath – most commonly from penetrating trauma. Bacterial proliferation in the sheath leads to increased pressure and disruption of the vascular supply and the critical gliding mechanism. If not treated expeditiously, this can lead to tendon necrosis and rupture.²⁹ Due to the synovial connections as described above, infection can travel quickly throughout the hand and proximally into the forearm. In patients with communicating radial and ulnar bursae, a horseshoe abscess can occur.

In 1914, Allen Kanavel described the physical findings of patients with pyogenic flexor tenosynovitis. Kanavel's




Fig. 16.7 Incisions for felon drainage. **(A)** Cross section of the distal fingertip, showing inflammation and collection of fluid within the septa. **(B)** A unilateral midlateral incision allows access to the septations of the distal pulp. Care needs to be taken to avoid the neurovascular bundles. **(C)** A single volar incision can be used. This approach has less risk to the digital neurovascular bundles. To avoid scar contracture, the incision should not pass the flexion crease.

cardinal signs include (1) tenderness over the course of the tendon sheath, (2) a flexed posture of the finger, and (3) excruciating pain on passive extension of the finger. Later a fourth sign, fusiform swelling of the finger, was added.^{1,3,4} Disproportionate pain on passive extension is the most sensitive and reproducible clinical sign. However, not all signs are present if the patient presents with a very early infection or if the patient is immunocompromised. Palpation over the flexor tendon sheath is helpful to differentiate pyogenic flexor tenosynovitis from other diagnoses such as gout, herpetic whitlow or septic arthritis.

The treatment of pyogenic flexor tenosynovitis includes both surgical and medical management. As most patients present after 24–48 hours after inoculation, surgical incision and irrigation of the flexor sheath is usually warranted. Parenteral antibiotic therapy should also be initiated. As direct inoculation is the most common source of infection, skin flora, i.e., *S. aureus* and *Streptococcus* species, should be covered and antibiotics should later be tailored to culture data. If non-operative treatment is chosen in the case of early tenosynovitis, then close observation is necessary.

Many surgical drainage approaches have been described varying from extensive open dissection of the sheath to limited exposure and catheter irrigation (Fig. 16.9).^{4,30} The goal of treatment is to adequately irrigate and drain the synovial space while protecting the critical structures of the sheath, i.e., the pulley system. We recommend a proximal incision made

proximal to the A1 pulley. Distally the tendon sheath is exposed either through a midaxial or volar zigzag incision. A 14-gauge angiocatheter or a 5 French pediatric feeding tube is placed in the proximal incision for irrigation. Irrigation should always proceed from proximal to distal to avoid proximal seeding of the infection. Wounds are left opened, usually wicked for the first 24 hours. If there is lack of clinical response within 24–48 hours using a limited exposure then more extensive debridement should be pursued (Fig. 16.10).

After surgical drainage, close observation is required and multiple trips to the operating room may be needed for adequate debridement and irrigation. Patients should remain on parenteral antibiotics as determined with consultation from infectious disease specialists. Active and aggressive hand therapy should begin as soon as tolerated to improve range of motion of the finger. The most common complication after flexor tenosynovitis is loss of active motion. Risk factors associated with poor outcomes include delayed presentation, age greater than 43 years, diabetes mellitus, peripheral vascular disease, renal failure, subcutaneous purulence, digital ischemia and polymicrobial infections.¹⁵




Fig. 16.8 Anatomy of the digital flexor tendon sheaths, radial and ulnar bursae. The synovial sheath envelops the flexor tendon from the insertion of the flexor digitorum profundus to the metacarpal neck proximal to the A1 pulley.




Fig. 16.9 Incisions for approaching infections of the (A) volar and (B) dorsal hand.

Hand

Deep space infections

In 1905, Allen Kanavel published his work on the fascial and synovial spaces of the hand. Kanavel used injection studies to define the fascial spaces of the hand and described their patterns of communication.^{1,3,4} Based on his findings, he identified the appropriate location of surgical incisions which are still used today. These potential subfascial or deep spaces include the subaponeurotic, thenar, midpalmar, hypothenar, interdigital webspace, and Parona's spaces (Fig. 16.11). Knowledge of the relevant anatomy associated with these spaces is critical for adequate management of infections associated with them.

Deep space infections of the hands are caused by direct penetrating trauma, contiguous spread from other areas of the hand, and more rarely, from hematogenous spread. *S. aureus* and *Streptococcus* species are most commonly implicated as the infectious organism. Antibiotic therapy in addition to incision, irrigation and debridement are the mainstay of management for deep space infections.³¹ There are multiple

accepted approaches to the deep spaces of the hand (see Fig. 16.9).

The subaponeurotic space is found on the dorsum of the hand in the space bound by the extensor tendons dorsally and the metacarpals with interosseous muscles volarly. Patients present with significant edema and erythema on the dorsum of the hand with difficulty and pain with passive and active finger extension. Subcutaneous infections are difficult to distinguish from subaponeurotic space infections but surgical intervention is advocated for both. Longitudinal incisions avoiding exposure and desiccation of the extensor tendons is preferred.

The thenar space is located volar to the fascia of the adductor pollicis muscle and dorsal or deep to the index flexor tendons. The radial extension is to the adductor pollicis insertion on the proximal phalanx of the thumb. The midpalmar septum of the third metacarpal is the ulnar extension of the space. On presentation, the thumb is often held in palmar abduction and is exquisitely tender to palpation. Often in more severe cases, the infection extends into the first webspace and dorsoradial aspect of the hand. This extensive infection has been described as a *dumbbell* or *pantaloon* infection.³²




Fig. 16.10 Pyogenic flexor tenosynovitis. (A) Clinical photo of index finger pyogenic flexor tenosynovitis caused by a dog bite. (B) The patient required an open debridement and multiple washouts to obtain control of the infection and remove nonviable soft tissue.

Incision and drainage can be performed from either a dorsal or volar, or more commonly, a combined approach, but should avoid running parallel to the first webspace to avoid a first webspace contracture.

The midpalmar space is located deep to the flexor tendons of the long, ring and small fingers and superficial to the long and ring finger metacarpals and interosseous muscles. It extends radial to the septum of the long finger metacarpal and ulnar to the hypothenar musculature. On presentation, volar hand edema is notable and there is loss of the palmar concavity. Patients have pain with passive motion of the long and ring fingers. Multiple incision options exist, but regardless of the choice, a large exposure is preferable to obtain access to this space while carefully protecting the critical neurovascular structures of the palm.

The hypothenar space infection is extremely rare. This space is bound radially by the hypothenar septum originating from the palmar fascia and is deep to the hypothenar musculature but superficial to the small finger metacarpal. On presentation, there is soft-tissue swelling of the hypothenar

eminence. A longitudinal incision is made over the hypothenar musculature extending through the hypothenar fascia.

The second, third and fourth interdigital web spaces are located beneath the palmar fascia and dorsally by the dorsal hand fascia. An infection of this space is termed a *collar button* abscess because it spreads volarly and dorsally but is narrowed at the intermetacarpal extension. On presentation, the fingers of the affected webspace are held in abduction (Fig. 16.12). Volar and dorsal incisions are advocated for adequate drainage of this space. Direct incision through the webspace should not be performed to avoid adduction contracture.

The space of Parona is located proximally deep to the flexor tendons and superficial to the pronator quadratus muscle. This space is contiguous with the radial and ulnar bursae and infections to this space are often extensions from infections of the hand. Patients present with significant forearm edema, tenderness and pain with finger flexion. Depending on the severity of the infection, acute carpal tunnel syndrome can also be seen.¹⁶ A longitudinal incision on the ulnar aspect of the forearm is recommended with extension distally across




Fig. 16.11 Deep spaces of the hand.




Fig. 16.12 Collar button abscess. **(A)** Volar view of hand with second interdigital webspace infection. **(B)** Dorsal view showing the index and long fingers held in abduction. Volar and dorsal incisions are recommended for adequate drainage of this space.

the wrist crease. This includes release of the transverse carpal ligament. The median nerve and flexor tendons are protected.

In general, incisions should be planned to allow for adequate irrigation and debridement of nonviable tissue while also protecting important neurovascular structures. The wounds created from surgical drainage and irrigation should most often be left open and packed with moist to dry dressings. If critical structures are exposed, tacking sutures can be placed while still allowing adequate packing of the affected spaces. Alternatively the wounds can be loosely closed over a silastic drain. The hand should be splinted, elevated and closely monitored for clinical improvement. One should have a low threshold for return to the operating room if there is lack of clinical improvement over the following 24–48 hours. Parenteral antibiotic therapy is begun after cultures are obtained and is later tailored to culture results. Early motion with the assistance of a hand therapist should be emphasized to avoid postoperative complications of tendon adhesions and joint stiffness.

Wrist/forearm

Necrotizing fasciitis

Clinical tips

Necrotizing fasciitis

- Necrotizing fasciitis is a surgical emergency.
- Most common risk factors include:
 - history of drug abuse
 - immunosuppression
 - diabetes.
- Group A β -hemolytic streptococcus is the most common organism.
- The characteristic findings include pathologic “dishwater” fluid or pus along the fascial planes. In involved areas, the subcutaneous tissues easily separate off the underlying fascia.
- All necrotic tissue and fibrinous material should be radically debrided.
- Plan for multiple washouts and debridements (every 24–48 hours) until infection is controlled.

Necrotizing fasciitis is a rare infection that requires emergent surgery. This infection spreads rapidly and threatens both life and limb. Despite the severity of the infection, it often begins after rather minor skin trauma. In a review of 317 affected limbs, demographic risk factors for necrotizing fasciitis included intravenous drug abuse, smoking and trauma, with diabetes being the most common medical comorbidity.³³ Immunosuppression, liver disease, and peripheral vascular disease have also been associated with this infection. Necrotizing fasciitis is often polymicrobial although group A β -hemolytic streptococcus is the most common organism identified in isolation.³⁴

The characteristic presentation for necrotizing fasciitis includes the painful limb with rapidly progressive erythema or bullae (Fig. 16.13). Across two series, the most common examination findings at the time of presentation were warmth (97%), erythema (95–100%), edema (82%) and disproportionate pain (98–100%).^{34,35} Patients are frequently hemodynamically unstable with elevated white blood cell counts, coagulopathy, and shock. When the infection is spreading up a limb along the fascial planes, the clinical situation can rapidly deteriorate in hours. Radiographs and CT or MRI may demonstrate gas within the soft tissues but the sensitivity and specificity of imaging for necrotizing fasciitis is variable. If surgical debridement will be delayed, pursuing advanced imaging in acute cases of necrotizing fasciitis is not recommended. The formal diagnosis of necrotizing fasciitis is dependent on microscopic examination of biopsied fascia.³⁶

Aggressive, emergent surgical debridement is required to treat necrotizing fasciitis. The infection typically extends wider than anticipated. The characteristic findings during surgery include pathologic “dishwater” pus along the fascial planes. In involved areas, the subcutaneous tissues easily separate off the underlying fascia. All necrotic tissue and fibrinous material is radically debrided. The skin and muscle




Fig. 16.13 Necrotizing fasciitis in a neutropenic patient with leukemia. **(A)** Subcutaneous emphysema present on forearm films. **(B,C)** Volar and dorsal views of upper extremity showing classic signs of progressive erythema and bullae are present. **(D–G)** Multiple washouts were performed to gain control of infection.

are not directly involved with this infection. Although antibiotics are not the primary treatment for this aggressive infection, empiric drugs are started immediately as all attempts are made to stabilize the patient. Empiric treatment includes a cephalosporin for Gram-positive coverage, gentamicin for Gram-negative effect, and penicillin for potential anaerobic involvement. Depending on the local prevalence, MRSA coverage may be advantageous. Antibiotic delivery is subsequently tailored according to culture results after the initial debridement.

In the best cases, surgical debridement preserves both the patient's life and limb. Planned, staged debridements of affected limbs are expected with an average of 3–4 debridements per patient.^{33,34,37} Debridements are repeated every 24–48 hours based on the patient's clinical condition.


Joints

Septic arthritis

Septic arthritis requires prompt diagnosis and treatment to prevent articular destruction. Any joint from the fingers to the wrist can be affected. Septic arthritis most commonly results from penetrating injury, hematogenous spread, or from extension of infection from surrounding tissue. "Fight bite" injuries over the proximal interphalangeal (PIP) and metacarpophalangeal (MCP) joints are the most common penetrating injury and in a series of 159 injured hands, joint penetration was confirmed in 96% of cases and intra-articular purulence encountered in all cases explored >24 hours after injury (Fig. 16.14).³⁸ Distal interphalangeal (DIP) joints are at risk for septic arthritis following rupture of mucous cysts (Fig. 16.15). *S. aureus* and *Streptococcus* are the most common pathogens producing septic arthritis. Infrequent but notable causes of mono-articular septic arthritis include *Neisseria gonorrhoeae* in the young adult and *Haemophilus influenzae* in children.

Septic arthritis is characterized by swelling and pain with near complete loss of joint motion (active and passive) secondary to pain. Any periarticular penetrating trauma complicated by subsequently increasing pain and lack of motion should be evaluated for a septic arthritis. Fluctuance is difficult to appreciate in the small joints of the fingers and wrist. Although C-reactive protein levels and erythrocyte sedimentation rate may be elevated, these markers are not specific to infection and do not differentiate between septic arthritis and systemic inflammatory arthropathy. Joint aspiration is useful as both a diagnostic and potentially therapeutic measure as the differential diagnosis routinely includes gout or pseudogout. The patient history is important and should include any history of inflammatory crystalline arthropathy (although the hand can be the first manifestation) and to note whether or not any recent systemic illness occurred.

Once diagnosed, septic arthritis requires drainage of the inflammatory fluid to preserve articular surfaces. Operative approach to the DIP, PIP, and MCP joints is standard dorsal incisions. For the DIP joint, a dorsal H or Y type incision affords excellent exposure while avoiding the nail bed tissue. The capsule of the DIP joint is excised from either side of the terminal tendon. The PIP joint is approached between one lateral band and the center slip of the extensor mechanism.



(A)



(B)

Fig. 16.14 Septic arthritis caused by "fight bite". (A) During clenched fist injury, the tendon and joint are usually penetrated. (B) A typical appearance of septic arthritis due to a "fight bite". A laceration is present over the metacarpal phalangeal joint and there is edema with surrounding erythema.

The MCP joint is approached either through the extensor hood (midline or adjacent to the extensor tendon) or by developing the interval deep to each sagittal band which allows complete capsulectomy without any compromise of the extensor apparatus. The surgical approach to any of these joints incorporates any open wounds or draining sinuses. For the septic wrist, debridement can be completed arthroscopically or open.³⁹ In our practices, we use a dorsal gentle S-shaped incision with elevation of the extensor compartments after opening the third extensor compartment. Either a longitudinal or ligament-sparing capsulotomy is performed and the radiocarpal, midcarpal, and distal radio-ulnar joints are debrided. Care is taken to preserve the dorsal radio-ulnar ligament and triangular fibrocartilage complex (TFCC).

After capsulectomy, the joints are irrigated and loose synovial tissue is debrided. No attempt is made to close the capsule and skin wounds are loosely approximated leaving room for small elastic drains. When gross purulence is encountered, it is our practice to routinely return to the operating room for a second debridement 48 hours later. Cultures are taken during




Fig. 16.15 Septic arthritis of distal interphalangeal (DIP) joint. (A) Dorsal and (B) lateral view of infected mucous cyst after attempted drainage by the patient. (C) X-rays demonstrate classic dorsal osteophyte of DIP joint with narrowing.

the initial debridement and an infectious disease specialist is consulted as parenteral antibiotics are typically recommended for several weeks.

If patients have a medical contraindication to surgery, serial aspiration with irrigation is performed. In that case, the involved joint is aspirated and then flushed with saline with inflow and re-aspiration until the fluid leaving the joint is clear.

Bone

Osteomyelitis

Osteomyelitis is defined as a microbial invasion of the bone. It accounts for 6% of hand infections and 70% of osteomyelitis cases involve a single bone, most often the distal phalanx.⁴⁰ A bone infection can lead to substantial morbidity and even




Fig. 16.16 (A) Chronic ulcerative wound in an IV drug abuser. (B,C) Forearm X-rays demonstrate underlying periosteal reaction of the ulna consistent with osteomyelitis.

amputation, thus its identification and adequate treatment are imperative.

There are numerous etiologies for osteomyelitis, but the most common mechanisms are penetrating wounds, open fractures, contiguous spread from an adjacent infection and hematogenous seeding from a distant infection.^{12,16} *S. aureus* and *Streptococcus* species are the usual offending organisms. A bone biopsy is the most accurate method for isolating the causative organism and allowing for narrowed antibiotic use.

In the development of osteomyelitis, there is a reproducible sequence of events. Initially causative organisms from etiologies given above will cause microthrombi within intraosseous vessels and periosteal elevation. This is followed by osteolysis. If the infection is allowed to progress, a sequestrum, or bone abscess, is formed. In effort to contain the infection, a sclerotic margin is formed around the infection called an involucrum. This *sequestrum involucrum* indicates chronic infection and prevents blood flow to the infection and limits antibiotic penetration.¹² Thus, in these circumstances open debridement is required.

Patients with osteomyelitis present with pain, erythema and edema. Often patients have been previously treated for superficial infections without resolution (Fig. 16.16). Systemic symptoms are rarely found at presentation. ESR and WBC are usually normal, but CRP levels can be elevated. Radiographic findings are usually absent early in the disease process, thus a high index of suspicion is needed to accurately diagnose osteomyelitis. After 2–3 weeks of infection, changes on plain radiographs can be seen (Fig. 16.17). These include osteolysis, osteopenia, osteosclerosis, periosteal reaction and metaphyseal rarefaction.^{12,41} The presence of a sequestrum or involucrum indicates advanced disease. Radionuclide WBC scans or MRI can be used to detect early disease prior to changes on plain radiographs.

The treatment of osteomyelitis involves early detection, surgical debridement of infected tissue, stabilization of bone (when necessary) and antibiotic therapy guided by bone biopsy and sensitivities. Parenteral therapy is the preferred method of antibiotic delivery for bone infections. However, a multidisciplinary approach including an infectious disease consultation is recommended. Early detection of osteomyelitis with the absence of osteonecrosis can sometimes be treated without surgical debridement and close follow-up.¹² Surgical techniques that can be employed to eradicate infection include creation of a cortical window and bone curettage. In severe





Fig. 16.17 (A) Initial X-ray of 2-year-old child with nail-bed injury. (B) X-ray 2 weeks after injury when patient presented with increased pain, erythema and edema of finger. There is cortical destruction of the middle phalanx consistent with osteomyelitis.

cases, bone resection and/or amputation may need to be performed. If a sequestrum is present, complete surgical debridement of the devitalized tissue is required to prevent recurrent infections.

Mimics of infection

Gout

Gout is a crystalline arthropathy that is typically a leading diagnosis in the differential when approaching acute infections. Patients with gout have abnormal uric acid metabolism and experience gout flares when uric acid crystals come out of solution in cool peripheral joints. Affected joints acutely become erythematous, painful, and swollen. These joints are similar to septic joints in that they are painful to move but typically exhibit more sensitivity to even light touch and the patients do not routinely have any antecedent infection or trauma that would produce a septic joint. Gout is the leading presumed diagnosis in an older patient with a spontaneous erythematous and painful DIP joint when the inflammation clearly is centered over the joint as opposed to being contiguous with the paronychia. The definitive diagnosis is established by identification of negatively birefringent crystals in joint fluid under polarized microscopy. Secondary bacterial infection can occur in the setting of gout so joint fluid is also sent for Gram stain and culture. Gout is treated with either non-steroidal anti-inflammatories (NSAIDs) or oral steroids. Relatively rapid improvement is expected within a few days. In chronic uncontrolled gout, painful tophi may develop and are surgically debulked if symptomatic. With recurrent gout attacks, patients should be counseled on dietary modifications and consideration is given to chronic suppressive medical treatment coupled with gout-specific medication for attacks.

Pseudogout

Pseudogout is a second crystalline arthropathy similar to gout. It also affects peripheral joints and presents with the same acute onset of warm, erythematous, painful joints. Pseudogout attacks result from crystallization of calcium pyrophosphate. This crystal is positively birefringent under polarized microscopy. Unlike gout, dietary modifications are not preventative. On radiographs, pseudogout characteristically produces calcified soft tissues such as the TFCC. Treatment consists of immobilization for comfort and either NSAIDs or steroid medication.

Pyogenic granuloma

Pyogenic granulomas are a benign process although the outward appearance is typically quite concerning for patients. This characteristically exophytic mass appears like a mass of granulation tissue that is friable and easily bleeds (Fig. 16.18). There is no surrounding erythema. These masses often follow a penetrating injury. Topical silver nitrate is the initial treatment. This can be repeated several times if needed. If the mass does not involute, surgical excision is expected to be curative. Under tourniquet control, a 1-mm border of skin is excised with the stalk of the granuloma. The underlying subcutaneous tissues are typically normal in appearance and recurrence is not expected.⁴² The wound can be closed primarily or left to heal by secondary intention.



Fig. 16.18 Pyogenic granuloma of finger after previous superficial trauma.

Pyoderma gangrenosum

This ulcerative skin lesion expands centrifugally with a necrotic center. It is associated with systemic diseases including ulcerative colitis and Crohn's disease in addition to diabetes and rheumatoid arthritis. When recognized, pyoderma gangrenosum is managed with corticosteroids and local wound care. Surgical debridement, although contraindicated, has often occurred prior to establishing the diagnosis.

Patient selection

A thorough history and physical as well as a high index of suspicion is required when evaluating patients who present with a painful, erythematous and swollen hand. The diagnosis of a hand infection has to be based not only on anatomical knowledge, but also on medical knowledge to distinguish surgical problems from rheumatological ones. The key to improved outcomes and decreased morbidity is early identification of infection combined with appropriate medical and surgical management.

Postoperative care

After treating infections surgically, most wounds are left open to drain and allow secondary healing as long as vital structures are not exposed. When closure is required, critical structures are covered and drains are placed to allow drainage. For most infections, we recommend soapy water soaks to be completed twice daily starting 1–2 days after debridement. Drains are removed at the first soak. Damp to dry dressings are continued until wounds have sealed.

For substantial infections with planned staged debridements, we recommend either damp to dry dressings or negative-pressure dressings. The negative-pressure dressing is highly effective in drawing out edematous fluid. If using negative-pressure dressings, then daily complete blood counts

should be monitored as hemoglobin values can drift down with the continuous fluid loss.

Outcomes, prognosis, and complications

Most hand infections are readily managed with surgical debridement and antibiotics. Risk factors for poor outcomes or the need for amputation to control infection include immunocompromised hosts (e.g., diabetics, transplant patients, rheumatoid arthritis patients on disease-modifying drugs) and patients that smoke tobacco or have compromised peripheral vasculature. In these patients with impaired healing potential, initial counseling should include the possibility of amputation or other salvage procedures due to inability to heal.

Most abscesses and focal infections will resolve without long-term sequelae. However, stiffness is a common complication following pyogenic flexor tenosynovitis or septic arthritis. This is frequently proportional to the degree of infection and is managed with early range of motion and aggressive therapy following the resolution of infection. However, even with simple “fight bite” infections, lost motion at the injured PIP joint is common with a recent series documenting a mean loss of 24° extension, and a loss of 30° of flexion.³⁸

Notably, a septic wrist is a marker of systemic frailty and illness. In a large series of 36 patients with 40 septic wrists both open and arthroscopic treatment were effective. Although repeated irrigation and debridement were frequent, the arthroscopically treated patients had fewer operations and shorter hospital stays. However, the 90 day perioperative mortality rate for this diagnosis was high with 18% in patients treated open and 21% in the patients treated arthroscopically.³⁹ Similar to the elevated mortality after femoral neck fracture in the older adult, the septic wrist is not the cause of mortality but the systemic illness necessary to produce a septic wrist is substantial.

When considering the ultimate outcome after necrotizing fasciitis, a life saved and a limb salvaged is a success. The incidence of amputation for necrotizing fasciitis is approximately 20–30%. The overall incidence of mortality after necrotizing fasciitis is also 20–30% across series.^{33,34,37} The odds of death increase with systemic illness. Anaya *et al.* determined in 166 patients that comorbid cardiac disease, WBC >30 000, and Cr >2 mg/dL were all risk factors for death.⁴³

Secondary procedures

Clinical tips

Secondary procedures

- Once the infection is eradicated, secondary procedures can optimize function.
- Scar contractures can be treated with Z-plasty releases to improve joint excursion.
- Flexor tenolysis may improve function after pyogenic flexor tenosynovitis but there must be:

- Tissue equilibrium
- Plateaued progression with hand therapy
- Significantly greater passive than active range of motion of the digit
- Patient compliance with hand therapy and a home exercise program.
- Arthrodesis is a reasonable solution to the painful stiff joint with arthrosis after infection.
- Amputation is always a consideration as a secondary procedure or immediate salvage depending on the extent of infection.
- When amputating digits for infection, amputate through joints with preservation of the articular surface on the proximal bone to keep that portion of the skeleton sealed.

After eradication or control of infection, secondary procedures may be required to optimize function. Even straightforward soft-tissue infections may leave scars that contract or limit joint excursion. For these superficial scars, we have had good success with standard Z-plasty scar rearrangement to restore tension-free motion. Tenolyses of the flexor or extensor tendons may be needed following either subcutaneous abscesses, deep space infections, or flexor tenosynovitis. When considering tenolysis, it is important that the soft tissues have reached an equilibrium at which point recurrent transient swelling has ceased and the tissues have softened from a hardened or “woody” state common after trauma. Second, patience is warranted in allowing the patient to truly plateau with therapy before adding another surgical insult to the digit. The patient should have significantly more passive than active range of motion to expect improvement from tenolysis. One must also consider each patient’s ability to participate in appropriate therapy as the success of tenolyses is strongly dependent on the postoperative course.

Arthrodeses are a more common secondary procedure after intra-articular infections. Arthrodesis is a reasonable solution to the painful stiff joint with arthrosis after infection. The authors recommend performing arthrodeses through prior incisions if possible and taking care to raise full-thickness flaps for exposure. For the interphalangeal joints, these flaps can raise the extensor apparatus with the skin as a single layer. In the hand and wrist, the authors have not routinely considered arthroplasty after infection. Despite being feasible after debridement and a prolonged course of antibiotics, arthroplasty is not expected to increase motion in what are usually stiff affected joints.

Lastly, amputation is always a consideration as a secondary procedure or immediate salvage depending on the infection. Persistent osteomyelitis or recalcitrant soft-tissue infections (e.g., fungal) are certainly well treated with amputation. Likewise, amputation for the post-infected digit that is either persistently hypersensitive or bypassed secondary to pain and stiffness is often the best option for the hand. When amputating digits for infection, the authors prefer to amputate through joints with preservation of the articular surface on the proximal bone to keep that portion of the skeleton sealed. For ray resections after infection, the authors recommend avoiding osteotomy and transposition of an adjacent metacarpal as

that necessitates internal fixation and requires healing at the transposition site.

Future directions

The identification and treatment of hand infections have remained relatively unchanged since first described by Allen

Kanavel in 1905. A clear understanding of hand anatomy and pathophysiology is important for early identification and effective medical and surgical management. Over the past few decades, the incidence and prevalence of MRSA infections have risen. As the offending microbial milieu changes, the development of effective antibiotic coverage is imperative for adequate treatment of infections.



Access the complete reference list online at

<http://www.expertconsult.com>

3. Kanavel A. An anatomical and clinical study of acute phlegmons of the hand. *Surg Gynecol Obstet.* 1905;1:221–259. *In this seminal manuscript from 1905, Allen Kanavel reports his work on the fascial and synovial spaces of the hand. He used injection studies to define the fascial spaces of the hand and described their patterns of communication. Based on his findings, he identified the appropriate location of surgical incisions which are still utilized today.*
7. Tosti R, Ilyas AM. Empiric antibiotics for acute infections of the hand. *J Hand Surg Am.* 2010;35:125–128.
12. Barbieri RA, Freeland AE. Osteomyelitis of the hand. *Hand Clin.* 1998;14:589–603, ix. *In this manuscript, Barbieri and Freeland review the important details of osteomyelitis. From pathophysiology and diagnosis to the medical and surgical management, the authors nicely outline and provide a comprehensive description of the critical factors that underlie this significant and often morbid hand infection.*
15. Pang HN, Teoh LC, Yam AK, et al. Factors affecting the prognosis of pyogenic flexor tenosynovitis. *J Bone Joint Surg Am.* 2007;89:1742–1748.
19. Harrison B, Ben-Amotz O, Sammer DM. Methicillin-resistant *Staphylococcus aureus* infection in the hand. *Plast Reconstr Surg.* 2015;135:826–830. *In this manuscript, the authors review and summarize the most recent literature on methicillin-resistant S. aureus infections of the hand. They provide a detailed description of the epidemiology, microbiology, clinical presentation, and treatment algorithms of MRSA hand infections. They argue that given the increased prevalence of community-acquired MRSA over the past two decades, empiric coverage for MRSA should be provided for the initial treatment of hand infections if local prevalence rates exceed 10–15%.*
25. Brook I. Paronychia: a mixed infection. *Microbiology and management.* *J Hand Surg Am.* 1993;18:358–359.
29. Schnall SB, Vu-Rose T, Holtom PD, et al. Tissue pressures in pyogenic flexor tenosynovitis of the finger. Compartment syndrome and its management. *J Bone Joint Surg Br.* 1996;78:793–795.
31. Burkhalter WE. Deep space infections. *Hand Clin.* 1989;5:553–559.
33. Angoules AG, Kontakis G, Drakoulakis E, et al. Necrotising fasciitis of upper and lower limb: a systematic review. *Injury.* 2007;38:S19–S26. *In this systematic review, the authors nicely describe the clinical presentation, predisposing factors, surgical management, and outcomes of necrotizing fasciitis affecting the extremities. A total of 451 patients were analyzed. They found that 22.3% of patients had an amputation or disarticulation of a limb to control infection. Mortality rate was as high as 21.9%.*
39. Sammer DM, Shin AY. Comparison of arthroscopic and open treatment of septic arthritis of the wrist. *J Bone Joint Surg Am.* 2009;91:1387–1393. *A septic wrist is a marker of systemic frailty and illness. In a large series of 36 patients with 40 septic wrists, the authors found that both open and arthroscopic treatment were effective. However, the arthroscopically treated patients had fewer operations and shorter hospital stays. The 90 day perioperative mortality rate was 18% in patients treated open, and 21% in the patients treated arthroscopically.*

References

- Kono M, Stern PJ. The history of hand infections. *Hand Clin.* 1998;14:511–518, vii.
- Gahhos FN, Ariyan S. Hippocrates, the true father of hand surgery. *Surg Gynecol Obstet.* 1985;160:178–184.
- Kanavel A. An anatomical and clinical study of acute phlegmons of the hand. *Surg Gynecol Obstet.* 1905;1:221–259. In this seminal manuscript from 1905, Allen Kanavel reports his work on the fascial and synovial spaces of the hand. He used injection studies to define the fascial spaces of the hand and described their patterns of communication. Based on his findings, he identified the appropriate location of surgical incisions which are still utilized today.
- Kanavel A. *Infections of the Hand*. 2nd ed. Philadelphia: Lea & Febiger; 1914.
- Flynn JE. Modern considerations of major hand infections. *N Engl J Med.* 1955;252:605–612.
- Pallin DJ, Egan DJ, Pelletier AJ, et al. Increased US emergency department visits for skin and soft tissue infections, and changes in antibiotic choices, during the emergence of community-associated methicillin-resistant *Staphylococcus aureus*. *Ann Emerg Med.* 2008;51:291–298.
- Tosti R, Ilyas AM. Empiric antibiotics for acute infections of the hand. *J Hand Surg Am.* 2010;35:125–128.
- Fowler JR, Ilyas AM. Epidemiology of adult acute hand infections at an urban medical center. *J Hand Surg Am.* 2013;38:1189–1193.
- Houshian S, Seyedipour S, Wedderkopp N. Epidemiology of bacterial hand infections. *Int J Infect Dis.* 2006;10:315–319.
- Türker T, Capdarest-Arest N, Bertoch ST, et al. Hand infections: a retrospective analysis. *Peer J.* 2014;2:e513.
- Robson MC, Heggors JP. Delayed wound closure based on bacterial counts. *J Surg Oncol.* 1970;2:379–383.
- Barbieri RA, Freeland AE. Osteomyelitis of the hand. *Hand Clin.* 1998;14:589–603, ix. In this manuscript, Barbieri and Freeland review the important details of osteomyelitis. From pathophysiology and diagnosis to the medical and surgical management, the authors nicely outline and provide a comprehensive description of the critical factors that underlie this significant and often morbid hand infection.
- Gunther SF, Gunther SB. Diabetic hand infections. *Hand Clin.* 1998;14:647–656.
- Stern PJ, Staneck JL, McDonough JJ, et al. Established hand infections: a controlled, prospective study. *J Hand Surg Am.* 1983;8:553–559.
- Pang HN, Teoh LC, Yam AK, et al. Factors affecting the prognosis of pyogenic flexor tenosynovitis. *J Bone Joint Surg Am.* 2007;89:1742–1748.
- McDonald LS, Bavaro MF, Hofmeister EP, Kroonen LT. Hand infections. *J Hand Surg Am.* 2011;36:1403–1412.
- Osterman M, Draeger R, Stern P. Acute hand infections. *J Hand Surg Am.* 2014;39:1628–1635, quiz 35.
- Bach HG, Steffin B, Chhadia AM, et al. Community-associated methicillin-resistant *Staphylococcus aureus* hand infections in an urban setting. *J Hand Surg Am.* 2007;32:380–383.
- Harrison B, Ben-Amotz O, Sammer DM. Methicillin-resistant *Staphylococcus aureus* infection in the hand. *Plast Reconstr Surg.* 2015;135:826–830. In this manuscript, the authors review and summarize the most recent literature on methicillin-resistant *S. aureus* infections of the hand. They provide a detailed description of the epidemiology, microbiology, clinical presentation, and treatment algorithms of MRSA hand infections. They argue that given the increased prevalence of community-acquired MRSA over the past two decades, empiric coverage for MRSA should be provided for the initial treatment of hand infections if local prevalence rates exceed 10–15%.
- Abrams RA, Botte MJ. Hand infections: treatment recommendations for specific types. *J Am Acad Orthop Surg.* 1996;4:219–230.
- Covey DC, Albright JA. Clinical significance of the erythrocyte sedimentation rate in orthopaedic surgery. *J Bone Joint Surg Am.* 1987;69:148–151.
- Patel DB, Emmanuel NB, Stevanovic MV, et al. Hand infections: anatomy, types and spread of infection, imaging findings, and treatment options. *Radiographics.* 2014;34:1968–1986.
- Palestro CJ, Love C, Tronco GG, et al. Combined labeled leukocyte and technetium 99m sulfur colloid bone marrow imaging for diagnosing musculoskeletal infection. *Radiographics.* 2006;26:859–870.
- Rockwell PG. Acute and chronic paronychia. *Am Fam Physician.* 2001;63:1113–1116.
- Brook I. Paronychia: a mixed infection. Microbiology and management. *J Hand Surg Am.* 1993;18:358–359.
- Bednar MS, Lane LB. Eponychial marsupialization and nail removal for surgical treatment of chronic paronychia. *J Hand Surg Am.* 1991;16:314–317.
- Hurst LC, Gluck R, Sampson SP, Dowd A. Herpetic whitlow with bacterial abscess. *J Hand Surg Am.* 1991;16:311–314.
- Doyle JR. Anatomy of the flexor tendon sheath and pulley system: a current review. *J Hand Surg Am.* 1989;14:349–351.
- Schnall SB, Vu-Rose T, Holtom PD, et al. Tissue pressures in pyogenic flexor tenosynovitis of the finger. Compartment syndrome and its management. *J Bone Joint Surg Br.* 1996;78:793–795.
- Draeger RW, Bynum DK Jr. Flexor tendon sheath infections of the hand. *J Am Acad Orthop Surg.* 2012;20:373–382.
- Burkhalter WE. Deep space infections. *Hand Clin.* 1989;5:553–559.
- Jebson PJ. Deep subfascial space infections. *Hand Clin.* 1998;14:557–566, viii.
- Angoules AG, Kontakis G, Drakoulakis E, et al. Necrotizing fasciitis of upper and lower limb: a systematic review. *Injury.* 2007;38:S19–S26. In this systematic review, the authors nicely describe the clinical presentation, predisposing factors, surgical management, and outcomes of necrotizing fasciitis affecting the extremities. A total of 451 patients were analyzed. They found that 22.3% of patients had an amputation or disarticulation of a limb to control infection. Mortality rate was as high as 21.9%.
- Wong CH, Chang HC, Pasupathy S, et al. Necrotizing fasciitis: clinical presentation, microbiology, and determinants of mortality. *J Bone Joint Surg Am.* 2003;85-A:1454–1460.
- Childers BJ, Potyondy LD, Nachreiner R, et al. Necrotizing fasciitis: a fourteen-year retrospective study of 163 consecutive patients. *Am Surg.* 2002;68(2):109–116.
- Chauhan A, Wigton MD, Palmer BA. Necrotizing fasciitis. *J Hand Surg Am.* 2014;39:1598–1601, quiz 602.
- Elliott DC, Kufera JA, Myers RA. Necrotizing soft tissue infections. Risk factors for mortality and strategies for management. *Ann Surg.* 1996;224:672–683.
- Shewring DJ, Trickett RW, Subramanian KN, et al. The management of clenched fist ‘fight bite’ injuries of the hand. *J Hand Surg Eur Vol.* 2015;40:819–824.
- Sammer DM, Shin AY. Comparison of arthroscopic and open treatment of septic arthritis of the wrist. *J Bone Joint Surg Am.* 2009;91:1387–1393. A septic wrist is a marker of systemic frailty and illness. In a large series of 36 patients with 40 septic wrists, the authors found that both open and arthroscopic treatment were effective. However, the arthroscopically treated patients had fewer operations and shorter hospital stays. The 90 day perioperative mortality rate was 18% in patients treated open, and 21% in the patients treated arthroscopically.
- Waldvogel FA, Papageorgiou PS. Osteomyelitis: the past decade. *N Engl J Med.* 1980;303:360–370.
- Gold RH, Hawkins RA, Katz RD. Bacterial osteomyelitis: findings on plain radiography, CT, MR, and scintigraphy. *AJR Am J Roentgenol.* 1991;157:365–370.
- Witthaut J, Steffens K, Koob E. Reliable treatment of pyogenic granuloma of the hand. *J Hand Surg Am.* 1994;19:791–793.
- Anaya DA, McMahon K, Nathens AB, et al. Predictors of mortality and limb loss in necrotizing soft tissue infections. *Arch Surg.* 2005;140:151–157, discussion 158.

17

Management of Dupuytren's disease

Andrew J. Watt and Jerry I. Huang

SYNOPSIS

- Dupuytren's disease is a benign fibromatosis of the palmar and digital fascia characterized by nodular thickening and subsequent contracture.
- Successful treatment requires a detailed understanding of the normal palmar and digital fascial structures and their corollary diseased states.
- Operative indications are based on the degree of contracture and the resultant functional disability of the hand.
- Palmar fasciectomy remains the mainstay of surgical treatment.
- Increasingly common treatments include percutaneous (needle) aponeurotomy and collagenase injection (enzymatic fasciotomy).
- Despite appropriate management, recurrence and disease progression remain the primary obstacles to treatment.

Introduction

Dupuytren's disease is a progressive disease of the palmar and digital fascial structures characterized by nodular thickening and subsequent contracture. Deformity of the hand occurs primarily at the metacarpophalangeal (MCP) and proximal interphalangeal (PIP) joint level, resulting in functional limitations. This disease process is quite familiar to hand surgeons and presents a challenge in terms of both treatment and prognosis.

Epidemiology

Dupuytren's disease belongs to the overarching category of benign superficial fibromatoses and, as such, is closely related to Peyronie's disease (penile fibromatosis) and Ledderhose's disease (plantar fibromatosis). Historically, Dupuytren's disease has been successively referred to as a Nordic, Caucasian, Anglo-Saxon, and finally a Viking disease.¹⁻⁴ Although most prevalent in populations with a strong northern European ancestry, Dupuytren's disease affects populations throughout the world. Critical evaluations of the migrations

that have occurred throughout history, particularly those originating in northern Europe, suggest that the disease likely originated among Celtic and Germanic tribes around 1200 BC and dispersed throughout Europe with the great migrations beginning around 200 BC.⁵ Few populations are spared at least anecdotal cases of Dupuytren's disease; however, the incidence remains highest among individuals of northern European ancestry, with overall estimates ranging from 2% to 42% depending on the population being studied.⁶ Men are six times more likely to develop Dupuytren's disease than are women and typically exhibit an onset in the fifth decade of life, in comparison to onset within the sixth decade for women.⁷ Population studies support an autosomal-dominant inheritance pattern with variable penetrance.⁶

Associations with repetitive trauma, alcohol abuse, hepatic disease, diabetes mellitus, smoking, chronic obstructive pulmonary disease, human immunodeficiency virus, malignancy (paraneoplastic manifestation), and epilepsy have been proposed.⁸⁻¹⁰ These associations are often weak and most likely represent factors that may increase the penetrance or exacerbate an underlying genetic predisposition.

Palmar and digital fascia

Dupuytren's disease is ultimately manifested as the transformation of the normal palmar and digital fascial structures to thickened diseased cords through the deposition of type I and type III collagen and the contractile forces generated by myofibroblasts. An intimate understanding of both the native and pathologic anatomy is paramount in assessing and appropriately treating patients with Dupuytren's disease.

Palmar fascia

The palmar fascia provides a flexible yet firm framework for the soft tissues of the palm, tethering the skin to the underlying musculoskeletal structures. Classic descriptions of the anatomy of the palmar fascia provided by Legueu, Juvara, and Testut have withstood the test of time.^{11,12} The palmar




Fig. 17.1 Anatomy of the palmar fascia. (Redrawn from Tubiana R, Leclercq C, Hurst L, et al. (eds) *Dupuytren's Disease*. London: Martin Dunitz, 2000, p. 22.)

fascia consists of two distinct layers: the deep fascia and the superficial fascia or palmar aponeurosis. The deep fascia covers the interosseous muscles and is not involved in Dupuytren's disease. The superficial fascia, in contrast, is affected by the pathologic progression of Dupuytren's disease.

The palmar aponeurosis is a triangular-shaped fascial structure consisting of longitudinal, transverse and vertical fibers with its apex in continuity with the palmaris longus tendon (Fig. 17.1). Although these structures are in continuity, the palmar aponeurosis is histologically distinct from the palmaris longus and is invariably present even in patients with an absent palmaris.

The longitudinal fibers course superficial to the flexor retinaculum, and form pretendinous bands. These bands travel distally and insert into the deep surface of the dermis at the distal palmar crease, contribute to the retrovascular fascial structures, and bifurcate around the flexor tendon sheath to insert on the radial and ulnar sides of the MCP joint.¹³

The transverse fibers are characterized by two distinct bands, one proximal and one distal. The proximal transverse fibers, located at the level of the distal palmar crease, course deep to the longitudinal pretendinous bands and are not typically affected by Dupuytren's disease.¹⁴ Radially, these fibers form the proximal commissural ligament of the first webspace. The distal transverse fibers, alternately referred to as the natatory ligament, course superficial to the longitudinal

pretendinous bands and are affected by Dupuytren's disease. The natatory ligament extends from the radial border of the index finger to the ulnar border of the small finger. Ulnarly, the natatory ligament divides to envelop the abductor digiti minimi (ADM) and the ulnar neurovascular bundle. Radially, the natatory ligament is continuous with the distal commissural ligament of Grapow within the first webspace.

The vertical fibers of Legueu and Juvara connect the superficial palmar aponeurosis to the deep fascia. These fibers form a series of eight vertical septa on the radial and ulnar sides of the flexor digital apparatus. These septa divide longitudinal compartments containing the flexor tendons from those containing the lumbricals and digital neurovascular bundles.^{11,15} Additional vertical fibers connect the superficial palmar fascia to the overlying dermis, providing resistance to shear forces within the palm.¹³

Digital fascia

The palmar and digital fascia is contiguous with a complex digital-palmar junction in which intermediate and deep fibers of the longitudinal bands bifurcate, contributing to the formation of digital retrovascular bands. Anatomic studies have revealed more variability in the anatomy of the digital fascia in comparison with the relatively constant palmar fascial anatomy; however, relative agreement exists over the basic structure. The finger is invested by an elliptical fascial covering consisting of volar and dorsal fascial sheets that lie superficial to the flexor and extensor mechanisms, respectively. These sheets unite along the radial and ulnar aspects of the finger. The volar and dorsal aspects of the finger are separated by a series of lateral structures that envelope the neurovascular structures of the finger.¹⁶ These lateral structures include Cleland's ligaments, Grayson's ligaments, and transverse retinacular ligaments. Cleland's ligaments consist of a series of dorsal fiber bundles that arise proximal and distal to the interphalangeal joint, fanning laterally to insert in the skin. These fiber bundles do not form a contiguous sheet and run within several planes dorsal to the neurovascular bundle. Grayson's ligaments are more distinct, arising from the volar surface of the flexor tendon sheath, fanning laterally to insert into the skin, volar to the neurovascular bundle. The transverse retinacular ligaments originate from the volar capsule of the PIP joint and course dorsally to insert into the lateral margin of the extensor mechanism¹⁷ (Fig. 17.2).

First webspace

The radial longitudinal fibers of the superficial palmar aponeurosis extend distally into the thumb, inserting into the dermis at the level of the MCP joint. Additional fibers insert into the intermuscular septum between the adductor pollicis and the first dorsal interosseous muscles while additional fibers insert into the flexor tendon sheath of the index finger.

The natatory ligament is contiguous radially with the distal commissural ligament within the first webspace. The proximal transverse fibers are contiguous with the proximal commissural ligament (Fig. 17.3).



Access the Historical perspective section online at

<http://www.expertconsult.com>

Historical perspective

Baron Guillaume Dupuytren did not provide the first description of Dupuytren's disease; however, his description was the most thorough. Felix Plater provided the first description of palmar contracture in his 1614 work *Observationum in hominis affectibus*. The original Latin text has been interpreted variably in translation; however, Plater's anatomic dissections support a role for the palmar fascia in progressive contracture of the palm.¹⁸

Henry Cline clearly described the pathologic anatomy and clinical findings present in Dupuytren's disease in notes that

have been discovered in the library of St. Thomas' Hospital in London.¹⁹ Cline's pupil, Astley Cooper, discussed the condition in his *A Treatise on Dislocations and Fractures of the Joints*, advocating fasciotomy.²⁰

Guillaume Dupuytren was unaware of these original descriptions when he first described the condition in a lecture delivered on December 5, 1831 at the Hôtel-Dieu, Paris. He described the case of a wine merchant with contracture of the ring and small fingers that he successfully treated with open fasciotomies. His lecture notes were subsequently published in *Leçons orales de Clinique Chirurgicale faites à l'Hôtel-Dieu de Paris* in 1832.^{21,22}




Fig. 17.2 Normal fascial anatomy of the digit.

Basic science and disease process

Basic science

Although Dupuytren's disease has been formally recognized and clinically treated for over two centuries, the etiology and pathogenesis of the disease remained a matter of both




Fig. 17.3 Normal fascial anatomy of the first webspace. 1, Distal commissural ligament (ligament of Grapow). 2, Proximal commissural ligament.

speculation and incidental correlation. It has been only over the past 30 years that surgeons and scientists have begun to unravel the cellular mechanisms that contribute to the development of the disease.

Histopathologic studies have provided the foundation of scientists' nascent understanding of Dupuytren's disease. Initial studies have demonstrated not only involvement of the palmar aponeurosis but also absence of adipose tissue, a paucity of sweat glands, and increased vascularity within the affected palm.²³ Histologically, nodular rests of myofibroblasts surrounded by dense collagen characterize affected tissue. Molecular analysis reveals a preponderance of type III collagen, which is not typically observed in mature palmar fascia, and increased concentrations of prostaglandins as well as several subtypes of transforming growth factor- β (TGF- β).^{24,25} DNA microarray analysis comparing diseased and control palmar fascia has revealed a host of gene expression changes, including both up- and downregulation of expression. These include genes previously implicated in the pathogenesis of Dupuytren's disease, including fibronectin, tenascin C, TGF- β , collagen III, IV, and VI, as well as novel genes, including musculoaponeurotic fibrosarcoma oncogene homolog B (MafB).²⁶ Although the intricate interrelationship between these gene expression patterns remains a field for future inquiry, this knowledge has provided potential clinical targets for pharmacologic intervention in halting or potentially preventing Dupuytren's disease.

In 1959, Luck described the pathogenesis of Dupuytren's contracture in pathologic terms consisting of proliferative, involutional, and residual phases. This description has provided a framework within which molecular advances may be analyzed as well as a foundation for clinicians' understanding of disease progression. The proliferative phase is characterized by nodule formation within the palmar fascia and biochemically by increased fibrinolytic activity. At this stage, fibroblasts differentiate into myofibroblasts and comprise the majority of nodular architecture. Myofibroblasts are fibroblastic in origin; however, they contain an actin microfilamentous structure analogous to smooth-muscle cells. These actin microfilaments are arranged in bundles oriented along the long axis of the cell and communicate with the extracellular matrix fibronectin, thereby allowing transmission of intracellular contractile forces to the extracellular tissues. Marked nodular thickening and signs of early joint contracture characterize the involutional phase. Throughout the involutional phase, type III collagen is synthesized and the myofibroblasts reorient along the lines of tension within the palm. Type III collagen deposition continues and is gradually replaced with type I collagen throughout the residual phase. Myofibroblasts have largely disappeared by the residual phase, resulting in a relatively hypocellular amalgam of type I and type III collagen.²⁷⁻²⁹

The inciting event resulting in myofibroblast proliferation remains unknown. Authors have suggested multiple hypotheses, including trauma, focal ischemia, and a host of growth factor and cytokine aberrations. Murrell *et al.* hypothesize that ischemia within the palmar fascia results in the generation of free radicals that damage the surrounding tissue. This damage incites repair with the deposition of collagen and the proliferation of myofibroblasts, and leads to further ischemia and disease progression.³⁰ Mechanical stress has been shown to upregulate myofibroblast differentiation and supports the

traumatic theory.³¹ Myofibroblast proliferation is also stimulated by a number of growth factors and cytokines, including TGF- β_2 and inhibited by platelet-derived growth factor (PDGF), basic fibroblastic growth factor, interleukin-1 α , and interleukin-1 β .³² Actin expression may also play a pivotal role in the progression of Dupuytren's disease and is increased by TGF- β_2 and decreased by PDGF-BB.³³ The expression of androgen receptors within Dupuytren's nodules has also raised the question of hormonal influence on disease development and progression. Myofibroblasts from Dupuytren's patients stimulated with 5 α -dihydrotestosterone demonstrated higher rates of proliferation than myofibroblasts from control subjects, suggesting that androgens may play a role in disease progression. This theory gains support from the male predominance of the disease. Ultimately, none of these theories and biomolecular interrelationships is mutually exclusive and Dupuytren's disease may very well represent the culmination of a host of environmental and cellular events in a genetically prone individual.

Disease process

The net effect of these cellular and pathologic mechanisms is the transformation of normal palmar and digital fascial structures into fibrotic diseased cords. Each normal anatomic structure within the palmar and digital fascial system maintains a pathologic correlate. Diseased components may be further subdivided into palmar, palmodigital, digital, first webspace, and hypothenar cords (Table 17.1).

Within the palm, involved pretendinous bands become pretendinous cords. These cords course distally and insert into the deep surface of the dermis at the distal palmar crease, resulting in pitting of the palmar skin. They are also continuous with the retrovascular fascial structures and contribute to formation of the spiral cord.¹³ The remaining fibers contribute to the formation of the central cord within the finger itself. The pretendinous cord is the primary contributor to MCP flexion contracture and is located superficially, leaving the deeper neurovascular structures undisturbed. Dissection within the palm, proximal to the distal flexor crease, is therefore relatively safe with respect to neurovascular bundles. The vertical fibers of McGrouther and the septa of Legueu and Juvara also become involved and may result in painful triggering with extension of the finger following full flexion (Fig. 17.4).

Two key cords are located within the palmodigital region. The spiral cord forms from the diseased confluence of the pretendinous band, spiral band, lateral digital sheet, and Grayson's ligament. The spiral cord wraps around the neurovascular bundle, displacing the digital nerve and artery medially, superficially, and proximally, placing them at risk for injury during skin incision and dissection (Fig. 17.5). The spiral cord not only displaces the neurovascular bundle, but also results in significant PIP joint contracture.³⁴ The natatory ligament, which traverses the palm transversely at the level of the metacarpal heads, is transformed into the natatory cord. The natatory cord results in webspace adduction contracture.

Table 17.1 Fascial anatomy of Dupuytren's disease

Diseased structure	Anatomic origin	Clinical significance
Palmar cords		
Pretendinous cord	Pretendinous band	MCP joint flexion contracture
Vertical cord	Vertical fibers of McGrouther or septa of Legueu and Juvara	Causes painful triggering
Palmodigital cords		
Spiral cord	Pretendinous band, spiral band, lateral digital sheet, Grayson's ligament	Displaces the neurovascular bundle medially and superficially (spiral nerve)
Natatory cord	Natatory ligament (distal fibers)	Webspace adduction contracture
Digital cords		
Central cord	Pretendinous cord (digital extension)	PIP joint flexion contracture
Retrovascular cord	Retrovascular band of Thomine	PIP and DIP joint flexion contracture; prevents full correction of PIP joint contracture
Lateral cord	Lateral digital sheet (often closely associated with pretendinous and natatory cord)	PIP and DIP joint flexion contracture; displaces neurovascular bundle medially
Abductor digiti minimi cord	Abductor digiti minimi tendon	PIP joint flexion contracture
Thumb and first webspace cords		
Proximal commissural cord	Proximal commissural ligament	First-web adduction contracture
Distal commissural cord	Distal commissural ligament	First-web adduction contracture
Thumb pretendinous cord	Pretendinous band	MCP joint flexion contracture

DIP, distal interphalangeal; MCP, metacarpophalangeal; PIP, proximal interphalangeal.




Fig. 17.4 Normal (A) and pathologic (B) palmodigital anatomy.

Within the finger, involved pretendinous bands become central cords. These cords are contiguous proximally with the pretendinous cords of the palm and insert laterally on the radial and ulnar side of the PIP joint and on the flexor tendon sheath of the middle phalanx. The central cord acts in concert with the spiral cord, contributing to PIP joint contracture. Additionally, the retrovascular band of Thomine becomes the retrovascular cord, which contributes to PIP and distal interphalangeal (DIP) joint contracture. The lateral digital sheet may also become involved in disease progression as the lateral

cord, contributing to the spiral cord and resulting in PIP and DIP joint contracture.³⁵

The first webspace may also be involved in Dupuytren's disease. The proximal and distal commissural ligaments, which represent the radial extension of the proximal transverse fibers of the palmar aponeurosis and the natatory ligament, respectively, become the proximal and distal commissural cords. These cords contribute to first-webspace adduction contracture. A thumb pretendinous band, analogous to the longitudinal pretendinous fascial structures of the fingers, evolves into a pretendinous cord and results in MCP joint contracture (Fig. 17.6).

In addition to the palmar and palmodigital cords analogous to those of the index, long, and ring fingers, the small finger




Fig. 17.5 Spiral cord. (A) Normal fascial palmodigital fascial structures contributing to the formation of the spiral cord. (B) Spiral cord. (C) Spiral cord: note displacement of the ulnar neurovascular bundle radially.




Fig. 17.6 Normal and pathologic anatomy of the first webspace. **(A)** Normal anatomy. **(B)** Pathologic anatomy. 1, Distal commissural ligament (ligament of Grapow). 2, Proximal commissural ligament.

has a unique ADM cord. This cord represents pathologic involvement of the fascia associated with the ADM tendon and results in an abduction contracture of the small finger.

Diagnosis/patient presentation

Clinical presentation

Patients with Dupuytren's disease present throughout the spectrum of disease progression, and diagnosis is made based upon history and clinical examination. The characteristic progression from nodule to fibrotic cord with contracture of the affected palm and digits is pathognomonic for Dupuytren's disease. Onset is typically insidious with progressive contracture and disability developing over the course of years. The earliest signs of disease consist of pitting or dimpling of the palm with distortion of the distal palmar crease resulting from connections between the dermis and longitudinal fibers of the palmar aponeurosis¹³ (Fig. 17.7). Distortion of the skin creases can appear as a deepening of the crease or widening of the crease (Hugh Johnson sign).³⁶ These skin changes are typically the first signs of the disease, preceding the development of nodules. Nodules develop within the palm and are the palpable manifestation of myofibroblast proliferation. These nodules are most commonly located within the ulnar aspect of the palm overlying the ring-finger ray at the level of the distal palmar crease and at the PIP joint level within the finger. Nodules may develop anywhere within the finger, palm, and, rarely, as proximal as the wrist. The nodules are typically painless; however, some patients note discomfort, particularly with grip, and a sensation of tension within the palm.

Disease progression is characterized by the development of longitudinal cords, most commonly in the ulnar aspect of the palm and extending distally into the fingers. The overlying skin is typically undisturbed in the proximal palm and increasingly adherent to the underlying cord distally (Fig. 17.8). The ring finger is most commonly affected, followed in prevalence by the small finger, thumb, middle, and index



Fig. 17.7 Early Dupuytren's disease: note the nodule formation within the ring ray at the level of the distal palmar crease.



Fig. 17.8 Palmar and palmodigital disease.



Fig. 17.9 Garrod's nodules.

fingers. A soft palpable fullness immediately adjacent to the cord at the level of the MCP joint may indicate displacement of the neurovascular bundle by a pathologic spiral cord (Short-Watson sign).³⁴

The distal course of the cord varies. The cord may terminate in the dermis at the distal palmar crease, laterally on each side of the MCP joint, or continue distally as the central digital cord. The digital cord typically terminates just distal to the PIP joint, either centrally or laterally. A large volar nodule located at the level of the proximal phalanx often becomes intimately associated with the dermis of the overlying skin. These relationships are discernible with palpation of the cords or clinical examination. Cords are unusual distal to the middle phalanx. When present, they often lie along the radial and ulnar aspects of the finger, crossing the DIP joint. Nodules and cords strictly isolated to the finger in the absence of palmar involvement are rare but may occur.

The net effect of myofibroblast activity within palmar nodules and the deposition of collagen as pathologic cords is progressive joint contracture. The MCP joint is typically involved first, followed, in more severe cases, by PIP joint contracture. Initially, joint contracture presents as limitation in hyperextension at the MCP joint and progresses to a permanent lack of extension. MCP and PIP joint contracture result in progressive disability of the hand. Common complaints include impairment in hand shaking, fitting of gloves, difficulty placing the affected hand in a pocket, and impairment in grasping large objects. The DIP joint is typically unaffected by Dupuytren's disease; however, deformities of both flexion and extension may occur. Flexion deformity results from involvement of the lateral and retrovascular cord. DIP hyperextension, in contrast, is compensatory in the setting of PIP flexion contracture, and results from imbalance of the flexor and extensor mechanisms.

Patients may also present with Garrod's nodules, or knuckle pads located dorsally over the PIP joints (Fig. 17.9). Garrod's nodules suggest a higher likelihood of bilateral hand involvement; however, their presence does not suggest stage or severity of disease, nor do they result in any functional limitation themselves.³⁷ Knuckle pads have been reported in 15% of patients with Dupuytren's disease and may occur in

isolation.^{38,39} Knuckle pads suggest a higher likelihood of concomitant fibromatoses, including Peyronie's (penile fibromatosis) and Ledderhose's disease (plantar fibromatosis). Peyronie's disease affects the tunica albuginea of the corpora cavernosa of the penis and is present in 1–3% of patients with Dupuytren's disease.^{40,41} Fibrosis develops as a well-circumscribed plaque, usually on the dorsum of the penis. The disease is generally painless; however, discomfort may occur with erection.⁴² Plantar fibromatosis is present in 5–20% of patients with Dupuytren's disease, presenting as a nodular thickening within the nonweight-bearing (arch) portion of the sole of the foot⁴³ (Fig. 17.10). These lesions are typically asymptomatic; however, they may produce discomfort or even severe pain with ambulation in a select number of cases.^{44,45} Contracture of the toes does not develop. Additional presentations of Dupuytren's disease include triggering secondary to involvement of the vertical palmar septa, and an isolated tender palmar nodule whose discomfort will typically dissipate with time.

Several other lesions have been reported in association with Dupuytren's disease; however, no clear relationship has been established. Matev reported involvement of the auricular concha.⁴⁶ Allen reported the presence of nodules within the



Fig. 17.10 Plantar fibromatosis.

tensor fascia lata in patients with Dupuytren's disease, and Hueston has described involvement of the Achilles tendon.^{44,47}

Differential diagnosis

Differential diagnosis of Dupuytren's disease includes campodactyly, traumatic scar contracture, burn scar contracture, Volkmann's ischemic contracture, intrinsic joint ankylosis, locked trigger finger, and spastic digital contracture. Callous formation, foreign body, desmoid fibroma, nodular fasciitis, and fibrosarcoma should also be considered in the differential for a primarily nodular palm. The classic history of nodule appearance with insidious progression to cord formation and joint contracture is pathognomonic for Dupuytren's disease. Diagnosis is further bolstered in the setting of a family history or in the presence of knuckle pads, Peyronie's disease, or Ledderhose's disease. No radiographic imaging or tissue diagnosis is required to confirm a diagnosis of Dupuytren's disease.

Patient selection

The primary objective of treatment in patients with Dupuytren's disease is correction of deformity, thereby reducing disability and restoring hand function. It therefore follows that the degree of joint contracture, and, more importantly, the extent of functional disability, are the primary indications for intervention. Commonly accepted surgical indications include greater than 30° of MCP joint contracture and any degree of PIP joint contracture, as these degrees of joint contracture are functionally limiting. The urgency of operative intervention is also related to the degree of joint involvement and, more critically, to the joint involved. Surgical intervention for MCP joint contracture is not urgent as the collateral ligaments are taut in MCP joint flexion. This position is protective with respect to joint motion. Surgical intervention may therefore be delayed without compromising functional outcome. In contrast, PIP joint contracture necessitates expeditious operative attention. Longstanding PIP joint contracture results in shortening of the collateral ligaments and precipitates articular changes with loss of subchondral bone resulting in a recalcitrant flexion contracture of the joint. In an effort to preserve functional PIP joint motion, surgery is indicated with any degree of contracture.

Additional operative indications include a functionally limiting first-web-space adduction contracture, small-finger abduction contracture, unremitting tenosynovitis secondary to a palmar nodule overlying the A-1 pulley, and palmar contracture resulting in maceration of the distal palmar crease.

Few contraindications to surgery exist beyond those considerations that would preclude regional or general anesthesia. Poor operative candidates include those patients with longstanding PIP joint contracture and documented underlying articular changes. These patients may require PIP arthroplasty, musculotendinous lengthening, joint fusion, or even amputation in more severe cases. Special consideration must be given to patients with a history of complex regional pain syndrome (CRPS). These patients should receive preoperative neuropathic medication therapy and operation should be performed under regional anesthesia. Relative contraindications also include conditions in which the micro- or macrovascular

circulation may be impaired, including tobacco abuse, peripheral vascular occlusive disease, and diabetes mellitus. Anticoagulants should be held in the preoperative period in order to minimize the risk of palmar hematoma. Antiplatelet agents, including aspirin and clopidogrel, should be discontinued 7–9 days prior to operative intervention, while warfarin should be held 3–5 days prior to surgery so as to allow for normalization of the patient's international normalized ratio.

Treatment

Treatment of Dupuytren's disease may be subdivided into modality therapy, injection, and surgical intervention. Although promising interventional treatments, including enzymatic lysis of diseased tissue with collagenase and percutaneous needle aponeurotomy, are emerging, treatment remains primarily surgical, and results for all interventions are tempered by high rates of disease recurrence and progression.

Modality therapy

A host of nonoperative treatments have been explored for the treatment of Dupuytren's disease. This array of therapies underscores both a physician and patient desire to develop nonoperative alternatives to palmar fasciectomy as well as the general ineffectiveness of these modalities. Extension splinting may prevent contracture; however, the splint must be worn continuously and is incompatible with functional use of the hand. Intermittent splinting has not demonstrated effectiveness in preventing the progression of Dupuytren's disease. Ultrasound therapy has been reported to soften palmar nodules but has not been effective in the treatment of cords or contracture.⁴⁸ External-beam radiation therapy has been advocated for the treatment of Dupuytren's disease; however, this therapy presents significant risk for the treatment of a benign condition and has not proven effective.^{49–51} Additional therapies, including the use of dimethyl sulfoxide, vitamin E, methylhydrazine, allopurinol, colchicine, and interferon- γ , have been investigated without beneficial results.^{52–56}

Injection treatment

Injection therapy has demonstrated greater promise than topical and modality therapies. Authors have investigated both the use of corticosteroid injection as well as enzymatic fasciotomy with a host of degradative enzymes, including trypsin and, most recently, clostridial collagenase.

Steroids have demonstrated a restrictive effect on the formation of fibrous tissue and scar. The use of corticosteroids as a postoperative adjunct was first reported in 1952.⁵⁷ The efficacy of steroid therapy remains a subject of debate with reports ranging from no efficacy to complete resolution of palmar nodules.^{52,58,59} Corticosteroid injections maintain complications, including dermal atrophy, skin depigmentation, and flexor tendon rupture. In general, corticosteroid injection may have a role in the treatment of a symptomatic palmar nodule; however, no efficacy in the treatment of Dupuytren's cords or joint contracture has been established, except as a potential adjunct to needle aponeurotomy.

The concept of targeting abnormal collagen deposition via enzymatic degradation followed by manual rupture is not novel. Reports of attempted enzymatic fasciotomy appear as

early as 1907, and over the past century greater refinement in the activity and specificity of the enzyme injected has occurred.⁶⁰ In 1965, Bassot reported his technique of “*exerèse pharmacodynamique*”, utilizing a mixture of trypsin, alphachymotrypsin, hyaluronidase, thiomucase, and lidocaine. Bassot reported correction of severe contracture in 34 patients.⁶¹ In 1971, Hueston reported his experience with a simplified formula consisting of trypsin, hyaluronidase, and Xylocaine, achieving favorable initial results.⁶² McCarthy reported his experience with enzymatic fasciotomy in 14 patients, noting recurrence of initial contracture in 75% of patients at an average of 2–3-year follow-up. He concluded that there was a similar rate of recurrence with both enzymatic fasciotomy and surgery.⁶³ This technique subsequently fell into disfavor given concerns for neurovascular injury and tendon rupture with the use of nonspecific degradative enzymes. Collagenase emerged as a candidate for enzymatic fasciotomy in 1996 and was approved by the FDA for clinical use in 2010.

Injection in enzymatic fasciotomy is performed with 0.58 mg clostridial collagenase diluted in 0.25 mL (MCP joint) or 0.20 mL (PIP joint) of sterile diluent. The cord is located by manual palpation and injection is performed at three points along the length of the cord via a single puncture with a 25-gauge needle. Care is taken to inject within the mid-substance of the cord as lateral injection may result in neurovascular injury, while deep injection results in intratendinous injection (Fig. 17.11). Patients generally return to clinic on postinjection day 1 for manual manipulation (Fig. 17.12). While manipulation on postinjection day 1 remains the manufacturer recommendation, Mickelson *et al.* demonstrated equivalent efficacy and safety of manipulation performed at day 1 versus day 7 in a randomized, prospective trial, suggesting that manipulation may be performed at the convenience of both the surgeon and the patient within a week of injection.⁶⁴ Night extension splinting is performed for 4 months following injection. A 1-month interval is allowed before repeat injection is attempted. Long-term disease recurrence rates as well as the clinical role of collagenase injection are evolving (Box 17.1).

BOX 17.1 Clinical tips: enzymatic fasciotomy

Enzymatic fasciotomy offers an alternative to open surgical treatment of Dupuytren's contracture. Successful treatment involves appropriate patient selection and adherence to proper injection technique.

1. Appropriate patients include those with a palpable Dupuytren's cord resulting in symptomatic MCP or PIP contracture.
2. Reconstitution should be meticulous and varies depending on the level of contracture.
3. The injector's nondominant hand provides traction on the finger, displacing the cord away from the underlying flexor tendon.
4. The dose is divided into thirds injecting in multiple locations along the cord.
5. Tactile feedback is critical. The cord is firm and resists easy injection.
6. Manipulation is performed in a controlled fashion. Placing the wrist in flexion for MCP manipulation and the MCP in flexion during PIP manipulation relieves stress of the underlying flexor tendons, isolating the cord.




Fig. 17.11 Collagenase injection technique.

Surgical treatment

Surgical treatment of Dupuytren's disease consists of both fasciotomy and fasciectomy. Fasciotomy involves division of the diseased cords without excision and may be performed via an open technique or percutaneously. Fasciectomy involves excision of the diseased cords. Fasciectomy varies in the treatment of the skin as well as the extent of surgical dissection (Table 17.2).

Percutaneous fasciotomy (needle aponeurotomy)

Percutaneous fasciotomy represents the least invasive operative modality for the treatment of Dupuytren's disease and was first described by de Seze and Debeyre in 1957.⁶⁵ The original technique described direct injection of corticosteroid into the affected cord followed by division of the cord via scoring with a 15-gauge needle and manual manipulation.⁶⁶ This technique has been modified and further refined by Foucher and its clinical utility is expanding as practitioners become more accustomed to the technique and comfortable





Fig. 17.12 Collagenase treatment of Dupuytren's disease. **(A)** Metacarpophalangeal and proximal interphalangeal joint contractures prior to collagenase injection. **(B)** Manipulation following collagenase injection: note ecchymosis-associated edema. **(C)** Correction of metacarpophalangeal and proximal interphalangeal joint contractures 1 month following treatment with collagenase.

with the pathologic anatomy. Using local anesthetic and a forearm tourniquet, a 19-gauge needle is used to score and divide the involved cords (Fig. 17.13). No corticosteroid is utilized to weaken the cord structure and division is carried out in a distal to proximal manner to avoid disappearance of the digital cord following proximal division.⁶⁷

Percutaneous fasciotomy is best suited for isolated palmar cords with moderate flexion at the MCP joint level. Distal fasciotomies, including treatment of PIP contractures and spiral cords, are being performed by practitioners familiar with the percutaneous technique and anatomy with increasing clinical efficacy and success. Diffuse infiltrating cords,

nodules, postsurgical recurrence, longstanding PIP flexion contracture, and deep lateral cords are poor indications for percutaneous treatment and carry a higher risk of complications (Box 17.2).

Open fasciotomy

First described by Dupuytren, open fasciotomy consists of division of the diseased cord under direct vision.⁶⁸ A limited longitudinal incision is made over the affected cord. The cord is visualized, isolated, and divided transversely. The resultant defect may be closed directly, rearranged with a Z-plasty incorporating the cord and skin, or closed with a skin graft.^{69–72} Open fasciotomy techniques reliably provide for correction, particularly in the setting of isolated MCP contractures; however, recurrence sufficient to warrant reoperation is reported in 43% of patients.⁷³

Table 17.2 Surgical options for the treatment of Dupuytren's disease

Surgical technique	Description
Fasciotomy	Division of diseased cords without excision.
Local fasciectomy	Removal of segment of diseased cord.
Regional fasciectomy	Removal of all diseased fascia as well as local region of grossly normal tissue.
Radical fasciectomy	Removal of the entire palmar and digital fascia.
Open-palm technique (McCash)	Division of the palmar aponeurosis without closure of the skin deficit created.
Dermatofasciectomy	Removal of the diseased fascia as well as the overlying skin. Closure typically obtained with the use of a full-thickness skin graft.

BOX 17.2 Clinical tips: percutaneous (needle) aponeurotomy

Percutaneous aponeurotomy involves division of Dupuytren's cords with a beveled needle under local anesthetic. Successful release requires detailed knowledge of the pathologic anatomy, meticulous technique, and a reliance on sensory feedback.

1. Extension of the involved finger by an assistant places traction on the cords within the finger and palm.
2. Only distinctly palpable cords should be addressed percutaneously.
3. The bevel of the needle is used to scrape and progressively weaken the involved cord in a longitudinal fashion.
4. Work on several areas of the same cord prior to rupturing or dividing the cord in order to maintain tension.
5. Avoid transverse movements as these present the greatest risk of neurovascular injury.




Fig. 17.13 Percutaneous (needle) aponeurotomy. **(A)** Preprocedure. Note 60° metacarpophalangeal flexion contracture. **(B)** Postprocedure, demonstrating correction of metacarpophalangeal flexion contracture with percutaneous technique. Note residual digital disease. **(C)** Open dissection. Note transection of cord which has been completed percutaneously. The proximity of the radial neurovascular bundle is well visualized. The palm was opened to address digital disease.

Fasciotomy is a simple and safe technique when performed within the palm. Its primary utility remains in elderly patients with an isolated palmar cord in whom substantive health problems preclude a more extensive procedure. Use of fasciotomy within the finger presents some risk of neurovascular injury and the technique has been largely supplanted by increasing familiarity with needle aponeurotomy.

Local fasciectomy

Local or limited fasciectomy is a technique designed to remove a portion of the diseased aponeurosis, disrupting continuity of the diseased tissue. This procedure is a compromise between removal all of the diseased aponeurosis via extensive palmar and digital dissection and fasciotomy. Theoretically, local fasciectomy limits the risk of complications associated with dissection, including palmar hematoma and neurovascular injury, while addressing the possibility of local recurrence by creating discontinuity of the diseased tissue.

A longitudinal or Z-plasty incision is performed over the involved cord analogous to that performed in an open fasciotomy. The cord is isolated and divided with resection of 1–2 cm of the cord itself. Residual diseased aponeurosis is left behind. The role of local fasciectomy is limited and overlaps with that of fasciotomy.

Regional (partial) fasciectomy

Until recent developments with needle aponeurotomy and enzymatic treatment, regional fasciectomy has provided the mainstay of operative treatment in Dupuytren's disease. Regional fasciectomy consists of excision of all macroscopically abnormal fibrous tissues within the palm and finger. Successful operative intervention requires an intimate understanding of the normal palmar and digital fascial anatomy as well as the pathologic correlates. This technique limits palmar dissection while disrupting the continuity of the aponeurotic tissue and limiting focal recurrence. By leaving residual aponeurosis, the possibility of disease progression remains. This technique is performed under regional or general anesthesia with a brachial tourniquet placed sufficiently high as to allow access to the medial arm should a skin graft be required. The arm is abducted, supinated on a hand table. A lead or Tupper hand is a valuable adjunct to allow the surgeon to work with minimal assistance. Loupe magnification is invaluable in allowing fine dissection of the common and proper neurovascular bundles.

Digital and palmar disease may be approached through a variety of incisions either separately or conjunction (Fig. 17.14). The skin incision should provide adequate exposure for dissection of the disease tissues and the neurovascular




Fig. 17.14 Surgical incisions for regional fasciectomy. Thumb illustrates T- with Z-plasties at the flexion creases, long finger illustrates Y to V advancement, ring finger illustrates traditional Brunner incision, and small finger illustrates axial incision with Z-plasties at the flexion creases.

bundles in the palm and fingers, preserve vascularized skin flaps to avoid skin necrosis, allow skin lengthening along the longitudinal axis of the finger, and avoid scar contractures. Although some surgeons advocate transverse palmar incisions, longitudinal incisions are more useful for digital exposure and may be extended into the palm for exposure of the aponeurosis. Longitudinal incisions with Z-plasties at the flexion creases or a zigzag Brunner-type incision both provide excellent exposure. Closure with Y to V tissue rearrangement provides for additional length and is particularly useful in patients with significant contracture in which a relative deficiency of skin exists upon correction of the contracture. Contracture of the first webspace is best approached through a T-incision combined with Z-plasties to prevent scar contracture. Transverse incisions within the palm allow for excellent palmar exposure and present no risk of flexion contracture; however, this approach typically requires relatively extensive undermining and does not lend itself to facile proximal or distal extension. When the skin is markedly adherent to the underlying diseased aponeurosis, the incision should pass through the center of this region to avoid extensive devascularization.

Following skin incision, dermal flaps are developed sharply with preservation of the subcutaneous tissue. A scalpel is used to sweep the skin/subcutaneous flaps sharply off the cord in the palm region. Proximal to the distal palmar crease, the digital neurovascular structures are safely deep to the cord itself, and are therefore protected. With the cord skeletonized, the digital nerves and arteries may be identified proximally and traced distally. All abnormal tissue is excised, including the involved vertical fibers of Legueu and Juvara. The proximal transverse metacarpal ligament is preserved as it is not affected by Dupuytren's disease. The aponeurosis may be in intimate association with the underlying flexor tendon sheath and pulley system; however, a natural plane of dissection

exists and the sheath is preserved. Once the palmar aponeurosis and pretendinous cords have been disrupted, the MCP joints will extend without constraint, allowing for more facile dissection within the finger.

Distal to the proximal transverse metacarpal ligament, the diseased tissue becomes increasingly adherent to the overlying dermis, necessitating sharp dissection. From this point distal, the dissection is focused on the neurovascular structures, and excision of diseased tissue is performed only after the nerve and artery have been identified and protected. Of particular note, the common digital arteries lie superficial to the common digital nerves within the palm, while the proper digital arteries lie deep to the digital nerves within the finger. The digital nerves bifurcate more proximally than the arteries, crossing over the digital arteries at the level of the metacarpal heads.

The termination of the pretendinous cords is variable, and each termination should be dissected separately and divided. Once the pretendinous cord has been divided, MCP extension is typically full. The natatory ligament, which crosses the tendons and neurovascular bundles superficially, is excised, thereby allowing release of any adduction contracture.

At the digital-palmar junctions, multiple anatomic components converge. The pretendinous cord, spiral cord, lateral digital sheet, and Grayson's ligament may coalesce to form a spiral band, displacing the neurovascular bundle medially, superficially, and proximally. Meticulous care is exercised in order to avoid damage to a displaced neurovascular bundle resulting from the presence of a spiral cord. Removal of diseased tissue within the finger is the most delicate portion of the operation. The path of the neurovascular bundles, altered by an assortment of fibrous cords, is unpredictable. The digital artery may, on occasion, be separated from its companion nerve by a sheet of fibrous tissue. To navigate this anatomy successfully and to avoid injury to the digital neurovascular structures, the digital artery and nerve should be identified distally within uninvolved tissue and traced proximally (Box 17.3).

Retrovascular cords are notoriously occult, and failure to recognize this structure often results in residual PIP contracture. DIP joint hyperextension is infrequent and is often associated with severe PIP contracture. Release of the PIP contracture typically corrects the distal deformity. Residual DIP hyperextension may require oblique tenotomy of the lateral bands of the extensor apparatus. Release of the lateral

BOX 17.3 Clinical tips: dissection of a spiral cord

Safe dissection of the neurovascular bundle which has been displaced proximally, medially, and superficially by a spiral cord is the most technically demanding component of an open fasciectomy. Several key techniques will ensure clinical success:

1. Identify the involved neurovascular bundle proximally within the normal tissue of the palm (outside the zone of disease).
2. Identify the involved neurovascular bundle distally within the normal tissue of the finger (outside the zone of disease).
3. Dissect from proximal to distal between these two "known" regions.
4. Division of the cord proximally may assist in distal dissection.
5. Avoid undue traction on the neurovascular bundle.




Fig. 17.15 Technique of check rein release. 1, Volar plate. 2, Check rein ligament. 3, Collateral artery. 4, Transverse arterial branch. (Redrawn after Tubiana R. *The Hand*. Philadelphia: WB Saunders, 1999, p. 463.)

bands is performed over the middle phalanx through a dorsal incision. The bands are allowed to slide distally, restoring DIP flexion.

Fasciectomy within the small finger and first webspace require special attention due to the unique pathologic anatomy in these regions of the palm. The small finger is often severely involved in the disease process and dissection is particularly difficult given the diminutive size of the ulnar digital artery and nerve. Fascia surrounding the ADM and its retrovascular correlate are routinely affected. This structure originates from the muscular fascia of the ADM immediately superficial to the ADM tendon and is frequently mistaken for the ADM tendon itself. The cord is usually deep and ulnar to the neurovascular bundle; however, the bundle may spiral dorsal to or through the cord. The dorsal ulnar sensory nerve may also be displaced volarly and should be identified prior to division of the ADM cord.

Although radial-sided palmar involvement in Dupuytren's disease is rare, a marked first-webspace adduction contracture and thumb MCP contractures may be quite functionally limiting. Contracture of the first webspace is best approached through a T-incision combined with Z-plasties to prevent scar contracture or a four-flap Z-plasty.⁷⁴ The neurovascular bundles should be carefully identified and preserved. The ulnar bundle is reliably found at the base of the thumb. The radial bundle, in contrast, may be quite difficult to localize as it is covered with decussating fibers at the level of the MCP joint, and should be identified more proximally within the thenar eminence. The proximal and distal commissural cords should be excised. In longstanding contractures of the first webspace, the dorsal structures may become contracted secondary to positional deformity rather than involvement of the Dupuytren's disease process, and may require release.

Several additional techniques may be required when complete range of motion cannot be restored with fasciectomy alone. These procedures should be employed judiciously with consideration given to the fact that a finger with mild residual PIP deformity is more functional than a stiff finger with full extension. Residual deformity may be attributed to shortening of the flexor tendon sheath, capsular contracture of the PIP joint, or articular changes within the PIP joint. The latter

is not amenable to further correction with manipulation of the soft tissue alone and requires arthrodesis or arthroplasty to address residual deformity. Shortening of the tendon sheath is addressed by making one or two transverse incisions within the sheath at the level of the PIP joint to allow for lengthening. The pulley system should be preserved. PIP joint contracture presents a more formidable challenge. Complete capsulectomy should be avoided in favor of a limited arthrolysis, which involves selective division of the volar plate check rein ligaments.^{75,76} Check rein division should be performed just proximal to the arterial branch for the vinculum longum, which is preserved⁷⁷ (Fig. 17.15). Once full passive extension is achieved, the integrity of the central slip should be assessed. If the central slip is deficient, the PIP joint should be immobilized postoperatively in static extension for 3 weeks. Alternatively, gentle passive manipulation under anesthesia may be performed.⁷⁸ This method does not allow for dramatic correction, but minimizes trauma and potential complications of recurrent PIP joint capsular contracture.

Radical fasciectomy

Radical fasciectomy involves extensive dissection of the palm and digital fascial structures in an effort to remove both normal and diseased palmar and digital fascia. This procedure has been proposed and advocated by several surgeons with the theoretic advantage of eliminating the risk of disease progression and recurrence.⁷⁹ This theoretic advantage has not been borne out in practice.^{80,81} The procedure has been plagued by significant postoperative complications, including hematoma and skin necrosis, and has largely been abandoned in favor of regional excision.

Dermatofasciectomy

Dermatofasciectomy involves excision not only of the involved facial structures of the palm and fingers, but the overlying skin as well. This practice has its foundation in the histopathological studies of Meyerding *et al.* that demonstrated pathologic changes in the palmar fascia, thinning of the subcutaneous tissue, and a reduction in the number of dermal sweat glands.²³ The dermis is often thought to

represent a repository for active disease and the nidus for disease recurrence. Although this relationship has never been definitively established, dermatofasciectomy retains a role primarily in the treatment of recurrent disease or in cases with extensive cutaneous involvement. Excised skin is allowed to heal secondarily (open-palm technique of McCash) or replaced with a full-thickness skin graft obtained from the groin or medial arm.⁸² The open-palm technique alleviates the risk of hematoma; however, it is complicated by prolonged healing times and scar contracture. This technique is advocated only for small lesions within the palm. Skin grafts provide a viable alternative to the open-palm technique; however, no skin graft can adequately replace the glabrous skin of the palm. Skin grafts have, however, been demonstrated to prevent local recurrence in several studies.^{83–88} A single series of 103 patients published by Logan and colleagues noted only nine histologically confirmed recurrences in patients treated with dermatofasciectomy.⁸⁸ Dermatofasciectomy is most clearly indicated in cases of recurrent disease and in patients with early-onset primary disease with significant skin involvement.

Postoperative care

Postoperative therapy in Dupuytren's disease couples early motion to maintain joint mobility with extension splinting to reduce the risk of early contracture. The interrelationship between these two opposing regimens is dictated by the procedure performed.

Patients undergoing enzymatic or percutaneous fasciotomy are placed in a soft, bulky dressing postoperatively in order to provide mild compression and for comfort. This dressing is removed 1–3 days after the procedure and patients are encouraged to use their hand normally as tolerated by level of comfort. Hand therapy is rarely required in order to facilitate mobilization and extension night splinting is encouraged for 3–4 months following contracture release.

Patients undergoing fasciectomy typically have more discomfort and postoperative stiffness compared with those undergoing percutaneous techniques. A volar splint is placed with the MCP and PIP joints in maximal extension, leaving unoperated fingers free. The fingertips should be visible to allow for assessment of perfusion. In the absence of a skin graft, this splint is taken down and physical therapy for active and passive range of motion is begun at 3–5 days after surgery. The suture lines are dressed daily with antibiotic-impregnated gauze and sutures are left in place for 14 days. Skin grafts are held in place with tie-over bolsters consisting of antibiotic gauze and this dressing is taken down after 5 days. In these patients, range of motion is delayed until postoperative day 7 to allow for sufficient revascularization of the graft.

Hand therapy is generally required in patients with severe MCP and any degree of PIP joint contracture and should be initiated as early as possible as allowed by postoperative pain and edema. Therapy first targets recovery of full finger flexion, followed by progressive restoration of finger extension. If articular interventions are performed, including check rein release, early dynamic splinting should be instituted. If central slip tenodesis was performed, immobilization must be continued for 3 weeks prior to the initiation of dynamic splinting.

Outcomes, prognosis, and complications

Percutaneous interventions in Dupuytren's disease seek to minimize wound complications and recovery. Complications arise as a consequence of the blind nature of these techniques. The short-term efficacy and complications of enzymatic fasciotomy have been well quantified in the phase III evaluation of clostridial collagenase. Edema (73%), bruising (51%), and injection site pain (32%) were the most commonly reported complications. Patients also noted discomfort with manual manipulation. No systemic side effects or type IV hypersensitivity reactions were noted. Serious complications included two tendon ruptures and one case of CRPS in 308 patients. Overall 64% of patients met the primary endpoint of correction of contracture to within 0–5° of full extension within 30 days of injection with an improvement of range of motion from 44° to 81°. When subdivided according to the joint treated, 76% of MCP contractures and 40% of PIP contractures met the primary endpoint with less severe contractures more reliably exhibiting correction.⁸⁹

With widespread use of collagenase, increasingly reliable data regarding efficacy has been published. The CORDLESS study provides 5-year follow-up on 644 patients who were successfully treated (met the initial primary endpoint of less than 5° of contracture following treatment) for MCP and PIP contracture with collagenase. At 5 years, 47% of joints demonstrated recurrence defined as 20° degrees or more loss of extension and 32% demonstrated greater than 30° loss of extension. Recurrence was 39% in MCP joints and 66% in PIP joints. 16% of patients required a secondary intervention within 5 years. Some 47% underwent surgical fasciectomy and 30% underwent additional collagenase injection. To date, there are no reported antibody-mediated reactions to collagenase despite the formation of antibodies to the enzyme isolated in 93% of patients.⁹⁰

Percutaneous (needle) aponeurotomy has been more widely employed and data regarding efficacy and prognosis have been established. In a multicenter trial in which 3736 percutaneous aponeurotomies were performed, 70% correction was reported in 93% of patients with stage I disease (less than 45° of flexion at the MCP and PIP), 78% of patients with stage II disease (45–90° of flexion at the MCP and PIP), 71% of patients with stage III disease (90–135° of flexion at the MCP and PIP), and 57% of patients with stage IV disease. Immediate failure to correct the underlying contracture is reported in 15–19% of patients.^{91,92} Two large series have evaluated complications in percutaneous fasciectomy. The first evaluated complications in 138 patients undergoing needle fasciotomy. Complications were reported as skin ruptures (16%), nerve transections (2%), and infections (2%).⁹¹ A larger multicenter study evaluating 799 patients undergoing 3736 percutaneous aponeurotomies reported complications including cutaneous rupture (2%), flexor tendon rupture (0.8%), and nerve transections (0.8%). Long-term data regarding recurrence and progression are sparse; however, Foucher *et al.* report a recurrence rate of 58% of patients undergoing needle aponeurotomy with a reoperation rate of 24% at 3.2 years.⁶⁷ Van Rijssen *et al.* evaluated recurrence in 115 patients treated with either needle aponeurotomy or limited fasciectomy and found an 85% recurrence

rate (defined as a greater than 30° increase in total passive extension deficit) compared with a 21% recurrence rate with limited fasciectomy at 5 years.⁹³

Techniques aimed at decreasing this high rate of recurrence have emerged as adjuncts to needle aponeurotomy including autologous fat injection and corticosteroid injection.^{94,95} While demonstrating some initial promise, both techniques are currently being evaluated more rigorously in randomized trials.

Complications in the surgical treatment of Dupuytren's disease may be categorized as perioperative, early postoperative, and late postoperative complications. Operative complications most commonly involve damage to the neurovascular bundle. Experienced surgeons have reported rates of arterial and nerve injury less than 0.4% and 2.3%, respectively.⁹⁶ Damage to the neurovascular bundle may be avoided by maintaining a high suspicion for a spiral nerve in all patients and particularly in those patients with PIP joint contracture. Dissection between the distal palmar crease and proximal digital crease should be specifically directed at identifying and preserving the neurovascular bundle. Nerve or vascular injury should be recognized and repaired immediately should it occur. The surgeon should be particularly vigilant during reoperation for recurrent contracture as a single digital artery may supply the digit. Digital ischemia is addressed intraoperatively by: (1) minimizing compression from skin closure and dressings; (2) infiltrating agents (papaverine, lidocaine) to decrease vasospasm; (3) decreasing extension of the digit to prevent unaccustomed stretch on the digital vessels; and (4) microsurgical exploration and repair as necessary (Box 17.4).

Early postoperative complications include infection, hematoma, skin necrosis, and postoperative flare reaction. Postoperative wound infection typically occurs in 1–4% of patients, but has been reported to be as high as 9.5%.⁹⁷ Infections are likely attributable to bacterial overgrowth within the macerated distal palmar crease as well as to tenuous blood supply to the palmar flaps. Another common complication of palmar dissection is postoperative hematoma, which often results in palmar skin necrosis if not identified and evacuated. The reported incidence in populations undergoing a variety of

surgical techniques is 2%; however, the risk with radical fasciectomy is significantly higher.⁹⁷ The risk of palmar hematoma may be minimized by obtaining hemostasis with the tourniquet deflated, prior to application of the final dressing, and by minimizing palmar dissection. Some authors advocate application of a pressure dressing; however, this intervention is unnecessary if meticulous operative hemostasis is obtained. The incidence of palmar hematoma may also be reduced with the use of the open-palm technique of McCash.^{82,96} Postoperative flare reaction may also occur. Flare reaction consists of significant pain, swelling, and joint stiffness, characteristically occurring in the third to fourth week following surgery. Flare reaction is significantly more common in women and its incidence is further increased with concomitant procedures, including carpal tunnel release.^{97,98} For this reason multiple procedures should not be performed at time of operation for Dupuytren's disease. This syndrome may be a precursor of CRPS, and the incidence is minimized with operation under regional anesthesia.

Late postoperative complications include CRPS, scar contracture disease recurrence, and disease progression. CRPS refers to a syndrome characterized by pain, allodynia, and hyperalgesia disproportionate to the extent of inciting injury accompanied by evidence of vasomotor instability. The reported incidence of CRPS in patients undergoing fasciectomy for Dupuytren's disease ranges between 4.5 and 40%, and varies on the choice of anesthetic. Regional analgesia provides the lowest postoperative incidence, with comparable results achieved with intravenous regional anesthesia accompanied by clonidine. The highest reported incidence occurs with general anesthesia.⁹⁹ For this reason, infraclavicular or axillary block should be considered the anesthetic method of choice when operating for Dupuytren's disease. Scar contracture occurs with longitudinal digital incisions. The risk of contracture is minimized by careful incisional planning, the use of Z-plasties at the flexion creases, or Brunner's incisions. Prolonged postoperative stiffness is reported in 10% of patients. The most common complication of Dupuytren's disease is recurrence. Recurrence is distinct from disease progression and is defined as the reappearance of Dupuytren's disease, nodules or cords, in a region previously cleared of abnormal fascia via operative excision. The incidence of recurrence varies with technique and ranges between 32 and 40% with open techniques, and is reported to be as high as 58% with percutaneous fasciotomy of the diseased cords.^{100,101} In general, recurrence may be minimized with appropriate digital dissection coupled with more extensive palmar dissection. The benefits of more extensive dissection must, however, be weighed against higher incidence of wound complications. Interestingly, most severe recurrences develop early, whereas later recurrences typically remain discrete, resulting in little or no functional disability.¹⁰² Recurrence does not invariably require additional surgery. Rodrigo and colleagues found that only 15% of patients required re-excision following disease recurrence.⁷³

BOX 17.4 Clinical tips: treatment of arterial insufficiency in Dupuytren's contracture release

Arterial insufficiency is a known surgical complication in the treatment of Dupuytren's disease. Ischemia may result from direct trauma to the digital artery as a consequence of dissection or, more commonly, as a result of traction and vasospasm as a previously contracted finger is straightened. The surgeon should have a methodical approach to the treatment of arterial insufficiency.

1. Flex the finger to alleviate traction on the digital artery.
2. Warm the finger with warm irrigant solution.
3. Apply topical papaverine (30 mg/mL) to facilitate smooth-muscle relaxation (lidocaine may be used alternatively or in addition to papaverine).
4. Be patient. Allow the relaxation, warming, and antivasospasm interventions time to work. The artery may require up to 10 minutes for the restoration of perfusion.
5. If arterial insufficiency persists beyond 10 minutes, explore the digital artery throughout the extent of dissection. Repair of a partial or complete laceration should be performed under the operating microscope. A vein graft may be necessary if undue tension is present.

Secondary procedures

Disease recurrence and progression are common in Dupuytren's disease and, consequently, operation for disease recurrence is the most common secondary procedure performed.

Severely contracted, functionally limiting fingers may require ray amputation; however, several alternatives to amputation exist and have gained an integral role in the treatment of recalcitrant disease. These procedures include skeletal traction, wedge osteotomy, total volar tenoarthrolysis, and PIP arthrodesis.

Skeletal traction

Severe PIP joint contractures may be addressed with the application of a dorsally based external distraction device. Described by Messina in 1989, the continuous elongation technique involves application of progressive continuous extension via an adjustable external device.¹⁰³ Full extension is typically achieved over the course of 2–4 weeks. This technique allows for ready access to the palm and a regional or dermatofasciectomy is performed concomitant with removal of the distraction device.

Biochemical studies have demonstrated an increase in the enzymatic activity of fibroblasts and increased collagen deposition in response to skeletal traction.¹⁰⁴ If left unaddressed, this stimulus results in disease progression, and, therefore, distraction alone is contraindicated unless coupled with subsequent fasciectomy. This technique is a useful addition to the surgeon's repertoire in addressing advanced Dupuytren's disease and may provide salvage in settings under which amputation might be considered.

Wedge osteotomy

Wedge osteotomy provides for a more functional range of motion in recalcitrant PIP contractures with residual flexion deformity despite attempts at surgical release. The operation consists of removal of a dorsal wedge from the proximal phalanx placing the PIP joint into a position in which the existing range of motion is functionally useful. Although advocated by some, wedge osteotomy maintains a very limited role in the treatment of advanced Dupuytren's disease.¹⁰⁵

Total volar tenoarthrolysis

Analogous to wedge osteotomy, total volar tenoarthrolysis redistributes the existing PIP range of motion to within a more functional range. Via a lateral digital approach, the volar plate and flexor digitorum superficialis and profundus are sectioned. This leaves the extensors and intrinsics as the only active determinants of digital motion. The finger passively falls into flexion due to the contracture of the palmar fascia.^{106,107}

PIP arthrodesis

Arthrodesis is indicated in patients with severe PIP joint contracture that has proven recalcitrant to surgical correction.

Underlying articular or degenerative change, pain upon restoration of motion, and immobility in a nonfunctional position are clear indications favoring PIP arthrodesis. MCP arthrodesis should be avoided as articular change does not occur with prolonged contracture at this joint and fusion at the MCP joint level is functionally limiting.

Amputation

Although commonly employed in the past in cases of severe primary contracture and recurrent, severe secondary contracture, amputation is now a relatively rare treatment of Dupuytren's disease. Skeletal traction has emerged as a useful adjunct in treating patients who might otherwise be considered candidates for amputation. Clear indications for amputation exist, including multiply recurrent contractures and in severely contracted fingers with nerve or vascular lesions. Ray amputation is preferable for the index, long, and ring fingers. Amputation at the MCP joint level is indicated to address small-finger contracture. Thumb amputation is contraindicated regardless of the severity of contracture. Dorsal skin should be preserved and may be useful in resurfacing the palm.

Future direction

The management of Dupuytren's disease remains a challenging problem for hand surgeons. Operative results are tempered by relatively high rates of disease recurrence and each subsequent operation affords a narrower margin for functional improvement and higher risk to the neurovascular structures of the hand. Novel techniques, including percutaneous aponeurotomy and enzymatic fasciotomy, have afforded new treatment options for both patients and surgeons. As these techniques are utilized over the coming years, their respective niches and relative weaknesses and strengths will become further defined.

Despite these advances in surgical and nonsurgical techniques, no modality offers a cure. The ultimate treatment is, as yet, undiscovered but will likely rely on arresting the underlying disease process, rather than attempting to treat the sequelae. Bench and clinical research continue to identify and evaluate new clinical targets and novel therapeutic interventions. The opportunity to modify the underlying disease process via pharmacotherapeutics and interventional treatments offers the greatest promise for functional preservation and disease prevention.



Access the complete reference list online at <http://www.expertconsult.com>

21. Dupuytren G. *Leçons orales de clinique chirurgicale faites à l'Hôtel-Dieu de Paris*. Paris: Baillière; 1832.
27. Luck JV. Dupuytren's contracture. A new concept of the pathogenesis correlated with the surgical management. *J Bone Joint Surg Am*. 1959;40:635–664. In this seminal manuscript, Luck provides a detailed description of the histopathologic anatomy and disease progression in Dupuytren's disease. Luck's proliferative, involutinal,

and residual phases provide a framework within which molecular advances may be analyzed and a foundation for clinicians' understanding of disease progression.

33. Shaw RB, Chong AK, Zhang A, et al. Dupuytren's disease: history, diagnosis, and treatment. *Plast Reconstr Surg*. 2007;120:44e–54e.
35. McFarlane RM. Patterns of Diseased Fascia in the Fingers in Dupuytren's Contracture. *Plast Reconstr Surg*. 1974;54:31–44. In this

manuscript, McFarlane details the normal and pathologic disease correlates in the progression of Dupuytren's disease. A detailed description of the formation of the spiral cord has provided the foundation for all subsequent manuscripts. The detailed illustrations are useful and frequently reproduced.

73. Rodrigo JJ, Niebauer JJ, Brown RL, et al. Treatment of Dupuytren's contracture: long-term results after fasciotomy and fascial excision. *J Bone Joint Surg Am.* 1976;58:380–387. Rodrigo's manuscript provides the first and largest assessment of the clinical outcomes following fascial excision in Dupuytren's disease. This manuscript established the commonly quoted 32% recurrence rate and established that only a portion of recurrences (15%) require reoperation.
79. McIndoe A, Beare RL. The surgical management of Dupuytren's contracture. *Am J Surg.* 1958;95:197–203.
83. Tonkin MA, Burke FD, Varian JP. The proximal interphalangeal joint in Dupuytren's disease. *J Hand Surg [Br].* 1985;10:358–364.
89. Hurst LC, Badalamente MA, Hentz VR, et al. Injectable collagenase *Clostridium histolyticum* for Dupuytren's contracture. *N Engl J Med.* 2009;361:968–979. This manuscript describes a multicenter, randomized, double-blind, placebo-controlled trial of clostridial collagenase injection in the treatment of Dupuytren's disease. A total of 64% of patients met the primary endpoint of correction to within 0–5° of full extension. When subdivided according to the joint treated, 76% of MCP contractures and 40% of PIP contractures met the primary endpoint, with less severe contractures more reliably exhibiting correction. This study provides the first large-scale assessment of the efficacy, safety, and reliability of clostridial collagenase injection therapy.
96. Bulstrode NW, Jemec C, Smith PJ. The complications of Dupuytren's contracture surgery. *J Hand Surg Am.* 2005;30:1021–1025.
101. Foucher G, Medina J, Navarro R. Percutaneous needle aponeurotomy: complications and results. *J Hand Surg [Br].* 2003;28:427–431. Foucher provides a detailed description of the technique of needle aponeurotomy, including operative indications, patient selection, and technical considerations. A review of the complications and outcomes provides the reader with a detailed understanding of the evolving role of percutaneous aponeurotomy in the treatment of Dupuytren's disease.

References

1. Early PF. Population studies in Dupuytren's contracture. *J Bone Joint Surg Br.* 1962;44:602–613.
2. Hueston JT. Dupuytren's contracture: the trend to conservatism. *Ann R Coll Surg Engl.* 1965;36:134–151.
3. Hueston JT. The management of ectopic lesions in Dupuytren's contracture. In: Hueston JT, Tubaina R, eds. *Dupuytren's Disease*. Edinburgh: Churchill Livingstone; 1974.
4. Hueston JT. Dupuytren's contracture and occupation. *J Hand Surg Am.* 1987;12:657–658.
5. McFarlane RM. On the origin and spread of Dupuytren's disease. *J Hand Surg Am.* 2002;27:385–390.
6. Ling RS. The genetic factor in Dupuytren's disease. *J Bone Joint Surg Br.* 1963;45:709–718.
7. Wilbrand S, Ekblom A, Gerdin B. The sex ratio and rate of reoperation for Dupuytren's contracture in men and women. *J Hand Surg Am.* 1999;24B:456–459.
8. Liss GM, Stock SR. Can Dupuytren's contracture be work related? Review of the evidence. *Am J Ind Med.* 1996;29:521–532.
9. Burge P, Hoy G, Regan P, et al. Smoking, alcohol, and the risk of Dupuytren's contracture. *J Bone Joint Surg Br.* 1997;79:206–210.
10. Leslie BM. Palmar fasciitis and polyarthritis associated with malignant neoplasm: a paraneoplastic syndrome. *Orthopedics.* 1992;15:1436–1439.
11. Legueu F, Juvara E. Des aponévroses de la paume de la main. *Bull Soc Anat Paris.* 1892;6:383.
12. Testut L. *Traité d'anatomie humaine*. Paris: Octave Doin; 1893.
13. McGrouther DA. The microanatomy of Dupuytren's contracture. *Hand.* 1982;13:215–236.
14. Tubiana R, Leclercq C, Hurst L, et al. *Dupuytren's Disease*. London: Martin Dunitz; 2000.
15. Bojsen-Moller F, Schmidt L. The palmar aponeurosis and the central spaces of the hand. *J Anat.* 1974;117:55–68.
16. Thomine JM. Conjonctif d'enveloppe des doigts et squelette fibreux des commissures interdigitales. *Ann Chir Plast.* 1965;3:194–203.
17. Weitbrecht J. Syndesmologia sive historia ligamentorum corporis humani (1742). In: *Syndesmology*. Philadelphia: WB Saunders; 1969 Kaplan EB, trans.
18. Belusa L, Buck-Gramko D, Partecke BD. Results of interphalangeal joint arthrolysis in patients with Dupuytren's disease. *Handchir Mikrochir Plast Chir.* 1997;27:158–163.
19. Cline H. Notes on pathology and surgery. Manuscript 28. St. Thomas Hospital Library, London, 1777. Dislocation from contraction of the tendon. In: Cooper A, ed. *A Treatise on Dislocations and Fractures of the Joints*. London: Longman; 1822.
20. Cooper A, ed. *A Treatise on Dislocations and Fractures of the Joints*. London: Longman; 1822.
21. Dupuytren G. *Leçons orales de clinique chirurgicale faites à l'Hôtel-Dieu de Paris*. Paris: Baillière; 1832.
22. Dupuytren G. Permanent retraction of the fingers produced by an affection of the palmar fascia. *Lancet.* 1834;2:222–225.
23. Meyerding H, Black J, Broders A. The etiology and pathology of Dupuytren's contracture. *Surg Gynecol Obstet.* 1941;72:582–590.
24. Kloen P, Jennings CL, Gebhardt MC, et al. Transforming growth factor-beta: possible roles in Dupuytren's contracture. *J Hand Surg Am.* 1995;20:101–108.
25. Kloen P. New insights in the development of Dupuytren's contracture: a review. *Br J Plast Surg.* 1999;52:629–635.
26. Lee LC, Zhang AY, Chong AK, et al. Expression of a novel gene, MafB, in Dupuytren's disease. *J Hand Surg Am.* 2006;31:211–218.
27. Luck JV. Dupuytren's contracture. A new concept of the pathogenesis correlated with the surgical management. *J Bone Joint Surg Am.* 1959;40:635–664. In this seminal manuscript, Luck provides a detailed description of the histopathologic anatomy and disease progression in Dupuytren's disease. Luck's proliferative, involutional, and residual phases provide a framework within which molecular advances may be analyzed and a foundation for clinicians' understanding of disease progression.
28. Brickley-Parsons D, Glimcher MJ, Smith RJ, et al. Biochemical changes in the collagen of the palmar fascia in patients with Dupuytren's disease. *J Bone Joint Surg Am.* 1981;63:787–797.
29. Tomasek JJ, Schultz RJ, Episalla CW, et al. The cytoskeleton and extracellular matrix of the Dupuytren's disease myofibroblast: an immunofluorescence study of a non-muscle cell type. *J Hand Surg Am.* 1986;11:365–371.
30. Murrell GA, Francia MJ, Bromley L. Modulation of fibroblast proliferation by oxygen free radicals. *Biochem J.* 1990;265:659–665.
31. Halliday NL, Tomasek JJ. Mechanical properties of the extracellular matrix influence fibronectin fibril assembly *in vitro*. *Exp Cell Res.* 1995;217:109–117.
32. Badalamente MA, Sampson SP, Hurst LC, et al. The role of transforming growth factor beta in Dupuytren's disease. *J Hand Surg Am.* 1996;21:210–215.
33. Shaw RB, Chong AK, Zhang A, et al. Dupuytren's disease: history, diagnosis, and treatment. *Plast Reconstr Surg.* 2007;120:44e–54e.
34. Short WH, Watson HK. Prediction of the spiral nerve in Dupuytren's contracture. *J Hand Surg Am.* 1982;7:84–86.
35. McFarlane RM. Patterns of Diseased Fascia in the Fingers in Dupuytren's Contracture. *Plast Reconstr Surg.* 1974;54:31–44. In this manuscript, McFarlane details the normal and pathologic disease correlates in the progression of Dupuytren's disease. A detailed description of the formation of the spiral cord has provided the foundation for all subsequent manuscripts. The detailed illustrations are useful and frequently reproduced.
36. Johnson HA. The Hugh Johnson sign of early Dupuytren's contracture. *Plast Reconstr Surg.* 1980;65:697.
37. Caroli A, Zanasi S, Marcuzzi A, et al. Epidemiology and structural findings supporting the fibromatous origin of dorsal knuckle pads. *J Hand Surg [Br].* 1991;16:258–262.
38. Mikkelsen OA. Dupuytren's disease. Initial symptoms, age of onset and spontaneous course. *Hand.* 1977;9:11–15.
39. Mikkelsen OA. Epidemiology of a norwegian population. In: McFarlane RM, McGrouther DA, Flint MH, eds. *Dupuytren's Disease*. Edinburgh: Churchill Livingstone; 1990.
40. Viljanto JA. Dupuytren's contracture: a review. *Semin Arthritis Rheum.* 1973;3:155–176.
41. McFarlane RM. Some observations on the epidemiology of Dupuytren's disease. In: Hueston JT, Tubiana R, eds. *Dupuytren's Disease*. 2nd ed. Edinburgh: Churchill Livingstone; 1985.
42. Vorstman B, Grossman JA, Gilbert DA, et al. *Maladie de la Peyronie*. In: Tubaina R, Hueston JT, eds. *La Maladie de Dupuytren*. 3rd ed. Paris: l'Expansion Scientifique Française; 1986:221–225.
43. Aviles E, Arlen E, Miller T. Plantar fibromatosis. *Surgery.* 1971;69:117–120.
44. Allen RA, Woolner LB, Ghormley RK. Soft tissue tumors of the sole – with special reference to plantar fibromatosis. *J Bone Joint Surg Am.* 1955;37:14–26.
45. Lettin A. Dupuytren's diathesis. *J Bone Joint Surg Br.* 1964;46:220–225.
46. Matev I. Dupuytren's contracture with associated changes in the plantar aponeurosis and in the auricular conchae. *Ann Hand Surg.* 1990;9:379–380.
47. Hueston JT. Dupuytren's contracture. In: Converse JM, ed. *Reconstructive Plastic Surgery*. Vol. 6. 2nd ed. Philadelphia: WB Saunders; 1977:3403–3427.
48. Stiles PJ. Ultrasonic therapy in Dupuytren's contracture. *J Bone Joint Surg Br.* 1966;48:452–454.
49. Keilholz L, Seegenschmiedt M, Sauer R. Radiotherapy for prevention of disease progression in early stage Dupuytren's contracture: initial and long-term results. *Int J Radiat Oncol Biol Phys.* 1996;36:891–897.
50. Falter E, Herndl E, Muhlbauer W. Dupuytren's contracture. When operate? Conservative preliminary treatment? *Fortschr Med.* 1991;109:223–226.
51. Weinzierl G, Flugel M, Geldmacher J. Lack of effectiveness of alternative nonsurgical treatment procedures in Dupuytren's contracture. *Chirurg.* 1993;64:492–494.

52. Vuopala LU, Kaipainen WJ. DMSO in the treatment of Dupuytren's contracture: a therapeutic experiment. *Acta Rheum Scand.* 1971;17:61–62.
53. Kirk JE, Cheiffi M. Tocopherol administration to patients with Dupuytren's contracture: effect on plasma tocopherol levels and degree of contracture. *Proc Soc Exp Biol Med.* 1952;80:565–568.
54. Dahmen G, Kerckhoff F. Possibilities and limitations of the conservative treatment of Dupuytren's contracture. *Med Monatsschr.* 1966;20:297–300.
55. Dominguez-Malagon HR, Alferian-Ruiz A, Chavarria-Xi-cotencatl P, et al. Clinical and cellular effects of colchicine in fibromatosis. *Cancer.* 1992;69:2478–2483.
56. Pittet B, Rubbia-Brandt L, Desmouliere A, et al. Effect of gamma-interferon on the clinical and biologic evolution of hypertrophic scars and Dupuytren's disease: an open pilot study. *Plast Reconstr Surg.* 1994;93:1224–1235.
57. Baxter H, Schiller C, Johnson LH, et al. Cortisone therapy in Dupuytren's contracture. *Plast Reconstr Surg.* 1952;9:261–273.
58. Kaufhold N. Die örtliche Behandlung mit 6-methylprednisolon (Urbason). *Munch Med Wochenschr.* 1962;104:2252–2253.
59. Ketchum LD. Dupuytren's contracture: triamcinolone injection. Correspondence Newsletter No 131, American Society for Surgery of the Hand, 1996.
60. Langemark V. Zur thiosinaminbehandlung der dupuytrenschen fascienkontraktur. *Munchen Med Wochenschr.* 1907;54:1308.
61. Bassot J. Treatment of Dupuytren's disease by isolated pharmacodynamic "exeresis" or "exeresis" completed by a solely cutaneous plastic step. *Lille Chir.* 1965;20:38–44.
62. Hueston JT. Enzymic fasciotomy. *Hand.* 1971;3:38–40.
63. McCarthy DM. The long term results of enzymatic fasciotomy. *J Hand Surg [Br].* 1992;17:356.
64. Mickelson DT, Noland SS, Watt AJ, et al. Prospective randomized controlled trial comparing 1 versus 7 day manipulation following collagenase injection for Dupuytren contracture. *J Hand Surg Am.* 2014;39:1933–1941.
65. De Seze S, Debeyre N. Traitement de la maladie de Dupuytren par l'hydrocortisone locale associée aux manœuvres de redressement (70 cas traités). *Rev Rhum.* 1957;24:540–550.
66. Lermusiaux JL, Debeyre N. Le traitement médical de la maladie de Dupuytren. In: De Seze S, Rickewaert A, Kahn MF, et al., eds. *L'actualité rhumatologique. Paris: L'Expansion Scientifique Française.* 1980.
67. Foucher G, Medina J, Navarro R. L'aponevrotomie percutanée à l'aiguille. Complications et résultats. *Chir Main.* 2001;20:206–211.
68. Dupuytren G. Contracture de petit doigt et de l'annulaire de la main gauche dissipé complètement par le simple débridement de l'aponévrose palmaire. *Gazette Hop.* 1831.
69. Watson JD. Fasciotomy and Z-plasty in the management of Dupuytren's contracture. *Br J Plast Surg.* 1984;37:27–30.
70. McGregor IA. Fasciotomy and graft in the management of Dupuytren's contracture. In: Hueston JT, Tubiana R, eds. *Dupuytren's Disease.* Edinburgh: Churchill Livingstone; 1985.
71. Thurston AJ. Conservative surgery for Dupuytren's contracture. *J Hand Surg [Br].* 1987;12:329–334.
72. Gonzalez RI. Open fasciotomy and wolfe graft for Dupuytren's contracture. In: Hueston JT, ed. *Transactions of the Fifth International Congress of Plastic and Reconstructive Surgery.* Melbourne: Butterworth; 1971.
73. Rodrigo JJ, Niebauer JJ, Brown RL, et al. Treatment of Dupuytren's contracture: long-term results after fasciotomy and fascial excision. *J Bone Joint Surg Am.* 1976;58:380–387. Rodrigo's manuscript provides the first and largest assessment of the clinical outcomes following fascial excision in Dupuytren's disease. This manuscript established the commonly quoted 32% recurrence rate and established that only a portion of recurrences (15%) require reoperation.
74. Tubiana R. Dupuytren's disease of the radial side of the hand. *Hand Clin.* 1999;15:149–159.
75. Curtis RM. Volar capsulectomy in the PIP joint in Dupuytren's contracture. In: Hueston JT, Tubiana R, eds. *Dupuytren's Disease.* Edinburgh: Churchill Livingstone; 1974.
76. Watson HK, Light TR, Johnson TR. Checkrein resection for flexion contracture of the middle joint. *J Hand Surg.* 1979;4:67–71.
77. Tubiana R. Overview on surgical treatment of Dupuytren's disease. In: Hueston JT, Tubiana R, eds. *Dupuytren's Disease.* London: Churchill Livingstone; 1985.
78. Breed CM, Smith PJ. A comparison of methods of treatment of PIP joint contractures in Dupuytren's disease. *J Hand Surg [Br].* 1996;21:246–251.
79. McIndoe A, Beare RL. The surgical management of Dupuytren's contracture. *Am J Surg.* 1958;95:197–203.
80. Hamlin E. Limited excision of Dupuytren's contracture. *Ann Surg.* 1952;135:94–97.
81. Dickie WR, Hughes NC. Dupuytren's contracture: a review of the late results of radical fasciectomy. *Br J Plast Surg.* 1967;20:311–314.
82. McCash CR. The open palm technique in Dupuytren's contracture. *Br J Plast Surg.* 1964;17:271–280.
83. Tonkin MA, Burke FD, Varian JP. The proximal interphalangeal joint in Dupuytren's disease. *J Hand Surg [Br].* 1985;10:358–364.
84. Ketchum LD, Hixson FP. Treatment of Dupuytren's contracture with dermofasciectomy and full thickness skin graft. *J Hand Surg Am.* 1987;12:659–663.
85. Makela EA, Jaroma H, Harju A. Dupuytren's contracture: the long-term results after day surgery. *J Hand Surg [Br].* 1991;16:272–274.
86. Searle AE, Logan AM. A mid-term review of the results of dermofasciectomy for Dupuytren's disease. *Ann Chir Main Memb Super.* 1992;11:375–380.
87. Kelly C, Varian J. Dermofasciectomy: a long-term review. *Ann Chir Main Memb Super.* 1992;11:381–382.
88. Logan AM, Armstrong JR, Huerren J. Dermofasciectomy in the management of Dupuytren's disease. Paper Presented at the 7th Congress of the International Federation of Societies for Surgery of the Hand, Vancouver, British Columbia, 1998.
89. Hurst LC, Badalamente MA, Hentz VR, et al. Injectable collagenase *Clostridium histolyticum* for Dupuytren's contracture. *N Engl J Med.* 2009;361:968–979. This manuscript describes a multicenter, randomized, double-blind, placebo-controlled trial of clostridial collagenase injection in the treatment of Dupuytren's disease. A total of 64% of patients met the primary endpoint of correction to within 0–5° of full extension. When subdivided according to the joint treated, 76% of MCP contractures and 40% of PIP contractures met the primary endpoint, with less severe contractures more reliably exhibiting correction. This study provides the first large-scale assessment of the efficacy, safety, and reliability of clostridial collagenase injection therapy.
90. Peimer CA, Blazar P, Coleman S, et al. Dupuytren's contracture recurrence following treatment with collagenase clostridium histolyticum (CORDLESS: collagenase option for reduction of Dupuytren long-term evaluation of safety study): 5 year data. *J Hand Surg Am.* 2015;40:1597–1605.
91. Badois FJ, Lermusiaux JL, Masse C, et al. Traitement non chirurgical de la maladie de Dupuytren par aponevrotomie à l'aiguille. *Rev Rhum.* 1993;60:808–813.
92. Lermusiaux JL, Lellouche H, Badois JF, et al. How should Dupuytren's contracture be managed in 1997? *Rev Rhum Engl Ed.* 1997;64:775–776.
93. van Rijssen AL, Werker PM. Percutaneous needle fasciotomy for recurrent Dupuytren's disease. *J Hand Surg Am.* 2012;37:1820–1823.
94. Hovius SE, Kan HJ, Smit X, et al. Extensive percutaneous aponeurotomy and lipografting: A new treatment for Dupuytren's disease. *Plast Reconstr Surg.* 2011;128:221–228.
95. McMillan C, Binhammer P. Steroid injection and needle aponeurotomy for Dupuytren contracture: a randomized controlled study. *J Hand Surg Am.* 2012;37:1307–1312.
96. Bulstrode NW, Jemec C, Smith PJ. The complications of Dupuytren's contracture surgery. *J Hand Surg Am.* 2005;30:1021–1025.
97. Zemel NP. Dupuytren's contracture in women. *Hand Clin.* 1991;7:707–711.

98. Nissenbaum M, Kleinert HE. Treatment considerations in carpal tunnel syndrome with coexisting Dupuytren's disease. *J Hand Surg Am*. 1980;5:544-547.
99. Reuben SS, Pristas R, Dixon D, et al. The incidence of complex regional pain syndrome after fasciectomy for Dupuytren's contracture: a prospective observational study of four anesthetic techniques. *Anesth Analg*. 2006;102:499-503.
100. Au-Yong IT, Wildin CJ, Dias JJ, et al. A Review of common practice in Dupuytren surgery. *Tech Hand Up Extrem Surg*. 2005;9:178-187.
101. Foucher G, Medina J, Navarro R. Percutaneous needle aponeurotomy: complications and results. *J Hand Surg [Br]*. 2003;28:427-431. *Foucher provides a detailed description of the technique of needle aponeurotomy, including operative indications, patient selection, and technical considerations. A review of the complications and outcomes provides the reader with a detailed understanding of the evolving role of percutaneous aponeurotomy in the treatment of Dupuytren's disease.*
102. Norotte G, Apoil A, Travers V. A ten year follow-up of the results of surgery for Dupuytren's disease. a study of 58 cases. *Ann Chir Main*. 1988;7:277-281.
103. Messina A. La TEC (technical di estensione continua) nel morbo di dupuytren grave. Dall' amputazione alla ricostruzione. *Riv Chir Mano*. 1989;26:253-256.
104. Bailey AJ, Tarlton JF, Van der Stappen J. The continuous elongation technique for severe Dupuytren's disease: a biochemical mechanism. *J Hand Surg [Br]*. 1994;19:522-527.
105. Eicher E, Moberg F. Moglichekeiten zur Vermeidung von Amputationen bei schwerer Dupuytren'scher Kontraktur. *Handchirurgie*. 1970;2:56-60.
106. Saffar PH. Total anterior teno-arthrolysis. Report of 72 cases. *Ann Chir Main*. 1983;2:345-350.
107. Foucher G, Legallard P. Anterior tenoarthrolysis in flexion contracture of the fingers. Apropos of 41 cases. *Rev Chir Orthop Reparatrice Appar Mot*. 1996;82:529-534.

18

Occupational hand disorders

Steven J. McCabe

SYNOPSIS

- Upper extremity problems that are attributed to the workplace require experience, a knowledge base, and skill set that set them aside from non-occupational injuries.
- To evaluate causation requires a careful history and physical examination as well as knowledge of the disease process and literature.
- The workers' compensation environment creates external forces on the provider and patient that can adversely affect patient management and recovery.
- Management of work-related upper extremity disorders should include non-surgical care when it is known to be efficacious.
- Return to meaningful employment and high quality of life are the desired outcomes.

Introduction

There are several reasons why upper extremity problems relating to work activities are considered as a distinct entity. The surgeon is frequently called upon to judge the validity of work attribution. Some upper extremity problems are closely identified with work activity and hence could correctly be called occupational injuries. High pressure injection injuries and vibration induced problems are closely identified with a certain occupational activity. In addition to these problems that are closely identified with specific work, there are upper extremity problems that seem to occur in greater than expected numbers, i.e., their incidence rate may be higher, in certain working populations. Although tendon entrapments are often seen in the non-working population, their occurrence is often attributed to work activity. The surgeon is often called upon to determine causation or if the upper extremity problem is related to the work activity. Second, illness related to the work place requires considerations for management not needed in problems unrelated to work. Documentation and justification of attribution to the workplace, guiding the return to some

form of modified work and full duty work are examples of issues in management that are more profound in the work-related injury. Finally, the outcomes of treatment in upper extremity problems related to the workplace are qualitatively and quantitatively different than similar problems not related to the workplace. Return to previous work is an outcome of interest unto itself. The surgeon will be involved in determining the return to regular or modified work activities, the completion of active medical care, and the assignment of a permanent impairment rating.

Hints and tips

- Some upper extremity problems are closely associated with work activity.
- Work-related upper extremity disorders require management considerations that are different than non-work-related problems.
- Return to full activity at work is one important outcome goal.

Causation

Physicians and surgeons are often called on to judge whether a specific work activity could cause the upper extremity problem of a patient. To do this, the surgeon must bring to bear all the evidence that is available from the history of injury, the time course of events since the injury, the physical examination, information from diagnostic tests, as well as knowledge of the upper extremity problem diagnosed in the patient.

Patient history

Initial events

The history must be detailed and thorough. It is important to consider the sequence of events, the history of injury, the

behavior of the patient, co-workers, and medical providers at the time of the injury. Often a careful history will reveal features of the injury that were previously unclear such as the nature of a crushing injury or the lack thereof. A severe injury will usually demand an immediate response and care. When a patient was able to complete vigorous work for the remainder of the day following an injury and reported the injury some days later, many severe injuries can be excluded. Similarly, a review of the original medical records is often informative. The description of the emergency room doctor or first examining physician provides contemporaneous information on the severity of injury. Severe swelling, bruising, or radiographic evidence of soft-tissue swelling or fracture at the time of the injury will all document the nature of the original injury. Similarly, a lack of physical findings at the time of the injury may be important for lingering symptomatic problems. The initial behavior of the patient and documentation of the injury before the initiation of the workers' compensation system of care and the influence of society will be informative for future management. For an observed traumatic event, immediate contemporaneous actions and information are the result of the injury whereas later behavior is a result of the injury and the influence of a number of other societal factors that have to be considered.

The course of illness

Through education and experience, surgeons understand the expected course of an illness and can detect when there is variation from this. When the course of illness varies to some large degree it is sometimes possible to determine that the symptoms and physical findings of a current evaluation could not be consistent with an injury that is described in the history and verified by review of initial medical records. In other words, knowledge of the natural course of an injury can be used to make strong statements about the lack of causation.

Physical examination

A detailed perceptive history and physical examination are required for careful evaluation of a work-related injury. The surgeon must use all of her senses to gather information. Open-ended questions, active listening, and fact checking are all important. Classic techniques such as repetition to check important physical findings, distraction, and use of a tool box of physical examination skills specific to the situation must be developed and practiced. Adequate time must be devoted to obtain accurate impressions and information.

Knowledge of the disease process and its causation

The concept of causation has evolved as our understanding of illness has changed. The concepts of Hill have stood the test of time as guidelines to evaluate associations as possibly causative, however it is clear there are no single or combination of characteristics of an association that can prove causation. The concept of causation requires in-depth knowledge of the content of the research to measure associations as well as their context and characteristics. It is difficult to suggest associations are causative from observational data alone. Therefore for many illnesses of the upper extremity related to

the workplace there will always be some uncertainty as to the accuracy of their attribution. This problem is magnified when considering an individual patient.

Hints and tips

- A detailed history, physical examination, and review of medical records surrounding the injury and the immediate following events are highly informative and important.
- The use of a special toolbox of physical examination skills can be used to evaluate the veracity of physical examination findings.
- Knowledge of the disease process and literature must be combined with the history and physical examination findings as noted above to make the best decision regarding attribution to the workplace.

The role of force and repetition

In 1991, Gerr and associates reported that: "Sufficient evidence is available at this time to conclude that several well-defined soft-tissue disorders of the upper extremities are etiologically related to occupational factors. These disorders include tendinitis of the hand and wrist, CTS, and hand-arm vibration syndrome. Force, repetition, and vibration have been established as risk factors in the etiology of these disorders."¹ These conditions are discussed further below.

Szabo has well advised against the use of "*cumulative trauma disorder*" or "*repetitive strain injury*" as diagnostic labels, suggesting the term "*work-related musculoskeletal disorders*" to describe an amorphous category of upper extremity problems, often characterized by pain, with no clear diagnosis or anatomic basis for symptoms, and clinical course that is not easy to understand given the traditional concepts of illness and injury.² It is plausible that highly repetitive activity of high enough force can lead to symptoms and disorders of the upper extremity but it seems most appropriate to consider these as attributes leading to potential causation rather than a diagnosis of an illness. Upper extremity pathology with a clear clinical diagnosis such as carpal tunnel syndrome (CTS) or de Quervain's tendonitis should be managed according to the standards available for the problem. A new diagnostic category is not required and confuses the management of the patient. Upper extremity problems without a clear diagnosis should be dealt with as such. A pseudo-diagnostic label will not help the patient recover from an illness.

Although the concept of causation is philosophical, practically, the best evidence that can be gathered would be the results of a randomized experiment where the causative agent is randomly distributed to two otherwise equivalent groups. Unfortunately, it is typically not possible to randomize the exposure to work activities. Failing this, it is important to understand this uncertainty and try to understand the consequences and minimize the negative impacts of this uncertainty.

What is the purpose of this attention being delivered to determine if the upper extremity problems are related to work and why is it the surgeon's responsibility to arbitrate this decision?

1. To provide the best management, the surgeon should have an accurate evaluation of the patient's illness,

which includes the pathology located in the upper extremity, how that is experienced by the patient, and the external factors that can influence the management and recovery.

2. It is important to the patient. In a work-related disorder the financial benefits of the workers' compensation system may be the only source of financial security for the patient.
3. An accurate and definitive decision about work attribution may be the best way to avoid the negative effects that accompany the workers' compensation system of insurance coverage. A rapid and accurate decision either affirmative or negative will reduce the potential for conflict and will be in the patient's best interest.
4. The surgeon is in the best position to gather and weigh all the evidence that is available.

Clinical care in illness related to the workplace

Injuries at the workplace can be broadly divided into acute traumatic injuries and those without a single identifiable traumatic incident.

When a worker suffers a verifiable traumatic injury at the workplace that is directly observed and an injury is present under any reproducible and acceptable method to define its presence, the attribution to work is not an issue. Efforts are provided at the best management and rehabilitation of the injured worker.

Millender *et al.* has divided the more chronic occupational injuries of the musculoskeletal system into four categories that provide a useful framework for discussion (Table 18.1).³

In category one, most patients are highly motivated and when the appropriate treatment is provided for the patient, the upper extremity problem resolves. The patient can resume work and there are no lingering effects. Happily in my experience this includes most injured workers.

In category two, some difficulties may arise as permanent impairment is possible. When the patient is left with permanent impairment the easiest resolution is for the injured

worker, upon recovery, to return to the same regular duty work that pre-dated the injury. If this is not possible, then a modified job with the same employer may be possible. Failing this, the worker may have to consider new work with a new employer, or retirement. This can be a difficult decision that requires coordination with a case manager or rehabilitation counselor. There are some patients with conditions usually well treated either non-surgically or surgically by the hand surgeon, who do not seem to have the capacity to recover to the extent that would let them return to their original job. This group of people may be difficult to identify before treatment begins but eventually they can be identified by a recovery that falls below the threshold that allows them to return to their pre-injury job. This group of patients is difficult for the hand surgeon to manage, and care should be taken to avoid a repetitious exposure to invasive treatments and repeated surgeries that never quite reach the expected result.

In category three, the patients may have pain that is out of proportion to their physical injury. They can be angry and frustrated at the lack of improvement, despite adequate medical care. Patients may have definite upper extremity pathology but this is difficult to improve to a degree that will be satisfactory to the patient. Surgeons will immediately recognize this group of patients, as features of the history and physical examination will be identified as falling outside the expected norms for the conditions being cared for. This embellishment of symptoms and physical findings may represent frustration on the part of the patient, an attempt to make the surgeon realize the depth of their problem, or conscious magnification of symptoms and findings. Unfortunately, this is a group of patients that is difficult for the surgeon to manage. An honest approach will result in anger on the part of the patient, but management that deals with the upper extremity problem as an isolated independent part of the patient will not succeed.

In category four, the diagnosis of the upper extremity problem is unclear. Many of these patients will have vague diagnoses and may have had surgical procedures. They may have previous experience with other workers' compensation injuries and may have seen other hand surgeons. For example the patient may present with a problem whose existence is controversial, its pathology unproven, its treatment ill-defined, and its outcome uncertain. The patient may be in conflict with their employer and may be terminated from employment. When the worker has this type of an upper extremity disorder, there may be conflict at every aspect of the patient's interaction with the surgeon and healthcare system. The role of the hand surgeon is to take a careful history, perform a physical examination, recommend the appropriate diagnostic tests and provide honest recommendations for further management. Going for a surgical "Hail Mary" will be a disappointing misadventure.

At each step of care, the surgeon must be aware of the play of internal and external forces that promote and limit recovery. The structure of the workers' compensation system can create perverse incentives the surgeon must be perceptive about and must guard against. The surgeon may have perceived or real pressures to do things that are uncomfortable from an ethical standpoint. For example the surgeon may be pressured to return the injured worker back to the workplace early after surgery on limited work such as "one-hand duty". Workers with pain in one extremity from a workplace injury

Table 18.1 Chronic occupational injuries of the musculoskeletal system

Category 1	Diagnosis is easily established, good methods are available for treating the condition, and the prognosis for returning to work is good.
Category 2	Diagnosis is established, but neither non-surgical nor surgical treatment is always successful in returning the patient to the original job.
Category 3	The condition combines definite physical problems and additional non-medical issues.
Category 4	Diagnosis is unclear

(Reproduced from Millender LH, Louis DS, Simmons BP (eds). *Occupational Disorders of the Upper Extremity*. New York: Churchill Livingstone; 1992.)

or recent surgery may be required to go to the workplace and answer the phone or even perform useless or demeaning tasks or simply sit in a room or lie on a stretcher. This so-called presenteeism is a warping of societal norms that has occurred to circumvent the negative impact of workers' compensation protections. The physician wants to do the best for the patient but feels those decisions are beyond the scope of their influence. The presence of "one-hand work" creates the aura of reasonableness creating a plausible justification for the surgeon to agree to this. An alternative perspective to the potential harm caused by early return to work is a belief that the early return to the workplace is important in the recovery of the injured worker. Although the literature is sparse in this area there is a belief that returning an injured worker to a routine including work will be beneficial and minimize illness behavior.

If pushed back to work early, the patient may feel trapped in a closed system. The patient can be suspicious of the compensation system and lose the sense of control of their healthcare. Attempts to recover this control can be self-destructive and misunderstood.

An awareness of these forces will help the surgeon provide the best care for the patient and prevent a fatalistic approach by both. A clear focus should be on providing the best possible care for the upper extremity problem with perception of and attention applied to the other concerns of the patient.

Hints and tips

- Clinical problems associated with occupational disorders have been observed to fall into specific patterns that can lead to frustration and uncertainty.
- Early return to modified work is a "double-edged sword" that requires further research evaluation.

Tendinopathy

Medial and lateral epicondylitis

Van Rijn and associates have reviewed the literature evaluating the associations between lateral and medial epicondylitis and work-related factors such as force, repetition, posture and psychological issues.⁴ They report that handling tools of weight >1 kg; repetitive movements >2 h/day; low job control, and low social support, are associated with lateral epicondylitis. Handling tools >5 kg two times, at a minimum of 2 h/day, or tools >20 kg at least 10 times per day; high-hand grip forces for >1 h/day; repetitive movements for >2 h/day and working with vibrating tools, are associated with medial epicondylitis. The clinical management of these conditions have recently been reviewed by Rineer and Ruch.⁵

Lateral epicondylitis

Lateral epicondylitis, tennis elbow, presents with well-localized lateral elbow pain that is exacerbated by certain activities such as gripping. The diagnosis is made by history and physical examination. Physical examination will show point tenderness directly over the lateral epicondyle. Pain will be increased with resisted wrist extension, especially in elbow extension.

A cross-sectional study of 3710 workers in France revealed that 90 (2.4%) had lateral epicondylitis. Age, BMI >25, and low social support (for men) were significant risk factors. Hard perceived physical exertion combined with elbow flexion/extension (>2 hr/day) and wrist bending (>2 hr/day) was a strong significant risk factor for elbow pain and epicondylitis.⁶

Interestingly, from 1994 to 2006 there was an increase in ambulatory surgery rates for lateral epicondylitis from 7.29 to 10.44 per 100,000 persons.⁷

More recently, however, there is heightened interest in non-surgical management of lateral epicondylitis as it has become disseminated that this condition will resolve over time. Treatment is therefore used to temporize symptoms.

Splinting, counterforce bracing, non-steroidal anti-inflammatory drugs (NSAIDs), physical therapy, steroid injection, or simple observation without intervention have all shown to result in satisfactory results for a majority of patients. In addition, new modalities are being evaluated continuously. Surgical treatment is reserved for long time failures. Recently studied predictors of failure of non-surgical treatment include a workers' compensation claim, prior injection, the presence of radial tunnel syndrome, previous orthopedic surgery, and duration of symptoms greater than 12 months.⁸

A variety of surgical techniques that typically include debridement or tenotomy of the extensor carpi radialis brevis origin are used with reported good success.

Tendinopathy at the wrist and hand

In a review of data collected in 1988, Tanaka *et al.*⁹ reported that the period prevalence for tendinopathies, including tendinitis, synovitis, tenosynovitis, de Quervain's, or epicondylitis, ganglion cyst, or trigger digit was 0.46% of the population working within the previous year. Of these, 28% were thought to be work-related. The authors found bending and twisting of the wrist at work and female gender were associated with reporting these disorders.

De Quervain's tenosynovitis

Tenosynovitis of the first dorsal compartment is the signature work-related tendinopathy (Fig. 18.1). Interestingly, this condition is commonly seen in new mothers and in the worker.

Symptoms of de Quervain's are typically well localized to the radial side of the wrist. The Finkelstein's test is a sensitive




Fig. 18.1 De Quervain's tenosynovitis. Tendons of first dorsal compartment and planned release on dorsal half of sheath.

test for this problem and point tenderness is a specific test. The diagnosis is made by history and physical examination. Occasionally there will be a small ganglion overlying the first compartment.

Non-surgical treatment, including oral non-steroidal anti-inflammatory medication, steroid injections, splinting and therapy are often used to treat de Quervain's tenosynovitis. A recent review by Ilyas, of non-surgical treatment, pointed out the lack of randomized trials for this common condition.¹⁰ Nevertheless, one randomized trial of injection of triamcinolone versus placebo showed benefit from the active drug.¹¹

The anatomy of the first dorsal compartment, specifically the presence of a septum between the extensor pollicis brevis and abductor pollicis longus is an interesting finding more prevalent in de Quervain's tenosynovitis requiring surgical treatment than in cadaveric dissection. This anatomic feature has direct surgical importance as each tendon must be identified and released during surgery (see Fig. 18.1).

Surgery is performed using local anesthesia. A longitudinally oriented zigzag incision is made directly over the first dorsal compartment. The subcutaneous tissue is gently spread to avoid injury to small branches of the radial nerve and the medial antebrachial cutaneous nerve of the forearm. The first dorsal compartment is identified and opened dorsal to the midline. After complete release, each tendon is identified making sure the extensor pollicis brevis is released. If it is not identified, it will lie in a separate tunnel on the dorsal margin of the open first compartment. This is easily released from within the first dorsal compartment. The tourniquet is released before wound closure and a short thumb spica splint is worn until suture removal about 10–14 days later.

Trigger finger

Trigger digit is one of the most common disorders of the hand. A comprehensive review with extensive references has been published by Moore.¹² A case-control study found associations of trigger digit with female gender (OR 7.57, 95% CI 5.07–11.31); diabetes (OR 3.72, CI 2.43–5.70); obesity (OR 1.49, CI 1.02–2.19); occupation as a homemaker (OR 2.44, 95% CI 1.62–3.69); seamstress (OR 4.8, CI 1.3–21.6); and secretary (OR 2.74, CI 1.38–5.52). It is not clear from the abstract if gender was controlled for in these calculations although it would seem to be difficult to accomplish.¹³ A study in a meat packing plant found a person-year incidence rate of 12.4% for workers using tools and 2.6% for those without tool use. The authors believe high worker turnover may cause an underestimation of the rate in the workplace.¹⁴

The diagnosis of trigger digit is relatively straightforward and relies on history and physical examination. Triggering will usually be demonstrable in the office. The patient who presents with no active triggering and work attribution should be managed without invasive intervention. These patients may have triggering in the morning or heightened sensitivity to symptoms. The author recommends initial management with a night-time splint and re-evaluation of these patients. Patients who present with triggering and the presence of a flexion contracture of the proximal interphalangeal (PIP) joint can present a challenge. The surgeon must point this out before treatment starts and combine treatment of the trigger digit with splinting and mobilization of the PIP joint (Fig. 18.2).




Fig. 18.2 Trigger digit. Location of A1 pulley and planned incision on radial side of the pulley.

Treatment for trigger digit includes rest, splinting, steroid injection, and open or percutaneous surgery. Splinting can be used at any joint and is primarily used at night. This is particularly valuable if the finger is locked upon waking in the morning as night-time splinting can prevent this problem. Steroid injection is the mainstay of initial management for trigger digit. A Cochrane review supports the use of steroid as an efficacious treatment.¹⁵ Kerrigan and Stanwix used decision analysis and showed that management with one or two injections prior to surgery minimizes the cost of management.¹⁶

To inject the A1 pulley, I have the patient's hand resting palm up on the examining table with the fingers pointed to my left. This allows me to position my hand over the patient's wrist and angle the needle in a slight proximal to distal direction. I identify its position in the tendon by gentle passive flexion and extension of the digit with my left hand. Using gentle pressure on the syringe the needle is slowly withdrawn until there is a drop in resistance to injection. The injection can also be performed at the digital palmar flexion crease with the needle tip angled in a proximal direction.

Surgical treatment is performed using local anesthetic. The A1 pulley is released under direct vision and unrestricted motion of the digit is demonstrated in the operating room. Percutaneous release of trigger digit has been reported in the literature and can be performed in the office with lower cost than traditional surgery. One randomized trial found a high success rate in both treatment groups without serious complications.¹⁷ Like many other surgical procedures, the choice of procedure will depend on surgeon training and experience and the wishes of the informed patient. The proximity of the

digital nerves to the A1 pulley in the index and the thumb must be considered.

Nerve compression

The work attribution of nerve compression has a well-documented history and is still the object of intense research effort. As research designs are improved the relationship of carpal tunnel syndrome to keyboard use, for example, has become less certain. A recent review of the literature reveals the association between keyboard use and CTS has been based on epidemiologic studies with significant flaws.¹⁸ In fact, Atroshi *et al.* recently reported a study where use of a keyboard was found to be protective of CTS.¹⁹

Additional evidence exists confirming the relationship between force and repetition and CTS²⁰ and lack of an association with computer use.

Subsequently a review of systematic reviews and meta-analysis of current research concluded “there is high evidence for an increased risk of CTS in activities requiring a high degree of repetition and forceful exertion. The evidence for vibration is moderate ... There is no further evidence that CTS is caused by working with a computer keyboard or mouse.”²¹

One other systematic review and meta-analysis has agreed with this lack of association between computer use and carpal tunnel syndrome²² while another suggests that “excessive computer use, particularly mouse usage, might be a minor occupational risk factor for CTS.”²³

It is clear from the literature there is an inverse relationship between the specificity of the diagnosis of a disorder and the prevalence of the disorder. In other words, as the diagnostic criteria become more specific, i.e., other non-carpal tunnel syndrome causes of symptoms are ruled out, the prevalence of CTS is reduced. The incidence rate of CTS when it is diagnosed with high specificity is quite low even in the population of patients using a keyboard suggesting that this is unlikely to be a major work-related condition in keyboard users.

A recent review of CTS and its epidemiologic associations suggested occupational factors play a minor and debatable role in the etiology of CTS. In spite of some objections to the development of a scorecard based on the characteristics of an association defined by Hill, this review is a comprehensive and thought-provoking discussion of the potential causation of work-attributed CTS.²⁴

Even if work-attributed CTS is an upper extremity problem defined administratively and not by causative mechanism or pathology, it has been found the attribution to the workplace results in inferior outcomes compared to non-work-related surgical care for CTS.²⁵ Manktelow and colleagues, in reviewing a large population of CTS patients, found that residual symptoms after release of the carpal tunnel are common.²⁶

For CTS that has been attributed to the workplace, I recommend the patient proceed with a course of non-operative treatment before surgery is considered. Non-surgical treatment is efficacious and the improvement after splinting and/or injection is a good diagnostic test of the ability of the patient to obtain improvement from further intervention. If the diagnosis is correct, then any improvement following efficacious non-surgical treatment will be a good indicator that the patient has at least some potential for improvement.²⁷ If absolutely no benefit is achieved from non-surgical care, then the surgeon should confirm the diagnosis as much as

possible and recommend a thorough course of non-surgical treatment. Further detailed information on nerve compression syndromes can be found in Chapter 24.

Hints and tips

- Evidence is accumulating to show the lack of association between keyboard use and carpal tunnel syndrome.

Vascular disorders

In some occupations, the heel of the hand is used as a hammer to push objects into place. Some commonly recognized activities are “hammering” a board into place or putting on a hub cap. The ulnar artery and ulnar nerve pass through Guyon’s canal and are susceptible to injury in the hypothenar area. Thrombosis, pseudoaneurysm formation, embolic phenomena, and nerve symptoms are possible.

The history is usually highly suggestive of ulnar artery or nerve problems. Examination of the fingers may show signs of emboli and the Allen’s test may show occlusion of the ulnar artery. The history will likely be specific if a pseudoaneurysm is present and it will usually be obvious on physical examination.

Treatment of the so-called hypothenar hammer syndrome is based on the presence of symptoms. The presence of an ulnar artery occlusion on the Allen’s test without symptoms or peripheral signs does not necessitate surgical intervention. If there are compression symptoms and findings related to the ulnar nerve in Guyon’s canal or evidence of ischemia or emboli, then imaging is indicated. Magnetic resonance imaging (MRI) will define localized vascular pathology as well as masses within or deep to Guyon’s canal. Surgery will usually be indicated in the presence of neurologic or vascular symptoms.

Surgery for hypothenar hammer syndrome will start with release of the ulnar artery and nerve from the wrist crease to distal to Guyon’s canal. The motor branch of the ulnar nerve should be identified and followed deep into the palm. For ulnar arterial lesions, the area of obstruction is resected and the flow in the hand is evaluated. Resection of the artery alone has been reported to increase flow to the hand by way of a regional sympathetic effect. Treatment of choice is to perform an interposition vein graft with a short saphenous vein or a forearm vein. Further detailed information on hand ischemia syndromes can be found in Chapter 22.

Hand–arm vibration syndrome (HAVS)

The relationship of vibration to upper extremity pathology has been the subject of extensive literature and regulatory interest. For the upper extremity surgeon, there are criteria that score the vascular and neurologic components of vibration injury.

The classification scheme that was produced at a workshop in Stockholm bears its name as the Stockholm Workshop Scale (Table 18.2) and is divided into neurologic symptoms and vascular symptoms.²⁸

Although there is clear experimental evidence that vibration can cause injury to tissues, many of the symptoms of vibration-induced injury can be caused by other means. For

Table 18.2 Stockholm Workshop Scale

Neurologic symptoms		
0 SN	Exposed to vibration but no symptoms	
1 SN	Intermittent numbness, with or without tingling	
2 SN	Intermittent or persistent numbness, reduced sensory perception	
3 SN	Intermittent or persistent numbness, reduced tactile discrimination and/or manipulative dexterity	
Vascular symptoms		
0	–	No attacks
1	Mild	Occasional attacks affecting only the tips of one or more fingers
2	Moderate	Occasional attacks affecting distal and middle (rarely also proximal) phalanges of one or more fingers
3	Severe	Frequent attacks affecting all phalanges of most fingers
4	Very severe	As in stage 3, with trophic skin changes in the fingertips
(Reproduced from McGeoch KL, Lawson IJ, Burke F, et al. Diagnostic criteria and staging of hand-arm vibration syndrome in the United Kingdom. <i>Ind Health</i> . 2005;43:527–534.)		

example, the vascular symptoms of vibration injury can also be caused by smoking, something that is highly prevalent in some populations. The relationship of vibration to vascular disorders is also potentially confounded not only by smoking but also other problems such as peripheral vascular disease of other etiologies. The neurologic symptoms of vibration injury are typical of peripheral nerve compression so there is often confusion between a diagnosis of CTS and vibration-induced injury. The relationship between vibration injury and nerve compression is not clearly elucidated. For patients with nerve compression symptoms, however, it seems prudent to limit exposure to future vibration.

Patient management

When a working patient has a vascular complaint or a history of numbness or tingling, the surgeon should enquire about vibration in the workplace as well as other potential causative mechanisms for the symptoms including a cardiovascular history, a smoking history, and a family history. Similarly, a detailed history related to nerve symptoms may be helpful. If the worker has been exposed to vibration, it is important to create a temporal history of the time and degree of exposure over their entire work history.

The physical examination will evaluate the upper extremity for evidence of vascular and neurologic findings. This will include measuring the blood pressure in each arm, listening to the heart and for bruits along the major vessels, palpating pulses at various levels, performing an Allen's test, and evaluating the fingertips for color, trophic changes, and temperature. The examination of the peripheral nervous system includes measuring sensory and motor function, and evaluation for sites of nerve compression.

Additional evaluations will often include electrodiagnostic testing and non-invasive vascular testing. Angiograms are not indicated unless there is evidence of a structural problem that may require surgical planning.

Patients presenting with vascular or neurologic symptoms should be advised to avoid exposure to vibration. This advice does not implicate vibration as a cause of their symptoms but seems prudent, given the experimental evidence of the potential for vibration to cause injury.

Management of the patient further depends on the accurate diagnosis and management of other pathology such as CTS.

Hints and tips

- There continues to be a great deal of confusion surrounding the relationship between HAVS and nerve compression disorders.

Return to work

Keeping the injured worker in the workplace or reintegration of the injured worker into the workplace, is a vital outcome of management of occupational illness of the upper extremity. When an injury forces a patient to leave the workforce, even temporarily, the surgeon should be aware of several possible points of view: (1) The injury or illness may be more severe causing symptoms that make work impossible. This can have implications in the application of more invasive treatment at an earlier stage of management. (2) The patient's work activities may be more physical, requiring more intense use of the upper extremities, something that will influence their potential for return. (3) The financial stakes for the employer become higher, as salary replacement and a history of lost time injury may be important. (4) When the injured worker is unable to work, a set of emotional circumstances is potentially set into play that can possibly make it difficult for the worker to return to work.

In trying to return the patient to work, the first consideration is whether the patient has the ability to work in any capacity. The second consideration is whether the change in ability to work is either permanent or temporary. For temporary changes in the ability to work, restricted duty work is often available if the employee has a work-related injury. This may take the form of one-hand work if the injury is limited to one extremity and the patient's general condition allows safe return. For a patient who has a temporary inability to work in any capacity the surgeon will need to follow the patient closely and communicate with the workplace about return to work when the medical situation allows. If the patient has an injury or illness that permanently prevents unrestricted work, the surgeon will play an important role in returning the patient to gainful employment. The first step is to determine the permanent restrictions that will be recommended to the patient to keep him/her safe in the workplace. For practical purposes, this is done when the patient has reached their level of maximum medical improvement. Further active medical management would not be expected to increase the patient's status. At this time, the patient can have an impairment rating

calculated to facilitate compensation for the permanent effects of the injury. The second step is to return the patient to the workforce. Given a permanent impairment the first choice of return to the workplace is the previous employer and return to the pre-injury work. If this is not possible due to the restrictions, then return to the previous employer in a modified work capacity is often the easiest plan. This may not be possible and the injured worker may be required to search for a new job, limited by the restrictions that have been imposed to ensure safety. It is obvious each step of the process can have a big influence on the patient's return to the workplace and the ability to find future employment.

Measuring impairment

In measuring permanent impairment, the surgeon is providing a basis for financial compensation of the patient for the permanent effects of an injury in the workplace. This measurement is often performed by hand therapists. This measurement is indicated at the time when no further diagnostic testing or interventions are planned for the patient. It is meant to be a tally of the permanent effects of an injury after all steps have been taken to minimize them. Often, when the surgeon perceives the patient has reached this stage of maximum medical improvement, the evaluation of permanent impairment and the decision about permanent work restrictions will be accomplished simultaneously. If this is straightforward and without conflict, this can be done by the surgeon at the time of a final visit. If there is conflict, or if the return-to-work restrictions are complicated, a hand therapist may be of assistance.

In some situations of work-related upper extremity illness, the patient may have prolonged symptoms and an inability to work, despite maximum care, the determination that the patient is at maximum medical improvement, the assignment of permanent restrictions, and the determination of an impairment rating can allow the patient to move on with their life and provide a stopping point for further non-beneficial interactions with the surgeon.

The most recent version of the *Guides to the Evaluation of Permanent Impairment*, 6th edn, put forward by the American Medical Association has a fundamental change in the evaluation of permanent impairment, shifting to the ICF model, *The International Classification of Functioning, Disability and Health*.²⁹ This is outlined in the first chapter, "Conceptual Foundations and Philosophy".

"In this edition there is a paradigm shift, which adopts a contemporary model of disablement: it is simplified, function-

ally based, and internally consistent to the fullest extent possible."

"The vision ... is articulated in terms of five specific new axioms":

1. The terminology and conceptual framework of the ICF are adopted
2. Diagnosis and evidence-based where possible
3. Simplicity and ease of application
4. Functionally based
5. Conceptual and methodological congruity between and within organ systems.

Measures of permanent impairment are primarily based on diagnosis and then modified, based on several factors such as severity and functional limitation. Whether these new guides will supplant the 5th edition is not yet clear.

Use of the 5th or 6th edition of "The Guides" will bring objectivity to the measurement of permanent impairment and protects the surgeon from influence of the patient or the employer and insurance carrier.

Summary

The care of the injured worker mirrors the care of all patients with upper extremity injury and illness. The additional superimposition of the legal framework of workers' compensation adds an extra dimension to the care of the injured worker. The upper extremity surgeon must be knowledgeable of the local regulations and must be perceptive to their influence on the patient, the workplace, and the surgeon, and maintain the ability to take the best care possible of the patient.

Future directions

The increased use of valid clinical research methods by hand surgeons continues to change our understanding of so-called occupational upper extremity disorders. A clear example of this is the elucidation of the relationship between keyboard use and carpal tunnel syndrome. The application of valid research methodology will continue to advance our understanding and care of the working patient. The concept of presenteeism as it pertains to the injured worker and to the aging worker is an area for fruitful research. Surgeons must be cautious to insure their actions are in the best interest of the patient, requiring perception of sometimes conflicting interests of patients, employers, and insurance carriers.



Access the complete reference list online at

<http://www.expertconsult.com>

2. Szabo RM, King KJ. Repetitive stress injury: diagnosis or self-fulfilling prophecy? *J Bone Joint Surg Am*. 2000;82:1314–1322. *This current concepts review is a sobering review of the lack of science surrounding the epidemic of repetitive motion injuries. Szabo logically in a step-by-step fashion updates the literature on the perspective of a hand surgeon regarding these diagnoses.*
8. Knutsen EJ, Calfee RP, Chen RE, et al. Factors associated with failure of nonoperative treatment in lateral epicondylitis. *Am J Sports Med*. 2015;43:2133–2137. *In this publication the authors point out the risk factors for failure of non-operative treatment for lateral epicondylitis.*
9. Tanaka S, Peterson M, Cameron L. Prevalence and risk factors of tendonitis and related disorders of the distal upper extremity among US workers: comparison to carpal tunnel syndrome. *Am J Ind Med*. 2001;39:328–335. *This study reviewed the results of a survey instrument in a large population and found that 0.46% of those people who had worked in the previous 12 months reported prolonged hand discomfort. 28% of these problems were thought by a medical person to be work-related. The authors estimate there were 520,000 patients with work-related musculoskeletal disorders of the distal upper extremity in 1988.*
21. Kozak A, Schedlbauer G, Wirth T, et al. Association between work-related biomechanical risk factors and the occurrence of

- carpal tunnel syndrome: an overview of systemic reviews and a meta-analysis of current research. *BMC Musculoskelet Disord.* 2015;16:231. *This study reviews the systematic reviews and meta-analysis on the relationship between work and CTS. The study confirms the role of biomechanical causality in CTS and essentially puts to bed the linkage between CTS and the keyboard.*
24. Lozano-Calderon S, Anthony S, Ring D. The quality and strength of evidence for etiology: the example of carpal tunnel syndrome. *J Hand Surg Am.* 2008;33A:525–538. *The authors perform an exhaustive evaluation of the literature on the relationship between activity and carpal tunnel syndrome. Although it may not be prudent to use the guidelines of Hill as criteria, the authors have an extensive reference list and thoughtfully analyze the literature.*
 25. Harris I, Mulford J, Solomon M, et al. Association between compensation status and outcome after surgery: a meta-analysis. *JAMA.* 2005;293:1644–1652. *An eye-opening article that documents what surgeons have known for years. Patients whose medical problems are attributed to the workplace have an inferior outcome. This manuscript looks at carpal tunnel syndrome as one example. It cries out to researchers, policy-makers, and society to try to understand and change this negative influence.*
 26. Manktelow RT, Binhammer P, Tomat LR, et al. Carpal tunnel syndrome: cross-sectional and outcome study in Ontario workers. *J Hand Surg Am.* 2004;29A:307–317. *This interesting study reports that ongoing symptoms after carpal tunnel release in the working population are common.*
 29. Rondinelli RD, ed. *Guides to the Evaluation of Permanent Impairment.* 6th ed. Chicago, IL: American Medical Association; 2008.

References

- Gerr F, Letz R, Landrigan PJ. Upper-extremity musculoskeletal disorders of occupational origin. *Annu Rev Public Health*. 1991;12:543–566.
- Szabo RM, King KJ. Repetitive stress injury: diagnosis or self-fulfilling prophecy? *J Bone Joint Surg Am*. 2000;82:1314–1322. *This current concepts review is a sobering review of the lack of science surrounding the epidemic of repetitive motion injuries. Szabo logically in a step-by-step fashion updates the literature on the perspective of a hand surgeon regarding these diagnoses.*
- Millender LH, Louis DS, Simmons BP, eds. Occupational disorders of the upper extremity: orthopaedic, psychosocial, and legal implications. In: *Occupational Disorders of the Upper Extremity*. New York: Churchill Livingstone; 1992:1–14.
- Van Rijn RM, Huisstede BM, Koes BW, et al. Associations between work-related factors and specific disorders at the elbow: a systematic literature review. *Rheumatology*. 2009;48:528–536.
- Rineer CA, Ruch DS. Elbow tendinopathy and tendon ruptures: epicondylitis, biceps and triceps rupture. *J Hand Surg Am*. 2009;34A:566–576.
- Herquelot E, Bodin J, Roquelaure Y, et al. Work-related risk factors for lateral epicondylitis and other cause of elbow pain in the working population. *Am J Ind Med*. 2013;56:400–409.
- Best MJ, Buller LT, Nigen D, et al. US national practice patterns in ambulatory operative management of lateral epicondylitis. *Am J Orthop*. 2015;44:E508.
- Knutsen EJ, Calfee RP, Chen RE, et al. Factors associated with failure of nonoperative treatment in lateral epicondylitis. *Am J Sports Med*. 2015;43:2133–2137. *In this publication the authors point out the risk factors for failure of non-operative treatment for lateral epicondylitis.*
- Tanaka S, Peterson M, Cameron L. Prevalence and risk factors of tendonitis and related disorders of the distal upper extremity among US workers: comparison to carpal tunnel syndrome. *Am J Ind Med*. 2001;39:328–335. *This study reviewed the results of a survey instrument in a large population and found that 0.46% of those people who had worked in the previous 12 months reported prolonged hand discomfort. 28% of these problems were thought by a medical person to be work-related. The authors estimate there were 520 000 patients with work-related musculoskeletal disorders of the distal upper extremity in 1988.*
- Ilyas AM. Nonsurgical treatment for de Quervain's tenosynovitis. *J Hand Surg Am*. 2009;34A:928–929.
- Peters-Veluthamalingal C, Winters JC, Groenier KH, et al. Randomized controlled trial of local corticosteroid injections for de Quervain's tenosynovitis in general practice. *BMC Musculoskelet Disord*. 2009;10:131.
- Moore JS. Flexor tendon entrapment of the digits (trigger finger and trigger thumb). *J Occup Environ Med*. 2000;42:526–545.
- De la Parra-Marquez ML, Tamez-Cavazos R, Zertuche-Cedillo L, et al. Risk factors associated with trigger finger. Case-control study]. *Cir Cir*. 2008;76:323–327.
- Gorsche R, Wiley JP, Renger R, et al. Prevalence and incidence of stenosing flexor tenosynovitis (trigger finger) in a meat-packing plant. *J Occup Environ Med*. 1998;40:556–560.
- Peters-Veluthamalingal C, van der Windt DAWM, Winters JC, et al. Corticosteroid injection for trigger finger in adults. *Cochrane Database Syst Rev*. 2009;(1):CD005617.
- Kerrigan CL, Stanwix MG. Using evidence to minimize the cost of trigger finger care. *J Hand Surg Am*. 2009;34A:997–1005.
- Bamroongshawgasame T. A comparison of open and percutaneous pulley release in trigger digits. *J Med Assoc Thai*. 2010;93:199–204.
- Thomsen JF, Gerr F, Atroshi I. Carpal tunnel syndrome and the use of computer mouse and keyboard: a systematic review. *BMC Musculoskelet Disord*. 2008;9:134.
- Atroshi I, Gummesson C, Ornstein E, et al. Carpal tunnel syndrome and keyboard use at work. A population-based study. *Arthritis Rheum*. 2007;56:3620–3625.
- Fan ZJ, Harris-Adamson C, Gerr F, et al. Associations between workplace factors and carpal tunnel syndrome: a multi-site cross sectional study. *Am J Ind Med*. 2015;58:509–518.
- Kozak A, Schedlbauer G, Wirth T, et al. Association between work-related biomechanical risk factors and the occurrence of carpal tunnel syndrome: an overview of systemic reviews and a meta-analysis of current research. *BMC Musculoskelet Disord*. 2015;16:231. *This study reviews the systematic reviews and meta-analysis on the relationship between work and CTS. The study confirms the role of biomechanical causality in CTS and essentially puts to bed the linkage between CTS and the keyboard.*
- Mediouni Z, de Roquemaurel A, Dumontier C, et al. Is carpal tunnel syndrome related to computer exposure at work? A review and meta-analysis. *J Occup Environ Med*. 2014;56:204–208.
- Shiri R, Falah-Hassani K. Computer use and carpal tunnel syndrome: a meta-analysis. *J Neurol Sci*. 2015;15:15–19.
- Lozano-Calderon S, Anthony S, Ring D. The quality and strength of evidence for etiology: the example of carpal tunnel syndrome. *J Hand Surg Am*. 2008;33A:525–538. *The authors perform an exhaustive evaluation of the literature on the relationship between activity and carpal tunnel syndrome. Although it may not be prudent to use the guidelines of Hill as criteria, the authors have an extensive reference list and thoughtfully analyze the literature.*
- Harris I, Mulford J, Solomon M, et al. Association between compensation status and outcome after surgery: a meta-analysis. *JAMA*. 2005;293:1644–1652. *An eye-opening article that documents what surgeons have known for years. Patients whose medical problems are attributed to the workplace have an inferior outcome. This manuscript looks at carpal tunnel syndrome as one example. It cries out to researchers, policy-makers, and society to try to understand and change this negative influence.*
- Manktelow RT, Binhammer P, Tomat LR, et al. Carpal tunnel syndrome: cross-sectional and outcome study in Ontario workers. *J Hand Surg Am*. 2004;29A:307–317. *This interesting study reports that ongoing symptoms after carpal tunnel release in the working population are common.*
- Edgell SE, McCabe SJ, Breidenbach WC, et al. Predicting the outcome of carpal tunnel release. *J Hand Surg Am*. 2003;28A:255–261.
- McGeoch KL, Lawson IJ, Burke F, et al. Diagnostic criteria and staging of hand-arm vibration syndrome in the United Kingdom. *Ind Health*. 2005;43:527–534.
- Rondinelli RD, ed. *Guides to the Evaluation of Permanent Impairment*. 6th ed. Chicago, IL: American Medical Association; 2008.

19

Rheumatologic conditions of the hand and wrist

Douglas M. Sammer and Kevin C. Chung

 Access video content for this chapter online at expertconsult.com

SYNOPSIS

- Rheumatoid arthritis is a systemic autoimmune inflammatory disease that affects the joints of the hand and wrist. Rheumatoid arthritis also affects the soft tissues, and can cause disease processes such as trigger finger and carpal tunnel syndrome.
- The diagnosis of rheumatoid arthritis is primarily clinical, and is supported by radiographic and laboratory studies. Although symptoms can usually be managed effectively with newer biologic medications, some patients require surgery to treat refractory pain or to improve hand function.
- Operations for rheumatoid arthritis can be broadly categorized into five groups: synovectomy, tendon surgery, soft-tissue rebalancing, arthrodesis, and arthroplasty. Specific techniques described include: wrist synovectomy, tendon transfers for tendon rupture, soft-tissue rebalancing, management of the distal ulna and distal radio-ulnar joint (DRUJ), wrist arthrodesis and arthroplasty, small joint arthrodesis and arthroplasty, and treatment of trigger fingers and carpal tunnel syndrome.

Introduction

Rheumatoid arthritis (RA) is a systemic autoimmune disease that affects 1% of adults (ranging from 0.33% to 6.8%, depending upon the population).¹ Although RA has many diverse clinical manifestations, the single underlying pathologic process is synovial inflammation, which progressively destroys joints and soft tissue leading to deformity and disability. Over the last 20 years, many advances in the medical management of RA have been made. New medications have improved the ability to control rheumatoid inflammation, and can dramatically slow or prevent disease progression.² In spite of these tremendous advances the hand surgeon continues to play a crucial role in treating RA. Many patients continue to suffer from recalcitrant pain or disability despite maximal medical management, and may benefit from surgical intervention.

In addition to RA, there are a number of diverse rheumatologic disorders that commonly affect the hand and wrist. These include systemic lupus erythematosus (SLE), scleroderma, gout, and others. These disorders frequently require surgical intervention.

Basic science/disease process

Etiology

Though much is understood about the pathogenesis of RA, the cause remains idiopathic. That being said, RA is known to have a genetic component. This is demonstrated by the fact that RA has a much higher concurrence rate in monozygotic twins (15–20%) than in dizygotic twins (5%), with susceptibility transferred in an autosomal recessive mode.^{3–5} In addition, there are certain ethnic groups such as the Pima Indians that exhibit a greater incidence of RA than the rest of the population, providing further evidence of a genetic component to RA.⁶

Many studies suggest that a multitude of genes play a role in contributing to susceptibility to RA. These include the class II major histocompatibility complex (MHC) genes and many others. The most well-understood genetic association is with the class II MHC genes, which may contribute up to 40% of the genetic component of RA.⁷ One class II MHC gene in particular, human leukocyte antigen (HLA) DR4 is associated not only with increased risk of disease, but also with increased disease severity.⁴

In addition to genetics, gender influences the development of RA. RA is more common in women than in men, with a ratio of 2:1 to 3:1. Multiple laboratory and clinical studies suggest that hormones, and estrogens in particular, affect the development of RA. However, the exact role of estrogen in the development of RA is not known.⁸

Although the mechanisms are not well understood, the environment plays a role in the etiology of RA as well. Smoking is a risk factor for the development of RA, particularly in




Fig. 19.1 The erosive synovial pannus consists of hypertrophic synovium and inflammatory cells.

susceptible men.⁹ Coffee intake and exposure to silica have also been associated with RA.⁴ In addition, infectious diseases likely act as a trigger in genetically susceptible individuals. Possible triggering agents include mycoplasma, enteric bacteria, Epstein-Barr virus, and other viral and bacterial triggers.¹⁰⁻¹³ In summary, RA is an idiopathic disease, but which is known to have both genetic and environmental components. The genetic susceptibility and environmental triggers are complex and varied, and are not fully understood.

Pathogenesis

The target tissue of RA is the synovium. The disease process begins when an antigen, a trigger for RA, is presented to T-cells within the synovium. A complex interaction between macrophages, B-cells, T-cells, and synoviocytes ensues, orchestrated by systemic inflammatory modulators and local cytokines. The end result is the formation of proliferating inflamed synovium, or pannus (Figs. 19.1 & 19.2). Once

initiated, this process becomes systemic and self-sustaining, and does not require the prolonged presence of the trigger antigen. The synovial pannus produces proteolytic enzymes such as metalloproteinases, serine proteases, cathepsins, and aggrecanases that erode cartilage, bone, and supporting soft-tissue structures. Cytokines secreted by the pannus activate osteoclasts in nearby bone, further contributing to bony erosions and joint destruction.¹⁴⁻¹⁶

Medical management

The medications used to treat RA include non-steroidal anti-inflammatory drugs (NSAIDs), corticosteroids, and disease-modifying anti-rheumatic drugs (DMARDs). In general, a combination of the above medications, with methotrexate as the basis, is used to control symptoms and the underlying disease. NSAIDs do little to affect the course of the disease, and are rarely used in isolation. They are effective, however, in treating symptoms such as joint pain, but must be used judiciously due to their gastrointestinal and renal side effects. Corticosteroids on the other hand are very effective in treating both the symptoms of RA and the underlying disease process. They can be administered systemically or locally, in the form of a joint injection. However, long-term systemic use is associated with substantial morbidity. Because of this, a minimal clinically-effective dose is used. Often, corticosteroids are used briefly to control acute symptoms or flare-ups, and are then tapered as DMARDs begin to work. DMARDs include a diverse array of medications that can be divided into two groups: conventional DMARDs and biologic DMARDs.

The conventional DMARDs include methotrexate, leflunomide (Arava), azathioprine (Imuran), Plaquenil, and gold.¹⁷ Methotrexate is the most commonly administered DMARD because of its effectiveness and favorable side-effect profile. It is generally taken orally once a week, in combination with folic acid in order to minimize side effects such as



Fig. 19.2 Gross appearance of synovial pannus.

hepatotoxicity and bone-marrow suppression. Leflunomide (Arava) is a daily oral pyrimidine antagonist, with side effects that include hepatotoxicity and marrow suppression. Plaque-nil, an antimalarial drug that is effective in the treatment of RA, is taken daily and has few serious side effects. Sulfasalazine is another common daily DMARD, and like many of the other conventional DMARDs it can cause leukopenia. Gold is rarely included in the anti-rheumatic regimen today due to significant side effects and the need for intramuscular injections.

Biologic DMARDs are those that target tumor necrosis factor alpha (TNF- α) and interleukin 1 (IL-1), or the cellular components of the immune system. Etanercept (Enbrel) is an anti-TNF- α that requires once-weekly subcutaneous injections. Infliximab (Remicade) is a TNF- α blocker that is administered every 1–2 months, intravenously. Adalimumab (Humira) is a TNF- α blocker that is injected subcutaneously every two weeks. All three are very effective in treating RA, especially when combined with methotrexate.^{18,19} However, the long-term toxicity of these new medications is unknown, and all three result in an increased susceptibility to infections.²⁰ Anakinra (Kineret) is a biologic DMARD that blocks IL-1 receptors, and requires daily subcutaneous injections. Like the anti-TNF- α biologics, it is associated with an increased susceptibility to infections. Rituximab (Rituxan) is an intravenously administered monoclonal antibody that targets certain B-cells, and lasts from many months up to a year. Abatacept (Orencia) is an antibody that targets T-cells, and requires a monthly intravenous injection.

The surgeon must be aware of the potential toxicities and side effects associated with these medications. The preoperative evaluation of patients on DMARDs should include laboratory panels to screen for hepatotoxicity and bone-marrow suppression. In addition, the surgeon must weigh the risk of increased susceptibility to infection with the benefits of surgery.

The perioperative management of DMARDs and other rheumatoid medications is somewhat controversial and should be coordinated with the patient's rheumatologist. The perioperative cessation of DMARDs or corticosteroids can result in an acute deterioration (rheumatoid flare-up) that is poorly tolerated by the patient. In fact, the flare-up may be so severe that it affects the patient's ability to participate in postoperative rehabilitation.^{21–23} In general, methotrexate should be continued throughout the perioperative period at its normal dose. Methotrexate does not appear to increase infection rates in patients with RA undergoing elective surgery.^{21,22} Furthermore, corticosteroids, when used alone or in combination with methotrexate, do not affect wound infection rates and should not be stopped in the perioperative period.²³ Data on the other conventional DMARDs are more limited, and their perioperative dosing should be discussed with the patient's rheumatologist.

The appropriate perioperative management of biologic DMARDs, particularly the TNF- α inhibitors, is less clear. There are few data and no large studies to guide perioperative dosing of the biologic DMARDs.²² Therefore, a conservative approach is recommended at this time. In general, the TNF- α inhibitors should be held 2–4 weeks before and after surgery.²² Similarly, few data exist regarding the other biologics, and a similar approach is recommended.²⁴

Hints and tips

Perioperative management of anti-rheumatic medications

Medication	Recommendation
Corticosteroids	Continue at normal preoperative dosage. Provide stress-dose at time of surgery if taking >5–10 mg/day, or if recently stopped long-term corticosteroid use.
Methotrexate	Continue at normal preoperative dosage.
Other conventional DMARDs	Discuss with rheumatologist, but in general continue.
Biologic DMARDs	Discuss with rheumatologist, but in general hold for 2–4 weeks before and after surgery.

Diagnosis/presentation

The onset of RA is usually in the 3rd to 6th decade of life. The incidence of RA in young men is one-third that of women, but increases to be equal to that of women by the 6th or 7th decades of life. From the onset, RA tends to affect the hands and wrists. In fact, the metacarpophalangeal (MCP) joints, proximal interphalangeal (PIP) joints, and the wrist are often affected earlier and more frequently than other joints in the body.²

Diagnostic criteria have been described, and are useful in making the diagnosis of RA. They include: (1) morning stiffness = 1 h; (2) soft tissue swelling of three or more joints; (3) soft tissue swelling of hand joints (PIP, MCP, wrist); (4) symmetrical soft tissue swelling; (5) subcutaneous nodules (rheumatoid nodules); (6) seropositivity for rheumatoid factor (RF); and (7) erosions or periarticular osteopenia in hand or wrist joints. Four of the seven criteria should be present for diagnosis, and criteria (1) through (4) must be present for 6 weeks or longer. Morning stiffness or stiffness after rest is common, and may be present for a number of hours, improving with hand use. The most sensitive findings are symmetric arthritis and arthritis of the hand joints. Classic radiographic changes, and the presence of rheumatoid nodules are less sensitive but very specific findings. RF is not only a marker for RA, but also correlates with disease severity.⁴ Although not one of the classification criteria, anti-citrullinated protein antibodies (ACPAs) are very specific for RA, and are useful in confirming the diagnosis.^{4,25} Like RF, ACPA seropositivity also correlates with disease severity.²⁶ In many cases, seropositivity to RF and ACPA develops prior to the onset of clinical disease. It should be noted, however, that some patients with RA will convert to seropositivity after the onset of disease, and some patients with RA will never become seropositive.

RA usually develops in multiple joints slowly over a period of months, although atypical presentations are not unusual.²⁷ In some cases, symptoms can occur rapidly over a few days. When symptoms develop rapidly, the diagnosis of RA is often not considered, and septic arthritis or some other cause of acute-onset joint inflammation is initially suspected. In other

cases, symptoms may involve one or two joints for some time before becoming polyarticular, confounding the diagnosis. Less commonly, some patients develop extra-articular disease (rheumatoid nodules, vasculitis, pericarditis, pleural effusion or interstitial disease, peripheral neuropathy, keratoconjunctivitis sicca, and many others), before synovitis and arthritis are evident.⁴ Palindromic rheumatism is a rare variant of RA, in which symptoms begin in a single joint. Symptoms worsen and spread to other joints for a few days, then disappear in reverse order. Although the disease resolves in some patients, about half eventually develop classic RA.²⁸ Finally, it has been noted that some patients tolerate RA quite well; a presentation termed arthritis robustus. This tends to occur in athletes or heavy laborers who have little pain or disability in spite of severe radiographic changes.

Any joint in the body can be affected by RA, including the articulations of the ossicles of the middle ear.^{29,4} However, joint involvement tends to follow a predictable pattern. Symptoms often begin in the MCP, PIP and wrist joints first, in part due to their high synovium to joint surface area ratio.³⁰ Larger joints like the knees, hips, shoulders and elbows are likely to be affected later in the disease process due to their lower synovium to joint surface area ratio.³¹ Within the hand, the DIP joints are generally spared, possibly because of their relatively small absolute amount of synovium. The synovial lining of tendons is also affected by RA, and can result in a multitude of symptoms, including carpal tunnel syndrome, tendon rupture, tendonitis, and trigger digits.

It should be remembered that RA is a systemic disease with multiple extra-articular manifestations. Rheumatoid nodules, vasculitis, pericarditis, pleural effusion, interstitial pulmonary disease, peripheral neuropathy, and keratoconjunctivitis sicca are some of the more common extra-articular effects of RA. Although rheumatoid nodules are present in only a minority of patients with RA, they are a common reason for presentation to the hand surgeon. Rheumatoid nodules develop secondary to the same autoimmune process that occurs in the joints. They occur most often on extensor surfaces or areas of contact pressure such as the olecranon process. However, they can appear anywhere, including within internal organs such as the lungs, heart, or central nervous system.³²



Fig. 19.3 PA radiograph of the left wrist, demonstrating early involvement of the DRUJ, as well as scattered carpal erosions from invasive synovitis.

Wrist involvement

Within the wrist and distal radioulnar joint (DRUJ), cartilage is degraded and bony erosions develop. Bony erosions occur first at sites of nutrient vessels and at the joint margins because there is no protective cartilage at these locations, thereby giving the invading pannus direct access to the bone.³³ Radiographic changes are first noted at the scaphoid waist, the ulnar styloid and the distal radioulnar joint (DRUJ) (Fig. 19.3).^{34,35} As the arthritis progresses, the radiocarpal joint becomes involved. Bony destruction tends to be more severe at the radiocarpal joint than the mid-carpal joint, although both joints are often involved.³⁶ In late stages, the volar lip of the distal radius becomes severely eroded, allowing proximal migration, volar translation and volar angulation of the lunate, with compensatory mid-carpal extension (Figs. 19.4 & 19.5).^{35,37}

The ligaments of the wrist and DRUJ are affected as well. As the pannus proliferates, it stretches and then directly invades the intrinsic and extrinsic wrist ligaments. Synovitis occurring at the scaphoid waist weakens the radioscapocapitate ligament, leading to ulnar translocation of the carpus (Figs. 19.6 & 19.7).³⁸ Destruction of the scapholunate ligament leads to carpal instability, and further contributes to ulnar translocation of the carpus. At the DRUJ, pannus invades the triangular fibrocartilage complex (TFCC), including the dorsal and palmar radioulnar ligaments, resulting in DRUJ instability and eventually dorsal dislocation of the ulnar head. Pannus also destroys the extensor carpi ulnaris (ECU) subsheath, resulting in volar subluxation of the ECU.^{39,40} The ECU's function as a wrist extensor and ulnar deviator is lost, contributing to supination and radial deviation of the carpus. The combination of dorsal dislocation of the ulnar head, carpal supination and volar subluxation of the ECU is termed the "caput ulnae" (Figs. 19.8 & 19.9).

Hints and tips

Diagnostic criteria for rheumatoid arthritis

Criterion	Details
1. Morning stiffness	1 h
2. Soft-tissue swelling	3 or more joints
3. Soft-tissue swelling	Symmetric
4. Soft-tissue swelling of hand	MCP, PIP, wrist joints
5. Subcutaneous nodules	Rheumatoid nodules
6. Seropositivity	Rheumatoid factor (RF)
7. Typical radiographic findings	Periarticular erosions/ osteopenia, hand or wrist

Four of the seven criteria must be present, and criteria 1–4 must be present for at least 6 weeks.



Fig. 19.4 PA radiograph of the right wrist, demonstrating severe involvement of the wrist.



Fig. 19.6 PA radiograph of the left wrist, demonstrating ulnar translocation of the carpus. Note that the lunate no longer sits in the lunate fossa.

End-stage wrist arthritis falls into three different clinical patterns, depending upon the degree of bony destruction and ligamentous instability.⁴¹ These patterns are: (1) ankylosis; (2) arthritic stable; and (3) arthritic unstable (subdivided into ligamentous unstable and bony unstable). In the ankylosing wrist, the carpus undergoes autofusion. Frequently, ankylosis occurs with the wrist in acceptable alignment, although this is not always the case. In the arthritic stable wrist, the arthritis follows a pattern similar to that of osteoarthritis. Ligamentous



Fig. 19.5 Lateral radiograph of the right wrist, demonstrating destruction of the volar lip of the radius, with volar subluxation of the carpus.



Fig. 19.7 PA radiograph of the right wrist, demonstrating even more severe ulnar translocation, and relative preservation of the mid-carpal joint as compared to the radiocarpal joint.




Fig. 19.8 Caput ulnae, with dorsal dislocation of the ulnar head and carpal supination.



Fig. 19.10 Extensor tenosynovitis protruding from under the extensor retinaculum distally.

destruction is limited, and the wrist remains stable over time. In the unstable wrist, there is progressive malalignment. In the ligamentous unstable wrist, bony destruction is minimal, whereas in the bony unstable wrist, there is severe loss of bone resulting in instability and eventually dislocation.

On the dorsal aspect of the wrist, synovitis develops within the extensor tendon compartments (**Fig. 19.10**). Depending upon the extent of the synovitis, there may be a bulge protruding beyond the distal and proximal margins of the extensor retinaculum, creating an hourglass appearance. Direct invasion of extensor tendons, combined with attritional wear over

sharp bony edges at the ulna and DRUJ can lead to tendon ruptures. The extensor tendons to the small finger are usually affected first. Extensor tendon ruptures often progress radially, eventually affecting all digits. This ulnar to radial progression of extensor tendon ruptures is called the Vaughan-Jackson syndrome (**Fig. 19.11**).⁴² Tendon ruptures are sudden, and may not be painful. They can be difficult to identify in patients with severe deformity, and must be differentiated from volar subluxation of the MCP joint, radial nerve palsy, and extensor tendon subluxation at the MCP joint. On the volar aspect of the wrist, sharp erosions on the scaphoid can result in attritional rupture of the flexor pollicis longus (FPL) tendon, known as a Mannerfelt lesion (**Fig. 19.12**).⁴³ Within the carpal tunnel, synovial pannus and tenosynovitis proliferate, creating a space-occupying lesion that results in carpal tunnel syndrome (**Fig. 19.13**).

Finger and thumb involvement

In the fingers the MCP and PIP joints are primarily affected, with relative sparing of the DIP joints. As cartilage is degraded,



Fig. 19.9 Lateral radiograph of the wrist, demonstrating a dorsally dislocated ulnar head.



Fig. 19.11 Patient with Vaughan-Jackson syndrome, demonstrating extensor tendon ruptures associated with a caput ulnae.




Fig. 19.12 Axial cross-section of the radial side of the wrist, demonstrating the Mannerfelt lesion. Note the proximity of the flexor pollicis longus tendon to the sharp erosion on the volar aspect of the scaphoid.

joint space narrowing is seen. Pannus invades at the margins of the joints, resulting in marginal bony erosions. The joint capsule and collateral ligaments are initially stretched and then directly invaded by the synovial pannus, resulting in instability and deformity.

At the MCP joints, the typical pattern of instability is volar subluxation and ulnar deviation, and is the result of multiple forces.^{44,45} Synovitis at the MCP joint erodes the dorsoradial portion of the joint capsule early in the disease process, creating an early tendency towards ulnar deviation (Fig. 19.14) and volar subluxation (Fig. 19.15).^{46,47} Radial deviation at the wrist creates an ulnar approach of the extensor tendons to the MCP joints, which further contributes to ulnar deviation (Fig. 19.16).⁴⁸ In addition, ulnar deviation forces during oppositional and key pinch stretch the dorsoradial portion of the capsule and the radial collateral ligament, particularly in the index and long fingers.⁴⁹ Finally, continued dorsoradial invasion of the pannus weakens the radial sagittal bands, causing ulnar subluxation of the extensor tendons between the metacarpal heads, which further increases ulnar deviation force on the MCP joints, and weakens extension power at the MCP joints (Fig. 19.17).^{35,50}



Fig. 19.14 Ulnar deviation at the MCP joints (ulnar drift).

One of two patterns of finger deformity can occur: the swan-neck (Fig. 19.18) or boutonniere deformity (Fig. 19.19). Although swan-neck deformity is more common, either deformity can occur and both can occur in the same hand. Swan-neck deformity can originate from pathology at the MCP joint, the PIP joint, or the DIP joint (Fig. 19.20). At the DIP joint the terminal tendon insertion attenuates or erodes, resulting in a mallet finger. This causes an imbalance in the extensor mechanism, with increased extension force at the PIP joint. MCP flexion also contributes to increased pull of the central slip at the PIP joint. When these increased extension forces are combined with synovial disruption of the PIP volar plate, PIP hyperextension occurs, resulting in swan-neck deformity. Swan-neck deformity can originate at the PIP joint



Fig. 19.13 Large proliferative flexor tendon tenosynovitis.



Fig. 19.15 Radiograph of bilateral hands, demonstrating flexion and volar subluxation of the MCP joints.




Fig. 19.16 Radial deviation and ulnar translocation at the wrist contribute to ulnar deviation at the MCP joints.

as well. Pannus stretches and erodes the volar plate and capsule, allowing hyperextension. Flexor tendon rupture may also contribute to a loss of flexion force at the PIP joint. The lateral bands slide dorsally, limiting PIP flexion. DIP joint flexion is a secondary phenomenon in this scenario, and is due to slack in the extensor mechanism combined with tightening of the flexor digitorum profundus (FDP) from PIP hyperextension. MCP pathology can initiate the development of swan-neck deformity as well. Flexed MCP position results in excessive pull through the extensor mechanism. The intrinsics also tighten over time, thereby hyperextending the PIP joint when MCP extension is attempted. The lateral bands also migrate dorsally, contributing to the deformity. The most debilitating result of swan-neck deformities is loss of flexion at the PIP joints, resulting in an inability to flex the fingers for pinching and grasping.

Boutonniere deformities are usually less debilitating than swan-neck deformities, because pinch and grasp are usually preserved. Unlike swan-neck deformities, boutonniere deformities always begin with pathology at the PIP joint ([Fig. 19.21](#)). The initial insult is stretching, erosion, and rupture of




Fig. 19.17 The extensor tendons displace ulnarly and volarly into the space between the metacarpal heads, making them ineffective as MCP extensors, and adding to ulnar deviation force.

the central slip insertion on the base of the middle phalanx. Attenuation of the dorsal capsule, transverse retinacular ligament and triangular ligament allows the lateral bands to sublux volar to the joint axis of rotation, becoming PIP flexors. The volar position of the lateral bands makes them even more effective extensors of the DIP joint, resulting in secondary DIP hyperextension.



Fig. 19.18 Classic swan-neck deformities of all fingers, with MCP flexion, PIP hyperextension, and DIP flexion.



Fig. 19.19 Boutonniere deformity of the right ring and small fingers, and left small finger. Left ring finger demonstrates very early boutonniere deformity.

Synovitis also develops within the flexor tendon sheath, and can lead to triggering or rupture of the flexor tendons. Trigger digits associated with RA are distinct in mechanism and pathology from nonrheumatoid trigger digits, and occur secondary to synovitis or small rheumatoid nodules in the flexor tendon.⁵¹ The specific location of the synovitis or rheumatoid nodules determines the presentation of the rheumatoid trigger finger. A nodule located proximal to the A1 pulley may present like a typical nonrheumatoid trigger finger with locking in flexion, or triggering during extension. A nodule just distal to the A2 pulley can result in the finger locking in extension, or triggering during flexion. Diffuse tenosynovitis or multiple nodules can result in swelling and loss of flexion and extension.^{52,53}

The rheumatoid thumb deformity can be organized into five categories. Type I, the most common, is a boutonniere deformity with MCP flexion, IP hyperextension, and radial abduction of the metacarpal (Fig. 19.22). Deformity begins when synovial pannus at the MCP joint erodes dorsally, attenuating and eventually rupturing the extensor pollicis brevis (EPB) tendon insertion, and displacing the extensor pollicis longus (EPL) ulnarly and volarly. Because of the loss of dorsal capsule and the loss of the EPB, the MCP joint flexes and subluxates volarly. Hyperextension at the IP joint occurs secondarily, and can be exacerbated in patients with an FPL rupture. Type III rheumatoid thumb deformity is a swan-neck deformity, and is the second most common deformity, presenting with MCP hyperextension, IP flexion, and metacarpal adduction contracture. This deformity begins at the carpometacarpal (CMC) joint, with attenuation of the volar beak ligament. As the CMC joint subluxates or dislocates, metacarpal adduction occurs in a similar fashion to nonrheumatoid CMC arthritis. MCP joint hyperextension occurs secondarily as the thumb compensates for the adducted metacarpal, and is exacerbated by volar plate attenuation or erosion from pannus invasion.




Fig. 19.20 (A) Swan-neck deformity originating from a mallet finger, with subsequent increased extension force at the PIP joint. (B) Swan-neck deformity originating at the PIP joint, with volar plate attenuation and possible FDS rupture due to PIP synovitis, and subsequent dorsal subluxation of the lateral bands.




Fig. 19.21 Boutonniere deformity secondary to synovitis at the PIP joint, with attenuation of the central slip, and subsequent volar subluxation of the lateral bands.

Types II, IV, and V are less common, but do occur. Type II rheumatoid thumb includes MCP flexion and IP extension, but unlike a type I boutonniere deformity, there is dislocation or subluxation at the CMC joint. Type IV is a gamekeeper's deformity secondary to synovial pannus destruction of the ulnar collateral ligament. Type V is MCP hyperextension, and compensatory flexion at the IP joint, similar to a swan-neck deformity (type III) but without metacarpal adduction contracture.

Patient selection

Perioperative considerations

Care must be taken during the preoperative workup of RA patients, because many unique problems can impact the safety and timing of surgery. Airway management can be quite difficult. Temporomandibular joint arthritis can limit oral opening, making intubation difficult. Glottic narrowing can also occur due to inflammation or arthritis of the cricoarytenoid joints, creating further difficulty with airway

management.⁵⁴ Atlantoaxial instability is another concern, and is quite common in patients with RA. Flexion of the neck during intubation in patients with significant instability can cause spinal cord injury or death. Therefore, preoperative cervical spine flexion–extension radiographs should be obtained in all rheumatoid patients preoperatively. Fiberoptic intubation with the patient in a cervical collar is recommended in patients with atlantoaxial instability.⁵⁵

Cardiac function can be affected as well. Pericardial effusion, constrictive pericarditis, or conduction block can occur secondary to RA. In addition, RA patients are at increased risk for coronary artery disease. Pulmonary involvement may include rheumatoid nodules, pleural effusion, and interstitial disease. Patients with long-standing disease are at risk for Felty's syndrome, a combination of splenomegaly, neutropenia, and secondary thrombocytopenia. For the above reasons, RA patients undergoing surgery should have a thorough preoperative anesthesia evaluation including an EKG, metabolic panel, complete blood count and differential, chest X-ray, and cervical spine radiographs.

Hints and tips

- Preoperative anesthesia clinic visit for all, regardless of general medical condition
- C-spine radiographs, including lateral flexion and extension views
- 12-lead EKG
- Chest X-rays
- Complete blood count (CBC) with differential
- Metabolic panel



Fig. 19.22 Boutonniere deformity of the thumb.

Goals of surgery

The goals of surgery in RA patients are pain relief, improvement of function, prevention of progression, and improvement of appearance. In general, pain relief can be accomplished reliably by arthrodesis or arthroplasty. Because of this, pain is the primary indication for surgery in the rheumatoid patient. Improvement of function is less reliably accomplished, and

although important, is a secondary indication for surgery. It is important to remember that deformity does not equal loss of function. Many patients have little pain and are able to function quite well in spite of severe deformity. These patients may not benefit from surgery. Slowing the progression of disease is a third priority, and is less often required in the era of effective DMARDs. However, in some situations, surgery is required to prevent progression of disease. For example, a Darrach procedure (resection of the distal ulna) and dorsal tenosynovectomy in the setting of an extensor tendon rupture can prevent or delay additional extensor tendon ruptures. Appearance is considered a last priority. However, aesthetic considerations should not be discounted as these issues are important to RA patients.

Sequence of surgery

In general, proximal problems within the upper extremity should be corrected first, particularly if they affect more distal problems. For example, wrist surgery should be performed prior to finger surgery, because the deformity at the wrist exacerbates the finger deformity. In practice however, the sequence of surgery may be dictated by patient preference. For example, a patient with severe swan-neck deformities and a pain-free but ulnarly subluxated wrist may not accept the idea of wrist surgery before correcting the finger deformity. Another consideration is the mobility of the patient. Many RA patients use crutches or canes for ambulation, or may even be confined to a wheelchair, resulting in a loss of mobility during the recovery period after hand surgery. The surgeon should discuss these issues with the patient preoperatively so that preparations can be made.

Treatment/surgical technique

Operations at the wrist

Wrist synovectomy/dorsal tenosynovectomy

A minority of patients will have persistent wrist synovitis or dorsal tenosynovitis that is painful and unresponsive to at least 6 months of maximal medical treatment. Wrist synovectomy and/or dorsal tenosynovectomy may be effective in improving pain in these patients.^{56,57} Whether this significantly slows the progression of disease is unknown.

A midline longitudinal incision is made over the dorsal wrist, and skin flaps are elevated at the level of the extensor retinaculum, preserving the radial and ulnar sensory nerves that lie within the subcutaneous tissue. If there is a large amount of synovitis, it can be seen deep to the attenuated extensor retinaculum (Fig. 19.23). The extensor retinaculum is incised along the radial border of the first extensor compartment, leaving enough substance intact for later closure. The retinaculum is elevated in an ulnar direction to, but not into the sixth extensor compartment, exposing the extensor tendons. The extensor retinaculum is often very attenuated, and care should be taken to preserve its integrity during elevation. Extensor tenosynovectomy is then performed. Working systematically, each extensor tendon is retracted individually and synovium is excised with curved tenotomy scissors (Fig. 19.24).



Fig. 19.23 Extensor tenosynovitis of the right wrist, with severely attenuated extensor retinaculum.

Clinical tip

- Always be prepared to perform tendon transfers when you are doing a tenosynovectomy.
- Ruptured tendons may be held together by thick pannus and adhesions.
- Be sure to talk to tenosynovectomy patients about the possibility of tendon transfer.

After completing the extensor tenosynovectomy, a posterior interosseous neurectomy may be performed to improve pain relief. The posterior interosseous nerve is identified on the floor of the fourth extensor compartment and a 2-cm segment is excised, with cauterization of the proximal stump.

If painful wrist synovitis is present, a ligament-sparing capsulotomy is made. Synovial pannus is identified at the radiocarpal and mid-carpal joints. With the wrist flexed and distracted, a synovial rongeur is used to remove all synovium




Fig. 19.24 The extensor tenosynovitis has been partially removed. Note the redundancy of the extensor tendons, which have been stretched by the long-standing tenosynovitis.



Fig. 19.25 One retinacular flap (the distal half of the retinaculum) has been placed deep to the extensor tendons to protect them from rough bony surfaces. The other flap (the proximal half of the retinaculum) has been sutured dorsal to the extensor tendons to prevent bow-stringing.

within the radiocarpal and mid-carpal joints. Any sharp edges are smoothed with a curette or rongeur. If DRUJ synovitis is present, a longitudinal incision is made over the DRUJ, in the floor of the fifth extensor compartment. This incision can be extended 90° ulnarly just proximal to the TFCC if necessary for additional exposure. Pronation also improves exposure of the DRUJ. Synovial pannus is removed with a synovial rongeur. Sharp bony edges are smoothed with a rongeur to prevent tendon ruptures. The capsulotomy incisions are closed with 3-0 absorbable suture.

If any rough bony surfaces remain exposed after closure of the capsule, the retinaculum can be divided transversely, creating two ulnarly based retinacular flaps. One flap is sutured deep to the extensor tendons, covering the exposed bony surfaces. The other retinacular flap is closed dorsal to the extensor tendons, leaving the EPL transposed (**Fig. 19.25**). Alternatively, if the ECU tendon is subluxated volarly, the retinaculum can be used to stabilize it. The ECU tendon is synovectomized and relocated to its normal position dorsal to the ulna. Half of the retinacular flap is placed deep to the ECU tendon, then wrapped back dorsally and radially and sutured to itself at the border of the fifth extensor compartment, securing the ECU dorsal to the wrist axis of rotation.

Clinical tips

- In some cases, the extensor retinaculum is attenuated and cannot be used to pad rough surfaces.
- Be sure to have acellular dermal matrix (dermal allograft) available for padding if needed.

Postoperative care

The wrist is immobilized for 2–3 weeks, followed by initiation of motion. If the DRUJ was debrided a sugar-tong splint should be used to prevent forearm rotation. If the wrist or DRUJ is unstable prior to surgery, a longer period of mobilization may be required.

Outcomes, prognosis, and complications

Synovectomy of the wrist or DRUJ usually relieves pain, but recurrence of synovitis is the rule rather than the exception, although the rate at which synovitis recurs is variable. Whether wrist synovectomy significantly alters the course of the disease is not known. Dorsal tenosynovectomy on the other hand likely prevents or delays the occurrence of extensor tendon ruptures.

Secondary procedures

If the patient develops recurrent painful synovitis after wrist joint synovectomy, a definitive wrist procedure such as arthrodesis may be indicated.

Hints and tips

- Allow at least 6 months of maximized medical treatment prior to considering surgery.
- Concomitant PIN neurectomy may improve pain relief.
- Ensure that all rough bony surfaces are smoothed and covered with soft tissue.

Distal ulna resection (Darrach procedure)

Distal ulna resection may be indicated for painful DRUJ instability, painful destruction of the DRUJ, or caput ulna syndrome with extensor tendon ruptures. It can be performed in isolation, but is often combined with extensor tenosynovectomy, extensor tendon repairs or tendon transfers, wrist arthrodesis, or wrist arthroplasty.

If performed in isolation, a 3-cm longitudinally oriented chevron incision is made over the dorsal aspect of the ulnar head (**Fig. 19.26**). If combined with another wrist procedure, skin flaps and retinacular flaps are elevated, and extensor tenosynovectomies are performed as described above. A longitudinal incision is made in the floor of the fifth extensor compartment, with a 90° extension ulnarly just distal to the head of the ulna, and just proximal to the TFCC. Although it



Fig. 19.26 Chevron incision made directly over the ulnar head, with skin flaps elevated and extensor retinaculum exposed.




Fig. 19.27 The DRUJ and ulnar head have been exposed through an incision in the floor of the fifth extensor compartment.



Fig. 19.28 The ulnar head has been removed. The distal end of the stump will be beveled dorsally.

is often destroyed, when the TFCC is present, it should be preserved. The capsule is elevated off the ulnar head, and the ulnar head and neck are dissected subperiosteally with a 15-blade and Freer elevator (**Fig. 19.27**). The ECU is usually subluxed volarly, and is elevated off the ulna during subperiosteal dissection. Hohmann retractors are used to provide exposure of the neck and head of the ulna. Once the ulnar head and neck have been exposed circumferentially, a sagittal saw is used to create a transverse osteotomy at the neck of the ulna, at the level of the proximal margin of the sigmoid notch of the radius. Any remaining soft-tissue attachments are released, and the ulnar head is removed (**Fig. 19.28**). The dorsal edge of the ulnar stump is then beveled with the sagittal saw, and rasped smooth to prevent tendon abrasion and rupture. Any remaining synovial pannus can now be easily accessed, and is debrided with a synovial rongeur.

Prior to closure, the ulnar stump should be stabilized and the normal relationship between the ulna and the carpus should be re-established or improved. The pronator quadratus is elevated subperiosteally from the volar aspect of the ulna, leaving its attachment to the radius intact. It is important to keep the periosteum attached to the pronator quadratus. It is then delivered through the interosseous space and draped dorsally over the ulnar stump. The ulna is reduced volarly. While maintaining the ulnar stump in reduction, the pronator quadratus and its periosteum are sutured securely to the dorsal aspect of the ulnar stump, using bone anchors if necessary (**Fig. 19.29**). In this position, the pronator quadratus serves as a buffer against impingement between the radius and ulna, and also helps prevent dorsal subluxation of the ulna.

Alternatively, a distally based slip of the ECU is elevated. The DRUJ capsule and periosteal flaps are closed with




Fig. 19.29 The pronator quadratus is released from the volar aspect of the ulna, passed through the interosseous space, and sutured to the dorsal aspect of the ulna.




Fig. 19.30 Distally based slip of ECU is used to stabilize the ulnar stump.

non-absorbable sutures, and are imbricated tightly with the ulna reduced volarly. The slip of ECU is then woven through the capsule at the distal end of the ulna, and is then sutured to the dorsal ulnar aspect of the radius. This sling helps stabilize the ulnar stump, and also reduces carpal supination (Fig. 19.30). Pre- and postoperative radiographs are shown in Fig. 19.31.

Postoperative care

The patient is placed in a sugar-tong splint in supination for 2–3 weeks prior to allowing wrist motion and forearm rotation. If a tendon transfer is done, the patient should be splinted for 4 weeks.



Fig. 19.31 Pre- and postoperative radiographs demonstrating resection of the ulnar head.

Outcomes, prognosis, and complications

One potential complication after distal ulna resection is extensor tendon rupture due to attrition over the sharp dorsal edge of the osteotomy. This is prevented by beveling and rasping down the dorsal edge of the osteotomy, and by performing a soft tissue stabilizing procedure at the time of the Darrach procedure, in order to minimize dorsal subluxation of the ulnar stump. Another potential complication is painful radio-ulnar convergence and impingement, which tends to occur during loading. Again, stabilization and/or padding of the distal ulna at the time of Darrach procedure as described above helps to minimize this.

Secondary procedures

Persistent painful instability or radio-ulnar impingement may be treated with a soft-tissue stabilization procedure using the ECU as described above. Alternatively, ulnar head implant arthroplasty may be considered to salvage the failed Darrach complicated by painful radio-ulnar impingement.

Hints and tips

- Create a dorsal bevel after making the transverse osteotomy, and smooth with a rasp to prevent attrition ruptures.
- Distal ulna resection should be performed at the time of extensor tendon transfers if the distal ulna was the source of extensor tendon rupture.
- A stabilizing procedure should be performed to decrease recurrent dorsal subluxation, minimize radioulnar convergence, and reduce carpal subluxation.




Fig. 19.32 Bilateral wrist radiographs demonstrating severe involvement of the radio-carpal joint, and relative sparing of the mid-carpal joint.

Partial wrist arthrodesis (radioscapholunate arthrodesis)

In some rheumatoid wrists, the radiocarpal joint becomes arthritic with relative preservation of the mid-carpal joint (Fig. 19.32). In these patients, radioscapholunate arthrodesis may be indicated to treat refractory pain secondary to radiocarpal arthritis. Patients should understand that they will lose approximately 60% of wrist flexion–extension, depending upon the quality of the mid-carpal joint. In addition, patients should be consented for the possibility of complete wrist arthrodesis if the mid-carpal joint is found to be substantially arthritic at the time of surgery.

The skin and retinacular incisions are the same as described above. Extensor tenosynovectomies are performed if required, and a posterior interosseous neurectomy is performed. An H-shaped capsulotomy is made, exposing the radiocarpal and mid-carpal joints. Radiocarpal and mid-carpal synovectomies are performed. The quality of the mid-carpal joint is assessed, and the decision to proceed with radiocarpal fusion versus complete wrist fusion is made. The radiocarpal joint is assessed as well. In some cases, the radioscaphoid articulation is preserved, allowing the surgeon to perform a radiolunate fusion, although in most instances the entire radiocarpal joint is arthritic. With the wrist flexed and distracted, a rongeur is used to remove the remaining articular cartilage and subchondral bone from the distal radius and the proximal articular surfaces of the lunate and scaphoid. The articular surfaces are prepared in this manner until bleeding cancellous bone is encountered. During joint surface preparation, the matching concave–convex surfaces of the radiocarpal joint should be preserved. The carpus is then reduced by maneuvering the lunate into neutral flexion–extension, correcting any scapholunate gap, and correcting ulnar translocation if present. The use of 0.062-inch K-wires as joysticks may be necessary for reduction. The scaphoid and lunate are temporarily held in reduction with 0.062-inch radiocarpal K-wires, and a mini c-arm is used to confirm carpal alignment. Next, the distal pole of the scaphoid is resected in order to improve

mid-carpal motion. A transverse osteotomy is made at the proximal margin of the distal pole of the scaphoid using a reciprocating saw. The distal pole is then removed piece-meal with a rongeur.

Autologous cancellous bone graft is packed into the fusion site. This should be obtained from the iliac crest, or from the resected distal pole of the scaphoid and from the distal ulna if a Darrach procedure has been performed. Bone graft should not be harvested from the distal radius, as this reduces the stability of the radioscapholunate fixation. Fixation is achieved with headless compression screws that are inserted into the dorsal aspect of the distal radius, and driven distally and volarly into the scaphoid and lunate. Three or four compression screws are used, with two passing from the radius into the scaphoid, and one or two passing from the radius into the lunate (Fig. 19.33). It is usually necessary to back out the temporary fixation K-wires in order to achieve compression. In addition, in order to achieve even compression when two screws are placed across one articulation, the screws should be simultaneously advanced. After screw placement, final c-arm views are used to confirm carpal alignment and screw position. The mid-carpal joint is directly examined to ensure that there is no screw penetration. If there is any concern about the stability of the fixation, supplemental K-wires can be placed. If the bone quality is too poor to support compression screws, as it often is in patients with rheumatoid arthritis, fixation can be performed with K-wires alone (Fig. 19.34). Other alternatives for fixation include staples or a T-shaped plate. The capsule is closed and the extensor retinaculum is closed with the EPL transposed.




Fig. 19.33 Radiocarpal arthrodesis, with compression screws. The distal pole of the scaphoid is resected to preserve mid-carpal motion. Triquetrum excision is optional.




Fig. 19.34 Radiocarpal arthrodesis with K-wires.

Postoperative care

The wrist is immobilized until bony union occurs. Active and passive range of motion and strengthening exercises are initiated after bony union occurs.

Complete wrist arthrodesis

Complete wrist arthrodesis is an effective treatment for the painful and unstable wrist. However, the loss of wrist motion after complete arthrodesis can cause significant functional difficulty, particularly if the patient has a stiff contralateral wrist. Because of this, it should be reserved for patients with recalcitrant pain or debilitating instability or malalignment, in spite of maximum medical management, steroid injections, and wrist splinting.

In patients with high quality bone, a dorsal wrist fusion plate or headless compression screws can be used (Figs. 19.35 & 19.36). However, if bone quality is poor, Steinmann pin fixation may be performed.^{58,59} The wrist is exposed as described above for radioscapulohumeral fusion. If indicated, a Darrach procedure is performed as described above. The radio carpal and mid-carpal joints are exposed. With the wrist flexed and distracted, a synovial rongeur is used to debride synovial pannus, allowing access to the articular surfaces. A rongeur is then used to remove articular cartilage and subchondral bone from the opposing articular surfaces, until bleeding cancellous bone is encountered (Fig. 19.37). A small Steinmann pin is drilled retrograde into the radius in order to create a track for the final Steinmann pin. The starting point on the radius is chosen carefully, in order to allow the Steinmann pin to pass directly into the isthmus of the medullary canal without any angulation. The correct starting point is usually in the dorsal half of the radius articular surface, and near the interval between the scaphoid and lunate fossae. Fluoroscopy is used



Fig. 19.35 Wrist arthrodesis with fusion plate. Use of a plate and screws is limited to patients with good bone quality.

to confirm the position of the Steinmann pin. The small Steinmann pin is removed and exchanged for the largest diameter Steinmann pin that will fit into the medullary canal of the radius. The large Steinmann pin is removed from the radius and then it is drilled antegrade through the carpus, exiting the carpus at the 2nd or 3rd intermetacarpal space, and exiting the skin between the MCP joints. With the radius and carpus reduced, the Steinmann pin is tapped retrograde back into the radius, and through the isthmus of the medullary canal (Fig. 19.38). It is cut distally at the skin, and then tapped 2–3 cm proximal to the level of the skin. If necessary, additional fixation with temporary K-wires can be used. Cancellous autograft is packed into the radiocarpal and mid-carpal joints. The



Fig. 19.36 Wrist arthrodesis with headless compression screws in a patient with good bone quality.




Fig. 19.37 Shaded areas represent the articulations that should be prepared for a complete wrist arthrodesis.

capsule is closed with 3-0 absorbable sutures, and the retinaculum and skin are closed as described above. The wrist is immobilized until union occurs.

An alternative is to use two smaller Steinmann pins. The technique is similar to that described above, except that one pin passes through the second intermetacarpal space, and one passes through the third intermetacarpal space. An oblique K-wire can be added to augment the fixation. The pins are cut deep to the skin, and can be removed after bony union is achieved (Figs. 19.39 & 19.40). If future MCP arthroplasty is planned, and there is no reason to preserve the articular surface of the metacarpal head, one pin can be advanced through the medullary canal of the long finger metacarpal, exiting the metacarpal head distally, and then tapped proximally into the radius after reduction. If a Steinmann pin is placed in the medullary canal of the long finger metacarpal, it should be tapped proximally to allow enough room for future MCP arthroplasty (Figs. 19.41 & 19.42). As noted above, in patients with high quality bone, a dorsal wrist fusion plate can be used. These plates allow compression across the wrist, and result in very stable fixation.

Postoperative care

The wrist is immobilized until bony union occurs.

Outcomes, prognosis, and complications

Limited or complete wrist arthrodesis reliably treats pain in RA when used for appropriate indications. Although the complication rate is less than that for total wrist arthroplasty, minor complications such as delayed skin healing, prominent hardware, tendon irritation, neuropathia, and pin-site issues

are not uncommon. Potential major complications include infection, loss of fixation, and nonunion. A deep infection requires hardware removal, serial debridement, and intravenous antibiotics. Nonunion, if it occurs, may or may not be symptomatic.

Secondary procedures

In some cases prominent hardware requires removal. Unless there is an indication for more urgent removal, this should be delayed for a year after union is achieved. After hardware removal, the wrist should be protected in a splint or cast for a minimum of 6 weeks.




Fig. 19.38 Wrist arthrodesis with a single Steinmann pin. The pin exits the carpus in the second intermetacarpal space, and is cut just below the skin for later removal. The oblique K-wire is optional.




Fig. 19.39 Wrist arthrodesis with two Steinmann pins. The pins exit the carpus in the second and third intermetacarpal spaces, and are cut just below the skin for later removal.




Fig. 19.41 Wrist arthrodesis with a single Steinmann pin placed in the medullary canal of the long finger metacarpal. Note that the length of the Steinmann pin should not prohibit future MCP arthroplasty.




Fig. 19.40 Wrist arthrodesis with two longitudinal Steinmann pins, and a third oblique pin for added fixation.

Hints and tips

- Resection of all cartilage and subchondral bone, with exposure of bleeding cancellous bone, is critical in order to achieve union.
- Compression screw or plate and screw fixation should be used only if bone quality is good, otherwise K-wires or Steinmann pins may be used for fixation.
- Assessment of bony union may be difficult with plain radiographs. In this situation, computed tomography (CT scan) is ideal for confirming union.




Fig. 19.42 PA and lateral radiographs demonstrating wrist arthrodesis performed with a single intramedullary pin. Note the large caliber of pin required to fill the medullary canal of the radius.

Total wrist arthroplasty

Total wrist arthroplasty is effective at relieving pain in patients with rheumatoid wrist arthritis. However, in spite of recent advances, wrist arthroplasty is associated with a high complication rate. In order to minimize complications such as loosening, migration, and dislocation, wrist arthroplasty should only be performed in patients who place low demands on their wrists. In addition, arthroplasty is only indicated in wrists with good bone stock that will support an implant. Furthermore, the patient must have functioning wrist flexors and extensors to benefit maximally from wrist arthroplasty. It is important to discuss complications such as infection, loosening, migration and dislocation with the patient, as well as the postoperative rehabilitation and long-term limitations that will be placed on wrist use. A number of implant designs are available worldwide. The most commonly used implants consist of cobalt chrome metal components, often with titanium plasma spray on the stems to improve osseointegration, and ultra-high molecular weight polyethylene on metal articulations. Because wrist implants are continually modified and refined, the details of the surgical technique change and the implant manufacturer's specific recommendations should be followed. The general steps of the operation are described below.

The dorsal wrist capsule is exposed as described above (Fig. 19.43). A distally based U-shaped capsulotomy is created, leaving a cuff of capsule on the radius for closure (Fig. 19.44). Radiocarpal and mid-carpal synovectomies are performed. A transverse carpal osteotomy is made, removing 2 mm of the head of the capitate, the proximal pole of the hamate, the proximal half of the scaphoid, and the entire triquetrum and lunate. With the wrist flexed, the surface of the radius is prepared using a guide and a burr or saw (Fig. 19.45). Next, a guide-wire is drilled into the radius. It should be in line with the medullary canal, with a starting point about 2–3 mm volar to the dorsal lip of the radius and near the interfossal ridge.



Fig. 19.43 A radially based retinacular flap has been elevated, exposing the extensor tendons. Synovectomy is being performed.



Fig. 19.44 A wrist capsulotomy has been made. The capsulotomy is U-shaped, and is distally based, providing full exposure of the wrist joint.

The distal radius is then sequentially broached, keeping the broach aligned with the medullary canal. After broaching, the radial trial component is placed and impacted. If it is proud, further broaching or burring of the radius may be required. Next, the radial trial is removed, and the carpus is prepared. This step varies depending upon the implant used. After



Fig. 19.45 An osteotomy has been made at the distal end of the radius. Note the saw-guide held in place with two K-wires.




Fig. 19.46 The radial and carpal components have been seated, and the joint reduced. Final position of the implant.

preparing the carpus, a trial reduction is performed with both the radial and carpal trial components. Articulation and range of motion are checked. Trials are removed, the wound is copiously irrigated, fresh towels are placed, and gloves are changed. The radial implant is placed first and impacted, and its position checked with fluoroscopy. Next, the carpal component(s) is placed and impacted, and the joint reduced (Fig. 19.46). Hardware position and alignment are checked with fluoroscopy (Fig. 19.47). Depending upon the implant design, carpal screws may be placed. Joint stability and ROM are checked, and final X-rays are taken. The tourniquet is let down, hemostasis is achieved, and the retinaculum is closed with the EPL transposed.

Postoperative care

The patient is splinted in 30° of extension for 2 weeks. ROM begins at 2 weeks under the guidance of a therapist, and protection of a removable splint for the next 6–8 weeks. Strengthening begins at 4–6 weeks. Patients are given a 20-lb lifting restriction, and sports and other heavy activities are prohibited. It is crucial for the patient to take preoperative antibiotics before dental, urologic, and gastrointestinal procedures, etc.



Fig. 19.47 PA and lateral radiographs demonstrating good position and alignment of the prosthesis.

Outcomes, prognosis, and complications

Total wrist arthroplasty effectively relieves wrist pain. However, the surgeon and patient are accepting a higher complication rate in order to preserve wrist motion. Major complications include implant instability or dislocation, migration, infection, fracture, loss of alignment, and persistent pain.

Secondary procedures

Although revision arthroplasty may be attempted, failed total wrist arthroplasty is most reliably treated with complete wrist arthrodesis. Wrist arthrodesis after failed total wrist arthroplasty is not straightforward, due to scarring and loss of bone stock. Difficulty with fixation and delayed union are not uncommon.

Hints and tips

- Total wrist arthroplasty is a “high risk–high reward” operation. The patient is accepting a relatively high complication rate for the chance to preserve wrist motion.
- The patient must be aware of lifetime limitations on upper extremity use.
- The patient must be instructed in taking antibiotics prior to dental, urologic, GI, and other invasive procedures or surgeries after total wrist arthroplasty.

Operations for the hand and fingers

MCP synovectomy and soft tissue reconstruction

Synovectomy and soft-tissue reconstruction of the MCP joints is a temporizing operation, and synovitis and deformity usually recur. It is only indicated in patients with persistent synovitis that does not respond to at least 6 months of maximum nonoperative management who have radiographically intact joints, correctable deformities, and substantial dysfunction. Patients with adequate function should not undergo MCP synovectomy and soft-tissue reconstruction, regardless of the presence of synovitis or deformity.

A transverse incision is made over the dorsal aspect of the MCP joints. Dissection is carried down to the extensor mechanism over each joint, using longitudinal spreading to protect the dorsal veins and sensory nerves. Often, the extensor tendon has subluxated ulnarly, and there may be attenuation or destruction of the radial sagittal band. The ulnar sagittal band is incised longitudinally, adjacent to the extensor tendon. A 15-blade is then used to separate the extensor mechanism from the underlying joint capsule. The capsule, which is usually very thin, is then incised transversely with a 15-blade, exposing the MCP joint. Synovial pannus is removed with a curette or small synovial rongeur. (It should be noted that PIP synovectomy can be performed as well for painful synovitis that is unresponsive to medical management, as demonstrated in Figs. 19.48 and 19.49).

The finger is checked for intrinsic tightness. The PIP joint is passively flexed while the MCP joint is alternately held in flexion, and then hyperextension. Increased resistance to PIP flexion when the MCP is held in hyperextension indicates



Fig. 19.48 A slightly curved incision has been made over the dorsal aspect of the PIP joint, and skin flaps have been elevated. The synovial pannus can be seen protruding ulnar to the central slip.



Fig. 19.49 Excision of the synovial pannus, working in a proximal to distal direction.

intrinsic tightness. In addition, ulnar sided intrinsic tightness is evaluated by testing the PIP joint with the MCP ulnarly versus radially deviated. If intrinsic tightness is present, an ulnar intrinsic release and cross-intrinsic transfer are performed.

On both sides of the finger, the soft tissue is elevated off the lateral bands using tenotomy scissors. The ulnar lateral band is divided distally and freed proximally to the musculotendinous junction. It is then transferred to the radial lateral band of the adjacent finger and secured with a modified Pulvertaft weave (**Fig. 19.50**). The cross-intrinsic transfer should be tensioned with the finger in neutral alignment. In the small finger the abductor digiti minimi is released with a 15-blade at its musculotendinous junction. Finally, the extensor tendons are mobilized radially and relocated centrally over the MCP joints. The radial sagittal band of each joint is imbricated. The MCP joints are then passively ranged. If the extensor mechanism tends to re-subluxate, or if the radial

sagittal band reconstruction is not secure, the extensor tendon should be sutured directly to the underlying joint capsule at the base of the proximal phalanx.

Postoperative care

A splint is applied with the MCP joints extended and in neutral radio-ulnar alignment. Active ROM in a dynamic MCP extension splint is begun once pain and edema have improved. A resting splint that holds the MCPs extended and in neutral alignment should be worn at night and at other times. Splinting can be weaned after 6–8 weeks, although night-time splinting may be continued indefinitely.

Outcomes, prognosis, and complications

Recurrence of synovitis and deformity should be expected over time. **Fig. 19.51** demonstrates a patient before and 1.5 years after MCP synovectomy and cross-intrinsic transfer.




Fig. 19.50 The ulnar lateral bands of the index, long and ring fingers are divided distally, and transferred to the radial lateral bands of the adjacent long, ring, and small fingers. The abductor digiti minimi of the small finger is divided.



Fig. 19.51 Preoperative (above) and postoperative (below) views of both hands after cross-intrinsic transfers.

Secondary procedures

Recurrent synovitis and deformity that are painful or adversely affect hand use are indications for arthroplasty.

MCP arthroplasty (silicone)

MCP arthroplasty is indicated in patients who have pain or substantial loss of function due to MCP deformity and arthritis (Video 19.2 [▶](#)). If the patient has reasonable hand function without pain, arthroplasty is not indicated regardless of the degree of deformity. PyroCarbon implants or surface replacement arthroplasty (SRA) implants can be used in rheumatoid patients in certain situations (Figs. 19.52 & 19.53). However, because of the soft-tissue laxity and joint instability associated with RA, silicone arthroplasty is generally preferred



Fig. 19.52 Index and long MCP arthroplasties with PyroCarbon implants. The use of PyroCarbon implants should be limited to patients without soft-tissue instability.



Fig. 19.53 MCP arthroplasty with surface replacement implant. The proximal component is made of cobalt-chrome, and the distal radiolucent component is made of ultra-high-molecular-weight polyethylene (UHMWPE).

(Fig. 19.54). A silicone implant acts as a spacer and internal mold that becomes encapsulated, and thereby provides some degree of alignment stability. A number of silicone MCP implants are commercially available. Although there are some minor differences in design, the surgical techniques are similar.

A transverse incision is made across the dorsal aspect of the MCP joints. If only one joint is undergoing arthroplasty, a longitudinal incision can be used. The extensor mechanism is exposed as described above. Because of the alignment of the fingers, arthroplasty is performed at the index finger and




Fig. 19.54 MCP arthroplasty with a silicone implant. The implant is relatively radiolucent, but the broached regions of the metacarpal and proximal phalanx that are occupied by the stems of the implant are visible on radiographs. The barrel of the implant which serves as a spacer between the two bones can be seen.

progresses ulnarly. A longitudinal incision is made in the ulnar sagittal band adjacent to the extensor tendon. The extensor mechanism is elevated off the joint capsule, and the extensor tendon is retracted radially. If intrinsic tightness is contributing to ulnar deviation, an ulnar intrinsic release can be performed as described above. The capsule is incised longitudinally with a 15-blade and synovectomy is performed. The ulnar collateral ligament is released by separating its proximal insertion from the lateral aspect of the metacarpal head. If possible, the radial collateral ligament is preserved. The MCP joint is then maximally flexed, exposing the metacarpal head. A starter awl is used to open the medullary canals of the metacarpal and proximal phalanx, and fluoroscopy is used to confirm appropriate alignment (Fig. 19.55). In order to center the awl in the medullary canal, the entrance point should be in the dorsal third of the articular surface (Fig. 19.56). A transverse osteotomy is made in the metacarpal head

just distal to the insertion of the collateral ligaments. The proximal phalanx is then brought into extension, and a transverse osteotomy is created at the proximal phalanx base, resecting only articular cartilage and subchondral bone (Fig. 19.57). Conservative osteotomies should be made initially, as more bone can be resected later if necessary. The medullary canals of the metacarpal and proximal phalanx are broached sequentially until an appropriately sized implant can be placed (Fig. 19.58). Trials are used to select an implant that matches the diameter of the medullary canals and covers the entire exposed bony surface, but that does not overhang. When broaching the medullary canals, the broach should be oriented in such a way as to minimize the rheumatoid deformity. For example, in the index finger, the rectangular broach should be positioned high on the dorsal ulnar side of the base of the proximal phalanx, and low on the radial palmar side. This helps bring the finger into supination when the implant is placed, and prevents pronation deformity. The small finger broaching should be done in the opposite manner to prevent supination deformity. After broaching is completed, a rasp is used to smooth all cortical surfaces that may come in contact with the implant. The trial is then placed and the joint is reduced (Fig. 19.59). The transverse barrel should seat against both osteotomy sites, but should not be compressed. The joint is then passively ranged. If the implant is compressed during extension, further bone resection is required. There should be no bony impingement with flexion and extension. The trial is removed, and the wound is copiously irrigated. Using fresh powder-free gloves, the final silicone implant is placed. The radial collateral ligament is imbricated using 3-0 Ethibond sutures. If release of the radial collateral ligament was required, it must be sutured back to the periosteum or to bone holes created prior to implant placement. The capsule is closed, and the radial sagittal band is imbricated, centralizing the extensor tendon. A cross intrinsic transfer may be performed as described above.

Of note, some patients with severe MCP disease are poor candidates for implant arthroplasty. For example, longstanding volar MCP subluxation or dislocation can result in erosion and remodeling of the base of the proximal phalanx to the extent that it cannot accommodate the stem of an implant. In these patients, a volar plate interposition arthroplasty is a reasonable alternative. The volar plate is released palmarly from its origin on the metacarpal through a separate palmar incision, while maintaining the attachment to the base of the proximal phalanx. The metacarpal head is resected as for implant arthroplasty through a dorsal approach. The joint is reduced, and the proximal end of the volar plate is anchored to the dorsal cortex of the metacarpal. The volar plate serves two purposes, acting as interposed soft tissue, and also suspending the base of the proximal phalanx to resist recurrent palmar subluxation.

Clinical tip

- When performing an MCP arthroplasty, if the dorsal base of the proximal phalanx is too eroded to support an implant, a volar plate arthroplasty should be performed. This will interpose soft tissue into the arthroplasty space, and suspend the proximal phalanx.




Fig. 19.55 A starter awl is used to open the subchondral bone at the head of the metacarpal and at the base of the proximal phalanx, in order to gain access to the medullary canal.

Postoperative care

Postoperatively, the wrist is splinted in 20° of extension, and the MCPs are splinted in extension and slight radial deviation. The IP joints are left free. Once edema and pain have improved, active motion with the guidance of a therapist is initiated. The patient wears an MCP extension splint in between exercises, and a dynamic MCP extension splint may be used for exercises if needed. Modifications of splinting position are frequently required, depending on the severity of the preoperative deformity, and on patient progress after surgery. Splinting is weaned at 6 weeks.

PIP arthroplasty

PIP arthroplasty can effectively relieve pain and improve alignment, while preserving joint mobility in patients with PIP arthritis. However, PIP arthroplasty is less reliable than MCP arthroplasty in terms of stability and correction of deformity. PIP arthroplasty should therefore be avoided in the index finger, which must resist strong ulnar deviation forces during pinch. It is most effective in patients with pain due to arthritis, who have relatively good soft tissue.

The procedure is similar to that for MCP arthroplasty described above. A dorsal longitudinal incision is made over the PIP joint, and skin flaps are elevated at the level of the extensor mechanism. The central slip is divided longitudinally from the mid-portion of the proximal phalanx to the central slip insertion, without disrupting the central slip insertion. The joint is flexed and a transverse capsulotomy is made. The

collateral ligaments should be preserved if possible. If collateral ligament recession is required for adequate exposure of the joint, the collateral ligaments are repaired prior to skin closure. A transverse osteotomy is made in the head of the proximal phalanx just distal to the collateral ligament insertion. An osteotomy is not required at the base of the middle phalanx, but osteophytes should be removed and the articular surface smoothed. Bony resection should be conservative, and further resection can be performed later if required. A starter awl is used to open the medullary canals, and fluoroscopy is used to confirm correct alignment. Broaches are then used to sequentially broach up the medullary canals of the proximal and middle phalanges. Trials are used to select the appropriate implant size as described above. The appropriately sized trial is placed, the joint is reduced and ranged, and checked for instability or impingement. If required, further bony resection and re-broaching is performed. The trial is removed and bone edges are smoothed. The wound is copiously irrigated, gloves are changed, and the final implants are inserted. If required, the central slip and collateral ligaments are reattached to bone using sutures passed through bone holes drilled with a Kirschner wire. The bone holes should be created and the sutures passed prior to placing the final implant. The divided central slip is approximated with absorbable sutures, and the skin is closed.

Postoperative care

Patients begin motion postoperatively, as soon as edema and pain are improved. Splinting is continued for at least 6 weeks postoperatively. The position and type of splinting required vary substantially, depending upon the preoperative deformity and patient's postoperative progress.

Outcomes, prognosis, and complications

Although the outcomes reported in the literature are variable, silicone MCP arthroplasty has been demonstrated in multiple studies to effectively treat pain, correct ulnar drift, improve



Fig. 19.56 In order to be in line with axis of the medullary canal, the starting point should be created at the junction of the middle and dorsal third of the articular surface.




Fig. 19.57 A sagittal saw is used to create osteotomies of the metacarpal head and base of proximal phalanx. Conservative osteotomies should be made at first, and revised if needed. The collateral ligaments should be preserved if possible.

MCP joint arc of motion, and improve appearance. These effects are often maintained for years, although slow deterioration usually occurs. At the PIP joint, arthroplasty typically relieves pain, but is not as effective at correcting deformity or improving motion. Potential complications include recurrence of deformity, extension lag or loss of flexion, fracture of silicone implant, dislocation of implant, silicone synovitis, and infection. Recurrence may be due to soft tissue changes, implant fracture, or inappropriate positioning of implant.

Secondary procedures

Revision arthroplasty after implant failure is possible, but should be reserved for patients with loss of hand function that is directly correlated to the failure of the implant. Often, overall upper extremity function is decreased not because of implant failure, but because of ongoing changes at the wrist, elbow, or shoulder. Furthermore, a fractured implant often

continues to function as a spacer, and the patient may not notice a change in joint function. When revision arthroplasty is performed, it is important to correct any issues that may have contributed to implant failure, such as soft tissue deforming forces, sharp bony edges, or inadequate bone resection.

Hints and tips

- Pyrolytic carbon or other surface replacement arthroplasties should be reserved for patients with stable joints and normal ligaments and soft tissue.
- Most RA patients who require MCP or PIP arthroplasty should have silicone rather than surface replacement arthroplasty.
- The surgeon should start with conservative osteotomies and broaching. More bone can always be resected if needed.




Fig. 19.58 The medullary canals are sequentially broached.

MCP and IP arthrodesis

Arthrodesis of the MCP or IP joints is a reliable method for treating refractory pain due to arthritis. Although motion is sacrificed, the complication rate of arthrodesis is less than that of arthroplasty, making it an attractive option in some clinical situations. Arthrodesis is most commonly indicated at the index or long finger PIP joint, where the ability to resist strong ulnar deviation forces during pinch is crucial.

The joint is exposed as described above for arthroplasty. The collateral ligaments can be divided in order to improve joint exposure. With the joint flexed, a rongeur is used to remove all articular cartilage and subchondral bone from the opposing articular surfaces, creating flat opposing cancellous surfaces. The flat cancellous surfaces must be created in such

a way that when they are apposed, there is full contact between the two surfaces with the joint in the desired amount of flexion, without radial or ulnar deviation. Next, two parallel 0.035 or 0.045-inch K-wires are drilled across the joint, entering the cortical bone dorsally at least 1 cm proximal to the arthrodesis site, and angled volarly into the medullary canal of the distal bone. The K-wires should be advanced until they enter cortical or subchondral bone distal to the osteotomy site. Next, a 0.045-inch K-wire is used to create a transverse hole in the distal bone, 1 cm distal to the arthrodesis site. A 24-gauge stainless steel wire is passed through the transverse hole in the distal bone. Both ends of the wire are then turned proximally, crossed over the dorsal aspect of the arthrodesis site and wrapped around the K-wires, creating a figure-of-eight (Figs. 19.60 & 19.61). The free ends are twisted down




Fig. 19.59 Final position of the implant.




Fig. 19.60 K-wire and stainless steel wire configuration for tension band arthrodesis of the PIP joint.

with a needle driver until strong compression is achieved. The excess wire is then cut and bent down against the bone. The two K-wires are retracted 2 mm proximally, bent 90° and cut, and then tapped back in to prevent a sharp protruding K-wire. The extensor mechanism is repaired, and the skin is closed. For the DIP joint, because fusion in a flexed position is not necessary, a headless compression screw provides effective fixation ([Fig. 19.62](#)).

Postoperative care

Light active finger motion is allowed immediately and a splint is worn for comfort only. Heavy activity is allowed after union is achieved.



Fig. 19.61 Lateral radiograph of a thumb MCP arthrodesis with tension band.



Fig. 19.62 PA views of DIP joint arthrodesis with headless compression screws.

Outcomes, prognosis, and complications

MCP or PIP arthrodesis effectively relieves pain at the expense of motion. Often, the severely arthritic and painful joint has little motion prior to surgery, and in many cases hand function is improved rather than worsened after arthrodesis. Although the complication rate is lower than that of arthroplasty, complications are not unusual, and may include delayed union or nonunion, infection, skin flap compromise, and hardware-related problems such as loss of fixation, palpability, and tendon irritation.

Correction of swan-neck deformity

Swan-neck deformity is more debilitating than boutonniere deformity because the fingers cannot be flexed into the palm for grasping objects. Swan-neck deformity can be divided into four types, based upon the degree joint mobility and arthritic changes. In a finger with type I deformity, full active PIP flexion is preserved, there is no intrinsic tightness, and patients have little if any functional problems. In a finger with type II deformity, intrinsic tightness is present. With the MCP in ulnar deviation and flexion, PIP flexion is possible. However, if the MCP deformity is corrected by placing it in extension and correcting ulnar deviation, the ulnar intrinsics are tightened, and PIP flexion becomes more difficult. Fingers with type III deformity have more severe intrinsic tightness, and PIP flexion is difficult or impossible regardless of MCP position. In the type IV deformity substantial arthritic changes are present.

In type I deformities, a silver ring splint that prevents PIP hyperextension, while at the same time allowing PIP flexion, is adequate treatment. For type II deformities an intrinsic release and a PIP extension block are required. A Bruner incision is made over the PIP joint and the flexor tendon sheath is exposed. The ulnar intrinsics are exposed through the volar incision and are released as described above. A transverse incision is then made in the midportion of the A2 pulley. One slip of flexor digitorum superficialis (FDS) is transected with tenotomy scissors as proximally as possible. The transected end which remains attached distally at the FDS insertion is passed through the slit in the A2 pulley, and turned distally. It is then sutured to itself near the FDS insertion through a small window in the flexor tendon sheath (Fig. 19.63). This is tensioned so that the joint cannot be passively extended beyond 20–30° of flexion. If the MCP joint is subluxated and ulnarly deviated, MCP arthroplasty and soft-tissue reconstruction should be performed as well. Persistent DIP flexion is treated with arthrodesis if necessary.

In type III deformity, the PIP joint is stiff regardless of MCP position. PIP flexion is limited not only by intrinsic tightness, but also because the lateral bands are fixed in a dorsal position. A dorsal skin contracture further complicates the deformity. The first goal is to regain passive mobility in the PIP joint. Serial casting or dynamic splinting should be used in an attempt to restore passive mobility. If passive mobility is restored, the type III swan-neck is converted to a type II swan-neck, and is treated accordingly. However, if nonoperative methods fail, passive motion must be restored surgically. A longitudinal incision is made over the PIP joint, with an oblique extension over the dorsal aspect of the middle phalanx. Skin flaps are elevated. A longitudinal incision is made on each side of the central slip, releasing the dorsally displaced

lateral bands (Fig. 19.64). The joint is passively flexed, and the lateral bands should slide volarly. If the joint cannot be flexed, a dorsal capsulotomy and collateral ligament recession may be required. An intrinsic release is performed as described above. The PIP joint is then pinned in flexion. The skin is closed proximally, but the oblique distal portion of the incision is allowed to gap open and heal secondarily (Fig. 19.65). This takes tension off the dorsal skin closure, and prevents skin necrosis.

In type IV swan-neck deformity with articular destruction, PIP arthrodesis is a reasonable option. In the ring and small fingers, PIP arthroplasty combined with an FDS sling is an alternative.

Postoperative care

The K-wire is removed and active and passive PIP motion within a dorsal blocking splint is initiated, as soon as finger edema is improved. After the finger has healed and passive mobility is restored, the swan-neck deformity can be treated with an FDS tenodesis. If present, MCP deformity should be corrected as well. Persistent DIP flexion is treated with arthrodesis.

Correction of boutonniere deformity

Boutonniere deformity is less functionally limiting than swan-neck deformity because the patient retains the ability to flex the finger for pinch and grasp. Furthermore, surgical treatment of boutonniere deformity creates the risk of converting a boutonniere deformity into a swan-neck deformity. Because of this, surgery should only be considered for moderate or severe boutonniere deformity that substantially affects hand function.

Stage I boutonniere deformity is mild, with only a slight extension lag at the PIP joint. The PIP joint is passively correctable and the MCP joint is normal. There is little functional limitation. However, if DIP joint hyperextension is severe, it can be treated with an extensor tenotomy.⁶⁰ A longitudinal incision is made over the dorsal aspect of the middle phalanx. Skin flaps are elevated and the extensor mechanism is exposed. An oblique incision is made through the entire extensor mechanism at the level of the middle of the middle phalanx, allowing the DIP joint to flex. Care should be taken not to injure the oblique retinacular ligament. If a mallet deformity occurs, it is treated with a splint or with DIP arthrodesis. Finger motion is allowed immediately postoperatively. A dynamic PIP extension splint is worn for 6 weeks postoperatively.

Stage II boutonniere deformity involves a more severe PIP flexion contracture of 30–40°. MCP hyperextension is present, and DIP hyperextension is more severe. If the PIP joint is not passively correctable serial casting should be attempted preoperatively. If serial casting fails to restore passive mobility, surgery is required to restore passive motion. Once the joint is supple, the boutonniere deformity can be corrected. A longitudinal incision is made over the PIP joint, and extended distally over the middle phalanx. An extensor tenotomy is performed as described above to allow DIP flexion. At the PIP joint, the goal is to shorten the central slip and correct the volar subluxation of the lateral bands. The central slip is transected 3 mm proximal to its insertion on the base of the middle phalanx, leaving enough for a later repair. A 15-blade




Fig. 19.63 Sublimis sling for correction of swan-neck deformity. A Bruner incision is made (A) exposing the FDS and FDP. One slip of FDS is isolated (B) and divided proximally (C). The FDS slip is then passed through an incision in the A2 pulley (D, E) and then sutured back on itself (F), creating a block to hyperextension of the PIP joint.




Fig. 19.64 An incision is made between the central slip and the lateral bands, allowing the lateral bands to relocate volarly with PIP joint flexion.




Fig. 19.65 When there is an insufficiency of dorsal skin in cases of long-standing swan-neck deformity, the distal portion of the incision is allowed to gap and heal secondarily.

is used to separate the central slip from the volarly subluxated lateral bands. A longitudinal incision is then made in the transverse retinacular ligament on each side of the finger, just volar to the lateral band. The lateral bands are then mobilized dorsally, and the PIP joint is brought into extension. The central slip is advanced distally towards the distal remnant at the central slip insertion. Excess central slip is excised, usually measuring about 5 mm in length, and the central slip is sutured to the remnant on the base of the middle phalanx using nonabsorbable sutures. Next, the lateral bands are sutured to the central slip using horizontal mattress sutures (Fig. 19.66). It should be possible to passively flex the PIP joint after tendon reconstruction.

In severe boutonniere deformity, the PIP joint is severely flexed and cannot be passively extended. In many cases, the PIP joint is arthritic or the joint surfaces have remodeled. PIP arthroplasty combined with soft-tissue reconstruction can be considered. However, in this situation PIP arthrodesis is probably the most reasonable option.

Postoperative care

The PIP joint is splinted in full extension for 4 weeks, and then finger motion is begun with a wire-foam dynamic extension splint during the day, and a volar PIP extension splint at night for 6 weeks.

Outcomes, prognosis, and complications

Outcomes after correction of swan-neck and boutonniere deformities are variable, and depend largely upon the severity of the original deformity. The most common complications are stiffness, recurrence, and pain. It should be emphasized that boutonniere deformity is in general a less debilitating deformity than swan-neck deformity, and the surgeon should be careful not to convert a boutonniere to a swan-neck by overcorrection.

Hints and tips

- Swan-neck deformities can be more debilitating than boutonniere deformities.
- The surgeon should be careful not to overcorrect a boutonniere deformity, thereby creating a swan-neck deformity.

Correction of thumb deformities

The most common thumb deformity is a boutonniere deformity (type I thumb deformity), with MCP flexion, IP hyperextension, and CMC abduction (Fig. 19.67). Early in the disease process the joints are passively correctable, and splinting may be adequate treatment. If splinting fails to improve function, reconstruction of the extensor mechanism can be performed. A dorsal incision is made over the MCP joint, and the extensor mechanism is exposed. An incision is made between the EPB and EPL tendons, and tenosynovectomies of the attenuated or ruptured EPB tendon and of the volarly subluxated EPL are performed. A transverse capsulotomy is made, leaving most of the capsule attached distally to the base of the proximal phalanx. MCP joint synovectomy is performed.




Fig. 19.66 Correction of boutonniere deformity. Excess central slip is excised and closed, and the volarly subluxated lateral bands are mobilized dorsally and sutured to the central slip. Care must be taken not to create a swan-neck deformity.




Fig. 19.67 Boutonniere deformity of the thumb. Synovitis at the MCP joint results in attenuation or rupture of the EPB near its insertion. The EPL is volarly subluxated.




Fig. 19.68 Swan-neck deformity of the thumb. Synovitis and subluxation at the CMC joint results in metacarpal adduction contracture and compensatory hyperextension at the MCP joint.

The EPL tendon is divided between the MCP and IP joints, and is mobilized proximally. This allows the IP joint to move into flexion. A small transverse incision is made in the distal aspect of the MCP joint capsule, just distal to the MCP joint. The MCP joint is then positioned in full extension, and the proximal EPL tendon is passed through the incision in the capsule. It is then turned proximally and sutured to itself under tension. The EPB is advanced and sutured to the base of the proximal phalanx and to the adjacent EPL tendon. The MCP joint is pinned in extension for 6 weeks. Motion at the IP joint is initiated immediately after surgery, but the IP joint is splinted in extension between exercises to prevent development of an extension lag. The MCP K-wire is removed in 6 weeks, splinting is discontinued, and motion is initiated.

In more severe boutonniere deformities, the MCP and IP joints can become fixed or arthritic. Treatment depends upon the status of these two joints. If the IP joint is fixed in extension but the articular surfaces remain intact, joint release with EPL release is performed. If the IP joint is arthritic, arthrodesis is performed. The fixed or arthritic MCP joint is treated with arthrodesis if motion can be preserved at the IP joint. If IP joint arthrodesis is required, the MCP joint should be treated with silicone arthroplasty and extensor tendon reconstruction.

Swan-neck deformity (type III thumb deformity) is the second most common thumb deformity. Dorsoradial CMC subluxation occurs, and metacarpal adduction contracture develops, followed by MCP hyperextension and IP flexion (Fig. 19.68). Early disease is treated with ligament reconstruction and tendon interposition (LRTI). More advanced disease is also treated with LRTI, but may also require a webspace release and adductor pollicis release. After trapezial resection, a four-flap Z-plasty is designed in the first webspace. The skin is incised and skin flaps are elevated. If the skin release alone is not sufficient to allow contracture release, dissection is carried down to the adductor pollicis and first dorsal interosseous. The contracted fascial bands of the adductor pollicis and first dorsal interosseous are released. If necessary, the adductor pollicis is released from its origin on the third meta-

carpal. The LRTI is then completed. Significant MCP hyperextension is treated with MCP arthrodesis.

Treatment for type II and type V thumb deformities is individualized, and depends upon the specific deformity at each joint. Type IV deformity, or gamekeeper's thumb, is treated with MCP arthrodesis.

Postoperative care

A thumb spica splint is used to immobilize the thumb for 4–6 weeks postoperatively. After 4–6 weeks, splinting is weaned and active motion is initiated. Motion is advanced, light activity is allowed, and gentle strengthening is initiated gradually, as tolerated.

Outcomes, prognosis, and complications

As with finger deformities, outcomes are related largely to the severity of the deformity and the degree of arthritis present before surgery.

Tendon surgery and carpal tunnel syndrome

Carpal tunnel syndrome

Carpal tunnel syndrome is common in RA patients and is secondary to the mass-effect of proliferative flexor tenosynovitis within the carpal tunnel. Very mild and intermittent carpal tunnel syndrome can be treated with medical management of the RA, splinting, and steroid injections. However, significant, constant, or progressive symptoms should be treated surgically. Standard carpal tunnel release is generally inadequate. An extended carpal tunnel release with flexor tenosynovectomy is usually required.

A standard carpal tunnel release is performed, and the carpal canal is examined for the presence of synovitis. If synovitis is present, the incision is extended distally to the distal palmar crease in a zig-zag fashion, and proximally across the wrist crease in a zig-zag fashion, continuing at least



Fig. 19.69 Carpal tunnel release in patients with rheumatoid arthritis usually requires an extensive flexor tenosynovectomy using an extensile exposure.

5 cm proximally in the forearm. Care is taken to keep the incision ulnar to the palmar cutaneous branch of the median nerve. Distal to the transverse carpal ligament, dissection is performed with tenotomy scissors, elevating skin flaps, while preserving the superficial palmar arch and the branches of the median nerve. Proximally, scissors are used to dissect down to the antebrachial fascia which is divided longitudinally, ulnar to the palmaris longus, exposing the full extent of the tenosynovitis (**Fig. 19.69**). Next the median nerve is identified proximally, where there is less synovitis, and a vessel loop is passed around it. Next, flexor tenosynovectomies are performed, beginning with the FDS tendons and progressing to the FPL and FDP tendons (**Fig. 19.70**). Each tendon should be addressed individually, working sequentially, and removing all hypertrophic synovium (**Fig. 19.71**). The fingers should be flexed by retracting on the flexor tendons, one by one, to ensure that excursion is not limited. The median nerve is examined. Hypertrophic synovium is carefully removed from the nerve with tenotomy scissors, preserving the deep motor branch distally, and the palmar cutaneous branch proximally. Finally, the floor of the carpal tunnel is examined. Sharp bony erosions or osteophytes should be removed using a rongeur, and soft tissue or capsule sutured over the smoothed area. The skin is closed with horizontal mattress sutures.



Fig. 19.70 Tenosynovectomy is performed one tendon at a time, while protecting the median nerve.



Fig. 19.71 The carpal tunnel is decompressed after tenosynovectomy.

Postoperative care

A volar forearm based wrist splint is applied for 2 weeks. Finger motion is initiated immediately. Full activity without restrictions may resume 5 weeks after surgery.

Outcomes, prognosis, and complications

Carpal tunnel release with flexor tenosynovectomy is effective at relieving carpal tunnel symptoms, particularly in patients who experience symptoms only intermittently, or who have had symptoms for a short period of time. Patients who have constant numbness, particularly if associated with two-point discrimination changes or thenar atrophy, will have slow or even incomplete relief of symptoms. Complications will be more common with carpal tunnel release in this population, due to the presence of adhesions and synovitis within the carpal canal.

Secondary procedures

Recurrence of carpal tunnel symptoms is minimized by effective medical control of the RA. However, if tenosynovitis recurs and leads to recurrent carpal tunnel symptoms, repeat carpal tunnel release and tenosynovectomy is indicated in order to relieve pressure on the median nerve. Secondary surgery is tedious, and great care must be taken to avoid injury to the median nerve. The incision and initial dissection should begin a few centimeters proximal to the original incision, so that the median nerve can be identified in a tissue plane that has not been previously operated on. Dissection is then carried distally, protecting the median nerve while completing the flexor tenosynovectomy through the distal forearm and carpal tunnel.

Hints and tips

- Carpal tunnel syndrome may be the initial presenting complaint in RA.
- RA patients typically require an extensile incision, with flexor tenosynovectomy.
- A standard or limited-incision carpal tunnel release is generally not indicated, and will not treat the underlying pathology.

Flexor tendon ruptures

Flexor tendon ruptures present with an acute loss of finger flexion. However, in a rheumatoid patient with limited motion due to flexor tenosynovitis or joint destruction, a flexor tendon rupture may go unnoticed. A difference between the active and passive finger ROM is suggestive of rupture, but can also be due to flexor tenosynovitis or a rheumatoid trigger finger.

FPL rupture is common, and is due to a sharp bony edge on the volar aspect of the scaphoid (Mannerfelt lesion). The incision for flexor tenolysis is made as described above. Flexor tenolysis is performed. The osteophyte is removed with a rongeur, and the capsule closed over the area to provide a smooth gliding surface (Fig. 19.72). If both ends of the ruptured tendon can be identified within the wrist and palm incision, a small bridge graft of palmaris longus




Fig. 19.72 Mannerfelt lesion. The osteophyte on the volar aspect of the scaphoid is identified and removed. Next, a flap of volar capsule is elevated and rotated to cover the rough bony surface.

or a strip of the FCR is used. It is weaved proximally and distally into the FPL using a Pulvertaft weave and 3-0 horizontal mattress sutures to secure the weave. It is important to resect frayed and damaged tendon edges, and graft into healthy tendon. If grafting within the palm is not possible, tendon transfer is required. A Bruner incision is made on the long finger over the proximal phalanx. The FDS is divided 1.5 cm proximal to its insertion and retracted into the palmar wound. Another Bruner incision is made over the thumb IP joint. Dissection is carried down to the flexor tendon sheath, and the FPL insertion. The sheath is opened near the FPL insertion, and the FPL is retracted and delivered into the distal thumb incision. The FPL is divided transversely with scissors, leaving a 1-cm stump attached to the insertion. The FPL stump is then divided longitudinally in its midline along its entire remaining 1 cm length, along its insertion. A small amount of elevation of the central portion of the insertion is performed, but care is taken to keep most of the insertion intact. The volar aspect of the base of the distal phalanx is roughened with a small rongeur to provide a surface for tendon healing. The FDS is delivered through the fibro-osseous canal of the thumb using a pediatric feeding tube. Two suture anchors with 3-0 Ethibond are placed in the base of the distal phalanx, between the split halves of the FPL stump. The FDS is then laid down between the split halves of the FPL and secured to the bone by tying it down to the suture anchors. Next, the two halves of the FPL stump are brought around and volar to the FDS tendon, and sutured to the FDS tendon with horizontal mattress sutures, reinforcing the insertion. Tension should be set so that IP extension occurs with wrist flexion, and full flexion into the palm occurs with wrist extension.

An isolated FDS rupture does not necessarily result in significant functional loss. An end-to-side suture to an adjacent FDS is performed if the rupture occurs within the palm or carpal tunnel, using a Pulvertaft weave. Flexor tenosynovectomy and treatment of any sharp bone edges should be performed. If the FDS rupture occurs within the finger, a tenosynovectomy with resection of the FDS should be performed.

FDP rupture may also not result in severe functional loss, if isolated. Flexor tenolysis, and treatment of any sharp bony edges should be performed. If the rupture occurs within the palm or wrist, an end-to-side suture to an adjacent FDP is performed. If FDP rupture occurs within the finger and the FDS is functional, the FDP is resected. If the DIP joint hyperextends during pinch or grip, DIP arthrodesis is performed.

Rupture of both the FDS and FDP results in significant functional loss. If the ruptures are within the palm or carpal tunnel, end-to-side suturing of the FDP to an adjacent tendon is performed. Alternatively, a bridge graft can be used as described above for the FPL, with the FDS serving as a donor graft. If both tendons have ruptured within the flexor tendon sheath, a staged reconstruction can be considered. However, the outcome of staged flexor tendon reconstruction in patients with RA is often disappointing, and patients should be counseled that recovery of motion will be limited. In patients with arthritis of the IP joints, the best option is arthrodesis of the PIP and DIP joints in a functional position, with preservation of some finger motion at the MCP via the intrinsics.

Postoperative care

If tendon transfers are performed, the hand and fingers are immobilized in such a way as to take tension off of the transfer. The transfer is immobilized for 3–4 weeks, after which motion and retraining are begun under the guidance of a therapist. It should be noted that there is an increasing interest in early movement protocols following tendon transfer surgery, and this may result in improved outcomes or earlier recovery.

Outcomes, prognosis, and complications

Patients have the potential to maintain good finger function after isolated rupture of the FDS or FDP, if their pre-rupture finger function was good and if they receive appropriate treatment in a timely fashion. However, if pre-rupture finger function was limited, outcomes will be poor even if the rupture is treated appropriately. Outcomes after rupture of both the FDS and FDP are poor, regardless of pre-rupture finger function or the method of treatment.

Trigger fingers

Triggering can occur due to the presence of rheumatoid nodules or because of hypertrophic synovium. A very small nodule or synovitis can significantly affect tendon excursion and finger function. Furthermore, the location of the pathology is variable. Although the source of triggering can often be located preoperatively, the surgeon should plan for the possibility of an extensile incision.

The operation is performed under sedation and with local anesthetic, so that the patient can actively flex the finger after tenosynovectomy. A Bruner incision is made over the finger. Initially, the incision is limited to the suspected area of pathology, and can be extended later if necessary. Skin flaps are elevated and the flexor tendon sheath is exposed, preserving the neurovascular bundles. A window is made within the flexor tendon sheath at the level of the cruciate pulley, or at the A1 or A3 pulley nearest the pathology. The flexor tendons are retracted out of the flexor tendon sheath individually through the window using a Ragnell retractor. Synovium is removed from the flexor tendons using tenotomy scissors or a synovial rongeur, taking care to preserve the vincula (Figs. 19.73 & 19.74). If a rheumatoid nodule is encountered, it is excised. If pathology is more extensive, more windows are created within the sheath at the cruciate, A1 or A3 pulleys, allowing full access to the tendons. Rarely, it is necessary to excise the FDS tendon in order to allow FDP excursion. Complete release of the A1 pulley is avoided to lessen the chance of abnormal pull of the flexor tendon that would contribute to ulnar deviation. The patient is awakened and asked to actively flex the finger. If active motion is less than passive motion, or if triggering has not resolved, the surgeon must search for further pathology.

Postoperative care

A light dressing is placed and active and passive motion is begun immediately postoperatively, including tendon gliding exercises.

Outcomes, prognosis, and complications

A good outcome is dependent upon identification and treatment of the cause of the triggering. In order to prevent




Fig. 19.73 Proliferative synovitis can be seen protruding through rents in the flexor tendon sheath.

the complication of persistent postoperative triggering, the surgeon must make sure that he or she has located and addressed all potential sources of triggering by having the patient actively range the finger prior to incision closure.

Extensor tendon ruptures

Extensor tendon ruptures most commonly occur at the wrist (Video 19.1 ▶). They are due to a combination of erosive tenosynovitis and attritional wear over a sharp spicule of bone at the ulnar side of the wrist, often arising from the ulnar head or DRUJ. Rupture of the EPL is common as well. In addition to treating the rupture, it is critical to address the underlying cause in order to prevent subsequent ruptures.

A dorsal wrist incision is made, skin flaps are elevated, and the retinaculum is incised as described above. A dorsal tenosynovectomy is performed as described above. The ruptured tendon is identified, and soft friable ends are resected with tenotomy scissors until the proximal and distal stumps consist




Fig. 19.74 A large piece of synovitis is being removed through a small opening in the flexor tendon sheath just distal to the A2 pulley.




Fig. 19.75 The small finger extensors (EDC and EDQ) have ruptured at the level of the wrist, and their distal ends can be seen just distal to the extensor retinaculum.

of healthy tendon. The cause of the rupture should be sought, and is usually related to a sharp edge of bone. Care should be taken to smooth down all bony surfaces. In many cases a Darrach procedure is indicated, and can be performed at this time as described above. Next, a retinacular strip is transferred volar to the extensor tendons to cover any remaining exposed areas of bone. Next, the tendon reconstruction is performed. Rarely, the tendon ends can be repaired primarily. In most cases, there is a substantial zone of injury that precludes direct repair.

The reconstruction depends upon the number of tendons ruptured. If the tendon(s) to a single finger is (are) ruptured, the distal stump(s) should be sutured to an adjacent tendon using an end-to-side Pulvertaft weave (Figs. 19.75 & 19.76). Alternatively, the extensor indicis proprius (EIP) can be transferred in an end-to-end fashion to the ruptured tendon (Fig. 19.77). For the EIP transfer, a longitudinal incision is made over the index MCP joint, extending distally to the middle of the proximal phalanx. Skin flaps are elevated, exposing the extensor mechanism. The interval between the ulnarly located EIP and the radially located extensor digitorum communis (EDC) is identified and incised longitudinally, separating the two tendons. The sagittal band is carefully elevated off the EIP with a 15-blade, for later repair. The EIP is divided as far distally as possible, and retracted into the dorsal wrist incision. The distal stump of the EIP is sutured to the adjacent EDC, the sagittal band is repaired and the skin is closed. The EIP is then Pulvertaft weaved into the EDC and extensor digiti quinti (EDQ) of the small finger. It is important to tension the transfer correctly, creating a natural cascade of the fingers. The wrist is passively flexed and extended, checking the tenodesis effect. With the wrist flexed, the MCP joint should easily come




Fig. 19.76 The small finger extensors (EDC and EDQ) have been transferred end-to-side to the ring finger EDC.

into full extension or slight hyperextension. With the wrist extended, it should be possible to passively flex the MCP joint. It is preferable to slightly over-tighten the transfer, as there will be some loosening with time.

If both the small and ring finger extensor tendons are ruptured, the ring finger EDC is transferred to the long finger EDC in an end-to-side fashion. The small finger extensors, however, will not reach the long finger EDC, and end-to-side transfer usually cannot be performed. Therefore, the EIP tendon is transferred end-to-end to the small finger extensors (Fig. 19.78). The EIP is transferred to both the EDC and EDQ of the small finger, using a Pulvertaft weave. Again, setting tension properly is critical. The natural cascade of the fingers and the tenodesis effect are used as a guide to set the tension.

If three or four of the extensor tendons are ruptured, an FDS transfer is often performed. With three ruptures, the long finger EDC is sutured to the adjacent intact index EDC, and the ring FDS or EIP is used to restore extension of the small and ring fingers (Fig. 19.79). With four ruptures, two FDS transfers are required. The long FDS is used to restore index and long finger extension, and the ring FDS is used to restore ring and small finger extension (Fig. 19.80). For FDS harvest, a Bruner incision is made over the proximal phalanx of the appropriate finger. Skin flaps are elevated, and the flexor tendon sheath exposed. A small opening is made in the flexor tendon sheath, and the FDS is divided 1.5 cm proximal to its insertion. A longitudinal volar incision is made in the distal forearm proximal to the wrist flexion crease, and ulnar to the palmaris longus. Dissection is carried down to the FDS tendons, and the divided FDS is retracted into the wrist incision. The FDS is passed around the radial subcutaneous border of the wrist and delivered into the dorsal wrist

incision. The transfer is completed and tensioned as described above.

Clinical tip

- The FDS tendons may be routed through an opening in the interosseous membrane for a straighter line of pull.
- It is critical to make a wide interosseous tunnel, both in transverse and in longitudinal dimensions so that the FDS tendons have a straight line of pull, and do not become entrapped.

EPL rupture is not always symptomatic, and may not require treatment. IP extension is usually preserved through the intrinsics, and MCP extension may or may not be lost. If MCP extension is lost and thumb function is affected, the EPL rupture is treated with an EIP to EPL transfer. The EIP is harvested as described above, and is retracted into the wrist incision. It is then passed distally to the dorsal aspect of the thumb, and transferred to the EPL with a Pulvertaft weave at the level of the metacarpal. It should be tensioned so that the MCP joint fully extends with the wrist flexed. With the wrist extended, it should be possible to passively flex the MCP joint.




Fig. 19.77 Rupture of the EDC and EDQ to the small finger. The EIP is transferred to the small finger extensors.




Fig. 19.78 Rupture of the small and ring finger extensors. The ring finger EDC is transferred end-to-side to the long finger EDC. The EIP is transferred end-to-end to the small finger extensors.

Postoperative care

For finger extensor tendon transfers, the wrist and MCP joints are splinted in extension for 4 weeks. Active motion and retraining is begun under the supervision of a hand therapist after 4 weeks. Gentle passive flexion can be started at 6 weeks, and strengthening at 8 weeks. Full activity and discontinuation of extension splinting occurs at 12 weeks. The thumb is protected in a thumb spica splint with the MCP and IP joints extended for 4 weeks, after which motion is initiated.

Outcomes, prognosis, and complications

Restoration of MCP extension can be reliably achieved with tendon transfers in patients who have preserved MCP joints. In patients with volarly subluxed and arthritic MCP joints, it is preferable to restore joint alignment and passive mobility by arthroplasty and soft-tissue reconstruction prior to performing tendon transfers. Any attempt to restore extension without first addressing MCP deformity or arthritis will result in suboptimal outcomes. Recurrent rupture can occur, and is minimized by correcting the underlying causes, including extensor tenosynovitis, rough bony surfaces, and the caput ulna.

Hints and tips

- Once an extensor tendon rupture occurs, subsequent ruptures can occur in rapid sequence.
- Although not an emergency, there is some urgency to treating the underlying cause.
- The surgeon should be careful to treat the underlying cause of the rupture when performing tendon transfers for extensor tendon rupture.
- The surgeon should have a low threshold for performing a distal ulna resection if there is concern that distal ulna or DRUJ pathology caused the ruptures.

Other rheumatologic disorders of the hand and wrist

Seronegative spondyloarthropathies

Seronegative spondyloarthropathies include Reiter's syndrome, psoriatic arthritis, ankylosing spondylitis, and inflammatory bowel disease-associated arthritis. The most common seronegative spondyloarthropathy to affect the hands is psoriatic arthritis. Patients are usually RF negative, have an inflammatory arthritis, and have psoriasis (Table 19.1). Psoriasis affects 2% of the population and onset usually occurs in the 2nd decade of life.⁶¹ Among patients with psoriasis, the prevalence of psoriatic arthritis is unknown, but ranges from approximately 5% to 40%.

Radiographic findings are diverse, and may include erosions and resorption, osteolysis, periostitis, ankylosis (often at the PIP joint), or juxta-articular bone formation. Radiographs may reveal a "pencil-in-cup" deformity at the DIP joint, which is the result of new marginal bone formation at the base of the distal phalanx, combined with osteolysis of the head of the middle phalanx.

Joint involvement can be symmetric or asymmetric, and may be oligoarticular or polyarticular. The small joints of the hands and feet are most commonly affected, and DIP involvement is often a prominent feature of psoriatic arthritis. Although tenosynovitis and tendon ruptures are rare, inflammation at tendon insertions may occur. Another occasional finding is dactylitis, which involves swelling and inflammation of an entire digit. The nails also develop abnormalities. Pitting is the classic finding, although onycholysis, nail dystrophy, leukonychia, and hyperkeratosis can occur as well. The most common finger deformity is a PIP flexion contracture, with compensatory MCP hyperextension. This is not a true boutonniere deformity. Swan-neck deformities can occur secondary to a mallet finger. In the thumb, a boutonniere deformity can occur, and the CMC joint can become arthritic as well. Wrist arthritis and DRUJ arthritis can occur as well. Rarely, severe osteolysis, or arthritis mutilans, results in collapse of the fingers known as the "opera glass hand".

Swan-neck deformity is treated in a similar fashion to swan-neck deformity associated with RA. Severe fixed PIP flexion contractures are treated with arthrodesis. MCP extension contractures with associated joint destruction are treated with silicone arthroplasty. Arthritis mutilans is treated with arthrodesis, often requiring bone graft. Wrist involvement is




Fig. 19.79 Rupture of the long, ring, and small finger extensors. The EDC of the long finger is transferred end-to-side to the EDC of the index finger. The EIP (A) or the FDS (B) can be transferred to the small and ring finger extensors.

Table 19.1 Characteristics of other rheumatologic conditions of the hand			
	Serology	Radiographs	Examination
Psoriatic arthritis	Negative	Erosions Resorption Osteolysis Periostitis Ankylosis (PIP) Juxta-articular bone formation Pencil-in-cup (DIP)	Psoriasis Nail abnormalities Dactylitis PIP flexion contracture Opera glass hand swan-neck deformity
SLE	ANA Anti-DNA Antiphospholipid antibody Leucopenia Hemolytic anemia Thrombocytopenia	Preservation of joints Secondary OA	Deformity similar to that seen in RA Malar rash Discoid rash Serositis Other
Scleroderma	ANA Anti-centromere Anti-topoisomerase I Anti-RNA polymerase	Tuft resorption Secondary OA	Cutaneous telangiectasia Raynaud's Cutaneous sclerosis Ischemic ulceration Joint contracture due to skin contracture
Gout	Hyperuricemia Negatively birefringent crystals (synovial analysis)	Sclerotic joint margins Overhanging edges Erosion from tophi (late) Joint destruction (late)	Red, hot, swollen joint MTP of great toe involvement Tophi
Pseudogout (CPPD)	Negative	Chondrocalcinosis of TFCC Scapholunate widening Scapholunate advanced collapse pattern arthritis	Presentation may be similar to osteoarthritis May be chronic inflammatory arthritis (mono-, oligo-, or polyarticular) May present as acute pseudogout attack (red, hot, swollen joint)




Fig. 19.80 Rupture of the extensor tendons to all four fingers. The long finger FDS is transferred to the index and long finger extensors, and the ring finger FDS is transferred to the ring and small finger extensors.

treated with limited intercarpal fusions or complete wrist arthrodesis, depending upon the pattern of joint involvement. A Darrach procedure may be indicated for DRUJ arthritis.

Systemic lupus erythematosus

Systemic lupus erythematosus (SLE) is a systemic autoimmune disease (see [Table 19.1](#)), in which tissue damage is caused by autoantibodies and immune complexes. It affects five in 10 000 people in the United States, and women are affected much more frequently than men (9:1). African Americans and Latinos are affected more often than Caucasians, and tend to have a more severe disease process. Susceptibility is related to multiple genes. Many potential environmental triggers have been implicated, including Epstein-Barr virus (EBV) infection, multiple medications, dietary factors and bacteria.

The diagnosis of SLE is primarily clinical, and is supported by positive laboratory findings. Extra-articular manifestations are diverse and may include malar rash, discoid rash, photosensitivity, cardiovascular disease, oral ulcers, arthritis, serositis, proteinuria, seizures, psychosis, leukopenia, hemolytic

anemia, thrombocytopenia, and many others. Seropositivity for antinuclear antibody (ANA) is very sensitive (95%), although there are cases of ANA-negative lupus. However, specificity is low and ANA may be positive in multiple rheumatologic diseases. Other supportive laboratory findings include anti-DNA, anti-Sm nuclear antigen, and antiphospholipid antibodies.

The IP joints, MCP joints, and wrist are commonly involved, and may be the initial presenting symptoms of the disease. Patients experience swelling, pain, effusion and morning stiffness. The arthritis associated with SLE is not erosive, and may not be deforming. If finger deformities do occur, they are very similar to those seen in rheumatoid arthritis. Volar subluxation and ulnar deviation occurs at the MCP joints, and swan-neck or boutonniere deformities may occur, but with an absence of destructive joint changes. In addition, tenosynovitis may occur, and may result in tendon ruptures. Synovitis within the carpal tunnel may lead to carpal tunnel syndrome. In addition, patients may develop subcutaneous nodules along the flexor tendons, histologically similar to those that develop in rheumatoid arthritis.

In many cases, the finger and wrist deformities that occur with SLE are passively correctable. In these cases splinting can be quite helpful. Intrinsic stretching can also be helpful to decrease MCP flexion and ulnar deviation. Because of poor soft-tissue quality, soft-tissue procedures alone are rarely successful, and the mainstays of surgery in the fingers are arthrodesis and arthroplasty, which can be combined with soft-tissue procedures. Partial wrist arthrodesis or total wrist arthrodesis may be beneficial, depending upon the deformity and instability pattern. The Darrach procedure is often indicated for dorsal subluxation of the ulna, which can often cause attrition ruptures. Because of the many organ systems involved, patients must have a thorough medical workup and preoperative clearance.

Scleroderma

Scleroderma, or systemic sclerosis (see [Table 19.1](#)), is a disease of the connective tissue and small blood vessels that affects multiple tissues. It is rarer than either rheumatoid arthritis or SLE, with a prevalence of <300 per 1 million in the United States. Like most rheumatologic disorders it is more common in women than men, and onset typically occurs in the 3rd or 4th decade of life. The disease is idiopathic, but there is a genetic component and an environmental trigger is likely required to initiate the disease. Systemic sclerosis can present as limited cutaneous disease (often involving the fingers or hands), diffuse cutaneous disease, or CREST syndrome (calcinosis, Raynaud's phenomenon, esophageal involvement, sclerodactyly, and telangiectasias). Systemic sclerosis can affect the lungs, resulting in interstitial disease and pulmonary fibrosis. Cardiac, vascular, renal, gastrointestinal and other organ systems are also commonly involved. The diagnosis is clinical, and is supported by antibody testing. Nail fold capillary microscopy is also helpful. ANA, anti-centromere, anti-topoisomerase I, anti-RNA polymerase antibodies are all associated with systemic sclerosis.

Raynaud's phenomenon affects almost all patients, and is present in limited cutaneous, diffuse cutaneous, and CREST forms of the disease. Critical ischemia, however, occurs due to vascular disease related to the systemic sclerosis, and is not

due to Raynaud's phenomenon. Occlusive vascular changes affect the medium-sized vessels, and the ulnar artery in particular. Ischemic ulceration may occur in the fingertips, on the extensor surface over flexed joints, and in areas of calcinosis. Ischemia-related resorption of the tufts can occur, and is termed acro-osteolysis. Cutaneous telangiectasia may be seen on the palm. Treatment of the vascular manifestations of the disease is outside the scope of this chapter.

Finger deformities are related to skin contracture, and to fibrosis and contracture of joint ligaments and capsule. Arthritis and joint destruction do not occur directly. If joint changes or arthritis are seen, they are usually osteoarthritic changes that occur secondary to prolonged deformity and abnormal motion. The most common deformity in the hand is PIP flexion contracture. These contractures can be severe, and dorsal skin ulceration can occur with tendon or joint exposure. MCP hyperextension occurs secondarily, and can become fixed as well. In addition, the first webspace contracture is common. Soft-tissue loss over joints should be treated conservatively, with Silvadene dressing changes and minimal debridement. Ultimately, bony debridement or amputation may be required. At times, skin breakdown occurs over an area of calcinosis. Removal with a curette and irrigation with saline is performed. For severe PIP contractures with intact overlying skin, arthrodesis may be indicated. Care should be taken when managing the skin, and minimal skin flap elevation should be performed. In addition, significant bony resection should be performed, in order to take tension off the overlying skin. A compression screw or removable K-wires should be used in order to avoid subcutaneous hardware. Dressings should be light, and noncompressive. Patients should be cautioned about the possibility of wound healing problems, potentially resulting in the need for amputation. At the MCP joint resection arthroplasty is indicated for severe fixed extension contracture. A volar longitudinal incision is made directly over the metacarpal head. Dissection is carried down to the flexor tendon sheath, retracting the neurovascular bundles radially and ulnarly. The A1 pulley is incised, and the flexor tendons retracted. A 15-blade is used to create a volar arthrotomy through the volar plate and joint capsule. Subperiosteal dissection is then performed, exposing the head and neck of the metacarpal. A sagittal saw is then used to resect the metacarpal head. Bony resection is performed until MCP flexion is possible. The skin is closed and the patient is splinted with the MCPs flexed. Motion is allowed as soon as skin healing has occurred. First webspace contracture is difficult to treat. Because of the stiff nature of the skin, Z-plasties are rarely successful, and the contracture must be treated more like a severe burn contracture. A long transverse incision is made in the first webspace. Dissection is carried down to the adductor pollicis and first dorsal interosseous. Tight fascial bands are released with tenotomy scissors until the thumb can be abducted. If thumb CMC arthritis or CMC subluxation contributes to the adduction deformity, trapeziectomy can be performed through a separate incision. A full-thickness skin graft is used to close the defect, and should be harvested from an area with minimal skin involvement.

Postoperative care

The thumb should be pinned in abduction for 6 weeks, followed by motion and intermittent splinting.

Crystalline arthropathy (gout)

Gout is characterized by recurrent bouts of acute arthritis, eventually progressing to chronic arthritis (see [Table 19.1](#)). It affects approximately 1% of the population, and is more common in men. Risk factors include obesity, alcohol use, hypertension, renal disease, and certain medications. Triggers for an acute gout attack include physiologic stress, fever, surgery, dehydration, and alcohol use. In addition, foods that are high in purine increase the risk of a gout attack, including oatmeal, mushrooms, lentils and spinach.

Initially gout attacks are monoarticular, and involvement of the MTP joint of the great toe is classic. The joint becomes swollen, red, and exquisitely painful. Initially radiographs may be negative. The acute attack may last from hours to many days. As gout progresses, it can become polyarticular, and systemic symptoms such as fever, chills, or sweats may be present. Hand and wrist involvement is common. Eventually chronic arthritis and tophi develop, with continued episodic acute attacks. In chronic gout radiographic findings include erosions with sclerotic margins, and overhanging edges of bone ([Fig. 19.81](#)). Definitive diagnosis is made by arthrocentesis and identification of crystals with negative birefringence under polarized light microscopy. For an acute attack, colchicine, indomethacin, or corticosteroids are often used. An intra-articular steroid injection is quite effective. Prophylaxis is provided by daily low-dose colchicine or indomethacin. In addition, xanthine oxidase inhibitors such as allopurinol, or uricosuric agents such as probenecid can be used to reduce serum uric acid levels. Chronic gouty arthritis is treated with selective arthrodesis of joints that are painful, or that have deformity that is affecting function. Large painful tophi, or tophi that are interfering with function can be excised.



Fig. 19.81 PA radiograph of the hand demonstrating large gouty tophi of the PIP joints, and overhanging erosions.



Fig. 19.82 PA radiograph of the left wrist demonstrating chondrocalcinosis of the TFCC and lunotriquetral ligaments consistent with pseudogout.

Crystalline arthropathy (pseudogout)

Pseudogout is another common crystalline arthropathy (see Table 19.1), and the incidence increases with age.⁶² Also known as calcium pyrophosphate dihydrate deposition disease (CPPD), pseudogout is characterized by the deposition of calcium pyrophosphate crystals within hyaline and fibrocartilage. Common radiographic findings include chondrocalcinosis of the TFCC (Fig. 19.82), and scapholunate advanced collapse (SLAC) pattern arthritis. Under polarized light microscopy, calcium pyrophosphate crystals are positively birefringent and rhomboid shaped, differentiating them from urate crystals. The clinical presentation is commonly one of chronic mono-, oligo-, or polyarthritis, although acute pseudogout attacks can occur. It is also common to see chondrocalcinosis as an incidental radiographic finding, not associated with clinical symptoms. Although the knee is most frequently affected, the wrist is second. Pseudogout attacks may last substantially longer than gout attacks, extending up

to 3 months' duration.⁶³ Although multiple medications are being studied for use in treating pseudogout, the mainstays of treatment are NSAIDs, corticosteroids, and colchicine.

Summary

Multiple diverse rheumatologic disorders exist, many of which commonly affect the hand and wrist. Although the medical management of rheumatologic diseases has dramatically improved, there are still many patients with recalcitrant pain and loss of function who may benefit from hand surgery. In most cases, arthritic pain can be effectively treated with arthrodesis or arthroplasty. Restoration of function is less reliably achieved, but is an important secondary goal. It is important for the patient to undergo a thorough medical and anesthesia workup prior to any surgery because of the many systemic manifestations associated with rheumatologic disorders.

Future directions

At times, differentiating between an acute gout attack and septic arthritis can be clinically challenging. The ability of arthrocentesis to distinguish gout versus infection may be limited by the amount of fluid obtained, or pre-existing antibiotic treatment. Recent research demonstrates that dual-energy computed tomography (DECT), also known as a "gout-map CT scan", may be used to differentiate between a joint with gout and an infected joint.⁶⁴ In addition to detecting monosodium urate crystals within a joint, DECT can be used to quantify the anatomic extent and severity of crystal deposition. The sensitivity and specificity for detecting gouty arthritis using DECT are approximately 75% and 93%, respectively.⁶⁴ Although the role of DECT in diagnosing gout requires further study, this technology shows substantial promise.



Access the complete reference list online at <http://www.expertconsult.com>

20. Bongartz T, Sutton AJ, Sweeting MJ, et al. Anti-TNF antibody therapy in rheumatoid arthritis and the risk of serious infections and malignancies: systematic review and meta-analysis of rare harmful effects in randomized controlled trials. *JAMA*. 2006;295:2275–2285.
24. Bongartz T. Elective orthopedic surgery and perioperative DMARD management: many questions, fewer answers, and some opinions. *J Rheumatol*. 2007;34:653–655. An excellent review of the current state of the evidence regarding perioperative DMARD management. An evidence-based, practical and conservative approach is recommended by the authors.
39. Linscheid RL, Dobyns JH. Rheumatoid arthritis of the wrist. *Orthop Clin North Am*. 1971;2:649–665.
41. Flury MP, Herren DB, Simmen BR. Rheumatoid arthritis of the wrist. Classification related to the natural course. *Clin Orthop Relat Res*. 1999;366:72–77. The authors present a classification system for the rheumatoid wrist that is now commonly used and frequently referenced. This classification system uses radiologic indicators to divide wrists into those that are stable (types I and II) and those that are unstable (type III).
42. Vaughan-Jackson OJ. Attrition ruptures of the tendons in the rheumatoid hand. *J Bone Joint Surg*. 1958;40A:1431. The brief paper by Vaughan-Jackson is a classic original description of extensor tendon attrition ruptures.
43. Mannerfelt L, Norman O. Attrition ruptures of flexor tendons in rheumatoid arthritis caused by bony spurs in the carpal tunnel. A clinical and radiological study. *J Bone Joint Surg Br*. 1969;51:270–277.
44. Flatt AE. Some pathomechanics of ulnar drift. *Plast Reconstr Surg*. 1966;37:295–303.
49. Flatt AE. *The Care of the Rheumatoid Hand*. St. Louis: Mosby; 1974. An excellent historical overview of surgical treatments for the rheumatoid hand, as well as descriptions of the mechanics of the disease process.
50. Shapiro JS, Heijna W, Nasatir S, et al. The relationship of wrist motion to ulnar phalangeal drift in the rheumatoid patient. *Hand*. 1971;3:68–75.
51. Nalebuff EA. Surgical treatment of tendon rupture in the rheumatoid hand. *Surg Clin North Am*. 1969;49:811–822. A detailed description of the surgical management of tendon ruptures by a hand surgeon with extensive experience in treating patients with rheumatoid arthritis.
55. Urban MK. Anaesthesia for orthopedic surgery. In: Miller RD, Eriksson LI, Fleisher LA, et al., eds. *Miller's Anesthesia*. Philadelphia: Churchill Livingstone; 2009.

References

- Gabriel SE. The epidemiology of rheumatoid arthritis. *Rheum Dis Clin North Am*. 2001;27:269–281.
- Ghaffar L, Mascella F, Pomponio G. Hand surgery in rheumatoid arthritis: state of the art and suggestions for research. *Rheumatology (Oxford)*. 2005;44(7):834–845.
- Evans TI, Han J, Singh R, et al. The genotypic distribution of shared-epitope DRB1 alleles suggests a recessive mode of inheritance of the rheumatoid arthritis disease-susceptibility gene. *Arthritis Rheum*. 1995;38:1754–1761.
- O'Dell JR. Rheumatoid arthritis. In: Goldman L, Ausiello D, eds. *Cecil Medicine*. 23rd ed. Philadelphia: Saunders; 2008.
- Seldin MF, Amos CI, Ward R, et al. The genetics revolution and the assault on rheumatoid arthritis. *Arthritis Rheum*. 1999;42:1071–1079.
- Enzer I, Dunn G, Jacobsson L, et al. An epidemiologic study of trends in prevalence of rheumatoid factor seropositivity in Pima Indians: evidence of a decline due to both secular and birth-cohort influences. *Arthritis Rheum*. 2002;46(7):1729–1734.
- Firestein GS. Etiology and pathogenesis of rheumatoid arthritis. In: Firestein GS, Budd RC, Harris ED, et al., eds. *Kelley's Textbook of Rheumatology*. Philadelphia: WB Saunders; 2008.
- Lang TJ. Estrogen as an immunomodulator. *Clin Immunol*. 2004;113:224–230.
- Linn-Rasker SP, van der Helm-van Mil AH, van Gaalen FA, et al. Smoking is a risk factor for anti-CCP antibodies only in rheumatoid arthritis patients who carry HLA-DRB1 shared epitope alleles. *Ann Rheum Dis*. 2006;65:366–371.
- Albani S, Ravelli A, Massa M, et al. Immune responses to the *Escherichia coli* dnaJ heat shock protein in juvenile rheumatoid arthritis and their correlation with disease activity. *J Pediatr*. 1994;124:561–565.
- Blaschke S, Schwarz G, Moneke D, et al. Epstein-Barr virus infection in peripheral blood mononuclear cells, synovial fluid cells, and synovial membranes of patients with rheumatoid arthritis. *J Rheumatol*. 2000;27:866–873.
- Cole BC, Griffiths MM. Triggering and exacerbation of autoimmune arthritis by the *Mycoplasma arthritis* superantigen MAM. *Arthritis Rheum*. 1993;36:994–1002.
- Hoffman RW, O'Sullivan FX, Schafermeyer KR, et al. *Mycoplasma* infection and rheumatoid arthritis: analysis of their relationship using immunoblotting and an ultrasensitive polymerase chain reaction detection method. *Arthritis Rheum*. 1997;40:1219–1228.
- Firestein GS, Paine MM, Littman BH. Gene expression (collagenase, tissue inhibitor of metalloproteinases, complement, and HLA-DR) in rheumatoid arthritis and osteoarthritis synovium. Quantitative analysis and effect of intraarticular corticosteroids. *Arthritis Rheum*. 1991;34:1094–1105.
- Hou WS, Li W, Keyszer G, et al. Comparison of cathepsins K and S expression within the rheumatoid and osteoarthritic synovium. *Arthritis Rheum*. 2002;46:663–674.
- Lark MW, Bayne EK, Flanagan J, et al. Aggrecan degradation in human cartilage. Evidence for both matrix metalloproteinase and aggrecanase activity in normal, osteoarthritic, and rheumatoid joints. *J Clin Invest*. 1997;100:93–106.
- Goekoop-Ruiterman YP, de Vries-Bouwstra JK, Allaart CF, et al. Comparison of treatment strategies in early rheumatoid arthritis: a randomized trial. *Ann Intern Med*. 2007;146:406–415.
- Bathoorn JM, Martin RW, Fleischmann RM, et al. A comparison of etanercept and methotrexate in patients with early rheumatoid arthritis. *N Engl J Med*. 2000;343:1586–1593.
- Lipsky PE, van der Heijde DM, St Clair EW, et al. Infliximab and methotrexate in the treatment of rheumatoid arthritis. Anti-Tumor Necrosis Factor Trial in Rheumatoid Arthritis with Concomitant Therapy Study Group. *N Engl J Med*. 2000;343:1594–1602.
- Bongartz T, Sutton AJ, Sweeting MJ, et al. Anti-TNF antibody therapy in rheumatoid arthritis and the risk of serious infections and malignancies: systematic review and meta-analysis of rare harmful effects in randomized controlled trials. *JAMA*. 2006;295:2275–2285.
- Grennan DM, Gray J, Loudon J, et al. Methotrexate and early postoperative complications in patients with rheumatoid arthritis undergoing elective orthopaedic surgery. *Ann Rheum Dis*. 2001;60:214–217.
- Jain A, Maini R, Nanchahal J. Disease modifying treatment and elective surgery in rheumatoid arthritis: the need for more data. *Ann Rheum Dis*. 2004;63:602–603.
- Jain A, Witbreuk M, Ball C, et al. Influence of steroids and methotrexate on wound complications after elective rheumatoid hand and wrist surgery. *J Hand Surg Am*. 2002;27:449–455.
- Bongartz T. Elective orthopedic surgery and perioperative DMARD management: many questions, fewer answers, and some opinions. *J Rheumatol*. 2007;34:653–655. *An excellent review of the current state of the evidence regarding perioperative DMARD management. An evidence-based, practical and conservative approach is recommended by the authors.*
- Union A, Meheus L, Humbel RL, et al. Identification of citrullinated rheumatoid arthritis-specific epitopes in natural filaggrin relevant for antifilaggrin autoantibody detection by line immunoassay. *Arthritis Rheum*. 2002;46:1185–1195.
- Nielen MM, van Schaardenburg D, Reesink HW, et al. Specific autoantibodies precede the symptoms of rheumatoid arthritis: a study of serial measurements in blood donors. *Arthritis Rheum*. 2004;50:380–386.
- Fleming A, Crown JM, Corbett M. Early rheumatoid disease. I. Onset. *Ann Rheum Dis*. 1976;35:357–360.
- Guerne PA, Weisman MH. Palindromic rheumatism: part of or apart from the spectrum of rheumatoid arthritis. *Am J Med*. 1992;93:451–460.
- Moffat DA, Ramsden RT, Rosenberg JN, et al. Otoadmittance measurements in patients with rheumatoid arthritis. *J Laryngol Otol*. 1977;91:917–927.
- Fleming A, Benn RT, Corbett M, et al. Early rheumatoid disease. II. Patterns of joint involvement. *Ann Rheum Dis*. 1976;35:361–364.
- Mens JM. Correlation of joint involvement in rheumatoid arthritis and in ankylosing spondylitis with the synovial: cartilaginous surface ratio of various joints. *Arthritis Rheum*. 1987;30:359–360.
- Jackson CG, Chess RL, Ward JR. A case of rheumatoid nodule formation within the central nervous system and review of the literature. *J Rheumatol*. 1984;11:237–240.
- Mannerfelt L. Surgical treatment of the rheumatoid wrist and aspects of the natural course when untreated. *Clin Rheum Dis*. 1984;10:549–570.
- Brook A, Corbett M. Radiographic changes in early rheumatoid disease. *Ann Rheum Dis*. 1977;36:71–73.
- Ruby LK, Cassidy D. Evaluation and treatment of the rheumatoid wrist. In: Watson HK, Weinzwieg J, eds. *The Wrist*. Philadelphia: Lippincott Williams & Wilkins; 2001:645–657.
- Hindley CJ, Stanley JK. The rheumatoid wrist: patterns of disease progression. A review of 50 wrists. *J Hand Surg [Br]*. 1991;16:275–279.
- Muramatsu K, Ihara K, Tanaka H, et al. Carpal instability in rheumatoid wrists. *Rheumatol Int*. 2004;24:34–36.
- Pirela-Cruz MA, Firoozbakhsh K, Moneim MS. Ulnar translation of the carpus in rheumatoid arthritis: an analysis of five determination methods. *J Hand Surg Am*. 1993;18:299–306.
- Linscheid RL, Dobyns JH. Rheumatoid arthritis of the wrist. *Orthop Clin North Am*. 1971;2:649–665.
- Spinner M, Kaplan EB. Extensor carpi ulnaris. Its relationship to the stability of the distal radio-ulnar joint. *Clin Orthop Relat Res*. 1970;68:124–129.
- Flury MP, Herren DB, Simmen BR. Rheumatoid arthritis of the wrist. Classification related to the natural course. *Clin Orthop Relat Res*. 1999;366:72–77. *The authors present a classification system for the rheumatoid wrist that is now commonly used and frequently referenced. This classification system uses radiologic indicators to divide wrists into those that are stable (types I and II) and those that are unstable (type III).*
- Vaughan-Jackson OJ. Attrition ruptures of the tendons in the rheumatoid hand. *J Bone Joint Surg*. 1958;40A:1431. *The brief paper by*

Vaughan-Jackson is a classic original description of extensor tendon attrition ruptures.

43. Mannerfelt L, Norman O. Attrition ruptures of flexor tendons in rheumatoid arthritis caused by bony spurs in the carpal tunnel. A clinical and radiological study. *J Bone Joint Surg Br.* 1969;51:270–277.
44. Flatt AE. Some pathomechanics of ulnar drift. *Plast Reconstr Surg.* 1966;37:295–303.
45. McMaster M. The natural history of the rheumatoid metacarpophalangeal joint. *J Bone Joint Surg Br.* 1972;54:687–697.
46. Littler JW. The finger extensor mechanism. *Surg Clin North Am.* 1967;47:415–432.
47. Watson HK, Weinzwieg J. Principles of rheumatoid arthritis. In: Watson HK, Weinzwieg J, eds. *The Wrist*. Philadelphia: Lippincott Williams & Wilkins; 2001:639–644.
48. Shapiro JS. The wrist in rheumatoid arthritis. *Hand Clin.* 1996;12:477–498.
49. Flatt AE. *The Care of the Rheumatoid Hand*. St. Louis: Mosby; 1974. An excellent historical overview of surgical treatments for the rheumatoid hand, as well as descriptions of the mechanics of the disease process.
50. Shapiro JS, Heijna W, Nasatir S, et al. The relationship of wrist motion to ulnar phalangeal drift in the rheumatoid patient. *Hand.* 1971;3:68–75.
51. Nalebuff EA. Surgical treatment of tendon rupture in the rheumatoid hand. *Surg Clin North Am.* 1969;49:811–822. A detailed description of the surgical management of tendon ruptures by a hand surgeon with extensive experience in treating patients with rheumatoid arthritis.
52. Howard LD Jr. Surgical treatment of rheumatic tenosynovitis. *Am J Surg.* 1955;89:1163–1168.
53. Stellbrink G. Trigger finger syndrome in rheumatoid arthritis not caused by flexor tendon nodules. *Hand.* 1971;3:76–79.
54. Vetter TR. Acute airway obstruction due to arytenoiditis in a child with juvenile rheumatoid arthritis. *Anesth Analg.* 1994;79:1198–1200.
55. Urban MK. Anaesthesia for orthopedic surgery. In: Miller RD, Eriksson LJ, Fleisher LA, et al., eds. *Miller's Anesthesia*. Philadelphia: Churchill Livingstone; 2009.
56. Allieu Y, Lussiez B, Asencio G. Long-term results of surgical synovectomies of the rheumatoid wrist. Apropos of 60 cases. *Rev Chir Orthop Reparatrice Appar Mot.* 1989;75:172–178.
57. Ishikawa H, Hanyu T, Tajima T. Rheumatoid wrists treated with synovectomy of the extensor tendons and the wrist joint combined with a Darrach procedure. *J Hand Surg Am.* 1992;17:1109–1117.
58. Clayton ML. Surgical treatment at the wrist in rheumatoid arthritis: a review of thirty-seven patients. *J Bone Joint Surg Am.* 1965;47:741–750.
59. Mannerfelt L, Malmsten M. Arthrodesis of the wrist in rheumatoid arthritis. A technique without external fixation. *Scand J Plast Reconstr Surg.* 1971;5:124–130.
60. Dolphin JA. Extensor tenotomy for chronic boutonniere deformity of the finger; report of two cases. *J Bone Joint Surg Am.* 1965;47:161–164.
61. Krueger G, Ellis CN. Psoriasis – recent advances in understanding its pathogenesis and treatment. *J Am Acad Dermatol.* 2005;53:S94–S100.
62. Pritchard MH. Gout and pseudogout: crystal-induced arthropathies. *Clin Endocrinol Metab.* 1981;10:141–161.
63. Macmullan P, McCarthy G. Treatment and management of pseudogout: insights for the clinician. *Ther Adv Musculoskelet Dis.* 2012;4:121–131.
64. Hu HJ, Liao MY, Xu LY. Clinical utility of dual-energy CT for gout diagnosis. *Clin Imaging.* 2015;39:880–885.

20

Osteoarthritis in the hand and wrist

Paige M. Fox, Brian T. Carlsen, and Steven L. Moran

 Access video content for this chapter online at expertconsult.com

SYNOPSIS

- Osteoarthritis is characterized by a loss of articular cartilage.
- The development of osteoarthritis is a dynamic process that represents an imbalance between destruction and repair of the articular cartilage. It can result from trauma, such as an intra-articular fracture or a ligamentous injury that results in abnormal load-bearing characteristics, or it can be idiopathic without an identifiable cause.
- Osteoarthritis can affect the entire joint, including the articular cartilage, subchondral bone, ligaments, joint capsule, synovial membrane, and periarticular muscles and tendons.
- Patients with osteoarthritis seek treatment because of pain, loss of function, or both. However, there is often a poor correlation between the patient's symptoms and radiographic findings.
- Osteoarthritis is more common in women. In the hand, the distal interphalangeal (DIP) joints of the fingers and the carpometacarpal (CMC) joint of the thumb are most commonly affected, followed in order by the finger proximal interphalangeal (PIP) and metacarpophalangeal (MP) joints.
- Radiocarpal arthritis is most commonly a result of traumatic injury and follows a regular progression over time as seen in scapholunate advanced collapse (SLAC) and scaphoid nonunion advanced collapse (SNAC) wrist arthritis patterns.
- Treatment of arthritis is directed toward alleviating pain and improving function.
- Treatment strategies include operative and non-operative treatments. Non-operative treatments include lifestyle modification, hot and cold therapy, splinting, oral or topical non-steroidal anti-inflammatory drugs (NSAIDs), and alternative therapies (diet modification, ultrasound, transcutaneous electrical nerve stimulation (TENS), and acupuncture).
- Surgical management of osteoarthritis includes load-altering procedures, joint debridement and/or synovectomy, arthrodesis, and arthroplasty procedures.
- The appropriate type of operation varies depending on multiple factors including patient age, demands placed on the joint, the requirement for motion to perform one's activities of daily living or job requirements, patient desires, and the likelihood of success of restoring function and alleviating pain.



Access the Historical perspective section online at

<http://www.expertconsult.com>

Introduction/epidemiology

- Osteoarthritis (OA) is a heterogeneous disease that includes conditions with different etiology, distribution, heredity, clinical presentation, and progression.
- It is characterized by mechanical and biological events that alter the homeostatic relationship of degradation and repair of the surrounding articular tissues.
- Although all joint tissues are involved, including the subchondral bone, damage to the articular cartilage is the hallmark of the disease.
- Osteoarthritis is the most common rheumatologic disorder in the world. It affects all races, sexes, and age groups.
- It is a major cause of adult morbidity. It is the cause of disability in 10% of the population over age 60.³
- The age-standardized prevalence of hand osteoarthritis was 44.2% in women and 37.7% in men in the Framingham OA Study.⁴ DIP, PIP and thumb base arthritis were more prevalent in women while metacarpophalangeal (MCP) and wrist OA were more frequent in men.
- It is estimated that 21% of the population or 46.4 million Americans in 2005 were affected by osteoarthritis.⁵
- Symptoms of OA may include joint pain, swelling, tenderness, stiffness, and crepitus. OA is typically considered a non-inflammatory condition to differentiate it from the inflammatory arthropathies such as rheumatoid and psoriatic arthritis.
- There is no cure for osteoarthritis and no effective method of altering the progression of the disease process.

Historical perspective

Osteoarthritis is evident across species, with evidence in other mammals, amphibians, certain species of birds, and even ancient dinosaurs. The disease is likely as old as man, with evidence of its existence in prehistoric man from 2 million years ago.^{1,2} The disease is considered synonymous with aging.

This chapter will review the presentation, evaluation, and treatments of osteoarthritis as it presents in the various joints of the hand and wrist. Both non-operative and operative approaches will be discussed, with particular attention to the indications and contraindications of specific treatments.

Basic science/disease process

OA is characterized by a loss of articular cartilage. It can be either primary or secondary in nature. *Primary OA* (idiopathic OA) occurs in the absence of antecedent trauma. The pathogenesis is likely heterogeneous; genetics, joint shape and underlying endocrine abnormalities can contribute. *Secondary OA* is the result of direct trauma to the joint and can occur as a result of fracture, dislocation, or infection.

In order to understand the pathophysiology of osteoarthritis, one must first consider the normal anatomy and biochemistry of the synovial joint. Normal articular cartilage consists of an extensive extracellular matrix composed primarily of proteoglycans, collagens (predominantly type II), and water. While chondrocytes compose only 1% of the volume of the cartilage extracellular matrix, they are responsible for maintaining its architecture and composition. The matrix is composed primarily of collagen, proteoglycans, proteins, and glycoproteins. Cartilage proteoglycans belong to two major classes: large aggregating molecules (aggrecans), and smaller non-aggregating molecules. The aggrecan molecule consists of a central protein core with about 100 glycosaminoglycan (GAG) side branches composed of repeating, negatively charged disaccharides. Aggrecan molecules form proteoglycan aggregates by linking with a long central hyaluronan molecule. The result is a very large molecule with 10^5 negatively charged groups. These groups fill voids in the cartilage framework and create a high osmotic pressure in the framework, providing a stiff construct resistant to compression. Non-aggregating proteoglycans and other matrix proteins serve a variety of functions in the matrix including framework stabilization, regulation of fibrillogenesis, and matrix metabolism through chondrocyte interactions.⁶ Such molecules include biglycan, decorin, fibromodulin, chondroadherin, cartilage oligomatrix protein, and fibronectin. The interstitial fluid provides an important function in terms of altering the cartilage friction coefficient with changes in pressure (load).⁷

Microscopically, articular cartilage can be divided into four zones based on the cartilage matrix composition and architecture.⁸ Zone 1 is the most superficial zone and is called the superficial or tangential zone. Here, the chondrocytes are flat and oriented parallel to the articular surface. The collagen is condensed and proteoglycans are sparse. The thin collagen fibers are arranged parallel to the articular surface. This construct resists shear force and has been compared to a “tough skin” that protects the underlying intermediate and deep zones.⁹ In zone 2, the intermediate zone, the chondrocytes are isolated or in isogenous groups and are surrounded by oblique collagen fibers. This zone is the thickest and is rich in proteoglycans. Proteoglycans are complex macromolecules composed of a protein core with attached glycosaminoglycan chains (chondroitin sulfate and keratan sulfate). The negative charge of the glycosaminoglycans accounts for the hydration and large swelling pressure of cartilage.¹⁰ Zone 3 is the radiate layer and includes large, round chondrocytes oriented



Fig. 20.1 Histological section of (A) normal and (B) abnormal cartilage. (A) Normal joint articular cartilage is connected to the bone through a layer of calcified cartilage. The basophilic line, or blue line, histologically separates the articular cartilage from calcified cartilage. The calcified cartilage receives nutrients through the epiphyseal vessel; the articular cartilage receives nutrients primarily through diffusion from the overlying joint fluid. (B) In joints affected by osteoarthritis, there is fraying in the superficial cartilage and decrease in articular cartilage thickness.

vertically with intervening radial collagen fibers. Zone 4 is the deepest layer or calcified layer. It lies adjacent to the subchondral bone and resists shear stress between cartilage and bone.⁹ Between zone 3 and zone 4 is the *tidemark* (Fig. 20.1). With age, articular cartilage becomes thin and there is relative advancement of the tidemark zone that occurs together with replacement of calcified cartilage with bone.¹¹ The result of this anatomic design is a shiny and slippery surface with a friction coefficient lower than any prosthetic replacement. This remarkable construct is able to withstand millions of loading cycles each year with forces that may reach up to 18 MPa.¹²

In the healthy, homeostatic state, the chondrocyte responds to the mechanical and biochemical environment by altering the synthesis and degradation its macromolecules. Two groups of enzymes function to degrade the extracellular matrix: matrix metalloproteinases (MMPs) and a *disintegrin* and metalloproteinase with *thrombospondin*-like motifs (ADAMTS). MMPs break down collagen¹³ and ADAMTS functions to break down aggrecan. The main MMP in cartilage is MMP-13 that breaks down type II collagen and the main ADAMTS in cartilage are ADAMTS-4 and ADAMTS-5.^{14,15}

The regulation of matrix degradation and synthesis is poorly understood, but cytokines play an important role in both anabolic and catabolic pathways.^{8,16,17} The interplay between these cytokines is complex. Anabolic activity seems to be a response of the structural needs of the matrix, as may occur in response to mechanical loading. Cytokines involved in the anabolic pathway include transforming growth factor-beta (TGF- β) and insulin-dependent growth factor I.⁸ Catabolism within the matrix involves a complex cascade that includes interleukin-1, stromelysin, aggrecanase, and plasmin, in response to stimulation or inhibition by TGF- β , tumor necrosis factor, tissue inhibitors of metalloproteinases, tissue plasminogen activator, plasminogen activator inhibitor, and other molecules.⁸

Pathophysiology

Osteoarthritis involves all of the tissues around the synovial joint, including the articular cartilage, joint capsule, ligaments, subchondral bone, metaphyseal bone, and the muscles acting across the joint. However, the principle pathological change is that of loss of articular cartilage. Other changes are noted such as subchondral sclerosis, subchondral cyst formation, and marginal osteophytes.^{8,18,19}

The earliest microscopic findings of OA are that of fibrillation and fraying of the superficial zone cartilage along with decreased staining for proteoglycans in the superficial and transitional zones and in-growth of blood vessels into the tidemark from subchondral bone (Fig. 20.1B).⁸ Progression of the disease leads to clefts in the articular surface, fracture of the superficial cartilage, and decrease in cartilage thickness. Enzyme activation leads to further destruction of the cartilage leading to complete loss of articular cartilage exposing dense and eburnated bone.⁸

Associated with these changes of the cartilage are alterations in the subchondral bone, specifically an increased density. This increased density can be seen as a sclerotic line on radiograph. These changes may be more pronounced at the joint periphery where the new bone formation may be so exuberant as to produce osteophytes. The exact pathophysiology of osteophyte formation is not known; however, it may be related to the release of anabolic cytokines from the matrix that stimulate the abnormal bone and cartilage growth.^{20,21}

The changes involving the joint also affect the periarticular tissues. The synovial membrane becomes inflamed as fragments of cartilage become embedded within them.²² As the joint loses motion due to mechanical factors and pain, the capsule and surrounding ligaments become stiff due to myotendinous contraction and ongoing edema. The lack of motion and use can lead to muscle atrophy.⁸

Diagnosis

The most common symptoms of OA are pain, swelling, and stiffness of the affected joint. Pain is the primary feature of the condition and is the focus of treatment. Examination confirms swelling, tenderness, and limited range of motion. In the case of post-traumatic arthritis, there may be joint instability associated with previous ligamentous injury.

Symptoms can dissipate with time and are not always correlated with the radiographic severity of disease.



Fig. 20.2 Posteroanterior radiograph of the hand of a 69-year-old male showing typical bony changes seen in advanced osteoarthritis. Osteophyte formation is seen at the distal interphalangeal and proximal interphalangeal joints and trapeziometacarpal joint of the thumb. Joint narrowing is seen within the fingers as well as evidence of subchondral sclerosis.

Osteoarthritis may also be present in the absence of pain. In a classic study looking at arthritis among miners in their 40s, Kellgren and Lawrence found that only 24% of miners with radiographic OA had pain and 8% of radiographically normal knees had pain.

Radiographs are the most helpful test in making the diagnosis. In primary and secondary OA, joint spaces are narrowed radiographically due to a loss of radiolucent articular cartilage. Subchondral bone remodeling can manifest as increased density within the subchondral bone or sclerosis. Osteophytes and loose bodies may also be present (Fig. 20.2).

In 1957, Kellgren and Lawrence described a grading system for the radiographic appearance of OA.²³ Findings considered included: (1) the presence of peripheral osteophytes; (2) periarticular ossicles (commonly found in association with DIP and PIP joints); (3) narrowing of joint cartilage and subchondral sclerosis; (4) small pseudocystic areas with sclerotic walls, typically in the subchondral bone; and (5) altered shape of the bone ends. The authors then classified the arthritis into five grades²³:

1. Normal joint
2. Doubtful
3. Minimal (but definitely present)
4. Moderate
5. Severe.

This system has been broadly applied for grading osteoarthritis in various joints; unfortunately the grading system can be ambiguous as there are no specific cut-off criteria between the grades. In a recent analysis by Schiphof and colleagues, the




Fig. 20.3 Typical appearance of a mucous cyst in this 67-year-old female with distal interphalangeal joint osteoarthritis. (A) A mass is palpable over the joint. (B) The cyst is clearly seen at the time of surgical exploration. (C) Mucous cysts may also present with nail grooving, which results from pressure on the germinal and sterile matrix of the nail.

authors note inconsistency in the application of the grading system within multiple cohort studies and have recommended the development of a single validated classification system.²⁴

Management of OA of the fingers

Hand and finger arthritis is one of the most common presentations of primary OA. Its onset is insidious with progressive aesthetic deformity followed by pain and functional limitation. Epidemiological studies of the joint-specific prevalence of hand arthritis consistently show the distal interphalangeal joint to be the site most frequently affected by OA, followed by the thumb CMC joint, and the PIP joint.²⁵ These studies typically defined OA based on the radiographic features described by Kellgren and Lawrence, which include the presence of osteophytes, joint space narrowing, subchondral sclerosis, and subchondral cysts.²³

Distal interphalangeal joint (DIP) arthritis

Diagnosis

Osteoarthritis of the DIP joint is common and affects females more frequently than males. Clinically, patients present with enlarged joints and hard, knobby protuberances overlying the DIP joints of multiple fingers. These, so called *Heberden's nodes*, are pathognomonic for the condition and are attributed to osteophyte formation with overlying soft-tissue thickening. These should be differentiated from a *mucous*

cyst. A mucous cyst is a dorsal synovial cyst, often limited to a single digit. They are often associated with lateral deviation of the distal phalanx, and a limited range of motion (Fig. 20.3).

Radiographically, joint space narrowing and osteophyte formation are common findings. However, the radiographic appearance of the DIP is not consistently associated with the patient's symptoms. Frequently, the only significant concern for the patient is the aesthetic appearance. Even patients with severe DIP deformity may have little pain or functional impairment and the presence of Heberden's nodes alone is not generally considered an indication for surgery.

Indications for surgery

The treatment of DIP OA is dictated by the severity of pain and functional limitation. Splinting allows the joint to be rested and protected from minor trauma. Splinting used in conjunction with oral or topical anti-inflammatory medication and lifestyle modification are the mainstays of non-operative treatment. This approach is usually sufficient to treat acute exacerbations of pain and swelling. Steroid injections can be attempted for temporary pain relief but are difficult to administer in such a small joint, and multiple repeated injections are not a convenient as a long-term treatment plan. When intractable pain, deformity, and misalignment are severe enough to interfere with precision pinch, oppositional pinch, and global hand function, surgery is indicated.

The surgical option for treatment of severe DIP arthritis is essentially limited to arthrodesis, which is well tolerated in the DIP position. Although implant arthroplasty is technically feasible, it is not commonly performed because of concerns of long-term joint instability.^{26–30}

Biomechanical effects of DIP fusion

The normal range of motion at the DIP joint is 0–60°; however, only 15% of digital flexion occurs at the DIP and the joint only contributes 3% of the overall flexion arc of the whole finger.³¹ Thus, of all finger joint fusions, DIP arthrodesis confers the least detrimental impact to hand motion, and is the well tolerated. One study of splint-simulated DIP fusion found a 20% reduction in grip strength, which was attributed to the *quadriggera effect*, as a result of the limited excursion of the flexor digitorum profundus (FDP) tendon in the fused digit.³² Significant loss of grip strength has not been shown in clinical studies.

DIP arthrodesis

Indications

The single most common indication for arthrodesis is intractable pain at the DIP joint that has failed all conservative treatments. Other less common indications include chronic mallet deformity, missed flexor tendon avulsions, or distal phalanx nonunions.

Techniques

A multitude of fixation techniques have been described,³³ including interosseous wiring,³⁴ percutaneous pinning, tension band wiring,^{35,36} bio-resorbable pinning,³⁷ plating,³⁸ oblique lag screw fixation,³⁹ and axial compression screw fixation.^{33,40} Regardless of the technique chosen, the joint is prepared in a similar manner and the requirements for a successful outcome are: (1) full apposition of the cancellous bone surfaces; (2) preservation of distal phalanx bone stock to allow for hardware purchase; (3) fusion in approximately 5–10° of flexion if possible; and (4) stable fixation.

Most techniques utilize a transverse skin incision overlying the joint. Oblique or axial extensions are made proximally and distally and skin flaps are raised to complete an H-shaped exposure centered over the joint. Alternatively, a midlateral or a Y-shaped dorsal incision can be used. Specific care should be taken to avoid injury to the germinal nail matrix located just distal to the extensor insertion. The extensor tendon and joint capsule are sharply divided in a transverse orientation, the collateral ligaments are divided, and the joint is maximally flexed to allow access to the articular surfaces.

With the base of the distal phalanx and the condyles of the middle phalanx exposed, a rongeur is used to remove dorsal and lateral osteophytes. The articular surfaces are decorticated until cancellous bone is visualized. Alternatively, osteotomies can be created with a small oscillating saw to achieve precise apposition of the cancellous bone. If power saws or burrs are to be utilized, copious irrigation should be maintained throughout the cutting process to avoid the risk of thermally induced osteonecrosis, which can elevate the risk of nonunion postoperatively.⁴¹

Interosseous wiring

Interosseous wiring involves securing the distal and middle phalanx together by means of one or two dental wires passed through bone tunnels. Interosseous wiring can be used to achieve some compression of the joint and is usually used in

conjunction with K-wires for greater stability. Zavitsanos *et al.* described a technique which allows the K-wires to be completely buried, minimizing the risk of infection.³⁴

K-wire fixation

After the joint is prepared, two crossed 0.045-inch Kirschner wires are passed across the joint. Alternatively, an axial K-wire and a single oblique wire can be used. A minimum of two wires needs to be used to prevent rotation. The wires are typically cut beneath the skin at the fingertip. This enables the patient to continue to use the finger in activities of daily living. The DIP joint is immobilized in a splint to protect the fusion. Once union is documented radiographically, the wires can be removed. Wire removal can be done in the office under digital block anesthesia.

Tension band wiring

With the joint surfaces prepared, two 0.045-inch K-wires are placed parallel across the joint. Distally, the pins are buried in the distal volar cortex of the distal phalanx while proximally the pins exit on the dorsal cortex of the middle phalanx. A transverse canal is made dorsal to the wires in the proximal distal phalanx. A 28-gauge dental wire is passed through this canal and secured proximally around the K-wires exiting on the dorsal proximal phalanx in a figure-of-eight fashion. The dental wire is twisted and secured and the K-wires are bent to assure the construct is as low profile as possible. The tension band construct is remarkably stable and early motion may be permitted in selected patients. If the hardware is bothersome, it can be removed after bony union.

Clinical tips

Tension band wiring

- Take down the collateral ligaments for clear visualization of the entire joint.
- A rongeur or small saw can be used to prepare the joint for fusion.
- K-wires can be placed retrograde from the joint into the middle phalanx to assure an appropriate trajectory that will capture a sufficient portion of the distal phalanx.
- After confirming the correct length of the parallel K-wires, back them out of the bone slightly, bend, and cut to length prior to gently tapping back into place. This will allow for better coaptation to the bone and make hardware irritation less likely.

Axial compression screw

A single axial compression screw (Fig. 20.4) can be used to reliably achieve DIP joint fusion. A traditional lag screw technique can be used but will result in prominent hardware at the fingertip and is discouraged. Buried headless compression screws are preferred. The technique for the use of a threaded headless compression screw initially involves preparation of the joint surfaces followed by the placement of an antegrade axial K-wire through the distal phalanx exiting at the hyponychium. The bone surfaces are then coapted in the position of fusion and the same wire is drilled retrograde back into the middle phalanx. The position of the wire and




Fig. 20.4 (A) Technique for fusion of distal interphalangeal (DIP) joint using axial compression screw. In preparation for fusion, all articular cartilage needs to be removed from the joint surface. A K-wire is then driven retrograde out of the distal phalanx. The joint is then reduced in preparation for fusion and the wire is then driven across the DIP joint. A cannulated drill is used to prepare the bones for screw placement. The screw may then be placed over the wire to complete the fusion. **(B)** Final position of screw within joint. **(C)** DIP fusion may also be accomplished with the use of K-wires alone or tension band technique.

arthrodesis are checked fluoroscopically, and a cannulated drill is used to prepare the channel for screw placement. The appropriate screw size is determined through fluoroscopic measurement, and a cannulated, fully threaded, self-tapping screw is inserted in a retrograde fashion to complete the fusion (see Fig. 20.4).

The screw should be long enough to engage the cortical isthmus of the middle phalanx. Occasionally, the intramedullary canal of the middle phalanx is too wide for the thread to engage the endosteal cortex even at the isthmus (e.g.,

thumb), and the chances of a stable construct are reduced. Additionally, specific attention should be paid to the antero-posterior (narrowest) diameter of the distal phalanx to ensure that the screw thread diameter is not greater than this measurement, otherwise dorsal fracturing and nail bed deformity can occur.⁴²

The major advantages of this technique over other methods of DIP fusion are buried hardware and stable fixation. Immobilization time with the use of compression screws has been shown to be significantly shorter when compared to other

techniques for DIP fusion. Patients may often be splinted for only 1–3 weeks, allowing patients to return to work earlier.⁴³ One disadvantage of this technique is the difficulty in achieving the optimal prehensile position at the DIP as the joint is typically fused straight due to the conical shape of the screw. Other reported complications have included a single case of skin necrosis of the fingertip requiring secondary amputation⁴⁴; this was likely due to unrecognized prominent hardware.

Complications of DIP fusion

Infection

Traditional fixation techniques for small joint arthrodesis include interosseous wiring, crossed K-wires, or a combination of these techniques. The rate of deep infection and osteomyelitis with these techniques remains up to 20% in some studies.⁴⁵ Surgeons who prefer this technique should consider burying the K-wires during the consolidation phase, as infection and nonunion rates are much lower with buried techniques are utilized.⁴⁶

Nonunion

Reported nonunion rates for DIP arthrodesis range from 0–20%. Several studies have reported low rates of nonunion with screw techniques^{44,45,47–49} as well as traditional techniques⁴⁶; however, a clear relationship between fixation technique and the rate of nonunion has not been shown for DIP arthrodesis.⁴⁵

Kirschner wire and interosseous wire techniques produce significantly less compression across the fusion site than compression screw techniques and compression itself has been shown to achieve more rapid fusion. In a biomechanical cadaver study comparing fixation techniques, the use of a single buried axial compression screw (Herbert screw) was shown to be superior in terms of fixation strength when compared to a combined K-wire/tension band technique.⁴² Despite this biomechanical study, retrospective clinical studies have noted similar nonunion rates when comparing compression screws, interosseous wiring, and crossed K-wires techniques; it is thought that nonunion rates most closely correlate with the amount cortical bone and condition of the bone stock at the time of operative procedure.⁴⁵

DIP arthroplasty

Distal interphalangeal joint arthroplasty is an uncommon procedure with few indications. The obvious advantage is maintained range of motion of the DIP, which may be beneficial in selected cases, e.g., in professional musicians.³⁰ There are few published series and these all report on the use of silicone interposition implants.^{27–29} The largest series reported 38 DIP arthroplasties of which 10% were removed by 10 years. The average range of DIP motion was 33° with an average extension lag of 12°.²⁸

Mucous cyst

Dorsal synovial cysts are commonly associated with DIP arthritis and develop in response to irritation of the joint by marginal osteophytes (see Fig. 20.3). Cysts slowly expand,

damaging the germinal matrix, resulting in nail deformity and nail grooving. Progressive thinning of the overlying skin and recurrent inflammation are also common. Infection can be troublesome, as communication with the joint risks the development of septic arthritis and recurrently symptomatic cysts should be removed surgically.

Needle aspiration of the mucous cyst with subsequent corticosteroid injection of the DIP joint is appealing because it can be performed in the office setting with minimal morbidity.^{50–52} Typically, the cyst is too small for effective needle aspiration and instead, multiple punctures are made with a 25-gauge needle and manual expression of the cyst fluid is performed. The joint may then be injected with a lidocaine and corticosteroid solution and wrapped snugly for several days. This technique has been associated with a 60% resolution of the cyst.⁵⁰ However, one must observe careful sterile technique to minimize chance of infection into the joint space.

If the cyst recurs surgical excision can be performed. Our preferred surgical technique consists of marking the margins of the cyst under loupe magnification followed by excision of the cyst and overlying attenuated skin. The underlying inflamed synovium should be debrided and associated dorsal and marginal osteophytes removed. Specific attention should be paid to preservation of the extensor insertion, which can be challenging as it may be significantly attenuated. Skin closure may require the use of local skin flaps in rare circumstances.^{50,53–55}

Fritz *et al.* reported the results of surgical excision of 86 mucous cysts. Nail deformities were present in 29% of patients preoperatively.⁵⁶ Postoperative loss of extension of 5–20° at the interphalangeal (IP) or DIP joints was seen in 17% of patients. One patient developed a superficial infection and two developed a DIP pyarthrosis, eventually requiring DIP arthrodesis. A total of 7% of patients without preoperative nail deformity developed one postoperatively; however, 60% of preoperative nail deformities were improved by the procedure. Recurrence was seen in 3% of cases and other complications included persistent swelling, pain, numbness, stiffness, and radial or ulnar deviation at the DIP joint.

Proximal interphalangeal (PIP) joint arthritis

Within the hand, the PIP joint is the third most frequently affected by OA. The joint is more commonly affected in females.²⁵ The PIP joint has been described as the “functional locus of the finger” as it produces 85% of intrinsic digital flexion and contributes 20% to the overall arc of finger motion.⁵⁷ Despite this, a full range of motion is not absolutely necessary for good hand function, and a 45–90° flexion arc allows for most activities.

As in DIP arthritis, PIP joints affected by OA are often enlarged and painful. Patients will complain of their inability to wear or remove rings from the affected fingers. *Bouchard's nodes* are pathognomonic for PIP OA and are bony protuberances at the joint, analogous to Heberden's nodes at the DIP joint. Range of motion at the PIP joint tends to be preserved until late in the disease process. Radiographic findings include joint space narrowing, subchondral sclerosis, and osteophytes (see Fig. 20.2).

Management

Patients with occasional or minor symptoms are medicated with oral or topical non-steroidal anti-inflammatory drugs. Resting the joint by splinting in *extension* can be used to decrease pain in acute exacerbations. Intra-articular steroid injections can also be used to decrease pain but repeated injections are impractical for the long-term management of severely symptomatic patients. When non-operative management strategies are insufficient to control the patient's symptoms, PIP joint OA is usually treated surgically, with either arthrodesis or implant arthroplasty. Vascularized joint transfer is technically feasible but uncommonly practiced due to significant donor site morbidity and inferior outcomes when compared with implant arthroplasty.⁵⁸⁻⁶¹

The decision for PIP arthrodesis or arthroplasty is dictated by the patient's functional needs, desires to preserve PIP motion, and the requirements for lateral stability at the joint. The ulnar three digits are important for generating grip strength. Maximal grip strength requires almost full PIP flexion to avoid the quadriga effect. The index finger's relatively independent FDP function does not impose a significant quadriga effect on the remaining digits during grasp. In comparison, the index finger is used to generate oppositional and adduction pinch strength, which requires PIP lateral stability but little PIP motion if metacarpophalangeal joint motion is preserved. Therefore, the decision for arthrodesis versus arthroplasty may be different for each digit involved. For example, arthrodesis of the index finger PIP joint provides finger stability for pinch and is well tolerated; however, for the ring and small finger PIP joints, implant arthroplasty may be preferred, as PIP joint motion in these digits is important for grip function and strength. If fusion is to be performed on the PIP joints of the ulnar three digits, care must be taken in placing the joints in enough flexion to preserve grip strength. A significant decrease in grip strength occurs when the PIP joint of the small finger is fused in less than 45° of flexion, and when the PIP joint of the middle and ring fingers are fused in less than 60° of flexion.⁶²

PIP arthrodesis

PIP arthrodesis can be accomplished using the same techniques as described for DIP arthrodesis. The optimal position of PIP fusion varies according to the digit, with some authors recommending 40° of flexion for index, 45° for the long, 50° for the ring and 55° for the small finger (Fig. 20.5)⁶³; however, this can be tailored according to the patient's occupation and recreational activities. Preoperative splints simulating fusion at various angles can be used to allow the patient to make a more informed decision.

Techniques

The PIP is approached dorsally through a longitudinal incision centered over the joint. The extensor tendon and joint capsule are split longitudinally and dissected radially and ulnarly. The central slip should be elevated subperiosteally off the base of the middle phalanx. The proximal origins of the collateral ligaments are divided and the joint is flexed to expose the joint surfaces. The bone ends are prepared using angled saw cuts on both phalanges. Alternatively, rongeurs or a burr can be used to create a concave-convex (cup and cone)




Fig. 20.5 Illustration of recommended fusion angles for distal interphalangeal (DIP), proximal interphalangeal (PIP), and metacarpophalangeal (MCP) joints. DIP fusion angles are often performed with 0–15° of flexion. PIP fusion angles increase as one moves from the index to the small finger, to correspond with the natural cascade of the hand. Recommended fusion angles for the PIP joint have been 40° of flexion for the index, 45° for the long, 50° of flexion for the ring, and 55° of flexion for the small. MCP fusion angles have been recommended to progress from 25° of flexion at the index to 40° of flexion at the small finger.

configuration on the opposing bone surfaces. The digit is necessarily shortened by preparation of the bone surfaces. Prolapse of the volar plate in between the bone ends may result in non union; the volar plate should be resected if this occurs. Fixation can be achieved by one of the following techniques:

Crossed K-wire technique

After preparation of the joint, two crossed 0.045-inch or larger Kirschner wires are passed obliquely across the joint in a coronal plane. Alternatively, an axial K-wire and a single oblique wire can be used. Similar to DIP fusion, the wires can be buried beneath the skin and removed once there is radiographic union. During this time, the joint is protected in an immobilizing splint.

Tension band wire technique

Tension band wiring uses a combination of K-wires and interosseous wire to achieve moderate stability and compression. After preparation of the joint, a transverse hole is drilled through the middle phalanx approximately 5 mm distal to the osteotomy and a 0.6-mm stainless steel wire is passed through the hole. Two parallel 1-mm K-wires are inserted across the joint, and left protruding through the dorsal cortex of the proximal phalanx. The steel wire is passed around the K-wires



Fig. 20.6 Lateral (A) and anteroposterior (B) radiographs of a long finger following proximal interphalangeal joint fusion using a tension band technique.

in a figure-of-eight fashion and tightened to produce compression of the construct. The wire ends and K-wires should be cut short and manipulated to lie flat on the dorsal cortex and prevent extensor tendon attrition. (Fig. 20.6). The dorsal soft tissues are closed and a splint is applied. A splint is worn for protection until radiographic union.

Compression screw

Arthrodesis of the PIP joint can be accomplished by antegrade insertion of a headless compression screw across the prepared joint (Fig. 20.7A). A K-wire is used to start a hole in the dorsal cortex of the proximal phalanx and oriented obliquely in a sagittal plane. The angle of insertion should correspond to the desired angle of fusion and the wire is inserted antegrade across the joint, into the middle phalanx. The position of the entry hole in the proximal phalanx should be at least 6 or 7 mm proximal to the joint to prevent fragmentation of the dorsal cortex, which can be a complication of this technique. The K-wire is used as a guide wire for the cannulated drill sequence required for the particular screw being used (as described above for DIP arthrodesis). Fluoroscopy is used to check alignment, and to choose an appropriately sized screw that is then inserted in an antegrade fashion, with the assistant holding manual compression of the bone surfaces. The thread should reach the cortical isthmus of the middle phalanx to achieve endosteal purchase. The dorsal soft tissues are closed and a bulky splint is applied. A thermoplastic splint can replace this after 7 days, which should be worn for approximately 3 weeks. The major advantage of this method of fixation is the substantial stability of the construct, which allows early mobilization, and less likelihood of hand stiffness.

Plating

For severely osteoporotic bone, or for salvage of failed fusion attempts using other methods, PIP arthrodesis may be obtained using mini-plates (1.7 mm up to 2.7 mm). Newer plate designs allow for compression or locking screw




Fig. 20.7 Example of a proximal interphalangeal joint fusion with (A) headless compression screw and (B) dorsal plating technique.

placement, which can significantly improve fixation in severely osteoporotic bone. Plates are applied using standard AO technique. Pre-contouring of the plates is required to achieve the appropriate angle (Fig. 20.7B).

PIP arthroplasty

Arthroplasty will allow for some preservation of joint motion. Arthroplasty techniques consist of soft-tissue interposition, silicone spacers, and a variety of constrained and unconstrained implants. Soft-tissue arthroplasties are mentioned for historical purposes but have been largely replaced by implants, silicone or other. Techniques for soft-tissue arthroplasty have included resection of the head of the proximal phalanx,⁶⁴ volar plate interposition,⁶⁵ and perichondrial transplant arthroplasty.^{66–68}

Currently, there are two popular approaches to implant arthroplasty – interposition silicone spacers including the Swanson implant (Wright Medical Technologies, Arlington, TN) and NeuFlex implant (DePuy, Warsaw, IN); and surface replacement or total joint replacement implants such as the SR-PIP implant (Small Bone Innovations, Morrisville, PA) and the PyroCarbon PIP (Integra, Plainsboro, NJ). The success of PIP implant arthroplasty is largely dependent on the condition of the surrounding soft tissues including the collateral ligaments, tendons, and volar plate. When these structures are preserved, implant arthroplasty has a higher success rate.

Silicone interposition arthroplasty

Silicone interposition implants consist of one-piece flexible, stemmed, hinged elastomer spacers that can be used in all digits after resection arthroplasty of the PIP joint. Swanson and Niebauer first devised these implants in the 1960s. The implant consists of a single silicone unit with a tapered proximal and distal stem with a central interposed flexion region, which is dorsally offset. The implant does not function as a true joint but rather a spacer that is stabilized by the fibrous capsule, which develops around the implant. The implant glides or “pistons” within the medullary canals during movement and this was originally believed to disperse forces over a broader surface area potentiating the life of the implant. Newer implant designs have maintained the same general concept but have incorporated a 30° pre-flexed hinge between the proximal and distal stems to facilitate finger flexion.

Technique

The PIP joint can be exposed by one of three surgical approaches – dorsally, laterally, or from the volar surface. We prefer a longitudinal dorsal approach in most cases, as it affords superior exposure to the joint and allows easier insertion of the implants. A 2–3 cm straight or curved dorsal incision is made over the PIP joint and continued through the center of the extensor tendon from mid-proximal phalanx until just distal to the insertion of the central slip on the middle phalanx. The two parallel halves of the central slip are then mobilized off the underlying middle phalanx. This produces radial and ulnar tendinous bands, each containing half of the central slip and a lateral band, which are allowed to sublux laterally when the middle phalanx is flexed, exposing the PIP joint. The joint is flexed to 90°, and osteophytes are removed as necessary. An alternative exposure of the PIP joint

involves the use of Chamay technique, where a distally based flap of the extensor mechanism is elevated from proximal to distal (Fig. 20.8). The flap is then repaired at the completion of the surgical procedure.⁶⁹

A micro-oscillating saw is used to make a transverse osteotomy at the distal-most portion of the flare of the proximal phalanx, just proximal to the condylar insertion of the collateral ligaments. In general, no resection of the base of the middle phalanx is necessary. Specially designed awls and broaches (specific to implant system used) are used both proximally and distally to open the intramedullary canal to allow the largest size implant. After a trial implant is inserted, the joint is taken through a range of motion to assess stability and fit and the definitive implant is placed. The soft tissues are closed and the hand and wrist are immobilized in the intrinsic plus position. Within a week, the patient is provided a dynamic splint and motion is initiated in a supervised rehabilitation program.

Surface replacement arthroplasty with non-constrained implants

The first PIP joint replacement prosthesis was described in 1959 by Brannon and Klein.⁷⁰ Numerous implant designs have since been produced and many have been abandoned due to implant failure, instability or high complication rates.^{71–74} At present, the two designs available in the United States are made of metal or PyroCarbon.

Clinical tips

PIP silicone arthroplasty

- A central dorsal approach provides easy access and clear visualization of the PIP joint.
- We prefer a central incision through the extensor tendon and central slip to the Chamay approach.
- Only the cartilaginous surface of the middle phalanx needs to be removed. No formal cut is made in the middle phalanx.
- If the insertion of the central slip is disrupted during implant placement, a non-absorbable suture should be used to repair the tendon to the bone through small holes placed in the dorsal cortex of the middle phalanx prior to final implant placement.
- A minimal or no-touch technique helps decrease the risk of infection when placing the final implant. Clean smooth forceps are ideal for placing the implant.

Linscheid and Dobyns introduced the first non-constrained PIP prosthesis in 1979 and this design is still available as the SR-PIP implant.⁷⁵ The proximal component is made of a chromium–cobalt alloy with a polished articular surface, and the distal component has an ultra-high molecular weight polyethylene (UHMWPe) articular surface fixed to a titanium base and stem. The articulating surfaces are a tongue-in-groove configuration, similar to the PIP joint anatomic design. For this reason, the manufacturer has described the system as “semiconstrained.” This congruency adds to the lateral stability of the joint. The titanium stems are textured and are




Fig. 20.8 The dorsal approach to the proximal interphalangeal joint involves either a longitudinal split of the extensor mechanism or the use of the Chamay approach. **(A)** The Chamay approach involves the creation of a distally based rectangular flap of extensor tendon. **(B)** The flap is mobilized distally and preserves the attachment of the central slip at the level of the middle phalanx. **(C)** This flap may then be repaired to the surrounding extensor mechanism at the end of the procedure.

designed to “press-fit.” However, non-cemented implants have been shown to have a higher incidence of subsidence and loosening.⁷⁶

Pyrolytic carbon implants have been developed for use in the PIP joint. Pyrolytic carbon is a substance similar to graphite, which is formed by the high-temperature pyrolysis (thermal decomposition) of hydrocarbons, and their subsequent recrystallization as a surface coating. Pyrolytic carbon is used in joint arthroplasty as a 0.5–1.0 mm coating on a graphite substrate and 1% tungsten is added to produce radio-opacity. The elastic modulus of PyroCarbon (23 GPa) is a much closer match to that of cortical bone (29 GPa), than other implant systems (titanium, 105 GPa; CoCr, 230 GPa), thus it is presumed that there should be less subsidence. The pyrolytic carbon proximal interphalangeal – PyroCarbon PIP – is a non-cemented, minimally constrained, two-component, non-linked total joint replacement implant. Joint stability is achieved as a function of the complementary shape of the component surfaces, but ultimately depends on surgical preservation of the collateral ligaments and soft tissues. Like the SR-PIP arthroplasty, the device can be cemented at the surgeon’s discretion.

Both the PIP pyrolytic carbon implant system and SR-PIP arthroplasty are approved for use by the US Food and Drug

Administration (FDA) as Humanitarian Use Devices (HUD). Such devices are authorized for use in PIP joint arthroplasty when the patient:

... has soft tissue and bone that can provide adequate stabilization and fixation under high-demand loading conditions after reconstruction; and needs a revision of a failed PIP prosthesis, or has pain, limited motion, or joint subluxation/dislocation secondary to damage or destruction of the articular cartilage.

Because these devices are used for HUD purposes, their use requires Institutional Review Board (IRB) approval. However, once approved, the IRB does not have to review and approve each individual case.

Patient selection

A trial of non-operative management is recommended in all patients with PIP OA prior to discussing operative intervention. Unconstrained surface-replacement implants rely on the preservation of the collateral ligaments for stability. Patients with gross ligamentous instability or who have damaged their collateral ligaments may not be appropriate candidates for arthroplasty and would be better served with fusion. Evidence

of insufficient bone stock, inadequate intramedullary space, marked soft-tissue compromise, or ongoing active or chronic infection, are all contraindications to implant arthroplasty, and an alternative surgical option should be pursued. Patients should be informed that average joint motion following arthroplasty is only 40–60°, and joint motion may deteriorate over time. Preoperatively, true anteroposterior (AP) and lateral radiographs are obtained of each PIP joint so that joints may be templated for implant sizes. The index finger PIP joint is subject to significant lateral force during pinch maneuvers. Therefore the surgeon and the patient must discuss the increased potential for complications after index finger PIP arthroplasty.

Technique for non-constrained or semiconstrained PIP arthroplasty

Surface replacement arthroplasty of the PIP joint can be performed through either a dorsal, lateral, or volar approach. Our preference is for the dorsal approach as it provides excellent exposure of the joint and facilitates implant placement (Fig. 20.9). A 2–3 cm straight or curved dorsal incision is made over the PIP joint and continued through the center of the extensor tendon from mid-proximal phalanx until just distal

to the insertion of the central slip on the middle phalanx. The two parallel halves of the central slip are then mobilized off the underlying middle phalanx. This produces radial and ulnar tendinous bands, each containing half of the central slip and a lateral band, which are allowed to sublux laterally when the middle phalanx is flexed, exposing the PIP joint. The joint is flexed to 90°, and osteophytes are removed as necessary.

A 0.035-inch K-wire is inserted into the dorsal third of the proximal phalanx head, and fluoroscopy is used to confirm a central position in the medullary canal. A starter awl is then used to enlarge the intramedullary canal. A cutting guide is then used to create a vertical osteotomy approximately 0.5–1 mm distal to the insertion of the collateral ligaments on the head of the proximal phalanx removing the articular cartilage. Next, the proximal phalanx is broached, until the medullary canal is filled with the largest broach possible. The lateral fluoroscopic view will be the first to show the size limitations of the intramedullary canal. Once the canal has been enlarged, a matched oblique cutting guide is used to create a back cut in the proximal phalanx, congruent with the sized implant shape. A proximal trial implant can then be inserted and checked radiographically for size and alignment.




Fig. 20.9 (A) The posteroanterior (PA) radiograph of a 73-year-old woman with advanced osteoarthritis of the proximal interphalangeal (PIP) joints of the index through ring fingers, who has elected to undergo PyroCarbon arthroplasty of the index and long finger PIP joints. The arthroplasties are performed through a dorsal approach. (B) The proximal phalanx is prepared initially with the aid of a cutting guide to remove the articular surface. (C) A broach is used to prepare the canal of the proximal phalanx so that it will accept the implant. (D) A back cut is then created in the proximal phalanx so the implant can be properly seated.





Fig. 20.9, cont'd (E) The proximal component is then trialed to assess the fit and position. (F) A similar procedure is then performed on the middle phalanx. (G) PA radiographs showing results at 1 year and functional result. The ring finger PIP was not treated because it was not producing pain and still had reasonable motion (H).

Hyperflexion of the joint then exposes the middle phalanx joint surface. Preparation of the middle phalanx proceeds similarly to the proximal phalanx with the goal of inserting the largest implant possible. Due to the increased amount of cortical bone in the middle phalanx a side-cutting burr is used to facilitate implant placement. Ideally the distal implant should be the same size as the proximal implant, but implants can be mismatched one size smaller or larger if necessary. The distal trial implant is then inserted and a good press-fit is checked. Apposition of both the dorsal and volar collar of the prosthesis against the osteotomy is required for a good outcome.

Prior to final implant insertion, holes are drilled with a fine K-wire into the dorsal bony ridge on the middle phalanx and non-absorbable sutures are placed to attach the central slip back to the bone. The distal implant is inserted and impacted, followed by the proximal implant, and the central slip is reconstructed using the previously placed sutures. If the collateral ligaments have been compromised during the implant placement, collateral ligament-stabilizing sutures should be placed to prevent ulnar or radial laxity or hyperextension. The

remainder of the tenotomy is closed longitudinally and the skin is closed with non-absorbable sutures. A padded dorsal, blocking splint is applied in a neutral position.

Postoperative therapy for PIP arthroplasty

Patients must adhere to strict hand therapy follow-up for approximately 10 weeks following surgery and this should be discussed preoperatively, as poor therapy compliance will lead to poor outcome (Fig. 20.10).⁷⁷ Hyperextension of the PIP joint must be avoided at all costs, and we therefore do not pursue complete joint extension, preferring to accept a 5–10° flexion deformity, as hyperextension will lead to joint dislocation.

During the first 2 weeks postoperatively, the patient is splinted or casted in full extension and minimal motion is allowed at the PIP joint. Strict elevation is encouraged to manage swelling. The plaster splint is removed after 10–14 days and sutures are removed and the patient is allowed to start a short arc motion protocol allowing for 30° of flexion at the PIP joints. Flexion is gradually increased each week to




Fig. 20.10 The typical splints used when rehabilitating the proximal interphalangeal (PIP) joints following surface-replacement arthroplasty. The PIP joints are allowed protected flexion with passive extension for the first several weeks following surgery.

achieve a goal of 70–90° of flexion by 6 weeks. Resting splints are discontinued after 6 weeks if there is no extension lag and active flexion is encouraged with no limits. Isolated pinching, deviation, and rotation should be avoided during the rehabilitation phase. Buddy taping may be used to increase motion of stiff joints.

Outcomes and complications of PIP arthroplasty

Successful implant arthroplasty of the PIP joint affords obvious benefits over arthrodesis; however, despite multiple advancements in implant design, uniformly predictable results have been difficult to achieve.⁷⁸ The major complications from PIP arthroplasty continue to be implant failure, instability, and loss of motion. Pellegrini and Burton compared arthrodesis and silicone and metal arthroplasty in 43 patients, and noted better pinch strength in the arthrodesis group, especially in the index finger. Few revisions were necessary in the silicone arthroplasty group; however, seven patients underwent revision of the metal prosthesis in order to improve lateral stability. All of these failed and required revision, and the authors concluded that arthrodesis remains the treatment of choice for the index finger, and silicone arthroplasty for the ulnar digits.⁷⁹

Silicone implants have been used for PIP replacement for over 40 years with several large series reported in the literature. Pain relief tends to be good and the degree of functional improvement and patient satisfaction is high; however, very few series report improvement in range of motion. The reported incidence of implant fracture with silicone arthroplasty is variable, ranging from 5–44%, and rotational malalignment and lateral deviation may occur with longer follow-up.^{80–82} The first large series of silicone interposition arthroplasty was reported by Swanson in 1972.⁸³ He reviewed 148 implants and there were no major complications. The series was later expanded to report 424 PIP joint arthroplasties. In this series, complete pain relief was achieved in 98% of patients, with an average increase in the arc of PIP motion of 10°.⁸⁴ Complications included bone resorption in 1.2% of cases and implant fracture in 5%. More recently, Takigawa *et al.* reviewed 70 implants with an average follow-up of 6.5 years and reported pain relief in 70%, improvement in

extension from 32° to 18°, but no change in total active motion of the PIP joint.⁸⁵ Complications included fractures in 15% of the implants, and nine joints required revision. Patients rated their outcome as good in 25 joints, fair in 27, and poor in 18.

Lin *et al.* reviewed their experience of 69 PIP silicone arthroplasties done through a volar approach.⁸¹ There was an improvement in the extension deficit from 17° to 8° but no improvement in overall arc of motion. Complete resolution of preoperative pain was noted in 67 of 69 joints and complications were observed in 12 joints, including five implant fractures and three cases of implant malrotation. More recent studies by Namdari and Weiss reported 4-year outcomes of 16 joint replacements using the pre-flexed NeuFlex silicone implant.⁸⁶ After an average 4-year follow-up, the mean range of motion was 61°, with 0° of extension lag. Pain relief was excellent or good in 84% and overall patient satisfaction was rated at 90%. Pettersson *et al.* compared this new implant with a traditional silicone implant design, and found better patient satisfaction but otherwise similar results.⁸⁷ Silicone interposition PIP arthroplasty remains popular and is often used as a benchmark comparison for newer surface-replacement implants such as metal or PyroCarbon systems.

The outcomes of metal surface-replacement arthroplasty was reported by Linscheid *et al.*, where they described the outcomes of 66 cemented CoCr-UHMWPE surface-replacement prostheses with an average 4.5-year follow-up.⁷¹ In this study, the average arc of motion improved from 35 to 47°, and total pain relief was achieved in 85%. There were a significant number of complications, including five swan-neck deformities; five unstable joints; coronal deviation in four joints, and 12 joints required re-operation.

Jennings and Livingstone reviewed 43 metal surface-replacement PIP arthroplasties with an average follow-up of 37 months, and found no change in arc of motion and a 25% revision rate.⁸⁸ Revision arthroplasties were generally performed for loosening of the components. They found a significantly higher loosening rate for uncemented components (39%) when compared with cemented components (4%). Johnstone *et al.* reported similar findings in their study.⁷⁶ Johnstone and colleagues noted a higher incidence of subsidence and component loosening in newer generation implants which were not cemented.⁷⁶ Luther *et al.* recently reported an average 27-month follow-up on 24 SR-PIP arthroplasty.⁸⁹ They found that 14 joints required re-operation (58%), including four that required removal. Despite this, 70% were satisfied with their final functional results.⁸⁹

The results of pyrolytic carbon arthroplasty for proximal interphalangeal joint replacement have been the subject of several recent studies.^{90–94} Bravo *et al.* published the largest and most comprehensive study to date.⁹¹ A total of 50 PIP PyroCarbon joint replacements were performed in 35 patients. The minimum follow-up was 27 months. The average age at the time of surgery was 53 years. Joints replaced included the index,¹⁵ middle,¹⁸ ring,¹⁰ and small.⁷ The mean preoperative range of motion was 40°, mean pinch and grip measurements were 3 and 19 kg, respectively, and the mean preoperative pain score was 6 by visual analog scale (0–10). Postoperatively, mean range of motion improved to 47°, mean pinch and grip measurements were 4 and 24 kg, respectively. Despite these modest improvements, the mean postoperative pain score was 1 and overall patient satisfaction was high

(80%). Fourteen joints required additional procedures and the revision arthroplasty rate was 8%. There were no cases of implant infection. Notably, radiographic evidence of subsidence was noted in 20 joints although there was no apparent loosening.

Tuttle *et al.* also reported a retrospective series of 18 joint replacements in eight patients.⁹³ The average active range of motion was unchanged, however there were no cases of lateral instability. Complete resolution of preoperative pain was apparent in only eight cases. Complications included two dislocations evident at the first office visit; five contractures (with a motion arc of <35°), and eight squeaky joints. Wijk *et al.* reported 2-year follow-up on 53 PIP PyroCarbon arthroplasty procedures.⁹⁴ Range of motion and grip strength were unchanged postoperatively; however, pain relief and occupational performance were improved and patient satisfaction was high. Revision surgery was required in seven patients, including two who required subsequent arthrodesis.

Chung *et al.* evaluated 14 patients (21 joints) prospectively. The mean arc of motion at 12 months was 38°, grip and pinch strength both improved postoperatively. Patient-rated outcomes were studied by questionnaire, showing a significant improvement in pain, satisfaction, and aesthetic outcome.⁵⁸

Herren *et al.* performed 17 PyroCarbon PIP joint arthroplasty procedures for osteoarthritis, which were followed prospectively for a mean of 20.5 months.⁹⁵ All patients noted significant pain relief with a reduction in mean preoperative pain score of 7.6 on a 10-point visual analog scale, to 1.3 at final follow-up. One patient required a revision procedure because of implant migration. Nunley *et al.* performed five PyroCarbon PIP arthroplasties on younger patients with post-traumatic arthritis.⁹² These were followed prospectively for 1 year and were found to have no statistically significant improvement in pain or motion arc, however grip strength increased significantly postoperatively.

Watts *et al.* reviewed outcomes and complications of 97 joints after pyrocarbon PIP arthroplasty with a minimum 2-year follow-up.⁹⁶ Thirteen percent of digits required a revision at an average of 15 months postoperative. There were no significant differences in preoperative and postoperative range of motion. Overall joint survivorship was 85%.

Branam *et al.* have published a study comparing the outcomes of pyrolytic carbon implants with silicone implants for PIP arthroplasty.⁹⁰ This retrospective study compared outcomes of 19 PyroCarbon implants with 23 silicone implants. Although differences in final motion arc and pain relief were statistically insignificant, coronal plane deformity was more prevalent, and more pronounced in patients who had silicone arthroplasty. Overall it is apparent that both joints provide benefits with regard to pain relief and preservation of some motion. The superiority of one type of implant over another has yet to be determined.

More recently the idea of hemiarthroplasty for management of PIP joint arthritis has become a reality. Pettersson *et al.* reviewed their experience with 42 fingers in 38 patients undergoing PIP joint hemiarthroplasty.⁹⁷ While there was significant improvement in the Disabilities of the Arm, Shoulder and Hand (DASH) and visual analog pain scales, there was no significant change in grip, pinch, or range of motion. Only four joints required revision for failure. Average follow-up at 4.6 years was overall promising.

OA of the metacarpophalangeal (MCP) joint

Anatomy and biomechanics

The MCP joint is a multiaxial condyloid joint that allows for flexion, extension, abduction, adduction, and a limited degree of circumduction. Circumduction or rotation is not a motion under active control, but is allowed for passively by the intrinsic joint mechanics. The joint contributes to 77% of the total arc of finger flexion.⁹⁸ The metacarpal head has been described as having a unique “cam” shape. However, this description is not true to its mechanical reality. A cam is mechanical link that translates rotational motion into linear motion or vice versa, typically with a rotating *eccentric* wheel. However, the head of the metacarpal is *round* and, therefore, the analogy is not valid. The circular metacarpal head is offset volar to the axis of the metacarpal shaft, which does result in differential tension of the collateral ligaments in flexion and extension. The unique three-dimensional shape of the head, being wider on its volar aspect, adds to the collateral ligament tension in joint flexion and limited lateral motion in this position. On the other hand, when the MCP joint is extended the collateral ligaments are lax and there is maximal abduction and rotation of the joint in this position.

The MCP joint capsule is composed of areolar tissue dorsally that is loosely reinforced by the extensor tendon and the sagittal band.^{99,100} Laterally, the collateral ligaments support the joint, while the volar plate provides volar support. The intrinsic muscles provide only modest, secondary capsular support. The ulnar and radial proper collateral ligaments are fan-shaped, thick, and wide, arising from the dorsal aspect of the metacarpal head and inserting into the volar aspect of the proximal phalanx. The accessory collateral ligaments are located volar to the origin of the proper collateral ligaments on the metacarpal head and interdigitate with the proper collateral ligaments distally. The collateral ligaments play a major role in stabilizing the MCP joint in all directions of joint displacement. The accessory collateral ligaments contribute primarily to abduction-adduction and rotational stability, while the volar plate prevents dorsal dislocation of the joint when fully extended. The dorsal capsule provides a very modest contribution to stability when the joint is in distraction and at the extremes of supination and pronation.^{99,100}

OA affects the MCP joint less commonly than other hand joints and is usually secondary to injury or trauma, e.g., intra-articular fracture, septic arthritis, chronic repetitive trauma in setting of heavy labor occupations, and occasionally in metabolic disorders such as hematochromatosis.¹⁰¹⁻¹⁰³ MCP OA usually affects the index and middle fingers.^{101,102} Conservative treatment with splinting, hand therapy, non-steroidal anti-inflammatory drugs, and steroid injections is the first-line treatment of MCP OA. Surgery is indicated for stiffness and/or pain that are refractory to non-operative treatments.

Resection and resurfacing arthroplasty

Resurfacing arthroplasty involves the resection of diseased metacarpal cartilage and bone, followed by the placement of

soft tissue into the joint space to prevent direct bone contact. This procedure was used historically to treat MCP OA but now is reserved as a salvage procedure for cases of failed implant arthroplasty. Tupper¹⁰⁴ described the use of the volar plate for interposition arthroplasty. The volar plate is detached proximally from the metacarpal head before the diseased cartilage and bone of the metacarpal head is resected. This distally based volar plate is then attached to the dorsal edge of the osteotomy by means of sutures preplaced through drill holes in the metacarpal. Before the joint capsule is closed, the collateral ligaments are reattached using horizontal mattress sutures preplaced through drill holes on the sides of the distal metacarpal.^{105,106} Other resection/interposition arthroplasty techniques using tendon and interosseous muscles have been described by Vainio¹⁰⁷ and Riordan and Fowler,¹⁰⁸ although not specifically for OA.

Costal perichondrium may also be used for joint resurfacing. After harvesting the perichondrium and cutting it to the size and shape of the joint surface, the perichondrial graft is secured by means of a horizontal mattress suture. There are limited and variable reports on the outcomes of using rib perichondrium for resurfacing arthroplasty.^{67,109} A study by Seradge⁶⁷ noted poor outcomes in patients over 40 years of age and uniform failure in cases of reconstruction after septic arthritis. He concluded that such patients constitute a contraindication for the procedure. If perichondrium is to be used it should be oriented with the deep surface facing the joint as this is the chondrogenic surface. Similarly if the retinaculum or volar plate are used for resurfacing, the synovial (deep) surface should be oriented facing the joint.¹⁰⁹

MCP Implant arthroplasty

MCP implant arthroplasty is most commonly used in patients with rheumatoid arthritis. These patients tend to have a lower demand on the hands and therefore make implant arthroplasty more appealing (Fig. 20.11). In distinction to patients with rheumatoid arthritis, patients with OA of the MCP joint tend to have preservation of the collateral ligaments and fewer issues with soft-tissue imbalance and thus can be excellent candidates for implant arthroplasty of the MCP joint. Contraindications for MCP arthroplasty are similar to PIP arthroplasty. The index finger MCP joint can be considered for arthroplasty, even in a manual laborer. MCP joint prostheses can be grouped into one of four basic groups: hinged designs, flexible (silicone) prostheses, surface-replacement prostheses, and PyroCarbon implants.

Hinged prostheses

Metal-hinged prostheses are rarely used today. The 1953, Brannon and Klein prosthesis was the first prosthesis to be used for MCP arthroplasty.⁷⁰ This simple, uniaxial metal prosthesis resulted in bone resorption with subsequent finger shortening and loss of range of motion. In the 1970s and 1980s, the hinge implants evolved into multiaxial designs made of metal, polymers, or ceramics. The two-component ball-and-socket Griffith-Nicoll prosthesis¹¹⁰ and ceramic prostheses^{111,112} were strong enough to prevent fracture, but postoperative range of motion was too limited for adequate joint function.¹¹⁰



Fig. 20.11 (A) Anteroposterior (AP) radiograph of a 62-year-old woman with longstanding history of rheumatoid arthritis. She complains of metacarpal phalangeal (MP) joint pain at all fingers and the thumb. She has previously undergone a Darrach procedure to control distal radioulnar joint arthritis. Radiographs show evidence of advanced arthritis at the MP joint of the thumb, index, long, ring, and small fingers. In addition, there is evidence of ulnar deviation of the long, ring, and small fingers. While there is radiocarpal arthritis, the patient has no pain at the wrist and the wrist shows no evidence of radiographic instability or radial deviation on the AP radiograph. (B) AP radiograph 6 months after surgery to address MP arthritis. Patient has undergone a thumb MP joint fusion using a compression screw, PyroCarbon joint replacement at the long and index finger MP joints, and silicone joint arthroplasty at the ring and small MP joints. Silicone arthroplasty was chosen for the ring and small finger because of poor soft tissue at the collateral ligaments. The silicone implant, unlike the PyroCarbon implant, does not rely on the collateral ligaments for radial and ulnar stability due to its constrained design.

Silicone constrained prostheses

The Swanson prosthesis was the first silicone MCP joint prosthesis and has been in use since the 1960s.¹¹³ This prosthesis has been widely used and studied, although primarily for rheumatoid arthritis (RA). The silicone elastomer is cross-linked, which creates a rubber-like form to the implant. The implant acts as a dynamic spacer and not a true joint. The prosthesis is held in position by a process of fibrous encapsulation, instead of osseointegration.¹¹³ The prosthesis does not flex at the central hinge section until the joint has been flexed beyond 45°. Instead, in early flexion, the implant bends at the interface between the stem and the hinge.¹¹⁴ This results in a high incidence of stem fracture. Beckenbaugh reported a fracture rate of 26% at 2.5 years when using the original Swanson MCP prosthesis. After this study, the silicone elastomer used in the prosthesis was modified to increase its tear propagation strength and its fatigue-crack growth resistance, and a newer, “high performance implant” was released.¹¹⁵ Kirschenbaum *et al.*¹¹⁶ reported a 10% fracture rate within 8.5 years of insertion of the modified Swanson implant. Fracture rates of around 5–7% have been reported at 2–5-year follow-up.^{117,118} Interestingly, many of these fractures do not require treatment as they go unnoticed by the patients.¹¹⁶ Other complications with the implant have included implant deformation and silicone synovitis.^{116,119,120}

The clinical experience with the Swanson implant in patients with RA constitutes the main body of the literature on this implant. However, Rettig *et al.*¹²¹ reported their experience with silicone MCP arthroplasty in the setting of OA. While the experience in RA can shed some light on the management of patients with OA, the outcome of silicone arthroplasty in this population is likely to be different than patients with OA. They reported 100% patient-reported overall improvement with a mean MCP flexion of 59°. This small study consisted of 12 patients and 14 MCP joints. In contrast to the literature on Swanson implant failures in the setting of MCP RA, this study, albeit small, demonstrated no Swanson implant fractures in patients with OA.

The limitations of the Swanson implant in patients with RA have motivated the development of new silicone implant designs like MCP Soft Skeletal Implant (Small Bone Innovations, Morisville, PA) and the NeuFlex implant (DePuy, Warsaw, IN). Studies are promising for the NeuFlex implant, an anatomically neutral silicone implant with a block-hinge design and a preformed 30° resting angle that approximates the relaxed MCP position. The logic for this design is that with the finger in repose, there is no stress on the implant, contrary to the Swanson design. *In vitro* studies also suggest that the NeuFlex implant has greater longevity than the Swanson implant before fracture.¹²² Weiss *et al.*¹²³ compared MCP joint mechanism after NeuFlex, Swanson and Sutter (previously made by Avanta) arthroplasty and found that the mechanics of the NeuFlex implant most closely matched that of an intact MCP joint. Only one study⁸⁶ specifically examines the *in vivo* use of NeuFlex implants in OA of the MCP joint. At 4-year follow-up, NeuFlex implants were associated with a mean flexion arc of 65°, a mean extension lag of 3°, no implant fractures, and high patient satisfaction.⁸⁶ Despite the limitations of the Swanson MCP prosthesis, it remains the current “gold standard” to which other implants are compared. Not only is it effective in relieving pain and improving motion arc,



Fig. 20.12 Example of silicone metacarpophalangeal arthroplasties of the index and long finger in a 63-year-old woman who was suffering from post-traumatic arthritis.

but it is also relatively cheap and easy to place and remove (Fig. 20.12).^{124–126}

Surface-replacement prostheses

Silicone implants are inadequate in patients who place a higher demand on the MCP joint due to employment or lifestyle. Surface-replacement prostheses are more appropriate in such patients unless the soft tissue around the MCP joint is inadequate to offer implant stability.^{127–130} Surface-replacement prosthetics attempt to recreate normal joint anatomy. They vary in their design: a single-component silicone implant with a Dacron-coated stem¹²⁷; a non-joined, two-component Pyrolite carbon implant¹²⁸; a four-component polyethylene-titanium implant¹²⁹; or a three-component titanium plate-silastic hinge implant.¹³⁰ Studies on surface-replacement prostheses are small, consisting mainly of RA patients, with short postoperative follow-up. With the exception of a 20% fracture rate with the Hagert prosthesis, the surface-replacement prostheses are associated with a high patient satisfaction, resolution of pain, improved cosmetic appearance, average range of motion of 47–60°, and a low fracture rate.^{127–130} The main problem with these implants is instability and dislocation.¹²⁸

Kung *et al.* developed a stable surface-replacement arthroplasty implant based on cadaveric evaluation of normal MCP joint articular geometry.¹³¹ The implant is a non-constrained, two-component implant with a hemispherical cobalt–chrome alloy metacarpal component with and an ultra-high molecular weight polyethylene phalangeal component. The head has lateral volar contours that increase lateral stability during

flexion. Also, its arc of rotation is greater than that of an anatomical joint to decrease the risk of palmar subluxation. The stem of each component may be “press-fit” or secured into the intermedullary canal with bone cement. When mechanically tested at different angles, axial loads, and directions of motion, this semiconstrained MCP joint implant demonstrates more intrinsic stability than cadaveric MCP joints.¹³¹

PyroCarbon arthroplasty

Pyrolytic carbon, formed by the pyrolysis of a hydrocarbon gas, has an elastic modulus similar to cortical bone.¹³² This makes the material ideal for implant–bone stress transfer, potentially reducing implant wear and subsidence.¹³² The implant is stabilized by appositional bone growth and does not require cement fixation.¹³³ PyroCarbon implants require minimal bone resection and preserve the collateral ligaments allowing for greater distribution of compressive forces. However, such nonconstraint prostheses are more likely to sublux or dislocate, especially in the setting of suboptimal soft-tissue support. It is for this reason that these implants are less stable in patients with RA. Cook *et al.* reported a 70% 16-year implant survival for the early PyroCarbon implant design. The patients in that study, the majority of whom had RA, had good outcomes.¹³⁴ A short-term study by Nunez and Citron¹³⁵ specifically focuses on the use of the implant in patients with OA; after a mean follow-up of 2.2 years, 10° of motion was gained, pain significantly improved, and there were no cases of implant failure. In 2007, a study by Parker and colleagues reported similar range of motion as previous reports.^{134,136} A systemic review of the literature, however, suggests that PyroCarbon prostheses may provide no significant advantage over the Swanson implant with regard to postoperative motion and that complication rates of both implant designs may be similar.⁵⁸ Overall, PyroCarbon arthroplasty has been shown to decrease pain, improve extension lag, and improve grip and pinch strength.^{134,136}

Technique for MCP joint arthroplasty with PyroCarbon implant

Prior to surgery AP and lateral radiographs are used to template the size of the implants needed for the surgical procedure, keeping in mind that most routine radiographs are magnified by 3%. The MCP joint is exposed through a longitudinal incision; alternatively, if several joints are to be replaced, a transverse incision can be made, as in the case of RA. The extensor mechanism is split centrally; alternatively, it can be mobilized from the radial or ulnar aspect of the sagittal bands (Fig. 20.13). If the extensor mechanism is divided from the sagittal bands for joint exposure, these structures will need to be reconstructed and the extensor mechanism must be centralized at the completion of the case.

Once the joint is exposed, a starter awl is used to identify the intramedullary canal of the metacarpal. An alignment guide is placed within the intramedullary canal and the cutting guide is attached to the alignment guide. Using the cutting guide, a 27.5° back cut is created into the metacarpal head. The guide is then removed and the remaining osteotomy is completed by hand. The cutting plane of the guide is

positioned 1.0–2.0 mm distal to the dorsal attachments of the collateral ligaments. Upon completing the metacarpal osteotomy, the proximal phalangeal base is prepared in a similar manner; however, the cutting plane is positioned 0.5–1.0 mm distal to the dorsal edge of the proximal phalanx and is tilted 5° distally from vertical. It is strongly recommended that a conservative osteotomy (limited to the joint’s articular surfaces) be performed initially to avoid damage to the collateral ligaments. Additional metacarpal and proximal phalanx can always be removed later if the joint space is too small to accommodate the implants.

Following completion of the osteotomies, the proximal phalanx is broached to accommodate the largest implant. The metacarpal is then broached to match the proximal phalanx. Trial components are then inserted and checked using fluoroscopy. Motion should allow for approximately 10–15° of hyperextension and full flexion. Impaction grafting with autograft or allograft can be used if there is any concern about implant seating against the intramedullary bone. When satisfied with the preliminary appearance of the trial implants and the MCP joint motion, the trials are removed, and permanent implants are press-fit into the intramedullary canals. Unlike the PIP PyroCarbon joints, the MCP implants should not be mismatched for size, as this may produce edge wear on the implant. Care must be taken to assure the correct axial rotation of the component by verifying that the dorsal surface of the component is parallel to the dorsal surface of the proximal phalanx. To prevent volar subluxation or dislocation of the implant, a capsular repair is performed and the extensor tendon is centralized.

Postoperatively, the hand is placed in a volar splint with the wrist at 10–15° of dorsiflexion and slight ulnar deviation; the MCP joints are placed in full extension, and the PIPs may be left in slight flexion (5–10°). Short arc (30°) MCP joint flexion is started on day 5–10. Flexion is increased weekly by 20° until full flexion is obtained. Nighttime and resting splints are worn for 6 weeks keeping the joint in full extension when not exercising to minimize and resultant extension lag (Fig. 20.14).

MCP arthrodesis

Current implant arthroplasty techniques have made MCP arthrodesis a final resort in the treatment of MCP OA. MCP arthrodesis can be very debilitating, particularly if the other joints of the fingers have limited motion due to OA. Arthrodesis can be considered whenever arthroplasty is not possible due to inadequate soft-tissue support or significant damage to the metacarpal or proximal phalanx bone stock. In general, the MCP joints should be fused in increasing flexion starting with 25° of flexion for the index finger and adding an additional 5° of flexion for each finger as one advances in an ulnar direction (Fig. 20.15). In preparation for arthrodesis, good cancellous-to-cancellous bone contact is essential and this may be achieved in a “ball-in-socket” or a flat surface configuration. There are many techniques for arthrodesis of the MCP joints. Intramedullary olecranon bone¹³⁷ and prosthetic pegs¹³⁸ have been described. Some 97–99% fusion rates have been reported with crossed Kirschner pin stabilization.^{139,140} In contrast, intraosseous wiring is associated with a 9% nonunion rate¹⁴¹ and an 8% nonunion was reported with AO screw arthrodesis.¹⁴² Arthrodesis with miniplates has been reported



Fig. 20.13 Technique for use of PyroCarbon metacarpophalangeal (MCP) joint arthroplasty. **(A)** posteroanterior (PA) radiographs of a 63-year-old male with osteoarthritis of the MCP joint, as demonstrated radiographically by joint narrowing of the index and long finger MCP joints. **(B)** The surgical exposure is obtained through a longitudinal incision over the MCP joint. **(C)** The joint surfaces are prepared with a cutting guide similar to proximal interphalangeal joint arthroplasty. After the articular cartilage has been removed, the proximal phalanx is broached in preparation for implant placement. Broach position is verified with intraoperative fluoroscopy. **(D)** A similar procedure is performed on the metacarpal. **(E)** The final implants are placed and the extensor mechanism is reconstructed with braided suture with the finger held in extension. **(F, G)** Final position of the implants on PA and lateral radiographs 6 months following the surgery.




Fig. 20.14 Splint design for rehabilitation of surface-replacement arthroplasty at the metacarpophalangeal joint.

to achieve 96% fusion rates (Fig. 20.16).¹⁴³ Alternatively, tension band arthrodesis allows for another means of fixation with acceptable fusion rates.^{144,145} Tension bands can transform distracting flexor tendon forces across an arthrodesis site to compressive forces dorsally, that stabilize the arthrodesis.

Clinical tips

MCP PyroCarbon arthroplasty

- Splitting the extensor tendon longitudinally down the middle provides good visualization of the entire joint throughout the procedure without the need to reposition the tendon.
- Be sure that the hole created in the metacarpal head for placement of the cutting guide is centrally located with an appropriate trajectory down the middle of the metacarpal medullary canal.
- Protect the collateral ligaments during the proximal and distal cuts. These structures are critical to avoid joint instability.
- Use imaging to confirm the correct trajectory when broaching.
- Impaction grafting is valuable to create a tight fit between the prosthesis and bone.

Vascularized joint transfer/costochondral replacement

Although not commonly performed, the MCP joint can be replaced with a free vascularized or pedicled transfer of another joint. When compared to implant arthroplasty, vascularized toe transfer is less effective in improving postoperative arc of motion.⁵⁸ Thus, in cases of OA of the MCP joint, vascularized joint transfers are only indicated in patients where implant arthroplasty is contraindicated or has already failed, in young manual workers where implants have a high failure rate, and/or in cases where there is inadequate bone stock for




Fig. 20.15 Metacarpophalangeal (MCP) joint fusion can be achieved with various techniques. Angled cuts in the proximal phalanx base and MCP head allow one to maximize surface contact and create appropriate fusion angles. MCP fusion angles increase as one moves from the index finger to the small finger. Recommended fusion angles for the MCP joints have been 25° of flexion for the index, 30° for the long, 35° of flexion for the ring and 40° of flexion for the small.



Fig. 20.16 Oblique radiograph of the index finger demonstrating an metacarpophalangeal joint fusion obtained with a dorsally applied mini-plate.

implant arthroplasty.¹⁴⁶ Vascularized joint transfers are also recommended in children, as it is the only procedure that preserves the epiphyseal growth plate and allows for some longitudinal growth.⁵⁸ Better functional results in MCP joint reconstruction can be seen with the use of the second metatarsophalangeal joint.¹⁴⁷ After harvesting the flap, the whole second ray should be amputated for rapid recovery of normal gait. A small dorsalis pedis flap can be raised for any associated hand skin defects.

OA of the thumb

The thumb accounts for 50% of overall hand function and, as such, it is the most important digit in the hand.³¹ Arthritis of the thumb can occur at the IP, MP, or trapeziometacarpal (TM) joints. Arthritis of the interphalangeal joint is managed in a manner similar to that of the finger DIP joints as described above. One needs to decide the degree of flexion in which to fuse the joint and the method of fixation (K wires, 90–90 interosseous wiring, or headless compression screw fixation). The technique of joint debridement and fixation is essentially the same as with the finger DIP joints. Similarly, mucous cyst formation can be a complication of IP joint arthritis of the thumb. This is managed similar to a manner identical to that described for DIP arthritis above.

MCP joint arthritis of the thumb

Osteoarthritis of the thumb MCP joint is relatively uncommon and frequently the result of injury, particularly chronic radial or ulnar collateral ligament injury.¹⁴⁸ While arthroplasty may be an appropriate option for the thumb MCP joint in rheumatoid arthritis, MCP arthrodesis has been the standard of care for OA of the thumb MCP joint for more than 50 years.¹⁴⁹ MCP thumb joint fusion is well tolerated due to the large degree of motion at the thumb CMC joint. As with the IP joint of the thumb, MCP joint fusion can be accomplished by a variety of techniques that have been outlined above, such as tension band wiring, crossed K-wires, or plate fixation. The primary decision is what position the joint should be fused. The position must be functional, that is, it should facilitate opposition to the fingers and not hinder the ability to oppose to the tip of the ring finger or small finger. This typically means fusing the joint in slight (15°) of flexion.¹⁴⁹ However, fusing the joint in slightly more flexion (20–40°) takes some work out of opposition for the CMC joint and may decrease the load across this joint and therefore be protective against the development of OA at this location or at least slow its progression.¹⁴⁹

Trapeziometacarpal arthritis

Etiology and epidemiology

Osteoarthritis of the TM joint of the thumb is very common, with a reported age adjusted prevalence of 7% in men and 15% in women.¹⁵⁰ In a retrospective study of patients presenting with distal radius fracture, the prevalence of TM arthritis rose steadily after age 40, with 91% of patients over 80 demonstrating arthritic changes (85% of men and 94% of women over age 80). While many patients remain relatively asymptomatic, a subset of patients will develop debilitating pain,

thumb weakness, and instability, severely limiting hand function. Many treatment options exist, including NSAIDs, splinting, and corticosteroid injections.^{151–154} When conservative options fail, surgical treatment should be considered.

The effect of basal thumb OA on disability and mortality is modest, and as such, it is likely underdiagnosed in clinical practice.¹⁵⁰ Basal thumb arthritis usually involves the carpometacarpal joint, but the scaphotrapezotrapezoid (STT) joint can also become involved. Combined CMC/STT disease is twice as likely to be symptomatic than isolated CMC arthritis.¹⁵⁵ Males with thumb arthritis are more likely to be symptomatic than females.¹⁵⁶

Epidemiological studies suggest that basal thumb arthritis is most common in postmenopausal women. While the prevalence of radiographic thumb carpometacarpal OA among men is 7%, it is more than double that (15%) in women¹⁵⁰ and quadruple that in the postmenopausal population.¹⁵⁵ The discrepancy is not as wide when considering only symptomatic disease; 5% of men and 7% of women over the age of 70 years suffer from symptomatic basal thumb OA.¹⁵⁶ Among postmenopausal women with radiographic evidence of basal thumb arthritis, the majority have isolated CMC disease; 6% have isolated STT disease; and 23 % have combined CMC/STT.¹⁵⁵ The gender differential seen in this disease may be explained by anatomic differences in the joint. Female CMC joints have greater reciprocal articular surface curvatures and lower degree of surface congruity, resulting in smaller contact areas with greater stresses.¹⁵⁷ Hormonal factors may also contribute to the development of basal thumb OA in females. Spector *et al.*¹⁵⁸ found an increased risk for the disease in women who had a hysterectomy. Interestingly, the relationship is not demonstrable with other hand joints, putting the validity of this relationship into question.¹⁵⁹ Other risk factors for thumb CMC OA have been extensively studied. Obesity is a strong determinant of thumb CMC OA in both sexes.^{150,160,161} Obesity causes OA by increasing the load on weight-bearing joints; however, the first CMC is not a weight-bearing joint. Obesity may predispose to CMC osteoarthritis via non-mechanical, biological mechanisms related to elevated serum lipids.¹⁶² Unlike weight-bearing joints,^{163,164} there is no independent association between thumb CMC OA and diabetes or hypertension.¹⁵⁹ Furthermore, while an association between thumb CMC OA and OA in weight-bearing joints has been reported by some investigators,^{165–167} others have dismissed this relationship.¹⁵⁰ While thumb CMC OA is not specifically associated with heavy physical activity,¹⁵⁹ it is clearly associated with occupations requiring repetitive thumb use (especially in the absence of enough rest breaks) and occupations that expose the thumb to greater than normal forces.

Family history is another strong predictor in the development of thumb CMC OA. In a classic twin study, Spector¹⁶⁸ provided clear evidence of a genetic link for the development of TM OA in females. Jonsson and colleagues¹⁶⁹ went on to suggest that the genetic influence increased with the severity of the disease.

Anatomy and biomechanics

The TM joint comprises the articulation between the trapezium and the base of the thumb metacarpal. The trapezium and first metacarpal base have reciprocal concavoconvex

surface, which resembles a biconcave saddle joint.¹⁷⁰ The trapezial surface is concave in an ulnar–radial direction and convex in a dorsopalmar direction. Reciprocally, the base of the first metacarpal is convex in an ulnar–radial direction and concave in a dorsopalmar direction. The radius of curvature of the metacarpal base is 34% greater than that of the trapezium and is thought to predispose to joint incongruity and instability.¹⁷¹ The trapezial surface flattens and transforms from a saddle type to a semicylindrical type joint with advancing arthritis.¹⁷² The scaphotrapezial (ST), trapeziotrapezoid and trapezium-index metacarpal joints are also considered as part of the basal joint of the thumb and can become involved in late stage OA.

Due to the bony incongruity and large cantilever forces, the CMC joint relies heavily on static ligamentous restraints for stability. Up to 16 ligaments have been identified^{171,173}, however, there are five major internal ligamentous stabilizers of the trapeziometacarpal (TMC) joint; these ligaments are the dorsal radial ligament, posterior oblique ligament, first intermetacarpal ligament, ulnar collateral ligament, and the anterior oblique ligament. The dorsal radial ligament provides stability in flexion, opposition, and pronation. The posterior oblique ligament prevents lateral subluxation. The first intermetacarpal ligament (IML) is taut in abduction, opposition, and supination; it holds the first metacarpal tightly against the second metacarpal. The IML is joined by the ulnar collateral ligament, which prevents lateral subluxation of the first metacarpal on the trapezium and controls for rotational stress. The fifth and most important ligament is the volar anterior oblique ligament (AOL) with its deep (dAOL) and superficial (sAOL) components. The ligament arises from the volar tubercle of the trapezium and inserts on the volar aspect of the thumb. The AOL is taut in extension, abduction, and pronation; it controls pronation stress and prevents radial translation. The dAOL serves as a pivot point for the TMC joint and guides the metacarpal into pronation while the thenar muscles work in concert to produce abduction and flexion. These fibers limit ulnar translocation of the metacarpal during palmar abduction while working with the sAOL to constrain volar subluxation of the metacarpal (Fig. 20.17).^{170,171,173}

The TM joint surface allows for biaxial movements – flexion/extension of the CMC and palmar abduction/adduction.¹⁷⁰ Capsular laxity allows for rotation of the metacarpal on the trapezium. Combined flexion, palmar abduction and rotation allow for opposition.¹⁷⁰ Cooney *et al.* radiologically demonstrated that the average total motions of the TM joint (defined as motions of the first metacarpal with reference to the third metacarpal) is 53° of flexion–extension, 42° of abduction–adduction, and 17° of axial rotation (pronation–supination).¹⁷⁴

Diagnosis and classification

The diagnosis of TM OA is usually made from the history and physical examination. Radiographs are used to stage the disease. When evaluating a patient with thumb base pain, the differential diagnosis is broad and includes: flexor carpi radialis (FCR) tendonitis, de Quervain's tenosynovitis, inflammatory arthritides, rheumatoid arthritis, gout, pseudogout, gamekeeper's thumb, radial sensory neuritis, and radiocarpal or STT arthritis.




Fig. 20.17 Diagram of the trapeziometacarpal joint looking from dorsal to palmar. A portion of the dorsal radial ligament (DRL) and posterior oblique ligament (POL) have been removed to show the palmar ligaments. The most important ligaments for thumb stability are the DRL, POL, ulnar collateral ligament (not depicted), first intermetacarpal ligament (IML), and the anterior oblique ligament, deep and superficial heads (DAOL, SAOL). DIML, dorsal intermetacarpal ligament.

Basal joint arthritis typically presents in females 50–70 years old who complain of worsening thumb pain interfering with activities of daily living. Patients often complain that activities requiring opposition or pinch grip, such as opening jars or carrying heavy objects between the thumb and fingers, produce pain at the base of the thumb. Complaints of stiffness or pain at rest are usually indicators of late stage disease. On physical examination, patients may show the following signs^{175,176}:

1. **Shoulder sign:** classically reveals squaring or prominence at the base of the thumb (dorsoradial subluxation secondary to ligamentous laxity and the pull of abductor pollicis longus (APL) on the base of the metacarpal).
2. **Point tenderness** at the CMC joint.
3. **Grind test:** pain on axial compression with rotation of the metacarpal on the trapezium is pathognomonic of CMC arthritis.
4. **Distraction test:** pain on thumb metacarpal base rotation and axial traction may be present in early stage disease due to joint capsule inflammation.
5. **Adduction deformity:** in later stages of the disease, the metacarpal adopts an adducted posture and the patient may develop a subsequent contracture of the first webspace.
6. **Hyperextension deformity:** as a result of the adduction deformity or severe joint stiffness, there may be a

compensatory hyperextension deformity of the thumb MCP joint.

7. *Thumb weakness*: pinch strength is almost always diminished and functional hand width is often narrowed.
8. *Carpal tunnel syndrome*: up to 43% of patients with TM OA may have evidence of median nerve compression on nerve-conduction studies.¹⁷⁷ The prevalence is even higher in women, worker's compensation patients, and those with diabetes mellitus. Given this high association, one should take great care to diagnose coexistent carpal tunnel syndrome in patients scheduled for basal joint surgery. If present, carpal tunnel syndrome can be treated at the same time of TM OA surgery.¹⁷⁷

AP, lateral, and oblique radiographs of the TM joint can be used to confirm the diagnosis and stage the disease. TM stress views (30° posteroanterior (PA) view with the patient forcefully pushing the radial aspects of their thumb tips against each other) can help assess the degree of joint subluxation and joint space loss.¹⁷⁸ Stress views also demonstrate the ST joint and the index finger TM joint very well. The Robert's view (AP view with the hand hyperpronated) also provides a clear image of all four trapezial articulations.¹⁷⁵ Only 28% of women who have radiographic signs of isolated TM arthritis and 55% of women with pantrapezial arthritis admit to symptoms of thumb arthritis, thus radiographic changes must always be correlated with physical signs prior to developing any treatment plan.¹⁵⁵

There are two frequently used classification systems for CMC arthritis. The Eaton classification (Table 20.1)¹⁷⁸ is most commonly used and is based on radiographic features alone. Individual symptoms may not correlate with the Eaton stage. In comparison, Burton classification (Table 20.2) is based on clinical and radiographic findings.^{179,180}

The Eaton classification of TM OA follows the progressive changes that occur with progression of disease. In stage I, the

Table 20.1 Eaton classification

Stage	Radiographic characteristics
Stage I	Normal or slightly widened trapeziometacarpal joint Trapeziometacarpal subluxation up to one-third of articular surface Normal articular contours
Stage II	Decreased trapeziometacarpal joint space Trapeziometacarpal subluxation up to one-third of articular surface Osteophytes or loose bodies <2 mm
Stage III	Decreased trapeziometacarpal joint space Trapeziometacarpal subluxation > one-third of articular surface Osteophytes or loose bodies ≥2 mm Subchondral cysts or sclerosis
Stage IV	Involvement of the scaphotrapezial joint or less commonly the trapeziotrapezoid or trapeziometacarpal joint of the index

(Data from Eaton RG, Littler JW. Ligament reconstruction for the painful thumb carpometacarpal joint. *J Bone Joint Surg Am.* 1973;55:1655–1666.)

Table 20.2 Burton classification

Stage	Findings
Stage I	Pain Positive grind test Ligamentous laxity Dorsoradial subluxation of CMC joint
Stage II	Instability Chronic subluxation Radiographic degenerative changes
Stage III	Involvement of the scaphotrapezial joint or less commonly the trapeziotrapezoid or trapeziometacarpal joint of the index
Stage IV	Stage II or III with degenerative changes of the MCP

CMC, Carpometacarpal; MCP, metacarpophalangeal.
(Reproduced from Braun RM, Feldman CW. Total joint replacement at the base of the thumb. *Semin Arthroplasty.* 1991;2:120–129; and Brunelli G, Monini L, Brunelli F. Stabilisation of the trapezio-metacarpal joint. *J Hand Surg Br.* 1989;14:209–212.)

joint appears normal or slightly widened, associated with effusion or ligamentous laxity. In stage II there is slight narrowing of the joint associated with cartilage loss. Joint debris such as loose bodies and osteophytes may be seen, but measure less than 2 mm in size and sclerotic changes are minimal. In stage III, the joint space is markedly narrowed or obliterated, subchondral sclerosis and cystic changes are apparent, dorsal subluxation is variably seen, and osteophytes and debris exceed 2 mm in size. The STT joint is spared (normal) in stage III. However, in stage IV, there is pantrapezial arthritis with STT joint involvement in addition to those changes seen in stage III (Fig. 20.18).¹⁷⁸

Non-operative treatment

Splinting alone may be effective in early stage disease. Reconstructive procedures aimed at providing pain relief, as well as restoring thumb motion and strength, are usually necessary in the later stages. Regardless of stage at presentation, all patients should undergo a trial of conservative management prior to operative intervention. This includes activity modification, splinting, NSAIDs, and steroid injections.

Teaching patients to avoid aggravating activities of the thumb improves their pain control and overall function.¹⁸¹ Patients should be advised to avoid twisting, lifting, gripping, and pinching movements. Joint protection by dividing stress among multiple hand joint and using assistive devices preserves the integrity of the joint structure and improves joint function, both in the short and the long term.^{182,183} Patients may be taught home hand exercises that aim to strengthen the thenar muscles, the abductor pollicis longus, and the extensor pollicis longus (EPL). These exercises counter the flexion-adduction force of the adductor pollicis muscle, prevent adduction contracture of the first webspace, and improve grip strength and global hand function.^{182,184,185} The use of a joint protection arthritis education program with educational-behavioral teaching methods has proven beneficial in adherence, pain, disease status, and functional ability in arthritis patients.¹⁸³ Such strengthening exercises, however, should only be recommended to patients with early stage OA without significant pain.



Fig. 20.18 Radiographs of Eaton stage I–IV trapeziometacarpal (TMC) osteoarthritis. **(A)** An example of stage I arthritis displaying a slightly widened TMC joint space due to ongoing synovitis. **(B)** An example of stage II arthritis with joint space narrowing and small osteophyte formation. **(C)** An example of stage III showing significant joint destruction and osteophyte formation but preservation of the scaphotrapeziotrapezoid (STT) joint. **(D)** An example of stage IV arthritis with narrowing and arthrosis at both the TMC and STT joints.

Splinting rests the joint and holds it in a position of maximum surface contact, thus increasing joint stability and diminishing mechanical stress.^{186,187} This often decreases the associated acute inflammation and pain enough that an adequate level of function returns. A long opponens splint holds the thumb in palmar abduction with the MP joint in 30° of flexion and pronation and the wrist in 15° of extension. This shifts the center of pressure dorsally and away from the palmar side of the CMC joint that is susceptible to OA.¹⁸⁷ A short opponens splint by definition does not immobilize the wrist. A modified short splint that only immobilizes the CMC is also commercially available.¹⁸⁶ Although the long and short splints are equally effective, patients tend to prefer the less bulky design of the short splints.¹⁸⁸ Splints may be prefabricated neoprene or custom-fitted thermoplast.^{189,190} While some authorities prefer the individualization and rigidity offered by the custom-fitted thermoplast splints,¹⁹⁰ neoprene splints offer

greater pain relief and are generally preferred by patients over the more rigid splints.¹⁸⁹ Patients are instructed to wear the splints whenever they feel basal thumb pain, whether it is day or night.¹⁸⁹ After 3–4 weeks, patients may notice a decreasing need for splinting. Recently, however, a randomized European trial suggested that patients with thumb CMC OA may need to be splinted longer (several months) before one can actually see significant improvement in their overall pain and disability.¹⁹¹

Medical therapy for basal thumb OA includes NSAIDs and intra-articular steroids. Systemic and topical NSAIDs help reduce synovitis, but they do not halt or reverse disease progression. There is no difference in the effectiveness of currently available NSAIDs.¹⁹² Intra-articular steroid injections can be used to resolve synovitis refractory to activity modification, splinting, and NSAID therapy. When followed by 3 weeks of splinting, a 40% success rate for subjective symptom

improvement has been reported.¹⁹³ While steroid injections seem to offer short-term pain relief in early basal thumb OA,¹⁹⁴ their long-term effectiveness is uncertain.¹⁹⁵ Steroid injections should not be more often than two to three times a year and should be used cautiously in very early stage disease as they can potentially accelerate arthritic degeneration. As demonstrated in a small 2004 randomized controlled trial, patients with stage IV disease are unlikely to benefit from steroid injections.¹⁵² With increasing evidence that hyaluronic acid contributes to joint hemostasis¹⁹⁶ and reduces pain in patients with knee OA,¹⁹⁷ investigators have studied injections of hyaluronic acid into the thumb CMC joint. While studies suggest that hyaluronic acid may result in some basal thumb pain relief, there is no evidence that its effectiveness is superior to that of steroids.¹⁹⁸ Interestingly, a recent prospective, randomized, double-blinded trial¹⁹⁹ studying hyaluronic acid and steroid injections found no improvement in pain, strength, range of motion, or disability with either when compared with placebo. However, this study did not exclude patients with advanced stage disease, and follow-up was limited to 26 weeks.

The technique for CMC injection is straight-forward; however, advanced disease associated with large osteophytes and distorted anatomy may present a challenge. The landmark for thumb CMC joint injections is the dorsoradial aspect of the proximal end of the first metacarpal.¹⁹⁰ The thumb is opposed against the little finger so that the proximal end of the first metacarpal is palpable. Traction is applied to the thumb in order to widen the CMC joint space. The CMC joint is then injected using a 25-gauge needle. The needle is inserted at a point proximal to the prominence at the base of the first metacarpal on the palmar side of the extensor pollicis brevis and the abductor pollicis longus tendons. The needle is advanced distally until it penetrates the joint capsule.¹⁹⁰ Fluoroscopy can be used if the joint anatomy is distorted. The anatomical snuff-box should be avoided because it contains the radial artery and superficial radial nerve. Several corticosteroid preparations are commercially available. Betamethasone is water soluble and does not leave intra-articular precipitates behind. About 1.5 mL of a 50/50 mix of betamethasone and 1% lidocaine without epinephrine may be used.¹⁹⁰

Surgical procedures for stage I disease

Surgery for TM arthritis is indicated in patients with persistent pain, instability, and decreased function refractory to conservative therapy. The type of procedure used is dictated by disease severity, depending primarily on whether the cartilage of the CMC joint is unaffected (stage I) or shows signs of degeneration (stages II–IV). Attritional changes in the beak ligament cause hypermobility and synovitis that precede any cartilaginous degeneration.²⁰⁰ The palmar articular cartilage neighboring the beak ligament is subject to compressive forces in early disease. Attrition of the beak ligament results in dorsal translation of the contact area with subsequent cartilage degeneration.²⁰¹ The goal of surgery in early stage of disease is to stabilize the joint, preventing further subluxation, and to offload the palmar cartilage, preventing further degeneration.²⁰² Surgical procedures that are appropriate for such early stage CMC arthritis include arthroscopy, metacarpal abduction–extension osteotomy, and volar ligament reconstruction.

Thumb CMC arthroscopy

Not only is arthroscopy diagnostic in cases of basal thumb arthritis, but also it can serve as primary therapy in early disease or as adjunctive therapy in advanced stages.^{203,204} Thumb CMC arthroscopy is viewed as a less invasive therapeutic intervention. Synovectomy, debridement, and thermal shrinkage capsulorrhaphy of the beak ligament may all be performed arthroscopically. Synovectomy and debridement are appropriate for early stage disease that failed conservative therapy.^{203,204} Arthroscopic intervention is not recommended for more advanced disease with significant cartilage loss. Menon²⁰⁵ described arthroscopic interposition arthroplasty (using tendon, fascia lata, or Gore-Tex patch) with excellent results. Badia, however, cautions against arthroscopic interposition arthroplasty for stage III disease in young, active patients (who may benefit more from arthrodesis) and in low-demand patients (who may benefit more from trapeziectomy with or without ligament reconstruction).^{203,204}

Thumb CMC arthroscopy is usually performed under regional anesthesia with tourniquet control. A total of 5–8 lb of longitudinal traction is applied on the thumb using a single finger trap. Joint distension is achieved by injecting 5 mL of normal saline into the joint under direct palpation. A radial portal (1-R) and an ulnar portal (1-U) are usually needed. The radial portal is placed just radial to the APL tendon, and the ulnar one is placed ulnar to EPL tendon. The dorsal radial ligament, posterior oblique ligament, and the ulnar collateral ligament are best evaluated using the radial portal. The ulnar portal allows for better assessment of the beak ligament.

A short barrel, 1.9-mm 30° arthroscope and a full-radius shaver with suction are utilized.^{203,204} A radiofrequency probe may be used to perform the synovectomy, the chondroplasty (in cases with focal cartilage wear), or the thermal capsulorrhaphy (in patients with ligamentous laxity). Performing an arthroscopic trapeziectomy in stage III disease requires burring away the articular cartilage and removing subchondral bone down to a bleeding surface. This increases joint space and allows for hematoma formation, optimizing tendon graft placement and adherence. A volar slip of APL or palmaris longus may be used as a tendon graft and is inserted into the joint space via a portal. The joint is protected in a thumb spica splint for 1–5 weeks depending on the pathology and the intervention.

Dorsal wedge extension osteotomy

The volar compartment of the CMC joint is where compressive forces localize when the thumb is in its functional position of flexion and adduction.²⁰¹ One way to unload this compartment in early disease is to perform a dorsal, closing wedge osteotomy of the thumb metacarpal that extends and abducts the metacarpal away from the trapezium joint surface. Pellegrini and his colleagues²⁰⁶ were the first to evaluate the biomechanical efficacy of a 30° dorsal wedge osteotomy. Their data suggested that the procedure is successful at offsetting the subluxing forces acting on the base of the metacarpal. This procedure was found to not only shift the joint load dorsally²⁰⁶ but also tighten the dorsoradial ligament and reduce overall joint laxity.²⁰⁷ In a cadaveric model of extension osteotomy, Shrivastava *et al.* demonstrated that the procedure reduced laxity in all directions (40% reduction in the dorsal–volar

direction, 23% reduction in the radial–ulnar direction, 15% reduction when distracted, and 15% reduction in pronation–supination).²⁰⁷ Because of the changes it creates in the articular forces, the procedure is contraindicated in cases of global joint instability and cases of non-reducible subluxation.

The technique for a dorsal wedge extension osteotomy is described by Tomaino.^{208,209} After establishing regional anesthesia and Esmarch bandage exsanguination, tourniquet control is applied, and a 3 cm dorsal incision is made from the base of the thumb metacarpal distally. The dorsal sensory branch of the radial nerve and lateral antebrachial cutaneous nerve as well as the extensor pollicis longus tendon are identified and protected. The CMC joint is identified using a 25-gauge needle. A transverse arthrotomy may be performed to document normal joint surfaces if the radiographs are questionable or if there is crepitance on examination.^{208,209} One centimeter distal to the joint, subperiosteal, circumferential dissection of the metacarpal is obtained. Using a microsagittal saw, a partial transverse osteotomy is performed in this location down to the volar cortex. A new saw blade is used to make a 30° osteotomy 5 mm distal to the first one. The two osteotomies are connected at the volar cortex completing a dorsally based 30° wedge of bone that is removed. The distal metacarpal is extended and compressed against the base. The reduction is secured in place with K-wires²⁰⁸ or two 11×8 staples.²⁰⁹ Plates or tension band technique can be used for fixation as well. The periosteum and skin is then closed, and a thumb spica splint is placed for 10 days. A thumb spica cast (with the interphalangeal joint left free) is then placed for an additional 4 weeks. At around 6 weeks postoperatively, the cast is replaced with a forearm-based thumb spica Orthoplast splint, and the patient is instructed to start gentle TM motion. Osteotomies heal at an average of 7 weeks. Unless union is delayed, grip and pinch exercises are started 8 weeks postoperatively.^{208,209}

Pain relief and improved hand function following extension osteotomy are likely related to both load transfer and increased joint stability. Some 80% of patients have good–excellent long-term pain relief.²⁰² At 2.1-year follow-up, grip and pinch strengths increase by an average of 8.5 and 3.0 kg, respectively.²⁰⁸ At 6.8-year follow-up, 82% of patients have normal grip and pinch strengths.²⁰² This procedure also has the added benefit of correcting any adduction contracture that may be present. Overall long-term patient satisfaction with this procedure is reported at 91–93%.^{202,208}

Volar ligament reconstruction

Since volar ligamentous laxity contributes to CMC joint instability and degenerative disease progression, early basal thumb OA can be addressed surgically by reconstructing the volar ligaments. Eaton and Littler described a technique for reconstructing the volar ligaments by passing the radial half of the FCR tendon through the base of the thumb metacarpal and then suturing it to the APL tendon. The procedure was initially described for the treatment of late disease¹⁷⁸; however, subsequent reports have confirmed the efficacy of the procedure in early disease.^{210,211} This procedure is viewed by many as the first of choice for early disease when there is only early chondromalacia.²¹¹ The presence of STT OA precludes use of this procedure. This technique has been reported to slow the radiographic progression of the disease in up to 94% of female

patients at 15-year follow-up.²¹¹ This compares favorably with the 17% reported radiographic prevalence of stage III–IV disease in postmenopausal women in the general population.¹⁵⁵ While it eliminates long-term pain in only 29% of patients, patients with persistent pain tend to have only mild pain and are generally satisfied with the procedure. The technique appears to be less effective in men and patients involved in worker compensation claims.²¹¹

Technique for Eaton–Littler procedure

Adequate thumb CMC joint exposure for volar ligament reconstruction usually necessitates a modified Wagner incision, which is a longitudinal incision that is located parallel to the long axis of the thumb metacarpal at the interval between the glabrous palmar and non-glabrous dorsal skin (Fig. 20.19). The dorsal sensory branch of the radial nerve and branches of the lateral antebrachial cutaneous nerve crossing the operative field must be identified and protected. The radial edge of the thenar muscles is elevated extraperiosteally off the metacarpal, exposing the trapezium, the metacarpal base and the CMC joint. The interval between EPL and extensor pollicis brevis is developed to expose the dorsal cortex of the metacarpal base. Using handheld awls or a cannulated drill over a K-wire, a tunnel is made in the metacarpal base in a dorsal to volar direction (perpendicular to the axis of the thumbnail, 1 cm distal to the dorsal surface of the joint aiming volarly just distal to the insertion of the beak ligament, and parallel to the articular surface). A 28-gauge stainless steel wire, or Hewson suture passer, is passed through the tunnel from volar to dorsal and is used to pass the tendon through the bone.²¹²

After incising the FCR tendon sheath longitudinally, the ulnar half of the FCR tendon is split longitudinally with a heavy suture.²¹² The tendon slip is harvested using multiple transverse incisions on the volar forearm from the level of the wrist to the level of the musculotendinous junction. The tendon is divided proximally and delivered through the subfascial plane into the distal incision. The split is completed distally to the level of the trapezium. The FCR tendon slip is then delivered through the metacarpal base in a volar to dorsal direction using the previously placed wire or tendon passer. After the tension is set, the tendon is secured to the periosteum of the dorsal cortex using 3-0 braided synthetic suture. The tendon is then secured beneath the APL tendon. The remaining tendon is directed volarly, looped around the FCR tendon, sutured to the FCR tendon, and finally redirected dorsally where it is sutured beneath the APL tendon. Although not absolutely necessary, the CMC joint may be further secured with K-wires. Finally, the thenar muscles are reapproximated, and the skin is closed.

Postoperatively, the thumb is immobilized in a short arm thumb spica cast for 4 weeks. After that, the thumb is protected in a thermoplast long opponens splint which is removed for hand therapy. Active and active-assisted range of motion of wrist, thumb CMC, MP, and interphalangeal joints are performed in hand therapy. Palmar abduction is started before radial abduction. During the first 2 weeks out of cast, opposition and flexion to the index and long fingers are encouraged. Strengthening is begun after 4 weeks of cast removal. This is started with minimal resistance putty and then gradually increased to unrestricted activity by 3 months postoperatively.²¹²




Fig. 20.19 Stress views of a 28-year-old female with right thumb pain and grade I radiographic changes (**A**), showing evidence of joint instability of the right trapeziometacarpal (TMC) joint. (**B**) The patient elected to undergo an Eaton–Littler procedure for stabilization of the TMC joint. The procedure is performed through a modified Wagner incision, which is a longitudinal incision parallel to the long axis of the thumb, in the interval between the glabrous and non-glabrous skin. (**C**) Vessel loop is around the radial artery. The TMC joint is easily exposed through the incision. (**D**) A strip of the flexor carpi radialis is then passed through a bone tunnel parallel to the base of the thumb metacarpal. (**E**) An anteroposterior radiograph of the thumb showing restoration of TMC joint congruity.

Procedures for stage II–IV disease

In stage II–IV disease, there is loss of articular cartilage. In such cases, joint salvage will not provide adequate pain relief. Surgical procedures to manage more advanced disease can be grouped into four major categories, which include: (1) trapeziectomy; (2) trapeziectomy with soft-tissue arthroplasty; (3) arthrodesis; and (4) replacement of the TM joint (prosthetic arthroplasty). The goal of surgery is to reduce pain while maintaining thumb strength and motion.

Trapeziectomy alone

Complete excision of the trapezium is the earliest described surgical procedure for CMC arthritis. It was first described by Gervis in 1947 at the Royal Society of Medicine.²¹³ His work was published the next year in the *Postgraduate Medical Journal*.²¹⁴ The procedure has been shown to be effective at resolving joint pain.^{215–217} The improvement in thumb pain allows for improvement in hand function despite some loss in grip and pinch strengths. Historical concerns with this procedure include the possibility of proximal migration of the thumb metacarpal producing painful metacarpo-scapoid impingement^{218–221} and thumb instability.^{216,222,223} This has led to the development of stabilization and suspensionplasty procedures in an attempt to return more thumb stability and prevent metacarpal subsidence.²²¹ Loss of trapezial space height has not been directly correlated with loss of grip or pinch strength.^{218,219} In addition, prospective studies have failed to show any difference in function or metacarpal subsidence when comparing simple trapeziectomy to soft-tissue procedures^{224,225} while partial trapeziectomy can be done, excising the whole bone is important in cases of STT disease.

Surgical technique for simple trapeziectomy

A dorsal approach to the thumb is usually employed.^{220,226} Blunt dissection is undertaken down to the first dorsal compartment and then continued dorsoulnarly to the radial artery. The artery and radial sensory nerves are dissected off the underlying CMC joint. The joint space can be identified by palpation and opened with a longitudinal capsulotomy that is ulnar to the first dorsal compartment, starting 5 mm on the metacarpal base and extending proximally until the scapho-trapezial joint is encountered. Longitudinal traction on the thumb may help visualization in cases of severe subluxation. The trapezium is identified by visualization of the saddle joint and the metacarpal base. Confirmation may be obtained with fluoroscopy. The trapezium is removed piecemeal from within the surrounding capsule using a rongeur, a knife, an elevator, or an osteotome. Attention to the FCR tendon at the base of the wound is paramount to avoid inadvertent injury. The wound is irrigated, and all small bone fragments are removed before closing the capsule and skin.^{218,224}

Postoperatively, the thumb is immobilized for 6 weeks, after which the patients are instructed to start range of motion exercises as they wean from using an elastic bandage splint over the course of 4 days. Activity is advanced as tolerated over another 10 days. Patients who, at that point, cannot touch the small finger metacarpal head with the tip of their thumb are referred to hand therapy.²²⁶

A variation of the simple trapeziectomy approach is trapeziectomy and distraction arthroplasty, also referred to as

hematoma arthroplasty, as blood is thought to fill the space left by the removed trapezium, eventually forming scar.^{220,226} A standard trapeziectomy is performed followed by temporary K-wire fixation of the thumb in a position of distraction, palmar abduction, and opposition for about 4 weeks. A single 1.6-mm (0.062-inch) K-wire is inserted percutaneously through the thumb and index metacarpal bases. The fixation is intended to promote dense hematoma formation and scarring in the area of the excised trapezium, hence reducing thumb subsidence. Transverse wire placement is preferred over a longitudinal as the latter may allow the thumb metacarpal to slide proximally along the wire into the trapeziectomy space.^{220,226} Unfortunately, as reported by Gray and Meals in 2007,²¹⁷ such fixation does not seem to prevent thumb subsidence. However, the procedure is associated with an 82% rate of pain resolution with an average of 11% and 21% increase in pinch and grip strengths, respectively. These results are equivalent to that of the more complex tendon interposition techniques. Despite its effectiveness, unless the patient is a low-demand elderly patient who does not have metacarpal subluxation,²²⁷ some authorities do not recommend hematoma arthroplasty as a primary treatment and suggest that it be avoided in young patients who require strong grasp and pinch strengths for work.^{216,228} However, recent comparative studies and a Cochrane review recommend trapeziectomy alone for the treatment of CMC arthritis since outcomes are similar among the different techniques but complications and costs are lower with trapeziectomy alone.^{224,225,229}

Trapeziectomy with ligament reconstruction and/or tendon interposition

Several procedures for tendon interposition arthroplasty are available (Video 20.1 ). These procedures consist of a complete or partial trapeziectomy and interposition of tendinous tissue in the trapeziectomy void. The different operations described for biological arthroplasty are distinguished by: (1) the choice of tendon used to fill the trapeziectomy void and prevent thumb subsidence, and (2) the choice of method used to stabilize the thumb following trapeziectomy. An attempt to reconstruct the intermetacarpal ligament anchoring the thumb metacarpal to the index metacarpal is known as *suspension arthroplasty*.

Froimson's fascial arthroplasty is one of the first described interposition arthroplasties that did not include any element of ligament reconstruction. After a standard trapeziectomy, half of the FCR tendon is harvested, rolled up in an "anchovy" fashion, and used to fill the trapeziectomy space. Froimson²³⁰ reported a 90% rate of pain relief at 88-month mean follow-up, but pinch power was reduced by 30%. Radiographically, the procedure resulted in a 50% decrease in the interval between the first metacarpal base and the scaphoid, but clinically the thumb shortening was minimal.

Burton and Pelligrini²²⁸ described a thumb ligament reconstruction performed with the radial half of the FCR tendon routed through the base of the thumb metacarpal, and the remaining length of the tendon was placed in the trapeziectomy void. This procedure has become known as the *ligament reconstruction and tendon interposition procedure*, or LRTI, and is one of the most common trapeziectomy soft-tissue reconstructive procedures performed (Fig. 20.20). At a mean 2-year follow-up, grip and pinch strengths increased 19% compared




Fig. 20.20 The Burton and Pelligrini procedure begins with the removal of the trapezium, followed by the harvest of a portion of the flexor carpi radialis tendon (or whole tendon, as illustrated). **(A)** The tendon is passed through a drill hole created in the base of the metacarpal in a volar to dorsal direction. **(B)** The tendon is then sewn to itself to stabilize the metacarpal base of the thumb. **(C)** The remaining tendon is then placed into the space left by the resected trapezium to function as an interpositional spacer.

with preoperative values.²²⁸ At 9-year follow-up, thumb function improved further (grip strength 93%, tip-pinch strength 65%, and key-pinch strength 34%), suggesting that the procedure is not only durable but also improves thumb function for several years postoperatively.²³¹ Loss of trapezial space averaged 11% at 2 years²²⁸ and 13% at 9 years postoperatively,²³¹ despite the interposition of a portion of the FCR tendon.

Another variation on LRTI is the Brunelli procedure.¹⁸⁰ Described in 1989, Brunelli utilized one of the slips of the APL tendons for the ligament reconstruction. The tendon is divided proximally, leaving its insertion intact. It is then passed through a tunnel created in the base of the thumb and index metacarpals and sutured to the second and third carpometacarpal ligaments. Tendon interposition may be achieved using a palmaris longus graft. Like ligament reconstruction with FCR, this form of ligament reconstruction has also been advocated for use in early (stage I) disease without performing a trapeziectomy.¹⁸⁰

Other modifications to the trapeziectomy procedure have included the use of tendon slings or *suspensionplasties*. Suspensionplasties are thought to resist the sagittal plane collapse that occurs when the weakened arthritic thumb is loaded during pinch.²²¹ Weilby described a suspensionplasty that avoids the use of bony tunnels by simply weaving a slip of FCR around the APL and remaining FCR in a figure-of-eight fashion (Fig. 20.21).²³² The procedure has been reported to relieve pain in 92% patients.²³³ It affects thumb mobility in 12% patients, and while it improves grip and pinch strengths, recovery usually takes 3–6 months.

Exposure for the Weilby suspensionplasty is accomplished using the modified Wagner incision previously described. The radial artery and sensory nerve are identified and protected. A radial slip of FCR is released at the level of its myotendinous junction and freed all the way distally to base of the metacarpal. A capsulotomy of the CMC joint is performed and followed by a trapeziectomy. If the scaphotrapezoidal joint appears arthritic on traction of the index and long fingers, a proximal trapezoidectomy is performed.²²¹ The thumb is then held in distraction and radial abduction, making sure the base of the first metacarpal is in line with the base of the second metacarpal. The slip of the FCR is then passed through a slit in the APL tendon. The tendon is then secured at its insertion through the APL. The remaining tendon is then passed in a figure-of-eight fashion around the APL and remaining FCR to form a firm sling at the base of the metacarpal. The tendon construct is secured with sutures and then the capsule and skin are closed.²³² This procedure may be performed alternatively with a slip of the APL passed through a slit in the FCR (see Fig. 20.21).²³⁴

At around 10 days postoperatively, a cast replaces the thumb spica splint for another 3 weeks. The patient is placed in a custom-made thumb spica splint when range of motion exercises are started at around 4 weeks postoperatively.




Fig. 20.21 The Weilby suspensionplasty uses a portion of the flexor carpi radialis (FCR) to create a sling below the metacarpal base to prevent proximal migration of the thumb. The slip of the FCR is wrapped between the abductor pollicis longus (APL) and the remaining slip of the FCR (**A**, **B**). (**C**) An intraoperative photograph of the weave being started by wrapping the slip of the FCR around the APL tendon.

Strengthening and opposition across the palm are delayed until around 8 weeks postoperatively. The splint is then weaned by 10 weeks.²²¹

Despite variation in surgical technique, there seems to be minimal outcome differences between simple trapeziectomy, trapeziectomy with ligament reconstruction, and LRTI. When compared in a 2004 prospective randomized trial,²³⁵ no difference in grip strength, pinch strength, or thumb subsidence was noted at 8.2-month follow-up between patients who underwent trapeziectomy and ligament reconstruction alone and patients who underwent ligament interposition as well. A randomized control trial published in 2014 compared the LRTI technique of Burton and Pellegrini to the Weilby in 79 patients. While the LRTI group had less pain and better Patient-Related Wrist and Hand Evaluation (PRWHE) at 3 months, these differences did not persist to 12 months, at which point both groups had similar results.²³⁶

A 2009 Cochrane review²²⁹ included nine studies involving 477 patients undergoing various procedures for basal thumb

OA. The review concluded that, “while no procedure appears to be superior over another in terms of pain, physical function, patient satisfaction, or range of motion, there is insufficient evidence at this time to be certain.” The review, however, did demonstrate that LRTI, when compared to simple trapeziectomy, is associated with 12% more adverse effects (including scar tenderness, tendon adhesion or rupture, sensory change, or complex regional pain syndrome type 1). The small number of studies included in this review and each study’s unclear risk of bias have raised some doubts with regard to these results.

Prosthetic arthroplasty

Silicone arthroplasty for the TM OA was introduced independently in the late 1960s by Swanson²³⁷ and Niebauer.²³⁸ The procedure had the theoretical advantage of minimizing proximal migration of the thumb metacarpal after trapeziectomy. Early reports showed good results in the short

term^{237,239}; however longer follow-up noted a high incidence of dorsoradial subluxation.²⁴⁰ Subluxation continued to be a problem even after modifications in technique and implant design.^{237,239,240} Reports of implant wear, silicone synovitis, and bone erosion also started emerging in the late 1980s.²⁴¹ With implant wear, investigators noted a 50% loss of implant height (especially on the ulnar border of the implant) at 4-year follow-up.²⁴² A 16% revision rate for silicone synovitis was also noted. Because of these complications, silicone implant CMC arthroplasty fell out of favor with most surgeons. Recently, however, Bezwada and colleagues²⁴³ showed that osteolysis, implant wear, and subluxation did not directly correlate with clinical or subjective outcomes. In their study, they reported an 84% rate of patient satisfaction with and no radiographic evidence of synovitis.

Comparative studies are few, but in 2005, Taylor *et al.*²¹⁵ performed a retrospective comparison between patients undergoing silicone arthroplasty, resection arthroplasty (with and without ligament reconstruction), and arthrodesis for the treatment of TM OA. Taylor found no significant differences in the clinical outcomes between silicone arthroplasty and resection arthroplasty over 5-year period. In this study, the arthrodesis group was found to have a higher re-operation rate.²¹⁵ While the follow-up may not be long enough to document clinical deterioration of silicone implants,²⁴⁴ this study suggests that silicone arthroplasty may be a reliable option for disabling, refractory basal thumb OA, especially in the low-demand patient. A newly developed one-piece silicone implant that has been shown to be biomechanically superior to LRTI may expand the current indications for silicone arthroplasty in CMC OA.²⁴⁵

Other types of TM arthroplasty have included metallic prostheses mainly of a ball-and-socket design.²⁴⁶ Constrained TM joint prostheses are more prone to loosening, while non-constrained prostheses dislocate more easily.²⁴⁶ The de la Caffiniere implant (ball-and-socket, cemented, semi-constrained prosthesis) is probably the most widely used and most studied.²⁴⁷ The implant has a cobalt–chromium ball inserted into the shaft of the metacarpal and a polyethylene cup placed in the trapezium. Outcome studies have shown that patients with preoperative complaints of pain or instability do better than those with preoperative stiffness as their major complaint.²⁴⁷ The implants have a 72–89% 16-year implant survival rate, with higher prevalence of loosening of the trapezial component and a greater need for revision surgery in working-age men.^{248,249} In lieu of a silicone prosthesis, this implant may be considered in women over the age of 60 years for whom joint stiffness is not a main complaint.^{246,250}

Other TM joint prostheses have produced high failure rates over time and have fallen from favor due to loosening, heterotopic bone formation and subsidence.^{251–253} More recent implant designs have focused on metacarpal resurfacing in hopes of producing a *hemiarthroplasty*. The PyroCarbon metacarpal replacement hemiarthroplasty (Integra, Plainsboro, NJ) has shown promise in grade II and III disease. Subluxation of the implant, however, is a likely complication if the trapezial cup is made too shallow (Fig. 20.22).²⁵⁴

Trapeziometacarpal arthrodesis

With the success of the above reconstructive techniques, arthrodesis is now usually reserved for young (<50 years)



Fig. 20.22 Example of a PyroCarbon arthroplasty of the thumb trapeziometacarpal joint.

high-demand patients who wish to maintain grip strength or as a salvage procedure for failed reconstructions. Although a previous report has suggested that mild pantrapezial arthritis is not an absolute contraindication for TM arthrodesis,²⁵⁵ most authorities feel that the procedure should not be performed in the setting of STT arthritis.^{256–258} The optimal position to fuse the joint is 35° of radial and palmar abduction with 15° pronation and 10° of extension.²⁵⁹ This position replicates the position of the thumb in a fully clenched fist with the distal phalanx of the thumb resting on the middle phalanx of the index finger. Methods for CMC arthrodesis include slotted bone grafts, cerclage wiring, tension band wiring, staples, K-wire fixation, and screw fixation.²⁵⁹ Screw and plate fixation has a higher rate of complications requiring hardware removal.²⁶⁰

Technique for arthrodesis

The surgical exposure for CMC arthrodesis (Fig. 20.23) is similar to that of a trapeziectomy. The base of the thumb metacarpal is delivered into the incision by flexing and adducting the shaft.²⁵⁹ The eburnated articular cartilage and



Fig. 20.23 Example of a trapeziometacarpal joint fusion.

bone of the trapezium and metacarpal base are removed, exposing the cancellous bone. Surfaces are molded to allow for maximum bone contact between the two ends. If K-wires are being used, three 0.045 wires are usually needed, with one wire placed parallel to the long axis of the bones and the other two crossing at 15° to the axis. The K-wires should not extend proximal to the trapezium unless the trapezium is too osteopenic to hold stable fixation. K-wires are usually removed 6–8 weeks postoperatively. Postoperatively, patients are immobilized in a thumb spica until fusion is confirmed radiographically.²⁵⁹

Successful fusion will result in diminished thumb opposition and an inability to lay the hand flat.²⁵⁹ Normal MP and ST joints, however, can compensate well for this limitation to allow for a functional thumb range of motion post-fusion. Post-fusion, MP joint and ST joint motions can increase by 75% and 25%, respectively.²⁵⁶

Common complications of CMC arthrodesis include nonunion, progression to peritrapezial arthritis, and symptomatic hardware requiring removal.²⁵⁹ Radial sensory neuritis may also occur. Many nonunions are asymptomatic. Symptomatic nonunions may be treated with repeat arthrodesis, simple

trapeziectomy, or LRTI.²⁵⁹ In the literature, radiographic nonunion rates range from 6–12.5%,^{255,258,261–264} with one study reporting a nonunion rate as high as 50%.²⁶⁵ There appears to be no correlation between nonunion rates and the use of bone grafts.²⁶⁶ Rizzo and colleagues recently reported on the outcomes of 126 patients following TM arthrodesis. Over the average follow-up period of 11.2 years, the incidence of radiographic STT arthritis was noted to be 31% and MP arthritis was identified in 12.7% of patients.²⁶⁶ Despite these high values, none of the patients with radiographic MP arthritis were symptomatic and only 6% of patients with STT arthritis were symptomatic.²⁶⁶

Despite its disadvantages and complications, patient satisfaction with TM arthrodesis is usually high, with adequate recovery of pinch and grip strength postoperatively. While some have reported satisfaction rates as low as 60–78%,^{261,264} most studies report a satisfaction rate >90%.^{257,265,267} Although arthrodesis is generally recommended for younger patients, the procedure actually has favorable outcomes in patients over 50 years as well.²⁶⁸

OA of the wrist

Etiology

Osteoarthritis of the wrist may be primary (idiopathic) or secondary. Causes of primary OA include avascular necrosis of the lunate or scaphoid (Kienbock's or Preiser's disease, respectively), which can lead to degenerative changes throughout the wrist in later stages.^{269,270} Congenital deformities, such as Madelung's deformity, can alter articular load patterns at the ulnocarpal, radiocarpal, and distal radial ulnar joints leading to the development of wrist OA. Perhaps the most common idiopathic OA of the wrist is that involving the STT joint. Epidemiologic studies note a very high incidence of STT arthritis in the general population. A radiographic and anatomic study by North and Eaton demonstrated an incidence of STT arthritis in 34% of wrists.²⁷¹ Another cadaver study reported the incidence of STT arthritis in 83% of cadaver wrists.²⁷²

Secondary causes of osteoarthritis of the wrist usually are related to trauma, with scapholunate ligamentous injury, distal radius fractures, and scaphoid fractures contributing most frequently to the development of secondary radiocarpal OA. Scapholunate interosseus ligament injury can lead to a progressive form of carpal instability, which may lead to the development of *scapholunate advanced collapse* (SLAC) arthritis.^{273,274} In 1984, Watson and Ballet published a review of 121 wrist radiographs with degenerative arthritis due to scapholunate advanced collapse.²⁷³ This pattern accounted for 55% of all wrists with degenerative changes and was the most common pattern of wrist arthritis. They found that arthritis initially involved the radial styloid (stage 1) and scaphoid waist, then progressed to involve the proximal scaphoid and scaphoid fossa of the radius (stage 2), with arthritis finally being identified in the midcarpal joint at the lunocapitate articulation (stage 3).²⁷³ Other authors have added a fourth stage, which describes pan-carpal arthritis with diffuse involvement of the radiocarpal and midcarpal joints, with or without involvement of the distal radioulnar joint (Fig. 20.24).^{275–277}




Fig. 20.24 Examples of scapholunate advanced collapse (SLAC) arthritis. **(A)** An example of stage II SLAC changes. There is evidence of advanced arthritis at the radial styloid and radioscaphoid fossa, but the midcarpal joint is still relatively free of arthritic changes. **(B)** A posteroanterior radiograph of a wrist with stage III SLAC changes. In addition to arthritis at the scaphoid fossa, there is narrowing of the capitulunate articulation, and midcarpal arthritis. **(C)** A lateral wrist radiograph in the same patient showing significant midcarpal instability with a dorsal intercalated segment instability (DISI) pattern.

The important point to note about SLAC arthritis is that the radiolunate joint is typically spared.^{274–279} However, a recent publication by Lane *et al.* suggests that in a minority of cases (5–6% of SLAC wrists), the lunate fossa may be arthritic as well.²⁸⁰ For this reason, it is important to assess the lunate fossa before committing to a particular reconstruction.

Wrist or forearm fracture can also lead to osteoarthritis of the wrist. The cause can be related directly to damage to the articular surface of the joint with an intra-articular fracture, with or without malunion. Alternatively, extra-articular distal radius fractures can result in malunion leading to abnormal joint wear.^{281,282} Extra-articular distal radius fracture malunion can result in radial shortening, loss of radial inclination, loss of volar tilt, supination of the distal fragment, or radial or ulnar translation of the distal fragment. Each of these malunion patterns can result in abnormal load patterns across the wrist or adaptive malalignment deformities that can resemble instability patterns.^{281,283} The end result of the abnormal load and wear may be osteoarthritis. In a classic report of intra-articular distal radius fractures, Knirk and Jupiter report 91% incidence of arthritis on late follow-up if there was any degree of articular step-off after fracture reduction and 100% incidence of arthritis (8/8) if there was >2 mm step-off of the articular surface.²⁸⁴ Only 11% of those wrists with a congruent articular reduction developed arthritis at late follow-up. The presence of wrist arthritis within this study adversely affected the clinical outcome.

The final major cause of wrist OA is the sequela of untreated or mal-united scaphoid fractures. It is estimated that between 5% and 10% of all scaphoid fractures will fail to heal.²⁸⁵ Scaphoid nonunion can lead to a pattern of carpal instability similar to that seen with scapholunate ligament injury.²⁸⁶ Like the SLAC wrist, scaphoid nonunion can lead to wrist arthritis in a predictable pattern and is termed *scaphoid nonunion advanced collapse* (SNAC) arthritis.^{279,285,287} There are three stages of

SNAC arthritis that have been adapted from the description by Ruby *et al.*: stage I involves arthritis at the radial styloid and scaphoid articulation^{279,287,288}; stage II involves progressive degeneration of the radioscaphoid articulation and scapho-capitate joint; stage III includes the pathology found in stages I and II but with progression to include the lunocapitate articulation (Fig. 20.25).^{279,288}

Patient evaluation

Evaluation of the patient with suspected wrist arthritis begins with a careful history and physical examination. Important aspects of the history include the mechanism of original injury, quality and location of the pain, and exacerbating and alleviating factors. It is important to note what measures the patient has already tried to treat the pain, such as splinting, steroid injection or NSAIDs. It is important to determine the degree to which the pain is affecting the patient's lifestyle and work, as this will dictate the decision to treat with non-operative methods or proceed to wrist salvage. This is an important consideration as surgery may require a significant investment by the patient in terms of time off work due to immobilization and a potential loss of wrist motion. For these reasons, it is often advisable to see the patient on more than one occasion and sometimes follow them for years before embarking on a reconstruction. In the meantime, pain is managed with non-operative means such as splinting, NSAIDs (oral and/or topical), and periodic steroid injections.

A critical evaluation of PA and lateral wrist radiographs is essential. In doing so, one should get a sense of the etiology of the OA, whether secondary or primary. One must note which articulations are involved and which are spared as this will dictate what surgical options are available, i.e., involvement of the lunocapitate articulation in the SLAC wrist.



Fig. 20.25 A posteroanterior wrist radiograph of a patient with stage II scapholunate advanced collapse (SLAC) arthritis.

Involvement of the lunocapitate articulation should give one pause before proceeding with a proximal row carpectomy reconstruction as this will leave an arthritic capitate head behind to articulate with the lunate fossa. In this situation, a midcarpal fusion, such as a scaphoidectomy and four-corner fusion may be more appropriate. Further imaging such as a computed tomography scan, magnetic resonance imaging, or bone scan is not part of the routine evaluation, but may be indicated in select situations to evaluate for early signs of midcarpal arthritis. Another helpful diagnostic adjunct is a selective injection of lidocaine, with or without steroid, into the joint in question. This test can be potentially useful for diagnosis as well as treatment. A study by Bell *et al.* looked at the diagnostic utility of midcarpal lidocaine (with or without corticosteroid) injection in patients with chronic wrist pain.²⁸⁹ They noted that patients with chronic wrist pain had an improvement in grip strength with the injection, whereas normal volunteers had a reduction in grip strength. In addition, those patients with an improvement of >6 kg or >28% improvement over baseline had a 73% sensitivity and 70% specificity of having intracarpal pathology at arthroscopy.

Surgical treatment

Surgery is directed at elimination of pain at the arthritic joint through debridement (radial styloidectomy), denervation (neurectomy), arthroplasty, or partial or total wrist arthrodesis. The specific treatment is carefully selected based on the patient's symptoms, expectations, pattern of arthritis, and functional demands. Biomechanical data is available to help predict the range of motion that may be expected with proximal row carpectomy, midcarpal joint fusion, and radiocarpal joint fusion.^{290,291} Based on these studies, midcarpal fusion can result in a wrist with 50–67% of the motion of the normal side, radiocarpal fusion will provide only 33–40% of contralateral motion. If the distal pole of the scaphoid is removed following a radioscapulohumeral fusion, an additional 15–20% of motion is possible. Proximal row carpectomy can preserve 50–75% of contralateral wrist motion.²⁷⁶

Technique for dorsal approach to the wrist

The surgical approach to the wrist should account for the likelihood of future additional procedures should the selected initial treatment option fail. A total wrist fusion represents the ultimate salvage for wrist arthritis. Since this is typically performed through a longitudinal dorsal wrist incision in line with the third metacarpal, this approach is recommended for limited salvage procedures, such as partial wrist arthrodesis. Following the skin incision, full-thickness flaps are raised in an ulnar and radial direction. The extensor retinaculum is opened over the third extensor compartment and the extensor pollicis longus tendon is transposed. The retinaculum is raised in a radial and ulnar direction. The second and fourth compartment tendons are retracted and the dorsal wrist capsule is exposed. A ligament sparing incision is made in the capsule (Fig. 20.26).^{292,293} The incisions create a radially based flap in line with the dorsal radiotriquetral ligament and dorsal intercarpal ligament. This approach gives excellent exposure of the midcarpal joint as well as the scaphoid.

Radial styloidectomy


For patients with early SLAC arthritis where arthritis is confined to the radial styloid, radial styloidectomy may be performed as a conservative palliative procedure, either in isolation or in combination with other another procedure. Radial styloidectomy is usually performed subperiosteally through the anatomic snuffbox. It is important to preserve the volar attachment of the radioscapulohumeral ligament during the procedure, which inserts into the radial styloid. If more than a 6–10 mm of styloid is removed, the radioscapulohumeral ligament origin will be significantly compromised, possibly resulting in ulnar translation of the carpus.^{294–296} The radial styloid fragment may be used as a bone graft for concomitant fusion procedures.

Neurectomy


Total denervation of the wrist is associated with improved pain without loss of motion and with minimal morbidity and convalescence.^{297–299} Partial denervation of the anterior interosseous nerve (AIN) and posterior interosseous nerve (PIN) is possible through a single dorsal incision.³⁰⁰ This procedure has been shown to provide partial relief of wrist pain in cases of radiocarpal arthritis at an average of 31 months after surgery.³⁰¹ In a study of 20 patients, performed by Weinstein and Berger, only three patients required additional procedures for pain relief following AIN/ PIN neurectomy. Most patients in this study continued to have some wrist pain, but the majority (90%) were significantly improved. Prior to proceeding with neurectomy, patients should undergo a selective AIN/PIN block with long-acting anesthetic to verify that pain relief will be adequate. This allows the patient to assess the level of relief that may be expected from the denervation procedure.³⁰¹

Proximal row carpectomy

Proximal row carpectomy (PRC) is an option when the proximal capitate articular surface and the lunate fossa of the radius are preserved (Fig. 20.27). In other words, there is no arthritis at the midcarpal joint or radiolunate joint. PRC



A



B

Fig. 20.26 Dorsal exposure to the wrist bones is accomplished through the use of a ligament-sparing capsulotomy. (A) A triangular shaped flap is designed over the dorsum of the wrist capsule extending from the Lister's tubercle to the triquetrum and back to the upper third of the scaphoid. (B) The capsulotomy runs in line with the fibers of the dorsal radioscaphocapitate ligament and the dorsal intercarpal ligament. S, scaphoid. L, lunate. C, capitate. T, triquetrum. H, hamate.



Fig. 20.27 A posteroanterior wrist radiograph of a proximal row carpectomy (PRC). A PRC involves the removal of the scaphoid, lunate and triquetrum. The lunate fossa of the radius and the articular surface of the capitate should be free of arthritic changes to maximize the outcome of this procedure.

entails removal of the entire proximal carpal row (scaphoid, lunate, and triquetrum) and results in the wrist functioning as a simple hinge joint. The capitate articulates with the lunate facet of the radius. The radius of curvature of the lunate fossa is larger than that of the capitate head and there is resultant incongruity at the new articulation. This incongruity may lead to articular wear between the capitate head and radius.

Proximal row carpectomy has some advantages over intercarpal fusions. It does not require a lengthy period of immobilization for an arthrodesis to heal. Krakauer *et al.* have compared proximal row carpectomy with intercarpal fusion.³⁰² They found that carpectomy preserved better motion, an average arc of 71° versus 54° for limited arthrodesis. Both types of procedure preserved reasonable strength and reduced pain.

There is limited data on long-term outcomes after PRC. Jebson and colleagues reported on 20 patients, 11 of who underwent PRC for osteoarthritis. Two patients in this series required wrist arthrodesis for persistent pain. The remaining 18 patients were evaluated at an average of 13 years following surgery. The average wrist range of motion and the average maximal grip strength was 63% and 83%, respectively, of the opposite extremity. Sixteen of the 18 patients had returned to their previous employment. Flattening of the capitate was present in 33% of patients and 22% of patients had some evidence of moderate to severe radiocapitate arthrosis. However, this finding did not correlate with patient satisfaction, wrist pain, or function.³⁰³ DiDonna and colleagues have also published similar findings in a long-term outcome study of PRC with a minimum of 10-year follow-up. There were four failures (18%) requiring fusion at an average of 7 years following initial surgery. The average flexion extension

arc was 72° with and average grip strength of 91% of the contralateral side. Of the 18 wrists that did not fail, all patients were either satisfied or very satisfied with the procedure, with an overall DASH score of 9. Degenerative changes were seen in 14 of 17 wrists at the radiocapitate articulation at follow-up. However, like the findings by Jebson, this did not correlate with symptoms.³⁰⁴

Four-corner fusion

Scaphoidectomy and four-corner fusion represents another method for treating midcarpal and radial-sided wrist arthritis (Fig. 20.28). This procedure entails excision of the scaphoid and fusion of the midcarpal joint (lunate, capitate, triquetrum, and hamate). This procedure does not require preservation of the lunocapitate articulation and therefore may be appropriate in more advanced stages of the SLAC/SNAC wrist; however, it does require preservation of the radiolunate articulation.²⁸⁰ In 1984, Watson presented outcomes of his “SLAC procedure” for the SLAC wrist.²⁷³ Although this SLAC wrist procedure was initially proposed to be used with a silicone scaphoid implant, scaphoid excision without an implant works equally well and avoids the long-term risk of silicone synovitis. Potential advantages of four-corner fusion over PRC include: the retention of the native radiolunate interface; and preservation of the lunate and capitate preserves carpal height, which arguably maintains the resting muscle tension across the wrist, preserving grip strength.^{273,274}

Several studies have examined the functional outcome following four-corner fusion.^{302,305–309} Ashmead *et al.* reported on 100 cases, of which final wrist flexion–extension arc

averaged 53% of the contralateral side and final grip strength averaged 80% of the contralateral side. Nonunion occurred in only 3% of patients; 51% of patients had total resolution of wrist pain, while 15% continued to have pain with daily activities or at rest.³⁰⁵ More recently, Neubrech *et al.* reported on over 500 four-corner fusions with greater than 10-year follow-up. Forty (6.7%) fusions required conversion to complete wrist arthrodesis while 11% of patients required revision surgery. Fifty-six patients returned for follow-up exam an average of 14 years after initial surgery. They had an average flexion–extension arc of 62.5° and an average grip strength of 84.9% compared to the unaffected wrist.³⁰⁹

Techniques ensuring successful outcome have focused on adequate decortication of the four bony surfaces and correction of the dorsiflexed lunate to re-establish a collinear relationship between the lunate and capitate. Failure to correct lunate position can lead to limited wrist extension, hardware abutment, and pain.^{305,306} The use of bone graft has not been shown to clearly correlate with fusion rates, nor has hardware choice; however, hardware complications have been noted with pins, staples, and circular plates.^{302,307,310} In Vance *et al.*'s study, nonunion and impingement occurred in 48% of cases treated with circular plate fixation in comparison to a 6% rate with traditional fixation (K-wires, staples, or compression screws). Plate fixation was also associated with a higher rate of patient dissatisfaction.³¹⁰

A variation of four-corner fusion can involve capitulunate arthrodesis alone. Early attempts using this limited arthrodesis were associated with high rates of nonunion, most likely due to a smaller bony contact areas for successful bony fusion.^{311–313} These results were significantly improved by Calandruccio and colleagues, who combined capitulunate fusion with scaphoid and triquetral excision.³¹⁴ This procedure may provide for more wrist motion than four-corner fusion but long-term data is still pending.



Fig. 20.28 A posteroanterior radiograph showing an example of a scaphoidectomy and four-corner fusion. This wrist salvage option is indicated if there is evidence of arthritis at the midcarpal joint and the scaphoid fossa.

Total wrist arthrodesis and total wrist arthroplasty

In advanced arthritis where longstanding changes have resulted in injury to the midcarpal joint and the lunate fossa, wrist arthrodesis and wrist arthroplasty may be the only options for wrist salvage. Arthroplasty may be an enticing option because of the potential for motion preservation; however, the normal wrist functions through complicated interactions at multiple articulations across the wrist joints. It is impossible for a prosthesis to duplicate this complexity of motion and strength.³¹⁵ Therefore, there is a compromise that occurs for motion at the expense of strength. For these reasons, wrist arthroplasty is carefully selected only for those patients with low-demand wrists or who have a fusion of the contralateral wrist.³¹⁶ Patients with rheumatoid arthritis as opposed to osteoarthritis of the wrist tend to match the patient profile more appropriately for total wrist arthroplasty. The choice of wrist arthroplasty is dependent on the patient's age, activity level, and status of the contralateral wrist.

Total wrist arthrodesis represents the ultimate salvage procedure for all types of wrist arthritis. It involves fusion of the radiocarpal, midcarpal and third carpometacarpal joint. Total wrist arthrodesis is an established method of achieving pain relief and maintaining strength in patients without alternative options such as those with pan-carpal arthritis. This procedure is typically performed with the use of a dorsal



Fig. 20.29 (A) A complete wrist fusion may be accomplished with either the use of a dorsal plate or (B) the use of large intramedullary pins.

wrist fusion plate, but alternative methods have also been described using pins alone. Because the distal radioulnar joint (DRUJ) is not involved in a standard wrist fusion, forearm rotation is still possible. The ideal position for wrist fusion is in mild extension with mild ulnar deviation. This position maximizes grip strength (Fig. 20.29).

Wrist fusion is usually performed through a dorsal incision centered over the fourth extensor compartment. Decortication of the radiocarpal joint, midcarpal, and third finger CMC joint have been recommended to obtain solid fusion throughout the carpus. Alternatively, a proximal row carpectomy can be performed and the capitate can be fused to the lunate fossa of the radius. This technique can be beneficial for cases of profound wrist contractures, where decreasing the carpal height may allow for improvement in wrist position; however, it dramatically decreases the area of bony contact through which the fusion may occur. Bone graft is not necessary if good opposition between the bone ends is achieved, but in difficult cases bone graft may be acquired from the iliac crest, radial styloid, or any bones that are removed from the carpus at the time of fusion. During plate fixation, screws are ideally placed within the shaft of the third metacarpal and shaft of the radius. It is often possible to place additional screws into the capitate for additional fixation. Pin fixation, which lacks the rigidity of plate fixation, is usually achieved by placing long Steinmann or Rush pins through the intermetacarpal space of the index/long and long/ring fingers. Following fusion, the wrist is placed into plaster immobilization for 6–8 weeks, or until bony consolidation is seen on plain radiographs.

Future directions

The likely future direction of osteoarthritis treatment is cartilage replacement or regeneration. Articular cartilage has a limited capacity for regeneration and repair when damaged, due to its primarily avascular nature. Blood or bone marrow, which would usually enter an injured site and provide support for healing, do not arrive to the site of cartilage damage. Microfracture and drilling techniques are based on improving the blood flow to an area of injured cartilage to increase healing factors that may allow for cartilage regeneration.

Tissue engineering, which involves the use of scaffolds, cells, and stimulating factors (alone and in combination), is a potential avenue for treating cartilage damage.³¹⁷ Multiple clinical trials have shown early promising results for cartilage repair. Collagen-based, hyaluronic acid-based, and fibrin-based matrices have all been examined.^{318–320} However, each material has its limitations and drawbacks. For example, cell migration is limited in fibrin-based matrices while collagen-based gels require placement under a periosteal cover to avoid displacement. More recently, interest has shifted toward three-dimensional tissue-engineered constructs.³²¹ In this emerging technology, cells can be laid down layer by layer into the preformed shape necessary to replace the area of damage. The layered cell organization more closely mimics native cartilage structure. Despite the significant advances in tissue engineering, this technology remains limited in clinical application today but provides hope for the future of osteoarthritis treatment.

 Access the complete reference list online at <http://www.expertconsult.com>

173. Bettinger PC, Linscheid RL, Berger RA, et al. An anatomic study of the stabilizing ligaments of the trapezium and trapeziometacarpal joint. *J Hand Surg Am.* 1999;24:786–798. *This article provides a comprehensive and well-illustrated description of the ligaments stabilizing the trapezium and TMC joint. An anatomic study of 37 cadaver hands was performed identifying 16 ligaments with attachments at this important joint. Insertions, fiber orientations, and positions producing ligament tension are described for each ligament. A discussion of the biomechanical role and clinical relevance of the most important ligaments is presented.*
211. Freedman DM, Eaton RG, Glickel SZ. Long-term results of volar ligament reconstruction for symptomatic basal joint laxity. *J Hand Surg Am.* 2000;25:297–304.
223. Burton R. Basal joint arthritis. Fusion, implant, or soft tissue reconstruction? *Orthop Clin North Am.* 1986;17:493–503.
225. Davis TR, Pace A. Trapeziectomy for trapeziometacarpal joint osteoarthritis: is ligament reconstruction and temporary stabilisation of the pseudarthrosis with a Kirschner wire important? *J Hand Surg Eur Vol.* 2009;34:312–321. *This is a randomized prospective study comparing two surgical treatment options for basal thumb arthritis. A total of 61 thumbs underwent trapeziectomy, LRTI, K-wire immobilization and 6 weeks of splinting and 67 thumbs underwent trapeziectomy alone and 3 weeks of immobilization with a soft bandage. Outcome measures included pain, DASH scores, and thumb and grip strengths, which were all assessed at 3 and 12 months. Detailed results are presented and no significant difference between the procedures was detected in any of the outcomes measures.*
227. Barron OA, Glickel SZ, Eaton RG. Basal joint arthritis of the thumb. *J Am Acad Orthop Surg.* 2000;8:314–323.
266. Rizzo M, Moran SL, Shin AY. Long-term outcomes of trapeziometacarpal arthrodesis in the management of trapeziometacarpal arthritis. *J Hand Surg Am.* 2009;34:20–26. *The authors performed a 33-year retrospective study of trapeziometacarpal (TMC) arthrodeses performed at Mayo Clinic. Amongst 241 procedures reviewed, they included 126 thumbs with adequate pre- and postoperative clinical and radiographic data at an average 11-year follow-up. They report improvement of preoperative pain scores, oppositional and appositional pinch strength, and grip strength ($p < 0.01$). There was no significant change of any thumb motion arc. Nonunion rate was 13% and was unrelated to the use of bone grafting. Radiographic progression of STT arthritis was seen in 39 thumbs, only eight of which were symptomatic. This study presents detailed long-term outcomes of TMC arthrodesis, providing level IV evidence for the management of TMC arthritis.*
283. Linscheid RL, Dobyns JH, Beabout JW, et al. Traumatic instability of the wrist. Diagnosis, classification, and pathomechanics. *J Bone Joint Surg Am.* 1972;54:1612–1632. *This is a seminal article from 1972 that presents the foundation for study of carpal instability. The authors describe wrist instability that develops as a result of scapholunate and other carpal ligament injuries in addition to instability from fracture dislocations, scaphoid fractures, and fractures of the distal radius and ulna. They provide the earliest comprehensive dialogue of the diagnosis of carpal instability. The article includes clinical and radiographic data, a detailed discussion of the biomechanics of carpal instability, and proposal of the now accepted classification of dorsal and palmar intercalated segment instability. The radiographic parameters and nomenclature presented in this article remain in use today. The article has been recognized as a “classic orthopedic reference” and a summary was republished in the Journal of Bone and Joint Surgery in 2002.*
304. DiDonna ML, Kiefhaber TR, Stern PJ. Proximal row carpectomy: study with a minimum of ten years of follow-up. *J Bone Joint Surg Am.* 2004;86:2359–2365. *The authors retrospectively evaluate the long-term results of 22 proximal row carpectomy procedures performed for the treatment of scapholunate advanced collapse, scaphoid nonunion with advanced collapse or Kienbock’s disease. Outcomes were assessed by means of follow-up radiographs, objective measurement of motion and grip strength, and the DASH questionnaire. Their surgical technique is reviewed and results at a minimum 10-year follow-up (average 14 years) are presented. There were four failures (18%) at an average of 7 years, all of which occurred in patients younger than 35 years. The authors report a wrist motion arc of 72° and grip strength of 91% of that of the contralateral side in the 18 (82%) successes. They conclude that proximal row carpectomy is a viable motion-preserving procedure for advanced carpal arthritis that provides satisfactory long-term results in most patients, and advise against it in patients younger than 35 years.*
305. Ashmead D, Watson HK, Damon C, et al. Scapholunate advanced collapse wrist salvage. *J Hand Surg Am.* 1994;19:741–750.
307. Wyrick JD, Stern PJ, Kiefhaber TR. Motion-preserving procedures in the treatment of scapholunate advanced collapse wrist: proximal row carpectomy versus four-corner arthrodesis. *J Hand Surg Am.* 1995;20:965–970.

References

- Swanson AB, de Groot Swanson G. Osteoarthritis in the hand. *Clin Rheum Dis*. 1985;11(1):393–420.
- Alarcon-Segovia D. Letter: Pre-Columbian representation of Herberden's Nodes. *Arthritis Rheum*. 1976;19:125–126.
- WHO. *The global economic and healthcare burden of musculoskeletal disease*. In: World Health Organization, Bone and Joint Decade 2000–2010: <<http://www.boneandjointdecade.org>>; 2001. Geneva: World Health Organization.
- Haugen IK, Englund M, Aliabadi P, et al. Prevalence, incidence and progression of hand osteoarthritis in the general population: the Framingham Osteoarthritis Study. *Ann Rheum Dis*. 2011;70:1581–1586.
- Helmick CG, Felson DT, Lawrence RC, et al. Estimates of the prevalence of arthritis and other rheumatic conditions in the United States. Part I. *Arthritis Rheum*. 2008;58:15–25.
- Aigner T, McKenna L. Molecular pathology and pathobiology of osteoarthritic cartilage. *Cell Mol Life Sci*. 2002;59:5–18.
- Ateshian GA. The role of interstitial fluid pressurization in articular cartilage lubrication. *J Biomech*. 2009;42:1163–1176.
- Buckwalter JA, Mankin HJ, Grodzinsky AJ. Articular cartilage and osteoarthritis. *Instr Course Lect*. 2005;54:465–480.
- Pollard TCB, Gwilym SE, Carr AJ. The assessment of early osteoarthritis. *J Bone Joint Surg Br*. 2008;90:411–421.
- Urban JP, Maroudas A, Bayliss MT, et al. Swelling pressures of proteoglycans at the concentrations found in cartilaginous tissues. *Biorheology*. 1979;16:447–464.
- Wigley C. Functional Anatomy of the Musculoskeletal System. Standring S, ed. *Grays Anatomy The Anatomical Basis of Clinical Practice*. 40th ed. London: Elsevier; 2008.
- Hodge WA, Fijan RS, Carlson KL, et al. Contact pressures in the human hip joint measured in vivo. *Proc Natl Acad Sci USA*. 1986;83:2879–2883.
- Mitchell PG, Magna HA, Reeves LM, et al. Cloning, expression, and type II collagenolytic activity of matrix metalloproteinase-13 from human osteoarthritic cartilage. *J Clin Invest*. 1996;97:761–768.
- Arner EC, Pratta MA, Trzaskos JM, et al. Generation and characterization of aggrecanase. A soluble, cartilage-derived aggrecan-degrading activity. *J Biol Chem*. 1999;274:6594–6601.
- Abbaszade I, Liu RQ, Yang F, et al. Cloning and characterization of ADAMTS11, an aggrecanase from the ADAMTS family. *J Biol Chem*. 1999;274:23443–23450.
- Trippel SB. Growth factor actions on articular cartilage. *J Rheumatol Suppl*. 1995;43:129–132.
- Lotz M, Blanco FJ, von Kempis J, et al. Cytokine regulation of chondrocyte functions. *J Rheumatol Suppl*. 1995;43:104–108.
- Buckwalter JA, Saltzman C, Brown T. The impact of osteoarthritis: implications for research. *Clin Orthop Relat Res*. 2004;(427 suppl):S6–S15.
- Felson DT. Risk factors for osteoarthritis: understanding joint vulnerability. *Clin Orthop Relat Res*. 2004;(427 suppl):S16–S21.
- van Beuningen HM, van der Kraan PM, Arntz OJ, et al. Transforming growth factor-beta 1 stimulates articular chondrocyte proteoglycan synthesis and induces osteophyte formation in the murine knee joint. *Lab Invest*. 1994;71:279–290.
- Middleton J, Arnott N, Walsh S, et al. Osteoblasts and osteoclasts in adult human osteophyte tissue express the mRNAs for insulin-like growth factors I and II and the type 1 IGF receptor. *Bone*. 1995;16:287–293.
- Myers SL, Flusser D, Brandt KD, et al. Prevalence of cartilage shards in synovium and their association with synovitis in patients with early and endstage osteoarthritis. *J Rheumatol*. 1992;19:1247–1251.
- Kellgren JH, Lawrence JS. Radiological assessment of osteoarthrosis. *Ann Rheum Dis*. 1957;16:494–502.
- Schipphof D, Boers M, Bierma-Zeinstra SM. Differences in descriptions of Kellgren and Lawrence grades of knee osteoarthritis. *Ann Rheum Dis*. 2008;67:1034–1036.
- Wilder FV, Barrett JP, Farina EJ. Joint-specific prevalence of osteoarthritis of the hand. *Osteoarthritis Cartilage*. 2006;14:953–957.
- Drake ML, Segalman KA. Complications of small joint arthroplasty. *Hand Clin*. 2010;26:205–212.
- Snow JW, Boyes JG Jr, Greider JL Jr. Implant arthroplasty of the distal interphalangeal joint of the finger for osteoarthritis. *Plast Reconstr Surg*. 1977;60:558–560.
- Wilgis EF. Distal interphalangeal joint silicone interpositional arthroplasty of the hand. *Clin Orthop Relat Res*. 1997;38–41.
- Brown LG. Distal interphalangeal joint flexible implant arthroplasty. *J Hand Surg Am*. 1989;14:653–656.
- Schwartz DA, Peimer CA. Distal interphalangeal joint implant arthroplasty in a musician. *J Hand Ther*. 1998;11:49–52.
- Moran SL, Berger RA. Biomechanics and hand trauma: what you need. *Hand Clin*. 2003;19:17–31.
- Morgan WJ, Schulz LA, Chang JL. The impact of simulated distal interphalangeal joint fusion on grip strength. *Orthopedics*. 2000;23:239–241.
- Leibovic SJ. Internal fixation for small joint arthrodeses in the hand. The interphalangeal joints. *Hand Clin*. 1997;13:601–613.
- Zavitsanos G, Watkins F, Britton E, et al. Distal interphalangeal joint arthrodesis using intramedullary and interosseous fixation. *Hand Surg*. 1999;4:51–55.
- Stahl S, Rozen N. Tension-band arthrodesis of the small joints of the hand. *Orthopedics*. 2001;24:981–983.
- Uhl RL, Schneider LH. Tension band arthrodesis of finger joints: a retrospective review of 76 consecutive cases. *J Hand Surg Am*. 1992;17:518–522.
- Arata J, Ishikawa K, Soeda H, et al. Arthrodesis of the distal interphalangeal joint using a bioabsorbable rod as an intramedullary nail. *Scand J Plast Reconstr Surg Hand Surg*. 2003;37:228–231.
- Mantovani G, Fukushima WY, Cho AB, et al. Alternative to the distal interphalangeal joint arthrodesis: lateral approach and plate fixation. *J Hand Surg Am*. 2008;33:31–34.
- Teoh LC, Yeo SJ, Singh I. Interphalangeal joint arthrodesis with oblique placement of an AO lag screw. *J Hand Surg [Br]*. 1994;19:208–211.
- Tomaino MM. Distal interphalangeal joint arthrodesis with screw fixation: why and how. *Hand Clin*. 2006;22:207–210.
- Eriksson RA, Albrektsson T, Magnusson B. Assessment of bone viability after heat trauma. A histological, histochemical and vital microscopic study in the rabbit. *Scand J Plast Reconstr Surg*. 1984;18:261–268.
- Wyrsh B, Dawson J, Aufranc S, et al. Distal interphalangeal joint arthrodesis comparing tension-band wire and Herbert screw: a biomechanical and dimensional analysis. *J Hand Surg Am*. 1996;21:438–443.
- Engel J, Tsur H, Farin I. A comparison between K-wire and compression screw fixation after arthrodesis of the distal interphalangeal joint. *Plast Reconstr Surg*. 1977;60:611–614.
- Lamas Gomez C, Proubasta I, Escriba I, et al. Distal interphalangeal joint arthrodesis: treatment with Herbert screw. *J South Orthop Assoc*. 2003;12:154–159.
- Stern PJ, Fulton DB. Distal interphalangeal joint arthrodesis: an analysis of complications. *J Hand Surg Am*. 1992;17:1139–1145.
- Jsselstein C, van Egmond DB, Hovius SE, et al. Results of small-joint arthrodesis: comparison of Kirschner wire fixation with tension band wire technique. *J Hand Surg Am*. 1992;17:952–956.
- Brutus JP, Palmer AK, Mosher JF, et al. Use of a headless compressive screw for distal interphalangeal joint arthrodesis in digits: clinical outcome and review of complications. *J Hand Surg Am*. 2006;31:85–89.
- El-Hadidi S, Al-Kdah H. Distal interphalangeal joint arthrodesis with Herbert screw. *Hand Surg*. 2003;8:21–24.
- Faithfull DK, Herbert TJ. Small joint fusions of the hand using the Herbert Bone Screw. *J Hand Surg [Br]*. 1984;9:167–168.

50. Rizzo M, Beckenbaugh RD. Treatment of mucous cysts of the fingers: review of 134 cases with minimum 2-year follow-up evaluation. *J Hand Surg Am.* 2003;28:519–524.
51. Fisher RH. Conservative treatment of mucous cysts. *Clin Orthop Relat Res.* 1974;88.
52. Dodge LD, Brown RL, Niebauer JJ, et al. The treatment of mucous cysts: long-term follow-up in sixty-two cases. *J Hand Surg Am.* 1984;9:901–904.
53. Imran D, Koukkou C, Bainbridge LC. The rhomboid flap: a simple technique to cover the skin defect produced by excision of a mucous cyst of a digit. *J Bone Joint Surg Br.* 2003;85:860–862.
54. Young KA, Campbell AC. The bilobed flap in treatment of mucous cysts of the distal interphalangeal joint. *J Hand Surg [Br].* 1999;24:238–240.
55. Kawakatsu M, Ishikawa K. Dorsal digital perforator flap for reconstruction of distal dorsal finger defects. *J Plast Reconstr Aesthet Surg.* 2010;63:e46–e50.
56. Fritz GR, Stern PJ, Dickey M. Complications following mucous cyst excision. *J Hand Surg [Br].* 1997;22:222–225.
57. Bowers WH. *The Interphalangeal Joints.* Edinburgh: Churchill Livingstone; 1987.
58. Squitieri L, Chung KC. A systematic review of outcomes and complications of vascularized toe joint transfer, silicone arthroplasty, and PyroCarbon arthroplasty for posttraumatic joint reconstruction of the finger. *Plast Reconstr Surg.* 2008;121:1697–1707.
59. Chen SH, Wei FC, Chen HC, et al. Vascularized toe joint transfer to the hand. *Plast Reconstr Surg.* 1996;98:1275–1284.
60. Hierner R, Berger AK. Long-term results after vascularised joint transfer for finger joint reconstruction. *J Plast Reconstr Aesthet Surg.* 2008;61:1338–1346.
61. Tsubokawa N, Yoshizu T, Maki Y. Long-term results of free vascularized second toe joint transfers to finger proximal interphalangeal joints. *J Hand Surg Am.* 2003;28:443–447.
62. Lista FR, Neu BR, Murray JF, et al. *Profundus tendon blockage (the quadriga syndrome) in the hand with a stiff finger.* In: 43rd Annual Meeting of the American Society for Surgery of the Hand. Baltimore, MD; 1988.
63. Tubiana R. Arthrodesis of the fingers. In: Tubiana R, ed. *The Hand.* Philadelphia, PA: WB Saunders; 1985:698–702.
64. Carroll RE, Taber TH. Digital arthroplasty of the proximal interphalangeal joint. *J Bone Joint Surg Am.* 1954;36:912–920.
65. Eaton RG, Malerich MM. Volar plate arthroplasty of the proximal interphalangeal joint: a review of ten years' experience. *J Hand Surg Am.* 1980;5:260–268.
66. Engkvist O, Johansson SH. Perichondrial arthroplasty. A clinical study in twenty-six patients. *Scand J Plast Reconstr Surg.* 1980;14:71–87.
67. Seradge H, Kutz JA, Kleinert HE, et al. Perichondrial resurfacing arthroplasty in the hand. *J Hand Surg Am.* 1984;9:880–886.
68. Wu G, Johnson DE. Perichondrial arthroplasty in the hand: a case report. *J Hand Surg Am.* 1983;8:446–453.
69. Rizzo M, Beckenbaugh RD. Proximal interphalangeal joint arthroplasty. *J Am Acad Orthop Surg.* 2007;15:189–197.
70. Brannon EW, Klein G. Experiences with a finger-joint prosthesis. *J Bone Joint Surg Am.* 1959;41:87–102.
71. Linscheid RL, Murray PM, Vidal MA, et al. Development of a surface replacement arthroplasty for proximal interphalangeal joints. *J Hand Surg Am.* 1997;22:286–298.
72. Condamine JL, Benoit JY, Comtet JJ, et al. Proposed digital arthroplasty critical study of the preliminary results. *Ann Chir Main.* 1988;7:282–297.
73. Minamikawa Y, Imaeda T, Amadio PC, et al. Lateral stability of proximal interphalangeal joint replacement. *J Hand Surg Am.* 1994;19:1050–1054.
74. Uchiyama S, Cooney WP 3rd, Linscheid RL, et al. Kinematics of the proximal interphalangeal joint of the finger after surface replacement. *J Hand Surg Am.* 2000;25:305–312.
75. Linscheid RL, Dobyns JH. Total joint arthroplasty: the hand. *Mayo Clin Proc.* 1979;54:227–240.
76. Johnstone BR, Fitzgerald M, Smith KR, et al. Cemented versus uncemented surface replacement arthroplasty of the proximal interphalangeal joint with a mean 5-year follow-up. *J Hand Surg Am.* 2008;33:726–732.
77. Feldscher SB. Postoperative management for PIP joint pyrocarbon arthroplasty. *J Hand Ther.* 2010;23:315–322.
78. Sweets TM, Stern PJ. Proximal interphalangeal joint prosthetic arthroplasty. *J Hand Surg Am.* 2010;35:1190–1193.
79. Pellegrini VD Jr, Burton RI. Osteoarthritis of the proximal interphalangeal joint of the hand: arthroplasty or fusion? *J Hand Surg Am.* 1990;15:194–209.
80. Hagert CG, Eiken O, Ohlsson NM, et al. Metacarpophalangeal joint implants. I. Roentgenographic study on the silastic finger joint implants, Swanson design. *Scand J Plast Reconstr Surg.* 1975;9:147–157.
81. Lin HH, Wyrick JD, Stern PJ. Proximal interphalangeal joint silicone replacement arthroplasty: clinical results using an anterior approach. *J Hand Surg Am.* 1995;20:123–132.
82. Iselin F, Conti E. Long-term results of proximal interphalangeal joint resection arthroplasties with a silicone implant. *J Hand Surg Am.* 1995;20:S95–S97.
83. Swanson AB. Flexible implant arthroplasty for arthritic finger joints: rationale, technique, and results of treatment. *J Bone Joint Surg Am.* 1972;54:435–455.
84. Swanson AB, Maupin BK, Gajjar NV, et al. Flexible implant arthroplasty in the proximal interphalangeal joint of the hand. *J Hand Surg Am.* 1985;10:796–805.
85. Takigawa S, Meletiou S, Sauerbier M, et al. Long-term assessment of Swanson implant arthroplasty in the proximal interphalangeal joint of the hand. *J Hand Surg Am.* 2004;29:785–795.
86. Namdari S, Weiss AP. Anatomically neutral silicone small joint arthroplasty for osteoarthritis. *J Hand Surg Am.* 2009;34:292–300.
87. Pettersson K, Wagnsjo P, Hulin E. NeuFlex compared with Sutter prostheses: a blind, prospective, randomised comparison of Silastic metacarpophalangeal joint prostheses. *Scand J Plast Reconstr Surg Hand Surg.* 2006;40:284–290.
88. Jennings CD, Livingstone DP. Surface replacement arthroplasty of the proximal interphalangeal joint using the PIP-SRA implant: results, complications, and revisions. *J Hand Surg Am.* 2008;33:1565, e1–11.
89. Luther C, Germann G, Sauerbier M. Proximal interphalangeal joint replacement with surface replacement arthroplasty (SR-PIP): functional results and complications. *Hand (N Y).* 2010;5:233–240.
90. Branam BR, Tuttle HG, Stern PJ, et al. Resurfacing arthroplasty versus silicone arthroplasty for proximal interphalangeal joint osteoarthritis. *J Hand Surg Am.* 2007;32:775–788.
91. Bravo CJ, Rizzo M, Hormel KB, et al. Pyrolytic carbon proximal interphalangeal joint arthroplasty: results with minimum two-year follow-up evaluation. *J Hand Surg Am.* 2007;32:1–11.
92. Nunley RM, Boyer MI, Goldfarb CA. Pyrolytic carbon arthroplasty for posttraumatic arthritis of the proximal interphalangeal joint. *J Hand Surg Am.* 2006;31:1468–1474.
93. Tuttle HG, Stern PJ. Pyrolytic carbon proximal interphalangeal joint resurfacing arthroplasty. *J Hand Surg Am.* 2006;31:930–939.
94. Wijk U, Wollmark M, Kopylov P, et al. Outcomes of proximal interphalangeal joint pyrocarbon implants. *J Hand Surg Am.* 2010;35:38–43.
95. Herren DB, Schindele S, Goldhahn J, et al. Problematic bone fixation with pyrocarbon implants in proximal interphalangeal joint replacement: short-term results. *J Hand Surg [Br].* 2006;31:643–651.
96. Watts AC, Hearnden AJ, Trail IA, et al. Pyrocarbon proximal interphalangeal joint arthroplasty: minimum two-year follow-up. *J Hand Surg Am.* 2012;37:882–888.
97. Pettersson K, Amilon A, Rizzo M. Pyrolytic carbon hemiarthroplasty in the management of proximal interphalangeal joint arthritis. *J Hand Surg Am.* 2015;40:462–468.

98. Ellis PR, Tsai TM. Management of the traumatized joint of the finger. *Clin Plast Surg*. 1989;16:457–473.
99. Minami A, An KN, Cooney WP 3rd, et al. Ligament stability of the metacarpophalangeal joint: a biomechanical study. *J Hand Surg Am*. 1985;10:255–260.
100. Schultz RJ, Storace A, Krishnamurthy S. Metacarpophalangeal joint motion and the role of the collateral ligaments. *Int Orthop*. 1987;11:149–155.
101. Feldon P, Belsky MR. Degenerative diseases of the metacarpophalangeal joints. *Hand Clin*. 1987;3:429–447.
102. Fam AG, Kolin A. Unusual metacarpophalangeal osteoarthritis in a jackhammer operator. *Arthritis Rheum*. 1986;29:1284–1288.
103. Ross JM, Kowalchuk RM, Shaulinsky J, et al. Association of heterozygous hemochromatosis C282Y gene mutation with hand osteoarthritis. *J Rheumatol*. 2003;30:121–125.
104. Tupper JW. The metacarpophalangeal volar plate arthroplasty. *J Hand Surg Am*. 1989;14:371–375.
105. Flatt A. *Care of the Arthritic Hand*. 4th ed. Philadelphia, PA: Mosby; 1983.
106. Bolis GU, Oni JA, Davis TR. Palmar plate interposition (Tupper) arthroplasty for post-traumatic metacarpophalangeal osteoarthritis. *J Hand Surg [Br]*. 1997;22:94–95.
107. Vainio K. Vainio arthroplasty of the metacarpophalangeal joints in rheumatoid arthritis. *J Hand Surg Am*. 1989;14:367–368.
108. Riordan DC, Fowler SB. Arthroplasty of the metacarpophalangeal joints: review of resection-type arthroplasty. *J Hand Surg Am*. 1989;14:368–371.
109. Netscher D, Eladounikdachi F, Gao YH. Resurfacing arthroplasty for metacarpophalangeal joint osteoarthritis: a good option using either perichondrium or extensor retinaculum. *Plast Reconstr Surg*. 2000;106:1430–1433.
110. Varma SK, Milward TM. The Nicolle finger joint prosthesis: a reappraisal. *J Hand Surg [Br]*. 1991;16:187–190.
111. Doi K, Kuwata N, Kawai S. Alumina ceramic finger implants: a preliminary biomaterial and clinical evaluation. *J Hand Surg Am*. 1984;9:740–749.
112. Minami M, Yamazaki J, Kato S, et al. Alumina ceramic prosthesis arthroplasty of the metacarpophalangeal joint in the rheumatoid hand. A 2–4 year follow-up study. *J Arthroplasty*. 1988;3:157–166.
113. Swanson A. Silicone rubber implants for replacement of arthritis or destroyed joints in the hand. *Surg Clin North Am*. 1968;48:1113–1127.
114. Gillespie TE, Flatt AE, Youm Y, et al. Biomechanical evaluation of metacarpophalangeal joint prosthesis designs. *J Hand Surg Am*. 1979;4:508–521.
115. Moller K, Sollerman C, Geijer M, et al. Avanta versus Swanson silicone implants in the MCP joint – a prospective, randomized comparison of 30 patients followed for 2 years. *J Hand Surg [Br]*. 2005;30:8–13.
116. Kirschbaum D, Schneider LH, Adams DC, et al. Arthroplasty of the metacarpophalangeal joints with use of silicone-rubber implants in patients who have rheumatoid arthritis. Long-term results. *J Bone Joint Surg*. 1993;75:3–12.
117. Jensen CM, Boeckstyns ME, Kristiansen B. Silastic arthroplasty in rheumatoid MCP-joints. *Acta Orthop Scand*. 1986;57:138–140.
118. Hansraj KK, Ashworth CR, Ebrahimzadeh E, et al. Swanson metacarpophalangeal joint arthroplasty in patients with rheumatoid arthritis. *Clin Orthop Relat Res*. 1997;11–15.
119. Carter PR, Benton LJ, Dysert PA. Silicone rubber carpal implants: a study of the incidence of late osseous complications. *J Hand Surg Am*. 1986;11:639–644.
120. Peimer CA, Medige J, Eckert BS, et al. Reactive synovitis after silicone arthroplasty. *J Hand Surg Am*. 1986;11:624–638.
121. Rettig LA, Luca L, Murphy MS. Silicone implant arthroplasty in patients with idiopathic osteoarthritis of the metacarpophalangeal joint. *J Hand Surg Am*. 2005;30:667–672.
122. Joyce TI, Unsworth A. NeuFlex metacarpophalangeal prostheses tested in vitro. *Proc Inst Mech Eng H*. 2005;219:105–110.
123. Weiss AP, Moore DC, Infantolino C, et al. Metacarpophalangeal joint mechanics after 3 different silicone arthroplasties. *J Hand Surg Am*. 2004;29:796–803.
124. Bieber EJ, Weiland AJ, Volenc-Dowling S. Silicone-rubber implant arthroplasty of the metacarpophalangeal joints for rheumatoid arthritis. *J Bone Joint Surg Am*. 1986;68:206–209.
125. Fleming SG, Hay EL. Metacarpophalangeal joint arthroplasty eleven year follow-up study. *J Hand Surg [Br]*. 1984;9:300–302.
126. Wilson YG, Sykes PJ, Niranjan NS. Long-term follow-up of Swanson's Silastic arthroplasty of the metacarpophalangeal joints in rheumatoid arthritis. *J Hand Surg [Br]*. 1993;18:81–91.
127. Kessler I. A new silicone implant for replacement of destroyed metacarpal heads. *Hand*. 1974;6:308–310.
128. Beckenbaugh R. Preliminary experience with noncemented nonconstrained total joint arthroplasty for the metacarpophalangeal joints. *Orthopedics*. 1983;6:962–965.
129. Hagert CG, Branemark PI, Albrektsson T, et al. Metacarpophalangeal joint replacement with osseointegrated endoprotheses. *Scand J Plast Reconstr Surg*. 1986;20:207–218.
130. Lundborg G, Brånemark PI, Carlsson I. Metacarpophalangeal joint arthroplasty based on the osseointegration concept. *J Hand Surg [Br]*. 1993;18:693–703.
131. Kung PL, Chou P, Linscheid RL, et al. Intrinsic stability of an unconstrained metacarpophalangeal joint implant. *Clin Biomech (Bristol, Avon)*. 2003;18:119–125.
132. Cook SD, Klawitter JJ, Weinstein AM. The influence of implant elastic modulus on the stress distribution around LTI carbon and aluminum oxide dental implants. *J Biomed Mater Res*. 1981;15:879–887.
133. Sibly TF, Unsworth A. Fixation of a surface replacement endoprosthesis of the metacarpophalangeal joint. *Proc Inst Mech Eng H*. 1991;205:227–232.
134. Cook SD, Beckenbaugh RD, Redondo J, et al. Long-term follow-up of pyrolytic carbon metacarpophalangeal implants. *J Bone Joint Surg Am*. 1999;81:635–648.
135. Nunez VA, Citron ND. Short-term results of Ascension pyrolytic carbon metacarpophalangeal joint replacement arthroplasty for osteoarthritis. *Chir Main*. 2005;24:161–164.
136. Parker WL, Rizzo M, Moran SL, et al. Preliminary results of nonconstrained pyrolytic carbon arthroplasty for metacarpophalangeal joint arthritis. *J Hand Surg Am*. 2007;32:1496–1505.
137. Moberg E, Henrikson B. Technique for digital arthrodesis. A study of 150 cases. *Acta Chir Scand*. 1960;118:331–338.
138. Nicolle F. Intramedullary peg arthrodesis. In: Tubiana R, ed. *The Hand*. Philadelphia, PA: WB Saunders; 1985:707–709.
139. Carroll RE, Hill NA. Small joint arthrodesis in hand reconstruction. *J Bone Joint Surg Am*. 1969;51:1219–1221.
140. McGlynn JT, Smith RA, Bogumill GP. Arthrodesis of small joint of the hand: a rapid and effective technique. *J Hand Surg Am*. 1988;13:595–599.
141. Lister G. Intraosseous wiring of the digital skeleton. *J Hand Surg Am*. 1978;3:427–435.
142. Buck-Gramcko D. Compression arthrodesis of joints in the hand. In: Tubiana R, ed. *The Hand*. Philadelphia, PA: WB saunders; 1985:703–705.
143. Wright CS, McMurtry RY. AO arthrodesis in the hand. *J Hand Surg Am*. 1983;8:932–935.
144. Stern PJ, Gates NT, Jones TB. Tension band arthrodesis of small joints in the hand. *J Hand Surg Am*. 1993;18:194–197.
145. Khuri S. Tension band arthrodesis in the hand. *J Hand Surg Am*. 1986;11:41–45.
146. Buncke HJ, Valauri FA. Vascularized toe-joint transplantation. In: Buncke HJ, ed. *Microsurgery: Transplantation-Replantation*. Philadelphia, PA: Lea & Febiger; 1991:102–110.
147. Tsai TM, Wang WZ. Vascularized joint transfers. Indications and results. *Hand Clin*. 1992;8:525–536.

148. Ring D, Herndon JH. Implant arthroplasty of the metacarpophalangeal joint of the thumb. *Hand Clin.* 2001;17:271–273, x.
149. Day CS, Ramirez MA. Thumb metacarpophalangeal arthritis: arthroplasty or fusion? *Hand Clin.* 2006;22:211–220.
150. Haara MM, Heliovaara M, Kroger H, et al. Osteoarthritis in the carpometacarpal joint of the thumb. Prevalence and associations with disability and mortality. *J Bone Joint Surg Am.* 2004;86:1452–1457.
151. Berggren M, Joost-Davidsson A, Lindstrand J, et al. Reduction in the need for operation after conservative treatment of osteoarthritis of the first carpometacarpal joint: a seven year prospective study. *Scand J Plast Reconstr Surg Hand Surg.* 2001;35:415–417.
152. Meenagh GK, Patton J, Kynes C, et al. A randomised controlled trial of intra-articular corticosteroid injection of the carpometacarpal joint of the thumb in osteoarthritis. *Ann Rheum Dis.* 2004;63:1260–1263.
153. Mureau MA, Rademaker RP, Verhaar JA, et al. Tendon interposition arthroplasty versus arthrodesis for the treatment of trapeziometacarpal arthritis: a retrospective comparative follow-up study. *J Hand Surg Am.* 2001;26:869–876.
154. Swigart CR, Eaton RG, Glickel SZ, et al. Splinting in the treatment of arthritis of the first carpometacarpal joint. *J Hand Surg Am.* 1999;24:86–91.
155. Armstrong AL, Hunter JB, Davis TR. The prevalence of degenerative arthritis of the base of the thumb in post-menopausal women. *J Hand Surg [Br].* 1994;19:340–341.
156. Zhang Y, Niu J, Kelly-Hayes M, et al. Prevalence of symptomatic hand osteoarthritis and its impact on functional status among the elderly: The Framingham Study. *Am J Epidemiol.* 2002;156:1021–1027.
157. Marzke MW, Marzke RF. Evolution of the human hand: approaches to acquiring, analysing and interpreting the anatomical evidence. *J Anat.* 2000;197:121–140.
158. Spector TD, Hart DJ, Brown P, et al. Frequency of osteoarthritis in hysterectomized women. *J Rheumatol.* 1991;18:1877–1883.
159. Kessler S, Stove J, Puhl W, et al. First carpometacarpal and interphalangeal osteoarthritis of the hand in patients with advanced hip or knee OA. Are there differences in the aetiology? *Clin Rheumatol.* 2003;22:409–413.
160. Hart DJ, Spector TD. The relationship of obesity, fat distribution and osteoarthritis in women in the general population: the Chingford Study. *J Rheumatol.* 1993;20:331–335.
161. Cicuttini FM, Baker JR, Spector TD. The association of obesity with osteoarthritis of the hand and knee in women: a twin study. *J Rheumatol.* 1996;23:1221–1226.
162. Lippiello L, Walsh T, Fienhold M. The association of lipid abnormalities with tissue pathology in human osteoarthritic articular cartilage. *Metabolism.* 1991;40:571–576.
163. Waite H, Nevinny D, Rosenthal J, et al. Association of osteoarthritis and diabetes mellitus. *Tufts Folia Med.* 1961;7:13–19.
164. Lawrence J. Hypertension in relation to musculoskeletal disorders. *Ann Rheum Dis.* 1975;74:451–456.
165. Sowers M, Lachance L, Hochberg M, et al. Radiographically defined osteoarthritis of the hand and knee in young and middle-aged African American and Caucasian women. *Osteoarthritis Cartilage.* 2000;8:69–77.
166. Hochberg MC, Lane NE, Pressman AR, et al. The association of radiographic changes of osteoarthritis of the hand and hip in elderly women. *J Rheumatol.* 1995;22:2291–2294.
167. Hirsch R, Lethbridge-Cejku M, Scott WW Jr, et al. Association of hand and knee osteoarthritis: evidence for a polyarticular disease subset. *Ann Rheum Dis.* 1996;55:25–29.
168. Spector TD, Cicuttini F, Baker J, et al. Genetic influences on osteoarthritis in women: a twin study. *BMJ.* 1996;312:940–943.
169. Jonsson H, Manolescu I, Stefansson SE, et al. The inheritance of hand osteoarthritis in Iceland. *Arthritis Rheum.* 2003;48:391–395.
170. Katarincic JA. Thumb kinematics and their relevance to function. *Hand Clin.* 2001;17:169–174.
171. Bettinger PC, Berger RA. Functional ligamentous anatomy of the trapezium and trapeziometacarpal joint (gross and arthroscopic). *Hand Clin.* 2001;17:151–168, vii.
172. North ER, Rutledge WM. The trapezium-thumb metacarpal joint: the relationship of joint shape and degenerative joint disease. *Hand.* 1983;15:201–206.
173. Bettinger PC, Linscheid RL, Berger RA, et al. An anatomic study of the stabilizing ligaments of the trapezium and trapeziometacarpal joint. *J Hand Surg Am.* 1999;24:786–798. *This article provides a comprehensive and well-illustrated description of the ligaments stabilizing the trapezium and TMC joint. An anatomic study of 37 cadaver hands was performed identifying 16 ligaments with attachments at this important joint. Insertions, fiber orientations, and positions producing ligament tension are described for each ligament. A discussion of the biomechanical role and clinical relevance of the most important ligaments is presented.*
174. Cooney WP 3rd, Lucca MJ, Chao EY, et al. The kinesiology of the thumb trapeziometacarpal joint. *J Bone Joint Surg Am.* 1981;63:1371–1381.
175. Glickel SZ. Clinical assessment of the thumb trapeziometacarpal joint. *Hand Clin.* 2001;17:185–195.
176. Tsai P, Beredjikian PK. Physical diagnosis and radiographic examination of the thumb. *Hand Clin.* 2008;24:231–237, v.
177. Florack TM, Miller RJ, Pellegrini VD, et al. The prevalence of carpal tunnel syndrome in patients with basal joint arthritis of the thumb. *J Hand Surg Am.* 1992;17:624–630.
178. Eaton RG, Littler JW. Ligament reconstruction for the painful thumb carpometacarpal joint. *J Bone Joint Surg Am.* 1973;55:1655–1666.
179. Braun RM, Feldman CW. Total joint replacement at the base of the thumb. *Semin Arthroplasty.* 1991;2:120–129.
180. Brunelli G, Monini L, Brunelli F. Stabilisation of the trapeziometacarpal joint. *J Hand Surg [Br].* 1989;14:209–212.
181. Neumann DA, Bielefeld T. The carpometacarpal joint of the thumb: stability, deformity, and therapeutic intervention. *J Orthop Sports Phys Ther.* 2003;33:386–399.
182. Stamm TA, Machold KP, Smolen JS, et al. Joint protection and home hand exercises improve hand function in patients with hand osteoarthritis: a randomized controlled trial. *Arthritis Rheum.* 2002;47:44–49.
183. Hammond A, Freeman K. One-year outcomes of a randomized controlled trial of an educational-behavioural joint protection programme for people with rheumatoid arthritis. *Rheumatology (Oxford).* 2001;40:1044–1051.
184. Poole JU, Pellegrini VD Jr. Arthritis of the thumb basal joint complex. *J Hand Ther.* 2000;13:91–107.
185. Pellegrini VJ. Pathomechanics of the thumb trapeziometacarpal joint. *Hand Clin.* 2001;17:175–184, vii–viii.
186. Colditz J. The biomechanics of a thumb carpometacarpal immobilization splint: design and fitting. *J Hand Ther.* 2000;13:228–235.
187. Moulton MJ, Parentis MA, Kelly MJ, et al. Influence of metacarpophalangeal joint position on basal joint-loading in the thumb. *J Bone Joint Surg Am.* 2001;83:709–716.
188. Weiss S, LaStayo P, Mills A, et al. Prospective analysis of splinting the first carpometacarpal joint: an objective, subjective, and radiographic assessment. *J Hand Ther.* 2000;13:218–226.
189. Weiss S, Lastayo P, Mills A, et al. Splinting the degenerative basal joint: custom-made or prefabricated neoprene? *J Hand Ther.* 2004;17:401–406.
190. Yao J, Park MJ. Early treatment of degenerative arthritis of the thumb carpometacarpal joint. *Hand Clin.* 2008;24:251–261, v–vi.
191. Rannou F, Dimet J, Boutron I, et al. Splint for base-of-thumb osteoarthritis: a randomized trial. *Ann Intern Med.* 2009;150:661–669.
192. Brooks PM, Day RO. Nonsteroidal antiinflammatory drugs – differences and similarities. *N Engl J Med.* 1991;324:1716–1725.
193. Day CS, Gelberman R, Patel AA, et al. Basal joint osteoarthritis of the thumb: a prospective trial of steroid injection and splinting. *J Hand Surg Am.* 2004;29:247–251.

194. Dieppe P. Are intra-articular steroid injections useful for the treatment of the osteoarthritis joint? *Br J Rheumatol*. 1991;30:199.
195. Joshi R. Intraarticular corticosteroid injection for first carpometacarpal osteoarthritis. *J Rheumatol*. 2005;32:1305–1306.
196. Laurent TC, Fraser JR. Hyaluronan. *FASEB J*. 1992;6:2397–2404.
197. Peyron J. Intraarticular hyaluronan injections in the treatment of osteoarthritis: state-of-the-art review. *J Rheumatol Suppl*. 1993;39:10–15.
198. Fuchs S, Monikes R, Wohlmeiner A, et al. Intra-articular hyaluronic acid compared with corticoid injections for the treatment of rhizarthrosis. *Osteoarthritis Cartilage*. 2006;14:82–88.
199. Heyworth BE, Lee JH, Kim PD, et al. Hyal versus corticosteroid versus placebo for treatment of basal joint arthritis: a prospective, randomized, double-blinded clinical trial. *J Hand Surg Am*. 2008;33:40–48.
200. Doerschuk SH, Hicks DG, Chinchilli VM, et al. Histopathology of the palmar beak ligament in trapeziometacarpal osteoarthritis. *J Hand Surg Am*. 1999;24:496–504.
201. Pellegrini VD Jr, Olcott CW, Hollenberg G. Contact patterns in the trapeziometacarpal joint: the role of the palmar beak ligament. *J Hand Surg Am*. 1993;18:238–244.
202. Hobby JL, Lyall HA, Meggitt BF. First metacarpal osteotomy for trapeziometacarpal osteoarthritis. *J Bone Joint Surg Br*. 1998;80:508–512.
203. Badia A. Trapeziometacarpal arthroscopy: a classification and treatment algorithm. *Hand Clin*. 2006;22:153–163.
204. Badia A. Arthroscopy of the trapeziometacarpal and metacarpophalangeal joints. *J Hand Surg Am*. 2007;32:707–724.
205. Menon J. Arthroscopic management of trapeziometacarpal joint arthritis of the thumb. *Arthroscopy*. 1996;12:581–587.
206. Pellegrini VD Jr, Parentis M, Judkins A, et al. Extension metacarpal osteotomy in the treatment of trapeziometacarpal osteoarthritis: a biomechanical study. *J Hand Surg Am*. 1996;21:16–23.
207. Shrivastava N, Koff MF, Abbot AE, et al. Simulated extension osteotomy of the thumb metacarpal reduces carpometacarpal joint laxity in lateral pinch. *J Hand Surg Am*. 2003;28:733–738.
208. Tomaino M. Treatment of Eaton stage I trapeziometacarpal disease with thumb metacarpal extension osteotomy. *J Hand Surg Am*. 2000;25:1100–1106.
209. Tomaino M. Thumb by metacarpal extension osteotomy: rationale and efficacy for Eaton stage I disease. *Hand Clin*. 2006;22:137–141.
210. Eaton RG, Lane LB, Littler JW, et al. Ligament reconstruction for the painful thumb carpometacarpal joint: a long-term assessment. *J Hand Surg Am*. 1984;9:692–699.
211. Freedman DM, Eaton RG, Glickel SZ. Long-term results of volar ligament reconstruction for symptomatic basal joint laxity. *J Hand Surg Am*. 2000;25:297–304. *This is a 15-year follow-up study of 24 pre-arthritis hypermobile TMC joints that underwent volar ligament reconstruction for symptomatic ligament laxity, after failed conservative therapy. At final follow-up, 17 patients (71%) complained of intermittent or daily pain, seven patients (29%) had no pain, and only two joints (8%) progressed to stage III radiographic arthritis. The authors present a thorough review of clinical, radiographic and intraoperative characteristics in relation to long-term clinical and radiographic outcomes of the procedure. They conclude that volar ligament reconstruction is indicated for the painful hypermobile TMC joint and limits the progression of degenerative arthritis.*
212. Glickel SZ, Gupta S. Ligament reconstruction. *Hand Clin*. 2006;22:143–151.
213. Gervis W. Osteo-arthritis of the trapezio-metacarpal joint treated by excision of the trapezium. *Proc R Soc Med*. 1947;40:492.
214. Gervis WH. Excision of the trapezium for osteo-arthritis of the trapezio-metacarpal joint. *Postgrad Med J*. 1948;24:262–264.
215. Taylor EJ, Desari K, D'Arcy JC, et al. A comparison of fusion, trapeziectomy and silastic replacement for the treatment of osteoarthritis of the trapeziometacarpal joint. *J Hand Surg [Br]*. 2005;30:45–49.
216. Kvarnes L, Reikerås O. Osteoarthritis of the carpometacarpal joint of the thumb. An analysis of operative procedures. *J Hand Surg [Br]*. 1985;10:117–120.
217. Gray KV, Meals RA. Hematoma and distraction arthroplasty for thumb basal joint osteoarthritis: minimum 6.5-year follow-up evaluation. *J Hand Surg Am*. 2007;32:23–29.
218. De Smet L, Sioen W, Spaepen D, et al. Treatment of basal joint arthritis of the thumb: trapeziectomy with or without tendon interposition/ligament reconstruction. *Hand Surg*. 2004;9:5–9.
219. Lins RE, Gelberman RH, McKeown L, et al. Basal joint arthritis: trapeziectomy with ligament reconstruction and tendon interposition arthroplasty. *J Hand Surg Am*. 1996;21:202–209.
220. Fitzgerald BT, Hofmeister EP. Treatment of advanced carpometacarpal joint disease: trapeziectomy and hematoma arthroplasty. *Hand Clin*. 2008;24:271–276, vi.
221. Tomaino MM. Suspensionplasty for basal joint arthritis: why and how. *Hand Clin*. 2006;22:171–175.
222. Iyer KM. The results of excision of the trapezium. *Hand*. 1981;13:246–250.
223. Burton R. Basal joint arthritis. Fusion, implant, or soft tissue reconstruction? *Orthop Clin North Am*. 1986;17:493–503. *This is a review article summarizing the relevant anatomy and clinical features of basal thumb arthritis. The author highlights some of the advantages and disadvantages of several surgical options, and discusses fundamental considerations for successful operative management.*
224. Davis TR, Brady O, Dias JJ. Excision of the trapezium for osteoarthritis of the trapeziometacarpal joint: a study of the benefit of ligament reconstruction or tendon interposition. *J Hand Surg Am*. 2004;29:1069–1077.
225. Davis TR, Pace A. Trapeziectomy for trapeziometacarpal joint osteoarthritis: is ligament reconstruction and temporary stabilisation of the pseudarthrosis with a Kirschner wire important? *J Hand Surg Eur Vol*. 2009;34:312–321. *This is a randomized prospective study comparing two surgical treatment options for basal thumb arthritis. A total of 61 thumbs underwent trapeziectomy, LRTI, K-wire immobilization and 6 weeks of splinting and 67 thumbs underwent trapeziectomy alone and 3 weeks of immobilization with a soft bandage. Outcome measures included pain, DASH scores, and thumb and grip strengths, which were all assessed at 3 and 12 months. Detailed results are presented and no significant difference between the procedures was detected in any of the outcomes measures.*
226. Mahoney JD, Meals RA. Trapeziectomy. *Hand Clin*. 2006;22:165–169.
227. Barron OA, Glickel SZ, Eaton RG. Basal joint arthritis of the thumb. *J Am Acad Orthop Surg*. 2000;8:314–323. *This review article is presented by leaders in the study of basal thumb arthritis. The basic science, diagnosis and classification of the condition are reviewed in detail. A treatment algorithm is presented and their techniques for volar ligament reconstruction, and LRTI are reviewed and illustrated.*
228. Burton RI, Pellegrini VD Jr. Surgical management of basal joint arthritis of the thumb. Part II. Ligament reconstruction with tendon interposition arthroplasty. *J Hand Surg Am*. 1986;11:324–332.
229. Wajon A, Carr E, Edmunds I, et al. Surgery for thumb (trapeziometacarpal joint) osteoarthritis. *Cochrane Database Syst Rev*. 2009;(4):CD004631.
230. Froimson A. Tendon interposition arthroplasty of carpometacarpal joint of the thumb. *Hand Clin*. 1987;3:489–505.
231. Tomaino MM, Pellegrini VD Jr, Burton RI. Arthroplasty of the basal joint of the thumb. Long-term follow-up after ligament reconstruction with tendon interposition. *J Bone Joint Surg Am*. 1995;77:346–355.
232. Weilby A. Tendon interposition arthroplasty of the first carpometacarpal joint. *J Hand Surg [Br]*. 1988;13:421–425.
233. Vadstrup LS, Schou L, Boeckstyns ME. Basal joint osteoarthritis of the thumb treated with Weilby arthroplasty: a prospective study on the early postoperative course of 106 consecutive cases. *J Hand Surg Eur Vol*. 2009;34:503–505.
234. Sigfusson R, Lundborg G. Abductor pollicis longus tendon arthroplasty for treatment of arthrosis in the first carpometacarpal joint. *Scand J Plast Reconstr Surg Hand Surg*. 1991;25:73–77.
235. Kriegs-Au G, Petje G, Fojtl E, et al. Ligament reconstruction with or without tendon interposition to treat primary thumb

- carpometacarpal osteoarthritis. A prospective randomized study. *J Bone Joint Surg Am.* 2004;86:209–218.
236. Vermeulen GM, Spekreijse KR, Slijper H, et al. Comparison of arthroplasties with or without bone tunnel creation for thumb basal joint arthritis: a randomized controlled trial. *J Hand Surg Am.* 2014;39:1692–1698.
 237. Swanson A. Disabling arthritis at the base of the thumb: treatment by resection of the trapezium and flexible (silicone) implant arthroplasty. *J Bone Joint Surg Am.* 1972;54:456–471.
 238. Niebauer JJ, Shaw JL, Doren WW. Silicone-dacron hinge prosthesis. Design, evaluation, and application. *Ann Rheum Dis.* 1969;28:56–58.
 239. Haffajee D. Endoprosthetic replacement of the trapezium for arthrosis in the carpometacarpal joint of the thumb. *J Hand Surg Am.* 1977;2:141–148.
 240. Swanson AB, deGoot Swanson G, Watermeier JJ. Trapezium implant arthroplasty. Long-term evaluation of 150 cases. *J Hand Surg Am.* 1981;6:125–141.
 241. Peimer C. Long-term complications of trapeziometacarpal silicone arthroplasty. *Clin Orthop Relat Res.* 1987;220:86–98.
 242. Pellegrini VD Jr, Burton RL. Surgical management of basal joint arthritis of the thumb. Part I. Long-term results of silicone implant arthroplasty. *J Hand Surg Am.* 1986;11:309–324.
 243. Bezawada HP, Sauer ST, Hankins ST, et al. Long-term results of trapeziometacarpal silicone arthroplasty. *J Hand Surg Am.* 2002;27:409–417.
 244. Sollerman C, Herrlin K, Abrahamsson SO, et al. Silastic replacement of the trapezium for arthrosis – a twelve year follow-up study. *J Hand Surg [Br].* 1988;13:426–429.
 245. Luria S, Waitayawinyu T, Nemecek N, et al. Biomechanic analysis of trapeziectomy, ligament reconstruction with tendon interposition, and tie-in trapezium implant arthroplasty for thumb carpometacarpal arthritis: a cadaver study. *J Hand Surg Am.* 2007;32:697–706.
 246. Earp BE. Treatment of advanced CMC joint disease: trapeziectomy and implant arthroplasty (silastic-metal-synthetic allograft). *Hand Clin.* 2008;24:277–283, vi.
 247. de la Caffiniere JY, Aucontorier P. Trapezio-metacarpal arthroplasty by total prosthesis. *Hand.* 1979;11:41–46.
 248. Chakrabarti AJ, Robinson AH, Gallagher P. De la Caffiniere thumb carpometacarpal replacements. 93 cases at 6 to 16 years follow-up. *J Hand Surg [Br].* 1997;22:695–698.
 249. van Cappelle HG, Elzenga P, van Horn JR. Long-term results and loosening analysis of de la Caffiniere replacements of the trapeziometacarpal joint. *J Hand Surg Am.* 1999;24:476–482.
 250. Badia A, Sambandam SN. Total joint arthroplasty in the treatment of advanced stages of thumb carpometacarpal joint osteoarthritis. *J Hand Surg Am.* 2006;31:1605–1614.
 251. Ruffin RA, Rayan GM. Treatment of trapeziometacarpal arthritis with silastic and metallic implant arthroplasty. *Hand Clin.* 2001;17:245–253, ix.
 252. Cooney WP, Linscheid RL, Askew LJ. Total arthroplasty of the thumb trapeziometacarpal joint. *Clin Orthop Relat Res.* 1987;220:35–45.
 253. Athwal GS, Chenkin J, King GJ, et al. Early failures with a spheric interposition arthroplasty of the thumb basal joint. *J Hand Surg Am.* 2004;29:1080–1084.
 254. Martinez de Aragon JS, Moran SL, Rizzo M, et al. Early outcomes of pyrolytic carbon hemiarthroplasty for the treatment of trapezial-metacarpal arthritis. *J Hand Surg Am.* 2009;34:205–212.
 255. Stark HH, Moore JF, Ashworth CR, et al. Fusion of the first metacarpotrapezium joint for degenerative arthritis. *J Bone Joint Surg Am.* 1977;59:22–26.
 256. Carroll RE, Hill NA. Arthrodesis of the carpo-metacarpal joint of the thumb. *J Bone Joint Surg Br.* 1973;55:292–294.
 257. Cavallazzi RM, Spreafico G. Trapezio-metacarpal arthrodesis today: why? *J Hand Surg [Br].* 1986;11:250–254.
 258. Bamberger HB, Stern PJ, Kiefhaber TR, et al. Trapeziometacarpal joint arthrodesis: a functional evaluation. *J Hand Surg Am.* 1992;17:605–611.
 259. Kenniston JA, Bozentka DJ. Treatment of advanced carpometacarpal joint disease: arthrodesis. *Hand Clin.* 2008;24:285–294, vi–vii.
 260. Forseth MJ, Stern PJ. Complications of trapeziometacarpal arthrodesis using plate and screw fixation. *J Hand Surg Am.* 2003;28:342–345.
 261. Chamay A, Piaget-Morerod F. Arthrodesis of the trapeziometacarpal joint. *J Hand Surg [Br].* 1994;19:489–497.
 262. Carroll R. Arthrodesis of the carpometacarpal joint of the thumb. A review of patients with a long postoperative period. *Clin Orthop Relat Res.* 1987;220:106–110.
 263. Eaton RG, Littler JW. A study of the basal joint of the thumb. Treatment of its disabilities by fusion. *J Bone Joint Surg Am.* 1969;51:661–668.
 264. Alberts KA, Engkvist O. Arthrodesis of the first carpometacarpal joint. 33 cases of arthrosis. *Acta Orthop Scand.* 1989;60:258–260.
 265. Clough DA, Crouch CC, Bennett JB. Failure of trapeziometacarpal arthrodesis with use of the Herbert screw and limited immobilization. *J Hand Surg Am.* 1990;15:706–711.
 266. Rizzo M, Moran SL, Shin AY. Long-term outcomes of trapeziometacarpal arthrodesis in the management of trapeziometacarpal arthritis. *J Hand Surg Am.* 2009;34:20–26. The authors performed a 33-year retrospective study of trapeziometacarpal (TMC) arthrodeses performed at Mayo Clinic. Amongst 241 procedures reviewed, they included 126 thumbs with adequate pre- and postoperative clinical and radiographic data at an average 11-year follow-up. They report improvement of preoperative pain scores, oppositional and appositional pinch strength, and grip strength ($p < 0.01$). There was no significant change of any thumb motion arc. Nonunion rate was 13% and was unrelated to the use of bone grafting. Radiographic progression of STT arthritis was seen in 39 thumbs, only eight of which were symptomatic. This study presents detailed long-term outcomes of TMC arthrodesis, providing level IV evidence for the management of TMC arthritis.
 267. Hartigan BJ, Stern PJ, Kiefhaber TR. Thumb carpometacarpal osteoarthritis: arthrodesis compared with ligament reconstruction and tendon interposition. *J Bone Joint Surg Am.* 2001;83:1470–1478.
 268. Fulton DB, Stern PJ. Trapeziometacarpal arthrodesis in primary osteoarthritis: a minimum two-year follow-up study. *J Hand Surg Am.* 2001;26:109–114.
 269. Herbert TJ, Lanzetta M. Idiopathic avascular necrosis of the scaphoid. *J Hand Surg [Br].* 1994;19:174–182.
 270. Lichtman DM, Mack GR, MacDonald RJ, et al. Kienbock's disease: the role of silicone replacement arthroplasty. *J Bone Joint Surg Am.* 1977;59:899–908.
 271. North ER, Eaton RG. Degenerative joint disease of the trapezium: a comparative radiographic and anatomic study. *J Hand Surg Am.* 1983;8:160–166.
 272. Bhatia A, Pisoh T, Touam C, et al. Incidence and distribution of scaphotrapezotrapezoidal arthritis in 73 fresh cadaveric wrists. *Ann Chir Main Memb Super.* 1996;15:220–225.
 273. Watson HK, Ballet FL. The SLAC wrist: scapholunate advanced collapse pattern of degenerative arthritis. *J Hand Surg Am.* 1984;9:358–365.
 274. Watson HK, Ryu J. Evolution of arthritis of the wrist. *Clin Orthop Relat Res.* 1986;57–67.
 275. Garcia-Elias M, Geissler W. *Carpal Instability*. 5th ed. Philadelphia, PA: Elsevier/Churchill Livingstone; 2005.
 276. Weiss KE, Rodner CM. Osteoarthritis of the wrist. *J Hand Surg Am.* 2007;32:725–746.
 277. Imbriglia J. *Proximal Row Carpectomy*. Philadelphia, PA: Lippincott; 2004:1331–1337.
 278. Watson HK, Ryu J, Akelman E. Limited triscaphoid intercarpal arthrodesis for rotatory subluxation of the scaphoid. *J Bone Joint Surg Am.* 1986;68:345–349.
 279. Enna M, Hoepfner P, Weiss AP. Scaphoid excision with four-corner fusion. *Hand Clin.* 2005;21:531–538.
 280. Lane LB, Daher RJ, Leo AJ. Scapholunate dissociation with radiolunate arthritis without radioscapoid arthritis. *J Hand Surg Am.* 2010;35:1075–1081.

281. Fernandez DL. Reconstructive procedures for malunion and traumatic arthritis. *Orthop Clin North Am.* 1993;24:341–363.
282. Fernandez DL. Malunion of the distal radius: current approach to management. *Instr Course Lect.* 1993;42:99–113.
283. Linscheid RL, Dobyns JH, Beabout JW, et al. Traumatic instability of the wrist. Diagnosis, classification, and pathomechanics. *J Bone Joint Surg Am.* 1972;54:1612–1632. This is a seminal article from 1972 that presents the foundation for study of carpal instability. The authors describe wrist instability that develops as a result of scapholunate and other carpal ligament injuries in addition to instability from fracture dislocations, scaphoid fractures, and fractures of the distal radius and ulna. They provide the earliest comprehensive dialogue of the diagnosis of carpal instability. The article includes clinical and radiographic data, a detailed discussion of the biomechanics of carpal instability, and proposal of the now accepted classification of dorsal and palmar intercalated segment instability. The radiographic parameters and nomenclature presented in this article remain in use today. The article has been recognized as a “classic orthopedic reference” and a summary was republished in the *Journal of Bone and Joint Surgery* in 2002.
284. Knirk JL, Jupiter JB. Intra-articular fractures of the distal end of the radius in young adults. *J Bone Joint Surg Am.* 1986;68:647–659.
285. Mack GR, Bosse MJ, Gelberman RH, et al. The natural history of scaphoid non-union. *J Bone Joint Surg Am.* 1984;66:504–509.
286. Fisk GR. Carpal instability and the fractured scaphoid. *Ann R Coll Surg Engl.* 1970;46:63–76.
287. Ruby LK, Stinson J, Belsky MR. The natural history of scaphoid non-union. A review of fifty-five cases. *J Bone Joint Surg Am.* 1985;67:428–432.
288. Cooney W. *Nonunions of the Carpus.* Philadelphia, PA: Lippincott Williams & Wilkins; 2004.
289. Bell SJ, Hofmeister EP, Moran SL, et al. The diagnostic utility of midcarpal anesthetic injection in the evaluation of chronic wrist pain. *Hand (N Y).* 2007;2:39–45, discussion 46–37.
290. Douglas DP, Peimer CA, Koniuch MP. Motion of the wrist after simulated limited intercarpal arthrodeses. An experimental study. *J Bone Joint Surg Am.* 1987;69:1413–1418.
291. Palmer AK, Werner FW, Murphy D, et al. Functional wrist motion: a biomechanical study. *J Hand Surg Am.* 1985;10:39–46.
292. Berger RA, Bishop AT, Bettinger PC. New dorsal capsulotomy for the surgical exposure of the wrist. *Ann Plast Surg.* 1995;35:54–59.
293. Berger RA, Bishop AT. A fiber-splitting capsulotomy technique for dorsal exposure of the wrist. *Tech Hand Up Extrem Surg.* 1997;1:2–10.
294. Nakamura R, Imaeda T, Tsuge S, et al. Scaphoid non-union with D.I.S.I. deformity. A survey of clinical cases with special reference to ligamentous injury. *J Hand Surg [Br].* 1991;16:156–161.
295. Nakamura T, Cooney WP 3rd, Lui WH, et al. Radial styloidectomy: a biomechanical study on stability of the wrist joint. *J Hand Surg Am.* 2001;26:85–93.
296. Siegel DB, Gelberman RH. Radial styloidectomy: an anatomical study with special reference to radiocarpal intracapsular ligamentous morphology. *J Hand Surg Am.* 1991;16:40–44.
297. Ekerot L, Holmberg J, Eiken O. Denervation of the wrist. *Scand J Plast Reconstr Surg.* 1983;17:155–157.
298. Ishida O, Tsai TM, Atasoy E. Long-term results of denervation of the wrist joint for chronic wrist pain. *J Hand Surg [Br].* 1993;18:76–80.
299. Wilhelm A. [Articular denervation and its anatomical foundation. A new therapeutic principle in hand surgery. On the treatment of the later stages of lunatomalacia and navicular pseudarthrosis]. *Hefte Unfallheilkd.* 1966;86:1–109.
300. Berger RA. Partial denervation of the wrist: a new approach. *Tech Hand Up Extrem Surg.* 1998;2:25–35.
301. Weinstein LP, Berger RA. Analgesic benefit, functional outcome, and patient satisfaction after partial wrist denervation. *J Hand Surg Am.* 2002;27:833–839.
302. Krakauer JD, Bishop AT, Cooney WP. Surgical treatment of scapholunate advanced collapse. *J Hand Surg Am.* 1994;19:751–759.
303. Jebson PJ, Hayes EP, Engber WD. Proximal row carpectomy: a minimum 10-year follow-up study. *J Hand Surg Am.* 2003;28:561–569.
304. DiDonna ML, Kiefhaber TR, Stern PJ. Proximal row carpectomy: study with a minimum of ten years of follow-up. *J Bone Joint Surg Am.* 2004;86:2359–2365. The authors retrospectively evaluate the long-term results of 22 proximal row carpectomy procedures performed for the treatment of scapholunate advanced collapse, scaphoid nonunion with advanced collapse or Kienbock’s disease. Outcomes were assessed by means of follow-up radiographs, objective measurement of motion and grip strength, and the DASH questionnaire. Their surgical technique is reviewed and results at a minimum 10-year follow-up (average 14 years) are presented. There were four failures (18%) at an average of 7 years, all of which occurred in patients younger than 35 years. The authors report a wrist motion arc of 72° and grip strength of 91% of that of the contralateral side in the 18 (82%) successes. They conclude that proximal row carpectomy is a viable motion-preserving procedure for advanced carpal arthritis that provides satisfactory long-term results in most patients, and advise against it in patients younger than 35 years.
305. Ashmead D, Watson HK, Damon C, et al. Scapholunate advanced collapse wrist salvage. *J Hand Surg Am.* 1994;19:741–750. The authors present a substantial series of 100 scaphoid excisions and four-corner fusions with an average 4-year follow-up. Long-term subjective, clinical, and radiographic data is presented. At the time of follow-up, 91% of cases had significant improvement in pain levels, and no patient described their pain as worse. Flexion/extension averaged 72° and grip strength was 80% that of the contralateral side. Nonunion occurred in only three cases and only two instances of radiolunate destruction were noted, both in conjunction with ulnar translation of the carpus. Outcomes with and without the use of silicone scaphoid spacers were found to be similar.
306. Tomaino MM, Miller RJ, Cole I, et al. Scapholunate advanced collapse wrist: proximal row carpectomy or limited wrist arthrodesis with scaphoid excision? *J Hand Surg Am.* 1994;19:134–142.
307. Wyrick JD, Stern PJ, Kiefhaber TR. Motion-preserving procedures in the treatment of scapholunate advanced collapse wrist: proximal row carpectomy versus four-corner arthrodesis. *J Hand Surg Am.* 1995;20:965–970. This is a retrospective cohort study comparing proximal row carpectomy (PRC) with four-corner fusion for scapholunate advanced collapse. Two cohorts of 19 patients each (from separate institutions performing exclusively either PRC or four-corner arthrodesis) were compared. The cohorts were well matched and the authors found significant improvement in function and pain with both procedures. Postoperative motion and functional outcomes were similar in both procedures. The authors discuss the surgical techniques, outcomes, and controversies related to the two procedures.
308. Cohen MS, Kozin SH. Degenerative arthritis of the wrist: proximal row carpectomy versus scaphoid excision and four-corner arthrodesis. *J Hand Surg Am.* 2001;26:94–104.
309. Neubrech F, Muhldorfer-Fodor M, Pillukat T, et al. Long-term results after midcarpal arthrodesis. *J Wrist Surg.* 2012;1:123–128.
310. Vance MC, Hernandez JD, DiDonna ML, et al. Complications and outcome of four-corner arthrodesis: circular plate fixation versus traditional techniques. *J Hand Surg Am.* 2005;30:1122–1127.
311. Viegas SF, Patterson RM, Peterson PD, et al. Ulnar-sided perilunate instability: an anatomic and biomechanical study. *J Hand Surg Am.* 1990;15:268–278.
312. Kirschenbaum D, Schneider LH, Kirkpatrick WH, et al. Scaphoid excision and capitulate arthrodesis for radioscapoid arthritis. *J Hand Surg Am.* 1993;18:780–785.
313. Kadji O, Duteille F, Dautel G, et al. [Four bone versus capitulate limited carpal fusion. Report of 40 cases]. *Chir Main.* 2002;21:5–12.
314. Calandruccio JH, Gelberman RH, Duncan SF, et al. Capitulate arthrodesis with scaphoid and triquetrum excision. *J Hand Surg Am.* 2000;25:824–832.
315. Adams BD. Complications of wrist arthroplasty. *Hand Clin.* 2010;26:213–220.
316. Murphy DM, Khoury JG, Imbriglia JE, et al. Comparison of arthroplasty and arthrodesis for the rheumatoid wrist. *J Hand Surg Am.* 2003;28:570–576.

317. Bhardwaj N, Devi D, Mandal BB. Tissue-engineered cartilage: the crossroads of biomaterials, cells and stimulating factors. *Macromol Biosci.* 2015;15:153–182.
318. Bartlett W, Skinner JA, Gooding CR, et al. Autologous chondrocyte implantation versus matrix-induced autologous chondrocyte implantation for osteochondral defects of the knee: a prospective, randomised study. *J Bone Joint Surg Br.* 2005;87:640–645.
319. Fulco I, Miot S, Haug MD, et al. Engineered autologous cartilage tissue for nasal reconstruction after tumour resection: an observational first-in-human trial. *Lancet.* 2014;384:337–346.
320. Ossendorf C, Kaps C, Kreuz PC, et al. Treatment of posttraumatic and focal osteoarthritic cartilage defects of the knee with autologous polymer-based three-dimensional chondrocyte grafts: 2-year clinical results. *Arthritis Res Ther.* 2007;9:R41.
321. Murphy SV, Atala A. 3D bioprinting of tissues and organs. *Nat Biotechnol.* 2014;32:773–785.

21

The stiff hand and the spastic hand

David T. Netscher, Kenneth W. Donohue, and Dang T. Pham

▶ Access video and video lecture content for this chapter online at expertconsult.com

SYNOPSIS

- Flexion and extension contractures may result from contractures of structures volar or dorsal to the joint, capsular/pericapsular structures, and bony deformity.
- Non-operative treatment is more effective in the early phase following injury and includes splinting, extremity elevation, compression gloves, moist heat, and ultrasound.
- Surgery is indicated for residual flexion contractures refractory to non-operative measures.
- Checkrein ligament release is key in proximal interphalangeal (PIP) joint flexion contracture surgery.
- Postoperative splint application maintains surgical correction.
- Salvage procedures for PIP joint flexion include disarticulation at the PIP joint or bone shortening with PIP joint fusion.
- In the spastic hand, non-surgical treatment for cerebral palsy includes splinting, occupational therapy, intramuscular botulinum toxin A, and intrathecal baclofen.
- Surgical treatment of spasticity is also indicated in specific situations.

Introduction

Hand stiffness arises as a result of flexion and extension contractures of the small joints of the hand. Limitation of extension or flexion may be both active and passive or active alone. The appropriate treatment should be decided following clinical evaluation of what tissue needs to be addressed. This chapter will first outline the general principles of evaluation and treatment of contractures, followed by specific treatment of spasticity.

The stiff hand

Diagnosis/patient presentation

Flexion contracture (Fig. 21.1)

Hints and tips

Clinical assessment

- Active versus passive range
- Joint lag versus joint contracture
- Anatomic structure – skin, fascia, pericapsular, bone
- “Seesaw” effect across two joints
- Intrinsic and extrinsic contractures

This may result from tightness in one or more of the structures on the palmar aspect of the joint^{1,2}:

- Skin: Contracture from scarring results from lacerations or palmar burns.
- Palmar fascia: Dupuytren contracture is the classic example.
- Flexor tendon sheath: Shortening and contracture may occur.
- Flexor tendon: This is due to tendon shortening or tendon adhesions. Temporary joint fixation in a particular position with locking and release by painful manipulation may result from a trigger finger within the tendon sheath but also may occur within the joint, especially at the metacarpophalangeal (MP) joint (intracapsular tumors, loose bodies, osteophytes, articular surface distortions).




Fig. 21.1 Flexion contracture may result from tightness of structures volar to the joint, including skin, flexor tendon sheath, tendons, volar palmar plate, and accessory collateral ligaments. In addition, a bone block may impede joint motion, whereas dorsal tendon adhesions may limit the ability to extend the joint.

Capsular and pericapsular structures

Collateral ligament

The collateral ligament at the PIP joint is taut in all positions of the joint and collateral ligaments are taut in flexion only at the MP joints.³ Thus, collateral ligament shortening never produces a flexion contracture at either joint. However, collateral ligament adherence to the lateral aspect of the proximal phalanx when the finger is flexed, does play a role in PIP joint flexion contracture.

Volar plate

When other structures are the primary cause of the flexion contracture, the volar plate becomes contracted at an early stage, especially at the interphalangeal joints.

Accessory collateral ligaments, transverse retinacular ligaments, and intrinsic tendons

Contracture of accessory ligaments, adherence of fibers of the transverse retinacular ligament to the collateral ligaments, and adhesions of intrinsic tendons in the lumbrical canals may cause flexion of MP joints.

Dorsal adhesions

Generally with flexion contracture, tightness of structures on the flexor aspect of the joint exists. However, joint extension may sometimes be prevented by incongruity of articular surfaces or adhesion of dorsal capsule or of an extensor tendon to the articular surface of the head of the proximal bone. In such a case, there is not only a flexion contracture but also limitation of flexion.

Bone

Bone block or exostosis can also cause flexion contracture.

Extension contracture

Limitation of flexion (extension contracture) (Fig. 21.2) can be caused by one or more structures on the dorsal aspect of the joint.^{1,2} However, they too can result from a “jamming” effect of volar structures that block flexion, such as a bone block or palmar plate adhesions.

Skin

This usually results from scar contracture.

Long extensors

Tendon shortening or adhesions limit joint flexion. With extensor tendon adhesions, active extension of the joint is limited or absent, and active extension falls short of passive extension.

Intrinsic muscles

Intrinsic contracture may follow ischemia, or muscle fibrosis may occur for non-ischemic reasons (rheumatoid arthritis, cerebral palsy). The “intrinsic plus” position of the hand is one in which the fingers are flexed at the MP joints and extended at the interphalangeal joints.³ A “saddle deformity”⁴ results from adhesions between lumbrical and interosseous muscles. With active intrinsic contraction, painful impingement on the deep transverse metacarpal ligament occurs with limitation of flexion (the transverse metacarpal ligament is the “saddle” and the two muscles are the “legs of the rider”).

Capsular and pericapsular structures

Dorsal capsule

The dorsal capsule may become scarred and contribute to extension contracture.

Collateral ligaments

Adhesions to the head of the proximal bone may limit flexion. In contrast to flexion contracture, which is more common in interphalangeal joints (especially proximal), stiffness in extension from collateral ligament shortening is more likely at MP joints. Collateral ligaments at the MP joints are relaxed in extension and taut in flexion.⁵ Loss of MP joint flexion can come about simply from immobilization in the incorrect, extended position. Collateral ligaments are at their tightest (the cam arc effect of the metacarpal head) at a range between 70° and 90° flexion.

Volar plate

Flexion is prevented by volar plate adhesions to the palmar surface of the proximal bony head. Palmar plate adhesions and collateral ligament tightness may both be causes of MP joint extension contracture.¹ They may be distinguished from each other. If the collateral ligaments are contracted, finger abduction-adduction in extension (normally about 45°) is greatly reduced. When palmar plate is the sole cause, attempted passive flexion produces an opening of the dorsal aspect of the joint. The volar lip at the base of the proximal phalanx jams against the adherent volar plate, and the




Fig. 21.2 (A) Extension contracture may result from tightness of dorsal structures, including skin, extensor tendons, collateral ligaments and joint capsule, as well as from a bone block. Volar structures may also impede the ability to flex the joint. **(B)** In addition, adhesions in the lumbrical canal and of the transverse retinacular ligament fibers may impede both flexion and joint extension.

unaffected (loose) collateral ligaments allow the flexion force to rock the dorsal lip away from the metacarpal head, felt as a subtle dorsal recess between head and base. This sign should always be sought intraoperatively as a residual impediment to passive flexion after tight collateral ligaments have been released.

Painful resistance to passive PIP joint flexion may indicate volar plate injury (volar plate test).⁶ Pain results from synovial involvement, and the most common cause is volar plate avulsion with or without a small bone fragment torn from the base of the middle phalanx. Positive volar plate test at 6–9 months following injury indicates that volar plate repair of the middle phalanx may be necessary.

Transverse retinacular ligaments

Transverse retinacular ligaments may be adherent to the lateral capsular ligament at the PIP joint.

Flexor tendon adherence

Flexor tendon adherence within the sheath may be sufficiently bulky to block full flexion of the interphalangeal joint.

Bone

This may be a true block or result from intraarticular incongruity. Chondral fractures may not be radiographically apparent and so may present a diagnostic problem (Fig. 21.3). Persistent waxing and waning joint swelling with limited flexion may result from a chondral fracture, which is more likely at the MP joint. Questioning the patient may lead to recollection of an injury that could have caused the proximal phalangeal base to impinge on the metacarpal head. Surgical exploration may reveal the chondral fracture and consequent

loose body in the joint. Computed tomography scanning may help in arriving at the correct diagnosis.

Seesaw effect

This results when a contractural element spans two joints. Presence of this sign helps in the diagnosis of structures that potentially contribute to a stiff joint.⁷ If one joint in a contracted system is flexed, the other joint can then be extended, and vice versa. This is seen, for example, when a longitudinal volar skin scar crosses both proximal and distal interphalangeal joints. The distal interphalangeal (DIP) joint can be extended only if the PIP joint is flexed. A similar effect is seen with adherent extrinsic flexor or extensor tendons (Fig. 21.4). For example, flexion of MP joints in the presence of a flexor tendon adhesion over the proximal phalanx has no effect on the flexion contracture of the PIP joint. If the adhesion lies proximal to the MP joint, flexion of that joint results in correction of the contracture apparently present in the PIP joint. Furthermore, with flexor tendon adhesions, passive flexion of the affected joint exceeds active flexion, provided the extensor tendon is healthy. Similarly, in the presence of a Volkmann contracture of the flexors in the forearm, passive extension of the finger joints is reduced with the wrist extended and not if the wrist is flexed.

If the extrinsic extensor tendon is adherent to the metacarpal, the limitation of extensor tendon excursion distal to that joint prevents simultaneous flexion of MP and PIP joints. This is the test for extrinsic tightness (Fig. 21.5A).^{8,9} The test of Bunnell for intrinsic tightness results from the seesaw phenomenon in which the band acts across two joints but is an extensor of one joint and a flexor of the adjacent joint.¹⁰ If the intrinsic musculotendinous system is foreshortened,



Fig. 21.3 (A) This patient had an osteochondral fracture involving the metacarpal head after a finger “jam” and presented with inability to flex at the metacarpophalangeal joint and joint swelling. The fracture involved about one-third of the articular surface but was still attached by a single collateral ligament. (B) Bone fixation restored perfect joint function.

extension of the MP joint, either actively or passively, increases the tone in the system and restrains flexion of the PIP joint. This is tested by passively extending the MP joint and passively flexing the PIP joint (Fig. 21.5B). If flexion of the PIP joint is greater when the MP joint is flexed than when it is extended, intrinsic tightness is present. In the swan-neck deformity, not only is there an extension contracture of the PIP joint, but that joint hyperextends because of volar plate

laxity. There is dorsal displacement of the lateral bands at the PIP joint. This slackens the distal tension on the extensor mechanism because of the fixed attachment of the central tendon at the PIP joint. Thus there is unopposed force of the flexor digitorum profundus at the distal joint, which then drops into flexion (Fig. 21.6A).⁹

A similar volar to dorsal seesaw effect occurs at the DIP joint secondary to action of the oblique retinacular ligament




Fig. 21.4 By adjusting the joints proximal to the joint that appears to be the cause of the contracture, the primary problem may be revealed. (A) If a patient has a proximal interphalangeal (PIP) flexion contracture, flexion of the metacarpophalangeal (MP) joint in the presence of flexor tendon adhesion at the proximal phalanx has no effect on the PIP flexion contracture. (B) If the flexor tendon adhesion is proximal to the MP joint, flexion of that joint will result in correction of the PIP joint contracture.




Fig. 21.5 (A) Test for extrinsic tightness. When the metacarpophalangeal (MP) joint is flexed (arrow), passive proximal interphalangeal (PIP) joint flexion is increasingly difficult. (B) Test for intrinsic tightness. When the MP joint is extended (arrow), passive PIP joint flexion is more difficult. (C) Boutonnière test. The oblique retinacular ligament is foreshortened so that when the PIP joint is extended (arrow), passive DIP joint flexion is difficult. (D) Central slip tendon excision is performed for extrinsic extensor tightness and wing tendon excision (oblique fibers and lateral bands) for intrinsic tightness – either of which might cause PIP hyperextension.




Fig. 21.6 (A) Swan-neck deformity with hyperextension at the proximal interphalangeal (PIP) joint. Dorsal displacement of the lateral bands slackens distal extensor tension, and so the unopposed flexor digitorum profundus draws the distal interphalangeal (DIP) joint into flexion. (B) Boutonnière deformity. The PIP joint drops into flexion because of central slip attenuation, and the lateral bands move volar. Excess extensor pull bypasses the PIP joint and hyperextends the DIP joint. The oblique retinacular ligament foreshortens.

and lateral bands, resulting in extension contracture at that joint. This occurs with the boutonnière deformity. When the central tendon insertion into the dorsal base of the middle phalanx ruptures or attenuates, the PIP joint drops into flexion and the lateral bands move volar to the axis of motion of that joint.¹¹ They will foreshorten and adhere in that position. Excess extensor pull that secondarily bypasses the PIP joint is imposed dorsally at the DIP joint with consequent recurvature at that joint (Fig. 21.6B). The oblique retinacular ligament is an extensor of the DIP joint and a flexor of the PIP joint.¹¹ It also foreshortens and this permits the DIP joint to be flexed as long as the PIP joint is maintained in flexion. Passively extending the PIP joint brings the DIP joint into extension, making passive flexion increasingly more difficult. This maneuver is the boutonnière test (Fig. 21.5C).

Volar plate and collateral ligament changes

Changes in the volar plate and collateral ligaments occur with flexion contractures. Flexion and extension contractures can occur at the PIP joint. In contrast, at the MP joints, extension contractures occur, but flexion contracture is rare due to volar plate and collateral ligament anatomy. The volar plate at MP joints is different anatomically from that of interphalangeal joints.

The protected position of MP joints is in flexion. The cam and volar flare shape of the metacarpal head places collateral ligaments in greatest tension during flexion (Fig. 21.7). The MP joint volar plate has crisscrossing bands of fibers that expand with joint extension and are collapsible with flexion.⁶ Thus, the volar plate at the MP joint is considerably longer in extension than in flexion (Fig. 21.8A).

In contrast, the interphalangeal joint collateral ligaments do not change in tightness with joint flexion and extension. The volar plate is relatively uncollapsible. Rather, the volar plate slides proximally and distally with flexion and extension

of the joint (Fig. 21.8B). The volar plate is not attached to the proximal phalanx as this would prevent full extension. The assembly lines are the two ridges on the volar lateral surfaces of the phalanx to which are attached the flexor sheath, Cleland ligaments, Grayson ligaments, oblique retinacular ligaments, and transverse retinacular ligaments, and the transverse metacarpal ligament and MP joint volar plate more proximally. Normally, there is no ligament structure between the volar plate of the PIP joint and the assembly line or extension of that joint would not be possible. Two bands (checkreins)^{6,12,13} form between the lateral proximal volar plate and the assembly lines after injury. These are pathologic structures (Fig. 21.9). They are thicker at the base attached to the volar plate and have a thinner, longer proximal apex attached to the assembly line. The communicating artery of the vincula system passes deep to the checkreins. With interphalangeal joint contracture, it is the checkreins that mainly prevent extension. Division of these checkreins and accessory collateral ligaments enables extension at the interphalangeal joint to be achieved when surgery is required. It is virtually never necessary to divide collateral ligaments.

Clinical tips

Post-traumatic contractures

- Dorsal hand edema
- Negative hand position driven by hydraulic MP joint fluid accumulation
- Reciprocal tone in tendons
 - Wrist flexed, finger MP extended
 - Finger MP extended, PIP flexed
- Fixed extension at MP and fixed flexion at PIP with time
- MP collaterals and PIP volar plate tight




Fig. 21.7 Cam-like action of the collateral ligaments at the metacarpophalangeal (MP) joint. Collateral ligaments are in greatest tension during flexion because of the cam and volar flare shape of the metacarpal head.




Fig. 21.8 (A) Crisscrossing bands of fibers make up the metacarpophalangeal (MP) joint volar plate, and these allow expansion with joint extension. **(B)** The volar plate at the proximal interphalangeal (PIP) joint is relatively uncollapsible. In contrast to the MP joint, the PIP volar plate slides proximally and distally with joint flexion and extension.

Basic science/disease process

Injury, infection, excessive immobilization, and inappropriate splinting of the hand all predispose to joint stiffness. The initial response to any insult of the hand is edema formation. Unless edema accumulation is prevented, joints assume the posture in which their ligaments are most relaxed.^{1,14,15} Ligament contracture and fibrosis then cause joints to become immobile in this abnormal position (Fig. 21.10), which is:

- Wrist: flexion
- Thumb: adduction
- MP joint: extension
- PIP joint: flexion.

This is the negative or injured hand position; wrist position and MP joint posture are the keys to its development. When the wrist is allowed to flex, increased tone in the extrinsic extensor tendons causes MP joints to extend. When nearly fully extended, the MP joint has maximum capsule and collateral ligament laxity as well as intracapsular fluid capacity. When the MP joint is fully flexed, intracapsular fluid capacity

is minimal and the ligaments are taut. After injury, edema fluid drives the MP joints hydraulically into extension. In this position, tension is increased in the flexors and decreased in the extensors. Thus, fingers flex at PIP and DIP joints. There is no hydraulic drive at PIP or DIP joints because there is only minimal change in collateral ligament tightness and fluid capacity of flexed versus extended interphalangeal joints. Positional changes in interphalangeal joints are thus secondary to changes in MP joints. Slight wrist flexion occurs in the neglected edematous hand because total power of flexors exceeds the extensors.¹⁶ Post-burn claw contractures from dorsal hand burns similarly drive the MP joints into fixed extension and the PIP joints into flexion. Thus, the traumatized hand, susceptible to joint stiffness, must be appropriately immobilized by placing it in the intrinsic plus position with MP joints in flexion and interphalangeal joints in extension.

Patient selection

These measures may be more effective early on after the injury during the edema phase and subsequent collagen phase of




Fig. 21.9 (A) Checkreins are attached by a broad base to the volar plate, and a tapering apex is attached to the assembly line. (B) Release of the proximal interphalangeal (PIP) flexion contracture requires excision of the checkreins, with care taken not to injure the transverse communicating vessel between the two digital arteries.

wound healing, when fluid can be displaced and collagen remodeled. Once a scar and fibrosis have reached maturity, it is less likely to respond to non-operative measures. These measures include splinting. Other hand therapy endeavors such as edema reduction (by extremity elevation and compression gloves), moist heat, and ultrasound may enhance the beneficial response achieved by splinting.¹⁷ Splinting involves the application of a non-elastic force in the direction of the desired correction. Initial splinting displaces tissue fluid during 5–12 min. This is the rapid gain phase of splinting. Only once this tissue edema has been displaced can the external forces of the splint result in collagen remodeling. Rapid deformity recurrence after a period of splinting should not discourage the patient because this is due to redistribution of tissue fluid originally displaced by exercise. Only if prolonged, will splinting eventually have the desired effect on collagen.¹⁸ As weeks pass, patients notice that less time and force are necessary to achieve the desired result and that the finger returns to its contracted position more slowly and less

severely after splint removal. Finally, active muscle contraction may be able to achieve complete joint range of motion, and the patient may then experience only morning stiffness that finally progressively resolves.

For PIP joint flexion contractures, the patient may wear a nighttime progressive static splint (Fig. 21.11). With a Joint Jack (Joint Jack Company, Glastonbury, CT), the patient tightens the screw every 2 or 3 min as tolerated, starting 1 h before bedtime. The screw can then be loosened half a turn at bedtime for comfort. A Joint-Jack may be difficult to keep in position on the little finger because its proximal base tends to rock off the ulnar border of the palm. In that case, a custom palm-based thermoplastic splint with Velcro straps that can be tightened over the PIP joint may be appropriate. High compression foam built into the brace supports the distal phalanx. For PIP joint flexion contractures of more than 60°, these splints may be inappropriate because they will place undue extension stress on the DIP joint. These splints must be fitted with care to avoid hyperextension stress at the DIP joint. The volar distal pressure should be on the volar plate of the DIP joint and not at the fingertip. Splints such as Wire-Foam finger extension splints (DeRoyal LMB Hand Rehab Products, San Luis Obispo, CA) are less bulky and may be more acceptable for daytime use by the active patient. Serial finger casting, with a new cast replaced every 3 days, may be helpful in a difficult, seemingly unresponsive case or when PIP joint flexion is >60°.

PIP joint extension contractures rarely occur as pure joint contractures. They nearly always involve structures other than joint capsule, such as extensor mechanism adhesions. A joint strap may be placed around the middle phalanx and the finger positioned in maximum passive flexion (Fig. 21.12). With time, the strap is tightened to increase flexion. Snug Coban wrapping about the palm and finger can accomplish the same objective.

A variety of flexion splints are available that place a static flexion force across MP joints when there are extension contractures at those joints. One such chronic progressive flexion splint is the Knuckle-Jack splint (Joint-Jack Company, East Hartford, CT).⁷

Treatment/surgical technique

PIP joint flexion contracture of more than 70° is unlikely to respond effectively to non-operative therapy alone. Furthermore, once a plateau in improvement has been reached with non-operative measures and there is still a functionally impairing residual deformity, surgery is indicated. Radiographic changes within a joint or an obstructing bone block may also persuade one to undertake surgery. Once swelling has resolved, and if the joint range of motion reaches an abrupt stop rather than having a gradual increase in resistance to passive motion, clinical judgment would make one believe that maximum benefit has been reached from splinting.

PIP joint flexion contracture

It is important to first evaluate whether there is shortage of skin. Prolonged joint contracture, even without soft-tissue scar, may result in longitudinal shortening of soft tissues. One may decide to make a mid-volar longitudinal incision that is broken up into multiple Z-plasties as the access incision. For




Fig. 21.10 (A) Posture of the relaxed uninjured hand. (B) Edema accumulates in the available space on the dorsum of the injured hand, drawing the wrist into flexion, the metacarpophalangeal joints into hyperextension, the proximal interphalangeal joints into flexion, and the thumb into adduction.

severe accompanying soft-tissue contracture, a transposition flap from the dorsolateral surface of the homolateral digit (Joshi flap)¹⁹ (Fig. 21.13) or cross-finger flap from an adjacent finger, or homodigital island flap may be planned.²⁰ If there is no soft-tissue deficit, any conventional volar zigzag type surgical approach may be used.²¹

Shortened checkrein ligaments are the primary abnormality.^{12,13} If a flexor tendon injury was the initiating event, a flexor tenolysis or secondary repair may be required. The flexor sheath just distal to the A2 pulley and the checkreins are cut free from their attachments to the proximal edge of the volar plate (see Fig. 21.9). Gentle passive extension may be required to break up other adhesions after checkrein resection to achieve full joint extension.

A “jumping” sensation is occasionally noted as the PIP joint is fully extended once checkrein release has been done. This is secondary to a cam effect of the collateral ligament and is relieved by cutting only the most dorsal fibers of both collateral ligaments.⁶

Tightness of the oblique retinacular ligaments may also contribute to the PIP joint flexion contracture, especially in association with DIP joint hyperextension in the boutonnière deformity. Transection of the oblique retinacular ligament is then indicated.

PIP joint extension contracture

A mid-dorsal longitudinal curvilinear surgical incision affords the luxury of not needing to close the entire incision proximally or distally, provided an adequate soft-tissue flap covers the extensor mechanism. In this way, soft-tissue closure will not limit the flexion achieved as a result of the joint release. A

dorsolateral skin incision may also adequately expose the extensor hood.

The transverse retinacular ligament fibers are divided and the lateral band is elevated while the central slip insertion is preserved.^{2,6} The dorsal joint capsule is incised and the joint passively flexed. Extensor tendon adhesions to the dorsum of the proximal phalanx are released. If the jump phenomenon occurs after dorsal capsulotomy, the most dorsal fibers of both collateral ligaments are cut until there is no residual jumping. In the presence of severe intra-articular fibrosis, both collateral ligaments may need to be divided and a small dissector used to free volar plate adhesions (without detaching the volar plate from its distal insertion).

Partial resection of the appropriate portion of the extensor mechanism in carefully selected cases is helpful in those patients who have intrinsic tightness or extrinsic extensor tendon tightness (see Fig. 21.5). In patients with extrinsic extensor tightness, the central tendon portion is resected. In those with intrinsic tightness, only the lateral bands and oblique fibers of the extensor hood are resected.²² Sagittal band fibers are left intact because they are the prime method through which extension is transmitted to the MP joint from the extensor mechanism.

Once the finger has been stiff in extension, the flexor tendons frequently become adherent in their bed. The operator should return and check function of these tendons by making a counterincision in the palm or forearm.^{2,6} By placement of traction on the flexors, the fingers should fully flex. Failure for this to occur necessitates performance of a flexor tenolysis as well. An excellent method of anesthesia administration when performing a tenolysis, is to use the tumescent technique of local anesthesia infiltration using a mixture of

lidocaine with epinephrine added. This enables the so-called “wide-awake” method of local anesthetic infiltration, avoiding the paralytic effects of prolonged tourniquet ischemia or of a regional block, and ensuring full cooperation of the patient. The end-point of the tenolysis or joint release is achieved only when the patient can actively reproduce normal function on the operating table.²³

MP joint extension contracture

A longitudinal dorsal skin incision is used. Sagittal band hood fibers are retracted distally and the dorsal capsule is transected.^{2,6,24} As the joint is flexed passively, one may note that the tight collateral ligament cannot pass over the condyles on the volar aspect of the metacarpal head. In such circumstances, it is necessary to transect the collateral ligaments proximally at their attachments to the metacarpal head. It may be necessary, as with extension contractures of the PIP joint, to free volar plate adhesions by inserting a blunt dissector into the volar plate pocket dorsal to that structure. If the jump phenomenon is encountered, it is managed in a fashion similar to that of the PIP joints.




Fig. 21.11 (A) Custom palm-based night proximal interphalangeal (PIP) extension splint. (B) Joint Jack splint. (C) Wire-Foam PIP extension splint.





Fig. 21.12 A flexion strap can be progressively tightened around the hand and finger for treatment of a proximal interphalangeal joint extension contracture.

Postoperative care

Extremity elevation reduces postoperative edema. A postoperative splint applied during the first week maintains the restored joint position. Thereafter, active mobilization is begun. Daily application of splints as well as a continuous night splinting is sometimes necessary for several weeks to months postoperatively to help minimize the risk of contracture recurrence. Continuous passive motion (CPM) may be a useful modality to maintain joint motion but it is not a substitute for maintaining active motion and tendon gliding and excursion.

Outcomes, prognosis, and complications

Full extension of PIP joint flexion contractures after operative release occurs in 96% of cases.^{12,13} There is frequently relapse,




Fig. 21.13 (A) Proximal interphalangeal (PIP) flexion contracture caused by longitudinal soft-tissue pterygium. (B,C) PIP soft-tissue transverse release that incorporates a Joshi transposition flap in the planning. (D) Soft-tissue release and flap transposed. (E) Flap inset and donor defect on ulnar side of digit is closed with hypothenar full-thickness skin graft.

though not complete recurrence, of the deformity despite adequate release and good postoperative management. After PIP joint flexion contracture release in patients with Dupuytren contractures, there is reported relapse in those with severe contractures from a preoperative mean of 78° to a postoperative mean of 36° .²⁵ With severe PIP flexion contractures, one can seldom expect to regain normal extension, although the deformity can be improved.

Neurovascular injury may occur during surgical release. However, even if there has not been a sharp injury to the digital neurovascular structures, ischemia to the finger may result from neurovascular overstretch when the finger has been previously flexed for a long time. Skin flaps may be thin

and ischemic and develop postoperative necrosis. Necrotic skin flaps may leave tendons and their sheaths exposed and in danger of desiccation, necessitating secondary soft-tissue reconstruction. Skin flap marginal necrosis may also lead to secondary wound healing and adverse scarring with relapse of contractures.

Excessive and unwarranted attempts at release of the volar plates, accessory collateral ligaments, and collateral ligaments, and use of excessive passive extending force in treatment of PIP joint flexion contracture may result in the joint subluxing into hyperextension. This results in a significant postoperative problem and the finger must then be held in a flexed position until adequate scarring heals the torn ligaments.

Cartilage necrosis may result at the distal end of the proximal phalanx when it is brought into full extension from a flexed position because of excessive pressure now applied on the fully extended joint surface.²⁶ Risk of overstretched neurovascular ischemia and cartilage necrosis may be heightened if a Kirschner wire has been used to temporarily fix the PIP joint in extension to maintain the contracture release.

A hyperextending force of the DIP joint by an improperly placed Joint Jack splint that applies excessive pressure on the fingertip may cause iatrogenic functional problems at the DIP joint. Dysesthesias to the fingertip, stiffness in both flexion and extension, and reflex sympathetic dystrophy are potential complications of contracture release.

Secondary procedures

A relapse of a functionally impairing PIP joint flexion contracture may necessitate disarticulation amputation at the PIP joint or bone shortening at the PIP joint arthrodesis site with fusion in a more favorable position. Either of these two options may be considered in the primary treatment of the patient who is too frail to undergo any other surgical management or the patient who lacks the motivation needed for successful postoperative management. The patient who is a heavy smoker and has a longstanding severe flexion contracture (more than 70°) of the PIP joint may also potentially be best served by PIP joint disarticulation amputation or perhaps fusion.

The spastic hand in cerebral palsy

Diagnosis/patient presentation

Treatment of cerebral palsy necessitates accurate assessment of the clinical problem, non-surgical modalities, as well as surgical treatment. Overall upper extremity function is classified by the nine-level House activity scale (Table 21.1).²⁷ Surgical intervention has been shown to improve limb function by 2.6 functional levels.

Patient selection

The age of the patient is important and the child should be at least 6 or 7 years old to cooperate with the preoperative assessment and postoperative therapy. The type of palsy is important and may be spastic, ataxic, or choreoathetotic. The last is a contraindication to tendon transfers. Surgery for athetoid patients usually will involve only joint stabilization through fusions such as at the MP joint of the thumb. The patients who derive the most benefit from surgery usually have spastic hemiparesis.²⁸ A hand with poor sensibility is less likely to be used after reconstructive surgery. Some believe that an intelligence quotient of >70 is desirable if surgery is contemplated, but others feel that intellect is less important.^{29,30}

Non-surgical treatment

Non-surgical modalities include splinting, occupational therapy, and pharmacologic intervention. Splinting may help prevent joint contractures. This requires a high level of compliance from patients and caregivers. It may also be a

Table 21.1 House functional classification for cerebral palsy

Grade	Designation	Activity level
0	Does not use	Does not use
1	Poor passive assist	Uses as stabilizing weight only
2	Fair passive assist	Can hold onto object placed in hand
3	Good passive assist	Can hold onto object and stabilize it for use by other hand
4	Poor active assist	Can actively grasp object and hold it weakly
5	Fair active assist	Can actively grasp object and stabilize it well
6	Good active assist	Can actively grasp an object and then manipulate it against other hand
7	Spontaneous use, partial	Can perform bimanual activities easily and occasionally uses the hand spontaneously
8	Spontaneous use, complete	Uses hand completely independently without reference to the other hand

(Reproduced with permission from House JH, Gwathmey FW, Fidler MO. A dynamic approach to the thumb-in-palm deformity in cerebral palsy. *J Bone Joint Surg Am.* 1981;63:216–225.)

necessary component of postoperative management. Many medications have been used, some of which have significant adverse drug reactions. The most commonly used are intramuscular injection of botulinum toxin A and intrathecal baclofen. Botulinum toxin injection relaxes muscles that may then be responsive to splinting and stretching in therapy.

Surgical technique

The typical spastic posture of the upper limb includes shoulder internal rotation, elbow flexion, forearm pronation, wrist flexion and ulnar deviation, thumb-in-palm, and clenched fist (Fig. 21.14). A thorough preoperative analysis of the pattern of spasticity is required and an assessment of joint contractures that may need to be released. Assessment of passive range of motion must be done slowly to overcome muscle spasticity. Joint contractures are assessed by evaluating particular muscles. Thus, positioning the wrist joint in flexion will allow passive finger extension if there is no joint contracture.

Spastic muscles need to be either released or weakened by lengthening to correct muscle imbalance around joints. At the wrist, there is usually poor volitional control of extensor carpi radialis longus, extensor carpi radialis brevis (ECRB), and extensor carpi ulnaris (ECU) and there is spastic overpull of flexor carpi radialis (FCR) and flexor carpi ulnaris (FCU). One next assesses which muscles are weak or have poor motor control. These flaccid muscles need to be augmented by tendon transfer. Finally, assess which muscles are available for transfer. Those under good voluntary control are the best for tendon transfer, though transfer of a spastic muscle may




Fig. 21.14 Typical spastic hemiplegic posture of the upper extremity shows shoulder internal rotation, elbow flexion, forearm pronation, wrist flexion and ulnar deviation, thumb-in-palm, and clenched fist deformities.

weaken the overpowered side and utilize it to strengthen the weaker side of the unbalanced joint. Severe joint contractures or joint instability may necessitate joint fusion.

Surgical treatment options by type of deformity

Shoulder

Shoulder surgery is rarely indicated. Occasionally, Z-lengthening of pectoralis major through a deltopectoral incision is done together with Z-lengthening of the subscapularis (or simple division by myotomy or recession from the scapula, which maintains subscapularis integrity) may be necessary. With a tight adduction contracture, there may be a soft-tissue deficit requiring flap reconstruction (although this is more frequently necessary with tight shoulder adduction contractures that may occur with spastic post-traumatic or stroke brain injury). Latissimus dorsi and teres major transfer to the posterolateral humerus at the greater tuberosity is seldom required, as is an external rotational humeral osteotomy.

Elbow

Mild flexion contractures may be improved simply by the necessary surgical procedures directed towards forearm pronation and wrist flexion (flexor-pronator muscle slide; or flexor aponeurotic release (FAR)) as these muscles cross the elbow. More significant flexion contractures (usually $>40^\circ$ or

50°) demand attention to biceps, brachialis, and possibly brachioradialis. Antecubital soft-tissue paucity may become apparent after the release, necessitating Z-plasty or even a flap (Fig. 21.15). If brachioradialis needs to be released, this can be done distally and the muscle turned up into the antecubital fossa for wound coverage and a skin graft placed over it.

Lacertus fibrosus is released and Z-lengthening of the biceps tendon done. If residual unacceptable contracture remains, then stepwise release of brachialis (which is weakened by intramuscular incision into the fibrous septae) and of the brachioradialis (either proximally or distally) is performed.^{28,31} Less severe flexion contracture can be treated by fractional biceps tendon lengthening (a series of transverse step cuts in the tendon). This retains biceps strength better than Z-lengthening. Postoperative elbow extension splinting is done for 4 weeks, followed by progressive range of motion and intermittent extension splinting.

Forearm pronation

This deformity has been classified into four groups^{28,32}:

- Group I: Active supination beyond neutral
- Group II: Active supination less than neutral
- Group III: No active supination; free passive supination, but with active pronator teres
- Group IV: No active supination; tight passive supination.

When treating the forearm pronation deformity in isolation, recommendations are: no surgery for group I; pronator quadratus release with or without FAR for group II; pronator teres release for group III, and pronator quadratus release and FAR for group IV. FAR consists of excision of a 2-cm transverse strip of fascia from the flexor-pronator mass as well as division of all fascial septae. This allows muscle fibers to be stretched, so releasing myostatic contracture without cutting tendons. Pronator teres re-routing involves taking down the distal insertion with a distal cuff of periosteum and then re-routing it through an interosseous membrane window and reattaching to the dorsoradial side of the radius with a suture anchor. Alternatively, a Z-tenotomy of pronator teres distal insertion is done, re-routing the distal segment around the radial side of the radius and reattaching the two ends.

However, often the forearm pronation deformity cannot be taken out of context with the wrist and finger flexion deformities. A flexor-pronator muscle slide used for the latter problems will often significantly improve forearm pronation, as will the Green FCU transfer for active wrist extension.³³

Wrist flexion

It is important to note the amount of digital flexor tightness that is also present. Digital flexor tightness can be quantitated by measurement of the Volkmann angle (Fig. 21.16). The wrist is flexed with the digits held extended. Wrist is then passively extended as much as possible while keeping digits extended. Full wrist extension can be accomplished in the absence of flexor tendon tightness. With digital flexor contracture, the wrist cannot be extended to neutral. As digits are extended, with wrist extended, one can assess selective digital spasticity. When PIP joint extension is limited, flexor digitorum superficialis (FDS) spasticity is suspected (flexor digitorum




Fig. 21.15 (A) Release of an elbow flexion contracture often results in a soft-tissue antecubital defect. (B,C) A transposition fasciocutaneous flap will cover the exposed vital structures in the antecubital fossa and then the donor defect over the proximal forearm muscles can be replaced with a split-thickness skin graft. (D) Final elbow extension accomplished.

profundus (FDP) spasticity may also be present). If full PIP joint extension is possible, but DIP joints do not extend, FDP spasticity is present.

The Zancolli classification of active finger and wrist extension is helpful (Table 21.2).³⁴ In the patient with active wrist extension, spastic wrist flexion, and no significant digital flexor tightness, a FAR procedure along with fractional lengthening of the FCU, Z-lengthening of the FCR, and release of palmaris longus may be required. In contrast, the patient with flexed fingers, but relatively little spasticity of wrist flexors, may benefit from fractional lengthening of the involved finger flexors. If the fingers can be extended only with the wrist in moderate flexion, then one can perform wrist flexor releases and additional finger flexor fractional lengthening. However, a flexor-pronator muscle slide will address simultaneous wrist and finger flexion and the forearm pronation deformity (Fig. 21.17 and Video 21.1 ▶).

Clinical tips

Flexor-pronator slide

- Allows each muscle to slide distally differentially, with each finding its “new” place of attachment
- Identify and mobilize median and ulnar nerve first before commencing release.
- Anterior interosseous nerve and artery are “safely” reflected volarly.
- May need to divide origin of posterior interosseous artery for mobilization of the deepest fibers of FDS to middle and ring fingers
- Splint wrist and fingers for 5–6 weeks to allow muscles to attach at new sites of origin
- Continue night position splinting.
- Flexion strength may take some months to return.




Fig. 21.16 Volkmann test for digital flexor tendon tightness. When wrist extension is less than neutral (Volkmann's angle), surgical intervention is indicated.

Table 21.2 Zancolli classification of active finger and wrist extension

Level	Designation	Description
1	Minimal flexion spasticity	Can completely extend the fingers with a neutral position of the wrist or with $<20^\circ$ of flexion
2	Moderate flexion spasticity	Fingers can be actively extended but only with $>20^\circ$ of flexion
2A		Can actively extend, partially or totally, the wrist with the fingers flexed
2B		Cannot actively extend the wrist with the fingers flexed because of flaccid paralysis of the wrist extensor muscles
3	Severe flexion spasticity	Cannot extend the fingers even with maximal flexion of the wrist

(Reproduced with permission from Zancolli EA, Zancolli ER Jr. Surgical management of the hemiplegia spastic hand in cerebral palsy. *Surg Clin North Am.* 1981;61:395–406.)

Only once the acute flexor spasm has been released is it possible to accurately assess if there is active wrist extension. This may be addressed by ECU transfer to ECRB or by brachioradialis transfer. Alternatively, the author has found that FCU can be transferred (and will have sufficient strength) several months after a flexor-pronator muscle slide has been performed. This may greatly improve grasp by removing the habitual grasp pattern of simultaneous wrist flexion. The fingers and wrist and elbow are splinted for 4 weeks postoperatively, with continued wrist splinting for another 6 weeks, and night positional splinting of the fingers.

Wrist fusion by proximal row carpectomy (PRC) and using those removed carpal bones for graft is reserved for very severe wrist flexion contractures (often with a non-functional hand). Shortening accomplished by PRC may reduce the need to shorten finger flexors.

Correction of wrist and finger flexion deformities may unmask intrinsic hand tightness. A simultaneous thenar release can be done through a curvilinear thenar incision (avoiding the median motor nerve branch), but the author prefers to address finger swan-neck deformities at a later date.




Fig. 21.17 A flexor-pronator muscle slide is an extensive procedure that involves identification of all neurovascular structures in the forearm and release of the muscular origins so that a distal slide can occur. (A) Wrist and digit contractures. (B) Muscle origin releases. (C) Muscle advancement. (D) Thenar intrinsic release. (E) Passive correction accomplished.

Thumb

Deformity as described by House and modified by Tonkin *et al.*³⁵ is a useful classification (Table 21.3). If the deformity is adduction without MP or IP joint deformity, then release of adductor pollicis is performed in conjunction with first

webspace Z-plasty. Release of the dorsal fascia or even first dorsal interosseous release may also be required. If there is tight thumb adduction with MP joint flexion (without significant IP joint deformity), then also release the flexor pollicis brevis through the same incision.³⁶ If both MP and IP joints are flexed together with thumb adduction, then add flexor pollicis

Table 21.3 Modified House classification of thumb deformity

Type	Deforming forces	Thumb position
1. Intrinsic	Adductor pollicis 1st dorsal interosseous Flexor pollicis brevis	Metacarpal adduction MCP joint flexion IP joint extension
2. Extrinsic	Flexor pollicis longus	MCP joint flexion IP joint flexion Metacarpal adduction less marked
3. Combined	Adductor pollicis 1st dorsal interosseous Flexor pollicis brevis Flexor pollicis longus	Metacarpal adduction MCP joint flexion IP joint flexion (True “thumb-in-palm” deformity)

MCP, Metacarpophalangeal; IP, interphalangeal.
(Reproduced with permission from Tonkin MA, Hagrick NC, Eckersley JR, et al. Surgery for cerebral palsy part III: classification and operative procedures for thumb deformity. *J Hand Surg Br.* 2001;26:465–470.)

longus (FPL) lengthening through a separate incision, performing either fractional lengthening or Z-lengthening (for more severe IP joint flexion).

In a patient who does not have sufficient antagonistic strength, tendon transfers will be needed to augment these

previously described releases. One must assess extrinsic thumb extensor function. If there is a functioning extensor pollicis longus (EPL) and weak abduction, re-routing EPL is helpful. EPL is transected proximal to the IP joint, the extensor mechanism is repaired, and the proximal end is re-routed through the first dorsal compartment and reattached to the radial side of the extensor mechanism, so changing its vector direction³⁰ or into the proximal phalanx. If there is MP joint hyperextension, then the re-routed EPL is inserted into the radial side of the distal metacarpal.³⁷ If there is no EPL function, brachioradialis to abductor pollicis longus transfer can be performed.

With MP joint hyperextension instability, then either a volar tenodesis or capsulodesis of the joint must be done or MP joint fusion performed.

Finger swan-neck deformity

If there is mild deformity, secondary to intrinsic spasticity, extrinsic silver ring splints may be used, or intrinsic muscle slide performed (Fig. 21.18). With a concomitant thumb adductor spasticity, and if a temporary ulnar nerve block favorably affects both the thumb-in-palm deformity and intrinsic finger spasticity, then one may, on occasion, consider ulnar motor neurectomy in Guyon's canal. With more severe PIP joint instability, an FDS distal slip tenodesis secured to the proximal phalanx works well (Fig. 21.19).³⁸




Fig. 21.18 (A) Patient with residual swan-neck deformities and intrinsic muscle contractures following more proximal release. (B) Interosseous muscle slide. (C,D) Final ability to flex and extend the fingers.




Fig. 21.19 A residual hyperextension swan-neck deformity at the PIP joint may be treated by (A) a proximal intrinsic release and (B) tenodesis using a distally based slip of, flexor digitorum superficialis that is re-routed back around the origin of the flexor tendon sheath or anchored into bone of the proximal phalanx.

Hints and tips

Spastic swan-neck deformity

- Differentiate between intrinsic “tightness” and “tightness” of extrinsic extensors.
- The former is treated by intrinsic release (dorsally) or volar fractional lengthening.
- The latter is treated surgically by central slip (“Fowler”) tenotomy.
- “Mild” swan-neck may be treated by figure-of-eight splinting.

Swan-neck deformity may result from either intrinsic spasticity or overpull of digital extensors. Each will cause overstretch of the PIP volar plate, resulting in hyperextension at that joint. Accurate diagnosis is essential, therefore, for proper surgical treatment.³⁹

These two variants of swan-neck deformity are distinguished by observing the MP joint position during active digital extension. Patients with intrinsic muscle spasticity

have MP joint flexion and PIP joint hyperextension. The Bunnell test will further confirm intrinsic spasticity. Patients who present with swan-neck deformity and full MP joint extension upon active digital extension have this deformity from overpull of the long digital extensors. Surgical treatment of the former is done through a transverse incision in the palm and fractional lengthening of lumbricals and volar and dorsal interossei,⁴⁰ avoiding the first dorsal interosseous if possible to reduce the risk of weakened pinch strength. Extensor digitorum communis overpull, on the other hand, is treated by central slip tenotomy about 1 cm proximal to the PIP joint.

PIP joint volar tenodesis may be required as a concomitant procedure if the volar plate is very lax or has been described as the sole treatment of swan-neck deformity. This is done by either using a slip of FDS tendon⁴¹ or using lateral bond translocation.⁴²

The spastic hand following stroke and traumatic brain injury

Patient selection

The principles of assessment and treatment are very similar to cerebral palsy. Procedures for flexed fingers are divided into functional procedures or those that are hygiene procedures.⁴³ The results of surgery are better when deformities are corrected early, before fixed joint contractures have developed. Surgery should not be considered as a treatment of last resort. “Non-functional” surgical procedures may actually help overall bodily function. For example, in spite of not having active function in the upper extremity after spastic releases, dressing may be facilitated or positioning the hand on a walker may improve ambulation.

Fingernails may dig into the palm and palm skin may be macerated. Clenched fist is often accompanied by a flexed wrist. Assess for active finger flexion. If the PIP joints flex while DIP joints remain extended, there is spasticity in the FDS rather than FDP.

Surgical technique

If there is skin maceration and no volitional flexion, then significant lengthening of flexor tendons is required and superficialis-to-profundus (STP) transfer is performed. At best, a mass action grasp pattern is achieved with the STP transfer and, at worst, passive restraint to extension is accomplished rather than a “floppy hand” with joint instability if simple tenotomies were to be performed. Associated procedures may be required such as thenar release and Z-lengthening of wrist flexors.

If there is volitional control of extrinsic finger flexors, and if the degree of flexion contracture is less severe, then fractional lengthening of FDS, FDP, and even FPL is done by sharply incising the intramuscular tendon fibers. A short volar splint may be used for postoperative comfort, but active exercises are begun immediately. A flexor-pronator muscle slide may sometimes be used for a more global correction of flexed elbow, forearm pronation, wrist and finger flexion.

Conclusions

Contractures in the upper extremity result not only from joint pathology but also from disorders of periarticular structures as well as tendon adhesions and muscle imbalance. The correct treatment is predicated on making the appropriate diagnosis. A variety of specific disorders are known to lead to contractures, but the most common conditions that the hand surgeon will have to treat are the consequences of trauma. Meticulous postoperative therapy and splinting are essential to optimize best functional outcome.

Future directions

With regard to joint contractures and stiff joints, wide-awake local anesthesia technique has added an extra dimension to

surgical treatment. With this approach, one can assess functional outcome in the operating room. The patient can immediately see the outcome while pain-free. This technique also serves as a bridge to ongoing postoperative hand therapy.

Biochemical and mechanical scar modification are ongoing directions for research. The introduction of corrective surgery will bring about all the phases of wound healing once again with inflammation, edema, collagen deposition, and scar remodeling. The postoperative problem of new scar formation following joint releases and tenolyses remain an issue.

In the area of spasticity, gait analysis has been pivotal in evaluating the lower extremity. We are now gaining insights from motion analysis laboratories for the upper extremity. This will not only help in the preoperative analysis of spastic problems but will also help in assessing postoperative functional outcomes.



Access the complete reference list online at <http://www.expertconsult.com>

1. Lister G. *The Hand: Diagnosis and Indications*. 3rd ed. New York, NY: Churchill Livingstone; 1993:191–198.
2. Curtis RM. Stiff finger joints. In: Grabb WC, Smith JW, eds. *Plastic Surgery*. 3rd ed. Boston, MA: Little Brown; 1979:598–603.
3. Smith RJ. Nonischemic contractures of the intrinsic muscles of the hand. *J Bone Joint Surg Am*. 1971;53:1313–1331. *This is a classic article that very lucidly describes the pathologic anatomy and treatment of the disorders of the intrinsic hand muscles.*
10. Eaton RG. The extensor mechanism of the fingers. *Bull Hosp Joint Dis*. 1969;30:39–47. *Another classic article that has stood the test of time and is recognized for its practical approach to the extensor mechanism and contributions to finger contractures.*
12. Watson HK, Light TR, Johnson TR. Check-rein resection for flexion contracture of the middle joint. *J Hand Surg Am*. 1979;4:67–71. *This article describes in detail the role of the volar plate in PIP flexion contractures and the importance of identifying the pathologically disordered checkrein ligaments.*
19. Joshi BB. Dorsolateral flap from same finger to relieve flexion contracture. *Plast Reconstr Surg*. 1972;49:186–189.
28. Lomita C, Ezaki M, Oishi S. Upper extremity surgery in children with cerebral palsy: review article. *J Am Acad Orthop Surg*. 2010;18:160–168. *This is a very concise article that is packed with practical information. It is a systematic review that includes spasticity of the elbow, forearm, wrist, thumb, and fingers in sequence.*
30. Manske PR. Redirection of extensor pollicis longus in the treatment of spastic thumb-in-palm deformity. *J Hand Surg Am*. 1985;10:553–560.
32. Gschwind CR. Surgical management of forearm pronation. *Hand Clin*. 2003;19:639–655.
35. Tonkin MA, Hagrick NC, Eckersley JR, et al. Surgery for cerebral palsy part III: classification and operative procedures for thumb deformity. *J Hand Surg [Br]*. 2001;26:465–470. *Another practical guide that classifies thumb deformity into “intrinsic” and “extrinsic” contractures or a combination of the two. This analysis of the deformity then translates into a useful surgical treatment algorithm.*

References

1. Lister G. *The Hand: Diagnosis and Indications*. 3rd ed. New York, NY: Churchill Livingstone; 1993:191–198.
2. Curtis RM. Stiff finger joints. In: Grabb WC, Smith JW, eds. *Plastic Surgery*. 3rd ed. Boston, MA: Little Brown; 1979:598–603.
3. Smith RJ. Nonischemic contractures of the intrinsic muscles of the hand. *J Bone Joint Surg Am*. 1971;53:1313–1331. *This is a classic article that very lucidly describes the pathologic anatomy and treatment of the disorders of the intrinsic hand muscles.*
4. Chicarilli ZN, Watson HK, Linberg GR, et al. Saddle deformity. Post-traumatic interosseous-lumbrical adhesions: review of 87 cases. *J Hand Surg Am*. 1986;11:210–218.
5. Flatt AE. The anatomy and kinesiology. In: Flatt AE, ed. *The Care of the Arthritic Hand*. 5th ed. St. Louis, MO: Quality Medical; 1995:5.
6. Watson WK, Weinzeig J. Stiff joints. In: Green D, Hotchkiss R, Pederson C, eds. *Green's Operative Hand Surgery*. 4th ed. New York, NY: Churchill Livingstone; 1999:552.
7. Laseter GF. Management of the stiff hand: a practical approach. *Orthop Clin North Am*. 1983;14:749–765.
8. Littler JW. Principles of reconstructive surgery of the hand. In: Converse JM, ed. *Reconstructive Plastic Surgery*. Philadelphia, PA: WB Saunders; 1964:1612–1632.
9. Littler JW. The finger extensor mechanism. *Surg Clin North Am*. 1967;47:415–432.
10. Eaton RG. The extensor mechanism of the fingers. *Bull Hosp Joint Dis*. 1969;30:39–47. *Another classic article that has stood the test of time and is recognized for its practical approach to the extensor mechanism and contributions to finger contractures.*
11. Little JW, Eaton RG. Redistribution of forces in correction of boutonniere deformity. *J Bone Joint Surg Am*. 1967;49:1267–1274.
12. Watson HK, Light TR, Johnson TR. Check-rein resection for flexion contracture of the middle joint. *J Hand Surg Am*. 1979;4:67–71. *This article describes in detail the role of the volar plate in PIP flexion contractures and the importance of identifying the pathologically disordered checkrein ligaments.*
13. Watson HK, Paul H. Pathologic anatomy. *Hand Clin*. 1991;7:661–668.
14. Brand TW. *Drag in Clinical Mechanics of the Hand*. St. Louis, MO: CV Mosby; 1985:61–87.
15. Bunnell S, Doherty EW, Curtis RM. Ischemic contracture local in the hand. *Plast Reconstr Surg*. 1948;3:424.
16. Flowers KR, Pheasant D. The use of torque angle curves in the assessment of digital joint stiffness. *J Hand Ther*. 1988;1:69–74.
17. Bissell JH. Clinical perspectives: therapeutic modalities in hand surgery. *J Hand Surg Am*. 1999;24:435–448.
18. Buckwalter JA. Effects of early motion on healing of musculoskeletal tissues. *Hand Clin*. 1996;12:13–24.
19. Joshi BB. Dorsolateral flap from same finger to relieve flexion contracture. *Plast Reconstr Surg*. 1972;49:186–189.
20. Netscher D, Schneider A. Homodigital and heterodigital island pedicle flaps. In: Rayan GM, Chung KC, eds. *Flap Reconstruction of the Upper Extremity: A Master Skills Publication*. Rosemont, IL: American Society for Surgery of the Hand; 2009:143–152.
21. Curtis M. Capsulectomy of the interphalangeal joints of the fingers. *J Bone Joint Surg Am*. 1954;36:1219–1232.
22. Burton RI, Melchior JA. Extensor tendons – late reconstruction. In: Green D, Hotchkiss R, Pederson C, eds. *Green's Operative Hand Surgery*. 4th ed. New York, NY: Churchill Livingstone; 1999:1955.
23. Lalonde DH. Wide awake flexor tendon repair. *Plast Reconstr Surg*. 2009;123:623–625.
24. Buch VI. Clinical and functional assessment of the hand after metacarpal phalangeal capsulotomy. *Plast Reconstr Surg*. 1974;53:452–457.
25. Weinzeig N, Culver JE, Fleegler EJ. Severe contractures of the proximal interphalangeal joint in Dupuytren's disease combined fasciectomy with capsuloligamentous release versus fasciectomy alone. *Plast Reconstr Surg*. 1996;97:560–566.
26. Field PL, Hueston JT. Articular cartilage loss in long-standing immobilization of interphalangeal joints. *Br J Plast Surg*. 1970;23:186–191.
27. House JH, Gwathmey FW, Fidler MO. A dynamic approach to the thumb-in-palm deformity in cerebral palsy. *J Bone Joint Surg Am*. 1981;63:216–225.
28. Lomita C, Ezaki M, Oishi S. Upper extremity surgery in children with cerebral palsy: review article. *J Am Acad Orthop Surg*. 2010;18:160–168. *This is a very concise article that is packed with practical information. It is a systematic review that includes spasticity of the elbow, forearm, wrist, thumb, and fingers in sequence.*
29. Zancolli VA, Goldner LJ, Swanson AB. Surgery of the spastic hand in cerebral palsy: report of the Committee on Spastic Hand Evaluation. *J Hand Surg Am*. 1983;8:766–772.
30. Manske PR. Redirection of extensor pollicis longus in the treatment of spastic thumb-in-palm deformity. *J Hand Surg Am*. 1985;10:553–560.
31. Tonkin MA. The upper limb in cerebral palsy. In: Gupta A, Kay SPJ, Scheker LR, eds. *The Growing Hand*. London: Mosby; 2000:447–459.
32. Gschwind CR. Surgical management of forearm pronation. *Hand Clin*. 2003;19:639–655.
33. Green WT, Banks HH. Flexor carpi ulnaris transplant and its use in cerebral palsy. *J Bone Joint Surg Am*. 1962;44:1343–1352.
34. Zancolli EA, Zancolli ER Jr. Surgical management of the hemiplegia spastic hand in cerebral palsy. *Surg Clin North Am*. 1981;61:395–406.
35. Tonkin MA, Hagrick NC, Eckersley JR, et al. Surgery for cerebral palsy part III: classification and operative procedures for thumb deformity. *J Hand Surg [Br]*. 2001;26:465–470. *Another practical guide that classifies thumb deformity into "intrinsic" and "extrinsic" contractures or a combination of the two. This analysis of the deformity then translates into a useful surgical treatment algorithm.*
36. Van Heest A, House J. Management of the spastic hand. In: Mathes SJ, Hentz VR, eds. *Plastic Surgery*. 2nd ed. Philadelphia, PA: Saunders/Elsevier; 2006:543–553.
37. Van Heest AE. Surgical technique for thumb-in-palm deformity in cerebral palsy. *J Hand Surg Am*. 2011;36:1526–1531.
38. Swanson AB. Surgery of the hand in cerebral palsy and the swan-neck deformity. *J Bone Joint Surg Am*. 1960;42:951–964.
39. Carlson MG, Gallagher K, Spirtos M. Surgical treatment of swan-neck deformity in hemiplegic cerebral palsy. *J Hand Surg Am*. 2007;32:1418–1422.
40. Matsuo T, Matsuo A, Hajime T, et al. Release of flexors and intrinsic muscles for finger spasticity in cerebral palsy. *Clin Orthop Relat Res*. 2001;384:162–168.
41. Swanson AB. Treatment of the swan-neck deformity in the cerebral palsied hand. *Clin Orthop*. 1966;48:167–171.
42. Tonkin MA, Hughes J, Smith KL. Lateral band translocation for swan-neck deformity. *J Hand Surg Am*. 1992;17:260–267.
43. Hisey MS, Keenan MAE. Orthopedic management of upper extremity dysfunction following stroke or brain injury. In: Green DP, Hotchkiss RN, Pederson WC, eds. *Green's Operative Hand Surgery*. 4th ed. Philadelphia, PA: Churchill Livingstone; 1999:287–324.

22

Ischemia of the hand

Hee Chang Ahn and Neil F. Jones

Access video content for this chapter online at expertconsult.com

SYNOPSIS

- Upper extremity ischemia is caused by many etiologies and may be classified into acute and chronic cases.
- A precise understanding of arterial anatomy is pertinent to preoperative diagnosis, patient selection, and operative procedure.
- A history of cold intolerance, Raynaud's phenomenon, and frequency of ischemic pain is important. Color changes, ulcerations, and infections are evaluated.
- Non-invasive vascular examination includes measurement of fingertip temperatures, Doppler ultrasound, segmental arterial pressures, and capillaroscopy.
- Various pharmacologic agents can be used to counteract the sympathetic effect on the muscular layers of the arterial wall in a conservative medical approach.
- Surgical intervention is directed at interrupting the sympathetic innervation of the muscle layer, by physical dilatation of the obstructed lumen, or by microsurgical reconstruction of the occluded lumen.



Access the Historical perspective section online at

<http://www.expertconsult.com>

Introduction

Hand ischemia occurs when the vascular system is no longer able to transport blood efficiently because of trauma, constriction, obstruction, or vasospasm. It is the critical vascular event that results in eventual tissue necrosis and even amputation without proper management. Compared with the lower extremity, the symptomatology and presentation is varied in the upper limb and it is frequently underdiagnosed. Upper extremity ischemia is caused by many etiologies³ and may be classified into acute and chronic cases (Box 22.1). Any microvascular injury that diminishes the vascular flow induces the acute ischemic conditions of the hand. Systemic, congenital, and genetic problems also cause chronic ischemic conditions.

Raynaud's phenomenon is a well-known vasospastic condition that affects 5–10% of the general population.^{4,5} Primary Raynaud's disease occurs in the absence of any underlying condition whereas secondary Raynaud's syndrome is associated with other vasospastic conditions.

Fuchs classified arterial disease according to the three arterial layers: the intima, media, and adventitia. Several of the most frequent pathologic processes (atherosclerosis, intimal hyperplasia) originate in the intimal layer. Endothelial disruption produces thrombotic occlusion and embolization.⁶ The media consists of smooth muscle cells, fibroblasts, and elastic tissue. Atherosclerosis also influences the loss of tissue integrity. The media can become chronically dilated in a diffuse (ectasia) or localized (aneurysm) pattern. The adventitia is involved in diffuse pathologic entities (arteritis, Buerger's disease). Jones categorized hand ischemia into subgroups of acute and chronic disease. There are multiple causes of upper extremity ischemia (see Box 22.1),³ but a classification system based on the underlying pathophysiologic mechanism responsible for producing the ischemia would seem to be most appropriate as a rationale for suitable treatment. Jones described five main pathophysiological mechanisms of hand ischemia: emboli, thrombosis, occlusive disease, vasospasm, and low-flow states.⁷

Regardless of its causes, ischemia of the hand is manifested by color and temperature changes, pale fingers, cold intolerance, numbness, digital ulcerations, and gangrenous changes. Despite appropriate treatments, such as smoking cessation, cold avoidance, biofeedback techniques, and pharmacological therapy, ischemia commonly progresses to the eventual consequence of amputation.^{8–13} This chapter provides an insight to accurate diagnosis and appropriate treatment to avoid devastating tissue losses.

Raynaud's phenomenon

Raynaud's disease is a rare disorder but it is an important cause of upper limb ischemia. This entity is often confused with Raynaud syndrome. Raynaud's phenomenon in patients

Historical perspective

Maurice Raynaud described Raynaud's phenomenon in 1862 and attributed the condition that bears his name to overactivity of the sympathetic nervous system, but a review of his cases reveals that most of his patients probably had small-vessel occlusive disease. He hypothesized that "local asphyxia of the extremities" was a result of "increased irritability of the central parts of cord presiding over vascular innervations."¹

Lewis first postulated a peripheral rather than central mechanism for Raynaud's disease caused by a "spasm of digital arteries". He stated that "the abnormal element in the reaction to cold is a direct reaction and due to a peculiar condition of the vessel wall locally: it is not the result of a reflex through the vasomotor nerves." However, the pathophysiology remained poorly understood.²

BOX 22.1 Etiology of acute and chronic ischemia of the hand

- Atherosclerosis: proximal (more common) or distal
- Buerger's disease
- Cervical rib compression
- Connective tissue disease
 - Scleroderma
 - Mixed connective tissue disease
 - Systemic lupus erythematosus
 - Rheumatoid arthritis
 - Wegener's granulomatous
- Emboli
 - Atrial fibrillation
 - Myocardial infarction
 - Poststenotic dilatation of subclavian artery
- Iatrogenic
 - Brachial artery: cardiac catheterization
 - Radial artery: arterial pressure cannulation
 - Hemodialysis access: shunts and fistulas
- Intra-arterial drug injection
- Myeloproliferative and immunologic disorder
 - Polycythemia
 - Leukemia
 - Myeloma
 - Cryoglobulinemia
- Renal vascular disease
- Post-irradiation
- Septicemia
- Trauma
 - Shoulder dislocation
 - Supracondylar fracture of the humerus
 - Posterior dislocation of the elbow
 - Hypothenar hammer syndrome
- Toxins
 - Heavy metals
 - Vinyl chloride
 - Others
- Vibratory tool disease

(Reproduced with permission from Jones NF, Emerson ET. Interposition vein graft configurations for microsurgical revascularization of the ischemic hand. *Tech Hand Up Extrem Surg*. 1999;3:121–130.)

with upper extremity ischemia is common and classically consists of an orderly progression of color changes (white, blue, and then red) and symptoms in the affected hand secondary to vasospasm. Pallor is followed by a cyanotic appearance, and culminates with reactive hyperemia and burning pain or dysesthesias. This classic pattern occurs in about two-thirds of affected patients. In 1932, Allen and Brown proposed that Raynaud syndrome/phenomenon be differentiated from Raynaud's disease in that no underlying organic cause can be found in Raynaud's disease.¹⁴ They listed the following criteria as necessary for the diagnosis of Raynaud's disease:

1. Bilateral symptoms
2. Absence of gangrene

3. No evidence of underlying organic disease
4. Symptoms present for at least 2 years.

Merritt,¹⁵ and Blunt and Porter¹⁶ argued that these criteria are confusing and perhaps obsolete, considering that Raynaud's phenomenon can be present for an average of 11.5 years prior to diagnosis of an underlying connective tissue disease.¹⁷ Furthermore, in one study using sensitive laboratory testing of patients with Raynaud's disease, more than one-half of patients were found to have some evidence of an underlying systemic disease.¹⁸

The relationship between vasospasm in Raynaud's phenomenon and occlusive disease continues to be controversial. Some researchers have suggested that occlusive disease may initiate vasospasm via humoral and/or sympathetic mediators. This concept is supported by the fact that excision of the occluded arterial segment in patients with traumatic ulnar artery thrombosis (hypothenar hammer syndrome) will improve the digital vasospasm often seen in this disorder.¹⁹ Vasospastic symptoms in patients with connective tissue disorders may also be related to an underlying abnormality of the vessel wall. Intimal hyperplasia, thrombosis, fibrosis, embolism, adventitial thickening, aneurysm formation, and calcification have all been found in patients with Raynaud's phenomenon.^{20,21} The question remains whether these changes are responsible for the vasospastic symptoms or merely potentiate vasospasm initiated at another site. Therefore, bypass of distal arterial occlusions may not only provide oxygen delivery via increased blood flow to the hand but also may remove a potential source of vasospasm.

Basic science

Anatomy

Embryology

The limb buds appear at 4 weeks of embryonic life as lateral swellings and the forearm vasculature evolves through several stages between 4 and 8 weeks (see Chapter 25). A median artery, ulnar artery, and radial artery arise in order from the brachial artery at the elbow, but the median artery involutes as the radial and ulnar arteries provide the majority of blood flow to the hand.

Arterial system in the forearm, hand, and digits

Variations in the vascular pattern of the deep and superficial palmar arches and the common digital arteries are frequent. Therefore, a precise understanding of arterial anatomy is pertinent to preoperative diagnosis, patient selection, and operative procedure.

Superficial palmar arch

The superficial palmar arch may be classified as either "complete" or "incomplete". This classification provides the simplest understanding of the anatomy of the arches.²² Gellman *et al.* defined an arch to be complete if there was an anastomosis between the vessels constituting it and an incomplete arch as having an absence of communication or anastomosis between the vessels constituting the arch.²³ Coleman and Anson also described an incomplete superficial arch as one

"in which the contributing arteries do not anastomose, or when the ulnar artery fails to reach the thumb and index finger."²² Koman *et al.*²⁴ also reported a complete arch in 78.5% of extremities. Gellman *et al.* reported a complete arch in 38 of 45 specimens studied (84.4%). In contrast to these studies, Fazan²⁵ reported that only 43% of right hands and 52% of left hands had complete arches.

Multiple variations of the superficial palmar arch have been classified into subgroups. According to Gellman's study, complete arches have been divided into five subgroups:

- Type A: The radioulnar arch is formed by anastomosis between the superficial volar branch of the radial artery and the continuation of the ulnar artery.
- Type B: The superficial arch is formed by a continuation of the ulnar artery and even provides common digital vessels to the thumb and index webspace.
- Type C: The median and ulnar arteries combine to form the superficial arch without a contribution from the radial artery.
- Type D: This is characterized by all three vessels (radial, median, ulnar) contributing to the arches.
- Type E: A branch from the deep palmar arch communicates with an ulnar artery-initiated superficial arch.

The main branches from the superficial palmar arch are the three common digital arteries to the index–middle, middle–ring, and ring–small finger webspaces^{22,26} and the proper digital artery to the ulnar border of the small finger.^{23,27,28}

When the princeps pollicis artery and a vessel to the radial side of the index finger (index radial digital artery) originate from the superficial palmar arch, this should be named as the first common digital artery.^{27,29}

Deep palmar arch

The deep palmar arch is less variable than the superficial arch. The radial artery forms the deep arch when it passes from dorsal to palmar by piercing the two heads of the first dorsal interosseous muscle. The arch then curves along the bases of the metacarpal bones. The deep arch may anastomose with one or both volar branches of the ulnar artery.^{23,30} At least one of the deep volar branches was present in all individuals in a recent study. The deep palmar arterial arch travels across the palm, deep to the flexor tendons, at the level of the carpometacarpal joints to connect with a deep arterial branch from the ulnar artery.^{22,31} The deep palmar arch gives rise to as many as five palmar metacarpal arteries that pass distally to the level of the metacarpal heads, where they branch dorsally to join the dorsal metacarpal arteries and also connect to the common digital artery through a small palmar arterial branch. Nystrom *et al.* described three palmar and three dorsal arches that connect the four forearm arteries (ulnar, median, radial, and interosseous arteries). Dorsal metacarpal arteries that originate from the dorsal carpal arches pass to their respective webspaces distally, where they join perforating vessels from the palmar circulation.³²

The most consistent of the dorsal vessels supplying the dorsal carpal rete, which consists of numerous small, thin vessels (0.3–0.5 mm), is the radial dorsal carpal branch. It branches off the radial artery 10–15 mm distally to the radial styloid.²³

When the superficial arch is well developed, the deep palmar arch is correspondingly less developed and vice versa. A reciprocal inverse relationship was also found between the common palmar digital arteries and the palmar metacarpal arteries.^{22,30,33,34}

Digital arteries

The ulnar digital arteries of the thumb and index finger are larger than the radial digital arteries. The radial digital artery is larger in the ring and small fingers. The difference between the radial and ulnar digital arteries is statistically significant only in the border digits. The anatomy of the thumb digital arteries is unique. The blood supply of the thumb comes mainly from the princeps pollicis artery, the terminal branch of the superficial palmar arch, and the first dorsal metacarpal artery. There are numerous sources of blood supply from the radial and ulnar arteries, including the palmar ulnar, palmar radial, dorsal ulnar and dorsal radial arteries. The first palmar metacarpal artery is absent in about 2% of patients.^{22,31} This accounts for the tolerance to ischemia by the thumb due to numerous collateral blood vessels.

According to the Hagen–Poiseuille's law, the blood viscosity, diameter, length and the pressure gradient influence flow through the digital arteries, and larger digital arteries can carry more blood. Strauch and de Moura described the numerous interconnections between the digital arteries beyond the metacarpophalangeal joints. These connections play an important role in hand ischemia if segmental arterial obstruction develops.³⁴

Micro-arterial system

Microvascular vessels are defined as having a diameter of <100 μm . Their role is to deliver oxygen and nutrients at a cellular level. They consist of nutritional capillary and thermoregulatory vessels.³³ In the digits, 80–90% of the total flow passes through thermoregulatory beds and 10–20% are involved in capillary nutrition.³⁵ In pathologic states, cellular hypoperfusion leads to ischemic symptoms and imbalance in the distribution of thermoregulatory and nutritional flow, resulting in cell death or damage.

Physiology of blood flow

Hemodynamics

Koman *et al.*²⁴ described macrovascular structures that are defined as vessels >100 μm . Their function is to deliver nutrients to the microvascular beds, provide adequate capacity for arteriovenous thermoregulatory flow, and drain nutritional and thermoregulatory beds.

Cellular control mechanisms

Blood flow does not only follow principles of fluid dynamics. There is compensation between arterial dilatation, collateral vessels, and resistance in the peripheral circulation. In a normal extremity, blood flow in the hand depends on sympathetic tone, metabolic demands, environmental events, local factors, and circulating humoral mediators. Alpha-adrenergic control is the dominant control arm of vasoconstriction; however, vasodilatation is initiated by endothelium-derived relaxing factor. Active vasoconstriction and vasodilatation may

be initiated by a central control process mediated through peripheral neural structures or circulatory factors or by local autoregulation, which is metabolic or myogenic. Metabolic autoregulation occurs in response to local metabolic needs and is mediated by decreased oxygen and build up of adenosine and potassium.³⁶ Myogenic autoregulation is mediated via transmural pressure and stretch-operated calcium channels.³⁷ The microcirculation is also affected by endothelial factors within blood vessels. The endothelium plays a major role in control of vasomotor tone and blood fluidity, lipid metabolism, and finally angiogenesis. The endothelium has been recognized as an active tissue responsible for elaborating both vasodilatory and vasoconstrictor substances. Endothelial cells respond to differences in intravascular pressure due to variations in the size of the lumen by releasing endothelium-derived relaxing factor.³⁸ Endothelium-derived relaxing factor produces active vasodilatation, and endothelin is a potent vasoconstrictor. Both compounds are released from the endothelial cells to regulate vascular flow. Endothelial cells can also release thromboxane A₂, prostacyclin, and molecules of thrombomodulin and heparan sulfate.

Pathophysiology

As described previously, Fuchs classified arterial disease according to the three arterial layers: intima, media, and adventitia. Several pathologic processes (atherosclerosis, intimal hyperplasia) originate from this intimal layer. Endothelial disruption produces thrombotic occlusion and embolization.⁴ The media consists of smooth muscle cells, fibroblasts, and elastic tissue. Atherosclerosis leads to loss of tissue integrity, and the media becomes chronic dilated in a diffuse (ectasia) or localized (aneurysm) pattern. The adventitia is involved in diffuse pathologic conditions (arteritis, Buerger's disease).

A classification system based on the underlying pathophysiological mechanism responsible for producing the ischemia would seem to be most appropriate as a rationale for determining treatment. The pathological processes that produce ischemia in any end organ (and the hand can be considered such an end organ) are emboli, "sludging" of blood in low-flow states, thrombosis, external compression, intimal proliferation progressing to occlusion (arteriosclerosis), and vasospasm.⁵

Emboli

Large emboli from the heart due to atrial fibrillation or myocardial infarction lodging at the bifurcation of the brachial artery are best managed by embolectomy by a vascular surgeon. However, smaller emboli or "micro-emboli" dislodged from an ulcerated atherosclerotic plaque in a large artery may lodge in the distal radial and ulnar arteries and digital arteries, and result in digital ulcerations or gangrene.

Trauma

Traumatic causes of ischemia can be occupational, iatrogenic, or secondary to an injury. Hypothenar hammer syndrome (HHS) first described by Van Rosen in 1934 is an uncommon cause of secondary Raynaud's phenomenon, and occurs mainly in patients who use the hypothenar part of their hand as a hammer.³⁹

Because of its anatomic configuration within Guyon's canal, the ulnar artery is particularly vulnerable to mechanical injury. The hook of the hamate bone presses against the superficial palmar branch of the ulnar artery in Guyon's canal, leading to the development of progressive periadventitial scarring, damage to the media, disruption of the internal elastic lamina, intimal damage, and subintimal hematoma of the ulnar artery. These events are postulated to be the pathophysiological mechanism whereby repetitive trauma causes thrombosis in competitive athletes (volleyball, karate, handball, and baseball).⁴⁰⁻⁴²

"Vibration white finger" or vibration-induced Raynaud's phenomenon is also related to repetitive trauma in workers who frequently use drills, jackhammers, and chainsaws. High-frequency vibration is assumed to affect the response of the sympathetic vasoconstrictor nerves and receptors, not only to mechanical- but also to thermal-induced pain.^{43,44}

Radial artery catheterization frequently results in radial artery thrombosis, although it is frequently asymptomatic because of communication between the radial and ulnar arterial systems. However, if the patient has an incomplete superficial palmar arch, distal ischemia may occur.²³ Cardiac catheterization via the brachial artery may result in thrombosis and distal emboli, with an incidence of approximately 0.6%.⁴⁵

Arteriovenous shunt operations in renal failure patients may also result in hand ischemia. The arteriovenous shunt may redirect a critical volume of blood flow away from the hand, resulting in a "steal" phenomenon producing severe motor and sensory deficits.^{46,47}

Systemic disease

Systemic disease may produce distal hand ischemia and/or Raynaud's symptoms, including connective tissue disease, vasculitis, malignancy, septicemia, arteriosclerosis, Buerger's disease, polycythemia, cryoglobulinemia, and chemical toxicity.¹⁵

Diagnosis/patient presentation

Evaluation

Evaluation of vascular competency should define the patient's vascular anatomy and function under stressed and unstressed conditions. Therefore, a combination of studies is needed. Most importantly, a complete history and physical examination is essential in establishing a diagnosis. Investigations including non-invasive or invasive vascular studies may be required for exact evaluation of the patient's status. The patient's symptoms and studies are carefully reviewed to identify those patients who require surgical intervention.

History and physical examination

A history of cold intolerance, Raynaud's phenomenon (Fig. 22.1), and frequency of ischemic pain is important, as is smoking history; occupation involving repetitive injury or vibration trauma, and systemic disease including diabetes, cardiac disease, arrhythmias, drug use, blood dyscrasias, and peripheral neurological abnormalities. Unilateral Raynaud's



Fig. 22.1 Triphasic color changes. (A) Fingers turn white. (B) Fingers turn purple.

symptoms are especially suspicious and are usually indicative of occlusive disease on the affected side.

McCabe *et al.* and Troum *et al.* developed a questionnaire that can be used to assess the severity of cold sensitivity and quantify the magnitude, duration, and frequency of vasospastic symptoms and their effect on function.^{48,49}

A thorough examination of the upper extremity for previous trauma, old scars or operative incisions, skin color, temperature, presence of digital ulcers, and motor and sensory evaluation of the three peripheral nerves should be routine. Observation of blood flow in the fingernails may help to diagnose ischemia due to connective tissue disease.^{25,50}

Palpation may detect an abnormal mass or thrill. The brachial, radial, and ulnar arterial pulses are also palpated. The Allen test allows rapid evaluation of the patency of radial and ulnar arterial inflow into the hand. A digital Allen test can occasionally be performed either by forcing blood out of the finger or by sequential compression of the digital arteries.^{51,52}

Color changes, ulcerations, and infections are evaluated. Non-healing ulcerations and/or impending gangrene associated with unilateral Raynaud's symptoms are presumptive evidence of thrombosis or embolism.^{25,53}

Diagnostic investigations

Non-invasive vascular examination includes measurement of fingertip temperatures, Doppler ultrasound, segmental arterial pressures, and capillaroscopy.

Capillaroscopy

The capillaries of the nail fold can be examined directly by specialized dynamic videophotometric capillaroscopy, which provides measurements of capillary diameter, red blood cell velocity, and total flow. It can be difficult to perform in 10–12% of individuals due to anomalous vessel orientation, varying length of capillary loops, hyperkeratotic skin, or dense pigmentation. Dynamic capillary videomicroscopy allows direct assessment of nutritional perfusion and arteriovenous shunting, and provides objective evidence of the effects of systemic disease on the microcirculation and objective confirmation of any improvement with medical intervention.²⁵

Ultrasound

The pencil Doppler probe can also be used to assess the patency of the distal radial and ulnar arteries at the wrist and the dorsal branch of the radial artery as it passes through the webspace, the superficial palmar arch, the common digital arteries, and each proper digital artery on the radial and ulnar aspects of each digit. Jones found the pencil Doppler probe to be the simplest, most informative technique providing precise determination of the patency of the arterial structures. Doppler evidence of occlusion of either the distal radial or ulnar arteries is one of the primary criteria for proceeding to invasive arteriography.^{1,5}

Segmental arterial pressures of the brachial artery at the elbow and the distal radial and ulnar arteries at the wrist may be measured with a pencil Doppler probe. A radial-brachial index (RBI) and a digital-brachial index (DBI) can be calculated with a value of ≤ 0.7 indicating that arterial outflow to the hand is decreased.⁵⁴

Duplex ultrasonography

A duplex ultrasonogram is non-invasive, repeatable, and can be used for follow-up investigation. Its most important advantage is presenting real-time blood flow information (Fig. 22.2).^{55,56}

Isolated cold stress testing

Cold stress testing was developed to provide an evaluation of the digital response to physiologic stress. Digital temperatures or digital plethysmography (pulse volume recordings) are measured before, during, and after application of a cold stress-immersion in cold water or a cold chamber at 4°C.⁵⁷ If the fall in digital temperature or drop in pulse volume recording can be partially ameliorated by a prior injection of local anesthetic, this implies that vasospasm is a likely mechanism for the ischemia.

Infrared thermography

Infrared thermography (IRT) provides a measure of the decreased skin temperature of patients with hand ischemia due to decreased superficial skin blood flow.⁴⁴ The advantage




Fig. 22.2 Duplex ultrasonogram.

of IRT is that it is non-invasive, easy to use and inexpensive (Fig. 22.3). However, it is influenced by the ambient temperature, and skin temperature itself does not reveal the condition of a blood vessel and cannot visualize the site of stenosis.

Angiography

Potential disadvantages of conventional angiography include bleeding, allergic response to the contrast media, and X-ray exposure. A major problem with invasive angiography is the vessel spasm induced by the contrast media (Fig. 22.4).^{23,56,58} This can be circumvented by performing angiography under a brachial plexus block or by preventing vasoconstriction by intra-arterial injection of 4 mg phentolamine.⁵⁹

Angiography defines the site and extent of thrombosis or occlusion of the distal radial and ulnar arteries and even the common digital and proper digital arteries.^{23,58,60} Jones⁵ has suggested some criteria for angiographic investigation of upper extremity ischemia as follows: (1) unilateral Raynaud's phenomenon; (2) progressive digital ulceration or gangrene despite good medical management; (3) recurrent digital ulceration; (4) Doppler evidence of occlusion of a major inflow artery; and (5) acute onset of ischemic symptoms.

Magnetic resonance and computed tomography angiography

More recently, high-resolution contrast-enhanced magnetic resonance (MR) angiography and computed tomography (CT) angiography continue to be refined to compete with conventional angiography.⁶¹ Even though enhanced MR angiography and CT angiography are non-invasive, the resolution still does not allow the same visualization of the digital arteries compared with conventional angiography. Currently, if the surgeon requires accurate visualization of the digital arteries, conventional angiography is still preferred (Fig. 22.5).




Fig. 22.3 Infrared thermography. (A) Normal temperature in the palm. (B) Ischemic fingers.



Fig. 22.4 Brachial angiography showing localized occlusion of the ulnar artery.



Fig. 22.5 Computed tomography angiography.

Hints and tips

Diagnostic approach

1. A history of Raynaud's phenomena is usually very diagnostic. Patients can bring digital photos of the color changes in their hands.
2. Thermal scan is a very easy tool for checking the temperature of various parts of the hand.
3. Even though arteriography is invasive, it is the most valuable investigation for detecting arterial abnormalities of the hand – obstruction, stenosis, ectasia, coiling, aneurysm, velocity of flow.
4. Occupational history is important for “vibration white finger”.

Patient selection

Acute ischemia

Acute arterial injury

Acute ischemia of the hand may occur following laceration of the brachial, radial, and ulnar arteries. Closed vascular injuries are often caused by high-energy trauma with accompanying fractures.⁶² High-energy trauma may cause hemorrhage, thrombosis, incomplete vessel injury with development of an aneurysm, compartment syndrome, or progressive thrombosis and distal embolization.⁶³ Specific injuries of the upper extremity that may result in ischemia of the hand include shoulder dislocation, posterior dislocation of the elbow, and supracondylar fracture of the humerus. Diagnosis is usually not difficult in patients with significant hemorrhage and distal ischemia. Undetected injury to non-critical vessels may result in a false aneurysm or formation of an arteriovenous fistula.⁶⁴ Thal described the indications for operative exploration.⁶⁵

Physical findings of a pulsatile hematoma, a thrill, an audible bruit, decreased peripheral pulses, or associated

neurologic deficits are very important, but the presence of a distal pulse is not reliable in the evaluation of vascular integrity (Box 22.2). Immediate diagnosis is crucial in patients with acute ischemia of the hand, and this has been accomplished most expeditiously with Doppler examination and angiography.

Arterial emboli

The heart is the most common origin for arterial emboli. Acute onset of pallor, pain, coolness, paresthesias, and pulselessness should lead to strong suspicion for embolism. Ischemia will produce muscle paralysis after an embolus proximal to the forearm muscles, but paralysis is not present in distal emboli. Segmental arterial pressures are helpful, and arteriography of the entire upper extremity will determine if there is a more proximal arterial source of emboli and also will help differentiate embolism from acute arterial thrombosis.⁶⁶

Iatrogenic injuries

- Cannulation of the radial artery
- Catheterization through the brachial artery
- Harvest of radial artery for coronary artery bypass
- Harvest of the radial forearm flap
- Drug injection injury
- Acquired arteriovenous fistula – for dialysis in renal failure.

Cannulation injury

Radial artery cannulation injuries have increased because of the increased frequency of arterial blood pressure monitoring. Repeated injury to the radial artery can cause acute thrombosis with distal embolization, pseudoaneurysm, and arteriovenous fistula. Because of concomitant endothelial injury in cannulation injuries of the radial artery, immediate resection of the involved segment and reconstruction with an arterial or vein graft is more effective than thrombectomy with small Fogarty catheters.

BOX 22.2 Signs of arterial injury

Hard signs

- Distal circulatory deficit
 - Ischemia
 - Absent or diminished pulses
- Bruit
- Expanding or pulsatile hematoma
- Arterial bleeding

Soft signs

- Small or moderate-sized hematoma
- Adjacent nerve injury
- Shock unexplained by other injuries
- Penetrating wound overlying course of major artery

(Reproduced with permission from Thal ER, Synder WH, Perry MO. Vascular injuries of the extremities. In: Rutherford RB (ed.). *Vascular surgery*, 4th edn. Philadelphia, PA: WB Saunders; 1995:713–735.)

Arterial injection injuries

Self-inflicted or inadvertent drug injection arterial injuries result in severe acute ischemia due to chemical endarteritis, arterial blockage by acid crystals, activation of the clotting cascade, and secondary vasospasm, which causes severe vasoconstriction and widespread thrombosis. Diagnostic modalities are the same as in other vascular injuries.⁶⁷

Acquired arteriovenous fistula

Arteriovenous fistulas may occur following trauma or infection but are usually created surgically to provide vascular access for patients undergoing hemodialysis.⁶⁸ End-to-end radial artery to cephalic vein anastomosis may result in both ischemic and neurological complications related to a “steal” phenomenon.⁶⁹ Side-to-side anastomosis (radiocephalic arteriovenous fistula) also may reduce digital blood flow to the thumb because of proximal shunting.⁷⁰ Dialysis access-associated “steal” syndrome occurs in 2–4% of surgically created arteriovenous fistulas.⁷¹ Diagnosis is usually obvious. For traumatic or post-injection fistulas, duplex sonogram imaging, technetium scanning, or MR angiography are diagnostic. Arteriography is usually not necessary unless embolization is selected as a treatment option.

Chronic ischemia

Arterial thrombosis

The ulnar artery is the most common site for thrombosis in the upper extremity. The anatomy of Guyon’s canal leaves the ulnar artery vulnerable at the hook of the hamate.⁵⁴

Repetitive trauma may damage the intima and cause hypothenar hammer syndrome. Ischemic pain or paresthesias in the ulnar two digits, color changes, and tenderness are the usual signs at presentation. Allen’s test will show poor inflow through the ulnar artery. Digital plethysmography (pulse volume recordings) quantifies the degree of compromised perfusion. Duplex sonogram or MR angiography will reveal occlusion of the ulnar artery. Arteriography may show the diagnostic “corkscrew” sign of hypothenar hammer syndrome due to alternating segmental stenoses.⁷²

Radial artery thrombosis occurs much less frequently compared to ulnar artery thrombosis. Ischemic pain and cold intolerance are confined to the thumb and index finger. Diagnostic modalities are similar to those described for ulnar artery thrombosis.

Vibration-induced “white finger syndrome” represents thrombosis of the digital arteries, and occurs most frequently in the index finger. A digital Allen test is helpful, but an ultrasonogram and angiography is diagnostic.⁴⁴

Aneurysm

Upper extremity aneurysms may be divided into two types. True aneurysms contain three layers of the arterial wall whereas a false aneurysm or pseudoaneurysm lacks endothelial cells. A true aneurysm occurs most frequently in areas of repetitive trauma or is related to atherosclerosis. A pseudoaneurysm is usually the result of a penetrating injury.

A painless, palpable mass is highly suspicious of an aneurysm but signs and symptoms of ischemia are very

uncommon. Rarely nerve compression may cause pain or sensory abnormalities. An aneurysm is readily identified by a Doppler duplex ultrasonogram. Arteriography defines the extent of involvement and allows for evaluation of collateral flow for preoperative planning.⁷³

Arteritis

Buerger’s disease

Buerger’s disease or thromboangiitis obliterans is an inflammatory disease of the small and medium-sized vessels of the upper and lower extremities.⁷⁴ Diagnosis is dependent on five criteria: (1) smoking history; (2) onset before 50 years of age; (3) arterial lesions below the knee; (4) upper limb involvement or migratory phlebitis; and (5) absence of atherosclerotic risk factors other than smoking. Surgical treatment by interposition or bypass vein grafting has been ineffective because the process occurs in the very distal vessels.

Connective tissue disorders

- Systemic sclerosis (scleroderma)
- Mixed connective tissue disease
- Systemic lupus erythematosus
- Wegner’s granulomatosis.

Ischemic symptoms in connective tissue disorders should be investigated with non-invasive modalities first, such as segmental arterial pressure measurements, pulse volume recordings, and cold stress testing. Angiography is necessary if surgery is contemplated.

Vasospastic disease

1. Primary Raynaud’s disease
2. Secondary Raynaud’s syndrome.

As described previously, the medical literature relevant to vasospastic disease or Raynaud’s syndrome is confusing and at times misleading. Koman²⁴ described the criteria of Raynaud’s disease and Raynaud’s phenomenon (Box 22.3, Table 22.1).

Vasospastic conditions are either defined as primary with absence of an identifiable etiology or secondary associated

BOX 22.3 Criteria defining Raynaud’s disease

- Characteristic triphasic digital color changes
- Bilateral hand movement
- Absence of occlusive disease
- Absence of gangrene or trophic changes (fingertip trophic findings permissible)
- Absence of identifiable systemic disease (e.g., collagen vascular disorder)
- Symptoms at least 2 year’s duration
- Female predominance

(Data from Dabich L, Bookstein JJ, Zweifler A, et al. Digital arteries in patients with scleroderma. Arteriographic and plethysmographic study. *Arch Intern Med.* 1972;130:708–714.)

Table 22.1 Raynaud's disease versus Raynaud syndrome

Characteristics	Disease	Syndrome
History		
Triphasic color change	Yes	Yes
Age >40	No	Yes
Progression rapid	No	Yes
Underlying disease	No	Yes
Female predominance	Frequent	Occasional
Physical examination		
Trophic findings (ulcer, gangrene)	Infrequent	Frequent
Abnormal Allen test	No	Common
Asymmetric findings	Infrequent	Frequent
Laboratory testing		
Blood chemistry	Normal	Frequently abnormal
Microangiography	Normal	Frequently abnormal
Angiography	Normal	Frequently abnormal
(Reproduced with permission from Koman LA, Ruch DS, Smith BP, et al. Vascular disorders. In: Green DP, Hotchkiss RN, Pederson WC (eds). <i>Green's Operative Hand Surgery</i> . New York, NY: Churchill Livingstone; 1999:2254–2302.)		

with an underlying cause. Based on this terminology, Raynaud's disease is primary and all other conditions are secondary.²⁵ The vessels in primary Raynaud's disease are not diseased, hence the prognosis is benign. Because the structure of the artery is normal, arterial reconstruction is not necessary, but occasionally patients who are refractory to medical treatment may be candidates for cervical sympathectomy or digital sympathectomy.

In comparison to primary Raynaud's disease, secondary Raynaud's syndrome has a more severe prognosis, which is primarily related to the severity of the underlying disease.¹⁵ Surgical treatment of the ischemia in secondary Raynaud's syndrome includes digital sympathectomy and arterial reconstruction.

Treatment

A detailed history, physical examination, and differential diagnosis are the first steps in the management of ischemia of the hand. An arteriogram is essential to evaluate the arterial system of the entire upper extremity from the aortic arch to the digital arteries. The aims of treatment are to restore blood flow to an ischemic limb, prevent thromboembolic complications, and preserve hand function by avoiding secondary muscle ischemia and necrosis through compartment syndrome.

Treatments are selected according to the cause of ischemia,²⁵ with options ranging from environmental modification to surgical intervention. Various pharmacologic agents can be used to counteract the effect of humoral factors on the muscular layers of the arterial wall in a conservative medical approach, whereas surgical intervention is directed at

interrupting the sympathetic innervation of the muscle layer or by physical dilatation of the obstructed lumen or by microsurgical reconstruction of the occluded lumen.

Non-surgical treatment

Environmental modification

Cessation of smoking, avoidance of cold exposure, and limitation of activities that precipitate symptoms are fundamental. Cigarette smoking increases vasoconstrictor tone and alters blood coagulability; both are detrimental to a patient with ischemic disease. Nicotine patches may be used because they do not impair nutritional blood flow.²⁵ It is important that patients are aware of the relationship between cold and emotional stress and the reflex vasospasm in their hands.⁵⁷ Most patients intuitively avoid these circumstances but should also be instructed in protective techniques.

Medical management

Pharmacological agents

Drug therapy is aimed at mitigating the sympathetic hyperactivity in vasospastic and occluded arteries. Topical nitroglycerine is a simple first-line treatment in an attempt to relieve the pain associated with digital ulcerations. Currently, calcium channel blockers are the optimal choice for vasospastic symptoms,⁷⁵ by preventing calcium influx in vascular smooth muscle cells, which, in turn, ameliorates sympathetically driven vasoconstriction. Nifedipine, 10–30 mg orally three times a day, or in a long-acting form (30–60 mg/day) sustained-release capsules once or twice a day is most commonly used.¹¹

Both tricyclic antidepressants and selective serotonin reuptake inhibitors have also proved efficacious in the treatment of chronic pain due to ischemia. However, some drugs that directly affect sympathetic tone (α -adrenergic antagonists) are often difficult for patients to tolerate due to their side effects.^{76,77} Local anesthetic blockade and intra-arterial vasodilators such as reserpine and guanethidine have been used systemically and by local injection, but long-term benefit has not been achieved.⁷⁸

For treatment of obstructive Raynaud's syndrome, vasodilator drugs that alter prostaglandin metabolism (prostaglandin E1, prostacyclin and its analogues), and rheologic agents (aspirin, pentoxifylline, piracetam) have been advocated.¹⁵ Some success has been reported with intra-arterial administration of prostaglandin E1, a potent vasodilator and inhibitor of platelet aggregation.⁷⁴

Recently, Van Beek *et al.* described a novel use for Botox (botulinum toxin A) in the management of vasospastic disorders.⁷⁵ Injection of botulinum toxin A into the hand appears to have a beneficial effect on intractable digital ulcerations and rest pain in patients with severe vasospastic disorders.⁷⁹

Thrombolytic therapy

Thrombolytic agents may be helpful for an embolic occlusion of a small vessel, especially if the agent is administered shortly after the acute embolic event. They can also be used preoperatively as an adjunct to vessel repair by lysing clot that is obscuring an underlying vascular abnormality (e.g.,

aneurysm), permitting the surgeon to plan reconstruction of the vessel abnormality.⁸⁰ Successful salvage of hand ischemia events has also been described with a combination of PGE1 and local fibrinolytic therapy with tissue plasminogen activator (rt-PA).⁸¹ Although some authors⁸² have doubted the benefit of fibrinolytic agents for treatment of a preformed thrombus in a small (0.82–1.5 mm) vessel, low-dose streptokinase has been shown to be clinically effective for a thrombus in the hand if the drug is administered locally as a continuous infusion within 36 h after the onset of symptoms.⁸³ Anticoagulation using intravenous heparin to prevent the propagation of thromboemboli and permit early lysis of thrombotic arterial occlusions should be instituted intraoperatively.^{84–86} The role of low-molecular weight heparin in contrast to intravenous heparin has not been addressed thus far. McClinton made the following suggestions to increase the likelihood of success: initiate the infusion as soon as possible, be alert to the effect of systemic anticoagulation, and proceed with surgical exploration if no lysis occurs after the initial 2-h high-dose treatment. Steroids and iloprost (a prostacyclin analogue with potent vasodilating and anti-aggregant properties) have anecdotal results.^{84,86} The role of phosphodiesterase inhibitors such as sildenafil has yet to be determined.

Biofeedback

Biofeedback training to develop central nervous system control over peripheral autonomic functions involves instruction in techniques that allow the conscious regulation of autonomic body processes. This entails consciously increasing digital blood flow or temperature.⁸⁷

Biofeedback improves symptoms most effectively in patients with Raynaud's disease, vasospasm from non-neural or non-vascular etiology, and Raynaud's phenomenon with adequate collateral circulation. However, it tends not to be helpful in secondary vasospastic disease.

Thermal biofeedback is effective in primary vasospastic disease increasing digital flow, raising digital temperatures, and reducing cold-induced symptoms 2–3 years after treatment.^{15,25,88}

Surgical treatment

Surgical intervention should be considered in patients who are refractory to medical treatment. Surgical options include reconstruction or bypass of occluded vessels by microvascular reconstruction with or without vein grafts and/or modification of sympathetic tone.^{49,89–91} Sympathetic tone may be reduced by (1) proximal cervicothoracic sympathectomy, (2) Leriche sympathectomy (resection and ligation of a thrombosed or occluded arterial segment), (3) peripheral periarterial sympathectomy, and (4) new techniques in balloon angioplasty with periarterial sympathectomy.

Embolectomy

Emboli can be removed through a brachial arteriotomy and passage of catheters both proximally and distally. Number 2 or 3 Fr Fogarty catheters can usually be threaded all the way into the hand. If distal pulses do not return following restoration of flow, completion angiography is mandatory.

In high-flow arteriovenous malformations when emboli diminished the blood flow, initial attempts to preserve the fistula and relieve the vascular steal were aimed at reducing

flow across the fistula by narrowing the fistula with bands. Even with precise intraoperative monitoring, this technique failed because of a high rate of fistula thrombosis.⁹² Berman *et al.*^{93,94} reported successful distal revascularization–interval ligation in more than 90% of patients.

Sympathectomy

When medical management has failed to control rest pain, or there is impending infarction of digits, or non-healing of ischemic ulcerations, digital artery sympathectomy is indicated.

Most of the sympathetic nerves in the upper extremity emerge from the spinal cord with the ventral roots of the second and third thoracic nerves⁹⁵ and are widely dispersed in the brachial plexus to the forearm and hand.^{90,96} Cervical sympathectomy has a long history in the treatment of secondary vasospasm, but has currently lost favor because it has a high relapse rate and is essentially of no benefit in connective tissue disease.^{15,95} Pick⁹⁶ first noted in his dissections of the sympathetic nervous system that some of the sympathetic nerves bypass the sympathetic trunk and pass first with proximal somatic nerves and then in the periarterial adventitia to the digits. Failure of cervical sympathectomy for upper extremity vasospastic disease may be due to branches that bypass the cervicothoracic sympathetic trunk and are not interrupted during the operative procedure of cervical sympathectomy.^{90,91}

Sympathetic nerve branches pass from the peripheral nerves to adjacent arteries at intervals along the extremity and travel in the perivascular tissue including the large and easily identifiable nerve of Henle. This nerve accompanies the ulnar artery along its course from forearm to the hand, supplying several large segments to the ulnar artery.⁹⁷ Pick⁹⁶ identified individual sympathetic nerve branches to the arterial structures from the wrist to the digits, providing a basis for the current approach to surgical sympathectomy of the hand and digits.⁹⁸ This anatomic concept has provided the basis for two types of peripheral sympathectomy.

Leriche sympathectomy (arteriectomy)

Leriche advocated excision and ligation of the thrombosed or diseased arterial segment to improve collateral circulation and interrupt the vasomotor disturbance. If there is adequate collateral flow, excision of a thrombosed arterial segment without reconstruction interrupts sympathetic control over the distal vessels and reduces vasospasm. Several surgeons determine intraoperatively whether adequate collateral flow exists (e.g., after excision of a segment of ulnar artery) by measuring digital arterial pressures.^{54,88,99} Zook *et al.*¹⁰⁰ have applied the Leriche sympathectomy concept to the digits by excising segments of occluded digital arteries when digital artery bypass was not possible.

Periarterial sympathectomy

Flatt⁹⁰ first introduced the concept of a sympathectomy at the digital level to apply its effect more distally in the extremity. Surgical stripping of the adventitia from arteries to interrupt the sympathetic innervation to the smooth muscle in the vessel media has been tried in situations of acute vasospasm following trauma or during microsurgery. However, this

technique may be ineffective because of the vasoconstrictive effect on the smooth muscle by humoral factors, including catecholamines encountered in ischemic conditions.

By directly removing the sympathetic nerve input from the arteries, it is possible to block alternative sympathetic pathways or receptor upregulation. Flatt divided connections carrying sympathetic nerve fibers between the digital nerve and digital artery by stripping a 3–4 mm long segment of adventitia from the common digital artery; eight patients had variable relief of their symptoms. Wilgis^{10,91} extended this surgical dissection to include a 2 cm segment of the common and proper digital arteries and used preoperative anesthetic blockade to predict which patients would benefit from the procedure. Both Flatt and Wilgis noted symptomatic relief in patients with primary vasospastic disease but did not achieve consistently good results in patients with connective tissue diseases.

Jones¹⁰¹ introduced a more radical digital sympathectomy, with an extended digital sympathectomy for patients with connective tissue disease both to interrupt the sympathetic fibers and to remove fibrous tissue that encircles and compresses the arteries. Both the radial and ulnar arteries at the wrist are exposed and stripped over a 3 cm distance. The incision for the ulnar artery is extended into the palm in an inverted J-shaped fashion so that the entire ulnar artery and superficial palmar arch can be stripped of adventitia and sympathetic nerve fibers. The common and proper digital arteries are stripped from their origin to the base of the fingers, but not as far as the proximal interphalangeal joint, under the operating microscope. If the thumb and index finger are involved, the dorsal branch of the radial artery¹⁰² is stripped from the anatomic snuffbox to the origin of the deep palmar arch. The high incidence of ulnar artery occlusion has been previously mentioned in connective tissue disorders. In such patients, if there is sufficient distal arterial run-off, microsurgical bypass grafting from the proximal ulnar artery to the superficial palmar arch or common digital arteries can be performed.^{15,101,103} Koman *et al.*¹⁰⁴ demonstrated that sympathectomy can increase the percentage of nutritional blood flow with resultant healing of ulcers and gangrene.

The authors suggest that two different sympathectomy procedures should be considered depending on the severity of the disease: In a limited digital sympathectomy, adventitia is stripped from the radial and ulnar digital arteries and common digital arteries (Video 22.1 ▶). In an extended, radical digital sympathectomy, adventitia is stripped from the radial and ulnar arteries, the common digital arteries and the proper digital arteries (Figs. 22.6 & 22.7).¹⁰⁵ Long-term follow up of peripheral sympathectomy was reported recently.¹⁰⁶

Because of the myogenic nature of the spasm, treatment may not just be directed towards the autonomic nervous system. The principle of mechanical dilatation is based on the observation of Bard,¹⁰⁷ who noticed that a vessel in a state of tonic contraction may respond by reflex dilatation when mechanical dilatation is applied. Vessel constriction should not be treated by physical dilatation until the nature of the lesion has been determined, intimal damage with or without thrombosis has been excluded, and if pharmacologic treatment has been ineffective. A closed technique may be tried initially in which heparinized saline solution is injected under pressure between occluding vascular clamps. An arteriotomy may be required and the vessel dilated with a small Fogarty catheter.

Clinical tips

Periarterial sympathectomy

1. A palmar incision along a skin crease will result in a less prominent scar and less contracture postoperatively.
2. Two step incisions along the horizontal palmar crease are sufficient to expose the common digital arteries.
3. The entire superficial palmar arch can be exposed through a longitudinal palmar crease incision.
4. The vena comitantes may also be removed with the periarterial adventitia, but it may result in postoperative edema of the hand.
5. Periarterial sympathectomy is routinely performed on both the radial and ulnar arteries at the wrist level and the second, third, and fourth common digital arteries in primary Raynaud's disease. However, sympathectomy of the proper digital arteries may also be necessary for "vibration white finger" disease and systemic sclerosis.

Arterial reconstruction

For small partial arterial injuries, closure in a transverse direction prevents narrowing of the lumen. Even with significant (up to 60%) arterial narrowing after transverse closure, flow is not affected.¹⁰⁸ A vein patch can be used to close a more extensive partial injury.^{65,88} Sharp arterial transections can often be repaired end-to-end if the vessel ends are mobilized sufficiently. More extensive untidy arterial injuries commonly require a reversed vein graft interposed between the proximal and distal arterial ends. The cephalic, basilic, distal greater saphenous, and distal lesser saphenous veins are used most frequently. Some 10–30% more length of vein than is estimated, is harvested and then the vein graft is reversed or the valves incised. For axillary and brachial arterial injuries, the greater saphenous vein is preferred.^{64,65} A local forearm vein can be used for distal brachial, radial, and ulnar artery repairs when the extremity has not sustained significant additional soft-tissue trauma. If forearm trauma precludes use of a local vein graft, leg or dorsal foot veins are used.⁶⁴

Arterial reconstruction for symptomatic thrombosis or occlusion can be managed by ligation alone, excision with end-to-end repair, or excision and interposition grafting. Surgical indications include (1) absence of an alternative arterial inflow, (2) two or more levels of occlusion that compromise potential collateral flow, (3) thrombosis extending beyond the origins of the common digital vessels, and (4) incomplete deep and superficial arches. The major indication for arterial reconstruction is inadequate perfusion with a DBI of <0.7; if an appropriate risk–benefit ratio exists, arterial reconstruction should be performed.²⁵

Surgical techniques include:

1. *In situ* and non-reversed vein grafts
2. Interposition reversed vein grafts
3. Interposition arterial grafts (Video 22.2 ▶)
4. Arterialization of venous flow
5. Free omental transfer.

The goal of arterial reconstruction is to increase digital blood flow and restore nutritional flow. Successful arterial





Fig. 22.6 Limited digital sympathectomy: (A) Preoperative. (B) Operative view. (C) Schematic drawing. (D) Postoperative view.




Fig. 22.7 Radical digital sympathectomy: **(A)** Radical sympathectomy of common and proper digital arteries in the palm and digits. **(B)** Schematic drawing of radical digital sympathectomy.

reconstruction in patients with underlying collagen vascular disease increases total digital blood flow and nutritional flow, diminishes symptoms, and promotes healing of ulcers.¹⁰⁹ Regardless of the etiology, the level and extent of occlusion, the adequacy of collateral flow, and any component of sympathetic overactivity obviously influence the results of reconstruction for arterial thrombosis and occlusion.

Jones advocated that if by stringent clinical and angiographic criteria, segmental thrombosis or occlusions are identified in the distal radial and/or ulnar arteries and the superficial palmar arch, and if adequate distal “run-off” can be demonstrated in the common digital arteries, microsurgical revascularization should be considered in patients with symptomatic hand ischemia unresponsive to medical management.⁵ Jones described four basic vein graft configurations that have evolved for revascularization of the hand, and this classification may be helpful in planning surgery.¹

For short segmental occlusions or thrombosis of the ulnar artery in Guyon’s canal, end-to-end anastomosis of a vein

graft or arterial graft from the ulnar artery in the distal forearm to the distal ulnar artery just proximal to the superficial palmar arch is classified as a type I configuration.

Occlusion of the distal radial artery is much rarer in comparison to ulnar artery occlusion. End-to-end anastomosis of a vein graft or arterial graft from the distal radial artery in the forearm to the deep palmar arch or princeps pollicis artery in the thumb-index webspace is classified as a type II configuration.

If the superficial palmar arch is involved but the common digital arteries are spared, reconstruction of the superficial palmar arch may become necessary with end-to-end anastomosis of the vein or arterial graft to the ulnar artery in the distal forearm and end-to-side anastomoses of the common digital arteries to the interposition vein graft. This type III configuration is commonly required in systemic disease manifest by secondary Raynaud’s disease. In this situation, a deep inferior epigastric arterial graft may be more useful than a vein graft. The deep inferior epigastric artery has numerous

branches that can be used to reconstruct a new palmar arch with end-to-end anastomoses to the common digital arteries. End-to-end anastomoses are easier to perform compared with end-to-side anastomoses if an interposition vein graft is used which may also cause turbulent flow.

There are other technical advantages to using an autologous deep inferior epigastric artery graft. The size match between the inflow ulnar artery and the proximal epigastric artery is excellent.¹¹⁰ The deep inferior epigastric artery tapers as it gives off branches and the size of these distal branches is a close match for anastomoses to the common digital arteries (Fig. 22.8).

In a type IV configuration, two interposition vein grafts or two deep inferior epigastric artery grafts are used to revascularize the superficial palmar arch or common digital arteries from the distal ulnar artery and the deep palmar arch or princeps pollicis artery from the distal radial artery.¹¹¹

In the Wake Forest classification of occlusive/vasospastic/vaso-occlusive disease (Table 22.2), Koman *et al.* recommended that arterial reconstruction is indicated in patients with refractory symptoms and inadequate collateral circulation (groups IIB and IIIB), and should be individualized in groups IIA and IIIA.²⁴

Clinical tips

Interposition vessel grafts

1. Volar wrist veins are very useful for interposition grafts for the proper digital arteries.
2. The deep inferior epigastric artery (DIEA) is a good source for superficial palmar arch and ulnar artery obstruction. The vessel diameters of the DIEA are a good match for the proximal ulnar artery and distal palmar arch. Branches of the DIEA are also a good match for the common digital arteries.
3. The cephalic vein is a useful donor vein for radial artery obstruction. It can be harvested through the same incision. The radial artery graft is placed superficial to the abductor pollicis longus (APL), extensor pollicis brevis (EPB), and extensor pollicis longus (EPL) tendons to prevent the compression of the graft by these tendons.
4. Distal anastomoses into the digital arteries are very challenging in the ischemic hand because of the obliterated artery. The intima of the artery is markedly thickened in secondary Raynaud's syndrome.
5. Graft anastomoses should be performed into healthy recipient vessels with good inflow and a normal appearing intima.
6. The hand and wrist should be immobilized in a short arm splint for at least 1 week.

Aneurysms

Treatment options include: (1) resection and ligation¹¹²; (2) excision of the damaged wall and "patch" grafting; (3) resection with end-to-end repair; and (4) resection with an interposition graft, depending on collateral flow and vasomotor tone.¹¹³

Table 22.2 Wake Forest classification of occlusive/vasospastic/vaso-occlusive disease

Group	Etiology	Comments
I	Raynaud's disease	Idiopathic
II	Raynaud's syndrome	Collagen vascular disease
A	Adequate circulation	
B	Inadequate circulation	
III	Secondary vasospasm/occlusive disease	Vascular injury
A	Adequate circulation	Occlusion/embolus
B	Inadequate circulation	
IV	Secondary vasospasm	Non-vascular injury Nerve/bone/soft tissue damage
(Reproduced with permission from Koman LA, Ruch DS, Smith BP, et al. Vascular disorders. In: Green DP, Hotchkiss RN, Pederson WC, eds. <i>Green's operative hand surgery</i> . New York: Churchill Livingstone; 1999:2254–2302.)		

Early excision of true or false aneurysms of the radial or ulnar arteries is strongly advocated to prevent distal embolization. An intraoperative Digital/Brachial Artery Index less than 0.7 after aneurysm excision indicates the need for arterial reconstruction.⁵⁴ Postoperative care and surgical outcomes are similar to those after reconstruction of ulnar artery thrombosis (Fig. 22.9).

Mycotic aneurysms are secondary to hematogenous or local bacterial infection that weakens the vessel wall and virtually all are now due to intravenous drug abuse.⁷³ Infection producing a soft-tissue swelling overlying an artery should be evaluated for the possibility of a false aneurysm to avoid an ill-advised incision and drainage procedure. If clinical examination is not conclusive, duplex scanning should be diagnostic. Excision and ligation of the artery are preferred if the feeding vessel is not critical to limb survival, otherwise excision and vein bypass around the infected area will restore arterial inflow.

Balloon angioplasty for stenotic lesions

Ahn applied the technique of balloon angioplasty to treating patients with secondary Raynaud's syndrome who had an arterial stenosis of their radial and ulnar arteries diagnosed by arteriography.¹¹⁴ After adventitial stripping of the affected radial and ulnar arteries, palmar arch, and common digital arteries, vessel dilatation was performed using a percutaneous transluminal coronary angioplasty balloon catheter. The balloon was inserted through a branch of the ulnar artery and advanced from the main artery through Guyon's canal, into the palmar arch and common digital arteries. Sequential dilatation of any stenotic segment was performed by inflation of the balloon to 6 atmospheres for 40 seconds.

Balloon catheter dilatation is a useful adjunct procedure and may potentiate the effects of digital sympathectomy. The technique can also be used for incomplete arterial occlusions up to 15 cm in length and may eliminate the need for interposition vein grafts (Fig. 22.10).






Fig. 22.8 Arterial graft using deep inferior epigastric artery (DIEA). **(A)** Occluded ulnar artery. **(B)** DIEA graft. **(C)** DIEA graft anastomosed between the ulnar artery and palmar arch. **(D)** Schematic drawing of the ulnar artery to the superficial palmar arch reconstruction.




Fig. 22.9 Ulnar artery aneurysm treated by resection and interpositional vein graft. (A) Aneurysm. (B) Resection. (C) Interpositional vein graft.

Other surgical options

Surgeons have investigated alternative options to salvage severely ischemic limbs when standard arterial bypass procedures are not possible. Two salvage procedures for impending digital loss are reversal of blood flow through the upper extremity veins and vascularized omental transfer to the dorsum of the hand.

King *et al.*¹¹⁵ reported arterialization of the venous system of the upper limb based on *in situ* vein bypass. *In situ* vein bypass is a standard vascular surgery technique that involves complete exposure of the chosen vein and ligation of all its branches. A small valvulotome is used to divide each half of the bicuspid valves in the vein all the way to the metacarpal heads distally. The vein is then anastomosed to a proximal artery (usually end-to-end to the brachial artery), shunting arterial blood through the vein into the hand. Patients are heparinized after this procedure. Pederson has used the concept of reverse venous flow to improve vascularity in severe hand ischemia. He anastomosed the distal portion of either the radial or ulnar artery to suitable hand veins, thereby creating a reverse-flow situation in an attempt to improve capillary perfusion. He reported his personal experience in

over 20 cases, and showed significant improvement in pain and ulceration after the procedure.^{116,117}

The recipient vein is prepared by removing the valves at the level of the metacarpal necks. The cephalic vein is well suited for this procedure because it has great interconnections with the dorsal venous system of the hand, which potentially allows for a single proximal anastomosis. Arterial branches are then ligated and the proximal end-to-side anastomosis is performed. Postoperative thrombosis and swelling of the limb may result.

A new blood supply can be supplied indirectly to the hand, by a second technique. A free omental flap is harvested and placed beneath the dorsal skin of the forearm and hand, and the superior gastro-epiploic artery and vein anastomosed to the brachial artery and cephalic vein at the elbow.^{116,117}

Treatment algorithm

All patients with chronic ischemia of the hand should obviously be treated pharmacologically with topical nitroglycerin, calcium channel blockers, vasodilators, and possibly botulinum toxin.⁷⁵ Patients with ischemic pain often follow an intractable course and surgical intervention is frequently




Fig. 22.10 Balloon angioplasty. (A) Ballooning of stenotic ulnar artery. (B) Ballooning of the palmar arch.

inevitable. Established gangrene, osteomyelitis, and septic arthritis usually require a digital amputation. Amputations are effective in relieving patients' pain, for which they are very grateful.

Arteriography, MR angiography or duplex ultrasound will allow delineation of the exact site and extent of any stenosis or complete occlusion, and assist in surgical planning. Indications for arteriography with the intent of surgical revascularization include the following:

- unilateral Raynaud's phenomenon;
- progressive digital ulceration or gangrene despite good medical management;
- recurrent digital ulceration; and
- Doppler evidence of occlusion of a major artery.⁵

Specific indications for surgical intervention in patients with chronic ischemia of the hand have been suggested.^{5,101} Options for surgical intervention include digital sympathectomy, balloon angioplasty, and microsurgical revascularization using interposition vein grafts or arterial grafts. In some patients these procedures can be combined.

In a patient with Raynaud's phenomenon unresponsive to pharmacological treatment, if angiography reveals no evidence of occlusion of the main inflow radial and ulnar arteries and satisfactory visualization of the three common digital arteries, digital sympathectomy should be considered.^{101,106}

If angiography reveals stenosis or occlusion of the radial or ulnar arteries over a distance of <3 cm, balloon angioplasty may be considered so that expansion of the vessel lumen may increase digital blood flow. Balloon angioplasty can also be combined with radical sympathectomy.

If angiography demonstrates segmental occlusions of the main inflow radial and/or ulnar arteries but there is satisfactory "run-off" in the common digital arteries, microsurgical revascularization of the superficial palmar arch from the ulnar artery and much less frequently microsurgical revascularization of the deep palmar arch from the radial artery can be considered.

Despite more complicated harvesting, a deep inferior epigastric artery graft may allow end-to-end anastomoses of the branches of the arterial graft to the common digital arteries, whereas an interposition vein graft requires end-to-side anastomoses. However, the more extensive the involvement of the ulnar or radial arteries, the more likely that an interposition vein graft rather than an interposition arterial graft is required.¹¹⁴

If the symptoms of chronic ischemia are localized to a single finger and angiography reveals a discrete segment of occlusion of a proper digital artery, resection of the segment of proper digital artery and reconstruction with an interposition vein graft or arterial graft may occasionally be considered (Fig. 22.11).¹¹⁸ Balloon angioplasty of a stenotic common digital artery or proper digital artery is very difficult and may result in vessel rupture.¹¹⁴

Clinical tips

Management strategy

1. Medication with calcium channel blockers is acceptable in both primary Raynaud's disease and secondary Raynaud's syndrome. However, patients with secondary Raynaud's syndrome usually need periarterial sympathectomy or vascular reconstruction.
2. Balloon angioplasty is useful in selected cases of stenosis and short occluded segments.
3. Arterial reconstruction with interposition grafts in Raynaud's syndrome may be performed earlier than before the appearance of gangrene of the fingers.
4. Amputation of gangrenous fingertips should be conservative to preserve the length and shape of fingers in women. Small ulcers may heal spontaneously after improvement in vascular inflow.
5. Ischemic pain usually improves after appropriate surgery to increase blood flow.

Postoperative care

After microsurgical revascularization procedures, a single bolus of heparin (1000–2400 IU, intravenous push) is administered immediately before the microsurgical clamps







Fig. 22.11 Proper digital artery reconstruction with reverse vein graft. (A) Preoperative. (B) Angiogram showing occlusion of the proper digital arteries to the middle finger. (C) Occlusion of the ulnar digital artery. (D) Resection and interposition vein graft. (E) Postoperative.

are removed and either heparin is maintained for 7 days, or dextran 40 is administered intravenously at 25 cc/h for 5 days. If there is extensive intimal damage or vascular compromise, full heparinization and conversion to Coumadin is advisable.

A bulky hand and forearm dressing with a dorsal plaster of Paris splint is applied with the hand in a functional position. A drain is left in place for 12–36 h. Circulation to the fingertips is assessed every hour for 6 h and then every 4 h for 24 h. Critical arterial reconstructions are monitored in the same way as replantations. Changes in color and capillary refill; temperature monitoring (loss of $>2^{\circ}\text{C}$ in 1 h); pencil Doppler monitoring or pulse oximetry can be used. If sedation is required, chlorpromazine (25 mg orally three times daily) is prescribed. The patient obviously discontinues smoking and avoids caffeine consumption. The patient is discharged home on aspirin 81 mg daily and continued for up to 3 months.

Sutures are removed at 10–14 days postoperatively. The hand is protected for 2–6 weeks in a lightweight splint and the patient is instructed to avoid any trauma to the surgical site. Some residual cold sensitivity, soreness, pillar-type palm pain, and ulnar nerve irritability are expected. Return to work is based on job type after 6–12 weeks, no athletic or work restrictions are necessary if the patient is asymptomatic.

Outcomes, prognosis, and complications

Complications after surgical intervention for ischemia of the hand include impaired healing of the incision, dehiscence, infection, stiffness of the fingers, and specifically after microsurgical revascularization, thrombosis of the anastomoses.

After digital sympathectomy, patients usually report improvement in their symptoms of pain and cold tolerance, reduction in the frequency and severity of Raynaud's episodes, and healing of digital ulcers.¹⁰¹

Microsurgical revascularization increases distal arterial perfusion, reduces symptoms of ischemic pain, promotes healing of ulcers, and prevents progression to gangrene in hands without adequate collateral circulation.¹⁰¹ Koman *et al.* have demonstrated that this is due to an increase in the ratio of nutritional to total flow without increasing total microvascular perfusion within digits.¹⁰⁴ Patency rates of 80–90% can be expected of interposition vein grafts for hypothenar hammer syndrome, but thrombosis of the grafts can occur and symptoms return in longer follow-up. Of 106 interposition vein graft reconstructions of the ulnar artery, 87 (82%) remained patent.^{40,99,119–122}

The prognosis for patients with chronic ischemia of their hands depends on the etiology, the severity, the response to treatment, and progression of the underlying condition.^{101,123} Prognosis seems to be worse in patients with diabetes and

renal vascular disease. Hartzell *et al.* reported that long-term follow-up of 27 patients revealed that while digital sympathectomy healed digital ulcers and decreased the number of ulcers in vasospastic disease in autoimmune patients, the efficacy was much lower in patients with vasospasm secondary to atherosclerosis. This might explain why the prognosis is worse in patients with underlying diabetes. Patients with chronic ischemia of their hands due to scleroderma show improvement after digital sympathectomy and microsurgical revascularization, but because of progression of the underlying disease, there is a significant recurrence of digital ulcers 2 years after surgery.²¹ Therefore, these procedures should be considered palliative rather than curative. Since digital sympathectomy and microsurgical revascularization cannot usually be repeated, recurrence of digital ulcerations may ultimately require amputations. Jones¹⁰¹ has suggested that the hand be considered an “end organ” just like the heart, brain, and kidneys and therefore hand ischemia may reflect similar pathology in these other organs.

Secondary procedures

Secondary procedures after digital sympathectomy or microsurgical revascularization are rare because of the postoperative scarring from the original operation. Revision surgeries at the same location are usually not advised. Digital amputation or even ray amputation would be a last option should the ischemia progress.

Future directions

Occlusive/thrombotic disease of the inflow ulnar and radial arteries to the hand will still be managed by excision of the occluded or thrombosed segment and interposition vein or arterial grafting. Technically proficient hand surgeons may be inclined to utilize the same excision and grafting of an occluded segment of the proper digital arteries in affected fingers. However, the newer technique of balloon angioplasty may eliminate the necessity for interposition vein or arterial grafting within the fingers themselves.

Even though there are anecdotal reports of the successful use of botulinum toxin and fat grafting for vasospastic conditions causing ischemia of the hand, more rigorous randomized trials will be necessary in the future. Finally, newer pharmacologic agents may be developed to treat Raynaud's phenomenon, but digital sympathectomy may still be indicated for those patients with increasing frequency and increasing severity of their Raynaud's symptoms. The results of digital sympathectomy in patients with connective tissue disorders will only be palliative and dependent on the progression of the underlying disease.



Access the complete reference list online at

<http://www.expertconsult.com>

3. Jones NF, Emerson ET. Interposition vein graft configurations for microsurgical revascularization of the ischemic hand. *Tech Hand Up Extrem Surg.* 1999;3:121–130. Despite the various causes of upper extremity ischemia, the presenting symptoms are usually predictable. These symptoms constitute acute ischemia, digital ulcers, and gangrene, Raynaud's phenomena, or claudication with exercise. For segmental arterial occlusive diseases in selected patients, microsurgical revascularization with bypass vein grafts may be effective. This study reviews such cases that are bypassable with vein grafts, and proposes a classification system for distal upper extremity bypass vein grafts.
7. Jones NF. Acute and chronic ischemia of the hand: pathophysiology, treatment, and prognosis. *J Hand Surg Am.* 1991;16:1074–1083. Fifty patients with acute and chronic ischemia of the hand were investigated using various methods over 4 years. For many causes of the ischemia, medical management with emergent intra-arterial streptokinase, heparin, or dextran was used, along with nifedipine and pentoxifylline in chronic cases. Surgical treatment such as stellate ganglion blocks, microsurgical revascularization, and digital sympathectomy was used. Eighteen patients underwent amputation due to end-stage gangrene, and long-term follow-up revealed 20% incidence of recurrent digital ulcerations.
12. Wilgis EF. Evaluation and treatment of chronic digital ischemia. *Ann Surg.* 1981;193:693–698. Forty-two patients were evaluated and treated for chronic digital ischemia. Manifestations of pain, severe cold intolerance and occasional tip ulceration were seen despite conservative treatment of vasodilators, tobacco abstinence, and beta-blockers. Direct microvascular reconstruction, thermal biofeedback, and digital sympathectomy were performed with improvement in 70% of patients.
21. Jones NF, Imbriglia JE, Steen VD, et al. Surgery for scleroderma of the hand. *J Hand Surg Am.* 1987;12:391–400. Out of 813 consecutive patients with scleroderma, 31 underwent one or more surgical procedures. Raynaud's phenomenon and digital tip ulcerations were controlled with vasodilators and meticulous local wound care. Frank gangrene was usually managed conservatively until autoamputation, but 23 digital amputations had to be performed. Digital sympathectomy and micro-revascularization were performed in selected patients. Arthrodesis was performed in patients with severe digital contractures.
25. Fazan VP, Borges CT, Da Silva JH, et al. Superficial palmar arch: an arterial diameter study. *J Anat.* 2004;204:307–311. Symptomatic vascular disorders of the upper extremity interfere with health-related quality of life, diminish function, and have a negative impact on patients and society. Although less prevalent than ischemic lesions of the lower extremity, heart, or brain, upper extremity vascular morbidity is a significant social burden. Aberrant microvascular flow secondary to acute or chronic trauma, congenital deformity, systemic processes, or genetic influences affect over 10% of the general population and 20–30% of premenopausal women. Pain, cold intolerance, numbness, ulceration, or gangrene can result from these vascular insufficiencies or incompetencies. Abnormal perfusion may occur secondary to congenital or acquired events that affect vascular structures, vascular function, or both. Vascular insufficiency occurs due to blood flow compromise with decreased cellular perfusion and resultant cell damage, cellular injury, and pain. Various approaches to diagnosis and management of vascular disorders based on physiologic factors are covered.
60. Kim YH, Ng SW, Seo HS, et al. Classification of Raynaud's disease based on angiographic features. *J Plast Reconstr Aesthet Surg.* 2011;64:1503–1511. We analyzed the angiographic features of the arterial supply of the hand at three levels: (1) radial or ulnar, (2) palmar arch and common digital, and (3) digital vessels. Subsequent surgical interventions were tailored according to disease types, and these included combinations of: digital sympathectomy, balloon angioplasty, and end-to-end interposition venous or arterial grafting. We classified Raynaud's disease into six types: type I and II involve the radial or ulnar arteries. Type I (27.3%) showed complete occlusion, while type II (26.2%) involved partial occlusion. Type IIIa (27.1%) showed tortuous, narrowed or stenosed common digital and digital vessels. Type IIIb (1.4%) is a subset which involved the digital vessel of the index finger related to exposure to prolonged vibration. Type IV and V showed global involvement from the main to digital vessels. Type IV (13.7%) showed diffused tortuosity, narrowing, and stenosis. Type V (4.3%) is the most severe, with paucity of vessels and very scant flow. Nearly half (47%) of the patients had associated systemic disease. This new classification provides objective and valuable information for decision-making regarding choice of surgical procedures for the treatment of patients with Raynaud's disease that had failed conservative therapy.
79. Neumeister MW. Botulinum toxin type A in the treatment of Raynaud's phenomenon. *J Hand Surg Am.* 2010;35:2085–2092. Raynaud's patients were injected with 50 to 100 units of onabotulinumtoxin A to improve perfusion of the digits. An institutional review board-approved retrospective review was undertaken to analyze outcomes. Laser Doppler scans were performed before and after injection to quantitatively measure perfusion. A total of 14 men and 19 women with Raynaud's phenomenon were injected with onabotulinumtoxin. Botulinum toxin appears to improve perfusion of the hand after direct injection around the neurovascular bundles. Further investigations are warranted to identify the exact mode of action in relieving vasospasm and alleviating pain.
90. Flatt AE. Digital artery sympathectomy. *J Hand Surg Am.* 1980;5:550–556.
91. Wilgis EF. Digital sympathectomy for vascular insufficiency. *Hand Clin.* 1985;1:361–367.
101. Jones NF. Ischemia of the hand in systemic disease. The potential role of microsurgical revascularization and digital sympathectomy. *Clin Plast Surg.* 1989;16:547–556.
103. Jones NF, Raynor SC, Medsger TA. Microsurgical revascularisation of the hand in scleroderma. *Br J Plast Surg.* 1987;40:264–269.
104. Koman LA, Smith BP, Pollock FE Jr, et al. The microcirculatory effects of peripheral sympathectomy. *J Hand Surg Am.* 1995;20:709–717.
106. Murata K, Omokawa S, Kobata Y, et al. Long-term follow-up of peripheral sympathectomy for chronic digital ischemia. *J Hand Surg Eur Vol.* 2012;37:788–793. This study investigates long-term clinical results (>10 years) of periarterial sympathectomy in chronic ischemic digits compared with intermediate-term results (3 years). Periarterial sympathectomy via the palm and volar wrist was carried out on 11 hands of seven patients with digital ischemia but no gangrene or severe ulceration. The periarterial sympathectomy via the palm and wrist could prevent long-term aggravation of symptoms of chronic digital ischemia when combined with adequate postoperative drug therapy.
109. Savvidou C, Tsai TM. Long-term results of arterial sympathectomy and artery reconstruction with vein bypass technique as a salvage procedure for severe digital ischemia. *Ann Plast Surg.* 2013;70:168–171. The aim of this study is to present a combined treatment of arterial sympathectomy and artery reconstruction with vein bypass technique in patients with severe digital ischemia. In all, 22 patients representing 53 digits received treatment during a 15-year period. Skin color and trophic changes including ulcers, necrosis, and amputation; pain level according to the visual analog scale; and functional assessment based on the disabilities of the arm, shoulder, and hand questionnaire were recorded. Based on the results of this study, vascular reconstruction combined with sympathectomy may be indicated on an individualized basis for patients with digital ischemia. This procedure can lead to healing of skin trophic changes, diminution of pain, avoidance of amputation, and long-term improvement in life quality.
111. Masden DL, Seruya M, Higgins JP. A systematic review of the outcomes of distal upper extremity bypass surgery with arterial and venous conduits. *J Hand Surg Am.* 2012;37:2362–2367. The aim of the authors was to conduct a systematic review of literature evaluating efficacy of venous and arterial grafts for distal upper extremity bypass surgery. Manual review produced 42 studies based on inclusion criteria of reported distal upper extremity bypass surgery, complete information on graft type used, examined patency of reconstruction, and described method for determining patency. In 145 patients, 152 grafts were performed for upper extremity revascularization, including 120 grafts for revascularization of distal ulnar artery circulation, 31 for distal radial artery circulation, and one for both distal ulnar and radial artery occlusions. Overall patency rate was 87% at an average follow-up of 34 months. This review showed a high patency rate and clinical efficacy of distal upper extremity bypass surgery with a mean follow-up of almost 3 years. There may be a benefit of using arterial versus venous conduits, although further examination is needed given the small number of arterial reconstructions reported.
123. Hartzell TL, Makhni EC, Sampson C. Long-term results of periarterial sympathectomy. *J Hand Surg Am.* 2009;34:1454–1460.

References

- Raynaud M. *Local Asphyxia and Symmetrical Gangrene of Extremities*. Paris: Rignoux; 1862.
- Lewis T. Experiments relating to the peripheral mechanism involved in spasmodic arrest of the circulation in the fingers, a variety of Raynaud's disease. *Heart*. 1929;15:7–101.
- Jones NF, Emerson ET. Interposition vein graft configurations for microsurgical revascularization of the ischemic hand. *Tech Hand Up Extrem Surg*. 1999;3:121–130. *Despite the various causes of upper extremity ischemia, the presenting symptoms are usually predictable. These symptoms constitute acute ischemia, digital ulcers, and gangrene, Raynaud's phenomena, or claudication with exercise. For segmental arterial occlusive diseases in selected patients, microsurgical revascularization with bypass vein grafts may be effective. This study reviews such cases that are bypassable with vein grafts, and proposes a classification system for distal upper extremity bypass vein grafts.*
- Kallenberg CG. Early detection of connective tissue disease in patients with Raynaud's phenomenon. *Rheum Dis Clin North Am*. 1990;16:11–30.
- Marcus S, Weiner SR, Suzuki SM, et al. Raynaud's syndrome. Using a range of therapies to help patients. *Postgrad Med*. 1991;89:171–182.
- Fuchs JC. The pathology of upper-extremity arterial disease. *Hand Clin*. 1993;9:1–4.
- Jones NF. Acute and chronic ischemia of the hand: pathophysiology, treatment, and prognosis. *J Hand Surg Am*. 1991;16:1074–1083. *Fifty patients with acute and chronic ischemia of the hand were investigated using various methods over 4 years. For many causes of the ischemia, medical management with emergent intra-arterial streptokinase, heparin, or dextran was used, along with nifedipine and pentoxifylline in chronic cases. Surgical treatment such as stellate ganglion blocks, microsurgical revascularization, and digital sympathectomy was used. Eighteen patients underwent amputation due to end-stage gangrene, and long-term follow-up revealed 20% incidence of recurrent digital ulcerations.*
- Landry GJ, Edwards JM, Porter JM. Current management of Raynaud's syndrome. *Adv Surg*. 1996;30:333–347.
- Miller LM, Morgan RF. Vasospastic disorders. Etiology, recognition, and treatment. *Hand Clin*. 1993;9:171–187.
- Seibold JR, Allegar NE. The treatment of Raynaud's phenomenon. *Clin Dermatol*. 1994;12:317–321.
- Ward WA, Van Moore A. Management of finger ulcers in scleroderma. *J Hand Surg Am*. 1995;20:868–872.
- Wilgis EF. Evaluation and treatment of chronic digital ischemia. *Ann Surg*. 1981;193:693–698. *Forty-two patients were evaluated and treated for chronic digital ischemia. Manifestations of pain, severe cold intolerance and occasional tip ulceration were seen despite conservative treatment of vasodilators, tobacco abstinence, and beta-blockers. Direct microvascular reconstruction, thermal biofeedback, and digital sympathectomy were performed with improvement in 70% of patients.*
- Belch J. Raynaud's phenomenon. *Cardiovasc Res*. 1997;33:25–30.
- Allen EV, Brown GE. Raynaud's phenomenon: a practical approach. *Am Fam Phys*. 1932;47:823–829.
- Merritt WH. Comprehensive management of Raynaud's syndrome. *Clin Plast Surg*. 1997;24:133–159.
- Blunt RJ, Porter JM. Raynaud syndrome. *Semin Arthritis Rheum*. 1981;10:282–308.
- Priollet P, Vayssairat M, Housset E. How to classify Raynaud's phenomenon. Long-term follow-up study of 73 cases. *Am J Med*. 1987;83:494–498.
- Porter JM, Rivers SP, Anderson CJ, et al. Evaluation and management of patients with Raynaud's syndrome. *Am J Surg*. 1981;142:183–189.
- Given KS, Puckett CL, Kleinert HE. Ulnar artery thrombosis. *Plast Reconstr Surg*. 1978;61:405–411.
- Dabich L, Bookstein JJ, Zweifler A, et al. Digital arteries in patients with scleroderma. Arteriographic and plethysmographic study. *Arch Intern Med*. 1972;130:708–714.
- Jones NF, Imbriglia JE, Steen VD, et al. Surgery for scleroderma of the hand. *J Hand Surg Am*. 1987;12:391–400. *Out of 813 consecutive patients with scleroderma, 31 underwent one or more surgical procedures. Raynaud's phenomenon and digital tip ulcerations were controlled with vasodilators and meticulous local wound care. Frank gangrene was usually managed conservatively until autoamputation, but 23 digital amputations had to be performed. Digital sympathectomy and micro-revascularization were performed in selected patients. Arthrodesis was performed in patients with severe digital contractures.*
- Coleman SS, Anson BJ. Arterial patterns in the hand based upon a study of 650 specimens. *Surg Gynecol Obstet*. 1961;113:409–424.
- Gellman H, Botte MJ, Shankwiler J, et al. Arterial patterns of the deep and superficial palmar arches. *Clin Orthop Relat Res*. 2001;383:41–46.
- Koman LA, Ruch DS, Smith BP, et al. Vascular disorders. In: Green DP, Hotchkiss RN, Pederson WC, eds. *Green's Operative Hand Surgery*. New York, NY: Churchill Livingstone; 1999:2254–2302.
- Fazan VP, Borges CT, Da Silva JH, et al. Superficial palmar arch: an arterial diameter study. *J Anat*. 2004;204:307–311. *Symptomatic vascular disorders of the upper extremity interfere with health-related quality of life, diminish function, and have a negative impact on patients and society. Although less prevalent than ischemic lesions of the lower extremity, heart, or brain, upper extremity vascular morbidity is a significant social burden. Aberrant microvascular flow secondary to acute or chronic trauma, congenital deformity, systemic processes, or genetic influences affect over 10% of the general population and 20–30% of premenopausal women. Pain, cold intolerance, numbness, ulceration, or gangrene can result from these vascular insufficiencies or incompetencies. Abnormal perfusion may occur secondary to congenital or acquired events that affect vascular structures, vascular function, or both. Vascular insufficiency occurs due to blood flow compromise with decreased cellular perfusion and resultant cell damage, cellular injury, and pain. Various approaches to diagnosis and management of vascular disorders based on physiologic factors are covered.*
- Ger R, Abrahams P, Olson TR. *Essentials of Clinical Anatomy*. 2nd ed. New York, NY: Parthenon; 1996.
- Clemete CD. *Anatomy. A Regional Atlas of the Human Body*. 4th ed. Baltimore, MD: Williams & Wilkins; 1997.
- Agur AMR. *Grant's Atlas of Anatomy*. 9th ed. Baltimore, MD: Williams & Wilkins; 1991.
- Al-Turk M, Metcalf WK. A study of the superficial palmar arteries using the Doppler ultrasonic flowmeter. *J Anat*. 1984;138:27–32.
- Karlsson S, Niechajev IA. Arterial anatomy of the upper extremity. *Acta Radiol Diagn (Stockh)*. 1982;23:115–121.
- Ikedo A, Ugawa A, Kazihara Y, et al. Arterial patterns in the hand based on a three-dimensional analysis of 220 cadaver hands. *J Hand Surg Am*. 1988;13:501–509.
- Nystrom NA, Fedele G, Zoldos J. Intrinsic vascular anatomy of the hand. *Atlas Hand Clin*. 1998;3:1–32.
- Edwards EA. Organization of the small arteries of the hand and digits. *Am J Surg*. 1960;99:837–846.
- Strauch B, de Moura W. Arterial system of the fingers. *J Hand Surg Am*. 1990;15(1):148–154.
- Clemete CD. *Functional Anatomy of the Circulation to the Lower Extremities. The Circulation to the Skin*. Chicago, IL: Year Book Medical; 1971:64–95.
- Rich NM, Baugh JH, Hughes CW. Acute arterial injuries in Vietnam: 1,000 cases. *J Trauma*. 1970;10:359–369.
- Faber JE, Meininger GA. Selective interaction of alpha-adrenoceptors with myogenic regulation of microvascular smooth muscle. *Am J Physiol*. 1990;259:H1126–H1133.
- Cooke JP. Endothelium-derived factors and peripheral vascular disease. *Cardiovasc Clin*. 1992;22:3–17.
- Marie I, Herve F, Primard E, et al. Long-term follow-up of hypothenar hammer syndrome: a series of 47 patients. *Medicine (Baltimore)*. 2007;86:334–343.
- Koman LA, Urbaniak JR. Ulnar artery insufficiency: a guide to treatment. *J Hand Surg Am*. 1981;6:16–24.

41. Pineda CJ, Weisman MH, Bookstein JJ, et al. Hypothenar hammer syndrome. Form of reversible Raynaud's phenomenon. *Am J Med.* 1985;79:561–570.
42. Sharma R, Ladd W, Chaisson G, et al. Images in cardiovascular medicine: hypothenar hammer syndrome. *Circulation.* 2002;105:1615–1616.
43. Ekenvall L, Lindblad LE, Carlsson A, et al. Afferent and efferent nerve injury in vibration white fingers. *J Auton Nerv Syst.* 1988;24:261–266.
44. Ziegler S, Zoch C, Gschwandtner M, et al. Thermoregulation and rheological properties of blood in primary Raynaud's phenomenon and the vibration-induced white-finger syndrome. *Int Arch Occup Environ Health.* 2005;78:218–222.
45. Babu SC, Piccorelli GO, Shah PM, et al. Incidence and results of arterial complications among 16,350 patients undergoing cardiac catheterization. *J Vasc Surg.* 1989;10:113–116.
46. Schanzer H, Schwartz M, Harrington E, et al. Treatment of ischemia due to "steal" by arteriovenous fistula with distal artery ligation and revascularization. *J Vasc Surg.* 1988;7:770–773.
47. Odland MD, Kelly PH, Ney AL, et al. Management of dialysis-associated steal syndrome complicating upper extremity arteriovenous fistulas: use of intraoperative digital photoplethysmography. *Surgery.* 1991;110:664–669; discussion 9–70.
48. McCabe SJ, Mizgala C, Glickman L. The measurement of cold sensitivity of the hand. *J Hand Surg Am.* 1991;16:1037–1040.
49. Troum SJ, Smith TL, Koman LA, et al. Management of vasospastic disorders of the hand. *Clin Plast Surg.* 1997;24:121–132.
50. Sumner DS. Evaluation of acute and chronic ischemia of the upper extremity. In: Rutherford RB, ed. *Vascular Surgery.* 4th ed. Philadelphia, PA: WB Saunders; 1995:918–935.
51. Allen EV. Thromboangiitis obliterans: methods of diagnosis of chronic occlusive arterial lesions distal to the wrist with illustrative cases. *Am J Med Sci.* 1929;178:237–244.
52. Ruch DS, Aldridge M, Holden M, et al. Arterial reconstruction for radial artery occlusion. *J Hand Surg Am.* 2000;25:282–290.
53. Bouhoutsos J, Morris T, Martin P. Unilateral Raynaud's phenomenon in the hand and its significance. *Surgery.* 1977;82:547–551.
54. Zimmerman NB. Occlusive vascular disorders of the upper extremity. *Hand Clin.* 1993;9:139–150.
55. Schmidt WA, Wernicke D, Kiefer E, et al. Colour duplex sonography of finger arteries in vasculitis and in systemic sclerosis. *Ann Rheum Dis.* 2006;65:265–267.
56. Balas P, Katsogiannis A, Katsiotis P, et al. Comparative study of evaluation of digital arterial circulation by Doppler ultrasonic tracing and hand arteriography. *J Cardiovasc Surg (Torino).* 1980;21:455–462.
57. Koman LA, Nunley JA, Goldner JL, et al. Isolated cold stress testing in the assessment of symptoms in the upper extremity: preliminary communication. *J Hand Surg Am.* 1984;9:305–313.
58. Arneklo-Nobin B, Albrechtsson U, Eklof B, et al. Indications for angiography and its optimal performance in patients with Raynaud's phenomenon. *Cardiovasc Intervent Radiol.* 1985;8:174–179.
59. Vaughan RS, Lawrie BW, Sykes PJ. Use of intravenous regional sympathetic block in upper limb angiography. *Ann R Coll Surg Engl.* 1985;67:309–312.
60. Kim YH, Ng SW, Seo HS, et al. Classification of Raynaud's disease based on angiographic features. *J Plast Reconstr Aesthet Surg.* 2011;64:1503–1511. We analyzed the angiographic features of the arterial supply of the hand at three levels: (1) radial or ulnar, (2) palmar arch and common digital, and (3) digital vessels. Subsequent surgical interventions were tailored according to disease types, and these included combinations of: digital sympathectomy, balloon angioplasty, and end-to-end interposition venous or arterial grafting. We classified Raynaud's disease into six types: type I and II involve the radial or ulnar arteries. Type I (27.3%) showed complete occlusion, while type II (26.2%) involved partial occlusion. Type IIIa (27.1%) showed tortuous, narrowed or stenosed common digital and digital vessels. Type IIIb (1.4%) is a subset which involved the digital vessel of the index finger related to exposure to prolonged vibration. Type IV and V showed global involvement from the main to digital vessels. Type IV (13.7%) showed diffused tortuosity, narrowing, and stenosis. Type V (4.3%) is the most severe, with paucity of vessels and very scant flow. Nearly half (47%) of the patients had associated systemic disease. This new classification provides objective and valuable information for decision-making regarding choice of surgical procedures for the treatment of patients with Raynaud's disease that had failed conservative therapy.
61. Winterer JT, Ghanem N, Roth M, et al. Diagnosis of the hypothenar hammer syndrome by high-resolution contrast-enhanced MR angiography. *Eur Radiol.* 2002;12:2457–2462.
62. Fitridge RA, Raptis S, Miller JH, et al. Upper extremity arterial injuries: experience at the Royal Adelaide Hospital, 1969 to 1991. *J Vasc Surg.* 1994;20:941–946.
63. Raskin KB. Acute vascular injuries of the upper extremity. *Hand Clin.* 1993;9:115–130.
64. Hess AV. Treatment of vascular injuries from penetrating and nonpenetrating trauma. *Hand Clin.* 1999;15:249–259, viii.
65. Thal ER, Snyder WH, Perry MO. Vascular injuries of the extremities. In: Rutherford RB, ed. *Vascular Surgery.* 4th ed. Philadelphia, PA: WB Saunders; 1995:713–735.
66. Maiman MH, Bookstein JJ, Bernstein EF. Digital ischemia: angiographic differentiation of embolism from primary arterial disease. *AJR Am J Roentgenol.* 1981;137:1183–1187.
67. Silverman SH, Turner WW Jr. Intraarterial drug abuse: new treatment options. *J Vasc Surg.* 1991;14:111–116.
68. Rich NM, Hobson RW 2nd, Collins GJ Jr. Traumatic arteriovenous fistulas and false aneurysms: a review of 558 lesions. *Surgery.* 1975;78:817–828.
69. Redfern AB, Zimmerman NB. Neurologic and ischemic complications of upper extremity vascular access for dialysis. *J Hand Surg Am.* 1995;20:199–204.
70. Bussell JA, Abbott JA, Lim RC. A radial steal syndrome with arteriovenous fistula for hemodialysis. Studies in seven patients. *Ann Intern Med.* 1971;75:387–394.
71. Shemesh D, Mabjeesh NJ, Abramowitz HB. Management of dialysis access-associated steal syndrome: use of intraoperative duplex ultrasound scanning for optimal flow reduction. *J Vasc Surg.* 1999;30:193–195.
72. Hammond DC, Matloub HS, Yousif NJ, et al. The corkscrew sign in hypothenar hammer syndrome. *J Hand Surg [Br].* 1993;18:767–769.
73. McClinton MA. Tumors and aneurysms of the upper extremity. *Hand Clin.* 1993;9:151–169.
74. Shionoya S. Buerger's disease (thromboangiitis obliterans). In: Rutherford RB, ed. *Vascular Surgery.* 4th ed. Philadelphia, PA: WB Saunders; 1995:235–245.
75. Van Beek AL, Lim PK, Gear AJ, et al. Management of vasospastic disorders with botulinum toxin A. *Plast Reconstr Surg.* 2007;119:217–226.
76. Cardelli MB, Kleinsmith DM. Raynaud's phenomenon and disease. *Med Clin North Am.* 1989;73:1127–1141.
77. Czop C, Smith TL, Rauck R, et al. The pharmacologic approach to the painful hand. *Hand Clin.* 1996;12:633–642.
78. Arquilla B, Gupta R, Gernshiemer J, et al. Acute arterial spasm in an extremity caused by inadvertent intra-arterial injection successfully treated in the emergency department. *J Emerg Med.* 2000;19:139–143.
79. Neumeister MW. Botulinum toxin type A in the treatment of Raynaud's phenomenon. *J Hand Surg Am.* 2010;35:2085–2092. Raynaud's patients were injected with 50 to 100 units of onabotulinumtoxin A to improve perfusion of the digits. An institutional review board-approved retrospective review was undertaken to analyze outcomes. Laser Doppler scans were performed before and after injection to quantitatively measure perfusion. A total of 14 men and 19 women with Raynaud's phenomenon were injected with onabotulinumtoxin. Botulinum toxin appears to improve perfusion of the hand after direct injection around the neurovascular bundles. Further investigations are

- warranted to identify the exact mode of action in relieving vasospasm and alleviating pain.
80. Quinones-Baldrich WJ. Principles of thrombolytic therapy. In: Rutherford RB, ed. *Vascular Surgery*. 4th ed. Philadelphia, PA: WB Saunders; 1995:334–352.
 81. Hering J, Angelkort B. Acute ischemia of the hand after intra-arterial injection of flunitrazepam. Local combined fibrinolysis therapy in three cases. *Dtsch Med Wochenschr*. 2006;131:1377–1380.
 82. Cooney WP 3rd, Wilson MR, Wood MB. Intravascular fibrinolysis of small-vessel thrombosis. *J Hand Surg Am*. 1983;8:131–138.
 83. Jelalian C, Mehrhof A, Cohen IK, et al. Streptokinase in the treatment of acute arterial occlusion of the hand. *J Hand Surg Am*. 1985;10:534–538.
 84. Gouny P, Gaitz JP, Vayssairat M. Acute hand ischemia secondary to intraarterial buprenorphine injection: treatment with iloprost and dextran-40 – a case report. *Angiology*. 1999;50:605–606.
 85. Comerota AJ, White JV, Grosh JD. Intraoperative intra-arterial thrombolytic therapy for salvage of limbs in patients with distal arterial thrombosis. *Surg Gynecol Obstet*. 1989;169:283–289.
 86. Andreev A, Kavrakov T, Petkov D, et al. Severe acute hand ischemia following an accidental intraarterial drug injection, successfully treated with thrombolysis and intraarterial iloprost infusion. Case report. *Angiology*. 1995;46:963–967.
 87. Freedman RR. Physiological mechanisms of temperature biofeedback. *Biofeedback Self Regul*. 1991;16:95–115.
 88. Wilgis EF. *Vascular Injuries and Diseases of the Upper Limb*. Boston, MA: Little, Brown; 1983.
 89. el-Gammal TA, Blair WF. Digital periarterial sympathectomy for ischaemic digital pain and ulcers. *J Hand Surg [Br]*. 1991;16:382–385.
 90. Flatt AE. Digital artery sympathectomy. *J Hand Surg Am*. 1980;5:550–556.
 91. Wilgis EF. Digital sympathectomy for vascular insufficiency. *Hand Clin*. 1985;1:361–367.
 92. Katz S, Kohl RD. The treatment of hand ischemia by arterial ligation and upper extremity bypass after angioaccess surgery. *J Am Coll Surg*. 1996;183:239–242.
 93. Berman SS, Gentile AT, Glickman MH, et al. Distal revascularization-interval ligation for limb salvage and maintenance of dialysis access in ischemic steal syndrome. *J Vasc Surg*. 1997;26:393–402; discussion 4.
 94. Wixon CL, Mills JL Sr, Berman SS. Distal revascularization-interval ligation for maintenance of dialysis access and restoration of distal perfusion in ischemic steal syndrome. *Semin Vasc Surg*. 2000;13:77–82.
 95. Harris JP, Satchell PM, May J. Upper extremity sympathectomy. In: Rutherford RB, ed. *Vascular Surgery*. 4th ed. Philadelphia, PA: WB Saunders; 1995:1008–1016.
 96. Pick J. *The Autonomic Nervous System*. Philadelphia, PA: JB Lippincott; 1970.
 97. McCabe SJ, Kleinert JM. The nerve of Henle. *J Hand Surg Am*. 1990;15:784–788.
 98. Morgan RF, Reisman NR, Wilgis EF. Anatomic localization of sympathetic nerves in the hand. *J Hand Surg Am*. 1983;8:283–288.
 99. Zimmerman NB, Zimmerman SI, McClinton MA, et al. Long-term recovery following surgical treatment for ulnar artery occlusion. *J Hand Surg Am*. 1994;19:17–21.
 100. Zook EG, Kleinert HE, Van Beek AL. Treatment of the ischemic finger secondary to digital artery occlusion. *Plast Reconstr Surg*. 1978;62:229–234.
 101. Jones NF. Ischemia of the hand in systemic disease. The potential role of microsurgical revascularization and digital sympathectomy. *Clin Plast Surg*. 1989;16:547–556.
 102. Yee AM, Hotchkiss RN, Paget SA. Adventitial stripping: a digit saving procedure in refractory Raynaud's phenomenon. *J Rheumatol*. 1998;25:269–276.
 103. Jones NF, Raynor SC, Medsger TA. Microsurgical revascularisation of the hand in scleroderma. *Br J Plast Surg*. 1987;40:264–269.
 104. Koman LA, Smith BP, Pollock FE Jr, et al. The microcirculatory effects of peripheral sympathectomy. *J Hand Surg Am*. 1995;20:709–717.
 105. Rhee SW, Ahn HC, Choi MSS, et al. Digital sympathectomy for treatment of Raynaud's syndrome. *Korean Soc Plast Reconstr Surg*. 2005;032:479–484.
 106. Murata K, Omokawa S, Kobata Y, et al. Long-term follow-up of peripheral sympathectomy for chronic digital ischemia. *J Hand Surg Eur Vol*. 2012;37:788–793. This study investigates long-term clinical results (>10 years) of periarterial sympathectomy in chronic ischemic digits compared with intermediate-term results (3 years). Periarterial sympathectomy via the palm and volar wrist was carried out on 11 hands of seven patients with digital ischemia but no gangrene or severe ulceration. The periarterial sympathectomy via the palm and wrist could prevent long-term aggravation of symptoms of chronic digital ischemia when combined with adequate postoperative drug therapy.
 107. Bard PH. *Macleod's Physiology in Modern Medicine*. St. Louis, MO: CV Mosby; 1941.
 108. Pichora DR, Masear VR. Efficacy of direct repair to partial arterial lacerations. *J Hand Surg Am*. 1994;19(4):552–558.
 109. Savvidou C, Tsai TM. Long-term results of arterial sympathectomy and artery reconstruction with vein bypass technique as a salvage procedure for severe digital ischemia. *Ann Plast Surg*. 2013;70:168–171. The aim of this study is to present a combined treatment of arterial sympathectomy and artery reconstruction with vein bypass technique in patients with severe digital ischemia. In all, 22 patients representing 53 digits received treatment during a 15-year period. Skin color and trophic changes including ulcers, necrosis, and amputation; pain level according to the visual analog scale; and functional assessment based on the disabilities of the arm, shoulder, and hand questionnaire were recorded. Based on the results of this study, vascular reconstruction combined with sympathectomy may be indicated on an individualized basis for patients with digital ischemia. This procedure can lead to healing of skin trophic changes, diminution of pain, avoidance of amputation, and long-term improvement in life quality.
 110. Smith HE, Dirks M, Patterson RB. Hypothenar hammer syndrome: distal ulnar artery reconstruction with autologous inferior epigastric artery. *J Vasc Surg*. 2004;40:1238–1242.
 111. Masden DL, Seruya M, Higgins JP. A systematic review of the outcomes of distal upper extremity bypass surgery with arterial and venous conduits. *J Hand Surg Am*. 2012;37:2362–2367. The aim of the authors was to conduct a systematic review of literature evaluating efficacy of venous and arterial grafts for distal upper extremity bypass surgery. Manual review produced 42 studies based on inclusion criteria of reported distal upper extremity bypass surgery, complete information on graft type used, examined patency of reconstruction, and described method for determining patency. In 145 patients, 152 grafts were performed for upper extremity revascularization, including 120 grafts for revascularization of distal ulnar artery circulation, 31 for distal radial artery circulation, and one for both distal ulnar and radial artery occlusions. Overall patency rate was 87% at an average follow-up of 34 months. This review showed a high patency rate and clinical efficacy of distal upper extremity bypass surgery with a mean follow-up of almost 3 years. There may be a benefit of using arterial versus venous conduits, although further examination is needed given the small number of arterial reconstructions reported.
 112. Louis DS, Simon MA. Traumatic false aneurysms of the upper extremity. A diagnostic problem. *J Bone Joint Surg Am*. 1974;56:176–179.
 113. Green DP. True and false traumatic aneurysms in the hand. *J Bone Joint Surg Am*. 1973;55:120–128.
 114. Ahn HC, Choi MSS, Lee HM, et al. Balloon catheterization and digital artery sympathectomy for Raynaud's disease. In: American Society of Plastic Surgery, ed. *Plastic Surgery*. San Francisco, CA: ASPS; 2006:6–11.
 115. King TA, Marks J, Berrettoni BA, et al. Arteriovenous reversal for limb salvage in unreconstructable upper extremity arterial occlusive disease. *J Vasc Surg*. 1993;17:924–932; discussion 32–33.
 116. Pederson WC. Management of severe ischemia of the upper extremity. *Clin Plast Surg*. 1997;24:107–120.

117. Pederson WC. Revascularization of the chronically ischemic hand. *Hand Clin.* 1999;15:629–642.
118. Tomaino MM. Digital arterial occlusion in scleroderma: is there a role for digital arterial reconstruction? *J Hand Surg [Br]*. 2000;25:611–613.
119. De Monaco D, Fritsche E, Rigoni G, et al. Hypothenar hammer syndrome. Retrospective study of nine cases. *J Hand Surg [Br]*. 1999;24:731–734.
120. Ferris BL, Taylor LM Jr, Oyama K, et al. Hypothenar hammer syndrome: proposed etiology. *J Vasc Surg.* 2000;31:104–113.
121. Koman LA, Urbaniak JR. Ulnar artery thrombosis. *Hand Clin.* 1985;1:311–325.
122. Mehlhoff TL, Wood MB. Ulnar artery thrombosis and the role of interposition vein grafting: patency with microsurgical technique. *J Hand Surg Am.* 1991;16:274–278.
123. Hartzell TL, Makhni EC, Sampson C. Long-term results of periarterial sympathectomy. *J Hand Surg Am.* 2009;34:1454–1460.

23

Neuropathic pain in the upper extremity

Catherine Curtin

SYNOPSIS

- Pain is a common issue for those who care for people with disorders of the upper limb, ranging from mild musculoskeletal pain to complex regional pain syndrome.
- Neuropathic pain is often the cause of persistent surgical pain.
- Neuropathic pain is defined by the International Association for the Study of Pain (IASP) as pain caused by a lesion or disease of the somatosensory nervous system.

Introduction

Pain is a common issue for those who care for people with disorders of the upper limb, ranging from mild musculoskeletal pain to complex regional pain syndrome.¹ There is the “healthy pain” that protects the injured limb while the tissue heals. Then there is the persistent pain after surgery or trauma that continues long after the tissue has healed. This persistent pain becomes a pathologic process and is most commonly neuropathic in origin. Post-traumatic and post-surgical neuropathic pain will be the focus of this chapter.²

Neuropathic pain is defined by the International Association for the Study of Pain (IASP) as “pain caused by a lesion or disease of the somatosensory nervous system.”³ Neuropathic pain is seen in many clinical settings such as nerve compression and nerve injury. Perhaps the most frustrating presentation of neuropathic pain is the pain that occurs after a technically perfect surgery. Every surgeon wants better outcomes. Early recognition and treatment of neuropathic pain will improve outcomes in these challenging cases.

Pain and surgery have always been intertwined. From before the advent of anesthesia, surgeons strove to increase their speed to reduce their patients’ suffering. Dr. Mitchell described neuropathic pain in a book explaining his experience with nerve injuries treated during the Civil War.⁴ Throughout the treatise, he noted intense pain associated

with these nerve injuries and uses the term *causalgia* to explain this “burning pain”. Surgeons have continued to try and improve the treatment of nerve pain. We have changed techniques, medications, and added other treatments. The knowledge of neuropathic pain and its mechanisms has greatly expanded since Dr. Mitchell’s time, but to this day, neuropathic pain remains a challenging problem. This chapter will provide the reader with information on the diagnosis and treatments available for the common complaint of neuropathic pain.

Terminology

Before progressing too far into this topic, it is first important to understand some basic definitions of terminology used within the pain field. Below are the IASP definitions for common pain vocabulary.

1. **Allodynia:** pain due to a stimulus that does not normally provoke pain. Example: “It hurts when the wind blows on my arm.”
2. **Dysesthesia:** an unpleasant abnormal sensation. Example: “My arm feels like it is rubbed raw by sand paper when my shirt touches it.”
3. **Hyperalgesia:** increased pain from a stimulus that normally provokes pain. Example: “Even a small bump feels like a sledge hammer hit me.”

Another term to be clarified is complex regional pain syndrome (CRPS). CRPS represents a severe subset of patients who have neuropathic pain as well as other symptoms impacting the skin and tissues of the injured area. This term CRPS is often used inappropriately, resulting in confusion and fear associated with the diagnosis of CRPS. This confusion is likely due to two factors. First is that the terminology for CRPS has changed with increased understanding of the pathophysiology. Mitchell first named it “*causalgia*”, where he described patients with nerve injuries, burning pain, glossy skin, and changes in hair and nails. In 1946, this process was

renamed reflex sympathetic dystrophy.⁵ But as all cases did not seem to be sympathetically mediated, so a group of pain researchers again changed the taxonomy to complex regional pain syndrome in 1995.⁶ CRPS has been subdivided this into two groups – type 1 (no known nerve injury) and type 2 (known nerve injury). There remains controversy whether this subdivision of CRPS is useful, as some believe all CRPS is mediated by some type of nerve injury, whether it can be identified or not.⁷

The second issue with CRPS is that there is no test to confirm the diagnosis; CRPS is a diagnosis based on history and physical exam. All patients with CRPS must have pain disproportionate to the trauma. The patients must also have a constellation of other sudomotor symptoms to receive a diagnosis of CRPS. What symptoms make a diagnosis of CRPS has been debated in the pain field, further adding to the confusion.⁸ Table 23.1⁹ presents the list of physical exam findings required for a diagnosis for CRPS based upon a consensus meeting of pain researchers in Budapest. Fig. 23.1A,B shows two hands with typical physical exam findings seen in the setting of CRPS. One thing about CPRS is clear: this complication has a great negative impact on the patient’s quality of life.¹⁰

Table 23.1 Diagnostic criteria for complex regional pain syndrome (CRPS)	
Must report at least one symptom in three of the following categories:	Must display at least one sign* at time of evaluation in at least two of the following categories:
1. Sensory: Reports of hyperalgesia and/or allodynia	1. Sensory: Evidence of hyperalgesia (to pinprick) and/or allodynia (to light touch and/or deep somatic pressure and/or joint movement)
2. Vasomotor: Reports of temperature asymmetry and/or skin color changes and/or skin asymmetry	2. Vasomotor: Evidence of temperature asymmetry and/or skin color changes and/or asymmetry
3. Sudomotor/edema: Reports of edema and/or sweating changes and/or sweating asymmetry	3. Sudomotor/edema: Evidence of edema and/or sweating changes and/or sweating asymmetry
4. Motor/trophic: Reports of decreased range of motion and/or motor dysfunction (weakness, tremor, dystonia) and/or trophic changes (hair, nail, skin)	4. Motor/trophic: Evidence of decreased range of motion and/or motor dysfunction (weakness, tremor, dystonia) and/or trophic changes (hair, nail, skin)
*A sign is counted only if it is observed at time of diagnosis. (Reproduced with permission from Harden RN, Oaklander AL, Burton AW, et al. Complex regional pain syndrome: practical diagnostic and treatment guidelines. <i>Pain Med.</i> 2013;14:180–229.)	




Fig. 23.1 (A) Hand in patient with complex regional pain syndrome (CRPS): note the shiny skin and edema. (B) Hand in CRPS: note the subtle color changes.

Epidemiology

There are several anatomic reasons that the limbs are at particular risk for the development of neuropathic pain. Chronic pain after extremity injury occurs in up to 79% of patients having surgery for traumatic injury to the feet and hands.^{11–12} First, the upper limb is richly innervated, putting more nerves at risk of injury after trauma. Second, the nerves of the upper limb travel long distances crossing multiple joints with wide arcs of motion, so the nerves need to glide. Thus, trauma and scarring can tether a nerve resulting in repeated traction of the nerve. Finally, there are several tight areas along the course of the nerves, so an injured swollen nerve is at risk for secondary entrapments. All these anatomic characteristics of the

upper limb mean that injury can result in irritated painful nerves.¹³

Surgical trauma can be the inciting factor for chronic pain. The literature has noted that persistent pain occurs in 20–50% of surgical patients.¹⁴ Carpal tunnel has a 20% rate of persistent pain. The most common complication after trigger finger release and distal radius fractures is pain.^{15–16} The mechanism of post-surgical chronic pain is thought to be persistent firing of nerves injured at the time of surgery.² Every surgical incision cuts cutaneous nerves and for a subset of patients this injury results in chronic pain. The mystery is: Why do many patients develop peri-incisional numbness after surgery but a subset of patients develops neuropathic pain? Later in the chapter we will discuss risk factors associated with persistent post-surgical pain.

Although neuropathic pain is not uncommon after surgery, the incidence of post-surgical CRPS is fortunately rare. Post-surgical CRPS is a devastating complication, preventing return of function and often causing prolonged disability. A few upper limb surgeries are particularly at risk for CRPS. CRPS after distal radius fracture care is well described, occurring in 1–30% of patients^{17–19} CRPS has also been described after palmar fasciectomy with rates reported as high as 17%.²⁰ Occasionally the patient with the seemingly smallest of traumas will develop CRPS.

Early recognition and treatment of the patient with CRPS is critical, as anecdotal evidence suggests that early intervention improves outcomes.

Risk factors

Much effort has been devoted assessing the risk factors associated with developing neuropathic pain, with the goal of identifying those at risk prior to surgery. Pain is clearly a complex multifactorial process but some patient characteristics have repeatedly been associated with post-surgical pain development. In 2017, there is no definitive risk assessment for postoperative pain. Listed below are some of the factors that have data suggesting an association with pain after surgery.

Gender

The available evidence clearly shows that women and men have different pain experiences. Women are more at risk for developing chronic pain and CRPS.²¹ An overall epidemiologic study found CRPS incidence 4:1 women to men.²² Jellead looked prospectively at distal radius fractures treated with a cast and found 32% developed CRPS and that women had a 5.77 greater odds of being in the CRPS group.¹⁷ Sennwald found that 40% of women who had Dupuytren's release developed CRPS.²⁰ Overall, the data suggests women are at higher risk for pathologic pain processes and that surgeons should be aware of this heightened risk.^{23–24}

High preoperative pain

Multiple studies have found that the patients with high preoperative pain values are more at risk of severe acute postoperative pain, which puts them at risk for chronic pain.^{21,25–26}

Psychological factors

There are many studies looking to associate pre-existing psychological conditions with the development of neuropathic pain. These studies often have significant limitations and results have been mixed. The overall theory is that patients with increased psychological distress have higher concentrations of circulating catecholamines, which makes them more sensitized to pain. Two psychological factors commonly discussed in relation to development of pain after trauma/surgery are depression and pain catastrophizing.

Depression

Depression has long been thought to be associated with pain, and studies have shown correlations between depression and pain after surgery.^{27,28} However, for much of the literature, it is difficult to assess the directionality of this relationship – does the depression cause the pain or is the pain causing the depression? The literature is mixed on this question, but a pooling of the available data found enough evidence to support depression as a risk factor for chronic post-surgical pain.²⁹ There are short forms to assess for depression in the clinic. One example is the Patient Health Questionnaire (PHQ-9), which has only nine questions.³⁰

Pain catastrophizing (PC)

There is increasing evidence that PC may be one of the most important psychological factors associated with prolonged pain after surgery. PC is a cognitive style in which patients have a “set of exaggerated and ruminating negative cognitions and emotions during actual or perceived painful stimulation.”³¹ These patients feel helpless and say things like “this is the worst pain in the world.” The Pain Catastrophizing Scale has 13 questions and was developed to capture the PC traits.³² PC has been found to be associated with poorer outcomes after distal radius fracture.³³ PC has been shown in meta-analysis to be one of the strongest predictors of prolonged pain after knee arthroplasty.³⁴ PC can be addressed with cognitive-behavioral therapy and there is increased interest in this psychological trait as a potential target for “pre-habilitation” before surgery.

Immobilization

Immobilization is often required to protect healing tissue. However, immobilization is not a benign intervention, and there is increasing evidence that immobilization can contribute to neuropathic pain.³⁵ It makes intuitive sense that immobilization, which prevents nerve gliding in an inflamed tissue bed, is not ideal. A study putting healthy volunteers in a cast for a month found that the subjects developed some of the changes associated with CRPS.³⁶ Another study also found that those immobilized after surgery had increased inflammatory factors as well as trophic factors similar to CRPS.³⁷

Diagnosis

Localizing the pain generator can be challenging to providers, as the patient's perception of neuropathic pain often is not dermatomal. It is difficult to target interventions when the

patient reports, “the whole arm hurts.” Strategies to diagnose neuropathic pain and to localize pain generator(s) are presented below.

Patient history

There are several clues in the patient history to suggest a neuropathic component to the pain. The first is the pain quality. Neuropathic pain is often described as burning or shooting. However, neuropathic pain can also be described as dull or sore.^{38–40} Thus, pain quality can help diagnose but should not rule out neuropathic pain. Pain severity can also provide a clue. Severe pain without a clear cause can point to activation of the somatosensory nervous system. If the pain is out of proportion to the injury, a neuropathic component is suspected. Pain duration beyond the time that tissue has healed points to a pathologic pain process, often of neuropathic origin.²

Physical examination

Physical examination can help differentiate neuropathic from musculoskeletal pain. The examination can also help localize area(s) of nerve irritation that are contributing to the pain. First, the examination should begin with inspection. If the patient is uncomfortable, apprehensive, and distressed before the examination begins, this can suggest that the pain has become a pathologic process (Fig. 23.2). Next, the provider should assess for the physical signs associated with CRPS such as edema, shiny skin, and temperature changes (see Table 23.1). These same physical exam findings can be found in patients with neuropathic pain who do not meet the criteria for a diagnosis of CRPS. The presence of these trophic signs does suggest a neuropathic pain component.

After the patient has been inspected, the provider should begin with gentle palpation. Allodynia or pain to light touch suggests a neuropathic pain process. If light touch of the skin is painful or unpleasant, then the pain is not generated from a deeper musculoskeletal problem.

After surgery, patients can have persistent pain from a “scar neuroma”. These patients will have tenderness to light touch or manipulation localized over the scar. Often the scar



Fig. 23.3 Patient with a scar neuroma: note the tethered area was site of maximal tenderness.

will be tethered or depressed at the area of maximal tenderness (Fig. 23.3).

The provider should then perform a standard full upper extremity examination looking for other potential causes of the pain. There are several specific tests that will help with identifying areas of symptomatic nerve entrapments.

Clinical diagnostics

Specific tests in the physical examination

Motor examination If the patient can tolerate it, a focused motor examination can provide useful information. Nerve entrapment can result in subtle changes in strength. The maneuvers proposed by Hagert are useful for assessing nerve entrapments.⁴¹ This examination technique assesses bilateral muscle strength simultaneously. By testing bilateral muscle groups at the same time, the examiner can see subtle differences between the two sides, suggesting areas of nerve pathology.

Cold perception Patients with nerve injuries or entrapments will often have changes in perception of temperature and these changes can localize injured nerves. In clinic, a quick inexpensive way to assess cold perception is to place a piece of ice in the finger of an exam glove and test the patient's cold perception on various nerve distributions.

Tinel's sign The Tinel's sign has long been used to assess nerve pathology. It is easy and quick and can help localize areas of nerve compression. However, this test has low sensitivity/specificity and wide variability between providers.^{42,43} Thus Tinel's sign provides information but should be used as one small piece of a full physical exam.



Fig. 23.2 Woman with complex regional pain syndrome (CRPS): note the posture with which she holds her arm.

Clinical tips

Scratch collapse test This is a newer test that is a useful addition to the physical exam.^{44,45} For this technique, the patient is seated with upper arms at their sides and elbows at 90° of flexion. The patient is asked to resist as the examiner pushes medially on forearm (loading shoulder external rotation). The examiner then lightly scratches the skin *directly* over the area of the suspected nerve entrapment. Then the examiner immediately repeats the loading of the shoulder external rotation. If the patient's external rotation is weaker, i.e., "collapses", this is a positive test. This test is particularly useful for less common proximal nerve entrapments such as radial tunnel, pronator syndrome, and thoracic outlet. The scratch collapse test is one more tool to help localize an area of nerve pathology.

Diagnostic testing

Neuro-diagnostic testing Neuro-diagnostic studies are key diagnostic tests for assessing peripheral nerve pathology. These studies can assess for neuropathy, localize nerve compression, and exclude more proximal spinal pathology. After trauma, patients have swelling, which can result in painful nerve entrapments, such as carpal tunnel syndrome. Treating the nerve entrapment is a key part to treating the pain. However, it is important to understand the limitations of these studies. There are patients with symptomatic nerve entrapments with normal neuro-diagnostic tests.⁴⁶ This is particularly true for proximal nerve entrapments such as radial tunnel or thoracic outlet. Remember, a negative nerve study does *not* rule out entrapment. These tests, like many of the others, provide one more piece of information for consideration.

Ultrasound Ultrasound is being increasingly utilized in evaluating nerve pathology.^{47,48} Ultrasound is attractive as it is not painful, dynamic, and does not expose the patient to

radiation. Ultrasound can identify swelling and changes in nerve architecture. As the nerves become smaller, the utility of ultrasound decreases. At this time, the role of ultrasound in the diagnosis of nerve injury/entrapments in the upper limb is still evolving.

Magnetic resonance imaging (MRI) MRI technology continues to improve, resulting in more detailed imaging of the nerves. However, like ultrasound, as the nerves become smaller, the utility of the exam decreases. MRI neurogram is a technique specifically designed to image nerves and it can also provide information about the surrounding tissue (presence of ganglions, etc.).⁴⁹ MRI neurogram assesses T2-weighted images looking for increased signal that identify the area of nerve injury or entrapment.^{50,51} MRI neurogram is currently useful for looking at larger nerve lesions such as thoracic outlet and cubital tunnel (Fig. 23.4).

Hybrid imaging techniques such as positron emission tomography (PET)/MRI are new innovations that expand the information provided. In this technology, the patient undergoes a PET scan and MRI of the affected area. Then the anatomic images of the MRI and the biological marker images of the PET are overlapped, providing more detail on the pathologic process⁵² (Fig. 23.5).

Diagnostic blocks Diagnostic blocks with local anesthetic are the most important tool for identifying the area of pain generation. If a patient has significant pain relief after a block, then the pain generator is somewhere distal to the blocked nerve. Diagnostic blocks are also useful as blocking one nerve can unmask a second site of pain. These anesthetic blocks can be done by the surgeon or in collaboration with a pain medicine specialist. There are several steps, described below, that are needed to ensure the diagnostic block generates the most useful information.




Fig. 23.4 Magnetic resonance imaging of the ulnar nerve.




Fig. 23.5 Positron emission tomography (PET) magnetic resonance imaging (MRI) showing the merging of the bright PET signal on the anatomy of the MRI. (Courtesy of Sandip Biswal.)

Clinical tips

Diagnostic blocks

Provider education This is crucial if another provider is performing the block. The provider of the block needs to understand what results are useful to the surgeon.

1. First, only one nerve is to be blocked at a time. A “field block” or a brachial plexus block, which anesthetizes the whole arm, does not provide enough information on what particular nerve is generating the pain signals. If several nerves are involved, then sequential blocks separated by hours or days will allow the patient to assess the amount of pain generated by each nerve.
2. Second, the location of the block needs to be clearly documented. The surgeon needs to know where along the course of the nerve the block was placed. For example, a block of the ulnar nerve at the wrist or above the elbow will be testing very different potential pain generators.

Patient education The patient needs to understand that the primary goal of the block is to diagnose the pain generator not treat it. This means there is no expectation of prolonged pain relief after the injection. If the patient does not understand that the critical time is the first hour after the block, the patient may report the “block did not work” because the pain returned after the anesthetic wore off. During the block, the patient must also assess the distribution of numbness. This information provides quality control, ensuring the nerve of interest was blocked and its corresponding sensory distribution was numb.

Diagnostic block pearls

- Have the patient document the percentage of pain relief during the first hour after the block.
- Have the patient try the usually painful activities during the hour after the block and document the percentage of pain relief.

Perioperative treatment

There has been extensive work on the use of pharmaceuticals around the time of surgery to prevent the transition to a chronic pain process.

Pre-surgical

Preoperative administration of gabapentinoids (gabapentin and pregabalin) may reduce acute and chronic pain after surgery. Numerous studies assessing the impact of preoperative gabapentinoid administration on post-procedure pain have found these medications reduce opioid consumption and postoperative acute pain scores by as much as 50%.^{53–56} The studies suggest that higher preoperative doses are more effective (900 mg for gabapentin 300 mg for pregabalin).⁵⁷

Intraoperative

1. Preemptive neural blockade through use of local or regional anesthetic techniques can reduce the number of

patients who have chronic postoperative pain.^{58–61}

Blocking the nerves prior to incision prevents the bombardment of the spinal cord with pain signals and theoretically decreases the excitation of the nociceptive response.

2. Ketamine is a non-competitive *N*-methyl-D-aspartate (NMDA) glutamate receptor antagonist long used as a general anesthetic agent. Several studies and a systematic review found that ketamine was a helpful adjunct to the treatment of surgical pain especially for painful procedures.⁶² In addition, evidence found that ketamine decreased postoperative pain in chronic opioid users, a challenging patient population for pain management.^{63–64}

Post-surgical

Multimodal pain management should be implemented if the surgeon is concerned about a patient at risk for post-surgical pain problems. The theory of multimodal treatment is to use several different medications with separate mechanisms of action.

Post-injury treatment

Despite best preventative efforts, there will be patients who develop or present with neuropathic pain and the clinical focus then turns to treatment. This requires a multidisciplinary approach including therapy, pain specialists, and psychological support. The surgeon cannot manage all facets of care but should be able to direct their patient to the appropriate resources.

Psychological

Often patients with pain have concomitant psychological pathology including anxiety, depression, post-traumatic stress disorder, or pain catastrophizing. Psychological care should be included in the treatment plan for these patients. To this end, some medications used to treat psychological problems (tricyclic antidepressants and selective serotonin and norepinephrine reuptake inhibitors) can also treat neuropathic pain. Thus, communicating with the patient’s mental health provider can potentially optimize medications and allow for a more coordinated treatment plan.

In addition, several psychological interventions can help treat patients with chronic pain. These psychological treatments include mindfulness-based stress reduction, cognitive-behavioral therapy, meditation, pain education, and relaxation. These approaches often require multiple treatment sessions delivered individually or in classes.

Medication

Medications are a standard part of most pain treatment and several are effective for neuropathic pain. The administration of these anti-neuropathic pain medications differs from opioids, requiring more patience from the provider and patient. Anti-neuropathic medications compared to opioids require more time to have an analgesic effect. Also, anti-neuropathic medications often need to be started at a low and likely ineffective dose. This is because the higher, effective dose can have

intolerable side effects (sedation, dizziness), but slow titration allows these side effects to be significantly minimized. This need for patience must be explained at the outset or the patient will discard a medication that may provide pain relief.

The gabapentinoids (gabapentin and pregabalin) are very useful in the treatment of neuropathic pain. These medications appear to modulate voltage-gated calcium channels existing on presynaptic pain-carrying neurons in the dorsal horn of the spinal cord.⁶⁵ In studies of other neuropathic pain conditions, such as diabetic neuropathy and post-herpetic neuralgia, the number needed to treat for gabapentin ranged from 4 to 6½.⁶⁶ The primary issue with these medications are the cognitive side effects; however, these can be ameliorated by slow titration.

Tricyclic antidepressants (nortriptyline, desipramine) have been found in many trials to be effective in the treatment of neuropathic pain.⁶⁷ They are thought to work by central mechanisms of inhibition of noradrenaline and serotonin uptake, as well as NMDA receptor antagonism and sodium channel inhibition. They also have a lower number needed to treat than the gabapentinoids. However, these medications need to be carefully monitored due to their potential severe adverse effects including cardiac issues, especially at higher doses. The surgeon, may not be comfortable monitoring the titration of these medications and could consider starting at a low dose and initiating a referral to a pain physician for titration. In addition, if the patient has comorbid depression, the hand provider could discuss the patient with their mental health provider to see if switching to tricyclic antidepressants might be feasible.

Serotonin–norepinephrine reuptake inhibitors such as duloxetine (trade name: Cymbalta) have been found to be effective against neuropathic pain and these medications do not have the anti-cholinergic or cardiac side effects.⁶⁷

Physical modalities

These treatments have long been a central pillar to the treatment of neuropathic pain. Standard hand therapy is useful in the patient with neuropathic pain, especially in the acute injury time period. These treatments focus on decreasing edema, promoting nerve gliding, and improving range of motion. There are also additional interventions uniquely targeting the pathologic pathways that promote neuropathic pain. Neuropathic pain causes changes at every level of the somatosensory system. Neuropathic pain-specific physical modalities attempt to modulate not only the peripheral pain generators but also the central components of the brain and spinal cord. The therapists will focus on left/right identification, graded motor imagery exercises, and mirror therapy.^{68–70} Neuropathic physical treatments require a distinct approach with care to not overstimulate, using short duration and repetitive interventions.

Surgical treatment of pain

Surgeons are often hesitant to operate on pain with historic recommendations to avoid surgery as it risks “flaring” the pain. However, as time has progressed, it has become clear that if an injured or compressed nerve is contributing to pain, surgical intervention may be a critical part of the rehabilitation plan.

The key to operating on neuropathic pain is to proactively employ all the treatment options discussed earlier. These patients should have the perioperative, intraoperative and postoperative treatments planned before surgery is considered. Psychological support should be in place for those with concomitant anxiety or depression. Therapy must be available to help the patient through the post surgical rehabilitation. If a thoughtful multimodal strategy is used, the risks of worsening the pain can be significantly decreased, making the surgery’s risk–benefit ratio in the patient’s favor.^{71–73}

Neuromas

Painful neuromas can potentially be improved with surgical correction. If possible, the best treatment for neuromas is neuroma excision followed by reconstruction with nerve grafts.⁷⁴ Another technique for a painful neuroma is end-to-side coaptation of the injured nerve to a healthy nerve, which is particularly useful for digital neuromas. Both these techniques restore a path for injured axons to reconnect with their end organs.

However, pure sensory neuromas are often distal and reconstructing the nerve is not an option. For these cases, surgical correction of a neuroma is more about recreating the injury and then attempting to alter the post-injury course to result in a non-painful neuroma. The goal is to place the new injured nerve stump in a new low-stimulation environment. The microenvironment impacts the development of the neuroma and the surgeon can optimize the neuroma placement.⁷⁵

The literature on neuroma resection is limited and heterogeneous. A prospective study of 34 patients found that surgically treated neuromas in the upper limb resulted in a decrease of the mean visual analog scale score from 6.8 to 4.9 ($p < 0.01$).⁷²

Nerve compression

Nerve release is a common technique for the surgeon who cares for the upper limb. Carpal tunnel and cubital tunnel syndromes are known pain generators and easily recognized by providers. Other sites of nerve compression should be considered and treated when working with neuropathic pain of the upper limb. Radial tunnel, pronator syndrome, quadrangular space entrapment, and thoracic outlet all can be addressed surgically if conservative treatment fails.⁷⁶

Neuro-stimulation

For the patient who has failed other treatments, neuro-stimulation can give pain relief. Neuro-stimulation is thought to work by blocking pain signals via the “gate theory”. The gate theory posits that stimulation of the nerve with non-painful signals can close the “gate” preventing other painful signals from being processed.⁷⁷ Most of the information in this field is related to spinal cord stimulators, which can reduce pain by 50%.⁷⁸ Neuro-stimulation is an exciting area that is being transformed by emerging technology. The current available devices are limited by lead failure, lead migration, and limited locations to place the bulky power sources. As technology miniaturizes the power sources and eliminates the leads, there will be an increase of uses for nerve stimulators in the patient with neuropathic pain.

Future directions

Given the enormous costs to the patient, society, and the healthcare system, there is a large amount of interest in improving neuropathic pain. Interesting new avenues of research include the role of the immune system in neuropathic pain. Emerging evidence suggests that some pain may be mediated through autoimmune mechanisms.^{79–80} This link

may open up new avenues of treatment through immune modulators.

On a healthcare system level, pain has taken on increased importance. The Institute of Medicine recently released a report, *Relieving Pain in America: A Blueprint for Transforming Prevention, Care, Education, and Research*.⁸¹ This report highlighted the impact of pain and presented specific timelines and goals. This focused effort will continue to push us towards improved pain care.



Access the complete reference list online at

<http://www.expertconsult.com>

3. IASP website. <http://www.iasppain.org/Education/Content.aspx?ItemNumber=1698#Centralneropathicpain>.
9. Harden RN, Oaklander AL, Burton AW, et al. Complex regional pain syndrome: practical diagnostic and treatment guidelines. *Pain Med.* 2013;14:180–229. *This is a systematic review by experts in the field. It provides information on the diagnosis of CRPS. The article then reviews the evidence for potential treatment modalities including physical, pharmacological, and psychological interventions.*
26. Mehta SP, MacDermid JC, Richardson J, et al. Baseline pain intensity is a predictor of chronic pain in individuals with distal radius fracture. *J Orthop Sports Phys Ther.* 2015;45:119–127.
36. Terkelsen AJ, Bach FW, Jensen TS. Experimental forearm immobilization in humans induces cold and mechanical hyperalgesia. *Anesthesiology.* 2008;109:297–307. *This study took 27 healthy controls and placed them in a forearm cast for 4 weeks. After cast removal the subjects had transient symptoms similar to CRPS including changes in skin temperature, mechanosensitivity, and thermosensitivity.*
40. Mackey S, Carroll I, Emir B, et al. Sensory pain qualities in neuropathic pain. *J Pain.* 2012;13:58–63.
41. Hagert CG, Hagert E, Slutsky DJ. Manual muscle testing: a clinical examination technique for diagnosing focal neuropathies in the upper extremity. In: *Upper Extremity Nerve Repair: Tips and Techniques. A Master Skills Publication.* Rosemont, IL: American Society for Surgery of the Hand; 2008:451–466. *This text provides a detailed description of the manual muscle testing to assess for nerve injury. There is detailed information on the physical exam and anatomy. It reviews the diagnosis of less common nerve entrapments such as pronator and radial tunnel syndrome.*
53. Dauri M, Faria S, Gatti A, et al. Gabapentin and pregabalin for the acute post-operative pain management. A systematic-narrative review of the recent clinical evidences. *Curr Drug Targets.* 2009;10:716–733.
54. Tiippana EM, Hamunen K, Kontinen VK, et al. Do surgical patients benefit from perioperative gabapentin/pregabalin? A systematic review of efficacy and safety. *Anesth Analg.* 2007;104:1545–1556. *This systematic review of 22 studies found that perioperative gabapentin provided postoperative pain relief, reduced opioid use, and limited opioid side effects. They also found that the most common adverse effects of gabapentin were dizziness and sedation.*
57. Carroll I, Hah J, Mackey S, et al. Perioperative interventions to reduce chronic postsurgical pain. *J Reconstr Microsurg.* 2013;29:213–222. *This manuscript reviews in detail pre-surgical interventions to reduce pain. It provides a clear algorithm with drug dosages for the patient at risk for chronic pain.*
73. Dellon AL, Mackinnon SE. Treatment of the painful neuroma by neuroma resection and muscle implantation. *Plast Reconstr Surg.* 1986;77:427–438.
76. Hagert E, Hagert CG. Upper extremity nerve entrapments: the axillary and radial nerves – clinical diagnosis and surgical treatment. *Plast Reconstr Surg.* 2014;134:71–78.
81. Institute of Medicine (US) Committee on Advancing Pain Research, Care, and Education. *Relieving Pain in America: A Blueprint for Transforming Prevention, Care, Education, and Research.* Washington, DC: National Academies Press (US); 2011.

References

- Li Z, Smith BP, Tuohy C, et al. Complex regional pain syndrome after hand surgery. *Hand Clin.* 2010;26:281–289.
- Shipton E. Post-surgical neuropathic pain. *ANZ J Surg.* 2008;78:548–555.
- IASP website. <http://www.iasppain.org/Education/Content.aspx?ItemNumber=1698#Centralneropathicpain>.
- Mitchell SW, Morehouse GR, Keen W. *Gunshot Wounds and Other Injuries of Nerves*. Philadelphia, PA: J.B. Lippincott; 1864:100–106.
- Evans J. Reflex sympathetic dystrophy. *Surg Clin North Am.* 1946;26:780–790.
- Stanton-Hicks M, Jänig W, Hassenbusch S, et al. Reflex sympathetic dystrophy: changing concepts and taxonomy. *Pain.* 1995;63:127–133.
- Oaklander AL, Rissmiller JG, Gelman LB, et al. Evidence of focal small-fiber axonal degeneration in complex regional pain syndrome-I (reflex sympathetic dystrophy). *Pain.* 2006;120:235–243.
- Harden RN, Bruehl S, Stanton-Hicks M, et al. Proposed new diagnostic criteria for complex regional pain syndrome. *Pain Med.* 2007;6:326–331.
- Harden RN, Oaklander AL, Burton AW, et al. Complex regional pain syndrome: practical diagnostic and treatment guidelines. *Pain Med.* 2013;14:180–229. *This is a systematic review by experts in the field. It provides information on the diagnosis of CRPS. The article then reviews the evidence for potential treatment modalities including physical, pharmacological, and psychological interventions.*
- Galer BS, Henderson J, Perander J, et al. Course of symptoms and quality of life measurement in complex regional pain syndrome: a pilot survey. *J Pain Symptom Manage.* 2000;20:286–292.
- Ferreira RC, Sakata MA, Costa MT, et al. Long-term results of salvage surgery in severely injured feet. *Foot Ankle Int.* 2010;31:113–123.
- Richards T, Garvert DW, McDade E, et al. Chronic psychological and functional sequelae after emergent hand surgery. *J Hand Surg Am.* 2011;36:1663–1668.
- Bruxelle J, Travers V, Thiebaut JB. Occurrence and treatment of pain after brachial plexus injury. *Clin Orthop Relat Res.* 1988;237:87–95.
- Kehlet H, Jensen TS, Woolf CJ. Persistent postsurgical pain: risk factors and prevention. *Lancet.* 2006;367:1618–1625.
- Belze O, Remerand F, Laulan J, et al. Chronic pain after carpal tunnel surgery: epidemiology and associated factors. *Ann Fr Anesth Reanim.* 2012;31:e269–e274.
- Boya H, Ozcan O, Oztekin HH. Long-term complications of open carpal tunnel release. *Muscle Nerve.* 2008;38:1443–1446.
- Jellad A, Salah S, Ben Salah Frih Z. Complex regional pain syndrome type I: incidence and risk factors in patients with fracture of the distal radius. *Arch Phys Med Rehabil.* 2014;95:487–492.
- Dijkstra PU, Groothoff JW, ten Duis HJ, et al. Incidence of complex regional pain syndrome type I after fractures of the distal radius. *Eur J Pain.* 2003;7:457–462.
- Roh YH, Lee BK, Noh JH, et al. Factors associated with complex regional pain syndrome type I in patients with surgically treated distal radius fracture. *Arch Orthop Trauma Surg.* 2014;134:1775–1781.
- Sennwald GR. Fasciectomy for treatment of Dupuytren's disease and early complications. *J Hand Surg Am.* 1990;15:755–761.
- Kalkman CJ, Visser K, Moen J, et al. Preoperative prediction of severe postoperative pain. *Pain.* 2003;105:415–423.
- Sandroni P, Benrud-Larson LM, McClelland RL, et al. Complex regional pain syndrome type I: incidence and prevalence in Olmsted county, a population-based study. *Pain.* 2003;103:199–207.
- Fillingim RB, King CD, Ribeiro-Dasilva MC, et al. Sex, gender, and pain: a review of recent clinical and experimental findings. *J Pain.* 2009;10:447–485.
- Ruau D, Liu LY, Clark JD, et al. Sex differences in reported pain across 11,000 patients captured in electronic medical records. *J Pain.* 2012;13:228–234.
- Katz J, Jackson M, Kavanagh BP, et al. Acute pain after thoracic surgery predicts long-term post-thoracotomy pain. *Clin J Pain.* 1996;12:50–55.
- Mehta SP, MacDermid JC, Richardson J, et al. Baseline pain intensity is a predictor of chronic pain in individuals with distal radius fracture. *J Orthop Sports Phys Ther.* 2015;45:119–127.
- Brander VA, Stulberg SD, Adams AD, et al. Predicting total knee replacement pain: a prospective, observational study. *Clin Orthop Relat Res.* 2003;416:27–36.
- Vranceanu AM, Jupiter JB, Mudgal CS, et al. Predictors of pain intensity and disability after minor hand surgery. *J Hand Surg Am.* 2010;35:956–960.
- Hinrichs-Rocker A, Schulz K, Järvinen I, et al. Psychosocial predictors and correlates for chronic post-surgical pain (CPSP) – a systematic review. *Eur J Pain.* 2009;13:719–730.
- Kroenke K, Spitzer RL, Williams JB. The PHQ-9: validity of a brief depression severity measure. *J Gen Intern Med.* 2001;16:606–613.
- Leung L. Pain catastrophizing: an updated review. *Indian J Psychol Med.* 2012;34:204–217.
- Sullivan MJL, Bishop SR, Pivik J. The Pain Catastrophizing Scale: development and validation. *Psychol Assess.* 1995;7:524–532.
- Teunis T, Bot AG, Thornton ER, et al. Catastrophic thinking is associated with finger stiffness after distal radius fracture surgery. *J Orthop Trauma.* 2015;29:e414–e420.
- Lewis GN, Rice DA, McNair PJ, et al. Predictors of persistent pain after total knee arthroplasty: a systematic review and meta-analysis. *Br J Anaesth.* 2015;114:551–561.
- Allen G, Galer BS, Schwartz L. Epidemiology of complex regional pain syndrome: a retrospective chart review of 134 patients. *Pain.* 1999;80:539–544.
- Terkelsen AJ, Bach FW, Jensen TS. Experimental forearm immobilization in humans induces cold and mechanical hyperalgesia. *Anesthesiology.* 2008;109:297–307. *This study took 27 healthy controls and placed them in a forearm cast for 4 weeks. After cast removal the subjects had transient symptoms similar to CRPS including changes in skin temperature, mechanosensitivity, and thermosensitivity.*
- Pepper A, Li W, Kingery WS, et al. Changes resembling complex regional pain syndrome following surgery and immobilization. *J Pain.* 2013;14:516–524.
- Cepeda MS, Wilcox M, Levitan B. Pain qualities and satisfaction with therapy: a survey of subjects with neuropathic pain. *Pain Med.* 2013;14:1745–1756.
- Celik EC, Erhan B, Lakse E. The clinical characteristics of neuropathic pain in patients with spinal cord injury. *Spinal Cord.* 2012;50:585–589.
- Mackey S, Carroll I, Emir B, et al. Sensory pain qualities in neuropathic pain. *J Pain.* 2012;13:58–63.
- Hagert CG, Hagert E, Slutsky DJ. Manual muscle testing: a clinical examination technique for diagnosing focal neuropathies in the upper extremity. In: *Upper Extremity Nerve Repair: Tips and Techniques. A Master Skills Publication.* Rosemont, IL: American Society for Surgery of the Hand; 2008:451–466. *This text provides a detailed description of the manual muscle testing to assess for nerve injury. There is detailed information on the physical exam and anatomy. It reviews the diagnosis of less common nerve entrapments such as pronator and radial tunnel syndrome.*
- Heller L, Ring H, Costeff H, et al. Evaluation of Tinel's and Phalen's signs in diagnosis of the carpal tunnel syndrome. *Eur Neurol.* 1986;25:40–42.
- Lifchez SD, Means KR, Dunn RE, et al. Intra- and inter-examiner variability in performing Tinel's test. *J Hand Surg Am.* 2010;35:212–216.
- Cheng CJ, Mackinnon-Patterson B, Beck JL, et al. Scratch collapse test for evaluation of carpal and cubital tunnel syndrome. *J Hand Surg Am.* 2008;33:1518–1524.
- Blok RD, Becker SJ, Ring DC. Diagnosis of carpal tunnel syndrome: interobserver reliability of the blinded scratch-collapse test. *J Hand Microsurg.* 2014;6:5–7.
- Witt JC, Hentz JG, Stevens JC. Carpal tunnel syndrome with normal nerve conduction studies. *Muscle Nerve.* 2004;29:515–522.
- Buchberger W, Schön G, Strasser K, et al. High-resolution ultrasonography of the carpal tunnel. *J Ultrasound Med.* 1991;10:531–537.

48. Abrishamchi F, Zaki B, Basiri K, et al. A comparison of the ultrasonographic median nerve cross-sectional area at the wrist and the wrist-to-forearm ratio in carpal tunnel syndrome. *J Res Med Sci*. 2014;19:1113–1117.
49. Kollmer J, Bendszus M, Pham M. MR neurography: diagnostic imaging in the PNS. *Clin Neuroradiol*. 2015;25(suppl 2):283–289.
50. Bendszus M, Wessig C, Solymosi L, et al. MRI of peripheral nerve degeneration and regeneration: correlation with electrophysiology and histology. *Exp Neurol*. 2004;188:171–177.
51. Cudlip SA, Howe FA, Griffiths JR, et al. Magnetic resonance neurography of peripheral nerve following experimental crush injury, and correlation with functional deficit. *J Neurosurg*. 2002;96:755–759.
52. Tung KW, Behera D, Biswal S. Neuropathic pain mechanisms and imaging. *Semin Musculoskelet Radiol*. 2015;19:103–111.
53. Dauri M, Faria S, Gatti A, et al. Gabapentin and pregabalin for the acute post-operative pain management. A systematic-narrative review of the recent clinical evidences. *Curr Drug Targets*. 2009;10:716–733.
54. Tiippana EM, Hamunen K, Kontinen VK, et al. Do surgical patients benefit from perioperative gabapentin/pregabalin? A systematic review of efficacy and safety. *Anesth Analg*. 2007;104:1545–1556. *This systematic review of 22 studies found that perioperative gabapentin provided postoperative pain relief, reduced opioid use, and limited opioid side effects. They also found that the most common adverse effects of gabapentin were dizziness and sedation.*
55. Mathiesen O, Moiniche S, Dahl JB. Gabapentin and postoperative pain: a qualitative and quantitative systematic review, with focus on procedure. *BMC Anesthesiol*. 2007;7:6.
56. Gilron I. Gabapentin and pregabalin for chronic neuropathic and early postsurgical pain: current evidence and future directions. *Curr Opin Anaesthesiol*. 2007;20:456–472.
57. Carroll I, Hah J, Mackey S, et al. Perioperative interventions to reduce chronic postsurgical pain. *J Reconstr Microsurg*. 2013;29:213–222. *This manuscript reviews in detail pre-surgical interventions to reduce pain. It provides a clear algorithm with drug dosages for the patient at risk for chronic pain.*
58. Kairaluoma PM, Bachmann MS, Rosenberg PH, et al. Preincisional paravertebral block reduces the prevalence of chronic pain after breast surgery. *Anesth Analg*. 2006;103:703–708.
59. Kairaluoma PM, Bachmann MS, Korpinen AK, et al. Single-injection paravertebral block before general anesthesia enhances analgesia after breast cancer surgery with and without associated lymph node biopsy. *Anesth Analg*. 2004;99:1837–1843.
60. Perttunen K, Tasmuth T, Kalso E. Chronic pain after thoracic surgery: a follow-up study. *Acta Anaesthesiol Scand*. 1999;43:563–567.
61. Obata H, Saito S, Fujita N, et al. Epidural block with mepivacaine before surgery reduces long-term post-thoracotomy pain. *Can J Anaesth*. 1999;46:1127–1132.
62. Laskowski K, Stirling A, McKay WP, et al. A systematic review of intravenous ketamine for postoperative analgesia. *Can J Anaesth*. 2011;58:911–923.
63. Loftus RW, Yeager MP, Clark JA, et al. Intraoperative ketamine reduces perioperative opiate consumption in opiate-dependent patients with chronic back pain undergoing back surgery. *Anesthesiology*. 2010;113:639–646.
64. Urban MK, Ya Deau JT, Wukovits B, et al. Ketamine as an adjunct to postoperative pain management in opioid tolerant patients after spinal fusions: a prospective randomized trial. *HSS J*. 2008;4:62–65.
65. Maneuf YP, Luo ZD, Lee K. Alpha2delta and the mechanism of action of gabapentin in the treatment of pain. *Semin Cell Dev Biol*. 2006;17:565–570.
66. Finnerup NB, Sindrup SH, Jensen TS. The evidence for pharmacological treatment of neuropathic pain. *Pain*. 2010;150:573–581.
67. Dharmshaktu P, Tayal V, Kalra BS. Efficacy of antidepressants as analgesics: a review. *J Clin Pharmacol*. 2012;52:6–17.
68. Moseley LG, Butler DS, Beames TB, et al. *The Graded Motor Imagery Book*. Adelaide, Australia: NOI Publications; 2012.
69. Bowering KJ, O'Connell NE, Tabor A, et al. The effects of graded motor imagery and its components on chronic pain: a systematic review and meta-analysis. *J Pain*. 2013;14:3–13.
70. Priganc VW, Stralka SW. Graded motor imagery. *J Hand Ther*. 2011;24:164–168.
71. Dellon L, Andonian E, Rosson GD. Lower extremity complex regional pain syndrome: long-term outcome after surgical treatment of peripheral pain generators. *J Foot Ankle Surg*. 2010;49:33–36.
72. Stokvis A, van der Avoort DJ, van Neck JW, et al. Surgical management of neuroma pain: a prospective follow-up study. *Pain*. 2010;151:862–869.
73. Dellon AL, Mackinnon SE. Treatment of the painful neuroma by neuroma resection and muscle implantation. *Plast Reconstr Surg*. 1986;77:427–438.
74. Guse DM, Moran SL. Outcomes of the surgical treatment of peripheral neuromas of the hand and forearm: a 25-year comparative outcome study. *Ann Plast Surg*. 2013;71:654–658.
75. Mackinnon SE, Dellon AL, Hudson AR, et al. Alteration of neuroma formation by manipulation of its microenvironment. *Plast Reconstr Surg*. 1985;76:345–353.
76. Hagert E, Hagert CG. Upper extremity nerve entrapments: the axillary and radial nerves – clinical diagnosis and surgical treatment. *Plast Reconstr Surg*. 2014;134:71–78.
77. Melzack R, Wall PD. Pain mechanisms: a new theory. *Science*. 1965;150:971–979.
78. Deer TR, Skaribas IM, Haider N, et al. Effectiveness of cervical spinal cord stimulation for the management of chronic pain. *Neuromodulation*. 2014;17:265–271.
79. Goebel A, Blas F. Complex regional pain syndrome, prototype of a novel kind of autoimmune disease. *Autoimmun Rev*. 2013;12:682–686.
80. Kohr D, Singh P, Tschernatsch M, et al. Autoimmunity against the beta2 adrenergic receptor and muscarinic-2 receptor in complex regional pain syndrome. *Pain*. 2011;152:2690–2700.
81. Institute of Medicine (US) Committee on Advancing Pain Research, Care, and Education. *Relieving Pain in America: A Blueprint for Transforming Prevention, Care, Education, and Research*. Washington, DC: National Academies Press (US); 2011.

Nerve entrapment syndromes

Elisabet Hagert and Donald Lalonde

Access video and video lecture content for this chapter online at expertconsult.com



SYNOPSIS

- Chronic nerve entrapment syndromes in the upper extremity are common and their occurrence is only likely to increase as risk factors such as diabetes, obesity, and advanced age become more prevalent in the general population.
- In most cases, the diagnosis is based on a good history and a proper physical examination.
- For more atypical presentations, a detailed clinical examination using a clinical triad of muscle testing, scratch collapse test, and specific pain points must be performed to rule out proximal nerve entrapments in the upper extremity.
- In the event of advanced muscle atrophy, muscle fibrillations, and severe sensory disturbances, consideration should be given to other neurologic conditions that mimic nerve entrapment syndromes such as mononeuritis, Parsonage–Turner syndrome, and motor neuropathies; not only will these conditions not respond to surgical decompression, they may in fact be exacerbated by operative management.
- When the diagnosis is unclear, electrodiagnostic tests and magnetic resonance or ultrasound imaging may be of benefit.
- The purpose of this chapter is to provide the reader with a comprehensive review of the pathophysiology, clinical diagnosis, and surgical treatment of nerve entrapment syndromes of the upper extremity.

Pathophysiology of chronic nerve compression

In carpal tunnel syndrome (CTS), the initial pathophysiology in chronic nerve compression (CNC) is seen clinically as paresthesias and an elevation in the static cutaneous sensory threshold as measured by Semmes–Weinstein monofilament testing. With increased compression, localized demyelination occurs followed by more diffuse demyelination.¹ At this stage, patients will experience muscle weakness and will demonstrate increased pressure thresholds for quickly adapting

fibers on vibrometry; two-point discrimination, measured in millimeters, remains unchanged. Superficial fascicles tend to undergo demyelination earlier and may explain varying patient symptoms within a single nerve distribution. In early CTS, for example, patients are more likely first to experience paresthesias in the long and ring fingers as the fascicles to these digits are most superficial within the median nerve. Wallerian degeneration and axonal damage is not seen until the final stages of CNC,^{2,3} at which point the patient presents with chronic numbness and thenar atrophy.

More proximal median nerve entrapments, such as the lacertus syndrome,⁴ will differ in clinical presentation as the most superficial fascicles in the nerve at the level of the lacertus fibrosus are motor fibers to the flexor carpi radialis, flexor pollicis longus, and the deep flexor of the index finger.⁵ Patients with early lacertus syndrome thus complain of diffuse weakness of pinch and grip, but the sensory symptoms are not evident until later stages, when deeper sensory fibers are affected. This is why lacertus syndrome is predominantly diagnosed by demonstrating weakness of the affected muscles on proper physical examination.

Double-crush syndrome

The double-crush syndrome (DCS) is an important concept in CNC. First proposed by Upton and McComas, the double-crush concept holds that compression of a peripheral nerve at one site increases susceptibility to compression at another site along the same nerve.⁶ This phenomenon appears to be the result of the disruption of anterograde or, in the case of “reverse DCS”, retrograde axoplasmic flow of neurotrophic factors.⁷ DCS has been demonstrated experimentally in animal models of chronic compression.^{8–11} Clinically, numerous examples of multiple sites of compression along the same nerve have been described and include reports of cervical radiculopathy and median nerve compression, CTS and pronator syndrome, and cubital tunnel syndrome and ulnar nerve compression in Guyon’s canal.^{12–15} The DCS concept suggests that two or more simultaneous points of compression, each of which might be

insufficient to cause symptoms on its own, could together produce symptoms of clinical severity. The underlying causes of DCS may include impaired axonal transport, changes in ion channel regulation, neuro-inflammatory processes and instances of neuroma-in-continuity.¹⁶

The presence of DCS places a great responsibility on the surgeon or therapist to perform a thorough physical examination to delineate the levels of nerve compression, using a combination of manual muscle testing algorithms and the scratch collapse test.^{17,18} In the surgical treatment of DCS, decompression of one of the two sites might be sufficient to address a patient's symptoms. The most distal nerve compression is typically decompressed first as it is usually the site of the more severe compression and lower surgical risk. If decompression in the distal extremity fails to relieve symptoms, decompression of the more proximal site, such as the intervertebral space or brachial plexus, should be considered.

Clinical examination of upper extremity nerve entrapments

The difficulty in diagnosis of upper extremity nerve entrapments lies in the variable spectrum of a patient's symptoms. Even in instances of apparent carpal tunnel syndrome, symptoms outside of the median innervated region in the hand are present in two-thirds of patients.¹⁹ In some cases, bilateral pain is present despite only unilateral nerve involvement.²⁰

Another aspect that influences a clinical presentation is the origin of the CNC, where disturbances in neural blood flow and axonal transport commonly occurs without axonal injury. This results in an inability to reliably use electrodiagnostic tools for a definitive diagnosis. Electrodiagnostics should rather be seen as a complimentary modality to a thorough clinical examination.¹⁸ The degree of nerve injury in CNC is most commonly associated to a Sunderland degree I, or a Seddon's neuropraxia.²¹ Possible loss of motor function will not be evident as muscle atrophy. However, muscle weakness can be shown through a clinical triad including: (1) manual muscle testing to delineate the level of nerve entrapment(s); (2) scratch collapse test to confirm and order the importance of nerve entrapment(s); and (3) pain and tenderness over the nerve at the level of entrapment(s).¹⁷

Manual muscle testing algorithm (Video 24.1 ▶)

Here is why proper physical examination with muscle testing is so important. The principle of grading of muscle strength was established by Seddon in the 1950s into six grades: M0 to M5.²² M0 to M3 represent weaknesses that are clinically apparent and found in instances of axonotmesis or complete nerve transections. M5 represents normal power with no loss of strength. The difficulty is diagnosing the M4 grade of muscle strength, which is defined as "contraction against gravity and resistance". If we look for it, we will commonly find M4 weakness in CNC, where changes in the nerve are not dependent on axonal injury. Since this type of muscle weakness can only be found using "resistance", it is only found through clinical examination of muscle strength. Based on this, the clinical entity of M4 may be referred to as the "hidden paresis", and one we must actively look for.²³

Out of the 60 muscles in the upper limb, about 45 are accessible to manual testing of individual strength. A simplified manageable, manual muscle testing protocol involving four positions and 12 muscles has been advocated.^{17,23} The efficacy (sensitivity and specificity) of manual muscle testing of antagonist muscles to determine levels of focal neuropathies in the upper extremities have been established in randomized and blinded level II studies to 88 and 93%, respectively.^{24,25} The principle is straightforward: distal to the level of nerve entrapment, distinct patterns of muscle weaknesses will be clinically present.

The four positions of muscle testing are as follows: (1) shoulder – testing of pectoralis and posterior deltoid; (2) elbow – testing of biceps, triceps and infraspinatus; (3) wrist – testing of extensor carpi ulnaris (ECU), extensor carpi radialis brevis (ECRB) and flexor carpi radialis (FCR); and (4) hand – testing of extrinsics (flexor pollicis longus, FPL; flexor digitorum profundus V, FDP V) and intrinsics (abductor pollicis brevis, APB; abductor digiti minimi, ADM) (Video 24.1 ▶).

The interpretation of each test is, of course, of outmost importance and will be delineated in each nerve entrapment section described in this chapter. Each muscle is also described in Table 24.1 related to possible level of involvement as well as in relation to position within the upper extremity (Fig. 24.1). The principle of the muscle testing algorithm is to investigate the upper extremity consistently from a proximal to a distal level of involvement, starting with the pectoralis and ending with the hand intrinsics.

Scratch collapse test (Video 24.2 ▶)

The scratch collapse test (SCT) was first described by Cheng, Beck, and Mackinnon in 2008,²⁶ and has since been used in several publications to clinically verify levels of nerve entrapment in the upper and lower extremities.^{4,17,27–29} In carpal tunnel and cubital tunnel syndromes, the SCT has a diagnostic accuracy of 82 and 89%, respectively, rendering this test more sensitive than the commonly used Tinel's and flexion nerve compression tests.²⁶

The concept of SCT is that a patient with a focal nerve entrapment has an area of skin allodynia located at the level of nerve entrapment. When scratching this area of skin, a brief spinal reflex causes a momentary loss of voluntary muscle contraction. Clinically, the patient is seated with elbows flexed to 90°, shoulders adducted and slightly externally rotated. The patient is asked to resist bilateral internal pressure applied by the examiner onto the forearms. The area of suspected nerve entrapment is then gently scratched and pressure again applied onto the forearms. In the event of a focal nerve compression, the patient will feel a distinct loss of muscle strength in the affected arm (Video 24.2 ▶).^{26,27}

In instances of suspected multiple points of nerve compression, topical ethyl chloride may additionally be used to grade the hierarchy of nerve compressions. By applying ethyl chloride over the primary level of nerve entrapment, underlying and subclinical levels of entrapment may be revealed to further aid the examiner in understanding a patient's symptoms.¹⁸ The use of SCT can thus aid the clinical diagnosis of nerve entrapment, where manual muscle testing is used to delineate the level of nerve entrapment and SCT is used to verify this level of entrapment.

Table 24.1 Interpretation of muscle exam: patterns of muscle weakness, nerve involvement, and level of entrapment

Weakness	Nerve	Level of entrapment
Pectoral	Cervical roots C6–T1	C6–T1 radiculopathy; possibly non-participating patient
Posterior deltoid	Axillary N.	Quadrilateral space
Biceps	Musculocutaneous N.	Proximal upper arm
Deltoid + biceps	Cervical roots C5–C6	C5–C6 radiculopathy
Pect + deltoid + biceps (+ triceps)	Infraclavicular brachial plexus	Subclavicular
Triceps	Radial N.	Triangular interval
Deltoid + triceps	Axillary + Radial N	Quadrilateral space + radial triangular interval
Triceps + FCR	Cervical root C7	C7 radiculopathy
Infra + supraspinatus	Suprascapular N.	Suprascapular notch
Infraspin + rhomboid	Cervical root C5	C5 radiculopathy
Rhomboid	Dorsal scapular N.	Middle scalene or proximal rhomboid edge
ECRB + EIP + EPL	Radial N.	Lateral intermuscular septum, distal upper arm
ECU	Radial N.	Radial tunnel syndrome – arcade of Frohse
EDC	Radial N.	Distal edge of supinator
FCR + FPL + FDP II	Median N.	Lacertus fibrosus
FDS III–IV	Median N.	Superficialis arcade
FPL + FDP II	Median N.	Anterior interosseous syndrome
APB	Median N.	Carpal tunnel
FDP V + ADM	Ulnar N.	Cubital tunnel
ADM	Ulnar N.	Guyon's canal zone 1
1-DIO	Ulnar N.	Guyon's canal zone 3

1-DIO, First dorsal interosseous; ADM, abductor digiti minimi; APB, abductor pollicis brevis; ECRB, extensor carpi radialis brevis; ECU, extensor carpi ulnaris; EIP, extensor indicis proprius; EPL, extensor pollicis longus; FCR, flexor carpi radialis; FDP, flexor digitorum profundus; FDS, flexor digitorum superficialis; FPL, flexor pollicis longus.

The last part in the clinical triad is the presence of pain upon compression and/or a positive Tinel's test at the level of nerve compression to further confirm the correct level of diagnosis.

Electrodiagnostic studies (EDS)

Although EDS are widely used in the evaluation of patients with suspected upper extremity nerve entrapments, the sensitivity and specificity of nerve entrapments aside from the carpal tunnel and cubital tunnel syndromes, is only between 30–65%.^{30,31} The pitfalls of EDS include technical- and operator-dependent errors, inability to distinguish mixed pattern type of nerve injuries, limitation in electromyographic studies where only a portion of muscle function is evaluated, and an inability to detect early nerve compression syndromes.³² These shortcomings have even lead some authors to advise against EDS,³³ and rather advocate the use of clinical examination techniques.¹⁸

When an atypical presentation or comorbidities cloud the clinical picture, symptom criteria and provocative tests can be combined with EDS to make the diagnosis. Electrodiagnostics are of particular use in grading nerve injuries in patients with suspected diabetic or alcohol-induced polyneuropathy, in patients with advance muscle atrophies and/or in patients

with peripheral muscle fibrillations where peripheral neuropathic disease may be suspected. Two aspects of electrodiagnostic tests are most often used to diagnose nerve entrapment syndromes: nerve conduction studies (NCS) and electromyography (EMG). Of the two studies, the former are especially helpful. An NCS is performed by placing two electrodes on the skin, along the course of the nerve (Fig. 24.2). The first electrode is used to stimulate a peripheral nerve to fire, and the second electrode is used to record the characteristics of the generated action potential at some distance away from the stimulation point. The electrodes typically detect only larger, faster-conducting fibers.

EMG studies assess the integrity of muscle function. Because muscle integrity is dependent on innervation, these studies help determine whether axonal damage has occurred.

Median nerve entrapments

Carpal tunnel syndrome

CTS is the most common nerve entrapment syndrome in the upper extremity, with an estimated incidence in the US of 1–3 cases per 1000 subjects per year and a prevalence of 50 cases per 1000 subjects per year.³⁴ The surgical release of carpal tunnel syndromes has the highest utilization rate of upper




Fig. 24.1 The patient chart routinely used for nerve entrapments. The patterns of muscle weakness found in clinical testing is mapped according to dermatome, as well as position in the arm. It allows for easier visualization as to level of nerve entrapment. 1-DIO, first dorsal interosseous; ADM, abductor digiti minimi; AP, adductor pollicis; APB, abductor pollicis brevis; ECRB, extensor carpi radialis brevis; ECRL, extensor carpi radialis longus; ECU, extensor carpi ulnaris; EDC, extensor digitorum communis; EIP, extensor indicis proprius; EPL, extensor pollicis longus; FCR, flexor carpi radialis; FDP, flexor digitorum profundus; FDS, flexor digitorum superficialis; FPB, flexor pollicis brevis; FPL, flexor pollicis longus; M, median nerve; R, radial nerve; U, ulnar nerve. (Reprinted with kind permission from Prof. Carl-Göran Hagert, MD, PhD.)




Fig. 24.2 Method for determining the median nerve conduction velocity (CV) in the forearm, recording at the thenar eminence.

extremity disorders in the US, with an average of about 40 surgical releases per 10000 subjects per year.³⁵ The economic burden from lost wages and productivity and treatment costs is considerable.³⁶ Despite the prevalence of CTS, debate remains over the accurate diagnosis and optimal treatment of the condition.

Anatomy

The anatomic boundaries of the carpal tunnel are defined dorsally by the carpus, and volarly by the transverse carpal ligament (TCL), which spans from the hamate and triquetrum on the ulnar side to the scaphoid and trapezium on the radial side. The median nerve is the most superficial structure within the canal. The median nerve may divide in the forearm or split within the carpal tunnel. Both presentations are associated with a persistent median artery. The recurrent motor branch to the thenar muscles usually arises off the median nerve in an extraligamentous position distal to the TCL (46–90%) (Fig. 24.3). Less frequently, the motor branch originates from

beneath the TCL (subligamentous, 31%) or perforates the TCL (transligamentous, 23%).³⁷ The palmar cutaneous branch typically arises off the radial aspect of the median nerve 5–6 cm proximal to the distal wrist crease. Additional branching pattern variations of the recurrent motor branch and palmar cutaneous branch have been described.³⁸

Etiology

In the vast majority of CTS cases, an underlying etiology cannot be identified. Women are more often affected than men.³⁹ Compression tends to be greatest at a point 1 cm distal to the distal wrist crease where the TCL is thickest.⁴⁰ In rare instances, structural causes such as a persistent median artery, ganglion cyst, hemangioma, or proximal lumbrical origin can increase pressure within the carpal tunnel.

Systemic conditions, such as renal failure, thyroid disease, rheumatoid arthritis, and diabetes mellitus, may also predispose patients to CTS. CTS can occur in up to 45% of pregnant women during the third trimester but usually




Fig. 24.3 Variations in median nerve anatomy in the carpal tunnel. **(A)** The most common branching pattern of the motor branch is extraligamentous. **(B)** Subligamentous branching pattern of the motor branch. **(C)** Transligamentous course of the recurrent motor branch. **(D)** The motor branch can rarely arise from the ulnar border of the median nerve. **(E)** The motor branch can also lie superficial to the transverse carpal ligament.

resolves postpartum.⁴¹ In the pediatric population, mucopolysaccharidoses are a frequent cause of CTS.⁴² To date, the only strong evidence linking occupation to CTS has been among operators of handheld vibratory tools.⁴³ Scientific support for a causative role for other repetitive work activities (e.g., typing) in the development of CTS is otherwise lacking.⁴⁴

History

A thorough history and physical examination are central to the diagnosis of CTS. Patients with CTS report nocturnal pain, numbness, and tingling in the thumb and radial fingers. Paresthesias are usually triggered by activities involving sustained wrist flexion or extension. Shaking and wringing of the hands tend to alleviate symptoms. Bilateral symptoms are common. Occasionally, paresthesias can radiate proximally along the median nerve to the forearm and may even involve the ulnar digits.

Clinical examination

Using the clinical triad described above (muscle exam, SCT, Tinel's test), patients with CTS should be examined using the manual muscle testing protocol with particular emphasis on the median innervated muscles: FCR, FPL, FDP II and APB. In a case of CTS, a weakness of APB may be found when comparing to the contralateral side. Actual manifest thenar atrophy has a high predictive value in CTS, but is not commonly observed.⁴⁵ It is of great importance to test FCR, FPL and FDP II strength in every patient with suspected CTS to rule out concomitant DCS and proximal median nerve involvement. The SCT has an estimated 82% accuracy as a clinical provocative test in CTS,²⁶ and is elicited by scratching over the carpal tunnel just distal to the wrist flexion crease (Video 24.2 ). Tinel's sign is elicited by gently percussing over the median nerve at the carpal tunnel. A positive sign is present if the patient describes an electrical shock sensation in the median nerve distribution. The low specificity and sensitivity of the sign may in part be due to the wide intra- and interexaminer variability with which it is elicited.⁴⁶

Other provocative tests that can be considered to aid in the evaluation of CTS include the Phalen's test and the Durkan's test. The Phalen's test is performed by having the patient place the elbow on a table and flex the wrist for 60 s. The test is considered positive if the patient reports paresthesias in the median nerve distribution. Durkan's median nerve compression test involves direct compression of the median nerve at the carpal tunnel for 30 s. A positive test is obtained if the patient reports numbness or tingling in at least one of the radial digits.⁴⁷ Other less frequently used provocative tests include the reverse Phalen's, tourniquet test and the flick maneuver.^{48,49} For multiple reasons, including poor study design, variability in outcome measures, and small datasets, no single test has been identified to diagnose CTS consistently. Of the above maneuvers, Durkan's compression test performed with a calibrated pressure device demonstrates the highest sensitivity (89%) and specificity (96%).⁴⁷ The sensitivities and specificities of Tinel's sign and Phalen's test are lower.^{50–52} Threshold sensory tests such as Semmes–Weinstein monofilament measurements tend to be more sensitive for detecting early CTS than innervation density measurements.⁵³

Given the utility of patient symptoms and physical findings, attempts have been made to develop formal clinical criteria for the diagnosis of CTS. Graham *et al.* generated a list of six clinical criteria (CTS-6) for the diagnosis of CTS, based on a validated statistical analysis of recommendations by an expert panel. The six criteria included: (1) nocturnal numbness; (2) numbness and tingling in the median nerve distribution; (3) weakness and/or atrophy of the thenar muscles; (4) Tinel sign; (5) Phalen's test; and (6) loss of two-point discrimination.⁵⁴ Similarly, an American Academy of Orthopaedic Surgeons (AAOS) panel reviewed the available literature and developed recommendations for diagnosing CTS; high-level evidence was lacking to support the majority of recommendations.⁵⁵ The CTS-6 lacks a recommendation regarding muscle exam, which should always be considered an important part of the clinical diagnosis of CTS to rule out possible proximal median nerve involvement.

Other diagnostic tools

CTS remains a clinical diagnosis, and the role of electrodiagnostic and imaging studies remains complementary. Electrodiagnostic tests are routinely performed, yet their validity is largely unproven. EMG and NCS have been shown to be poor predictors of symptom severity or functional impairment.⁵⁶ Patients with clinical evidence of CTS and negative NCS studies have been shown to have identical clinical improvement after surgery as patients with positive NCS findings.⁵⁷ Distal motor and sensory latencies greater than 4.5 and 3.5 ms, respectively, are generally considered positive.⁵⁸

Ultrasound is inexpensive, reproducible, available to all, and actually shows compression objectively in the live human. A recent level 1 study comparing the use of ultrasound and electrodiagnostic testing in CTS revealed an equivalent sensitivity (89%) and a greater specificity (90% vs. 80%) of ultrasound in accurately diagnosing CTS.⁵⁹ Since ultrasound can be performed by the surgeon in an office setting, independent of radiological evaluation, the cost-effectiveness and safety is promising in the diagnosis of CTS.

Clinical tips

If nerve conduction studies are positive, the patient most likely has carpal tunnel syndrome that will respond to surgery, particularly if the findings are profound. Surgery may still be helpful even if the nerve conduction studies are negative, particularly if the patient provides a classic history of numbness at night or with prolonged wrist flexion.

Patient selection

Non-operative treatment

There is a role for both non-surgical modalities in the management of CTS (Table 24.2).⁵⁵ Splinting is the most widely used. On the basis of two well-designed studies, splinting has been shown to be more effective than no treatment at relieving symptoms for at least 3 months.^{60,61} No difference has been demonstrated between continuous splinting and nocturnal splinting alone.⁶²

Table 24.2 American Academy of Orthopaedic Surgeons clinical practice guidelines for the treatment of carpal tunnel syndrome (CTS): recommendations

1. Non-surgical treatment is an option for early CTS. Surgery is an option when there is evidence of median nerve denervation
2. A second non-surgical treatment or surgery is recommended when initial non-surgical treatment fails after 2–7 weeks
3. There is no evidence to support specific treatment recommendations for CTS associated with diabetes, cervical radiculopathy, hypothyroidism, polyneuropathy, pregnancy, rheumatoid arthritis, or CTS in the workplace
- 4a. Local steroid injection or splinting is recommended prior to treatment with surgery
- 4b. Oral steroids and ultrasound are also options for treatment
- 4c. Carpal tunnel release is recommended for treatment of CTS based on level I evidence
- 4d. Heat therapy does not have evidence to support its use in CTS
- 4e. Other non-surgical treatment modalities are not recommended for treatment of CTS
5. Surgical treatment with complete division of the flexor retinaculum is recommended, regardless of the technique used
6. Skin nerve preservation, epineurotomy, flexor retinacular lengthening, internal neurolysis, tenosynovectomy, and ulnar bursa preservation are not recommended in the performance of carpal tunnel surgery
7. Use of preoperative antibiotics is an option that may be decided upon by the surgeon
8. Wrist immobilization is not recommended postoperatively after routine carpal tunnel release. No recommendation is made regarding use of postoperative rehabilitation
9. It is suggested that physicians use one or more patient response tools to assess results after carpal tunnel treatment in performing research

Clinical tips

Most patients with carpal tunnel syndrome will experience nocturnal numbness, or numbness with sustained wrist flexion as occurs with driving or talking on the telephone. Patients who experience symptomatic relief with splinting are also likely to respond well to surgery.

Steroid injection has been extensively reviewed.⁶³ It provides greater clinical improvement in symptoms 1 month after injection compared to placebo.^{64,65} In addition, local injection provides superior symptom relief compared to systemic steroid administration for up to 3 months.⁶⁶ Two local corticosteroid injections do not provide significant added clinical benefit compared to one injection.⁶⁷ Steroid injection in combination with splinting has also been shown to be better than splinting only at 6-month follow-up.⁶⁸

Treatment/surgical technique

Surgery is the treatment of choice when non-surgical treatments have failed or when APB weakness and/or sensory disturbance is advanced. Release of the TCL may be performed using an open or endoscopic technique. Open carpal tunnel release (OCTR) remains the most common method of decompression.

Clinical tips

For almost pain-free local anesthesia using the wide-awake approach, never advance the needle tip ahead of the infiltrated local anesthetic. Palpate the wheal of local anesthetic so it is firm ahead of the slowly advancing needle tip. Remember: "Blow slow before you go" (video 24.3 ►).

Wide-awake OCTR

The wide-awake approach (local infiltration without sedation or tourniquet) has been shown to be safe and cost-effective and is the preferred method of the authors.^{69,70} Tumescence field infiltration of 20 mL of 1% lidocaine with 1:100 000 epinephrine is performed (Fig. 24.4 and Video 24.11 ►). A 3-cm incision is made in line with the flexed ring finger paralleling the thenar crease and ending just distal to the distal wrist flexion crease. The palmar fascia and TCL are incised longitudinally to expose the median nerve. In cases where a prominent palmaris brevis muscle is present, one should attempt to preserve it, dividing the TCL deep to it (Fig. 24.5). The ligament and forearm fascia releases are extended distally to divide all distal TCL fibers completely in the fat pad and proximally beneath the wrist flexion crease for about 1 cm into the forearm. The authors prefer to perform skin closure using buried intradermal 5-0 absorbable monofilament sutures, thereby obviating the need for suture removal (as shown in video 24.4 ►, which also contains detailed advice provided to patients intraoperatively). A light dressing only is applied, as postoperative splinting has not been shown to improve pain relief or surgical outcome.⁷¹ Patients are allowed to remove the dressing and shower the day after surgery. A new dressing may be applied for padding and protection for up to a week. Patients are advised to elevate and rest the hand for the first 2 postoperative days. In most cases, ibuprofen and acetaminophen provide sufficient analgesia over this time. After the second postoperative day, any residual pain is usually the result of overexertion; a gradual return to full activities is advised with pain serving as a guide. Most patients can return to full work activities by 8 weeks. Patients are advised that mild discomfort at the operative site and decreased grip strength can persist for several more months.

Endoscopic carpal tunnel release (ECTR)

ECTR techniques were developed in an attempt to avoid problems occasionally experienced following OCTR, namely




Fig. 24.4 Method of local anesthesia infiltration for the wide-awake approach to open carpal tunnel release. **(A)** Up to 10 cc of 1% lidocaine with 1 : 100 000 epinephrine local anesthetic is infiltrated superficial and deep to the antebrachial fascia of the distal volar forearm, producing a clear wheal proximal to the planned incision. **(B,C)** Infiltration then continues distally deep superficial to the proximal transverse carpal ligament under the incision. Paresthesia induction is contraindicated as the needle can damage nerve fascicles.




Fig. 24.5 Preservation of prominent palmaris brevis or thenar muscles during open carpal tunnel release. In the authors' experience, postoperative pain and grip strength are improved with preservation of palmaris brevis or thenar muscles encountered during dissection with no compromise of decompression. The transverse carpal ligament is divided deep to the muscle under direct visualization.

scar tenderness and pillar pain. Popular approaches include the dual-portal technique of Chow and the single-portal technique of Agee.^{72,73}

Using the Chow technique, proximal and distal incisions are made deep to the TCL. The endoscope and blade assembly are passed from the proximal incision through the distal incision, deep to the TCL. The distal TCL is released using a probe knife. A second cut is made in the midsection of the TCL with a triangular knife and joined to the first cut using a retrograde knife. The endoscope is then repositioned and in a similar fashion the probe knife used to cut the proximal TCL. A retrograde knife is inserted into the midsection of the TCL and drawn proximally to complete the release.

In the Agee ECTR, a small transverse skin incision is made at the ulnar border of the palmaris longus tendon, midway between the flexors carpi ulnaris and radialis, and proximal to the wrist flexion creases. A distally based forearm fascia flap is elevated to reveal the proximal edge of the TCL. With the wrist in extension, the endoscopic blade assembly is inserted into the canal in line with the ring finger. The TCL is visualized and divided distally to proximally.

OCTR vs. ECTR

Both OCTR and ECTR are practiced widely, with proponents of both techniques continuing to debate the merits of one over the other. A common argument in favor of ECTR over OCTR has been reduced postoperative pain and a shorter return to vocational activities. Although these findings have been borne out in some studies,^{74–76} other studies show that any differences between techniques in patient symptoms, function, and satisfaction equalize by 1 year.^{77,78} Supporters of OCTR have, in turn, cited a higher incidence of postoperative neurovascular complications as a reason to avoid ECTR.⁷⁹ More recent studies have failed to support this higher risk in ECTR.^{74,75,77,78,80} Cost has been another factor in the debate between OCTR and ECTR. A 1998 cost-effectiveness analysis comparing the two techniques concluded that ECTR is cost-effective provided

major complications occur 1% less often than in OCTR.⁸¹ Previous prospective studies have not shown a substantial cost difference between the techniques if the cost of ECTR equipment is excluded.^{74,75,77}

Outcomes and complications

While advanced thenar wasting and complete anesthesia are not likely to resolve following surgery, pain associated with CTS typically does, regardless of its duration. Although response to carpal tunnel release is widely held to be worse among elderly and diabetic patients, this has not been borne out by a number of recent studies.^{82–84} Overall, outcomes following carpal tunnel release are excellent, with patient satisfaction, symptom relief, and functional improvement observed in more than 94% of cases.^{83,85}

Clinical tips

Patients can be advised that, although carpal tunnel release relieves most of the numbness most of the time in most patients, it does not relieve all of the numbness all of the time in all people. If constant numbness has been present for an extended period of time, return of normal sensation after carpal tunnel release is less likely. Surgery may be helpful in alleviating shoulder, arm, elbow, or forearm pain associated with the numbness.

Complications of carpal tunnel release include, but are not limited to, injuries to the motor and palmar cutaneous branches and main trunk of the median nerve; hypertrophic scarring; pillar pain; superficial palmar arterial arch injury; incomplete TCL release; tendon adhesions; infection; wound hematoma; stiffness; and recurrence. The most common complication with OCTR is pillar pain (25%), followed by laceration of the palmar cutaneous branch of the median nerve.⁸⁶ Incomplete TCL release is the most frequent complication of ECTR.⁷⁴ Recurrent CTS symptoms are seen in up to 20% of cases.⁸⁷ Ultrasound is an easy and reliable tool in evaluating the median nerve at the carpal tunnel, where an increase in cross-sectional area, hypervascularity, and reduced echogenicity are signs of persistent nerve compression.⁸⁸

Clinical tips

All patients with failed and/or recurrent carpal tunnel release should be examined regarding strength in the FCR, FPL, FDP II to rule out a proximal median nerve entrapment at the elbow, lacertus syndrome, as a possible cause of incomplete recovery following carpal tunnel surgery (video 24.5 ▶).

Median nerve entrapments in the elbow and forearm

Background

Compression of the median nerve in the forearm and elbow has traditionally been regarded as a rare entity and far less common than CTS. Recent publications, however, are raising

an awareness regarding the presence of proximal median nerve entrapments as a cause of arm pain, hand weakness, and possible sensory deficits within the median innervated area.^{4,89} The presence of median nerve entrapments has traditionally been called the “pronator syndrome”, after the first description by Seyffarth in 1951 of a pronator teres compression of the median nerve.⁹⁰ Later, the pronator syndrome has become a collective entity denoting a median nerve entrapment that can exist from the upper arm to the distal forearm.⁹¹ With the advent of more thorough physical exams in patients with upper extremity pain and dysfunctions, a delineation of entrapment levels is seen. Proximal median nerve entrapments can thus be divided into three separate entities: the lacertus syndrome⁴; the superficialis syndrome⁸⁹; and the anterior interosseous (AIN) syndrome.⁹²

Lacertus syndrome

Compression of the median nerve by the lacertus fibrosus, or bicipital aponeurosis, at the level of the cubital fossa was first described by Laha in 1978.⁹³ It has later been described in relation to repetitive and strenuous work with the arm in a pronated position,⁹⁴ and is slightly more common in computer workers than manual laborers.²³ In the largest published prospective study on lacertus syndrome, women and men were affected equally, as was the dominant/non-dominant hand.⁹⁵

Anatomy

Akin to the carpal tunnel, at the level of the lacertus fibrosus the median nerve passes through a “tunnel”, where the bottom is the medial trochlea of the humerus, the lateral and medial walls are the brachialis and pronator muscles, respectively, and the roof is the lacertus fibrosus (Fig. 24.6). The lacertus fibrosus thus acts like the transverse carpal ligament, being a strong fibrous band that may constrict the median nerve at the level of the elbow.⁹⁶ According to Sunderland,⁵ at this level, the median nerve is organized such that the branches to the pronator teres and FCR are located anteriorly, and the branches to the FPL and FDP II, medially, whereas the sensory branches are located more deeply in the nerve. The motor symptoms will therefore appear before sensory symptoms in the instance of lacertus syndrome.

History

The most common complaints in patients with lacertus syndrome is a loss of key- and tip-pinch strength, a loss of fine motor skills, and sense of clumsiness (dropping objects). It is rarely associated with transient paresthesias in the median nerve-innervated region of the hand and there are no nocturnal symptoms of numbness as in CTS.²³ The presence of volar forearm pain is common in the later stages of lacertus syndrome, usually located in the cubital fossa and proximal volar forearm. It may at times be mistaken for medial epicondylitis due to the pain distribution in the medial elbow region.

Clinical examination

The clinical triad of muscle testing, SCT, and pain upon compression will reveal the following in a patient with lacertus syndrome: (1) distinct weakness when manually testing the strength of the muscles innervated by the median nerve

distal to the lacertus fibrosus, especially the FPL, FDP II and FCR; (2); a positive SCT over the median nerve at the level of the lacertus fibrosus; and (3) pain upon external pressure of the median nerve at the proximal edge of the lacertus fibrosus (video 24.5 ▶).

Non-operative treatment

In patients with early onset of symptoms, a trial of local triamcinolone injections at the edge of the lacertus fibrosus may have success in reducing, even eliminating, symptoms. The effect of local cortisone is most likely a combination of reduced swelling around the nerve, as well as an effect in reducing the neuro-inflammatory response in the nerve.⁹⁷

Wide-awake surgical release

The surgery is performed according to the wide-awake technique (video 24.5 ▶), with an awake patient and no tourniquet: 20–30 min preoperatively, the patient is anesthetized using 30–40 mL 1% lidocaine (10 mg/mL) with epinephrine (5 µg/mL) with 2–3 mL sodium bicarbonate (50 mg/mL) solution added. Using a 27-inch gauge needle, the anesthesia is slowly infiltrated from the medial elbow crease and obliquely 4 cm distally and centrally to cover the course of the lacertus fibrosus. A 2–3 cm transverse incision is placed in the flexion crease of the cubital fossa, from 1 cm medial of the biceps tendon to 2 cm lateral of the medial epicondyle. Careful dissection is made subcutaneously to the pronator teres (PT) fascia, taking great care to identify and protect branches of the medial antebrachial cutaneous nerve (MACN). The PT fascia is incised and followed laterally, allowing exposure of the lacertus fibrosus, which is subsequently divided. By retracting PT medially, the median nerve is readily seen. Any focal adhesions to the underlying brachialis muscle may then be released. At this point, the strength of the FPL and FDP II is again tested intraoperatively before the skin is closed, as return of muscle strength is usually immediate after proper release of the nerve (video 24.5 ▶).

Intraoperative examination of the superficialis sling actively flexing on the surgeon's small finger in the wound of the lacertus release can delineate further compression at this point. It could be released through a separate incision if identified.

After cauterization, the wound is closed with intradermal 4-0 monocryl sutures, a small soft dressing applied, and immediate mobilization encouraged. Patients with non-manual labor return to work within 1–2 days postoperatively.

In a retrospective 10-year follow-up of surgically released median nerves at the level of the lacertus fibrosus vs. conservatively treated patients, the surgical patients had no return of symptoms but only 30% of the conservatively treated patients had relief of symptoms.⁹⁸ The surgical release at this level can thus be considered safe, minimally invasive, and effective.

Superficialis syndrome – AIN syndrome

In the traditional release of pronator syndrome, this fibrous flexor digitorum superficialis (FDS) arch has been considered one of the important pressure points to release. About 6 cm distal to the cubital fossa and medial epicondyle, the FDS arch




Fig. 24.6 Anatomy of proximal median nerve entrapments. **(A)** The lacertus syndrome is entrapment at the level of the lacertus fibrosus, resulting in weakness in the flexor carpi radialis, flexor pollicis longus (FPL) and the deep flexor to the index finger (FDP II). During surgery, the lacertus fibrosus should be completely transected. **(B)** The arch of the flexor digitorum superficialis (FDS) is the level of entrapment for the superficialis syndrome, with weakness in FDS IV and often paresthesias in the hand. This arch should be completely opened when performing superficialis syndrome surgery.

is found as a fibrous structure between the PT and FDS (see Fig. 24.6). The FDS arch is always located proximal to the bifurcation of the main median nerve and the anterior interosseous nerve. Originally, the AIN syndrome was described to occur under the fibrous arch of the FDS or the PT, but median nerve compression at these levels will not only involve the AIN but also the main median nerve and should be referred to as the superficialis syndrome. Pure AIN entrapment thus occurs distal to the FDS arch, after the bifurcation between the AIN and the main median nerve (see Fig. 24.6). Isolated entrapment of the AIN is the most uncommon of the proximal median nerve entrapments.

History

Like the lacertus syndrome, the patient with a median nerve entrapment at the FDS arch will complain of volar forearm pain and weakness in pinch. One distinct difference in presentation is that the superficialis syndrome also is associated with sensory disturbances within the median innervated region of the hand.

Contrarily, the AIN presents with a pure motor weakness and no sensory disturbance. There may be a history of forearm pain preceding the motor weakness. If instead there is a history of transient shoulder pain following a viral infection




Fig. 24.6, cont'd (C) Anterior interosseous nerve (AIN) syndrome is a rare compression of the motor nerve, resulting in FPL, FDP II and pronator quadratus weakness but no paresthasias. After releasing the FDS arch, the AIN is followed distally to ensure proper release.

that precedes the motor weakness, the surgeon should consider the possibility of Parsonage–Turner syndrome (brachial neuritis or neuropathic amyotrophy).^{99,100}

Clinical examination

The muscle testing of a superficialis syndrome will reveal a weakness in FPL and FDP II but, contrary to lacertus syndrome, a distinct weakness in FDS IV and no weakness in the FCR. The SCT is positive at the level of the FDS arch, and external compression over the median nerve will cause numbness in the hand. Tinel's is often positive at the same level. Superficialis sling compression of the median nerve can also be palpated internally at the time of a wide-awake lacertus

release, as described in the lacertus section above. The patient flexes the long and then the ring fingers while the surgeon has his/her fifth finger under the superficialis sling through the lacertus wound after lacertus release. Superficialis compression can be released at the time of lacertus release through a separate incision if identified with active movement during surgery.

Because the AIN innervates the FPL, FDP II–III, and pronator quadratus, patients with a complete AIN palsy should exhibit no motor function in these three muscles unless a Martin–Gruber connection or ulnar contribution to the middle finger, FDP III, is present.¹⁰¹ In incomplete AIN palsy, isolated FPL involvement is most typically observed. SCT will be positive over the branch of the AIN, about mid-forearm. Pressure over the AIN may elicit pain, but should never elicit sensory symptoms (negative Tinel's test).

Non-operative treatment

The conservative management of superficialis and AIN syndrome is identical to that of the lacertus syndrome, with a trial of steroid injections, physiotherapy, and activity-modification regimes. In the event of a Parsonage–Turner as a cause of the AIN palsy, the conservative management should also take into consideration any possible involvement of the shoulder girdle, such as adhesive capsulitis, to ensure a proper return of function in the entire upper extremity.¹⁰²

Surgical release

The surgical release of the median nerve at the level of the FDS arch is usually performed using the Zancolli mini-invasive approach⁸⁹ and following the principles of wide-awake anesthesia. Lidocaine–epinephrine 1%, 30–40 mL buffered with 2–3 mL bicarbonate, is slowly infiltrated from about 2 cm distal to the cubital fossa and about 5 cm distally and centrally in the forearm, over the level of the FDS arch. A 3-cm transverse skin incision is placed over the FDS arch. Blunt dissection is made with careful retraction of the MACN, to the lateral edge of the PT fascia that is incised, to allow medial retraction of the muscle. Between the PT and FDS, the fibrous arch is found. Then the median nerve proximal to this edge is located and the nerve followed for about 3 cm distally, to ensure complete release.


In an AIN syndrome, following the release of the FDS arch, a more distal approach is undertaken to securely identify and release the AIN distal to the bifurcation from the main median nerve. Skin closure and postoperative management follows that of the lacertus syndrome.

Ulnar nerve entrapments

Ulnar nerve compression in Guyon's canal

Background

Compression of the ulnar nerve in Guyon's canal may also be called "ulnar tunnel syndrome".¹⁰³ The most common cause of ulnar nerve compression at the wrist is external compression by a space-occupying lesion, most commonly a ganglion.¹⁰⁴ The zone within which the ganglion arises can typically be determined on the basis of patient symptoms and



Anatomy

Zone I contains both sensory fibers to the ulnar ring and little fingers and motor fibers to the hypothenars and interossei, and extends from the proximal edge of the volar carpal ligament to the bifurcation of the ulnar nerve.

Zone III is located ulnar to zone II and is bordered volarly by palmaris brevis and dorsally by the hypothenar muscles. The superficial branch contained in zone III is predominantly sensory with only a few motor fibers to palmaris brevis. Loss of palmaris brevis function is rarely, if ever, noticed by patients, and so for practical reasons the superficial branch is considered to be purely sensory.

Patients with ulnar nerve compression in Guyon's canal may present with a history of paresthesias in the small and ring fingers, ulnar-sided wrist pain, decreased grip strength, or clawing of the ring and little fingers. A history of wrist trauma, long-distance cycling, or vocational exposure to repetitive hand vibration is not uncommon. Patients with ulnar nerve entrapment at the wrist may also suffer from CTS; carpal tunnel release can often eliminate ulnar symptoms as it has been shown to decompress Guyon's canal indirectly.¹¹⁰

The manual muscle testing should include an evaluation of the FDP V to rule out a more proximal involvement of the ulnar nerve (at elbow level). Furthermore, the muscle exam will help delineate the level of Guyon's canal involvement. Weakness of the ADM is associated with a zone I entrapment; normal strength in the ADM but weakness in the first dorsal interosseus signifies a zone II entrapment.

In addition to the above testing, an Allen test should be performed to assess for potential ulnar artery thrombosis (hypothernar hammer syndrome). Palpation of the ulnar wrist may reveal a ganglion, tumor, aneurysm, or hook of hamate fracture.

Ultrasound is a useful tool in Guyon's canal entrapments as it can directly reveal potential ganglion cysts as well as evaluate the blood flow in the ulnar artery.¹¹¹ Computed tomography and magnetic resonance imaging (MRI) is of use primarily in suspected carpal fractures or in the absence of ultrasound. Electrodiagnostic tests may be an adjunct to confirm the level of entrapment,¹¹² but physical examination is the foundation for proper diagnosis.

Surgical release

Although conservative methods such as non-steroidal anti-inflammatory drugs (NSAIDs) and splinting are often an option, if an anatomic cause of nerve compression is present, surgical intervention is warranted. A 6–7-cm incision is marked between the hook of the hamate and pisiform extending into the ulnar forearm. Proximally, the FCU is retracted ulnarly to expose the ulnar artery and nerve that are then traced distally. The volar carpal ligament and palmaris brevis are incised. A careful examination is made for any ganglion or tumor. The deep motor branch is subsequently decompressed by dividing the fibrous edge of the hypothenar muscles and any fascial bands arising from the hook of hamate. The sensory branch is then traced superficial to the fibrous hypothenar arch where it is most commonly impinged upon by an aneurysm or thrombosis of the ulnar artery or a ganglion in Guyon's canal.

Postoperatively, patients are allowed to remove the dressing and shower the day after surgery. A dressing may be reapplied for padding and protection for a week. Patients can return to work when they no longer experience pain while performing their duties, usually by 8 weeks.¹¹³

Cubital tunnel syndrome

Compression of the ulnar nerve at the cubital tunnel is very common and second only to CTS in incidence. The diagnosis of cubital tunnel syndrome is primarily clinical, as electrodiagnostic tests can often be negative despite significant symptoms and exam findings.

Clinical tips

Patients can be advised that the results following cubital tunnel surgery are not as good as those following carpal tunnel surgery and that numbness (or muscle power) may not improve significantly after surgery. By performing cubital tunnel surgery, we may at least prevent further nerve damage and disease progression.

Anatomy

In the upper arm, the ulnar nerve travels posterior to the medial intermuscular septum anterior to the medial head of the triceps. The arcade of Struthers is a deep brachial fascial band that joins the intermuscular septum and invests the ulnar nerve approximately 8 cm proximal to the medial epicondyle. This is a rare but potential site of ulnar nerve compression about the elbow. The medial antebrachial cutaneous nerve passes posterior to the ulnar nerve immediately proximal to or at the epicondyle; injury to this nerve can result in significant postoperative neuroma and pain. The ulnar nerve travels posterior to the medial epicondyle and medial to the olecranon to enter the cubital tunnel. The tunnel roof comprises a tight fascial layer that extends from the FCU to the arcuate ligament of Osborne, while the floor is defined by the ulnar collateral ligament. Upon exiting the cubital tunnel, the ulnar nerve travels into the forearm between the ulnar and humeral FCU heads, then deep to the deep flexor pronator aponeurosis. The most common site of entrapment for the

cubital tunnel syndrome is at the ligament of Osborne, just distal to the medial epicondyle.²⁷

History

A thorough history should include the onset of symptoms, presence of grip or pinch weakness, numbness, aggravating and alleviating activities, comorbidities (i.e., diabetes, peripheral neuropathies), and previous elbow trauma. Perhaps the single most important feature on history, however, is the chronicity of the symptoms. Intermittent symptoms elicited by elbow flexion are likely due to transient ischemia of the nerve and will respond well to treatment. Constant numbness or weakness responds less predictably to surgery.

Clinical examination

The manual muscle testing is important to exclude more proximal nerve involvement, and should always include a thorough examination of shoulder and elbow strength. In the presence of a cubital tunnel syndrome, the focus of the muscle exam should be on the FDP V and ADM to delineate if the entrapment is at the elbow or wrist level. A cubital tunnel syndrome will correspond to a weakness of both the FDP V and ADM.

In addition to the muscle exam, the SCT is of use in staging the level of ulnar nerve entrapment at the cubital tunnel. The most common site of entrapment, and the focus of potential nerve release, is at Osborne's ligament.²⁷ The Tinel's sign is also of aid in staging the site of nerve entrapment.

Another provocative test is the elbow flexion pressure test. The sensitivity of Tinel's sign is 70%, while that of the elbow flexion pressure test is 98%.¹¹⁴ The latter test is considered positive if symptoms are elicited after 60 s of digital pressure applied over the cubital tunnel with the elbow in flexion.

Radiographs may be obtained to assess for elbow arthritis or post-traumatic deformity. Electrodiagnostic testing can be helpful to confirm the diagnosis or rule out a peripheral neuropathy or other sites of compression. An ulnar nerve motor conduction velocity across the elbow of less than 50 m/s is generally considered positive. Electrodiagnostic results must be interpreted carefully, however, as they have been shown to have a false-negative rate of more than 10% in the setting of cubital tunnel syndrome.³³ Patients with clinical symptoms but negative electrodiagnostic results should still be considered for surgical release as this renders positive outcomes and resolution of symptoms.¹¹⁵

Non-surgical treatment

Patients with mild or intermittent symptoms can often be successfully treated with local steroid injections, activity modification, splinting, and physiotherapy (nerve mobilization techniques).¹¹⁶ Nocturnal splinting to prevent elbow flexion of more than 45° can be particularly helpful. Surgical intervention should be considered if non-operative modalities fail to improve symptoms after more than 2–4 months or if symptoms worsen during the period of conservative treatment.¹¹³

Surgical release

Controversy persists as to the optimal surgical management of cubital tunnel syndrome, a fact underscored by the

numerous techniques currently used by experienced surgeons to treat the condition. These techniques include *in situ* and endoscopic decompression, submuscular transposition, intramuscular transposition, subcutaneous transposition, and/or medial epicondylectomy. Since the most common site of nerve compression is just distal to the medial epicondyle, at Osborne's ligament, our preferred approach is a simple, *in situ* decompression using wide-awake techniques.

***In situ* decompression – the authors' preferred technique**

We prefer to perform this procedure using the wide-awake approach (local infiltration without sedation or tourniquet). If the release is planned to the Osborne's ligament and distal of the medial epicondyle alone, the following is used: field infiltration of 20–40 mL of 1% lidocaine with 1:1–200 000 epinephrine buffered with 2–4 mL of bicarbonate, infiltration from the level of the sulcus to about 5 cm distal of the medial epicondyle. After waiting 20–30 min, a 3-cm skin incision is made just distal of the sulcus.¹¹⁷ Blunt dissection is made to the FCU fascia where Osborne's band is identified. Just proximal of this, the ulnar nerve can be seen and followed distally as Osborne's and other constricting bands are released (Video 24.12 )

Simple decompression

In a patient where more proximal ulnar nerve involvement is suspected, we prefer a simple decompression (videos 24.6  and 24.7) with the use of 0.5–1% lidocaine with 1:200 000 epinephrine beginning 8–10 cm proximal to the medial epicondyle to ensure anesthesia in the MACN distribution. Care should be taken to avoid branches of this nerve during subsequent dissection. Beginning proximally, the arcade of Struthers is released, followed by Osborne's ligament and the FCU fascia. The ulnar nerve is left undisturbed in its bed. The elbow is placed through a range of motion to check for any residual compression sites or subluxation of the nerve. If the latter is present, we prefer to perform a medial epicondylectomy (see below) to ensure that the ulnar nerve rolls smoothly over the medial border of the elbow.

Endoscopic decompression

Endoscopic decompression techniques make use of a small 15–35-mm incision over the ulnar nerve at the level of the condylar groove.^{118–120} Tunneling forceps are used to create a space superficial to the fascia covering the nerve and deep to the subcutaneous tissue. An endoscope is placed in this space and blunt scissors used to release any points of constriction over the nerve under direct visualization.

Submuscular–subcutaneous transposition

With elbow flexion, the ulnar nerve is placed under tension and compression as the cubital tunnel volume decreases. The goal of transposition is to move the nerve anterior to the axis of elbow flexion, thereby decreasing tension on the nerve. Critics of this technique feel that dissection of the nerve from its bed compromises the segmental blood supply of the nerve.¹²¹

In the submuscular transposition, the proximal nerve is identified and traced distally following release of the arcade of Struthers. To prevent the formation of a new compression

site proximally, a segment of the intramuscular septum is excised. The nerve is then unroofed to the level of the deep flexor pronator aponeurosis. The nerve is dissected free from its bed and transposed anterior to the medial epicondyle. The motor branches to the FCU and the FDP are preserved. The flexor pronator muscle mass is divided 1–2 cm distal to the medial epicondyle. The median nerve must be identified and preserved. The flexor pronator mass is repaired over the transposed nerve with a stepwise lengthening technique to avoid causing a new compression site.

In the subcutaneous transposition, instead of elevating the flexor pronator mass, the ulnar nerve is instead maintained in its transposed position by suturing the loose epineurium to the forearm fascia.

Medial epicondylectomy

The medial epicondylectomy technique is primarily used following a simple decompression with a tendency for ulnar nerve subluxation. The principles of anesthesia and nerve release follow that of the simple decompression. The medial epicondyle is exposed in a subperiosteal plane, maintaining the origin of the flexor pronator mass with the periosteum. The anteromedial edge of the epicondyle is scored with an osteotome. The epicondylectomy is performed along a plane midway between the sagittal and coronal planes of the humerus, all the while preserving the attachments of the ulnar collateral ligament. The flexor pronator origin is then reattached over the epicondylectomy site¹¹³ (Fig. 24.8).

Outcomes and complications

Controversy over the optimal operative management of cubital tunnel syndrome is ongoing, with numerous comparative studies demonstrating no statistical difference in outcomes with any given technique. Simple decompression has been shown to be effective in treating cubital tunnel syndrome, with results equivalent to those of anterior transposition.^{122–124} Goldfarb *et al.* recently demonstrated a 93% success rate with *in situ* decompression.¹²⁵ Similarly, a retrospective study comparing medial epicondylectomy alone with medial epicondylectomy and anterior subcutaneous transposition showed no statistical differences.¹²⁶

Recurrent or unrelieved symptoms are much more frequent than with CTS. Predictors of revision surgery include previous elbow fractures and should be assessed for prior to planning surgery.¹²⁷ The posterior branch of the MACN is at potential risk of injury, and can result in a painful neuroma and hyperesthesia.¹²⁸ Ulnar nerve subluxation following simple decompression can lead to persistent pain. Hematoma is more frequently observed following the endoscopic technique than open approaches.^{119,120} Medial epicondylectomy is complicated by persistent elbow pain in up to 45% of patients.¹²⁹

Radial nerve entrapments

The radial nerve originates from the posterior cord in the brachial plexus. It traverses posterior of the shoulder and upper arm, transverses into the anterior compartment through the lateral intermuscular septum (LIS) in the distal




Fig. 24.8 Medial epicondylectomy technique. **(A)** The ulnar nerve is protected while the common flexor pronator origin is elevated from the medial epicondyle. **(B)** The proper plane of the osteotomy is between the sagittal and coronal planes.

forearm and continues deep under the brachioradialis (BR) where it divides into the posterior interosseous nerve (PIN) and sensory branch of the radial nerve (SBRN). Along its course, the radial nerve may become compressed at two locations in the upper arm, three in the forearm, and one at the wrist. In this section, we will describe four of the more common radial nerve entrapments encountered: two in the upper arm – triangular interval syndrome and lateral intermuscular syndrome; one in the forearm – radial tunnel syndrome (PIN entrapment); and Wartenberg syndrome (SBRN entrapment).¹⁷

Wartenberg's syndrome – entrapment of the SBRN

Anatomy

The SBRN travels down the forearm immediately deep to the BR. It emerges into the subcutaneous plane approximately 9 cm proximal to the radial styloid by passing between BR and extensor carpi radialis longus (ECRL) (Fig. 24.9). It is at this arcade that the nerve becomes compressed. The SBRN provides sensation to the dorsum of the three radial digits to the level of the proximal interphalangeal joints.

History and clinical examination

Patients with Wartenberg's syndrome report isolated pain or dysesthesias over the dorsoradial aspect of the hand. The presence of motor weakness suggests a more proximal site of compression. There may be a preceding history of trauma to the area (i.e., handcuffs, forearm fracture). It is important to differentiate Wartenberg's syndrome from de Quervain's tenosynovitis, as both may present with radial wrist pain.¹³⁰ Since Finkelstein's test will elicit pain in both of these diagnoses, it may further lead to a misinterpretation of symptoms.¹³¹ The key differences between the two lie in the presence of a positive Tinel's test at the BR–ECRL arcade in Wartenberg's syndrome and no pain upon palpation of the first dorsal extensor compartment.¹³² A positive SCT will usually also be present at the level of the BR–ECRL arcade.

Non-surgical treatment

Spontaneous resolution of symptoms is common in Wartenberg's syndrome. Indeed, many cases respond by simply eliminating the inciting factor, such as a tight watchband or bracelet. Rest, splinting, and NSAIDs are also effective. Evidence to support the use of corticosteroids is limited and should be considered carefully, as steroid injections at this level may cause subcutaneous and skin atrophies.¹³³

Surgical release

In patients who fail to respond to conservative treatment, surgical decompression may be considered. Wide-awake surgical technique using 10–20 mL lidocaine–epinephrine is advantageous as the patient then can cooperate during surgery to ensure proper gliding of the SBRN following release. A longitudinal incision is made from 5 cm proximal of the radial styloid and 4–5 cm proximally, making sure to stay slightly volar to the Tinel's sign, thereby avoiding injury to the lateral antebrachial nerve and preventing tethering of the incision scar over the superficial radial nerve. The fascia between the brachioradialis and ECRL is divided and the superficial radial nerve carefully freed from its bed. At times, a radial slip of the BR tendon must be removed to allow adequate passage of the nerve. In addition to nerve gliding, postoperative care may involve a desensitization program. An overall success rate of 74% has been reported following surgical decompression.¹³⁰




Fig. 24.9 Anatomy of the superficial sensory branch of the radial nerve. The fascia between the extensor carpi radialis longus and brachioradialis is released in patients with Wartenberg's syndrome.

Radial tunnel syndrome – PIN compression in the proximal forearm

Radial nerve entrapment in the proximal forearm, at the arcade of Frohse, the fibrous proximal edge of the supinator muscle,¹³⁴ is referred to by several names: radial tunnel syndrome (RTS); posterior interosseous nerve (PIN) syndrome; and supinator syndrome. Regardless of label, this compression signifies an entrapment of the PIN.

Anatomy

The PIN arises from the bifurcation of the radial nerve in the proximal forearm. The PIN has traditionally been considered a “pure motor nerve”, which is not entirely correct. While it is true that the PIN contains the motor innervation to the forearm extensors distal to the elbow and the abductor pollicis longus, the terminal branch of the PIN contains important sensory innervation of the dorsal wrist joint,¹³⁵ and is a source of both proprioceptive¹³⁶ and nociceptive¹³⁷ afference from the wrist.

The PIN does not innervate the ECRL, ECRB, BR, or anconeus muscles; these muscles instead receive their innervation from the main radial nerve. Immediately distal to the bifurcation, the PIN travels through the radial tunnel, a 5-cm space originating at the level of the radiocapitellar joint and traversing between the superficial and deep layers of the supinator muscle.¹³⁸

Within the area of the radial tunnel there are described five potential sites of compression: (1) fibrous bands to the radiocapitellar joint between the brachialis and brachioradialis; (2) the recurrent radial vessels, or so-called leash of Henry; (3) the proximal edge of the ECRB; (4) the proximal edge of the supinator, or so-called arcade of Frohse; and (5) the distal edge of the supinator. The arcade of Frohse is by far the most common site of PIN compression, where high pressures (up to 200 mmHg) on the nerve may be elicited during active contraction of the supinator muscle.¹³⁹ Compression of the PIN at the distal edge of the supinator is exceedingly rare and should be considered an entirely separate nerve entrapment as it presents with completely different symptoms than the RTS.

History

RTS is frequently found in conjunction with, or misdiagnosed as, lateral epicondylitis,¹⁴⁰ with a reported prevalence of 95% failed epicondylitis-treated patients in a series of surgically released RTS.²³ It is not uncommon that both conditions may exist in the same patient, and in our experience, RTS should always be considered in cases where lateral epicondylitis patients have failed to respond to conservative treatments.

The most common complaint in RTS is pain in the dorsal and proximal aspect of the forearm, with pain presenting primarily after exertion and at night. In lateral epicondylitis, tenderness is localized to the ECRB insertion, while in radial tunnel syndrome the point of tenderness is 3–4 cm distal over the mobile wad.¹⁴¹ In a retrospective review of surgically treated RTS, the syndrome was found to be more common in men, manual workers, and affecting the dominant hand.²³

Clinical examination

The most superficial fascicle in the radial nerve at the level of the arcade of Frohse is the branch to the ECU.⁵ Based on this, the testing of strength in the ECU has been reported as a reliable clinical test (video 24.8 ▶).^{142,143} With the patient seated, shoulder at 90° elevation and extended elbow, the patient ulnarly deviates the wrist. The examiner places one hand over the radial aspect of the distal radius, the other on the ulnar side of the hand, and then asks the patient to resist as the examiner radially deviates the wrist.²³ Always compare the strength in the healthy arm before testing the affected arm to facilitate examination and diagnosis. SCT is positive at the level of the arcade of Frohse, about three fingerbreadths distal to the lateral epicondyle, and pain upon compression is evident at the same level.

Clinical tips

In a patient with chronic lateral epicondylitis, “tennis elbow”, that fails to respond to conservative treatments, always test the strength of the extensor carpi ulnaris (ECU). Weakness of the ECU is indicative of a radial tunnel syndrome, a diagnosis that is a source of pain in the lateral elbow and proximal forearm and frequently misdiagnosed as lateral epicondylitis.

Non-operative treatment

An initial treatment of local corticosteroid at the level of the arcade of Frohse may be therapeutic. Indeed, one study showed a 72% response rate to local injection in patients with radial tunnel syndrome at 6 weeks of follow-up; in the majority of these responders, pain relief persisted for more than 2 years.¹⁴⁴ Conservative management such as avoidance of aggravating activities, hand therapy management (stretching, nerve gliding, splinting), adaptation of the workplace, and use of NSAIDs have been shown to be helpful.¹⁴⁵

Surgical release

Surgery is recommended for RTS if there is no appreciable improvement in motor function by 2–3 months, or even earlier in cases of nocturnal and residual pain. Our preferred technique for is the posterior approach, as this allows an easy exposure of the proximal edge of the supinator, ability for possible concomitant release of a tense ECRB edge, and results in more aesthetically pleasing scars as compared to the volar approach (Fig. 24.10).

The procedure is usually done in general anesthesia and using a tourniquet. However, the wide-awake approach is also possible. If performing a wide-awake release, 20–30 mL lidocaine–epinephrine should be infiltrated in the dorsal proximal forearm, from just distal to the lateral epicondyle

and about 5 cm distally and obliquely. We also inject 10 mL lidocaine–epinephrine in the volar aspect of the brachioradialis muscle, over the volar aspect of the radial nerve, to block possible pain sensation when releasing the PIN toward the volar aspect of the supinator.

An oblique dorsal incision is made distal to the lateral epicondyle. Following incision of the forearm extensor fascia, blunt dissection is performed between the ECRB/L, and the muscles retracted. Identify the SBRN and follow this proximally to the radial nerve bifurcation to identify the PIN. This can then be followed distally, to the point where it enters into the arcade of Frohse, beneath the proximal edge of the supinator. Release 2–3 cm of the proximal supinator fascia to complete the neurolysis. Immediate mobilization is encouraged, but limited to 1 kg loading during the first 2 weeks postoperatively. Full load is generally allowed 4 weeks postoperatively.

Outcomes following surgery

Hashizume *et al.* demonstrated full recovery in 16 of 17 patients who underwent surgical decompression of the PIN after symptom onset.¹⁴⁶ Hagert and Hagert reported complete return of ECU strength and pain relief in 40 of 45 patients released (88%).²³ Interestingly, Simon Perez *et al.* reported identical results in their recent publication, with good to excellent results in 37 of 42 patients (88%).¹⁴⁷

In their systematic review of observational studies, Huisstede *et al.* noted the success of surgical decompression ranged from 67% to 92%.¹⁴⁸ This variability in success rates may be due in part to the presence of concomitant lateral epicondylitis in some patients; other studies have shown poorer outcomes among patients with coexistent lateral epicondylitis.^{140,149}

Lateral intermuscular syndrome – radial compression in the distal upper arm

Anatomy

In the distal upper arm, as the radial nerve passes from the dorsal to the volar compartment of the upper arm, it passes through the LIS. This septum is a taut fascia, covering the lateral aspect of the humerus from the deltoid insertion proximally, to the lateral epicondyle distally. The radial nerve pierces the LIS approximately 10 cm proximal to the lateral epicondyle¹⁵⁰ to exit between the brachialis and BR volarly (Fig. 24.11).

History and clinical examination

The primary complaint is of an aching pain in the distal, lateral upper arm.¹⁵¹ The pain is usually aggravated with physical exertion, such as repetitive elbow extension/flexion. This type of radial nerve entrapment is most commonly encountered in manual laborers and athletes.^{151,152}

When performing the muscle exam, a pattern of muscle weakness involving wrist extension and thumb/index finger extension is found (video 24.9 ●). It is important to thoroughly examine the triceps strength, as simultaneous weakness of the triceps will denote a more proximal radial nerve involvement. Positive SCT is found where the radial nerve pierces the septum, about 10 cm proximal of the lateral epicondyle. The level of positive SCT and maximum point of tenderness upon




Fig. 24.10 The posterior approach to the radial tunnel. The plane between the extensor carpi radialis and longus is developed. The proximal edge of the supinator is released, slightly to the side of the nerve to avoid direct scarring. ECRB, Extensor carpi radialis brevis; ECRL, extensor carpi radialis longus.




Fig. 24.11 The anatomy of the radial nerve in the upper arm. Proximally, the radial nerve enters into the triangular interval, bordered by the teres major cranially, the long head of triceps medially and the lateral head laterally. Distally, the radial nerve passes through the lateral intermuscular septum to exit between the brachialis and brachioradialis.

compression over the nerve will guide the surgeon in planning the level of surgical release.

Non-surgical treatment

In an acute onset of lateral upper arm pain and weakness, a resolution of symptoms can be expected with local steroid injections, NSAIDs, activity modifications, and rest. In a majority of patients, the onset of symptoms is more gradual. Conservative management should always be attempted before proceeding to surgical release.

Surgical release

The procedure is usually done under general anesthesia. The use of a tourniquet is optional, but generally facilitates the

surgical procedure. The skin incision is planned from about 5 cm proximal of the lateral epicondyle and about 10 cm in a proximal direction. Perform blunt dissection to the triceps, incise the fascia, and retract the muscle posteriorly. Identify the posterior antebrachial cutaneous nerve in the distal aspect of the wound, superficial to the fascia. Follow the cutaneous nerve proximally, as it will lead to the radial nerve. After identifying the bifurcation, the main radial nerve can be followed distally while releasing constricting fibrous bands compressing the nerve at the LIS.¹⁷ The patient is allowed to start immediate motion without load to allow nerve gliding through the septum. Manual work is restricted until 4–6 weeks postoperatively.

Triangular interval syndrome – radial compression in the proximal upper arm

Anatomy

In the proximal upper arm, just distal to the shoulder girdle, the radial nerve passes through the triangular interval that is bordered medially by the long head of the triceps, laterally by the lateral head of the triceps, and by the teres major cranially (Fig. 24.11). Entrapment of the radial nerve at this level is relatively rare but has been described in physically active adults,¹⁵³ and is sometimes referred to as the triangular interval syndrome (TIS).¹⁵⁴

History and clinical examination

Pain of a dull and aching character located to the dorsolateral aspect of the upper arm, slightly distal to the axilla, is the principal symptom in radial nerve entrapment at this level. The patient may describe worsening of pain following strenuous use of the triceps, either in relation to work or athletic activity. Nocturnal pain is common. Intermittent paresthesias in the dermatome of the radial nerve, from the upper arm into the forearm, may also occur.

Like the lateral intermuscular syndrome described above, the manual muscle testing will reveal weakness of wrist and finger extension, but also when testing the strength in the triceps. The triceps is examined with the patient in a seated position, adducted arms and elbows flexed to 90°. The examiner holds underneath the forearms of the patient from behind, while the patient tries to push the arms beyond 90° flexion. If the symptoms have persisted over time, electrodiagnostic examinations can be helpful to reveal EMG changes in the triceps indicative of a proximal radial nerve entrapment.

Non-surgical treatment

As with other radial nerve entrapments, the principal of conservative management includes local steroid injections at the site of the triangular interval, activity modifications, and physiotherapy. In a majority of instances, the conservative management will be successful in resolving the pain.

Surgical release

If the patient has failed conservative management for about 3 months and pain is persistent, surgical management is indicated.

In general anesthesia and with the patient in a semi-prone position, a dorsolateral skin incision is performed from the distal edge of the deltoid and about 5–6 cm distally. If the patient has a concomitant axillary nerve entrapment, the skin incision used for the axillary release may be extended distally. The edge of the posterior deltoid muscle is identified as the most superficial and cranial muscle. By lifting this edge, the teres major (TMa) can be identified underneath. The radial nerve is seen just distal to the edge of TMa, before it enters into the triangular interval. A muscular septum connecting the lateral and long heads of the triceps is the primary cause of compression at this level. The fascial edge is released while carefully protecting the radial nerve. Skin closure and postoperative management is identical to that described in the lateral intermuscular syndrome.

Clinical tips

In a patient with clinical signs of high radial nerve involvement (weakness in the triceps, wrist and finger extension, paresthesias in the radial innervated region), always perform a muscle exam to test the strength in shoulder abduction. Concomitant axillary nerve entrapment and high radial nerve entrapment may exist and should be treated simultaneously.

Other nerve compressions of the upper extremity

Axillary nerve entrapment

Anatomy and etiology

The quadrilateral space (QS) is defined by the teres minor (TMi) superiorly, the neck of the humerus laterally, the long head of triceps medially, and the upper border of TMa inferiorly (Fig. 24.12). The axillary nerve and the posterior circumflex humeral artery (PCHA) travel through this space. In the QS, the nerve branches into an anterior division that innervates the middle and anterior deltoid, and a posterior division. The posterior division supplies motor innervation to the posterior deltoid and TMi and is the portion most commonly compressed.

Reported causes of entrapment include ganglion, muscle hypertrophy, scapular fracture, and glenoid labral cysts; however, fibrous bands are the most common cause of compression.^{155–159} Compression of the axillary nerve in the QS is a nerve compression most commonly found in young active adults, such as overhead-throwing athletes.^{160,161} Axillary nerve compression has also recently been highlighted as a possible cause of shoulder pain in spinal cord-injured patients where manual wheelchair propulsion appears to predispose to hypertrophy and scarring of the quadrilateral space.¹⁶²




Fig. 24.12 Anatomic boundaries and contents of the quadrilateral space.

History

Patients with QS syndrome present with a gradual increase in diffuse pain over the posterior aspect of the shoulder, commonly nocturnal pain with an inability to sleep on the affected shoulder. Paresthesias over the deltoid may also be a complaint, as is a feeling of weakness in shoulder strength and endurance.^{17,163}

Clinical examination

The manual muscle testing will reveal a weakness in the posterior deltoid when comparing to the contralateral side (video 24.10 ▶). With the patient seated, arms elevated to 90° and slightly abducted, the patient is asked to resist as the examiner pushes on the forearms inward. It is important to rule out weakness of the pectoralis, as combined weakness of pectoralis and posterior deltoid is indicative of a brachial plexus affliction. Furthermore, strength in the infraspinatus should be tested, as a combined posterior deltoid and infraspinatus weakness indicates a C5/C6-radiculopathy, or a combined axillary and suprascapular compression, rather than an isolated axillary nerve entrapment (Fig. 24.13).

When performing the SCT test, scratching posteriorly over the QS may elicit a positive response. Tenderness is usually noted over the QS posteriorly. In severe cases, wasting of the deltoid may be present.

Other diagnostic tools

EMG has been shown to be insensitive but specific for QS syndrome.¹⁶⁴ Originally, angiography was considered the investigation of choice, as PCHA occlusion was considered pathognomonic of the condition.¹⁶³ However, as fibrous bands and scarring are the most common cause of entrapment, angiography is usually negative. MRI findings of TMi atrophy and presence of fatty infiltrations may also confirm the diagnosis.^{165,166} Recently, the use of ultrasound to look for fatty infiltrations in the TMi and performing Doppler examination of the PCHA has been advocated as a reliable and cost-effective modality.¹⁶⁷



Fig. 24.13 Clinical image. Patient with right-sided supraspinatus (arrows) and posterior deltoid (arrowheads) atrophy due to C5–C6 radiculopathy.

Non-surgical treatment

In cases of early onset QS syndrome, an initial trial of steroid injections, activity modifications, NSAIDs, and strengthening exercises are often effective in relieving pain and restoring function. In patients with significant deltoid atrophy or with a clear structural compression, however, a surgical approach is indicated.

Surgical release

In a recent review of QS syndrome, it has been suggested that it should be separated into a neurogenic and a vascular syndrome depending on the cause of compression.¹⁶⁸ In the instance of a vascular etiology, a ligation of the artery with or without thrombolysis is advocated.

Since the neurogenic component with fibrous entrapment of the axillary nerve is most commonly seen, a nerve release in the QS is our treatment of choice (video 24.10 ▶).¹⁷

In general anesthesia and with the patient in a lateral, or three-quarters prone, position, a 10-cm dorsal skin incision is made along the inferior border of the posterior deltoid. Perform blunt dissection to the posterior deltoid and lift the posterior edge. The TMi will be seen underneath. Locate and release the axillary nerve branch innervating the TMi, then follow this branch toward the axilla, as it will facilitate identification of the axillary nerve as it exits the QS. Release the fibrous bands around the nerve but be cautious as the PCHA is adjacent to the nerve. The patient is allowed to start immediate motion without load; full load is allowed 4–8 weeks postoperatively.

Musculocutaneous nerve compression

Anatomy and etiology

The musculocutaneous nerve arises from the lateral cord of the brachial plexus. Shortly after its origin, it innervates the coracobrachialis muscle. The musculocutaneous nerve then pierces through a tight muscle fascia to innervate the biceps brachii and brachialis muscle. Where the musculocutaneous nerve pierces through the fascia between the coracobrachialis and short head of the biceps is a potential site of nerve entrapment.^{169,170} The terminal branch of the musculocutaneous nerve is the lateral antebrachial cutaneous nerve, which pierces through the distal fascial edge of the biceps, just proximal of the elbow, providing sensation in the volar lateral aspect of the forearm.

Isolated entrapment of the musculocutaneous nerve is a relatively rare clinical entity. It has been reported as a complication following shoulder arthroscopy and proximal biceps tenodesis,^{171,172} as well as a complication following heavy weightlifting or strenuous overuse of the biceps.^{173,174}

History and clinical examination

The patient usually presents with a complaint of arm weakness, at times upper arm pain and paresthesias in the lateral forearm.

Clinically, bilateral testing of biceps strength will reveal a weakness on the affected side. SCT may be positive where the musculocutaneous nerve passes between the coracobrachialis and biceps brachii, about 8–10 cm distal to the shoulder joint.



Fig. 24.14 Clinical image. Patient with right-sided biceps (arrows) atrophy due to musculocutaneous nerve entrapment. (Reprinted with kind permission from Prof. Carl-Göran Hagert, MD, PhD.)

Pain upon compression at this site may elicit painful paresthesias into the forearm. EMG is helpful to determine possible atrophy of the biceps muscles (Fig. 24.14). In the event of normal biceps strength but paresthesias in the volar lateral forearm, an isolated entrapment of the lateral antebrachial cutaneous nerve should be suspected.¹⁷⁵ If a biceps weakness is found in combination with weakness of the pectoralis and posterior deltoid, a more proximal brachial plexus entrapment is probable.

Non-surgical treatment

The choice to treat conservatively is based on the degree of biceps involvement. In early stages of entrapment, a conservative regime of NSAID and activity modifications are usually sufficient.

Surgical release

Should atrophy of the biceps muscles be evident, clinically and/or at EMG, surgical release of the musculocutaneous nerve is indicated.

With the patient in a supine position, shoulder abducted, an incision is made from about 2 cm distal to the coracoid process and about 10 cm distally into the upper arm. The distal edge of the pectoralis minor is elevated to reveal the coracobrachialis muscle. At this level, the bifurcation of the musculocutaneous nerve and lateral cord to the median nerve can be identified. By following the musculocutaneous nerve through the coracobrachialis, the tight fibrous bands over the nerve and between the coracobrachialis and biceps brachii can be released. Skin closure and postoperative management includes early range-of-motion exercises but refraining from elbow flexion with load during the first 4–8 weeks.

Suprascapular nerve compression

Anatomy and etiology

Although compression of the suprascapular nerve is considered a rare entity and a diagnosis of exclusion,¹⁷⁶ this nerve entrapment has received much attention in recent years as a cause of shoulder pain in elite athletes. With the advent of arthroscopic management of suprascapular nerve entrapments, this rare nerve compression syndrome has become among the most published nerve disorders in the past 3 years.

From its origins from the upper trunk of the brachial plexus, the suprascapular nerve courses through the posterior cervical triangle to reach the suprascapular notch (Fig. 24.15).

The suprascapular notch is found medial to the coracoid process and bordered superiorly by the transverse scapular ligament. Recent investigations into the anatomy of the transverse scapular ligament has this as a primary source of nerve compression.¹⁷⁷ After innervating the supraspinatus muscle, the nerve reaches the spinoglenoid notch at the lateral base of the scapular spine. This is bordered by the spinoglenoid ligament, and serves as a second common site of suprascapular nerve compression.^{178,179}

History and clinical examination

Suprascapular compression neuropathy should be suspected in younger athletes, in particular overhead-throwing athletes, or laborers who perform repetitive overhead activities. The most common causes of suprascapular compression is trauma, inflammation, pressure from ganglion cysts, or in relation to rotator cuff injuries.¹⁸⁰ Patients commonly present with dull




Fig. 24.15 Anatomy of the dorsal scapular and suprascapular nerves. The dorsal scapular nerve passes underneath the medial scalene muscle and more distally, just underneath the proximal edge of the rhomboids, medial to the medial upper corner of the scapula. Both muscles can compress the dorsal scapular nerve. The suprascapular nerve passes under the transverse scapular ligament and through the suprascapular notch. Similarly, the spinoglenoid notch is covered by the spinoglenoid ligament. Both ligaments can compress the suprascapular nerve.

posterolateral shoulder pain and dysfunction. The diagnosis can be delayed by months as treatment is erroneously directed towards the cervical spine, rotator cuff, or glenohumeral joint.

The clinical examination should include muscle testing of the infraspinatus, where weakness in external shoulder rotation is evident. Supraspinatus strength may also be reduced and is tested with the shoulder abducted to 60° as the patient tries to resist and adduction motion by the examiner. Supraspinatus strength is, however, rather difficult to assess as deltoid function often masks an underlying supraspinatus weakness. In advanced cases, infra- and supraspinatus atrophy may be evident. SCT may be positive over the suprascapular notch, and pain may be exacerbated by arm adduction and internal rotation that tighten the spinoglenoid ligament.¹⁸¹

Other diagnostic tools

MRI studies are the primary imaging modality in suprascapular entrapments as they can reveal atrophy and fatty infiltration in the infraspinatus, as well as concomitant rotator cuff injuries.¹⁸² Ultrasound may also be of use to examine for possible presence of ganglion cysts and changed, hypoechoic, appearance in the suprascapular nerve.¹⁸³ EMG studies may also be obtained but carry an increased rate of false-negative and -positive findings,¹⁸⁴ and is not found to correlate to outcomes of treatment.¹⁸⁰

Non-surgical treatment

Most patients with suprascapular neuropathy have an underlying etiology of overuse, and activity modification, NSAIDs, and strengthening exercise is adequate to relieve pain and restore function in up to 80% of patients.¹⁸⁵ If a ganglion cyst is the cause of nerve entrapment, an ultrasound-guided aspiration of the cyst may relieve the symptoms.¹⁸⁰ In patients with significant muscle atrophy or with a clear structural compression, however, a non-surgical approach is unlikely to be of benefit and may in fact lead to further dysfunction.¹⁸⁶

Surgical release

Traditionally, the suprascapular notch has been decompressed via a trapezius-splitting incision along the scapular spine.¹⁸⁷ Although the arthroscopic approach carries with it a learning curve,¹⁸⁸ the advantages with smaller incisions and visualization of the suprascapular nerve is now rendering arthroscopic suprascapular nerve release the treatment of choice. Iannotti and Ramsey have described the arthroscopic decompression of the suprascapular nerve at the spinoglenoid notch.¹⁸⁹ Bhatia and colleagues have recently demonstrated an arthroscopic approach to release both suprascapular and spinoglenoid notch.¹⁹⁰ Several long-term studies are showing favorable results with arthroscopic release, both with regard to pain relief, return to activities, and normalization of EMG.¹⁸⁰

Dorsal scapular nerve compression

Anatomy and etiology

The dorsal scapular nerve originates from the C5 root, just proximal to the upper cord of the brachial plexus. The nerve pierces the middle scalene muscle, a potential point of

compression, to pass posteriorly beneath the levator scapulae, which it innervates (see Fig. 24.15). After the levator, the nerve passes beneath the proximal edge of the rhomboid major, just medial to the medial upper corner of the scapula, at which point the nerve is most commonly entrapped.¹⁹¹

Although a rare entrapment, compression of the dorsal scapular nerve should be recognized as a cause of unilateral interscapular pain and discomfort. Some authors believe the presence of the dorsal scapular nerve entrapments to be grossly underestimated.^{191,192} The most common cause of entrapment is related to traction injuries of the neck, repetitive overhead exertions, or direct pressure on the nerve.¹⁹²⁻¹⁹⁴ Recently, dorsal scapular nerve entrapment has been recognized as a source of interscapular pain in spinal cord-injured patients.¹⁶²

History and clinical examination

The clinical presentation is one of gradual onset of dull pain along the medial border of the scapula, at times radiating into the posterior neck.¹⁹⁵ Paresthesias are not a common finding as the dorsal scapular nerve is primarily a motor nerve.

The most common clinical finding is a subtle lateralization of the scapula, giving an appearance of mild scapular winging.^{193,196} Winging may become more noticeable as the arm is lowered from an elevated position.¹⁹⁷ SCT may be positive just medial to the medial upper corner of the scapula, where the nerve moves underneath the proximal edge of the rhomboids. Pain is usually evident upon compression at this level. It is important to test the strength in the infraspinatus as concomitant scapular winging and infraspinatus weakness may be a sign of C5-radiculopathy. Electrodiagnostics may be of use, but the accuracy of these studies is limited to about 50%.¹⁹²

Non-surgical treatment

As with the suprascapular nerve entrapment, patients with dorsal scapular nerve involvement frequently have a history of overhead overuse, and activity modifications, strengthening exercises of the rhomboids, and local steroid injections can provide resolution of symptoms.

Surgical release

Before planning a release of the dorsal scapular nerve, it is important to delineate if the primary point of compression is at the middle scalene muscle or at the proximal edge of the rhomboid muscles. In the former, a complete division of the middle scalene muscle has been advised with good resolution of symptoms. In our experience, the latter is more common and will be described below.

The surgical release at the level of the medial scapular corner is suitable for the wide-awake approach. With the patient in a lateral position, the affected scapula upward, an infiltration of 40 mL lidocaine–epinephrine is performed from the cranial edge of the levator scapulae to 3–5 cm caudal of the upper medial scapular corner. A straight incision is made on the medial upper aspect of the scapula. Identify the levator scapulae and lift the distal edge to identify the cranial border of the rhomboid major muscle. Here, the dorsal scapular nerve rides around the medial upper corner of the scapula, about 1.5 cm from the medial edge,¹⁹⁸ and beneath the tight

fascial edge of the rhomboids. The fascial edge is released and the patient is asked to actively move the scapula to ensure proper nerve gliding.

Future directions

Since electrodiagnostics are frequently inaccurate in diagnosing entrapments other than carpal or cubital tunnel syndromes, a combination of thorough clinical examination (manual muscle testing, SCT, and provocative tests) must be the foundation for a proper diagnosis and treatment. This chapter on nerve compressions has focused on recognizing the importance of clinical examination skills in patients with upper extremity pain and/or dysfunctions. One future challenge lies in constructing clinical studies reporting on the efficacy of

various diagnostic algorithms and subsequent conservative and/or surgical treatments.

The advent of higher-resolution MRIs (8-Tesla) and refined ultrasound techniques will likely become increasingly important diagnostic tools in nerve entrapment syndromes, with a higher accuracy to find fatty muscle infiltrations due to disrecreet denervations, changes in nerve echogenicity and the presence of possible externally compressing factors.

The area of nerve compression syndromes offers the curious researcher and clinician ample opportunity to investigate, explore, and discover. As the 1906 Nobel Prize winner Dr. Santiago Ramón y Cajal wrote, “Even granting that the genius subjected to the test of critical inspection emerges free from all error, we should consider that everything he has discovered in a given domain is almost nothing in comparison with what is left to be discovered.”



Access the complete reference list online at

<http://www.expertconsult.com>

4. Hagert E. Clinical diagnosis and wide-awake surgical treatment of proximal median nerve entrapment at the elbow: a prospective study. *Hand (N Y)*. 2013;8:41–46. *This article provides a detailed review of the lacertus syndrome and outcomes following minimal nerve release in 44 patients.*
5. Sunderland S. The intraneural topography of the radial, median and ulnar nerves. *Brain*. 1945;68:243–299. *The original work highlighting the nerve anatomy and internal topography, which is essential in understanding patterns of muscle weakness in patients with nerve entrapments.*
6. Upton AR, McComas AJ. The double crush in nerve entrapment syndromes. *Lancet*. 1973;2:359–362.
7. Mackinnon SE. Double and multiple “crush” syndromes. Double and multiple entrapment neuropathies. *Hand Clin*. 1992;8:369–390. *A comprehensive review of double-crush syndrome and the use of careful clinical examination to elicit symptoms in patients.*
18. Tang DT, Barbour JR, Davidge KM, et al. Nerve entrapment: update. *Plast Reconstr Surg*. 2015;135:199e–215e. *The most recent review of nerve entrapment pathophysiology in relation to clinical concepts.*
21. Tapadia M, Mozaffar T, Gupta R. Compressive neuropathies of the upper extremity: update on pathophysiology, classification, and electrodiagnostic findings. *J Hand Surg Am*. 2010;35:668–677. *This article summarizes the current developments in the basic science of chronic nerve compression and provides a review of the double-crush phenomenon as well as electrodiagnostic tests.*
23. Hagert CG, Hagert E. Manual muscle testing – a clinical examination technique for diagnosing focal neuropathies in the upper extremity. In: Slutsky DJ, ed. *Upper Extremity Nerve Repair* – *Tips and Techniques: A Master Skills Publication*. Rosemont, IL: The American Society for Surgery of the Hand; 2008:451–466. *This book chapter summarizes the use of the manual muscle testing technique to diagnose upper extremity nerve entrapments.*
34. Bickel KD. Carpal tunnel syndrome. *J Hand Surg Am*. 2010;35:147–152. *This review examines the ongoing challenges in developing clinical criteria for the diagnosis of carpal tunnel syndrome as well as reviewing current treatment approaches.*
69. Lalonde D, Bell M, Benoit P, et al. A multicenter prospective study of 3,110 consecutive cases of elective epinephrine use in the fingers and hand: the Dalhousie Project clinical phase. *J Hand Surg Am*. 2005;30:1061–1067. *This article firmly established the safe use of epinephrine in hand surgery, launching the concept of wide-awake hand surgery in clinical practice.*
70. Leblanc MR, Lalonde J, Lalonde DH. A detailed cost and efficiency analysis of performing carpal tunnel surgery in the main operating room versus the ambulatory setting in Canada. *Hand (N Y)*. 2007;2:173–178. *The authors examine the benefits of the wide-awake approach to carpal tunnel release compared to carpal tunnel surgery performed in the main operating suite under general anesthesia in terms of cost and overall efficiency. The wide-awake approach to carpal tunnel release allows the hand surgeon to improve productivity without compromising patient safety or outcomes.*
198. Tubbs RS, Goodrich D, Watanabe K, et al. Anatomic landmarks for selected nerves of the head, neck, and upper and lower limbs. In: Tubbs RS, ed. *Nerves and Nerve Injuries*. New York, NY: Elsevier; 2015:575–588. *This chapter provides a comprehensive and illustrative review of peripheral nerve anatomy in relation to surface landmarks, a practical guide to surgeons treating nerve entrapment syndromes.*

References

- Mackinnon SE, Dellon AL, Hudson AR, et al. Chronic human nerve compression – a histological assessment. *Neuropathol Appl Neurobiol*. 1986;12:547–565.
- Gupta R, Steward O. Chronic nerve compression induces concurrent apoptosis and proliferation of Schwann cells. *J Comp Neurol*. 2003;461:174–186.
- Gupta R, Rummeler LS, Palispis W, et al. Local down-regulation of myelin-associated glycoprotein permits axonal sprouting with chronic nerve compression injury. *Exp Neurol*. 2006;200:418–429.
- Hagert E. Clinical diagnosis and wide-awake surgical treatment of proximal median nerve entrapment at the elbow: a prospective study. *Hand (N Y)*. 2013;8:41–46.
- Sunderland S. The intraneural topography of the radial, median and ulnar nerves. *Brain*. 1945;68:243–299. *The original work highlighting the nerve anatomy and internal topography, which is essential in understanding patterns of muscle weakness in patients with nerve entrapments.*
- Upton AR, McComas AJ. The double crush in nerve entrapment syndromes. *Lancet*. 1973;2:359–362.
- Mackinnon SE. Double and multiple “crush” syndromes. Double and multiple entrapment neuropathies. *Hand Clin*. 1992;8:369–390.
- Dellon AL, Mackinnon SE. Chronic nerve compression model for the double crush hypothesis. *Ann Plast Surg*. 1991;26:259–264.
- McLean WG. Pressure-induced inhibition of fast axonal transport of proteins in the rabbit vagus nerve in galactose neuropathy: prevention by an aldose reductase inhibitor. *Diabetologia*. 1988;31:443–448.
- Nemoto K, Matsumoto N, Tazaki K, et al. An experimental study on the “double crush” hypothesis. *J Hand Surg Am*. 1987;12:552–559.
- Suzuki Y, Shirai Y. Motor nerve conduction analysis of double crush syndrome in a rabbit model. *J Orthop Sci*. 2003;8:69–74.
- Carroll RE, Hurst LC. The relationship of thoracic outlet syndrome and carpal tunnel syndrome. *Clin Orthop Relat Res*. 1982;149–153.
- Hurst LC, Weissberg D, Carroll RE. The relationship of the double crush to carpal tunnel syndrome (an analysis of 1,000 cases of carpal tunnel syndrome). *J Hand Surg [Br]*. 1985;10:202–204.
- Osterman AL. The double crush syndrome. *Orthop Clin North Am*. 1988;19:147–155.
- Galarza M, Gazzeri R, Gazzeri G, et al. Cubital tunnel surgery in patients with cervical radiculopathy: double crush syndrome? *Neurosurg Rev*. 2009;32:471–478.
- Schmid AB, Coppieters MW. The double crush syndrome revisited – a Delphi study to reveal current expert views on mechanisms underlying dual nerve disorders. *Man Ther*. 2011;16:557–562.
- Hagert E, Hagert CG. Upper extremity nerve entrapments: the axillary and radial nerves – clinical diagnosis and surgical treatment. *Plast Reconstr Surg*. 2014;134:71–80.
- Tang DT, Barbour JR, Davidge KM, et al. Nerve entrapment: update. *Plast Reconstr Surg*. 2015;135:199e–215e. *The most recent review of nerve entrapment pathophysiology in relation to clinical concepts.*
- Caliandro P, La Torre G, Aprile I, et al. Distribution of paresthesias in carpal tunnel syndrome reflects the degree of nerve damage at wrist. *Clin Neurophysiol*. 2006;117:228–231.
- Fernandez-de-las-Penas C, de la Llave-Rincon AI, Fernandez-Carnero J, et al. Bilateral widespread mechanical pain sensitivity in carpal tunnel syndrome: evidence of central processing in unilateral neuropathy. *Brain*. 2009;132:1472–1479.
- Tapadia M, Mozaffar T, Gupta R. Compressive neuropathies of the upper extremity: update on pathophysiology, classification, and electrodiagnostic findings. *J Hand Surg Am*. 2010;35:668–677.
- Seddon HJ. *Peripheral Nerve Injuries*. The Nerve Injuries Committee of the Medical Research Council. London: Her Majesty's Stationary Office; 1954:1–451.
- Hagert CG, Hagert E. Manual muscle testing – a clinical examination technique for diagnosing focal neuropathies in the upper extremity. In: Slutsky DJ, ed. *Upper Extremity Nerve Repair – Tips and Techniques: A Master Skills Publication*. Rosemont, IL: The American Society for Surgery of the Hand; 2008:451–466. *This book chapter summarizes the use of the manual muscle testing technique to diagnose upper extremity nerve entrapments.*
- Jepsen JR, Laursen LH, Kreiner S, et al. Neurological examination of the upper limb: a study of construct validity. *Open Neurol J*. 2009;3:54–63.
- Jepsen JR, Laursen LH, Hagert CG, et al. Diagnostic accuracy of the neurological upper limb examination II: relation to symptoms of patterns of findings. *BMC Neurol*. 2006;6:10.
- Cheng CJ, Mackinnon-Patterson B, Beck JL, et al. Scratch collapse test for evaluation of carpal and cubital tunnel syndrome. *J Hand Surg Am*. 2008;33:1518–1524.
- Brown JM, Mokhtee D, Evangelista MS, et al. Scratch collapse test localizes Osborne's band as the point of maximal nerve compression in cubital tunnel syndrome. *Hand (N Y)*. 2010;5:141–147.
- Gillenwater J, Cheng J, Mackinnon SE. Evaluation of the scratch collapse test in peroneal nerve compression. *Plast Reconstr Surg*. 2011;128:933–939.
- Turan I, Hagert E, Jakobsson J. The scratch collapse test supported the diagnosis and showed successful treatment of tarsal tunnel syndrome. *J Med Cases*. 2013;4:746–747.
- Bridgeman C, Naidu S, Kothari MJ. Clinical and electrophysiological presentation of pronator syndrome. *Electromyogr Clin Neurophysiol*. 2007;47:89–92.
- Werner CO, Rosen I, Thorngren KG. Clinical and neurophysiologic characteristics of the pronator syndrome. *Clin Orthop Relat Res*. 1985;231–236.
- Freedman M, Helber G, Pothast J, et al. Electrodiagnostic evaluation of compressive nerve injuries of the upper extremities. *Orthop Clin North Am*. 2012;43:409–416.
- Greenwald D, Blum LC 3rd, Adams D, et al. Effective surgical treatment of cubital tunnel syndrome based on provocative clinical testing without electrodiagnostics. *Plast Reconstr Surg*. 2006;117:87e–91e.
- Bickel KD. Carpal tunnel syndrome. *J Hand Surg Am*. 2010;35:147–152.
- Jain NB, Higgins LD, Losina E, et al. Epidemiology of musculoskeletal upper extremity ambulatory surgery in the United States. *BMC Musculoskelet Disord*. 2014;15:4.
- Foley M, Silverstein B, Polissar N. The economic burden of carpal tunnel syndrome: long-term earnings of CTS claimants in Washington State. *Am J Ind Med*. 2007;50:155–172.
- Dahlin LB, Aulicino PL, Bergfield TL. Anatomical variations of the median nerve at the wrist. *Orthop Rev*. 1992;21:955–959.
- Lindley SG, Kleinert JM. Prevalence of anatomic variations encountered in elective carpal tunnel release. *J Hand Surg Am*. 2003;28:849–855.
- Mondelli M, Aprile I, Ballerini M, et al. Sex differences in carpal tunnel syndrome: comparison of surgical and non-surgical populations. *Eur J Neurol*. 2005;12:976–983.
- Ikeda K, Osamura N, Tomita K. Segmental carpal canal pressure in patients with carpal tunnel syndrome. *J Hand Surg Am*. 2006;31:925–929.
- Ekman-Ordeberg G, Salgeback S, Ordeberg G. Carpal tunnel syndrome in pregnancy. A prospective study. *Acta Obstet Gynecol Scand*. 1987;66:233–235.
- Wraith JE, Alani SM. Carpal tunnel syndrome in the mucopolysaccharidoses and related disorders. *Arch Dis Child*. 1990;65:962–963.
- Palmer KT, Harris EC, Coggon D. Carpal tunnel syndrome and its relation to occupation: a systematic literature review. *Occup Med (Lond)*. 2007;57:57–66.
- Nathan PA, Istvan JA, Meadows KD. A longitudinal study of predictors of research-defined carpal tunnel syndrome in industrial workers: findings at 17 years. *J Hand Surg [Br]*. 2005;30:593–598.

45. Gomes I, Becker J, Ehlers JA, et al. Prediction of the neurophysiological diagnosis of carpal tunnel syndrome from the demographic and clinical data. *Clin Neurophysiol.* 2006;117:964–971.
46. Lifchez SD, Means KR Jr, Dunn RE, et al. Intra- and inter-examiner variability in performing Tinel's test. *J Hand Surg Am.* 2010;35:212–216.
47. Durkan JA. A new diagnostic test for carpal tunnel syndrome. *J Bone Joint Surg Am.* 1991;73:535–538.
48. Cranford CS, Ho JY, Kalainov DM, et al. Carpal tunnel syndrome. *J Am Acad Orthop Surg.* 2007;15:537–548.
49. Hansen PA, Mickleson P, Robinson LR. Clinical utility of the flick maneuver in diagnosing carpal tunnel syndrome. *Am J Phys Med Rehabil.* 2004;83:363–367.
50. Beekman R, Schreuder AH, Rozeman CA, et al. The diagnostic value of provocative clinical tests in ulnar neuropathy at the elbow is marginal. *J Neurol Neurosurg Psychiatry.* 2009;80:1369–1374.
51. D'Arcy CA, McGee S. The rational clinical examination. Does this patient have carpal tunnel syndrome? *JAMA.* 2000;283:3110–3117.
52. El Miedany Y, Ashour S, Youssef S, et al. Clinical diagnosis of carpal tunnel syndrome: old tests – new concepts. *Joint Bone Spine.* 2008;75:451–457.
53. Gelberman RH, Szabo RM, Williamson RV, et al. Sensibility testing in peripheral-nerve compression syndromes. An experimental study in humans. *J Bone Joint Surg Am.* 1983;65:632–638.
54. Graham B, Regehr G, Naglie G, et al. Development and validation of diagnostic criteria for carpal tunnel syndrome. *J Hand Surg Am.* 2006;31:919–924.
55. Keith MW, Masear V, Chung KC, et al. American Academy of Orthopaedic Surgeons Clinical Practice Guideline on diagnosis of carpal tunnel syndrome. *J Bone Joint Surg Am.* 2010;91:2478–2479.
56. Chan L, Turner JA, Comstock BA, et al. The relationship between electrodiagnostic findings and patient symptoms and function in carpal tunnel syndrome. *Arch Phys Med Rehabil.* 2007;88:19–24.
57. Concannon MJ, Gainor B, Petroski GF, et al. The predictive value of electrodiagnostic studies in carpal tunnel syndrome. *Plast Reconstr Surg.* 1997;100:1452–1458.
58. Palumbo CF, Szabo RM. Examination of patients for carpal tunnel syndrome sensibility, provocative, and motor testing. *Hand Clin.* 2002;18:269–277, vi.
59. Fowler JR, Munsch M, Tosti R, et al. Comparison of ultrasound and electrodiagnostic testing for diagnosis of carpal tunnel syndrome: study using a validated clinical tool as the reference standard. *J Bone Joint Surg Am.* 2014;96:e148.
60. Manente G, Torrieri F, Di Blasio F, et al. An innovative hand brace for carpal tunnel syndrome: a randomized controlled trial. *Muscle Nerve.* 2001;24:1020–1025.
61. Premoselli S, Sioli P, Grossi A, et al. Neutral wrist splinting in carpal tunnel syndrome: a 3- and 6-months clinical and neurophysiologic follow-up evaluation of night-only splint therapy. *Eura Medicophys.* 2006;42:121–126.
62. Walker WC, Metzler M, Cifu DX, et al. Neutral wrist splinting in carpal tunnel syndrome: a comparison of night-only versus full-time wear instructions. *Arch Phys Med Rehabil.* 2000;81:424–429.
63. Marshall S, Tardif G, Ashworth N. Local corticosteroid injection for carpal tunnel syndrome. *Cochrane Database Syst Rev.* 2007;(2):CD001554.
64. Armstrong T, Devor W, Borschel L, et al. Intracarpal steroid injection is safe and effective for short-term management of carpal tunnel syndrome. *Muscle Nerve.* 2004;29:82–88.
65. Dammers JW, Roos Y, Veering MM, et al. Injection with methylprednisolone in patients with the carpal tunnel syndrome: a randomised double blind trial testing three different doses. *J Neurol.* 2006;253:574–577.
66. Wong SM, Hui AC, Tang A, et al. Local vs systemic corticosteroids in the treatment of carpal tunnel syndrome. *Neurology.* 2001;56:1565–1567.
67. Wong SM, Hui AC, Lo SK, et al. Single vs. two steroid injections for carpal tunnel syndrome: a randomised clinical trial. *Int J Clin Pract.* 2005;59:1417–1421.
68. Ucan H, Yagci I, Yilmaz L, et al. Comparison of splinting, splinting plus local steroid injection and open carpal tunnel release outcomes in idiopathic carpal tunnel syndrome. *Rheumatol Int.* 2006;27:45–51.
69. Lalonde D, Bell M, Benoit P, et al. A multicenter prospective study of 3,110 consecutive cases of elective epinephrine use in the fingers and hand: the Dalhousie Project clinical phase. *J Hand Surg Am.* 2005;30:1061–1067.
70. Leblanc MR, Lalonde J, Lalonde DH. A detailed cost and efficiency analysis of performing carpal tunnel surgery in the main operating room versus the ambulatory setting in Canada. *Hand (N Y).* 2007;2:173–178. The authors examine the benefits of the wide-awake approach to carpal tunnel release compared to carpal tunnel surgery performed in the main operating suite under general anesthesia in terms of cost and overall efficiency. The wide-awake approach to carpal tunnel release allows the hand surgeon to improve productivity without compromising patient safety or outcomes.
71. Finsen V, Andersen K, Russwurm H. No advantage from splinting the wrist after open carpal tunnel release. A randomized study of 82 wrists. *Acta Orthop Scand.* 1999;70:288–292.
72. Chow JC. Endoscopic carpal tunnel release. Two-portal technique. *Hand Clin.* 1994;10:637–646.
73. Agee JM, McCarroll HR Jr, Tortosa RD, et al. Endoscopic release of the carpal tunnel: a randomized prospective multicenter study. *J Hand Surg Am.* 1992;17:987–995.
74. Trumble TE, Diao E, Abrams RA, et al. Single-portal endoscopic carpal tunnel release compared with open release: a prospective, randomized trial. *J Bone Joint Surg Am.* 2002;84:1107–1115.
75. Abrams R. Endoscopic versus open carpal tunnel release. *J Hand Surg Am.* 2009;34:535–539.
76. Larsen MB, Sorensen AI, Crone KL, et al. Carpal tunnel release: a randomized comparison of three surgical methods. *J Hand Surg Eur Vol.* 2013;38:646–650.
77. Ferdinand RD, MacLean JG. Endoscopic versus open carpal tunnel release in bilateral carpal tunnel syndrome. A prospective, randomised, blinded assessment. *J Bone Joint Surg Br.* 2002;84:375–379.
78. Macdermid JC, Richards RS, Roth JH, et al. Endoscopic versus open carpal tunnel release: a randomized trial. *J Hand Surg Am.* 2003;28:475–480.
79. Palmer AK, Toivonen DA. Complications of endoscopic and open carpal tunnel release. *J Hand Surg Am.* 1999;24:561–565.
80. Schmelzer RE, Della Rocca GJ, Caplin DA. Endoscopic carpal tunnel release: a review of 753 cases in 486 patients. *Plast Reconstr Surg.* 2006;117:177–185.
81. Chung KC, Walters MR, Greenfield ML, et al. Endoscopic versus open carpal tunnel release: a cost-effectiveness analysis. *Plast Reconstr Surg.* 1998;102:1089–1099.
82. Leit ME, Weiser RW, Tomaino MM. Patient-reported outcome after carpal tunnel release for advanced disease: a prospective and longitudinal assessment in patients older than age 70. *J Hand Surg Am.* 2004;29:379–383.
83. Weber RA, DeSalvo DJ, Rude MJ. Five-year follow-up of carpal tunnel release in patients over age 65. *J Hand Surg Am.* 2010;35:207–211.
84. Thomsen NO, Cederlund R, Rosen I, et al. Clinical outcomes of surgical release among diabetic patients with carpal tunnel syndrome: prospective follow-up with matched controls. *J Hand Surg Am.* 2009;34:1177–1187.
85. Amadio PC. Interventions for recurrent/persistent carpal tunnel syndrome after carpal tunnel release. *J Hand Surg Am.* 2009;34:1320–1322.
86. Ludlow KS, Merla JL, Cox JA, et al. Pillar pain as a postoperative complication of carpal tunnel release: a review of the literature. *J Hand Ther.* 1997;10:277–282.
87. Tung TH, Mackinnon SE. Secondary carpal tunnel surgery. *Plast Reconstr Surg.* 2001;107:1830–1843. quiz 1844,1933.
88. Kerasnoudis A, Tsivgoulis G. Nerve ultrasound in peripheral neuropathies: a review. *J Neuroimaging.* 2015;25:528–538.

89. Zancolli ER 3rd, Zancolli EP 4th, Perrotto CJ. New mini-invasive decompression for pronator teres syndrome. *J Hand Surg Am*. 2012;37:1706–1710.
90. Seyffarth H. Primary myoses in the M. pronator teres as cause of lesion of the N. medianus (the pronator syndrome). *Acta Psychiatr Neurol Scand Suppl*. 1951;74:251–254.
91. Hartz CR, Linscheid RL, Gramse RR, et al. The pronator teres syndrome: compressive neuropathy of the median nerve. *J Bone Joint Surg Am*. 1981;63:885–890.
92. Kiloh LG, Nevin S. Isolated neuritis of the anterior interosseous nerve. *Br Med J*. 1952;1:850–851.
93. Laha RK, Lunsford D, Dujovny M. Lacertus fibrousus compression of the median nerve. Case report. *J Neurosurg*. 1978;48:838–841.
94. Stal M, Hagert CG, Moritz U. Upper extremity nerve involvement in Swedish female machine milkers. *Am J Ind Med*. 1998;33:551–559.
95. Hagert E. Clinical diagnosis and wide-awake surgical treatment of proximal median nerve entrapment at the elbow: a prospective study. *Hand (N Y)*. 2013;8:41–46.
96. Pratt N. Anatomy of nerve entrapment sites in the upper quarter. *J Hand Ther*. 2005;18:216–229.
97. Shibayama M, Kuniyoshi K, Suzuki T, et al. The effects of locally injected triamcinolone on entrapment neuropathy in a rat chronic constriction injury model. *J Hand Surg Am*. 2014;39:1714–1721.
98. Stal M, Hagert CG, Englund JE. Pronator syndrome: a retrospective study of median nerve entrapment at the elbow in female machine milkers. *J Agric Saf Health*. 2004;10:247–256.
99. Pan YW, Wang S, Tian G, et al. Typical brachial neuritis (Parsonage-Turner syndrome) with hourglass-like constrictions in the affected nerves. *J Hand Surg Am*. 2011;36:1197–1203.
100. Parsonage MJ, Turner JW. Neuralgic amyotrophy; the shoulder-girdle syndrome. *Lancet*. 1948;1:973–978.
101. Rodriguez-Niedenfuhr M, Vazquez T, Parkin I, et al. Martin-Gruber anastomosis revisited. *Clin Anat*. 2002;15:129–134.
102. Smith CC, Bevelacqua AC. Challenging pain syndromes: Parsonage-Turner syndrome. *Phys Med Rehabil Clin N Am*. 2014;25:265–277.
103. Chen SH, Tsai TM. Ulnar tunnel syndrome. *J Hand Surg Am*. 2014;39:571–579.
104. Kuschner SH, Gelberman RH, Jennings C. Ulnar nerve compression at the wrist. *J Hand Surg Am*. 1988;13:577–580.
105. Brooks DM. Nerve compression syndromes. *J Bone Joint Surg Br*. 1963;45:445–446.
106. Costigan DG, Riley JM Jr, Coy FE Jr. Thrombofibrosis of the ulnar artery in the palm. *J Bone Joint Surg Am*. 1959;41:702–704.
107. Patterson JM, Jaggars MM, Boyer MI. Ulnar and median nerve palsy in long-distance cyclists. A prospective study. *Am J Sports Med*. 2003;31:585–589.
108. Taylor AR. Ulnar nerve compression at the wrist in rheumatoid arthritis. Report of a case. *J Bone Joint Surg Br*. 1974;56:142–143.
109. Baird DB, Friedenbergs ZB. Delayed ulnar-nerve palsy following a fracture of the hamate. *J Bone Joint Surg Am*. 1968;50:570–572.
110. Ginanneschi F, Filippou G, Reale F, et al. Ultrasonographic and functional changes of the ulnar nerve at Guyon's canal after carpal tunnel release. *Clin Neurophysiol*. 2010;121:208–213.
111. Harvie P, Patel N, Ostlere SJ. Prevalence and epidemiological variation of anomalous muscles at Guyon's canal. *J Hand Surg [Br]*. 2004;29:26–29.
112. Cavallo M, Poppi M, Martinelli P, et al. Distal ulnar neuropathy from carpal ganglia: a clinical and electrophysiological study. *Neurosurgery*. 1988;22:902–905.
113. Mackinnon S. Compression neuropathies. In: Green DP, ed. *Green's Operative Hand Surgery*. New York, NY: Churchill Livingstone; 2005:999–1045.
114. Novak CB, Lee GW, Mackinnon SE, et al. Provocative testing for cubital tunnel syndrome. *J Hand Surg Am*. 1994;19:817–820.
115. Roberts GL, Maclean AD, Logan AJ. Ulna nerve decompression at the elbow in patients with normal nerve conduction tests. *Hand Surg*. 2015;20:260–265.
116. Svernlöv B, Larsson M, Rehn K, et al. Conservative treatment of the cubital tunnel syndrome. *J Hand Surg Eur Vol*. 2009;34:201–207.
117. Lan ZD, Tatsui CE, Jalali A, et al. Outcomes of a novel minimalist approach for the treatment of cubital tunnel syndrome. *J Clin Neurosci*. 2015;22:964–968.
118. Tsai TM, Bonczar M, Tsuruta T, et al. A new operative technique: cubital tunnel decompression with endoscopic assistance. *Hand Clin*. 1995;11:71–80.
119. Hoffmann R, Siemionow M. The endoscopic management of cubital tunnel syndrome. *J Hand Surg [Br]*. 2006;31:23–29.
120. Ahcan U, Zorman P. Endoscopic decompression of the ulnar nerve at the elbow. *J Hand Surg Am*. 2007;32:1171–1176.
121. Ogata K, Manske PR, Lesker PA. The effect of surgical dissection on regional blood flow to the ulnar nerve in the cubital tunnel. *Clin Orthop Relat Res*. 1985;195–198.
122. Nabhan A, Ahlhelm F, Kelm J, et al. Simple decompression or subcutaneous anterior transposition of the ulnar nerve for cubital tunnel syndrome. *J Hand Surg [Br]*. 2005;30:521–524.
123. Keiner D, Gaab MR, Schroeder HW, et al. Comparison of the long-term results of anterior transposition of the ulnar nerve or simple decompression in the treatment of cubital tunnel syndrome – a prospective study. *Acta Neurochir (Wien)*. 2009;151:311–315, discussion 316.
124. Jariwala A, Bansal N, Nicol GM, et al. Outcome analysis of cubital tunnel decompression. *Scott Med J*. 2015;60:136–140.
125. Goldfarb CA, Sutter MM, Martens EJ, et al. Incidence of re-operation and subjective outcome following in situ decompression of the ulnar nerve at the cubital tunnel. *J Hand Surg Eur Vol*. 2009;34:379–383.
126. Baek GH, Kwon BC, Chung MS. Comparative study between minimal medial epicondylectomy and anterior subcutaneous transposition of the ulnar nerve for cubital tunnel syndrome. *J Shoulder Elbow Surg*. 2006;15:609–613.
127. Krogue JD, Aleem AW, Osei DA, et al. Predictors of surgical revision after in situ decompression of the ulnar nerve. *J Shoulder Elbow Surg*. 2015;24:634–639.
128. Lowe JB 3rd, Maggi SP, Mackinnon SE. The position of crossing branches of the medial antebrachial cutaneous nerve during cubital tunnel surgery in humans. *Plast Reconstr Surg*. 2004;114:692–696.
129. Efstathiopoulos DG, Themistocleous GS, Papagelopoulos PJ, et al. Outcome of partial medial epicondylectomy for cubital tunnel syndrome. *Clin Orthop Relat Res*. 2006;444:134–139.
130. Lanzetta M, Foucher G. Entrapment of the superficial branch of the radial nerve (Wartenberg's syndrome). A report of 52 cases. *Int Orthop*. 1993;17:342–345.
131. Dellon AL, Mackinnon SE. Radial sensory nerve entrapment. *Arch Neurol*. 1986;43:833–835.
132. Lanzetta M, Foucher G. Association of Wartenberg's syndrome and De Quervain's disease: a series of 26 cases. *Plast Reconstr Surg*. 1995;96:408–412.
133. Dellon AL, Mackinnon SE. Radial sensory nerve entrapment in the forearm. *J Hand Surg Am*. 1986;11:199–205.
134. Konjengbam M, Elangbam J. Radial nerve in the radial tunnel: anatomic sites of entrapment neuropathy. *Clin Anat*. 2004;17:21–25.
135. Hagert E, Garcia-Elias M, Forsgren S, et al. Immunohistochemical analysis of wrist ligament innervation in relation to their structural composition. *J Hand Surg Am*. 2007;32:30–36.
136. Hagert E, Persson JK, Werner M, et al. Evidence of wrist proprioceptive reflexes elicited after stimulation of the scapholunate interosseous ligament. *J Hand Surg Am*. 2009;34:642–651.
137. Dellon AL. Partial dorsal wrist denervation: resection of the distal posterior interosseous nerve. *J Hand Surg Am*. 1985;10:527–533.
138. Urch EY, Model Z, Wolfe SW, et al. Anatomical study of the surgical approaches to the radial tunnel. *J Hand Surg Am*. 2015;40:1416–1420.
139. Werner CO, Haefner F, Rosen I. Direct recording of local pressure in the radial tunnel during passive stretch and active contraction of the supinator muscle. *Arch Orthop Trauma Surg*. 1980;96:299–301.

140. Lee JT, Azari K, Jones NF. Long term results of radial tunnel release – the effect of co-existing tennis elbow, multiple compression syndromes and workers' compensation. *J Plast Reconstr Aesthet Surg.* 2008;61:1095–1099.
141. Roles NC, Maudsley RH. Radial tunnel syndrome: resistant tennis elbow as a nerve entrapment. *J Bone Joint Surg Br.* 1972;54:499–508.
142. Hagert CG. The ECU test to reliably diagnose radial nerve entrapment in the proximal forearm. In: *Annual Conference of the Swedish Society for Surgery of the Hand.* Stockholm, Sweden: 1981.
143. Lundborg G. *Peripheral Nerve Injury and Repair.* New York, NY: Churchill Livingstone; 1998:238.
144. Sarhadi NS, Korday SN, Bainbridge LC. Radial tunnel syndrome: diagnosis and management. *J Hand Surg [Br].* 1998;23:617–619.
145. Eaton CJ, Lister GD. Radial nerve compression. *Hand Clin.* 1992;8:345–357.
146. Hashizume H, Nishida K, Nanba Y, et al. Non-traumatic paralysis of the posterior interosseous nerve. *J Bone Joint Surg Br.* 1996;78:771–776.
147. Simon Perez C, Garcia Medrano B, Rodriguez Mateos JJ, et al. Radial tunnel syndrome: results of surgical decompression by a posterolateral approach. *Int Orthop.* 2014;38:2129–2135.
148. Huisstede B, Miedema HS, van Opstal T, et al. Interventions for treating the radial tunnel syndrome: a systematic review of observational studies. *J Hand Surg Am.* 2008;33:72–78.
149. Jalovaara P, Lindholm RV. Decompression of the posterior interosseous nerve for tennis elbow. *Arch Orthop Trauma Surg.* 1989;108:243–245.
150. Artico M, Telera S, Tiengo C, et al. Surgical anatomy of the radial nerve at the elbow. *Surg Radiol Anat.* 2009;31:101–106.
151. Adolfsson LE, Nettelblad H. Radial nerve entrapment in the upper arm as a cause of lateral arm pain: a report of four cases. *Scand J Plast Reconstr Surg Hand Surg.* 2001;35:217–220.
152. Streib E. Upper arm radial nerve palsy after muscular effort: report of three cases. *Neurology.* 1992;42:1632–1634.
153. Ng AB, Borhan J, Ashton HR, et al. Radial nerve palsy in an elite bodybuilder. *Br J Sports Med.* 2003;37:185–186.
154. Sebastian D. Triangular interval syndrome: a differential diagnosis for upper extremity radicular pain. *Physiother Theory Pract.* 2010;26:113–119.
155. Robinson LR. Role of neurophysiologic evaluation in diagnosis. *J Am Acad Orthop Surg.* 2000;8:190–199.
156. Ishima T, Usui M, Satoh E, et al. Quadrilateral space syndrome caused by a ganglion. *J Shoulder Elbow Surg.* 1998;7:80–82.
157. Francel TJ, Dellon AL, Campbell JN. Quadrilateral space syndrome: diagnosis and operative decompression technique. *Plast Reconstr Surg.* 1991;87:911–916.
158. Amin MF, Berst M, el Khoury GY. An unusual cause of the quadrilateral space impingement syndrome by a bone spike. *Skeletal Radiol.* 2006;35:956–958.
159. McClelland D, Paxinos A. The anatomy of the quadrilateral space with reference to quadrilateral space syndrome. *J Shoulder Elbow Surg.* 2008;17:162–164.
160. McAdams TR, Dillingham MF. Surgical decompression of the quadrilateral space in overhead athletes. *Am J Sports Med.* 2008;36:528–532.
161. Monteleone G, Gismant M, Stevanato G, et al. Silent deltoid atrophy in beach volleyball players: a report of two cases and literature review. *Int J Sports Phys Ther.* 2015;10:347–353.
162. Curtin C, Hagert CG, Hultling C, et al. *Nerve entrapment as a cause of shoulder pain in the spinal cord injured patient.* Paper presented at Tetra Hand 2013, Hong Kong.
163. Cahill BR, Palmer RE. Quadrilateral space syndrome. *J Hand Surg Am.* 1983;8:65–69.
164. Bredella MA, Tirman PF, Fritz RC, et al. Denervation syndromes of the shoulder girdle: MR imaging with electrophysiologic correlation. *Skeletal Radiol.* 1999;28:567–572.
165. Linker CS, Helms CA, Fritz RC. Quadrilateral space syndrome: findings at MR imaging. *Radiology.* 1993;188:675–676.
166. Cothran RL Jr, Helms C. Quadrilateral space syndrome: incidence of imaging findings in a population referred for MRI of the shoulder. *AJR Am J Roentgenol.* 2005;184:989–992.
167. Chen H, Narvaez VR. Ultrasound-guided quadrilateral space block for the diagnosis of quadrilateral syndrome. *Case Rep Orthop.* 2015;2015:378627.
168. Brown SA, Doolittle DA, Bohanon CJ, et al. Quadrilateral space syndrome: the Mayo Clinic experience with a new classification system and case series. *Mayo Clin Proc.* 2015;90:382–394.
169. Guerri-Guttenberg RA, Ingolotti M. Classifying musculocutaneous nerve variations. *Clin Anat.* 2009;22:671–683.
170. Kim SM, Goodrich JA. Isolated proximal musculocutaneous nerve palsy: case report. *Arch Phys Med Rehabil.* 1984;65:735–736.
171. Yung H, Lagemann GM, Lin A, et al. Lateral antebrachial cutaneous nerve entrapment after shoulder arthroscopy: a case report. *PM R.* 2015;7:889–894.
172. Ma H, Van Heest A, Glisson C, et al. Musculocutaneous nerve entrapment: an unusual complication after biceps tenodesis. *Am J Sports Med.* 2009;37:2467–2469.
173. Swain R. Musculocutaneous nerve entrapment: a case report. *Clin J Sport Med.* 1995;5:196–198.
174. Mastaglia FL. Musculocutaneous neuropathy after strenuous physical activity. *Med J Aust.* 1986;145:153–154.
175. Davidson JJ, Bassett FH 3rd, Nunley JA 2nd. Musculocutaneous nerve entrapment revisited. *J Shoulder Elbow Surg.* 1998;7:250–255.
176. Freehill MT, Shi LL, Tompson JD, et al. Suprascapular neuropathy: diagnosis and management. *Phys Sports Med.* 2012;40:72–83.
177. Podgorski M, Topol M, Sibinski M, et al. New parameters describing morphological variations in the suprascapular notch region as potential predictors of suprascapular nerve entrapment. *BMC Musculoskelet Disord.* 2014;15:396.
178. Rengachary SS, Burr D, Lucas S, et al. Suprascapular entrapment neuropathy: a clinical, anatomical, and comparative study. Part 3: comparative study. *Neurosurgery.* 1979;5:452–455.
179. Mall NA, Hammond JE, Lenart BA, et al. Suprascapular nerve entrapment isolated to the spinoglenoid notch: surgical technique and results of open decompression. *J Shoulder Elbow Surg.* 2013;22:e1–e8.
180. Hill LJ, Jelsing EJ, Terry MJ, et al. Evaluation, treatment, and outcomes of suprascapular neuropathy: a 5-year review. *PM R.* 2014;6:774–780.
181. Plancher KD, Luke TA, Peterson RK, et al. Posterior shoulder pain: a dynamic study of the spinoglenoid ligament and treatment with arthroscopic release of the scapular tunnel. *Arthroscopy.* 2007;23:991–998.
182. Leclerc LE, Shi LL, Lin A, et al. Complete fatty infiltration of intact rotator cuffs caused by suprascapular neuropathy. *Arthroscopy.* 2014;30:639–644.
183. Peck E, Strakowski JA. Ultrasound evaluation of focal neuropathies in athletes: a clinically focused review. *Br J Sports Med.* 2015;49:166–175.
184. Ringel SP, Treihart M, Carry M, et al. Suprascapular neuropathy in pitchers. *Am J Sports Med.* 1990;18:80–86.
185. Martin SD, Warren RF, Martin TL, et al. Suprascapular neuropathy. Results of non-operative treatment. *J Bone Joint Surg Am.* 1997;79:1159–1165.
186. Antoniou J, Tae SK, Williams GR, et al. Suprascapular neuropathy. Variability in the diagnosis, treatment, and outcome. *Clin Orthop Relat Res.* 2001;131–138.
187. Post M. Diagnosis and treatment of suprascapular nerve entrapment. *Clin Orthop Relat Res.* 1999;92–100.
188. Yamakado K. Quantification of the learning curve for arthroscopic suprascapular nerve decompression: an evaluation of 300 cases. *Arthroscopy.* 2015;31:191–196.
189. Iannotti JP, Ramsey ML. Arthroscopic decompression of a ganglion cyst causing suprascapular nerve compression. *Arthroscopy.* 1996;12:739–745.

190. Bhatia S, Chalmers PN, Yanke AB, et al. Arthroscopic suprascapular nerve decompression: transarticular and subacromial approach. *Arthrosc Tech*. 2012;1:e187–e192.
191. Tubbs RS, Tyler-Kabara EC, Aikens AC, et al. Surgical anatomy of the dorsal scapular nerve. *J Neurosurg*. 2005;102:910–911.
192. Sultan HE, Younis El-Tantawi GA. Role of dorsal scapular nerve entrapment in unilateral interscapular pain. *Arch Phys Med Rehabil*. 2013;94:1118–1125.
193. Argyriou AA, Karanasios P, Makridou A, et al. Description of an unusual case with dorsal scapular neuropathy causing rhomboids palsy and scapular winging. *J Back Musculoskelet Rehabil*. 2015;28:883–885.
194. Debeer P, Van Den Eede E, Moens P. Scapular winging: an unusual complication of bracing in idiopathic scoliosis. *Clin Orthop Relat Res*. 2007;461:258–261.
195. Chen D, Gu Y, Lao J, et al. Dorsal scapular nerve compression. Atypical thoracic outlet syndrome. *Chin Med J*. 1995;108:582–585.
196. Akgun K, Aktas I, Terzi Y. Winged scapula caused by a dorsal scapular nerve lesion: a case report. *Arch Phys Med Rehabil*. 2008;89:2017–2020.
197. Gentchos EJ. Isolated peripheral nerve lesions of the brachial plexus affecting the shoulder joint. *University of Pennsylvania Orthop J*. 1999;40–44.
198. Tubbs RS, Goodrich D, Watanabe K, et al. Anatomic landmarks for selected nerves of the head, neck, and upper and lower limbs. In: Tubbs RS, ed. *Nerves and Nerve Injuries*. New York, NY: Elsevier; 2015:575–588. *This chapter provides a comprehensive and illustrative review of peripheral nerve anatomy in relation to surface landmarks, a practical guide to surgeons treating nerve entrapment syndromes.*

Congenital hand I: Embryology, classification, and principles

Michael Tonkin and Kerby Oberg

Access video content for this chapter online at expertconsult.com 

SYNOPSIS

- Consistency of terminology is necessary for optimal communication.
- Limb outgrowth and patterning are controlled by specific signaling centers within the developing limb bud via the activation and interaction of molecular messengers.
- Anomalies of limb development result from:
 - spontaneous mutation of genetic material
 - inheritance of abnormal genes
 - subtle or gross insult to the limb bud.
- The anomaly may be isolated or syndromic.
- The International Federation of Societies for Surgery of the Hand (IFSSH) has recommended that the Swanson classification (previously approved by the IFSSH) be replaced by the Oberg, Manske, Tonkin (OMT) classification, which separates malformations from deformations and dysplasias. Malformations are further sub-divided according to the axis of limb development that is primarily involved and whether the insult affects the whole of the upper limb or the hand plate only. This classification incorporates our increasing understanding of the molecular basis of limb development.
- Assessment and treatment are specific for each child and family but are based on a detailed understanding of the processes of limb development, the psychological and physical effects of limb anomalies, and simple surgical principles.

Introduction

Limb development

The upper limb bud appears during the fourth week of development as an outgrowth on the sides of the embryo. Cells of the somatic lateral plate mesoderm form the skeletal framework of the limb, while mesoderm from the somite migrates in to form the muscular component and contributes to the limb's vascular network. Over the next 4 weeks, growth and differentiation transform the limb bud into an elegant

asymmetric organ that is one of the defining features of the human species. The limb bud growth and differentiation are under the control of signaling centers, specialized areas within the limb that dictate, in concert, the appropriate sequential events of development.

The establishment of signaling centers and their subsequent behavior are under genetic control. The genes and the morphogens (proteins) they encode control the process of limb growth and differentiation and act as messengers between signaling centers and developing cells.

As knowledge of the process of limb development becomes more sophisticated, an understanding of the causation of limb anomalies becomes clearer.

Genetic mutations can disrupt the molecular function of a number of proteins orchestrating limb development, including secreted proteins (ligands), ligand receptors, and transcription factors. The mutation may be inherited or may arise spontaneously. Environmental factors, such as thalidomide, which resulted in an epidemic of limb malformations during the 1960s, radiation, nutritional defects, and infections may affect the molecular pathways of development or be responsible for a more gross insult resulting in tissue hemorrhage and/or necrosis. For example, if such direct damage occurs obliterating the apical ectodermal ridge (AER), an important signaling center that directs limb outgrowth, transverse truncation will result.

Classification

Congenital anomalies in the hand demand a reproducible and consistent terminology, a universal language that allows discussion of complex clinical entities, indications for treatment, and comparisons of results.

Swanson's classification was adopted by the IFSSH in 1976 as the standard system by which congenital hand anomalies were described.¹ It is derived from ideas existing in the 1960s regarding limb embryology and is largely based on morphological appearance. Knight and Kay² have presented an extended version, attempting to incorporate a list of all

congenital anomalies. Regrettably, this classification is intrinsically unsuited to alterations based on causation and etiology at a molecular level.

In 2014, the IFSSH Scientific Committee for Congenital Conditions recommended that the Oberg, Manske, Tonkin (OMT) classification replace that of Swanson.³ This system utilizes dysmorphological terminology, separating congenital upper limb anomalies into *malformations*, *deformations*, and *dysplasias*. Malformations, the majority of encountered anomalies, are further sub-divided according to which axis of formation and differentiation is primarily affected and whether the consequence affects primarily the hand plate alone or the whole upper limb. It is probable that the causation of some anomalies will confound our attempts to assign a specific site in the molecular pathway and/or the anatomical site in the limb bud and the time at which the aberration occurs. However, the OMT system would appear to be a more logical approach to classification.

Assessment and principles of treatment

It is clear that the terminology applied to congenital anomalies should reflect a language common to, and understood by, the geneticist, the anatomist, the pathologist, and the surgeon. For this reason, these authors have chosen to link the terminology of embryology of the limb bud at the molecular level, the terminology of dysmorphology, and the terminology of classification. This consistency would appear to provide less controversy in a rapidly changing field of knowledge. Furthermore, such an approach is of benefit when attempting to explain to parents how the limb normally forms and how any particular anomaly may occur. This process plays a vital role in the assessment of any specific anomaly and leads to a sensible plan of management.

Limb development (embryology)

Overview of upper limb morphogenesis

Around day 26 (4 weeks) after fertilization (Carnegie stage 12), the upper limb bud appears as an oblong ventrolateral bulge on the body wall between somites 9–12 (C5–8) (Fig. 25.1).⁴ The emerging limb bud is composed of somatic lateral plate mesoderm covered by ectoderm. Subsequent limb bud growth and differentiation are described in terms of three coordinate axes: proximodistal, dorsoventral (dorsovolar), and anteroposterior (or radioulnar) (Fig. 25.2), each controlled by distinctive regions – signaling centers.

The ectoderm overlying the distal edge of the limb bud at the dorsovolar boundary thickens and forms a distinct ridge of stratified ectoderm, the AER.⁵ The thickened AER is critical for proximodistal outgrowth and also adds mechanical rigidity to the distal rim of the limb bud, flattening it along the dorsovolar axis. Excision of the AER in chicken embryo limb buds prevents further proximodistal outgrowth and results in limb truncation.⁶ Underlying the AER, the distal undifferentiated mesoderm has been termed the progress zone (PZ). Cells in the PZ ultimately differentiate into specific cell types and are directed to specific positions within the limb.

The dorsal ectoderm is a critical signaling center for directing formation of dorsal and volar characteristics of the limb.

Table 25.1 Timing of hand formation

Time after fertilization	Hand development
27 days	Development of arm bud
28–30 days	Further development of arm bud
34–36 days	Elongation of arm bud
34–38 days	Formation of hand paddle
38–40 days	Early separation of digits
44–46 days	Digits separated
Week 9–10	Formation of fingernails begins

(Reproduced from Gupta A, Kay SPJ, Scheker LR (eds). *The Growing Hand: Diagnosis and Management of the Upper Extremity in Children*. London: CV Mosby; 2000:25.)

Excision and rotation of dorsal ectoderm cause the formation of dorsal structures on the limb ventral surface.⁷ Another collection of mesodermal cells at the distal ulnar (posterior) margin is called the zone of polarizing activity (ZPA). Although not morphologically distinct, these cells direct radioulnar patterning and coordinate asymmetric limb patterning with the other signaling centers during development. Removal of the ZPA in animal models leads to loss of the ulna and the ulnar digits.⁸ Conversely, transplantation of these cells to the anterior (radial) aspect of limb buds of chicken embryos will result in formation of a mirrored complement of ulnar digits radially.⁹

Over the next week, the limb bud expands and elongates, particularly along the proximodistal axis (Table 25.1). By day 33 of development (Carnegie stage 14), differential growth and programmed cell death transform the distal portion into a paddle-shaped hand plate. There is also progressive mesodermal condensation along the proximodistal axis, forming a tripartite skeleton composed of a proximal section, the stylopod (humerus), a middle section, the zeugopod (radius and ulna), and a distal section, the autopod (hand). The joints become fully evident about day 51 (Carnegie stage 20) when the elbow and wrist joints flex, and by day 56 (end of the eighth week, Carnegie stage 23), the major morphologic features of the limb are complete (see Fig. 25.1).

The molecular control of limb outgrowth and patterning

During early embryonic development, Hox transcription factors set up a segmental body plan along the cranial–caudal axis.¹⁰ By the fourth week of development the presumptive upper limb fields are established, triggering the expression of Tbx5, which initiates limb formation and determines forelimb identity.¹¹ Tbx5 upregulates Fgf10 in the limb mesoderm and Wnt3 in the distal ectoderm.^{12,13} Mesodermal Fgf10, in conjunction with ectodermal Wnt3, TP63, Dlx5/6, and radial fringe (R-fng), transform the distal ectodermal at the dorsovolar boundary into the thickened AER.^{14–17} Formation of the AER initiates the expression of AER-related Fgf proteins (including Fgf2/4/8/9/17),^{18–19} which, in turn, act on the mesoderm just underneath the AER to sustain Wnts and Fgf10 expression in the PZ. This reciprocal loop of ectodermal and mesodermal Fgf/Wnt proteins promotes progressive proximodistal outgrowth^{20,21} (Fig. 25.3). In the absence of Wnt3 or




Fig. 25.1 Upper limb and hand development. **(A)** Human embryo at Carnegie stage 13 (about 28 days of development), showing early limb buds. **(B)** Close-up dorsal view of the arm bud. The anterior or radial (Rad) aspect is cranial and the posterior or ulnar (Uln) aspect is caudal. **(C)** Cross-section through an upper limb bud at 32 days of development (Carnegie stage 14), showing dorsal (Do)–ventral (Ve) limb bud flattening and the thickened apical ectodermal ridge at the distal tip of the limb bud (that runs along the dorsal–ventral border from anterior to posterior). Pr, proximal; Di, distal. **(D)** The hand plate at 41 days of development (Carnegie stage 17). The scalloped edge conforms to the condensing digital mesenchyme. **(E)** Limb at 46 days of development (Carnegie stage 19). Separate fingers are evident. The proximal limb skeleton is well developed and ossification has begun in the humerus and shoulder girdle. **(F)** The embryo at 49 days of development (Carnegie stage 20), showing ossification centers in the upper limb, lower limb, and face. Note that upper limb development is more advanced than lower limb development. **(G)** Upper limbs at week 8 (Carnegie stage 22). The fingers are completely separate and ossification centers have developed in the forearm, i.e., radius and ulna. **(H)** The upper limb at week 9 (Carnegie stage 23). Metacarpal and distal phalangeal ossification has begun. **(I)** The upper limb at week 11. Ossification in proximal and middle phalanges is now evident in addition to distal phalanges and metacarpals. **(J)** The hand at week 12, showing developing nail fields (nails become visible during week 16). (Portions redrawn from England MA. A Colour Atlas of Life Before Birth. London: Year Book Medical Publications; 1983.)

Fgf10, limbs fail to develop and tetra-amelia results.^{22,23} Application of Fgfs to the distal chick limb bud after AER removal will return proximodistal limb outgrowth.¹⁹ Within the PZ, mesodermal cells persist in an undifferentiated or receptive state, allowing the signaling centers to direct their fates.

The ZPA in the posterior (ulnar) limb mesoderm secretes a potent morphogen, sonic hedgehog (Shh), that regulates radioulnar patterning²⁴ (see Fig. 25.3). Shh induces posterior (ulnar) proliferation of the limb bud expanding its width.^{25,26} Moreover, Shh posteriorizes (ulnarizes) the developing




Fig. 25.2 Limb bud coordinate axes and signaling centers: **(A)** The forelimb (boxed region) of a Carnegie stage 13 embryo depicting the three coordinate axes – each with its own signaling center: the apical ectodermal ridge (AER) coordinating proximodistal (Pr–Di) outgrowth and differentiation; dorsoventral (Do–Vo) asymmetry is regulated by dorsal ectoderm; radioulnar asymmetry is controlled by the zone of polarizing activity (ZPA). Within the progress zone (PZ) the fate of mesodermal cells is determined by these signaling centers. The axes and signaling centers are shown in three different orientations: **(B)** dorsal view, **(C)** lateral, end-on view, and **(D)** axial cross-section. (Modified from Oberg KC, Greer LF, Naruse T. *Embryology of the upper limb: the molecular orchestration of morphogenesis*. Handchir Mikrochir Plast Chir. 2004;36:98–107.)




Fig. 25.3 Morphologic impact of signaling centers. Upper panel: Role of apical ectodermal ridge (AER)-related Fgfs (orange) on skeletal outgrowth (humerus, blue; radius and ulna, green; hand, magenta). Middle panel: Role of Shh secretion from the zone of polarizing activity (ZPA): influence on the forearm and digits (depicted in purple). Lower left panel: Role of Wnt7a (medium green) and Lmx1b (light green), from the dorsal ectoderm and mesoderm respectively, in tendon and ligament formation in a digit. Do, dorsal; Vo, volar; Pr, proximal; Di, distal; PZ, progress zone. Lower right panel: Illustration depicting communication between signaling centers – reciprocal Shh–Fgf loop (black bidirectional arrow). Wnt7a influence on Shh expression (black unidirectional arrow). Rad, Radial; Uln, ulnar.

forearm and defines the identity of the ulnar four digits. In a naturally occurring chicken mutant, limb-specific *Shh* expression is lacking and the upper limbs develop without ulnas and without digits.²⁷ Application of exogenous *Shh* to the posterior (ulnar) aspect of the limb bud can fully recover normal limb morphology. Furthermore, application of *Shh* to the anterior margin produces mirrored duplication of ulnar digits radially.²⁴

The AER and the ZPA are also closely linked by a reciprocal feedback loop that maintains *Shh* expression at the distal posterior (ulnar) border of the limb bud adjacent to the AER during progressive outgrowth.^{28–30} Removal of the AER causes regression of *Shh* expression and ablation of the ZPA induces a loss of *Fgf* signaling.²⁹ Secretion of *Wnt7a* from the dorsal ectoderm induces the homeodomain transcription factor *Lmx1b* in the underlying mesoderm and asymmetrically dorsalizes the developing limb^{31,32} (see Fig. 25.3). *Wnt7a* also contributes to the maintenance of *Shh* secretion from the ZPA,³³ linking the dorsoventral and radioulnar axes. Removal of dorsal ectoderm reduces *Shh* expression and disrupts posterior (ulnar) patterning.³⁴ Thus, *Shh* plays a pivotal role during limb development linking dorsoventral, proximodistal, and radioulnar axes during outgrowth.³⁴

Around the end of the fifth week of development, the hand plate becomes visible. Current data suggest that digit number is established by an intrinsic Turing-type pattern generator within the hand plate using reciprocal activator (Bmps) and inhibitor (Wnt) interactions to define the alternating digit and interdigit pattern^{35,36} (Fig. 25.4). Interplay between *Hox* transcription factors (particularly *Hoxd9–13* and *Hoxa9–13*) and the *Shh*/*Gli3* pathway subsequently establishes digit morphology^{37–40} (Fig. 25.5). *Shh* also induces an ulnar to radial (posterior to anterior) gradient that appears to involve Bmps in at least two roles in the formation and differentiation of

digits. First, Bmps induce programmed cell death or apoptosis via discrete interdigital signaling centers, in part by repressing *Fgf* expression in the overlying AER.^{41–43} In addition, Bmps play a role in completing digital identity via the phalanx-forming region, a region overlying the distal digital anlagen that regulates *Sox9* expression and chondrogenesis.⁴⁴ Applying a Bmp-laden bead or transplanting Bmp-expressing interdigital tissue from the third interdigital space to the second transforms the second digit into a third digit.⁴¹ The phalanx-forming region also maintains digit-associated *Fgf* expression in the overlying AER for continued digital outgrowth.⁴⁴ With regression of the phalanx-forming region and loss of overlying *Fgf*, the terminal phalanges form at the distal tip of each digit, invoking a unique mechanism of ossification that includes membranous ossification in addition to anlagen formation.^{45,46} The terminal phalanx is also demarcated by persistent expression of *Msx1* in the mesoderm, and *Sp8* in the ectoderm.⁴⁷

The development/differentiation of specific tissues

Limb bud formation and the progressive morphologic changes evident externally are accompanied by differentiation of various tissues internally that are regulated by the coordinate signaling centers described above. Differentiation of these tissues is coincident, but will be discussed separately to add clarity and to relate timing of formation to tissue-specific malformations.

Limb vasculature

As the limb bud grows, nutrients and oxygen are needed to maintain rapid cell proliferation and the secretory activity of




Fig. 25.4 Determining the number of digits. An intrinsic Turing-like patterning mechanism for digit formation has been proposed using computational modeling and experimental evidence.^{35,36} In the upper left-hand corner is a diagram of a diffusion-driven instability model proposed by Turing. In the limb, evidence suggests that Bmp (red) is the activator while Wnt (yellow) is the inhibitor of diffusion-driven instability. Both factors are regulating the expression of *Sox9* (blue), the precursor of cartilage formation. Fgfs and the *Hox*/*Gli* pathway modulate the relative influence of the activator and inhibitor. Fgfs from the apical ectodermal ridge (AER) determine digit length and in concert with the distal *Hox*/*Gli* pathway limit digit number (green bar/gradient on the right). In addition, *Fmn1* restricts Bmp expression and mutations in *Fmn1* cause increased levels of Bmp with disruption of normal forearm (radioulnar synostosis) and hand (oligosyndactyly) patterning.^{143,144} The bottom of the illustration has a series of hand plates (note hand plate development remains static in this illustration to aid in illustrating features of the model) that show the progression from fluctuating activator-inhibitor interactions (noise) to a stabilized 5-digit pattern. On the right, progressive loss of digit suppressing *HOX*/*GLI* transcription factors (green bar) causes an increase in the number of digits patterned by the autonomous patterning mechanism. (Modified from Oberg KC, Ros MA, Goldfarb CA. *New Insights on upper limb development: digitizing the hand*. *IFSSH Ezine*. 2014;4(2):16–22.)




Fig. 25.5 Hand plate development. After the digit number has been established by intrinsic Turing patterning, the Shh pathway (with Gli3 repressor counter gradients) defines dependent/independent domains (boundaries indicated by dashed line) that determine digit morphologies. Interdigital mesoderm (ID1–ID5) regulates regression of the overlying apical ectodermal ridge (AER; orange) and digit morphologies of the adjacent anterior condensing digit via the phalanx-forming region (PFR; magenta) capping the distal tip of each anlagen. The PFR, in concert with the AER, determines phalanx size, length and joint position. The interdigital tissue subsequently undergoes Bmp-mediated programmed cell death (speckled regions). As the AER overlying the digit regresses, the distal or ungual phalanx forms and is demarcated by expression of mesodermal Msx1 (blue) and ectodermal Sp8 (green). (Image adapted from Oberg KC, Feestra JM, Manske PR, et al. *Developmental biology and classification of congenital anomalies of the hand and upper extremity*. J Hand Surg [Am]. 2010;35:2066–2076.)

the signaling centers. Induction of a primitive vascular system in the limb begins with transformation of mesoderm into angioblasts, cells that express the basic helix–loop–helix transcription factor Tal-1 and the vascular endothelial growth factor (VEGF) receptor Flk1.⁴⁸ A dense meshwork of primitive vascular channels forms *de novo* from angioblasts in the limb mesoderm.^{49,50} Angioblasts formed in nearby somites also migrate into the limb bud and contribute to the formation of new limb vessels through continued vasculogenesis.⁵¹ As angioblasts aggregate, differentiate into endothelium, and form primitive vascular tubes, new vascular markers emerge. Flk1 persists to allow further remodeling by VEGF, Tal-1 diminishes and VE-cadherin, a cell–cell adhesion molecule, is upregulated.

The primitive vascular network undergoes significant remodeling as the limb develops. By stage 13, the vascular channels coalesce proximally to form a central artery (subclavian) that connects to the dorsal aorta via the seventh intersegmental artery⁵² and two peripheral veins form that drain

into the posterior cardinal system.⁵⁰ In addition to vasculogenesis, angiogenesis, i.e., vessel sprouting from a preformed vessel, also contributes to the definitive architecture of the limb vasculature.

Construction of the vascular pattern is under the direction of the coordinate signaling centers and involves the regulation of specific VEGF family members and VEGFR3 receptors.^{52–54} The final vascular pattern progresses from proximal to distal (Fig. 25.6) – with formation of the axillary artery by stage 17 and the brachial and major forelimb branches by stage 19. The median artery is prominent in the forearm.⁵⁵ Distally the capillary plexus persists. Ulnar differentiation precedes radial differentiation and is evident distally by the radial artery merging with an extensive primitive capillary plexus radially, while the ulnar side of the axis is already forming the palmar arch which communicates with the ulnar associated capillary plexus.⁵⁶ The median and interosseous arteries decrease in size. The median artery degenerates, providing blood supply to the median nerve only.⁵⁵




Fig. 25.6 Vasculogenesis of the developing upper limb. Progressive vascular remodeling from Carnegie stage 13 through 21, showing: subclavian artery (S), axillary (A), brachial (B), median (M), radial (R), ulnar (U), interosseous (I), palmar arches (PA), and digital (D) arteries (red). Note the primitive vascular plexuses persist distally on the radial aspect at stage 19. The veins have also remodeled during this period, from a distal sinus and anterior (radial) and posterior (ulnar) marginal veins, into the distinctive veins of the limb (illustrated in blue).

The vascular network must include arteries, capillaries, and veins. The diameter of each is dictated by blood flow, blood pressure, shear stress, and the accumulation of vascular smooth muscle around the vessel.⁴⁹ Formation of vascular smooth muscle around limb arteries lags behind vessel formation by about 2 days. It is unclear whether these muscle cells are derived from the endothelial cells or are condensations of the surrounding mesoderm. Furthermore, the mechanism underlying differential smooth-muscle accumulation in arteries and veins is unknown. Arteries are also differentiated from veins by the expression of Ephrin B2, a membrane-bound ligand, while the Eph-B4 receptor highlights veins. Presumptive capillaries will be negative to both Ephrin B2 and the Eph-B4 receptor.

By stage 21, the major vessel architecture is complete. The majority of vascular anomalies arise between stages 17 and 21, i.e., between days 41 and 52 or largely within the seventh and early eighth week of development. Lymphatics follow a similar course, albeit less well delineated, and are also composed of angioblasts that migrate into the limb from somitic mesoderm.⁵¹ A defining molecular difference in lymphatic vessels is the coexpression of PROX-1 and LYVE-1.⁵⁷

Skeletogenesis

Under the influence of the limb signaling centers, Sox9, a high-mobility group transcription factor, is upregulated in a targeted population of limb mesoderm.⁵⁸ Sox9 transforms these cells into chondrogenic precursors and induces condensation, the first step in limb skeletogenesis.^{59,60} Chondrogenesis occurs in a proximal to distal progression (Fig. 25.7). The expression of Sox5 and Sox6 is required for further differentiation of chondrogenic precursors into chondrocytes to form cartilage anlagen.⁶¹

At precise locations within the forming skeletal anlagen, synovial joints form. Hoxa transcription factors (Hoxa9–13) exhibit expression patterns along the proximodistal axis that correlate with skeletal segmentation.⁶¹ In addition, several molecules are known to participate in the process of joint formation, including Wnt14 and Gdf5. The first morphologic

evidence of joint formation is the compact cellular condensation called the interzone that expresses Wnt14.⁶² In addition, Gdf5 is induced in the proximal portion of the interzone, covering the distal end of the proximal anlagen.^{63,64} The central region of the interzone begins to expand, accumulates hyaluronan, and becomes hypocellular in a process termed cavitation.^{65,66} The two cellular regions of the interzone begin to differentiate into the opposing articular cartilage surfaces. Patterning signals and movement work in concert to shape the joint into its definitive morphology⁶⁴ (Fig. 25.8). Mesoderm surrounding the developing joint condenses to form the joint capsule.⁶⁷

Endochondral ossification converts the cartilage anlagen into the skeletal framework of the growing limb. This process is under precise regulation and involves Runx2, Twist1, Fgfs, Indian hedgehog (Ihh), and vascular endothelial growth factors (Vegfs).⁶⁰ Chondrocytes are induced to proliferate, undergo hypertrophy, and then die, leaving an extracellular cartilage matrix. This matrix is subsequently invaded by blood vessels, osteoclasts, and differentiating osteoblasts. Osteoblast differentiation is also under the control of Runx2 and Osterix (Osx), a bone-specific transcription factor.⁶⁸ Ossification begins within the diaphysis of anlagen at the primary ossification center during early fetal development. Subsequently, vascular invasion of the proximal epiphysis occurs, followed by the distal epiphysis forming secondary ossification centers later in development. Each metacarpal and digital phalanx has two ossification centers, a primary center within the diaphysis and a single secondary center that develops postnatally.

Bony malformations are most likely to involve the disruption of Sox9 and the progressive proximal to distal anlagen formation, i.e., radiohumeral synostosis would occur earlier in development than polydactyly or syndactyly.

Myogenesis

Muscular development of the upper limb is a coordinated effort between segment-specific tendon primordium, migrating myocytes, and migrating motor neurons.^{69,70} There are




Fig. 25.7 Skeletogenesis of the developing upper limb. By Carnegie stage 17 there is partial rotation of the humerus (Hu, blue) at the shoulder and the elbow joint is starting to form. Radius (Rad, green); ulna (Uln, green); hand, magenta.




Fig. 25.8 Joint formation. (Modified from Pacifici M, Koyama E, Iwamoto M. Mechanisms of synovial joint and articular cartilage formation: recent advances, but many lingering mysteries. *Birth Defects Res C Embryo Today*. 2005;75:237–248.)

three phases to myogenesis.⁷¹ Embryonic myogenesis establishes the primary myotubes and the basic muscle layout. Later, a second wave of myogenesis occurs with secondary myofibers surrounding primary myofibers and contributing to the bulk of the muscle mass present at birth. Finally, satellite cells that take up residence in the basal lamina surrounding myofibers will contribute to postnatal growth and muscle regeneration.⁷²

During early limb bud formation, limb mesoderm condenses to form the proximal tendon primordium (PTP), establishing a target and an initial scaffold for migration of myocytes.⁶⁹ Myocyte precursors of the limb arise from the dorsolateral aspect of associated somites (the dermomyotome subdivision) and express the Pax3 transcription factor. Muscle precursors for the limb and body wall express c-Met, a surface receptor that is modulated by scatter factor initially

emanating from the lateral plate mesoderm and then later from other sites, including the PZ. Scatter factor acts as a chemoattractant to promote myocyte precursor migration. A population of the myocyte precursors further differentiates into limb-specific precursors, demarcated by Lbx1 expression⁷³ (Fig. 25.9).

During embryonic myogenesis, limb-specific myocytes migrate into the proximal limb bud, initially as dorsal and ventral masses (Fig. 25.9). Continued migration, however, is not haphazard; rather, myocyte precursors are directed into muscle anlagen by the tendon primordium, e.g., the ventral mass migrates into the biceps and brachialis under the direction of the PTP (Fig. 25.10, Carnegie stage 15). With continued proliferation and differentiation, the myocytes upregulate MyoD and Myogenin, declaring their commitment as myocytes. These myocytes will then coalesce to form fibers and




Fig. 25.9 Early neuromuscular development in the upper limb. (A) Dorsovolar view of presumptive myocyte migration into the limb from the lateral aspect of the dermomyotome (DM) – molecular markers listed in gray box. (B) Motor and sensory projection of processes into the developing limb. SK, Sclerotome; SF, scatter factor; Do, dorsal; Vo, volar; Pr, proximal; Di, distal; Cut, cutaneous; Proprio, proprioception.




Fig. 25.10 Muscular development in the upper limb. Progressive myocyte migration and muscle formation between Carnegie stages 13 through 21 showing the ventral or volar surface. Note the resting flexed position of the upper limb in the stage 21 embryo rotates the upper arm so that the elbows shift from dorsal to caudal and the forearm rotates medially at the elbow. The palmaris longus and flexor carpi radialis are not shown. PTP, Proximal tendon primordium; ITP, intermediate tendon primordium; DTP, distal tendon primordium; Bi, biceps; Tri, triceps; B, brachialis; BR, brachioradialis; PL, flexor pollicis longus; FDP, flexor digitorum profundus; FCU, flexor carpi ulnaris; FDS, flexor digitorum superficialis.

begin to produce myosin filaments. Satellite cells, important for later growth and muscle regeneration, take up residence just under the basal lamina of the developing myofibers.⁷² Concurrently, the tendon primordia further define the shape of specific muscles with discrete tendinous attachments. For example, expression of *Lmx1b* within the dorsal tendons directs the unique pattern of extensor attachments⁷⁴ and it is likely that each upper limb muscle is shaped by a unique combination of patterning factors.⁷⁵

As in other aspects of upper limb development, there is progressive differentiation from proximal to distal. Thus, as the muscles of the upper arm take shape, migrating myocytes invade the forearm to associate with the PTP and a new mesodermal condensation forming at the presumptive wrist, the intermediate tendon primordium. In the forearm, the superficial muscles differentiate before the deep muscles. By Carnegie stage 17, the distal tendon primordia form and associate with migrating myocytes destined to be muscles of

the hand (see Fig. 25.10). The intrinsic muscles arise from five embryonic muscle layers, which differentiate and fuse in a complex but logical manner.^{76,77} Following embryonic myogenesis, a second wave of myocyte precursors migrate into the limb and coalesce around primary myofibers, forming secondary myofibers and adding bulk to the muscle masses as the fetus grows. It is during this secondary or fetal myogenesis that formation of motor endplates occurs and neuromuscular communication begins, further differentiating the forming muscle with slow and fast fiber types.^{78,79}

Innervation

Outgrowth of nerves into the limb bud lags behind muscle migration (Fig. 25.11) and involves both motor and sensory neurons.⁸⁰ Motor neurons are specified early during spinal cord development by exposure to *Shh*, initially from the notochord and later from the floor plate of the developing




Fig. 25.11 Nervous development in the upper limb. Progressive innervation of the upper limb and formation of the brachial plexus. Rt, Nerve roots; T, trunks; U, upper; M, middle; L, lower; C, cords; Lat, lateral; Med, medial; Pst, posterior; A, axillary; Mc, musculocutaneous; R, radial; Md, median; U, ulnar.

neural tube.^{81,82} Motor neurons begin to express a combination of transcription factors (e.g., Hb9/Mnx1, Lhx3/4) that promote motor neuron migration into discrete columns within the spinal cord and direct their axons to specific muscle groups.⁷⁰ Within the limb fields (specified by Hox6 in the forelimb and Hox10 in the hindlimb), a Hox accessory factor, FoxP1, is expressed that assists in deciphering the subsequent Hox-specific code within the limb for appropriate axon targeting.⁸³ As the axons of the motor neurons enter the limb, those expressing Lim1 (Lhx1) will project into the dorsal Lmx1b-expressing compartment of the limb to target dorsal extensor muscle groups. The remaining axons express Isl1 and will enter the ventral compartment to target flexor muscles of the limb.

Sensory processes accompany the axons of motor neurons into the limb. The cell bodies of sensory neurons reside within the dorsal root ganglion (DRG), which is derived from neural crest cells. Specification of sensory neurons within the DRG is characterized by upregulation of neurogenin1 and 2 (Ngn1/2) and brain-specific homeobox/POU domain protein 3A (Brn3a). Furthermore, cutaneous sensory neurons also express a runt homeodomain transcription factor 1 (Runx1), while neurons involved in proprioception express Runx2.

The nerve roots, containing motor and sensory processes from C4 to T1, coalesce to form a meshwork or plexus that eventually leads to the formation of three major trunks in the upper limb – upper, middle, and lower (see Fig. 25.11, Carnegie stage 15). The segregation of dorsal and ventral processes as the nerves project into the limb divides the plexus into dorsal (posterior) and ventral (anterior) divisions, which form the posterior, lateral, and medial cords, whose names relate to their anatomic positions in the adult. The posterior cord gives rise to the axillary and radial nerves. The lateral cord gives rise to the musculocutaneous nerve and contributes to the median nerve. The medial cord forms the ulnar nerve and combines with processes from the lateral cord to form the median nerve.

The initial trajectory of processes is independent of neuromuscular communication and instead depends on a combinatorial expression of transcription factors that guide processes to targets expressing specific patterning factors within the limb.⁸⁰ However, during secondary or fetal myogenesis, patterning factors, motor endplate formation, and neuromuscular communication are required for fiber-type differentiation and survival of both muscles and nerves.^{70,73,78}

Anomalies of limb development and their classification

Background

Congenital anomalies in the hand and upper limb demand a reproducible and consistent terminology, a universal language that allows discussion of complex clinical entities, indications for treatment, and comparisons of results. The terminology of dysmorphology offers a basis for understanding the etiology of congenital limb anomalies.⁸⁴ A *malformation* is an abnormal formation of tissue resulting from abnormal cell formation. *Deformation* differs from a malformation as the insult is to cells that have already formed normally. It is a deformation of

normal tissue. *Dysplasia* is a lack of normal organization of cells into tissue. Dysmorphologists describe a fourth term, *disruption*. As this process involves alteration of tissue that is already formed, for the purposes of classification it is reasonable to include those conditions that are considered to be disruptions alongside those considered to be deformations. Although the pathogenesis of some specific anomalies remains obscure, the concept of separating malformations, deformations, and dysplasias provides a sound structure for categorizing congenital upper limb anomalies.

Ideally, a classification of congenital hand anomalies would be based on etiology, with such a classification indicating the site in the molecular pathway and/or the anatomical site in the limb bud at which the aberration occurs, and one that also is indicative of the timing of the causative disruption.

The first classification was probably that of Isidore St. Hilaire in 1832.⁸⁵ This introduced terms such as “phocomele” (seal limb), “hemimele” (part of the limb missing), and “ectromele” (limb absence). Frantz and O’Rahilly based their classification on skeletal appearance.⁸⁶ They introduced the concepts of terminal and intercalary defects, subsequently adding the subcategories of transverse and longitudinal deficiencies and including the involvement of pre- or postaxial position within the limb.⁸⁶ Kelikian has summarized the contributions of many authors in his classic text, *Congenital Deformities of the Hand and Forearm*, but acknowledged that “We have not as yet attained enough latitude of knowing about congenital hand anomalies to formulate a comprehensive classification.”⁸⁷

Subsequently, the currently accepted surgical classification of upper limb anomalies was that based on the proposals of Swanson *et al.* in 1968,⁸⁸ refined by Swanson and colleagues in 1976¹ and 1983,⁸⁹ accepted by the IFSSH and then expanded by Knight and Kay in 2000² and Upton in 2006⁹⁰ to encompass all anomalies. Although this system served us well, an increasing number of surgeons, pathologists, and geneticists working in the field of congenital limb anomalies began to question the adequacy of this classification and have suggested alternative approaches.^{91–94}

Problems of the Swanson classification

The Swanson classification was derived from an understanding of normal embryological development that was available in the 1960s and 1970s. The system is based upon clinical and radiological assessments that describe failures in certain anatomical structures. The two major groups of this classification do offer an indication of the timing of the causative insult by separating “failure of formation” from “failure of differentiation”. However, formation and differentiation occur together, and it may be impossible to determine whether any specific anomaly is one or the other. Furthermore, the need to create separate groups for “duplication”, “undergrowth”, and “overgrowth” is illustrative of the inherent limitations of using these descriptive terms as components of a classification system, as these anomalies could also be considered as failures of formation and/or differentiation.

A system based on appearance is unable to incorporate changes based on our increasing understanding of etiology and causation at a molecular level. Attempts to do so create contradictions that are difficult to resolve. A consideration of central clefting and symbrachydactyly is illustrative. The




Fig. 25.12 (A,B) Clinical and radiological appearance of the association of clefting, syndactyly, and polydactyly.

Swanson classification places central clefting of the hand within the “failure of formation” group as a “central longitudinal deficiency”. However, many would not view this condition as a longitudinal deficiency in the manner of radial and ulnar longitudinal deficiencies for the following reasons: the limb anomalies are usually confined to hands and feet; the terminology erroneously suggests the presence of a central axis within the developing limb; the elegant experimental work and clinical observations of Miura,⁹⁵ Ogino,⁹⁶ and others have drawn attention to the association of clefting with syndactyly and polydactyly (Fig. 25.12). Consequently, the Japanese Society for Surgery of the Hand (JSSH) introduced an extra group within the Swanson classification, this being an “abnormal induction of rays”.⁹⁷ Although the introduction of this new group was attractive and well based, such modifications of the IFSSH classification introduced significant contradictions.

In this new subclassification of the JSSH, central polydactyly became an “abnormal induction of rays”. However, radial and ulnar polydactyly remained under the group “duplication”. Morphologically, the process of duplication, be it central, radial, or ulnar, appears to be similar (Fig. 25.13). All could be considered as an “abnormal induction of rays”.

Syndactyly, be it simple or complex with phalangeal synostosis, was moved from “failure of differentiation” to “abnormal induction” (Fig. 25.14). Yet under the system proposed by the JSSH, symbrachydactyly, which has a component of syndactyly, became a “transverse failure of formation”. Brachydactyly, which may include symbrachydactyly as a subcategory, remained within group 5, “undergrowth”. Carpal synostoses and symphalangism remained within “failure of differentiation”, although they both occur commonly in symbrachydactyly. All could be considered as an “abnormal induction of rays”. Indeed, a longitudinal radial

deficiency in the forearm could be considered as an abnormal induction of forearm radial structures. Whether any particular condition is a failure of formation, a failure of differentiation, or an abnormal induction is probably a dated and unhelpful concept, the differences being those of semantics.

In the search for evidence to support the suggestion that syndactyly, central polydactyly, and clefting should be classified within a single and new group, it is helpful to review the conditions with these characteristics that have a known genetic basis. Synpolydactyly (syndactyly type II) is caused by an identified gene – *HoxD13* – mapped to a known chromosomal locus – 2q31–32.⁹⁸ Clefting has not been described as an association of this genetic abnormality. Central longitudinal deficiency (clefting or split-hand/foot malformation) is also inherited in an autosomal-dominant manner. Its locus is known and differs from that of the synpolydactyly gene mutation. Type I syndactyly, in which there is non-separation of digits 3 and 4 in the hands, often accompanied by non-separation of digits 2 and 3 in the feet, also involves an abnormal gene, not yet identified, but which has been mapped to yet another locus.⁹⁹ From this, it becomes apparent that a particular phenotype may result from abnormalities in several genes at different chromosomal loci in one or many of the complex pathways involved in normal hand development, rather than from one constant gene abnormality. There may also be variations in phenotypic expression of single-gene mutations. It would appear that complex interactions involving formation of extra digits and joining of those digits are associated with cleft formation.¹⁰⁰ However, it is less certain that an inexorable teratogenic sequence obligatorily links isolated cases of polydactyly and syndactyly with clefting.¹⁰¹

The separation of symbrachydactyly from brachydactyly, noted above, also imposes apparent contradictions. The JSSH considers symbrachydactyly to be synonymous with




Fig. 25.13 (A–C) Clinical and (D–F) radiological appearance of central, radial, and ulnar polydactyly at the proximal phalangeal level.

“transverse failure of formation” and therefore suggested that symbrachydactyly be moved from group 5, “undergrowth”, to group 1 of the Swanson classification.^{97,102} This necessitates combining transverse deficiencies, in which terminal ectodermal elements are absent, with symbrachydactyly, in which the initial deficiency is middle phalangeal and, even in severe cases, terminal elements – nail and terminal phalangeal remnants – remain (Fig. 25.15). The Japanese allow for this by adding a “peripheral hypoplasia type” to the five types of the symbrachydactyly subclassification, so that all transverse deficiencies are included as a form of symbrachydactyly. Others consider this to be contradictory, believing symbrachydactyly to be a distinct entity, and to have a clear definition of intersegmental failure, which does not encompass terminal transverse deficiencies.¹⁰³ Regardless, the term “undergrowth”

represents an appearance only and is unable to embrace the above concepts.

The groups documented as “duplication”, “overgrowth”, and “constriction ring syndrome” suffer from similar limitations. It became clear that increasing problems with the Swanson classification demanded an alternative approach.

The OMT classification

Oberg, Manske and Tonkin developed a classification system that incorporated newer knowledge of the etiology, molecular genetics, and developmental biology of congenital limb anomalies,^{93,94} which was presented in the third edition of this text.¹⁰⁴ This system has undergone three major objective assessments, which have resulted in some modifications.^{105–107}




Fig. 25.14 Syndactyly in association with (A) symbrachydactyly short finger type; (B) mitten hand; (C) ulnar longitudinal deficiency; (D) Greig cephalopolysyndactyly syndrome.

The main alteration involves those conditions that were previously placed separately as not primarily involving one of the three specific axes (unspecified axis). These have been incorporated into the two main malformation subgroups – upper limb and hand plate alone. Other more minor modifications and additions are included in Table 25.2. The reviews have confirmed the efficacy of the OMT classification with good inter- and intra-observer reliability.

All anomalies are placed within one of three groups defined at the beginning of this section: group 1, malformations; group 2, deformations; and group 3, dysplasias (see Table 25.2).

The anomalies that were documented under groups 1, 2, 3, and 5 in the Swanson scheme become malformations (group

1). This classification scheme does not attempt to separate an abnormal formation from an abnormal differentiation. Malformations are subdivided according to whether the insult affects the upper limb as a whole or the hand plate alone, and whether it primarily involves one of the three axes of growth and patterning described in the preceding section of this chapter. This approach incorporates an understanding of the mechanism of insult and the site within the developing limb that is primarily affected.^{93,94} Symbrachydactyly, for instance, is an example of abnormal tissue formation and differentiation within the proximal–distal axis, as are the other transverse failures of formation (Fig. 25.16). Radial longitudinal deficiency involves primarily the radial–ulnar axis (Fig. 25.17) and loss of dorsalization of hand and upper limb structures in nail–patella syndrome involves the dorsal–ventral axis. In all of these anomalies, the whole of the upper limb may be involved, e.g., thumb hypoplasia with radial aplasia. Duplications that affect the whole of the upper limb, such as ulnar dimelia, are malformations with abnormal axial patterning



Fig. 25.15 Symbrachydactyly monodactylous type with terminal ectodermal elements.



Fig. 25.16 Symbrachydactyly with short arm, hand, and fingers.

Table 25.2 Modified classification of congenital anomalies of the hand and upper limb (updated January 28, 2015)

I. Malformations	
A. Abnormal axis formation/differentiation – entire upper limb	
1. Proximal–distal axis i. Brachymelia with brachydactyly ii. Symbrachydactyly a) Poland syndrome b) Whole limb excluding Poland syndrome iii. Transverse deficiency a) Amelia b) Clavicular/scapular c) Humeral (above elbow) d) Forearm (below elbow) e) Wrist (carpals absent/at level of proximal carpals/at level of distal carpals) (with forearm/arm involvement) f) Metacarpal (with forearm/arm involvement) g) Phalangeal (proximal/middle/distal) (with forearm/arm involvement) iv. Intersegmental deficiency a) Proximal (humeral – rhizomelic) b) Distal (forearm – mesomelic) c) Total (phocomelia) v. Whole limb duplication/triplication 2. Radial–ulnar (anterior–posterior) axis i. Radial longitudinal deficiency – thumb hypoplasia (with proximal limb involvement) ii. Ulnar longitudinal deficiency iii. Ulnar dimelia iv. Radioulnar synostosis v. Congenital dislocation of the radial head vi. Humeroradial synostosis – Elbow ankyloses vii. Madelung deformity 3. Dorsal–ventral axis i. Ventral dimelia a) Furhmann/Al-Awadi/Raas–Rothschild syndromes b) Nail–patella syndrome ii. Absent/hypoplastic extensor/flexor muscles 4. Unspecified axis i. Shoulder a) Undescended (Sprengel) b) Abnormal shoulder muscles c) Not otherwise specified ii. Arthrogryposis	iv. Triphalangeal thumb v. Ulnar dimelia (mirror hand – no forearm/arm involvement) vi. Ulnar polydactyly 3. Dorsal–ventral axis i. Dorsal dimelia (palmar nail) ii. Ventral (palmar) dimelia (including hypoplastic/aplastic nail) 4. Unspecified axis i. Soft tissue a) Syndactyly b) Camptodactyly c) Thumb in palm deformity d) Distal arthrogryposis ii. Skeletal deficiency a) Clinodactyly b) Kirner's deformity c) Synostosis/symphalangism (carpal/metacarpal/phalangeal) iii. Complex a) Complex syndactyly b) Synpolydactyly – central c) Cleft hand d) Apert hand e) Not otherwise specified
II. Deformations	
A. Constriction ring sequence	
B. Trigger digits	
C. Not otherwise specified	
III. Dysplasias	
A. Hypertrophy	
1. Whole limb i. Hemihypertrophy ii. Aberrant flexor/extensor/intrinsic muscle 2. Partial limb i. Macrodactyly ii. Aberrant intrinsic muscles of hand	
B. Tumorous conditions	
1. Vascular i. Hemangioma ii. Malformation iii. Others 2. Neurological i. Neurofibromatosis ii. Others 3. Connective tissue i. Juvenile aponeurotic fibroma ii. Infantile digital fibroma iii. Others 4. Skeletal i. Osteochondromatosis ii. Enchondromatosis iii. Fibrous dysplasia iv. Epiphyseal abnormalities v. Others	
B. Abnormal axis formation/differentiation – hand plate	
1. Proximal–distal axis i. Brachydactyly (no forearm/arm involvement) ii. Symbrachydactyly (no forearm/arm involvement) iii. Transverse deficiency (no forearm/arm involvement) a) Wrist (carpals absent/at level of proximal carpals/at level of distal carpals) b) Metacarpal c) Phalangeal (proximal/middle/distal) 2. Radial–ulnar (anterior–posterior) axis i. Radial deficiency (thumb – no forearm/arm involvement) ii. Ulnar deficiency (no forearm/arm involvement) iii. Radial polydactyly	

Table 25.2 Modified classification of congenital anomalies of the hand and upper limb (updated January 28, 2015)—cont'd

IV. Syndromes*	
A. Specified	
1. Acrofacial dysostosis 1 (Nager type)	23. Leri–Weill Dyschondrosteosis
2. Apert	24. Moebius sequence
3. Al-Awadi/Raas–Rothschild/Schinzal phocomelia	25. Multiple synostoses
4. Baller–Gerold	26. Nail–patella
5. Bardet–Biedl Carpenter	27. Noonan
6. Beales	28. Oculodentodigital dysplasia
7. Catel–Manzke	29. Orofaciodigital
8. Constriction band (amniotic band sequence)	30. Otopalatodigital
9. Cornelia de Lange (types 1–5)	31. Pallister–Hall
10. Crouzon	32. Pfeiffer
11. Down	33. Pierre Robin
12. Ectrodactyly–Ectodermal Dysplasia–Clefting	34. Poland
13. Fanconi pancytopenia	35. Proteus
14. Fuhrmann	36. Roberts–SC phocomelia
15. Goltz	37. Rothmund–Thomson
16. Gorlin	38. Rubinstein–Taybi
17. Greig Cephalopolysyndactyly	39. Saethre–Chotzen
18. Hajdu–Cheney	40. Thrombocytopenia absent radius
19. Hemifacial Microsomia (Goldenhar syndrome)	41. Townes–Brock
20. Holt–Oram	42. Trichorhinophalangeal (types 1–3)
21. Lacrimoauriculodentodigital (Levy–Hollister)	43. Ulnar–mammary
22. Larsen	44. VACTERLS association
	B. Others

*The specified syndromes are those considered most relevant; however, many other syndromes have a limb component categorized under “B. Others”.
 VACTERLS, vertebral defects, anal atresia, cardiac defects, tracheo-esophageal fistula, renal anomalies, and limb abnormalities.
 (Source: http://ifssh.info/2015_OMT_Classification_Congenital_Report.pdf)

within the radial–ulnar axis. All of these are classified within group 1A, according to the axis involved, unless the axis is unspecified.

Alternatively, the primary defect may reside within the hand plate alone and not involve proximal limb components. It may affect one of the axes of development or be of unspecified axis. This approach allows incorporation of Swanson group 3 “duplications”, radial and ulnar polydactyly, into a

group that indicates intuitively the anatomical site and the axis in which the aberration occurs (Fig. 25.18). The triphalangal thumb may best be included in this group. Dorsal dimelia of the little finger is an example of hand plate involvement involving the dorsal–ventral axis (Fig. 25.19). All of these conditions are classified within group 1B. The cleft hand complex, isolated syndactyly, and central synpolydactyly are examples of hand plate conditions of unspecified axis. This satisfies the concern that cleft hand complex is not a longitudinal deficiency but rather a primary insult to the hand plate (Figs. 25.12 & 25.20).

Group 2 in Table 25.2 allows the classification of amniotic band sequence (constriction ring syndrome) as a deformation, separating it from the malformations of group 1. The insult affects a part already formed (Fig. 25.21).

Group 3, dysplasias, includes many otherwise difficult-to-classify conditions that have previously been listed according to their appearance. Limb hypertrophy and macrodactyly that is consequent upon tumor formation are examples (Fig. 25.22), as are the other tumorous conditions. All of these were previously classified either as a “failure of differentiation” (tumorous conditions) or purely as a descriptive term – “overgrowth” for macrodactyly or limb hypertrophy. There may be dissent as to whether these conditions are in fact malformations or deformations instead of dysplasias. Indeed, increasing knowledge may demand their future transfer to either group 1 or group 2. This system allows such adjustments.

This classification has the advantages of allowing inclusion of all groups within a logical framework; of utilizing a common terminology; and of indicating a site of anatomical insult in



Fig. 25.17 Radial longitudinal deficiency affecting arm, forearm, hand, and digits of both limbs in brothers with Holt–Oram syndrome.



Fig. 25.18 (A,B) Radial and ulnar duplications demonstrate involvement of radial and ulnar axial abnormalities within the hand.



Fig. 25.19 (A,B) Dorsal dimelia of the little finger.



Fig. 25.20 Cleft hand complex affecting the hand only.

the developing or developed limb bud. The common descriptive terms, which are familiar to all surgeons, are placed within this framework. Each common descriptive diagnosis, such as radial longitudinal deficiency, retains its surgical subclassification, i.e., groups 0–4 for radial aplasia and Blauth groups 1–5 for thumb hypoplasia. These surgical subclassifications are discussed in subsequent chapters devoted to specific anomalies.



Fig. 25.21 Constriction ring syndrome with acrosyndactyly.



Fig. 25.22 Macrodactyly.

Although aberrations in some molecular pathways have been identified as causative of specific anomalies, it is not yet possible to develop a classification that relates cause and effect at the molecular level for all limb anomalies. Furthermore, the complex interaction between the various signaling centers and the cascades of molecular pathways that they control must be appreciated. Hence, any disruption of one signaling center or pathway will have consequences within other signaling centers and pathways, both upstream and downstream. However, many but not all of the current contradictions and flaws find solutions in this method of classification, which also allows adaptation based on evolving knowledge. Of importance is the necessity to utilize a system that allows recording of all anomalies present in any particular child. It is not a contradiction to document more than one diagnosis per child. If, for instance, polydactyly, clefting, and syndactyly occur together, then this is simply classified under “cleft hand complex”. However, if a limb presents with apparently unassociated anomalies, such as syndactyly and clinodactyly, these are documented separately.

A further addition has been to list the common syndromes. This allows cross-reference with specific anomalies when the anomaly is part of a syndrome. For instance, Holt–Oram syndrome is documented and the limb anomaly – radial longitudinal deficiency (entire upper limb or hand plate alone) – is also documented.

In 2014, the IFSSH Scientific Committee for Congenital Conditions recommended adoption of the OMT classification system.³ That committee accepted that no classification system is perfect, that the classification of some conditions remains controversial and, for these, the principle of “best fit” is utilized. The Committee recommended that, as the OMT system has the ability to be flexible and respond to new developments and additional conditions, there be reviews at 3-year intervals and modifications as appropriate following those reviews.

Assessment of the child and family

There are great rewards in treating children who are unfortunate enough to be born with hands we recognize as less than perfectly formed. Adaptive ability in the child is quite extraordinary, such that some question the wisdom of surgical interference for many presentations. Furthermore, initially, the hand is normal to the child. It is a growing awareness of the “normal” environment that alters the child’s perception. However, it is the observation of many that the child reflects the attitudes of others. If parents, relatives, friends, doctors, or therapists consider the problem to be overwhelming, the child will be more likely to have a problem.

For the surgeon, the opportunity to observe the development of the child and hand function during growth and learning provides a satisfaction that cannot be underestimated. Decision-making must be precise and involve parents and child such that all develop a confidence that the treatment is both appropriate and in capable hands. Few surgical fields allow greater application of surgical principles to the management of deformity and loss of function. The aim is to achieve optimal hand function – prehensile grasp and dexterity of fingers and thumb for fine activity – whilst also striving for optimal appearance.

The involvement of family doctor and pediatrician, therapist, and psychologist in the overall management of child and family is necessary. The geneticist can assist in identifying inheritance factors and advise regarding risk of recurrence for subsequent children. Specialist medical care is often required, as involvement of systems other than the musculoskeletal system is common. Specifically, cardiac, hematological, neurological, gastroenterological, and urological systems must be investigated for abnormalities. Many syndromic patterns have been described and alert the surgeon and treating physicians to probable associations. Finally, support groups can be of significant benefit. Often parents and children find great solace and encouragement from discussing their problems with others with similar afflictions.

The clinic

A calm, private, and warm environment is conducive to optimal assessment. Parents, often young, may be overwhelmed by the medical and paramedical attention that has been directed towards them and their child. At the initial introduction, the child and parents should not be confronted by too many foreign faces, perhaps only the surgeon and one other. Minimally, the surgical congenital hand clinic should also have immediate access to experienced occupational therapists and physiotherapists. In developed societies, an assessment of all other systems has been completed or is in progress before consultation with the hand surgeon. However, it is vital that the treating surgeon has sufficient understanding of the processes of normal and abnormal limb development and is sensitive to the association of other system anomalies with specific hand and upper limb anomalies. The parents expect and should receive information from the surgeon regarding: the cause and mechanism of dysmorphogenesis; the likelihood of recurrence in subsequent children, and the likelihood of recurrence in future children of the presenting child; a description of the dysfunction the child is

likely to confront in the future; and the possible methods and timing of procedures aimed at improving function and appearance. Photographs and models of pre- and postoperative example cases are beneficial in demonstrating expected outcomes. They also provide reassurance that surgery is not disfiguring.

History

Following introductions, a preliminary examination through observation alerts the surgeon to possible diagnoses and associations. A detailed history of the pregnancy, its duration and any untoward events, the lie of the child *in utero*, and the method of delivery and birth weight provide valuable information. The presence of a positive family history of limb anomalies in siblings, parents, and the relatives of parents is suggestive of an inherited disorder. The surgeon should always question as to whether there are anomalies in other systems and whether a general pediatric review has been performed. The need for further specific system review may become apparent during the assessment.

Examination

Observation of the child at play provides much information, which may be withheld if the surgeon approaches a direct physical examination of the child either too early in the assessment process or too brusquely.

An understanding of developmental milestones is integral to recognition of delayed or abnormal functional development (Table 25.3).¹⁰⁸ The child’s upper limb movements are mainly reflexive at birth. There is a rudimentary grip via digit flexion. The thumb is clasped within the palm but exhibits reflex extension when startled.^{109,110}

The development of prehension is well summarized by the work of Erhardt and Lindley.¹¹¹ These patterns are depicted in Fig. 25.23. They demonstrate the development from rudimentary grasp utilizing an ulnar power grip, to precision function radially incorporating the thumb. Fig. 25.24 demonstrates the

Table 25.3 Development of hand control

Hand control	When achieved (months)
Grasp small objects by ulnar–palm prehension	4
Grasp by partial thumb opposition	5
Transfer objects between hands	6
Grasp by full thumb opposition	7
Bang an object on a flat surface	7
Drink from cup held in hand with assistance	9–10
Pincer grasp	12
Scribble with crayon	13–15
Throw ball	18
Build a tower with 4–6 blocks	24
(Reproduced from: Gupta A, Kay SPJ, Schecker LR (eds). <i>The Growing Hand: Diagnosis and Management of the Upper Extremity in Children</i> . London: CV Mosby; 2000:51.)	




Fig. 25.23 (A–D) The development from rudimentary grasp, utilizing an ulnar power grip to precision function radially incorporating the thumb. (Redrawn after Erhardt RP. *Developmental Hand Dysfunction: Theory, Assessment, and Treatment*, 2nd edn. San Antonio: Therapy Skill Builders; 1994.)




Fig. 25.24 Change in weight-bearing through the upper limbs through the first 5 months of life. (Redrawn after Erhardt RP. *Developmental Hand Dysfunction: Theory, Assessment, and Treatment*, 2nd edn. San Antonio: Therapy Skill Builders; 1994.)




Fig. 25.25 Timing of appearance of ossification centers and closure of growth plates. (Reproduced from Upton J. *Classification of upper limb congenital differences and general principles management*. In: Mathes SJ (ed.) *Plastic Surgery*, 2nd edn, vol. 8. Philadelphia: Elsevier; 2006:27.)

change in weight-bearing through the upper limbs over the first 5 months of life.

Determination of hand dominance is usually not possible in the first year or so but becomes apparent by age 5.^{112–114}

A general examination includes observation of the facial appearance with specific attention to eyes, ears, mouth, and jaw, examination of the spine and lower limbs, observation and palpation of the chest wall and abdomen where appropriate, and examination of all four limbs.

It often allays the child's distrust for the surgeon to take the mother's hand, gently examine this and return it to its owner, before attempting the same with the child. The experienced examiner will note any deformity and size discrepancy, diminished passive and active ranges of motion in any particular joint, often in association with poorly developed or absent skin creases, and joint instability. Some changes are subtle. A close examination of a child with second-web syndactyly in the feet may reveal subtle webbing of the third webs in the hands. This may also be present in the hands of the parent(s). Obvious thumb hypoplasia in one hand may be accompanied by subtle changes in the other.

All findings must be precisely recorded. Tracings, measurements of girth, and clinical photographs provide objective data for comparison at subsequent assessments.

Investigations

The mainstay of investigation is radiological. Plain X-rays should be requested for the specific anomaly with which the child presents but should be extended to a broader skeletal survey as indicated. Of course, the immature skeleton will not

reveal the complete picture. For instance, the Wassel classification of thumb duplication relies on relative skeletal maturity to distinguish a type 1 from a type 2. The bony connection present in the former may not be apparent at the base of the terminal phalanges in initial X-rays until ossification of a cartilaginous connection has occurred. In most instances, X-rays should be repeated immediately prior to surgical intervention as the skeletal appearance may have changed. It is helpful to have available in the clinic sample hand X-rays and charts that detail the timing of appearance of ossification centers and closure of growth plates (Fig. 25.25).^{115,116} The method of Greulich and Pyle¹¹⁷ and that of Tanner *et al.*¹¹⁸ are the most commonly used for measurement of skeletal maturation. In the former, the patient's radiograph is matched with an atlas image of the appropriate age.¹¹⁷ One must be careful to differentiate actual age and maturity. The Tanner and Whitehouse method is more complex and is based on the rate of development of 19 individual bones.¹¹⁸ Both methods suffer from the problem of variation between races. Progress is delayed in European children in comparison with those from Africa and North America.¹¹⁹ Poor nutrition results in slower maturation. Maturation in girls is more rapid than in boys by 2 years.

Fluoroscopy, tomography, and arthrography may all have a limited place in the assessment of the pediatric hand, often more for injury than for congenital anomaly. Computed tomography and magnetic resonance imaging have replaced many of these modalities but do require sedation or general anesthesia for the child. Ultrasonography has many characteristics that make it an ideal imaging modality in that there is no ionizing radiation, and it is painless and inexpensive. However, it is operator-dependent and differentiation between

tissues can be problematic. It is helpful in assessing cartilaginous contours prior to ossification.

Vascular studies, such as angiography, magnetic resonance angiography (MRA), or Doppler flow studies, may be considered prior to procedures involving vascularized tissue transfer, including toe transfers, particularly to parts with anomalous anatomical development. In particular, angiography and MRA, although uncommonly performed, may be indicated in some specific vascular reconstructions and for assessment of vascular tumors.

It is beyond the scope of this chapter to detail a complete investigation of all systems of the child with congenital limb anomalies. The incidence of associated anomalies is high. For instance, thrombocytopenic absent radius, Fanconi anemia, Holt–Oram syndrome and the VACTERLS association may accompany a longitudinal radial deficiency. A cardiac echogram, renal ultrasound, and blood examinations are routine.

Diagnosis

Following the assessment and investigations, a classifiable diagnosis is usually evident. The surgeon, with assistance from medical colleagues, will have determined whether the anomaly is isolated or syndromic; whether a genetic abnormality is present through either a spontaneous mutation or an inheritance pattern; and whether there has been an abnormal formation of tissue, a breakdown of normal tissue, or a lack of organization of cells into normal tissue.

Principles of surgical management

Indications

When considering surgery, the following question must always be asked: “Is reconstructive surgery likely to improve function and/or appearance with minimum risk?” That a part

is incomplete or inadequate is not in itself an indication for surgical reconstruction.

Function

A stable shoulder, arm, elbow, and forearm enable appropriate positioning of the hand in space for function. The instability, deformity, and shortening of radial longitudinal deficiencies, for instance, severely compromise hand function. Hand function itself depends on the ability to use a mobile thumb ray against other parts of the hand, ulnar digits for grasp and radial digits for precision pinch. Adequate digit length, stability, and motion are necessary components of optimal hand use. Surgical decisions may be best guided by a simple assessment, asking whether the size and number of digits are appropriate, whether deformity requires correction, whether stability is a problem, and whether an improvement in mobility would benefit.

Some decisions regarding surgery are relatively easy. Most parents and children will request that an extra digit be removed, particularly if it gets in the way (Fig. 25.26). Occasionally social and/or religious mores will dictate otherwise. Removal of a type 3 hypoplastic thumb, with subsequent pollicization of the index finger, may prove to be less palatable for parents, as they fear a decision that results in four rather than five digits. As a principle, when confronted with the option of reconstruction or removal of a part, it is perhaps wiser to advise reconstruction if the part is incorporated into the child’s activities, even if in an inefficient manner. The child and surgeon may benefit from the opinions of others who are experienced in this field of surgery. Advice from a knowledgeable colleague is particularly reassuring.

It is often not possible to restore normal function, even for what would appear to be a straightforward reconstruction of a Wassel type 1 thumb duplication, in which some joint instability and some compromise in interphalangeal joint motion may remain postoperatively. For complex duplications, full function and normal size are difficult to achieve,



Fig. 25.26 The obvious deformity of thumb triplication.

and pollicization never creates a normal thumb. Trigger thumb release should result in normal use and appearance. Clinodactyly of the little finger may represent no functional deficit preoperatively. Surgical interference should be carefully considered. Surgery for camptodactyly may improve extension at the expense of full flexion.

Appearance

The stigmata associated with an abnormal appearance are obvious. The hands are expressive and communicative. Deformity of a part is often more obvious than its absence and its correction may clearly result in an improved appearance for all eyes (Fig. 25.27). However, for many severe deformities it is simply not possible to create a normal-looking hand. Surgery to improve appearance in these cases must be undertaken realistically. Whether the appearance is improved, remains the same, or is poorer following surgery is simply in the eye of the beholder. Toe transfer for symbrachydactyly is one procedure that excites argument, with some adamant that appearance is improved and some adamant that it is not and that appearance should not play a role in decision-making. Probably the argument is irrelevant. The hand remains different regardless of the surgical reconstruction and the surgeon should not impose his or her views regarding appearance. Postoperative questionnaires in which patients and parents state their belief in an improved appearance are often flawed,

as many psychological factors are involved, including that of guilt in having given birth to a “less than normal” child and the responsibility of having made a decision to subject that child to surgical intervention.

It is the responsibility of the surgeon to provide advice based on training, experience, and a knowledge of the literature. However, should that advice be rejected, the doctor-patient/parent relationship must not become adversarial. Repeated assessments over a period of time will usually lead to an agreeable solution.

Timing

The question of timing is vexatious. Surgical results may be compromised by the technical difficulties of procedures on small structures in early life. This must be balanced against the principle of providing the child with a final result as early as possible, such that learned patterns of use do not compromise optimal function following appropriate surgical reconstructions. It is a reasonable approach to allow the child to adapt to the new hand as early as possible. However, cortical plasticity allows significant adaptation at older ages and, if the surgeon is doubtful that the surgery is indicated or the parents demand delay, it is preferable to wait. If functional improvement is unlikely and if the indication for surgery is one of a questionable improvement in appearance, perhaps the child should make this decision for him- or herself at an older age.

Parents may wish to defer surgery in the hope that there is something new on the horizon that will, if not cure, at least improve the outcome. It is the surgeon's responsibility to encourage hope but to discourage unrealistic expectations. Having failed to make a decision at the optimal time, these decisions rarely become easier with further passage of time. Web pages are full of information, some beneficial, some not. Some is simply advertising.

Table 25.4 details common practice as it relates to timing of specific surgical procedures, although it is recognized that more urgent treatment of life-threatening conditions will delay hand surgery.¹²⁰ It will be seen that many anomalies are treated within the first 2 years of life. In principle, the development of progressive deformity is an indication to operate earlier. An example is a syndactyly of the fourth web with terminal phalanx fusion (Fig. 25.28). Release of the first web, such as in an Apert hand, should be early. It is beneficial to complete most surgical procedures prior to school age, particularly in those instances in which appearance is significantly improved, such that teasing and ridicule by other schoolchildren are minimized. However, some procedures, such as minor revision surgery for the Apert hand or limb lengthening for the short forearm of a radial longitudinal deficiency, may be indicated at an older age (Fig. 25.29).

Finally, expectations of all involved must be realistic. Despite the rewards for surgeon, child, and family following surgery for congenital limb anomalies, an apparently successful and pleasing surgical result may be compromised by recurrent deformity, inadequate growth, uncontrolled growth, or the development of instability or immobility. At the time of operation the surgeon needs to be aware of the presence of factors that may, with time, subsequently alter the early result. In principle, these require correction at the initial surgery.



Fig. 25.27 (A,B) Pleasing appearance and function following pollicization.

Table 25.4 Common practice relating to timing of specific surgical procedures

Condition	Procedure	Timing
Syndactyly		
Simple	Release	12 months
Unequal digits with bony tether	Release	6 months
Including thumb	Release	6 months
Apert's acrosyndactyly	Sequential simultaneous bilateral releases	Begin at 6 months
Constriction ring syndrome		
Digit at risk	Release	Immediate
Acrosyndactyly	Release	6 months
Floating digit(s)	Excision	3 months
Thumb duplication	Reconstruction	12 months
Postaxial or central polydactyly	Reconstruction	12 months
Absent or inadequate thumb	Pollicization	12–18 months
Thumb hypoplasia	Reconstruction	12–18 months
Central longitudinal deficiency	Reconstruction	12–18 months
Symbrachydactyly	Toe phalangeal transfer Vascularized toe transfer	12–24 months 2–3 years
Radial longitudinal deficiency	Distraction Stabilization	3–6 months 6–12 months
Clinodactyly	Physeolysis Osteotomy	4–6 years Late
Camptodactyly		
Fixed with joint changes	Joint and soft-tissue release	12–18 months
Soft tissue	Release and transfers	After 2 years
Trigger thumb	Release	After 12 months

(Reproduced from Tonkin MA. An introduction to congenital hand anomalies. *Handchirurgie*. 2004;36:75–84.)

Congenital trigger thumb

Although congenital trigger thumb does not fit well into any classification scheme for congenital hand anomalies, it is one of the most common pediatric hand problems in practice.

Etiology

Pediatric trigger thumb is a stenosing tenovaginitis of the flexor pollicis longus tendon within its fibro-osseous tunnel, with the obstruction to tendon glide occurring at the A1 pulley. Controversy continues as to whether this is a true congenital condition or whether it is an acquired condition. The distinction between the two would appear to rely on whether or not the condition is present at birth. Although many authors have described presence at birth, the majority of these studies depend upon a retrospective history from the parents. The presence of trigger thumb in twins, the frequent bilateral nature of trigger thumb, and the association of trigger thumb with trisomy 13 are factors that have been used to support the theory of a congenital cause.^{121–125} However, several investigators have performed assessments within the early postnatal period, finding an absence of trigger thumbs in a combined number of 9000 neonates.^{126–128} The study of Kikuchi and Ogino examined 1116 babies within 14 days of birth.¹²⁹ None presented with trigger thumbs. Of 601 children

assessed by a questionnaire at 12 months of age, only two had developed trigger thumbs within that period, an incidence of 3.3 per 1000 live births. Three other children subsequently developed trigger thumbs, one bilateral, after the age of 12 months. Although response to the 12-month questionnaire was only obtained from 53% of patients and the true prevalence of trigger thumb after 12 months in this cohort of patients cannot be established, this study does tend to suggest that trigger thumb deformity is an acquired condition and is not present at birth. However, if the incidence of one patient per 2000 live births, as described by Ger *et al.*, is accurate, the number of children required to establish an absence of trigger thumb at birth would need to be far greater than those examined in the study.¹³⁰

Trauma has been incriminated as a possible cause of acquired trigger thumb. However, the absence of this history is more usual than not. Furthermore, the definition of what is a traumatic incident and what is not in a 2-year-old is unclear.

Notta described a node affecting the flexor tendons of digits that impeded their movement.¹³¹ Notta's node is palpable proximal to the A1 pulley in children with a locked flexion deformity. If the deformity is correctable, either actively or by the examiner's passive extension of the digit, the node can be felt to click as it passes beneath the A1 pulley. Some consider the node to be primary, preventing passage of the tendon past the edge of the obstructing A1 pulley. Most believe that this is a secondary phenomenon consequent upon



Fig. 25.28 Deformity of ring finger secondary to a four–five syndactyly.

the bunching of the tendon as its passage is impeded. It seems to disappear following surgical release, which supports the latter theory.

Two other observations are interesting. The first is that there is a percentage of “trigger thumbs” that present with the digit locked in extension. In this instance, the failure to glide through the A1 pulley is from distal to proximal when Notta’s node presumably abuts against the distal end of the A1 pulley. The literature does not provide us with an incidence of triggering in extension; indeed some may have interpreted this as a spontaneous resolution of triggering in a digit previously locked in flexion.

The second observation is that many children with a trigger thumb have hyperextensibility of the metacarpophalangeal joint. Ligamentous laxity is greater in children. No study has made a comparison of the incidence and degree of metacarpophalangeal joint hyperextension in children with and without trigger thumbs. However, it is logical to propose that the diameter of the A1 pulley, which is attached to the palmar plate of the metacarpophalangeal joint, decreases during hyperextension of the metacarpophalangeal joint, potentially restricting gliding of the tendon.

The current evidence suggests that the appearance of trigger thumb is more likely to be after birth. There is no real evidence of a primary pathological process other than a mismatch in size between the flexor tendon and the pulley.

Management

The rate of spontaneous resolution following observation and the rate of resolution following a combination of observation, manipulation and splinting, vary. Ger *et al.* found no cases of

resolution in 53 thumbs diagnosed before the age of 6 months, following 40 months of nonoperative therapy.¹³⁰ Steenwerckx *et al.* reported similar findings in 57 thumbs after 6 months.¹³² Other reports document high rates of spontaneous resolution,^{132–138} up to 96% for those thumbs that trigger during active extension, with a lesser resolution rate for those with a fixed flexion posture.¹³³ Dinham and Meggitt observed a spontaneous recovery rate of 30% in those children presenting with trigger thumb prior to the age of 6 months and a rate of 12% for those presenting between 6 and 30 months.¹²⁴ They advised treatment guidelines accordingly, advising that trigger deformities present in the early postnatal period should be observed for 12 months; those presenting between the ages of 6 and 30 months should be observed for 6 months; and that operative treatment should be performed before the age of 4 years to prevent the creation of residual flexion deformities. Although there has been an occasional report of interphalangeal (IP) joint radial deviation and a rotational deformity of the IP joint in older children,¹³⁹ there are no reported instances of persistent deformity if the condition is corrected surgically by the age of 3 years, or even later, according to some authors.¹⁴⁰



Fig. 25.29 (A,B) Correction of deformity and length for radial longitudinal deficiency at age 8.

Recently Baek *et al.* found a 63% rate of spontaneous resolution in 71 trigger thumbs.¹⁴¹ No treatment was instituted in these children who were assessed 6-monthly for a minimum period of 2 years. They found that the flexion deformity can be expected to improve even in those patients who did not have complete resolution. The general trend in the literature pertaining to children of Asian descent is to recommend a prolonged period of observation with or without splinting and passive exercises.

From the above it can be seen that the necessity for and timing of surgery for pediatric trigger thumbs are open to debate. Most would advise surgery for persistent painful episodes of triggering. Intermittent, non-painful triggering may be safely observed for a prolonged period of time, with or without the addition of night splinting in extension, without fear of the complication of joint deformity. It is questionable as to whether or not treatment with night splints for an extended period of time (up to 5 years or longer) is a greater imposition on child and parents than a surgical procedure. It is the author's (MT) practice to offer the parents surgical release if there is a persistent flexion or extension contracture for longer than 3 months and/or if there is accurate documentation by the parents of an uncorrectable flexion contracture for 12 months. However, this advice is offered along with the information that spontaneous resolution may well occur, even in these circumstances.

Surgical procedure (Video 25.1 ►)

The surgical procedure is performed as day-only surgery under general anesthesia and with an arm tourniquet. The

incision is transverse at the base of the thumb (metacarpophalangeal joint level). This incision is not easily extensible and therefore its position is important if one is to obtain an optimal view of the A1 pulley. If Notta's node is easily palpable, an incision centered on this node provides very adequate access. Often, this leads the surgeon to an incision halfway between the two basal thumb creases that are present in most hands. The neurovascular bundles of the thumb lie more anteriorly than those of the digits. The A1 pulley should be visualized and palpated with the tip of forceps to identify its proximal and distal edges. The surgeon or assistant should not attempt to passively correct the flexion deformity manually prior to incision of the A1 pulley. Full and easy correction following pulley release provides evidence of a complete release. The incision should be made in the midline of the pulley or erring to its radial side. This avoids continuing the incision through the fibers of the oblique pulley, whose origin on the ulnar side abuts the distal end of the A1 pulley. Occasionally, there are further transverse fibers just distal to, but separate from, the A1 pulley, which deserve release.

With careful attention to detail, complications should be minimal to nil. Absorbable 6/0 Vicryl Rapide sutures avoid the necessity for suture removal. Bathing and massage can begin at about 7–10 days postoperatively. Although Michifuri *et al.*¹⁴² reported a complication rate of 15%, including digital nerve injury, this is not the author's (MT) experience. There may be some inflammatory response during wound healing but this settles once the sutures have dissolved or are rubbed out with massage.



Access the complete reference list online at <http://www.expertconsult.com>

1. Swanson AB. A classification for congenital limb malformations. *J Hand Surg.* 1976;1:8–22. *This is a widely cited classification scheme for congenital anomalies of the limb. The rationale for its design and use is presented.*
3. Ezaki M, Baek GH, Horii E, Hovius S. IFSSH Scientific Committee on Congenital Conditions. *J Hand Surg Eur Vol.* 2014;39:676–678.
10. Burke AC, Nelson CE, Morgan BA, et al. Hox genes and the evolution of vertebrate axial morphology. *Development.* 1995;121:333–346. *Hox genes are known to play a role in anterior–posterior segmental identity. This study describes in situ hybridization and immunolocalization data in chick and mouse embryos demonstrating correlation between Hox expression and morphological boundaries.*
19. Martin GR. The roles of FGFs in the early development of vertebrate limbs. *Genes Dev.* 1998;12:1571–1586.
25. Towers M, Mahood R, Yin Y, et al. Integration of growth and specification in chick wing digit-patterning. *Nature.* 2008;452:882–886. *This manuscript discusses a series of experiments investigating the role of Sonic hedgehog expression gradients in influencing digit development in a chick wing model. The molecular mechanisms explored provide perspective in understanding human congenital limb anomalies.*
29. Laufer E, Nelson CE, Johnson RL, et al. Sonic hedgehog and Fgf-4 act through a signaling cascade and feedback loop to integrate growth and patterning of the developing limb bud. *Cell.* 1994;79:993–1003. *Sonic hedgehog and Fgf-4 were experimentally regulated to clarify the role these molecules play in early limb development. A positive-feedback loop between the posterior mesoderm and the apical ectodermal ridge is described to mediate their expression.*
69. Kardon G. Muscle and tendon morphogenesis in the avian hind limb. *Development.* 1998;125:4019–4032. *A temporal series of chick embryos was stained and examined to establish morphogenetic developmental patterns. Experiments highlighting the role of interaction between different tissue types (e.g., muscle and bone) in development are presented.*
84. Jones KL. Morphogenesis and dysmorphogenesis. In: Jones KL, ed. *Smith's Recognizable Patterns of Human Malformations.* 6th ed. Philadelphia, PA: Elsevier Saunders; 2006:783–795.
94. Oberg KC, Feestra JM, Manske PR, et al. Developmental biology and classification of congenital anomalies of the hand and upper extremity. *J Hand Surg Am.* 2010;35:2066–2076.
105. Tonkin MA, Tolerton SK, Quick TJ, et al. Classification of congenital anomalies of the hand and upper limb: development and assessment of a new system. *J Hand Surg Am.* 2013;38:1845–1853.
106. Ekblom AG, Laurell T, Arner M. Epidemiology of congenital upper limb anomalies in Stockholm, Sweden, 1997 to 2007: application of the Oberg, Manske, and Tonkin classification. *J Hand Surg Am.* 2014;39:237–248.
107. Goldfarb CA, Wall LB, Bohn DC, Moen P, Van Heest AE. Epidemiology of congenital upper limb anomalies in a Midwest United States population: an assessment using the Oberg, Manske, and Tonkin classification. *J Hand Surg Am.* 2015;40:127–132.
111. Erhardt RP, Lindley SG. Functional development of the hand. In: Gupta A, Kay SPJ, Scheker LR, eds. *The Growing Hand.* London: Harcourt; 2000:71–81.

References

- Swanson AB. A classification for congenital limb malformations. *J Hand Surg.* 1976;1:8–22. This is a widely cited classification scheme for congenital anomalies of the limb. The rationale for its design and use is presented.
- Knight SL, Kay SPJ. Classification of congenital anomalies. In: Gupta A, Kay SPJ, Scheker LR, eds. *The Growing Hand*. London: Harcourt; 2000:125–135.
- Ezaki M, Baek GH, Horii E, Hovius S. IFSSH Scientific Committee on Congenital Conditions. *J Hand Surg Eur Vol.* 2014;39:676–678.
- Tickle C. Embryology. In: Gupta A, Kay SPJ, Scheker LR, eds. *The Growing Hand: Diagnosis and Management of the Upper Extremity in Children*. London: CV Mosby; 2000:25–32.
- Fallon JF, Kelley RO. Ultrastructural analysis of the apical ectodermal ridge during vertebrate limb morphogenesis. II. Gap junctions as distinctive ridge structures common to birds and mammals. *J Embryol Exp Morphol.* 1977;41:223–232.
- Summerbell D, Lewis JH. Time, place and positional value in the chick limb-bud. *J Embryol Exp Morphol.* 1975;33:621–643.
- MacCabe JA, Errick J, Saunders JW Jr. Ectodermal control of the dorsoventral axis in the leg bud of the chick embryo. *Dev Biol.* 1974;39:69–82.
- Hinchliffe JR, Gumpel-Pinot M. Control of maintenance and anteroposterior skeletal differentiation of the anterior mesenchyme of the chick wing bud by its posterior margin (the ZPA). *J Embryol Exp Morphol.* 1981;62:63–82.
- Summerbell D. The control of growth and the development of pattern across the anteroposterior axis of the chick limb bud. *J Embryol Exp Morphol.* 1981;63:161–180.
- Burke AC, Nelson CE, Morgan BA, et al. Hox genes and the evolution of vertebrate axial morphology. *Development.* 1995;121:333–346. Hox genes are known to play a role in anterior–posterior segmental identity. This study describes in situ hybridization and immunolocalization data in chick and mouse embryos demonstrating correlation between Hox expression and morphological boundaries.
- Minguillon C, Nishimoto S, Wood S, et al. Hox genes regulate the onset of Tbx5 expression in the forelimb. *Development.* 2012;139:3180–3188.
- Agarwal P, Wylie JN, Galceran J, et al. Tbx5 is essential for forelimb bud initiation following patterning of the limb field in the mouse embryo. *Development.* 2003;130:623–633.
- Ng JK, Kawakami Y, Buscher D, et al. The limb identity gene Tbx5 promotes limb initiation by interacting with Wnt2b and Fgf10. *Development.* 2002;129:5161–5170.
- Restelli M, Lopardo T, Lo Iacono N, et al. DLX5, FGF8 and the Pin1 isomerase control ΔNp63α protein stability during limb development: a regulatory loop at the basis of the SHFM and EEC congenital malformations. *Hum Mol Genet.* 2014;23:3830–3842.
- Laufer E, Dahn R, Orozco OE, et al. Expression of radical fringe in limb-bud ectoderm regulates apical ectodermal ridge formation. *Nature.* 1997;386:366–373.
- Zakany J, Zacchetti G, Duboule D. Interactions between HOXD and Gli3 genes control the limb apical ectodermal ridge via Fgf10. *Dev Biol.* 2007;306:883–893.
- Rodriguez-Esteban C, Schwabe JWR, De La Pena J, et al. Radical fringe positions the apical ectodermal ridge at the dorsoventral boundary of the vertebrate limb. *Nature.* 1997;386:360–365.
- Lewandoski M, Sun X, Martin GR. Fgf8 signalling from the AER is essential for normal limb development. *Nat Genet.* 2000;26:460–463.
- Martin GR. The roles of FGFs in the early development of vertebrate limbs. *Genes Dev.* 1998;12:1571–1586.
- Barrow JR, Thomas KR, Boussadia-Zahui O, et al. Ectodermal Wnt3/beta-catenin signaling is required for the establishment and maintenance of the apical ectodermal ridge. *Genes Dev.* 2003;17:394–409.
- Kawakami Y, Capdevila J, Buscher D, et al. WNT signals control FGF-dependent limb initiation and AER induction in the chick embryo. *Cell.* 2001;104:891–900.
- Niemann S, Zhao C, Pascu F, et al. Homozygous WNT3 mutation causes tetra-amelia in a large consanguineous family. *Am J Hum Genet.* 2004;74:558–563.
- Sekine K, Ohuchi H, Fujiwara M, et al. Fgf10 is essential for limb and lung formation. *Nat Genet.* 1999;21:138–141.
- Riddle RD, Johnson RL, Laufer E, et al. Sonic hedgehog mediates the polarizing activity of the ZPA. *Cell.* 1993;75:1401–1416.
- Towers M, Mahood R, Yin Y, et al. Integration of growth and specification in chick wing digit-patterning. *Nature.* 2008;452:882–886. This manuscript discusses a series of experiments investigating the role of Sonic hedgehog expression gradients in influencing digit development in a chick wing model. The molecular mechanisms explored provide perspective in understanding human congenital limb anomalies.
- Zhu J, Nakamura E, Nguyen MT, et al. Uncoupling Sonic hedgehog control of pattern and expansion of the developing limb bud. *Dev Cell.* 2008;14:624–632.
- Ros MA, Dahn RD, Fernandez-Teran M, et al. The chick oligozeugodactyly (ozd) mutant lacks sonic hedgehog function in the limb. *Development.* 2003;130:527–537.
- Niswander L, Jeffrey S, Martin GR, et al. A positive feedback loop coordinates growth and patterning in the vertebrate limb. *Nature.* 1994;371:609–612.
- Laufer E, Nelson CE, Johnson RL, et al. Sonic hedgehog and Fgf-4 act through a signaling cascade and feedback loop to integrate growth and patterning of the developing limb bud. *Cell.* 1994;79:993–1003. Sonic hedgehog and Fgf-4 were experimentally regulated to clarify the role these molecules play in early limb development. A positive-feedback loop between the posterior mesoderm and the apical ectodermal ridge is described to mediate their expression.
- Sun X, Lewandoski M, Meyers EN, et al. Conditional inactivation of Fgf4 reveals complexity of signalling during limb bud development. *Nat Genet.* 2000;25:83–86.
- Riddle RD, Ensini M, Nelson C, et al. Induction of the LIM homeobox gene Lmx1 by WNT7a establishes dorsoventral pattern in the vertebrate limb. *Cell.* 1995;83:631–640.
- Vogel A, Rodriguez C, Warnken W, et al. Dorsal cell fate specified by chick Lmx1 during vertebrate limb development. *Nature.* 1995;378:716–720.
- Woods CG, Stricker S, Seemann P, et al. Mutations in WNT7A cause a range of limb malformations, including Fuhrmann syndrome and Al-Awadi/Raas-Rothschild/Schinzler phocomelia syndrome. *Am J Hum Genet.* 2006;79:402–408.
- Yang Y, Niswander L. Interaction between the signaling molecules WNT7a and SHH during vertebrate limb development: dorsal signals regulate anteroposterior patterning. *Cell.* 1995;80:939–947.
- Raspopovic J, Marcon L, Russo L, et al. Modeling digits. Digit patterning is controlled by a Bmp–Sox9–Wnt Turing network modulated by morphogen gradients. *Science.* 2014;345:566–570.
- Sheth R, Marcon L, Bastida MF, et al. Hox genes regulate digit patterning by controlling the wavelength of a Turing-type mechanism. *Science.* 2012;338:1476–1480.
- Glugaszevska B, Silahtaroglu A, Menzel C, et al. Breakpoints around the HOXD cluster result in various limb malformations. *J Med Genet.* 2006;43:111–118.
- Fromental-Ramain C, Warot X, Lakkaraju S, et al. Specific and redundant functions of the paralogous Hoxa-9 and Hoxd-9 genes in forelimb and axial skeleton patterning. *Development.* 1996;122:461–472.
- Knezevic V, De SR, Schughart K, et al. Hoxd-12 differentially affects preaxial and postaxial chondrogenic branches in the limb and regulates Sonic hedgehog in a positive feedback loop. *Development.* 1997;124:4523–4536.
- Zakany J, Kmita M, Duboule D. A dual role for Hox genes in limb anterior–posterior asymmetry. *Science.* 2004;304:1669–1672.
- Dahn RD, Fallon JF. Interdigital regulation of digit identity and homeotic transformation by modulated BMP signaling. *Science.* 2000;289:438–441.
- Weatherbee SD, Behringer RR, Rasweiler JJ, et al. Interdigital webbing retention in bat wings illustrates genetic changes underlying amniote limb diversification. *Proc Natl Acad Sci USA.* 2006;103:15103–15107.

43. Yoon BS, Pogue R, Ovchinnikov DA, et al. BMPs regulate multiple aspects of growth-plate chondrogenesis through opposing actions on FGF pathways. *Development*. 2006;133:4667–4678.
44. Suzuki T, Hasso SM, Fallon JF. Unique SMAD1/5/8 activity at the phalanx-forming region determines digit identity. *Proc Natl Acad Sci USA*. 2008;105:4185–4190.
45. Casanova JC, Sanz-Ezquerro JJ. Digit morphogenesis: is the tip different? *Dev Growth Differ*. 2007;49:479–491.
46. Gruneberg H, Lee AJ. The anatomy and development of brachypodism in the mouse. *J Embryol Exp Morphol*. 1973;30:119–141.
47. Casanova JC, Badia-Careaga C, Uribe V, et al. Bambi and Sp8 expression mark digit tips and their absence shows that chick wing digits 2 and 3 are truncated. *PLoS ONE*. 2012;7:e52781.
48. Drake CJ, Fleming PA. Vasculogenesis in the day 6.5 to 9.5 mouse embryo. *Blood*. 2000;95:1671–1679.
49. Vargesson N. Vascularization of the developing chick limb bud: role of the TGFbeta signalling pathway. *J Anat*. 2003;202:93–103.
50. Caplan AI. The vasculature and limb development. *Cell Differ*. 1985;16:1–11.
51. He L, Papoutsi M, Huang R, et al. Three different fates of cells migrating from somites into the limb bud. *Anat Embryol (Berl)*. 2003;207:29–34.
52. Tamura K, Amano T, Satoh T, et al. Expression of *rigf*, a member of avian VEGF family, correlates with vascular patterning in the developing chick limb bud. *Mech Dev*. 2003;120:199–209.
53. Swift MR, Weinstein BM. Arterial-venous specification during development. *Circ Res*. 2009;104:576–588.
54. Trelles RD, Leon JR, Kawakami Y, et al. Expression of the chick vascular endothelial growth factor D gene during limb development. *Mech Dev*. 2002;116:239–242.
55. Mrazkova O. Ontogenesis of arterial trunks in the human forearm. *Folia Morphol (Praha)*. 1973;21:193.
56. Rodriguez-Niedenfuhr M, Papoutsi M, Christ B, et al. Prox1 is a marker of ectodermal placodes, endodermal compartments, lymphatic endothelium and lymphangioblasts. *Anat Embryol (Berl)*. 2001;204:399–406.
57. Karunamuni G, Yang K, Doughman YQ, et al. Expression of lymphatic markers during avian and mouse cardiogenesis. *Anat Rec (Hoboken)*. 2010;293:259–270.
58. Kawakami Y, Rodriguez-Leon J, Belmonte JC. The role of TGFbetas and Sox9 during limb chondrogenesis. *Curr Opin Cell Biol*. 2006;18:723–729.
59. Akiyama H, Chaboissier MC, Martin JF, et al. The transcription factor Sox9 has essential roles in successive steps of the chondrocyte differentiation pathway and is required for expression of Sox5 and Sox6. *Genes Dev*. 2002;2813–2828.
60. Karsenty G. Transcriptional control of skeletogenesis. *Annu Rev Genomics Hum Genet*. 2008;9:183–196.
61. Yokouchi Y, Sasaki H, Kuroiwa A. Homeobox gene expression correlated with the bifurcation process of limb cartilage development. *Nature*. 1991;353:443–445.
62. Hartmann C, Tabin CJ. Wnt-14 plays a pivotal role in inducing synovial joint formation in the developing appendicular skeleton. *Cell*. 2001;104:341–351.
63. Storm EE, Kingsley DM. GDF5 coordinates bone and joint formation during digit development. *Dev Biol*. 1999;209:11–27.
64. Pacifici M, Koyama E, Iwamoto M. Mechanisms of synovial joint and articular cartilage formation: recent advances, but many lingering mysteries. *Birth Defects Res C Embryo Today*. 2005;75:237–248.
65. Craig FM, Bayliss MT, Bentley G, et al. A role for hyaluronan in joint development. *J Anat*. 1990;171:17–23.
66. Dalgleish AE. *Development of the Limbs of the Mouse*. Stanford, CA: Stanford University; 1964:1–269.
67. Mitrovic D. Development of the diarthrodial joints in the rat embryo. *Am J Anat*. 1978;151:475–485.
68. Nakashima K, Zhou X, Kunkel G, et al. The novel zinc finger-containing transcription factor Osterix is required for osteoblast differentiation and bone formation. *Cell*. 2002;108:17–29.
69. Kardon G. Muscle and tendon morphogenesis in the avian hind limb. *Development*. 1998;125:4019–4032. *A temporal series of chick embryos was stained and examined to establish morphogenetic developmental patterns. Experiments highlighting the role of interaction between different tissue types (e.g., muscle and bone) in development are presented.*
70. Sharma K, Izpisua Belmonte JC. Development of the limb neuromuscular system. *Curr Opin Cell Biol*. 2001;13:204–210.
71. Messina G, Cossu G. The origin of embryonic and fetal myoblasts: a role of Pax3 and Pax7. *Genes Dev*. 2009;23:902–905.
72. Otto A, Collins-Hooper H, Patel K. The origin, molecular regulation and therapeutic potential of myogenic stem cell populations. *J Anat*. 2009;215:477–497.
73. Brohmann H, Jagla K, Birchmeier C. The role of Lbx1 in migration of muscle precursor cells. *Development*. 2000;127:437–445.
74. Dreyer SD, Naruse T, Morello R, et al. Lmx1b expression during joint and tendon formation: localization and evaluation of potential downstream targets. *Gene Expr Patterns*. 2004;4:397–405.
75. Francis-West PH, Antoni L, Anakwe K. Regulation of myogenic differentiation in the developing limb bud. *J Anat*. 2003;202:69–81.
76. Cihak R. Ontogenesis of the skeleton and intrinsic muscles of the human hand and foot. *Ergebn Anat Entwicklungsgesch*. 1972;46:1.
77. Cihak R. Differentiation and rejoining of muscular layers in the embryonic human hand. *Birth Defects*. 1977;13:97.
78. Hughes SM, Salinas PC. Control of muscle fibre and motoneuron diversification. *Curr Opin Neurobiol*. 1999;9:54–64.
79. Ontell M, Kozeka K. The organogenesis of murine striated muscle: a cytoarchitectural study. *Am J Anat*. 1984;171:133–148.
80. Dasen JS. Transcriptional networks in the early development of sensory-motor circuits. *Curr Top Dev Biol*. 2009;87:119–148.
81. Litingtung Y, Chiang C. Control of Shh activity and signaling in the neural tube. *Dev Dyn*. 2000;219:143–154.
82. Oh S, Huang X, Liu J, et al. Shh and Gli3 activities are required for timely generation of motor neuron progenitors. *Dev Biol*. 2009;331:261–269.
83. Dasen JS, De CA, Wang B, et al. Hox repertoires for motor neuron diversity and connectivity gated by a single accessory factor, FoxP1. *Cell*. 2008;134:304–316.
84. Jones KL. Morphogenesis and dysmorphogenesis. In: Jones KL, ed. *Smith's Recognizable Patterns of Human Malformations*. 6th ed. Philadelphia, PA: Elsevier Saunders; 2006:783–795.
85. St. Hilaire I. *Histoire Générale et Particulière des Anomalies de l'Organisation chez l'Homme et les Animaux*. Paris: JB Baillière; 1832:670–702.
86. Frantz C, O'Rahilly R. Congenital skeletal limb deficiencies. *J Bone Joint Surg Am*. 1961;43:1202–1224.
87. Kelikian H. *Congenital Deformities of the Hand and Forearm*. Philadelphia, PA: WB Saunders; 1974:51–88.
88. Swanson A, Barsky A, Entin M. Classification of limb malformations on the basis of embryological failures. *Surg Clin North Am*. 1968;48:1169–1179.
89. Swanson A, Swanson GD, Tada K. A classification for congenital limb malformation. *J Hand Surg Am*. 1983;8:693–702.
90. Upton J. The hand and upper limb: congenital anomalies. In: Mathes SJ, ed. *Plastic Surgery*. Vol. 8. 2nd ed. Philadelphia, PA: Saunders Elsevier; 2006:32–35.
91. Luijsterburg AJ, Sonneveld GJ, Vermeij-Keers C, et al. Recording congenital differences of the upper limb. *J Hand Surg*. 2003;28B:205–214.
92. Tonkin MA. Description of congenital hand anomalies: A personal view. *J Hand Surg*. 2006;31B(5):489–497.

93. Manske PR, Oberg KC. Classification and developmental biology of congenital anomalies of the hand and upper extremity. *J Bone Joint Surg Am.* 2009;91(suppl 4):3–18.
94. Oberg KC, Feestra JM, Manske PR, et al. Developmental biology and classification of congenital anomalies of the hand and upper extremity. *J Hand Surg Am.* 2010;35:2066–2076.
95. Miura T. Syndactyly and split hand. *Hand.* 1976;8:125–130.
96. Ogino T. Teratogenic relationship between polydactyly, syndactyly and cleft hand. *J Hand Surg.* 1990;15B:201–209.
97. Congenital Hand Committee of the JSSH. Modified IFSSH Classification. *J Jpn Soc Surg Hand.* 2000;17:353–365.
98. Muragaki Y, Mundlos A, Upton J, et al. Altered growth and branching patterns in synpolydactyly caused by mutations in HOXD13. *Science.* 1996;272:548–551.
99. Percin EF, Percin S, Egilmez H, et al. Mesoaxial complete syndactyly and synostosis with hypoplastic thumbs: an unusual combination or homozygous expression of syndactyly type I? *J Med Genet.* 1998;35:868–874.
100. Naruse T, Takahara M, Takagi M, et al. Busulfan-induced central polydactyly, syndactyly and cleft hand or foot: a common mechanism of disruption leads to divergent phenotypes. *Dev Growth Differ.* 2007;49:533–541.
101. de Graaf E, van Baren MJ, Heutink P. Clinical genetics of the upper limb. In: Hovius SER, Foucher G, Raimondi PL, eds. *The Pediatric Upper Limb.* London: Martin Dunitz; 2002:9–19.
102. Miura T, Nakamura R, Horii E. The position of symbrachydactyly in the classification of congenital hand anomalies. *J Hand Surg.* 1994;19B:350–354.
103. Buck-Gramko D. Cleft hands: classification and treatment. *Hand Clin.* 1985;1:467–473.
104. Tonkin MA, Oberg K. Congenital hand I: principles, embryology and classification. In: Neligan PC, ed. *Plastic Surgery.* 3rd ed. London: Elsevier Saunders; 2013:526–547.
105. Tonkin MA, Tolerton SK, Quick TJ, et al. Classification of congenital anomalies of the hand and upper limb: development and assessment of a new system. *J Hand Surg Am.* 2013;38:1845–1853.
106. Ekblom AG, Laurell T, Arner M. Epidemiology of congenital upper limb anomalies in Stockholm, Sweden, 1997 to 2007: application of the Oberg, Manske, and Tonkin classification. *J Hand Surg Am.* 2014;39:237–248.
107. Goldfarb CA, Wall LB, Bohn DC, Moen P, Van Heest AE. Epidemiology of congenital upper limb anomalies in a Midwest United States population: an assessment using the Oberg, Manske, and Tonkin classification. *J Hand Surg Am.* 2015;40:127–132.
108. Iyer VG. Development and maturation of the nervous system. In: Gupta A, Kay SPJ, Scheker LR, eds. *The growing hand: diagnosis and management of the upper extremity in children.* London: CV Mosby; 2000:47–51.
109. Erhardt R. *Developmental Hand Dysfunction: Theory, Assessment, and Treatment.* 2nd ed. San Antonio: Therapy Skill Builders; 1994.
110. Axelrod JA. The gradual unfolding: from infancy to adult. In: Gupta A, Kay SPJ, Scheker LR, eds. *The Growing Hand.* London: Harcourt; 2000:65–70.
111. Erhardt RP, Lindley SG. Functional development of the hand. In: Gupta A, Kay SPJ, Scheker LR, eds. *The Growing Hand.* London: Harcourt; 2000:71–81.
112. Crinella FM, Beck FW, Robinson JW. Unilateral dominance is not related to neuropsychological integrity. *Child Dev.* 1971;42:2033–2054.
113. Steffen H. Cerebral dominance: the development of handedness and speech. *Acta Paedopsychiatr.* 1975;41:223–235.
114. Van Camp SS, Bixby MB. Eye and hand dominance in kindergarten and first grade children. *Merrill Palmer Q.* 1977;23:129–139.
115. Upton J. Classification of upper limb congenital differences and general principles management. In: Mathes SJ, ed. *Plastic Surgery.* Vol. 8. 2nd ed. Philadelphia, PA: Elsevier; 2006:25–50.
116. Roberts A, Ashton B. Biology of postnatal limb growth. In: Gupta A, Kay SPJ, Scheker LR, eds. *The Growing Hand: Diagnosis and Management of the Upper Extremity in Children.* London: CV Mosby; 2000:53–56.
117. Greulich W, Pyle S. *Radiologic Atlas of Skeletal Development of the Hand and Wrist.* 2nd ed. Stanford, CA: Stanford University Press; 1959.
118. Tanner J, Whitehouse RH, Marshall WA, et al. *Assessment of Skeletal Maturity and Prediction of Adult Height.* London: Academic Press; 1975.
119. Hall C, Shaw DG. Normal radiologic variants and skeletal maturation. In: Gupta A, Kay SPJ, Scheker LR, eds. *The Growing Hand.* London: Harcourt; 2000:57–64.
120. Tonkin MA. An introduction to congenital hand anomalies. *Handchirurgie.* 2004;36:75–84.
121. Fahey JJ, Bollinger JA. Trigger-finger in adults and children. *J Bone Joint Surg Br.* 1954;36:1200–1218.
122. Neu BR, Murray JF. Congenital bilateral trigger digits in twins. *J Hand Surg.* 1983;8:350–352.
123. Vyas BK, Sarwahi V. Bilateral congenital trigger thumb: role of heredity. *Indian J Pediatr.* 1999;66:949–951.
124. Dinham JM, Meggitt BF. Trigger thumbs in children: a review of natural history and indications for treatment in 105 patients. *J Bone Joint Surg Br.* 1974;56:153–155.
125. Flatt AE. *The Care of Congenital Hand Anomalies.* St. Louis, MO: CV Mosby; 1977:50–51, 58–60.
126. Rodgers WB, Waters PM. Incidence of trigger digits in newborns. *J Hand Surg Am.* 1994;19:364–368.
127. Slakey JB, Hennrikus WL. Acquired thumb flexion contracture in children: congenital trigger thumb. *J Bone Joint Surg Br.* 1996;78:481–483.
128. Moon WN, Suh SW, Kim IC. Trigger digits in children. *J Hand Surg [Br].* 2001;26:11–12.
129. Kikuchi N, Ogino T. Incidence and development of trigger thumb in children. *J Hand Surg Am.* 2006;31:541–543.
130. Ger E, Kupcha P, Ger D. The management of trigger thumb in children. *J Hand Surg Am.* 1991;16:944–947.
131. Notta A. Recherches sur une affection particulière des gaines tendineuses de la main, caractérisée par le développement d'une nodosité sur le trajet des tendons fléchisseurs des doigts et par l'empêchement de leurs mouvements. *Arch Gen Med.* 1850;24:142–161.
132. Steenwerckx A, De Smet L, Fabry G. Congenital trigger digit. *J Hand Surg Am.* 1996;21:909–911.
133. Ishikura T, Murakami T, Kumagai S, et al. Conservative treatment of trigger thumbs in children (in Japanese). *J Japan Soc Surg Hand.* 1984;1:349–452.
134. Negoro H, Shioda M, Hatanaka I, et al. Conservative treatment of trigger thumbs [in Japanese]. *Seikeigeka.* 1981;32:1732–1734.
135. Tsushima S, Ohmizo M. Splinting of trigger thumb [in Japanese]. *Sagyoryoho (Occupational therapy).* 1989;8:610–616.
136. Nemoto K, Nemoto T, Terada N, et al. Splint therapy for trigger thumb and finger in children. *J Hand Surg [Br].* 1996;21:416–418.
137. Dunsmuir RA, Sherlock DA. The outcome of treatment of trigger thumb in children. *J Bone Joint Surg Br.* 2000;82:736–738.
138. Mulpruek P, Prichasuk S. Spontaneous recovery of trigger thumbs in children. *J Hand Surg [Br].* 1998;23:255–257.
139. Herdem M, Bayram H, Togrul E, et al. Clinical analysis of the trigger thumb of childhood. *Turk J Pediatr.* 2003;45:237–239.
140. Skov O, Bach A, Hammer A. Trigger thumbs in children: a follow-up study of 37 children below 15 years of age. *J Hand Surg [Br].* 1990;15:466–467.
141. Baek GH, Kim JH, Chung MS, et al. The natural history of pediatric trigger thumb. *J Bone Joint Surg Am.* 2008;90:980–985.

142. Michifuri Y, Murakami T, Kumagai S, et al. Natural history of the trigger fingers in children [in Japanese]. *Seikeigeka (Orthop Surg)*. 1978;29:1648–1650.
143. Dimitrov BI, Voet T, De SL, et al. Genomic rearrangements of the GREM1-FMN1 locus cause oligosyndactyly, radio-ulnar synostosis, hearing loss, renal defects syndrome and Cenani–Lenz-like non-syndromic oligosyndactyly. *J Med Genet*. 2010;47:569–574.
144. Zhou F, Leder P, Zuniga A, et al. Formin1 disruption confers oligodactylism and alters Bmp signaling. *Hum Mol Genet*. 2009;18:2472–2482.

26

Congenital hand II: Longitudinal, central, and transverse deficiency

Scott Oishi and Lesley Butler

SYNOPSIS

- Clinical evaluation of the entire patient is essential as multiple associated findings may exist.
- It is important to remember that untreated patients function very well, so any surgery, needs to be assessed on an individual case basis and should only be performed if there is a realistic goal of increasing function.
- If a syndactyly exists but the finger tips are separated and no significant tethering exists, reconstruction should be delayed until the child is in the 2–3 year-old age range as to minimize possible effects of anesthesia as well as to allow the fingers to be bigger and easier to perform surgery on.

Introduction

Upper limb development occurs very early during fetal development, with ingrowth into the ectoderm by the mesoderm signaling the initiation of limb bud development.^{1–3} This begins about 28 days after fertilization and is completed by about day 56. The development is regulated by a complex feedback mechanism that determines growth, orientation, and differentiation of the three axes: longitudinal, radio-ulnar, and ventral–dorsal. Critical areas include the apical ectodermal ridge (AER), zone of polarizing activity (ZPA), and the dorsal ectoderm, which are regulated by fibroblast growth factors (FGF), sonic hedgehog, and the Wingless-type (Wnt) pathway respectively³ (Fig. 26.1). It should be noted, however, that these pathways do not act solely independently and instead rely on feedback mechanisms from each other for growth and differentiation of the upper limb. Abnormalities occurring during this crucial time period of development can lead to abnormalities of longitudinal, central, and transverse deficiencies. In a series of eloquent experiments, Ogino and his group were able to induce ulnar and radial longitudinal deficiencies in rats by administering busulfan at different points in early development of the upper limb (weeks 4 and

5 of fetal development). Greater doses of busulfan led to both a higher incidence and severity of ulnar or radial longitudinal deficiency.^{4–5} Transverse deficiencies have not been reproduced in animal models; however, it is speculated that subclavian artery disruption at an early developmental stage may lead to the clinical findings associated with transverse deficiencies.⁶

Patients with longitudinal, central, and transverse deficiency can face significant societal issues as they grow and it is important for them to have support groups, child-life specialists, and child psychologists available, not only to them, but also to their parents. Counseling for the parents is also important at the first visit regarding potential etiologies of the underlying conditions as many of them have significant feelings of guilt and confusion. At Texas Scottish Rite Hospital for Children, we started a hand camp many years ago, which has been an integral part of treatment of these patients, as it allows them to interact and talk with other children with either the same or different congenital hand difference diagnosis.

Radial longitudinal deficiency

Basic science/disease process

Radial longitudinal deficiency (RLD) is the most common upper limb longitudinal deficiency, with an incidence that has been reported as between 1:5000–100 000 live births,^{7–9} being bilateral in 38% to 58%.⁹ It can range from involvement of the entire upper limb to thumb involvement alone. In 1976, the International Federation of the Societies for Surgery of the Hand (IFSSH) adopted the classification system of congenital hand differences proposed by Swanson.¹⁰ In this classification, RLD is considered in the IB group (failure of formation – longitudinal arrest). Since its publication, many conditions have been found to not fit into this system. An expanded classification system, OMT (Oberg–Manske–Tonkin), has recently been introduced to more accurately categorize congenital hand differences.¹¹ (see Table 25.2 for




Fig. 26.1 Limb bud coordinate axes and signaling centers.³ AER, Apical ectodermal ridge; Di, distal; Do, dorsal; Pr, proximal; Rad, radial; Uln, ulnar; Vo, volar; ZPA, zone of polarizing activity. (Redrawn after Oberg KC, Feenstra JM, Manske PR, et al. *Developmental biology and classification of congenital anomalies of the hand and upper extremity*. J Hand Surg Am. 2010; 35:2066–2076.)

2015 version). In this system, RLD with thumb hypoplasia and forearm involvement would be I.A.2.i, and thumb hypoplasia without forearm involvement would be I.B.2.i. Although many cases occur as a sporadic mutation, some are related to an inherited condition. For example, Holt–Oram syndrome is an autosomal-dominant condition that has been mapped to a mutation on chromosome 12 at the location of the *TBX-5* gene.¹² In affected individuals, this presents as RLD along with cardiac abnormalities. Although the most common cardiac abnormality present is a septal defect, conduction abnormalities can also be the lone cardiac finding. Obviously this can be an important consideration for the patient undergoing surgery, and must be conveyed to the anesthesiologist. TAR (thrombocytopenia absent radius) syndrome is inherited in an autosomal-recessive fashion and can present with profound thrombocytopenia as a newborn. However, this usually improves/resolves over the first year of life and overall prognosis is good. These patients usually have bilateral involvement with thumbs that are present, albeit hypoplastic. Another autosomal-recessive condition is Fanconi’s anemia and RLD. This anemia usually is not seen in routine blood counts done as a newborn, and is identified only by DEB (diepoxybutane) chromosome breaking testing. VACTERL (vertebral anomalies, anal atresia, cardiac abnormalities, tracheoesophageal fistula, esophageal atresia, renal

agenesis, and limb anomalies) represents an association and is not an inherited disorder. A minimum of three of these clinical findings need to be present before the VACTERL diagnosis is made. Thalidomide was a medication which previously was given to pregnant women to treat nausea and morning sickness, but was unfortunately found to have a high incidence of RLD and other skeletal deficiencies in the newborn when given between days 38 and 45 of fetal growth.¹³ In addition, maternal use of valproic acid, phenobarbital, and aminopterin, as well as fetal alcohol syndrome, have also been associated with RLD.^{14–16}

Diagnosis/patient presentation

Bayne and Klug (1987) initially classified radial deficiency into four types¹⁷; however, this was later expanded by James *et al.*¹⁸ to include types 0/N and also by Goldfarb *et al.* (2005) to include a more proximal variant (phocomelic), type V¹⁹ (Table 26.1). A type 0 radius is of normal length (<2 mm short), with the 0/N modifier reflecting whether the carpus is normal (N) or abnormal (0); a type I radius is at least 2 mm short (measured between distal physis of radius and ulna); a type II radius is termed a “miniature radius” with proximal and distal physes present; a type III radius only has remnant of radius with absent distal physis; and type IV is an absent

Table 26.1 Modified classification of radial longitudinal deficiency.

Type	Thumb	Carpus	Distal radius	Proximal radius
N	Hypoplastic or absent	Normal	Normal	Normal
0	Hypoplastic or absent	Absence, hypoplasia, or coalition	Normal	Normal, radioulnar synostosis, or congenital dislocation of the radial head
1	Hypoplastic or absent	Absence, hypoplasia, or coalition	>2 mm shorter than ulna	Normal, radioulnar synostosis, or congenital dislocation of the radial head
2	Hypoplastic or absent	Absence, hypoplasia, or coalition	Hypoplasia	Hypoplasia
3	Hypoplastic or absent	Absence, hypoplasia, or coalition	Physis absent	Variable hypoplasia
4	Hypoplastic or absent	Absence, hypoplasia, or coalition	Absent	Absent

(Adapted from James M, McCarroll R, Manske PR. The spectrum of radial longitudinal deficiency: a modified classification. J Hand Surg Am. 1999;24:1145–55.)

radius. The type V radius reflects a more proximal involvement of the upper limb.

The hypoplastic thumb was classified as by Blauth (1967) into types I–V.²⁰ An important distinction was made by Manske (1995) who introduced a type IIIA and type IIIB, which has implications on the treatment offered to the patient and family.²¹ Type I hypoplastic thumbs are a little smaller than normal thumbs but possess all the structures usually present in an unaffected thumb. As a result, they very rarely need any surgical treatment. In type II thumbs, the thenar musculature is poorly developed with associated adduction contracture of the first ray and variable amounts of metacarpal–phalangeal (MP) joint laxity. As hypoplasia progresses to type III, a loss of extrinsic musculotendinous units is noted. Type III has been further subdivided into an A or B depending on whether the carpometacarpal (CMC) joint is stable.²¹ This has important ramifications on the type of reconstruction that is performed. Type IV is the *pouce flottant*, or floating thumb, and type V is an absent thumb.²² (Fig. 26.2).

Patient selection

Because of the appearance of the upper limb, the hand surgeon may have early involvement in the care of the affected patient. It is imperative that a thorough history is taken, as well as a complete physical examination. This should include evaluation of the lower extremities, hips, back, head and neck area, as well as the upper extremities. In addition, because of the possible associated anomalies, it is important to make sure the patient has had a complete blood count (CBC), echocardiogram, and renal ultrasound. If a significant sacral dimple (+/– hairy patch) was noted on examination, a spinal ultrasound is warranted to rule-out tethered cord. Obtaining a DEB test at the time of initial evaluation is advocated by some, because infants with Fanconi's anemia have a normal CBC and may not display signs of aplastic anemia until 3–4 years of age or older.²² In the past, low incidence and high cost of DEB testing argued against routinely obtaining it; however, the advent of more successful treatment of these patients by pediatric hematologists at earlier ages has made DEB testing more routine in our practice.

Clinical tips

RLD – evaluation for surgery

- Careful evaluation of the entire patient.
- Scoliosis screening.
- Complete blood count, renal ultrasound, echocardiogram.
- +/- DEB test.

Upper limb evaluation usually reveals some radial deviation at the level of the wrist with some degree of thumb hypoplasia. It is important to note that the severity of the radial hypoplasia does not necessarily correlate with degree of thumb hypoplasia (Fig. 26.3A,B). In other words, a patient with a type IV radius may have a type I hypoplastic thumb, and *vice versa*. The physical examination should note the motion at the shoulder, elbow, wrists, and fingers, with notation of the resting position of the radius and degree of passive correction. Degree of thumb hypoplasia as well as the nature of the fingers (supple or stiff) is also important to note in the




Fig. 26.2 Thumb hypoplasia, types I to V: type I, hypoplastic type; type II, + missing intrinsics; type IIIA, + missing extrinsics, stable carpometacarpal (CMC) joint (circle); type IIIB, + unstable/missing CMC; type IV, *pouce flottant*; type V, absent joint.²² (With permission from Herring JA, Tachdjian MO. *Texas Scottish Rite Hospital for Children. Tachdjian's Pediatric Orthopaedics*, 4th edn. Philadelphia, PA: Saunders/Elsevier; 2008.)



Fig. 26.3 (A) Type IV radius and type II hypoplastic thumb. (B) Type 0/N radius and type IV hypoplastic thumb.

initial evaluation. If the patient is a newborn, radiographs may not be of much use and can usually wait until they are seen at the 6–12 month-old time interval.

The role of the occupational therapist is crucial, as stretching of the wrist is begun when the newborn is first seen. When the child is of adequate size, a splint is fashioned to aid in the stretching of the wrist. On subsequent visits it is crucial to observe and document the use-pattern of the fingers. In other words, when the child grasps objects, is it between: thumb–index finger (if thumb present); index–middle finger; or ring–little finger? This becomes important when considering surgical intervention, not only for the thumb but also the wrist. If a child grasps primarily between the ring and little fingers, any attempt to formally centralize the wrist (discussed later) may actually worsen function as it may prevent the child from getting his/her hand to the mouth. Also, it has been shown in these patients that the average growth of the ulna in an untreated patient is 64% of normal, with centralized patients achieving only 48–58% of normal length, which can further limit access of the hand to the mouth.²³ Additionally, in a recent article, Ekblom (2014) reported that in RLD patients, grip strength, key pinch, forearm length, and elbow and digital motion are more important than radial angulation of the wrist for daily activity and participation.²⁴

Surgical treatment and postoperative care

As the child reaches a year of age, he/she can be assessed for suitability for surgical intervention. As stated above, some patients actually benefit from having a radially deviated wrist and would be greatly impaired if it was placed in a straight, stiff position. Other important considerations include the generalized health of the patient. As many associated organ

systems can be affected in these patients, no surgery should be contemplated until after medical clearance is obtained.

A common procedure for the wrist is distraction with some variation of centralization, whether it be centralization or radialization.^{25–33} In general terms, this involves surgically placing the carpus on the distal end of the ulna. Centralization, without distraction, was described by Sayre in 1893 with multiple modifications being made over the years by other surgeons.²⁵ An important addition was by Kessler in 1989, who introduced the concept of pre-distraction of the soft tissues prior to centralization, as many surgeons noted difficulty performing centralization without it because of the severity of soft-tissue contractures.²⁸ The age that this is performed, as well as the speed of distraction, varies depending on the surgeon.^{28,30,31,33} In the classic centralization procedure, a notch is made in the carpus to align the third metacarpal with the ulna. In the radialization procedure, described by Buck-Gramcko, the carpus is balanced on the ulna with the second metacarpal in alignment with the ulna.³² Dorsoradial muscle mass is then transferred to the dorsoulnar side in an attempt to re-balance the forces across the wrist. The greatest problem with these procedures is that the wrist deformity tends to recur over time,³⁴ with potential for ulnar physeal injury and ultimately a shorter forearm.²³ Also, only one published study has shown functional benefit of the procedure,³⁵ with most reporting no significant improvement using validated outcome studies.^{24,36} In addition, as stated above, in some patients elbow stiffness and/or ulnar prehension exists which makes wrist radial deviation an advantageous position for getting the hand to the mouth.

An alternative to centralization for severe cases (types III and IV) is the soft-tissue release and bilobed flap procedure³⁷ (Fig. 26.4). In this procedure the non-essential soft-tissue




Fig. 26.4 Diagram of rotation for dorsal and volar bilobed flaps with corresponding clinical photographs.³⁷ (Reproduced with permission from Vuillermin C, Wall L, Mills J, et al. *Soft tissue release and bilobed flap for severe radial longitudinal deficiency*. J Hand Surg Am. 2015;40:894–9.)


structures are released with use of a bilobed flap for skin closure. Our original procedure involved a dorsal approach, but we have now transitioned to a volar approach based on several factors: improved, less conspicuous scars and better exposure for identification and safe release of tight radial structures. Under tourniquet control, the skin flaps are incised and raised off the investing fascia. This dissection plane, in addition to wide flap bases, preserves maximal blood supply to the tips of the flaps. During dissection, the dorsal branch of the ulnar nerve as well as sensory branches of the radial nerve should be identified and preserved. At this point, all tight fascial bands along the radial wrist are released. It is important to not perform extensive dissection around the distal ulna as it may compromise physeal blood flow and lead to growth arrest. If a pure wrist flexor is identified inserting into the radial carpus, it can be released and transferred to the ulnar wrist. The median nerve and finger flexors can be in a very aberrant location and must be carefully identified and preserved. After this is performed, usually the wrist can be brought to a neutral position in both the radial/ulnar and extension/flexion axes. It is important to place a Kirschner wire for stabilization with the wrist in maximum correction which is directed obliquely from the distal ulnar

metadiaphysis to the radial carpus to prevent motion during flap healing. This wire is carefully placed as to not cross the ulnar physis. At 4 weeks, the wire is removed and a custom static wrist orthosis is fashioned, with institution of range of motion exercises and stretching. The orthosis is continued full-time for 6 weeks, then transitioned to night-time use only.

It is understood that recurrence of some radial deviation at the wrist is the anticipated outcome; however, it preserves motion of the wrist with an improved resting position. In addition, there is no potential for ulnar physeal injury, thereby allowing the ulna to grow to its full potential, which, as stated above, is approximately two-thirds of normal. In patients with TAR syndrome, a significant elbow flexion contracture can be present and can be effectively treated by releasing the so-called brachioradialis muscle, which has been previously described.³⁸ This muscle has a high origin on the humerus and inserts on the radial carpus, thereby causing a significant elbow flexion contracture along with deformity at the wrist. At a later time, if the patient and family desire a straighter wrist position, a Vilkkii procedure can be offered as an alternative.³⁹ (Fig. 26.5A,B) In this procedure, a distractor is placed and the hand is gradually brought out, if not overcorrected, over a period of 6 weeks. This can be a very difficult distraction as the



Fig. 26.5 (A) A 5½-year-old male with RLD. (B) Initial surgery with bilobed flap/soft-tissue release and distractor placement.



deformity is not only radial but also volar. At this point, a vascularized second metatarsal–phalangeal toe joint is transferred to the radial side of the distal forearm. (Fig. 26.6A,B) The distraction device is left on another 6 weeks and then removed. This results in a straighter wrist while preserving wrist motion. However, we have found that most patients/parents are satisfied with the soft-tissue release alone and do not want to proceed with the toe joint transfer.

Surgical treatment options for the thumb

Type I hypoplastic thumbs have all the structures and thus do not usually need reconstruction. Type II hypoplastic thumbs usually can benefit from an opponensplasty +/- MP joint ligament reconstruction if significant instability is present. I prefer a flexor digitorum superficialis (FDS) ring transfer; however, a Huber transfer (abductor digiti minimi) has also been used to reconstruct opposition. (Fig. 26.7A–C) In addition, many of these patients also benefit from a four-flap Z-plasty of the first webspace. This is performed by first elevating the flaps for the four-flap Z-plasty in the first web and exposing the ulnar

base of the proximal phalanx as well as the metacarpal neck. Next, an incision is made along the radial side of the thumb, exposing the radial metacarpal neck. A bone tunnel is then made through the metacarpal neck/head area to allow the FDS ring finger tendon to be passed through it. Next, an incision is made over the A1 pulley of the ring finger, and the FDS tendon is isolated and transected distally. An incision is then made over the volar–ulnar wrist or the transverse carpal ligament, depending on which pulley is to be utilized. The FDS tendon is then retracted proximally and re-directed around the desired pulley to the radial incision that had already been made. If only the MP (metacarpal–phalangeal) ulnar collateral ligament (UCL) is to be reconstructed, then the entire tendon is passed through the bone tunnel and across the joint to the ulnar base of the proximal phalanx. A suture anchor or bone tunnel can be used, but it is obviously essential to be distal to the proximal phalanx physis. If the radial collateral ligament (RCL) also needs to be reconstructed, then the tendon can be split: half passed through the bone tunnel, while the other half is passed across the radial side of the MP joint to reconstruct the RCL. The Z-plasty flaps are



Fig. 26.6 (A) 6 weeks post-distraction. (B) After graft incorporation (note the open physis of the toe transfer).

rotated and sutured in place. A pin is placed across the MP joint with the patient in cast immobilization for 4 weeks. After the 4-week period, the patient is then placed in a basic opposition splint, and range-of-motion (ROM) exercises instituted with the splint gradually being weaned over a 4-week period.

Clinical tips

RLD – considerations for thumb surgery

- Observe patient to ensure he/she attempts use of thumb for pinch (i.e., does not bypass it), otherwise pollicization may be the better procedure.
- Metacarpal must be large enough to allow bone tunnel to be made.
- Patient must be able to participate in postoperative rehabilitation.
- Avoid injury to the proximal phalanx physis when decided on insertion point for FDS tendon.

In general, type IIIA thumbs benefit from reconstruction as stated above; however, type IIIB thumbs require index finger pollicization because of the gross instability of the CMC joint. Type IV and V thumb hypoplasia is treated with an index pollicization if warranted clinically. Prior to performing a pollicization, it is important to observe the child's prehensile grasp. If he/she preferentially pinches between the index and middle finger, then a pollicization is indicated (Fig. 26.8A–D). If, however, the index finger is stiff and pinch is between the ring and little finger, then pollicization will not likely improve function. In some countries, because of cultural considerations, a toe transfer is preferred over a pollicization.⁴⁰ Extensive details for thumb reconstruction can be found in Chapter 27.

Outcomes, prognosis, and complications

In summary, early treatment for patients with RLD includes stretching and splinting of the wrist if significant radial

deviation is present. A thorough evaluation of the patient is warranted due to the many medical conditions that may also be present. As the child approaches the age range of 12–18 months, consideration for surgery on the wrist can be undertaken, if warranted, as long as underlying medical issues do not preclude it. At about 2 years of age, index pollicization can be performed if this is indicated. Tendon transfers/MP stabilization procedures usually are not performed until the child is older, in the range of 4–6 years old, as structures are larger and rehabilitation easier and more effective. Genetic counseling can be important for parents because of the many associated syndromes and the varying inheritance patterns that exist.

Ulnar longitudinal deficiency

Basic science/disease process

The incidence of ulnar longitudinal deficiency (ULD) is much less than that of radial longitudinal deficiency, approximately one-quarter, and usually is unilateral. In the Swanson classification, this represents a IB, and in the OMT classification it is I.A.2.ii (upper limb including hand) or 2.ii (hand only).¹¹ In contradistinction to RLD, most cases of ULD are sporadic and rarely have associated heart and hematopoietic abnormalities. In addition, ULD patients can have musculoskeletal anomalies such as fibular and tibial ray deficiency, proximal femoral focal deficiency, scoliosis, clubfeet, and absent patellae, which are not usually seen in RLD patients. Interestingly, radial hand abnormalities are not infrequent. This is thought to be due to an insult in the ZPA, which resides on the ulnar side of the developing hand. Depending on the severity of the insult, this can affect the development and growth of both ulnar and radial hand structures.

Diagnosis/patient presentation

Bayne (1982) classified the forearm/elbow into four types based on the length and size of the ulna. Type I is a hypoplastic




Fig. 26.7 (A) Preoperative photographs of a type IIIA hypoplastic thumb. (B) Intraoperative photograph of design of opponensplasty. (C) Postoperative opposition and metacarpal-phalangeal joint stability.

ulna with proximal and distal ulnar epiphyses present.⁴¹ Minimal deformity or shortening is noted. Type II is absent distal or middle third of ulna with possible fibrous anlage and consequential radial bowing. However, the elbow is stable. Type III is a total absence of the ulna with an unstable elbow. Type IV is an absent ulna with radiohumeral synostosis. In addition, there is possible progressive ulnar deviation at the wrist secondary to a fibrous anlage, although this is controversial.⁴¹ As in RLD, a type 0 has been added, to represent patients who display hand plate abnormalities only.⁴² Also, as in RLD, a type V has been added, to represent more proximal involvement (phocomelic)¹⁹ (Fig. 26.9). Cole and Manske (1997) classified the hand based on the appearance of the thumb and first webspace as this is critical for hand function⁴³ (Fig. 26.10). In type A, the thumb and first webspace are normal. In type B, the thumb is mildly deficient with a narrow first webspace. Opposition is present with intact extrinsic tendons. In type C, there is a more severe first webspace deficiency with varying degrees of thumb involvement, including possible syndactyly to the index finger and malrotation of the thumb into the plane of the palm. Opposition function is lost and dysfunction of the extrinsic tendons is present. Type D represents an absent thumb. As in RLD, there

is no correlation between the severity of ulna and hand involvement.

Patient selection

As in any child with an upper limb anomaly, it is important to perform a thorough examination from head to toe. As stated above, lower extremity abnormalities can be present in ULD and must be documented and appropriate referrals made if present. In the upper limb, the hand can be in a variety of positions, including facing backwards in some cases of type IV ULD, but a significantly short extremity is usually present. The elbow can be stable or unstable depending on ulna involvement, with restricted or absent forearm pronation/supination. The wrist may have some ulna deviation but is usually stable. Oligodactyly in the hand with varying degrees of deficiency in the fingers/thumb that are present is the usual clinical scenario. This can include underlying possible bony anomalies such as metacarpal synostosis or aberrant bony anatomy of the hand/fingers, which may represent further deforming forces. Syndactyly may also be present to varying degrees in the fingers.



Fig. 26.8 (A) Preoperative photograph and radiograph for pollicization (note the pronated position of the index finger). (B) Intraoperative photograph of design of incisions along with photograph of final closure. (C) Postoperative function. (D) Postoperative radiograph showing good stability at the base and open physes of the pollicized digit.




Fig. 26.9 Schematic of Bayne's classification of ulnar longitudinal dysplasia.^{22,41} (Reproduced with permission from original publication: Herring JA, Tachdjian MO. *Texas Scottish Rite Hospital for Children. Tachdjian's Pediatric Orthopaedics, 4th edn. Philadelphia, PA: Saunders/Elsevier; 2008.*)




Fig. 26.10 Bayne and Manske classifications for ulnar dysplasia. H, Humerus; R, radius; U, ulna; * indicates progressive involvement of the thumb-index webspace.²² (Reproduced with permission from original publication: Herring JA, Tachdjian MO. *Texas Scottish Rite Hospital for Children. Tachdjian's Pediatric Orthopaedics, 4th edn. Philadelphia, PA: Saunders/Elsevier; 2008.*)

These children are usually of normal to above-normal intelligence and function very well. At times, adaptive devices can be very helpful with activities of daily living, and it is imperative that therapists are involved with the care of these patients. It should be noted that since these children are usually extremely functional, any surgery that is contemplated must have a specific goal to increase use/function prior to proceeding.

Surgical treatment and postoperative care

While most ULD children are able to bring the hand to the mouth, some type IV children (radiohumeral synostosis) have his/her elbows fused in a position with the hand facing backwards. These children can benefit from a flexion osteotomy to put the hand in a position to reach the mouth. Importantly, this is usually not a rotational osteotomy as clinically it is apparent that most times the deformity is one of hyperextension, not rotation, based on the thumb position. The osteotomy is usually performed in the supracondylar region of the humerus. It is important to Doppler out and mark the course of the brachial artery prior to surgery. Also, removal of 1–2 cm of bone usually allows the osteotomy to be

Clinical tips

ULD – evaluation for surgery

- Assess the child for proximal femoral focal deficiency, fibular and tibial deficiency, scoliosis, clubfeet, and absent patellae.
- Anomalies of the heart and hematopoietic systems are rare.
- The deficit in the hand can include ulnar, radial, or both sides of the hand.
- Carefully assess the function of the hand as well as radiographs since variable anatomy may be present and separation of digits may not be warranted.




Fig. 26.11 (A) Preoperative photograph and radiograph of ULD with hand facing backwards. (B) Immediate postoperative photograph, immediate postoperative radiograph, and final follow-up radiograph.

performed without undue tension on the neurovascular structures, which is a potential serious complication. This osteotomy can usually be stabilized with K-wires +/- intraosseous wire. It is then held immobilized until radiographic evidence of union is noted (Fig. 26.11A,B). As expected, this will usually improve function in these children as it enables them to reach the hand to the mouth.

In some patients, release of the ulnar anlage can be beneficial as it acts as a tether that can cause increasing deformity, radial bowing, and ulnar wrist deviation as the child grows (usually type II or IV). Interestingly, histology of this structure has shown it to be hyaline cartilage proximally and fibrocartilage more distally. Serial X-rays and clinical examinations will determine the appropriate patients and timing for the surgery as not all ULD patients will benefit from this. Of note, this should be done when the patient still has significant radial growth potential remaining, as release of the tether will allow correction of much of the angular deformity over time. To do this, an incision is made over the ulnar border of the forearm/wrist with careful identification of the ulnar neurovascular bundle, if present, as the flexor carpi ulnaris is usually not present. It is essential to completely dissect out and release the distal portion of the anlage which attaches to the carpus and sometimes the radius. After this is performed, the "tether" effect should be alleviated and passive motion should be markedly improved. If severe bowing is present or not much growth remains in the radius, then an osteotomy can be performed at the same setting. The extremity

is then casted until wound healing has taken place (bone healing if osteotomy was performed) (Fig. 26.12A-C). Stretching and splinting is instituted along with serial follow-up radiographs.

The majority of surgical procedures in ULD patients are usually focused on the hand. Depending on the type of hand deformity present, surgery can involve first webspace reconstruction, syndactyly reconstruction, and/or thumb reconstruction (Fig. 26.13A,B). It is imperative that a thorough clinical and radiographic examination be performed prior to contemplating any surgical reconstruction. Because of the unusual anatomy that can exist, no syndactyly reconstruction is warranted and/or feasible at times (Fig. 26.14A,B). Also, when syndactyly reconstruction is undertaken, careful exploration of the neurovascular and tendinous structures is warranted since at times separation is not technically feasible. First webspace reconstruction is accomplished either through standard webspace deepening techniques or flap reconstruction in severe cases. A difficult situation exists when the thumb is in the plane of the palm. Since opposition function is so crucial in these patients, performing a rotational osteotomy through the metacarpal can be helpful. However, significant memory in the periosteum and other deforming forces can exist and can cause recurrence of the deformity. To address these, the periosteum should be scored circumferentially as well as a release and re-insertion of the adductor and thenars, if present. At times, opposition transfer is also required to provide enhanced function of the thumb.




Fig. 26.12 (A) 10-month-old with ULD and severe deformity due to ulna tether. (B) Photograph depicting ulna anlage excision and osteotomy of same patient at 1 year of age. (C) Follow-up at age 3 years (left) and 9 years (right) of age showing maintained longitudinal growth without recurrent deformity.




Fig. 26.13 (A) Preoperative photograph and radiograph of ULD patient with syndactyly. (B) Postoperative photograph and radiograph.



Fig. 26.14 (A) Preoperative photograph and radiograph of ULD patient not suitable for syndactyly separation, but rather rotational thumb osteotomy alone. (B) Immediate postoperative photograph of rotational osteotomy of thumb with no syndactyly release.

Outcomes, prognosis, and complications

ULD is less common than RLD and is distinguished from it in several important ways. As opposed to RLD, patients with ULD usually do not have associated cardiac, renal, gastrointestinal, or hematopoietic abnormalities. Instead, they can have associated musculoskeletal abnormalities and, therefore, a thorough lower extremity exam is warranted. Surgical treatment is usually centered on issues present in the hand including webspace insufficiency, syndactyly, and/or thumb (if present) position.

Central deficiency

Basic science/disease process

The etiology of central deficiency is thought to be a defect in the AER, which has been reproduced in the chick embryo by removing the central portion.⁴⁴ Of note, complex polysyndactyly and central deficiency are two phenotypes that can result from the same teratogen, and are thus related. This has been shown in eloquent experiments by Ogino (1990), who gave busulfan to a litter of rats, which resulted in both phenotypes (Fig. 26.15). A logical explanation for the sequence of this exists in his paper and is beyond the scope of this chapter.⁴⁵

Autosomal-dominant inheritance pattern is present in many patients, and has been localized to chromosomes 3, 7, and 10. However, *de novo* mutations are also quite common. An interesting inherited central deficiency is EEC (ectrodactyly ectodermal dysplasia, cleft lip/palate), which has been localized to 7q11.2–q21.3. In this syndrome, central deficiencies can be present in all four limbs as well as cleft lip/palate, sparse and brittle hair, external ear abnormalities, hearing loss, ophthalmologic abnormalities, and genitourinary problems, although phenotypic expression is highly variable.

Split-hand/split-foot syndrome also has an autosomal-dominant inheritance pattern with variable penetrance.

Diagnosis/patient presentation

In the original IFSSH classification, this was I.B.3. In the OMT classification, cleft hand is 3.11.c. Manske (1995) published a classification that is useful in guiding treatment in these patients.⁴⁶ His classification is based on the first webspace: type 1, normal web; type 2A, thumb web mildly narrowed; type 2B, thumb web severely narrowed; type 3, syndactylized web; type 4, thumb web merged with cleft with index finger suppressed; and type 5, absent thumb and web suppressed with ulna ray remaining.⁴⁶

Patient selection

Because of the phenotypic variability, it is imperative to examine the entire patient. Classically, the cleft deformity in the hands and feet has been described as “V” shaped; but in the monodactylous form, only the ulnar digit may be present. Syndactyly between digits adjacent to the cleft is common, as is variable metacarpal and phalangeal anatomy. Evaluation of ectodermal-derived structures is also important because of possible EEC syndrome. Radiographs yield important information regarding underlying bony abnormality as well as possible presence of aberrant osseous structures.

As in other patients with congenital hand differences, therapists are essential members of the team as they provide teaching as well as assistive devices if necessary.

Surgical treatment and postoperative care

Adrian Platt commented that these patients are “a functional triumph and social disaster”, meaning that these patients are very functional and any considerations for surgery should take this into account, especially when deciding to operate on



Fig. 26.15 Cleft hand and central synpolydactyly hand in same patient.



Fig. 26.16 Cleft hand with transverse element.

a cleft solely for cosmetic reasons.⁴⁷ Certainly Manske's classification offers generalized principals for treatment based on the importance of the first webspace for grasp. Creating an adequate first webspace certainly provides increased grasp and is of significant benefit to the patient. Depending on underlying anatomy, the thumb-index fingers may be better left together, based on clinical examination and radiographic appearance.

At times there can be a transverse bone present in cleft hands and, if not addressed, this can be a significant deforming force as the child grows (Fig. 26.16). Excision at the base of the transverse bone should ensure removal of potential physis of the transverse bone to decrease risk of recurrence. In addition, underlying structures such as the collateral ligaments may need to be repaired/reconstructed after removal of the transverse bone.

If thumb-index finger release is to be performed along with cleft closure (types 2B and 3), many techniques have been described. Popular skin incision designs that are utilized include Snow-Littler,⁴⁸ Miura-Komada,⁴⁹ and more recently Upton.⁵⁰ I prefer a slightly modified version of Upton, as the design is much simpler and the risk of wound problems is much less than that seen in the Snow-Littler and Miura-Komada procedures (Fig. 26.17A-C). After the skin incisions are made, meticulous technique must be utilized to preserve vascularity of the skin flaps, as partial or moderate skin flap loss can be a frequent complication. No matter which incision is used, it is imperative that thorough exploration of the neurovascular structures is performed to assure the anatomy will allow transposition and closure of the cleft without undue risk to the digit. Also, assessment of the adductor muscle insertion is essential and re-positioning performed, if warranted, as it sometimes is attached to the index finger. Fascia and other aberrant muscle may also need to be released in order to adequately release the first web. After this is performed, transposition of the index metacarpal to the middle metacarpal is performed if technically feasible. The origin of the adductor muscle off the middle metacarpal is carefully identified and preserved, with the index metacarpal being transposed just distal to this point after adjusting for appropriate length. This can be stabilized with K-wires, interosseous

wires, or a combination of both. If a third metacarpal is not present, an osteotomy at the base of the index metacarpal can help with re-positioning the finger in the plane of the ring and little finger. In either case, reconstruction of an intermetacarpal ligament is performed using bone tunnels and local tissue such as A1 pulleys, free tendon graft, or a combination of these.

In cases of central clefts with a normal thumb-index web, closure can be performed with local flaps producing good results in terms of function and aesthetic appearance. Usually transposition of the metacarpal is warranted as well as reconstruction of the intermetacarpal ligament using localized tissue or graft.

In some cases, no separation/closure should be performed since the function is good and any attempts at separation and transposition may actually make the digits unstable.

In cases of four-limb involvement, where the pediatric orthopedists are planning Symes amputation, consideration should be given to use of toes as a potential transfer to the hand, if indicated, to improve overall function, especially if a type 5 cleft (absent thumb) is present.

Outcomes, prognosis, and complications

In summary, it is imperative that every patient be evaluated separately and decisions regarding surgical intervention be made on a case-by-case basis. Surgery should be reserved for patients in whom improved function and cosmetic appearance can be achieved with minimal potential morbidity. If patients are not selected appropriately, poor outcomes along with significant scarring can occur.

Transverse deficiencies

Basic science/disease process

As mentioned earlier, this condition is thought to be caused by disruption of the subclavian vascular axis as described by Bavinck and Weaver.⁶ They hypothesize that occlusions occur at specific locations around the sixth week of embryonic




Fig. 26.17 (A) Preoperative photograph and radiograph of a cleft hand. (B) Intraoperative photographs and follow-up radiograph. (C) Final follow-up radiograph.

development. Depending on the timing and location of the insult, different phenotypes may arise. In addition, there may be associated findings of Poland's (varying amounts of pectoralis muscle absence), Moebius syndrome, Klippel-Feil, and even Sprengel deformity.⁶

No animal model has been developed that re-creates this deformity. This is usually a sporadic occurrence that presents unilaterally. Four-limb transverse deficiency associated with aplasia cutis congenita is the exception (Adams-Oliver) and can have either an autosomal-dominant or recessive inheritance pattern.

An interesting transverse deficiency has been reported from our institution that we feel has a different etiology than symbrachydactyly.⁵¹ The phenotypical presentation is that of a transverse deficiency with no ectodermal elements in affected digits. Instead, fleshy bulbous soft-tissue sleeves are present, and the severity seems to be most on the ulnar side of the hand (Fig. 26.18). Because of the lack of ectodermal elements and involvement pattern, we feel that this represents a different etiology than the more commonly occurring symbrachydactyly (subclavian artery supply disruption sequence).

Diagnosis/patient presentation

This is one of the diagnoses that did not clearly fit into any of the categories that Swanson described in his classification

system. In the OMT system, this is I.A.1.ii(a,b) for whole limb or I.B.1.ii for hand plate alone without forearm/arm involvement.¹¹ The diagnostic phenotype shows great diversity, including short-finger type, monodactylous type, atypical type, and peromelic type. As opposed to patients with central deficiency which have a "V" deformity, these patients display a "U" deformity along with nubbins (remnants of ectoderm). Interestingly, Poland's is usually seen more commonly with the short-finger variant than with the peromelic type.

Patient selection

Examination of these patients should begin in the head and neck region to assess for possible Moebius syndrome. Next, a careful examination of the neck and trunk for clinical evidence of Klippel-Feil, Sprengel's, and/or Poland's is warranted. In children with Poland's, the findings can be solely a lack of the sternal head of the pectoralis major or be the entire muscle with involvement of the chest wall with involvement of the pectoralis minor and latissimus dorsi muscles. In infants, it can be very difficult to identify the very mild cases of Poland's and reassessment at a later date is necessary. The findings in the upper extremity can be divided into four types: (1) short-finger type, (2) monodactylous type, (3) atypical cleft type, and (4) peromelic type (Fig. 26.19A–D). In patients with the peromelic type, the level of truncation can be the hand, carpus,



Fig. 26.18 Hypodactylia (note the lack of ectodermal elements).



Fig. 26.19 (A) Short finger symbrachydactyly. (B) Monodactylous symbrachydactyly. (C) Atypical symbrachydactyly. (D) Peromelic symbrachydactyly.



Fig. 26.20 Adaptive devices for activities.

or forearm, with nubbins being present distally. Ogino (1989) reported the order of radiographic findings found in the progression of symbrachydactyly. The most common finding in all types was hypoplasia of the central rays followed by progressive brachymesophalangia leading to absence of middle phalanges then more proximally to include metacarpals.⁵² Many times, the middle phalanx hypoplasia can be significant enough to affect joint motion at the proximal interphalangeal and distal interphalangeal joints. Even in severe forms of symbrachydactyly (peromelic), nubbins consisting of nail and underlying distal phalanx are present as these are derived from ectodermal tissue.

Clinical tips

Transverse deficiencies – evaluation for surgery

- Clinical evaluation of the entire patient is necessary as multiple associated findings may exist.
- It is important to remember that untreated patients function very well, so any surgery, except syndactyly reconstruction, needs to be assessed on an individual case basis and should only be performed if there is a realistic goal of increasing function.
- If a syndactyly exists but the finger tips are separated and no significant tethering exists, reconstruction should be delayed until the child is 2–3 years of age as to minimize possible effects of anesthesia as well as to allow the fingers to be bigger and easier to perform surgery on.

Surprisingly, these patients usually have very few limitations, even with the most severe form. Most do not benefit from prostheses as they are most commonly passive, insensate devices and actually impair function in these children. For patients and parents that are interested, reports of 3D-printer prostheses have emerged and initial data is promising as a cheaper alternative to myoelectric devices, which can be very costly.⁵³ Prostheses made to aid with specific activities, however, can be very useful. These are usually custom-made

to suit the needs of the child and enable them to more easily perform activities such as jumping rope, riding bikes, and sports (Fig. 26.20).

Surgical treatment and postoperative care

Parents of patients with the peromelic type of symbrachydactyly can occasionally desire removal of the nubbins for cosmetic reasons or because they frequently get traumatized. In my experience, this is a rare occurrence and most parents prefer to leave the nubbins and let the child make their own decision when they are older regarding excision. At that time it is extremely rare that they desire any surgery for this.

Short-finger type symbrachydactyly patients often have webspaces that can benefit from deepening. The timing of this depends on the severity and webspaces involved. In general, because of the new reports of potential harm from general anesthesia in young patients, we try not to perform this surgery until after 2 years of age.⁵⁴ Exceptions would be if significant tethering of digits is present and/or significant first webspace narrowing, in which case surgery would be performed at an earlier age. If the middle phalanges are severely hypoplastic, it is important to discuss with the parents that even after separation the fingers may not have full range of motion, so that they have realistic expectations.

Non-vascularized toe phalanx transfer has been advocated by some in certain forms of symbrachydactyly to provide more length to the fingers.⁵⁵ In this procedure, portions of toe phalanges, including periosteum, are transferred to soft-tissue sleeves in the hand to provide more length. This must be performed at a very young age for optimal results. Despite some encouraging results, long-term studies show variable amounts of reabsorption along with significant donor site morbidity⁵⁶ (Fig. 26.21). Due to our own experience, and that of others, we are not advocates of this procedure.

Free vascularized toe transfers can be extremely beneficial to patients with the monodactylous form of symbrachydactyly, as it adds an ulnar digit which can provide increased grasp capabilities (Fig. 26.22). In this procedure, usually the second toe is harvested and transferred using standard



Fig. 26.21 Patient who underwent non-vascularized toe transfer to the right hand (left) with bone graft resorption and poor donor site (right).

microvascular techniques to the ulnar side of the hand in a position that allows tip-to-tip pinch with the thumb. Flexor function of the transferred digit can be very difficult to achieve as the recipient flexor tendons tend to be coalesced together in the distal wrist/carpal tunnel region. As stated above, these patients are usually very functional with very few limitations and they (along with parents) usually do not desire to pursue this procedure.

Patients with Poland's present a very difficult problem for the reconstructive surgeon. Some patients do not like the lack of fullness in the anterior axillary fold as they feel it draws unwanted attention and also limits what can be worn due to the asymmetry. In these children, I assess them for presence of ipsilateral latissimus dorsi muscle and, if present, discuss potential rotational flap to address this. In the young child, this can be performed with very limited incisions, thereby having limited morbidity. In my experience, this has yielded excellent results and happy patients/parents. In patients/parents that are interested, I perform this procedure at the age of 8–10 years. Girls present a very difficult reconstruction, as not only do they require breast reconstruction, but also the




Fig. 26.22 (A) Preoperative photograph and radiograph of monodactylous symbrachydactyly. (B) Postoperative photograph exhibiting useful function along with a postoperative radiograph following vascularized toe transfer. (C) Donor site following toe harvest.

nipple is usually severely hypoplastic and in an aberrant location. In early teenage years, an expander can be placed with serial expansion until adulthood, at which point replacement with a permanent implant is performed along with nipple repositioning/reconstruction.

Outcomes, prognosis, and complications

Phenotypic variation is common in patients with transverse deficiency. Treatment depends on what, if any, deformity is present and can range from syndactyly reconstruction to free vascularized toe transfer. These patients usually are very functional and have an excellent long-term prognosis.

Future directions

For now, even though many RLD patients have genetic mutations that can be identified, it is hard to believe that any genetic manipulation is on the horizon that can alter the phenotypical presentation, as upper extremity development occurs very early in gestation. Likely alternative procedures that provide stability and position of the wrist with retained motion long term are possibly in our near future. Perhaps this will include a variation of the procedure Innocenti⁵⁷ uses for reconstruction after tumor excision in the distal radius. He utilizes a vascularized fibular head, which provides potential benefits of good stability of the wrist, retained motion, and growth potential, which is likely similar to that of the ulna. In addition, a portion of the biceps tendon can be taken with the fibular head to be used for ligamentous reconstruction in the wrist. At this point, the potential complication of peroneal nerve injury has limited its use. However, with improved dissection techniques and anatomical studies, this risk is likely to be decreased in the future. It is important to

remember, however, that untreated patients are very functional, so any surgical intervention is largely cosmetic in nature and must not inhibit or worsen function.

As stated earlier, prosthetic hands/arms in the past have been of very little functional use for congenital upper extremity-absence patients, as they have been insensate and non-functional. Recently there have been significant advances in the development of functional myoelectric prostheses following traumatic amputation that may be of some value to selected congenital absence patients in the future.^{58,59} However, these tend to be very costly, and recently there have been reports of 3D printing being a cheaper alternative.⁵³

Although vascularized composite allografting (VCA) has become more accepted, its significant morbidities make it unlikely to become commonplace treatment for these patients. Perhaps tissue engineering for generation/regeneration of fingers/limbs may be a possible alternative if cell expansion can be perfected to the point of making it a viable option; however, this is likely many years away.⁶⁰

Longitudinal, central, and transverse deficiencies are diagnoses that are treated often by the pediatric hand surgeon. It is imperative that the surgeon treating these conditions is knowledgeable regarding the proper work-up that should be performed for each condition, as well as appropriate referrals and genetic counseling that should be obtained. These patients are usually seen and treated from infancy until adulthood and thus go through many stages of physical and psychological development, which must be addressed. In fact, some of the social issues far outweigh any decision-making regarding surgery. These patients are usually very functional, so careful consideration before proceeding with surgery is warranted. Lastly, it is imperative to have a multidisciplinary team to properly evaluate and treat these children as their needs are certainly not static or identical in nature.



Access the complete reference list online at <http://www.expertconsult.com>

2. Daluiski A, Yi SE, Lyons KM. The molecular control of upper extremity development: implications for congenital hand anomalies. *J Hand Surg Am.* 2001;26:8–22. *Upper limb embryology is a very complex process which requires a precise series of events to occur. Knowledge of the normal sequence of events is imperative to understanding the etiology of congenital upper limb differences and thus be able to confer proper information to parents.*
5. Kato H, Ogino T, Minami A, Ohshio I. Experimental study on radial ray deficiency. *J Hand Surg [Br].* 1990;15:470–476. *This is an important reference as it provides an animal model for radial longitudinal deficiency. In this study the authors were able to reproduce radial longitudinal deficiency by the administration of a teratogen at a specific time during fetal development.*
6. Bavinck JN, Weaver DD. Subclavian artery supply disruption sequence: hypothesis of a vascular etiology for Poland, Klippel-Feil, and Möbius anomalies. *Am J Med Genet.* 1986;23:903–918. *Symbrachydactyly is a very common congenital hand anomaly. At present, no animal model exists for this condition, but in this reference the authors describe the accepted etiology for symbrachydactyly as well as its associated conditions.*
11. Tonkin MA, Tolerton SK, Quick TJ, et al. Classification of congenital anomalies of the hand and upper limb: development and assessment of a new system. *J Hand Surg Am.* 2013;38:1845–1853.
24. Ekblom AG, Dahlin L, Rosenberg HE, et al. Hand function in adults with radial longitudinal deficiency. *J Bone Joint Surg Am.* 2014;96:1178–1184.
33. Goldfarb CA, Murtha Y, Gordon JE, et al. Soft-tissue distraction with a ring external fixator before centralization for radial longitudinal deficiency. *J Hand Surg Am.* 2006;31:952–959.
37. Vuillermin C, Wall L, Mills J, et al. Soft tissue release and bilobed flap for severe radial longitudinal deficiency. *J Hand Surg Am.* 2015;40:894–899.
39. Vilkki SK. Vascularized metatarsophalangeal joint transfer for radial hypoplasia. *Semin Plast Surg.* 2008;22:195–212.
45. Ogino T. Teratogenic relationship between polydactyly, syndactyly, and cleft hand. *J Hand Surg [Br].* 1990;15:201–209. *This is a landmark reference as the author showed that in an animal model he could create either polysyndactyly or cleft hand using the same teratogen given at the same time during fetal development. Further, an excellent explanation is given that explains how this can occur.*
46. Manske PR, Halikis MN. Surgical classification of central deficiency according to the thumb web. *J Hand Surg Am.* 1995;20:687–697. *Classification of central deficiency with its surgical implications.*

References

- Dy C, Swarup I, Daluiski A. Embryology, diagnosis, and evaluation of congenital hand anomalies. *Curr Rev Musculoskelet Med*. 2014;7:60–67.
- Daluiski A, Yi SE, Lyons KM. The molecular control of upper extremity development: implications for congenital hand anomalies. *J Hand Surg Am*. 2001;26:8–22. *Upper limb embryology is a very complex process which requires a precise series of events to occur. Knowledge of the normal sequence of events is imperative to understanding the etiology of congenital upper limb differences and thus be able to confer proper information to parents.*
- Zaleske DJ. Development of the upper limb. *Hand Clin*. 1985;1:383–390.
- Ogino T, Kato H. Clinical and experimental studies on ulnar ray deficiency. *Handchirurg Mikrophir Plast Chir*. 1988;20:330–337.
- Kato H, Ogino T, Minami A, Ohshio I. Experimental study on radial ray deficiency. *J Hand Surg [Br]*. 1990;15:470–476. *This is an important reference as it provides an animal model for radial longitudinal deficiency. In this study the authors were able to reproduce radial longitudinal deficiency by the administration of a teratogen at a specific time during fetal development.*
- Bavinck JN, Weaver DD. Subclavian artery supply disruption sequence: hypothesis of a vascular etiology for Poland, Klippel-Feil, and Möbius anomalies. *Am J Med Genet*. 1986;23:903–918. *Symbrachydactyly is a very common congenital hand anomaly. At present, no animal model exists for this condition, but in this reference the authors describe the accepted etiology for symbrachydactyly as well as its associated conditions.*
- Lourie GM, Lins RE. Radial longitudinal deficiency. A review and update. *Hand Clin*. 1998;14:85–99.
- Koskimies E, Lindfors N, Gissler M, et al. Congenital upper limb deficiencies and associated malformations in Finland: a population-based study. *J Hand Surg*. 2011;36:1058–1065.
- Urban MA, Osterman AL. Management of radial dysplasia. *Hand Clin*. 1990;6:589–605.
- Swanson AB. A classification for congenital limb malformations. *J Hand Surg Am*. 1976;1:8–22.
- Tonkin MA, Tolerton SK, Quick TJ, et al. Classification of congenital anomalies of the hand and upper limb: development and assessment of a new system. *J Hand Surg Am*. 2013;38:1845–1853.
- Bonnet D, Terrett J, Pequignot-Viegas E, et al. Gene localization in 12q12 in Holt-Oram atrio-digital syndrome. *Arch Mal Coeur Vaiss*. 1995;88:661–666.
- Lamb DW. Radial club hand. A continuing study of sixty-eight patients with one hundred and seventeen club hands. *J Bone Joint Surg Am*. 1977;59:1–13.
- Verloes A, Frikiche A, Gremillet C, et al. Proximal phocomelia and radial ray aplasia in fetal valproic syndrome. *Eur J Pediatr*. 1990;149:266–267.
- Lindhout D, Stewart PA, Reuss A, et al. Prenatal ultrasound in antiepileptic drug exposure (abstract). *Teratology*. 1988;37:473–474.
- Pauli RM, Feldman PF. Major limb malformations following intrauterine exposure to ethanol: two additional cases and literature review. *Teratology*. 1986;33:273–280.
- Bayne LG, Klug MS. Long-term review of the surgical treatment of radial deficiencies. *J Hand Surg Am*. 1987;12:169–179.
- James M, McCarroll R, Manske PR. The spectrum of radial longitudinal deficiency: a modified classification. *J Hand Surg Am*. 1999;24:1145–1155.
- Goldfarb CA, Manske PR, Busa R, et al. Upper-extremity phocomelia reexamined: a longitudinal dysplasia. *J Bone Joint Surg Am*. 2005;87:2639–2648.
- Blauth W. The hypoplastic thumb. *Arch Orth Unfallchir*. 1967;62:225–246.
- Manske PR, McCarroll HR Jr, James M. Type III-a hypoplastic thumb. *J Hand Surg Am*. 1995;20:246–253.
- Kozin SH. Upper-extremity congenital anomalies. *J Bone Joint Surg Am*. 2003;85-A:1564–1576.
- Sestero A, Van Heest A, Agel J. Ulnar growth patterns in radial longitudinal deficiency. *J Hand Surg Am*. 2006;31:960–967.
- Eklblom AG, Dahlin L, Rosenberg HE, et al. Hand function in adults with radial longitudinal deficiency. *J Bone Joint Surg Am*. 2014;96:1178–1184.
- Sayre RH. A contribution to the study of club-hand. *Trans Am Orthop Assoc*. 1893;6:208–216.
- Manske PR, McCarroll HR Jr, Swanson K. Centralization of the radial club hand: an ulnar surgical approach. *J Hand Surg Am*. 1981;6:423–433.
- Watson HK, Beebe RD, Cruz NI. A centralization procedure for radial clubhand. *J Hand Surg Am*. 1984;9:541–547.
- Kessler I. Centralization of the radial club hand by gradual distraction. *J Hand Surg [Br]*. 1989;14:37–42.
- Tonkin MA, Nanchahal J. An approach to the management of radial longitudinal deficiency. *Ann Acad Med Singapore*. 1995;24(suppl 4):101–107.
- Smith AA, Greene TL. Preliminary soft tissue distraction in congenital forearm deficiency. *J Hand Surg Am*. 1995;20:420–424.
- Nanchahal J, Tonkin MA. Pre-operative distraction lengthening for radial longitudinal deficiency. *J Hand Surg [Br]*. 1996;21:103–107.
- Buck-Gramcko D. Radialization as a new treatment for radial club hand. *J Hand Surg Am*. 1985;10:964–968.
- Goldfarb CA, Murtha Y, Gordon JE, et al. Soft-tissue distraction with a ring external fixator before centralization for radial longitudinal deficiency. *J Hand Surg Am*. 2006;31:952–959.
- Damore E, Kozin SH, Thoder JJ, et al. The recurrence of deformity after surgical centralization for radial clubhand. *J Hand Surg Am*. 2000;25:745–751.
- Kotwal PP, Varshney MK, Soral A. Comparison of surgical treatment and nonoperative management for radial longitudinal deficiency. *J Hand Surg Eur Vol*. 2012;37:161–169.
- Holtslag I, van Wijk I, Hartog H, et al. Long-term functional outcome of patients with longitudinal radial deficiency: cross-sectional evaluation of function, activity, and participation. *Disabil Rehabil*. 2013;35:1401–1407.
- Vuillermin C, Wall L, Mills J, et al. Soft tissue release and bilobed flap for severe radial longitudinal deficiency. *J Hand Surg Am*. 2015;40:894–899.
- Oishi SN, Carter P, Bidwell T, et al. Thrombocytopenia absent radius syndrome: presence of brachioradialis muscle and its importance. *J Hand Surg Am*. 2009;34:1696–1699.
- Vilkkki SK. Vascularized metatarsophalangeal joint transfer for radial hypoplasia. *Semin Plast Surg*. 2008;22:195–212.
- Tan JS, Tu YK. Comparative study of outcomes between pollicization and microsurgical second toe-metatarsal bone transfer for congenital radial deficiency with hypoplastic thumb. *J Recon Microsurg*. 2013;29:587–592.
- Bayne LG. Ulnar club hand (ulnar deficiencies). In: Green DP, ed. *Operative Hand Surgery*. New York: Churchill Livingstone; 1982:245–257.
- Havenhill TG, Manske PR, Patel A, et al. Type 0 ulnar longitudinal deficiency. *J Hand Surg Am*. 2005;30:1288–1293.
- Cole RJ, Manske PR. Classification of ulnar deficiency according to the thumb and first web. *J Hand Surg Am*. 1997;22:479–488.
- Kosher RA, Savage MP, Chan SC. In vitro studies on the morphogenesis and differentiation of the mesoderm adjacent to the apical ectodermal ridge of the embryonic chick limb-bud. *J Embryol Exp Morphol*. 1979;50:7–97.
- Ogino T. Teratogenic relationship between polydactyly, syndactyly, and cleft hand. *J Hand Surg [Br]*. 1990;15:201–209. *This is a landmark reference as the author showed that in an animal model he could create either polysyndactyly or cleft hand using the same teratogen given at the same time during fetal development. Further, an excellent explanation is given that explains how this can occur.*

46. Manske PR, Halikis MN. Surgical classification of central deficiency according to the thumb web. *J Hand Surg Am.* 1995;20:687–697. *Classification of central deficiency with its surgical implications.*
47. Flatt AE. *The Care of Congenital Hand Anomalies.* 2nd ed. St. Louis, MO: Quality Medical Publishing; 1994.
48. Snow J, Littler J. *Surgical treatment of cleft hand.* In: Transactions of the Society of Plastic and Reconstructive Surgery: 4th Congress in Rome. Amsterdam: Excerpta Medica Foundation; 1967:888–893.
49. Miura T, Komada T. Simple method for reconstruction of the cleft hand with an adducted thumb. *Plast Reconstr Surg.* 1979;64:65–67.
50. Upton J, Taghinia A. Correction of the typical cleft hand. *J Hand Surg Am.* 2010;35:480–485.
51. Knight JB, Pritsch T, Ezaki M, Oishi SN. Unilateral congenital terminal finger absences: a condition that differs from symbrachydactyly. *J Hand Surg Am.* 2012;37(1):124–129.
52. Ogino T, Minami A, Kato H. Clinical features and roentgenograms of symbrachydactyly. *J Hand Surg [Br].* 1989;14:303–306.
53. Gretsche KE, Lather HD, Peddada KV, et al. Development of novel 3D-printed robotic prosthetic for transradial amputees. *Prosthet Orthot Int.* 2016;40:400–403.
54. Aker J, Block RI, Biddle C. Anesthesia and the developing brain. *AANA J.* 2015;83:139–147.
55. Cavallo AV, Smith PJ, Morley S, et al. Non-vascularised free toe phalanx transfers in congenital hand deformities – the Great Ormond Street experience. *J Hand Surg [Br].* 2003;28:520–527.
56. Tonkin MA, Deva AK, Filan SL. Long term follow-up of composite non-vascularized toe phalanx transfers for aphalangia. *J Hand Surg [Br].* 2005;30:452–458.
57. Innocenti M, Delcroix L, Manfrini M, et al. Vascularized proximal fibular epiphyseal transfer for distal radial reconstruction. *J Bone Joint Surg Am.* 2004;86-A:1504–1511.
58. Datta D, Ibbotson V. Powered prosthetic hands in very young children. *Prosthet Orthot Int.* 1998;22:150–154.
59. Cheesborough JE, Smith LH, Kuiken TA, et al. Targeted muscle reinnervation and advanced prosthetic arms. *Semin Plast Surg.* 2015;29:62–72.
60. Weinand C, Gupta R, Weinberg E, et al. Toward regenerating a human thumb in situ. *Tissue Eng Part A.* 2009;15:2605–2615.

Congenital hand III: Thumb hypoplasia

Amir Taghinia and Joseph Upton III

Access video content for this chapter online at expertconsult.com 

SYNOPSIS

- The thumb ray is the prime ray of the hand – its size, position, mobility, independence, and relations to the other digits are critical to function.
- The thumb is considered hypoplastic if any portion of the ray, skeletal or soft tissue, is deficient or absent.
- Growth and function of the thumb in the first year of life follows a predictable pattern.
- Although new procedures have expanded options for reconstruction, standard procedures such as first webspace deepening, tendon transfers, and collateral ligament reconstruction remain the best options for treatment.
- Pollicization continues to be the treatment of choice for severe hypoplasia with a non-functional carpometacarpal joint, the floating thumb, or the absent thumb.
- Associated conditions of thumb hyperplasia include VACTERL, Fanconi anemia and other hematologic abnormalities, Holt–Oram syndrome, and thrombocytopenia absent radius (TAR) syndrome.



Access the Historical perspective section online at

<http://www.expertconsult.com>

Introduction

The hypoplastic thumb represents a wide spectrum of functional and aesthetic differences. Before classification and management of the deficient thumb, a careful surgeon must assess its: (1) size; (2) position; (3) relation to other fingers of the hand; (4) osseous components; (5) joint integrity and stability; (6) intrinsic and extrinsic musculotendinous units; (7) first webspace depth and width; (8) associated malformations of the hand and elsewhere; and (9) functional consequences for the child. A thumb should be considered hypoplastic when

there is a deficiency of any one or all structures that contribute to the “normal” thumb. In the past, all definitions were restricted to the radiographic appearance alone; however, presently, we understand that soft-tissue deficiencies also contribute to the overall diagnosis.

For the first 3 months of life, the thumb is adducted and flexed within the palm and serves primarily as a pacifier. However, by 9 months of age, this first ray gains its independence and mobility from the palm, and at 1 year of age, it has become a crucial portion of the hand.¹⁵ In the normal hand, the strength and mobility needed for a wide variety of pinch and grasp functions rapidly develop, and by the time the baby is ambulatory, the thumb is used creatively and independently to manipulate the environment.

As relied upon in the past, a complete evaluation of the osteoarticular column will require plain radiographs. Normal primary ossification centers of the phalanges and metacarpal of the thumb appear in the second to fourth fetal months, but abnormalities of the skeleton of the thumb (e.g., triangular or trapezoidal bones) may not be seen radiographically until well into the first or second year of life. Secondary ossification centers within the epiphyses of the thumb normally appear between 13 months to 4 years of age.¹⁶ The delayed appearance of both primary and secondary ossification centers in the hypoplastic thumb is highly relevant to the diagnostic process because their appearance is often delayed in proportion to the degree of hypoplasia.

Basic science/disease process

Incidence

The true incidence of thumb hypoplasia is difficult to determine due to the large number of congenital malformations within which a hypoplastic thumb is a component part. All reported reviews are subject to study of the genetic composition of the patient population as well as any discrepancies of nomenclature and sampling. Entin^{17,18} reported a 16%

Historical perspective

The history of thumb reconstruction mirrors the development of hand surgery as a subspecialty. As such, advances in diagnosis, classification, and treatment of these conditions are relatively new – having occurred in the past 6 decades. Because many children with thumb anomalies have more serious conditions, advances in anesthesia also had to take place to make surgery safer and more predictable.

In terms of diagnosis and classification, Flatt stressed function potential and designated the digits as “adequate” or “inadequate”^{1,2}; Bayne relied upon localized positions of deficiencies³; and three generations of German authors referred to the degree of skeletal hypoplasia.^{4–6} The system proposed by Blauth recognizes the progressive degree of hypoplasia from a slight size discrepancy, with all normal structures present, to total aplasia of the thumb. In time, this

system has been amended by others,^{7,8} who subdivided type III (severe hypoplasia) into two groups – those with an intact carpometacarpal (CMC) joint (IIIA) and those without (IIIB) – and is very important in terms of management. Recently, Tonkin wrote a thorough summary of the grading systems, clarifying the definitions of grades of thumb hypoplasia, and proposing a modification of the Blauth classification.⁹

Progress in the treatment of thumb hypoplasia mirrored advances in diagnosis and classification. Working independently in Europe, Gosset¹⁰ and Hilgenfeldt¹¹ developed the procedure of digital transposition for post-traumatic thumb losses. In the decades following World War II, Bunnell described similar digital transpositions.¹² Littler¹³ refined their techniques and applied them to congenital differences. Following the thalidomide crisis in Europe, Buck-Gramcko¹⁴ amassed a large clinical experience and set present day standards for pollicization.

incidence of thumb hypoplasia in his Canadian patients, while Flatt published an 11.2% incidence of thumb abnormalities and a 3.6% incidence of thumb hypoplasia or aplasia from his clinic in Iowa.² We have seen a 37% incidence within our entire registry, which includes many additional categories.¹⁹ The majority of the children treated surgically are those with radial dysplasia – with and without a partial or complete absence of the radius. We have also seen a high incidence in syndromic patients, such as those with the Apert syndrome, who are commonly referred to large children's hospitals for treatment of their multiple malformations. Other populations include those with constriction ring syndrome (CRS), cleft hands, and symbrachydactyly hands, all of whom may have some degree of thumb hypoplasia.

Etiology

Because radial or preaxial longitudinal deficiencies occur in many conditions with a wide variety of etiologies, the causes for these malformations span the entire spectrum of genetic, environmental, teratogenic, and other factors (Table 27.1).²⁰ Therefore, consultation with a genetic specialist is strongly recommended, and referral to standard genetic textbooks or the Online Mendelian Inheritance in Man (OMIM) website (<http://www.ncbi.nlm.nih.gov/omim>) is a must for any pediatric hand surgeon.

Associated conditions

The many potential associations with thumb and radial hypoplasias and aplasia may involve any organ system within the body. Most significant are those with cardiovascular, gastrointestinal, and genitourinary involvement. Associated hematologic problems, specifically Fanconi anemia, can be detected early but usually become clinically apparent later in childhood. The most common of these associated conditions is outlined herein.

VACTERL

These children may have a wide spectrum of anomalies, including: Vertebral malformations; Anal atresia or hypoplasias; Cardiovascular anomalies; all degrees of Tracheoesophageal fistuli; Esophageal atresia; Renal malformations, and Limb abnormalities – which in the upper extremity involve all degrees of radial dysplasia. A patient does not need to fulfill every category on this list to be considered VACTERL.

Fanconi anemia and other hematologic abnormalities²¹

Children with Fanconi anemia (FA) develop different degrees of pancytopenia, the most extreme of which can be life threatening.^{22,23} Most of these children are small with growth restriction. Although many other organ systems may be abnormal, deficiencies of the thumb and, to a lesser extent, the entire radial ray are the most common and are present at birth in over half of these cases. Although in the past FA children were rarely diagnosed early in life, this condition can be diagnosed any time with a diepoxybutane (DEB) test.^{22,24} Recently, Webb, *et al.*²⁵ looked at the incidence of Fanconi anemia in children with congenital thumb anomalies referred for DEB testing in a tertiary care pediatric center, and found that of 81 patients

Table 27.1 'Thumb/radial hypoplasia/aplasia/dysplasia associations'

Frequent in	Occasional in
Thumb^a/radial^b hypoplasia/aplasia	
Aase syndrome ^{a,b}	Cat-eye syndrome ^b
Baller–Gerold syndrome ^{a,b}	de Lange syndrome ^{a,b}
Facio-auriculo-vertebral spectrum ^a	Fetal aminopterin effects ^a
Fanconi syndrome ^{a,b}	Fetal: valproate effects ^a
Holt–Oram syndrome ^{a,b}	Fibrodysplasia ossificans
Levy–Hollister syndrome ^{a,b}	progressive ^a
Nager syndrome ^a	MURCS association ^a
Radial aplasia–thrombocytopenia	Nager syndrome ^b
(TAR) Syndrome ^{a,b}	Seckel syndrome ^b
Roberts–SC phocomelia syndrome ^{a,b}	Trisomy 13 syndrome ^b
Rothmund–Thomson syndrome ^a	Trisomy 18 syndrome ^b
Townes syndrome ^a	
VACTERL association ^{a,b}	
13q-syndrome ^a	
EEC syndrome	
Metacarpal hypoplasia – first,^c all^d	
CHILD syndrome ^d	de Lange syndrome ^c
Coffin–Siris syndrome ^d	Larsen syndrome ^d
Cohen syndrome ^d	Robinow syndrome ^d
Diastrophic dysplasia ^c	Triploidy syndrome ^c
Dyggve–Melchior–Clausen syndrome ^c	
Grebe syndrome ^d	
Oro-palato-digital syndrome, type II ^d	
Partial trisomy 10q syndrome ^c	
Poland anomaly ^d	
Ruvalcaba syndrome ^d	
Short rib–polydactyly, Majewski type ^d	
Short rib–polydactyly, non-Majewski type ^d	
Tricho-rhino-phalangeal syndrome ^d	
Trisomy 9p syndrome ^d	
5p-syndrome ^d	
18q-syndrome ^d	
Broad thumb	
Apert syndrome	Robinow syndrome
Carpenter syndrome	Trisomy 13 syndrome
Pfeiffer syndrome	
Rubinstein–Taybi syndrome	
Saethre–Chotzen syndrome	

^{a,b,c,d}Refers to the hypoplasia/aplasia associations of the listed syndromes. For example, Aase syndrome has both thumb and radial hypoplasia but Nager syndrome has just thumb hypoplasia.

(Data from Jones KL. *Smith's Recognizable Patterns of Human Malformations*, 5th edn. Philadelphia, PA: WB Saunders; 1997; and Rayan G, Upton J. *Congenital Hand Anomalies and Associated Syndromes*. Berlin: Springer-Verlag; 2014.)

with thumb anomalies who underwent testing, six had a positive test (7%). The authors noted that patients with thumb hypoplasia *and* other associated conditions such as café-au-lait spots and short stature appear to be at increased risk of FA. Treatment of FA children with oxymetholone and prednisone therapy has a 70% response rate, and non-responders can be treated with bone marrow transplantation.²² In 40

years, the senior author has treated four children who died prematurely as a result of Fanconi anemia – children who could have potentially benefited from life-saving bone marrow transplant if the diagnosis was made early.

Clinical tips

Fanconi anemia

The low incidence of Fanconi anemia should be balanced against the life-threatening consequences of a missed diagnosis to guide testing in the current healthcare environment. The DEB tests costs between \$1000 and \$1200. The hematologists at our center have noted that all patients with Fanconi anemia have high mean corpuscular volume (MCV) on routine blood testing. Accordingly, one could consider DEB testing only in those patients with thumb hypoplasia who have high MCV and another clinical finding on examination (as noted above). Additional data is needed to lend credence to this consideration.

Holt–Oram syndrome

Two pediatricians, Dr. Holt in Philadelphia and Dr. Oram in London, independently described the association of congenital heart disease and radial longitudinal defects of the upper limb, and their names have subsequently been associated with all degrees of congenital cardiovascular malformations and radial dysplasia. Interestingly, there is no correlation between the severity of the anatomic deficiency in one system relative to the other. Common to the upper limbs are a stiff hypoplastic thumb joined to a stiff index digit by a complete simple syndactyly, radial deficiencies, and proximal radioulnar synostoses. Often, hypoplasia of the glenohumeral joint is not diagnosed until adolescence when shoulder abduction is diminished.

Thrombocytopenia absent radius syndrome (TAR)

This unique group of children may be born with normal hematologic parameters, but they usually have a low platelet count, which may decrease rapidly during the first year of life. They are easily distinguished from children with other types of radial dysplasia due to the presence of a thumb despite all degrees of radial deficiencies. The thumb is hypoplastic, and extrinsic flexion and extension vary tremendously. Thenar intrinsic muscles are usually present and provide some palmar abduction by age 2 years of age. The low platelet count commonly reaches normal levels by ages 4–5 years, and the clinical results from centralization are among the best.

Diagnosis and patient presentation

Classification

The varying degrees of differences between hypoplastic thumbs have been classified in a number of ways that have few common characteristics. Nevertheless, a well-accepted classification system has emerged that guides treatment. The



Fig. 27.1 Thumb hypoplasia. Molds of the right hand in six children with the five classic types of thumb hypoplasia are displayed. Type III has been subclassified into two categories: one with an intact carpometacarpal (CMC) joint (IIIA) and one without an intact CMC joint (IIIB). The type IV is often called the *pouce flottant* or floating thumb.

five designated types of thumb hypoplasia–aplasia are shown in Fig. 27.1. These anomalies are commonly associated with radial (preaxial) dysplasia, and the majority of congenital hand surgeons consider most types of thumb hypoplasia with a normal radius as part of this spectrum. It is well recognized that there are concomitant soft-tissue anomalies that accompany the skeletal abnormalities. Since the correlation of soft-tissue and skeletal deficiencies has been so well defined, this refined system works very well for clinical decision-making.

The classification system proposed by Blauth⁵ continues to be the most commonly used. The modification proposed by Manske⁸ subdivides the type III thumb into those with stable carpometacarpal (CMC) joints and those with unstable CMC joints. This subdivision has significant implications for treatment, as the best reconstructive operation for the unstable CMC joint is index finger pollicization.

Hypoplasia of the thumb is associated with many other congenital differences, specifically central and transverse deficiencies. Because the anatomical make-up of the thumb does not always allow for easy categorization under the current system, we have included five additional categories,¹⁹ which include the constriction ring syndrome, central deficiencies, radial duplication, the five-fingered hand, and short skeletal rays. In these conditions, the thumb ray usually has characteristic deficiencies that would fall into the German type II and III hypoplasia categories^{5,26} and the anatomical abnormalities relevant to clinical decision-making will be presented here.

Clinical presentation (types of hypoplasia)

In the past, routine radiographs were the sole tool used for diagnosis of the hypoplastic thumb. However, this mode of assessment did not reveal any detail about the normal and abnormal soft-tissue structures of individual hands. Therefore, surgeons today use a more complete analysis of intrinsic muscles, webspace size, intrinsic muscles, extrinsic tendons, joint stability, and function – all of which impact directly upon treatment. It is difficult to adequately classify a hypoplastic thumb in a newborn infant. The authors have found it best to wait until the child is about 1 year of age, at which time physical characteristics and functional use are the main determinants of classification.

Clinical tips

Evaluating MP joint laxity

It is often quite difficult to differentiate between a normal and a lax metacarpophalangeal joint in an infant with thumb hypoplasia. Whereas absence of thenar musculature and a diminutive webspace are usually obvious, the MP joint is quite elastic and floppy in many normal infants. The authors have found that it is best to wait until the child is older to fully evaluate the MP joint. Functional observation of the older child can be as valuable a tool as physical examination. An older infant or younger toddler who can grasp a large object (such as a flashlight) in one hand using the thumb likely has a stable MP joint. Another who uses the thumb metacarpal head to stabilize the object likely has too much laxity and will need reconstruction.

Type I: mild hypoplasia

In this most mild type of hypoplasia, the thumb is slender and slightly shorter than a normally configured first ray (Fig. 27.2). The phalanges and metacarpal can be slightly thinner than usual, but the trapezium and scaphoid are present and the distal radius and styloid process are not affected. The interphalangeal (IP), metacarpophalangeal (MP), and CMC joints are stable and exhibit normal passive and active motion. While there may be a slight hypoplasia and weakness of the abductor pollicis brevis (AbPB), opponens pollicis (OP), and lateral head of the flexor pollicis brevis (FPB) muscles, all intrinsic muscles are present.²⁶ The joints, ligament and capsules, tendons, nerves, and vascular structures are all normal, and there may be minimal narrowing of the first webspace.



Type I

Fig. 27.2 Type I thumb hypoplasia – mild. (A) The skeletal ray is well segmented and may be short. All intrinsic muscles and extrinsic tendons are intact. First webspace narrowing is minimal to moderate. (B) Clinical appearance and (C) radiograph of a child who did not require any surgical correction. Although his thenar muscles are weak, there were no significant functional problems.

Type II: moderate hypoplasia

The metacarpal and phalanges are all present but small, and the trapezium, trapezoid, scaphoid, and – to a lesser extent – lunate may be hypoplastic. The first webspace is short with the thumb adducted, the ulnar collateral ligament at the MP joint lax, and median innervated thenar muscles underdeveloped or occasionally absent (Fig. 27.3).²⁷ Normally, the flexor pollicis brevis (FPB) and opponens pollicis (OP) are innervated by the median nerve, but the FPB varies, reported to be 40% median, 48% ulnar, and 12% both median and ulnar.²⁸ The ulnar innervated intrinsics, particularly the adductor pollicis (AddP), pull the metacarpal into adduction and

narrow the first webspace, which, when explored surgically, has tight fibrous bands between muscle groups. Type II thumbs contain two neurovascular bundles, and the recurrent motor branch of the median nerve is consistently found.

Many different muscle and tendon anomalies seen on the radial side of the hand have been identified in conjunction with the type II and IIIA thumbs. In fact, the clinical designation of a given thumb may vary greatly due to this large spectrum of soft-tissue abnormalities. The absence of IP or MP flexion or extension creases in a slender thumb is the best clinical indicator of flexor and/or extensor abnormalities. Within this designation, many variations of the long flexor to the thumb (flexor pollicis longus; FPL) may be found. Both




Fig. 27.3 Type II thumb hypoplasia – moderate. **(A)** There is minimal to moderate shortening of the skeletal ray. All bones are present and ligaments at the metacarpophalangeal (MP) joint may be lax. The ulnar innervated intrinsic muscles, adductor pollicis and first dorsal interosseous (second metacarpal origin) are strong, and the median innervated intrinsics are very weak. Anomalous anatomy is common. Adduction contractures from fibrous structures and MP joint instability accompany a deficient first webspace. **(B)** Clinical appearance and radiograph of a child with a type II hypoplasia of the right hand. The thenar intrinsic muscles are hypoplastic, the first webspace tight, and the thumb much narrower than normal. Key pinch was weak, and the patient could not hold heavy objects between the thumb and digits. In addition, the ulnar collateral ligament was weak at the MP joint.

the tendon and the muscle belly of the FPL may be abnormal,²⁹ may have proximal duplications,³⁰⁻³⁴ and may have a more radial distal insertion.³¹ In some patients, one can observe this muscle originating from the index profundus tendon,³¹ the transverse carpal ligament, or the fascia of the thenar intrinsics and inserting into the flexor sheath³⁰ and/or the extensor mechanism.³⁵ In other cases, this muscle may be absent entirely.³⁶⁻⁴⁰ Some of these anomalies may represent abnormal radial wrist extensors or short thumb abductors instead of malformed or malpositioned terminal thumb flexors.⁴¹ Occasionally, a small abnormal “musculus lumbricalis pollicis” muscle may extend from the thumb origin across the first webpace and attach to the flexor system of the index finger.⁴² We have seen this peculiar (atavistic) muscle extending across the first webpace in children with the Freeman-Sheldon syndrome and in complex thumb duplications at the metacarpal level.

The extrinsic extensors may have abnormal insertions,^{43,44} extend over the MP joint in a non-centralized position, and reveal abnormal connections with the extrinsic flexor.^{33,35,42,45} These abnormal insertions of both flexor and extensors, combined with their deviated course, conspire to make both tendons act primarily as radial deviators and not primary flexors or extensors. This deviation is further accentuated by the lax ulnar collateral ligament at the MP joint, resulting in more deviation. Tupper⁴⁵ has called this “pollex abductus” and noted that when these muscles contract, there is no IP flexion or extension, only abduction or radial deviation of the thumb. Many anatomical variations of this structure exist, but the functional result is the same (Fig. 27.4). A recent paper by Graham *et al.*³³ has summarized the large list of muscle and tendon abnormalities that often originate in the forearm. Although type II thumbs may present with these intratendinous connections, the abducted posture and wide degree of muscle and tendon anomalies are primarily seen with type IIIA thumbs (see Fig. 27.4). When followed proximally to the wrist and forearm level, many of these tendons have abnormal origins and long muscle bellies that extend well beyond the wrist into the metacarpal region.

Type III: severe hypoplasia

In these cases, the degree of skeletal shortening and narrowing is much more pronounced, particularly at the metacarpal level (Figs. 27.5 & 27.6). The hand and wrist may be radially deviated due to hypoplastic/aplastic carpal bones. The trapezium is usually very small, and frequently the scaphoid is absent. The distal radius is smaller in size and the styloid process absent, giving the radius a blunted appearance.⁴⁶ The extreme amount of anatomic variation within this group prompted Manske and colleagues to subdivide this group into type IIIA with a full-length metacarpal and an intact CMC joint and type IIIB with a tapered first metacarpal and no CMC joint.⁸ Buck-Gramcko has included an additional variation called type IIIC thumb, which possesses only the metacarpal.⁴⁷ There are no tendons or muscles in this variant, and the skin bridge is much wider than that seen in type IV. In the B and C variants, a fibrous band may connect the hypoplastic metacarpal to a cartilaginous nubbin that represents either a trapezium or metacarpal base. Often, a small abductor pollicis tendon attaches to this remnant.

Median innervated intrinsic muscles are either severely hypoplastic or absent entirely; however, if they are present, they may actively flex the MP joint. The ulnar innervated AddP pulls the metacarpal medially. The MP joint is lax on both radial and ulnar sides and anatomically either collateral ligament and the volar plate may be severely hypoplastic or missing. The small thumb with a short webpace is abducted at the MP joint due to the frequent pollex abductus deformity. The radial origin of the first dorsal interosseous from the thumb metacarpal is more severely affected than that from the index metacarpal. In the forearm, radial head is usually hypoplastic and commonly subluxed, occasionally dislocated.

Abnormal anatomy is the rule. The many intrinsic and extrinsic anatomical variations described within the type II group may exist with greater degrees of hypoplasia. Usually, the extrinsic flexor and extensor are present and weak, but in some cases they may be missing.^{36,40,43} The flexor retinaculum is poorly developed with either attenuation or absence of the major pulleys. In some patients, the motor branch of the median nerve is absent, and there may only be one neurovascular bundle.³¹ The radial origin of the first dorsal interosseous to the index finger is severely hypoplastic, and the first web-space is severely restricted. Pollex abductus anomalies are common and must be recognized and corrected if IP flexion and/or extension is to be achieved.

Type IV: floating thumb

These thumbs (*pouce flottant*, French; *pendeldaumen*, German) arise distally from the palm and usually lie along the radial midaxial border (Fig. 27.7). They are attached only by a soft-tissue pedicle, which has been described by Littler as “Nature’s own neurovascular pedicle”, due to the presence of a digital artery, two vena comitantes, and one or two nerves within the skin bridge.^{48,49} There may be anomalous vascular or neural rings, involving neurovascular structures¹⁵ that could affect the outcome of a pollicization. There is no metacarpal, and two small phalanges tend to be present within the soft-tissue envelope, which contains a nail. It is important to note that a diminutive nail represents the presence of a distal phalanx. Intrinsic muscles do not insert onto these bones. A first dorsal interosseous muscle (abductor indicis) may be detected by abduction of the index finger. At the carpal level, the trapezium and less often the scaphoid are missing. The radial styloid may be absent, but the distal end of the radius is normal in most of these children.

Clinical tips

Aesthetic augmentation

The *pouce flottant* in type IV or the ablated thumb in type IIIB thumbs can be used for additional bulk in the thenar area. The technique is easy and improves appearance in these deficient hands. The part is stripped of skin, nail, and skeletal elements and rendered a vascularized adipofascial flap based on its original blood supply. It is then transposed into the thenar area at the conclusion of the procedure for additional bulk.⁴⁹






Fig. 27.4 Pollex abductus. **(A)** In severe type II and many type III thumbs, there may be very little, if any, interphalangeal joint flexion and there may be a radial deviation of the thumb at the metacarpophalangeal (MP) joint. This is due to the abduction force created by the combined action of the extrinsic flexor and extensor tendons joined by intertendinous connections, the "pollex abductus". **(B–E)** Within types II and III thumb hypoplasias (and proximal thumb polydactylies), a very wide spectrum of intratendinous connections may vary between a wide, loose, almost areolar band (top) to a complete coalition the flexor and extensor into a single tendon. With excursion from either the flexor or extensor side, the resultant movement in all these thumbs is abduction of the MP joint.




Fig. 27.5 Type IIIA thumb hypoplasia – severe. (A) These thumbs exhibit more severe skeletal hypoplasia, including the carpal bones. Median nerve innervated thumb intrinsic muscles are severely hypoplastic or absent, and the ulnar-innervated muscles are present but weak. Extrinsic tendons are abnormal, the “pollex abductus” deformity is frequent, the first webspace is small, and the metacarpophalangeal (MP) joint is unstable (more on the ulnar than the radial sides). The carpometacarpal (CMC) joint and thumb metacarpal are intact in IIIA thumbs. (B–E) The clinical appearance and radiograph show a short slender metacarpal, an intact CMC joint, severe hypoplasia of the thenar eminence, and a lax MP joint. The absent interphalangeal flexion crease is indicative of a deficient or absent flexor pollicis longus.

Type V: aplasia

The thumb is completely absent in this category (Fig. 27.8). In half of our patients⁵⁰ and half those reported by Platt,⁵¹ there is an associated deficiency of the radius. When the radius is normal, the index digit is normal and has strong abduction at the MP joint due to the presence of a strong first dorsal interosseous muscle (e.g., abductor indicis muscle). Many of these children with a normal radius will demonstrate “auto-pollicization”.⁵⁰ The pulp of the index finger widens and the digit pronates and sits in a more abducted position resulting in a widening of the intermetacarpal space and attenuation of the intermetacarpal ligament. At best, this posture is a poor substitute for normal key pinch. In the case of a deficient radius, the index ray is stiffer, shorter, and often joined by a

simple syndactyly to the long digit. There is a direct correlation between the degree of radial hypoplasia and the index finger deficiencies; the index ray is never normal when there are significant associated radial deficiencies. In these hands, the degree of stiffness decreases from the radial to the ulnar digits and the fifth finger is always the best on the hand.

Type VI: central deficiencies – cleft hand and symbrachydactyly thumb

Cleft hand (typical)

Cleft hand is characterized by hypoplasia or aplasia of the central ray(s) of the hand thus forming a “V” or funnel-shaped cleft (Fig. 27.9). All degrees of simple syndactyly of the first




Fig. 27.6 Type IIIB thumb hypoplasia – severe. **(A)** The median-innervated thenar intrinsic muscles are absent entirely. There is severe hypoplasia of the adductor pollicis muscle, flexor pollicis brevis – lateral head, and the ulnar origin of the first dorsal interosseous. The carpometacarpal joint articulation of the proximal metacarpal is absent. The metacarpophalangeal joint is very lax or absent on both radial and ulnar sides. Flexor and extensor extrinsic tendons are severely hypoplastic or absent. **(B,D)** Clinical appearance and **(C)** radiograph shows a 4-year-old patient with a well formed but functionless floppy thumb. There is no skeletal stability or extrinsic flexion or extension. Very small flexor or extensor tendons may be present and can result in some movement.

web are seen, resulting in moderate to severe deficiencies of the first webspace. In addition, all degrees of hypoplasia, extending to aplasia of the central two rays, may exist.^{7,8} The ulnar two digits in the ring and fifth positions are commonly webbed with simple syndactylies. The thumb in the cleft hand anomaly is usually slightly small with all components of the osteoarticular skeleton present. A Blauth type II thumb classification would be appropriate for the strict constructionist.²⁶ The wrist and forearm bones are normal, and the median innervated thenar intrinsics are present. The major deficiency of the thumb in this form of hypoplasia is that the ulnar innervated intrinsic muscles are severely hypoplastic or absent. In particular, the ulnar innervated adductor pollicis is

usually severely hypoplastic or absent, and the first dorsal interosseous is moderately hypoplastic and contracted. The presence or absence of the third metacarpal is often an excellent indicator of the status of the AddP muscle. Finally, the extrinsic flexor and extensor musculotendinous units to the thumb tend to be unaffected. [Fig. 27.9](#) appears online only.

In another variation of typical cleft hand, thumb polydactylies at all levels may be observed. The more distal type I and II polydactylies⁵² are often associated with the absence of index phalanges that have an intact metacarpal. Super digits and transversely oriented tubular bones at the distal metacarpal level with complete absence of the index (and long) digits are often seen in this variation.⁵³ With more proximal type III,

VI A Typical cleft hand thumb




Fig. 27.9 Thumb in typical cleft hand. **(A)** Three layers of median innervated intrinsic muscles are present in most typical cleft hands. Commonly, the index ray is joined to the thumb by a simple syndactyly. All degrees of absence of the long rays may present. The first dorsal interosseous is present and tight, and the degree of adductor pollicis hypoplasia is proportional to the amount of the third metacarpal present. A very small adductor pollicis is illustrated here. **(B)** A sampling of molds shows the wide variation in the size and depth of the central clefting. The thumbs are smaller than normal, and the longer thumbs with flexion contractures are triphalangeal.

Type IV




Fig. 27.7 Type IV thumb hypoplasia – floating thumb. **(A)** The hypoplastic thumb is attached to the hand only by a soft-tissue bridge, which contains neurovascular structures and rarely hypoplastic tendons and fascia. There is no skeletal connection. **(B,C)** The attached thumb is small with diminutive phalanges and a nail. There is no active flexion or extension. The radial deviation of the wrist and hand is due to hypoplasia of the trapezium, scaphoid and lunate.

IV and V polydactylies, the central (third) ray is often severely hypoplastic or absent.^{54,55} Triphalangeal rays may also be encountered with the proximal duplications at the metacarpal level.

Symbrachydactyly thumb

Most refer to these atypical cleft hands as symbrachydactyly (Fig. 27.10). This form of deficiency is always unilateral, with varying degrees of hypoplasia of the central three rays of the hand. Nubbins with minute nail complexes may be present on the distal border of the palm, representing the index, long, and ring fingers, but commonly these central three digits are completely absent with varying degrees of hypoplasia of the central three metacarpals. Fig. 27.10 appears online only.

All degrees of variation exist, and no two hands are identical. The thumb in this condition is invariably smaller with severe hypoplasia or aplasia of the phalangeal components. Occasionally, a metacarpal and distal phalanx are present with a flail thumb at the MP joint level. With an intact third metacarpal, a functional adductor pollicis muscle is often present. Most of these thumbs have very weak adduction power. Usually, the median innervated thenar intrinsic muscles are intact and range from small to normal in size. The thumb CMC joint is well segmented and mobile, and the IP joint of the thumb may exhibit decreased passive and active motion due to weak extrinsic flexor and extensors. Upon exploration, the FPL tendon often courses to a hypoplastic or absent muscle belly in the distal forearm. In the severely hypoplastic thumb, there is marked limitation of MP and CMC motion, an absent IP flexion crease, and only a rudimentary FPL tendon. The anomalies seen with the extrinsic flexors and extensors are similar to those described for the types II and IIIA hypoplastic thumbs. The fifth ray is usually the best in the hand with intact intrinsic and

extrinsic musculotendinous units. Frequently, this digit has a radial clinodactyly and a completely unstable MP joint, and the entire hand is hypoplastic. Radius and ulna are present and of equal length but may be small in comparison to the opposite limb.

Type VII: constriction ring syndrome

Constriction ring syndrome (amniotic band sequence, Street-er's dysplasia, fenestrated syndactyly, acrosyndactyly) is a condition that can affect one or all limbs and less commonly the face. As defined by Patterson,⁵⁶ limb involvement can result in any of the following deformities: (1) simple constriction rings, which may be partial or circumferential; (2) constriction rings with distal deformity, with or without concomitant lymphedema; (3) acrosyndactyly (distal fusion, fenestrated syndactyly); or (5) amputation(s) (Fig. 27.11). Fig. 27.11 appears online only.

Hypoplasia of the thumb is seen in this condition when there is a deficiency in the length of the thumb, which may have a transverse failure of formation at any level. Occasionally, the existing skeletal and soft-tissue components of the first ray may be hypoplastic. The hallmark of the amniotic band sequence is that the anatomy proximal to the level of amputation or level of congenital amputation is normal. Superficial or deep rings around the thumb can be associated with hypoplasia or lymphedema of the distal segment of the digit that contains hypoplastic nail remnants and slender, truncated phalanges. Acrosyndactyly (*acros*: peak, Greek) usually involves the central three rays of the hand but can also involve the thumb and fifth digit. Thumb amputation may occur at any level. The most practical way to classify these losses is at one of three levels: (1) distal to IP joint; (2) proximal phalanx, and (3) metacarpal (see Fig. 27.11). Motion of the IP joint is usually severely affected – even with amputations or deep constriction rings distal to it.

VI B Symbrachydactyly thumb




Fig. 27.10 Symbrachydactyly thumb (atypical cleft). **(A)** The border thumb and fifth rays are the most complete in the hand. Thenar and hypothenar muscles are present and often small. Central digits are represented by hypoplastic nubbins. There are all degrees of metacarpal hypoplasia within the central three rays of the hand. Extrinsic flexors and extensors are present but abnormal. **(B)** A very wide range of variation is present in these hands.




Fig. 27.11 Constriction ring syndrome thumbs. **(A)** The thumb in these hands may present with a shallow or deep constriction ring or an amputation at any level along the skeletal ray. The phalanges at the level of loss are characteristically narrow and taper to the distal stump. **(B)** The intrinsic muscles are all present up to the level of the amputation. The proximal anatomy in this condition is normal. **(C)** The thumb is absent on the left and shows increasing length in these molds. No two hands are identical. There is great variation in the depth and location of constriction rings along the digits.




Fig. 27.8 Type V thumb hypoplasia/aplasia. (A–C) With complete aplasia, no thumb structures are present. In approximately half of these patients, the radius is normal. The trapezium, trapezoid, and scaphoid are often hypoplastic and a strong first dorsal interosseous (abductor indicis) pulls the index digit in abduction and in as much pronation as the intermetacarpal ligament will allow. (D–F) Index digits, which are not abducted, are often stiff at the interphalangeal joints and are commonly associated with some degree of radial hypoplasia or aplasia. The amount of stiffness decreases from radial to ulnar digits. Accordingly, the ring and small fingers are always the most functional components of these hands.

Type VIII: five-fingered hand

In this type of hypoplasia, the thumb is smaller in width and longer in length and has the characteristics of a finger. As the radial border digit, it lies in the same plane as the ulnar four digits and is non-opposable. It is usually the same length as the adjacent index finger. The digit is slender and may be joined to the index finger in an incomplete simple syndactyly. A severe deficiency or nonexistent first web is often present, and some type of transverse metacarpal ligament is also

present. The skeletal anatomy is similar to that of the index ray: a metacarpal with a distal growth center and three phalanges with proximal growth centers. The scaphoid is usually absent or hypoplastic. The thenar musculature (AbPB, FPB, OP muscles) are also absent as is the AddP. Instead, the usual digital intrinsics are present – namely, a lumbrical, palmar, and dorsal interosseous (Fig. 27.12). The extrinsic flexors and extensors mimic those of the normal fingers. Because the radial digit lies in the same plane as the other fingers in the hand, manipulation of objects is usually performed by

utilizing lateral scissoring between the first two digits – or between the second and third if a first web syndactyly is present. Left untreated, those patients without a first web syndactyly tend to attenuate the transverse metacarpal ligament and “auto-pollicize” into an abducted and slightly pronated posture. [Fig. 27.12](#) appears online only.

We have seen variants of this condition in which hypoplastic thenar muscles are present with a metacarpal that has a proximal physis. These thumbs are triphalangeal and also contain a lumbrical muscle that originates from the flexor digitorum profundus (FDP) tendon.

Type IX: radial polydactyly

Despite the level of arborization, each partner thumb is hypoplastic to varying degrees, with the radial duplicate usually being the most severely affected. Rarely are Wassel type II, III, and IV partner thumbs of equal size and conformity. The complexity of the deformity and, therefore, the surgical correction increases as the level of the duplication progresses proximally. Associated triphalangia of the ulnar partner further complicates any surgical reconstruction. Specific abnormalities in each thumb are seen in the nail plate, the osteoarticular column, and both the intrinsic and extrinsic musculotendinous units. The nail plate of each partner is always more narrow than that of the unaffected thumb, and the entire skeletal ray is hypoplastic in all polydactylies proximal to the MP joint.

Musculotendinous abnormalities are common with the extrinsic extensor almost universally shared. Indeed, nearly half of the patients presented in papers on pollex abductus involve duplicate thumbs.^{42,45} Deviation of the partners toward each other indicates abnormal insertions of the extrinsic tendons into the distal phalanges, and connections between the extrinsic flexors and extensors are not unusual. These tendinous interconnections will limit function and cause digital angulations. The first web is usually unaffected in polydactylies involving the distal phalanx, but as the level of arborization lies more proximally, the first webspace becomes increasingly deficient and tight.

Type X: syndromic short skeletal thumb ray

Deficiencies of the osteoarticular column of the thumb may result in a short, hypoplastic thumb ([Fig. 27.13](#) ). Bony abnormalities can occur as isolated bone (brachymetacarpia, brachyphalangia), all bones in combination, or as part of a generalized syndrome, such as the acrocephalosyndactyly (e.g., Apert, Pfeiffer, Carpenter, etc.) syndromes or the Rubinstein-Taybi syndrome. Joint function is usually impaired on either side of the abnormal bone(s). In patients with anomalies of a single bone, brachymetacarpia, or brachyphalangia, the remaining components of the thumb tend to be unaffected, and in patients with generalized syndromes, other abnormalities of the thumb components are common. In the acrocephalosyndactyly (ACS) syndromes, delta phalanges are common. They usually involve the proximal phalanx with a longitudinal epiphyseal bracket on the radial side. This abnormal growth plate checks longitudinal growth on the radial side and results in radial clinodactyly of the thumb (“hitch hiker’s thumb”) – which becomes more severe over time. The metacarpal is usually short and the distal phalanx is short and

broad. Incidentally, many feel that the abnormal proximal phalanx and broad distal phalanx are variations of a polydactyly. Musculotendinous anomalies are associated with poor joint function but are not as common as those with type IIIA thumbs. Deficiencies of the first web are most common, occurring along a spectrum of mild adduction contracture to complex syndactyly involving the first two rays. [Fig. 27.13](#) appears online only.

The whole spectrum of patients with metabolic bone diseases, skeletal dysplasias, benign skeletal tumors, and many syndromes may include thumb hypoplasia. In general, very little surgical correction is required for these youngsters. The need for surgical improvement is determined by very critical observation of these children at play.²⁰

Patient selection

General considerations

The child with thumb hypoplasia may present many unique problems with both pinch (precision, pulp, key) and grasp (precision, span, power), despite his/her ability to adapt remarkably to the functional deficiency.⁵⁷ The ideal prerequisites for reconstruction of a functional thumb include^{19,58}:

1. A mobile, stable CMC joint with an intact metacarpal
2. A scar-free first webspace of adequate width and depth lined with full-thickness skin
3. Mobility in at least two of its three joints (CMC, MP, IP)
4. MP joint stability, particularly of the ulnar collateral ligament
5. Adequate motors for strong MP or IP flexion and extension
6. Capacity to be placed in a palmar abducted (i.e., opposition) position for pinch and grasp maneuvers.


All six of these components should be considered in any detailed analysis of the thumb.

Timing

As researchers and clinicians struggle with the possibilities of fetal surgery, many surgeons wonder if they should wait rather than performing reconstructive procedures of the congenitally different hand as soon as possible ([Fig. 27.14](#)). Early reconstruction of the hypoplastic or absent thumb is certainly attractive in an effort to allow the infant to adapt more rapidly with optimal cortical representation. This ideal needs to be tempered with the knowledge that a congenital hand difference is, in itself, not a life-threatening condition (but may be associated with one), and the surgeon can use time to allow the affected part to grow, to observe development, and to assess the functional needs. The construction of the thumb with a stable osteoarticular column of adequate length, mobile joints, growth potential, scar-free first web, and gliding muscle tendon units is not easily accomplished in very small hands – despite refined microvascular instruments and skills.

However, the arguments that are forwarded by the proponents of the early surgery persist. The most powerful arguments include anatomic, cognitive, and psychological factors. Anatomically, the release of tethered musculotendinous units

IX Five-fingered hand



(A)



(B)

Fig. 27.12 Five-fingered hand. **(A)** In the five-fingered hand, the normal complement of median innervated thenar intrinsic muscles are absent. First dorsal interosseous, volar interosseous, and lumbrical muscles are present in this ray, which anatomically is a digit, not a thumb. **(B)** The clinical appearance (preoperative) on the left shows that the patient has tried to flex and auto-pronate this ray to become a thumb.

X Short skeletal ray




Fig. 27.13 Type X short skeletal ray. **(A)** A short thumb with or without radial clinodactyly is seen in many syndromes. The primary osseous abnormalities are usually seen at the proximal phalangeal joint level. The median and ulnar innervated intrinsic muscles are all present and very hypertrophied. Extrinsic and intrinsic flexors and extensors are normal up to the phalangeal level. **(B)** The left thumbs of children with four different syndromes all look similar: (from left to right) Rubinstein-Taybi; Pfeiffer; Greig cephalopolysyndactyly; Apert acrocephalosyndactyly.



Fig. 27.14 Timing – plaster molds made of patients with type V hypoplasia made at ages (left to right): 32 weeks' gestation, 12 months and 8 years of age demonstrate the tremendous growth difference. Despite their discrepant sizes, the anatomy of these hands was remarkably similar with normal index active and passive range of motion. Any surgery on the hand on the left would be quite challenging.

and joint contractures will allow unrestricted growth, and physiological adaptation of the reconstructed thumb will occur secondary to growth and functional use. On a cognitive level, early surgery will allow the development of the child with a reconstructed thumb to occur prior to thumb corticalization, which takes place at around 18 months of age. Psychologically, correction will alleviate anxiety in the parents and, therefore, in the child.

These purported advantages should be weighed against risks that include: (1) growth-related complications; (2) functional need assessment, and (3) patient cooperation. Another risk that has been on the forefront of pediatric surgery recently remains the long-term cognitive effects of general anesthesia in early childhood and infancy. Although answers are not yet known, multi-center trials are in progress.

In slightly older patients, the affected thumb is larger so potential problems with osteotomies, alteration of growth, skeletal fixation, joint reconstruction, and potential for compromise of blood supply are reduced.⁵⁹ Also with an older patient, the surgeon is better able to accurately assess the functional needs of the child according to his or her interests, current adaptations, and lifestyle. Finally, an older child is potentially a more cooperative patient.

Surgical correction of the hypoplastic or absent thumb must be individualized. As these children may have other congenital anomalies, an early assessment of the upper limb deficiencies and a coordinated management plan can be formulated and instituted.

In the absence of other organ system complications, we try to perform pollicization when the child is between 12 and 18 months of age. Pollicization is often preceded by centralization of the hand and wrist between 5 and 8 months of age in those with radial longitudinal deficiency. The timing for

correction of type IIIB deformities may be problematic. Though pollicization is the procedure of choice, some parents and families simply will not allow it. We agree with other surgeons that the alternatives involve difficult reconstructions, often including one or more stages, and are wisely deferred until the child is aged 4–5 years, a time when the hand is larger and the patient may be more cooperative with the postoperative therapy regimen.^{33,60}

For thumbs that need reconstruction alone without pollicization, the authors feel that ligament reconstruction of a lax metacarpophalangeal joint should be deferred until the child is large enough so that bone tunnels can be made safely. This timing typically coincides to between 2 and 3 years of age.

Treatment

This section on treatment is divided into two parts: in the first part, treatment considerations will be outlined for each type of thumb hypoplasia, and in the second part, surgical techniques will be outlined in detail for each particular clinical problem.

Treatment considerations for thumb hypoplasia (types I–V)

Type I: mild hypoplasia

These children are not usually functionally impaired (see Fig. 27.2). In fact, many type I thumb hypoplasia patients, along with their parents, do not recognize anything abnormal about these hands. These thumbs are commonly found in patients who have a more severe radial dysplasia in the opposite upper limb. However, in this stronger limb, they have very little or no difficulty with key pinch, pulp-to-pulp pinch, opposition and grasping activities. Since functional problems are rare, surgical correction is not often needed. Occasionally, a child with a type I hypoplastic thumb will require a release of a mildly contracted web (see type II management). All web releases involve more than simple skin incisions. Careful attention⁶¹ must be directed to tight fascial bands within the webspace, anomalous tendon and muscle anatomy, and joint ankylosis. Of all the methods available, the four-flap Z-plasty provides the best contour and appearance (Fig. 27.15). Dorsal transposition flaps from the index finger^{36,62} and rotation flaps⁶¹ are effective but require skin grafting on the visible dorsal surface of the hand. Of course, any method must be carefully individualized to the patient.

Type II: moderate hypoplasia

Five specific problems in the type II thumbs must be addressed individually: (1) narrowed first webspace; (2) instability of the MP joint; (3) poor palmar abduction (opposition) for pinching and grasping; (4) lack of IP joint flexion, and (5) abduction posturing of the thumb ("pollex abductus") (see Figs. 27.3 & 27.4). In this type of hypoplasia, not all of these specific problems coexist. Usually, all that is needed to correct these thumbs is a release of the first webspace and stabilization of the MP joint, with or without a transfer for palmar abduction or opposition. When the surgeon encounters a pollex abductus deformity, she/he should next look for abnormalities of the




Fig. 27.15 First webspace release. **(A)** The skin markings have been made for a four-flap Z-plasty, which include two 90° incisions perpendicular to the tight web between the thumb and index finger. Each is then bisected at a 45° angle. **(B)** After the four separate flaps have been mobilized, reflected dense septal bands may be identified between the skin and muscle fascia, and larger fascial bands between the intrinsic muscle groups. **(C)** Incision and excision of these bands may require dissection to the carpometacarpal joint level. **(D)** Trimming and minor flap adjustments are always needed with the proper inset of the more mobile dorsal flaps with the more rigid palmar flaps. A skin redundancy on the radial side of the index finger has been eliminated with a straight extension. **(E)** The preoperative appearance is seen with a dorsal view. **(F)** The postoperative contour is shown from the palmar surface. This technique provides the best contour of all available methods of first web release.

flexor pollicis longus (FPL) muscle. A more detailed description of treatment options is presented later in this chapter.

Type IIIA: severe hypoplasia

Most hand surgeons agree that this variation should be reconstructed surgically (see Fig. 27.5). The five individual problems are the same as listed in type II, and the options and preferred solutions are listed below. Most authors opt to complete all necessary procedures including widening of the first webspace, stabilization of the MP joint, and some type of opposition transfer at one time. The major variable becomes the status of the flexor mechanism, which may require a staged approach. After 35 years of experience, our preference has been to replace the very anomalous flexor mechanism with a tendon transfer in the presence of at least one good pulley at the level of the metacarpal head. The treatment of the more deficient type IIIB and IIIC varieties constitutes one of the more interesting ongoing controversies in hand surgery.

Type IIIB, type IIIC: severe hypoplasia

For most hand surgeons in Europe, North America and South America, pollicization is the treatment of choice because a well-performed pollicization provides a much better and more predictable outcome than any alternative types of staged reconstruction (see Fig. 27.6).

However, cultural and parental beliefs may demand one of two alternatives – staged reconstructions with^{63–66} and without⁶⁷ a microvascular joint transfer, which have both become popular in the Asian countries. Osteoplastic thumb reconstruction has a long history.^{5,68–70} The osteoarticular column is connected with an intercalated bone graft between the index and hypoplastic thumb metacarpal (Fig. 27.16). Multiple stages are then needed to first stabilize MP and IP joints and construct pulleys. At that point, tendon transfers are performed for opposition as well as IP flexion and extension. The major disadvantages of this procedure include the lack of CMC mobility, lack of growth, poor motion, and the multiple stages required. Insensate abdominal pedicle flaps have been used to provide tissue for an adequate first webspace. Fig. 27.16 appears online only.

Another alternative is to transfer either the second^{67,71–74} or third⁷⁵ metatarsophalangeal joint in a hyperextended position to create a new CMC joint and proximal metacarpal. This composite joint must be harvested with a large dorsalis pedis pedicle, which provides venous drainage and adds bulk to the deficient thenar region. Tendon transfers are then performed to provide motion at either the MP or IP joints.

The management of these thumbs remains controversial. Without exception, most hand surgeons prefer a well-performed pollicization over a staged. Any reconstruction will require: (1) stabilization of the thumb metacarpal with first web release; (2) MP joint stabilization and opponensplasty, and (3) staged extrinsic tendon transfers – flexor digitorum superficialis (FDS)-ring to FPL for thumb flexion and extensor indicis proprius (EIP) to extensor pollicis longus (EPL) for thumb extension. Additional transfers for adduction may also be required. The size of these thumbs at birth make reconstruction appear attractive to many parents who are often reluctant, some strongly insistent, about considering any option other than ablation and pollicization. Observation

of the child at play will usually direct the surgeon and family towards the best course of management. For instance, a child who bypasses the hypoplastic thumb before reconstruction will usually continue to do so following reconstruction. Most undecided parents usually make up their minds after observing other patients with pollicized digits.

Type IV: floating thumb

Index finger pollicization is the treatment of choice (see Fig. 27.7) unless there are too many cultural or parental concerns, in which case alternatives noted above can be used.

Type V: aplasia

Index finger pollicization is the treatment of choice (see Fig. 27.8). Osteoplastic reconstructions and microvascular transfers are not. The technique is described in detail in the next section.

Clinical conditions and surgical treatment (types I–V)

Deficient first webspace

The correction and widening of the first webspace is the most effective single procedure performed for congenital hand differences! A scar-free web line, created by full-thickness flaps, is essential for thumb mobility and growth. The many options include: (1) local transposition flaps^{76–78}; (2) local rotational or sliding flaps with or without skin grafts^{2,36,62,79}; (3) regional vascular island flaps⁸⁰; (4) free fasciocutaneous tissue transfer^{81,82}; (5) distant pedicled flaps^{26,68,83}; and (6) the use of skin expansion.^{19,84,85}

For all type II thumbs, local flaps are all that are necessary. Each of the techniques utilizes the same principle, lengthening the contractual limb of the Z-plasty by transposing tissue perpendicular to it. In general, the four-flap Z-plasty⁷⁷ is preferred because it provides the most predictable contour and release (see Fig. 27.15). The five-flap (“jumping man”) technique⁷⁸ is equally effective but usually involves small flaps with vulnerable tips. A simple Z-plasty, on the other hand, does not give the proper contour and usually creates a central depression at the base of the webspace.⁸⁶ The surgeon should learn and refine one or two techniques and not experiment with a new one on each case. The use of local flaps with skin grafts, either on the dorsum of the hand or on the index ray, are popular^{36,62} but not preferred in this population due to the conspicuous appearance of the dorsal grafts and the associated contracture when harvested along the radial side of the index finger. If the hand requires repeated operations, such as those needed in the Apert hand, dorsal advancement or sliding flaps may be effective because with each procedure the dorsal tissue is re-advanced to create a broader webspace.^{84,87} The most frequent error in the treatment of these hands is the tendency to use local tissue when the deficit requires more tissue to be moved into the webspace.

Additional methods must be considered with more severe narrowing of the first webspace seen with type II and type IIIA thumbs. Distally based radial artery or dorsal interosseous arterial flaps can provide more than enough tissue to line the first webspace and allow primary closure of the donor




Fig. 27.16 Spectrum of metacarpal hypoplasia. (A–D) There is no arbitrary distinction between specific categories of thumb hypoplasia based on the skeletal appearance alone. These thumbs, which show varying degrees of hypoplasia with a presumably intact carpometacarpal joint, would be classified as type IIIA. (E–H) The smaller metacarpals in these examples would signify type IIIB thumbs. (I–L) These thumbs, with no skeletal connection, would be classified as “floating thumbs”, type IV. When a syndactyly exists between the thumb and index digit, an associated congenital heart defect (the Holt–Oram syndrome) may be present.

site.^{80,84} The preferred axial vessel donor is the radial artery. Preoperative Allen testing must demonstrate an intact palmar arch. We do not hesitate to obtain imaging if there is any question. The authors recommend against the ulnar artery distally based flap unless this artery, the major conduit to the hand, is revascularized with a reversed vein graft. Free groin flaps based on the superficial circumflex artery are very effective with minimal donor site morbidity. The major disadvantages are the anomalous vascular anatomy and the specialized training necessary for pediatric microsurgery. Distant pedicle flaps are not indicated and should be considered only under very special circumstances.

Technique of first web release with four-flap Z-plasty

The contractual limb of the Z-plasty is marked first along the leading edge of the web with the thumb and index finger abducted as much as possible (see Fig. 27.15). The length of this limb determines the lengths of each of the four flaps. At each end of this line, two lines of the same length are drawn at right angles (90°), with the most radial line passing along the dorsal side of the web (parallel to the thumb metacarpal), and the most ulnar border passing on the palmar side of the web, which is usually very close to the thenar flexion crease. These two right angles are then bisected, creating four flaps (two palmar, two dorsal), each with a tip angle of 45°. The less mobile glabrous skin on the palmar surface is incised first as minor adjustments are often necessary and more easily accomplished with the mobile dorsal skin. Dorsal veins and nerves are protected with spreading dissection, and all four flaps are retracted as the webspace is inspected. The radial neurovascular bundle to the index finger is protected. Often an arborization of the ulnar digital artery on the thumb side runs along the distal, leading edge of the adductor pollicis muscle. If the procedure has been designed well, the skin flaps fall into place as the thumb and index finger are abducted.

Skin incisions alone are usually inadequate for a full release of this webspace. Tight fascial investments of the thenar muscles and intermetacarpal bands must be excised before a dramatic release is obtained (see Fig. 27.15B,C). If necessary, these explorations extend to the level of the CMC joint, where branches of the princeps pollicis artery should be protected. The origin of the first dorsal interosseous (1st DI) on the thumb metacarpal is next inspected and partially recessed if necessary. Any release of the AddP from the third metacarpal carries a potential loss of important pinch strength. Although the 1st DI and AddP rarely require release with type II thumbs, they are frequently the tightest deforming forces in severe contractures associated with type IIIA thumbs. When muscle recessions or releases are performed as part of the web release, a 0.35 mm C-wire is often used to hold the index and thumb metacarpals in an abducted position for 3 weeks postoperatively. If the radial digital artery (arteria radialis indicis) to the index finger remains as the tightest structure, it can be ligated when there is a common digital artery to the second webspace.

Occasionally in type II thumbs, anomalous muscles acting as adductors may be encountered passing from the flexor surface of the thumb to the extensor surface of the index finger.⁴² These muscles should be excised. Additional MP joint stabilization procedures or tendon transfers are performed before the flaps are closed with 6-0 mild chromic sutures.

Metacarpophalangeal joint instability

Often the release of a moderate or severe first webspace contracture will unmask a lax ulnar collateral ligament at the MP joint level. Stabilization of this lax joint in type II and IIIA thumbs can be accomplished with a number of procedures: (1) tightening of the existing ligament and capsule³³; (2) free tendon graft reconstruction⁵⁰; (3) arthrodesis, or chondrodesis⁸; and (4) ligament reconstruction using the end of a tendon used to improve palmar abduction (opposition).^{57,79} In the growing child, all must be performed without injury to the growth plate. Simple imbrication of the attenuated collateral ligament on one or both sides of the MP joint is advocated by some³³ for type II and IIIA thumbs but has not been durable in our series. Reefing of the attenuated ulnar collateral ligament and joint capsule can be addressed by either plication or incision and closure of the lax structures with a “pants over vest” repair. The extensor mechanism, with its attenuated shroud fibers, is usually displaced radially and needs to be identified and mobilized from the dorsal joint capsule. A free palmaris longus tendon graft passed either through subperiosteal tunnels in the young child or through drill holes in the older youngster is more predictable. One portion of the graft must be palmar enough to reconstruct the volar accessory portion of the ligament. Both radial and ulnar sides of the joint require reconstruction in most type IIIA thumbs. When an FDS is used simultaneously for palmar abduction (opposition), one slip is passed through a bone tunnel in the metacarpal neck to be used on the ulnar side and the other slip for the radial side of the joint (Fig. 27.17C). Excess tendon on either side may be used for pulley reconstruction if needed.

In type IIIA thumbs with flail joints and poor or absent extrinsic motors, stability of the MP joint is much more critical than motion. Here a chondrodesis in the young child or arthrodesis in the adolescent is indicated. In the young child, the metacarpal head can be shaved without injury to the growth plate and then fused to the epiphysis of the proximal phalanx.^{8,43} Thumbs that have grown in an abducted position and have an asymmetrical joint can only be stabilized by fusion. These stabilization procedures must be held with small wires with the joint in slight (20°) flexion. Unless held rigidly, these thumbs can easily drift into hyperextension with minimal cast motion.

Technique of tendon graft stabilization

A palmaris or another common tendon donor is harvested (ring finger FDS can be used in case of simultaneous opposensplasty) and the MP joint adequately exposed. An extension of the most radial limb of a four-flap Z-plasty provides good exposure for both sides of the joint (see Fig. 27.17). After inspection of the extrinsic flexor and extensor tendons with or without intratendinous fibrous connections (pollex abductus), joint capsule and collateral ligaments are inspected and imbricated if present. A subperiosteal vertical tunnel is made distal to the growth plate along the metaphysis of the proximal phalanx, and a transverse gauge hole proximal to the metacarpal head will provide the bone fixation for the graft. The tendon is then passed from the metacarpal fixation point, beneath the extensor shroud, through the periosteal tunnel from dorsal to palmar. It is then passed below the adductor aponeurosis and shroud to the metacarpal. At this point, it is




Fig. 27.17 Type IIIA thumb metacarpophalangeal (MP) joint instability. **(A)** The total absence of median innervated thenar muscles and an unstable MP joint are characteristic of a type IIIA hypoplastic thumb (inset). **(B)** The superficial flexor tendon to the ring finger has been looped around the flexor carpi ulnaris and passed through Guyon's canal toward the thumb. **(C)** The transfer is secured tightly and both free ends are used to reconstruct the absent collateral ligaments. The inset shows the upper (cord) and lower (volar accessory) portions of the new radial collateral ligament. **(D)** Three months postoperatively, the transfer is strong and the MP joint stable on both ulnar and radial sides.

important that the upper portion of this graft mimic the cord (upper) portion of the collateral ligament and the lower portion provide stability similar to that of the volar accessory portion of the collateral ligament. If this lower portion is fixed at or dorsal to the axis of joint rotation, an MP joint extension contracture will predictably result. The graft is tightened with non-absorbable sutures in 10–15° of flexion and in neutral between radial and ulnar deviation. Pin fixation should not be necessary.

When the ring FDS transfer is performed for palmar abduction (opposition), either bifurcation of the tendon is of adequate length for radial and ulnar collateral ligament reconstructions.

Most type IIIA and some type II thumbs need both sides of the joint stabilized.

Poor/absent palmar abduction (opposition)

The degree of first webspace contracture is a good clinical indication of the degree of hypoplasia of thumb abductors, and the need for opposition transfers can be determined both by thenar muscle examination and assessment of the thumb position during play activities. Often the child tends to use key pinching maneuvers because he or she cannot abduct the thumb adequately to obtain a pulp-to-pulp pinch or grasp




Fig. 27.18 Abductor digiti quinti minimi (ADQM) transfer for opposition. **(A)** The radiograph of this type IIIA thumb shows a small webspace and tightly adducted first metacarpal. **(B)** The clinical photo shows a marked deficiency of the median innervated thenar muscles. The radial and ulnar collateral ligaments are stable. **(C,D)** The abductor digiti quinti muscle is isolated on its origin from the pisiform and passed through a subcutaneous tunnel above the palmar fascia to the radial side of the thumb. If two distal tendons can be dissected, separate insertions into the thumb are performed. If one tendon is present, the preferred insertion is into the radial collateral ligament region. When a proximal dissection of the muscle is performed, its neurovascular bundle must be preserved. **(E)** The patient shown in **(A)** is seen 16 years later with functional palmar abduction from the muscle transfer.

and will use a two-handed grasp for holding larger objects. Substitution for the missing or hypoplastic thenar intrinsic muscles is not effective without a mobile CMC joint, adequate first webspace, and stable MP joint. Most commonly, adequate palmar abduction (opposition) of the thumb is created by transfer of either the abductor digiti quinti minimi (ADQM)⁸⁸⁻⁹³ or the flexor digitorum superficialis (FDS) of the long or ring finger (Figs. 27.17 & 27.18).^{27,51,94,95} We have used the abductor digiti minimi transfer more frequently in patients with radial dysplasia who have undergone pollicization; in these patients, maximum flexor strength to the ulnar side of the hand is paramount.

Technique of ADQM transfer

The muscle is raised from an incision extending from the pisiform proximally to the midaxial line of the proximal phalanx (see Fig. 27.18). A skin island can be taken with the muscle,⁵⁸ which is then detached from its distal extensor and bone insertions. The myocutaneous flap provides the advantages of improving the soft-tissue deficit in the palm and minimizing tightness in the tunnel as a cause of muscle ischemia (Fig. 27.19). Color match is excellent and the borders of this flap are almost indistinguishable on long-term follow up.




Fig. 27.19 Abductor digiti minimi myocutaneous flap for opponensplasty. This patient had a pollicization procedure but opposition was weak. **(A)** The incisions have been made, showing the markings and position of flap harvest. **(B)** The flap is fully mobilized, the digital nerve to the small finger and dorsal sensory branch of the ulnar nerve have been exposed and protected. **(C)** The flap transferred and inset. **(D)** Long-term follow up showing strong opposition.

Clinical tips

Myocutaneous Huber transfer

The authors have been using a myocutaneous Huber transfer more routinely. The advantage of this flap is that it enhances the bulk in the thenar area, while minimizing ischemia of the muscle as it traverses a tight tunnel in the palm. When harvesting this flap, it is best to place sutures affixing the skin to the underlying muscle to avoid shear injury to small perforators. The skin flap usually looks pale once the tourniquet is deflated after it is fully inset. However, if centered right over the muscle, the authors have not seen any necrosis.

If there are difficulties separating the ADQM from the flexor digiti quinti minimi muscle (FDQM), both muscles must be raised as a single unit.⁸⁹ A distal nutrient artery from the ulnar digital artery to the fifth finger must be ligated if present.⁹⁶ Additional length can be obtained with detachment from the pisiform⁸⁸ and retention on the flexor carpi ulnaris tendon. During this extra mobilization, the proximal axial pedicle to the muscle must be inspected carefully. The muscle is then passed through a very generous subcutaneous tunnel made between the skin and palmar fascia and then attached to the metacarpal, the radial collateral ligament at the MP joint, or the abductor aponeurosis. When a skin island is included, an open incision is made across the palm for inset. Insertion to the proximal phalanx or extensor mechanism should

not be performed with any laxity of the ulnar collateral ligament.

Technique of FDS transfer

Harvest of the FDS tendon to the ring finger is done through a longitudinal incision at the base of the ring finger (see Fig. 27.17). The A1 pulley is released, the finger flexed, and both slips of the FDS pulled into the wound and cut as far distally as possible. The tendon is then delivered through an incision over the flexor carpi ulnaris (FCU) dorsally and then passed through a subcutaneous tunnel to the radial side of the thumb where the insertion options are the same as ADQM. The pivot point for the transfer is either through Guyon's canal or around the FCU. It is not advisable to make a loop from a slip of the FCU through which the tendon pivots. The thumb is placed in 45° of palmar abduction and held with a transverse C-wire through the thumb and index metacarpals. One slip of the FDS tendon is passed through a transverse drill hole proximal to the metacarpal head and secured. The two slips of the ring FDS are then used for reconstruction of the radial and ulnar collateral ligaments as described (see Fig. 27.17). At the same time, the existing ligament and capsule are tightened.

Lack of IP joint motion

The most difficult function to reconstruct in type II and IIIA thumbs is IP joint motion. Dorsal capsulotomy and tendon recanalization will improve the minimal deformities. In the pollex abductus anomaly, flexors and extensors with good proximal excursion need to be centralized with pulley construction. In cases of poor motion, tendon transfers are performed at a second stage or avoided entirely. An available ring FDS is the most appropriate for IP flexion and an EIP for IP joint extension. Secondary transfers for extension include brachioradialis (BR) or extensor carpi radialis longus (ECRL) plus a tendon graft to the EPL.⁵⁰

Pollex abductus

The clinical presentation of thumb abduction with limited IP motion is indicative of this anomaly (see Fig. 27.4).^{42,97} Both the flexor and extensor tendons are exposed through a radial incision or via the retracted flap of the webspace release. Exploration and traction on the extrinsic tendons will give an estimation of distal IP motion and proximal muscle belly excursion. The interconnecting bands are divided and excised along the radial side of the MP joint and proximal phalanx. The incision on the radial side of the thumb should be extended until all interconnecting bands are severed and independently restored to both flexor and extensor tendons. The reconstruction here depends upon the degree of anomalous anatomy. Absence of both the short and long thumb flexors (FPB and FPL) will severely impair both pinch and grip functions. In those without a pollex abductus, the FPL is usually satisfactory and the pulley system can be strengthened by a slip of tendon – usually taken from the end of an FDS transfer. A piece of extensor retinaculum will also make a good pulley.⁹⁸ The FPL in the pollex abductus has a poor proximal excursion and can be transferred to the base of the thumb to act as an abductor pollicis longus (AbPL). Transfer of these abnormal aberrant tendons

into a normal position to improve IP joint motion is not effective.

Following release of the extrinsic tendons and excision of anomalous muscles, a difficult decision must be made with regard to construction of the terminal flexor and at least one strategic pulley. Interphalangeal joint flexion can be created by transfer of an unscarred FDS tendon (ring or long) at the same time that palmar abduction (opposition) is restored by an ADQM (Huber) transfer.

Technique of pollicization

Even though pollicization greatly enhances the function of these hands, it is important to remember that the index finger is only placed in a more strategic position to simulate a thumb (Video 27.1 ). The newly created CMC joint was the index MP joint and, therefore, does not have the same degree of freedom as the normal CMC joint of the thumb (Figs. 27.20 & 27.21). Since the normal cone of thenar intrinsic muscles are absent, the strength and stability of these thumbs in both pinch and grasp maneuvers does not approach normal.

Principles

The principles of this procedure, the most elegant in hand surgery, include: (1) transposition of the index digit as a vascular island; (2) a rotation and recession shortening of the ray; (3) a rebalancing of muscles and tendons; and (4) incisions to create a normal first web. Recently described technical refinements to the procedure improve appearance and function.⁵⁸ The operation itself is divided into a number of steps.

Incisions and plan

A number of different incisions have been used over the past three decades (see Fig. 29.21A).^{15,14,58,99–104} Although the markings of Buck-Gramcko^{14,105} are used most frequently, we prefer a modification of the Littler incisions, which permit much greater flexibility for construction of a broad thumb–index webspace.^{50,58,106} A racquet-shaped incision is made around the base of the index ray along the MP flexion crease and extends down the radial border of the hand. The site of the new thenar flexion crease is made in the palm, and the distal portion of the incision is connected to the incision around the index ray. It is best to plan these incisions as though no thumb or thumb remnant was present and to incorporate this extra tissue into the flap designs only if appropriate. If a type IIIB, C, or type IV thumb is present, the skeleton is filleted from its soft-tissue envelope and intrinsic muscles transferred to the new thumb. In certain deficient hands, the soft tissue of the extraneous digit can be isolated on a vascular pedicle, as a vascularized adipofascial flap, and placed in the thenar area to augment the deficiency (Fig. 27.22 ).⁴⁹ Fig. 27.22 appears online only.

Dissection and exposure

The dorsal flap is raised in the subcutaneous fat plane above the large dorsal veins, nerves, and lymphatics – all of which are preserved in a single layer of fat and areolar tissue above the extensor mechanism. Usually one large vein is present on either side of the dorsum of the digit. The neurovascular structures are dissected, and the palmar flap is raised above the level of the palmar aponeurosis, exposing the superficial palmar arch. The common digital bundle to the index–long




Fig. 27.22 Adipofascial flap for thenar augmentation in pollicization. **(A)** This patient is undergoing ablation of a type IIIB thumb and subsequent pollicization. The arrow points to the pedicle of the type IIIB thumb. **(B)** The rudimentary thumb has been stripped of its skeletal and integumentary structures, and rendered an adipofascial flap. The forceps hold the flap in its new position in the new thenar eminence. **(C)** Preoperative mold. **(D)** Postoperative mold after flap transfer and pollicization.





Fig. 27.20 Pollicization. (A) Rebalancing of the extrinsic and intrinsic muscles from a left index finger to the new left thumb (right). DP, Distal phalanx; MP, middle phalanx; PP, proximal phalanx; M, metacarpal; DIPJ, distal interphalangeal joint; PIPJ, proximal interphalangeal joint; MPJ, metacarpophalangeal joint; CMCJ, carpometacarpal joint; EDC, extensor digitorum communis tendon; EIP, extensor indicis proprius tendon; EPL, extensor pollicis longus; 1st PI, first palmar interosseous (ulnar interosseous) muscle; 1st DI, first dorsal interosseous muscle (radial interosseous; abductor indicis); AbPB, abductor pollicis brevis muscle; AddP, adductor pollicis muscle; FPB, flexor pollicis brevis muscle; AbPL, abductor pollicis longus tendon(s). (B) The preoperative markings are compared to the (C) clinical appearance 6 months following pollicization. The dot in the mid-palmar aspect of the index finger is relocated to the midportion of the thenar flexion crease in the postoperative state.

webspace and the floating thumb (if present) are exposed but individually dissected. Arterial loops around the nerve are present in less than 10% of our cases; however, neural loops around the artery are more common and are opened by gently spreading the nerve back to the level of the superficial arch. Use of microinstruments is recommended. We have not commonly seen the arterial anomalies previously described¹⁰⁷ and do not feel preoperative angiography is necessary. The radial bundle to the index digit is usually hypoplastic but rarely absent. In the presence of a thumb, a common bundle gives one artery to the thumb and one to the index ray. With clear retraction of the neurovascular structures and skeletal and extensor origins of the volar interosseous, first dorsal interosseous and adductor pollicis (if a thumb is present) are

detached and the muscles dissected back to their periosteal origin. The index extrinsic flexors are not altered and its lumbrical is left intact. Then the A1 pulley is decompressed. On the dorsal side, the extrinsic extensor digitorum communis and extrinsic indicis proprius to the index are isolated and divided at the level of the MP joint. The lateral bands are gently separated from the common extensor at over the proximal phalanx, which will soon become the new thumb metacarpal.

Skeletal shortening

From both dorsal and palmar approaches, a subperiosteal dissection of the metacarpal is completed and osteotomy sites




Fig. 27.21 Pollicization technique. **(A)** The illustration and palmar view show the site of the incisions. The most important marking is the location of the future thenar flexion crease within the palm. **(B)** The volar base of the index finger will be the midportion of this flexion crease. **(C)** The dorsal marking is made and the visible dorsal draining veins marked by arrows. **(D)** The palmar flaps are elevated above the palmar aponeurosis. **(E)** The common digital bundle to the index-long webspace is isolated. The arborization to the radial side of the long finger (red loop) will be ligated. Note the neuroma in the dissected sensory nerve to the “floating thumb”, which was ligated in the newborn nursery. **(F)** A neural loop around the common vessels to the webspace must be carefully teased apart back to the level of the palmar arch. **(G)** A full release of the first annular (A1) pulley is completed. **(H)** The transverse metacarpal ligament is exposed before its transection, which then provides increased mobility of the ray for the intrinsic muscle dissection. **(I)** The dorsal venous system is easily exposed by scissor dissection between the two layers of dorsal fat/areolar tissue.











Fig. 27.21, cont'd (J) The first dorsal interosseus (abductor indicis) muscle has been detached from its distal bone and extensor insertions. Two distinct muscles are often found. (K) The illustration and (L) clinical picture show that the muscles are attached to their periosteal origin, which has been elevated off the metacarpal. The distal osteotomy is through the epiphysis and the proximal cut leaves the dorsal cortex of the metacarpal base. (M) The metacarpal head becomes the new thumb trapezium and is placed in a hyperextended position in front of the metacarpal base. Interosseous suture fixation is preferred to C-wires, which can cause problems in young children. (N) With the thumb in its new position, the available skin is then draped over the dorsal surface before the cut-back incision is made. This maneuver makes maximal use of the all available tissue. (O) The extrinsic tendons have been shortened and reattached, and the intrinsic muscles have been attached distally either to bone or the extensor mechanism via the lateral bands. (P) The normal appearing first webspace is a gentle curve between the metacarpophalangeal joint of the thumb and that of the long finger. The shaded area represents the area covered by the additional flaps rotated to create this web. (Q) After closure, a broad web allowing maximal abduction should be present. (R) The same hand is seen 5 years later.

marked (Fig. 27.23 ). The intrinsic muscle origins are carefully protected during this dissection, which extends anterior to the index metacarpal to the level of the CMC joint. The proximal osteotomy site is marked and an oblique cut made through the metacarpal, leaving a small post of dorsal cortex to which the metacarpal head will be attached. The distal metacarpal osteotomy is made through the epiphysis in order to arrest the growth of the metacarpal head, which becomes the new thumb trapezium. Careful dissection around this area is necessary to avoid injury to the vessels supplying the proximal phalanx.⁵⁹ The index finger is now “recessed and rotated”¹⁰⁸ and secured anterior to the base of the index metacarpal with one or more interosseous sutures.^{58,98,109} In this position, the MP joint must be hyperextended^{110,111} between 60 and 80°, a position which permits only a few degrees of additional extension of the new joint. Non-absorbable sutures are preferred to C-wires, which can become problematic in young children. This difficult fixation is facilitated by optimal assistance and retraction. At this point in the operation, the tourniquet is deflated for a minimum of 30 min. Fig. 27.23 appears online only.

Tendon and intrinsic muscle rebalancing

The dorsal flap is first draped over the repositioned index finger, which is held in 45° of palmar abduction, and the dorsal cutback incision is made (Fig. 27.21O). This incision is intentionally delayed because optimal use of all available skin can be crucial for creation of a broad webspace. Once made, wide exposure to the new thumb is provided. The extensor digitorum communis (EDC) is advanced and sutured to the ulnar base of the index proximal phalanx (now the thumb metacarpal), so that it provides both extension and pronation. The independent EIP is advanced, a portion resected and sutured side by side to the extensor hood with the new thumb held in no more than 10° of MP and IP flexion. Recently, we have accomplished this by simple plication.¹³ In rare instances, when there is only one extensor on the index finger, this should be used as the EPL.¹⁰⁵

The intrinsic muscle rebalancing is critical to the resting posture of the thumb. The small first volar interosseous, which becomes the new AddP, is attached either to the ulnar collateral ligament at the MP joint or into the wing tendon of the extensor mechanism.^{13,112} Preferably, the much larger 1st DI (or abductor indicis), which becomes the new AbPB, is inserted into the radial collateral ligament or the radial base of the new proximal phalanx. When two separate muscles are dissected, one is inserted into bone and the other into the wing tendon (lateral band) on the radial side of the extensor mechanism. Nothing is done with the lumbrical attached to the index FDP. Additional muscles may be found and used when a hypoplastic thumb is present to increase the bulk of the thenar portion of the hand. In those cases, where the 1st DI (abductor indicis) is absent,^{46,108,113} the EDC can be transferred to the palmar surface of the new thumb metacarpal (formerly index proximal phalanx).

The final position of the new thumb is in extension (not hyperextension), which will be properly balanced within 3–5 months when the extrinsic flexors auto-tighten. Primary shortening of the new extrinsic flexor can be performed initially, but is especially reserved for those with a stiff index finger.¹¹⁴

Skin closure and web construction

Following skeletal rotation and recession and reattachment of all available musculotendinous parts, one of the most challenging portions of this procedure, the tension-free closure, begins (see Fig. 27.21P,Q). Each hand has a different amount of tissue with which to create a normal-appearing, broad thumb–index webspace. First, the new thumb thenar flexion crease is sutured with the thumb in the appropriate amount of pronation in the palmar abducted position. In this position, the dorsal flap of the hand is advanced over the new thumb, and the dorsoradial flap of the index finger is advanced toward the MP joint of the long finger to create a normal-appearing webspace.¹¹⁵ This may require additional mobilization and trimming of flaps. As a rule, we try to avoid a straight-line closure dorsally. Finally, the flaps on the radial side of the thumb are trimmed and closed. This skin closure provides a remarkable amount of stability to the new thumb's position. While many different incisions have been proposed,^{116,117} this particular one is a modification of the Littler and Buck-Gramcko approaches.^{13,105} The major differences are that the position of the new thenar crease is the most important point to be determined and the cutback incision into the index is delayed until the available skin can be draped over the index.

Treatment of other types of thumb hypoplasia (types VI–X)

Type VI: central deficiencies – cleft hand and symbrachydactyly thumb

Cleft hand

In treating a patient with the cleft hand anomaly, the following principles should be followed:

1. Release the first web syndactyly and contracture.
2. Maintain maximal thumb mobility.
3. Complete ulnar transposition of the index digit.
4. Preserve the adductor pollicis, if present.
5. Rotate full-thickness skin flaps into the first webspace.
6. Release any syndactyly involving the two ulnar digits.
7. Create an intermetacarpal ligament between index and ring fingers.
8. Treat the thumb polydactyly in a standard fashion.

Several procedures and modifications have been described to accomplish these principles for the management of this condition.^{30,54,76,118–122} Flaps of the cleft skin based on either the volar or dorsal surface have been used. Unfortunately, both of these designs suffer from the same anatomical problem: The skin flap from the cleft is a random pattern flap, and the viability of the distal portion of the flap can be suspect. Tajima has described closure of the newly created first web with a dorsal sliding flap.⁹⁵ This design poses less risk to the blood supply of the skin flap.

Our preferred method of thumb correction utilizes incisions much like those designed for a pollicization. Incisions are made around the index finger at the same level. The digit is then transposed as a vascular island to the long position. The metacarpal is usually disarticulated and transposed at the CMC joint level. Dorsal and palmar flaps are raised and



Fig. 27.23 Cleft (typical) hand thumb. **(A)** The left hand and **(B)** radiograph of a young child with an unusual cleft hand shows a triphalangeal thumb, a duplication at the metacarpal level, a short index ray with no distal two phalanges, and a transverse bone connecting the long and ring metacarpals at the metacarpophalangeal joint level. The schematic illustration shows the proposed reconstruction. **(C–F)** In a first stage, the index ray (c) was transposed on top of the long metacarpal (f). Only the ulnar portion of the transverse bone (h) was saved because it articulated with the ring proximal phalanx. At the second stage, shown here, the thumb duplication (a,b) was transferred on top of the index ray to make a longer and more complete digit. Nerves and tendons were all joined. **(G–I)** The patient developed a very functional pinch between the long (and untouched) triphalangeal thumb and the index finger. At skeletal maturity, her hand and radiograph are seen. The patient has become a very confident young lady and, in fact, has won regional New England piano competitions.

sutured directly to the skin flaps created by incision of the ulnar side of the cleft. Simple or complex Z-plasties can then be performed on either side of the thumb-index webspace as deemed necessary for contour improvement (see Fig. 27.22 .

When these thumbs are triphalangeal, one of two options is preferred. A stable, well-aligned, mobile but long thumb is usually left uncorrected, and these longer thumbs function very well. However, the longer, flexed, or deviated triphalangeal thumbs should be treated. Shortening the thumb may require excision of the extra phalanx or osteotomies; the former approach invariably leads to stiffness. Improving alignment in the flexed or deviated triphalangeal thumb can also be challenging as the anomalous phalanx can be small. Excision of this phalanx may lead to stiffness and closing wedge osteotomies can be technically difficult. If the extra phalanx is small, the best option is to perform a closing wedge osteotomy and fuse it on its distal or proximal side to the neighboring phalanx.

A number of autosomal-dominant cleft hand and foot syndromes exist. In these patients, a transverse failure of formation of the thumb may be present at the metacarpal or phalangeal level. When no phalangeal segments are present, vascularized toe to thumb transfer using the distal portion of the great toe (if present) is preferred for thumb reconstruction. Distraction lengthening is another alternative.^{50,123,124} Motion in these thumbs is poor, but sensation is good, and function is very gratifying because the deformities are always bilateral. Secondary procedures for correction of intrinsic joint laxity or deviation are common.

Symbrachydactyly thumb

Observation of these children at play will provide insight into the need for any thumb reconstruction. Children with symbrachydactyly tend to be among the most functional, as virtually all can oppose (not touch) the thumb to the small finger. They all have the components of a basic hand: a mobile radial ray, a cleft, and an additional ray or post on the opposite side of the hand for pinching and grasping functions. Even those with no phalangeal components can effectively grasp or pinch using only their metacarpal motion. Consequently, most of these children will not require any operative intervention, and to do so may be quite meddlesome. A hypoplastic thumb with good MP motion, stable joints, and present thenar intrinsics should be left alone.

Excision of non-functional nubbins will improve the shape of the cleft and provide a deeper webspace for grip. If these are not removed early in life, some patients and/or their families become psychologically attached to them and resist any suggestion of ablation. Some patients with this anomaly have a thumb deficient in length and unable to oppose to the highly mobile ulnar border digit. Distraction lengthening can improve both function and appearance. These patients may also lack pulp-to-pulp pinch due to poor pronation of the thumb during pinch maneuvers. Rotational osteotomies at the metacarpal level will resolve this problem by placing the digits in a more favorable position. The severely hypoplastic thumb, with an absent or diminutive proximal phalanx and a flail MP joint, is best treated with a non-vascularized toe phalangeal transfer into the proximal phalangeal level (Fig. 27.24 .

a more stable, functional post. These transfers are more likely to grow if performed before 1 year of age. Ablation of the small distal phalanx and second toe microvascular transfer is an option best performed between 2 and 4 years of age. Fig. 27.24 appears online only.

The ulnar digit in symbrachydactyly will often have an unstable MP joint and radial clinodactyly due to its asymmetrical proximal phalanx. The flexor tendons are usually strong and the extensors present but unbalanced. Stabilization of MP joints with chondrodesis, bone grafts, and non-vascularized toe phalanges have all been performed with varying degrees of success. When positioned as stable posts, these fifth rays function quite well for hooking and balancing maneuvers. With time and growth, most of these fifth rays are lengthened with distraction techniques.

Type VII: constriction ring syndrome

The following principles apply to the management of these thumbs:

1. Immediate treatment of emergency conditions such as vascular compromise and progressive lymphedema
2. Early liberation of the thumb ray when involved with syndactyly
3. Release of adduction contractures within the first webspace when present and resurfacing with full-thickness tissue if needed prior to any augmentation of thumb length.

Following release of the first ray, the functional requirements of the patient need to be accurately determined and the tissue(s) available carefully assessed. In those with distal amputations at the phalangeal level at or beyond the interphalangeal joint, no operative intervention may be the best course of action. Often all that needs to be corrected is a proximal constriction ring. Although the nail and palmar pulp may be atrophic, these thumbs are quite functional. Instability at the IP joint is easily corrected with a collateral ligament reconstruction using either a tendon graft or local tissues. Thumb length can be augmented utilizing one of three methods:

1. Distraction lengthening at the metacarpal level
2. Non-vascularized toe phalangeal transfer
3. Composite vascularized toe-to-thumb transfer – constriction ring syndrome is the most common indication for toe-to-thumb transfers in children.

Distraction lengthening is best performed at the metacarpal level when satisfactory bone stock is present. The metacarpal can be easily – but slowly – be lengthened up to 100% of its length as a two-staged procedure that includes application of distraction apparatus and osteotomy followed by bone grafting of the intercalated gap and internal fixation (Fig. 27.25 .



Fig. 27.24 Symbrachydactyly (atypical cleft) thumbs. **(A,B)** The left hand of this child with the Moebius syndrome was reconstructed with a second toe transfer at age 18 months and is seen on the right at age 5 years during the distraction lengthening of the fifth metacarpal. The distraction was done in two stages: (1) osteotomy and application of distractor and (2) bone grafting. **(C,D)** Ten years later, the second toe transfer continued to grow in comparison to the ulnar metacarpal post. **(E,F)** The left hand and radiograph of another patient with generous soft-tissue nubbins, which represent the thumb and digits. **(G,H)** He was an ideal candidate for non-vascularized toe phalangeal transfer to the thumb and index rays. The first webspace was also deepened and widened with local flaps. Despite the limited mobility, this reconstruction was very functional. Despite the limited mobility of the hand, he had very functional use of this hand as a helper hand.




Fig. 27.25 Constriction ring syndrome (CRS) thumb treated with distraction lengthening. **(A)** The radiograph of a young girl with a congenital amputation at the thumb interphalangeal joint level with a tight first webspace. Note the tapered appearance of the proximal phalanx. **(B)** A distraction apparatus in place is pulling each end of the metacarpal away from the osteotomy site at mid-diaphyseal level. One clockwise turn of the screw equaled a 1.0 mm gain. **(C)** The new bone regenerate (callotasis) advances toward the midportion of the gap created. The stretching injury to soft tissue is impressive! All vessels, nerves and tendons are intact. **(D)** This thumb metacarpal is now as long as the index. **(E)** Five years later both metacarpals are growing but the index is now longer. **(F)** The first webspace was deepened to increase thumb mobility and increase its span. **(G)** Although shorter than normal, this thumb has functioned very well on her dominant hand.

Transfer of non-vascularized toe phalanges^{125,126} is an excellent way to provide length and growth potential to an empty, redundant soft-tissue envelope – occasionally seen distal to the level of amputation in this condition. Extraperiosteal harvest and transfer of the third or fourth toe proximal phalanx will result in survival and growth of the phalanx in 90% of patients under 2 years of age (Fig. 27.26).¹²⁵ Our own experience has not been as successful since only 70% of these phalanges transferred early in life have retained normal growth potential. Survival and growth will occur in patients over 2 years of age but at a less predictable rate. The second toe is spared so that the entire toe is available for vascularized composite transfer if required. Secondary distraction lengthening of the transferred phalanx can be performed if further length is required. Fig. 27.26 appears online only.

In patients with a congenital amputation through the proximal phalanx or metacarpal, composite microvascular transfer of a second toe has been our procedure of choice. The great toe can be transferred either as a complete or as a modified unit (Fig. 27.27), but this option has been reserved for uncorrected thumb deformities, which present later in childhood. Since there is normal anatomy proximal to the level of amputation or band and there is an intact CMC joint, an excellent functional and aesthetic result of the “thoe” can be obtained. The presence of functional thenar intrinsics will also enhance the result (see Fig. 27.27). In several children, we have first lengthened a deficient metacarpal with an intact CMC joint in order to provide a good foundation for second toe transfer. The keys to the distraction procedure are to proceed slowly, to minimize soft-tissue dissection, and to avoid injury to growth centers. The major problem with any toe transfer is the availability of toes, which, like the fingers, may be hypoplastic or aplastic in the CRS. Fig. 27.27 appears online only.

Various types of on-top plasties have been described in the hand literature, and most consist of transfer and distal advancement of composite soft-tissue and bone segments from adjacent fingers. We prefer free transfers to these local transfers, which tend to require extensive dissection and secondary contractures within the first webspace. However, local ray transfers as pollicization procedures can be very effective, especially when the index ray is transferred to augment the thumb. A careful surgeon should avoid injury to the median and ulnar innervated thenar intrinsic muscles, including the adductor pollicis and its origin from the third metacarpal.

Type VIII: five-fingered hand

The optimal management of these patients is to pollicize the radial digit.¹²⁷ The technique employed is similar to that for thumb aplasia (type V). Rebalancing of the intrinsic musculature is paramount to the success of the procedure. In the five-fingered hand anomaly, the dorsal interosseous to the radial digit is only unipennate, and secondary opponensplasty with an ADQM or ring FDS transfer is occasionally necessary. The most important procedure is the creation of a broad first webspace with unscarred flap tissue.

When seen later in childhood or during adolescence, two other options are available: (1) the construction of a first webspace with a forearm flap plus arthrodesis of the proximal interphalangeal joint (PIP) joint or (2) a rotational recession

osteotomy of the first metacarpal with pollicization and intrinsic rebalancing (Fig. 27.28). This condition should not be confused with a triphalangeal thumb, in which the thumb is somewhat shorter than the other digits. Fig. 27.28 appears online only.

Although an extra phalanx is present by definition, extrinsic and intrinsic muscle anatomy mimics a thumb more than a finger. The extra phalanx is often angulated and is commonly associated with radial polydactyly.

Type IX: radial polydactyly

The management of patients with radial polydactyly will vary for the level of duplication and are discussed in more detail elsewhere in this book. In general, the surgeon should use the best parts of each thumb to construct the finest thumb possible. Distal polydactylies (types I and II) are usually managed by preservation of the ulnar duplicate, with extra soft tissue provided from the radial thumb. The resulting nail is smaller than the one on the normal side. The Bilhaut procedure is avoided if possible due to the predictable problems of nail ridging, diminished IP joint motion, and a flat nail contour. Baek's modification of the Bilhaut–Cloquet procedure improves appearance outcomes.^{128,129} Polydactylies at the proximal phalangeal level (types III and IV) are commonly managed with ablation of the radial partner and closure with tissue from this thumb. Musculotendinous abnormalities need to be addressed with the division of interconnections and centralization of insertions. Advancement of the detached thenar intrinsics into the retained extensor mechanism is mandatory, and collateral ligament preservation and reattachment is key to providing a stable MP joint. The metacarpal head will be broad in these patients and requires trimming on the redundant radial side. Closing wedge osteotomy of the metacarpal may also be required to realign the newly constructed thumb. Appropriate trimming of excess skin should result in wound closure, which should be positioned in the high midaxial position. Polydactylies in the metacarpal shaft (type V) can often be managed by simple ablation of the radial partner and concomitant four-flap Z-plasty for any first web deficiency. Polydactylies at the CMC joint level (type VI) and triphalangeal varieties all need to be dealt with on their merit. Digital transposition of the ulnar thumb onto the retained base of the radial partner is commonly performed. Skeletal realignment, tendon repositioning, and first web releases can usually be completed in a single stage.

Type X: syndromic short skeletal thumb ray

Many patients with short thumbs do not require any treatment as the length deficiency is mild. In those who do have an obvious length deficiency, distraction lengthening with a secondary bone graft to the subsequent bony defect at the metacarpal level is possible.

Patients with generalized syndromes require a multidisciplinary approach to their management, and hand procedures can be coordinated with other required treatments. Children with complex hand anomalies, such as those with Apert syndrome, require special attention so that the function of these thumbs and hands can be optimized.

First web syndactyly needs to be managed in the first 3–6 months of life so that the child can develop prehension without interference. The same options for treatment are outlined in




Fig. 27.26 Constriction ring syndrome (CRS) thumb treated with toe phalanx. **(A–D)** This child with CRS acrosyndactyly had the fibrous connections holding all fingertips released in the newborn nursery. The thumb ends at the metaphysis of the proximal phalanx and the index finger at the middle phalanx. Non-vascularized toe phalanges from the third and fourth toes were transferred on top of the index and thumb. **(B,E)** The periosteum is intact, and the collateral ligaments and volar plate are attached to the skeletal part at the amputation stump. Joint motion was preserved in this child. **(F,G)** A four-flap Z-plasty deepened the first webspace and improved her grasping ability. She is now 20 years of age and has had normal growth of the transferred phalanges. No further reconstruction has been performed.





Fig. 27.27 Constriction ring syndrome (CRS) thumb treated with microvascular toe transfer. **(A–C)** This boy, born with acrosyndactyly, demonstrated thumb loss at the interphalangeal (IP) joint level, no first webspace, and congenital amputations of the index and long digits at the phalangeal level. Connecting bands present at birth were released in the newborn nursery. His first surgery was a distally based radial forearm fasciocutaneous flap to the first webspace and release of the camptodactyly of the ring finger. **(D–F)** Thumb length was augmented with a modified great toe transfer. A methylmethacrylate mold of the opposite normal thumb is used to measure and contour the larger great toe at the time of operation. The incision markings are shown on the ipsilateral great toe, and the specimen is seen in transit to the recipient left thumb. **(G,H)** The thumb is seen 4 years later. Sensation is normal, and motion measures 30° at the IP joint and 50° at the metacarpophalangeal joint. The contour has been excellent. No revisions have been performed.



Fig. 27.28 Five-fingered hand. (A,D) The right hand of a child with bilateral five fingered hands is shown. She has auto-rotated the most radial digit into a pseudo thumb position in an effort to functional more effectively. (B,E) In one procedure, the thumb was shortened and fused at the proximal interphalangeal joint and a first webspace created with a radial forearm fasciocutaneous flap, which is seen below before, during, and 5 years after the procedure. A superficial flexor tendon was transferred to improve palmar abduction (opposition). (C,F) There has been no contracture or diminution of this webspace, which was lined with full-thickness flap tissue.

the previous section of this chapter. The deficiency of the first web in the majority of the children with craniosynostoses can be adequately treated with a four-flap Z-plasty. In the more complex type II and type III hand anomalies in Apert syndrome, where there is complete syndactyly of the first web, tissue expansion of the first web can be a very satisfactory means of producing a long-lasting release of the first web.⁸⁴ The deficiencies of length and angulation in these complex anomalies can be addressed with osteotomy and an iliac crest bone graft (Fig. 27.29). More recently, we have found distraction lengthening to be a better alternative. Our preference has been to straighten these thumbs at 4–6 years of age and lengthen them with distraction during early adolescence. The results are remarkable. Fig. 27.29 appears online only.

Postoperative care

For nearly all of the aforementioned operations, immobilization in a well-padded long arm cast is required for at least 3–4 weeks. We prefer to remove the cast under light general anesthesia to minimize the traumatic experience for the child and to inspect and clean the wounds.

Once the cast is removed, for the next 6–8 weeks the hand is wrapped in Coban at night to reduce swelling. A thumb-spica thermoplast splint is worn at night and outside the house for additional protection during this period of time as well. After pollicization, the child works with the parents using special play activities, during which time the long and ring digits are buddy taped to encourage key pinch and grasp using the new thumb. It comes as no surprise that we have seen a positive correlation between good functional results and involved, attentive parents. Other than monthly evaluations by an occupational therapist, no additional therapy is necessary. Some children start to use the reconstructed or new thumb quite early; whereas, others are hesitant. In pollicized digits, return of flexor function may take a few months. By 6 months postoperatively, all children will have actively integrated the thumb into the activities of daily living.

Outcomes, prognosis, and complications

Type I

There are no difficulties with key pulp or nail pinch, grasp, or precision pinch that requires palmar abduction of the thumb. However, the recorded strengths may not reach normal levels. The motion depends on the condition of the joints, and strength of key pinch and chuck pinch are directly related to the existing thenar musculature.

Type II

Although these are not normal thumbs, functional restoration following early surgery is quite good. Although motion of the MP joint is decreased following ligament stabilization or chondrodesis, good mobility of the CMC and IP joints will provide excellent function. Attempts to stabilize through chondrodesis can result in a nonunion. In these thumbs, flexion at the IP joint level is diminished and pinch strength

is reduced not because of a poor AddP muscle but due to the weak flexor pollicis longus, which is usually malformed. Precision and power grasp between the thumb and three opposing digits is much less than normal. The amount and degree of loss is proportional to the anatomical variations encountered, including the pollex abductus abnormality, deficient flexor muscle mass, and the amount of surgery required for correction. Stiff thumbs with poor mobility are much more common when there is a partial or complete loss of the radius in the same forearm.

Type IIIA

The type IIIA reconstructed thumbs are short, slender, less mobile than the type II thumbs, and functional use is highly individual. The only certainty is that these thumbs are never normal. Many studies have correlated the outcome with the degree of anatomical abnormality and the amount surgery required.^{33,115} Following MP joint stabilization, motion is diminished; following web release, the first ray is much more mobile and grasp is markedly improved; and following opposition transfers, palmar abduction is maintained if the muscle or tendon transfer is functional. Chondrodesis in young children frequently fails and needs to be repeated as arthrodesis when they are older. Thumb IP joint flexion is rarely normal and, in fact, the chance of obtaining good functional flexion in a child born without a flexion crease is very poor. With a pollex abductus anomaly and a lax or flail MP joint, both MP and IP joint motion will be significantly reduced following reconstruction. The average IP motion in Lister's series was 21° following one- or two-staged reconstruction of the flexor mechanism in the presence of multiple musculotendinous anomalies.¹³⁰ Children receiving flexor reconstruction also require joint stabilization at either the MP or IP joints. Efforts to release anomalous flexor tendons, interconnections, and/or muscles and use these parts to salvage IP joint motion can be very frustrating, particularly if one watches these children grow beyond adolescence.

Types IIIB, IIIC, and IV

The clinical outcomes following pollicization are not controversial and will be discussed with the type V thumbs. If pollicization is not undertaken, staged reconstructions following intercalated bone graft and/or tendon graft stabilization are predictable. The webspace remains deficient. The thumbs are rigid with poor MP or IP joint motion, and the collateral ligament reconstruction at the MP joint level becomes lax with time. Outcome studies^{67,73,131–133} indicate that these reconstructed thumbs are short, slender, and relatively immobile. There is no metacarpal growth, and as teenagers these children often express dissatisfaction with the thumb “they do not use”. However, long-term follow-up interviews with a number of these children, now adults, reveal that some of these patients and their families are very attached to and enthusiastic about their small and stiff thumbs.¹³²

Some surgeons feel that the functional pinch and appearance is well worth the effort involved in complicated microvascular reconstructions.^{72,73,95,134} However, the potential lack of growth and immobility are major deterrents. The advantage of the microvascular procedures to stabilize the metacarpal base and augment soft tissue is that of growth and restoration of an adequate first webspace. The functional results of a




Fig. 27.29 Type X short skeletal ray. **(A)** The preoperative appearance and thumb radiographs of a young boy with bilateral radial clinodactyly of the thumbs (“hitchhiker thumbs”) associated with the Rubenstein–Taybi syndrome. **(B)** The soft tissue was lengthened on the radial side with a large Z-plasty, and a composite graft and the bone seen lengthened here with an opening wedge osteotomy and corticocancellous bone graft held with two C-wires. **(C)** The same thumbs are seen 7 years later. The right side has grown normally, and on the left side, the deformity has recurred because of the premature closure of the most radial border of the physis.

number of small series^{67,71–73,75,95,135} verify that stability can be achieved but motion is severely impaired. These thumbs are small and have a rudimentary nail complex and scarred webspace, which is generally less aesthetically acceptable than a well-executed index pollicization (Fig. 27.30). The technical difficulties and risks of any free tissue transfer in young children may also be significant. Fig. 27.30 appears online only.

When a staged reconstruction for a floating thumb (type IV) is chosen, the first ray is small, narrow, and stiff. The thumb does not grow at the metacarpal level if a bone graft has been used (Fig. 27.31), but will grow and have some CMC joint stability if a vascularized joint has been transferred. Most of these transfers have taken place in Asian countries due to cultural preferences. Fig. 27.31 appears online only.

Types IIIB, IIIC, IV, and V: pollicization

Our experience with more than 300 pollicization procedures is similar to that of Buck-Gramcko, who performed over twice this number.^{105,111} It is critical to understand that the new thumb will never be normal. The adequacy of the functional and aesthetic postoperative result depends entirely upon the preoperative condition of the index finger.

A child with normal skin, bones, joints, tendons and muscles will achieve an excellent outcome from a *properly performed* pollicization. A youngster with a stiff, partially mobile digit associated with a radial club hand due to a radial absence will have a less functional outcome (see below). In such a hand, it is important to accurately position the new thumb in greater opposition to the other digits avoid too much CMC extension, which would position the thumb in a very vulnerable posture. Although assessment of these procedures is difficult, there is no paucity of outcome reports.^{7,46,60,101,114,136–149} Most corroborate the principle that preoperative condition determines postoperative result.

Although work on the development of more useful outcome measures continues,¹⁴⁸ the most thorough study of long-term outcomes is the report by Manske *et al.*⁶⁰ When considered as a single group of patients, total active range of motion averaged 50% of normal, standard grip strength 21%, lateral pinch 22%, and use in normal activities 84% of normal. Interestingly, these results are not significantly altered by the age of the patient at the time of operation. Furthermore, studies have documented that the function and strength of these neo-thumbs improve as the children grow.¹⁴⁵ The senior author strongly supports this observation.

The appearance of a pollicized digit is much more difficult to quantify due to the subjective interpretation required. Some have tried to quantify appearance by measuring the length of the digit in relation to the PIP flexion crease, the resting posture of the new thumb, and rotation relative to the other digits.^{137,143} Meanwhile, others have emphasized the creation of an aesthetic webspace, which avoids the appearance of a finger positioned on the side of the hand.^{58,60,106} We have observed that the parents are almost uniformly pleased with the postoperative appearance of pollicization and that the young patients do not express much of an opinion until they are teenagers, at which time many will let you know whether they like their thumbs or not. Just ask!

The influence of the age at the time of pollicization is always debated. As stated earlier, many surgeons postulate

that under ideal circumstances this operation should be completed within the first year of life to provide an earlier cortical awareness of the new “thumb”. Developmental scientists have demonstrated that the child is aware of the thumb as a radial post by 1 year of age.¹⁵⁰ Some argue that since there is no thumb, the index digit is the radial substitute and that pollicization represents a repositioning of the radial post. Manske’s data⁶⁰ does not support early pollicization for functional reasons. We feel that the size of the hand and the experience, knowledge, and confidence of the surgeon are more important considerations because the surgeon has only one chance to get a pollicization right.

When considering complications, the major learning curve relates to the incisions, muscle rebalancing, and the creation of a normal first webspace. It has been well documented that complication rates are low in experienced hands.¹⁵¹ Devascularization due to injury to the neurovascular pedicle can occur, particularly in patients with radial longitudinal deficiency and no radial digital artery. This potential problem is avoided by microvascular repair and vein grafting if needed. Invariably, skin flap necrosis and the resulting contractures and disfigurement are related to technical problems during surgery. Venous compromise has been reported,¹⁵¹ and may be due to excessive dissection of the dorsal veins, kinking, tight dressings, or abnormal anatomy. Injury to the innervation of intrinsic muscles may go unrecognized during dissection and can be reconstructed with later transfers. To avoid this problem, these muscles are left attached to the periosteum and are not dissected proximal to the level of the palmar arch. Adduction contractures of the new thumb are the result of either poor positioning and immobilization of the skeletal ray or tight first volar interosseous muscle pull. Aseptic necrosis of the new trapezium (formally the metacarpal head) has been seen, as has growth arrest of the proximal phalanx (new metacarpal).⁵⁹ Ossification of the periosteal tissue can occur due to the periosteum left behind with the intrinsic muscles. Symptomatic spicules are simply excised.

Other types of thumb hypoplasia (types VI–X)

Type VI: central deficiencies – cleft hand and symbrachydactyly thumb

Cleft hand

Since most of these thumbs would fall into the Blauth type I or II hypoplasia categories, the results are similar. The major considerations for function relate to the adequacy of the webspace construction and the integrity of the 1st DI and AddP muscles that are so important in all types of pinch. Strength will be lost from the thumb when the 1st DI is either recessed or detached during the index transposition. Every effort should be made to preserve what AddP muscle is present and its periosteal origin. When the index is transposed into the long position, this periosteum is reattached to the index metacarpal. Grip strength is more dependent on the ulnar three digits and not on the thumb.

Symbrachydactyly thumb

This thumb is universally smaller than the normal thumb on the contralateral hand. Once stabilized, it provides a mobile radial ray for the rest of the hand, and IP joint motion is either



Fig. 27.30 Type IIIB microvascular reconstruction. **(A,B)** The radiograph and clinical picture show a type IIIB thumb in which there is no proximal metacarpal or carpometacarpal joint. This thumb has no skeletal attachment to the rest of the hand. **(C,D)** A second-toe metatarsophalangeal joint, with covering soft-tissue flap, has been transferred to provide the skeletal connection and stability. The picture shown is at skeletal maturity. Tendon transfers were needed to provide extrinsic flexion and extension to the thumb, and the skin flap helped build up the thenar region. (Case provided by G. Foucher, MD)



Fig. 27.31 Type IIIB staged reconstruction. **(A,B)** The preoperative radiograph and clinical appearance of a type IV thumb in a child whose parents insisted upon saving it. **(C,D)** A bridging iliac corticocancellous bone graft was used to stabilize the thumb, which became an immobile post and did not grow commensurately with the child. At age 14 years, the same child came to the authors' clinic and asked when she would be given a "normal" thumb.

diminished or absent. When the IP flexion crease is absent at birth, attempts to restore motion with joint releases and extrinsic tendon reconstructions are dismal. Flexor tendon grafts are also disappointing due to the malformed motors in the forearm. If attempted, wrist flexors or extensors should be used. It is difficult to make any generalizations here due to the very wide clinical spectrum of these thumbs.

Type VII: constriction ring syndrome

The functional outcome of a thumb with a congenital amputation at the interphalangeal joint level is excellent, provided there is a broad, unscarred webspace between the thumb and the next digit. Thumbs lengthened with non-vascularized toe phalangeal transfers have the advantage of increased length with little mobility at the MP joint level. Thumbs lengthened with vascularized toe transfers have the advantages of normal length, normal sensation if performed in young children, and the disadvantage of less-than-normal motion.⁸² The functional results of these transfers in this group are superior due to the normal anatomical motors in the forearm.

Type VIII: five-fingered hand

The results are similar to those described for index pollicization without radial dysplasia. Similar outcomes have been achieved in those who had forearm flaps followed by rotation-recession osteotomies at the metacarpal level. These thumbs are all well positioned in palmar abduction but lack forceful adduction, power pinch, and grasp. The thumbs are long and slender and do not have normal or close-to-normal key pinch and thumb-to-index grasping strength.

Type IX: radial polydactyly

Refer to Chapter 28 in this volume.

Type X: syndromic short skeletal ray thumb

Results must be individualized to the specific thumb condition. For those with the Apert syndrome, the thumb is longer, motion is present at the MP and CMC joints, and the degree of independent function depends more upon the quality of the first webspace.

Thumbs that have been lengthened with distraction techniques are longer, thin at the phalangeal level, and stiffer at joints distal to the distraction. If distracted slowly, at approximately 0.5 mm/day, damage to the intrinsic muscles is minimized. With a normal CMC joint and intact thenar muscles, these thumbs become very functional.

Secondary procedures

Additional procedures have been unusual in our experience. The most common has been opposition transfers for patients with a partial or complete absence of the radius and inadequate median innervated thenar muscles. In all of these patients, this procedure was discussed as part of the initial “game plan” prior to pollicization. In our series, eight patients have required an osteotomy to correct the CMC hyperextension, and in seven patients (treated early in the series), it was necessary to stop persistent growth of the metacarpal. Eleven children have come back as adults to have symptomatic bone

spicules from retained periosteum removed. Extensor tendon tenolysis or shortening was necessary in only ten hands. It is expected that the revision rate would be higher if our patient population were less mobile and diligent about long-term follow-up.

Many revisions have been performed on patients whose pollicization was performed by another surgeon. The most common problems were: (1) poor position of the skeletal ray; (2) excessive scarring from initial skin loss; (3) adherent extensor tendons; and (4) lack of palmar abduction (opposition). Ten patients have come back as adults: five to have a carpal tunnel release and five to have a painful, dysplastic carpal bone removed. Symptoms were related to repetitive activities at work and/or pregnancy, and all patients were between 20 and 35 years of age.

The inadequate index finger

The inadequate index finger deserves special attention because in many clinical cases, a less than normal (i.e., stiff) index finger is available for potential pollicization (Fig. 27.32). These cases include:

1. A syndactylized index ray in a child with Holt–Oram syndrome
2. An index joined to the long finger with a complete simple syndactyly (i.e., typical cleft hand, index–long syndactyly with absent or hypoplastic thumb)
3. A stiff index finger associated with a complete or partial absence of the radius
4. A stiff index ray with a fixed proximal interphalangeal joint flexion contracture with or without a complete or partial absence of the radius
5. The mirror hand (ulnar dimelia)
6. The five-fingered hand. Fig. 27.32 appears online only.

In all of these cases, the clinical deficiencies of the index ray are obvious on physical examination, and the major question is whether anything can be accomplished surgically to improve either the clinical function or appearance of the hand. The absence of flexion creases indicates that there has been very little if any motion *in utero* and that there are deficient joints, muscles, and/or tendinous structures. At surgery, fibrous bands are present between the phalanges, which may not appear joined on radiographs. Flexion contractures (camptodactyly) may be present in the index or all digits with decreasing degrees of severity from the radial to the ulnar digits. These clinical situations do not present frequently but occur more often than anticipated. In our experience, one of these clinical scenarios is present at least 15% of the time.¹⁰⁶

There are no standard guidelines for treatment in the literature and surgical recommendations are more dependent upon a given surgeon’s experience than on practical reasoning. Most recommendations have been overwhelmingly conservative.^{7,51,101,106,111,130,138,139,143,152–156} Options for reconstruction include: (1) no surgical treatment; (2) rotation-recession osteotomy of the index ray¹⁵⁷; (3) formal pollicization of the index ray; or (4) pollicization of the fifth finger.

The determination of what to do and how to do it can be made much easier by an analysis of larger series of pollicizations.¹⁵⁸ Logically, the quality of the result depends predominantly upon the preoperative condition of the index ray.



Fig. 27.32 Inadequate index finger. **(A)** This 7-year-old boy with bilateral absence of the radius shows his pectoralis major muscle transfer, which is now working as an elbow flexor. After preliminary distraction, the hand and wrist were centralized over the distal ulna. **(B)** The characteristic widening of the distal ulna is seen. From ulnar to radial, the PIP joints of the digits had increasing fixed flexion contractures to the extent that the index finger was flexed 100° and was useless. After a successful pollicization on his other hand, the patient asked for improvement of this hand. **(C)** First, the proximal and middle phalanges were shortened, and an arthrodesis was performed at the PIP joint level. **(D)** Next, a rotation-recession osteotomy placed the new thumb in enough palmar abduction to allow pulp-to-pulp pinch with the long finger and grasping of small objects. This position purposefully keeps the thumb from becoming caught in pants pockets and other objects. **(E)** Internal plate and screw fixation was used. Motion was present only at the metacarpophalangeal joint. Within weeks of the operation, he began to use this previously ignored digit.

For those with syndromic associations, which include major central neurologic deficits, no surgical treatment is indicated. Pollicization alone for the stiff index digit is considered by some for aesthetic reasons alone. Often, a more mobile index has been moved to the thumb position on the opposite hand. It is important to place the stiffer thumb in a more adducted position. Proper length and the creation of a normal web that extends to the index PIP joint in the thumb position are both crucial to a good appearance.

The position of the pollicized index finger is crucial for a pinch to the long finger and a grasp to the fifth finger (see Fig. 27.32). Usually, the new thumb will have diminished extrinsic motion, particularly in extension, because the muscles originating on the radial side of the forearm are either abnormal or absent. It is most important that this thumb be positioned for good opposition to the fifth finger, a posture that places it in less abduction than normal. If placed in too much palmar abduction and extension, this immobile post will become caught on objects or within pockets.

One alternative, rarely chosen for these patients, is the rotation–recession osteotomy in lieu of a formal pollicization.¹⁵⁷ We have preferred this procedure in older children, teenagers, and adults with a stiff, flexed index finger, those with scarring from previous procedures, mirror hands, the five-fingered hand, and the very stiff index ray associated with a radial club hand. The principles of treatment are the same, but the ray is not shortened to the full extent of a formal pollicization. Any intrinsic muscles that are present are reattached and the extrinsic flexors and extensor tendons are shortened as appropriate. The position of the new thumb must be very carefully chosen for optimal pinch. Many patients with radial longitudinal deficiency are born with camptodactyly involving all proximal interphalangeal joints, which becomes progressively more severe in the most radial index and long digits. In these contracted digits, we also perform full releases with Z-plasties or full-thickness skin grafts if needed. Then we consider a rotation–recession osteotomy instead of a classic pollicization.

The possible combination of deformities with congenital hand differences is almost infinite, and there are many instances in which it is possible to pollicize an index digit after a number of previous procedures involving this ray have been completed. Most examples involve either a syndactylized

index finger within a mitten hand or a typical cleft hand in which the index and long fingers are joined within a simple syndactyly.^{159,160} In either case, the syndactyly is released before formal repositioning of the index digit.

Future directions

The care of congenital thumb differences has not changed dramatically in the past few years. Advancement of knowledge and technique is slow but steady. Investigations in the genetic basis of these differences continues to progress. As we have continued to refine genetic and biochemical understanding of congenital hand differences, a new, more comprehensive classification system has emerged and is gaining broad acceptance. Meanwhile, while the principles have remained the same, technical advancements^{49,58,79,93} in surgical treatment continue to improve patient care. Lastly, despite many hurdles, investigators continue to improve quantification and measurement of outcomes in this field,^{148,161,162} promising global standardization of measuring outcomes.



Bonus images for this chapter can be found online at

<http://www.expertconsult.com>

- Fig. 27.9 Thumb in typical cleft hand.
- Fig. 27.10 Symbrachydactyly thumb (atypical cleft).
- Fig. 27.11 Constriction ring syndrome thumbs.
- Fig. 27.12 Five-fingered hand.
- Fig. 27.13 Type X short skeletal ray.
- Fig. 27.16 Spectrum of metacarpal hypoplasia.
- Fig. 27.22 Adipofascial flap for thenar augmentation in pollicization.
- Fig. 27.23 Cleft (typical) hand thumb.
- Fig. 27.24 Symbrachydactyly (atypical cleft) thumbs.
- Fig. 27.25 Constriction ring syndrome (CRS) thumb treated with distraction lengthening.
- Fig. 27.26 Constriction ring syndrome (CRS) thumb treated with toe phalanx.
- Fig. 27.27 Constriction ring syndrome (CRS) thumb treated with microvascular toe transfer.
- Fig. 27.28 Five-fingered hand.
- Fig. 27.29 Type X short skeletal ray.
- Fig. 27.30 Type IIIB microvascular reconstruction.
- Fig. 27.31 Type IIIB staged reconstruction.
- Fig. 27.32 Inadequate index finger.



Access the complete reference list online at

<http://www.expertconsult.com>

5. Blauth W. [The hypoplastic thumb]. *Arch Orthop Unfallchir.* 1967;62:225–246. This article presents early classification of thumb hypoplasia that has become the “gold standard” of diagnosis. Despite minor modifications, today’s well-accepted classification system still bears Blauth’s name.
7. Manske PR, McCarroll HR Jr. Reconstruction of the congenitally deficient thumb. *Hand Clin.* 1992;8:177–196. This article clearly defines the anatomical and functional differences between type IIIA and IIIB thumbs. The authors conclude that CMC joint stability and extrinsic tendon abnormalities allow differentiation between these two types of thumb hypoplasia. They recommend reconstruction for IIIA thumbs and ablation with pollicization for IIIB thumbs.
13. Littler J. The neurovascular pedicle method of digital transposition for reconstruction of the thumb. *Plast Reconstr Surg.* 1953;12:303–319. This is a classic article on the technique of digital transposition by a master hand surgeon. He refined the techniques for traumatic thumb loss developed by Bunnell and others after the Second World War and applied them to congenital cases.
14. Buck-Gramcko D. Pollicization of the index finger. Method and results in aplasia and hypoplasia of the thumb. *J Bone Joint Surg Am.* 1971;53:1605–1617. Buck-Gramcko obtained a large experience with pollicization after the thalidomide crisis in Europe. This seminal paper describes the classic technique that he developed, which remains the present-day standard for pollicization.
49. Upton J, Sharma S, Taghinia AH. Vascularized adipofascial island flap for thenar augmentation in pollicization. *Plast Reconstr Surg.* 2008;122:1089–1094.
60. Manske PR, Rotman MB, Dailey LA. Long-term functional results after pollicization for the congenitally deficient thumb. *J Hand Surg Am.* 1992;17:1064–1072. This is a well-documented study on the long-term outcomes of pollicization. The results show that the pollicized digit is quite functional, albeit never achieving as much strength or

- mobility as a normal thumb. Outcomes fell into two categories depending on the preoperative state of the index finger. They found no difference in outcome between patients who underwent pollicization very early in life and others who underwent pollicization in early childhood.*
73. Foucher G, Medina J, Navarro R. Microsurgical reconstruction of the hypoplastic thumb, type IIIB. *J Reconstr Microsurg.* 2001; 17:9–15.
77. Woolf R, Broadbent T. The four-flap Z-plasty. *Plast Reconstr Surg.* 1972;49:48–51.
114. Bartlett GR, Coombs CJ, Johnstone BR. Primary shortening of the pollicized long flexor tendon in congenital pollicization. *J Hand Surg Am.* 2001;26:595–598.
147. Clark DI, Chell J, Davis TR. Pollicisation of the index finger. A 27-year follow-up study. *J Bone Joint Surg Br.* 1998;80:631–635.

References

- Flatt A. *The Care of Congenital Hand Anomalies*. St. Louis, MO: CV Mosby; 1977:55–79.
- Bayne LG, Klug MS. Long-term review of the surgical treatment of radial deficiencies. *J Hand Surg Am*. 1987;12:169–179.
- Flatt A. *The Care of Congenital Hand Anomalies*. 2nd ed. St Louis, MO: Quality Medical Publishing; 1994:292–314.
- Buck-Gramcko U, Buck-Gramcko D. Free toe transplantation in congenital hand defects. *Handchir Mikrochir Plast Chir*. 1995;27:181–188.
- Blauth W. [The hypoplastic thumb]. *Arch Orthop Unfallchir*. 1967;62:225–246. This article presents early classification of thumb hypoplasia that has become the “gold standard” of diagnosis. Despite minor modifications, today’s well-accepted classification system still bears Blauth’s name.
- Müller W. *Die angeborenen Fehlbildungen der menschlichen Hand*. Leipzig, Germany: Thieme; 1937.
- Manske PR, McCarroll HR Jr. Reconstruction of the congenitally deficient thumb. *Hand Clin*. 1992;8:177–196. This article clearly defines the anatomical and functional differences between type IIIA and IIIB thumbs. The authors conclude that CMC joint stability and extrinsic tendon abnormalities allow differentiation between these two types of thumb hypoplasia. They recommend reconstruction for IIIA thumbs and ablation with pollicization for IIIB thumbs.
- Manske PR, McCarroll HR Jr, James M. Type III-A hypoplastic thumb. *J Hand Surg Am*. 1995;20:246–253.
- Tonkin MA. On the classification of congenital thumb hypoplasia. *J Hand Surg Eur Vol*. 2014;39:948–955.
- Gosset J. La pollicisation de l’index (Technique chirurgicale). *J Chir (Paris)*. 1949;65:403–413.
- Hilgenfeldt O. *Operativer Daumenersatz und beseitigung von Greifstörungen bei Fingerverlusten*. Stuttgart: Ferdinand Enke Verlag; 1950.
- Bunnell S. Digit transfer by neurovascular pedicle. *J Bone Joint Surg Am*. 1952;34:772–774.
- Littler J. The neurovascular pedicle method of digital transposition for reconstruction of the thumb. *Plast Reconstr Surg*. 1953;12:303–319. This is a classic article on the technique of digital transposition by a master hand surgeon. He refined the techniques for traumatic thumb loss developed by Bunnell and others after the Second World War and applied them to congenital cases.
- Buck-Gramcko D. Pollicization of the index finger. Method and results in aplasia and hypoplasia of the thumb. *J Bone Joint Surg Am*. 1971;53:1605–1617. Buck-Gramcko obtained a large experience with pollicization after the thalidomide crisis in Europe. This seminal paper describes the classic technique that he developed, which remains the present-day standard for pollicization.
- Edgerton M, Snyder G, Webb W. Surgical treatment of congenital thumb deformities (including impact of correction). *J Bone Joint Surg Am*. 1965;47:1453–1474.
- Caffey J. *Pediatric X-Ray Diagnosis: A Textbook for Students and Practitioners of Pediatrics, Surgery and Radiology*. 7th ed. Chicago, IL: Year Book Medical Publishers; 1978.
- Entin M. Reconstruction of congenital anomalies of the upper extremities. *J Bone Joint Surg Am*. 1959;41:681–701.
- Entin M. Congenital anomalies of the upper extremity. *Surg Clin North Am*. 1960;40:497.
- Coombs C, Upton J. The hypoplastic and absent thumb. In: Bentz M, ed. *Pediatric Plastic Surgery*. Stamford, CT: Appleton and Lange; 1997:907–957.
- Rayan GM, Upton J. *Congenital Hand Anomalies and Associated Syndromes*. 2014th ed. Springer; 2014:500.
- Fanconi G. Familiäre infantile perniziösaartige anämie. *Jahr Kind*. 1927;117:257.
- Auerbach AD, Rogatko A, Schroeder-Kurth TM. International Fanconi anemia registry: relation of clinical symptoms to diepoxybutane sensitivity. *Blood*. 1989;73:391.
- Alter BP. Fanconi’s anemia current concepts. *Am J Pediatr Hematol Oncol*. 1992;14:170–176.
- Giampietro PF, Adler-Brecher B, Verlander PC, et al. The need for a more accurate and timely diagnosis in Fanconi Anemia: a report of the International Fanconi Anemia Registry. *Pediatrics*. 1993;91:1116–1120.
- Webb ML, Rosen H, Taghinia A, et al. Incidence of Fanconi anemia in children with congenital thumb anomalies referred for diepoxybutane testing. *J Hand Surg Am*. 2011;36:1052–1057.
- Blauth W, Schneider-Sickert F. *Congenital Deformities of the Hand: An Atlas of Their Surgical Treatment*. Berlin: Springer-Verlag; 1981:10–72.
- Su C, Hoopes JE, Daniel R. Congenital absence of the thenar muscles innervated by the median nerve: report of a case. *J Bone Joint Surg Am*. 1972;54:1087–1090.
- O’Rahilly R. Morphological patterns in limb deficiencies and duplications. *Am J Anat*. 1951;89:135–194.
- Lane W. Abnormal muscle of the hand. *J Anat Physiol*. 1887;21:674.
- Miura T, Komada T. Single method for reconstruction of the cleft hand with an adducted thumb. *Plast Reconstr Surg*. 1979;64:65–67.
- Blair W, Buckwalter JA. Congenital malposition of the flexor pollicis longus – an anatomy note. *J Hand Surg Am*. 1983;8:93–94.
- Blair W, Omer GE. Anomalous insertion of the flexor pollicis. *J Hand Surg Am*. 1981;6:241–244.
- Graham T, Cleveland OH, Louis DS. A comprehensive approach to surgical management of the Type IIIA hypoplastic thumb. *J Hand Surg Am*. 1998;23:3–13.
- Dellon A, Rayan G. Congenital absence of the thenar muscles: report of two cases. *J Bone Joint Surg Am*. 1981;63:1014–1015.
- Fitch RD, Urbaniak JR, Ruderman RJ. Conjoined flexor and extensor pollicis longus tendons in the hypoplastic thumb. *J Hand Surg Am*. 1984;9:417–419.
- Strauch B. Dorsal thumb flap for release of adduction contracture of the first web space. *Bull Hosp Joint Dis*. 1975;36:34–39.
- Miura T. An appropriate treatment for postoperative Z-formed deformity of the duplicated thumb. *J Hand Surg Am*. 1977;2:380–386.
- Koster G. Isolated aplasia of the flexor pollicis longus: a case report. *J Hand Surg Am*. 1984;9:870–871.
- Tsuchida Y, Kasai S, Kojima T. Congenital absence of the flexor pollicis longus and brevis: a case report. *Hand*. 1976;8:294–297.
- Arminio J. Congenital anomaly of the thumb: absent flexor pollicis longus tendon. *J Hand Surg Am*. 1979;4:487–488.
- Chase R. Discussion of pollex abductus due to congenital malposition of the flexor pollicis longus. *J Bone Joint Surg Am*. 1969;51:1290.
- Lister G. Pollex abductus in hypoplasia and duplication of the thumb. *J Hand Surg Am*. 1991;16:626–633.
- Neviaser R. Congenital hypoplasia of the thumb with absence of the extrinsic extensors, abductor pollicis longus and thenar muscles. *J Hand Surg Am*. 1979;4:301.
- Kobayashi A, Ohmiya K, Iwakuma T, et al. Unusual congenital anomalies of the thumb extensors: report of two cases. *Hand*. 1976;8:17–21.
- Tupper J. Pollex abductus due to congenital malposition of the flexor pollicis longus. *J Bone Joint Surg Am*. 1969;51:1285–1290.
- Kleinman WB. Management of thumb hypoplasia. *Hand Clin*. 1990;6:617–641.
- Buck-Gramcko D. Congenital malformations. In: Nigst H, Buck-Gramcko D, Millesi H, Lister G, eds. *Hand Surgery*. Stuttgart: Thieme; 1988:12.1–12.114.
- Littler J. *Reconstruction of the thumb, The Monks Lecture*. 1977.
- Upton J, Sharma S, Taghinia AH. Vascularized adipofascial island flap for thenar augmentation in pollicization. *Plast Reconstr Surg*. 2008;122:1089–1094.
- Upton J. Treatment of congenital forearm and hand anomalies. In: May J, Littler JWL, eds. *Plastic Surgery*. Philadelphia, PA: WB Saunders; 1990:5352–5356.

51. Flatt A. The absent thumb. In: *The Care of Congenital Hand Anomalies*. 2nd ed. St. Louis, MO: Quality Medical Publishing; 1994.
52. Wassel H. The results of surgery for polydactyly of the thumb. *Clin Orthop*. 1969;64:175–193.
53. Wood V. Super digit. *Hand Clin*. 1990;6:673–684.
54. Barsky A. Cleft hand: classification, incidence and treatment. Review of the literature and report of nineteen cases. *J Bone Joint Surg Am*. 1964;46(A):1707–1720.
55. Ogino T. Cleft hand. *Hand Clin*. 1990;6:661.
56. Patterson T. Congenital ring constrictions. *Brit J Plast Surg*. 1961;14:1–31.
57. Lister G. Absent tendons excluding thumb deficiencies. In: Buck-Gramcko D, ed. *Congenital Malformations of the Hand and Forearm*. London: Churchill Livingstone; 1998:327–330.
58. Taghinia AH, Littler JW, Upton J. Refinements in pollicization: a 30-year experience. *Plast Reconstr Surg*. 2012;130:423e–433e.
59. Lochner HV, Oishi S, Ezaki M, et al. The fate of the index metacarpophalangeal joint following pollicization. *J Hand Surg Am*. 2012;37(8):1672–1676.
60. Manske PR, Rotman MB, Dailey LA. Long-term functional results after pollicization for the congenitally deficient thumb. *J Hand Surg Am*. 1992;17:1064–1072. *This is a well-documented study on the long-term outcomes of pollicization. The results show that the pollicized digit is quite functional, albeit never achieving as much strength or mobility as a normal thumb. Outcomes fell into two categories depending on the preoperative state of the index finger. They found no difference in outcome between patients who underwent pollicization very early in life and others who underwent pollicization in early childhood.*
61. Caroli A, Zanasi S. First web-space reconstruction by Caroli's technique in congenital hand deformities with severe thumb ray adduction. *Br J Plast Surg*. 1989;42:653–659.
62. Friedman R, Wood VE. The dorsal transposition flap for congenital contractures of the first web space: a 20 year experience. *J Hand Surg Am*. 1997;22:664–670.
63. Foucher G, Greant P, Merle M, Michon J. [Congenital abnormalities of the thumb. Contribution of microsurgical technics]. *Chirurgie*. 1988;114:60–66.
64. Foucher G, Navarro R, Medina J, Allieu Y. [Pollicization, remains of the past or current operation]. *Bull Acad Natl Med*. 2000;184:1241–1253.
65. Cooney WP 3rd, Wood MB. Microvascular reconstruction of congenital anomalies and post-traumatic lesions in children. *Hand Clin*. 1992;8:131–146.
66. Reichert B, Berger A. [Microsurgical tissue transplantation for correction of hand abnormalities]. *Handchir Mikrochir Plast Chir*. 1994;26:200–205, discussion 206.
67. Nishijima N, Matsumoto T, Yamamuro T. Two-stage reconstruction for the hypoplastic thumb. *J Hand Surg Am*. 1995;20:415–419.
68. Barsky A. *Congenital Anomalies of the Hand and Their Surgical Treatment*. Springfield, IL: Charles C. Thomas; 1958:114–121.
69. Barsky A. Congenital anomalies of the thumb. *Clin Orthop*. 1959;15:96–110.
70. Matthews D. Congenital absence of functioning thumb. *Plast Reconstr Surg*. 1960;26:487–493.
71. Yamauchi YFA, Yanagihara Y, Yoshizaki K. Reconstruction of floating thumb – especially on the use of vascularized metatarsophalangeal joint grafting. *Seikeigeka Mook*. 1979;30:1645–1648.
72. Ono H, Tamai S, Yajim H, et al. Vascularized toe joint transfer for floating thumb. *J Jpn Soc Surg Hand*. 1979;8:510–514.
73. Foucher G, Medina J, Navarro R. Microsurgical reconstruction of the hypoplastic thumb, type IIIB. *J Reconstr Microsurg*. 2001;17:9–15.
74. Fujimaki A, Yamauchi Y. Application of microsurgery in congenital anomaly of the hand. *Seikeigeka Mook*. 1984;35:142–150.
75. Kanaya F, Tokeshi M, Annri H, et al. Transposition of the third metatarsus for the reconstruction of Blauth Type III hypoplastic thumb. *J Jpn Soc Surg Hand*. 1996;12:776–780.
76. Sandzen SJ. Classification and functional management of congenital central defect of the hand. *Hand Clin*. 1985;1:483–498.
77. Woolf R, Broadbent T. The four-flap Z-plasty. *Plast Reconstr Surg*. 1972;49:48–51.
78. Hirshowitz B, Karev A, Rouso M. Combined double Z-plasty and Y-V advancement for thumb web contracture. *Hand*. 1975;7:291.
79. Christen T, Dautel G. Type II and IIIA thumb hypoplasia reconstruction. *J Hand Surg Am*. 2013;38:2009–2015.
80. Upton J, Havlik RJ, Coombes CJ. Use of forearm flaps for the severely contracted first web space in children with congenital malformations. *J Hand Surg Am*. 1996;21:470–477.
81. Kay SP, Wiberg M. Toe to hand transfer in children, Part I: Technical aspects. *J Hand Surg [Br]*. 1996;21:723–734.
82. Kay SE, Wiberg M, Bellew M, Webb F. Toe to hand transfer in children. Part 2: Functional and psychological aspects. *J Hand Surg [Br]*. 1996;21:735–745.
83. Bunnell S. *Surgery of the Hand*. 3rd ed. Philadelphia, PA: Lippincott; 1956:81–91.
84. Coombs C, Mutimer KL. Tissue expansion for the treatment of complete syndactyly of the first web. *J Hand Surg Am*. 1994;19:968–972.
85. Upton J. Management of disorders of separation – syndactyly. In: Mathes SJ, ed. *Plastic Surgery, Vol 8: The Hand and Upper Limb, Part 2*. 2nd ed. Philadelphia, PA: Saunders; 2006:139.
86. Furnas D, Fischer G. The Z-plasty: biomechanics and mathematics. *Brit J Plast Surg*. 1971;24:144–160.
87. Fereshetian S, Upton J. The anatomy and management in the Apert thumb. In: Upton J, Zuker R, eds. *Clin Plast Surg*. Philadelphia, PA: WB Saunders; 1991:365–380.
88. Littler J, Cooley S. Opposition of the thumb and its restoration by abductor digiti quinti transfer. *J Bone Joint Surg Am*. 1963;45:1389–1396.
89. Manske P, McCarroll H. Abductor digiti minimi opponensplasty in congenital radial dysplasia. *J Hand Surg Am*. 1978;3:552–559.
90. Ogino T, Minami A, Fukuda K. Abductor digiti minimi opponensplasty in hypoplastic thumb. *J Hand Surg [Br]*. 1986;11:372–377.
91. Huber E. Hilssoperation bei medianuslahung. *Dtsch Z Chir*. 1921;162:271–275.
92. Chao VT, Low CK. Reconstruction of a supinated hypoplastic thumb with combined Huber transfer and derotation osteotomy: a case report. *Ann Acad Med Singapore*. 1999;28:875–876.
93. Upton J, Taghinia AH. Abductor digiti minimi myocutaneous flap for opponensplasty in congenital hypoplastic thumbs. *Plast Reconstr Surg*. 2008;122:1807–1811.
94. Lister G. The choice of procedure following thumb amputation. *Clin Orthop*. 1985;May:45–51.
95. Tajima T, ed. *Reconstruction of the Floating Thumb*. London: Churchill Livingstone; 1998:369–373.
96. Oberlin C, Gilbert A. Transfer of the abductor digiti minimi (quinti) in radial deformities of the hand in children. *Ann Chir Main*. 1984;3:215–220.
97. Lister G. *Pollex abductus*. Presented in Symposium on Congenital Deformities of the Upper Limb. May 1988.
98. Lister G. Intraosseous wiring of the digital skeleton. *J Hand Surg Am*. 1978;3:427–435.
99. Harrison SH. Pollicisation in children. *Hand*. 1971;3:204–210.
100. Malek R, Grossman JA. The skin incision in pollicization. *J Hand Surg Am*. 1985;10:305–306.
101. Egloff DV, Verdan C. Pollicization of the index finger for reconstruction of the congenitally hypoplastic or absent thumb. *J Hand Surg Am*. 1983;8:839–848.
102. White W. Fundamental priorities in pollicisation. *J Bone Joint Surg Br*. 1970;52:438–443.
103. Zancolli E. Transplantation of the index finger in the absence of the thumb. *J Bone Joint Surg Am*. 1960;42:658–660.
104. Carroll R. Pollicization. In: Green D, ed. *Operative Hand Surgery*. 2nd ed. New York, NY: Churchill Livingstone; 1988:2263–2280.

105. Buck-Gramcko D. Pollicization in congenital malformations of the hand and forearm. In: *Congenital Malformations of the Hand and Forearm*. London: Churchill Livingstone; 1998:379–402.
106. Upton J. Pollicization for the aplastic thumb. In: Marsh J, ed. *Current Therapy in Plastic and Reconstructive Surgery: Trunk and Extremities*. Toronto: BC Decker; 1989:232–236.
107. Huffstadt AJ, Broker FH. Arterial patterns in the hand and pollicisation. *Handchirurgie*. 1978;10:31–35.
108. Littler J. Digital transposition. *Curr Pract Orthop Surg*. 1966;3:157–172.
109. Dobyns J, et al. Congenital hand deformities. In: Green DP, ed. *Operative Hand Surgery*. London: Churchill Livingstone; 1982:277–281.
110. Buck-Gramcko D. [Pollicization of the index finger by aplasia and hypoplasia of the thumb. Indications, methods, results]. *Handchirurgie*. 1971;3:45–59.
111. Buck-Gramcko D. Complications and bad results in pollicization of the index finger (in congenital cases). *Ann Chir Main Memb Super*. 1991;10:506–512.
112. Riordan D. Technique of pollicization. In: Crenshaw AH, ed. *Campbell's Operative Orthopedics*. 5th ed. St. Louis, MO: CV Mosby; 1971:278–280.
113. Hentz VR, Littler JW. Abduction–pronation and recession of second (index) metacarpal in thumb agenesis. *J Hand Surg Am*. 1977;2:113–117.
114. Bartlett GR, Coombs CJ, Johnstone BR. Primary shortening of the pollicized long flexor tendon in congenital pollicization. *J Hand Surg Am*. 2001;26:595–598.
115. Manske PR, McCarroll HR Jr. Index finger pollicization for a congenitally absent or nonfunctioning thumb. *J Hand Surg Am*. 1985;10:606–613.
116. Blauth W. [Principles of pollicization with special emphasis on new incision methods]. *Handchirurgie*. 1970;2:117–121.
117. Buck-Gramcko D. [Pollicization of the index in case of aplasia and hypoplasia of the thumb. Methods and results]. *Rev Chir Orthop Reparatrice Appar Mot*. 1971;57:35–48.
118. Snow J, Littler J. Surgical treatment of the cleft hand. In: *Transactions of the 4th International Congress on Plastic Reconstructive Surgery*, Rome 1967. Amsterdam: Excerpta Medica Foundation; 1969:888–893.
119. Ueba Y. Plastic surgery for the cleft hand. *J Hand Surg Am*. 1981;6:557–560.
120. Tada K, Kursaki E, Yonenobu K, Tsuyuguchi Y, Kawai H. Central polydactyly – a review of 12 cases and their surgical treatment. *J Hand Surg Am*. 1982;7:460–465.
121. Buck-Gramcko D. Cleft hands: classification and treatment. *Hand Clin*. 1985;1:467–473.
122. Nutt J, Flatt A. Congenital central hand deficit. *Hand Surg*. 1981;6:48–60.
123. Matev I. [Congenital absence of the thumb]. *Z Orthop Ihre Grenzgeb*. 1966;102:166–169.
124. Kessler I, Baruch A, Hecht O. Experience with distraction lengthening of digital rays in congenital anomalies. *J Hand Surg Am*. 1977;2:394–401.
125. Goldberg N, Watson H. Composite toe (phalanx with epiphysis) transplants in the reconstruction of the aphalangic hand. *J Hand Surg Am*. 1982;7:454–459.
126. Carroll R. Insertion of toe phalangeal grafts in hypoplastic digits. In: Flatt A, ed. *The Care Congenital Hand Anomalies*. St. Louis, MO: CV Mosby; 1977:143–144.
127. Kessler I. Five-fingered hand. One-stage pollicization of the radial finger. *Isr J Med Sci*. 1970;6:280–283.
128. Baek GH, Gong HS, Chung MS, et al. Modified Bilhaut-Cloquet procedure for Wassel type-II and III polydactyly of the thumb. Surgical technique. *J Bone Joint Surg Am*. 2008;90(Suppl2 Pt1):74–86.
129. Baek GH, Gong HS, Chung MS, et al. Modified Bilhaut-Cloquet procedure for Wassel type-II and III polydactyly of the thumb. *J Bone Joint Surg Am*. 2007;89:534–541.
130. Lister G. Reconstruction of the hypoplastic thumb. *Clin Orthop*. 1985;52–65.
131. Horii E, Nakamura R, Innoye G, et al. Functional assessment for thumb hypoplasia by questionnaire. *J Jpn Surg Hand*. 1996;12:772–775.
132. Tan JSW, Tu Y-K. Comparative study of outcomes between pollicization and microsurgical second toe-metatarsal bone transfer for congenital radial deficiency with hypoplastic thumb. *J Reconstr Microsurg*. 2013;29:587–592.
133. Shibata M, Yoshizu T, Seki T, et al. Reconstruction of a congenital hypoplastic thumb with use of a free vascularized metatarsophalangeal joint. *J Bone Joint Surg Am*. 1998;80:1469–1476.
134. Tsai TM, Lim BH. Free vascularized transfer of the metatarsophalangeal and proximal interphalangeal joints of the second toe for reconstruction of the metacarpophalangeal joints of the thumb and index finger using a single vascular pedicle. *Plast Reconstr Surg*. 1996;98:1080–1086.
135. Shabata M, Yoshizu T, Seki T, et al. Reconstruction of hypoplastic thumb using toe transfer. In: Yastamaki M, ed. *Current Trends in Hand Surgery*. Amsterdam: Elsevier; 1995:467–471.
136. Gilbert A. [Current treatment of malformations of the hand]. *Chirurgie*. 1990;116:180–183.
137. Percival NJ, Sykes PJ, Chandraprakasam T. A method of assessment of pollicisation. *J Hand Surg [Br]*. 1991;16:141–143.
138. Roper B, Turnbull TJ. Functional assessment after pollicisation. *J Hand Surg [Br]*. 1986;11:399–403.
139. Sekiguchi J, Ohmori K, Kobayashi S, et al. Functional results after pollicization in congenital cases. *J Jpn Soc Surg Hand*. 1994;10:890–894.
140. Harrison SH. Pollicization for congenital deformities of the hand. *Proc R Soc Med*. 1973;66:634–637.
141. Kozin SH, Weiss AA, Webber JB, et al. Index finger pollicization for congenital aplasia or hypoplasia of the thumb. *J Hand Surg Am*. 1992;17:880–884.
142. Langlais F, Malek R. [Pollicizations in congenital malformations of the thumb. Indications, technical problems, results, apropos of 30 cases]. *Ann Chir*. 1973;27:1217–1223.
143. Sykes PJ, Chandraprakasam T, Percival NJ. Pollicization of the index finger in congenital anomalies. *J Hand Surg [Br]*. 1991;16:144–147.
144. Staines KG, Majzoub R, Thornby J, et al. Functional outcome for children with thumb aplasia undergoing pollicization. *Plast Reconstr Surg*. 2005;116:1314–1323, discussion 1324–5.
145. Aliu O, Netscher DT, Staines KG, et al. A 5-year interval evaluation of function after pollicization for congenital thumb aplasia using multiple outcome measures. *Plast Reconstr Surg*. 2008;122:198–205.
146. Netscher DT, Aliu O, Sandvall BK, et al. Functional outcomes of children with index pollicizations for thumb deficiency. *J Hand Surg Am*. 2013;38:250–257.
147. Clark DI, Chell J, Davis TR. Pollicisation of the index finger. A 27-year follow-up study. *J Bone Joint Surg Br*. 1998;80:631–635.
148. Zlotolow DA, Tosti R, Ashworth S, et al. Developing a pollicization outcomes measure. *J Hand Surg Am*. 2014;39:1784–1791.
149. Tonkin MA, Boyce DE, Fleming PP, et al. The results of pollicization for congenital thumb hypoplasia. *J Hand Surg Eur Vol*. 2015;40:620–624.
150. Erhardt R. Sequential levels in the development of prehension. *Am J Occup Ther*. 1974;592–596.
151. Goldfarb CA, Monroe E, Steffen J, et al. Incidence and treatment of complications, suboptimal outcomes, and functional deficiencies after pollicization. *J Hand Surg Am*. 2009;34:1291–1297.
152. Harrison H. Upper limb anomalies: pollicization for congenital deformities of the hand. *Proc Roy Soc Med*. 1973;66:634–638.
153. Michon J, Merle M, Bouchon Y, et al. Functional comparison between pollicization and toe-to-hand transfer for thumb reconstruction. *J Reconstr Microsurg*. 1984;1:103–112.

154. Ward JW, Pensler JM, Parry SW. Pollicization for thumb reconstruction in severe pediatric hand burns. *Plast Reconstr Surg.* 1985;76:927–932.
155. Dijkstra R, Bos KE. Functional results of thumb reconstruction. *Hand.* 1982;14:120–128.
156. Harrison SH. Pollicisation in cases of radial club hand. *Br J Plast Surg.* 1970;23:192–200.
157. Hentz VR. The surgical management of congenital hand anomalies. In: Littler J, ed. *Reconstructive Plastic Surgery*. Philadelphia, PA: WB Saunders; 1977:3306–3349.
158. De Kraker M, Selles RW, van Vooren J, et al. Outcome after pollicization: comparison of patients with mild and severe longitudinal radial deficiency. *Plast Reconstr Surg.* 2013;131:544e–551e.
159. Eaton C, Lister GD. Syndactyly. *Hand Clin.* 1990;6:555–575.
160. Netscher DT, Eladounikdachi F. Two case reports of pollicization of a previously syndactylized index finger for congenitally absent thumb. *Ann Plast Surg.* 2003;51:607–610, discussion 611–6.
161. Ekblom AG, Dahlin LB, Rosberg H-E, et al. Hand function in children with radial longitudinal deficiency. *BMC Musculoskelet Disord.* 2013;14:116.
162. Ekblom AG, Dahlin LB, Rosberg H-E, et al. Hand function in adults with radial longitudinal deficiency. *J Bone Joint Surg Am.* 2014;96:1178–1184.

Congenital hand IV: Syndactyly, synostosis, polydactyly, camptodactyly, and clinodactyly

Steven E. R. Hovius and Christianne A. van Nieuwenhoven

SYNOPSIS

- Syndactyly is one of the most common congenital differences in the upper extremity and can be classified as incomplete (soft tissue only, not extending to the tip), complete (soft tissue only, extending to the tip), complex (with distal bony union), or complicated (with more than only distal bone fusion).
- Timing of surgery depends on the fingers involved and whether the syndactyly is cutaneous or not. In the simple digit 3–4 syndactyly there is no hurry, while in the simple thumb–index syndactyly release is undertaken early. When bony fusion accompanies syndactyly (complex/complicated), these fusions should be separated early to prevent asymmetric growth if the fused fingers have different lengths.
- Creating a web and nail fold and adding skin to the inner borders of the digits in complete syndactyly are the three key elements in separating the digits.
- Poland syndrome is characterized by unilateral absence of the sternocostal head of the pectoralis muscle combined with ipsilateral short and webbed fingers. The central three digits are most affected. It can vary from a smaller hand, simple syndactyly to symbrachydactyly, up to more severe hypoplasia of the entire arm.
- Apert syndrome (acrocephalosyndactyly) is characterized by craniosynostosis with complex acrosyndactyly of both hands and feet. Common features of both hands in Apert syndrome are: brachyclinodactyly of the thumb, complex syndactyly of index/long/ring finger, symbrachyphalangism and simple syndactyly of the fourth web. Three different types of hand malformations can be recognized: the flat, “spade” hand (type I), the constricted cupped, “mitten” hand (type II), and the coalesced “rosebud” hand (type III).
- The surgical sequence in correction of Apert syndrome is release of thumb and index or deepening of the first web and separation of digit 4 and 5, followed by separation of the other digits and correction of clinodactyly of the thumb. If present, 4–5 metacarpal synostoses can be separated.
- Symphalangism is a longitudinal bony fusion of the finger and/or toe joints. In hereditary symphalangism, the proximal interphalangeal joint is mostly involved.
- In metacarpal synostosis, curvature of the epiphysis, discrepancy in length between the two involved metacarpals, and the shape of the bones will direct the choice of treatment. Surgical treatment in metacarpal synostosis is functional and aesthetic. Consultations are necessary until skeletal maturity because of angulation, length discrepancies, and rotation that can occur due to growth.
- Congenital radioulnar synostosis is less common than the post-traumatic version. In most cases of radioulnar synostosis, the proximal third is involved, with bilateral involvement in 60%. It is common in craniofacial hand disorders. Treatment is recommended in patients with a fixed pronation of more than 60° and complaints of disability in daily life.
- Polydactyly of the hand can be divided into radial, central (digit 2, 3, and 4), and ulnar polydactyly, referring to the region of the extra digit or part of a digit. It can occur isolated or syndromic. Syndromes are more associated with ulnar polydactyly than radial polydactyly. The most commonly used classification for radial polydactyly is the Wassel classification (also known as the Iowa system). Ulnar polydactyly is either classified into two or three types.
- Timing of surgery is arbitrary. Surgery is recommended in the first year of life by many authors, and depends on the severity of the condition. Floating little fingers are often removed early. At the first operation, as much correction as possible is performed on both soft tissues and bones. Correct alignment and balancing forces on the joints and bones is crucial. Growth will make insufficiently corrected tissue worse.
- Inadequate correction in proximal radial polydactyly leads to complications such as S- and Z-deformities mostly due to imbalance. In distal polydactyly it can lead to nail deformities and broadness of the distal end of the thumb.
- Triphalangeal thumb can vary from a longer thumb with deviation due to the extra phalanx to a non-opposable thumb with an inadequate first web and aberrant muscles and tendons, with the thumb in the same plane as the hand, resembling a five-fingered hand. Triphalangeal thumb can be associated with polydactyly, syndactyly, cleft hand, and longitudinal ray deficiency (e.g., Holt–Oram syndrome). It occurs isolated or as an autosomal-dominant trait.
- In less complex opposable triphalangeal thumbs, primary surgical strategies are focused on the distal two joints of the “thumb” comprising correction of deviation, reduction of additional length, and joint stabilization. In more complex non-opposable triphalangeal

thumbs, treatment not only is concentrated on the middle and distal phalanx but also on balancing of the metacarpophalangeal joint and carpometacarpal joint, together with reduction of metacarpal length up to formal pollicization. Additional polydactyly and syndactyly, if present, will also need attention.

- Camptodactyly is a contracture of the PIPJ in the anteroposterior direction (*campto* = arched; *dactylos* = finger). Camptodactyly is mostly sporadic without obvious family history. The most involved finger is the little finger, followed by the ring finger. All fingers can be involved. It can occur in the first year of life and progress further or present during adolescence. Conservative treatment is mostly advocated. Multiple surgical treatment regimens have been proposed, varying from full release, tendon transfers, and skin grafts to correction osteotomy, arthroplasty, and arthrodesis. All techniques have relative merit.
- Clinodactyly is derived from *klineia* (to bend, incline, or slope) and *dactylos* (finger, toe) and is used for a deviated finger in a radioulnar direction. The deviation is caused by an abnormally shaped bone. The middle phalanx of the little finger and the proximal phalanx of the thumb are the most frequently involved. Treatment can be a closed wedge osteotomy, reversed wedge osteotomy or an opening wedge osteotomy, with or without bone graft or a physiolysis.



Access the Historical perspective section online at

<http://www.expertconsult.com>

Syndactyly

Introduction

The distal end of the “normal” web lies on the palmar side roughly at the mid-level of the proximal phalanx.¹ A more distal web is called syndactyly. Syndactyly is one of the most common congenital hand malformations with an incidence of 1 in 2000 live births. Familial syndactyly is reported in 15–40% of syndactylies.^{2,3} They are more common in Caucasians than in people from African descent. About 50% of patients have bilateral involvement. Males are more affected than females varying from 46–84%. The incidence of ray involvement in syndactyly is in digit 3–4: 50%; digit 4–5: 30%; digit 2–3: 15%, and digit 1–2: 5%.^{1,2} It can appear isolated or in association with other deformities in the upper or lower extremity or as part of a syndrome (like Poland syndrome or Apert syndrome). Syndactyly can be associated with polydactyly and/or clefting (like in synpolydactyly, Greig syndrome, oculodentodigital syndrome and cleft hand).

Syndactyly can be classified as incomplete (soft tissue only, not extending to the tip), complete (soft tissue only, extending to the tip), complex (with distal bone union) or complicated (with more than only distal bone fusion) (Fig. 28.1).² For the first web, the terms simple, complex, and complicated are used most.

Basic science/disease process

In the developing limb bud, fingers become apparent at day 41–43 and are fully separated at day 53.^{5–7} Apoptosis is needed for separation of the fingers. This process is mediated by bone morphogenic protein 4 (BMP-4).⁸ Current understanding

relates these anomalies to differentiation disturbances in the developing hand plate.⁹

Diagnosis/patient presentation

Syndactyly can be present in a large variety of forms as it is only a descriptive term. The fingers can be normal or anomalous; the number of affected fingers can differ, as well as the nature of involvement (Fig. 28.2).

In the patient with cutaneous syndactyly, only the soft tissues between the fingers are attached. These skin bridges can vary from supple to tight, influencing surgery. In the incomplete form, the attachment usually ends just before the proximal interphalangeal joint (PIPJ). In the complete form, the nails can be separated with full pulps of the affected fingers to conjoined nails with ridges and insufficient pulp on the attached sides. If the involved fingers have normal bone structure, the joints and tendons are mostly normal. If not, like in symbrachydactyly, the tendons and joints will be affected as well as the neurovascular bundles that can divide more distally. When fingers are of unequal length, the longest finger will tend to bend and rotate more during growth especially if the distal ends are fused.

Complex syndactyly with distal bone fusion involving only two fingers can be recognized by a tapered distal end with inward rotation of the fingers and abnormally ridged or confluent nails. When more fingers are distally fused, they can be flat to very cupped with anomalous nails, abnormal bones with different lengths, and abnormally located, insufficiently developed joints.

Complicated syndactyly is characterized by an abnormal bone structure inside the syndactyly with fusions, rudimentary bones, missing bones, abnormal joints, and sometimes cross bones.^{5,10}

Patient selection

Timing of surgery depends on the fingers involved and whether the syndactyly is cutaneous or not.

Early indications for surgery are syndactylies between fingers of unequal length; and/or distal bone fusions; and in complex or complicated acrosyndactyly especially if the thumb is involved. These early indications are to prevent asymmetric growth and/or to create a possibility to grasp.¹¹ In the simple digit 3–4 syndactyly, there is no hurry.

Simple syndactyly release can be performed from 6 months onwards. Most surgeons will operate on these children between 1–2 years to prevent anesthesia problems.¹²

In complicated syndactylies for some affected rays, the support for the individual fingers is often not enough to let them function well following separation, although parents or children often request to separate these fingers. Careful assessment of the maturity of each individual finger is necessary before release of syndactyly is undertaken. The choice to separate can be extremely difficult, especially in symbrachydactyly.

Treatment/surgical technique

Treatment of syndactyly should not only address the key points of adequate release but also be achieved in the least number of operations while minimizing complications.¹² Release of syndactyly implicates separation of conjoined skin

Historical perspective

By 1801, fingers had already been separated by straight line incisions leaving the wounds to heal by secondary intention. In 1808, Rudtorffer guided a wire from dorsal to ventral between the fingers proximally creating an epithelialized sinus and then separated the fingers distally from it. In 1810, Zeller used dorsal triangular flaps to reconstruct the defect following separation to create a web. As scarring and necrotic flaps developed from these techniques, Dieffenbach performed a dorsal rectangular flap in 1845. Furthermore, Valpeau reported using stitches to separate the fingers in 1847 and Norton reported using a dorsal and palmar triangular flap in 1881. Thus, as early as the last half of the 19th century, the basic techniques of flaps for web reconstruction still used today were described. Concerning the further distal separation, Faniel described, in 1911, a Z-shaped incision to cover the defects after separation. In 1940, Cronin introduced the zigzag approach.⁴




Fig. 28.1 (A) Incomplete, (B) complete, (C) complex, and (D) complicated syndactyly. (Redrawn after Upton J. *Management of disorders of separation – syndactyly*. In: Mathes SJ (ed.). *Plastic Surgery*, Vol. 8, 2nd revised edn. Philadelphia, PA: Saunders Elsevier; 2006:140.)

and subcutaneous tissue preserving integrity of the neurovascular bundles. Furthermore, conjoined ligaments and bands and existing sites of osseous union are divided. On the dorsal side, subcutaneous fat can be removed but care has to be taken to prevent damage to the neurovascular bundle. For safety reasons, two adjacent complete syndactylous fingers are not separated at the same time as vascular anatomy can be different. In short multiple syndactylous fingers, for instance, dominant digital vessels can only exist on the lateral sides of the conjoined fingers. Sometimes it is necessary to sacrifice one of the vessels in a distal bifurcation. The nerves in these cases can mostly be dissected more proximally. In young children, bone or cartilaginous fusions can be separated by knife or osteotome.¹¹ Care should be taken to remove possible hidden polydactyly. Especially in cases where the fourth web is involved, a polydactylous distal phalanx and/or remnant of the middle phalanx can be present.

Key points in syndactyly release are^{11,13,14}:

- Creation of a web
- Treating the lateral soft-tissue defects
- Separation of the fingertips.

Creation of a web

The web in syndactyly can basically be created by a dorsal flap, a palmar flap, or a combination of both. These techniques have already been practiced in the second half of the 19th century and are still used today. To these techniques have been added flaps with slightly different design or flaps more proximal from the dorsum of the hand.^{14–19} We use a dorsal cloverleaf flap or manta ray type flap because the wings will cover partly the lateral side of the proximal phalanx and the tip is interdigitated on the palmar side, preventing linear scars in the web itself as well as palmarly. In an effort to prevent skin grafts, dorsal metacarpal flaps have been used to create the web, followed by primary closure of the fingers




Fig. 28.2 (A) Nearly complete syndactyly, (B) complex syndactyly radial side, and (C) complicated syndactyly.

(Fig. 28.3).^{18–20} In order to prevent web creep in the future, we advise the use of a dorsal flap that will cover the newly made web without scars that might interfere during growth. In addition, appearance of the hand is important. Visible skin grafts on the dorsal hand will darken in time, and are experienced as aesthetically less pleasing by patients. Therefore, we advise choosing a flap that will allow for primary closure on the dorsal hand and fingers with the skin grafts at the mid-lateral sides of the fingers, if grafts are needed at all.

For the first web, different kinds of Z-flaps (four flap, double, double opposing, five flap) or transposition flaps from the dorsum of the hand and index or thumb are used depending on the width and deepness of the created defect following release. Also pedicled flaps and free flaps have been advocated for the larger defects.²¹ In the first web, the release of the tight fascia on the first dorsal interosseous muscle in combination with the fascia on the adductor muscle is essential to create a

deeper web. Sometimes even the insertion of the adductor muscle is shifted more proximally to open the web.

Upton has published an excellent overview of all the different flaps for web reconstruction.⁵ For incomplete syndactyly, many variations of rotating Z-flaps have been described for web reconstruction (Fig. 28.4).²²

Treating the lateral soft-tissue defects

In syndactyly, the shortage of skin is very often underestimated. In the regular simple syndactyly, skin shortage is at least 36% of the circumference of the finger that is separated. Cronin has popularized the zigzag skin separation distal to the flap for web reconstruction.²³ The created triangular flaps provide coverage at the PIPJ. The triangular flaps can either be fully or partially interdigitated depending on the extent of the skin shortage. In this way, the areas for skin grafting can



Fig. 28.3 Release of complete syndactyly with dorsal cloverleaf flap. (A) Proximal dorsal triangles can be closed primarily. (B) Interdigital flaps are approximated, additional skin grafts applied, and direct closure at the nail wall is performed. (C) Note web flap.

be diminished and placed on less demanding parts of the fingers. Full-thickness skin grafts (FTSG) are mostly used to cover the defects (Fig. 28.5). They can be taken from the groin more laterally to prevent later hair growth on the grafts or from other sites like the inner side of the upper arm or from the cubital fossa. Also thicker split-thickness skin grafts (STSG) can be taken from the non-weight-bearing part of the sole of the foot. Withey *et al.* used only STSGs at the proximal base of the inner sides of the released fingers together with a

large number of triangular flaps. The remaining defects were left open resulting in good scars.²⁴

Separation of the fingertips

If the nails are separately developed in complete syndactyly, the pulp can be separated and the skin advanced to the rim. If the nails are partly fused with a deep furrow and indentation on the pulp side, then simple separation and primary



Fig. 28.4 (A,B) Incomplete first web release with five-flap Z-plasty.




Fig. 28.5 Release of complex syndactyly of digit 4 and 5. **(A)** Note also ulnar polydactyly; **(B,C)** with 10-year follow-up.

closure is often still possible. If the nails are conjoined, with hardly or no ridge, nail wall reconstruction with flaps is necessary. Buck-Gramcko has introduced the pedicled pulp flaps for nail wall reconstruction from the adjacent finger pulp.²⁵ The disadvantage of these flaps is the sometimes thinner fingertips. Alternatives are the use of a thenar flap, but this has the disadvantage that the finger has to be supple to reach the thenar easily and it is a two-stage procedure.²⁶

Surgical pearls

Desyndactylization

- Choose a flap without scars in the web, i.e., dorsal cloverleaf flap or manta ray type flap.
- Perform primary skin closure on dorsal part fingers and hand.
- Reconstruct nail walls with pulp flaps if a confluent nail is present.
- Use full-thickness skin grafts for defects, preferably situated at the midlateral area of the fingers.
- Take time to suture the skin; time spent will contribute to the result.

Postoperative care

Perioperative paraffin gauze is applied on the wounds and grafts, followed by moist dressings, synthetic cotton, and an elastic bandage. The elbow, forearm, and hand are subsequently covered with a longitudinal adhesive bandage to prevent removing the dressing. The general consensus among most authors is to perform wound inspection in the first 2 weeks after operation.^{14,25}

In the last 5 years, we introduced a 6-week regimen with fewer complications and a lower workload for the doctor and, more importantly, for the parents. Most additional procedures

needing immobilization are covered in this 6-week time span. Only one direct postoperative outpatient clinic contact is needed before starting hand therapy (if necessary). Further immobilization is dependent on surgery for associated malformations.

Outcomes, prognosis, and complications

Outcome can be related to web creep, scarring, graft-take, rotation, deviation and loss of function.

Early complications can be skin slough, flap necrosis, infection, and up to nearly complete adhesion of fingers.

Web-creep has been reported to be from 0% to 12% depending on the technique used, the long-term follow-up, and the variety of included patients. Re-operations have been performed for web creep in up to 8% of patients.^{20,27–30}

With regard to skin grafts, FTSGs have a better skin quality than STSGs; they can also create problems such as graft loss; skin contracture; web creep; hair growth; hyperpigmentation, and hypertrophic scarring.^{19,25,31–35}

Skin contractures in using STSGs are reported to occur in 40%, while this occurs in only 22% when using FTSGs.³³ Flexion contractures are reported in a series with long-term follow-up to be 13% and rotation and lateral deviation in 12%.³⁶ Hair growth when using FTSGs from the groin is reported as being 71%.³⁰ Leaving small areas open between numerous triangular flaps seems to result in less scarring and there is no difference in web creep versus the classical approach.²⁴ The choice of donor site for skin grafts depends on the amount needed. If little donor site skin is needed, we will use the wrist crease or elbow crease. This skin is more like the skin of the hand. Scars are placed in the crease, and over time, they become inconspicuous. We do not use groin skin anymore but, instead, skin at the abdominal fold in cases where a substantial amount of skin is needed (for example, Apert syndrome or multiple desyndactylized fingers). The scar will be hidden by regular underwear, and the skin is less




Fig. 28.6 Resyndactyly following separation. Note initial operation with separation 3–4 instead of starting with 2–3 and 4–5 at (A) the first operation and (B) long-term follow-up following re-separation.

hair-bearing or pigmented than groin skin. Moreover, if skin is needed in multiple operations over time, there is an almost unlimited possibility to harvest skin at this site.

In a group treated with dorsal metacarpal flaps or extended dorsal interdigital flaps and primary closure, results were better, avoiding all the problems with skin grafts.^{18–20}

In complex and complicated syndactylies following separation, rotated and deviated fingers can occur, as well as insufficient functioning of the individual separated fingers. Joint instabilities are also possible and may be underestimated. This is, however, a consequence of the initial deformity and is difficult to treat.

Patients should be followed till the end of growth to detect later problems such as web creep, scar contractures, and bony deviations due to different types of delta phalanges. Re-do releases of residual syndactyly is often undertaken, especially at the first web in more complex cases (Fig. 28.6).

Secondary procedures

Secondary procedures are: scar contracture release and re-deepening of webs with or without flaps. In complicated syndactylies, ligament reconstructions, osteotomies, chondrodesis, and arthrodeses may be necessary.

Poland syndrome

Introduction

The reported incidence of Poland syndrome is approximately 1 in 7000–100 000. There is a male predominance, especially in sporadic cases, and the right side is involved in 60–75% of the cases. In females, however, the left and right side occurrence is almost equal. In familial Poland syndrome, the male:female ratio and side predominance is the same.

History

In 1841, Poland³⁷ described cadaver findings as a student demonstrator of anatomy. He reported deficiency of the external oblique muscle, absence of the sternal and costal portion of the major pectoral muscle, as well as absence of the minor pectoral muscle and portions of the serratus magnus muscle. In the ipsilateral shorter hand, all middle phalanges were absent except for the middle finger, with webbing between the proximal phalanges. However, absence of the pectoral muscle without a hand deformity has been described in 1826 by Lallemand, and Froriep was the first to point out the combination of absence of the pectoralis muscle together with ipsilateral syndactyly in 1839.³⁸

Basic science/disease process

Several mechanisms in the pathogenesis of Poland syndrome have been described. Despite some familial occurrence, no inheritance patterns have been determined. The most prevailing theory focuses on the interruption of blood supply to the limb bud in the sixth week of gestation. The interruption will cause hypoplasia to the ipsilateral subclavian artery or one of the branches^{39,40} determining the diversity of the defect. However, although most prevailing, this theory is now disputed.

Diagnosis/patient presentation

In Poland syndrome, patients present with a broad range of ipsilateral trunk, upper limb, and hand anomalies. The classical presentation comprises a combination of absence of the sternocostal portion of the pectoral major muscle, hypoplastic arm, and a hypoplastic hand with a simple syndactyly usually of all webspaces (Fig. 28.7). The thoracic deformities might range from the classical absence to complete hypoplastic shoulder girdle with involvement of the ribs and nipple, scoliosis, and seldom dextrocardia.^{41,42} Furthermore, Poland syndrome can be associated with multiple other malformations, ranging from craniofacial, internal organs, to the lower extremity.^{43,44}

Patient selection

Because of the variety in clinical presentation in Poland syndrome, each treatment is individualized, based on the functional and aesthetic possibilities.

Treatment/surgical technique

Because of the wide scope in presentation of the syndactyly and symbrachydactyly, several treatment options are possible.



Fig. 28.7 Symbrachydactyly and pectoralis major anomaly and smaller breast on the right side.

Reconstruction of the breast, deficient muscle contour, or chest wall deformity is beyond the scope of this chapter.

Postoperative care

See Chapter 27 for symbrachydactyly treatment.

Outcomes, prognosis, and complications

Outcome is very much related to the original defect and the reconstruction used.

In syndactylous hypoplastic fingers, the separated individual fingers can be less functional than before the operation, resulting in poor outcome. Normally, similar outcome and complications occur as in syndactyly and symbrachydactyly. For prognosis and complications on non-vascularized and vascularized toe transfers, see Chapters 14 and 27.

Secondary procedures

The secondary procedures relate to the broad variety of treatment options available for the treatment of the hand in Poland syndrome. Secondary procedures are mostly re-deepening of scarred webs. If tightened ligaments become lax, arthrodesis of the unstable joint can be done after the growth plate is closed.

Apert syndrome

Introduction

Acrocephalosyndactyly syndrome is characterized by craniosynostosis combined with acrosyndactyly (distal part of the

fingers fused) and symphalangism (congenital ankylosis of the proximal phalangeal joints) of the index, long, and ring fingers of both hands and a radial clinodactyly of the thumb in a symmetrical way. The little finger is usually the best finger with a simple syndactyly at the fourth web. Both feet are also affected.

The birth prevalence of Apert syndrome ranges from 7.6 to 22.3 per million live births, the lowest incidence being in Hispanics and the highest in Asians. Males and females are equally affected.⁴⁵ In the authors' series, the male:female ratio was 1.5:1.

The craniofacial features in Apert syndrome consist of a variety of skull deformities originating from premature closure of the coronal and often lamboid sutures of the skull, and a midface hypoplasia. These deformities can lead to a high incidence of intracranial pressure and obstructive sleep apnea. Craniofacial operations include early cranial vault expansion and, if indicated, midface advancement is performed later in life. Other differences are an oily skin, hyperhidrosis decreased eyesight and hearing, and increased strabismus. Children often display impaired language development and motor skills.

In the lower extremity, the hips become increasingly stiff over time. The knees demonstrate mild to moderate genu valgum. The feet have simple and complete syndactyly. If present, medial polydactyly is mostly at the base of the first metatarsal. The foot deformity causes shoe-fitting problems and an abnormal gait, and possible pain due to calluses over the prominent second and third metatarsal heads. The acrosyndactyly of the feet is encountered less in contrast to the hand. However, the problems caused by the foot deformity in Apert disease is more appreciated. In recent years, treatments have been introduced to improve the aspect of the foot by desyndactylization in the less severe cases and osteotomies to address to the pronouncing metatarsals at the ball of the foot and the malformation of the calcaneal bone.

History

Apert, a French physician in Paris, described nine collected cases in 1906, but probably Wheaton was the first to describe it in 1894.^{46,47}

Basic science/disease process

Apert syndrome is caused by a mutation in the gene encoding fibroblast growth factor receptor 2 (FGFR2). The gene map locus is 10q26. Two mutations are well recognized and are related to substitutions at two amino acid positions P253R and S252W in FGFR2. The more severe type of Apert hand is mostly related to the P253R mutation. In our series, nearly all type III Apert hands were attributed to this mutation. Most cases are sporadic, but autosomal-dominant inheritance has been reported.^{48,49}

Diagnosis/patient presentation

In the Apert syndrome child, the level of function depends more on his/her intellectual capacity than the severity of extremity involvement. Most Apert children are capable of self care over 5 years of age. Regarding the upper extremity, motion of the shoulder is not normal and decreases with age. In the older Apert patient, a marked deltoid muscular atrophy

is often encountered. These patients appear to have anterior subluxation of the humeral head.⁵⁰ The elbow deformities can differ more extensively between these patients than at the shoulder. Elbow function can be slightly decreased, but mostly do not worsen over the years.⁵⁰

Upton has classified the Apert syndrome hand into types I, II, and III for ease of clinical decision-making (Table 28.1). In the type I hand, there is a radially deviated small thumb with a shallow first web. The index, long, and ring fingers display complete or complex syndactyly. The little finger is attached by a simple complete or incomplete syndactyly and can mostly move at the distal interphalangeal joint (DIPJ). The metacarpophalangeal joints (MPJs) have adequate range of motion. In the type II hand, the thumb is radially deviated and has an incomplete or complete simple syndactyly with the index. The index, long, and ring fingers are distally fused, creating a curve in the palm with divergent metacarpals. The little finger is attached to the ring with a mostly complete but simple syndactyly.

In the type III hand (“rosebud” hand), the thumb, index, long, and ring fingers are distally fused either by cartilaginous or bony attachments. The thumb can be very difficult to identify separately from the index. The little finger is united to the ring by simple complete syndactyly. The nails can be confluent or have ridges indicating the distal finger underneath. Proximal synostosis at the base of the fourth to fifth metacarpal can be present, as well as carpal fusions.⁵¹ In the authors’ series of 66 patients, the ratio of type III : type II : type I hands was 4 : 3 : 3; although Upton reports that type III is the most uncommon.

Up to 7% ulnar polydactyly has been reported.⁵² In the authors’ series, there is one case of a duplicated distal phalanx of the index and two cases of duplication at the little finger (5%). In the type III hand, finger nails growing through surrounding skin causing frequent paronychial infections is frequently seen.

The flexion creases are often absent. Dimples on the dorsum indicate the MPJs. Distal to the MPJs, neurovascular structures can vary considerably in branching, or are absent. Distal in the hand, tendons can have a different shape and course. In most cases, either the pulley system is hypoplastic or absent. Regarding the thumb, adduction, palmar abduction, and flexion are mostly present. The first dorsal interosseous is hypertrophic and fan shaped, extending to the delta phalanx of the thumb in the more severe types. The abductor pollicis brevis muscle (APB) is anomalous as it inserts into the radial

aspect of the distal phalanx of the thumb causing radial deviation.⁵³ Lumbricals, if present, act as MPJ flexors. The hypothenar muscles are present and normal.

The proximal phalanx of the thumb is abnormal and triangular shaped. The interphalangeal joint (IPJ) and the carpometacarpal joint (CMCJ) have little motion, while the MPJ is mobile. With skeletal maturity, the IPJ fuses after first being segmented. The distal phalanx and nail matrix are broad.^{54,55}

Symphalangism at the proximal interphalangeal joints of the index, long, and ring finger is a persistent finding. In border digits (the index and the fifth), the epiphyseal growth plate can be aberrant at the MPJ causing lateral deviation following separation.

Patient selection

Many articles have been published on treatment timing in Apert syndrome.^{51,54,56–58} Most philosophies try to diminish the number of operations by releasing as many fingers as possible in one session. The way this is accomplished varies among authors (Table 28.2).

Treatment/surgical technique

Separation of thumb and fingers, correction of thumbs, and mobilization of the little finger in as few operations as possible is the surgical goal. The authors’ preferred method is illustrated in Table 28.3 and Figs. 28.8 and 28.9.

Separation of fingers

Mostly dorsal flaps are used to create webs. For the remaining distal syndactyly, fingers can be separated by zigzag or straight incisions in the fingers with symphalangism. Nail walls can be reconstructed with flaps from the adjacent finger pulp.

The residual defects are covered with skin grafts. Chang only used local flaps and skin grafts, while Zuker *et al.* and Kay use groin flaps for the central digits and the first web, respectively.^{21,56,58} Often further corrections are necessary to deepen webs.

Habenicht uses small external fixators to transversely distract the complicated and complex syndactyly of the central fingers, with separation of the distal bone fusions. The created skin is used for coverage of the defects instead of skin grafts. Other methods such as silastic sheets and tissue expanders to separate fingers have been discarded.⁵⁹

Table 28.1 Common features of hands in Apert syndrome			
Type	Thumb	Digit 2, 3, 4	Digit 5
Type I	Brachyclinodactyly Incomplete 1st web syndactyly	Symphalangism Complex syndactyly	Simple (incomplete) syndactyly of 4th web or separate digit MC 4–5 synostosis possible
Type II	Brachyclinodactyly Simple (incomplete) syndactyly	Symphalangism Complex syndactyly	Complete syndactyly Duplication P3 possible MC 4–5 synostosis possible
Type III	Brachydactyly Complex syndactyly Paronychial infections Skin maceration	Symphalangism Complex syndactyly Paronychial infections Skin maceration	Complete syndactyly Duplication P3 possible MC 4–5 synostosis possible
MC, metacarpal; P3, distal phalanx.			

Table 28.2 Reported treatments in Apert syndrome				
Zuker <i>et al.</i> ⁵⁶	Upton ⁵¹	Fearon ⁵⁷	Guero ⁵⁴	Chang <i>et al.</i> ⁵⁸
First stage				
Bilateral 3 months of age	Bilateral 1–6 months of age	Both hands and feet 9–12 months of age	Bilateral 9–10 months of age	Bilateral 6–15 months of age
1st-web four-flap Z-plasty or dorsal skin flap web-index 2nd and 4th-webspace with dorsal flap	1st-webspace with dorsal skin flap Resection index 4th-web release Incision of nailfold/ macerations	Deepening of 1st-web and 3rd-web one hand Release of 2nd- and 4th-web on other hand Similar releases on feet	1st-web release with Buck-Gramcko flap Release APB Release of 4th-web for a three-fingered hand Release of 3rd-web for a four-fingered hand	Release of border digits
Second stage				
Unilateral Before age 3	Within 6 months of 1st stage Unilateral Before 3 years of age	3 months after 1st stage	Unilateral; 6 months between unilateral stages	Unilateral Before age 2; 3 months between unilateral stages
Groin flap in 3rd-web if necessary	Long-ring release Re-deepening 1st-web	Release of the remaining webs on both feet and hands	In four-fingered hand: release of 4th-web In three-fingered hand: release of 2nd-web, removal of 4th ray	Release of middle digit mass Excision of bone, leaving three digits Opening wedge osteotomy thumb clinodactyly
Goal				
Four fingers and thumb		Two-stage syndactyly release of all fingers and toes	Three/four fingers and thumb	Three/four fingers and thumb
Additional				
	4–6 years	9–12 years		
	Metacarpal synostosis correction Thumb clinodactyly correction Re-deepening 1st-web	Dorsal osteotomies at “PIP” for anatomic position Correction of radial clinodactyly Addressing foot disorders if present		
APB, Abductor pollicis brevis muscle; PIP, proximal interphalangeal joint.				

Table 28.3 Apert syndrome – authors' preferred treatment			
Stage	Age	Procedures	Types
First	3 months	Both hands Thumb separation with dorsal cloverleaf flap with straight line incision distally 1st-web deepening with double-opposing Z-plasty Index amputation if necessary 4th-web separation with cloverleaf flap with straight line incision distally 2nd, 3rd, 4th distal digit separation with modified Buck-Gramcko flaps 2nd-web separation with cloverleaf flap with straight line incision distally Skin release radial side thumb with Z-plasty and release of APB Open or reversed wedge osteotomy of clin odactyly of thumb	All types Type II and III Type I Only severe type III All types Only type III Type I and II Type I, II, III Type I, II, III
Second	12 months	One hand Separation of 3rd-web with cloverleaf flap with straight line incision distally Separation of 2nd-web with cloverleaf flap with straight line incision distally Re-deepening of the 1st-web Synostosis MC4–5 (excised bone can be used for the wedge osteotomy of thumb	In all types In type I, II, and if amputation index in III If no amputation in type III If necessary in all types If present
Third	<24 months	Same as second stage, on contralateral side	




Fig. 28.8 (A) Apert hand: left, dorsal view; (B) right hand, palmar view; and (C) postoperative result at 18 years of age.



Fig. 28.9 (A) Apert type III hand, left. Long-term follow-up: (B) left hand, dorsal view; and (C) right hand, palmar view. The second ray was amputated because of a very narrow web, shortage of pulp of the index finger and severely rotated and deviated bony structures.

Thumb and first web

A well-separated thumb is crucial in these hands. In a shallow first web (in the type I hand), a four- or five-flap Z-plasty can be utilized. In a complete or nearly complete syndactyly (in the type II hand), a large dorsal flap is used to create a first web.⁶⁰ Tight fascia around the adductor muscle is released to open up the first web.

Preferably, a hand with four fingers and a thumb is created. In the type III hand, however, it can be necessary to sacrifice the index to create a useful first web with a dorsal flap^{61,62} (Fig. 28.9).

Clinodactyly of the thumb is often corrected in the second stage because of more skeletal maturity. The tight skin on the radial side at IPJ level can be released with a Z-plasty. The APB is released from the distal phalanx. The triangular bone is treated as in clinodactyly (see below). There is a tendency to treat the thumb clinodactyly and APB release at the first operation, interfering the pull of the APB on the deviation of the thumb as soon as possible.

Dao *et al.* considered the abnormal radiodistal insertion of the APB responsible for the deviation of the thumb, and released the APB muscle and tendon distally without performing a corrective osteotomy.⁵³ In the type III hand, the thumb is short and has less bone volume distally; therefore, an opening wedge osteotomy is performed, secured by a longitudinal K-wire. Due to the increased bony healing in Apert disease, this will suffice.

Additional procedures

Synostosis, if present, at the proximal fourth–fifth metacarpal should be separated early to improve function of the fifth ray in this rather stiff hand. Aberrant growth plates at the index and little finger can cause clinodactyly after separation. Wedge osteotomies may be needed secondarily to correct this deviation. Even without aberrant growth plates, the border digits tend to laterally deviate. Lengthening procedures of the fingers and especially the thumb are performed to improve appearance, and also function in type III hands with short thumbs.

Postoperative care

Postoperatively, the hand is carefully dressed and covered by a small plaster splint. Over this plaster, a completely covering adhesive bandage is applied preventing elbow extension. At the outpatient clinic 6 weeks later, the hand is inspected and if wound healing is achieved after 6 weeks, the hand(s) can be used. Despite the skin abnormality in Apert syndrome, no additional problems are seen using this bandage regime.

Outcomes, prognosis, and complications

Hand function is improved the most if the thumb is separated together with separation of the little finger, as it is the best finger. In this way, the thumb can adduct powerfully with the ulnar proximal part of the thumb. Also, a sort of tripod pinch with the more mobile little finger is ensured. Movement of the fingers, except the little finger is only at the MPJ. Lengthening of the thumb and separation of the remaining fused fingers does not improve function considerably; however, it is requested to improve the appearance.

Complications

The hyperhidrosis and oily skin makes the skin grafts prone to maceration, skin slough, and even infection. Barot and Caplan reported a 22% partial skin graft loss.⁶³ Guero operates on these children in winter, to diminish sweltering bandages and casts.⁵⁴ Secondary procedures for web contractures are therefore common. The revision rate for secondary web contracture varies among authors from 3% to 18%.^{54,57,58,63} In the authors' series, there has been 13% secondary contracture release. Revising web contractures depends very much on the surgeon's idea of contracture. Patients rarely complain of web contractures. The author tends to deepen the first web more if syndactyly release of the fingers is planned. Other described interventions are amputation of a finger due to limited opening of the first webspace or because of ankylosis.⁵⁴

Secondary procedures

Secondary operations include:

- Web deepening with advancing of the primary flap or skin grafting the newly created defect.
- Wedge osteotomies of the border digits as necessary to correct the deviation following separation due to partial closure of the epiphyseal plate.
- Extra thumb lengthening is sometimes required in very short thumbs in type III hands.

Synostosis

Introduction

Synostosis is derived from the Greek: *syn* = together, *osteon* = bone; it is defined as a union of two or more adjacent bones. Abnormalities in union of the bones of the upper extremity occur at all levels because of a failure of segmentation. Fusions may occur at more than one level. For instance in Apert syndrome, symphalangism in conjunction with metacarpal synostosis and carpal fusion may also occur. Most synostotic differences present with another condition. The presence of a synostotic anomaly does not necessitate surgical treatment, but is dictated by functional needs and aesthetics.

Symphalangism was first described by Cushing as an autosomal-dominant genetic skeletal disorder⁶⁴ and is characterized by longitudinal bone fusions along the finger and toe joints. Most commonly, the PIPJ is fused. Associated bone fusions are carpal or tarsal synostosis, and stapes fixation resulting in conductive deafness. Flatt and Wood⁶⁵ classified the congenital difference as true symphalangism with normal length of digits; with symphalangism in symbrachydactyly; or associated with other anomalies (i.e., Apert or Poland). The incidence of true symphalangism is 0.03–4%.⁶⁰ Because of the conjunction with other conditions, the general incidence of all types of symphalangism is not known.

Metacarpal synostosis is a rare congenital anomaly, with wide anatomical variations. The fourth and fifth metacarpals are usually affected. The synostosis is more common in patients with a craniofacial and hand difference. Incidences in a large group of congenital hand anomalies range from 0.02%⁶⁶ to 0.07%.⁶⁷ Buck-Gramcko and Wood distinguished three groups based on the length of fusion: type I, fusion at the base;

type II, fusion of about half; type III, more than half; IIIa, separated metacarpophalangeal joints (MCPJ); and IIIb, common MCPJ.⁶⁷ A classification, useful for treatment, has been proposed by Foucher *et al.*⁶⁸ It comprises the shape of the synostosis, the growth direction of the epiphysis, the deformity of the finger distal from the synostosis, the webbing, and the hypoplasia of the metacarpal bone.

Carpal coalitions are reported rarely, and often go unnoticed. All combinations of carpal fusions have been mentioned, with the most frequent synostosis being between the triquetrum and lunate, and the hamate and capitate.^{69,70} In a predominantly white population, an incidence with a range of 0.07–0.1% has been mentioned,^{71,72} compared with 8% in a Nigerian population. Despite the fact that coalition will theoretically impair the movement of the wrist, no disabilities have been described.

Radioulnar synostosis is a rare upper limb malformation and is defined as a fusion of the proximal ends of the radius and ulna, which will prohibit normal rotational movement of the radius around the ulna. Radioulnar synostosis can be unilateral or bilateral (60%), of autosomal-dominant inheritance, or associated with other congenital differences. In one-third of cases, syndromes and anomalies are listed.^{5,73,74}

History

The term symphalangism was used by Cushing in 1916,⁶⁴ describing a family with dominant inherited ankylosis of the PIPJs of the hand. One year later, Drinkwater reported the anomaly as “Talbot fingers”, because of the digital anomaly in the Talbot family in England in 14 generations. Today, the term “symphalangism” is used in isolated finger deformities as well as in concurrent anomalies or syndromes.

Metacarpal synostosis was recognized and illustrated by Kelikian,⁷⁵ and is known throughout history by several names, such as fifth ray anomaly, congenital metacarpal malformation, absent fifth metacarpal, bilateral ulnar thumbs, and congenital fusion.

Radioulnar synostosis was first described by Sandifort in 1793, and in 1932, Fahlstrom⁷⁶ reviewed 185 reported cases since the first description.

Basic science/disease process

Mutations in genes involved in limb development and mutations in the *Noggin* gene (*NOG*) have been associated with synostosis. An interruption of apoptosis responsible for the segmentation is believed to be the most common cause for synostosis. The gene responsible for the hereditary form of symphalangism (*SYM* or *SYM1*) is the *NOG*, which maps to human chromosome 17 (17q21–q22).⁷⁷ Mutations in *HOXA11* are associated with radioulnar synostosis.

Diagnosis/patient presentation

In hereditary symphalangism, the PIPJ is the most commonly involved joint with a compensatory movement in the DIPJ and normal movement of the MPJ. The DIPJ is involved in symbrachydactyly. At physical examination, the fingers are slender, with atrophic skin, and the flexion creases are absent at the involved joints. The anomaly presents at one or more fingers, from ulnar to radial. The thumb is seldom involved. In radiographic examination of the child's hand, a pseudo

joint can be visible, represented by the cartilaginous bar between the two bones. Later in life, radiographs will show a minimal joint space due to full coalition at the joint.

In metacarpal synostosis, the most common fusion is between the fourth and fifth metacarpals (Fig. 28.10A). A short and abducted little finger is seen in these cases. However, the extent of deformity is dependent on the plane of the joint space and the configuration of the epiphysis of the involved metacarpal heads. A radiograph will give insight into the skeletal abnormality and will guide in the abnormalities of soft-tissue alignment.

Patients with radioulnar synostosis (Fig. 28.10B) will present within the first 3 years of life because of the inability to perform tasks in daily life such as holding objects two-handed. In severe cases, they will hyperabduct their shoulder, and compensate with a hypermobility of the wrist for the excessive pronation.



Fig. 28.10 (A) X-ray of metacarpal 4–5 synostosis. (B) X-ray of bilateral carpal and radioulnar synostosis.

Patient selection/treatment/surgical technique

The treatment of symphalangism is mostly conservative. Because of anomalies of the flexor and extensor tendons, early surgical intervention is not successful. In well-segmented joints only, exploration and release of the collateral ligaments and dorsal capsule may improve function; however, results are not predictable. Arthrodesis in a more functional position of the involved joints at skeletal maturity will improve function and grip. Distraction lengthening of the stiff fingers in symbrachydactyly may improve the pinch between the thumb and a short index finger. It can lead to possible better aesthetics; however, the treated fingers can become thin and stiff.

The indications for treatment of a metacarpal synostosis are both functional and aesthetic, and depend on the type of fusion. The abducted little finger may get caught in pockets and therefore be a problem. The goal of treatment will be a longitudinal, axially oriented ray with the MCP joint in line with the other joints, preserving its motion and joint surface, and correction of angulation and rotation. Less functional digits should be positioned out of the way of the thumb to little finger prehension.⁵ Several operative treatments have been advocated, depending on the type of synostosis^{5,68} ranging from osteotomy alone^{68,78} to lengthening with bone graft or callodistractor^{5,68,79} and longitudinal splitting combined with an interposition bone graft.⁵

Carpal synostosis will only need treatment in painful fibrocartilaginous coalition. If this is the case, it is advised to fuse the involved carpal bones.

In radioulnar synostosis, only few patients will need surgery because patients will compensate with wrist and shoulder movement. Treatment is recommended when a patient is compromised in daily actions with a fixed pronation of 60° or more in unilateral and bilateral cases.

To restore movement, longitudinal osteotomy at the fusion site in combination with a vascularized adipofascial flap and alignment of the radial head⁸⁰ has been performed. Several types of osteotomies have been described. Only resection of the synostosis is disappointing with rapid re-fusion as a result. To prevent re-fusion, the anconeus muscle has been used, as well as pedicled and free vascularized fat flaps.^{80,81} Derotational osteotomies are performed just distal to the fusion,⁸² or at the proximal radius and distal ulna.^{83,84}

Postoperative care

In symphalangism, postoperative treatment consists of passive movement of the released joints. When an osteotomy is performed, treatment should be focused on the type of fixation. If a metacarpophalangeal joint is released, with or without additional tendon transfers, these should be addressed accordingly.

Outcomes, prognosis, and complications

In most of the cases, metacarpal synostosis will not need treatment. If treating metacarpal synostosis, early problems are the diminished metacarpophalangeal movement, mostly present preoperatively, and insufficient alignment of the involved digits in metacarpal synostosis. Late problems may be a recurrent abduction of the little finger, and a re-ankylosis at the osteotomy site, despite interposition.

In radioulnar synostosis, improved function and decreased musculoskeletal discomfort in adjacent joints are reported, with up to 80% having good to excellent results.⁸⁰ As mentioned earlier, even with an interposition graft, re-ankylosis is possible with increased pronation. Neurologic and vascular compromise, and Volkmann ischemic contracture have been reported,⁸⁵ especially in cases of longitudinal osteotomy at the fusion site. This should be avoided by monitoring the degree of rotation and removing a segment at the osteotomy site.⁵

Secondary procedures

Secondary procedures performed on metacarpal synostosis and radioulnar synostosis are re-operations because of incomplete correction, re-ankylosis, or loss of motion. Because of the influence of growth, children should be observed until skeletal maturity, especially in metacarpal synostosis. Less motion in the metacarpophalangeal joint should also be addressed.

Polydactyly

Introduction

Polydactyly (*poly* = more; *dactylos* = finger) refers to the disorder in which patients have more than five digits on at least one extremity. Together with syndactyly and camptodactyly, it is the most common congenital upper extremity difference. The disorder is easily detected leading to cosmetic concern of the parents and, if not treated, cosmetic concern of the affected child. Additionally, depending on the level of the duplication, it can cause functional impairment. Polydactyly of the hand can be divided into radial, central, and ulnar polydactyly, referring to the region of the extra digit or part of a digit.⁸⁶

The incidence of polydactyly varies depending on the studied population. Region, race, and combined numbers of all polydactylies, or only radial- or ulnar-sided polydactyly, provide very different incidences in published series. The incidence can range from 2% to 30% when considering all types of polydactylies and up to 40% in the Chinese population. The prevalence of polydactylies is 10.7 of 1000 live births in people with an African descent compared with 2.5 of 1000 live births in Chinese people and 1.6 of 1000 live births in Caucasians. Ulnar polydactyly is 10 times more common in those of African descent and twice as common in males, whereas radial polydactyly is more common in Asians. Central polydactyly is extremely rare in all published studies.

At the authors' center, out of 200 new patients per year with congenital hand deformities, about 15% have polydactyly, including 50% with radial polydactyly, 9% with central polydactyly, and 33% with ulnar polydactyly (some in combination). In the authors' series, 42% of polydactylies are bilateral.

Radial polydactyly is mostly isolated, whereas syndromic association is more common in ulnar polydactyly. Furthermore, ulnar polydactyly is mostly bilateral and can be associated with syndactyly and polydactyly of the feet. Children born to parents with nubbins or floating little fingers inherit the same type of polydactyly. Children born to parents with more developed extra little fingers can present with all types of polydactyly.⁸⁷

Many syndromes have been described in combination with different kinds of polydactyly. Already, over 97 genetic

Table 28.4 Common syndromes associated with polydactyly

Syndrome	Hand difference	Concurrent symptoms
Radial polydactyly		
Holt–Oram	Hypoplastic thumb to bifid thumb Different anomalies of the upper limb, unilateral or bilateral	Cardial abnormalities
Fanconi anemia	Variety of radial differences of the hand Radial dysplasia	Pancytopenia, abnormalities of heart, lungs, kidneys and digestive tract, deafness, eye/eyelid problems, short stature
Townes–Brocks	Polydactyly	Imperforate anus, abnormally shaped ears, kidney abnormalities, hearing loss, heart defects, genital malformations
Ulnar polydactyly		
Bardet–Biedl	Ulnar polydactyly in majority of cases, might be in combination with syndactyly	Poor vision, reduced or loss of smell, cardiovascular disease, urogenital disease, mental and growth retardation, obesity
Smith–Lemli–Opitz	Polydactyly Syndactyly of second and third toe	Microcephaly, mental retardation, malformations of the heart, kidneys, gastrointestinal tract and genitalia
Trisomy 13	Polydactyly Abnormal palm pattern, overlapping fingers over thumb	Microcephaly, mentally and motor challenged, eye defects, meningomyelocele, rocker-bottom feet, cutis aplasia, cleft palate, urogenital defects, heart defects
Combined polydactyly		
Greig syndrome	Variety of polydactyly with or without syndactyly, broad thumbs	Ocular hypertelorism, macrocephaly Polydactyly of the feet (medial and/or lateral)

syndromes have been associated with polydactyly.⁸⁸ In syndromes, there may be anomalies of the hands and feet. Moreover, combinations of polydactyly in the hand can occur, such as radial with ulnar, and central with ulnar. In the Greig syndrome (cephalopolysyndactyly), polydactyly can occur in any combination. For common syndromes associated with polydactyly, see Table 28.4.

A separate entity is the mirror hand or ulnar dimelia. In the forearm, two ulnae exist without a radius. Because the medial side is a mirror image of the lateral side, the term mirror hand became popular. It is extremely rare.⁷⁵ The classic mirror hand is unilateral, usually with seven to eight fingers without a thumb, and is not combined with other anomalies. The etiology is unknown. The inheritance pattern has not been found. Geneticists believe it to be a spontaneous mutation.

History

Polydactylous hand and footprints have been found when studying rock art and petroglyphs, some dated 1000 AD. The first time that polydactyly was referred to in literature was in the Old Testament, where in a battle in Gath, a giant had six fingers on each hand, and six toes on each foot. The term polydactyly is first described by Kerckring in 1670. Since then, many reports have been made on polydactyly.

Basic science/disease process

Genetic aspects

In the patient with isolated radial polydactyly, a diminished genetic penetrance exists, with a variable expression. Furthermore, in numerous families with inherited isolated dominant radial polydactyly and triphalangeal thumb, a connection with chromosome 7q36 is demonstrated. In this particular

chromosome lies the regulatory element of the SHH protein. In isolated ulnar polydactyly an autosomal-dominant inheritance pattern occurs, with a diminished genetic penetrance and a variable expression. It is genetically heterogeneous, implying that the cause lies in mutations in various genes.

Diagnosis/patient presentation

Radial polydactyly

In radial (preaxial) polydactyly, the most commonly used classification is the Wassel classification.

The Wassel classification (Fig. 28.11)⁸⁹ is based on radiology and is easy to remember. The levels of duplication of the different types are: type I at the distal phalanx; type II at the IPJ; type III at the proximal phalanx; type IV at the MCPJ; type V at the metacarpal; and type VI at the CMCJ. Thumbs, of which at least one is triphalangeal, are type VII – this can be either at the MCPJ or at the CMCJ.

In most series, the three most common Wassel types are, respectively, Wassel IV (about 50%); Wassel II (about 20%), and Wassel VII (about 12%). The percentages are variable in the different reported series.^{90–92} As 31% in our polydactyly series could not be well classified, we modified the classification system.⁹² The essence lies in keeping the Wassel classification but naming the differences such as deviation and triphalangism (see below).

At first consultation, following medical history and general physical examination, both upper limbs are examined. If the index to little finger is normal, with normal hand and finger creases, and a normal hypothenar region, the examination is concentrated on the radial side of the hand. In our experience, it is worthwhile performing this systematically, as quite often more anomalies are present than only an extra thumb.




Fig. 28.11 Wassel type I–VII.

The examination is performed from proximal to distal, starting with examination of the thenar muscles. The thenar musculature varies widely from normal to severely hypoplastic. In the Wassel I and II, the thenar musculature is mostly normal, in contrast to the Wassel V, VI, and VII. Hypermobile joints should always be related to the other joints in the hands. It is important to look for creases both dorsally and palmarly. If creases are present, then an active movement in that particular joint can be expected.

The CMCJ in polydactyly can be normal, stiff or hypermobile. If abnormalities in the CMCJ are present, they are mostly encountered in the more proximal polydactylies. If polydactyly is situated at the CMCJ, the MCPJ in the best thumb can be near normal. In these cases, the movement is dependent on the presence of a syndactyly between the duplication.

Depending on the location of the polydactyly, the MCPJ can be stiff, normal moving, or hypermobile and hypoplastic. For instance, in a polydactyly involving the MCPJ, quite often the duplication moves as a block. In most of these cases, the radial-sided thumb is hypoplastic and stiff, and the ulnar thumb is the better one, often moving well at the IPJ. Finally, the IPJ can present with normal movement, stiffness, or hypermobility. If the duplication is at the IPJ, both parts can move as a block. The range of motion in those cases is typically less than in a normal IPJ. In an asymmetric duplication at the IPJ, the best-developed part usually moves better.

Normal examination includes extrinsic and intrinsic movement. In a newborn, it is often difficult to distinguish between these movements. However, flexion and extension can be evaluated, as well as the presence of palmar abduction. In duplicated thumbs, the flexor pollicis longus is Y-shaped in the majority of cases, with a less developed tendon to the most hypoplastic thumb. Therefore, flexion can be seen simultaneously in both thumbs. The extensor apparatus is usually less developed or absent in the more hypoplastic thumb. It can be Y-shaped as in the flexor and asymmetrically attached, therefore, deviating the distal part. The fingertips can be either normal or asymmetric. The asymmetric side is typically found on the opposing sides of the two thumbs. The nails are smaller and asymmetrical in most cases. The first web is nearly always normal in the distal duplications. In more proximal polydactylies, the first web can be narrower than the normal contralateral side.

Ulnar polydactyly

Ulnar (postaxial) polydactyly classifications include either two or three types. In the two-stage classification according to Temtamy and McKusick, type A comprises an extra little finger at the MCPJ, or more proximal including the CMCJ. The little finger can be hypoplastic or fully developed. Type B varies from a nubbin to an extra, non-functional little finger part on a pedicle. In the three-type classification, type I includes nubbins or floating little fingers, type II includes duplications at the MCPJ, and type III includes duplications of the entire ray.^{90,93,94}

The most common presentation of ulnar polydactyly is a small appendix on a skin pedicle, in which a neurovascular bundle is present. The appendix, in most cases attached at the ulnar border of the proximal phalanx, has mostly a small nail and thus a distal phalanx, and is non-functional. Sometimes two bones are present. If the extra little finger is more developed, the more common site of duplication is at the MCPJ. In these cases, the fifth metacarpal is broad. Depending on the extent of development and the attachment at the MCPJ, the extra little finger flexes and extends well. Full motion of the MCPJ of the normal fifth finger can be affected. Flexor tendons and extensor tendons are usually Y-shaped and asymmetrical, as in the duplicated thumb. The extra finger is usually abducted at the MCPJ and radially deviated at the PIPJ. The hypothenar muscles are attached at the ulnar side of the extra digit and palmarly at the broad MCPJ.

If the extra little finger is at the base of the metacarpal or at the CMC, the joint of the finger is usually well developed. Physical examination of ulnar polydactyly depends on the development of the extra little finger. Nevertheless, the same rules apply, as described in the examination of radial polydactyly.

Central polydactyly

In central polydactyly, the second, third and/or fourth digit can be involved in the duplication. Fully developed extra independent fingers are rare. In order of appearance, the most frequently affected is the ring finger, followed by the long finger, and ultimately the index finger. Frequently, the duplication of the fourth finger is partial

and hidden by a syndactyly, typically to the third finger. A number of varieties are possible because the duplication often is not confined to one finger. In addition to the bony deformity and aberrant growth plates, anomalies of the flexor and extensor tendons and neurovascular structures are present.

In ulnar dimelia (mirror hand), the hand looks very peculiar and is restricted in function due to the lack of a thumb and the presence of multiple digits. Seven to eight fingers are present without a thumb. Syndactyly can occur. The wrist is broad and mostly flexed. The arm is shorter with a broad elbow, an extension deficit, and restricted forearm rotation and shoulder movement.

Patient selection

Polydactylies are usually treated surgically. Functional impairment can vary from slight to severe, depending on the extent of the deformity. Polydactylies can be a nuisance in, for example, shaking hands, putting hands in pockets or narrow spaces, and wearing gloves. However, most parents visit the outpatient clinic with their child for aesthetic and social reasons. In patients with a syndrome with serious concomitant disease, surgery can be delayed or even be avoided.

Treatment/surgical technique

The timing of surgery is arbitrary. Surgery is recommended at the end of the first year of life by many authors, as it is important to be able to identify the structures properly and to minimize the anesthetic risks. Floating little fingers are often removed early in the newborn nursery under local anesthesia.

Knowledge of patho-embryology and patho-anatomy is essential to obtain long-term good results. Try to visualize aberrant anatomy without too much dissection!

Hints and tips

Radial polydactyly

Principles in treatment of radial polydactyly are:

- "Make one thumb from two, do not simply excise one."
- Decide which thumb should be kept.
- Do not just excise the most hypoplastic thumb but preserve tendons, ligaments and skin to align, balance and augment the residual thumb.
- At the first operation as much correction as possible is performed on both soft tissues and bones.
- Always be aware and search for less obvious anatomical anomalies, besides the extra digit.
- Align articular surfaces as axial and as congruent as possible by transverse and longitudinal osteotomies.
- Perform ligament reconstructions or releases.
- Balance tendon insertions.
- Adjust skin cover as accurately as possible.
- Postoperative dressings should be meticulously applied and resistant to removal by the child.

The surgical technique of Wassel type II and type IV will be discussed further, as they are the most frequent types.

Radial polydactyly at the IPJ (Wassel type II)

Wassel type II thumbs usually have a broad proximal phalanx with two (partial) distal phalanges with varying degrees of fusion of the bones or epiphyses (Fig. 28.12). In the case of an unequal duplication, it is straightforward to select the smaller thumb to be excised. The incision can be made dorsally in a zigzag manner for good exposure. The authors prefer a more lateral incision because it leaves less conspicuous scars. First the nail and nail bed of the smaller thumb is excised and then the skin over the extensor tendon is developed, if present. At the lateral side distal to the IPJ, the collateral ligament with periosteum or a small piece of cartilage is dissected proximally. The IPJ is then opened and inspected. The flexor tendon, if present, is identified and preserved and released distally. In excising the extra phalanx, the cartilage can be cut intra-articularly at the junction, corresponding to the former two thumbs. This leaves a surplus of skin, a proximally attached ligament, either (or not) an extensor and flexor tendon, and a broad proximal phalanx. On the side of the excised distal phalanx, a longitudinal wedge of bone from the articular surface of the proximal phalanx is removed, taking care not to remove the collateral ligament. If necessary, a transverse wedge is removed distally leaving the IPJ surface intact and subsequently placing the IPJ perpendicular to the axis of the proximal phalanx. Then the extensor and flexor of the remaining distal thumb are inspected. Mostly, the smaller part of the flexor will be excised at the border of the remaining flexor tendon. The smaller extensor tendon can be used to augment the extensor tendon of the remaining thumb. This extra extensor tendon is best used as a graft and not left in continuity with the extensor tendon to the remaining (ulnar) thumb. If the extensor tendon is used to reinforce the collateral ligament, it could influence extension of the remaining thumb. The collateral ligament is attached to the remaining distal phalanx. The remaining skin is carefully inserted on the lateral side, taking care to augment the deficient pulp on that side, while bulkiness of skin should be prevented.

In the event of two equal hypoplastic distal thumbs, which are fortunately less frequent, the two outer halves can be joined after excising the two inner halves longitudinally, in the Bilhaut–Cloquet operation.⁹⁵ Instead of the Bilhaut–Cloquet operation, the authors prefer a good smaller nail than a larger nail with a broad ridge, which draws attention. Therefore, one nail and nail bed is removed in nearly all cases and the usually insufficient pulp is augmented by the radial pulp of the excised thumb. In rare cases, a modified Bilhaut procedure can be used, augmenting a curved nail by elevating the nail bed from the bone, and supporting the radial side by bone from the radial (removed) thumb.

Radial polydactyly at the MCPJ (Wassel type IV)

Wassel type IV thumbs often demonstrate a hypoplastic or smaller extra thumb on the radial side. The operative technique has great similarities with the operation at the IPJ (Fig. 28.13). The radial thumb is excised preserving the radial collateral ligament with some cartilage, and after dissecting the extensor and flexor tendons, the joint is inspected. The broad






Fig. 28.12 (A) Wassel type II operative technique. (B,C) Wassel type II preoperatively and (D,E) postoperatively 2 years later (same child bilateral).




Fig. 28.13 (A) Wassel type IV operative technique. (B,C) Wassel type IV preoperatively and (D) Wassel type IV, at 15 years follow-up.

distal metacarpal is treated in the same way as the proximal phalanx in the IPJ in the Wassel type II, by excising a portion. The proximal phalanx is then aligned after exploring the flexor and extensor tendons of the remaining thumb. The flexor tendon can be asymmetrically situated without pulleys. Asymmetric tendons should be realigned in the “ulnar” thumb. If deviation at the IPJ is present, it should also be corrected with a transverse wedge osteotomy at the distal end of the proximal phalanx, as it will not adjust spontaneously during growth. In diamond-shaped polydactylies, IPJ corrections are always necessary. In equal-sized thumbs, the ulnar thumb is usually preserved as the ulnar collateral ligament is more important. The radial collateral ligament is subsequently reconstructed, providing stability on the new radial side of the MCPJ. With the radial collateral ligament, the thenar musculature is also reattached. Again, skin coverage of the radial side should be meticulously adjusted to the residual defect. Adjustment of the first web is rarely necessary in Wassel type II and IV.

Ulnar polydactyly

In the floating little finger type, the pedicle is excised at its base and the neurovascular bundle is buried to prevent painful neuromas in the scar (Fig. 28.14). It can be performed in the newborn nursery under local anesthesia. Care should be taken to avoid residual polydactyly at the base as this can occur when a ligature is used around the pedicle. Revisions may be necessary later in life. To prevent this residue, the use of vascular clips has been introduced. These can be positioned flush to the skin of the little finger, only leaving a scar. If a more developed extra little finger exists, the same principles apply as for radial polydactyly.

Central polydactyly

The basic problem in central polydactyly, in the majority of cases, is the often bizarre configuration of the skeleton with duplication and aberrant bones hidden by syndactyly. As the variety in presentation is extensive, basic rules should be followed (alignment of bones and articular surfaces) and, if possible, balanced by available tendons. However, involved fingers are insufficient or hypoplastic, and the joints are stiff. Syndactyly releases should be performed only if the fingers will obtain sufficient support (Fig. 28.15).

Mirror hand

Reconstruction in the very rare mirror hand can include elbow correction, osteotomies at the forearm to improve supination, and correction of flexion deformities at the wrist. The hand mostly involves resecting two or three fingers on the lateral side making a thumb of the best finger (usually the extra long finger) and creating a sufficient first web.⁹⁰

Postoperative care

The reconstructed hand following polydactyly is immobilized for 6 weeks, allowing finger movement in the bandage. Following the initial 6 weeks, and depending on the level and complexity of the reconstruction, further treatment consists of uninhibited full motion to a removable splint for several weeks. Hand exercises under supervision are seldom

necessary. In the simple ulnar polydactyly, a bandage is given for 2 days, as in regular wound care.

Outcomes, prognosis, and complications

When reconstruction in a congenital hand is performed, definitive outcome can only be assessed after growth has been completed. Therefore, it is advisable to check children several times during growth. At our outpatient clinic, examination is performed as described (Table 28.5). Specific attention is paid to nail deformities, movement and stability of joints, active range of motion, and appearance, broadness and malalignment of the skin. Older children and parents hardly complain of lack of function even though joints can be stiff. Painful thumbs are very rare. However, they do complain about appearance, often masked by an insignificant functional complaint. Teenagers often visit the outpatient clinic wanting the aesthetic outcome to be improved.

Outcome can be divided into unavoidable and avoidable results. In the unavoidable outcome in Wassel type II, the distal part of the thumb can be from nearly normal to hypoplastic, depending on the initial presentation. Insufficient pulp, smaller nails, and less developed IPJs are inevitable. In nail bed reconstructions, the nail will never be completely normal.

Table 28.5 Polydactyly: sequence of examination of the first ray

Feature	To be noted
Aspect	
Appearance	Normal/hypoplastic
Alignment	Straight/deviated
Position	Flexed/extended
Skin	
Creases	Normal/absent at joint(s)
Fingertip	Normal/asymmetric pulp
Syndactyly	Complete/incomplete
1st-web	Normal/narrow
Nails	
Nails	Normal/asymmetric/broad/small
Joints	
CMC, MP, IP	Stable/hypermobility/unstable Normal/impaired movement/stiff
Bones	
MC, P1, P2, (P3)	Normal/broad/slender
Muscle/tendon	
Thenar	Normal/hypoplastic
Extension	Present/absent/aberrant
Flexion	Present/absent/aberrant
Adduction	Present/absent/aberrant
Palmar abduction	Present/absent/aberrant
Radial abduction	Present/absent/aberrant
CMC, Carpometacarpal joint; MP, metacarpophalangeal joint; IP, interphalangeal joint; MC, metacarpal; P1, proximal phalanx; P2, middle phalanx; P3, distal phalanx.	



Fig. 28.14 (A,B) Ulnar polydactyly at metacarpophalangeal joints, preoperatively with X-ray, and (C) at 4 years follow-up.




Fig. 28.15 Bilateral central polydactyly with syndactyly (synpolydactyly): (A,B) preoperative right hand and X-ray; and (C) at 6 years follow-up, of both hands.




Fig. 28.16 Z-deformity following resection of only radial extra ray without further correction in unilateral Wassel type IV.

Avoidable outcomes in Wassel type II relate to inappropriate alignment, resulting in nail deformities, scarring at the nail wall, and extra nail development. If the collateral ligament is constructed with cartilage or a small piece of bone from the excised phalanx, new formation of bone can be the result. At the IPJ, incongruent alignment causes deviation, instability, or stiffness. Too much resection at the base of the distal phalanx damages growth of the remaining distal phalanx.

In the unavoidable outcome in Wassel type IV, the residual thumb is always less developed than the normal contralateral thumb.¹ The pulp is often less developed, the nail is usually smaller, and motion can vary from nearly normal to stiff, especially at the IPJ.^{96,97} Goldfarb found only a difference in nail width; however, motion was not taken into account in this study. But even though the thumb appears smaller, patients are satisfied as long as it is well shaped.^{97,98}

Avoidable outcomes in Wassel type IV also relate to inappropriate alignment. IPJ and MCPJ angulation decreases the aesthetic outcome.^{96,97} Deviations at either the IPJ or MPJ can mostly be prevented at initial operation by aligning the articular surfaces and balancing the thumb properly. Too much resection at the MPJ results in growth disturbances at the proximal phalanx of the remaining thumb. In late S- and zigzag deformities (Fig. 28.16), proper initial alignment has not been accomplished. Residual unstable IPJs or MCPJs can develop following improper ligamentous reconstruction at the initial stage.

In ulnar polydactyly, a small painful mass can remain following ligation or inadequate resection of the pedicle of the extra floating little finger. If the extra finger originates at the MCPJ, full flexion at the MCPJ might not be possible as the joint is not normally developed.

Secondary procedures

Growth can make secondary interventions advisable without really being complications. Possible secondary procedures, either or not in combination, can include:

- Ligament reconstruction
- Tenolysis
- Tendon rebalancing

- Opposition transfers (sometimes in the more proximal Wassel types)
- Nail deformity correction
- Osteotomy and alignment of articular surfaces
- Neurolysis and neuroma treatment in adult patients
- Arthrodesis of IPJ or MCPJ
- Scar revision.

Triphalangeal thumb

Introduction

The general incidence is estimated by Lapidus as being 1 in 25 000 live births.⁹⁹ Of all patients with a triphalangeal thumb (TPT), two-thirds have a family history of thumb abnormalities. They mostly have bilateral deformities and have non-opposable thumbs.³ TPT can be inherited as an autosomal-dominant trait.¹⁰⁰ Sporadic cases are mostly unilateral and supposed to be opposable. In our series, which comprised many inherited cases, thenar muscle deficiency varied considerably. This muscle deficiency is related to the degree of opposability of the thumb.¹⁰¹ In the Netherlands, the incidence of TPT is probably higher than stated in most reports, due to a number of families with an autosomal-dominant trait.

History

A thumb with three phalanges was first reported by Columbi in 1559,⁷⁵ and later by Dubois in 1826.¹⁰² Many authors have proposed treatment ranging from nothing to extensive surgery.

Basic science/disease process

By combining family pedigrees, the inheritance pattern of TPT is as an autosomal-dominant trait.¹⁰⁰ The location of the gene has been discovered on chromosome 7q36 in 1994.¹⁰³

Diagnosis/patient presentation

A wide variety of phenotypes can occur with TPT. Anatomical differences are not only restricted to the extra phalanx, therefore a thorough examination should be performed of both upper extremities.

The extra middle phalanx is a constant finding in TPT. Its shape can vary from a very small wedge-shaped extra phalanx resulting in a deviation at the IPJ to a fully developed extra phalanx resulting in a long thumb. Other features can be a near normal to very hypoplastic thenar musculature, a near normal to contracted and less deep first web, and an extra partial or fully developed ray. The thumb can be in the same plane as the other fingers with a finger-like appearance, hence the name of five-fingered hand in some of these cases.

In TPT, both IPJs are mobile. In the small wedge-shaped middle phalanx, no clinical distinction can be made in movement at the proximal or distal IPJ. When the middle phalanx is trapezoidal or rectangular, often active movement is possible at both joints.

The MPJ can be stable to very unstable; hyperextension at this joint is common. The CMCJ can vary from hypoplastic to malformed, resulting in variations from a less mobile to an unstable joint. The CMCJ can also be absent. Also the




Fig. 28.17 Our radial polydactyly and triphalangeal thumb classification. (Reproduced with permission from Zuidam JM, Selles RW, Ananta M, et al. A classification system of radial polydactyly: inclusion of triphalangeal thumb and triphalangism. *J Hand Surg Am.* 2008;33:373–377.)

trapezium and scaphoid can be hypoplastic, malformed, or absent.

In inherited cases, differences are often bilateral. An extra ray is common in these patients, and triplications may occur. The ulnar thumb is nearly always the best developed in cases of two thumbs.

In TPT, other malformations can also occur such as syndactyly, ulnar polydactyly, cleft hand, longitudinal radial deficiency, differences of the lower extremities, and as part of a syndrome with abnormalities in one or more of the other systems.^{104–106}

The aforementioned makes classification of TPT difficult. Wood^{107,108} classified TPT on the shape of the extra phalanx, distinguishing three types of an extra middle phalanx in the thumb: delta type, trapezoid type, and full rectangular type. Buck-Gramcko created a classification with six types, based on treatment options, including joint mobility, webspace,

intrinsic and extrinsic muscle abnormalities. If TPT is combined with polydactyly, further classifications are possible. Wassel classified all possible combinations into Wassel VII. Our group has developed a classification for TPT combined with duplication or triplication, based on the Wassel classification in which TPT is classified according to the joint (Fig. 28.17).

Patient selection

In TPT, the patient's precision grip is impaired as a result of diminished opposition, joint instability, or additional length, leading to alternative, compensating maneuvers. If syndactyly or an extra thumb is also present, proper use of the hand is further decreased. Children may compensate easily for these drawbacks. Parents of young patients and older children with TPT, however, often want the anomaly corrected for

appearance and very rarely for functional deficits. Timing of operation is not always clear in minor defects, such as small triangular phalanges.

The authors' series includes a high number of dominant hereditary triphalangeal thumbs, with or without polydactyly. The affected parent was often intensively teased at school and therefore wished their child to be operated before going to school.

Because of the presence of cortical representation of a thumb, a hard indication to operate very early is not present, as a new learning process is not necessary. In only rare cases is a scissors grip between index and middle finger used. It is advisable to operate on these patients before the age of 2 years for early adaptation of the cortex to the newly created thumb.

Treatment/surgical technique

Bunnell^{109,110} advised not to operate on TPTs. Beatson¹¹¹ and Milch,¹¹² among others,^{113,114} proposed removal of the abnormal phalanx to reduce length and to correct deviation. After removal of the extra phalanx, the risk of an angulated joint as end result exists.^{115,116} Buck-Gramcko¹¹⁷ stated that resection of the delta type extra phalanx and ligament reconstruction in the young child gives adequate results in a single procedure.

For patients with a trapezoidal or rectangular extra middle phalanx, several types of osteotomies are described such as resection of the distal joint and part of the distal phalanx followed by arthrodesis¹¹⁶ to excision of the PIPJ.² Buck-Gramcko¹¹⁷ added an osteotomy of the first metacarpal with reinsertion of the intrinsic muscles and widening of the first web. If necessary, an opposition transfer was also performed.

In the "five-fingered" hand, pollicization is advised.¹¹⁸ If the first web needs only minimal deepening, a four-flap Z-plasty¹¹⁹ can be used. Foucher¹²⁰ described a W-transposition flap in which skin and subcutaneous tissue is used from the dorsoradial side of the proximal phalanx of the index to provide skin for the first web. A large rotation flap of the dorsum of the hand can be used in a non-opposable TPT where, in addition to deepening, lengthening of the first web is required.^{117,121} In larger deficiencies of the first web, where the ray is placed in palmar abduction (such as in patients with a five-fingered hand), Upton¹²² favors a distally based radial forearm fasciocutaneous flap.

An opposition transfer can be performed if hypothenar muscle deficiency exists. The most used tendon transfers for opposition transfer are the abductor digiti minimi muscle (Huber technique¹²³), the superficial flexor of the ring finger,¹¹⁴ and the flexor carpi ulnaris.¹²⁴

When TPT is accompanied by radial polydactyly, Wassel⁸⁹ and Wood¹¹⁵ advised extirpation of the TPT even if the other biphalaengeal thumb is more rudimentary. Wood transposed the rudimentary biphalaengeal thumb to the base of the metacarpal of the TPT, creating a shorter thumb. This transposition can be combined with a metacarpal osteotomy. Upton,¹²⁵ on the other hand, excises the rudimentary biphalaengeal thumb, retains the triphalaengeal thumb, and corrects the TPT. No clear evidence exists regarding the best technique as most published series are small.

Timing of operation differs not only for the several types of TPT but also among various authors. Buck-Gramcko¹¹⁷

excises the short middle phalanx before the age of 6 years, because if the child is older, the joint does not remodel anymore. Wood,¹⁰⁸ on the other hand, operates between 6 months and 2 years of age.

Authors' preferred method of treatment¹²⁶

Delta middle phalanx

In children <6 years, resection of the extra phalanx is performed under fluoroscopy control (Figs. 28.18 & 28.19). Subsequently, the radial collateral ligament at the new IPJ is released and the ulnar collateral ligament tightened. The skin is released on the radial side with a Z-plasty and adjusted on the ulnar side by excision of skin. When the child is older, a corrective osteotomy with arthrodesis at the DIPJ is advised. This latter technique can be also performed in the trapezoidal middle phalanx.

Rectangular middle phalanx and five-fingered hand

Via a Y-shaped incision dorsally a reduction osteotomy of the middle phalanx is made followed by arthrodesis of the distal interphalaengeal joint. In this method, a 1–1.5 cm shortening is achieved. The skin is then closed as a "V". As the shortening is not enough, this procedure is combined with a shortening, rotation, and palmar abduction corrective osteotomy at the metacarpal level to correct for position and length of the thumb (1–1.5 cm extra shortening). Furthermore, the extensor tendons as well as the intrinsics are shortened. In recent years, a volar plate tightening at the MCPJ has been added to prevent hyperextension. Basically, this procedure resembles a pollicization. The original CMC1J, even though it is not optimal, is better and more stable than a reconstructed CMCJ in a formal pollicization. For this reason, the author does not use a formal pollicization in the five-fingered hand.

First web deficiency

Correction can mostly be performed with a simple four- or five-flap Z-plasty. When more skin is needed, a flap from the dorsoradial side of the index is used as described above. In case of polydactyly, the extra skin from the radial discarded extra thumb can be used to shift to the ulnar thumb, while the skin of the ulnar thumb is used for the first web (Fig. 28.20).

Postoperative care

For postoperative care, see the section on [radial polydactyly](#), above.

Outcomes, prognosis, and complications

The authors' group performed a long-term follow-up of operated (40 patients, 68 hands) and non-operated patients (15 patients, 29 hands). Patients scored their function and appearance. The improvement in appearance was significant in the operated group; the improvement in function was higher but not significant. There was a trend towards a stronger thumb in the operated group; however, no opposition transfer had been performed.

Treatment of patients with TPT is not easy and often underestimated due to a lack of knowledge of possible deformities that may occur; therefore, many of these are left uncorrected. Skin problems, infection, and mal-union or non-union are




Fig. 28.18 (A,B) Operative technique of extirpation of the middle phalanx in the young child (note the skin and ligament correction on both sides).

very rare. In our experience of treating patients with TPTs, one of the problems is unpredictable growth of the thumb, especially of the first metacarpal after initial shortening. This results in longer thumbs than intended (method of measuring: thumb tip is distal to the PIPJ of the index).¹²⁷ Parents and older children should, therefore, be informed. Furthermore, the arthrodesis of the distal IPJ can give a nail deformity. The V-Y approach can avoid this when performed with caution in relation to the nail bed.

Secondary procedures

Secondary procedures that are not directly related to complications include an opposition transfer to improve opposition strength. Not many patients feel this operation is necessary. Thumb length corrections can be performed using epiphysiodesis or shortening osteotomies when growth has stopped. Occasionally, volar plate-tightening procedures are offered for hypermobile MCPJs.




Fig. 28.19 (A,B) Preoperative triphalangeal thumb with delta phalanx and (C) postoperative result following resection of the middle phalanx of the thumb and ligament reconstruction; note the reduction in length.




Fig. 28.20 (A) Right hand preoperatively in bilateral polydactyly with triphalangeal thumb. (B) X-ray with one side operated following reduction–arthrodesis at the distal interphalangeal joint and reduction–rotation and abduction osteotomy at the first metacarpal with shortening of the intrinsic and resection of the radial ray. (C) Long-term follow-up of correction on right side.

Camptodactyly

Introduction

Camptodactyly is a contracture of the PIPJ in the anteroposterior direction (*campto* = arched; *dactylos* = finger). It occurs as consequence of an anatomical imbalance of the extrinsics and anomalous insertion of intrinsics to the affected finger(s). Camptodactyly can be sporadic without previous family history. Familial cases can inherit in an autosomal-dominant pattern. In about 30% of cases, camptodactyly has a familial background. This condition can furthermore be present in many syndromes such as Holt–Oram syndrome and Poland syndrome. Prevalence can vary considerable from 1–24%.¹²⁸ Camptodactyly usually stops being progressive with skeletal maturity.

History

The description of camptodactyly was first introduced by Tamplin in 1846.¹²⁹ One of his pupils, Adams, considered the skin deficiency on the palmar side as a secondary effect.¹³⁰ The term “camptodactyly” was first used by Landouzy in 1906.¹³¹ Depending on the author, camptodactyly can either be only an isolated PIPJ flexion contracture or also include those fingers where the PIPJ cannot be actively extended but have supple joints.¹³² All structures surrounding the PIPJ have been associated with the pathogenesis of camptodactyly. Attention has been drawn to an imbalance of the flexor and extensor mechanism.^{133,134} Subsequently, the role of the anomalous lumbrical insertion to the superficial flexor was described as a consistent finding.^{135–137} Most authors describe the bone changes of the joint and shortage of the skin as secondary to the contracture.

Basic science/disease process

As a consequence of the imbalance of flexors and extensors, flexion at the PIPJ occurs; this can lead to deformation of the intra-articular bone ends with a stiff joint as a result, and deficient skin on the palmar side. With increasing age, the extensor mechanism becomes more insufficient, leading to a further extension lag. Other mechanisms have also been described, such as circulatory disturbance, skin shortness, subcutaneous bands, lumbrical abnormality, short flexor superficialis, shortness of the flexor profundus, and retraction of the collateral ligaments and volar plate.

Diagnosis/patient presentation

The functional defect is mostly limited, and therefore appearance is mainly the concern. In severe forms however, functional deficit can be substantial, especially when more fingers are affected. The fifth finger is the most affected (>70%), followed by the fourth finger (<20%). The other fingers are involved in less than 10% of patients with camptodactyly.

Patients with camptodactyly can be divided into three groups:

1. The newborn male or female patient with camptodactyly of mostly the fifth and/or fourth finger and sometimes all fingers.

2. The adolescent, mostly female, with sudden onset or increasing camptodactyly of mostly only the fifth finger following growth spurts.
3. Severe camptodactyly associated with other malformations.^{138,139} However, it is disputed by others if this group should be diagnosed as camptodactyly.¹³²

Foucher *et al.*¹⁴⁰ recognized four conditions: (Ia) the early and stiff; (Ib) the early and correctable camptodactylies; (IIa) the late and stiff; (IIb) the late and correctable deformities. Tests to assess degree of severity of camptodactyly are as follows¹⁴⁰:

1. Can the PIPJ be actively extended while the wrist is held in a neutral position?
2. Does skin blanching appear while extending the finger as much as possible at both the MPJ and PIPJ?
3. Does the PIPJ flex when the wrist and MCPJ are extended (the superficial flexor tenodesis test)?
4. Can the PIPJ extend passively by tenodesis effect while the MCPJ and wrist are held in flexion (central band or Smith test)?
5. Can the PIPJ actively extend while the MCPJ is held in slight flexion (the Bouvier maneuver)?
6. Is the flexor digitorum superficialis (FDS) of the little finger independently working from the fourth finger?

Patient selection

The best patient to operate on is the patient who has a supple PIPJ but cannot actively extend the PIPJ well. Furthermore, patients should be selected on the basis of expected compliance to hand therapy.

The older patient with a stiff PIPJ is a bad candidate for release of the PIPJ with the intention to obtain a reasonable moving PIPJ.

Treatment/surgical technique

A splint is applied for all patients with camptodactyly in which the PIPJ is not supple (Fig. 28.21). The splint stresses the PIPJ gradually to as much extension as possible. The MCPJ is in flexion in a forearm splint. A reduction to <30° extension lag is considered good enough to refrain from surgery.

The duration of splinting therapy before further surgical treatment varies from 3 to 12 months. Some authors consider an extension lag of 60° as an indication for surgery.¹³²

If the splinting program demonstrates a passively improved joint without improved active extension or if the joint movement is not improved, surgery can be indicated. In the older patient, one should think twice before surgery is performed, especially when joint movement is not improved. In non-compliant patients or parents, surgery is not recommended.

A variety of operations has been proposed as the etiology is unclear. Operations range from skin plasties, arthrolysis, tenotomies, tendon transfers, and osteotomies to arthrodesis. The authors' preferred technique is based on the algorithm and description of the operative technique by Foucher.^{132,140}

In the correctable PIPJ, mostly skin and fibrous bands release are performed, with exploration of the lumbrical muscle, interosseus muscles, FDS and flexor digitorum profundus (FDP). Very often, the lumbrical is anomalous together with the FDS (Fig. 28.22). If the FDS is usable, and pulling on

the lateral band gives extension to the PIPJ, an FDS tendon transfer to the lateral band will be performed.

In the non-correctable PIPJ, which improves after splinting, an extensive skin release is performed with a Malek flap (proximally based palmar homodigital flap). Subsequently, the flexor sheath just proximal from the PIPJ is opened transversely and the checkreins, accessory ligament, and if necessary the palmar plate is released creating passive extension. The intrinsics and extrinsics of the operated finger are explored and released if an anomaly is present. An FDS tendon transfer is used from the same or otherwise adjacent finger to restore active extension. The transfer is attached to either the lateral band, if sufficient, or to the central band, if the lateral band is not sufficient.^{132,140}




Fig. 28.21 (A) Note the flexed proximal interphalangeal joint of digit 5 and less of digit 4 before splinting. (B) After long-term night splinting.




Fig. 28.22 The lumbrical muscle inserts into the flexor digitorum superficialis at the A1 pulley.

Postoperative care

Postoperative care consists of a splint, the duration of which depends on the technique used. A K-wire for 2 weeks can be used for the PIPJ following release of the joint. Compliance to hand therapy is essential.

Outcomes, prognosis, and complications

In the young child, long-term splinting during the night of the stiff PIPJ results in a good outcome, with an 80–92% improvement rate after long-term splinting.^{141,142} In the Caucasian hand, these good results could not be achieved in the same way. Young children with stiff joints do react well with splinting, resulting in a mean improvement of 40° following 19 months of splinting.^{139,140} The variety of operations that has been proposed inevitably results in various outcomes ranging from 14% to 35% improvement.^{132,143} Because of this insufficient outcome, and even sometimes worsening of the contracture, some authors prefer to rely only on splinting.

Foucher created an algorithm in which patients presenting late with a stiff joint are not operated. In all other patients, splints were applied. If no satisfactory improvement in extension was present, surgery was performed resulting in improvement rates from 68% to 88%, depending upon whether or not the joint was passively correctable.¹⁴⁰ Complications can include: insufficient possibility to extend the PIPJ after surgical treatment, osteoarthritis, recurrence of contracture, and stiffness and pain.

Secondary procedures

Secondary procedures include: re-release of capsular contracture, corrective osteotomy, or formal PIPJ arthrodesis.

Clinodactyly

Introduction

Clinodactyly is reserved for radioulnar deviations in the hand and lateromedial deviations in the foot. The angle of deviation defining clinodactyly varies among authors from >8° to

$>15^\circ$.^{144,145} Clinodactyly is a symptom and not a disease. It may be isolated or may be associated with other congenital malformations, such as in Down syndrome or Apert syndrome. Burke described 25 syndromes associated with clinodactyly.¹⁴⁶ The incidence varies from 1–19.5%, depending on the degree of angulation used to determine clinodactyly.¹⁴⁷ Depending on the inclusion criteria, different groups can be distinguished: familial clinodactyly usually without associated differences (brachymesophaalangism); clinodactyly with associated malformations; asymmetric injury to the growth plate; and triphalangeal thumb.

Brachymesophaalangism is the most frequently encountered form of clinodactyly. It is the result of an articular surface that is not perpendicular to the longitudinal axis due to the abnormally shaped bone. The phalanx looks like a delta phalanx without the osseous rim as in the delta phalanx with a C-shaped epiphysis. The middle to distal phalanx ratio is 1:1, compared with 1.3:1 in normal fingers.¹⁴⁸

Second, an aberrant growth plate surrounding one side of the delta phalanx in a “C” shape results in deviation at the involved joint(s). Other names for delta phalanx are triangular bone and longitudinally bracketed epiphysis.^{149–151} Reports suggest that anomalies with a delta phalanx should be clearly distinguished from the classical clinodactyly.¹⁵² As it is not clear, the authors would reserve clinodactyly for a congenital difference with or without a C-shaped epiphysis. Angulations after injury to the growth plate in an otherwise normal finger or a deviation in a joint following syndactyly release are secondary conditions.

History

Early reports exist on curvatures in the finger in the dorsopalmar plane.¹⁵³ Clinodactyly, however, refers to an angulation in the radioulnar plane. Smith described the condition in mongolism in 1896.¹⁴⁶ As clinodactyly is a physical sign, defining this group is difficult and has been variably described over the past century.

Basic science/disease process

Clinodactyly is considered to be a congenital deformity at the phalangeal level. The mode of inheritance of clinodactyly is as an autosomal-dominant trait with incomplete penetrance.¹⁵⁴ The middle phalanx is ossified later in embryonic development than the other phalanges, and latest in the little finger. Brachyphalangism therefore appears most in the little finger.¹⁵⁵ In proximal phalanges, however, aberrant growth plates also occur resulting in clinodactyly and brachyphalangism, and often in selected fingers. The exact etiology is still unknown.

Diagnosis/patient presentation

The most common form of clinodactyly is seen in the middle phalanx of the little finger presenting with an inward deviation of more than 10° . A positive family history in these patients is frequent. These little fingers mostly do not scissor over or under the ring finger, making this deformity more an aesthetic than a functional problem. Scissoring can also be prevented by abducting the little finger in the MCPJ. The deviation is clinically not only visible at the PIPJ but also at the DIPJ.



Fig. 28.23 Clinodactyly of the thumb.

The thumb is next in line in frequency of occurrence (Fig. 28.23). The thumb can be an isolated occurrence or as part of a syndrome. The angle of deviation can amount to 70° . In Apert syndrome, the thumb can be severely deviated. The fingers are less involved and, in most series, the least affected is the long finger. More than one digit can be affected. Over half of the patients present with a delta phalanx. As a considerable number of patients present with clinodactyly after epiphyseal closure, the presence of a delta phalanx is difficult to assess radiologically. X-rays of both hands and affected fingers in two directions are a prerequisite in making the diagnosis.

Patient selection

Clinodactyly in the little finger without scissoring is not often treated operatively because of the risk of impairing joint motion in a normal functioning finger. In those patients where function is impaired, an indication to operate can exist. In a more severe deviation with a longitudinally bracketed epiphysis, age of surgery depends on the technique. Resection of the lateral physis with interposition of fat is performed at a younger age than a formal wedge osteotomy with or without bone graft. In syndromic clinodactyly, correction of clinodactyly depends very much on the associated abnormalities.

Treatment/surgical technique

Treatment for clinodactyly can be divided into the following procedures:

- Opening wedge osteotomy with or without bone graft
- Closing wedge osteotomy
- Reversed wedge osteotomy
- Release of soft tissues on the concave side

- Tightening of soft tissues on the convex side
- Physiolysis.

Although a closing wedge osteotomy is advised for moderate and severe deviations ($>30^\circ$),¹⁵⁶ the authors are not in favor of using this technique, as the affected finger will be further shortened.¹⁵⁷ An open wedge osteotomy lengthens the digit the most and is preferred. In the more severe deviations, however, bone correction only will not be enough. Release of soft tissue (collateral ligaments and the skin) on the contracted side is also necessary. The thenar musculature at its insertion in the radially deviated thumb should also be released, otherwise recurrence is inevitable. Tightening of soft-tissue structures, especially collateral ligaments on the convex side, can also be useful.

In the less severe deviations, a reverse wedge osteotomy works well but is technically more demanding (Fig. 28.24). The advantage of the reverse wedge is that no other donor site is necessary. In the open wedge technique and in the reverse wedge technique, the graft is transfixed with a percutaneous K-wire either with or without a suture to hold the bone graft in position.



Fig. 28.24 (A) Reversed wedge osteotomy of the ring finger preoperatively and (B) postoperatively, the wedge is placed at the radial side of the proximal phalanx.

In 1987, Vickers described a new technique by excising the continuous region of the physis and diaphysis in the isthmic region of the middle phalanx via a lateral incision. The bone is further removed in this region with a burr or curette. The remaining cavity is filled with a fat graft. This operation is called physiolyis and works well in younger children (under the age of 6 years), with less severe clinodactyly, and a trapezoidal phalanx.^{158,159}

Postoperative care

In the physiolyis technique, the operated finger can be taped to the adjacent finger for approximately 2 weeks. In the closing wedge technique, 3 weeks of immobilization is enough. In the reverse and open wedge osteotomies, also depending on the soft-tissue correction, 4–6 weeks immobilization is often carried out.

Outcomes, prognosis, and complications

Reversed wedge osteotomies normally heal well. Slight angulations in the dorsal–palmar plane following surgery mostly disappear during growth. In open wedge osteotomies, skin and ligament release can be insufficient, leading to skin tightness and recurrence of angulation. In physiolyis, results in children over 5 years are not as good as in younger children. Furthermore, it works well in less severe clinodactylies.

Complications of the bone can be mal-union or malrotation. Non-union in children is very rare. Even if the X-ray demonstrates a non-consolidated osteotomy, the fibrous tissue bridging the two parts can prevent movement, and will have no clinical implications. Furthermore, extensor tendon adhesions can result in a mallet-like deformity. In some cases, stiffness of joints can occur. Pain is rarely an issue.

Secondary procedures

Secondary procedures mainly address recurrence of the deviation either by insufficient release or excision of the physis or by inadequate soft-tissue release. A new osteotomy and soft-tissue release can be performed.

Future directions

The OMT classification

When classifying congenital hand and upper limb differences, the Oberg, Manske, Tonkin (OMT) classification is used. This classification was first introduced in 2010,¹⁶⁰ and was approved by the Scientific Committee for Congenital Conditions of the International Federation of Societies for Surgery of the Hand (IFSSH)¹⁶¹ to substitute the Swanson classification.¹⁶² Since 2010, the OMT classification has been subject to assessments with subsequent modifications, the last being published in 2015.¹⁶³ At this moment, the OMT classification is still a flexible and fluid classification, adapting to new developments and additional conditions.

The OMT classification is designed to accommodate the current knowledge of limb embryogenesis, classifying congenital hand and upper limb differences in one of three groups: malformations, deformations and dysplasia (Fig. 28.25). The malformations group comprises the most




Fig. 28.25 Oberg, Manske, and Tonkin (OMT) classification. (Reproduced with permission from Oberg KC, Feensra JM, Manske PR, Tonkin MA. Developmental biology and classification of congenital anomalies of the hand and upper extremity. J Hand Surg Am. 2010;35:2066–76; and Ezaki M, Baek GH, Horii E, et al. IFSSH Scientific Committee on Congenital Conditions. J Hand Surg Eur Vol. 2014;39:676–8.)

diagnoses (74–90% of total in several analyses) and is further divided according the involvement of the whole limb or the hand plate alone. These two groups are subdivided according the three axis of limb development (i.e. proximal–distal, radial–ulnar, dorsal–ventral) and an additional unspecified axis. The deformations group is subdivided into: constriction ring sequence, trigger digits, and not otherwise specified; the dysplasia group is subdivided into hyperplasia and tumorous conditions, with further subdivision (see Fig. 28.25). Additionally, if a syndrome is present with a congenital upper limb difference, this will be cross-referenced according to a list of syndromes that can be or are accompanied with a syndrome.

As yet we do not have a full understanding of the basis of all differences at the level of cell signaling and molecular pathways, but as this becomes clearer, its incorporation into the classification is possible, giving a fuller categorization of congenital hand and upper limb differences. With regard to this changing knowledge, the IFSSH Scientific Committee for Congenital Conditions has been advised to review and improve the OMT classification every 3 years.

With regard to future obligations regarding patient-related outcome measures, the OMT classification can form the basis of classifying the subjects researched. It is therefore important that the most recent OMT classification is used when presenting data on outcome. Furthermore, with the Patient Reported Outcome Measurement (PROM) getting a lead in reporting quality of care and outcome of healthcare providers for research purposes or in evaluating healthcare by insurance companies, outcome measures for congenital hand and upper limb malformations should be formalized and incorporated by the teams treating them. At this moment, an outcome set specifically for congenital hand and upper limb differences is being formulated and will be evaluated globally by congenital

hand teams with incorporation of this outcome set in daily practice as an ultimate goal.

Postoperative regime

With regard to changes in insight and the will to improve healthcare, with minimal stress for the patient and their parents as a goal, we have introduced a different regime of postoperative bandage in our clinic. With the phases of wound healing in our mind, we decided to treat our patients postoperatively with a bandage that would stay put for 6 weeks. In this period, complete wound healing takes place for regular wounds and skin grafts. Furthermore, the best moment for taking care to achieve an ultimate position of the fingers and hand after reconstruction in the bandage is at the time the patient is under general anesthesia. With respect to the debate on children and general anesthesia, our goal is to minimize the number of operations and duration of an operation. Because of this combination, we decided to have the bandage removed after approximately 6 weeks and start hand therapy according to a regular schedule. Parents receive information about alarm signals regarding the bandage, as is given with the regular shorter bandage regimes. Preliminary data of the last 5 years show far fewer infections with the new regime, with fewer prescriptions of antibiotics. An additional advantage to this regime is the number of bandage changes the patient is subjected to: instead of daily changes after 2 weeks until 6 weeks after the operation, this is decreased to only one after 6 weeks. This decreases the stress for the patient and parents in a period where bonding between the both is important. Because of this outcome, we introduced this regime as a standard practice, fitting our ideas on wound healing, anesthesia, psychology, and logistics of our outpatient clinic.



Access the complete reference list online at <http://www.expertconsult.com>

1. Dobyns JH, Doyle JR, Von Gillern TL, et al. Congenital anomalies of the upper extremity. *Hand Clin.* 1989;5:321–342.
9. Ogino T. Teratogenic relationship between polydactyly, syndactyly and cleft hand. *J Hand Surg [Br].* 1990;15:201–209.
13. Tonkin MA. Failure of differentiation part I: Syndactyly. *Hand Clin.* 2009;25:171–193. *This is a review of the classification, incidence, indication, and review of surgical techniques and complications in syndactyly in different hand anomalies associated with syndactyly.*
16. Niranjana NS, Azad SM, Fleming AN, et al. Long-term results of primary syndactyly correction by the trilobed flap technique. *Br J Plast Surg.* 2005;58:14–21.
51. Upton J. Apert syndrome. Classification and pathologic anatomy of limb anomalies. *Clin Plast Surg.* 1991;18:321–355. *An excellent overview of Apert syndrome concerning limb anomalies.*
56. Zuker RM, Cleland HJ, Haswell T. Syndactyly correction of the hand in Apert syndrome. *Clin Plast Surg.* 1991;18:357–364.
57. Fearon JA. Treatment of the hands and feet in Apert syndrome: an evolution in management. *Plast Reconstr Surg.* 2003;112:1–19.
68. Foucher G, Navarro R, Medina J, et al. Metacarpal synostosis: a simple classification and a new treatment technique. *Plast Reconstr Surg.* 2001;108:1225–1234.
89. Wassel HD. The results of surgery for polydactyly of the thumb. *Clin Orthop Relat Res.* 1969;64:175–193.
96. Ogino T, Ishii S, Takahata S, et al. Long-term results of surgical treatment of thumb polydactyly. *J Hand Surg Am.* 1996;21:478–486. *Some 113 hands with reconstruction of radial polydactyly and an average follow-up of 4 years were evaluated. According to Tada's evaluation, 97 hands were classified as good, 12 hands as fair, and four hands as poor. The type of deformity, type of procedure, and skill of the surgeon influenced the outcome. Wassel type III, V, and VI and triphalangeal thumb polydactyly have a higher incidence of unsatisfactory results.*
97. Goldfarb CA, Patterson JM, Maender A, et al. Thumb size and appearance following reconstruction of radial polydactyly. *J Hand Surg Am.* 2008;33:1348–1353.
126. Hovius SE, Zuidam JM, de Wit T. Treatment of the triphalangeal thumb. *Tech Hand Up Extrem Surg.* 2004;8:247–256. *In the triphalangeal thumb, the extra phalanx can have different shapes, from wedge to rectangular. Furthermore, the involved joints, ligaments, muscles, and tendons of the first ray, from distal interphalangeal joint to radiocarpal joint can be hypoplastic, malformed, or absent with varying degrees of stiffness or instability. Also, the first web can be insufficient and radial polydactyly as well as other hand deformities can be present. In this series depending on the malformation, operations varied from removal of the delta phalanx with ligament reconstruction to multiple osteotomies and rebalancing as well as pollicization.*
140. Foucher G, Lorea P, Khouri RK, et al. Camptodactyly as a spectrum of congenital deficiencies: a treatment algorithm based on clinical examination. *Plast Reconstr Surg.* 2006;117:1897–1905. *Camptodactyly is classified into four groups. Camptodactyly can be correctible or non-correctible and can be moderate or severe. Careful assessment with clinical tests can distinguish the possible treatment, varying from splinting, the lasso procedure with or without lumbrical repositioning, and tendon transfer of the FDS of the fourth or fifth finger.*
150. Wood VE, Flatt AE. Congenital triangular bones in the hand. *J Hand Surg Am.* 1977;2:179–193.

References

- Dobyns JH, Doyle JR, Von Gillern TL, et al. Congenital anomalies of the upper extremity. *Hand Clin.* 1989;5:321–342.
- Flatt A, ed. *The Care of Congenital Hand Anomalies*. 1st ed. St. Louis, MO: Quality Medical; 1977:109–117.
- Temtamy SA, McKusick VA. The genetics of hand malformations. *Birth Defects Orig Artic Ser.* 1978;14:i–xviii, 1–619.
- van der Biezen JJ, Bloem JJ. Dividing the fingers in congenital syndactyly release: a review of more than 200 years of surgical treatment. *Ann Plast Surg.* 1994;33:225–230.
- Upton J. Failure of differentiation and overgrowth. In: Mathes SJ, ed. *Plastic Surgery*. 2nd ed. Philadelphia, PA: Saunders Elsevier; 2006:265–322.
- Sadler TW. *Langman's Medical Embryology*. 8th ed. Philadelphia, PA: Lippincott Williams and Wilkins; 2000.
- Streeter GL. Developmental horizons in human embryos IV. A review of the histogenesis of cartilage and bone. *Contrib Embryol.* 1949;33.
- Bakrania P, Ugur Iseri SA, Wyatt AW, et al. Sonic hedgehog mutations are an uncommon cause of developmental eye anomalies. *Am J Med Genet A.* 2010;152A:1310–1313.
- Ogino T. Teratogenic relationship between polydactyly, syndactyly and cleft hand. *J Hand Surg [Br].* 1990;15:201–209.
- Havlik RJ. Failure of differentiation of the human hand. In: Bentz ML, Bauer BS, Zuker RM, eds. *Principles and Practice of Pediatric Plastic Surgery*. St Louis, MO: Quality Medical; 2008:1191–1231.
- Buck-Gramcko D. Progress in the treatment of congenital malformations of the hand. *World J Surg.* 1990;14:715–724.
- Dao KD, Shin AY, Billings A, et al. Surgical treatment of congenital syndactyly of the hand. *J Am Acad Orthop Surg.* 2004;12:39–48.
- Tonkin MA. Failure of differentiation part I: Syndactyly. *Hand Clin.* 2009;25:171–193. *This is a review of the classification, incidence, indication, and review of surgical techniques and complications in syndactyly in different hand anomalies associated with syndactyly.*
- Smith PJ, Harrison SH. The “seagull” flap for syndactyly. *Br J Plast Surg.* 1982;35:390–393.
- Bauer TB, Tondra JM, Trusler HM. Technical modification in the repair of syndactylism. *Plast Reconstr Surg.* 1956;17:385–392.
- Niranjan NS, Azad SM, Fleming AN, et al. Long-term results of primary syndactyly correction by the trilobed flap technique. *Br J Plast Surg.* 2005;58:14–21.
- Colville J. Syndactyly correction. *Br J Plast Surg.* 1989;42:12–16.
- Hsu VM, Smartt JM Jr, Chang B. The modified V-Y dorsal metacarpal flap for repair of syndactyly without skin graft. *Plast Reconstr Surg.* 2010;125:225–232.
- Sherif MM. V-Y dorsal metacarpal flap: a new technique for the correction of syndactyly without skin graft. *Plast Reconstr Surg.* 1998;101:1861–1866.
- Ekerot L. Syndactyly correction without skin-grafting. *J Hand Surg [Br].* 1996;21:330–337.
- Kay S, Coady M. The role of microsurgery and free tissue transfer in the reconstruction of the paediatric upper extremity. *Ann Acad Med Singapore.* 1995;24(4 suppl):113–123.
- Foucher G, Medina J, Navarro R, et al. [Value of a new first web space reconstruction in congenital hand deformities. A study of 54 patients]. *Chir Main.* 2000;19:152–160.
- Cronin TD. Syndactylism: results of zig-zag incision to prevent postoperative contracture. *Plast Reconstr Surg (1946).* 1956;18:460–468.
- Withey SJ, Kangesu T, Carver N, et al. The open finger technique for the release of syndactyly. *J Hand Surg [Br].* 2001;26:4–7.
- Buck-Gramcko D. *Congenital Malformations in Hand Surgery*. Stuttgart: Thieme Verlag; 1988.
- van der Biezen JJ, Bloem JJ. The double opposing palmar flaps in complex syndactyly. *J Hand Surg Am.* 1992;17:1059–1064.
- Jose RM, Timoney N, Vidyadharan R, et al. Syndactyly correction: an aesthetic reconstruction. *J Hand Surg Eur Vol.* 2010;35:446–450.
- Frick L, Fraisse B, Wavreille G, et al. Results of surgical treatment in simple syndactyly using a commissural dorsal flap. About 54 procedures. *Chir Main.* 2008;27:76–82.
- D’Arcangelo M, Gilbert A, Pirrello R. Correction of syndactyly using a dorsal omega flap and two lateral and volar flaps. A long-term review. *J Hand Surg [Br].* 1996;21:320–324.
- Lumenta DB, Kitzinger HB, Beck H, et al. Long-term outcomes of web creep, scar quality, and function after simple syndactyly surgical treatment. *J Hand Surg Am.* 2010;35:1323–1329.
- Eaton CJ, Lister GD. Syndactyly. *Hand Clin.* 1990;6:555–575.
- Toledo LC, Ger E. Evaluation of the operative treatment of syndactyly. *J Hand Surg Am.* 1979;4:556–564.
- Brown PM. Syndactyly – a review and long term results. *Hand.* 1977;9:16–27.
- Deunk J, Nicolai JP, Hamburg SM. Long-term results of syndactyly correction: full-thickness versus split-thickness skin grafts. *J Hand Surg Br.* 2003;28:125–130.
- Percival NJ, Sykes PJ. Syndactyly: a review of the factors which influence surgical treatment. *J Hand Surg Br.* 1989;14:196–200.
- Johne B. *Operative Behandlung der Syndactylie: Zeitpunkt – Technik – Ergebnisse*. Hamburg University; 1979.
- Poland A. Deficiency of the pectoral muscle. *Guy's Hosp Bull.* 1841;6:191–194.
- Ravitch MM. Poland syndrome – a study of an eponym. *Plast Reconstr Surg.* 1977;59:508–512.
- Bouvet JP, Leveque D, Bernetieres F, et al. Vascular origin of Poland syndrome? A comparative rheographic study of the vascularization of the arms in eight patients. *Eur J Pediatr.* 1978;128:17–26.
- Goldberg MJ, Mazzei RJ. Poland syndrome: a concept of pathogenesis based on limb bud embryology. *Birth Defects Orig Artic Ser.* 1977;13:103–115.
- Eroglu A, Yildiz D, Tunc H. Dextrocardia is a component of left-sided Poland syndrome. *J Thorac Cardiovasc Surg.* 2005;130:1471–1472.
- Moir CR, Johnson CH. Poland syndrome. *Semin Pediatr Surg.* 2008;17:161–166.
- Ireland DC, Takayama N, Flatt AE. Poland syndrome. *J Bone Joint Surg Am.* 1976;58:52–58.
- Al-Qattan MM. Classification of hand anomalies in Poland syndrome. *Br J Plast Surg.* 2001;54:132–136.
- Tolarova MM, Harris JA, Ordway DE, et al. Birth prevalence, mutation rate, sex ratio, parents’ age, and ethnicity in Apert syndrome. *Am J Med Genet.* 1997;72:394–398.
- Mantilla-Capacho JM, Arnaud L, Diaz-Rodriguez M, et al. Apert syndrome with preaxial polydactyly showing the typical mutation Ser252Trp in the FGFR2 gene. *Genet Couns.* 2005;16:403–406.
- Apert ME. De l’acrocephalosyndactylie. *Bull Mem Soc Med Hop Paris.* 1906;23:1310–1313.
- Lajeunie E, Cameron R, El Ghouzzi V, et al. Clinical variability in patients with Apert’s syndrome. *J Neurosurg.* 1999;90:443–447.
- Wilkie AO, Slaney SF, Oldridge M, et al. Apert syndrome results from localized mutations of FGFR2 and is allelic with Crouzon syndrome. *Nat Genet.* 1995;9:165–172.
- Kasser J, Upton J. The shoulder, elbow, and forearm in Apert syndrome. *Clin Plast Surg.* 1991;18:381–389.
- Upton J. Apert syndrome. Classification and pathologic anatomy of limb anomalies. *Clin Plast Surg.* 1991;18:321–355. *An excellent overview of Apert syndrome concerning limb anomalies.*
- Cohen MM Jr, Kreiborg S. Hands and feet in the Apert syndrome. *Am J Med Genet.* 1995;57:82–96.
- Dao KD, Shin AY, Kelley S, et al. Thumb radial angulation correction without phalangeal osteotomy in Apert’s syndrome. *J Hand Surg Am.* 2002;27:125–132.
- Guero SJ. Algorithm for treatment of Apert hand. *Tech Hand Up Extrem Surg.* 2005;9:126–133.
- Fereshtetian S, Upton J. The anatomy and management of the thumb in Apert syndrome. *Clin Plast Surg.* 1991;18:365–380.

56. Zuker RM, Cleland HJ, Haswell T. Syndactyly correction of the hand in Apert syndrome. *Clin Plast Surg*. 1991;18:357–364.
57. Fearon JA. Treatment of the hands and feet in Apert syndrome: an evolution in management. *Plast Reconstr Surg*. 2003;112:1–19.
58. Chang J, Danton TK, Ladd AL, et al. Reconstruction of the hand in Apert syndrome: a simplified approach. *Plast Reconstr Surg*. 2002;109:465–471.
59. Ashmead D, Smith PJ. Tissue expansion for Apert's syndactyly. *J Hand Surg Br*. 1995;20:327–330.
60. Buck-Gramcko D. Angeborene fehlbildungen der hand. In: Nigst H, Buck-Gramcko D, Millesi H, eds. *Handchirurgie*. Stuttgart: Thieme; 1988:12.1–12.115.
61. Dobyns JH. The hand and Apert's syndrome (discussion). *J Bone Joint Surg*. 1970;52A:894–895.
62. Van Heest AE, House JH, Reckling WC. Two-stage reconstruction of Apert acrosyndactyly. *J Hand Surg Am*. 1997;22:315–322.
63. Barot LR, Caplan HS. Early surgical intervention in Apert's syndactyly. *Plast Reconstr Surg*. 1986;77:282–287.
64. Cushing H. Hereditary ankylosis of proximal phalangeal joints (sympalangism). *Genetics*. 1919;1:90–96.
65. Flatt AE, Wood VE. Rigid digits or symphalangism. *Handchir Mikrochir Plast Chir*. 1975;7:197–214.
66. Buckwalter JA, Flatt AE, Shurr DG, et al. The absent fifth metacarpal. *J Hand Surg Am*. 1981;6:364–367.
67. Buck-Gramcko D, Wood VE. The treatment of metacarpal synostosis. *J Hand Surg Am*. 1993;18:565–581.
68. Foucher G, Navarro R, Medina J, et al. Metacarpal synostosis: a simple classification and a new treatment technique. *Plast Reconstr Surg*. 2001;108:1225–1234.
69. Delaney TJ, Eswar S. Carpal coalitions. *J Hand Surg Am*. 1992;17:28–31.
70. Mortier JP, Kuhlmann JN, Baux S. [Scapholunate synostoses within the framework of congenital carpal synostoses]. *Ann Chir Main*. 1986;5:323–327.
71. Carlson DH. Coalition of the carpal bones. *Skeletal Radiol*. 1981;7:125–127.
72. Hughes PC, Tanner JM. The development of carpal bone fusion as seen in serial radiographs. *Br J Radiol*. 1966;39:943–949.
73. Yammine K, Salon A, Pouliquen JC. Congenital radioulnar synostosis. Study of a series of 37 children and adolescents. *Chir Main*. 1998;17:300–308.
74. Elliott AM, Kibria L, Reed MH. The developmental spectrum of proximal radioulnar synostosis. *Skeletal Radiol*. 2010;39:49–54.
75. Kelikian H. *Congenital Deformities of the Hand and Forearm*. Philadelphia, PA: WB Saunders; 1974.
76. Fahlstrom S. Radio-ulnar synostosis. *J Bone Joint Surg*. 1932;14:395–403.
77. Polymeropoulos MH, Poush J, Rubenstein JR, et al. Localization of the gene (SYM1) for proximal symphalangism to human chromosome 17q21-q22. *Genomics*. 1995;27:225–229.
78. Yamamoto N, Endo T, Nakayama Y. Congenital synostosis of the fourth and fifth metacarpals treated by free bone grafting from the fusion site. *Plast Reconstr Surg*. 2000;105:1747–1750.
79. Horii E, Miura T, Nakamura R, et al. Surgical treatment of congenital metacarpal synostosis of the ring and little fingers. *J Hand Surg [Br]*. 1998;23:691–694.
80. Funakoshi T, Kato H, Minami A, et al. The use of pedicled posterior interosseous fat graft for mobilization of congenital radioulnar synostosis: a case report. *J Shoulder Elbow Surg*. 2004;13:230–234.
81. Kanaya F, Ibaraki K. Mobilization of a congenital proximal radioulnar synostosis with use of a free vascularized fascio-fat graft. *J Bone Joint Surg Am*. 1998;80:1186–1192.
82. Castello JR, Garro L, Campo M. Congenital radioulnar synostosis. Surgical correction by derotational osteotomy. *Ann Chir Main Memb Super*. 1996;15:11–17.
83. Hung NN. Derotational osteotomy of the proximal radius and the distal ulna for congenital radioulnar synostosis. *J Child Orthop*. 2008;2:481–489.
84. Murase T, Tada K, Yoshida T, et al. Derotational osteotomy at the shafts of the radius and ulna for congenital radioulnar synostosis. *J Hand Surg Am*. 2003;28:133–137.
85. Simmons BP, Southmayd WW, Riseborough EJ. Congenital radioulnar synostosis. *J Hand Surg Am*. 1983;8:829–838.
86. Swanson AB, Swanson GD, Tada K. A classification for congenital limb malformation. *J Hand Surg Am*. 1983;8:693–702.
87. Barsky AJ. *Congenital Anomalies of the Hand and their Surgical Treatment*. Springfield, IL: Charles C Thomas; 1958:48–64.
88. Biesecker LG. Polydactyly: how many disorders and how many genes? *Am J Med Genet*. 2002;112:279–283.
89. Wassel HD. The results of surgery for polydactyly of the thumb. *Clin Orthop Relat Res*. 1969;64:175–193.
90. Upton J. Disorders of duplication. In: Mathes SJ, ed. *Plastic Surgery*. 2nd ed. Philadelphia, PA: Saunders Elsevier; 2006:215–228.
91. Al-Qattan MM. The distribution of the types of thumb polydactyly in a Middle Eastern population: a study of 228 hands. *J Hand Surg Eur Vol*. 2010;35:182–187.
92. Zuidam JM, Selles RW, Ananta M, et al. A classification system of radial polydactyly: inclusion of triphalangeal thumb and triplication. *J Hand Surg Am*. 2008;33:373–377.
93. Stelling F. The upper extremity. In: Ferguson AB, ed. *Orthopedic Surgery in Infancy and Childhood*. Baltimore: Williams and Wilkins; 1963:282–402.
94. Turek S. *Orthopaedic Principles and their Application*. Philadelphia, PA: JP Lippincott; 1967.
95. Bilhaut M. Guérison d'une pousse bifide par un nouveau procede operatoire. *Cong Fran de Chir*. 1889;4:576–580.
96. Ogino T, Ishii S, Takahata S, et al. Long-term results of surgical treatment of thumb polydactyly. *J Hand Surg Am*. 1996;21:478–486. Some 113 hands with reconstruction of radial polydactyly and an average follow-up of 4 years were evaluated. According to Tada's evaluation, 97 hands were classified as good, 12 hands as fair, and four hands as poor. The type of deformity, type of procedure, and skill of the surgeon influenced the outcome. Wassel type III, V, and VI and triphalangeal thumb polydactyly have a higher incidence of unsatisfactory results.
97. Goldfarb CA, Patterson JM, Maender A, et al. Thumb size and appearance following reconstruction of radial polydactyly. *J Hand Surg Am*. 2008;33:1348–1353.
98. Tada K, Kurisaki E, Yonenobu K, et al. Central polydactyly – a review of 12 cases and their surgical treatment. *J Hand Surg Am*. 1982;7:460–465.
99. Lapidus PW, Guidotti FP, Coletti CJ. Triphalangeal thumb. Report of six cases. *Surg Gynecol Obstet*. 1943;77:178–186.
100. Zguricas J, Snijders PJ, Hovius SE, et al. Phenotypic analysis of triphalangeal thumb and associated hand malformations. *J Med Genet*. 1994;31:462–467.
101. Zguricas J, de Raeymaecker DM, Snijders PJ, et al. Psychomotor development in children with triphalangeal thumbs. A preliminary study. *J Hand Surg Br*. 1998;23:526–529.
102. Dubois P. Sexdigitaire (pouce à de trois phalanges). *Arch Gén Méd*. 1826;4:148.
103. Heutink P, Zguricas J, van Oosterhout L, et al. The gene for triphalangeal thumb maps to the subtelomeric region of chromosome 7q. *Nat Genet*. 1994;6:287–292.
104. Haas SL. Three phalangeal thumbs. *AJR Am J Roentgenol*. 1939;42:677–682.
105. Phillips RS. Congenital split foot (lobster claw) and triphalangeal thumb. *J Bone Joint Surg*. 1971;53:247–257.
106. Miura T, Nakamura R, Horii E, et al. Three cases of syndactyly, polydactyly, and hypoplastic triphalangeal thumb (Haas's malformation). *J Hand Surg Am*. 1990;15:445–449.
107. Wood VE. Treatment of the triphalangeal thumb. *Clin Orthop Relat Res*. 1976;120:188–200.

108. Wood VE. *The Triphalangeal Thumb*. Edinburgh: Churchill Livingstone; 1998.
109. Bunnell S. *Surgery of the Hand*. 3rd ed. London: JB Lippincott; 1944.
110. Smith H, Campbell WD, Speed JS. *Campbell's Operative Orthopedics*. 2nd ed. Philadelphia, PA: WB Saunders; 1949.
111. Beatson GT. Congenital deformity of both thumbs. *Scott Med Surg J*. 1897;1:1083–1088.
112. Milch H. Triphalangeal thumb. *J Bone Joint Surg Am*. 1951;33:692–697.
113. Cotta H, Jager M. [Familial triphalangism of the thumb and its surgical treatment]. *Arch Orthop Unfallchir*. 1965;58:282–290.
114. Miura T. Triphalangeal thumb. *Plast Reconstr Surg*. 1976;58:587–594.
115. Wood VE. Polydactyly and the triphalangeal thumb. *J Hand Surg Am*. 1978;3:436–444.
116. Peimer CA. Combined reduction osteotomy for triphalangeal thumb. *J Hand Surg Am*. 1985;10:376–381.
117. Buck-Gramcko D. The triphalangeal thumb. In: Buck-Gramcko D, ed. *Congenital Malformations of the Hand and Forearm*. Edinburgh: Churchill Livingstone; 1998:403–424.
118. Buck-Gramcko D. Pollicization of the index finger. Method and results in aplasia and hypoplasia of the thumb. *J Bone Joint Surg Am*. 1971;53:1605–1617.
119. Woolf RM, Broadbent TR. The four-flap Z-plasty. *Plast Reconstr Surg*. 1972;49:48–51.
120. Foucher G, Medina J, Navarro R, et al. Correction of first web space deficiency in congenital deformities of the hand with the pseudokite flap. *Plast Reconstr Surg*. 2001;107:1458–1463.
121. Tajima T, Watanabe Y, Uchiyama J. [Treatment and study of the hypoplastic thumb]. *Keisei Geka*. 1967;10:227–234.
122. Upton J, Havlik RJ, Coombs CJ. Use of forearm flaps for the severely contracted first web space in children with congenital malformations. *J Hand Surg Am*. 1996;21:470–477.
123. Huber E. Relief operation in the case of paralysis of the median nerve. 1921. *J Hand Surg [Br]*. 2004;29:35–37.
124. Scharizer E. Dreigliedrige daumen. *Fortschr Röntgenstr*. 1929;40:693–694.
125. Upton J, Schoen S. Triphalangeal thumb. In: Gupta A, Kay SP, Scheker LR, eds. *The Growing Hand*. 1st ed. London: Mosby; 2000:255–268.
126. Hovius SE, Zuidam JM, de Wit T. Treatment of the triphalangeal thumb. *Tech Hand Up Extrem Surg*. 2004;8:247–256. In the triphalangeal thumb, the extra phalanx can have different shapes, from wedge to rectangular. Furthermore, the involved joints, ligaments, muscles, and tendons of the first ray, from distal interphalangeal joint to radiocarpal joint can be hypoplastic, malformed, or absent with varying degrees of stiffness or instability. Also, the first web can be insufficient and radial polydactyly as well as other hand deformities can be present. In this series depending on the malformation, operations varied from removal of the delta phalanx with ligament reconstruction to multiple osteotomies and rebalancing as well as pollicization.
127. Zuidam JM, Dees EE, Lequin MH, et al. The effect of the epiphyseal growth plate on the length of the first metacarpal in triphalangeal thumb. *J Hand Surg Am*. 2006;31:1183–1188.
128. De Haas WHD. Camptodactylie. *Ned Tijdschr Geneesk*. 1957;101:2121–2124.
129. Tamplin R. *Lecture on the Nature and Treatment of Deficiencies*. London: Longman, Brown, Green; 1846:256–267.
130. Adams W. On congenital contraction of the fingers and its association with “hammer toe”; its pathology and treatment. *Lancet*. 1891;138:111–114.
131. Oldfield MC. Campylodactyly: flexor contracture of the fingers in young girls. *Br J Plast Surg*. 1956;8:312–317.
132. Smith PJ, Grobbelaar AO. Camptodactyly: a unifying theory and approach to surgical treatment. *J Hand Surg Am*. 1998;23:14–19.
133. Millesi H. Camptodactyly. In: Littler J, Cramer L, Smith J, eds. *Symposium on Reconstructive Hand Surgery*. St. Louis, MO: Mosby; 1974:175–177.
134. Smith RJ, Kaplan EB. Camptodactyly and similar atraumatic flexion deformities of the proximal interphalangeal joints of the fingers. A study of thirty-one cases. *J Bone Joint Surg Am*. 1968;50:1187–1203.
135. Courtemanche AD. Campylodactyly: etiology and management. *Plast Reconstr Surg*. 1969;44:451–454.
136. McFarlane RM, Classen DA, Porte AM, et al. The anatomy and treatment of camptodactyly of the small finger. *J Hand Surg Am*. 1992;17:35–44.
137. McFarlane RM, Curry GI, Evans HB. Anomalies of the intrinsic muscles in camptodactyly. *J Hand Surg Am*. 1983;8:531–544.
138. Gupta A, Burke FD. Correction of camptodactyly. Preliminary results of extensor indicis transfer. *J Hand Surg [Br]*. 1990;15:168–170.
139. Benson LS, Waters PM, Kamil NI, et al. Camptodactyly: Classification and results of nonoperative treatment. *J Pediatr Orthop*. 1984;14:814.
140. Foucher G, Lorea P, Khouri RK, et al. Camptodactyly as a spectrum of congenital deficiencies: a treatment algorithm based on clinical examination. *Plast Reconstr Surg*. 2006;117:1897–1905. *Camptodactyly is classified into four groups. Camptodactyly can be correctible or non-correctible and can be moderate or severe. Careful assessment with clinical tests can distinguish the possible treatment, varying from splinting, the lasso procedure with or without lumbrical repositioning, and tendon transfer of the FDS of the fourth or fifth finger.*
141. Hori M, Nakamura R, Inoue G, et al. Nonoperative treatment of camptodactyly. *J Hand Surg Am*. 1987;12:1061–1065.
142. Miura T, Nakamura R, Tamura Y. Long-standing extended dynamic splintage and release of an abnormal restraining structure in camptodactyly. *J Hand Surg [Br]*. 1992;17:665–672.
143. Engber WD, Flatt AE. Camptodactyly: an analysis of sixty-six patients and twenty-four operations. *J Hand Surg Am*. 1977;2:216–224.
144. Smith DW. Recognizable patterns of human malformation: genetic, embryologic, and clinical aspects. *Major Probl Clin Pediatr*. 1970;7:1–368.
145. de Marinis FM, de Marinis R. Frequency of clinodactyly in children between the age of 5 and 12. *Acta Genet Med Gemellol (Roma)*. 1955;4:192–204.
146. Burke F, Flatt A. Clinodactyly. A review of a series of cases. *Hand*. 1979;11:269–280.
147. Flatt A. *The Care of Congenital Hand Anomalies*. 1st ed. St. Louis, MO: Quality Medical; 1977:154–163.
148. Schmid F, Moll H. *Atlas der Normalen und Pathologischen Handskeletentwicklung*. Berlin: Springer Verlag; 1960.
149. Jaeger M, Refior HJ. The congenital triangular deformity of the tubular bones of hand and foot. *Clin Orthop Relat Res*. 1971;81:139–150.
150. Wood VE, Flatt AE. Congenital triangular bones in the hand. *J Hand Surg Am*. 1977;2:179–193.
151. Theander G, Carstam N. [Longitudinally bracketed diaphysis]. *Ann Radiol (Paris)*. 1974;17:355–360.
152. Jones GB. Delta phalanx. *J Bone Joint Surg Br*. 1964;46:226–228.
153. Tamplin RW. *Lectures on the Nature and Treatment of Deformities Delivered at the Royal Orthopaedic Hospital*. London: Longman, Brown, Green; 1896:256.
154. Hersch AH, de Marinis FM, Stecher RM. On the inheritance and development of clinodactyly. *Am J Hum Genet*. 1953;5:257–268.
155. Fürst J. Ein Fall von Verkürzten und Zweigliedrigen Fingern Begleitet von Brustmuskeldecten und anderen Missbildungen. *Zeitschr Morphol Antropol*. 1900;2:56–76.
156. Ali M, Jackson T, Rayan GM. Closing wedge osteotomy of abnormal middle phalanx for clinodactyly. *J Hand Surg Am*. 2009;34:914–918.
157. Al-Qattan MM. Congenital sporadic clinodactyly of the index finger. *Ann Plast Surg*. 2007;59:682–687.

158. Vickers D. Clinodactyly of the little finger: a simple operative technique for reversal of the growth abnormality. *J Hand Surg [Br]*. 1987;12:335–342.
159. Caouette-Laberge L, Laberge C, Egerszegi EP, et al. Physiolysis for correction of clinodactyly in children. *J Hand Surg Am*. 2002;27:659–665.
160. Oberg KC, Feenstra JM, Manske PR, Tonkin MA. Developmental biology and classification of congenital anomalies of the hand and upper extremity. *J Hand Surg Am*. 2010;35:2066–2076.
161. IFSSH Scientific Committee on Congenital Conditions. *J Hand Surg Eur Vol*. 2014;39:676–678.
162. Swanson AB, Barsky AJ, Entin MA. Classification of limb malformations on the basis of embryological failures. *Surg Clin North Am*. 1968;48:1169–1179.
163. Tonkin MA, Oberg KC. The OMT classification of congenital anomalies of the hand and upper limb. *Hand Surg*. 2015;20:336–342.

Congenital hand V: Overgrowth, undergrowth, and generalized skeletal deformities

Julie Colantoni Woodside, Shelley Noland, and Terry Light

SYNOPSIS

- Contemporary understanding of limb embryology and morphologic characteristics has shaped the Oberg–Manske–Tonkin (OMT) classification of upper extremity anomalies. The OMT classification categorizes congenital upper extremity anomalies as malformation, deformation, or dysplasia.
- Undergrowth of the upper extremity affects a portion of or the entire extremity. Variable presentations include hypoplasia or aplasia of bone and soft tissue. These may be associated with a syndrome.
- Overgrowth includes syndromes as well as isolated conditions of enlargement such as macrodactyly. The presentation and natural history of macrodactyly in the upper limb varies greatly. Treatment by debulking or amputation may require sequential procedures to balance growth, appearance, and function.
- Generalized skeletal anomalies of the hand include conditions such as multiple hereditary osteochondromas, Maffucci syndrome, and Ollier disease. Treatment of skeletal abnormalities of the hand and forearm requires accurate diagnosis and careful monitoring during years of rapid skeletal growth. Surgical intervention is indicated to preserve joint motion.

Classification

Historically, the Swanson classification, accepted by the International Federation of Societies for Surgery of the Hand (IFSSH) in 1974 has been the most widely used classification for congenital abnormalities of the upper limb.¹ A new classification system, developed by Oberg, Manske, and Tonkin (OMT)² is based on a more contemporary understanding of developmental biology. The OMT system uses dysmorphic descriptions and the three axes of the limb development to classify conditions based on their effect on the hand plate and/or the entire limb. The IFSSH adopted this classification with some modifications in 2014³ (see Chapter 25 and Table 25.2 for most recent update).

The OMT classification categorizes abnormalities as malformations, deformations, or dysplasias. Malformations are further divided into the developmental axis (proximal–distal, anteroposterior, and dorsal–ventral) and the extent of involvement as either affecting the entire limb or simply the hand. Deformations include any disruption to a portion of the upper limb that has already been formed. Dysplasias are abnormalities in size, shape, and organization of cells including conditions that are associated with cellular atypia or tumor formation.² The intra-observer reliability of the classification system is 85–99% with perfect agreement in inter-observer reliability of 64%, moderate of 19%, fair of 3%, and slight of 13%, and poor of 1%. Undergrowth conditions and brachydactyly show poor agreement, while arthrogryposis, Madelung deformity, and symbrachydactyly show slight agreement.⁴

Overgrowth

Introduction

Congenital limb enlargement and overgrowth is a rare condition affecting 1/100,000 live births.⁵ The natural history and presentation of overgrowth conditions such as macrodactyly varies greatly. Upper extremity overgrowth can be associated with several syndromes including Beckwith–Wiedemann, Proteus, and CLOVES.⁶ The diagnosis and understanding of these conditions has advanced in recent years with genetic sequencing of involved tissues. Mutations in the *PIK3CA* gene are associated with overgrowth of fibroadipose tissue. Segmental and progressive growth of the subcutaneous, muscular, neural, and skeletal tissues can be found in tissues with the *PIK3CA* gene mutation.⁷

Keppler-Noreuil *et al.*⁷ studied 35 patients with overgrowth and found 25 had phenotypes consistent with fibroadipose overgrowth, hemihyperplasia, multiple lipomatosis, or macrodactyly. Thirty-three of 35 demonstrated one of two genotype mutations. All of these patients had progressive,

asymmetric overgrowth. Six had upper extremity manifestations. The distal aspect of the limb was often the first to area to manifest overgrowth; proximal progression of enlargement could develop with further growth. Sixty percent (21/35) of cases were unilateral, 42% had renal abnormalities, and all patients showed adipose dysregulation. In the patients with hand manifestations, all had surgery, none had ovarian/testicular manifestations, one had an enlarged kidney (this patient had global, bilateral presentation), one had a congenital heart defect, and four had vascular malformations.⁷ Overall weight and height were normal except in three patients whose height was less than fifth percentile.⁷

Neurofibromatosis may also present with overgrowth in which the skin and subcutaneous tissue planes are enlarged by soft-tissue neurofibromas, schwannomas, and other nerve sheath tumors.⁸

Proteus syndrome has a variety of soft-tissue and skeletal abnormalities in addition to overgrowth of the hands or feet. These patients have cerebriform, hyperkeratotic skin on their palms and soles. They may develop cartilaginous masses, joint stiffness (flexion contracture), angulation, and rotational deformities in the hands. This is a progressive overgrowth in which all tissues are larger than normal without adipose infiltration.⁸

Patients with hemihypertrophy present after birth with enlargement of one extremity, or one side of the body. The hands usually have a flexed wrist with ulnar deviation of the digits and a flexed, adducted thumb. The muscle-tendon groups do not have normal excursion and progressive contractures are seen with growth of the limb.⁸

Klippel-Trénaunay syndrome is associated with a slow-flow vascular lesion that contains capillaries, veins, and/or lymphatic components, with enlarged hands or extremities due to skeletal, adipose, and vascular growth.⁸

CLOVE syndrome includes capillary malformations, lipomatous overgrowth, vascular malformations, epidermal nevi, and skeletal distortions with central nervous system components.

Other syndromes including Maffucci syndrome and Ollier disease show enlargements due to vascular malformations and enchondromas.⁸

To delineate these overlapping overgrowth disorders associated with similar genetic mutations, Keppler-Noreuil *et al.* reported the collaboration of several clinicians that outlined specific characterization of disease for management and prognosis.⁶ All cases of *PIK3CA*-related overgrowth spectrum (PROS) are sporadic, with mosaic distribution of involved tissues. The condition may be evident at birth or may be detected in early childhood presentation. Children may either have isolated findings or a spectrum of features. Most, but not all, are progressive. The authors stress that although these are distinct clinical disorders, there is still much overlap in PROS.⁶

Macrodactyly

Macrodactyly describes the overgrowth of bony and fibroadipose tissue, often in a pattern that mimics a local nerve. Muscular overgrowth may be associated with macrodactyly.^{9,10} Macrodactyly is sporadic unilateral 90% of the time, and not associated with malignant transformation.¹⁰ Rios *et al.*¹⁰ genetically sequenced and histologically examined specimens from macrodactylous tissue (n=6) and confirmed mutations

Table 29.1 Types of macrodactyly

Type	Description
I	Macrodactyly with lipofibromatosis of a nerve, static or progressive
II	Macrodactyly associated with neurofibromatosis
III	Macrodactyly associated hyperostosis
IV	Macrodactyly associated hemihypertrophy
(Reproduced with permission from Upton J. Mathes SJ, Hentz VR (eds). Failure of Differentiation and Overgrowth. In: <i>Plastic Surgery</i> , 2nd edn. Philadelphia, PA: Saunders; 2005.)	

in the *PI3K* gene. The rate of growth, location, and the severity should be evaluated on an individual patient basis.¹¹ Four types of macrodactyly have been defined by Upton (Table 29.1).¹²

The clinical presentation varies with each patient. The hand may show overgrowth with excessive adipose formation. Affected digits often deviate away from each other due to asymmetric over growth in the adjacent sides of adjacent digits (Fig. 29.1). Overgrowth in the palm and forearm is often apparent as well as fat deposits extending up to the axilla and chest wall.⁸ Excessive adipose tissue, commonly seen along the median nerve in the hand (nerve territory-oriented macrodactyly)⁹ usually requires multiple debulking surgical procedures, epiphysiodesis of the phalanges, osteotomy, arthrodesis, and/or amputation of hypertrophic digits. Neural elements are often enlarged along the palmar aspect of the hand.⁹ In contrast, the vessels are usually of normal or smaller size.¹⁰

Macrodactyly can be static or progressive. The static type shows enlargement at birth with proportional growth as the child grows. *Macrodystrophia lipomatosa* refers to the progressive form of macrodactyly with associated osseous and



Fig. 29.1 This pediatric patient with macrodactyly shows an enlarged middle and slightly enlarged index finger with middle finger deviation away from the index finger. (Courtesy of OrthoCarolina Hand Fellowship Teaching File.)



Fig. 29.2 A 14-month-old male patient with congenital, progressive macrodactyly.

adipose overgrowth. Occasionally, the overgrowth appears static in the distal aspect of the extremity but progresses proximally. This progression may follow surgical debulking or partial amputation.⁹ Timing of surgery differs between the two types. Reduction surgeries and epiphysiodesis are performed later in the static type and outcomes are more predictable. Patients with the progressive form may require earlier and repeat surgeries, while patients with unrestricted, progressive growth may require amputations of large bulky parts (Figs. 29.2 & 29.3A–E).⁸

Skeletal components can demonstrate increase in length, width, and girth. Involved epiphyses can show asymmetry

and accelerated growth. Premature osteoarthritis is common in the affected by the third decade.⁸ Standard radiographs of macrodystrophia lipomatosa show osseous and soft-tissue overgrowth with splayed, broad, elongated phalanges and secondary degenerative joint disease.^{9,13,14}

Magnetic resonance imaging of the affected area may show deposits of fat within the nerve sheath, bone marrow, periosteum, muscles, and subcutaneous tissues, with fatty tissue masses and proportional enlargement of mesenchymal tissues.^{13,15} The fatty masses are hyperintense on T1 images and have a lower signal on T2 images.

Though reports vary, there appears to be a relationship between fibrolipomatous hamartoma of nerve and macrodystrophia lipomatosa.^{16,17} Histological analysis shows abnormal fatty tissue interspersed with nerve bundles with endoneural and perineural fibrosis.^{16,18} The perineurium in macrodactyly is thickened and the number of myelinated axons is reduced.¹⁰ Swollen, dissociated Schwann cells, interstitial fat, and dense endoneural connective tissue are frequent findings.¹⁰ Because the nerves in the palm are enlarged compressive neuropathies are common. If this compressive neuropathy is unrecognized the patient may develop altered sensory function.⁸

Treatment

Treatment of patients with overgrowth conditions is patient specific and attempts to address both function and appearance. Surgical planning should consider patient age, clinical syndrome, severity, progression, deformity, function, range of motion, and the expectations of the patient and family




Fig. 29.3 (A–E) This patient underwent index ray amputation. (Courtesy of OrthoCarolina Hand Fellowship Teaching File.)

members. Discussions with the family should include arthritis and stiffness, recurrence, and the possibility of multiple procedures. Serial radiographs demonstrate the extent of deformity and progression while magnetic resonance imaging (MRI) scans demonstrate other abnormalities that may be present. Timing for procedures is patient specific. Epiphysiodesis should be considered when the digit or hand reaches the size of one of the adult parents. Other surgeries include debulking, osteotomies, and neuroplasty. Amputation is considered early in very aggressive cases or when reconstruction may not provide optimal outcomes.⁸

Surgical incision placement is important, as volar scars can lead to hypertrophy and contracture. Midaxial incisions are preferable as they can be used at revision surgeries. Palmar incisions distal to the carpal tunnel should be in zig-zag configuration. Only one side of a digit should be worked on at a time for the prevention of vascular compromise. Arterial segments can be reconstructed with vein grafts as needed to preserve blood flow. Care should be taken to preserve sensation, especially on the ulnar thumb and radial index finger for pinch.⁸

Digit salvage may be possible through soft-tissue and skeletal reduction surgeries. Growth arrest will halt longitudinal growth of the digit and can be accomplished through use of a drill, an osteotome, or a burr to destroy the physis. Physeal stapling is potentially reversible and in selected instances may allow gradual correction of angular deformity. Soft-tissue debulking should be thorough with preservation of digital arteries and at least two dorsal veins per digit. Precise surgical techniques are important for salvage of vincular branches to the flexor tendons and to perform neuroplasty and pulp reduction. The remaining skin will be reinnervated from the remaining digital nerve⁸ (Figs. 29.4–29.10).

Historically, a number of strategies have been advocated for the surgical management of macrodactyly. Barsky reduced the longitudinal axis through resection of the distal portion of the middle phalanx, distal interphalangeal joint (DIP) and distal phalangeal physis with sacrifice of the often relatively stiff DIP joint motion.¹⁹ The author also described stapling or wiring of the epiphyseal plate and concluded that results from surgery are not entirely satisfactory. Tsuge described resection of all three physes of the phalanges combined with tip-plasty.²⁰ Hoshi shortened the digit through resection of the DIP joint with fusion and unilateral longitudinal soft-tissue wedge resection. Millesi described a resection of the distal phalanx of the thumb with shortening of the proximal phalanx through an oblique shortening osteotomy.²¹ Ogino described a resection osteotomy of the proximal phalanx, osteotomy with fusion of the DIP joint and tip and unilateral soft-tissue resection.²² Bertelli performed longitudinal resection osteotomies of the distal, middle, and proximal phalanges with tip and unilateral soft-tissue resection.²³

Outcomes

Cerrato *et al.*¹¹ evaluated 21 patients with isolated macrodactyly of one or more digits. Right hand involvement was seen in 67%, progressive overgrowth in 67%, and nerve-territory orientation in 57% (the others with lipomatous forms). The territory affected in 10 out of the 12 nerve-territory orientation patients was in the median nerve distribution. Enlarged




Fig. 29.4 (A,B) A male patient with macrodactyly of the small finger with overgrowth on the ulnar aspect and radial curvature of the digit.

nerves were seen intraoperatively in all nerve-oriented and lipomatous patients. The most common finger involved was the middle finger (67%) followed by the index finger (47%). Those with progressive overgrowth underwent more surgeries: 4.1 versus 1.8 per patient. Nearly all patients (19/21) underwent soft-tissue debulking, with other procedures including closing wedge osteotomies (11 patients), partial amputation/osteotomy (9 patients), epiphysiodesis (7 patients), and ray amputations (6 patients). Other associated procedures included neuroplasties of median, ulnar, and radial nerves and syndactyly release. Closing wedge osteotomy was employed for angulation greater than 30° or for correction





Fig. 29.5 (A,B) Same patient as in Fig. 29.4: a coronal and axial cut of an MRI through the macrodactyly digit showing increased signal with fatty tissue proliferation along the volar and ulnar aspect of the digit.



Fig. 29.6 Same patient as in Fig. 29.4: anterior-posterior X-ray of the hand showing the radial curvature of the digit.



Fig. 29.7 Same patient as in Fig. 29.4: (A,B) surgical planning for debulking procedure.




Fig. 29.8 Same patient as in Fig. 29.4: enlarged digital nerve lying on top of hemostat supplying the overgrown tissue.



Fig. 29.9 Same patient as in Fig. 29.4: nerve entering into tissue being excised.

of digital scissoring. The authors recommend epiphysiodesis when the affected digits reached the adult length of their parents' hands.

Hardwicke *et al.*²⁴ reviewed 32 patients with macrodactyly, 20 affecting the upper limb. There was a slight male predominance in their series (male:female = 1:0.66). The authors




Fig. 29.10 Same patient as in Fig. 29.4: (A) digit before closure and excised tissue and (B) finger after tissue debulking and closure.

found the middle ray affected most frequently with an average of 2.5 digits affected, usually adjacent. Six of 20 cases were progressive; 16 of the 20 cases were treated surgically. Patients underwent an average of 2.5 surgeries with static disease requiring fewer surgeries.

Overview

Overgrowth conditions can be associated with syndromes or can be isolated, as in macrodactyly. Patients have varied presentations and should have an individual approach for treatment options. Progressive overgrowth requires a more aggressive approach and will require more surgeries than static conditions.

Clinical tips

Overgrowth

- Macrodactyly may be associated with an overgrowth syndrome.
- Can be static or progressive – each patient needs an individual treatment approach.
- Progressive types require a more aggressive approach and more surgeries than static types.

Undergrowth

Introduction

Congenital upper limb anomalies occur in approximately 5.25 per 10000 live births. Among these anomalies, undergrowth anomalies occur approximately 1.19 per 10000 live births.²⁵ Undergrowth conditions are classified as malformations in the OMT classification and are subclassified as either under the entire limb or hand plate only along the proximal–distal axis.³

Brachydactyly

Brachydactyly, Greek for “short finger”, is a condition isolated to the hand plate that presents with shortened digits. Some types show autosomal-dominant inheritance patterns.²⁶ Brachydactyly may occur in isolation but more commonly it is associated with other hand malformations.²⁷ The index and small fingers are the most commonly involved digits while the middle phalanx is the most commonly affected bone. Brachymetacarpia refers to brachydactyly isolated to the metacarpals.⁵

Bell²⁸ defined subgroup types of brachydactyly (Table 29.2). Brachydactyly has also been associated with hereditary multiple exostosis.²⁹

Treatment

Treatment of brachydactyly depends on the severity of shortening. Typically, function is preserved and surgical

Table 29.2 Groups of brachydactyly

Type	Description
A	Shortened middle phalanges
B	Short or absent middle or distal phalanges with deformed thumbs and great toes
C	Deformity of the middle and proximal phalanges of the index and middle fingers with shortening of the metacarpals
D	Short and broad distal phalanx of the thumb and great toes
E	Shortening of one or more of the metacarpals

intervention usually focuses upon aesthetic concerns.²⁷ In brachymetacarpia, the patient will often present with one knuckle that is not apparent when the patient makes a fist. This abnormality usually does not limit the patient’s function, unless the thumb or index fingers are involved.³⁰ The metacarpal physis usually closes prematurely and the resultant metacarpophalangeal joint demonstrates limited flexion (Fig. 29.11A,B). To address the loss of length, one may consider distraction lengthening of the affected bone. In cases of severe ray shortening or in cases in which multiple digits are affected, hand function can be compromised. Options for treatment of such cases include webspace deepening, osteotomy and bone grafting, non-vascularized toe phalanx transfer, distraction lengthening, and microsurgical toe to hand transfers.³¹

Although brachydactyly, symbrachydactyly, and transverse deficiency primarily affect the hand plate, others can also affect the entire upper limb.³

Clinical tips

Brachydactyly

- Brachydactyly can affect the entire finger or individual bones of the finger.
- Treatment is usually observation, but surgical options include: phalangeal and metacarpal lengthening, osteotomy, and web deepening.




Fig. 29.11 (A,B) Anterior–posterior (AP) and comparison AP X-rays of a skeletally immature patient with middle finger brachymetacarpia with premature closure of metacarpal head growth plates. (Courtesy of OrthoCarolina Hand Fellowship Teaching File.)

Sybrachydactyly

Sybrachydactyly, is a rare upper limb anomaly seen in approximately 0.6 per 10000 live births. It most commonly affects males (73%) and is typically unilateral (left side 67%, right side 27%). Between 1% and 7% of patients have bilateral presentation. Only 7% have associated anomalies or a positive family history.³²

Surgeon classification of the different manifestations of sybrachydactyly is inconsistent. The previous IFSSH classification system categorized sybrachydactyly under categories I, II, and V; or failure of formation, differentiation, and undergrowth, respectively.³³ The OMT classifies the condition as a malformation in the failure of axis formation/differentiation of the entire limb and/or hand plate.^{2,4} Blauth and Gekler subdivided sybrachydactyly into four types (Table 29.3).³⁴

Sybrachydactyly is divided into four types: (1) short finger type; (2) oligodactylic, atypical cleft hand; (3) monodactylic; and (4) peromelic. Sybrachydactyly presents with a hand or entire limb that is shorter and smaller than the uninvolvement upper limb. The digits are short, underdeveloped and often have incomplete syndactyly.³⁵ Since the mesoderm is primarily affected, the fingernails and distal phalangeal tufts (ectodermal elements) are often preserved.³⁶ The central digits and middle phalanges are usually more severely affected.³⁶ Patients may present with small nubbins that have nails present. Digital amputations due to constriction bands are distinguishable by the presence of other bands elsewhere on the body and absent distal finger and nail. Anatomic structures proximal to the hand are often hypoplastic in sybrachydactyly, while proximal structures are usually normal in hands affected by constriction ring syndrome.^{35,36}

Poland association (PA) is the association of sybrachydactyly with unilateral absence or hypoplasia of the sternal head of the pectoralis major muscle. There is no known

genetic etiology. In contrast to sybrachydactyly without PA, PA is seen more commonly on the right side.³⁷ It has been suggested that the cause is disruption of the subclavian artery during growth and development causing underdevelopment of the limb.³⁸ Catena *et al.*³⁷ demonstrated that 57.7% of PA patients had associated upper limb anomalies including hypoplastic hand without functional or morphologic anomalies (8%), sybrachydactyly with five functioning fingers (20.6%), sybrachydactyly and some functioning fingers (14.9%), and sybrachydactyly with absent or non-functioning fingers (4.6%).

Treatment

The individual presentation of each hand provides a guide for treatment. Treatment should aim to increase the child's functional capability. An untreated aplastic hand without digits can serve as a helping hand and can be fitted with a prosthesis. A monodactylous hand usually has a functioning thumb and a palm width with hypoplastic or normal metacarpals. Bimanual tasks with thumb and palm grip/pinch and pressing or hooking with one finger are possible. With a bidactylous hand, usually a thumb and an ulnar digit, two-finger pinch is possible but grip is usually weak.^{35,39} These children have difficulty with cylindrical pinch, or wrapping their finger around a larger object with the thumb underneath. If the child has three functioning digits, then tip, palm, and cylindrical grip are possible, although they will still lack full-power grip.⁵ With four or five digits, power grip is increased, although the fingers may have unstable interphalangeal joints; these children may be capable of single-hand prehension.²

Treatment of these hands may include excision of nubbins, syndactyly release, webspace deepening, joint stabilization, bone transfer, and microvascular second toe transfer.³⁵ Since many manual skills are developed by the age of 3 years,^{40,41} early reconstruction can help in the development of grasp and pinch.⁴²

Hypoplastic nubbins, which may have rudimentary, difficult to care for nails, may occasionally block the prehensile function of adjacent digits. These small digits can be excised if the family wishes and if they have extrinsic tendons, these can be used for toe-to-hand transfer or free phalanx toe transfer.³⁵

Often the interphalangeal joints that are present in hypoplastic digits are unstable to pinch. In older skeletally immature children, these joints may benefit from physis-preserving interphalangeal arthrodesis. The phalangeal condyle is denuded of articular cartilage and is fused to the secondary ossification center of the more distal phalanx.³⁵ Distraction lengthening of the digit can be performed and combined with other procedures.⁴³ Digits with distal webs or syndactyly should undergo web deepening or syndactyly release with or without full-thickness skin grafting.³⁵

Non-vascularized toe phalanx transfer can add osseous stability to digits if an adequate soft-tissue sleeve is present. The proximal phalanx of the third or fourth toe is harvested extraperiosteally with its proximal collateral ligaments and plantar plate. The soft tissues are sutured to the metacarpal head creating a stable articulation. Harvesting the graft extraperiosteally and preserving the distal articular surface prevents resorption.³¹ Goldberg and Watson⁴⁴ found 91%

Table 29.3 Subdivisions of sybrachydactyly

Sybrachydactyly type	Description
Short finger (brachymesophalangia)	All four fingers are short and incompletely formed with a relatively normal thumb; middle phalanges may be missing with incomplete syndactyly
Oligodactylic (atypical cleft hand):	The central portion of the hand is aplastic, whereas the borders digits are less severely affected
Monodactylic	The fingers are absent or aplastic, whereas the thumb is present
Peromelic	Pesembles a transverse amputation at the metacarpophalangeal joint level, may have nubbins with or without nail remnants
(Reproduced with permission from Julie C. Woodside, MD,* Terry R. Light, MD* Sybrachydactyly — Diagnosis, Function, and Treatment. <i>J Hand Surg Am.</i> Vol. 41, January 2016).	

radiolucent physes and 83–100% growth of the contralateral phalanx if the patient was between 6 and 18 months old at the time of surgery. As the patient's age at surgery increased, the percentage of open physes decreased (67% if between 18 months and 5 years; 50% if older than 5 years), but the percentage of growth remained the same. Over time, patients have reported donor site morbidity in the residual foot. Concerns have been related to the appearance of the foot and footwear issues related to abnormal toe position. Donor toes may be short, floppy and unstable. Deformity is sometimes noted in adjacent toes.⁴⁵ Donor toe deformity may be minimized by iliac crest bone graft placed at the donor site.⁴⁶

Distraction lengthening of a short phalanx or metacarpal can be accomplished with or without intercalary bone grafting. The technique expands the osseous and soft-tissue length of the digit and does not require neurovascular reconstruction.⁴⁷ Kessler *et al.*⁴⁷ in 1977 applied osteotomy and distraction lengthening of one or more metacarpals in 11 children between 5 and 11 years of age, achieving 2.5–4 cm of length. Each patient underwent a second procedure for interposition of bone graft to encourage earlier healing. Arslan³⁰ reviewed six patients who underwent distraction osteogenesis without grafting for brachydactyly. Indications were decreased pinch and cosmesis. A proximal metaphyseal osteotomy and external fixator were used in all but one patient who had a diaphyseal osteotomy. After a 6-day resting period, lengthening was accomplished at 0.25 mm/day until desired length and the fixator was then left in place until consolidation (average 12.25 weeks). Pinch improved in the patients with thumb (n=2) and index finger (n=2) lengthening, but those performed for cosmesis of ring finger (n=2) brachymetacarpia were dissatisfied with the scar tissue appearance from the pin sites.

Thumb and first webspace abnormalities are common. The supinated thumb can lie in the plane of the hand, with limited grasp and pinch.⁴⁸ The thumb may be adducted and retropulsed. Metacarpal rotational osteotomy can better position the thumb for pinch. Deepening the first web with release of tight fascia and contracted muscle can be done at the same surgery. A dorsal rotational flap, dorsal and palmar triangular flaps, or a four-flap Z-plasty can be used to widen the first webspace.⁴⁹ Langer *et al.*⁴⁸ combined first webspace deepening with an abduction–rotational osteotomy of the thumb metacarpal in 14 patients. The average palmar abduction of the metacarpal was 73° with pronation of 60–90° for pulp-to-pulp pinch. In some patients, Huber transfer for opposition, metacarpal lengthening, interphalangeal joint arthrodesis, long finger metacarpal lengthening, and syndactyly release were performed in conjunction with the thumb reconstruction. Patients underwent an average of four surgeries per hand. Because of recurrent deformity, three of 14 patients underwent revision osteotomy, while eight of 14 underwent repeat first web deepening. All patients were ultimately able to perform key pinch, lateral pinch, and experienced subjective improvement in function and appearance. Five patients were unable to oppose the thumb to any digit.

Adding sensate digits to a hand can increase a child's prehension, pinch, grasp, and function. Microsurgical toe transfers are useful for a child with an absent thumb distal to the carpometacarpal joint, absent digits except an ulnar finger, and for an adactylous hand.⁴² The adactylous hand will

require one mobile digit and at least a stable post or another mobile digit to achieve prehension. Survival rates are generally greater than 95%.⁵⁰ The procedure was first described by Cobbett⁵¹ and Buncke⁵² as a single-stage second toe transfer to the hand. When transfer of two toes is recommended, it may be accomplished in one or two stages, harvesting the second toe from each foot. Surgery is usually delayed until ages 2–5 years to allow the vessels to be of adequate size.⁵⁰ The symbrachydactyly hand presents challenges different from those following traumatic amputation or in a child with constriction ring syndrome, since the hand with symbrachydactyly often has hypoplastic or absent musculotendinous units, nerves, and arteries.^{53,54} Often, the common extensor and flexor mass are used as motors for the transfer. The median nerve is occasionally absent, requiring that other nerves such as the dorsal sensory branches of the radial nerve are used to achieve volar reinnervation.⁵⁵

Jones *et al.*⁵⁰ reported a microvascular success rate of greater than 97% with micro-anastomosis re-exploration required in 8.5% of 82 digits. Vilkki³⁹ reported that 14 of 17 patients undergoing toe transfer achieved the ability to actively pinch. Although most re-operations are performed because of limited digital motion, tenolysis has not been shown to improve motion. Transferred digits function primarily as a post.^{53,56} In a series of 28 second toe transfers in 14 patients, Van Holder *et al.*⁵⁷ found a mean extension deficit of 20° and total active flexion of 80°. In contrast, in a series of 65 second toe transfers in 58 patients, Foucher *et al.*⁵⁸ reported an average extensor lag of 25° but total active motion of only 38°.

The long-term outcomes of microsurgical toe transfers have been reported by Kaplan and Jones⁴² using the Pediatric Outcomes Data Collection Instrument (PODCI). In 12 patients with an average follow-up of 7.6 years post-surgery, two re-operations were performed: a tenolysis with arthrodesis and a sural nerve grafting with a rotational osteotomy. The parents reported lower scores for upper extremity function, sports and physical function, and global function, and levels of happiness similar to general population while the patients reported lower than normal scores in upper extremity function and transfer and mobility but levels of happiness higher than the normal population.

Kay *et al.*⁵⁶ reported the psychological outcomes after toe-to-hand transfers in 17 patients with symbrachydactyly. Both the parents and patients had a high level of satisfaction for appearance, function, reaction of others, well-being, and donor site. The authors also found lengths of up to 100% of the contralateral toe with normal growth (Figs. 29.12–29.16).

Clinical tips

Symbrachydactyly

- Symbrachydactyly patients can be evaluated based on number of functioning digits.
- This can be used to strategize a treatment plan to advance their function.
- Conservative observation as well as surgical procedures from nubbin removal, web deepening, to toe transfer are available treatment options.




Fig. 29.12 (A) A comparison bilateral anterior–posterior (AP) X-ray of a 9-month-old male with bilateral symbrachydactyly and (B) an AP X-ray of just the right hand. These show shortened digits with absent middle phalanges and retained proximal and distal phalanges.



Fig. 29.13 (A,B) Left hand dorsum and palm of the patient from Fig. 29.12 with shortened digits and syndactylized small and ring fingers.



Fig. 29.14 (A,B) The patient from Figs. 29.12 and 29.13 with hands side by side and just the dorsum of the right hand. This shows distal webs beyond the metacarpal phalangeal joints



Fig. 29.15 (A,B) The patient from Figs. 29.12–29.14: postoperative photographs of the palmar left and right hands, respectively. The left hand underwent separation with full-thickness skin grafting of the ring and small fingers. The right hand underwent webspace deepening of the ring–small and index–middle fingers.

Skeletal abnormalities

Introduction

Generalized skeletal abnormalities include multiple hereditary osteochondromas, Maffucci syndrome, and Ollier disease.

Multiple hereditary osteochondromatosis

Multiple hereditary osteochondromatosis (MHO) is a skeletal dysplasia that affects bones that develop through endochondral ossification. It is inherited through an autosomal-dominant pattern and is also referred to as *multiple hereditary exostoses* and *multiple exostoses*.⁵⁹ Osteochondromas are common, benign bone tumors that usually form in the metaphysis of long tubular bones. Upper limb osteochondromas are commonly noted in the proximal humerus, distal radius and ulna, and metacarpals and phalanges.^{60–62} They are evident in

skeletally immature children, growing over the first decade of life and usually decrease in growth and stop growing at skeletal maturity.⁶² They are cartilage-capped exostoses that can be solitary or associated with a skeletal dysplasia as in MHO (Figs. 29.17 and 29.18).

MHO usually shows full penetrance and is usually associated with a defect in either the *EXT1* (chromosome 8) or *EXT2* (chromosome 11). These genes have a role in regulating chondrocyte maturation and differentiation, which, in turn, affects endochondral ossification.⁶³ Reports suggest that between 30% and 60%^{59,61,64} have forearm involvement while between 30% and 79%^{62,63,65–67} demonstrate hand involvement.

Osteochondromas in the hand are usually asymptomatic but can cause bone shortening and angulation. If a distal phalangeal osteochondroma is subungual, the lesion may distort nail growth. In patients with multiple lesions, operative intervention may be necessary for large lesions or to address deformity.⁶³ Woodside *et al.*⁶² reviewed 83 hands of patients with an average age of 11 years at initial presentation



Fig. 29.16 The patient from Figs. 29.12–29.15: dorsal view of the right hand following webspace deepening.




Fig. 29.17 X-ray of a 16-year-old male with familial multiple hereditary osteochondromas (MHO) with a large osteochondroma of the volar aspect of the radial.



Fig. 29.18 A clinic photograph of the prominence, the patient hand median neuropathy with a Tinel's sign over the mass.

and found the small finger was the most often affected and the thumb the least often affected. Most of the lesions were sessile, smaller tumors with <50% of the bone affected. Patients had an average of 13.1 tumors per hand and the involvement of five bones per hand. An average of two bones per hand had angulation and shortening. The metacarpals of the small and index finger were the most commonly affected bone and the metacarpals on the ulnar side of the hand tended to have the most shortening and angulation. At follow-up (average 4.6 years), an increase of 2.7 lesions per hand in the number of detected tumors was evident. Spontaneous regression of eight tumors was noted in one hand while an increase of 16 tumors was noted in another hand. Patients of 7–10 years of age demonstrated the most tumors. The largest increase

over time was seen in children age 2–6 years at initial presentation, likely reflecting rapid skeletal growth. As the patients reached skeletal maturity, the tumors stabilized and little change was seen. Cates *et al.*²⁹ and Wood *et al.*⁶⁸ also found increased involvement of the small finger and metacarpophalangeal joints of the ring and small finger, with sessile lesions the most common.

MHO of the forearm can cause bowing of the radius, shortening of the ulna with disruption of the radioulnar joint, ulnar deviation of the wrist, and radial head dislocation.^{59,61,69,70} Solomon theorized that the radius either bowed or dislocated at the radiocapitellar joint in response to relative shortening of the ulna.⁶⁷ Burgess and Cates⁶⁰ reviewed 35 patients and 65 forearms (average: 11-year follow-up) using defined radiographic measurements and using normal values from Gindhart⁷¹ (Table 29.4). The results did not show a correlation of the radial articular deformity with the degree of negative ulnar variance, which does not support a theory of ulnar tethering causing the distal radial deformity. There was a strong correlation between radial and ulnar growth deficits, with the ulna occurring at a more rapid rate. Wood⁷² and Cates⁶⁰ observed isolated distal radius metaphyseal exostosis did not affect forearm length. Ulnar shortening of more than 8% was significantly correlated with radial head dislocation. The authors also found that carpal slip was not related to any other measurements or to the severity of the disease process.⁶⁰

Gottschalk *et al.*⁵⁹ reviewed 48 patients with 76 affected forearms, initial average age of 12 years, with 7-year follow-up to determine the natural history of the forearm deformity seen in MHO patients. Forearms are classified according to osteochondroma location: (1) in distal ulna only; (2) distal radius and ulna; (3) distal radius only; (4) diaphysis of radius or ulna; and (5) proximal radius or ulna. The authors measured radial articular angle, percent ulnar variance, radial bow, radial length, and ulnar length on radiographs as

Table 29.4 Measurements for forearm multiple hereditary osteochondromatosis

Measurement	Definition
Ulnar variance (UV)	Shortening of the ulnar relative to the radius
Percent ulnar variance (PUV)	Ulnar variance/length of the linear axis of the forearm
Radial articular angle (RAA)	Angle of inclination of the distal articular surface of the radius from the linear axis of the forearm
Radial bow (RB)	Greatest distance the radial diaphysis deviates from the linear axis of the forearm divided by the length of the linear axis
Percent carpal slip (PCS)	Percentage of the lunate unsupported by the radius
Radial length (RL)	Center of proximal physis to center of distal physis
Radial shortening (RS)	Mean radial length of controls* minus the radial length of the patient
Radial z-score (R-z)	Radial shortening corrected for the standard deviation of the radial length of controls* [patient's length (mm) – normal length]/one standard deviation = ratio is the deviation of the length of the radius from that controls*
Ulnar shortening (US)	Predicted length of the linear axis minus ulnar length
Ulnar z-score (U-z)	Ulnar shortening/standard deviation

*Based on Gindhart PS. Growth standards for the tibia and radius in children aged one month through eighteen years. *Am J Phys Anthropol.* 1973;39:41-8. (Measurements from radiographs as described by Burgess RC, Cates H. Deformities of the forearm in patients who have multiple cartilaginous exostosis. *J Bone Joint Surg Am.* 1993;75:13-8.)

described by Burgess.⁶⁰ The authors did not find any significant differences in radiographic measurements with regards to the forearm classification. The smallest radial z-scores (R-z) and ulnar z-scores (U-z), indicating more severe shortening, were found in type 1 forearms that presented with a dislocated radial head. Type 4 had the largest R-z and U-z scores, or the least radial and ulnar shortening. Twelve of the 13 forearms with radial head dislocations were type 1. When type 1 forearms retained a reduced radiocapitellar joint, significant differences were seen in radial shortening (−2.2 cm vs. −3.8 cm), ulnar shortening (−3.2 cm vs. −5.2 cm), and percent ulnar variance (7% vs. 10%). The authors conclude that the results support the ulnar tether theory for radial head dislocation.⁷³ When followed longitudinally, patients with an osteochondroma of the distal ulna have a normal-appearing radius that gradually deforms with increased shortening of the ulna that can lead to eventual dislocation of the radial head. This suggests a tether around the distal radioulnar joint that impedes longitudinal radial growth, and with more severe ulnar shortening, increased radial shortening and deformity (bowing, articular surface tilting, and radial head dislocation) can be seen.⁵⁹

Treatment

Treatment remains controversial and varies from conservative observation to aggressive surgical intervention. Peterson⁶⁹ recommends intervention to prevent radial head dislocation for at-risk forearms. Surgical treatment includes excision of osteochondroma when it interferes with growth or function or causes pain, ulnar lengthening with osteotomy to prevent further radial deformity, ulnar tether release, hemiepiphyseal stapling of the radius, and osteotomy of the radius.^{59,69,72,74} Diligent radiographic monitoring of these patients is necessary.

Ollier disease and Maffucci syndrome

Ollier disease is a rare (estimated 1/100 000) congenital, non-hereditary condition that affects cartilage ossification. Involved patients form enchondromas at the metaphyseal ends of bones.⁷⁵ Enchondromas are intraosseous cartilaginous tumors. They are usually benign and can be solitary lesions or multiple. Multiple enchondromas in a region are termed Ollier disease.⁷⁵ When multiple regional enchondromas are associated with soft-tissue and visceral hemangioma malformations, the disease is termed Maffucci syndrome.⁷⁶ The metacarpals and phalanges are the common sites of hand involvement.^{75,77}

Patients present with palpable bony masses on the finger or hand and usually unilateral asymmetry of the extremity. The lesions in the metacarpals or phalanges expand the cortex and cause palpable lesions. The affected bones are often short and deformed. Radiographs can demonstrate calcifications with stippled appearance and metaphyseal widening. Initially enchondromas are adjacent to the growth plate cartilage; with growth, enchondromas migrate away from the physis.⁷⁵ Tomlinson *et al.*⁷⁷ reviewed 22 hands in 11 patients at an average age of 17 years. Tomlinson found an average of 8.1 bones affected per hand, with the most common bones being the proximal phalanges of the middle, ring, and small fingers on the left, and proximal and middle phalanges of the middle finger and middle phalanx of the ring finger on the right. The index finger and thumb were the least commonly affected bones (Fig. 29.19A–C).

Malignant transformation is possible within enchondromas. The malignant lesions show cortical erosions, extension of tumor into soft tissues, and irregularity of the surface of the tumor, while enchondromas demonstrate uniform mineralization.⁷⁵ Chondrosarcomas are less well circumscribed and show poor demarcation. Maffucci syndrome is associated




Fig. 29.19 (A–C) Anterior–posterior, oblique, and lateral X-rays of a skeletally mature patient with Ollier disease and multiple enchondromas in the ring and small fingers.

with a high risk of malignant transformation, generally quoted as being between 17% and 50%. One study has suggested that there is up to 100% chance of malignancy with very long-term follow-up. Ollier disease has a smaller risk (25–30%) of malignancy than does Maffucci syndrome.^{76,78,79}

Most multiple enchondroma patients do not have functional limitations from hand tumors, some may experience shortening, limitations from tumor size, and problems with hand appearance.⁸⁰ Kim *et al.*⁸⁰ reviewed three patients on whom six procedures were performed on 30 bones for cosmesis. All enchondromas showed thinned and bulging cortices. A flap of this expanded cortex was raised, the lesion curetted and some of the bone flaps were trimmed to reduce the volume of the bulging cortex. Some lesions were filled with bone substitute. The authors noted bony union in all patients with improvement in hand appearance without compromising finger range of motion. Seventy-four percent had at least a 30% reduction in bulging on radiographs. Thirty-seven percent had greater than 40% reduction.

Sassoon *et al.*⁸¹ reviewed 80 patients surgically treated with solitary and multiple enchondromas of the hand and found that the ring and small fingers were the most commonly affected and the thumb was the least frequently affected. The majority of lesions were monocentric with cortical expansion, and centralized within the bone. Patients in Sassoon's series with multiple enchondromas showed full healing after surgery with new bone formation in 61%, restoration of full motion in 86%, recurrence in 21%, and one case of malignant transformation. The malignant transformation occurred in a 55-year-old female with Maffucci syndrome who underwent amputation through the small finger metacarpophalangeal joint.

Clinical tips

Osteochondromas

- MHO shows multiple osteochondromas in the skeleton and can affect the hand and upper extremity.
- These osteochondromas can be associated with bone shortening, angulation, and blocking motion of joints.
- Treatment of multiple osteochondromas involves observation or surgical excision.
- Ollier disease is a condition of multiple enchondromas, while Maffucci syndrome has these and hemangiomas. Maffucci syndrome has a higher malignant transformation rate.

Future directions

Research involving the *PIK3CA*-related overgrowth spectrum and advances in genetic testing and gene therapy will greatly advance our understanding of the disease and help to possibly provide different treatment options. Current ongoing research in functional capabilities in children with symbrachydactyly will help advance the physician's understanding and allow better treatment selections to help improve that function. Registries that track these more rare conditions can allow cooperative studies of larger populations of patients with congenital hand anomalies and, with the addition of a new classification system, future research will be more streamlined from physician to physician.



Access the complete reference list online at <http://www.expertconsult.com>

4. Tonkin MA, Tolerton SK, Quick TJ, et al. Classification of congenital anomalies of the hand and upper limb: development and assessment of a new system. *J Hand Surg Am.* 2013;38:1845–1853. *The new OMT classification is changing how the congenital upper limb anomaly community discusses and performs research. This classification takes into account what research has developed on limb embryology and used the morphologic characteristics to allow for a very straightforward usable system.*
6. Keppler-Noreuil KM, Rios JJ, Parker VE, et al. *PIK3CA*-related overgrowth spectrum (PROS): diagnostic and testing eligibility criteria, differential diagnosis, and evaluation. *Am J Med Genet A.* 2015;167:287–295. *This article and discovery of the PIK3CA gene related to overgrowth syndromes advances testing and will possibly allow for genetic-based therapies for treatment. Recognition of genetic causes for syndromes and diseases helps to advance our understanding and guide research to develop testing and treatments.*
11. Cerrato F, Eberlin KR, Waters P, et al. Presentation and treatment of macrodactyly in children. *J Hand Surg Am.* 2013;38:2112–2123. *This is a comprehensive article that addresses presentation, disease characteristics, treatment, and outcome of macrodactyly in children. It also addresses lipomatous versus nerve-territory macrodactyly.*
35. Woodside JC, Light TR. Symbrachydactyly – diagnosis, function, treatment. *J Hand Surg Am.* 2016;41:135–143. *This is a comprehensive review of symbrachydactyly discussing diagnosis, the function of patients with the syndrome, and treatment options. It is a comprehensive review of current research and ideas of approach to the patient.*
39. Vilkki SK. Advances in microsurgical reconstruction of the congenitally adactylous hand. *Clin Orthop Relat Res.* 1995;45–58.
42. Kaplan JD, Jones NF. Outcome measures of microsurgical toe transfers for reconstruction of congenital and traumatic hand anomalies. *J Pediatr Orthop.* 2014;34:362–368.
43. Buck-Gramcko D. Symbrachydactyly: a clinical entity. *Tech Hand Up Extrem Surg.* 1999;3:242–258.
50. Jones NF, Hansen SL, Bates SJ. Toe-to-hand transfers for congenital anomalies of the hand. *Hand Clin.* 2007;23:129–136. *This is an excellent resource for indications, timing for surgery, and the surgical technique of toe-to-hand transfers in the pediatric population. It contains high-quality images and outcomes for patients postoperatively.*
60. Burgess RC, Cates H. Deformities of the forearm in patients who have multiple cartilaginous exostosis. *J Bone Joint Surg Am.* 1993;75:13–18.
64. Stanton RP, Hansen MO. Function of the upper extremities in hereditary multiple exostoses. *J Bone Joint Surg Am.* 1996;78:568–573.

References

- Swanson AB. A classification for congenital limb malformations. *J Hand Surg Am.* 1976;1:8–22.
- Oberg KC, Feenstra JM, Manske PR, Tonkin MA. Developmental biology and classification of congenital anomalies of the hand and upper extremity. *J Hand Surg Am.* 2010;35:2066–2076.
- Ezaki M, Baek GH, Horii E, et al. IFSSH Scientific Committee on Congenital Conditions. Classification of congenital hand and upper limb anomalies. *J Hand Surg Eur Vol.* 2014;39:676–678.
- Tonkin MA, Tolerton SK, Quick TJ, et al. Classification of congenital anomalies of the hand and upper limb: development and assessment of a new system. *J Hand Surg Am.* 2013;38:1845–1853. *The new OMT classification is changing how the congenital upper limb anomaly community discusses and performs research. This classification takes into account what research has developed on limb embryology and used the morphologic characteristics to allow for a very straightforward usable system.*
- Flatt AE. *The Care of Congenital Hand Anomalies.* 2nd ed. St. Louis, MO: Quality Medical Publishing; 1994.
- Keppler-Noreuil KM, Rios JJ, Parker VE, et al. PIK3CA-related overgrowth spectrum (PROS): diagnostic and testing eligibility criteria, differential diagnosis, and evaluation. *Am J Med Genet A.* 2015;167:287–295. *This article and discovery of the PIK3CA gene related to overgrowth syndromes advances testing and will possibly allow for genetic-based therapies for treatment. Recognition of genetic causes for syndromes and diseases helps to advance our understanding and guide research to develop testing and treatments.*
- Keppler-Noreuil KM, Sapp JC, Lindhurst MJ, et al. Clinical delineation and natural history of the PIK3CA-related overgrowth spectrum. *Am J Med Genet A.* 2014;164:1713–1733.
- Carty MJ, Taghinia A, Upton J. Overgrowth conditions: a diagnostic and therapeutic conundrum. *Hand Clin.* 2009;25:229–245.
- Ho CA, Herring JA, Ezaki M. Long-term follow-up of progressive macrodystrophia lipomatosa. A report of two cases. *J Bone Joint Surg Am.* 2007;89:1097–1102.
- Rios JJ, Paria N, Burns DK, et al. Somatic gain-of-function mutations in PIK3CA in patients with macrodactyly. *Hum Mol Genet.* 2013;22:444–451.
- Cerrato F, Eberlin KR, Waters P, et al. Presentation and treatment of macrodactyly in children. *J Hand Surg Am.* 2013;38:2112–2123. *This is a comprehensive article that addresses presentation, disease characteristics, treatment, and outcome of macrodactyly in children. It also addresses lipomatous versus nerve-territory macrodactyly.*
- Upton J, Mathes S, Hentz V, eds. Failure of Differentiation and Overgrowth. In: *Plastic Surgery*, 2nd ed. Philadelphia, PA: Saunders; 2005.
- Soler R, Rodríguez E, Bargiela A, et al. MR findings of macrodystrophia lipomatosa. *Clin Imaging.* 1997;21:135–137.
- Sone M, Ehara S, Tamakawa Y, et al. Macrodystrophia lipomatosa: CT and MR findings. *Radiat Med.* 2000;18:129–132.
- Gupta SK, Sharma OP, Sharma SV, et al. Macrodystrophia lipomatosa: radiographic observations. *Br J Radiol.* 1992;65:769–773.
- Silverman TA, Enzinger FM. Fibrolipomatous hamartoma of nerve. A clinicopathologic analysis of 26 cases. *Am J Surg Pathol.* 1985;9:7–14.
- Tsuge K, Ikuta Y. Macrodactyly and fibro-fatty proliferation of the median nerve. *Hiroshima J Med Sci.* 1973;22:83–101.
- Brodwater BK, Major NM, Goldner RD, Layfield LJ. Macrodystrophia lipomatosa with associated fibrolipomatous hamartoma of the median nerve. *Pediatr Surg Int.* 2000;16:216–218.
- Barsky AJ. Macrodactyly. *J Bone Joint Surg Am.* 1967;49:1255–1266.
- Tsuge K. Treatment of macrodactyly. *Plast Reconstr Surg.* 1967;39:590–599.
- Millesi H. *Camptodactyly.* St. Louis, MO: Mosby; 1974.
- Ogino T. *Macrodactyly.* London: Churchill Livingstone; 1998.
- Bertelli JA, Pigozzi L, Pereima M. Hemidigital resection with collateral ligament transplantation in the treatment of macrodactyly: a case report. *J Hand Surg Am.* 2001;26:623–627.
- Hardwicke J, Khan MA, Richards H, et al. Macrodactyly – options and outcomes. *J Hand Surg Eur Vol.* 2013;38:297–303.
- Koskimies E, Lindfors N, Gissler M, et al. Congenital upper limb deficiencies and associated malformations in Finland: a population-based study. *J Hand Surg Am.* 2011;36:1058–1065.
- Burgess RC. Brachydactyly type C. *J Hand Surg Am.* 2001;26:31–39.
- Temtamy SA, Aglan MS. Brachydactyly. *Orphanet J Rare Dis.* 2008;3:15.
- Bell J. *The Treasury of Human Inheritance: On Hereditary Digital Anomalies.* London: Cambridge University Press; 1951.
- Cates HE, Burgess RC. Incidence of brachydactyly and hand exostosis in hereditary multiple exostosis. *J Hand Surg Am.* 1991;16:127–132.
- Arsalan H. Metacarpal lengthening by distraction osteogenesis in childhood brachydactyly. *Acta Orthop Belg.* 2001;67:242–247.
- Nguyen ML, Jones NF. Undergrowth: brachydactyly. *Hand Clin.* 2009;25:247–255.
- Eklblom AG, Laurell T, Arner M. Epidemiology of congenital upper limb anomalies in Stockholm, Sweden, 1997 to 2007: application of the Oberg, Manske, and Tonkin classification. *J Hand Surg Am.* 2014;39:237–248.
- Swanson AB, Swanson GD, Tada K. A classification for congenital limb malformation. *J Hand Surg Am.* 1983;8:693–702.
- Blauth W, Gekeler J. [Morphology and classification of symbrachydactylia]. *Handchirurgie.* 1971;3:123–128.
- Woodside JC, Light TR. Symbrachydactyly – diagnosis, function, treatment. *J Hand Surg Am.* 2016;41:135–143. *This is a comprehensive review of symbrachydactyly discussing diagnosis, the function of patients with the syndrome, and treatment options. It is a comprehensive review of current research and ideas of approach to the patient.*
- Knight JB, Pritsch T, Ezaki M, et al. Unilateral congenital terminal finger absences: a condition that differs from symbrachydactyly. *J Hand Surg Am.* 2012;37:124–129.
- Catena N, Divizia MT, Calevo MG, et al. Hand and upper limb anomalies in Poland syndrome: a new proposal of classification. *J Pediatr Orthop.* 2012;32:727–731.
- Bavinck JN, Weaver DD. Subclavian artery supply disruption sequence: hypothesis of a vascular etiology for Poland, Klippel-Feil, and Möbius anomalies. *Am J Med Genet.* 1986;23:903–918.
- Vilkki SK. Advances in microsurgical reconstruction of the congenitally adactylous hand. *Clin Orthop Relat Res.* 1995;45–58.
- Case-Smith J. Clinical interpretation of “development of in-hand manipulation and relationship with activities”. *Am J Occup Ther.* 1995;49:772–774.
- Gordon A, Forssberg H. Development of neural mechanisms underlying grasping in children. In: Connolly K, Forssberg H, eds. *Neurophysiology and Neuropsychology of Motor Development.* London: MacKeith Press; 1997:214–231.
- Kaplan JD, Jones NF. Outcome measures of microsurgical toe transfers for reconstruction of congenital and traumatic hand anomalies. *J Pediatr Orthop.* 2014;34:362–368.
- Buck-Gramcko D. Symbrachydactyly: a clinical entity. *Tech Hand Up Extrem Surg.* 1999;3:242–258.
- Goldberg NH, Watson HK. Composite toe (phalanx and epiphysis) transfers in the reconstruction of the aphalangic hand. *J Hand Surg Am.* 1982;7:454–459.
- Garagnani L, Gibson M, Smith PJ, et al. Long-term donor site morbidity after free nonvascularized toe phalangeal transfer. *J Hand Surg Am.* 2012;37:764–774.
- Bourke G, Kay SP. Free phalangeal transfer: donor-site outcome. *Br J Plast Surg.* 2002;55:307–311.
- Kessler I, Baruch A, Hecht O. Experience with distraction lengthening of digital rays in congenital anomalies. *J Hand Surg Am.* 1977;2:394–401.
- Langer JS, Manske PR, Steffen JA, et al. Thumb in the plane of the hand: characterization and results of surgical treatment. *J Hand Surg Am.* 2009;34:1795–1801.

49. Li WJ, Zhao JH, Tian W, et al. Congenital symbrachydactyly: outcomes of surgical treatment in 120 webs. *Chin Med J*. 2013;126:2871–2875.
50. Jones NF, Hansen SL, Bates SJ. Toe-to-hand transfers for congenital anomalies of the hand. *Hand Clin*. 2007;23:129–136. *This is an excellent resource for indications, timing for surgery, and the surgical technique of toe-to-hand transfers in the pediatric population. It contains high-quality images and outcomes for patients postoperatively.*
51. Cobbett JR. Free digital transfer. Report of a case of transfer of a great toe to replace an amputated thumb. *J Bone Joint Surg Br*. 1969;51:677–679.
52. Buncke HJ, Buncke CM, Schulz WP. Immediate Nicoladoni procedure in the rhesus monkey, or hallux-to-hand transplantation, utilising microminiature vascular anastomoses. *Br J Plast Surg*. 1966;19:332–337.
53. Gilbert A. Toe transfers for congenital hand defects. *J Hand Surg Am*. 1982;7:118–124.
54. Eaton CJ, Lister GD. Toe transfer for congenital hand defects. *Microsurgery*. 1991;12:186–195.
55. Richardson PW, Johnstone BR, Coombs CJ. Toe-to-hand transfer in symbrachydactyly. *Hand Surg*. 2004;9:11–18.
56. Kay SP, Wiberg M, Bellew M, et al. Toe to hand transfer in children. Part 2: Functional and psychological aspects. *J Hand Surg [Br]*. 1996;21:735–745.
57. Van Holder C, Giele H, Gilbert A. Double second toe transfer in congenital hand anomalies. *J Hand Surg [Br]*. 1999;24:471–475.
58. Foucher G, Medina J, Navarro R, et al. Toe transfer in congenital hand malformations. *J Reconstr Microsurg*. 2001;17:1–7.
59. Gottschalk HP, Kanauchi Y, Bednar MS, et al. Effect of osteochondroma location on forearm deformity in patients with multiple hereditary osteochondromatosis. *J Hand Surg Am*. 2012;37:2286–2293.
60. Burgess RC, Cates H. Deformities of the forearm in patients who have multiple cartilaginous exostosis. *J Bone Joint Surg Am*. 1993;75:13–18.
61. Solomon L. Bone growth in diaphysial aclasis. *J Bone Joint Surg Br*. 1961;43:700–716.
62. Woodside J, Ganey T, Gaston RG. Multiple osteochondroma of the hand: initial and long-term follow-up study. *Hand*. 2015;10:616–620.
63. Stieber JR, Dormans JP. Manifestations of hereditary multiple exostoses. *J Am Acad Orthop Surg*. 2005;13:110–120.
64. Stanton RP, Hansen MO. Function of the upper extremities in hereditary multiple exostoses. *J Bone Joint Surg Am*. 1996;78:568–573.
65. Black B, Dooley J, Pyper A, et al. Multiple hereditary exostoses. An epidemiologic study of an isolated community in Manitoba. *Clin Orthop Relat Res*. 1993;212–217.
66. Schmale GA, Conrad EU, Raskind WH. The natural history of hereditary multiple exostoses. *J Bone Joint Surg Am*. 1994;76:986–992.
67. Solomon L. Hereditary Multiple Exostosis. *J Bone Joint Surg Br*. 1963;45:292–304.
68. Wood VE, Molitor C, Mudge MK. Hand involvement in multiple hereditary exostosis. *Hand Clin*. 1990;6:685–692.
69. Peterson HA. Deformities and problems of the forearm in children with multiple hereditary osteochondromata. *J Pediatr Orthop*. 1994;14:92–100.
70. Fogel GR, McElfresh EC, Peterson HA, et al. Management of deformities of the forearm in multiple hereditary osteochondromas. *J Bone Joint Surg Am*. 1984;66:670–680.
71. Gindhart PS. Growth standards for the tibia and radius in children aged one month through eighteen years. *Am J Phys Anthropol*. 1973;39:41–48.
72. Wood VE, Sausser D, Mudge D. The treatment of hereditary multiple exostosis of the upper extremity. *J Hand Surg Am*. 1985;10:505–513.
73. Masada K, Tsuyuguchi Y, Kawai H, et al. Operations for forearm deformity caused by multiple osteochondromas. *J Bone Joint Surg Br*. 1989;71:24–29.
74. Pritchett JW. Lengthening the ulna in patients with hereditary multiple exostoses. *J Bone Joint Surg Br*. 1986;68:561–565.
75. Silve C, Jüppner H. Ollier disease. *Orphanet J Rare Dis*. 2006;1:37.
76. Casal D, Mavioso C, Mendes MM, et al. Hand involvement in Ollier disease and Maffucci syndrome: a case series. *Acta Reumatol Port*. 2010;35:375–378.
77. Tomlinson PJ, Turner J, Monsell FP. The distribution of enchondromata in the hands of patients with Ollier's disease. *J Hand Surg Eur Vol*. 2010;35:154–155.
78. Schwartz HS, Zimmerman NB, Simon MA, et al. The malignant potential of enchondromatosis. *J Bone Joint Surg Am*. 1987;69:269–274.
79. Sun TC, Swee RG, Shives TC, et al. Chondrosarcoma in Maffucci's syndrome. *J Bone Joint Surg Am*. 1985;67:1214–1219.
80. Kim E, Miyake J, Kataoka T, et al. Corticoplasty for improved appearance of hands with Ollier disease. *J Hand Surg Am*. 2012;37:2294–2299.
81. Sassoon AA, Fitz-Gibbon PD, Harmsen WS, et al. Enchondromas of the hand: factors affecting recurrence, healing, motion, and malignant transformation. *J Hand Surg Am*. 2012;37:1229–1234.

30

Growth considerations in pediatric upper extremity trauma and reconstruction

Marco Innocenti and Carla Baldrighi

 Access video and video lecture content for this chapter online at expertconsult.com

SYNOPSIS

- Skeletal growth is possible because of the presence of an active physis.
- The physis is a temporary anatomical structure physiologically regulated by several factors. It can be hindered by congenital conditions (chondrodysplasias), direct damage, or interruption of its blood supply.
- Regardless of its etiology, when the physis and/or the epiphysis are damaged in a skeletally immature individual, three main issues must be addressed: restoration of longitudinal growth, restoration of joint congruency and function, and replacement of the osseous defect.
- Therapeutic options include completion of epiphyseal arrest, resection of physeal bar, and epiphyseal distraction.
- Where there is involvement of the whole epiphysis, autologous epiphyseal transfer may achieve the dual goals of restoring joint function and growth potential. The longer the period of time between the epiphyseal insult and the expected end of growth, the stronger the indication for surgical treatment.

Introduction

- The growth plate is a temporary anatomical entity, which allows axial growth in long bones. Once skeletal maturity is approached, the function of the growth plate gradually decreases and eventually stops.
- Trauma, infection, irradiation, thermal injury, tumors, and congenital disorders may affect the growth plate and interfere with the growth process.
- Any damage to the growth plate in a skeletally immature individual leads to growth disturbance with deformity and/or length discrepancy.
- Goals of the surgical treatment should be restoration of the physiological growth, prevention of angular deformities, and correction of established deviation of bones and joints.

Basic science/disease process

Anatomy and physiology of the epiphyseal growth plate

The physis (also known as growth plate, epiphyseal plate, epiphyseal growth plate, epiphyseal cartilage) is a highly specialized and organized cartilaginous structure derived from the mesoderm. It develops in the bone bud, secondary to the primary ossification centers (metaphysis) and is responsible for longitudinal and circumferential bone growth.¹ The physis must be distinguished from the epiphysis, or secondary ossification center (Fig. 30.1).

The physis consists of proliferating chondrocytes surrounded by synthesized extracellular matrix. The extracellular matrix is composed of water, collagen fibrils (mainly types II, IX, X, and XI) and proteoglycans (aggrecan, decorin, annexin II, V, and VI) arranged to form a sort of sponge with very small pores.² This arrangement confers peculiar mechanical properties that permit the physis to be “hard” when an axial load is applied rapidly (a jumping child) or “soft” when deformed slowly (when chondrocytes secrete new extracellular matrix).³

The physis is traditionally divided into horizontal zones of chondrocytes at different stages of maturation (see Fig. 30.1). The resting zone (reserve zone or germinal matrix), immediately adjacent to the epiphysis, contains small, uniform, irregularly scattered chondrocytes, also referred to as stem cells, with low rates of proliferation but rich in storage materials (lipids and cytoplasmic vacuoles) for later growth.^{4,5} The resting zone is responsible for protein synthesis and for maintaining a germinal structure. Injury to this layer results in cessation of growth.

When chondrocytes enter into the proliferative zone they undergo rapid duplication, increase the synthesis of collagen, in particular types II and XI,⁴ and become flat and well organized into longitudinal columns. Mitotic activity is present




Fig. 30.1 Cross-sectional anatomy of the physis.

only at the base of these columns. This layer is responsible for longitudinal growth of the bone via active cell division. These first two zones have an abundant extracellular matrix that confers a great deal of mechanical strength, in particular in response to shear forces.

Further morphological changes – maturation, degeneration, and provisional calcification – take place in the transformation (or hypertrophic) zone, divided into upper and lower hypertrophic zones.

The presence of provisional calcification⁴⁻⁶ confers shear resistance to the lower hypertrophic zone. In contrast, the upper hypertrophic zone containing scant extracellular matrix is the weakest portion of the physis and it is here that most injury or alteration to the physis occurs.⁷⁻⁹

In continuity with the metaphysis is the zone of endochondral calcification where the mineralization process of the matrix becomes more intensive.

The periphysis is a fibrochondroosseous structure that surrounds the physis of tubular bones and plays an important role in skeletal development¹⁰ (see Fig. 30.1): (1) it allows gradual circumferential growth of the physis; (2) it continues to maintain its transverse diameter¹¹; and (3) it is critical to the overall stability of the growth plate and to support for the physis bone–cartilage junction.¹¹⁻¹³

The part of the periphysis adjacent to the epiphysis is a wedge-shaped group of germinal cells known as the zone of Ranvier, while the part adjacent to the metaphysis is known as the ring of LaCroix. Histologically, the Ranvier and LaCroix zones are a single structure (see Fig. 30.1).

Chondrocyte proliferation and differentiation in the physis, and therefore longitudinal skeletal growth, are regulated at both a systemic and local level.¹⁴ A number of endocrine, paracrine, and autocrine factors and their respective receptors are involved in this process. Amongst these, the parathyroid hormone-related protein (PTHrP) and the Indian hedgehog (Ihh) play a prominent role in skeletal maturation.^{1,15-18} There is also mechanical control of growth, which is important in pediatric orthopedic surgery because it is the basis of the widely used epiphysiodesis and epiphyseal distraction procedures.³

Vascular anatomy of the growth plate

The epiphyseal and physeal cartilage vascular anatomy in newborn and early postnatal life is integral to long-bone development and differs from later postnatal periods. In late fetal and early postnatal life, epiphyseal cartilage canals (or transphyseal vessels) are seen passing through the physeal cartilage and communicating with the metaphyseal marrow. Such vessels play an active role in forming the secondary ossification centers¹⁸⁻²⁰ but their primary earlier function is to provide nutrition by diffusion to epiphyseal chondrocytes.

The transphyseal vessels are constantly obliterated several months after birth. Once the obliteration has occurred, the physeal cartilage becomes an avascular structure supplied by the epiphyseal vessels by diffusion, and by the metaphyseal vessels invading the lowermost regions of the hypertrophic zone.^{21,22}

The main vascular supply to the germinal zone is from the epiphyseal vessels. Two types of epiphyseal vascularization are described.²³ Type A epiphyses are almost entirely covered by articular cartilage, and the epiphyseal vessels enter the epiphysis after traversing the perichondrium. With this anatomical configuration, the blood supply to the epiphysis, and consequently to the germinal zone, is susceptible to damage if the epiphysis is separated from metaphysis. Type B epiphyses are only partially covered by articular cartilage. Their blood supply enters from the epiphyseal side and is protected from vascular injury during separation. The proximal femur and proximal radius are the only two examples of type A epiphyses.

Growth plate closure and skeletal age assessment during puberty

It is generally assumed that long bone physes close at 14 years of skeletal age in females and at 16 years in males while the axial skeleton completes its development later.²⁴⁻²⁶ In 50% of normal children and adolescents, skeletal age does not differ from chronological age.²⁷ Prediction of limb length discrepancy and final standing height, as well as decisions regarding when to perform an epiphysiodesis, are first subjected to determination of skeletal age.

A complication unique to physeal injuries is growth disturbance. Once damage to the physis has occurred, the predicted amount of growth remaining from that specific physis must be determined to plan the treatment. This can be accomplished by determining the skeletal age of the patient and then using information on physeal growth rates and patterns assembled by Green and Anderson.²⁸⁻³²

Treatment decisions are often made during puberty. Puberty is the period of time in the growing individual characterized by a significant increase in growth rate.^{33,34} In girls, puberty starts at 11 years and ends at 13 years of skeletal age; in boys, it starts and ends 2 years later (13 years and 15 years of skeletal age).²⁷ Peak height growth and Tanner stage 2³⁵ signal the beginning of puberty. The 2 years of pubertal growth spurt are known as acceleration phase followed by a deceleration phase that continues until skeletal maturity.

The radiographic markers currently used to assess skeletal age are all based on the appearance of ossification centers in specific skeletal segments at specific times. Several age assessment methods are based on the use of anteroposterior




Fig. 30.2 Olecranon maturation according to Dimeglio *et al.*,³⁵ with significant changes occurring every 6 months. **(A)** two ossification centers (girls 11 years; boys 13 years); **(B)** half-moon shape (girls 11.5 years; boys 13.5 years); **(C)** rectangular shape (girls 12 years; boys 14 years); **(D)** beginning of fusion (girls 12.5 years; boys 14.5 years); and **(E)** complete fusion (girls 13 years; boys 15 years).

radiographs of the left hand and wrist.^{36–39} Other methods use left elbow radiographs.^{27,40} The axial skeleton can also be used to determine the skeletal age: Risser sign⁴¹ is based on the appearance of the left iliac apophysis of the pelvis. However, other radiographs can be used to assess skeletal age.²⁷

Different assessment methods become helpful at different ages. The Greulich and Pyle atlas³⁶ is probably the most common and widely used method to assess skeletal age. This technique, however, has some limitations, especially during puberty because it does not make it possible to assess skeletal age at 6-month intervals during the 2 years of peak growth rate.²⁷ On the other hand, during the pubertal acceleration phase, the elbow, at the level of the distal epiphysis ossification centers and the olecranon apophysis, undergoes peculiar and identifiable morphological changes every 6 months^{27,40}

(Figs. 30.2 & 30.3). Elbow ossification centers always appear in a determined sequence (the mnemonic is CRITOE: capitulum, radial head, internal (medial) epicondyle, trochlea, olecranon, external (lateral) epicondyle). The ages of appearance, as a general guide, are 1–3–5–7–9–11 years.

During the acceleration phase, the skeletal age is best assessed with X-rays of the left hand and left elbow.^{42–45} In the deceleration phase, the growth rate decreases significantly. The remaining growth in both boys and girls is around 6 cm, of which 4.5 cm belong to the trunk and skull. During this phase, the most useful tools for skeletal age assessment are again the left hand and the Risser stage.

Regardless of the assessment method used, skeletal age alone is not enough and it should be related to other clinical and radiological findings such as standing and sitting height, Tanner stage, and annual growth rate.




Fig. 30.3 Pubertal diagram. Acceleration phase, between skeletal age of 11 and 13 years in girls and 13 and 15 years in boys; Risser sign is 0. End of the acceleration phase, complete elbow and distal phalanx of the thumb closure; Risser sign is still 0.

Diagnosis/patient presentation

Conditions affecting the growth plate

A complication unique to physeal injuries is growth disturbance. Trauma is the most common cause of physeal injury and growth disturbance, but physeal growth arrest may as well occur after infection, tumor, irradiation, thermal injury, laser beam exposure, and sequelae of Blount's disease (growth disorder with bowing of the tibia).⁴⁶⁻⁴⁹

Trauma

Incidence and distribution in the upper extremity

Physeal injuries represent 15–30% of all fractures in children⁵⁰⁻⁵⁴ and frequently involve the upper extremities.^{53,55} The incidence varies with age, with a peak in adolescence.^{53,55,56} The upper hypertrophic zone, just above the area of provisional calcification, is the weakest layer of the physis and where most injuries to the physis occur.⁷⁻⁹ This observation implies that, after most injuries, the germinal layer of the physis remains intact and attached to the epiphysis. Consequent normal growth should resume unless insult to the blood supply of the germinal layer or development of a “bony bridge” across the injured physis occurs.⁵⁷

Classification of physeal fractures

Several classification systems for physeal injuries have been described.⁵⁸⁻⁶⁴ The Salter and Harris classification (Fig. 30.4)⁶⁵ is by far the most widely used system. This classification helps to distinguish different types of fractures and provides prognostic information as well. In Salter–Harris type I (see Fig. 30.4), the injury is a separation of the epiphysis from the metaphysis. It occurs entirely through the physis and therefore the surrounding bone is not involved. It is rare and tends to be seen in infants or pathologic fractures, such as those secondary to rickets or scurvy. Because the germinal layer remains with the epiphysis, growth is not hindered unless blood supply is interrupted (traumatic separation of the proximal femoral epiphysis). Often, X-rays of a child with a type I Salter–Harris fracture will appear normal. Healing of type I fractures tends to be rapid, and complications are rare.

In Salter–Harris type II injury (see Fig. 30.4), the fracture extends along the hypertrophic zone of the physis but then it continues and exits through the metaphysis. This is the most common type of growth plate fracture, and tends to occur in

older children. The epiphyseal fragment contains the entire germinal layer as well as a metaphyseal fragment, known as Thurston Holland's sign. The periosteum on the side of the metaphyseal fragment is usually intact and provides stability after reduction. Growth disturbance is uncommon because the germinal layer remains intact.

In Salter–Harris type III injury (see Fig. 30.4), the fracture starts through the hypertrophic zone and exits through the epiphysis. These injuries also tend to affect older children. By definition, type III fractures cross the germinal layer and are usually intra-articular. Consequently, they raise concerns about growth and, when displaced, they require anatomic, and often open, reduction.

In Salter–Harris type IV injury (see Fig. 30.4), the fracture starts from the metaphysis and then extends through the physis and into the epiphysis. By definition these fractures disturb the germinal layer and are usually intra-articular. Consequently, these injuries may impair normal growth and affect articular congruency. In type IV injuries, an anatomic reduction is mandatory in order to prevent osseous bridging across the physis and to restore the articular surface.

A Salter–Harris type V injury (see Fig. 30.4) occurs when the physis is crushed from a pure compression force. It is so rare that some authors question whether such an injury exists.⁶⁶ For those authors who have reported on this injury,^{65,67} it carries the most concerning prognosis as the growth disturbance is almost a rule. It often requires later surgical treatment to restore limb length and alignment.

Despite being widely used, the Salter–Harris classification excludes a few physeal injuries: the Rang's type VI epiphyseal injury,^{62,63} which represents an injury to the perichondral ring, and two additional injuries described in the Peterson classification system (Fig. 30.5),⁵⁶ which is very similar to the Salter–Harris scheme. The Peterson type I fracture is a transverse fracture of the metaphysis that extends longitudinally into the physis. Clinically, this type of fracture is commonly seen in the distal radius. The Peterson VI fracture is an open injury associated with loss of the physis.

Treatment of physeal fractures

Growth plate injuries that are less severe, and occur closer to the time of closure of the growth plate, carry the best prognosis. More severe injuries occurring in younger patients require observation and possibly treatment to prevent problems. The principles of treatment of physeal fractures are the same as those involved in the treatment of all fractures, with a few important considerations.




Fig. 30.4 Salter–Harris classification of physeal fractures. (Redrawn after Salter RB, Harris R. Injuries involving the epiphyseal plate. *J Bone Joint Surg Am.* 1963;45:587–621.)




Fig. 30.5 Peterson classification of physeal fractures. Type VI injuries are open and associated with loss of the physis. (Redrawn after Peterson HA. *Physeal fractures: part 3. Classification.* J Pediatr. Orthop. 1994;14:439.)

The goal in the treatment of physeal injuries is to obtain and maintain an acceptable reduction while avoiding any further damage to the germinal layer of the physis during reduction. Thus the most important goal, and the most subjective one, is to establish the limits of acceptable reduction.

The age of the patient, the location and displacement of the fracture, and the time elapsed since the injury must be all taken into consideration when assessing a non-anatomic reduction. Although animal studies have not shown that delay in reduction produces a growth disturbance,⁶⁸ the recommendation is to accept any displacement in type I and II injuries after 7–10 days^{9,69} and rather plan an osteotomy later. As a general rule, the remodeling potential is inversely proportionate to the age of the patient and is also related to the location and type of injury. Consequently, a greater deformity can be accepted in younger children.

Because type III and IV injuries are by definition intra-articular, the focus must be on achieving an anatomic reduction regardless of the age of the patient and the time that has elapsed since the injury. Once the physeal fracture has been reduced, the reduction can be maintained with cast, pins, internal fixation, or combinations of these three.

Tumor

Bone sarcoma involving the epiphysis

Most of the common primary malignant bone tumors occur in patients aged under 30 years.⁷⁰ Typically, osteosarcoma and Ewing sarcoma are found in adolescents and young adults, but they may also be diagnosed during infancy. The current approach to systemic therapy⁷⁰ includes preoperative (neoadjuvant) chemotherapy and postoperative (adjuvant) chemotherapy for both osteosarcoma and Ewing sarcoma. Radiotherapy is indicated only in Ewing sarcoma and it may be the only local treatment in cases of tumor in unfavorable locations, such as spine and pelvis, and in all cases where radical surgery is unlikely to be successful. Postoperative radiotherapy is indicated in all cases of intralesional resections with the aim of reducing the risk of local recurrence.

With advances in bone reconstruction, the role of surgery has become predominant in the treatment of primary bone tumors, and the percentage of limb salvage versus amputation has significantly increased. In the upper limb, bone sarcomas are more frequently located in the distal radius and proximal humerus. Although the tumor is usually initially

located at the metaphyseal level, the growth plate and the physis are always to be considered as a possible target of sarcoma invasion. From a functional standpoint, it is critical to know whether the surgical resection may spare the epiphysis or not.

In the past, the growth plate was thought to be a biologic barrier to bone tumor invasion^{71–73}; unfortunately this theory has not proven to be valid^{74–76} (Fig. 30.6). The current view is that invasion of the physis must always be suspected when



Fig. 30.6 Osteosarcoma involving the proximal epiphysis and the adjoining diaphysis in a 6-year-old child.




Fig. 30.7 Classification of physeal bars. Type A, peripheral; type B, central, surrounded by normal physis; type C, central, traversing the physis.

the tumor is located in the proximity of the growth plate and all patients should be investigated with magnetic resonance imaging (MRI). In the event of epiphyseal involvement, the oncological resection must include the epiphysis and the only possible reconstructive option for such a defect in the pediatric age group is autologous epiphyseal transplant.

Congenital chondrodysplasia

Chondrocyte proliferation and differentiation in the physis, and therefore skeletal growth, are regulated by various endocrine, paracrine, and autocrine factors. Any disturbance of the epiphyseal growth plate physiology and development results in various skeletal abnormalities known as dysplasia or chondrodysplasia. These cases may also require reconstruction to maintain growth.

Patient selection

When the physis is damaged and deformity results or is foreseen, several treatment options are available. The best treatment for a growth plate injury depends on the individual situation. Although physeal injuries are common, problems arising are rare, occurring in only 1–10% of all physeal fractures.^{9,53,56} Comminuted fractures, high-energy injuries, and physeal injuries that cross the germinal layer are more prone to result in physeal arrest with subsequent growth disturbance. Physeal injuries are most common in adolescents close to skeletal maturity. In these individuals, the remaining growth is limited.^{9,53,56} Consequently, even when it occurs, physeal arrest will produce minimal or no length discrepancy or angular deviation and will seldom require treatment.

Growth disturbance resulting from a physeal fracture is usually evident 2–6 months after the injury, but it may take up to a year to manifest.⁹ This information is important both to warn the parents about possible complications and to anticipate close long-term follow-up. In fact, the management of a post-traumatic growth disturbance is easier when directed exclusively towards treating the arrest rather than tackling both the arrest and the acquired deformity.

Growth disturbance is usually a consequence of the development of a bony bridge, or bar, across the physis.⁵⁷ However, when the injury only reduces rather than stops the growth rate of a portion of the physis, it may still produce asymmetric growth and angular deformity with no development of bony bridge.⁷⁷ If the bony bar involves a large portion of the physis, it may stop the physeal growth completely. However, in most cases, the bony bar is confined to a rather small portion of the physis and the growth stops only at that point. The remaining healthy physis continues to grow, creating a tethering effect, which may produce either a shortening or a progressive significant angular deformity, or both.

The extent and location of the bar, the skeletal age of the patient, and the amount of growth remaining from the physis must all be determined to plan the treatment of a physeal bar appropriately. Plain radiography, tomography, computed tomography (CT), or MRI^{46,78–81} may all be used to assess the anatomy of a physeal bar. MRI is by far the preferred method currently used to investigate physeal anatomy.^{82–85} In particular, fat-suppressed, 3D, gradient-recalled echo sequences can provide an accurate 3D reconstruction of the physis and estimate the percentage of physeal arrest.⁸⁵ The classification of partial physeal arrests is based on their location within the physis (Fig. 30.7): peripheral (type A) or central (type B or C). In type B, the bar develops in the center of the physis and is surrounded by a perimeter of healthy physis. This may create a tethering effect that “tents” the epiphysis, leading to joint deformity. In type C (central) the bar traverses the entire physis (front to back or side to side) while the physis on both sides of the bar is normal.

Treatment/surgical technique

Treatment of physeal arrest

Different treatment options are available for the management of physeal arrests. These options include observation, completion of a partial physeal arrest, epiphysiodesis, physeal bar resection, or physeal distraction.

Observation

Observation may be the best option when the physeal bar involves the entire physis with complete growth arrest if existing limb length inequality and/or angular deformity are acceptable, or if the individual is close to skeletal maturity with little longitudinal growth remaining.

Completion of a partial physeal arrest and epiphysiodesis

Completion of a partial physeal arrest may be indicated if there is an acceptable existing angular deformity that may become clinically unacceptable if left untreated. To avoid significant limb shortening of the upper extremity, the surgeon must evaluate the predicted remaining growth and foresee a lengthening procedure if necessary. In the upper extremity limb, length discrepancy is a relative issue but the asynchronous rate of longitudinal growth between two bones in an anatomic region where the two bones are paired in close longitudinal relationship, as in the forearm, or asynchronous growth in an anatomic region where the harmonic activity of

several physes contributes to the final size and shape of the bone, such as the distal humerus, might lead to a great risk of anatomic distortion. If the likelihood of length inequality is high, epiphysiodesis of a non-injured physis should be performed at the time of completion of the physal arrest.

Epiphysiodesis is an established method of limb length equalization or angular deformity correction in children and adolescents with projected limb length discrepancies at maturity as great as 5 or 6 cm. It consists of temporarily stopping or permanently destroying the activity of the whole or just a part (hemiepiphysiodesis) of the growth plate. First introduced by Phemister in 1933,⁸⁶ epiphysiodesis has evolved into various reversible or irreversible, open or percutaneous techniques, with and without instrumentation. The ideal tool should be minimally invasive, have minimal morbidity, and be reliably reversible. Pitfalls include errors in the prediction of growth and planning of the surgery. In particular, with non-reversible techniques, timing must be precise. Overcompensation for limb length discrepancy or creation of an opposite angular deformity can be very distressing for the patient, family, and surgeon. Although many different techniques have proven their efficacy, percutaneous epiphysiodesis using transphysal screws combines the minimal invasiveness of a percutaneous technique with reversibility.⁸⁷

Physal distraction

Physal distraction is an alternative treatment for partial physal arrest. Physal distraction uses the growth plate as a zone of least resistance. It involves the damaged physis and therefore acts at the site of the deformity. It requires a force to be applied longitudinally across the physis, permitting both lengthening and angular correction on multiple planes, with external control of the correction until consolidation. Prior resection of the bony bar is not necessary.

A distinction must be made between distractional epiphysiodesis and chondrodiastasis,^{88,89} chondrodiastasis,⁹⁰ and hemichondrodiastasis.⁹¹

The chondrodiastasis technique employs large forces or rapid rate of distraction (>1 mm/day) or both.⁹² This provokes a distraction and opening of the physis that provides a rapid *in situ* correction from the bony bar without prior bar resection, but almost invariably it produces a premature physal fusion.^{93,94} This notion limits the indications to patients nearing skeletal maturity and preventive lengthening according to predicted limb length discrepancy.^{94,95} In the literature, physal

distraction techniques are mostly reported for the treatment of lower limb deformities and little is known about their application in the upper limb.

Bar resection

If a portion of the physis has prematurely closed, but the remainder of the physis is healthy and there is substantial growth remaining, resection of the physal bar and insertion of interposition materials are indicated. This technique in fact preserves longitudinal bone growth ability.^{96,97} The procedure was first introduced by Langenskiöld and has been documented in both human and animal models.^{47,79,96,98–101}

The surgical technique of bar resection consists in removing the bone bridge along with the neighboring portions of metaphysis and epiphysis and filling the cavity with an inert material that will prevent recurrence of physal bar formation (Fig. 30.8).

Type A peripheral bars can be removed under direct vision, taking care to resect a wide cuff of periosteum. Type B and C central bars need to be approached through a window in the metaphysis or through an osteotomy (see Fig. 30.8A–C). Their resection may be facilitated by the use of fluoroscopy, fiber optic lighting, and dental mirrors, as well as magnifying loupes (see Fig. 30.8D).

Physal bar resection is recommended when all the following conditions are present: the remaining physis must be undamaged and must be large enough to permit growth to continue; and there should be a significant amount of growth remaining in that physis before physiologic physal closure. Bars involving more than 50% of the physal surface are unlikely to respond to surgical treatment.^{48,62,79,96–98,100} Despite the acceptance that younger patients, with higher growth potential, will benefit from physal bar resection, there is still no agreement in quantifying the amount of this growth potential.^{79,98,101}

According to Bright,¹⁰² indications for a bone bridge resection are as follows: there must be more than 50% of remaining healthy physis; the expected physal growth must last for 2 years or more; there must be good soft-tissue coverage of the lesion; and, in the case of growth arrest due to infection, the infection must have been absent for more than 1 year.

Once the bar is completely resected, various interpositional materials can be used to fill the void and prevent transphysal bone bridge formation.^{62,79,98} Of the interposition materials described, fat is the most commonly used.^{96,103} It has the advantage of being autologous and immediately available.




Fig. 30.8 (A) Central bar. (B) Bar resection through metaphyseal approach. (C) Assessing the resection.

Failure to prevent re-formation of the physeal bridge^{104,105} may be due to the fact that fat may not provide adequate hemostasis of the cavity and may migrate.^{97,106}

Silicone (Silastic) has been experimentally used in both human and animal studies with good results,^{102,107} but Silastic has been withdrawn from the market.⁹⁹ Methylmethacrylate, commercially known as Cranioplastic, is a material used to fill partial defects of the skull, is radiolucent, and is thermally non-conductive. The advantage as interposition material⁹⁷ is that its solid structure may help to support an epiphysis if a large metaphyseal defect has been created.¹⁰⁶ It may, however, damage the healthy physis because of heat produced by the exothermic reaction during the solidifying phase.¹⁰⁸ It may also be problematic to remove if further reconstructive procedures are required. Rarely, it can migrate from the physis into the diaphysis, and cause a pathological fracture.¹⁰⁹

Expanded polytetrafluoroethylene (EPTFE) membrane (Gore-Tex dura substitute; WL Gore, Flagstaff, AZ, USA) is generally used as an artificial dura substitute. The advantages of EPTFE membrane are that it is inert, non-reactive, unaffected by long-term exposure within the body,¹¹⁰ easy to handle, and provides good hemostasis. The disadvantage is that, being a soft material, it does not provide sufficient mechanical support and it is therefore only recommended when the resected area is at most 30% of the cross-section of the physis.¹¹¹

Bone wax is readily available and commonly used in medical applications to control bleeding. It has been successfully used as interposition material with the advantages of being inexpensive and permitting good hemostasis. It is not associated with excessive complications.¹¹² The disadvantage is that it does not offer a good mechanical support to the physis after bar resection.

Regardless of which interposition material is selected, the purpose is to fill the cavity created in the physis with the material so that bar formation is prevented. After bar resection, radiographic markers should be placed on each side of the physis to assess growth resumption.

Results after bar resection are variable. Even with appropriate patient selection and standardized operative technique, failure may result. Graft dislocation out of the cavity is one of the causes of failure.¹¹³ It is therefore recommended that the interposition material be anchored so that it will not dislodge, allowing bleeding into the cavity.⁹⁷ It is important that, even when growth resumes, premature closure of the physis is to be expected.^{56,79,98,106,113}

Physeal bar resection with interposition of certain materials plays a role in the treatment of partial physeal arrest; however, its results are relatively modest.

Corrective osteotomies, lengthening or shortening

Epiphysiodesis and resection of the bone bridge with the insertion of interposition materials^{96,97} are the two main methods to treat partial physeal arrest that also prevent further progression of angular deformity. In addition, for mild deformities of less than 20°, we can expect spontaneous remodeling after bar resection,^{96,97,114} although this has not been universally reported.⁷⁷ When an angular deformity is already evident, corrective osteotomy is indicated because remodeling sufficient to correct the deformity cannot be expected. Corrective osteotomy should be considered for

any angular deformity that is judged to be “clinically unacceptable”.^{79,98,97,106}

It is well known that the physeal growth rate responds to the force applied on the physis itself: growth is stimulated by both mild tension and mild compression.¹¹⁵ However, according to the Hueter–Volkmann principle,¹¹⁶ when compression on the growth plate exceeds a certain level, growth is indeed suppressed.¹¹⁵ If the compression is applied only on one side of the physis, worsening of the deformity may ensue. Improved alignment may therefore facilitate more normal growth.

Bone lengthening involves the principle of distraction-induced osteogenesis and the use of an external fixator. Because of the non-weight-bearing status of the upper extremity, limb length discrepancy of the upper limbs is better tolerated and of less functional and cosmetic significance than their counterparts in the lower extremity. For these reasons, along with the incumbent risks associated with the surgery, indications for bone-lengthening procedures in the upper extremities are confined to selected cases.^{104,117–128}

Reported complications of upper limb lengthening include pin tract infections, complications related to callus stability and formation (callus deformities after fixator removal, re-fractures, and malunions), diminished range of motion, elbow flexion contractures, pin-related nerve injuries, temporary radial nerve paresis as a complication of humeral lengthening, and sympathetic dystrophy.^{129–133} Considerable morbidity results from nerve injury secondary to the transfixing wires.^{132,133} In addition, in distraction lengthening of the upper limb, the bone formation takes longer compared to the lower limb because of the lack of weight-bearing. Therefore the external fixator must be kept on for several months. The length of treatment further decreases patient compliance and can be a major issue in young children and adolescents.

Epiphyseal transfer of the proximal fibular epiphysis

Access the Historical Perspective section online at
<http://www.expertconsult.com>

Indications

The main indications for epiphyseal reconstruction are loss of an epiphysis following trauma, tumor resection, or infection in children. Vascularized epiphyseal transfer is a procedure that can simultaneously achieve the double goal of reconstructing a lost joint and maintaining growth potential. Because of its biological and morphological characteristics, the proximal fibula is by far the best donor site for reconstruction of large bone defects of the upper extremity. In fact, unlike other bone segments suggested for vascularized epiphyseal reconstruction,^{158,159} the proximal end of the fibula contains a true epiphysis with a growth plate that, if properly revascularized, maintains its growth potential at the recipient site. In addition, the fibula is a tubular bone with a long expendable diaphysis that is perfectly suited for upper limb reconstruction, allowing safe and stable bone fixation.

The two most common locations of bone sarcomas of the upper extremity in the pediatric age group are the distal

Historical perspective

The first reports of free non-vascularized epiphyseal transplant date back to the end of the 19th century.^{134–136} All attempts in the pre-microsurgical era had discouraging results in terms of graft survival and growth. Early revascularization of the growth plate was identified as the crucial condition in determining success.¹³⁷ In the past 30 years, advancements in microvascular surgery led to experimental research with several studies proving the feasibility of vascularized epiphyseal transfer in animal models.^{138–146}

In the 1980s, this procedure was successfully introduced into clinical practice.^{147–149} These first encouraging results convinced the scientific community to refine further the technique and expand its indications. During the past 15 years, an increasing number of papers have successfully reported on limited series of reconstruction of either the proximal humerus or the distal radius and ulna with this technique.^{150–157}

metaepiphysis of the radius and the proximal humerus, with a slightly higher incidence for the latter. Due to morphological and dimensional similarities, the proximal fibula is ideal for distal radius reconstruction.¹⁵⁴ In addition, under the influence of a new biomechanical environment, the plasticity of the immature bone allows remarkable remodeling of the epiphysis after its transfer into the new anatomic location. Since the forearm is a two-bone segment and severe wrist deformity may result from asymmetrical growth of radius and ulna, the younger the patient, the greater is the indication for epiphyseal transfer in this location.

Case study

Resection of the entire radius for sarcoma

Sometimes the extension of the sarcoma is so wide that resection of the entire radius is required (Fig. 30.9). In such case, the reconstruction with proximal fibular epiphysis is particularly demanding. It is actually impossible to restore the entire length of the radius and, in addition, the absence of interosseous membrane would lead to unacceptable instability and proximal migration of the graft.

In the two cases of our series, we performed a bone fixation of the fibula to the midshaft of the ulna in a neutral pronation/supination (Fig. 30.10A). This is a sort of radioulnar synostosis, which provides a stable neoradius with the only drawback of abolishing pronation and supination.

The only conceptual concern that may be related to this choice is the risk to have a divergent growth of the two bones, because the ulna is straight and the new radius has an angle of about 45° with the longitudinal axis of the forearm.

However, in our experience, a longitudinal remodeling occurred and over the years the distal portion of the new radius migrated medially toward the ulna (see Fig. 30.10B), thus improving the stability of the joint and its function (Fig. 30.11).

Despite the anatomic mismatch between the fibular head and the glenoid fossa and the difference in transverse diameter of the shafts between the humerus and the fibula,¹⁵¹ autologous proximal fibular transplant remains the best option for



Fig. 30.9 Sarcoma involving extensively the radius. Resection of the entire bone is required.

Fig. 30.10 (A) Bone fixation of the fibula to the midshaft of the remaining ulna. Radioulnar synostosis in neutral pronation/supination position is created, providing a stable neoradius but eliminating pronation and supination. **(B)** Longitudinal remodeling of the physis occurred over the years.



Fig. 30.11 Long-term clinical outcome: functional flexion–extension of the wrist and wrist stability are restored after surgery.

autogenous reconstruction of the proximal humerus (Fig. 30.12). Over time, the fibular diaphysis undergoes hypertrophy, which minimizes the size discrepancy. Moreover, remodeling of the fibular head, although less impressive than in distal radius reconstruction, is expected, leading to more than acceptable shoulder joint stability and function (Fig. 30.13).

Proximal fibula epiphyseal transfer has proven to be an excellent option in limb salvage surgery in pediatric oncologic cases. Congenital differences of the upper limb, such as radial dysplasia, may also benefit from this surgical procedure. These cases, though, raise a few concerns and considerations: the new radius may be expected to grow more than the native ulna, which usually is hypoplastic, thus developing wrist instability and ulnar deviation. Limited literature is available at the moment on epiphyseal transfer for radial dysplasia with encouraging results reported by Yang *et al.*,¹⁶⁰ only on Bayne and Klug type III radial longitudinal deficiency. There is no report on long-term outcomes that could help to validate the technique.^{149,153,161}

Vascularized epiphyseal transplant based on the anterior tibial vascular system is a long and demanding procedure with high rate of complications, although transient, at the donor site. For these reasons, the cost–effectiveness ratio should be carefully evaluated. From personal experience of 30 cases, we have concluded that distal radius reconstruction is indicated up to 13 years of age because the radius and ulna require symmetrical growth until skeletal maturity. On the other hand, the humerus tolerates well a length discrepancy from both functional and cosmetic standpoints, setting the age limit for such a procedure at around 10 years of age.¹⁶²

Vascular supply of the proximal fibular epiphysis

In the past 30 years, the vascular anatomy of the proximal fibular epiphysis has been extensively investigated in order to define the best pedicle supplying both the epiphysis and the diaphysis of such a graft. There is general agreement that the proximal epiphysis of the fibula is supplied by two vascular sources: (1) the lateral inferior genicular artery; and (2)

the recurrent branches of the anterior tibial artery. The role of the two systems is differently emphasized according to different authors,^{163–167} but the majority of reports confirm that the anterior tibial artery provides the major contribution to the blood supply of the proximal fibular growth plate. Summarizing the data available in the literature, the lateral inferior geniculate artery mostly supplies the capsule of the proximal tibiofibular joint, the anterior and posterior recurrent branches of the anterior tibial artery supply the epiphysis, and the peroneal artery supplies the fibular shaft. It has also been experimentally demonstrated^{165,166} that the anterior tibial artery is able to vascularize the proximal two-thirds of the fibular diaphysis through tiny musculoepiosteal perforators that distribute to the periosteum of the shaft.

Almost all possible vascular pedicle combinations have been described in use in clinical practice. Pho *et al.* reported on 3 cases¹⁴⁸ where the peroneal artery was used as the pedicle, postulating that the presence of intercommunicating branches between the metaphyseal and epiphyseal systems allowed for




Fig. 30.12 In proximal humerus reconstruction, the smaller fibula is usually inserted inside the humeral medullar canal with a periosteal flap overlapping the bony junction. This type of assemblage improves stability and ability to heal. Vascular anastomoses are usually performed end-to-end to the deep humeral vessels.



Fig. 30.13 Reconstruction of the proximal humerus at 5-year follow-up. The transferred proximal fibula underwent significant remodeling and hypertrophy as well as enough longitudinal growth to prevent limb length discrepancy.

acceptable blood supply to the growth plate based solely on the peroneal artery. Although this is probably anatomically possible if enough soft tissue is left around the fibular neck, further experiences^{151,156} have had disappointing results on the growth rate of grafts supplied by the peroneal artery alone.

The use of a bipedicle graft has been suggested,^{147,149,151} with the purpose of providing two separate blood supplies to the epiphysis and the diaphysis. This option, however, is technically demanding, time-consuming, and requires two anastomoses at the recipient site. In addition, the physis is very susceptible to ischemia, and normal growth can be expected only if ischemia time is less than 3 h.¹⁶⁸ For these reasons, a single-pedicle graft is definitely a better choice.

The anterior tibial system has proven to be adequate in supplying both the epiphysis and the shaft and it is therefore the preferred pedicle for such a graft (Fig. 30.14). A potential disadvantage to the use of the anterior tibial vascular system is that the pedicle is very short (the distance between the division of the popliteal artery and the origin of the recurrent branch at the fibular neck). To overcome this issue, it has been suggested to use a reverse-flow pedicle.^{151,154,161} In this way, long vessels are provided, allowing comfortable anastomosis at the recipient site.

Harvest technique of the proximal fibula based on the tibialis anterior artery (Video 30.1 🎥)

The flap includes the proximal fibular epiphysis and a variable amount of the adjoining diaphysis. The epiphyseal

articular surface is oriented upward and medially to form the proximal tibiofibular joint. The biceps femoris tendon and the lateral collateral ligament are inserted in the lateral and proximal aspect of the epiphysis, which is also where the origins of the peroneus longus and extensor digitorum longus muscles are located. The common peroneal nerve crosses the fibular neck, moving toward the anterior compartment of the leg. The superficial branch is located in the space between the extensor digitorum longus and peroneus longus muscles, while the deep branch reaches the interosseous membrane and joins the anterior tibial vessels, giving several motor branches to the surrounding muscles. Proceeding proximally, the dissection of the vascular pedicle with preservation of the motor branches becomes increasingly demanding because of the increasing number of motor branches surrounding the vessels.

The harvest technique (Video 30.1 🎥) has been refined over the years and has been finally described in detail^{169,170} with the purpose of standardizing it and making it reproducible. The aim of the procedure is to harvest the proximal




Fig. 30.14 The anterior tibial artery supplies the growth plate and proximal epiphysis by means of a recurrent epiphyseal branch and the proximal two-thirds of the diaphysis by means of musculoepiosteal perforator branches.


fibula, preserving the blood supply to both the epiphysis and diaphysis with the least possible local morbidity. The following step-by-step description is the optimal surgical sequence according to the experience of the senior author (Video 30.1 ▶).

Skin incision

The surgical approach is developed in the plane between tibialis anterior and extensor digitorum longus muscles because this allows for direct visualization of the neurovascular bundle. The skin incision is therefore located in the anterolateral aspect of the leg and is extended proximally up to the neck of the fibula where it proceeds posteriorly and proximally over the biceps femoris tendon (Fig. 30.15).

Exposure of the anterior tibial pedicle

The anterior tibial artery and veins lie on the interosseous membrane. The peroneal nerve surrounds the vessel according to a very intricate tridimensional pattern and delivers several motor branches to the muscles of the anterior



A



B

Fig. 30.15 (A,B) An anterolateral approach is used for the harvest of the proximal fibula based on the anterior tibial vascular system. The skin incision is on the projection of the intermuscular space between the tibialis anterior and extensor digitorum longus muscles. The incision is prolonged proximally and posteriorly over the tendon of biceps femoris muscle.




Fig. 30.16 During the diaphyseal dissection of the pedicle, great care must be paid to isolating the peroneal nerve and its motor branches to the muscles of the anterior compartment.

compartment of the leg (Fig. 30.16). These motor branches are more numerous in the proximal part of the leg and it is therefore recommended to start the dissection distally and proceed proximally, maintaining the same plane to the fibular neck. Great care should be taken not only in dissecting the nerve from the vessels but also in preserving the small perforator branches of the anterior tibial artery that pierce the extensor digitorum longus and peroneus longus muscles, interposed between the vascular pedicle and the fibular shaft, supplying the periosteum of the proximal two-thirds of the diaphysis.

Dissection of the peroneal nerve at the fibular neck

The point where the peroneal nerve approaches the fibular neck is an important anatomic landmark. The nerve is in close contact with the bone and is covered by the proximal portion of extensor digitorum longus and peroneus longus muscles, which must be sharply divided in order to expose and protect the nerve and its motor branches (Fig. 30.17). Medially, at the same level, the recurrent epiphyseal branch of the anterior tibial artery rises from the main artery and pierces the muscular cuff and feeds the epiphysis. Its direct dissection is unnecessary and potentially dangerous; it is therefore recommended to preserve the proximal insertion of the muscles attached to the proximal epiphysis in order to protect the fragile epiphyseal vascular network.

Section of the interosseous membrane and distal osteotomy

The interosseous membrane must be sharply detached from the tibia, and all the soft tissue interposed between it and the vascular bundle must be carefully protected (Fig. 30.18). The perforator vessels to the shaft of the fibula branch off laterally and pierce the of extensor digitorum longus and peroneus longus muscle bellies. In order to maintain the vascular connection between the artery and bone, a longitudinal strip of muscle approximately 1 cm wide should be preserved around the harvested fibula (Fig. 30.19). The fibula is cut distally at the desired length, and an extra portion of periosteum is left in order improve healing capacity at the recipient site. The anterior tibial artery and veins are ligated as distally as possible to obtain a long reverse-flow pedicle.





Fig. 30.17 (A,B) The peroneal nerve is an important landmark in proximal dissection. The nerve is exposed in its intramuscular portion by means of sharp section of the extensor digitorum longus and peroneus longus muscles. The muscular cuff proximal to the section must be left intact because it protects the recurrent branch to the growth plate of the anterior tibial artery.




Fig. 30.18 Sharp detachment of the interosseous membrane from the tibia. Note the location of the vascular pedicle and its relationship to the peroneal nerve.

Harvest of the biceps femoris tendon and capsulotomy of the proximal tibiofibular joint

The insertions of the biceps femoris tendon and the lateral collateral ligaments are almost at the same point at the apex of the fibula. The tendon should be divided in two strips (**Fig. 30.20**): the posterior portion is harvested with the fibula to provide additional soft tissue useful for stabilization of the recipient joint; the anterior half is used to reinforce the lateral collateral ligament after its reinsertion on the lateral aspect of tibial metaphysis by means of staples or transosseous sutures. Gentle external rotation of the fibula allows for the division of the medial and posterior capsule of the proximal tibiofibular joint after coagulation of the lateral inferior genicular artery.




Fig. 30.19 The perforator branches to the diaphysis are too small and fragile to allow a direct intramuscular dissection. It is therefore suggested that a strip of muscle containing the perforators be left intact between the vascular pedicle and the bone.





Fig. 30.20 (A,B) The biceps femoris tendon is longitudinally divided in two strips. One is harvested with the bone flap and may be used to improve the stability of the joint after the transfer. The second one is fixed to the lateral aspect of the tibia to reinforce the lateral collateral ligament.




Fig. 30.21 After release of tourniquet and 20–30 min of reperfusion of the flap, the tibialis anterior artery is ligated and severed just distal to its emergence from the popliteal artery.

Final dissection of the proximal portion of the vascular pedicle

The anterior tibial artery should be dissected up to the division of the popliteal artery (Fig. 30.21). The recurrent branch rises from the anterior tibial artery approximately 2 cm distal to its origin, and is often difficult to identify. For this reason, it is advisable to preserve all the small vessels, which pierce the muscular cuff toward the fibular epiphysis. After release of the tourniquet, the muscular cuff surrounding the epiphysis, the diaphyseal periosteum, and the medullary canal are carefully inspected. After a few seconds, bleeding should be observed at the three levels, confirming the successful harvest of the proximal fibula, based on the anterior tibial artery pedicle (Fig. 30.22). Due to low tolerance to ischemia, it is suggested to wait 20–30 min before clipping and dividing the proximal pedicle.

Details regarding the selection of flap vena comitans is given in Box 30.1; osteosynthesis in Box 30.2; and selection of recipient vessels in Box 30.3.

Postoperative care

Donor site

In order to protect the reconstructed lateral collateral ligament, a cast at 30° flexion of knee and neutral ankle position is applied. In children below the age of 8 years, the cast is maintained for 4 weeks; in older and compliant children, the cast may be substituted after 2 weeks with a brace of appropriate size, for a total of 4 weeks of immobilization. The rehabilitation program is started at 1 month postoperatively with the aim of recovering full motion of the knee without compromising stability (Box 30.4).

Recipient site

A long spica cast or a shoulder brace is applied for 4 weeks, respectively, after distal radius and proximal humerus




Fig. 30.22 At the end of the dissection, before severing the vascular pedicle, the tourniquet is released to reset the ischemia time. Bleeding should be observed from both the epiphysis and the medullar canal after a few minutes. 1, posterior articular capsule is severed; 2, bleeding from the bone is observed.

BOX 30.1 Selection of flap vena comitans

The proximal epiphyseal fibular transfer based on the anterior tibial artery is a reverse-flow flap; however, an adequate venous return is guaranteed by the presence of several small shunts that interconnect the two venae comitantes, allowing the reverse venous flow to bypass the valves. Due to this intricate pattern of valves and shunts, usually, only one of the two venae comitantes has adequate return flow: it is instrumental, for a good outcome, to identify which one is.

After 20–30 min with the tourniquet down, the two venae comitantes are ligated and divided proximally leaving intact the flow through the artery. Within a couple of minutes, the venous flow is inverted and bleeding is evident from one of the two venae comitantes. The bleeding vein is tagged to be anastomosed at the recipient site. (Fig. 30.23).

During the dissection of the vascular bundle care must be taken not to interrupt these delicate venous shunts.




Fig. 30.23 (A) Pattern of valves and shunts of venae comitantes. (B) When the flow is inverted, bleeding is usually evident from one of the two venae comitantes.

BOX 30.2 Osteosynthesis

Humerus reconstruction

The arm is a single bone segment with a high mechanical stress, particularly in case of rotation against resistance. For this reason, a stable bone fixation must be provided; long plates are therefore preferred over less invasive options such as K-wires and screws. However, the implant cannot be too stiff for risk of fracture at the level of the most proximal screw, which is the weakest point of the implant (Fig. 30.24A). In order to provide a more elastic and less invasive bone fixation, we advocate the use of locking compression plates (LCP). The fibula is usually placed for a couple of centimeters in the medullary canal of the distal stump of the humerus and a periosteal flap is wrapped around the bony junction. Then a long LCP plate is placed. Three bicortical screws are used in the humeral portion while few unicortical screws are used in the fibular portion (see Fig. 30.24B). This type of assemblage provides a very stable bone fixation at the junction between fibula and humerus and a minimally invasive and elastic fixation in the fibular segment.

Radius reconstruction

Similarities in size and shape between the radius and the fibula facilitates osteosynthesis in the forearm. Also in this case, LCP plates are the preferred method of bone fixation. As an alternative, lag screws and step-cut osteotomy may be used. The wrist joint is temporarily stabilized with a K-wire which is usually removed 1 month after surgery, in addition the strip of biceps femoris tendon is woven in the residual capsule in order to provide additional stability to the joint. By contrast, the distal radioulnar joint is intentionally left lax without any type of stabilization in order to maintain full range of pronation and supination.




Fig. 30.24 (A) Humerus implant: the weakest portion of the implant is at the passage between the hardware and the bone, with higher risk of fracture at these levels especially in case of rigid implants. (B) More elastic and less invasive bone fixation.

BOX 30.3 Selection of recipient vessels

The harvest of the fibula based on a reverse-flow anterior tibial artery pedicle allows for a long distal pedicle, which may be easily anastomosed to the recipient vessels.

In humeral reconstruction, the deep brachial artery, satellite of the radial nerve, is usually preferred for end-to-end anastomosis with the fibular vessels. If the venae comitantes are too small, the cephalic vein or one of the venae comitantes of the brachial artery may be chosen for venous anastomosis.

In case of radius reconstruction, there are more choices. When the radial artery is resected together with radius, the proximal stump can be easily anastomosed with the fibular pedicle end to end. Alternatively, the anterior interosseous artery may be used end to end because its sacrifice has a negligible impact on hand blood supply.

BOX 30.4 Postoperative rehabilitation: donor site

- After 4 weeks of immobilization, the cast or the splint are removed and passive range of motion of knee and ankle is initiated.
- The use of crutches is virtually impossible because of the surgery involving the upper limb and is therefore avoided.
- During the therapy sessions, the child is also helped to get acquainted with the upright position standing only on the non-operated leg.
- The splint is repositioned only at night for 4 more weeks.
- A transient palsy of the peroneal nerve occurs in almost all cases. Great care is taken to avoid equinus deformity of the foot with Achilles tendon retraction. A Codivilla spring is used routinely in all cases of peroneal palsy and maintained until complete recovery. Passive mobilization of the ankle is taught to parents and performed 3–5 times per day.
- Full weight-bearing is usually possible at 2 months after surgery.
- The rehabilitation program is eventually tailored to each patient considering their clinical condition and the necessity of adjuvant chemotherapy.

reconstruction. The rehabilitation program follows the immobilization period and must take into account different variables such as type and stability of bone fixation, amount of muscles excised during the resection, and age and compliance of the patient.

Outcomes, prognosis, and complications

Analysis of the results takes into account the survival of the grafts, as well as their consolidation, longitudinal growth, and remodeling. In a personal series of 27 cases of upper limb skeletal reconstruction after bone sarcoma resection with epiphyseal transplant, all the transferred bones except one survived and healed with the recipient bone in a period of time ranging from 1 to 2 months. This variability depended on the age of the child and the length of the reconstructed segment. In some cases, the viability of the transplant was confirmed by bone scan.

Significant axial growth, calculated by the progressive increase in the distance between the tip of the metal plate used for bone fixation and the apex of the epiphysis of the transferred fibula, has been observed in approximately 70% of cases monitored. Its extent was variable depending on factors that are only partially known, amongst which the patient's age was predominant. The annual growth trend varied between 0.7 and 1.35 cm (Fig. 30.25), and in all cases there was prevention of future length discrepancy with the opposite limb. As far as the radius is concerned, symmetrical growth was observed in the neoradius in all cases, not only with respect to the opposite limb, but also to the adjacent ulna, which confirms the integration of the fibula into its new anatomical site. The average flexion of the wrist was 75°, while the average extension was 63°. The overall range of movement was equal to on average 70% of the opposite hand, which allowed for excellent functional recovery. The pronation range was also restored.



Fig. 30.25 Postoperative radiograph and 4-year follow-up of one case of distal radius reconstruction. In this case, the average growth per year was 0.9 cm.

In cases of humeral reconstruction, the functional outcomes were not as positive. The morphological and dimensional discrepancy between the fibular head and the glenoid fossa may lead to proximal migration of the fibular epiphysis and, in some cases, subacromial displacement. Moreover, the extent of soft tissue involved in the neoplasia and consequently removed further hinders functional recovery. In all monitored cases, however, shoulder abduction between 70° and 100° was observed.

Premature ossification of the growth plate and consequent end of growth were observed in five cases of humeral reconstruction. Two of these transplants were based on peroneal vessels, which, in our opinion, are not as reliable in ensuring correct epiphyseal perfusion. In the other three cases, the epiphyseal artery was probably damaged during stabilization in the glenohumeral joint. Five fractures of the neohumerus and two of the neoradius were observed. All the fractures but one healed conservatively in due time. Replacement of an inadequate fixation was performed in one case.

In four cases of proximal humerus reconstruction, incorrect alignment between the fibula head and glenoid fossa was observed. In these cases, the epiphysis migrated subacromially. The reasons for this complication are the anatomical mismatching between fibular head and glenoid fossa and the extensive oncological excision of muscles and ligaments with consequent joint stability. All the four cases, however, recovered an acceptable range of motion.

With transosseous suture of the lateral collateral ligament at the donor site, no residual instability of the knee was ever observed. Neuropraxia of the peroneal nerve occurred in approximately two-thirds of cases. This was probably caused by stretching of small motor branches during the dissection. This deficit resolved spontaneously within 1 year in all but two cases. One of the patients had a permanent residual paralysis of the tibialis anterior and one of the extensor digitorum longus muscles.

Secondary procedures

Secondary procedures may be necessary at both the donor and the recipient site.

Donor site

In case of permanent palsy of the peroneal nerve, a tendon transfer is indicated to restore the function of the tibialis anterior muscle. In our series, we observed no cases of knee joint instability.

Recipient site

A feared complication is the total loss of the graft due to failure to restore its blood supply. We did not observe this complication but its treatment would require the use of a massive frozen allograft as salvage procedure. In the majority of cases, the fate of an osteoarticular allograft in the medium/long term is a massive resorption of the articular cartilage, which should be treated with a prosthetic replacement of the allogenic humeral head.

In our experience, we have observed premature growth arrest, probably due to vascular damage to the physis, in five cases of proximal humerus reconstruction. Despite the limb

length discrepancy, all patients have an acceptable function and no further surgery was required.

A relatively frequent complication is graft fracture in proximal humerus reconstruction. In our series, this event was usually successfully treated conservatively with immobilization in a cast. Nonetheless, revision of the hardware and cancellous bone grafting may be considered in cases of displaced fractures.

Future directions

Although epiphyseal transfer proved to be a reliable and effective reconstructive option in case of skeletal disorders involving an immature epiphysis, this procedure is not widely used yet. The technique is well standardized, and several papers are now available in the literature reporting, in the vast

majority of cases, either the reconstruction of the proximal humerus or the distal radius. In the future, new recipient sites might be added to the classic ones, taking advantage of the high remodeling potential of the immature fibular head. We have recently used this technique for mandible reconstruction on a child affected by osteoblastoma of the mandibular condyle, with encouraging results. In selected cases, other joints might benefit from reconstruction with vascularized proximal epiphyseal transfer.

Congenital differences at the wrist level, such as radial and ulnar dysplasia, are now successfully treated with this procedure. A few cases of radial dysplasia have been, indeed, reported recently with good results.¹⁶⁰ These cases, though, need a longer follow-up to evaluate the growth rate. These initial results are very encouraging, and epiphyseal transfer of the proximal fibula may be a valid alternative to the procedure described by Vilkki,¹⁷¹ which is, at present, the only alternative to the conventional techniques.



Access the complete reference list online at

<http://www.expertconsult.com>

3. Rauch F. Bone growth in length and width: the yin and yang of bone stability. *J Musculoskelet Neuronal Interact.* 2005;5:194–201. *This entertaining article presents in a very approachable manner the morphophysiology of the growth plate and the mechanisms that regulate bone growth.*
27. Canavese F, Charles YP, Dimeglio A. Skeletal age assessment from elbow radiographs. Review of the literature. *Chir Organi Mov.* 2008;92:1–6. *A useful method to assess skeletal age during puberty is presented in this article. The paper also offers an accurate description of growth during puberty and contains a review of the literature of other methods used for skeletal age assessment in growing individuals.*
85. Sailhan F, Chotel F, Guibal AL, et al. Three-dimensional MRI imaging in the assessment of physeal growth arrest. *Eur Radiol.* 2004;14:1600.
98. Birch JG. Surgical technique of physeal bar resection. *Instr Course Lect.* 1992;41:445.
147. Tsai TM, Ludwig L, Tonkin M. Vascularized fibular epiphyseal transfer: a clinical study. *Clin Orthop.* 1986;210:228–234. *In this article, a clinical series of eight pediatric patients who underwent joint reconstruction by means of fibular epiphyseal transplant is reported. Four of the patients showed continued growth of the transplanted bone. A double-pedicled flap was described for the first time in this pioneering report.*
148. Pho RW, Patterson MH, Kour AK, et al. Free vascularised epiphyseal transplantation in upper extremity reconstruction. *J Hand Surg Am.* 1988;13:440–447.
156. Innocenti M, Delcroix L, Romano GF, et al. Vascularized epiphyseal transplant. *Orthop Clin North Am.* 2007;38:95–101.
165. Taylor GI, Wilson KR, Rees MD, et al. The anterior tibial vessels and their role in epiphyseal and diaphyseal transfer of the fibula: experimental study and clinical applications. *Br J Plast Surg.* 1988;41:451–469. *This is the first article reporting both an experimental and clinical experience in proximal fibular epiphyseal transfer based on the anterior tibial vascular system. The most remarkable finding consisted of assessing the ability of the anterior tibial artery to supply not only the proximal growth plate but also a considerable amount of fibular shaft. This improvement in the knowledge of the vascularity of the proximal fibula allowed reliable use of a fibula flap with a single pedicle.*
170. Innocenti M, Delcroix L, Manfrini M, et al. Vascularized proximal fibular epiphyseal transfer for distal radial reconstruction. *J Bone Joint Surg Am.* 2005;87(suppl 1):237–246. *In this article, the operative technique for harvesting the proximal fibula supplied by the anterior tibial vascular system is reported in detail. A step-by-step description of the procedure is provided and supported by anatomical drawings and related clinical pictures. Recommendations and pitfalls may help the reader in approaching this reconstructive technique.*

References

- Burdan F, Szumilo J, Korobowicz A, et al. Morphology and physiology of the epiphyseal growth plate. *Folia Histochem Cytobiol.* 2009;47:5–16.
- Allen DM, Mao JJ. Heterogeneous nanostructural and nanoelastic properties of pericellular and interterritorial matrices of chondrocytes by atomic force microscopy. *J Struct Biol.* 2004;145:196–204.
- Rauch F. Bone growth in length and width: the yin and yang of bone stability. *J Musculoskelet Neuronal Interact.* 2005;5:194–201. *This entertaining article presents in a very approachable manner the morphophysiology of the growth plate and the mechanisms that regulate bone growth.*
- Ballock RT, O'Keefe RJ. The biology of the growth plate. *J Bone Joint Surg Am.* 2003;85:715–726.
- Melrose J, Smith SM, Smith MM, et al. The use of Histochoice for histological examination of articular and growth plate cartilages, intervertebral disc and meniscus. *Biotech Histochem.* 2008;83:47–53.
- Sawae Y, Sahara T, Sasaki T. Osteoclast differentiation at growth plate cartilage-trabecular bone junction in newborn rat femur. *J Electron Microscop.* 2003;52:493–502.
- Haas S. The localization of the growing point in the epiphyseal cartilage plate of bone. *Am J Orthop Surg.* 1917;15:563.
- Harris W. The endocrine basis for slipping of the upper femoral epiphysis. *J Bone Joint Surg Br.* 1950;32:5.
- Salter R. Epiphyseal plate injuries. In: Letts R, ed. *Management of Pediatric Fractures.* New York, NY: Churchill Livingstone; 1994:11.
- Seeman E. Periosteal bone formation – a neglected determinant of bone strength. *N Engl J Med.* 2003;349:320–323.
- Iannotti J, Goldstein S, Khun J, et al. Growth plate and bone development. In: Simon SR, ed. *Orthopaedic Basic Sciences.* Rosemont, IL: American Academy of Orthopaedic Surgeons; 1994:191.
- Juster M, Moscofian A, Balmalin-Oligo N. Formation of the skeleton: VIII. Growth of the long bone: periostealization of the metaphyseal bone. *Bull Assoc Anat (Nancy).* 1975;59:437.
- Oestreich AE, Ahmad BS. The periphysis and its effect on the metaphysis: I. Definition and normal radiographic pattern. *Skeletal Radiol.* 1992;21:5.
- van der Eerden BC, Karperien M, Wit JM. Systemic and local regulation of the growth plate. *Endocr Rev.* 2003;24:782–801.
- Kronenberg HM. Developmental regulation of the growth plate. *Nature.* 2003;423:332–336.
- Kronenberg HM. PTHrP and skeletal development. *Ann N Y Acad Sci.* 2006;1068:1–13.
- Kozhemyakina E, Lassar AB, Zelzer E. A pathway to bone: signaling molecules and transcription factors involved in chondrocyte development and maturation. *Development.* 2015;142:817–831.
- Zhu M, Zhang J, Dong Z, et al. The p27 pathway modulates the regulation of skeletal growth and osteoblastic bone formation by parathyroid hormone-related peptide. *J Bone Miner Res.* 2015;30:1969–1979.
- Wilsman NJ, van Sickle DC. The relationship of cartilage canals to the initial osteogenesis of secondary centers of ossification. *Anat Rec.* 1970;168:381–392.
- Burkus JK, Ganey TM, Ogden JA. Development of the cartilage canals and the secondary center of ossification in the distal chondroepiphysis of the prenatal human femur. *Yale J Biol Med.* 1993;66:193–202.
- Trueta J, Morgan JD. The vascular contributions to osteogenesis. *J Bone Joint Surg Br.* 1960;42B:97–109.
- Shapiro F. Epiphyseal and physeal cartilage vascularization: a light microscopic and tritiated thymidine autoradiographic study of cartilage canals in newborn and young postnatal rabbit bone. *Anat Rec.* 1998;252:140–148.
- Dale GG, Harris WR. Prognosis of epiphyseal separation: an experimental study. *J Bone Joint Surg Br.* 1958;40-B:116–122.
- Bayley N. Individual patterns of development. *Child Dev.* 1956;27:45.
- Prader A. Normal growth and disorders of growth in children and adolescents. *Klin Wochenschr.* 1981;59:977.
- Westh RN, Menelaus MB. A simple calculation for the timing of epiphyseal arrest: a further report. *J Bone Joint Surg Br.* 1981;63:117.
- Canavese F, Charles YP, Dimeglio A. Skeletal age assessment from elbow radiographs. Review of the literature. *Chir Organi Mov.* 2008;92:1–6. *A useful method to assess skeletal age during puberty is presented in this article. The paper also offers an accurate description of growth during puberty and contains a review of the literature of other methods used for skeletal age assessment in growing individuals.*
- Anderson M, Green W. Lengths of the femur and tibia: norms derived from orthoroentgenograms of children from five years of age until epiphyseal closure. *Am J Dis Child.* 1948;75:279.
- Anderson M, Green WT, Messner MB. Growth and predictions of growth in the lower extremities. *J Bone Joint Surg Am.* 1963;45-A:1–14.
- Anderson M, Messner MB, Green WT. Distribution of lengths of the normal femur and tibia in children from one to eighteen years of age. *J Bone Joint Surg Am.* 1964;46:1197–1202.
- Green WT, Anderson M. Experience with epiphyseal arresting correcting discrepancies in length of the lower extremities in infantile paralysis: a method of predicting the effect. *J Bone Joint Surg Am.* 1947;29:659.
- Green WT, Anderson M. Skeletal age and the control of bone growth. *Instr Course Lect.* 1960;17:199.
- Dimeglio A. *La Croissance en Orthopédie.* Montpellier: Suramps Medical; 1987.
- Exner GU. *Normalwerte in der Kinderorthopädie. Wachstum und Entwicklung.* Stuttgart: Thieme; 1990.
- Tanner JM, Whitehouse RH. Clinical longitudinal standards for height, weight, height velocity and weight velocity and stages of puberty. *Arch Dis Child.* 1976;51:170–179.
- Greulich WW, Pyle SI. *Radiographic Atlas of Skeletal Development of Hand and Wrist.* 2nd ed. Stanford, CA: Stanford University Press; 1959.
- Sempé M, Pavia C. *Atlas de la Maturation Squelettique.* Paris: SIMEP; 1979.
- DeRoo T, Schroder HJ. *Atlas van de Skeletale Leeftijd.* Dordrecht: Intercontinental Graphics; 1977.
- Tanner JM, Whitehouse RH, Marshall WA, et al. *Assessment of Skeletal Maturity and Prediction of Adult Height (TW Method).* London: Academic Press; 1975.
- Sauvegrain J, Nahm H, Bronstein N. Etude de la maturation osseuse du coude. *Ann Radiol.* 1962;5:542–550.
- Risser JC. The Iliac apophysis; an invaluable sign in the management of scoliosis. *Clin Orthop.* 1958;11:111–119.
- Dimeglio A. Growth in pediatric orthopaedics. In: Morris T, Weinstein SL, eds. *Lovell & Winter's Pediatric Orthopaedics.* 6th ed. Philadelphia, PA: Lippincott: Williams and Wilkins; 2005:35–61.
- Dimeglio A, Charles YP, Daures JP, et al. Accuracy of the Sauvegrain method in determining skeletal age during puberty. *J Bone Joint Surg Am.* 2005;87:1689–1696.
- Charles YP, Canavese F, Dimeglio A. Skeletal age determination from the elbow during pubertal growth. *Orthopade.* 2005;34:1052–1060.
- Charles YP, Daures JP, de Rosa V, et al. Progression risk of idiopathic juvenile scoliosis during pubertal growth. *Spine.* 2006;31:1933–1942.
- Birch JG, Herring JA, Wenger DR. Surgical anatomy of selected physis. *J Pediatr Orthop.* 1984;4:224.
- Langenskiöld A. Growth disturbances after osteomyelitis of femoral condyles in infants. *Acta Orthop Scand.* 1984;55:1.
- Langenskiöld A, Osterman K. Surgical treatment of partial closure of the epiphyseal plate. *Reconstr Surg Traumatol.* 1979;17:48.

49. Peterson HA, Wood MB. Physeal arrest due to laser beam damage in a growing child. *J Pediatr Orthop*. 2001;21:335.
50. Bisgard J, Martenson L. Fractures in children. *Surg Gynecol Obstet*. 1937;65:464.
51. Compere E. growth arrest in long bones as a result of fractures that include epiphysis. *JAMA*. 1935;105:2140.
52. Mann DC, Rajmaira S. Distribution of physeal and non-physeal fractures in 2650 long bone fractures in children aged 0–16 years. *J Pediatr Orthop*. 1990;10:713.
53. Mizuta T, Benson WM, Foster BK, et al. Statistical analysis of incidence of physeal injuries. *J Pediatr Orthop*. 1987;7:518.
54. Worlock P, Stower M. Fracture patterns in Nottingham children. *J Pediatr Orthop*. 1986;6:656–660.
55. Peterson HA, Madhok R, Benson JT, et al. Physeal fractures: Part 1. Epidemiology in Olmsted County, Minnesota, 1979–1988. *J Pediatr Orthop*. 1994;14:423.
56. Peterson HA. Physeal fractures: Part 3. Classification. *J Pediatr Orthop*. 1994;14:439.
57. Chung R, Foster BK, Xian CJ. The potential role of VEGF-induced vascularization in the bony repair of injured growth plate cartilage. *J Endocrinol*. 2014;221:63–75.
58. Aitken A. The end results of the fractured distal radial epiphysis. *J Bone Joint Surg Am*. 1935;17:302.
59. Aitken A. The end results of the fractured distal tibial epiphysis. *J Bone Joint Surg Am*. 1936;18:605.
60. Aitken A. End results of fractures of the proximal humeral epiphysis. *J Bone Joint Surg Am*. 1936;18:1036.
61. Foucher M. De la divulsion des epiphyses. *Cong Med Fr (Paris)*. 1863;1:63.
62. Odgen JA. *Skeletal Injury in the Child*. Philadelphia, PA: Lea & Febiger; 1981.
63. Odgen JA. Injury to the growth mechanism of the immature skeleton. *Skeletal Radiol*. 1981;6:237.
64. Poland J. *Traumatic Separation of the Epiphyses*. London: Smith, Elder; 1898.
65. Salter R, Harris W. Injuries involving the epiphyseal plate. *J Bone Joint Surg Am*. 1963;45:587.
66. Peterson HA, Burkhart SS. Compression injury of the epiphyseal growth plate: fact or fiction? *J Pediatr Orthop*. 1981;1:377.
67. Skak SV. A case of partial physeal closure following compression injury. *Arch Orthop Trauma Surg*. 1989;108:185.
68. Egol KA, Karunakar M, Phieffer L, et al. Early versus late reduction of a physeal fracture in an animal model. *J Pediatr Orthop*. 2002;22:208.
69. Rang M. Injuries of the epiphysis, growth plate and perichondral ring. In: Rang M, ed. *Children's Fractures*. Philadelphia, PA: JB Lippincott; 1983:23.
70. Gloeckler Ries LA, Reichman ME, Riedel Lewis D, et al. Cancer survival and incidence from the Surveillance, Epidemiology, and End Results (SEER) program. *Oncologist*. 2003;8:541–552.
71. Mahboubi S. Radiologic approach to primary bone lesions. In: *Pediatric Bone Imaging: A Practical Approach*. Boston, MA: Little Brown; 1989:175.
72. Kuettner KE, Pauli BU, Soble L. Morphological studies on the resistance of cartilage to invasion by osteosarcoma cells in vitro and in vivo. *Cancer Res*. 1978;38:277–287.
73. Brem H, Folkman J. Inhibition of tumor angiogenesis by cartilage. *J Exp Med*. 1975;141:427–439.
74. Enneking WF, Kagan A. Transepiphyseal extension of osteosarcoma: incidence, mechanism and implications. *Cancer*. 1978;41:1526–1537.
75. Panuel M, Gentet JC, Scheiner C, et al. Physeal and epiphyseal extent of primary malignant bone tumors. Correlation of preoperative MRI and the pathologic examination. *Pediatr Radiol*. 1993;23:421–424.
76. Norton KI, Hermann G, Abdelwahab IF, et al. Epiphyseal involvement in osteosarcoma. *Radiology*. 1991;180:813–816.
77. Herring JA, ed. *Tachdjian's Pediatric Orthopaedics*. 4th ed. Philadelphia, PA: Saunders Elsevier; 2007.
78. Carlson WO, Wenger DR. A mapping method to prepare for surgical excision of a partial physeal arrest. *J Pediatr Orthop*. 1984;4:232.
79. Kasser JR. Physeal bar resection after growth arrest about the knee. *Clin Orthop Relat Res*. 1990;255:68.
80. Loder R, Swinford AE, Kuhns LR, et al. The use of the helical computed tomographic scan to assess bony physeal bridges. *J Pediatr Orthop*. 1997;17:356.
81. Oestreich AE. Imaging on the skeleton and soft tissue in children. *Curr Opin Radiol*. 1992;4:55.
82. Cheon JC, Kim IO, Choi IH, et al. Magnetic resonance imaging of the remaining physis in partial physeal resection with graft interposition in a rabbit model. A comparison with physeal resection alone. *Invest Radiol*. 2005;40:235.
83. Craig JG, Cramer KE, Cody DD, et al. Premature partial closure and other deformities of the growth plate: MR imaging and three dimensional modeling. *Radiology*. 1999;210:835.
84. Eklund K, Jamarillo D. Patterns of premature physeal arrest: MR imaging of 111 children. *AJR Am J Roentgenol*. 2002;178:967.
85. Sailhan F, Chotel F, Guibal AL, et al. Three-dimensional MRI imaging in the assessment of physeal growth arrest. *Eur Radiol*. 2004;14:1600.
86. Phemister DB. Operative arrestment of longitudinal growth of bone in the treatment of deformities. *J Bone Joint Surg Am*. 1933;15:1–15.
87. Khoury JG, Tavares JO, McConnell S, et al. Results of screw epiphysodesis for the treatment of limb length discrepancy and angular deformity. *J Pediatr Orthop*. 2007;27:6.
88. Zazjyalov PV, Plaksin IT. Elongation of crural bones in children using a method of distraction epiphysiolysis. *Vestn Khir Im I I Grek*. 1967;103:67–70.
89. Zazjyalov PV, Plaksin IT. Distraction epiphyseolysis for lengthening of the lower limbs in children. *Khirurgiia (Mosk)*. 1968;7:121–123.
90. De Bastiani G, Aldegheri R, Renzi Brivio L. Indicazioni particolari dei Fissatori esterni. *G Ital Fissatore Esterno*. 1979;501:31.
91. Aldegheri R, Trivella G, Lavini F. Epiphyseal distraction. Hemichondrodysplasia. *Clin Orthop Relat Res*. 1989;241:128–136.
92. De Bastiani G, Aldegheri R, Renzi Brivio L, et al. Chondrodysplasia-controlled symmetrical distraction of the epiphyseal plate. Limb lengthening in children. *J Bone Joint Surg Br*. 1986;68:550–556.
93. Kershaw CJ, Kenwright J. Epiphyseal distraction for bony bridges: a biomechanical and morphologic study. *J Pediatr Orthop*. 1993;13:46–50.
94. Canadell J, de Pablos J. Correction of angular deformities by physeal distraction. *Clin Orthop Relat Res*. 1992;283:98–105.
95. Langlois V, Laville JM. Physeal distraction for limb length discrepancy and angular deformity. *Rev Chir Orthop Reparatrice Appar Mot*. 2005;91:199–207.
96. Langenskiöld A. Surgical treatment of partial closure of the growth plate. *J Pediatr Orthop*. 1981;1:3–11.
97. Peterson H. Partial growth plate arrest and its treatment. *J Pediatr Orthop*. 1984;4:246–258.
98. Birch JG. Surgical technique of physeal bar resection. *Instr Course Lect*. 1992;41:445.
99. Bright RW. Operative correction of partial epiphyseal plate closure by osseous-bridge resection and silicone-rubber implant: an experimental study in dogs. *J Bone Joint Surg Am*. 1974;56:655.
100. Langenskiöld A. An operation for partial closure of an epiphyseal plate in children, and its experimental basis. *J Bone Joint Surg Br*. 1975;57:325.
101. Langenskiöld A. Partial closure of the epiphyseal plate: principles of treatment. 1978. *Clin Orthop Relat Res*. 1993;297:4.
102. Bright RW. Partial growth arrest: identification, classification, and the results of treatment. *Orthop Trans*. 1982;6:65–66.
103. Broughton NS, Dickens DRV, Cole WG, et al. Epiphyseolysis for partial growth plate arrest. *J Bone Joint Surg Br*. 1989;71B:13–16.
104. Lamoureux J, Verstrecken L. Progressive upper limb lengthening in children: a report of two cases. *J Pediatr Orthop*. 1986;6:481–485.

105. Williamson RV, Staheli LT. Partial physeal growth arrest: treatment by bridge resection and fat interposition. *J Pediatr Orthop.* 1990;10:769–776.
106. Ogden JA. Current concepts review: the evaluation and treatment of partial physeal arrest. *J Bone Joint Surg Am.* 1987;69A:1297–1302.
107. Mackoud WS, Bright R. Bar resection and Silastic interposition in distal radial physeal arrest. *Orthop Trans.* 1989;13:1–2.
108. Cabanela ME, Coventry MB, Maccarty CS, et al. The fate of patients with methyl methacrylate cranioplasty. *J Bone Joint Surg Am.* 1972;54A:278–281.
109. Shea KG, Rab GT, Dufurrena M. Pathological fracture after migration of cement used to treat distal femur physeal arrest. *J Pediatr Orthop B.* 2009;18:185–187.
110. Setzen G, Williams EF. Tissue response to suture materials implanted subcutaneously in a rabbit model. *Plast Reconstr Surg.* 1997;100:1788–1795.
111. Inoue T, Naito M, Fujii T, et al. Partial physeal growth arrest treated by bridge resection and artificial dura substitute interposition. *J Pediatr Orthop B.* 2006;15:65–69.
112. Yoshida T, Kim WC, Tsuchida Y, et al. Experience of bone bridge resection and bone wax packing for partial growth arrest of distal tibia. *J Orthop Trauma.* 2008;22:142–147.
113. Hasler CC, Foster BK. Secondary tethers after physeal bar resection: a common source of failure? *Clin Orthop Relat Res.* 2002;405:242–249.
114. Oesterman K. Operative elimination of partial premature epiphyseal closure. An experimental study. *Acta Orthop Scand.* 1972;147(suppl):1–79.
115. Frost HM. Biomechanical control of knee alignment: some insights from a new paradigm. *Clin Orthop.* 1997;335:335–342.
116. Mehlman CT, Araghi A, Roy DR. Hyphenated history: the Hueter–Volkmann law. *Am J Orthop.* 1997;26:798–800.
117. Bagatur AE, Doúan A, Zorer G. Correction of deformities and length discrepancies of the forearm in children by distraction osteogenesis. *Acta Orthop Traumatol Turc.* 2002;36:111–116.
118. Hosny GA. Unilateral humeral lengthening in children and adolescents. *J Pediatr Orthop B.* 2005;14:439–443.
119. Janovec M. Short humerus: results of 11 prolongations in 10 children and adolescents. *Arch Orthop Trauma Surg.* 1991;111:13–15.
120. Lee FY, Schoeb JS, Yu J, et al. Operative lengthening of the humerus. *J Pediatr Orthop.* 2005;25:613–616.
121. Mader K, Gausepohl T, Pennig D. Shortening and deformity of radius and ulna in children: correction of axis and length by callus distraction. *J Pediatr Orthop B.* 2003;12:183–191.
122. Burge P. Lengthening in the upper limb [editorial]. *J Hand Surg [Br].* 1993;18B:141–143.
123. Dahl MT. The gradual correction of forearm deformities in multiple hereditary exostoses. *Hand Clin.* 1993;9:707–718.
124. Irani RN, Petrucelli TC. Ulnar lengthening for negative ulnar variance in hereditary multiple osteochondromata. *J Pediatr Orthop.* 1993;1:143–147.
125. Price CT, Mills WL. Radial lengthening for septic growth arrest. *J Pediatr Orthop.* 1983;3:88–91.
126. Pritchett JW. Lengthening the ulna in patients with hereditary multiple exostoses. *J Bone Joint Surg Br.* 1986;68B:561–565.
127. Masada K, Tsuyuguchi Y, Kawai H, et al. Operations for forearm deformity caused by multiple osteochondromas. *J Bone Joint Surg Br.* 1989;71B:24–29.
128. Linscheid RL. Ulnar lengthening and shortening. *Hand Clin.* 1987;3:69–78.
129. Abe M, Shirai H, Okamoto M, et al. Lengthening of the forearm by callus distraction. *J Hand Surg [Br].* 1996;21B:151–163.
130. Kiss S, Pap K, Vizkelety T, et al. The humerus is the best place for bone lengthening. *Int Orthop.* 2008;32:385–388.
131. Paley D. Problems, obstacles, and complications of limb lengthening by the Ilizarov technique. *Clin Orthop.* 1990;250:81–104.
132. Tetsworth K, Krome J, Paley D. Lengthening and deformity correction of the upper extremity by the Ilizarov technique. *Orthop Clin North Am.* 1991;22:689–713.
133. Villa A, Paley D, Catagni MA, et al. Lengthening of the forearm by Ilizarov technique. *Clin Orthop Relat Res.* 1990;250:125–137.
134. Helferich U. Versuche über die transplantation des intermediärknorpels wachsender. *Röhrenknochen Dtsch Z Chirurgie.* 1899;51:564.
135. Haas S. The experimental transplantation of the epiphysis with observations on the longitudinal growth of bone. *JAMA.* 1915;65:1965–1971.
136. Biscard JD. Transplanted epiphyseal cartilage. *Arch Surg.* 1939;39:1028–1030.
137. Harris W, Martin R, Tile M. Transplantation of epiphyseal plates. *J Bone Joint Surg Am.* 1965;47A:897–914.
138. Donski PK, Carwell GR, Sharzer LA. Growth in revascularized bone grafts in young puppies. *Plast Reconstr Surg.* 1979;64:239–243.
139. Donski PK, O'Brien BM. Free microvascular epiphyseal transplantation: an experimental study in dogs. *Br J Plast Surg.* 1980;33:169–178.
140. Bowen CVA. Experimental free vascularized epiphyseal transplants. *Orthopedics.* 1986;9:893–898.
141. Bowen CVA, O'Brien BM. Experimental study of the microsurgical transfer of growth plates. *Can J Surg.* 1984;27:446.
142. Bowen CVA, Ethridge CP, O'Brien BM, et al. Experimental microvascular growth plate transfers. Part 1 – Investigation of vascularity. *J Bone Joint Surg Br.* 1988;70B:305–310.
143. Bowen CVA, O'Brien BM, Gumley GJ. Experimental microvascular growth plate transfers. Part 2 – Investigation of feasibility. *J Bone Joint Surg Br.* 1988;70B:311–314.
144. Nettelblad H, Randolph MA, Weiland AJ. Physiologic isolation of the canine proximal fibular epiphysis on a vascular pedicle. *Microsurgery.* 1984;5:98–101.
145. Nettelblad H, Randolph MA, Weiland AJ. Free microvascular epiphyseal plate transplantation. An experimental study in dogs. *J Bone Joint Surg Am.* 1984;66:1421–1430.
146. Manfrini M, Randolph MA, Andrisano A, et al. Orthotopic knee grafts in rats: a model for growth plate transplantation. *Microsurgery.* 1988;9:242–245.
147. Tsai TM, Ludwig L, Tonkin M. Vascularized fibular epiphyseal transfer: a clinical study. *Clin Orthop.* 1986;210:228–234. In this article, a clinical series of eight pediatric patients who underwent joint reconstruction by means of fibular epiphyseal transplant is reported. Four of the patients showed continued growth of the transplanted bone. A double-pedicled flap was described for the first time in this pioneering report.
148. Pho RW, Patterson MH, Kour AK, et al. Free vascularised epiphyseal transplantation in upper extremity reconstruction. *J Hand Surg Am.* 1988;13:440–447.
149. Zhong-Wei C, Guang-Jian Z. Epiphyseal transplantation. In: Pho RW, ed. *Microsurgical Technique in Orthopaedics.* London: Butterworths; 1988:121–128.
150. Wood MB, Gilbert A. *Microvascular Bone Reconstruction.* London: Martin Dunitz.; 1997:85–89.
151. Innocenti M, Ceruso M, Manfrini M, et al. Free vascularised growth plate transfer after bone tumor resection in children. *J Reconstr Microsurg.* 1998;14:137–143.
152. Ad-El DD, Paizer A, Pidhorts C. Bipedicled vascularized fibula flap for proximal humerus defect in a child. *Plast Reconstr Surg.* 2001;107:155–157.
153. Amr SM, el-Mofty AO, Amin SN. Further experiences with transplantation of the head of the fibula. *Handchir Mikrochir Plast Chir.* 2001;33:153–161.
154. Innocenti M, Delcroix L, Manfrini M, et al. Vascularized proximal fibular epiphyseal transfer for distal radial reconstruction. *J Bone Joint Surg Am.* 2004;86-A:1504–1511.
155. Bae DS, Waters PM, Sampson CE. Use of free vascularized fibular graft for congenital ulnar pseudoarthrosis; surgical decision making in the growing child. *J Pediatr Orthop.* 2005;25:755–762.

156. Innocenti M, Delcroix L, Romano GF, et al. Vascularized epiphyseal transplant. *Orthop Clin North Am.* 2007;38:95–101.
157. Papadopoulos NA, Weigand C, Kovacs L, et al. The free vascularized fibula transfer: long term results of wrist reconstruction in young patients. *J Reconstr Microsurg.* 2009;25:3–13.
158. Teot L, Giovannini UM, Colonna MR. Use of free scapular crest flap in pediatric epiphyseal reconstructive procedures. *Clin Orthop Relat Res.* 1999;365:211–220.
159. Mayr JM, Pierer GR, Linhart WE. Reconstruction of part of the distal tibial growth plate with an autologous graft from the iliac crest. *J Bone Joint Surg Br.* 2000;82:558–560.
160. Yang J, Qin B, Li P, et al. Vascularized proximal fibular epiphyseal transfer for Bayne and Klug type III radial longitudinal deficiency in children. *Plast Reconstr Surg.* 2015;135:157e–166e.
161. Sawaizumi M, Maruyama Y, Okaiima K, et al. Free vascularised epiphyseal transfer designed on the reverse anterior tibial artery. *Br J Plast Surg.* 1991;44:57–59.
162. Innocenti M, Baldrighi C, Menichini G. Long-term results of epiphyseal transplant in distal radius reconstruction in children. *Handchir Mikrochir Plast Chir.* 2015;47:83–89.
163. Restrepo J, Katz D, Gilbert A. Arterial vascularization of the proximal epiphysis and the diaphysis of the fibula. *Int J Microsurg.* 1980;2:48–51.
164. Bonnel F, Lesire M, Gomis R, et al. Arterial vascularization of the fibula microsurgical transplant techniques. *Anat Clin.* 1981;3:13–23.
165. Taylor GI, Wilson KR, Rees MD, et al. The anterior tibial vessels and their role in epiphyseal and diaphyseal transfer of the fibula: experimental study and clinical applications. *Br J Plast Surg.* 1988;41:451–469. *This is the first article reporting both an experimental and clinical experience in proximal fibular epiphyseal transfer based on the anterior tibial vascular system. The most remarkable finding consisted of assessing the ability of the anterior tibial artery to supply not only the proximal growth plate but also a considerable amount of fibular shaft. This improvement in the knowledge of the vascularity of the proximal fibula allowed reliable use of a fibula flap with a single pedicle.*
166. Menezes-Leite MC, Dautel G, Duteille F, et al. Transplantation of the proximal fibula based on the anterior tibial artery: anatomical study and clinical application. *Surg Radiol Anat.* 2000;22:235–238.
167. Mozaffarian K, Lascombes P, Dautel G. Vascular basis of free transfer of proximal epiphysis and diaphysis of fibula: an anatomical study. *Arch Orthop Trauma Surg.* 2009;129:183–187.
168. Stark RH, Matloub HS, Sanger JR, et al. Warm ischemic damage to epiphyseal growth plate: a rabbit model. *J Hand Surg Am.* 1987;12:54–61.
169. Innocenti M, Delcroix L, Romano GF. Epiphyseal transplant: harvesting technique of the proximal fibula based on the anterior tibial artery. *Microsurgery.* 2005;25:284–292.
170. Innocenti M, Delcroix L, Manfrini M, et al. Vascularized proximal fibular epiphyseal transfer for distal radial reconstruction. *J Bone Joint Surg Am.* 2005;87(suppl 1):237–246. *In this article, the operative technique for harvesting the proximal fibula supplied by the anterior tibial vascular system is reported in detail. A step-by-step description of the procedure is provided and supported by anatomical drawings and related clinical pictures. Recommendations and pitfalls may help the reader in approaching this reconstructive technique.*
171. Vilkkki SK. Vascularized joint transfer for radial club hand. *Tech Hand Up Extrem Surg.* 1998;2:126–137.

31

Vascular anomalies of the upper extremity

Joseph Upton III and Amir Taghinia

 Access video content for this chapter online at expertconsult.com

SYNOPSIS

- Vascular anomalies of the upper limb are divided into tumors (including hemangiomas) and malformations.
- Hemangiomas have a biphasic growth phase consisting of proliferation and spontaneous involution; malformations tend to expand slowly throughout life.
- Hemangiomas are usually treated conservatively, whereas vascular malformations can be managed by observation, sclerotherapy, embolization, and/or surgical resection.
- Surgical resections can be predictably performed if basic principles are followed; venous malformations, lymphatic malformations, and combined lesions are most amenable. Many technical refinements have made these operations safer and more predictable.
- Fast-flow lesions with or without fistulae comprise the most difficult group of lesions; their natural history is one of gradual progression.
- New discoveries in the biochemical pathways responsible for these lesions hold promise for future medical therapy.

Clinical tip

Vascular anomalies are complex problems and are best approached by a multidisciplinary team. In our center, we have a weekly conference and a separate weekly clinic where the team meets to discuss individual patients. Representatives from radiology, general (pediatric) surgery, hematology, anesthesiology, plastic surgery, dermatology, and scientists from the laboratory all attend. Other specialists such as neurosurgeons, orthopedic surgeons, oral surgeons, ophthalmologists, endocrinologists, and head and neck surgeons are called as needed. Thus, a comprehensive approach to patient care can be undertaken, with immediate availability of ultrasound imaging and expert opinion. This approach has been monumental in the correct diagnosis and treatment of hundreds of patients.

Introduction

During the past five decades, there has been a steady, almost exponential increase in our knowledge of vascular anomalies. A biological classification system has evolved and is under constant refinement.¹ A careful physical examination augmented with advanced imaging will yield an accurate diagnosis from the vast myriad of possibilities. A multidisciplinary team can offer individualized treatment with some degree of predictability. Improvements in minimally invasive radiological procedures have dramatically transformed treatment of these lesions. With discovery of biochemical agents and pathways responsible for these lesions, widening application of medical therapies show promising outcomes. However, in many patients, surgical treatment is often the best remedy and should not be viewed as the last resort. A carefully planned and well-orchestrated procedure and rehabilitation can yield remarkable outcomes.²

Classification and Overview

The etiology of vascular birthmarks has long stimulated the fertile imagination of humans. Historically, classification systems have reflected a balance between folklore and science. Well into the 19th century, the doctrine of maternal impressions dictated that a gravid mother's craving for strawberries, sight of an accident, or emotional longing could imprint a vascular blemish, a *naevus maternus*, on her unborn child.^{3,4} With the development of the microscope, a vast number of histological terms have been introduced. Despite these academic advances, most lesions are still inaccurately labeled as hemangiomas. Study of the histopathology and natural history of these lesions spawned intriguing embryological classifications,^{5,6} which seemed logical at the time but failed to distinguish involuting from non-involuting lesions and offered little guidance in management. In the late 1970s, Mulliken and Folkman proposed a working hypothesis that these cells could be distinguished by their cellular characteristics and

subsequently surgical specimens were analyzed by selected histological stains, electron microscopy, and autoradiography (uptake of tritiated thymidine into DNA). On the basis of these studies, two types of lesions were present: those that showed endothelial hyperplasia, called *hemangiomas*, and those that did not, called *malformations*. A binary schema based on biologic activity was proposed¹ and accepted by the International Society for the Study of Vascular Anomalies (ISSVA) in 1996.⁷ This system has been corroborated by both radiological studies^{8,9} and immunohistological staining.¹⁰ However, “no system is carved in stone and must be written on recyclable paper” and is in a constant state of revision. For example, the initial category of “hemangiomas” has been changed to “vascular tumors” to include all vascular tumors in all age groups. A particular vascular lesion may be moved from one category to another or may be discarded completely with expansion of clinical experience and basic science investigation. For the past 30 years, this system has been very helpful to the upper limb surgeon in the proper diagnosis and management of these lesions (Table 31.1). Most frustrating are

the large number of eponyms with and without abbreviations, which have been attached to these lesions. These terms are often used indiscriminately without specific reference to cell type, flow characteristics, and growth. Adding to the confusion is the common association of growth disturbances. Both overgrowth and undergrowth with and without dysplastic fat deposition may accompany vascular anomalies. The summary in Table 31.2 helps delineate our present state of knowledge of this nosologic quagmire. The recent discovery that somatic activating mutations in the phosphatidylinositol-3-kinase (PIK3CA)/mammalian target of rapamycin (mTOR) pathway appear to underlie a number of overgrowth phenotypes (termed PIK3CA-related overgrowth spectrum, PROS)¹¹ promises to provide some degree of molecular differentiation to these disorders.^{12–14} Table 31.2 appears online only.

A correct diagnosis impacts directly upon appropriate treatment and an incorrect diagnosis may result in unnecessary or harmful remedies. Most upper limb surgeons designate all fast-flow anomalies with or without arteriovenous fistulae as Parkes Weber syndrome (PWS). However, PWS patients comprise a very small percentage of the fast-flow group, which comprises about 15% of upper extremity fast-flow malformations.¹⁵ Not all slow-flow combined malformations should be called Klippel-Trénaunay syndrome (KTS), an eponym we reserve for combined capillary-lymphaticovenous malformation (CLVM) lesions. The venous malformation (VMs) collectively comprise the largest clinical group of patients evaluated by the hand surgeon. The majority are small lesions involving all portions of the upper limb and/or ipsilateral chest wall. Other subgroups have emerged. The diffuse VMs involving all structures within the upper limb including bone have been designated Bockenheimer lesions,¹⁶ originally described as “diffuse genuine phlebectasias”, and are not amenable to surgery with the exception of pathologic fractures and localized areas of symptomatic thromboses. Maffucci patients commonly get skeletal enchondromas but many of the skeletal lucencies may be clusters of VMs, which are also found in abundance within the soft-tissue planes.^{17,18} The glomuvenous (GVM) lesions occur in clusters with a characteristic appearance, are painful, have been localized to chromosome 1p21–22, and in the past were called glomus tumors or glomangiomas.¹⁹ They have been renamed to stress the fact that they are malformations and not tumors (as suggested by the suffix “oma”). The VMs seen in the blue rubber bleb nevus syndrome (BRBNS) also have a characteristic cutaneous appearance, are also familial and often confused with GVM, Maffucci and capillary malformations-venous malformations (CM-VM).²⁰ The associated gastrointestinal lesions, often localized to the small bowel, are often the cause of anemia and iron deficiencies (see Table 31.7).

Lymphatic malformations (LMs) often occur in combination with other vascular elements but the most common varieties are either isolated or diffuse LMs, which may involve any portion of the upper limb and/or ipsilateral chest wall.¹⁵ Lymphangiomatosis conditions are not of primary concern to the upper limb surgeon as they involve visceral organs and/or the lungs and in the long run are life endangering. Nevertheless, a microsurgical approach to treatment of central lymphatic conduction anomalies may be of some utility.²¹ LMs in the Gorham-Stout syndrome involve skeletal structure including the humerus, radius, ulna and tubular bones of the hand.²² Pathologic fractures can occur.

Table 31.1 ISSVA classification of vascular anomalies

Vascular tumors	Vascular malformations
Slow-flow vascular malformations	
Hemangioma:	Capillary malformations (CM):
Infantile hemangioma (IH)	Port-wine stain
Congenital (CH)	Telangiectasias
Non-involuting	Angiokeratoma
congenital	Venous malformations (VM):
hemangioma (NICH)	Common sporadic VM (VM)
Rapidly involuting	Blue rubber bleb syndrome
congenital	(BRBS) or Bean syndrome
hemangioma (RICH)	Glomuvenous malformation (GVM)
Hemangiomatosis	Familial cutaneous and mucosal
Pyogenic granuloma	venous malformation (VMCM)
Kaposiform	Maffucci syndrome
hemangioendothelioma	Diffuse VM (Bockenheimer)
(KHE)	Lymphatic malformations (LM):
Rare tumors:	Common lymphatic malformation
Hemangioendothelioma	(LM)
Infantile fibrosarcoma	Lymphangiomatosis
Hemangiopericytoma	Gorham-Stout syndrome
Giant cell angioblastoma	
Fast-flow vascular malformations	
	Arterial malformation (AM)
	Arteriovenous malformation (AVM)
	Arteriovenous fistula (AVF)
	Complex-combined vascular
	malformations
	CVM, CLM, LVM, CLVM (Klippel-
	Trénaunay),
	CM-AVM (Parkes Weber), AVM-LM
	Proteus, hemihypertrophy,
	capillary-lymphatic-overgrowth-
	vascular-epidermal nevus
	(CLOVE)
ISSVA, International Society for the Study of Vascular Anomalies.	


Table 31.2 Diagnostic work-up of vascular anomalies

	Clippel-Trénaunay (KT)	Parkes Weber (PW)	Lipomatous	CLOVES	Hemihypertrophy	Proteus	Maffucci
Capillary stain	Present, deep purple	Present, pink, often diffuse	Rare	Present, pink, diffuse, truncal	Uncommon	Present, pink, often diffuse	Absent (rarely reported)
Progressive overgrowth	Present	Present	Present, symmetrical	Present, often extensive	Either overgrowth or undergrowth	Absent at birth, haphazard, unrelenting, disproportional	Secondary to enchondroma growth, moderate to massive
Hemodynamics	Slow flow	Fast flow	Slow flow	Slow flow	Slow flow	Slow flow	Slow flow
Vascular anomalies	VM, LVM	AVM, AVFs	Absent	VM, LVM, LM	Absent	VM, LM, CM	VM including within bone, hand common
Associated anomalies	Common: GI, GU, genitalia Hypoplastic lymphatics Deep venous anomalies	Rare, Cobb syndrome	Absent	No visceral	Skin, CNS, heart, GU, dental, others	Cerebriform soles/palms, linear nevi, dysregulated fat, lung cysts, neoplasm, facial phenotype	None
Limb enlargement	Moderate, disproportionate digits and toes common	Arm, leg length discrepancy	Moderate, nerve-territory oriented	Moderate	Macroductily, syndactily, polyductily, club feet	Major, asymmetrical	Disproportionate
Limb affected	Upper 5%, lower 95%	Upper 23%, lower 77%	Equal	Equal	Arms, hands equally	Arms/legs, hands/feet equal	All
Skeletal changes	Unusual, can occur with large lesions	Common, direct involvement, demineralization	Common, symmetrical	Marked scoliosis, lower limb	Hip dysplasia, scoliosis, increased bone age	Skull hyperostosis, vertebral megalospondylos dysplasia	Gross distortion, asymmetry, limb length discrepancy, phalanges common scoliosis, short stature, fractures
Macroductily	Diffuse enlargement	Minimal to moderate	Moderate to gigantic	Diffuse or longer with flexion contractures	Digits longer with flexion or extension contractures	Asymmetrical, moderate to gigantic	Digits longer with asymmetrical masses, increased size due to tumors
Dysregulated fat	Present within malformation	Present	Common, entire limb and axilla	Present	Multiple lipomas	Lipomas, regional fat absence	Present occasionally
Nerve involvement	Absent	Absent	Intermittent	Intermittent	Absent, compression neuropathies with contractures	Absent	Absent

Continued

Table 31.2 Diagnostic work-up of vascular anomalies—cont'd

	Klippel-Trénaunay (KT)	Parkes Weber (PW)	Lipomatous	CLOVES	Hemihypertrophy	Proteus	Maffucci
Muscle anomalies	Displaced by VM, LVM	Displaced by malformation	Absent	Absent	Common, atavistic intrinsic and extrinsic muscles	Absent	None
Associated neoplasms	Absent	Absent	Absent	Absent	Renal, adrenal and CNS	Ovarian, parotid	Chondrosarcoma (17.5–30%), many others less frequently, ovarian, CNS
Coagulopathy	Present	Normal	Normal	Normal	Normal	Normal	None
Increased cardiac output, CHF	No	Yes	No	No	No	No	No
Clinical prognosis	Stable	Often progressive deterioration Steal phenomenon Worse with CHF or amputations	Good, related to size and weight of limb	Progressive deterioration with extensive limb involvement	Progressive contractures (flexion or extension, intrinsic)	Progressive growth of affected regions	Good with local Rx; Ollier's patients increased problems
Risks	DVT, risk increased postoperatively	Infection, CHF, gangrene	Secondary arthritis	Scoliosis, pulmonary compromise	Neoplasms: pheochromocytoma, Wilms, hepatoblastoma	Neoplasms, PE, depression	Pathologic fractures
Genetics	Unknown	Unknown	Unknown	Unknown	Unknown	Unknown	Unknown



AVF, Arteriovenous fistula; AVM, arteriovenous malformation; CHF, congestive heart failure; CLOVES, congenital lipomatous overgrowth with vascular malformations, epidermal nevi, and skeletal anomalies; CM, capillary malformation; CNS, central nervous system; DVT, deep vein thrombosis; GI, gastrointestinal; GU, genitourinary; LM, lymphatic malformation; LVM, lymphatico-venous malformation; PE, pulmonary embolism; Rx, treatment; VM, venous malformation.

There are many conditions in which vascular anomalies, *overgrowth* or *undergrowth* coexist and with our present state of knowledge, it is difficult to draw clear lines due to the increasing amounts of growth factors found in the omnipresent dysplastic fat tissue within these extremities. Often at their vascular clinic reviews, the authors encounter lesions that do not fit into any specific category and are designated as “PUVA”, for *provisionally unique vascular anomalies*. With time, this large group of “unknowns” will become more precisely defined. Several examples of recent breakthroughs in clinical diagnosis and biochemical markers include: discovery of PIK3CA^{12,13,23} in overgrowth conditions, and the identification of CLOVES syndrome (congenital lipomatous overgrowth with vascular malformations, epidermal nevi, and skeletal anomalies) as well as fibro-adipose vascular anomaly (FAVA).²⁴

Children with CLOVES present with large extremity and truncal CMs, moderate to marked overgrowth, large fatty tumors, either LMs or VMs, and epidermal nevi.^{25,26} They have characteristic upper extremity anomalies including macrodactyly, syndactyly, joint contractures, wide spade-like hands, with hyperextension/hyperabduction of the thumb. Previously, most of these cases had been called “macrodactylies”, “gigantism”, or Proteus and did not fit the criteria for the Proteus syndrome (see Table 31.2),^{27,28}

FAVA was recently described as an entity similar to but distinct from venous malformation.²⁴ This lesion is dense and does not contain large vascular channels amenable to traditional sclerotherapy or steroid injections. It usually affects muscles in the extremities. Pain is the hallmark symptom and surgical resection the only known effective treatment.

Another group of confusing lesions can be found in the fast-flow group, where all lesions should not be called Parkes Weber (PWS) anomalies. Most fast-flow lesions are easily diagnosed by their clinical characteristics, palpable bruits, shunts, and progressive growth. A small group of these children seen by the extremity surgeon may have mild hypotonia, fast-flow deeper lesions and frontal bossing. Males have a nevus on the glans of the penis. In the past they were placed in the Bannayan–Riley–Ruvalcaba syndrome (BRRS) or the Cowden syndrome. Genetic testing is diagnostic and they are now called the PTEN hamartoma-tumor syndrome (PHTS) (see Table 31.8).^{29,30} The hand surgeon may also see the capillary malformation–arteriovenous malformation (CM–AVM) syndrome, which initially appears to be an innocent CM, which are pinkish red and surrounded by a small halo. One-third of these patients may have an existing AVM and 12% may evolve into a PWS and intracranial AVMs should be considered. This condition is hereditary and is caused by a mutation in *RASA1*.^{31,32} The PWS describes a diffuse AVM of an overgrown extremity with an overlying CM.³³ In contrast to lesions with direct arterial–venous shunting (AVMs with arteriovenous fistulas [AVFs]), PWS lesions show diffuse involvement of all soft-tissue structures with fast-flow arterioles in the initial absence of large draining veins. Large shunts develop secondarily. The lower extremity is involved much more frequently than the upper limb.

Diagnosis/patient presentation


Evaluation begins with a detailed history and physical examination. In contrast to the rapid growth and slow

involution that characterize infantile hemangioma (IH), vascular malformations usually continue to grow. Although vascular malformations are by definition present at birth, many are inconspicuous and some do not appear until late childhood. Dermal ectasias, such as the relatively common capillary malformation (“port-wine stain”), are usually noted in the newborn nursery. Rarely, later in life will it become obvious that some of these capillary stains overlie a slow-flow (venous or lymphatic) anomaly or a fast-flow (arteriovenous) malformation. Venous and lymphatic malformations often coexist and may be quite insidious in their initial presentation. Venous malformations may not manifest until late childhood or adolescence; large lesions are usually obvious within the first 4–8 years of life. Fortunately, the vast majority of vascular malformations are correctly diagnosed by clinical examination alone.^{4,15,34,35} It is important to obtain baseline functional data including length and circumference of the affected and unaffected limbs early in life and to follow these children as they grow. The clinical characteristics of the more common malformations will be described with the individual case presentations.

The diagnostic work-up varies for each type of vascular anomaly (Table 31.3). Ultrasonography is the “go-to” initial radiological test for these lesions, and can easily confirm the initial distinction between a vascular tumor and vascular malformation.³⁶ In our center, the ultrasound is typically done in the clinic room with a portable machine. This diagnostic tool not only pinpoints the location of the lesion but also enables its identification as either slow-flow or fast-flow. Expensive diagnostic studies are unnecessary in the case of a diffuse or localized, asymptomatic slow-flow malformation or a small fast-flow lesion amenable to simple excision and closure. When a patient is symptomatic or if an operation is being considered for a large vascular anomaly, one should learn as much as possible about the size, extent, depth, and three-dimensional (3D) characteristics of the lesion. Magnetic resonance imaging (MRI) with contrast (gadolinium) is the “gold standard”. Fat-suppressed T1-weighted sequences with contrast will differentiate between a vascular tumor and malformation.³⁷ MRI can also help distinguish between lesions similar to VM such as FAVA²⁴ or intramuscular hemangioma (Enzinger type).³⁸

Computed tomography (CT) can be used to detect interosseous involvement or skeletal distortion caused by a vascular malformation and help delineate soft-tissue planes. Large cystic cavities in an LM are clearly depicted. New 3D rendering of both fast-flow and slow-flow malformations using CT technology provides very impressive views of the entire malformation and its relationship to neighboring soft tissue and skeletal structures. Three-dimensional rendering of computed tomography angiography (CTA) can be invaluable preoperatively. Plain radiology of the affected region provides very little information other than showing the presence of phleboliths and interosseous involvement or other skeletal distortions. Angiography has very little use in the diagnosis of slow-flow malformations, although it is indispensable in the diagnosis and assessment of fast-flow lesions.¹⁵ The angioarchitecture and 3D anatomy of the malformation can be precisely determined and the arterial suppliers and draining veins clearly identified. Indirect and direct phlebography techniques are sometimes used for diagnostic and therapeutic purposes for VM in the extremity.

Table 31.3 Vascular anomalies and overgrowth conditions

Diagnostic work-up	Condition		
	Hemangioma	CM	VM
Physical examination	++++	++++	++++
Ultrasound	+++	–	+
MRI, MRV, MRA	++	–	+++
Radiographs	–	–	++ phleboliths bone
CT	+	–	+
Angiography	–	–	–
Biopsy	+	–	+
			
	Condition		
	LM	Combined	AVM
Physical examination	++++	++++	++++
Ultrasound	+	+	+++
MRI, MRV, MRA	+++	+++	+++
Radiographs	+ bone	+ bone	+ bone
CT	+	+	+
Angiography	–	–	++
Biopsy	+	+	+
			

AVM, Arteriovenous malformation; CM, capillary malformation; CT, computed tomography; LM, lymphatic malformation; MRA, magnetic resonance angiography; MRI, magnetic resonance imaging; MRV, magnetic resonance venography; VM, venous malformation.

Treatment/surgical technique

The treatment of vascular anomalies has evolved significantly. Although many of these lesions were treated surgically in the past, advanced knowledge and minimally invasive techniques have changed our approach. Now, most of these lesions are best treated by interventional radiologists. As we further elucidate the molecular basis of vascular anomalies, medical therapy continues to improve. Examples include steroids and beta-blockers for infantile hemangioma. Moreover, sirolimus (also known as rapamycin) is being used more frequently

to treat large, difficult lesions with promising outcomes.³⁹ Despite many advancements, however, a subset of these lesions is still best treated with surgery.

Surgical treatment of vascular anomalies is not an endeavor for the timid or the arrogant (Video 31.1 ▶). A well-balanced approach that incorporates calculated risk and cautious execution is necessary – one that can only be cultivated with experience. The surgeon who devotes a practice to the treatment of these lesions is obligated to document meticulously and analyze critically – habits that will serve one well for life-long learning. Most lesions can never be absolutely eradicated. Re-expansion or recurrence is the rule, despite significant

Table 31.4 Principles of management

1. Clear explanation of surgery and complications. Give parents time to make decisions
2. Carefully planned and thorough dissection within a well-defined region
3. Meticulous hemostasis under tourniquet control, bloodless field
4. Fine instruments, magnification, good assistance
5. Judicious incision placement. Avoid dorsum of hand or digit
6. Identification of all structures, preservation tendons, joints, and nerves
7. Dissect no more than half of a digit or limb at a time
8. Avoid vascular compromise. One side at a time. One vessel intact
9. Avoidance intraneural dissections. Neuromas are a nemesis
10. Quick operating rehearsed with assistance if possible
11. Resect marginal skin. Tension free closures. Good tissue coverage
12. Thoughtful, meticulous closures. Subcuticular techniques best
13. Liberal use of drains, tissue sealants, and delayed closures
14. Appropriate early immobilization and subsequent early joint range of motion
15. Aggressive treatment of complications. Amputation of functionless extremities
16. Conscientious, regular follow-up for those with significant malformations
17. A full explanation of potential complications to parents and patients

extirpative operations. This is an important consideration in preoperative planning, patient counseling, and future interventions.

Surgical principles gain acceptance with time and must be periodically reassessed and refined, particularly in this rapidly advancing field. Principles should not be confused with techniques that change frequently, and are modulated to a great extent by technology. Many of the following surgical principles have evolved from the early operative experience with vascular malformations (especially the fast-flow types), which was punctuated with complications (Table 31.4).^{2,3}

1. *Preoperative planning* should include correlation of the size, extent, and involvement of structures with physical examination and imaging. All studies should be reviewed preoperatively; serial studies of growing children are often invaluable in demonstrating the true extent of involvement. A thorough explanation of all potential complications must be given to the patient and/or parents.
2. The surgeon should mentally *outline the extent of the resection and abide by it*. Use of the pneumatic tourniquet and complete exsanguination is necessary to visualize normal and abnormal structures clearly, regardless of the size of the malformation. Once the operative field becomes bloodstained, the identification of nerves, tendons, intrinsic muscles, and other structures is more difficult.
3. *Placement of incisions* is important – particularly in children. A high midaxial incision in the digit is preferred, as it can be used again and is hidden. With growth, palmar scars within or near the palm can lead

to contracture. If a palmar approach is chosen, a zigzag incision is preferred, utilizing existing skin creases. If multiple debulking procedures are contemplated in the upper arm or forearm, each incision should be planned carefully to avoid unnecessary scarring. The medial surface of the arm, elbow and forearm is the least conspicuous. Incisions in the weight-bearing plantar surfaces of the foot should be avoided. The placement of incisions in the medial arch, along the borders of the foot, and on the dorsal surfaces is safe. Scars in the webspaces or along eponychial and/or paronychia folds will contract and are likely to become problematic.

4. *Magnification*, either loupe or microscopic, makes a tremendous difference in the identification and preservation of normal neurovascular structures. Small vessels, such as vincular pedicles to the flexor tendons and nutrient vessels to the carpal bones, should be saved if uninvolved. Often, vascular anomalies will displace, but not typically invade, neighboring soft tissues.
5. *Avoid vascular compromise*. Only one-half of a digit should be dissected at a time (see Table 31.6). If possible, at least one or two large dorsal veins per finger should be preserved to enhance venous drainage, especially when excising a diffuse lymphatic lesion in the hand or foot. The superficial venous system should not be resected unless a deep system has been identified. When a critical arterial segment to a digit, hand, or foot is removed, this segment should be reconstructed with a vein graft so that at least one digital artery is preserved per digit and one major artery supplies the hand or foot with a functional intact palmar or plantar arch.
6. *Avoid intraneural dissection* whenever possible, despite gross involvement. Although many vascular malformations, particularly VMs and PTEN lesions, are entangled in nerves, dissection often leaves incontinuity neuromas with partial or complete loss of distal sensory or motor function. The symptoms are usually much worse than the initial ones.
7. *Avoid partial dissections within large muscle groups*. Removal of the entire muscle *en bloc* is preferred to avoid a secondary contracture of the entire musculotendinous unit. If more than half of a skeletal muscle is excised piecemeal, a secondary contracture is likely. VMs, mixed CLVMs, capillary malformation-arteriovenous malformation (CM-AVM) and lymphatico-venous malformations (LVMs) are the most problematic lesions. The best treatment for large FAVA lesions appears to be *en bloc* excision of the entire involved muscle.
8. *Replace abnormal or ischemic skin* with a skin graft or a flap. Tissue with questionable viability can be observed and resected later, if necessary. It is usually best to remove and replace skin that is heavily scarred from a previous procedure, chronically infected and ulcerated, populated by lymphatic vesicles or deprived by a proximal steal phenomenon.
9. *Drains* should be used liberally, and delayed primary closure of the wound should be considered. Persistent postoperative bleeding is usually best treated with direct pressure, elevation, and immobilization, rather

than by re-exploration. Baseline coagulation studies should be performed for large/diffuse VMs and LVMs. Liberal use of tissue sealant products is encouraged.

10. *Immobilize the operated extremity* in a young child or adolescent. In the treatment of children with vascular anomalies, the postoperative lack or loss of immobilization is the single most important cause of wound dehiscence, maceration, and chronic infection.
11. The surgeon who has the courage to treat difficult fast-flow lesions should also *be prepared to amputate a symptomatic non-functional or painful digit or extremity* following unsuccessful attempts at palliation. The reconstructive surgeon need not view amputation as a failure.
12. *Follow-up evaluation* should be performed compulsively at yearly intervals. The true extent of the lesion can never be absolutely eradicated short of an amputation. Early childhood, adolescence, and pregnancy are times when change may occur in vascular malformations due to hormonal influences. Malformations may expand dramatically during pregnancy, with use of high-estrogen anti-ovulation medication, or following trauma. Large AVMs, LMs or mixed lesions may be well tolerated as young children only to become burdensome as teenagers due to their expansion, bulk, ulceration, and appearance or steal symptoms.
13. *Give the patient and parents adequate time to make their decision.* The diagnosis and treatment of vascular anomalies is a rapidly changing field. It is important to keep both parents and patients at the appropriate age clearly informed about the natural history of their particular malformation, options for treatment and new types of therapies. These patients and parents often have questions that are not easily answered by their family physician. It is axiomatic that the surgeon provide a *clear explanation of all potential complications* and expected outcomes prior to any surgical treatment.

Clinical tips

In large lesions, it is usually best to do a staged excision. Thorough dissection limited to a specified area should be performed so that subsequent re-entry into a densely scarred bed will be unnecessary. Limited staged (but thorough) excisions are usually better than one extensive dissection that leaves behind abnormal tissue. This way, the surgeon can minimize likelihood of re-entering an area of previous dissection. For example, the digits (including the thumb) should be debulked in stages. We typically debulk one side of a digit through a midlateral incision (half of the dorsal and half of the volar surface), and return several months later to debulk the other side. A single procedure is usually best for the dorsum of the hand, wrist, and palm of the same extremity in a patient with a diffuse LM or VM. In these patients, it is usually best to start distal to minimize swelling of involved digits once the more proximal structures are debulked.

Clinical tips

Caveats of palmar dissections

Multiple technical refinements have made these dissections, once considered impossible, both predictable and safe. These are summarized in [Table 31.5](#).

Clinical tips

Caveats of thumb/digital dissections

Surgical approaches to the thumb and digit are similar to those summarized above and have become much safer with microvascular techniques. These are summarized in [Table 31.6](#).

Vascular tumors

Infantile hemangioma (IH)

Basic science/disease process

IH is usually single and involves the upper limb in 15% of cases. The median time of appearance is at age 2 weeks. When dermis is involved, the skin initially appears pink but can evolve to deep red. Deeper lesions may cause a pale, bluish discoloration ([Fig. 31.1](#)). This lesion grows very fast during the first 9 months (proliferating phase), begins to shrink by 12 months (involuting phase), and involution is complete by 5 years (involution phase) leaving residual telangiectasias, fibrofatty residuum and redundant, atrophic skin.^{34,37,40}

Diagnosis/patient presentation

Some 90% of IH diagnoses are made by history and physical examination. Handheld Doppler demonstrates fast flow. Ultrasonography shows fast flow, elevated resistance and increased venous drainage.³⁶ On MRI scans, hemangiomas are isointense on T1, hyperintense on T2, and enhance during proliferating phase. Rarely is biopsy needed. Immunostaining for GLUT1, a glucose transporter specific to IH, will differentiate this lesion.¹⁰

The majority of IH involve the head and neck, lumbosacral region, and liver. The PHACES association includes IH on the face with at least one of the following: posterior fossa brain malformation, hemangioma, arterial cerebrovascular anomaly, coarctation of the aorta and cardiac defects, eye/endocrine abnormalities, and sternal clefting or a supraumbilical raphe. These children need the appropriate specialty consultations.

Treatment/surgical technique


Most IH are managed by observation because 90% are small, localized, and do not impair function. To protect against ulceration and/or maceration during the proliferating phase, topical antibiotic cream and a petrolatum gauze barrier may be used. Ulcerated wounds are treated with local wound care and rarely need biologic coverage such as skin grafts. Those

Table 31.5 Caveats of palmar dissections

1. Anatomy complex. Have three-dimensional perspective.
2. Compulsive hemostasis under tourniquet. Avoid inkwell phenomenon.
3. Proximal to distal dissection of nerves. Look for epineural fat and follow epineural connective tissue plane.
4. Identify deep motor branch of ulnar nerve in Guyon's canal and mid-palm.
5. Median and ulnar nerves often involved. Take your time.
6. Although displaced, arterial is anatomy normal. Follow adventitial connective tissue plane. Save palmar arches.
7. Completely resect involved intrinsics to avoid contracture.
8. Try to preserve first dorsal interosseous and adductor pollicis muscles.
9. Simple muscle splitting for localized calcified thrombi.
10. Tissue sealants and drains to avoid bleeding
11. Postoperative compression of thumb and digits easy with Coban
12. Postoperative compression of palm difficult. Wrapping ineffective. Uniform pressure with vacuum-assisted closure device for open wounds or dorsal/palmar splints for closed wounds.
13. Stay within a well-defined region. Tendency to be too aggressive
14. Resect and replace marginal skin.



Diffuse VM palm




Motor branch of the ulnar nerve




Dissection complete

Table 31.6 Caveats of thumb/digital dissections


1. Anatomy much easier than palm; outline region to be debulked *before* exsanguination
2. Incisions: midaxial or midlateral, avoid zigzag incisions in glabrous skin to avoid hypertrophic scars; utilize dorsal extension creases if necessary
3. Tourniquet control: digital for distal half and regular proximal digit and thumb
4. Subdermal flap elevation 1st, deeper dissection later
5. Decompress Grayson and Cleland ligaments to identify neurovascular bundle; these structures distorted but always present
6. One side of digit (palmar and dorsal at a time; leave one bundle untouched and do not dissect more than 270° around digit.
7. Identify and dissect along paratenon of extensor; remove malformation between extensor and bone.
8. Preserve vincular vessels at joint space level and dorsal sensory branches of digital nerves: dissect along adventitial planes (arteries) and epineural plane (nerves); keep neurovascular bundle intact.
9. Complete excision of malformation; extend along vincular vessels if necessary.
10. Palmar dissection restricted to ipsilateral side of digit or thumb
11. Palmar pulp dissection: "berry pick" VM, LM, or LVM out of septal pockets and keep nerve attachments to skin intact
12. Extend dissection into palm to level of metacarpophalangeal joint and distal palmar flexion crease.
13. Tissue sealants and drains to avoid bleeding
14. Drape redundant skin over digit and release tourniquet before resection; tension free closure.
15. Postoperative compression dressing held with Coban



Diffuse VM



Ulnar neurovascular bundle



Radial neurovascular bundle



Closure




Fig. 31.1 Infantile hemangioma (IH). **(A)** This well-localized, solitary IH on the dorsal forearm has a bluish hue. **(B)** The MRI shows a multilobular, isointense lesion on T2-sequence. **(C)** Excision included extensive dorsal tenosynovectomy. **(D)** Two weeks later active extension is initiated.

that are small but cause functional problems can be injected with steroids.⁴¹

Problematic lesions too large to treat with intralesional corticosteroid injections are first managed with oral prednisone started at 3 mg/kg per day for 1 month and then tapered until it is discontinued 10–12 months later.³⁷ Complications of long-term corticosteroid therapy are well known and usually disappear with discontinuation of therapy. Recently, propranolol has been used but its efficacy and safety compared to corticosteroids is debated.^{42,43} Atenolol may have a better risk profile than propranolol, and its use is gaining substantial support.⁴⁴ Alternatively, the child may be switched to vincristine; interferon is no longer used in those under 12 months of age due to spastic diplegia.

Surgery in the upper limb (during the proliferation phase) is indicated only for problematic ulcerations or large lesions interfering with function. The particular child in Fig. 31.2 has a large, chronically ulcerated lesion that envelopes the neurovascular structures. Excision and neuroplasty through a high midaxial incision both enabled functional use of the digit and avoided secondary contracture of the digit.

After involution, the hemangioma can leave redundant skin with fibrofatty soft tissue. Though these lesions pose no functional problem, they can be unsightly. Small lesions can

be excised in one stage, whereas larger ones require a staged approach.

Congenital hemangioma

Basic science/disease process

The upper limb surgeon must be familiar with a variant known as congenital hemangioma (CH).⁴⁵ In contrast to infantile hemangioma, congenital hemangioma are rare lesions fully grown at birth that do not exhibit the proliferation and regression so typical of IH. These lesions appear differently with a red-violaceous color, coarse telangiectasias, a central pallor, and a peripheral halo. There are two variations of CH: the rapidly involuting congenital hemangioma (RICH)⁴⁶ and the non-involuting congenital hemangioma (NICH)⁴⁷ (Fig. 31.3). Both lesions are commonly seen in the extremities and have an equal sex distribution. RICH involutes rapidly after birth; 50% of the lesion is gone by 7 months and involution is complete by 14 months of age. Fibrofatty deposits are not present. NICH does not regress and persists as raised, lumpy, plaque-like lesions with a characteristic peripheral halo. A persistent fast-flow component remains unchanged.



Fig. 31.2 Infantile hemangioma (IH). (A) An expanding IH with chronic ulceration and bleeding in a 9-month-old child. (B) Excision was performed through a high midaxial incision and normal skin creases.

Diagnosis/patient presentation

Diagnosis is made by physical examination, clinical course and ultrasonography. CH lesions do not stain for GLUT1.

Treatment/surgical technique

RICH does not require operative management early in life, as it undergoes accelerated regression. Only large lesions in other parts of the body may need oral corticosteroid or second-line drug therapy. NICH may require intralesional corticosteroid injection in problematic regions of the upper limb. Large, lumpy masses within the palm of the hand, interdigital web-spaces, or those causing muscle or tendon impairment are best excised. Large lesions on the arm, forearm, and within the antecubital fossa are excised later in childhood.

Pyogenic granuloma

Basic science/disease process

Pyogenic granuloma (PG) is a solitary red papule that grows rapidly, forming a stalk. It has been called a lobular capillary hemangioma.⁴⁸ It is small with an average diameter of 6.5 mm. The male to female ratio is 2:1. It commonly involves skin and, in the upper extremity, it is most problematic on the glabrous surfaces of the digits, in nail folds (Fig. 31.4), within webspaces and flexion creases. It appears as a red papule growing on the end of a stalk. Persistent bleeding and constant ulceration are common. PG is distributed all over the body including the mucous membranes; cheeks, lips, oral cavity, eyelids and forehead. Histological examination will differentiate PG from hemangioma.⁴⁹

Diagnosis/patient presentation

Diagnosis is made by physical examination because the appearance is classic.

Treatment/surgical technique

Numerous treatments have been described for PG: curettage, shave excision, laser therapy, or excision. Complete excision is preferred in the hand and upper limb. Skin graft coverage may be necessary for large resulting defects.

Vascular malformations

Capillary malformations

Basic science/disease process

CM consists of dilated capillaries in the superficial dermis. CM is most often solitary, but has a wide range in size and may occur in any region of the extremity (Figs. 31.5A,B & 31.5C–F). With time and aging, these pink lesions will often darken and develop some fibrovascular overgrowth. They can be associated with deeper vascular lesions, both slow-flow (Klippel–Trénaunay, CLOVES) and fast-flow (Parkes Weber, CM–AVM, PTEN) (see Tables 31.2 & 31.8) and with skeletal and soft tissue hypertrophy. A CM on the face in one or more of the trigeminal nerve distributions is indicative of




Fig. 31.3 Congenital hemangioma (CH). **(A)** Extensive skin ulceration may occur during proliferation and involution. CH requires local wound care. **(B)** A non-involting congenital hemangioma (NICH) shows coarse telangiectasias, hard nodules surrounded by a peripheral halo. **(C)** A rapidly involuting congenital hemangioma (RICH) shows typical enlargement and coarse telangiectasias during infancy. **(D)** Several years later with no treatment.

Sturge–Weber syndrome.⁵⁰ These patients are at risk for seizures, retinal detachment, glaucoma, and stroke. Fig. 31.5C–F appears online only.

Diagnosis/patient presentation

Diagnosis is made by physical examination. Deeper lesions must be studied with radiographs, scans, and ultrasonography.

Treatment/surgical technique

No treatment is necessary for extremity CMs. Pulsed dye laser (585 nm) can effectively decrease the intensity of the cutaneous blush.^{51,52} Patients (including infants) are often treated

awake and with topical anesthesia. More dramatic outcomes are obtained in the head and neck region and face than in the trunk and extremities. Multiple treatments are often necessary. Outcomes in younger children are better than adults; results show 90% lightening of lesions, 50–90% improvement, and 20% minimal change. Many will re-darken with time.⁵³ Occasionally, a dark purple, overgrown extremity CM will be resected or replaced with a graft.

Lymphatic malformations

Basic science/disease process

LM results from an error in the embryonic development of the lymphatic system. Since lymphatic and venous systems have



Fig. 31.4 Pyogenic granuloma (PG). A periungual PG with typical stalk will continue to bleed unless completely removed with curettage or excision. In the young child, this must be differentiated from an unreduced Salter I injury of the distal phalanx (Seymour fracture).

a common origin, combined lymphatico-venous malformations (LVM) occur frequently.^{54,55} LM is characterized by the size of the malformed channels: microcystic, macrocystic, or combined. Most lymphatic lesions are noted at birth or within the first 2 years of life. Large macrocystic lesions may be slightly compressible and those with smaller channels are rubbery, a characteristic distinguishing feature. They do not decompress with overhead elevation. Overlying skin may appear normal, have a bluish hue or contain clear or pink vesicles. Dark vesicles are indicative of intralesional bleeding. Dermal involvement often overlies a large lymphatic lesion

and this skin may be thick and exhibit cutaneous puckering much like the *peau d'orange* skin seen in lymphedema. Cutaneous vesicles may coalesce, drain clear fluid, bleed, and lead to chronic wounds and sepsis.

LM may be located anywhere within the upper limb and is characteristically macrocystic in the cervicofacial and neck ("cystic hygroma"), mediastinum, and axilla (Figs. 31.6 & 31.7) and microcystic in the distal forearm, wrist, and hand. LMs may be accompanied by increased amounts of dysplastic fat adding to the bulk of the malformation. It is unusual for LMs to directly involve muscle tissue as they are primarily found within the subcutaneous tissue planes. The most problematic regions are within intertriginous skin folds, interdigital webspaces, nail folds and within open wounds caused by vesicle leakage.

There is no characteristic pattern of skeletal involvement with LM. The long and tubular bones of the extremities and joints are rarely affected. The eponym "Gorham disease" is used for skeletal involvement.⁵⁶ Extensive LM may be associated with skeletal disuse atrophy. Smaller lesions confined to the distal extremities can present with overgrowth of the hand or foot. LMs and combined lesions containing lymphatic components (CLVM, LVM) can progress to gigantism. Joints are rarely affected but can become severely restricted by the bulky LM (see Table 31.2).

Diagnosis/patient presentation

Some 90% of LMs are diagnosed by history and physical examination. Small, superficial lesions do not require further diagnostic work-up.³⁴ Large or deep lesions may require MRI scans to confirm the diagnosis, define the 3D characteristics



Fig. 31.5 Capillary malformation (CM) variations. (A) Solitary CM over the thenar region in a teenager; stain-darkened during the adolescent growth spurt. (B) Localized CM plus large arteriovenous malformation (AVM) with multiple arteriovenous fistulas in a young child with a palpable bruit.



Fig. 31.5, cont'd (C) CM plus overgrowth of thumb, long and ring digits in a child with CLOVES. (D) Extensive CM plus lipomatous overgrowth, syndactyly, and no skeletal overgrowth. (E) Limb of child with CM-AVM. (F) CM in an older man. Note variable effect of laser treatment on the dorsal forearm. CM darkened with cobblestone appearance during the adult years.



Fig. 31.6 Macrocystic axillary lymphatic malformation (LM) in a neonate. **(A)** This extensive LM was diagnosed by prenatal ultrasonography; child born by caesarean section. Constant fluid shifts and intralesional bleeding complicated initial management. **(B)** At 6 months, an aggressive debulking was performed with isolation and preservation of all neurovascular structures. Surgery took 6 h with a blood loss of <100 cc. A dramatic result was obtained with compression wrapping.

of the LM and plan treatment. These scans show characteristic fluid-filled spaces, multiple septations of variable thickness, hyperintense T2-weighted sequences due to water content, and slight rim enhancement following contrast administration. Diffuse enhancement is not present. Direct puncture of macrocystic lesions further delineates the architecture of the lesion prior to sclerotherapy. Large venous channels are often present and bleeding into a large macrocyst is the rule rather than the exception.⁵⁷ Ultrasonography (US) shows multiloculated macrocysts with “rim enhancement” and hypo-echoic microcystic lesions with little flow. Histologic confirmation of LM is rarely necessary. LM characteristically shows abnormally walled channels filled with eosinophilic, protein-rich fluid and collections of lymphocytes. Positive immunostaining is seen with lymphatic markers D2-40 and LYVE-1.⁵⁸

Treatment/surgical technique

LM is a benign condition, and intervention for small asymptomatic lesions is not necessary. More aggressive management is reserved for symptomatic lesions that cause pain, infection, compression neuropathies, significant deformity, or functional impairment. An infected LM within the extremity can be controlled with local wound care, oral antibiotics, and occasionally intravenous antimicrobial therapy. The rapidly advancing “wild fire” infections seen in these lesions can cause sepsis but will regress as rapidly as they progressed with appropriate treatment. Sclerotherapy is the first-line management for large, problematic macrocystic LMs. Several sclerosants have been used: doxycycline,⁵⁹ sodium tetradecyl sulfate (SDS), ethanol, bleomycin,⁶⁰ and OK-432.⁶¹ SDS is the most widely used. Ethanol has the highest complication rate and is particularly toxic to neurovascular structures (see Fig. 31.14). OK-432 is very effective but not widely available. Multiple injection sessions are required for all but the smallest lesions. Swelling, compartment syndromes and skin extravasation are the most common complications encountered in the upper limb. We prefer sclerotherapy for the macrocystic LMs primarily located in the head and neck, axilla, and proximal portions of the upper extremity. Microcystic lesions are best treated surgically.

Resection is reserved for: (1) symptomatic LM causing bleeding or fluid loss, infection, bleeding, pain, or obstruction of function; (2) lesions (microcystic) that cannot be adequately treated with sclerotherapy; and (3) small, well-localized lesions that can be resected for cure. Surgical principles and technical caveats have been outlined. The neonate in Fig. 31.6 presented a good example. Despite sclerotherapy, issues such as bleeding, fluid shifts, and metabolic derangement could not be adequately managed. Resection included a careful identification of all neurovascular structures within and beyond the brachial plexus and excision of large amounts of involved tissue. Characteristically, the LM in this baby was confined to the subcutaneous tissue planes and extended only *between* muscle groups. Staged debulking of large upper extremity LMs is much safer than large radical resections. We often start with the bulkiest chest wall, axillary, and arm regions before extending more distal into the forearm and hand (see Fig. 31.7). Areas of involved skin are preferentially removed and only one side of a forearm, wrist, hand, or digit are debulked at one operation. Flap compromise, wound dehiscence, and infection are early problems and tendon adherence, neuromas, and joint stiffness may be encountered later.

Because of its complex anatomy, the hand is the most difficult region to dissect for an LM or any other type of vascular malformation. There are very few natural fascial planes within the indurated lymphatic tissue, which may have been scarred by previous inflammation. However, smooth, areolar connective tissue planes can usually be found around both nerves and arteries and should be followed meticulously. Of all surgical principles outlined previously, limited and thorough dissection is most important for LM in the hand (see Table 31.4). In contrast to the digits and thumb, postoperative edema is almost impossible to control, and may affect joint mobility and tendon gliding. At this level, all LMs are microcystic and are accompanied by a large amount of adipose tissue, with the consistency ranging from soft to hard rubber (see Fig. 31.8B). Resection in the hand is reserved for those lesions causing functional impairment. These procedures are lengthy




Fig. 31.7 Chest wall and forearm lymphatic malformations (LM). **(A)** A rubbery, hard LM involving the entire arm and chest wall with a normal hand in a 16-month-old child. **(B,C)** Staged resections started with the chest wall where pectoralis major, latissimus dorsi, and serratus anterior muscles have been preserved. The forearm was debulked in two additional stages. **(D)** Three months postoperatively, following three operations.

and tedious. Incisions through glabrous skin must be well designed, as there is a tendency for hypertrophic scar formation, particularly when there is dermal involvement. With dorsal debulking, several large dorsal veins should be preserved in continuity with the cephalic drainage system of the forearm. Nevertheless, removal of these veins does not predictably cause venous congestion (see [Table 31.5](#)).

Dorsal LMs in the thumb and fingers are common and are the easiest in the limbs to debulk (see [Table 31.6](#)). Muscle is usually not involved, and the LM usually does not extend below or penetrate through flexor or extensor tendons. The entire dorsal area can be debulked, along with removal of one-half of any involved palmar portion in one procedure. Liposuction, even with ultrasonic technique, is not a good option because of the firm, rubbery consistency of microcystic LM and potential for injury to neurovascular structures. Involved dorsal skin should be excised and replaced by thick split-thickness or full-thickness skin grafts. Multiple digits can be debulked during one operation, and the dorsum of the hand at another stage. Midaxial incisions are preferred ([Figs. 31.8 & 31.9A–C](#)). A large dorsal vein in the hand or digit is preserved. Vincular vessels at the joint space level are preserved whenever possible. Incisions through the glabrous

surfaces of the palm or digit have a predilection for hypertrophic scarring. Intradigital commissures and webspaces must be closed in their normal configuration. Coban™ effectively controls postoperative edema with circumferential wrapping. [Fig. 31.9B,C](#) appears online only.

Outcomes, prognosis, and complications

The degree of functional gain and appearance is proportional to the extent of the malformation. The use of the pneumatic tourniquet in limb surgery significantly decreases the recurrence rate seen in the head and neck region.^{62,63} Frequency of complications such as persistent drainage, wound dehiscence, and skin loss is less than 8%; secondary neuromas and hypertrophic scarring are much more common (20%).¹⁵ With appropriate postoperative therapy and splinting, joint stiffness can be minimized. Upper extremities with large, heavy, edematous hands will always be “helping extremities” and digits with limited range of motion will never be normal due to the scar from previous surgeries and residual LM within the remaining soft tissue. However, extremities with well-localized LM can be expected to function normally following well-planned and executed surgery.



Fig. 31.8 Lymphatic malformation (LM) hand. **(A)** A 4-year-old child presented with an extensive microcystic LM of the entire forearm, wrist, and hand. The dorsum was approached through an ulnar incision with preservation of dorsal venous system, nerves, and extensor tendons. **(B)** The LM along the digits is microcystic, indurated and envelops all structures. Joint spaces are not involved. **(C)** Multiple digits and thumb are debulked during a single stage. **(D)** With continued compression wrapping and exercise, contour and function have been maintained 15 years later.

Venous malformation

Basic science/disease process

VM is the most common vascular anomaly. It is comprised of thin walls and abnormal smooth muscle cells, arranged in clumps instead of in a concentric orientation. VMs show




Fig. 31.9 Lymphatic malformation (LM) digit. **(A)** LM along the side of a digit.

gradual dilatation and expansion with time and growth.³ Although VMs are present at birth, they are not always obvious. Within the first 5–6 years of life, all but the smallest or deepest lesions will become clinically evident. Less than 10% are clinically indolent until adolescence. Approximately, 40% of all VMs involve the extremities and more than half of these involve deeper structures including muscle, bone, nerve and connective tissue planes. They grow commensurately with the child, and slowly expand during the adolescent growth spurt. VM is typically sporadic and solitary and half have a somatic mutation in the endothelial receptor TIE2.⁶⁴

VM may range from small, localized skin lesions to diffuse malformations involving all tissue planes including bones and joints. These lesions become engorged when the limb is in a dependent position and decompress when the limb is held above the level of the heart (Fig. 31.10). Most VMs are located in the subcutaneous plane superficial to the muscular fascia, but in contrast to LM, VM may involve muscles directly.⁶⁵ The majority of VMs are solitary and asymptomatic. Often they are multiloculated, incompletely decompressed




Fig. 31.9, cont'd (B) Lymphatic microcysts and small venous thromboses are studded within dysplastic adipose tissue. (C) The neurovascular bundle has been dissected with preservation vincular branches at the joint levels.




Fig. 31.10 Venous malformation (VM) hand. **(A)** In a dependent position, the hand with a diffuse VM becomes engorged; bulk and weight become a functional impediment. **(B)** Calcified phleboliths are often present. **(C)** Functional motion is impaired only by the malformation. **(D)** After elevation there is no pain, fullness, or congestion. This patient has an extensive VM involving the entire hemithorax with a large stagnant venous collecting system in the axilla. Consequently, she is on long-term anticoagulation.

with elevation, and have palpable regions of scar from previous inflammation around intralesional thrombi, which feel like small peas in a sac.

The configuration, size, and caliber of venous channels in VMs have no pattern, such as the characteristic microcystic and macrocystic cavities and channels of an LM. Large-caliber veins may be located on a digit, foot, and leg or within the axilla. Often these large, dilated, redundant draining veins of extremities place the patient at risk for clot formation and subsequent pulmonary embolism.

VMs do not progress from a slow-flow to fast-flow state; they grow (expand) commensurately with the child. Any enlargement following a partial resection represents redirection of flow into adjacent anomalous channels. There is definitely hormonal modulation with medium and large lesions. They often increase in size during the adolescent growth spurt, menses, while on anti-ovulant medication, and during pregnancy. In women who experience an exacerbation of their symptoms during pregnancy, there is no postpartum reduction to the previous size. Patients must

be followed carefully through adolescence and subsequent pregnancies.^{15,35}

Functional problems are related to the size, weight, and location of the VM. Pain and paresthesias are usually the result of local inflammation around intralesional thrombi or nerve compression, usually at the elbow, wrist, hand and/or tarsal tunnel of the foot. Areas of phlebothrombosis or local hemorrhage become swollen, firm and painful, especially when compressive garments are applied. Most symptoms are aggravated after exercise involving repetitive movements such as lifting, gripping, running, or kicking. Many VMs will be surprisingly large with minimal, if any, symptoms in young children.

Syndromes with VM

There is an emerging group of syndromes which contain VM and which have become clinically distinct (Table 31.7). Less than 20% of all VM patients will have a syndromic designation with a very specific pattern of malformation including

glomovenous malformation (GVM)^{66,67} and capillary malformation venous malformation (CMVM).⁶⁸ In the blue rubber bleb nevus syndrome (BRBNS),^{69,70} small blue nodules are present in isolation or with extensive connections. A small number of upper limb patients present with combined lymphatic-venous malformations with or without capillary staining: LVM, CLVM (Klippel-Trénaunay). Understandably, this group of lesions can be confusing but the management is similar. [Table 31.7](#) appears online only.

Complications of untreated VMs include pain, swelling, bulk, and contour deformity and psychosocial morbidity. Intralesional thromboses are the most frequent cause for pain. VM can cause leg-length discrepancy, hypoplasia due to disuse atrophy, pathologic fracture, hemarthrosis, and degenerative arthritis. VM of muscle may result in pain, weakness, fibrosis leading to joint contracture and subsequent disability.⁶⁵ Phlebothromboses within large, stagnant venous channels in the arm, axilla and ipsilateral chest wall have been the focus for pulmonary embolism. A coagulation profile should be obtained in all patients with an extensive VM, with or without capillary or lymphatic components, particularly if there is any history of bleeding, ecchymosis or hemarthrosis. High-risk patients should be placed on anticoagulation therapy (see below).

Diagnosis/patient presentation

At least 90% of VMs are diagnosed by history and physical examination. Dependent position of the anomaly will confirm the diagnosis: VM will enlarge due to reduced venous return in the extremity ([Fig. 31.10C,D](#)). Small, superficial, asymptomatic lesions require no further work-up. However, larger and/or deeper lesions should be evaluated by MRI to: (1) confirm diagnosis; (2) define the 3D extent of the lesion, and (3) plan long-term treatment. VM is hyperintense on T2-weighted sequences. In contrast to LM, VM will enhance with contrast, show phleboliths as signal voids, and may involve muscle. US may be used for some localized lesions; characteristic findings show slow-flow anechoic-hypoechoic channels separated by more solid regions of variable echogenicity. Phleboliths are hyperechoic with acoustic shadowing. Magnetic resonance venography (MRV) is helpful for large lesions of the arm, forearm, and chest wall. CT scans are used to assess skeletal VM.^{57,71} Histological diagnosis of VM is rarely necessary, but may be indicated if there is a suspicion of malignancy or if the imaging is not confirmatory. Arteriography is not helpful (see [Table 31.2](#) .

Treatment/surgical technique

Compression garments are the first-line of treatment and are used to reduce blood stagnation within the lesion, thereby reducing the chance of expansion, localized intralesional coagulopathy (LIC), phlebolith formation, and pain. Those with pain and large lesions are given daily aspirin (81 mg) to prevent clotting. Large lesions are at risk for the vicious cycle of blood stagnation, stimulation of thrombin, and conversion of fibrinogen to fibrin. Subsequent fibrinolysis results in LIC. A chronic coagulopathy can cause either thrombosis (phlebolith formation) or bleeding. Low molecular-weight heparin (LMWH) is considered for those children and adults with significant LIC or those at risk for disseminated intravascular coagulation (DIC). Those with large VMs and low fibrinogen

levels pre-sclerosis are given LMWH 14 days before and after the procedure. Anticoagulation is held for 24 h perioperatively (12 h before and after the intervention) to prevent bleeding complications. Patients who develop a serious thrombotic problem, such as a pulmonary embolus, require long-term anticoagulation or a vena caval filter.

Sclerotherapy is the next treatment option for symptomatic lesions that cause pain, functional impairment, a mass effect, or major contour problems.^{15,72} In the arm, elbow, and proximal forearm, sclerotherapy is safer and more effective than resection ([Fig. 31.11](#) ). Symptomatic regions must be specifically targeted. Although sclerotherapy reduces the size of the malformation, it generates a tremendous amount of scar and does not remove the malformation. The VM usually re-expands, and multiple sessions are invariably needed, sometimes for a lifetime. Direct puncture sclerotherapy is used for VM. Most patients are managed under anesthesia using US guidance. The most common complications are skin ulceration (10–15%), local extravasation, compartment syndrome in the arm or forearm and secondary contracture (see [Fig. 31.14A](#)).⁽¹⁵⁾ Sclerotherapy in the palm or near large nerves can result in painful neuropathy and should be avoided. [Fig. 31.11](#) appears online only.


Post-treatment monitoring is required for large lesions with an extremity surgeon on-call for problems. Large VMs of the axilla and arm contain anomalous veins too large for sclerotherapy; these should be embolized. Sclerotherapy is most effective for small and large VM in the axilla, arm, elbow, and proximal forearm where muscle may be directly involved. Surgical resection is preferred in the distal forearm, wrist, thumb, and digits, where there is little muscle tissue ([Figs. 31.12](#)  & [31.13](#)). The secondary scar generated by sclerotherapy in these regions is detrimental to nerve function, tendon and muscle gliding and joint motion. Large vascular channels respond better to sclerotherapy than small nests or clusters of VM commonly seen in GVMs or Maffucci patients. Surgical resection is preferred. We prefer to avoid sclerotherapy prior to resection, as it can cause scarring and complicate the dissection field. [Fig. 31.12](#) appears online only.

Resection is reserved for VMs that are well localized in a single muscle group (such as the intrinsic muscles of the hand), lesions with thromboses, and those causing neurologic impairment or compressive problems (see [Table 31.5](#)). In the distal extremity, resection of the entire involved muscle group is preferred, especially for a small muscle-tendon unit. Examples include the intrinsic muscles for which other muscles can substitute or the extrinsic flexors for which tendon transfers are possible. Partial resection of these small muscle-tendon units cannot be recommended; this fails to improve function. Flexion contractures followed by prolonged rehabilitation often occurs after subtotal resection of muscles. The indications for surgical resection are primarily functional, but can also be aesthetic.

The principles of treatment are summarized in [Table 31.4](#). The advantages of surgical resection in the upper extremity are: (1) a pneumatic tourniquet is used to provide a bloodless field; (2) all anatomic structures can be identified; (3) only the malformation is removed; (4) nerves, muscles, and tendons may be left injured; and (5) well-localized lesions can be completely removed. However, the recovery time is longer; the rehabilitation more difficult; and there is always a chance of local VM re-expansion in adjacent regions.

Table 31.7 Variations of venous malformations (VM)

	Common VM	BRBS	GVM	CMVM	Maffucci	Diffuse VM
Name, eponym	Venous malformation	Blue rubber bleb syndrome; bean	Glomuvenous malformation; glomangioma	Capillary malformation, venous malformation	Maffucci syndrome	Genuine phlebectasis of Bockenheimer; diffuse VM
Capillary stain	Absent	Absent	Absent	Present; involves mucous membranes; purple older	Absent	Absent
Skin appearance	Bluish discoloration, present at birth; wide distribution	Dark blue spots present at birth	Thickened and purple early; present at birth; cobblestone appearance	Skin, mucous membranes	Bluish to purple; thickened; nests and nodules	Diffuse; large, tortuous venous channels
Genetics	50% mutation in endothelial TIE2	Unknown	Mutation glomulin gene; chromosome 1 p21-22	Mutation TIE2, chromosome 9p21; possible 2nd hit mutation	Unknown	Unknown
Pattern	Sporadic; common; sexes equal	AD; sexes equal	AD; sexes equal	AD; 1% all VMs; sexes equal	Sporadic; sexes equal; rare	Sporadic; sexes equal
Hemodynamics	Slow-flow	Slow-flow	Slow-flow	Slow-flow	Slow-flow	Slow-flow
Limb affected	All parts of body	All parts of body	All parts of body	Skin, mucosa, muscle	All limbs	All limbs
Skeletal involvement	Present, unusual	None	None	None	90% hands and feet; enchondromas	Present, diffuse, pathologic fractures
Visceral involvement	Yes	Yes; particularly bowel	None	None	None	None
Pathology	Deficient smooth muscle in vessel walls; dilated vessels; thrombus formation	Similar to VM, well delineated, thin-walled dilated vessels	Cuboidal glomus cells	Similar to common VM	Similar to VM; thick spindle cells	Similar to common VM



AD, Autosomal-dominant inheritance.




Fig. 31.13 Venous malformation (VM) palm. **(A)** This 6-year-old child with a diffuse VM of the palm could not wear garments due to painful intralesional thrombi. **(B)** The coronal T2-weighted images show multiple signal voids within a diffuse, through-and-through VM. The mid-palm was most symptomatic. **(C)** The dissection begins with identification of the palmar arch (red loops) and median and ulnar nerves (yellow loops). VM contains multiple thrombi admixed with dysplastic fat. **(D)** A complete proximal-to-distal resection was completed with preservation of all neurovascular structures, flexor tendons, and lumbrical muscles, including their motor branches. **(E)** Five years later, normal sensation and motion has been maintained. VM remains but is not symptomatic.

The proximal forearm presents one of the most difficult operative fields for the extremity surgeon due to the high density of important anatomic structures in a compact space. Subcutaneous VMs are not problematic in this area. Intramuscular lesions are difficult to resect because the potential for damage to adjacent muscle and injury to the many small motor branches of the median nerve, and particularly the posterior interosseous nerve on the dorsal forearm. Localized lesions deep within the flexor pronator region are difficult to approach without damage to the wrist flexors and deep digital and thumb flexors. Sclerotherapy is the first line of treatment (see Fig. 31.11). On the dorsal surface, it is much easier to identify and decompress the radial nerve through the Arcade of Frohse; however, the risk for injury to extensively involved extensor muscle bellies is high. VMs in this region are usually diffuse and extend well beyond the fascial planes into the muscles. Commonly, VMs and other vascular anomalies

involve the dorsal interosseous system along the entire length of the interosseous membrane and may extend into the volar compartments. Surgical decompression of the cubital tunnel, radial tunnel as well as the volar side of the median nerve usually relieves neurogenic pain, which may also be secondary to bleeding, thrombophlebitis, or phleboliths within the VM. Neural wrapping with acellular dermal matrix, autogenous vein, other alloplastic materials or local uninvolved tissue is a helpful adjunct to any neuroplasty in this region.

The distal forearm, wrist, palm, thumb, and digits are more amenable to surgical extirpation because less muscle mass and more solid tendinous and neural structures occupy the region. Frequently, what appears to be a superficial lesion in the distal forearm and wrist extend deep to and through the interosseous membrane and involve the rete system. Resections in this region must be thorough, and usually includes removal of the interosseous membrane. Denervation of both




Fig. 31.11 Sclerotherapy. Radiographic studies of the vulnerable proximal third of the forearm show a venous malformation (VM), which is ideal for sclerotherapy: **(A)** Isointense to adjacent skeletal muscle on axial T1 sequence; **(B)** enhances on axial T1 plus gadolinium contrast; **(C)** shows signal voids on axial T2 representing phleboliths; **(D)** fills with direct puncture and injection of contrast; **(E)** shows small calcified phleboliths on radiographs; **(F)** has multilobulated structure with signal voids on sagittal T2 sequences.




Fig. 31.12 Venous malformation (VM) distal forearm. **(A,B)** A middle-aged man presented with carpal tunnel symptoms. Coronal T1 (above) shows a lesion with signal voids and T2 sequences (below) demonstrate enhancement, both consistent with VM. **(C,D)** Enhanced T1-weighted sequences show extension across the interosseous membrane.



Fig. 31.12, cont'd (E) Excision included the pronator quadratus muscle. **(F)** Full function returned 6 weeks postoperatively.



Fig. 31.14 Complications of interventional radiology. Intrinsic compartment releases were necessary following sclerosis of this diffuse venous malformation of the entire palm of the hand. Ethanol was used to embolize this arteriovenous malformation with a nidus within the palm. The distal portions of the thumb, index, and long digits were lost.

and anterior and posterior interosseous nerves will alleviate postoperative wrist pain (see Fig. 31.12). The median and ulnar nerves are frequently involved in this region, but intra-neural dissection is indicated only when there are symptoms. Secondary neuromas within the main nerves or their sensory branches at the wrist level can be severely disabling for both children and adult patients. A deep palmar VM commonly enlarges within the first webspace and extends along the adductor pollicis muscle beneath the first dorsal interosseous muscle. Both muscles are important in pinch and should be preserved if they are not extensively involved. Deep

dissection beneath the palmar arch will often expose the deep motor branch of the ulnar nerve (see Fig. 31.13).

What appears to be localized VM in the palm and dorsum of the hand is always much more extensive than it appears clinically. The margins of many VMs may not be evident on MRI or MRV scans. Dissection in this region is difficult and general guidelines must be strictly observed (see Table 31.5). Sclerotherapy in this portion of the hand has many potential complications due to the high concentration of neurovascular structures, gliding tendons, and delicate intrinsic muscles (Fig. 31.14).

Outcomes, prognosis, and complications

Few outcome studies are available due to the extremely variable presentation of VMs within the upper extremity and the many syndromic designations and confusion in terminology. VMs can be resected with predictable results. Early complications often beget later problems and less than optimal outcomes. Problems occur in up to 20% of patients and are seen early (swelling, hematoma, delayed wound healing, skin necrosis) or late (neuroma, scar contracture, joint stiffness). Wrist and forearm flexion contractures following partial intermuscular resections are common for proximal forearm lesions. Symptomatic neuromas develop in 35% of those who have intraneural dissections.

Arteriovenous malformation

Arteriovenous malformation (AVM) results from an error in vascular development during embryogenesis in which an absent capillary bed causes shunting of blood directly from an artery into a venous system. This shunt occurs through a direct arteriovenous connection (fistula) or abnormal feeding vessels between an artery and a vein (nidus). This observation of Halsted in 1919 may explain why these AV connections are common in the central nervous system, where apoptosis is rare.^{73,74} A number of genetic abnormalities have been described (Table 31.8). These lesions are present at birth only in one-third of patients; 15% involve the extremities. Almost 80% become clinically evident before the termination of adolescence and the natural history is one of slow progressive growth and expansion! These malformations worsen with time and are staged by the Schobinger system (Table 31.9). It is not unusual for a lesion to progress from quiescent through destructive phases. The timing of progression is not predictable when first seen. Table 31.8 appears online only.

Not all fast-flow lesions in the upper limb should be labeled as PWS. We have separated these lesions into four categories in which the arteriovenous flow is related to: (1) a direct AVM (Fig. 31.15); (2) flow through a nidus (see Figs. 31.14B & 31.19); (3) flow through a vascular tumor (see Fig. 31.17) and finally; (4) diffuse high-flow vessels perfusing all tissue planes (see Figs. 31.18 & 31.21). PWS is rare and should be restricted to the last condition.

Basic science/disease process

The cardinal features of AVM in a limb are warmth, pain, paresthesias, hyperhidrosis, and compression neuropathy. A

CM may be the only initial sign of an AVM, which may not become evident until later in childhood. Vascular thrills and bruits are not always marked. In some patients, a pulsating mass and accompanying thrill may be psychologically disturbing. Many patients seem to tolerate symptoms for a lifetime (see Fig. 31.15). AVM may be present at the dermal level. Cutaneous mottling and atrophy, progressing to ulceration, are secondary to the “steal phenomenon”, i.e., blood is shunted to the proximal portion of the limb, resulting in peripheral vascular insufficiency, usually first evident in the fingers, toes, hands, and feet (Fig. 31.16). Chronic infection, ulceration, recurrent bleeding, and intractable pain are the end-stage problems in these unfortunate patients. Paradoxical increased blood flow but decreased tissue perfusion hampers wound healing. These malformations are regional and are rarely found with associated fast-flow anomalies elsewhere in the body. Patients with an AVM involving the entire extremity and ipsilateral chest wall or those involving the entire lower extremity and pelvic region often demonstrate a positive Nicoladoni sign, a decrease in pulse rate with application of a pneumatic tourniquet to the affected extremity. A large AVM in an extremity can cause cardiopulmonary overload (Fig. 31.17 & see Fig. 31.21). Some children develop extraordinary postures to alleviate their pain (Fig. 31.18). AVMs do not cause disseminated intravascular coagulopathy. Intralesional bleeding can cause compartment compression. Bony hypertrophy and elongation are present in more than half of these affected limbs. Skeletal involvement carries an unfavorable prognosis but is not an absolute contraindication to surgical intervention. Fig. 31.18 appears online only.

Diagnosis/patient presentation

AVM can mimic other extremity malformations and there are many vascular conditions containing fast-flow malformations (see Table 31.8). Most lesions are diagnosed by history and physical examination, and fast-flow characteristics are confirmed by Doppler probe in the clinic. MRI may be obtained to: (1) confirm the diagnosis; (2) outline the true extent of the lesion; and (3) plan management. The T2-weighted sequences show tortuous, dilated, arteries and large draining veins, enhancement, and flow voids. The “nidus” is identified as a blush within the central portion of the lesion (Fig. 31.17A & see Fig. 31.19B). Magnetic resonance angiography (MRA) and CTA scans demonstrate the 3D characteristics and are preferred over angiogram by most interventional radiologists.³³ Extremity surgeons prefer angiography to show the caliber and flow dynamics of the shunts prior to any surgery.^{2,15} Anatomic abnormalities are common in the upper limb and include: giant feeding vessels; persistent interosseous vessels; corkscrew configuration of arteries; large median artery; duplicated brachial systems; and large draining veins. Palmar arches are often obliterated with active shunting, and muscle groups may be completely replaced by active AVFs. CT scans are indicated for skeletal involvement. Although critical in the evaluation of other malformations, histopathological diagnosis of AVM is rarely necessary but can be important to rule out rare malignancies such as infantile fibrosarcoma.


Treatment/surgical technique

The puzzling question with fast-flow lesions is their unpredictable natural history and rate of progression. Simple

Table 31.9 Schobinger clinical staging system

Stage I	Quiescent	AVM mimics a capillary malformation or involuting hemangioma
Stage II	Expansion	Lesion larger, warmer, throbbing with thrill or bruits
Stage III	Destruction	Stage II plus ulcers, hemorrhage, persistent pain, tissue necrosis and bone destruction
Stage IV	Decompensation	Stage III plus increased cardiac output and cardiac failure

Table 31.8 Combined and fast-flow malformations

	Parkes Weber (PWS)	Ostler-Rendu-Weber	CM-AVM	PTEN-AVM	CLM	Klippel-Trénaunay
Eponym/ name	Parkes Weber; AVM with AVF	Hereditary hemorrhagic telangiectasia (HHT)	CM-AVM	PTEN-hamartoma syndrome (PTHS) Cowden, BRRS	CLM; CM-LM confused with CLOVES	KT; CLVM
Vascular malformation	Diffuse AVM with AVFs lymphedema	CM, visceral AVMs in liver and lungs	CM –small, pink	Multiple AVMs, VM	CM, LM	CM; VM (varicose veins); LM
Skin appearance	Pseudo CM on skin lymphedema	Telangiectasia lips, fingers mucosal-nasal epistaxis	Pinkish lesion with halo	CM; possible VM bluish discoloration	CM	Capillary stain, bluish pink, vesicles, maceration
Hemodynamics	Fast-flow	Fast-flow AVFs	Fast-flow in 30%	Fast-flow AVM in 50%	Slow-flow	Slow-flow
Cardiac compromise	Common	Rare, anemia	Possible	None	None	Possible
Arteriovenous fistuli	Multiple, often aneurismal		None	Multifocal	None	None
Lateral/deep venous anomalies	None	None	None	Clusters abnormal veins	Tortuous draining veins	Common; vein of Servelle lateral arm as in leg; varicose veins
Coagulopathy	None	None	None	Unusual	None	Present
Pattern	Lower → upper extremities		Lips, intraoral	Legs>arms/hand	Extremities equal	Lower>upper extremities
Genetics	Unknown	HHT1 mutation of endoglin HHT2 mutation ALK1	Mutation <i>RASA1</i> ; positive family history	PTEN mutation	None	Unknown
Associated anomalies	Rare pelvic AVM; Cobb syndrome	AVM cerebral, spinal, liver and pulmonary	Cerebral AVM 7%	Macrocephaly; penile freckling (males); lipomas	None	Common: GI, GU, genital pelvic organs
Limb hypertrophy	Major, disproportionate osteolysis can occur	None	Absent	Absent	Uncommon; can occur	Minor to moderate
Symptoms	Warmth, pain, hypertrophy, sweating	Nasal epistaxis GI bleeding anemia	Warmth, pain, mass	Pain, mass effect; function	Cellulitis, size, bulk	Ulcers, cellulitis, weight and bulk
Venous stasis, skin ulcers	Ischemic changes; pseudo Kaposi changes	Telangiectasia ± bleeding	None	Absent	Vesicular maceration	Common
Clinical prognosis	Poor; progressive expansion	Good	Progressive with AVM	Progressive	Good	Stable; severe overgrowth common
						

AVF, Arteriovenous fistula; AVM, arteriovenous malformation; BRRS, Bannayan–Riley–Ruvalcaba syndrome; CLOVES, congenital lipomatous overgrowth with vascular malformations, epidermal nevi, and skeletal anomalies; CLVM, capillary–lymphatico-venous malformation; CM, capillary malformation; GI, gastrointestinal; GU, genitourinary; LM, lymphatic malformation.




Fig. 31.18 Parkes Weber syndrome (PWS). **(A)** A 6-year-old child with a capillary malformations (CM) of the wrist and hand, and a pulsatile mass of her distal forearm. Diagnosis of PWS was made and she was treated with a compression garment. Flexion contractures gradually developed in the wrist and all digits. **(B)** Angiogram at age 7 showed diffuse hypervascularity and multiple microfistuli without large draining veins. **(C)** Pain gradually increased as she grew. She learned to control this pain by dislocating her glenohumeral joint, a maneuver that compressed the massively enlarged subclavian artery and vein. She often slept in this position.



Fig. 31.15 Natural history of fast-flow arteriovenous malformation (AVM). **(A)** A 67-year-old adult executive complained of gradual swelling and pulsation in the hand since teenage years. Attempted surgical removal of symptomatic regions had been aborted due to excessive bleeding. **(B)** Early angiographic sequences showed large, tortuous macro-fistulous shunts involving radial and ulnar arterial systems and both palmar arches; very little flow to the distal digits.




Fig. 31.16 Fast-flow arteriovenous malformation (AVM) with steal phenomenon. **(A)** Angiogram of a 21-year-old patient who presented with an asymptomatic bruit of the wrist shows an AVM involving the radial and interosseous systems. **(B)** Inverted arteriographic images taken 20 years later show large tortuous radial and interosseous vessels leading to large aneurysms with shunting in the distal metacarpal region. **(C)** Tip discoloration of the thumb and long digit caused by steal phenomenon. Distal ischemia of the thumb will ultimately progress to tissue necrosis.




Fig. 31.17 CLOVES with arteriovenous malformation (AVM). **(A)** A 6-month-old baby was referred with large AVM of right arm and forearm, failure to thrive, and refractory cardiac failure. Arm amputation was recommended by many consultants but refused by the family. **(B)** Angiography showed nidus located at level of elbow and forearm. **(C)** Massively enlarged draining veins were encountered. Dissection proceeded toward the center of the mass. **(D)** Individual branches of axillary and brachial artery were mapped and surgically ligated. The dysplastic radial artery (red loop) was replaced with a graft; median, ulnar and radial nerves (yellow loops) were preserved despite massive stretching. **(E)** Incision healed well and patient maintained full elbow flexion/extension and sensation. There were also truncal capillary malformations, overgrowth of multiple limbs, and epidermal nevi. He was later diagnosed as CLOVES.

observation is the initial treatment in all but the most symptomatic AVMs. Compression garments may be of some help (see Fig. 31.18C). The goal of treatment is to control the progression of the malformation and to alleviate symptoms: pain, ulceration, bleeding, distal discoloration, or functional problems. Management options include embolization, surgical resection or a combination (Fig. 31.19). Surgical resection offers the best chance for long-term control, but re-expansion rate following extirpation is high and the deformity created by the resection may be significant. Radical extirpation may often create a deformity worse than the malformation itself. Amputation is the definitive cure, which may be achieved with functional limitations (see Fig. 31.21). Therefore, embolization is the first line of intervention for type A and B lesions in the Schobinger I (quiescence) or II (expansion) stages. Well-localized lesions respond better than diffuse

AVMs involving multiple tissue planes, but all lesions will re-expand to some degree, especially if the central nidus has not been obliterated.

It is important that the extremity surgeon understand the rationale of embolization, which is often used as the primary treatment for these lesions. Inert substances are injected into the nidus to obliterate the abnormal vascular channels, promote ischemia and ultimate scarring of the malformation. Substances used for this process may be liquid (ethanol, *n*-butyl cyanoacrylate (*n*-BCA), onyx or solid (polyvinyl alcohol particles, PVA), or coils of many varieties. It is critical that these materials are delivered directly to the nidus of the AVM. Obstruction of the inflow vessels is the major problem with selective embolization and will result in: (1) collateralization of vessels; (2) expansion of the malformation; and (3) aggravation of symptoms.⁷⁵ More recently, radiologists at our center




Fig. 31.19 Arteriovenous malformation (AVM) of hand. **(A)** Professional wrestler presented with painful mass in thenar eminence. Thrill first noted during adolescence. **(B)** Angiography demonstrated AVM nidus at superficial palmar arch, supplied by radial, interosseous and ulnar vessels. Distal digital and thumb arterial vaso-architecture was normal. Embolization performed with *N*-butylcyanoacrylate (NBCA). **(C)** Post-embolization study showed obliteration of most of AVM with residual large draining veins. **(D)** Two days after embolization, the mass was explored: yellow vessel loops mark recurrent motor branch and multiple sensory branches of the median nerve. **(E)** All nerves, flexor tendons, and uninvolved thenar muscles were preserved during resection. **(F)** Five years later, he continues to demonstrate good function. Palmar abduction is present (abductor pollicis muscle), but key pinch is weak due to subtotal loss of the adductor pollicis muscle.

have focused on obliteration of the outflow in high-flow lesions that have only a few large outflow venous channels. This approach has shown promising results but longer-term studies are needed to corroborate initial findings.

For temporary preoperative embolization, Gelfoam powder, PVA, and Embosphere are used instead of liquid agents. Over the past decade, our interventional radiologists have preferred onyx, an ethylene-vinyl alcohol copolymer. At the time of resection, the embolized tissue with its attendant inflammation will have a mass effect, which facilitates

resection. Excision should be completed within 36–72 h post-embolization, before recanalization restores blood flow to the region of the lesion. The major complications to embolization are skin ulceration, local compartment syndrome, and rarely, distal ischemia (see Fig. 31.14B). Extremity surgeons must be available following these procedures in interventional radiology.

Resection is indicated whenever the AVM leads to chronic ulceration or bleeding, compartment compression, nerve compression, uncontrolled congestive heart failure (CHF),

gangrene, or unrelenting pain. The procedure must be tailored to the patient's needs. In all but the most localized lesions, resection for AVM in a limb is palliative. The surgeon who undertakes resection of an AVM in a limb must have specific objectives that can be accomplished during a safe tourniquet time. The general principles of treatment outlined earlier for slow-flow anomalies also apply to fast-flow anomalies (see Table 31.4). Problems arising during these procedures can get out of control; these are well known to all surgeons who have written about operating on these anomalies. Dramatic outcomes can be achieved with a well-planned and executed procedure (Fig. 31.20). There is no predictable procedure that when performed in childhood will prevent subsequent expansion of an AVM, short of a limb amputation. In few other areas of hand surgery is careful explanation of potential complications so important. Amputation of a very symptomatic, almost parasitic part is encouraged. Severe pain and bleeding are often the precipitating symptoms (Fig. 31.21). Figs. 31.20 and 31.21 appear online only.

The same anatomic concerns outlined with the slow-flow malformations apply to this group of very dynamic lesions. Nerves and tendons should be preserved. Heavily involved muscle groups should be resected. Revascularization of the hand, digit or thumb should be performed if both axial vessels have been excised. Similarly, marginal skin requires resection and appropriate resurfacing.

PTEN-associated vascular anomaly (PTEN-AVA)

Basic science/disease process

The PTEN (phosphatase and tensin homologue) gene encodes a tumor suppressor lipid phosphatase.²⁹ Children with these PTEN mutations have the PTEN hamartoma-tumor syndrome (PHTS). This is an autosomal-dominant condition, which in the literature has previously been called the Cowden syndrome or the Bannayan–Riley–Ruvalcaba syndrome (BRRS).^{30,76} The PTEN mutation is associated with multiple benign and malignant tumors that require surveillance.

Males and females are equally affected. The lower extremities, especially the thighs and calf musculature, are involved much more frequently than the upper extremities, where the arm and forearm regions are more involved than the wrist and hands. Half (54%) of these patients have fast-flow malformations with arteriovenous shunting and are designated PTEN-AVA. These children have distinctive macrocephaly; males have penile freckling and these masses can be large and multiloculated. Large amounts of adipose tissue surround the shunts and the mass effect of the affected limb may result in functional compromise. The lesions directly involve the muscles, surround neurovascular tissues, and extend within intramuscular fascial planes. Bone is usually not involved. Lesions may grow to massive proportions.

Diagnosis/patient presentation

The diagnosis is made by physical examination and imaging (Fig. 31.22), and confirmed by histological and genetic analysis. Histology shows tortuous arteries with mural hyperplasia. Fig. 31.22 appears online only.

Treatment/surgical technique

Although sclerotherapy has been used to control large tortuous veins and isolated clusters, surgical resection is the definitive treatment of choice. Extirpation may be more difficult if prior sclerotherapy has been performed. Resections in the arm, forearm, and hand often involve microvascular dissections of involved neurovascular structures.

Parkes Weber syndrome (PWS)

PWS is an eponym denoting a fast-flow malformation in association with soft tissue and/or skeletal overgrowth and overlying CM.^{32,33} The term is incorrectly used in its association with KTS and should not be used to describe all fast-flow lesions within the extremities.

Basic science/disease process

No genetic foci or mutations have been identified to date.

Diagnosis/patient presentation

The diagnosis is made by physical examination and ultrasound. The lower extremity is involved much more frequently than the upper. Diffuse or localized CMs are often present; other skin changes include pseudo Kaposi lesions, lymphedema, and skin ulceration late in the progression of the malformation. Lymphedema is common. The angiograms in a classic PWS do not initially show specific AVFs with large draining veins. These early studies show diffuse high-flow vessels infiltrating the involved soft-tissue and skeletal structures without large draining veins so characteristic of shunts. The CM is often diffuse and irregular and covers the region of underlying hypervascularity (Fig. 31.21) & see Fig. 31.18). PWS should be distinguished from other fast-flow lesions: PTEN-AVA, other vascular tumors, AVM with AVFs, and CM-AVM. MRI, MRA, ultrasound, and biopsy are warranted with an increase in symptoms. The clinical prognosis is one of progressive expansion and destructions. Fig. 31.21 appears online only.

Treatment/surgical technique

Management is identical with the indications and principles previously presented for fast-flow lesions. Initial treatment is always conservative, but these children should be followed through adolescence and adulthood. Symptomatic regions respond to selective embolization. Cardiac compromise may be insidious; cardiologists must evaluate these children yearly. Regional resections are warranted for selective cases but must be carefully planned and executed with the realization that these lesions are often progressive. Amputation of non-functional digits, hands, and arms is usually delayed; pain is often the precipitating factor for an amputation. Experience has taught us that amputations of parasitic parts is often unnecessarily delayed either by the reluctant surgeons or anxious parents with unrealistic expectations.

Outcomes, prognosis, and complications

Children must be monitored both for cardiac symptoms and overgrowth issues. The progress may be slow and not predictable early in life. All patients have some degree of pain,





Fig. 31.20 Arteriovenous malformation (AVM) with arteriovenous fistuli of thumb. **(A)** A 60-year-old man presented with pulsatile bleeding from excoriated regions of his right thumb. He first noted swelling as a young child, and lived with periodic bleeding and ulceration his entire life. **(B)** Arteriography showed extensive macro-fistulous AVM involving radial side of his dominant hand. **(C)** Congenital absence of his left hand made him completely dependent on right upper limb. **(D)** Following resection of scarred and unstable pulp surface and debulking entire thumb, resurfacing accomplished with neurovascular island flap from ulnar side of long finger. **(E)** Flap extended to nail plate distally and included entire working pulp surface of thumb. **(F)** This grateful patient has a stable functional thumb, which he perceives is on ulnar side of the long finger.




Fig. 31.21 Parkes Weber syndrome. **(A,B)** Teenager with type C arteriovenous malformation, and his parents wanted to save the hand. Index ray had been resected for uncontrollable pulsatile bleeding. The thumb was ulcerated; patient was suicidal because of unrelenting pain. **(C)** Angiography showed massively tortuous and enlarged axial vessels feeding microfistulous shunts within forearm and hand with involvement of all soft-tissue and skeletal structures. **(D)** Later sequence demonstrates extent of shunting and lack of distal digital perfusion. **(E)** Chest radiograph and electrocardiogram confirmed congestive heart failure (Schobinger Stage IV). **(F)** Below-elbow amputation followed by predictable recovery, normal adolescent growth spurt, and good function with his prosthesis.




Fig. 31.22 High-flow PTEN lesion of the forearm. **(A)** This teenager has a large lesion of the forearm but has very little to no functional deficit. **(B)** Sagittal T2-weighted MRI images show the extensive nature of the lesion that involves the entire volar forearm down to the interosseous membrane. **(C)** PTEN lesions densely surround and involve large nerves. In this case, the median nerve is completely involved (white arrow), although the patient does not have any nerve symptoms at this point.

swelling, overgrowth, and nerve compression at some anatomic level. Selective embolization successfully controls symptoms in 70% of patients. We have never documented regression of this type of malformation.

Capillary malformation–arteriovenous malformation (CM–AVM)

Basic science/disease process

This is an autosomal-dominant condition caused by a loss-of-function mutation in the *RASA1* gene.^{31,33} Patients usually present with a positive family history of similar lesions.

Diagnosis/patient presentation

The CM is evident by physical examination and is distinguished by a faint halo around the lesion. We have seen these in the upper extremity. Almost 10% of patients have an underlying fast-flow AVM involving the central nervous system, a very frequent location for AVMs. A full neurologic examination is indicated with a cranial MRI. Extracranial AVMs are rare in patients. Lesions are common in the lips or mouth.

Treatment/surgical technique

No treatment is necessary for the upper extremity CM. AVMs are followed symptomatically and treated as previously outlined.

Klippel–Trénaunay syndrome (KTS)

KTS is an eponym denoting a slow-flow capillary–lymphaticovenous malformation designated as CLVM and is readily distinguished from PWS by the slow-flow dynamics of the malformation.

Basic science/disease process

No positive genetic associations have been made.

Diagnosis/patient presentation

An accurate physical examination will determine the presence of both lymphatic and venous components, as the CM is obvious at birth. There is a wide range in clinical presentation.^{77–79} There are no major hemodynamic alterations in the cardiovascular system. The lower extremities (95%) are involved much more frequently than the upper (5%) and the trunk and pelvis are rarely affected. The limb hypertrophy is not as profound as in patients with the Proteus syndrome, CLOVES syndrome, or in hemihypertrophy patients. However, upper limb involvement may be accompanied by massive soft-tissue enlargement of not only the upper limb but also the chest wall. In 10% of these limbs, hypoplasia may be present. Kyphoscoliosis and pulmonary compromise often develop as the child grows. Leg-length discrepancy is common. KTS patients are not at risk for Wilms tumors and do not need to be screened with abdominal ultrasound examination.⁸⁰ The VM pattern is similar to phlebectasias with large draining veins in the arm and axilla. There are usually diffuse clusters of large veins and sinuses involving muscle, fascial planes, and occasionally bone. All forms of LM may

be present including skin vesicles, coalesced vesicles causing maceration and ulcers, macrocysts in the proximal portion of the upper limb, and microcysts in the more distal regions. All lesions are accompanied by large amounts of adipose tissue. Occasionally VM predominate; the upper limb equivalent of the lateral “vein of Servelle” is present and does communicate with the deep venous drainage system along the axial vessels to the limb. Because the genitourinary and gastrointestinal systems are commonly involved, these patients may be very symptomatic. Similar to the foot, massive enlargement of the wrist and hand with splaying of the digits with or without ulnar deviation may occur.

Treatment/surgical technique

Management is initially conservative and depends upon the predominance of the venous or lymphatic components. Management of the venous components is initially conservative. Epiphysiodesis to control bilateral growth symmetry is not as essential in the arm as it is in the lower extremity. Nerve compressions and lymphatic components respond very well to surgery. Surgical principles are the same. In the upper limb, resection is performed to improve function, relieve compression neuropathies, and restore motion and contour. Those with large lesions, chest wall involvement and those with large stagnant venous collecting systems in the arm and axilla are at risk for pulmonary embolus and are maintained on anticoagulants. Staged contour resections are difficult but well worth the effort.

Outcomes, prognosis, and complications

Clinical outcomes vary with the size and extent of the LVM and are similar to those for large isolated VMs and LMs. Outcome studies for upper limb KTS patients do not exist.

CLOVES syndrome

Congenital lipomatosis overgrowth, vascular malformations, epidermal nevi, and scoliosis syndrome (CLOVES) constitutes the components of a recently described overgrowth condition.^{12,25,26,28} This disease entity has been linked to somatic activating mutations in the *PIK3CA* gene.^{11,12,25}

Basic science/disease process

The upper extremity is usually involved. Previously, many of these children were diagnosed as Proteus patients but did not satisfy the criteria for inclusion. CLOVES patients do not have uncontrolled progressive skeletal overgrowth, and the soft-tissue enlargement consists primarily of dysplastic adipose tissue. Truncal CMs are present in all patients. Patients may also have fast-flow AVMs (see Fig. 31.17). Overgrowth in the limb is similar to that seen with LMs. It may or may not be oriented along a nerve territory (see Table 31.2).

Typical upper extremity findings include polydactyly, syndactyly, macrodactyly, and stiffness. Fatty overgrowth may extend proximally to the hand and forearm. Many patients have a large, spade-like hand (Fig. 31.23), an appearance that is accentuated when there is fatty overgrowth in the palm. In about half of these patients, the thumb is positioned in a hyperextended and hyper-abducted posture (see Fig. 31.22). Fig. 31.23 appears online only.




Fig. 31.23 Right and left hands in a patient with CLOVES syndrome. These pictures and radiographs demonstrate the prototypical CLOVES hands. Splaying of the digits with overgrowth and stiffness of one or more digits is common. In this patient, **(A and B)** the left thumb is hyperabducted to an extreme, lying directly opposite of the index finger. The lesions on the dorsum of the right hand **(C and D)** are subcutaneous lymphatic malformations.

Diagnosis/patient presentation

Diagnosis is based on clinical findings and starts with physical examination. Imaging can be tailored to specific areas as involvement with multiple different kinds of vascular anomalies is not uncommon. Differential diagnosis includes multiple overgrowth syndromes but differentiation based on clinical findings is usually possible. Guidelines for genetic PIK3CA testing have been recently proposed.¹¹

Treatment/surgical technique

Resection of the lipomatous component, staged debulking and appropriate epiphysiodesis of the forearm and hand are predictable and useful for the individual patient. Skeletal angulation and rotation at all levels are corrected with osteotomies. For massively overgrown digits that are non-functional, the surgeon should consider amputation to allow better function for the rest of the hand.

Fibro-adipose vascular anomaly (FAVA)

FAVA is a recently described vascular malformation that appears in skeletal muscle in the extremities.²⁴ Long-term

experience is lacking in this entity mainly because it was not recognized until recently.

Basic science/disease process

Most FAVA cases involve the leg. In the upper extremity, the forearm is most commonly involved. Small lesions involve portions of muscle whereas larger ones can involve an entire muscle or muscle group. The hallmark clinical finding in this lesion is pain that is worsened with activity. Contractures are common in larger lesions as more muscle is involved.

Diagnosis/patient presentation

Lesions appear similar to venous malformations on MRI but have larger fat and soft-tissue components. These lesions replace normal muscle fibers with fibrofatty overgrowth and phlebectasia (dilation of veins). Similar findings are noted on gross specimens. On histology, lesions show dense fibrous tissue, fat, and lymphoplasmacytic aggregates within atrophied skeletal muscle. There can be large, irregular, and sometimes excessively muscularized venous channels and smaller, clustered channels.




Fig. 31.24 Fibro-adipose vascular anomaly (FAVA) of forearm. **(A)** A 12-year-old female with a large painful lesion of the entire volar forearm and progressive flexion contractures of the wrist, thumb, and digits. **(B)** MRI post-contrast images show extensive involvement of the flexor-pronator mass. **(C)** Intraoperative view after excision of the lesion. The median nerve is involved. The mass was hard and densely infiltrated with fibro-adipose tissue and clusters of phlebectasia. **(D)** Reconstruction was performed with tendon transfers and free functional gracilis muscle transfer. **(E)** Postoperative view.

Treatment/surgical technique

Sclerotherapy, cryotherapy, and steroid injections have not been effective in treating this lesion. Pain may be relieved temporarily, but usually recurs. Surgical therapy is the only measure that provides long-lasting pain relief and improvement of contractures. Unfortunately, it usually involves resection of the involved muscle tissue – which can cause loss of function. In smaller lesions, functional compromise is less likely. In larger lesions of the forearm (e.g., those that involve most of the flexor/pronator mass) we have relied on local tendon and free muscle (gracilis) transfers to replace diseased muscle. The excision procedure is done in one procedure and the free tissue transfer several days later (Fig. 31.24).

Future directions

Since the last publication of this chapter, several exciting breakthroughs have been made in the molecular and clinical understanding of these lesions. These have been referenced liberally throughout the chapter and include discovery of somatic mutation in PIK3CA¹² and the mTOR^{11,39} pathway as responsible for several overgrowth disorders, delineation of the fibro-adipose vascular anomaly that mainly affects the extremity (FAVA),²⁴ and further understanding in the molecular basis of other vascular anomalies.⁸¹ There has been increasing use of mTOR inhibitors (rapamycin) to treat difficult, large malformations and early results have been promising with a tolerable adverse-effect profile. Nevertheless, there has been

variability in response, and additional work is needed to better understand these lesions and reasons why some respond better than others. More basic science breakthroughs are inevitable and they promise better understanding and improved patient outcomes.



Access the bonus content for this chapter online at

<http://www.expertconsult.com>

Fig. 31.5 (C) CM plus overgrowth of thumb, long and ring digits in a child with CLOVES. **(D)** Extensive CM plus lipomatous overgrowth, syndactyly, and no skeletal overgrowth. **(E)** Limb of child with CM–AVM. **(F)** CM in an older man.

Fig. 31.9 (B) Lymphatic microcysts and small venous thromboses are studded within dysplastic adipose tissue. **(C)** The neurovascular bundle has been dissected with preservation of vascular branches at the joint levels.

Fig. 31.11 Sclerotherapy. Radiographic studies of the vulnerable proximal third of the forearm show a venous malformation (VM), which is ideal for sclerotherapy.

Fig. 31.12 Venous malformation (VM) distal forearm.

Fig. 31.18 Parkes Weber syndrome: a 6-year-old child with a capillary malformations of the wrist and hand, and a pulsatile mass of her distal forearm.

Fig. 31.20 Arteriovenous malformation with arteriovenous fistuli of thumb.

Fig. 31.21 Parkes Weber syndrome: teenager with type C arteriovenous malformation, and his parents wanted to save the hand.

Fig. 31.22 High-flow PTEN lesion of the forearm.

Fig. 31.23 Right and left hands in a patient with CLOVES syndrome. These pictures and radiographs demonstrate the prototypical CLOVES hands.

Table 31.2 Diagnostic work-up of vascular anomalies.

Table 31.7 Variations of venous malformations.

Table 31.8 Combined and fast-flow malformations.



Access the complete reference list online at

<http://www.expertconsult.com>

- Mulliken JB, Glowacki J. Hemangiomas and vascular malformations in infants and children: a classification based on endothelial characteristics. *Plast Reconstr Surg.* 1982;69:412–422. *This classic article helped clarify the delineation between hemangiomas and vascular malformations. The classification is based on histologic differences in the tissue; these endothelial characteristics are correlated with the natural history of hemangiomas vs. vascular malformations.*
- Upton J, Taghnia A. Special considerations in vascular anomalies: operative management of upper extremity lesions. *Clin Plast Surg.* 2011;38:143–151.
- Kurek KC, Luks VL, Ayturk UM, et al. Somatic mosaic activating mutations in PIK3CA cause CLOVES syndrome. *Am J Hum Genet.* 2012;90:1108–1115.
- Upton J, Coombs CJ, Mulliken JB, et al. Vascular malformations of the upper limb: a review of 270 patients. *J Hand Surg.* 1999;24:1019–1035. *This is a large series of patients with vascular malformations of the upper limb. The diagnosis and treatment of various types is reviewed in retrospective fashion.*
- Alomari AI, Spencer SA, Arnold RW, et al. Fibro-adipose vascular anomaly: clinical–radiologic–pathologic features of a newly delineated disorder of the extremity. *J Pediatr Orthop.* 2014;34:109–117. *Delineates a new anomaly termed fibro-adipose vascular anomaly, FAVA.*
- Sapp JC, Turner JT, van de Kamp JM, et al. Newly delineated syndrome of congenital lipomatous overgrowth, vascular malformations, and epidermal nevi (CLOVE syndrome) in seven patients. *Am J Med Genet A.* 2007;143A:2944–2958. *This is a presentation of the recently described CLOVES syndrome.*
- Tan W-H, Baris HN, Burrows PE, et al. The spectrum of vascular anomalies in patients with PTEN mutations: implications for diagnosis and management. *J Med Genet.* 2007;44:594–602.
- Parkes Weber F. Right-sided hemihypertrophy resulting from right-sided congenital spastic hemiplegia with a morbid condition of the left side of the brain revealed by radiogram. *J Neurol Neurosurg Psych.* 1922;37:301–311.
- Upton J, Mulliken JB, Murray JE. Classification and rationale for management of vascular anomalies in the upper extremity. *J Hand Surg.* 1985;10:970–975.
- Van der Horst CM, Koster PH, de Borgie CA, et al. Effect of the timing of treatment of port-wine stains with the flash-lamp pumped pulsed-dye laser. *N Engl J Med.* 1998;338:1028–1033. *Treatment of flat capillary vascular malformations is optimally treated with the flash-lamp pumped pulsed-dye laser. This is because the wavelength of hemoglobin is targeted. This article discusses optimal dosing and timing of treatment.*

References

- Mulliken JB, Glowacki J. Hemangiomas and vascular malformations in infants and children: a classification based on endothelial characteristics. *Plast Reconstr Surg*. 1982;69:412–422. *This classic article helped clarify the delineation between hemangiomas and vascular malformations. The classification is based on histologic differences in the tissue; these endothelial characteristics are correlated with the natural history of hemangiomas vs. vascular malformations.*
- Upton J, Taghinia A. Special considerations in vascular anomalies: operative management of upper extremity lesions. *Clin Plast Surg*. 2011;38:143–151.
- Mulliken JB, Young A. *Vascular Birthmarks: Hemangiomas and Malformations*. Philadelphia, PA: W.B. Saunders; 1988.
- Mulliken JB, Burrows PE, Fishman SJ, eds. *Mulliken and Young's Vascular Anomalies: Hemangiomas and Malformations*. 2nd ed. New York, NY: Oxford University Press; 2013.
- Malan E, Puglionisi A. Congenital angiodysplasias of the extremities. I. Generalities and classification; venous dysplasias. *J Cardiovasc Surg (Torino)*. 1964;5:87–130.
- Malan E, Puglionisi A. Congenital angiodysplasias of the extremities. II. Arterial, arterial and venous, and haemolymphatic dysplasias. *J Cardiovasc Surg (Torino)*. 1965;6:255–345.
- Enjolras O, Mulliken JB. Vascular tumors and vascular malformations (new issues). *Adv Dermatol*. 1997;13:375–423.
- Meyer JS, Hoffer FA, Barnes PD, et al. Biological classification of soft-tissue vascular anomalies: MR correlation. *AJR Am J Roentgenol*. 1991;157:559–564.
- Takahashi K, Mulliken JB, Kozakewich HP, et al. Cellular markers that distinguish the phases of hemangioma during infancy and childhood. *J Clin Invest*. 1994;93:2357–2364.
- North PE, Waner M, Mizeracki A, et al. GLUT1: a newly discovered immunohistochemical marker for juvenile hemangiomas. *Hum Pathol*. 2000;31:11–22.
- Keppler-Noreuil KM, Rios JJ, Parker VER, et al. PIK3CA-related overgrowth spectrum (PROS): diagnostic and testing eligibility criteria, differential diagnosis, and evaluation. *Am J Med Genet A*. 2015;167:287–295.
- Kurek KC, Luks VL, Ayturk UM, et al. Somatic mosaic activating mutations in PIK3CA cause CLOVES syndrome. *Am J Hum Genet*. 2012;90:1108–1115.
- Rios JJ, Paria N, Burns DK, et al. Somatic gain-of-function mutations in PIK3CA in patients with macrodactyly. *Hum Mol Genet*. 2013;22:444–451.
- MacLellan RA, Luks VL, Vivero MP, et al. PIK3CA activating mutations in facial infiltrating lipomatosis. *Plast Reconstr Surg*. 2014;133:12e–9e.
- Upton J, Coombs CJ, Mulliken JB, et al. Vascular malformations of the upper limb: a review of 270 patients. *J Hand Surg*. 1999;24:1019–1035. *This is a large series of patients with vascular malformations of the upper limb. The diagnosis and treatment of various types is reviewed in retrospective fashion.*
- Kubiena HF, Liang MG, Mulliken JB. Genuine diffuse phlebectasia of Bockenheimer: dissection of an eponym. *Pediatr Dermatol*. 2006;23:294–297.
- Lewis RJ, Ketcham AS. Maffucci's syndrome: functional and neoplastic significance. Case report and review of the literature. *J Bone Joint Surg Am*. 1973;55:1465–1479.
- Kaplan RP, Wang JT, Amron DM, et al. Maffucci's syndrome: two case reports with a literature review. *J Am Acad Dermatol*. 1993;29(Pt 2):894–899.
- Boon LM, Mulliken JB, Enjolras O, et al. Glomuvenous malformation (glomangioma) and venous malformation: distinct clinicopathologic and genetic entities. *Arch Dermatol*. 2004;140:971–976.
- Fishman SJ, Smithers CJ, Folkman J, et al. Blue rubber bleb nevus syndrome: surgical eradication of gastrointestinal bleeding. *Ann Surg*. 2005;241:523–528.
- Fishman SJ, Burrows PE, Upton J, et al. Life-threatening anomalies of the thoracic duct: anatomic delineation dictates management. *J Pediatr Surg*. 2001;36:1269–1272.
- Hirayama T, Sabokbar A, Itonaga I, et al. Cellular and humoral mechanisms of osteoclast formation and bone resorption in Gorham-Stout disease. *J Pathol*. 2001;195:624–630.
- Luks VL, Kamitaki N, Vivero MP, et al. Lymphatic and other vascular malformative/overgrowth disorders are caused by somatic mutations in PIK3CA. *J Pediatr*. 2015;166:1048–1054, e1–5.
- Alomari AI, Spencer SA, Arnold RW, et al. Fibro-adipose vascular anomaly: clinical–radiologic–pathologic features of a newly delineated disorder of the extremity. *J Pediatr Orthop*. 2014;34:109–117. *Delineates a new anomaly termed fibro-adipose vascular anomaly, FAVA.*
- Sapp JC, Turner JT, van de Kamp JM, et al. Newly delineated syndrome of congenital lipomatous overgrowth, vascular malformations, and epidermal nevi (CLOVE syndrome) in seven patients. *Am J Med Genet A*. 2007;143A:2944–2958. *This is a presentation of the recently described CLOVES syndrome.*
- Alomari AI. Characterization of a distinct syndrome that associates complex truncal overgrowth, vascular, and acral anomalies: a descriptive study of 18 cases of CLOVES syndrome. *Clin Dysmorphol*. 2009;18:1–7.
- Carty MJ, Taghinia A, Upton J. Overgrowth conditions: a diagnostic and therapeutic conundrum. *Hand Clin*. 2009;25:229–245.
- Bloom J, Upton J. CLOVES syndrome. *J Hand Surg*. 2013;38:2508–2512.
- Marsh DJ, Coulon V, Lunetta KL, et al. Mutation spectrum and genotype–phenotype analyses in Cowden disease and Bannayan-Zonana syndrome, two hamartoma syndromes with germline PTEN mutation. *Hum Mol Genet*. 1998;7:507–515.
- Tan W-H, Baris HN, Burrows PE, et al. The spectrum of vascular anomalies in patients with PTEN mutations: implications for diagnosis and management. *J Med Genet*. 2007;44:594–602.
- Eerola I, Boon LM, Mulliken JB, et al. Capillary malformation-arteriovenous malformation, a new clinical and genetic disorder caused by RASA1 mutations. *Am J Hum Genet*. 2003;73:1240–1249.
- Parkes Weber F. Right-sided hemihypertrophy resulting from right-sided congenital spastic hemiplegia with a morbid condition of the left side of the brain revealed by radiogram. *J Neurol Neurosurg Psych*. 1922;37:301–311.
- Revenu N, Boon LM, Mulliken JB, et al. Parkes Weber syndrome, vein of Galen aneurysmal malformation, and other fast-flow vascular anomalies are caused by RASA1 mutations. *Hum Mutat*. 2008;29:959–965.
- Finn MC, Glowacki J, Mulliken JB. Congenital vascular lesions: clinical application of a new classification. *J Pediatr Surg*. 1983;18:894–900.
- Upton J, Mulliken JB, Murray JE. Classification and rationale for management of vascular anomalies in the upper extremity. *J Hand Surg*. 1985;10:970–975.
- Paltiel HJ, Burrows PE, Kozakewich HP, et al. Soft-tissue vascular anomalies: utility of US for diagnosis. *Radiology*. 2000;214:747–754.
- Mulliken JB, Fishman SJ, Burrows PE. Vascular anomalies. *Curr Probl Surg*. 2000;37:517–584.
- Allen PW, Enzinger FM. Hemangioma of skeletal muscle. An analysis of 89 cases. *Cancer*. 1972;29:8–22.
- Fogel AL, Hill S, Teng JMC. Advances in the therapeutic use of mammalian target of rapamycin (mTOR) inhibitors in dermatology. *J Am Acad Dermatol*. 2015;72:879–889.
- Kilcline C, Frieden IJ. Infantile hemangiomas: how common are they? A systematic review of the medical literature. *Pediatr Dermatol*. 2008;25:168–173.
- Couto JA, Greene AK. Management of problematic infantile hemangioma using intralesional triamcinolone: efficacy and safety in 100 infants. *J Plast Reconstr Aesthetic Surg JPRAS*. 2014;67:1469–1474.
- Lawley LP, Siegfried E, Todd JL. Propranolol treatment for hemangioma of infancy: risks and recommendations. *Pediatr Dermatol*. 2009;26:610–614.
- Frieden IJ, Drolet BA. Propranolol for infantile hemangiomas: promise, peril, pathogenesis. *Pediatr Dermatol*. 2009;26:642–644.
- Ábarzúa-Araya A, Navarrete-Dechent CP, Heusser F, et al. Atenolol versus propranolol for the treatment of infantile hemangiomas: a

- randomized controlled study. *J Am Acad Dermatol*. 2014;70:1045–1049.
45. Boon LM, Enjolras O, Mulliken JB. Congenital hemangioma: evidence of accelerated involution. *J Pediatr*. 1996;128:329–335.
 46. Berenguer B, Mulliken JB, Enjolras O, et al. Rapidly involuting congenital hemangioma: clinical and histopathologic features. *Pediatr Dev Pathol*. 2003;6:495–510.
 47. Enjolras O, Mulliken JB, Boon LM, et al. Noninvoluting congenital hemangioma: a rare cutaneous vascular anomaly. *Plast Reconstr Surg*. 2001;107:1647–1654.
 48. Mills SE, Cooper PH, Fechner RE. Lobular capillary hemangioma: the underlying lesion of pyogenic granuloma. A study of 73 cases from the oral and nasal mucous membranes. *Am J Surg Pathol*. 1980;4:470–479.
 49. Patrice SJ, Wiss K, Mulliken JB. Pyogenic granuloma (lobular capillary hemangioma): a clinicopathologic study of 178 cases. *Pediatr Dermatol*. 1991;8:267–276.
 50. Thomas-Sohl KA, Vaslow DF, Maria BL. Sturge-Weber syndrome: a review. *Pediatr Neurol*. 2004;30:303–310.
 51. Van der Horst CM, Koster PH, de Borgie CA, et al. Effect of the timing of treatment of port-wine stains with the flash-lamp pumped pulsed-dye laser. *N Engl J Med*. 1998;338:1028–1033. *Treatment of flat capillary vascular malformations is optimally treated with the flash-lamp pumped pulsed-dye laser. This is because the wavelength of hemoglobin is targeted. This article discusses optimal dosing and timing of treatment.*
 52. Jasim ZF, Handley JM. Treatment of pulsed dye laser-resistant port wine stain birthmarks. *J Am Acad Dermatol*. 2007;57:677–682.
 53. Huikeshoven M, Koster PHL, de Borgie CAJM, et al. Redarkening of port-wine stains 10 years after pulsed-dye-laser treatment. *N Engl J Med*. 2007;356:1235–1240.
 54. Wigle JT, Oliver G. Prox1 function is required for the development of the murine lymphatic system. *Cell*. 1999;98:769–778.
 55. Sabin F. On the origin of the lymphatic system from the veins and the development of lymph hearts and thoracic duct in the pig. *Am J Anat*. 1902;1:367–389.
 56. Gorham LW, Stout AP. Massive osteolysis (acute spontaneous absorption of bone, phantom bone, disappearing bone); its relation to hemangiomatosis. *J Bone Joint Surg Am*. 1955;37:985–1004.
 57. Choi DJ, Alomari AI, Chaudry G, et al. Neurointerventional management of low-flow vascular malformations of the head and neck. *Neuroimaging Clin N Am*. 2009;19:199–218.
 58. Florez-Vargas A, Vargas SO, Debelenko LV, et al. Comparative analysis of D2-40 and LYVE-1 immunostaining in lymphatic malformations. *Lymphology*. 2008;41:103–110.
 59. Burrows PE, Mitri RK, Alomari A, et al. Percutaneous sclerotherapy of lymphatic malformations with doxycycline. *Lymphat Res Biol*. 2008;6:209–216.
 60. Alomari AI, Karian VE, Lord DJ, et al. Percutaneous sclerotherapy for lymphatic malformations: a retrospective analysis of patient-evaluated improvement. *J Vasc Interv Radiol JVIR*. 2006;17:1639–1648.
 61. Smith MC, Zimmerman MB, Burke DK, et al. Efficacy and safety of OK-432 immunotherapy of lymphatic malformations. *Laryngoscope*. 2009;119:107–115.
 62. Padwa BL, Hayward PG, Ferraro NF, et al. Cervicofacial lymphatic malformation: clinical course, surgical intervention, and pathogenesis of skeletal hypertrophy. *Plast Reconstr Surg*. 1995;95:951–960.
 63. Saijo M, Munro IR, Mancier K. Lymphangioma. A long-term follow-up study. *Plast Reconstr Surg*. 1975;56:642–651.
 64. Limaye N, Wouters V, Uebelhoer M, et al. Somatic mutations in angiopoietin receptor gene TEK cause solitary and multiple sporadic venous malformations. *Nat Genet*. 2009;41:118–124.
 65. Hein KD, Mulliken JB, Kozakewich HPW, et al. Venous malformations of skeletal muscle. *Plast Reconstr Surg*. 2002;110:1625–1635.
 66. Brouillard P, Boon LM, Mulliken JB, et al. Mutations in a novel factor, glomulin, are responsible for glomuvenous malformations (“glomangiomas”). *Am J Hum Genet*. 2002;70:866–874.
 67. Brouillard P, Ghassibé M, Penington A, et al. Four common glomulin mutations cause two thirds of glomuvenous malformations (“familial glomangiomas”): evidence for a founder effect. *J Med Genet*. 2005;42:e13.
 68. Vikkula M, Boon LM, Carraway KL, et al. Vascular dysmorphogenesis caused by an activating mutation in the receptor tyrosine kinase TIE2. *Cell*. 1996;87:1181–1190.
 69. Oranje AP. Blue rubber bleb nevus syndrome. *Pediatr Dermatol*. 1986;3:304–310.
 70. Bean WB. *Blue Rubber-Bleb nevi of the Skin and Gastrointestinal Tract. Vascular Spiders and Related Lesions of the Skin*. 1st ed. Springfield, IL: Charles C Thomas; 1958:17–185.
 71. Burrows PE, Laor T, Paltiel H, et al. Diagnostic imaging in the evaluation of vascular birthmarks. *Dermatol Clin*. 1998;16:455–488.
 72. Burrows PE, Mason KP. Percutaneous treatment of low flow vascular malformations. *J Vasc Interv Radiol JVIR*. 2004;15:431–445.
 73. Halsted WS. Congenital arterio-venous and lymphatico-venous fistulae. Unique clinical and experimental observations. *Proc Natl Acad Sci USA*. 1919;5:76–79.
 74. Liu AS, Mulliken JB, Zurakowski D, et al. Extracranial arteriovenous malformations: natural progression and recurrence after treatment. *Plast Reconstr Surg*. 2010;125:1185–1194.
 75. Wu IC, Orbach DB. Neurointerventional management of high-flow vascular malformations of the head and neck. *Neuroimaging Clin N Am*. 2009;19:219–240.
 76. Eng C. PTEN: one gene, many syndromes. *Hum Mutat*. 2003;22:183–198.
 77. Baskerville PA, Ackroyd JS, Lea Thomas M, et al. The Klippel-Trenaunay syndrome: clinical, radiological and haemodynamic features and management. *Br J Surg*. 1985;72:232–236.
 78. Samuel M, Spitz L. Klippel-Trenaunay syndrome: clinical features, complications and management in children. *Br J Surg*. 1995;82:757–761.
 79. Jacob AG, Driscoll DJ, Shaughnessy WJ, et al. Klippel-Trénaunay syndrome: spectrum and management. *Mayo Clin Proc*. 1998;73:28–36.
 80. Greene AK, Kieran M, Burrows PE, et al. Wilms tumor screening is unnecessary in Klippel-Trenaunay syndrome. *Pediatrics*. 2004;113:e326–e329.
 81. Couto JA, Vivero MP, Kozakewich HPW, et al. A somatic MAP3K3 mutation is associated with verrucous venous malformation. *Am J Hum Genet*. 2015;96:480–486.

32

Peripheral nerve injuries of the upper extremity

Simon Farnebo, Johan Thorfinn, and Lars B. Dahlin

 Access video content for this chapter online at expertconsult.com

SYNOPSIS

- Nerve regeneration after injury is orchestrated by delicate processes in neurons, non-neural cells, and other cells at various levels from the periphery to the central nervous system.
- The clinical effects of a nerve injury include not only impaired sensory and motor function, but also symptoms such as impaired dexterity, sensitivity to cold, and pain. Therefore, they have a severe impact on activities of daily living.
- Correct diagnosis and classification of the injury are crucial for appropriate treatment.
- The surgical approach and technique, as well as timing of surgery, are factors of importance for outcome.
- The type of injury, condition of the wound, and the vascularity of the wound bed are key factors influencing surgical decision-making.
- Various techniques for nerve repair are described, including epineurial, fascicular, and end-to-side repair, and techniques for nerve reconstruction.
- Factors of importance for outcome, such as age, delay before repair, and level of injury are discussed, as are means of evaluation after surgery.

Introduction

A nerve injury may have a profound impact on the patient's activities of daily living, with subsequent effects on professional life and leisure time.¹ Patients may have to change profession, or be left with a permanently impaired ability to work. Nerve injuries may, therefore, generate not only costs for society within the healthcare system for treatment and rehabilitation, but also outside the healthcare system resulting from lost production.² Nerve injuries most commonly affect the upper extremity. The incidence of injuries to the hand has been calculated as 7–37/1000 inhabitants/year in Europe.³ Similar data are available for children (incidence 2.7/1000 children/year). Most hand injuries are minor, but injuries to

the nerves (accounting for about 3% of hand injuries) usually impair hand function.^{3,4} Few reports exist about the specific incidence of nerve injuries, but the incidence has been reported to be 13.9/100 000 person/year.⁵ Most of the injuries to the hand (10%) and the wrist (63%) required less than a week in hospital. However, few inpatient and outpatient data have been reported. The incidence of a digital nerve injury is estimated to be 6.2/100 000 inhabitants/year. The general pattern of distribution of both hand and nerve injuries between the sexes is that it is usually young (median age 29 years) men (up to 75%) who are injured. The incidence of a radial nerve injury associated with a fracture of the shaft of the humerus is around 0.12/10 000 inhabitants and year.⁶ Based on these reports one may estimate that 70 000 and 29 000 patients in the European Community and in the US, respectively, injure a nerve trunk annually.

The costs of treatment and rehabilitation, including those for loss of production, after a nerve injury, may be substantial. The costs for injuries to a median and an ulnar nerve are roughly 70 000 USD and 45 000 USD, respectively²; 87% of these costs are the result of lost production. Costs are higher for patients with coexisting tendon injuries (≥ 4 tendons). In addition, costs within the healthcare sector are higher for patients who had to change jobs after the injury and in patients in whom both the median and the ulnar nerves were injured. Up to 69% of patients with an ulnar or median nerve injury are back in full-time work by 1 year after the nerve injury.^{2,7,8} Age is one important factor for outcome after nerve repair,^{2,9} which is probably based on better cerebral adaptation to the injury, particularly in young children. The clinical effects of a nerve injury include not only subjective impaired sensory and motor functions, but also subjective complaints, such as impaired dexterity, cold sensitivity, and pain¹⁰; thus, it can have a severe impact on activities of daily living. Altogether, nerve injuries can cause considerable problems for individual patients and costs for society. In the present chapter, the principles for repair and reconstruction of nerve injuries are outlined, with emphasis on the fact that such injuries should be treated promptly.

Basic science and natural history

Anatomy

Gross anatomy: the upper extremity

The brain and the spinal cord (central nervous system) are connected to targets by the peripheral nervous system, which consists of cranial nerves, spinal nerves with roots and rami, and peripheral nerve trunks with the peripheral components of the autonomic nervous system. The anterior and posterior nerve roots (that emerge from rootlets attached to the spinal cord) merge into the spinal nerve, where the anterior primary rami form the brachial plexus in the upper extremity (Fig. 32.1). The posterior primary ramus runs posteriorly, and supplies the muscle and skin of the posterior part of the neck and trunk; it does not enter the extremity. The anterior primary rami of the cervical nerve roots C5–8 and the ramus of T1 form the brachial plexus, from which the upper extremity receives its innervation through various branches.

C5–6 roots form the upper trunk of the brachial plexus, C7 forms the middle trunk, and C8–T1 form the inferior trunks. These trunks divide into anterior and posterior divisions in which the lateral and medial cords are formed from the anterior division, while the posterior divisions form the posterior cord, which mainly innervates the extensor muscles in the upper extremity. In contrast, the lateral and medial cords innervate the flexor muscles in the extremity. The musculocutaneous nerve originates from the lateral cord. The median nerve is formed by the joining of the lateral and medial cords, whereas the ulnar nerve branches from the medial cord

together with the medial cutaneous nerves to the arm (brachial) and forearm (antebrachial). The radial and axillary nerves originate from the posterior cord. There is a segmental pattern of sensory and motor innervation (Fig. 32.2).

The anatomy of the plexus and the nerve trunks may vary considerably from person to person. Variations are seen in the forearm, where a “Martin Gruber” anastomosis may be found in as many as 15%, particularly between the anterior interosseous nerve and the ulnar nerve. A similar anastomosis may also be present more distally – Riche–Cannieu (branch between the motor branch of the ulnar nerve and the thenar branch of the median nerve in the thenar region in the hand: Fig. 32.3).

The neuron and supporting cells

The cell bodies of the motor and sensory neurons are located in the spinal cord and in the dorsal root ganglia, respectively, with their axons extending out to their respective targets in the periphery. The sensory neuron is pseudo-unipolar, with one branch of the axon extending into the posterior part of the spinal cord. The transition from the central to the peripheral nervous system takes place in the rootlets (or less often, in roots of the nerves) of the transitional zone, which are almost cone-shaped.¹¹ In the central part, the neurons are surrounded by oligodendrocytes and astrocyte processes, whereas in the peripheral nervous system axons are closely associated with Schwann cells. In myelinated nerve fibers, each axon is embraced by a series of continuous Schwann cells that create the myelin sheath. The border between individual and enwrapping Schwann cells is called the node of Ranvier (Fig. 32.4). Each nerve fiber is enclosed in a basal lamina (or basement membrane). In contrast, several thinner axons run in troughs in one Schwann cell – non-myelinated nerve fibers. The diameter of nerve fibers varies, and extends from 0.4 to 1.25 μm (non-myelinated) and from 2 to 22 μm (myelinated).¹² The number of nerve fibers also varies with nerve trunks. In addition, the number of nerve fibers decreases with age: as many as 26% of the nerve fibers may disappear between the second and eighth decades.

The nerve trunk

A number of nerve fibers are enclosed in bundles around which there are flattened supporting cells and layers of collagen that form the perineurium. These bundles of fibers surrounded by the perineurium are called fascicles, which are embedded in loose connective tissue (called epineurium); this is composed of collagen fibers and fibroblasts (Figs. 32.4 & 32.5). The space inside the fascicles is called the endoneurial space, in which the pressure is slightly positive (endoneurial fluid pressure); it consists of collagen fibrils, and cells such as fibroblasts and occasional macrophages and mast cells. Lymphocytes (CD4+ and CD8+) and macrophages are not generally found in the endoneurium (except after injury), but may be present in the epineurium. The amount of connective tissue varies among nerve trunks, and also within the same nerve trunk. More abundant connective tissue is therefore located in the nerve trunk at sites where extra protection is needed (such as joints and superficial nerve trunks). The term “mesoneurium” refers to the additional loose areolar tissue that is




Fig. 32.1 The anterior and posterior nerve roots, which emerge from rootlets attached to the spinal cord.




Fig. 32.2 The origin of the nerves of the brachial plexus (C5–Th1, top), and their target muscles.

located superficially to the epineurium. This tissue allows for the gliding of the nerve trunk (excursion) during movements of the extremity.

There is topographical segregation of fascicles and nerve fibers in the nerve trunks, particularly in their peripheral parts.^{13,14} The latter anatomical feature permits dissection of a bundle of fascicles that can be used in nerve transfers.

Blood supply

Nerve trunks receive their blood supply from segmental blood vessels (Fig. 32.6), which branch into plexuses in the epineurium, perineurium, and in the endoneurial space. The blood vessels inside the fascicles consist mainly of capillaries, which are provided by circulation through blood vessels that pierce the perineurium obliquely. The epineurial blood vessels are more susceptible to trauma than the endoneurial vessels and so epineurial edema develops more easily than endoneurial edema. Because of the extensive reserve capacity of the

intraneural blood supply, it is possible to mobilize a nerve over an extended length without disturbing the blood supply. In addition, the blood vessels adjacent to the nerve trunks have a coiled appearance that allows excursion of the nerve trunk. In addition to the vasa nervorum, there are also nervi nervorum, such as free nerve endings in the epineurium, perineurium, and endoneurium.

Physiology

To allow for propagation of the action potential, ions are exchanged between the axon and the extracellular space at the nodes of Ranvier (see Fig. 32.4). As this exchange occurs only at the nodes of Ranvier in myelinated nerve fibers, the conduction velocity jumps from node to node. In myelinated nerve fibers this saltatory conduction induces high conduction velocity. In contrast, the propagation of impulses is more continuous in non-myelinated nerve fibers. After a nerve has been injured, the process of Wallerian degeneration (see




Fig. 32.3 An anatomical preparation of the Riche–Cannieu anastomosis in the palm. This highly variable, although common, anastomosis between the median nerve motor branch and the deep ulnar nerve provides a potential pathway for enormous variation in intrinsic muscle innervation.




Fig. 32.6 Principal blood supply of nerve segment, highlighted in red.

below) takes some time in humans, which explains why it is possible to record propagation of an impulse in an injured nerve by electrical stimulation at neurography for many days after the injury. It is generally agreed, therefore, that neurography should be done no earlier than 3–4 weeks after the injury if signs of degeneration are to be found.

The cytoskeleton of the axon contains neurofilaments and centrally located microtubules. Essential molecules are transported along the microtubules both from the cell body down to the periphery (anterograde) and from the periphery up to the cell body (retrograde) with energy-dependent axonal transport. This transport has several functions, such as recycling of materials that are not used in the periphery, provision of membrane constituents, neurotransmitters, and necessary cytoskeletal components to the axon. Transfer of important molecules is essential for survival and signaling, both in the normal state and after nerve injury. After cellular injury, these signals are rapidly initiated from the environment by translation into intracellular messengers or commenced in the axon at the site of injury. These changes involve profound alterations in transcription, translation, and post-translational processes in the cells after the injury.

Degeneration and regeneration

After a nerve injury, deep and intense processes are initiated in the injured neurons and their axons and in the non-neuronal cells, particularly the Schwann cells. In the cells a number of temporary and spatially orchestrated mechanisms guide survival and regeneration. In addition, there are mechanisms that lead to apoptosis of the cells. The signal transduction processes are not clarified, and this is a target of intense research. After the peripheral nerve trunk has been injured by transection or avulsion, the proximal part of the axon is resealed to form a new surface on the tip of the axon – a process that is influenced by the presence of calcium. There is usually a slight retraction of the proximal axon, which is related to the number of injured Schwann cells. At the tip of the axon, signals are formed in the signal transduction processes and transferred to the nucleus of the neuron where the functions are changed from maintenance to survival and growth.

The distal nerve segment

Schwann cells are extremely important for the function of the peripheral nerve, both in the normal state and after injury. After injury, there is disintegration of the axons and the myelin sheath in the distal nerve segment, the latter released by Schwann cells. It is important to remove myelin and




Fig. 32.4 Close-up of myelinated axon and the node of Ranvier.




Fig. 32.5 Schematic presentation of a peripheral nerve. Colors for identical structures are the same as in Fig. 32.4.

the disintegrated axon to allow and prepare a conducive environment for the regenerating axons. Both macrophages and Schwann cells can therefore contribute to the cleaning up mechanisms, where their relevance varies over time.

The timing of nerve repair is of crucial importance for a successful outgrowth of axons after injury,^{15,16} which can be related to a large number of factors that are up- and down-regulated by Schwann cells after nerve injury. After the Schwann cells have been activated, they proliferate along the inside of their basal lamina, and form the bands of Büngner.

Neurotrophic factors and their receptors are upregulated in Schwann cells after injury, and these may include neurotrophins (such as nerve growth factor and brain-derived neurotrophic factor), fibroblast growth factors (such as β -fibroblast growth factor), neuropoietic cytokines (such as ciliary neurotrophic factor and leukemia-inhibitory factor), and other groups of factors, such as insulin-like growth factor, transforming growth factor, and interleukins.

Apoptosis (programmed death) of various cells, such as macrophages and Schwann cells, an event that is initiated by release of pro-apoptotic molecules from the mitochondria (intrinsic pathway), can be activated through the death cell surface receptors (extrinsic pathway; like Fas and tumor necrosis factor receptor 1). The number of apoptotic Schwann cells in the distal nerve segment is increased if the transected nerve is repaired after a delay.¹⁷

All these changes in the injured neuron and its axon and in the Schwann cells have the common goal of regrowth of the axons into the distal nerve segments down to their targets. Regrowth is a delicate process in which numerous sprouts emerge from the distal part of each axon. On the tip of each sprout there is a growth cone, which is formed as a small hand on which the “finger-like” filopodia palpate the environment with the purpose of finding guidance structures (Fig. 32.7). Intricate mechanisms direct rate and direction of extension of the growth cones, where actin filaments are polymerized and organized.^{18,19} Microtubules are polymerized in the growth cones. The growth is a dynamic process, where the filopodia/growth cone is repulsed or attracted depending on the local mechanisms and the structure of the environment.

The extracellular matrix is extremely important for the outgrowth and advancement of the growth cone. Proteins, such as laminin, fibronectin, galactins, tenascin, and collagens, stimulate outgrowth. Laminin exerts its stimulatory effect through cell surface glycoproteins called integrins, which interact with the intracellular actin in the growth cone and in the filopodia, thus navigating outgrowth of the axon. Precise knowledge about how axons grow and how growth is directed is still limited.

Diagnosis and presentation

Formal classification of injury

Nerve injuries can be divided into two main groups: those that will temporarily block nerve conduction without loss of axonal architecture, and those with severe damage that will result in axonal degeneration distal to the injury (Fig. 32.8). This may be one useful clinical way of approaching nerve injuries, but more formal classifications have been presented to describe the complexity of the lesions further, in particular the Seddon classification,²⁰ in which injuries were divided into




Fig. 32.7 As the nerve is severed (A), activated macrophages and Schwann cells will immediately start the removal of myelin and remnants of the disintegrated axon, to allow for a conducive environment for the regenerating axons (B). Within just a few hours numerous sprouts emerge from the distal part of each axon and form the sprout growth cone that will guide the regeneration process distally (C), until nerve regeneration is complete (D).

three groups of increasing severity (neuropraxia, axonotmesis, and neurotmesis). This classification was modified by Sunderland²¹ and by Mackinnon²² to include six degrees of injury. In Table 32.1 we summarize the differences between the three classifications, and the specific neural changes are illustrated in Fig. 32.9.

Neuropraxia

First-degree injury

In neuropraxia there is a physiological block of conduction, but no disruption of the neural architecture at the site of injury, and there are no degenerative changes within the nerve. The pathogenesis is most often external compression, surgical traction, or local ischemia. Complete recovery is the general rule, and the healing time can vary from a few days to 3–4 months. Tinel’s sign is not present over the site of injury.

Axonotmesis

Second-degree injury

In second-degree injuries, true degeneration of axons is initiated. Axonal damage leads to distal (Wallerian) degeneration, although the basal lamina of the Schwann cells remains intact. The axons regenerate through their own endoneurial tubes by axonal contact and guidance of the regenerating growth cones at a rate of 1–3 mm/day. No topographical mismatch will occur, and the integrity of sensory and motor nerve fibers remains intact. Tinel’s sign is present, and the progress of recovery can be followed by the gradual recovery of motor




Fig. 32.8 Schematic flowchart of neuronal response to nerve compression and interruption of axonal continuity.

Table 32.1 Comparison between the Seddon, Sunderland, and MacKinnon classifications of nerve injury

Seddon	Sunderland	MacKinnon	Description
Neuropraxia	1		Local physiologic block with paralysis but no anatomic disturbance of the nerve. Full recovery is expected
Axonotmesis	2		Nerve injury with degeneration of the distal segment. Intact endoneurium and perineurium. Full recovery occurs at rate of 1.5 mm/day
	3		Endoneurial damage with subsequent scarring and incomplete regeneration. Variable recovery
Neurotmesis	4		Nerve damaged with complete internal structural disorganization. Nerve trunk remains intact. No functional recovery unless operative intervention
	5		Nerve trunk cut completely. Early operative intervention necessary for restoration of some function
		6	Mixed nerve injury

or sensory function distal to the injury. Full recovery is expected.

Third-degree injury

In a third-degree injury, the architecture within the perineurium is disrupted together with axonal damage. The fascicles

remain intact, although progression of axonal regrowth will be with less precision as the axonal guidance is impaired and mismatch of fibers will occur. Axonal mismatch follows to a larger extent in proximally based injuries as the fascicular organization is usually of mixed motor and sensory patterns. The clinical outcome is hard to predict, mainly because of subsequent intrafascicular scarring and the failure of some




Fig. 32.9 Schematic of damaged structures within an axon according to the classification of Sunderland grades 1–5. Change in color (red) and pattern indicates damage to each structure. Yellow represents an axon and its neuron.

axons to regenerate. Tinel's sign is present and progresses distally with recovery. Microsurgical resection and grafting may not be beneficial in these cases.

Neurotmesis

Fourth-degree injury

In a fourth-degree lesion, the epineurium is intact, but all other parts of the nerve are damaged. The formation of an intraneural scar impairs both axonal regeneration and reinnervation, and typically forms a neuroma at the site of injury. A more profound retrograde neuronal effect than in a third-degree injury is expected, and this causes a higher incidence of neuronal death. Tinel's sign is usually present over the site of the injury, but there are no signs of recovery, or proximal-to-distal progression of regeneration. The injury requires complete excision of the neuroma and microsurgical nerve repair, usually with nerve grafting.

Fifth-degree injury

In a fifth-degree injury, the nerve is completely transected. Recovery of function is dependent on surgical repair, with or without nerve grafting. These injuries are most commonly associated with injuries that include the surrounding structures, such as tendons, muscles, bones, or blood vessels.

Sixth-degree injury

The sixth-degree injury was added by Mackinnon to take account of mixed injuries,²² for example those that occur after closed traction damage to a nerve, or gunshot or stab wounds that cause partial injuries to a nerve. This type of injury is often referred to as a neuroma in continuity, in which all degrees of nerve injury, from normal to neurotmesis, may coexist within the scarred nerve. A neuroma in continuity typically results from failure of the regenerating nerve growth cone to proceed beyond the injury to reach its peripheral targets. It occurs within an intact nerve with continuity in response to internally damaged axons and fascicles, resulting in a distal portion of the nerve that no longer, more or less, functions properly. Surgical exposure is often necessary and intraoperative electrodiagnostic studies can help to distinguish fascicles with signs of recovery from those without (grades IV and V).

Clinical examination

A correct diagnosis is crucial. Confirmation of a nerve injury is usually not hard, even though every nerve injury is unique in its character and highly variable in its symptoms. Lack of active movement, such as against resistance, because of paralysis of the muscles supplied by the nerve, can be seen immediately after the injury if the nerve is completely transected. However, when motor defects are minor or overshadowed by more striking sensory deficits, the diagnosis can sometimes be overseen, particularly in an incoherent patient. The patient's history and understanding of the mechanism of the injury are therefore important for the evaluation of the injury and identification of those that will be improved by operation. It is important that every patient with a

dysfunctional nerve and a wound overlying the course of a nerve is regarded as having a transected nerve until proved otherwise (Fig. 32.10).

Functional evaluation

Motor and sensory function should be carefully examined and documented in all patients with injured extremities. Motor evaluation should include pinch and grip strength, and assessment of weakness and atrophy of individual muscles. Sensory function should be evaluated with the patient unable to see what the examiner is doing. Acutely, it may be easy to assess the patient's ability to feel pain, such as that applied by forceps, in the innervation area of an individual nerve such as a digital nerve. Assessment of two-point discrimination and the patient's ability to separate sharp and blunt objects for testing of protective sensation can also be used. Loss of sympathetic function, with vasomotor and sudomotor paralysis, gives the loss of ability to produce sweat in the innervated segment of skin, which will look red, dry, and "polished." Tinel's sign is present, and continuous severe pain over the region of injury usually indicates a more severe injury.

Electromyography/neurography

In case of confusing diagnostic signs, electrophysiological studies can help to establish the diagnosis and to identify injured nerve branches, although the results must be interpreted with caution during the first 3–4 weeks. It may take up to 4 or even 6 weeks after the injury before signs of nerve degeneration and muscular denervation can be detected.²³ It is stressed that waiting for an electrophysiological examination should not delay exploration of an injured nerve if indication for surgery is strong.

Intraoperative conduction studies can be of help, particularly in the case of a previously closed injury that has failed to show satisfactory recovery at follow-up. Intraoperative examination enables a higher grade of specificity as the observed nerve or even individual nerve fascicles can be anatomically isolated, and action potentials across the scarred area can be evaluated.²⁴ If electrical recovery is recorded over the area of interest, the patient can be classified as Sunderland grade II or III, in which case spontaneous full recovery is expected. If no electrical recovery can be seen, the patient should be graded Sunderland grade IV or V and will most likely benefit from nerve resection and grafting. However, in the case of a neuroma in continuity (sixth-degree injury), the picture is more complex. Some fascicles will need resection and grafting, whereas others are actually grade II–III and will recover spontaneously. In these cases, postoperative outcome may be uncertain and the decision to operate is hard as intervention may result in a tedious and potentially damaging dissection with internal and external neurolysis and resection of damaged sections. However, it may sometimes be possible to distinguish injured fascicles that require nerve grafting from intact healthy fascicles intraoperatively. Intraoperative electrophysiology is therefore warranted and extremely helpful in decision-making during the procedure.

Wound inspection

Peripheral nerve transections rarely occur in isolation. Depending on the extent of the injury, surrounding structures




Fig. 32.10 Algorithm for open and closed nerve injuries. Flowchart showing timing of surgical exposure and nerve repair.

may be crushed, lacerated, avulsed, or otherwise damaged. Extensive tissue damage and an unclear zone of injury together with a contaminated wound are factors that influence management and may result in delayed neural repair. Extensive debridement and cleaning of the wound are essential for a satisfactory final outcome, and to decrease the risk of a complicating infection and subsequent scarring.

Sharply transected nerves are easier to manage than crushed or avulsed ones. In a sharp transection, the zone of injury is limited, and the nerve can usually be prepared and repaired at the primary operation. If, however, the nerve is seriously crushed or longitudinally avulsed, the zone of injury is harder to establish and delayed excision of the damaged nerve followed by repair may improve outcome.

Ideally the repaired nerve should be surrounded by a well-nourished soft-tissue bed, muscle, or fat. In severe cases, this implies that the damaged soft tissues surrounding the injured nerve need to be replaced by a soft-tissue transfer to reconstitute a gliding surface either before secondary reconstruction or in connection with the primary reconstruction.

Patient selection

All patients with a suspected nerve injury should be judged individually as a number of factors must be considered before the decision to explore is made (see Fig. 32.10). When one is considering sharp lacerations, traction injuries, blast injuries, or a combination, some key factors must be considered that will be of decisive importance in the timing of operation and the approach, including the type of injury and condition of the wound, and the vascularity of the wound bed.^{25,26}

Type of nerve injury

In cases where there are clinical signs of nerve injury, but there is no wound, the treatment should be conservative for the first 4–6 weeks, when clinical signs of recovery of function can be investigated. If at this point there has still not been a complete spontaneous recovery, electrophysiological examination can be done. This may be repeated if there is only partial, but insufficient, recovery before any operation is considered. In case of a closed injury where no recovery has been seen at all after 3 months, clinical and electrophysiological examination should be considered.²⁷ If there are no signs of spontaneous recovery during this period, exploration of the injured nerve is indicated. However, if there is partial recovery during the first 3 months, regular re-evaluation may be indicated for up to another 3 months.²⁸ The important point is to see if any recovery at all is present.

Nerve injuries with open wounds should always be explored. If the nerve is in continuity, it should be treated as a closed injury, and the clinical and electrophysiological function should be evaluated for up to 3 months. In contrast, a clear-cut injury with the nerve ends closely approximated is suitable for immediate repair, whereas a crush injury usually is not. In the latter case, there might be difficulties in distinguishing between viable and non-viable tissue, which would

call for careful debridement before any nerve repair is tried. In addition, when the patient presents with signs of an incomplete injury for which there is a chance that spontaneous recovery can yield a better outcome than immediate repair, reconstruction is preferred at a later stage only if the clinical results of conservative treatment are not satisfactory. Therefore, one of the most challenging aspects of a nerve injury will be the decision-making regarding timing of nerve exploration and reconstruction in complex cases such as open crush injuries or gunshot wounds. In these cases, the primary goal should always be to go for careful debridement and viable tissue coverage. Nerve reconstruction can thus only be considered when the surrounding tissue provides a viable environment for the nerve (see [condition of the wound](#), below). In case of an open injury, where the patient presents with a sensory and/or motor function deficit, but with a macroscopically intact nerve upon surgical exposure, a close follow-up is essential for assessment of the nerve function. Such cases, which include open wound crush injuries and gunshot wounds, should, as the surrounding tissue envelope has healed, be treated the same way as closed traction injuries ([Table 32.2](#)). Neurological examination is performed regularly, sometimes together with recurrently performed neurophysiological testing, and surgery is usually performed if no signs of regeneration or reinnervation occur (e.g., for some injuries, exploration after 3 or 4 months). It is, however, important to stress that all open wounds, where the patient presents with a sensory or motor loss, should be explored in the acute setting, in order to obtain the best outcome.

Condition of the wound

The state of the wound is important. A clean wound calls for an early repair, whereas an untidy wound needs careful debridement to remove non-viable tissue before any nerve reconstruction is undertaken. In severe cases, there may be a need for multiple debridements. In these cases, the nerve repair is better planned as a secondary reconstruction that can be done when other structures have healed with better chances of satisfactory soft-tissue coverage of the reconstructed nerve. Such a reconstruction is preferable within 3 weeks. At the time of re-exploration, the zone of injury is likely to be better defined, and scar tissue can more easily be extracted.

Table 32.2 Differing treatments for different types of nerve injury

Type of nerve injury	Neurography/EMG	Exploration	Revision	Repair or reconstruction
Sharp transection	–	Immediate	Immediate	Immediate
Open wound – nerve crush injury	4–6 weeks [§]	Immediate	Immediate	Immediate* Delayed [†]
Closed traction injury	4–6 weeks	Delayed	–	3–4 months [‡]
Open wound – gunshot wound	4–6 weeks [§]	Immediate	Immediate	Immediate* Delayed [†]

*If there is macroscopic nerve discontinuity on exploration, repair or reconstruction should be performed after repeated revision to ensure that the wound is tidy.

[†]If there is nerve continuity on exploration, the nerve injury should be treated as a closed injury so that repair or reconstruction is performed only when there is no sign of nerve regeneration (Tinel's sign), e.g., for some injuries, exploration after 3–4 months.

[‡]Repair or reconstruction is performed after 3–4 months if there are no clinical signs of nerve regeneration or reinnervation.

[§]If the nerve is in continuity on exploration, neurography/EMG can be performed in the same manner as for closed injuries. EMG, electromyogram.

Treatment and surgical techniques

Immediate compared with delayed nerve repair

General principles

Any nerve injury may be repaired immediately, or after a certain delay. If the conditions are favorable, immediate primary suture is the method of choice, resulting in the most favorable outcome,²⁹ as based on the neurobiological temporally diverse events outlined above. One of the most important prerequisites for primary repair is that it must be completed with little or no tension,^{30–32} otherwise a nerve graft should be considered.³³ Several authors have argued that more than 80% of all nerve lesions can be sutured immediately with a primary end-to-end coaptation.^{34,35} In these studies, it had to be possible to coapt the nerve endings with a single 9-0 nylon suture, without either separating the endings from each other or tearing the epineurium, to qualify for a primary end-to-end suture.

Primary immediate repair is technically easier than delayed repair, as approximation by rotation of the distal and proximal ends is more obvious when the epineurial vessels are present and clearly visible.³⁶ The elastic recoil of nerve endings that inevitably occurs as the nerve is injured is also easier to overcome in the acute phase. As time passes, the nerve endings will become embedded in fibrous scar tissue and end-to-end coaptation will be more difficult without tension or more extensive mobilization.

Clinical tips

- Ensure optimal condition of the wound bed.
- Careful debridement of injured and lacerated tissue is imperative.
- If the zone of injury of the nerve is unclear, go for secondary nerve reconstruction.

Timing

Immediate repair is preferable within the first 48 h, but some authors have suggested that it may also be done successfully during the first 1–3 weeks³⁷; however, recent experimental neurobiological data have clearly pointed out the advantage of early nerve repair. This implies that patients who present with uncomplicated open nerve injuries that happened more than 48 h previously benefit from nerve repair that is delayed in the sense that it is done after the wound has healed completely. Practically, the implication is that the nerve should be repaired as soon as possible, preferably within 2–3 weeks of the injury. The rationale for this approach is to reduce the risk of iatrogenic infection secondary to operation on a contaminated wound. A longer delay will also cause difficulties in doing primary repair due to scar formation and retraction of nerve endings, but most importantly, injured parts of the nerve ends should be resected to obtain viable nerve ends for optimal coaptation.

A delayed nerve repair, i.e., more than 3 weeks after the injury, usually requires a nerve graft. Nerve graft procedures

can be done several months later, but the regenerative response of neurons and particularly of Schwann cells decreases over time (see sections on [physiology](#), above, and [autografts](#), below).³⁸

Clinical tips

- Open wounds should always be explored as soon as possible if a nerve injury is suspected.
- Delay in nerve repair or reconstruction causes impaired functional outcome.
- If the nerve is in continuity, it should be treated as a closed injury.

Surgical approach

The incisions follow the general principles of plastic surgery in that the main objective is to prevent contractures and scars in areas of maximum sensory perception ([Fig. 32.11](#)). Wide exposure is often recommended to obtain a detailed anatomical overview, and it offers a safer dissection as the area of injury can be approached from healthy tissue outside the zone of injury. This often means that the traumatic wound needs to be extending proximally and distally, which is particularly important in secondary reconstructions.

Clinical tips

- Wide exposure and careful dissection to obtain well-vascularized tissue flap are vital for nerve coverage.
- Approach the nerve injury from viable tissue – thus, “from the known to the unknown.”
- Use of a tourniquet is always advised.

Principles of nerve repair

General principles

Proper and thorough microsurgical technical skills are crucial in nerve repair. An atraumatic approach with minimal tissue damage, using microsurgical instruments under either loupe magnification or a microscope, is essential ([Video 32.1](#) ▶).




Fig. 32.11 Small stab wound on the radial side of the index finger. Loss of sensation distal to the wound calls for exploration. A modified Bruner incision is used.




Fig. 32.12 A lacerated nerve and the cut-off line for debridement. The dashed line illustrates suggested resection line to reach healthy nerve tissue.

First, the injured nerve ends must be identified. Non-viable tissue must be resected, preferably with a surgical blade or using microsurgical scissors, to allow visualization of healthy fascicles that help the adaptation in primary nerve repair (Figs. 32.12–32.14 and Video 32.2 ▶). When repairing a nerve it is preferable to align the nerve according to its fascicular pattern, which may help topographical arrangement and improve outcome. If later reconstruction is planned (secondary reconstruction), the nerve ends may be tagged with a non-resorbable suture, and sutured to other structures in the wound. This is primarily to prevent the retraction of the nerve that inevitably happens after transection, but also to facilitate identification at a secondary procedure. If the nerve is allowed to retract, it will become tethered in fibrous scar tissue and lose its elasticity and normal excursion. The normal longitudinal excursion of the nerve needs to be taken into consideration, as the immediate demand for suitable length will depend on it. The normal excursion of the median and ulnar nerves is thought to be around 1.5 cm at the wrist when taking the wrist from full extension to full flexion.^{39,40} This length should preferably be added to the nerve deficit when estimating the total defect and assessing whether a nerve graft is needed or not. In a primary repair, the longitudinal extension is




Fig. 32.13 Standard epineurial repair with nylon sutures. To get proper fascicular alignment, nerve endings are aligned based on the pattern of the blood vessels within the epineurium.

retained and the nerve can therefore be approximated with minimal tension.

Second, the ultimate aim is a tension-free repair to enable the nerve to heal in optimal conditions. Usually, some dissection of the nerve trunk is necessary to achieve this. Even a small elongation through longitudinal traction will have a potentially devastating effect on the vascular supply to the nerve endings, with subsequent effects on the viability of the Schwann cells,²⁹ as stretching of a nerve trunk has been shown to impair intraneural microcirculation.⁴¹ Nerve blood flow decreases approximately 50%, with substantial recovery in 30 min after 8% elongation, whereas 15% elongation produces approximately an 80% reduction in blood flow with minimal recovery.³⁰ Some dissection of the nerve trunks proximal and distal to the injury is therefore often needed to alleviate tension, and this can be done without interfering with the segmentally approaching blood vessels. Other means of alleviating tension, such as transposing the ulnar nerve anteriorly






Fig. 32.14 Peripheral nerve repair of a digital nerve using standard epineurial end-to-end coaptation. (A) Nerve injury with minimal gap. (B) Epineurial suture. (C) Complete coaptation with minimal tension.





Fig. 32.15 Patient with a median nerve injury that is repaired with standard epineurial end-to-end coaptation at minimal tension. (A) Nerve injury with minimal gap. (B) Mushrooming seen when healthy nerve tissue is reached after resection. (C) Complete coaptation with minimal tension.

and therefore increasing excursion over the elbow, can be considered to enable a tension-free direct suture. It is, however, important to bear in mind that mobilization by dissection can theoretically impair the blood supply to the nerve endings. This issue has been an issue of debate,⁴²⁻⁴⁴ although clinical experience from ulnar nerve transposition points to the fact that intraneural microcirculation can resist considerable mobilization, and that gentle handling of the nerve can be acceptable.^{43,44}

As complete lesions almost always result in some retraction of the nerve endings, there is in most instances a gap between the ends that makes a completely tension-free suture rare. The

nerve endings generally need trimming, which means that some nerve tissue has to be resected to reach viable parts. Under the microscope this is seen as “mushrooming” of the fascicles together with slight retraction of the epineurium from the neural stumps (Fig. 32.15B). It is hard to give a general rule for how much tension is acceptable in each individual case, but if flexion of a joint is necessary to shorten the distance between the nerve ends, the resulting tension will usually be too great, and further dissection or nerve grafting should be considered (Figs. 32.16A & 32.17A).

Third, the nerve endings should be rotated to their correct positions by matching fascicles, branches, or the longitudinal





Fig. 32.16 Patient with a lacerated median nerve that, after resection of the destroyed part, remains with a nerve deficit (A) that is bridged with multiple cables of sural nerve grafts (B,C). Note that the individual cables are about 15% longer than the gap.




Fig. 32.17 (A) Digital nerve laceration. (B) The nerve gap was bridged with a single autograft from the lateral cutaneous antebrachial nerve.

epineurial vessels of the two nerve endings, which decreases the risk of mismatch between bundles of axons (Figs. 32.15A & 32.18). Correct coaptation facilitates a good postoperative outcome.

Nerve endings are commonly coapted with interrupted 9-0 or 10-0 nylon sutures. It is generally thought that a minimal amount of suture material is preferable, and the number of sutures should be no greater than the minimum number required to ensure coaptation of the nerve stumps. It is important that the nerve ends are not closed too tightly so that the fascicles become malaligned and crumple in the process.⁴⁵ Outward-pointing fascicles are sometimes found, and should be cut with microscissors. They are then able to retract to within the coaptation and will subsequently probably be able to regenerate sufficiently.

Other means, apart from nylon sutures, of maintaining the primary repair can be considered, particularly if the repair is to be made by a relatively inexperienced surgeon. The use of fibrin glue as an alternative, or as an adjunct, to epineurial sutures has been evaluated in rats after transection of the sciatic nerve.^{46,47} The results showed that fibrin glue is as good as suturing in experienced hands, and superior to sutures when the surgeon is inexperienced.^{43,46}




Fig. 32.18 End-to-end coaptation. Note that the epineurial vessels match.

Clinical tips

- Proper magnification, appropriate equipment, and microsurgical skills are crucial.
- Resect non-viable tissue carefully, possibly stepwise, to visualize healthy nerve endings – look for mushrooming.
- Important for tension-free coaptation – if flexion of joints is needed, consider nerve reconstruction.
- Aim at fascicular match – look for intraneural vessels to help with alignment in repair and reconstruction.

Epineurial compared with fascicular repair

The nerve trunks may be adapted either at the level of the epineurium (see Fig. 32.12) or the fascicles (Fig. 32.19). Which method is preferable has been a matter of debate, probably because the scientific evidence is not entirely clear as the data are based on experimental studies in rats and primates with their inherent methodological problems.^{48,49}

The theoretical advantage of the fascicular repair over the epineurial repair is that it facilitates regeneration with a better chance of keeping the axonal specificity to sensory or motor end organs. However, fascicular repair requires a more profound dissection to identify the individual fascicles at the two ends, which in turn may increase the risk of compromising the vascular supply. An epineurial repair with careful rotation of the nerve trunks is therefore thought to be as effective, particularly more distally. The dissection is technically more difficult as the individual fascicles are hard to identify clearly distally. A group fascicular adaptation is preferable, for example with lesions of the ulnar nerve at the wrist. Great care should be taken to make sure that sensory and motor fascicles are located both proximally and distally through dissection, and coapted separately (Fig. 32.20).

Clinical tips

- Epineurial repair is preferable as long as it is technically possible.
- Apply a limited number of sutures, maybe with fibrin glue as an adjunct to sutures.
- Group fascicular repair is a good option when sensory and motor fascicles are distinct, such as with the ulnar nerve at the wrist level.




Fig. 32.19 Group fascicular repair with nylon sutures. Corresponding groups of fascicles are sutured through the interfascicular epineurium.




Fig. 32.20 Ulnar nerve injury at the wrist level. Note how the motor and sensory fascicles are anatomically separated. A group fascicular coaptation is performed.

End-to-side nerve repair

When conventional surgical methods are unavailable, particularly if the proximal stump is absent, or after injuries to nerve proximally in the extremity (such as in high ulnar nerve injuries), the distal end of an injured nerve can be attached to an “uninjured” donor nerve.^{50,51} Collateral or terminal sprouting of donor nerve axons occurs, and donor site morbidity associated with the harvest of a nerve graft is avoided. In addition, the distance traveled by regenerating axons to reach their targets is shortened. Theoretically this implies that a single neuron possesses the ability to innervate two targets, but one of the branches is probably pruned away.⁵¹ Several studies have indicated that the outgrowth of axons from the donor nerve requires an axonal injury to induce sprouting.⁵² At present, experimental and clinical experience with end-to-side coaptation has, at best, achieved mixed results, depending on the type of reinnervated nerve and donor nerve.⁵³ More extensive clinical and laboratory experiments are presently produced, which is required before end-to-side suturing generally can be included with the more established techniques of nerve repair.^{54,55} However, for reinnervation of muscles from motor donor nerves, the end-to-side techniques have been reported to be useful.⁵⁶

Wound closure and immobilization

The wound should be closed with interrupted sutures and a local anesthetic may be given before dressing. It is preferably given through a blunt cannula inserted between the stitches. Sharp needles should be avoided to reduce the risk of neurovascular damage proximal to the injury if the site of repair/reconstruction is located superficially.

A plaster should be applied, primarily to restrict excessive movement, avoiding tension in the repair, and still allow some range of movement for controlled early mobilization. The plaster should position the extremity in such a way that it both releases tension and prevents excessive movement. For digital nerve injuries, the wrist is immobilized at 30° of flexion and the metacarpophalangeal joints at 70°. The splint is usually extended just past the proximal interphalangeal joints to prevent hyperextension. Immobilization with plaster of Paris, with controlled restricted range of movement, is usually maintained for 3 weeks before full range of movement is allowed in digital nerve repairs. In repairs of larger nerve trunks a prolonged protection of the suture line may be recommended up to 6 weeks postoperatively, to avoid extensive extension of the wrist or elbow.

Nerve reconstruction

Clinical tips

- Always consider a nerve reconstruction to alleviate tension at the coaptation site when trauma or debridement has left a nerve deficit or when joint movements are expected.
- Autologous nerve grafts are still considered the gold standard compared to artificial conduits.

Autografts

Nerve reconstruction involves the use of a nerve graft to overcome a lack of continuity after an injury (see Figs. 32.16 & 32.17). The use of autologous grafts is still the method of choice despite the fact that other strategies, such as nerve and muscle allografts or synthetic materials, have been proposed, but they demand a more complex approach than a primary nerve repair to be successful.

The rationale for using a nerve autograft in reconstruction is to alleviate all tension at the site of suture. If tension is completely avoided, axonal sprouting to cross the two sites of repair will be easier than over a primary repair site under unfavorable conditions.⁵⁷ The axonal outgrowth through the nerve graft depends on the diameter of the graft and the vascularity of the tissue bed. The selection of donor nerve will therefore be much influenced by size, as survival is dependent on diffusion from the surrounding tissues. Neovascularization will occur through capillary ingrowth from the periphery and nerve ends.^{57,58} Smaller nerves (for example, the sural, and the medial and lateral antebrachial cutaneous nerves) will therefore revascularize easily, and thicker nerves will carry the risk of central necrosis and scarring as a result of poor diffusion. Only one cable is needed when smaller nerves, such as digital nerves, are bridged (see Fig. 32.17), whereas multiple cables may be needed to bridge the gap in larger damaged nerve trunks (see Figs. 32.16 & 32.21).

Approach and preparation

The initial steps in preparing the nerve tissue are no different from those for primary nerve repair. However, when the ends are being resected to create a clean-cut surface, it is important to expose the nerve carefully, including the whole zone of injury. This enables proper evaluation of the viability and vascularization of the nerve and surrounding tissues. In crush or high-velocity injuries, this principle is central. As with all tissue injuries in which the zone of injury is not clear, late effects on viability call for second looks and re-evaluations. When the nerve is explored after the surrounding tissue has healed, it is important to remove any scar tissue carefully, or preferably to approach the nerve lesion through a separate incision. This includes raising a flap that at closure of the wound will enable good tissue coverage.

Nerve ends

A good way to find out whether the nerve endings are viable is to look for “mushrooming” (see Fig. 32.15B), which is a sign of transected viable axons that will be able to sprout after




Fig. 32.21 Schematic presentation of autograft repair. Each segment is coapted to the corresponding group of fascicles of the nerve endings. Note how the individual grafts are applied quite loosely.

reconstruction from the resection site, indicating that the nerve is a suitable recipient for a nerve graft.

The gap

To harvest a proper graft it is essential to calculate the maximum gap that is going to be bridged, and this has to be done in relation to any movement of a joint that might occur later on.

Length of graft

Because the graft may shrink slightly, it should be about 15% longer than the maximum gap.⁵⁹ Nerve excursion must be considered, and length is best assessed with all adjacent joints fully extended (or in certain cases, such as radial nerve injury at upper arm, in a flexed position).

Harvest of the graft

The size of the nerve trunk to be bridged is the main factor to be considered when deciding which donor nerve will be most suitable to use as a graft. Donor site morbidity and functional deficit also have to be considered when choosing the proper donor nerve (Table 32.3).⁶⁰ Patients should be well informed about these aspects before the harvest. The most common grafts are the sural nerve, the medial antebrachial cutaneous nerve, the lateral antebrachial cutaneous nerve, or the terminal branch of the posterior interosseous nerve.

Gentle handling is of great importance and must follow the same principles as handling of all nerves. As the graft is harvested, great care must be taken that it is kept moist in a gauze soaked in saline. The grafts are sharply cut to proper

length and a few millimeters of extra epineurium is removed from the ends of the graft.

Coaptation and maintenance

The nerve graft is preferably reversed at the time of placement to decrease the risk of diversion of regenerating axons through these cut-off branches. Depending on the size of the nerve trunk, the whole nerve or individual fascicles can be sutured using 9-0 or 10-0 nylon, if possible with fibrin glue as an adjunct. A sufficient number of fascicles are used to bridge the defect, preferably with one cable for each severed group of fascicles (see Figs. 32.16C & 32.21). The coaptation should not be too tight, as this can easily lead to crumpled nerve endings. Fibrin glue may be interposed to reinforce and lessen the risk of separation between the graft and nerve endings. Fibrin glue may also give an instant better match between the graft and the nerve end. The number of sutures should be kept to one or two. If multiple cables are used, the individual grafts are positioned so that they do not adhere too closely to each other. This is to allow diffusion of oxygen and other nutrients, and allow for rapid revascularization from the recipient bed. It must be stressed therefore that the viability of the tissue bed is of crucial importance for optimal survival of Schwann cells and successful axonal regeneration.

Donor nerves

Sural nerve

The sural nerve is often thought to be the main donor nerve for free grafting, because it can easily be harvested in lengths between 30 and 40 cm⁶¹; it originates from the tibial nerve dorsal to the knee joint (Fig. 32.22), and it has communicating branches from the peroneal nerve at levels distal to this. These communicating branches need to be identified and transected before the nerve is pulled out.

The sural nerve is identified through a short longitudinal incision halfway between the lateral malleolus and the Achilles tendon. If the nerve is gently pulled distally, the proximal course of the nerve can be palpated and extracted through 3–5 small transverse incisions that usually pose a minor aesthetic problem for the patient (Fig. 32.23). Alternatively a long dorsal incision can be used, which enables an easier dissection of the nerve and its small branches. It is preferable to cut the nerve beneath the fascia to reduce the risk of a troublesome neuroma. Nerve strippers can be used and endoscopic harvest has been suggested to reduce aesthetic morbidity at the donor site.⁶² The area of diminished or absent sensation after the graft has been harvested is shown in Fig. 32.24, but is usually considered to be of minor importance to the patient.⁶⁰

Medial and lateral antebrachial cutaneous nerves

The medial cutaneous nerve can be harvested from the distal border of the axillary groove to below the elbow (10–12 cm). In the forearm it is located medially (8–10 cm), close to the brachial vein, where it divides into three branches (Fig. 32.25). These branches correspond well in size to digital nerves. The consequences are usually of minor importance to the patient (Fig. 32.26).

The lateral cutaneous nerve (10–12 cm) is the terminal branch of the musculocutaneous nerve. It is identified at the

Table 32.3 Common nerves used as autografts

Donor nerve	Length (cm)	Sensory defect
Sural nerve	30–40 cm	Dorsal aspect of lower leg and lateral foot
Medial antebrachial cutaneous nerve	10–12 cm* 8–10 cm†	Medial forearm
Lateral antebrachial cutaneous nerve	10–12 cm	Lateral forearm
Superficial sensory branch of the radial nerve	25 cm	Radial dorsal hand

*Above elbow.
†Below elbow.




Fig. 32.22 Course of the sural nerve in the lower leg, shown in orange.




Fig. 32.24 Area of diminished or absent sensation after harvest of the sural nerve.




Fig. 32.23 Incisions to enable harvest of the sural nerve, shown by dotted lines.




Fig. 32.25 Medial antebrachial cutaneous nerve shown in orange, and basilic vein.




Fig. 32.26 Area of diminished or absent sensation after harvest of the medial antebrachial cutaneous nerve.

lateral border of the biceps tendon where it parallels the cephalic vein (Fig. 32.27).

A few short incisions are generally sufficient to harvest these nerves adequately. The consequences are usually regarded as more troublesome for the patient after lateral antebrachial cutaneous nerve harvest than after harvest of the medial antebrachial cutaneous nerve (Figs. 32.28 & 32.29).

The terminal branch of the posterior interosseous nerve

The terminal branch of the posterior interosseous nerve is simple to harvest dorsally just proximal to the wrist, lying on the interosseous membrane.⁶³ Generally, one can harvest a 4–5-cm long segment (1–3 fascicles), which may fit into a small digital nerve defect. Harvest causes no complications or loss of function, which is beneficial, especially in reconstructions of digital nerve defects. This was recently exemplified in a retrospective study, where posterior interosseous nerve grafts were shown superior to the medial cutaneous nerve of the forearm, especially in terms of donor site morbidity.⁶⁴

Superficial sensory branch of the radial nerve

The superficial sensory branch is formed as the radial nerve is divided into a deep (the posterior interosseous nerve) and a superficial branch at the elbow level. The superficial branch runs beneath the brachioradialis muscle to surface distally about 8 cm from the tip of the radial styloid between the tendon of brachioradialis and the tendon of extensor carpi radialis (Fig. 32.30). It provides a 25 cm-long nerve graft, but is rarely used because it tends to cause painful neuromas. It is primarily used when large quantities of nerve grafts are needed in brachial plexus injuries. In the presence of a median or ulnar nerve injury, it is considered a relative contraindication to use it as a donor for nerve grafts (Fig. 32.31).

Other

The saphenous nerve (40 cm) has been used primarily in plexus injuries and as a vascularized nerve graft. The lateral femoral cutaneous nerve (20 cm) can be used as a last choice, but has the disadvantages of comparatively large sensory loss, and painful neuromas.




Fig. 32.27 Lateral antebrachial cutaneous nerve shown in orange and cephalic vein.




Fig. 32.28 Area of diminished or absent sensation after harvest of the dorsal aspect of the lateral antebrachial cutaneous nerve.

Tubular repair and artificial conduits

Autologous nerve grafts are still considered to be the gold standard for bridging defects in nerves. The superiority in outcome is thought to be mainly the result of their ability to provide a biocompatible scaffold that contains both Schwann cells and their basal lamina. These factors promote regeneration through natural production of growth factors and adhesion molecules, which will help stimulate neurite elongation and direction on site.⁶⁵ However, there are disadvantages with autografts, some of which have been mentioned above. Harvesting requires an extra surgical incision to obtain an otherwise healthy sensory nerve. There are limited sources of graft material, and the injured nerve and donor nerve may be mismatched at grafting.⁶⁶

Our present inability to gain full functional recovery with autografts has been the main driving force behind the development of alternative means to bridge nerve defects. Tissue engineering has in recent years offered the opportunity to develop biodegradable guiding materials with tailored properties that imitate normal biological features. Structural stability is enabled, and both growth factors and supportive cells, such as Schwann cells or stem cells, can be added to give physical guidance to the regenerating axons. However, the

latter procedure is far from clinical practice, but may be a possibility in the future. Formation of a longitudinally oriented fibrin matrix and accumulation of various tropic and trophic factors will ensue within the conduit, and this will further improve the physical conditions for nerve regeneration. Obviously, donor morbidity after graft harvest will be eliminated.

Biological conduits

The first attempt to bridge a nerve defect with a tube was published by Glück, who used a piece of decalcified bone to bridge a nerve gap.⁶⁷ Since then, several biological scaffolds have been used, including veins,^{68,69} arteries,⁷⁰ muscles,⁷⁰ tendons,⁷¹ and combinations such as vein-muscle grafts,^{72,73} and acellular nerve allografts,⁷⁴⁻⁷⁶ with variable outcomes. The main theoretical advantage of using biological constructs with a core matrix is the availability of a longitudinally oriented basal lamina and extracellular matrix components that direct and improve the regeneration of axons. In contrast, bridging methods using only tubular material, such as vein grafts or non-degradable or degradable nerve conduits (several are commercially available) lack this function and may be less attractive, at least theoretically. The use of composite




Fig. 32.29 Areas of diminished or absent sensation after harvest of volar aspect of the lateral antebrachial cutaneous nerve.




Fig. 32.30 Superficial sensory branch of the radial nerve.

biological conduits, such as combinations of veins and muscles, has therefore been explored. The main rationale for using this combination, apart from it being of autologous origin, has been that a collapse of the vein is prevented by filling the lumen, and that the vessel wall prevents the risk of axons sprouting outside the muscle. Nerve regeneration is propagated along the longitudinally oriented muscle fibers and no foreign material is used in the bridging process. In a recent retrospective study of nerve reconstructions of up to 6 cm-long digital nerve defects, comparing autografts, muscle-in-vein grafts, and direct nerve repair,⁷⁷ it was found that muscle-in-vein grafts yielded similar outcome as the nerve autografts, which have been slightly, but not significantly, worse than the ones after direct nerve suture. One advantage of muscle-in-vein grafts is the lack of donor site sensory morbidity.

Processed nerve allografts

Processed nerve allografts provide decellularized and predegenerated human nerve tissue as an alternative to conventional nerve autografts or tube conduits for nerve reconstruction. These grafts have shown promising results both in animal studies and early clinical studies, where they

have been proven to be safe and effective in sensory nerves up to 30 mm; however, the maximal length of the nerve defect is not yet established.⁷⁸⁻⁸¹

The three-dimensional structure of these acellular scaffolds contains many of the beneficial characteristics of nerve autografts. This includes not only the physical structure of the epineurium, and fascicles with endoneurial tubes, but also protein structures and guidance molecules specific for nerve tissue. It is hypothesized that the grafts thereby function as a guide for tissue regeneration, by stimulating a rapid revascularization and repopulation with host Schwann cells.

Today, commercially available processed nerve allografts are all manufactured from donated human peripheral nerve tissue. A detergent protocol is used to remove all cells and cause a pre-Wallerian degeneration of the nerve tissue in order to cleave growth inhibitors. The tissue is then sterilized prior to use as an off-the-shelf product.

In a large multicenter observational study, the RANGER Study registry, 71 nerve gaps in sensory, mixed, and motor nerves were reconstructed in 56 subjects. Overall, a meaningful level of recovery, defined as motor nerve function of M3 to M5 and sensory function of S3 to S4, was achieved in 86% of the patients with repairs with graft lengths up to 50 mm. Meaningful levels of recovery were also found in 89% of




Fig. 32.31 Area of diminished or absent sensation after harvest of the superficial sensory branch of the radial nerve.




Fig. 32.32 A nerve defect bridged by a nerve conduit.

digital nerve repairs, 75% of median nerve repairs, and 67% of ulnar nerve repairs.^{79,82} In a follow-up study of short-gap (i.e., 5–15 mm) sensory recovery, using the same material, it was shown that the outcome for nerve allografts were equivalent to previous data on autograft and exceeded those of conduits.⁸³

Non-degradable conduits

The first artificial conduits used in preclinical and human trials were composed of non-resorbable polymers based on silicone and polytetrafluoroethylene^{84,85} (Fig. 32.32). Silicone was chosen because of its inert material properties and because it is tolerated well by the recipient.⁸⁶ It has been used successfully in hand surgery for arthroplasty and two-stage tendon-grafting procedures for the last two decades. As silicone tubes are non-degradable and impermeable to large molecules, they also provide the necessary biological isolation from scar-forming elements of the wound and allow for accumulation of growth factors. A longitudinally oriented fibrin matrix containing macrophages is formed and there is migration of Schwann cells, ingrowth of axons, and neovascularization of the newly formed nerve trunk. Silicone tubes were used in a clinical prospective randomized study that compared tube repair and microsurgical nerve repair in median and ulnar nerve injuries.⁸⁷ Results showed no significant differences in outcome between the two methods, except for a decrease in cold intolerance in the conduit group at the 5-year follow-up.⁸⁸ The authors concluded that tubular repair may be preferable in the future when appropriate bioresorbable materials are available. However, utilization of a silicone tube is not an alternative when there is a nerve defect.

Biodegradable conduits

Increasing interest has turned towards the use of biodegradable materials as conduits. Ideally, the material from which the tube is made should be highly biocompatible and allow degradation to non-toxic end products. They should be mechanically stable, yet still flexible and porous to ensure supply of nutrients and provide a microenvironment that allows for the production of functional tissue.^{65,89–91}

Polymer-based materials, such as collagen, polyglycolic acid polymer, and polylactide-caprolactone polymer, and other available materials such as chitosan conduits,⁹¹ offer a high degree of flexibility in chemical and physical properties and are available commercially. Future inclusion of fillers, such as Schwann cells, or incorporation of biologically active substances in the polymers that are released as the tube is degraded are areas of massive research. Yet, at present, clinical experience in terms of randomized trials is lacking,⁹² although

increasing numbers of studies have reported promising results regarding recovery of both sensory^{93–95} and motor function.^{96,97}

In a level II study, Boeckstyns *et al.* randomized ulnar or median nerve injuries to repair with a collagen nerve conduit or with conventional microsurgical techniques. The use of collagen conduits was found to have a recovery of sensory and motor functions that were equivalent to that after direct suture when the nerve gap was 6 mm or less, as evaluated at 24 months after repair. At 12 months, however, there was a significantly better motor recovery in the direct suture group. Also, ulnar nerve lacerations were found to have a poorer prognosis compared to median nerve lacerations.⁹⁸

Another recent prospective long-term follow-up on digital nerve reconstructions with collagen nerve conduits found that sensibility continued to improve in most cases after 12 months. Also, it was shown that the improvement of sensibility was associated with a significantly shorter nerve gap length with significantly better results if the gap length was <10 mm.⁹⁹

Fillers

The main purpose of inserting filler structures in the conduits, whether in the form of guidance channels, hydrogels, or others, is to apply haptotactic cues (contact-mediated) to support axonal regeneration or chemotactic cues (diffusible) to guide the regenerating axons.¹⁰⁰ The most commonly used haptotactic cues are extracellular matrix proteins such as collagen, laminin, and fibronectin. Neurotrophic factors, such as nerve growth factor, glial-derived neurotrophic factor, and neurotrophin NT-3, are additives that act as chemotactic cues that will promote neuronal regrowth and sprouting.⁶⁵ Addition of cellular components, such as Schwann cells¹⁰¹ and stem cells,¹⁰² can further be used to improve the regeneration by creating a more optimal microenvironment. In the future, it is possible that “off-the-shelf” conduits may be filled with autologous supporting cells that are harvested and immediately prepared from the patient’s injured nerve segments.¹⁰³

Other techniques

Preclinical studies have indicated that shorter digital nerve defects can be bridged by applying longitudinal resorbable sutures that will act as a guide for the fibrin matrix that is formed to fill the defect. Schwann cells and axons will follow this matrix and thereby overcome the defect. The newly formed nerve trunk, which can be made in a branched pattern, is subsequently surrounded by a new perineurium-like structure and provides functional recovery.¹⁰⁴

Nerve transfers

In recent years there has been an increasing interest in the use of nerve transfers in nerve reconstruction.¹⁰⁵ This technique has primarily been used in brachial plexus injuries, and is based on the assumption that less important nerves can be sacrificed, transected, and rerouted to be attached to a functionally more important nerve segment.^{106,107} It can also be used after other proximal nerve injuries, and the procedure transfers a proximal nerve injury to a distal one. This is a tempting and valuable method that can be used when patients present late with nerve injuries, even in young patients.¹⁰⁸ The topic is further discussed in Chapter 33.

Clinical tips

- Current literature supports the use of conduits or acellular nerve allografts for reconstructions of nerve defects when the defects are limited, for example in digital nerves and larger nerves (median and ulnar nerves). In larger defects, conduits and allografts should be used with caution, and until proven effective for longer distances, we suggest nerve grafting for long defects.
- For sensory digital nerve defects, especially if the proximal stump is absent, cross-over end-to-side neurotaphy is a reconstructive option.

Postoperative care

General aspects

The role of early active mobilization after microsurgical nerve repair has been debated. It has been hypothesized that it may cause a change in tension at the site of nerve repair, which in turn will result in impaired functional outcome.^{109,110} Experimental studies have indicated that intraneural scarring at the repair site can impede revascularization and reduce axonal regeneration across the suture line as a result of tension.^{32,111} However, immobilization may result in an increase in scar tissue that surrounds the reconstructed nerve. Tethering of the nerve by scar tissue may lead to additional pain on movement.¹¹² Maintenance of full range of movement of the neuromuscular unit and preservation of movement of small joints are of importance in the postoperative phase. Intermittent, controlled mobilization in a protected splint is therefore thought to be beneficial for the patient. Most importantly, the nerve grafts should be applied at minimal tension with joints in an extended position and in a manner that allows subsequent full range of motion without causing tension over the repair sites. Surgeons should supervise physiotherapy and occupational therapy, check advancement of Tinel's sign and return of muscle function, which is recovered during rehabilitation.

Postoperative movement training

Dorsal splinting may be maintained for 3 weeks in a manner that allows intermittent early gentle mobilization within a protected range without putting the microsurgical repair at risk or tension. Although some authors have advocated that the nerve should be allowed to rest for 8 days before active and passive mobilization,³³ an earlier start to training may be appropriate within the limits of bandages and restrictive splinting. It is thought that early active movements may reduce the risk of the nerve being tethered in scar tissue,^{59,112} which is a possible effect if rigid immobilization is adopted. Elevation of the hand is recommended for the first week postoperatively. Sutures and plaster are usually removed at 3 weeks and active exercises of the fingers can then be initiated. Prolonged protection of the suture line may be recommended up to 6 weeks postoperatively, to avoid extensive extension in the wrist. These general principles apply for digital nerves as well as major nerve trunks and nerve grafts.

Sensory re-education

Cortical reorganization

After an acute nerve transection, the brain must compensate for the loss of sensory input.¹¹³ First, a gross decrease in the number of fibers is seen, as well as a topographical mismatch. A "silent area" is created in the nerve's representational area in the brain. However, adjacent cortical areas expand instantly and occupy this former nerve territory.^{114–117} These changes are mediated by the unmasking of normally inhibited synaptic connections in the vicinity of this "silent area", and a reorganization of the somatosensory cortex occurs through processes of brain plasticity. This period is referred to as *phase 1* during rehabilitation – before any reinnervation has occurred in the hand. During this phase some training may be initiated.

Because of the mismatch and misdirection of the regenerating axons that happens at the repair site, areas of skin in the hand and muscles will not be reinnervated by their original axons to a large extent.¹¹⁸ The original well-organized hand representation in the sensory and motor cortex alters into a distorted and mosaic-like pattern with disappearance of, and overlapping of, fingers.¹¹⁴ As a result of misdirection and remapping of the representation of the cortical hand, "the hand speaks a new language to the brain" (*phase 2* during rehabilitation). A sensory relearning program that helps the brain to decipher the signals may assist it in interpreting the new language, which works well and improves outcome.¹¹⁹ Recent data have indicated that it is beneficial for this process to begin when the reorganization in the sensory cortex has already started (*phase 1*)¹¹⁶ and that this should not be postponed until touch can be perceived in the hand, as was earlier believed. Effectiveness in the relearning process is probably greatly influenced by the individual motivation of each patient. Coping strategies that are individualized for each patient should be considered, as adaptation to the condition is an evolving process by which the patient's own resources can be used to overcome problems in daily activities.

Sensory re-education in phase 1

During the early postoperative period (*phase 1*), various "babysitting" methods can be used until the hand becomes reinnervated by the outgrowing axons. Functional similarities exist between perception and imagery (the premotor cortex can be activated by just imagining a movement – so-called "motor imagery"). The corresponding phenomenon for sensory function is "sensor imagery". Imagining the hand being touched activates the same cortical areas as if the hand is really being touched.

Activation of "mirror motor neurons" in the premotor cortex by mere observation of hand motor actions by others plays a fundamental part in action, imitation, and action understanding.¹²⁰ Reading or listening to action words related to hand movements activates hand representational areas in the motor cortex and observation of touching a hand activates the corresponding representational areas in the sensory cortex. The patient's observation of the denervated hand being touched is already initiated during the first days postoperatively, which may activate the cortical hand area as a result of visuotactile interaction.¹²¹

In early sensory training, the multimodality of the brain is activated; the cortical audiotactile interaction is used to activate cortical sensory areas by listening to the sound of touch. A sensor glove, provided with minimicrophones at its fingertips, can be applied to the denervated hand.¹²² Active touch of items is associated with a specific “friction sound”, depending on the texture touched, which is transmitted to earphones. The patient can “listen to what the hand feels.” If the sensor glove is used in the early phase after nerve repair, tactile discrimination may be improved considerably. To conclude, early re-learning, i.e., starting within the first week after a median or an ulnar nerve injury and conventional nerve repair, by using this described guided plasticity seems to have a potential to improve outcome during the first 6 months.¹²¹

Improving effects of sensory re-education – phase 2

A relearning process is required to adapt to the new and distorted afferent sensory input caused by axonal misdirection when familiar objects are touched. For this purpose, sensory re-education is routinely used in phase 2, when the hand has started to reinnervate, to regain tactile gnosis. Ways of touching, and the capacity to localize touch, are trained, followed by touching and exploration of items, presenting shape and textures of varying and increasing difficulty with eyes open and closed. Vision assists training and improves the deficient sense.

Repeated sessions of cutaneous anesthesia of the forearm increase the effects of sensory re-education and result in expansion of representation of the cortical hand¹²² (Fig. 32.33). The hand is given more “brain space”, which enables the improved processing of sensory impulses. Repeated application of a cutaneous anesthetic cream (lidocaine/prilocaine: EMLA), combined with intensive sensory re-education, increases the effects of sensory re-education with a

considerable improvement in tactile gnosis (functional sensibility) in patients with repaired median nerves.^{123,124}

Outcome

Assessment of outcome

Final evaluation of sensory and motor function should not be made until after rehabilitation has finished. Depending on the type of injury, the rehabilitation period may last for 12–24 months postoperatively to allow for reinnervation and sensory re-education,¹²⁵ although some authors claim that a follow-up time of at least 3 years is necessary to evaluate the final outcome.¹²⁶

General aspects

Even though extensive amounts of data have been published on the results of nerve repair, there is no consensus on how to evaluate the outcome in a standardized manner. Different protocols for assessing the outcome have been proposed,^{125,127–129} but none has been adapted uniformly. The evaluation instrument most widely accepted is the Hightet Scale from 1954, adopted by the British Medical Research Council (MRC) (Table 32.4).

The outcome after nerve repair depends on to what extent the regeneration of the axons is successful, and how many of the axons reach their end target. Several factors that influence the results after nerve repair have been documented.

MRC scale

Several modifications of the British Medical Research Council's scale for nerve recovery have been described,¹³⁰ and the modification by Dellon *et al.* is probably the most used.¹³¹ The sensory function is evaluated according to how the patient describes levels of recovery (see Table 32.1). Critics claim that

Table 32.4 The Hightet Scale from 1954, adopted by the British Medical Research Council

Motor grade	Level of recovery
M0	No recovery
M1	Perceptible contraction in proximal muscles
M2	Perceptible contraction in proximal and distal muscles
M3	Contraction possible against gravity
M4	Contraction possible against resistance
M5	Full recovery in all muscles
Sensory grade	Level of recovery
S0	No recovery
S1	Recovery of deep cutaneous sensibility
S1+	Recovery of superficial pain and sensibility
S2	Recovery of superficial pain and some touch
S2+	S2 recovery with hypersensitivity
S3	Recovery of pain and touch without hypersensitivity
S3+	S3 recovery with localization and some two-point discrimination
S4	Complete recovery with normal two-point discrimination




Fig. 32.33 Brain plasticity. Repeated sessions of cutaneous anesthesia of the forearm increase the effects of sensory re-education and result in expansion of representation of the cortical hand. The hand is given more “brain space”, which enables the improved processing of sensory impulses.

the MRC scale is based on subjective findings without any attempt to standardize defined methods of evaluation, which complicates our ability to compare different sets of patients as well as results from different observers.

The Rosen score

To enable improved interpretation of patients' functional outcome after nerve repair (median and ulnar nerves),

Rosen and Lundborg presented a protocol that illustrated patients' functional limitation in activities of daily living.¹²⁸ This protocol is based on previous studies that investigated what methods are most effectively used to study the temporal aspects of the outcome after nerve repair.¹²⁵ Three domains of function were described: (1) sensory; (2) motor function; and (3) pain and discomfort. A total score is calculated that correlates significantly with the MRC scale, which was shown in a study of 70 patients who had been treated for

nerve transection at the wrist or distal forearm level. The total score also correlated strongly with the patients' overall estimation of the impact of the injury on activities of daily living.¹²⁸

Factors that affect outcome

General aspects

Ruijs *et al.* presented an excellent meta-analysis of 23 papers based on data from individual patients about motor and sensory recovery after microsurgical repair of the median and ulnar nerves.¹²⁵ Prognostic factors that have an impact on outcome varied for motor and sensory recovery. For motor recovery, age, delay before repair, level of injury, and type of injured nerve were important, and for sensory recovery, age and delay before repair were the most important.

Age

In several studies of digital nerve repairs, there was a close positive correlation between the younger age of the patient and the recovery of sensation.^{132–134} For more proximal injuries of the median, ulnar, or radial nerves in the forearm, age also seems to be the factor that played the most important part in the outcome. Children (mean age 6 years) that were evaluated a minimum of 1 year after primary repair of injury to the median nerve were all considered to have regained normal function.¹³⁵ In comparison, 95 patients (age 15–55 years) with primary or secondary repair, or grafting, of injuries of the median and ulnar nerves³⁰ showed that only the younger patients who had primary distal repair had excellent results, with normal sensitivity and motor function. These findings are supported by other authors in similar case series.^{127,136–138} Patients under 16 years are four times more likely to have satisfactory outcome in motor recovery, and also a significantly increased chance of satisfactory sensory recovery, with lower age.¹²⁶

The superior results in children may, to some extent, be explained by better peripheral nerve regeneration and shorter regeneration distances. However, it is likely that a greater adaptability of the brain is of predominant importance for the functional outcome in children.^{139,140} This hypothesis is confirmed by recent data that showed that early sensory re-education programs improve functional outcome in adults because of improvements in training-induced plasticity.¹⁴¹

More importantly, in a recent long-term follow-up, the age factor was extensively investigated indicating that children with injured median and ulnar nerves during childhood recovered significantly better than those injured during adolescence.¹⁴² However, in spite of excellent clinical recovery among the children injured during childhood, the electroneurography response was poor,¹⁴³ indicating that a better cerebral plasticity is the crucial factor for outcome. Recently, a functional magnetic resonance imaging (fMRI) study showed that the children that had their median nerve injured at the age of 1–13 years had an activation pattern in the brain similar to healthy subjects and that changes in both cerebral hemispheres may explain differences in clinical outcome between children injured during childhood and adolescence.¹⁴⁴

Digital nerves

In several studies of primary repair of the digital nerves, the results of immediate repair of digital nerves were “normal”, “excellent”, or “good” in 37–68% of the nerves repaired after a follow-up of 8–32 months.^{132–134,145,146} In terms of static two-point discrimination (S2PD), “normal” sensory function has been defined in these studies as the equivalent to the uninjured digit or S2PD of 5 mm or less, whereas “excellent” function has been defined as a S2PD of 7–10 mm. To summarize, after microsurgical repair of a digital nerve injury, about half improve to have normal or fair sensation.

Nerve trunks

The motor outcome of lesions to the larger nerve trunks seems to be dependent on their target organ. This is indicated by the results in a series of 1837 nerve lesions that outcome after repair (primary suture, secondary suture, or graft repair) of the median nerve was superior to the outcome of repair of lesions to the radial nerve, which in turn was better than that after ulnar nerve repair.¹⁴⁷ The better outcome of motor function in median nerves than in ulnar nerves is also supported by others.^{126,148,149} Recovery of sensation, on the other hand, has not been shown to differ between the median and ulnar nerves,¹²⁶ and combined median and ulnar nerve injuries.^{126,150,151} The theoretical explanation may be that the ulnar nerve innervates the delicate intrinsic muscles of the hand, and the demand of an accurate innervation is theoretically greater than that of the median or radial nerves that innervate muscles that do not undertake delicate movements to the same extent. However, it is difficult to compare the outcome after injury to various nerve trunks due to their individual characteristics.

Level of injury

Lesions that are more proximal have a worse outcome than more distal lesions.¹³⁸ This may be explained by the fact that a proximal injury induces a more severe impact on the individual neuron, with higher risk of neuronal cell death, and that the axons have to regenerate over a large distance to reach the targets.^{152,153}

Type of repair

In a study of 654 lesions of the ulnar nerve, the functional outcome (grade 3 or better) after suture repair (72%) was superior to that after graft repair (67%).^{147,154} In the same series, neurolysis was done for patients with ulnar entrapment, and in comparison these patients achieved a functional outcome of grade 3 or better in 92% of the repairs, indicating the importance of preserving the continuity of nerve trunks if possible. A nerve repair therefore achieves better results than a nerve graft.¹⁵⁵

Type of injury

Injuries with the nerve in continuity have a good prognosis, and so a nerve crush leads to better functional recovery than a transected nerve trunk. However, a transection injury can often be treated by a primary repair, whereas a crush injury, if it does not recover spontaneously, may require a nerve graft, which will lead to an impaired outcome.

Postoperative dysfunction

General aspects

Peripheral nerve injuries often have a dramatic impact on a person's capacity to function adequately, as the functional outcome often fails to reach the level of motor or sensory function present before the injury, at least in adults.^{138,156} As most nerve injuries in the upper extremity are seen in young men,^{34,157} there is a high probability of disability and subsequent social consequences.⁸ The accompanying amount of post-traumatic stress after hand and forearm injuries has been evaluated and shown to be comparable with the psychological distress found among survivors of big disasters.¹⁵⁸ Other symptoms, such as pain, dysesthesia, and cold intolerance,¹⁰ may also affect the outcome, and cause lifelong impairment of hand function. However, patients may have different strategies to cope with their injuries, whether it is a nerve injury or another serious hand injury.¹⁵⁹

Complex regional pain syndrome

Complex regional pain syndrome (CRPS) is a clinical diagnosis that involves regional pain together with autonomic dysfunction, functional impairment, and atrophy. According to the classification, CRPS type 1 occurs with no evidence of peripheral nerve injury, whereas CRPS type 2 requires known damage to nerve structures. CRPS can be a disabling condition in many cases, and about half of patients with untreated symptoms for more than a year will have extensive residual dysfunction. Cigarette smokers and women are at increased risk of CRPS, and even though it may occur at any age, most patients are around 45 years. During operation, common sites of injury to peripheral nerves that may elicit CRPS are damage to the dorsal branch of the ulnar nerve, the palmar cutaneous branch of the median nerve, and the superficial branch of the radial nerve. However, CRPS may be initiated after any type of nerve injury. The symptoms are pain that is often described as burning or aching, and it is usually induced by a small stimulus that in the normal patient would not result in such a response to pain. It may affect the tissues surrounding the area of injury, or the whole extremity. In addition, there may be some kind of trophic changes, such as edema and stiffness, together with changes of the skin, nails, and hair. The limb may be perceived as different in temperature from the opposite side.

Other

Numbness, weakness, and abnormal pain with or without discoloration after exposure to mild to severe pain can be problematic after peripheral nerve injury.^{160–162} In fact, cold intolerance is regarded by many authors as the most disabling symptom after nerve repair or other trauma to the upper extremity.^{10,163–165} The mechanism behind hypersensitivity to cold is not known, but its presence has been inversely correlated to sensory recovery.^{166–168} In addition, predictors associated with cold intolerance are coexisting injury to major vessels,^{167,169,170} crush injury,^{170,171} early postoperative pain,^{162,172} and the level of the nerve injury.¹⁶⁴

In a study by Ruijs *et al.* on 107 patients with median or ulnar nerve injury, or a combination of the two, numbness was

reported as the most frequent symptom (80%). Other symptoms were stiffness (77%), weakness (72%), pain (63%), change in skin color (50%), and swelling (33%). Most of the patients (59%) were considered to have abnormal cold intolerance. In this group, a larger proportion (70%) had combined ulnar and median nerve injuries, whereas isolated nerve injuries were less common (median nerve 57% and ulnar nerve 56%). Even though there was no difference in sensory recovery between women and men, cold intolerance was more common in women than in men. Importantly, time since injury did not correlate with the presence of cold intolerance (follow-up time 2–10 years).¹⁶⁸ This is also supported by other investigators,¹⁶⁵ indicating that cold intolerance is a stationary condition when the maximum sensory recovery has been achieved.

There is currently no treatment available that is specifically directed against cold intolerance, although possible effects of treatment by Pavlovian conditioning, a behavioral treatment for digital cold sensitivity where whole-body cold exposure becomes associated with warm hands, has been reported recently in patients with hand injuries.¹⁷³ In addition, CRPS may be a severely disabling condition that may be treated with substances like gabapentin and pregabalin¹⁷⁴ and other strategies.¹⁷⁵ This poses a pedagogic challenge to the treating physician when addressing the patient's expectations of the final outcome after nerve repair.

Future directions

Nerve injuries, extending from minor digital nerve injuries up to severe injuries to the brachial plexus in the upper extremity as well as less common injuries in the lower extremity, represent one of the most challenging clinical problems for the treating surgeons and physicians. A variety of factors influence outcome and each individual nerve injury is unique in its entity; thus each case also requires consideration of factors such as motivation for rehabilitation and coping strategies of the patient. Efforts to improve diagnostic tools and treatment strategies have to be directed towards all components. In the future, improved imaging techniques, like three-dimensional high-resolution magnetic resonance imaging with diffusion tensor imaging and tractography and pre- and intraoperative high-resolution sonography, may improve the diagnostic accuracy; however, an initial and appropriate basic clinical examination is still the key for early treatment. Proper evaluation systems are needed to examine fully new surgical and rehabilitation techniques, such as the nerve transfers, end-to-side repair and the EMLA concept (see above), respectively. In addition, a continuous search for the secrets of intracellular signaling in neurons, Schwann cells, and other cells may provide the knowledge needed for the introduction of pharmacological treatment, not only of any neuropathic pain, but also to improve regeneration as an adjunct to surgical repair and reconstruction. Hopefully genomic and proteomic development may lead to improved repair and reconstruction strategies, with or without utilization of stem cells in the future.¹⁷⁶

Acknowledgments

Financial support for this work was received from the Swedish Research Council (MEDICINE). We appreciate all the help from Professor Jørgen Tranum Jensen and his colleagues at the Panum Institute, University of Medicine and Dentistry, Copenhagen, Denmark.



Access the complete reference list online at <http://www.expertconsult.com>

3. Rosberg HE, Dahlin LB. Epidemiology of hand injuries in a middle-sized city in southern Sweden: a retrospective comparison of 1989 and 1997. *Scand J Plast Reconstr Surg Hand Surg*. 2004;38:347–355.
15. Sulaiman OA, Gordon T. Role of chronic Schwann cell denervation in poor functional recovery after nerve injuries and experimental strategies to combat it. *Neurosurgery*. 2009;65(suppl):105–114.
37. Dvali L, Mackinnon S. Nerve repair, grafting, and nerve transfers. *Clin Plast Surg*. 2003;30:203–221. *A comprehensive review of various techniques to repair and reconstruct injured peripheral nerve trunks.*
57. Millesi H. Techniques for nerve grafting. *Hand Clin*. 2000;16:73–91, viii. *The principles of nerve grafting provided by one of the pioneers in peripheral nerve surgery.*
87. Lundborg G, Rosen B, Dahlin L, et al. Tubular versus conventional repair of median and ulnar nerves in the human forearm: early results from a prospective, randomized, clinical study. *J Hand Surg Am*. 1997;22:99–106. *One of the few prospective randomized studies comparing microsurgical and tubular nerve repairs in humans.*
92. Weber RA, Breidenbach WC, Brown RE, et al. A randomized prospective study of polyglycolic acid conduits for digital nerve reconstruction in humans. *Plast Reconstr Surg*. 2000;106:1036–1045, discussion 1046–1038.
114. Merzenich MM, Jenkins WM. Reorganization of cortical representations of the hand following alterations of skin inputs induced by nerve injury, skin island transfers, and experience. *J Hand Ther*. 1993;6:89–104. *A classic paper from 1990s describing reorganization of the cerebral cortex by various manipulations such as nerve injury.*
126. Ruijs AC, Jaquet JB, Kalmijn S, et al. Median and ulnar nerve injuries: a meta-analysis of predictors of motor and sensory recovery after modern microsurgical nerve repair. *Plast Reconstr Surg*. 2005;116:484–494, discussion 495–486.
128. Rosen B, Lundborg G. A model instrument for the documentation of outcome after nerve repair. *J Hand Surg Am*. 2000;25:535–543. *A specific evaluation instrument to evaluate outcome after median and ulnar nerve repairs, enabling a score and suitable for follow-up of the individual patient and particularly in clinical trials.*
131. Dellon AL, Curtis RM, Edgerton MT. Reeducation of sensation in the hand after nerve injury and repair. *Plast Reconstr Surg*. 1974;53:297–305.
159. Cederlund RI, Ramel E, Rosberg HE, et al. Outcome and clinical changes in patients 3, 6, 12 months after a severe or major hand injury – Can sense of coherence be an indicator for rehabilitation focus? *BMC Musculoskelet Disord*. 2010;11:286.

References

- Chemnitz A, Dahlin LB, Carlsson IK. Consequences and adaptation in daily life – patients' experiences three decades after a nerve injury sustained in adolescence. *BMC Musculoskelet Disord*. 2013;14:252.
- Rosberg HE, Carlsson KS, Hojgard S, et al. Injury to the human median and ulnar nerves in the forearm – analysis of costs for treatment and rehabilitation of 69 patients in southern Sweden. *J Hand Surg [Br]*. 2005;30:35–39.
- Rosberg HE, Dahlin LB. Epidemiology of hand injuries in a middle-sized city in southern Sweden: a retrospective comparison of 1989 and 1997. *Scand J Plast Reconstr Surg Hand Surg*. 2004;38:347–355.
- Ljungberg E, Rosberg HE, Dahlin LB. Hand injuries in young children. *J Hand Surg [Br]*. 2003;28:376–380.
- Asplund M, Nilsson M, Jacobsson A, et al. Incidence of traumatic peripheral nerve injuries and amputations in Sweden between 1998 and 2006. *Neuroepidemiology*. 2009;32:217–228.
- Ekholm R, Adami J, Tidermark J, et al. Fractures of the shaft of the humerus. An epidemiological study of 401 fractures. *J Bone Joint Surg Br*. 2006;88:1469–1473.
- Bruyins CN, Jaquet JB, Schreuders TA, et al. Predictors for return to work in patients with median and ulnar nerve injuries. *J Hand Surg Am*. 2003;28:28–34.
- Jaquet JB, Luijsterburg AJ, Kalmijn S, et al. Median, ulnar, and combined median–ulnar nerve injuries: functional outcome and return to productivity. *J Trauma*. 2001;51:687–692.
- Onne L. Recovery of sensibility and sudomotor activity in the hand after nerve suture. *Acta Chir Scand Suppl*. 1962;(suppl 300):1–69.
- Carlsson IK, Nilsson JA, Dahlin LB. Cut-off value for self-reported abnormal cold sensitivity and predictors for abnormality and severity in hand injuries. *J Hand Surg Eur Vol*. 2010;35:409–416.
- Berthold C, Fraher J, King RH, et al. Microscopic anatomy of the peripheral nervous system. In: Dyck PJ, Thomas PK, eds. *Peripheral Neuropathy*. Philadelphia, PA: Elsevier Saunders; 2005:35–91.
- Geuna S, Raimondo S, Ronchi G, et al. Chapter 3: Histology of the peripheral nerve and changes occurring during nerve regeneration. *Int Rev Neurobiol*. 2009;87:27–46.
- Jabaley ME, Wallace WH, Heckler FR. Internal topography of major nerves of the forearm and hand: a current view. *J Hand Surg Am*. 1980;5:1–18.
- Torebjork HE, Ochoa JL. Specific sensations evoked by activity in single identified sensory units in man. *Acta Physiol Scand*. 1980;110:445–447.
- Sulaiman OA, Gordon T. Role of chronic Schwann cell denervation in poor functional recovery after nerve injuries and experimental strategies to combat it. *Neurosurgery*. 2009;65(suppl):105–114.
- Xu QG, Forden J, Walsh SK, et al. Motoneuron survival after chronic and sequential peripheral nerve injuries in the rat. *J Neurosurg*. 2010;112:890–899.
- Saito H, Kanje M, Dahlin LB. Delayed nerve repair increases number of caspase 3 stained Schwann cells. *Neurosci Lett*. 2009;456:30–33.
- Kalil K, Dent EW. Touch and go: guidance cues signal to the growth cone cytoskeleton. *Curr Opin Neurobiol*. 2005;15:521–526.
- Zhou FQ, Cohan CS. How actin filaments and microtubules steer growth cones to their targets. *J Neurobiol*. 2004;58:84–91.
- Seddon H. Three types of nerve injury. *Brain*. 1943;66:237.
- Sunderland S. A classification of peripheral nerve injuries producing loss of function. *Brain*. 1951;74:491–516.
- Mackinnon SE. New directions in peripheral nerve surgery. *Ann Plast Surg*. 1989;22:257–273.
- Wilbourn AJ. The electrodiagnostic examination with peripheral nerve injuries. *Clin Plast Surg*. 2003;30:139–154.
- Kline D, Hudson A. Nerve action potential recordings. In: Kline D, Hudson A, eds. *Nerve Injuries*. Philadelphia, PA: WB Saunders; 1995:101–116.
- Siemionow M, Sari A. A contemporary overview of peripheral nerve research from the Cleveland Clinic microsurgery laboratory. *Neurol Res*. 2004;26:218–225.
- Spinner RJ, Kline DG. Surgery for peripheral nerve and brachial plexus injuries or other nerve lesions. *Muscle Nerve*. 2000;23:680–695.
- DeFranco MJ, Lawton JN. Radial nerve injuries associated with humeral fractures. *J Hand Surg Am*. 2006;31:655–663.
- Campbell WW. Evaluation and management of peripheral nerve injury. *Clin Neurophysiol*. 2008;119:1951–1965.
- Birch R, Raji AR. Repair of median and ulnar nerves. Primary suture is best. *J Bone Joint Surg Br*. 1991;73:154–157.
- Yi C, Dahlin LB. Impaired nerve regeneration and Schwann cell activation after repair with tension. *Neuroreport*. 2010;21:958–962.
- Clark WL, Trumble TE, Swiontkowski MF, et al. Nerve tension and blood flow in a rat model of immediate and delayed repairs. *J Hand Surg Am*. 1992;17:677–687.
- Schmidhammer R, Zandieh S, Hopf R, et al. Alleviated tension at the repair site enhances functional regeneration: the effect of full range of motion mobilization on the regeneration of peripheral nerves – histologic, electrophysiologic, and functional results in a rat model. *J Trauma*. 2004;56:571–584.
- Millesi H. Nerve grafts: indications, techniques, and prognoses. In: Omer GE, Spinner M, van Beek AL, eds. *Management of Peripheral Nerve Problems*. 2nd ed. Philadelphia, PA: W.B. Saunders; 1998:280–289.
- McAllister RM, Gilbert SE, Calder JS, et al. The epidemiology and management of upper limb peripheral nerve injuries in modern practice. *J Hand Surg [Br]*. 1996;21:4–13.
- de Medinaceli L, Prayon M, Merle M. Percentage of nerve injuries in which primary repair can be achieved by end-to-end approximation: review of 2,181 nerve lesions. *Microsurgery*. 1993;14:244–246.
- Dahlin LB. Techniques of peripheral nerve repair. *Scand J Surg*. 2008;97:310–316.
- Dvali L, Mackinnon S. Nerve repair, grafting, and nerve transfers. *Clin Plast Surg*. 2003;30:203–221. *A comprehensive review of various techniques to repair and reconstruct injured peripheral nerve trunks*.
- Dahlin LB. The role of timing in nerve reconstruction. *Int Rev Neurobiol*. 2013;109:151–164.
- McLellan DL, Swash M. Longitudinal sliding of the median nerve during movements of the upper limb. *J Neurol Neurosurg Psychiatry*. 1976;39:566–570.
- Wilgis EF, Murphy R. The significance of longitudinal excursion in peripheral nerves. *Hand Clin*. 1986;2:761–766.
- Lundborg G, Rydevik B. Effects of stretching the tibial nerve of the rabbit. A preliminary study of the intraneural circulation and the barrier function of the perineurium. *J Bone Joint Surg Br*. 1973;55:390–401.
- Ogata K, Naito M. Blood flow of peripheral nerve effects of dissection, stretching and compression. *J Hand Surg [Br]*. 1986;11:10–14.
- Lundborg G. Ischemic nerve injury. Experimental studies on intraneural microvascular pathophysiology and nerve function in a limb subjected to temporary circulatory arrest. *Scand J Plast Reconstr Surg Suppl*. 1970;6:3–113.
- Maki Y, Firrell JC, Breidenbach WC. Blood flow in mobilized nerves: results in a rabbit sciatic nerve model. *Plast Reconstr Surg*. 1997;100:627–633, discussion 634–625.
- Shaw Wilgis EF. Epineurial Repair: Technique and long-term results. In: Omer GE, Spinner M, van Beek AL, eds. *Management of Peripheral Nerve Problems*. 2nd ed. Philadelphia, PA: W.B. Saunders; 1998:271–273.
- Whitlock EL, Kasukurthi R, Yan Y, et al. Fibrin glue mitigates the learning curve of microneurosurgical repair. *Microsurgery*. 2010;3:218–222.
- Martins RS, Siqueira MG, Da Silva CF, et al. Overall assessment of regeneration in peripheral nerve lesion repair using fibrin glue, suture, or a combination of the 2 techniques in a rat model. Which

- is the ideal choice? *Surg Neurol.* 2005;64(suppl 1):10–16, discussion S11:16.
48. Brushart TM, Tarlov EC, Mesulam MM. Specificity of muscle reinnervation after epineurial and individual fascicular suture of the rat sciatic nerve. *J Hand Surg Am.* 1983;8:248–253.
 49. Grabb WC, Bement SL, Koepke GH, et al. Comparison of methods of peripheral nerve suturing in monkeys. *Plast Reconstr Surg.* 1970;46:31–38.
 50. Viterbo F, Franciosi LF, Palhares A. Nerve graftings and end-to-side neurorrhaphies connecting the phrenic nerve to the brachial plexus. *Plast Reconstr Surg.* 1995;96:494–495.
 51. Bontioti E, Kanje M, Lundborg G, et al. End-to-side nerve repair in the upper extremity of rat. *J Peripher Nerv Syst.* 2005;10:58–68.
 52. Bontioti E, Dahlin LB, Kataoka K, et al. End-to-side nerve repair induces nuclear translocation of activating transcription factor 3. *Scand J Plast Reconstr Surg Hand Surg.* 2006;40:321–328.
 53. Tos P, Colzani G, Ciclamini D, et al. Clinical applications of end-to-side neurorrhaphy: an update. *Biomed Res Int.* 2014;2014:646128.
 54. Paprottka FJ, Wolf P, Harder Y, et al. Sensory recovery outcome after digital nerve repair in relation to different reconstructive techniques: meta-analysis and systematic review. *Plast Surg Int.* 2013;2013:704589.
 55. Pannucci C, Myckatyn TM, Mackinnon SE, et al. End-to-side nerve repair: review of the literature. *Restor Neurol Neurosci.* 2007;25:45–63.
 56. Schmidhammer R, Nogradi A, Szabo A, et al. Synergistic motor nerve fiber transfer between different nerves through the use of end-to-side coaptation. *Exp Neurol.* 2009;217:388–394.
 57. Millesi H. Techniques for nerve grafting. *Hand Clin.* 2000;16:73–91, viii. *The principles of nerve grafting provided by one of the pioneers in peripheral nerve surgery.*
 58. Almgren KG. Revascularization of free peripheral nerve grafts. An experimental study in the rabbit. *Acta Orthop Scand Suppl.* 1975;154:1–104.
 59. Birch R. Nerve repair. In: Green H, Pederson RN, Wolfe WC, eds. *Green's Operative Hand Surgery.* Vol. 1. Philadelphia, PA: Elsevier; 2005:1075–1112.
 60. Hallgren A, Björkman A, Chemnitz A, et al. Subjective outcome related to donor site morbidity after sural nerve graft harvesting: a survey in 41 patients. *BMC Surg.* 2013;13:39.
 61. de Moura W, Gilbert A. Surgical anatomy of the sural nerve. *J Reconstr Microsurg.* 1984;1:31–39.
 62. Hallock GG. Endoscopic retrieval of the sural nerve. *J Reconstr Microsurg.* 1995;11:347–350.
 63. Thomsen NO, Mojaddidi M, Malik RA, et al. Biopsy of the posterior interosseous nerve: a low morbidity method for assessment of peripheral nerve disorders. *Diabet Med.* 2009;26:100–104.
 64. Stang F, Stollwerck P, Prommersberger KJ, et al. Posterior interosseous nerve vs. medial cutaneous nerve of the forearm: differences in digital nerve reconstruction. *Arch Orthop Trauma Surg.* 2013;133:875–880.
 65. Chiono V, Tonda-Turo C, Ciardelli G. Chapter 9: Artificial scaffolds for peripheral nerve reconstruction. *Int Rev Neurobiol.* 2009;87:173–198.
 66. Battiston B, Geuna S, Ferrero M, et al. Nerve repair by means of tubulization: literature review and personal clinical experience comparing biological and synthetic conduits for sensory nerve repair. *Microsurgery.* 2005;25:258–267.
 67. Glück T. Über neuroplastische auf dem wege der transplantation. *Arch Klin Chir.* 1880;25:606.
 68. Chiu DT, Janecka I, Krizek TJ, et al. Autogenous vein graft as a conduit for nerve regeneration. *Surgery.* 1982;91:226–233.
 69. Walton RL, Brown RE, Matory WE Jr, et al. Autogenous vein graft repair of digital nerve defects in the finger: a retrospective clinical study. *Plast Reconstr Surg.* 1989;84:944–949, discussion 950–942.
 70. Itoh S, Shinomiya K, Samejima H, et al. Experimental study on nerve regeneration through the basement membrane tubes of the nerve, muscle, and artery. *Microsurgery.* 1996;17:525–534.
 71. Brandt J, Dahlin LB, Lundborg G. Autologous tendons used as grafts for bridging peripheral nerve defects. *J Hand Surg [Br].* 1999;24:284–290.
 72. Geuna S, Tos P, Battiston B, et al. Bridging peripheral nerve defects with muscle–vein combined guides. *Neurol Res.* 2004;26:139–144.
 73. Brunelli GA, Battiston B, Vigasio A, et al. Bridging nerve defects with combined skeletal muscle and vein conduits. *Microsurgery.* 1993;14:247–251.
 74. Sondell M, Lundborg G, Kanje M. Vascular endothelial growth factor stimulates Schwann cell invasion and neovascularization of acellular nerve grafts. *Brain Res.* 1999;846:219–228.
 75. Karabekmez FE, Duymaz A, Moran SL. Early clinical outcomes with the use of decellularized nerve allograft for repair of sensory defects within the hand. *Hand (N Y).* 2009;4:245–249.
 76. Whitlock EL, Tuffaha SH, Luciano JP, et al. Processed allografts and type I collagen conduits for repair of peripheral nerve gaps. *Muscle Nerve.* 2009;39:787–799.
 77. Manoli T, Schulz L, Stahl S, et al. Evaluation of sensory recovery after reconstruction of digital nerves of the hand using muscle-in-vein conduits in comparison to nerve suture or nerve autografting. *Microsurgery.* 2014;34:608–615.
 78. Taras JS, Amin N, Patel N, et al. Allograft reconstruction for digital nerve loss. *J Hand Surg Am.* 2013;38:1965–1971.
 79. Cho MS, Rinker BD, Weber RV, et al. Functional outcome following nerve repair in the upper extremity using processed nerve allograft. *J Hand Surg Am.* 2012;37:2340–2349.
 80. Karabekmez FE, Duymaz A, Moran SL. Early clinical outcomes with the use of decellularized nerve allograft for repair of sensory defects within the hand. *Hand (N Y).* 2009;4:245–249.
 81. Kvist M, Sondell M, Kanje M, et al. Regeneration in, and properties of, extracted peripheral nerve allografts and xenografts. *J Plast Surg Hand Surg.* 2011;45:122–128.
 82. Neubauer D, Graham JB, Muir D. Nerve grafts with various sensory and motor fiber compositions are equally effective for the repair of a mixed nerve defect. *Exp Neurol.* 2010;223:203–206.
 83. Rinker BD, Ingari JV, Greenberg JA, et al. Outcomes of short-gap sensory nerve injuries reconstructed with processed nerve allografts from a multicenter registry study. *J Reconstr Microsurg.* 2015;31:384–390.
 84. Lundborg G, Dahlin LB, Danielsen N, et al. Nerve regeneration in silicone chambers: influence of gap length and of distal stump components. *Exp Neurol.* 1982;76:361–375.
 85. Wang-Bennett LT, Coker NJ. Analysis of axonal regeneration through the silicone regeneration chamber: a retrograde tracing study in the rabbit facial nerve. *Exp Neurol.* 1990;107:222–229.
 86. Dahlin LB, Anagnostaki L, Lundborg G. Tissue response to silicone tubes used to repair human median and ulnar nerves. *Scand J Plast Reconstr Surg Hand Surg.* 2001;35:29–34.
 87. Lundborg G, Rosen B, Dahlin L, et al. Tubular versus conventional repair of median and ulnar nerves in the human forearm: early results from a prospective, randomized, clinical study. *J Hand Surg Am.* 1997;22:99–106. *One of the few prospective randomized studies comparing microsurgical and tubular nerve repairs in humans.*
 88. Lundborg G, Rosen B, Dahlin L, et al. Tubular repair of the median or ulnar nerve in the human forearm: a 5-year follow-up. *J Hand Surg [Br].* 2004;29:100–107.
 89. Teixeira AI, Duckworth JK, Hermanson O. Getting the right stuff: controlling neural stem cell state and fate in vivo and in vitro with biomaterials. *Cell Res.* 2007;17:56–61.
 90. Lietz M, Dreesmann L, Hoss M, et al. Neuro tissue engineering of glial nerve guides and the impact of different cell types. *Biomaterials.* 2006;27:1425–1436.
 91. Haastert-Talini K, Geuna S, Dahlin LB, et al. Chitosan tubes of varying degrees of acetylation for bridging peripheral nerve defects. *Biomaterials.* 2013;34:9886–9904.
 92. Weber RA, Breidenbach WC, Brown RE, et al. A randomized prospective study of polyglycolic acid conduits for digital nerve reconstruction in humans. *Plast Reconstr Surg.* 2000;106:1036–1045, discussion 1046–1038.

93. Bushnell BD, McWilliams AD, Whitener GB, et al. Early clinical experience with collagen nerve tubes in digital nerve repair. *J Hand Surg Am*. 2008;33:1081–1087.
94. Taras JS, Jacoby SM. Repair of lacerated peripheral nerves with nerve conduits. *Tech Hand Up Extrem Surg*. 2008;12:100–106.
95. Mackinnon SE, Dellon AL. Clinical nerve reconstruction with a bioabsorbable polyglycolic acid tube. *Plast Reconstr Surg*. 1990;85:419–424.
96. Rosson GD, Williams EH, Dellon AL. Motor nerve regeneration across a conduit. *Microsurgery*. 2009;29:107–114.
97. Navissano M, Malan F, Carnino R, et al. Neurotube for facial nerve repair. *Microsurgery*. 2005;25:268–271.
98. Boeckstyns ME, Sørensen AI, Viñeta JF, et al. Collagen conduit versus microsurgical neurorrhaphy: 2-year follow-up of a prospective, blinded clinical and electrophysiological multicenter randomized, controlled trial. *J Hand Surg Am*. 2013;38:2405–2411.
99. Lohmeyer JA, Kern Y, Schmauss D, et al. Prospective clinical study on digital nerve repair with collagen nerve conduits and review of literature. *J Reconstr Microsurg*. 2014;30:227–234.
100. Pfister LA, Papaloizos M, Merkle HP, et al. Nerve conduits and growth factor delivery in peripheral nerve repair. *J Peripher Nerv Syst*. 2007;12:65–82.
101. Guenard V, Kleitman N, Morrissey TK, et al. Syngeneic Schwann cells derived from adult nerves seeded in semipermeable guidance channels enhance peripheral nerve regeneration. *J Neurosci*. 1992;12:3310–3320.
102. Terenghi G, Wiberg M, Kingham PJ. Chapter 21: Use of stem cells for improving nerve regeneration. *Int Rev Neurobiol*. 2009;87:393–403.
103. Brandt J, Nilsson A, Kanje M, et al. Acutely-dissociated Schwann cells used in tendon autografts for bridging nerve defects in rats: a new principle for tissue engineering in nerve reconstruction. *Scand J Plast Reconstr Surg Hand Surg*. 2005;39:321–325.
104. Scherman P, Kanje M, Dahlin LB. Sutures as longitudinal guides for the repair of nerve defects – influence of suture numbers and reconstruction of nerve bifurcations. *Restor Neurol Neurosci*. 2005;23:79–85.
105. Moore AM, Franco M, Tung TH. Motor and sensory nerve transfers in the forearm and hand. *Plast Reconstr Surg*. 2014;134:721–730.
106. Mackinnon SE, Novak CB. Nerve transfers. New options for reconstruction following nerve injury. *Hand Clin*. 1999;15:643–666, ix.
107. Brown JM, Shah MN, Mackinnon SE. Distal nerve transfers: a biology-based rationale. *Neurosurg Focus*. 2009;26:E12.
108. Dahlin LB, Cöster M, Björkman A, et al. Axillary nerve injury in young adults – an overlooked diagnosis? Early results of nerve reconstruction and nerve transfers. *J Plast Surg Hand Surg*. 2012;46:257–261.
109. Millesi H. The nerve gap. Theory and clinical practice. *Hand Clin*. 1986;2:651–663.
110. Steinberg D, Koman L. Factors affecting the results of peripheral nerve repair. In: Gelberman RH, ed. *Operative Nerve Repair and Reconstruction*. Philadelphia, PA: JB Lippincott; 1991:349–364.
111. Lee WP, Constantinescu MA, Butler PE. Effect of early mobilization on healing of nerve repair: histologic observations in a canine model. *Plast Reconstr Surg*. 1999;104:1718–1725.
112. Winograd JM, MacKinnon SE. Peripheral nerve injuries: repair and reconstruction. In: Mathes SJ, ed. *Plastic Surgery*. Vol. 7. Philadelphia, PA: Saunders Elsevier; 2006:471–514.
113. Rosén B, Chemnitz A, Weibull A, et al. Cerebral changes after injury to the median nerve: a long-term follow up. *J Plast Surg Hand Surg*. 2012;46:106–112.
114. Merzenich MM, Jenkins WM. Reorganization of cortical representations of the hand following alterations of skin inputs induced by nerve injury, skin island transfers, and experience. *J Hand Ther*. 1993;6:89–104. A classic paper from 1990s describing reorganization of the cerebral cortex by various manipulations such as nerve injury.
115. Lundborg G. *Nerve Injury and Repair. Regeneration, Reconstruction and Cortical Remodeling*. 2nd ed. Philadelphia, PA: Elsevier; 2004.
116. Rosen B, Lundborg G. Sensory re-education following nerve repair. In: Slutsky D, ed. *Upper Extremity Nerve Repair – Tips and Techniques: A Master Skills Publication*. Rosemont, IL: American Society for Surgery of the Hand; 2008:159–178.
117. Silva AC, Rasey SK, Wu X, et al. Initial cortical reactions to injury of the median and radial nerves to the hands of adult primates. *J Comp Neurol*. 1996;366:700–716.
118. Lundborg G, Björkman A. Cortical effects of nerve injury. In: Slutsky DJ, ed. *Upper Extremity Nerve Repair – Tips and Techniques: A Master Skills Publication*. Rosemont, IL: American Society for Surgery of the Hand; 2008:29–37.
119. Imai H, Tajima T, Natsumi Y. Successful reeducation of functional sensibility after median nerve repair at the wrist. *J Hand Surg Am*. 1991;16:60–65.
120. Rizzolatti G, Craighero L. The mirror-neuron system. *Annu Rev Neurosci*. 2004;27:169–192.
121. Lundborg G, Rosen B, Lindberg S. Hearing as substitution for sensation: a new principle for artificial sensibility. *J Hand Surg Am*. 1999;24:219–224.
122. Rosén B, Chemnitz A, Weibull A, et al. Cerebral changes after injury to the median nerve: a long-term follow up. *J Plast Surg Hand Surg*. 2012;46:106–112.
123. Rosen B, Björkman A, Lundborg G. Improved sensory relearning after nerve repair induced by selective temporary anaesthesia – a new concept in hand rehabilitation. *J Hand Surg [Br]*. 2006;31:126–132.
124. Lundborg G, Björkman A, Rosen B. Enhanced sensory relearning after nerve repair by using repeated forearm anaesthesia: aspects on time dynamics of treatment. *Acta Neurochir Suppl*. 2007;100:121–126.
125. Rosen B, Dahlin LB, Lundborg G. Assessment of functional outcome after nerve repair in a longitudinal cohort. *Scand J Plast Reconstr Surg Hand Surg*. 2000;34:71–78.
126. Ruijs AC, Jaquet JB, Kalmijn S, et al. Median and ulnar nerve injuries: a meta-analysis of predictors of motor and sensory recovery after modern microsurgical nerve repair. *Plast Reconstr Surg*. 2005;116:484–494, discussion 495–486.
127. Medical Research Council. Nerve Injuries Committee. Results of nerve suture. In: Seddon H, ed. *Peripheral Nerve Injuries*. London: Her Majesty's Stationery Office; 1954.
128. Rosen B, Lundborg G. A model instrument for the documentation of outcome after nerve repair. *J Hand Surg Am*. 2000;25:535–543. A specific evaluation instrument to evaluate outcome after median and ulnar nerve repairs, enabling a score and suitable for follow-up of the individual patient and particularly in clinical trials.
129. Rosen B. Recovery of sensory and motor function after nerve repair. A rationale for evaluation. *J Hand Ther*. 1996;9:315–327.
130. Novak CB, Kelly L, Mackinnon SE. Sensory recovery after median nerve grafting. *J Hand Surg Am*. 1992;17:59–68.
131. Dellon AL, Curtis RM, Edgerton MT. Reeducation of sensation in the hand after nerve injury and repair. *Plast Reconstr Surg*. 1974;53:297–305.
132. al-Ghazal SK, McKiernan M, Khan K, et al. Results of clinical assessment after primary digital nerve repair. *J Hand Surg [Br]*. 1994;19:255–257.
133. Chaise F, Friol JP, Gaisne E. Results of emergency repair of wounds of palmar collateral nerves of the fingers. *Rev Chir Orthop Reparatrice Appar Mot*. 1993;79:393–397.
134. Efstathopoulos D, Gerostathopoulos N, Mitsizis D, et al. Clinical assessment of primary digital nerve repair. *Acta Orthop Scand Suppl*. 1995;264:45–47.
135. Hudson DA, Bolitho DG, Hodgetts K. Primary epineural repair of the median nerve in children. *J Hand Surg [Br]*. 1997;22:54–56.
136. Hudson DA, de Jager LT. The spaghetti wrist. Simultaneous laceration of the median and ulnar nerves with flexor tendons at the wrist. *J Hand Surg [Br]*. 1993;18:171–173.

137. Polatkan S, Orhun E, Polatkan O, et al. Evaluation of the improvement of sensibility after primary median nerve repair at the wrist. *Microsurgery*. 1998;18:192–196.
138. Bolitho DG, Boustred M, Hudson DA, et al. Primary epineural repair of the ulnar nerve in children. *J Hand Surg Am*. 1999;24:16–20.
139. Lundborg G, Rosen B. Sensory relearning after nerve repair. *Lancet*. 2001;358:809–810.
140. Fornander L, Nyman T, Hansson T, et al. Age- and time-dependent effects on functional outcome and cortical activation pattern in patients with median nerve injury: a functional magnetic resonance imaging study. *J Neurosurg*. 2010;113:122–128.
141. Lundborg G, Rosen B. Hand function after nerve repair. *Acta Physiol (Oxf)*. 2007;189:207–217.
142. Chemnitz A, Björkman A, Dahlin LB, et al. Functional outcome thirty years after median and ulnar nerve repair in childhood and adolescence. *J Bone Joint Surg Am*. 2013;95:329–337.
143. Chemnitz A, Andersson G, Rosén B, et al. Poor electroneurography but excellent hand function 31 years after nerve repair in childhood. *Neuroreport*. 2013;24:6–9.
144. Chemnitz A, Weibull A, Rosén B, et al. Normalized activation in the somatosensory cortex 30 years following nerve repair in children: an fMRI study. *Eur J Neurosci*. 2015;42:2022–2027.
145. Sullivan DJ. Results of digital neurorrhaphy in adults. *J Hand Surg [Br]*. 1985;10:41–44.
146. Wang WZ, Crain GM, Baylis W, et al. Outcome of digital nerve injuries in adults. *J Hand Surg Am*. 1996;21:138–143.
147. Murovic JA. Upper-extremity peripheral nerve injuries: a Louisiana State University Health Sciences Center literature review with comparison of the operative outcomes of 1837 Louisiana State University Health Sciences Center median, radial, and ulnar nerve lesions. *Neurosurgery*. 2009;65(suppl):11–17.
148. Deutinger M, Girsch W, Burggasser G, et al. Peripheral nerve repair in the hand with and without motor sensory differentiation. *J Hand Surg Am*. 1993;18:426–432.
149. Rosen B, Lundborg G. The long term recovery curve in adults after median or ulnar nerve repair: a reference interval. *J Hand Surg [Br]*. 2001;26:196–200.
150. Kabak S, Halici M, Baktir A, et al. Results of treatment of the extensive volar wrist lacerations: “the spaghetti wrist”. *Eur J Emerg Med*. 2002;9:71–76.
151. Noaman HH. Management and functional outcomes of combined injuries of flexor tendons, nerves, and vessels at the wrist. *Microsurgery*. 2007;27:536–543.
152. Hart AM, Terenghi G, Wiberg M. Neuronal death after peripheral nerve injury and experimental strategies for neuroprotection. *Neurol Res*. 2008;30:999–1011.
153. Ygge J. Neuronal loss in lumbar dorsal root ganglia after proximal compared to distal sciatic nerve resection: a quantitative study in the rat. *Brain Res*. 1989;478:193–195.
154. Kim DH, Han K, Tiel RL, et al. Surgical outcomes of 654 ulnar nerve lesions. *J Neurosurg*. 2003;98:993–1004.
155. Bontioti EN, Kanje M, Dahlin LB. Regeneration and functional recovery in the upper extremity of rats after various types of nerve injuries. *J Peripher Nerv Syst*. 2003;8:159–168.
156. Allan CH. Functional results of primary nerve repair. *Hand Clin*. 2000;16:67–72.
157. Noble J, Munro CA, Prasad VS, et al. Analysis of upper and lower extremity peripheral nerve injuries in a population of patients with multiple injuries. *J Trauma*. 1998;45:116–122.
158. Jaquet JB, Kalmijn S, Kuypers PD, et al. Early psychological stress after forearm nerve injuries: a predictor for long-term functional outcome and return to productivity. *Ann Plast Surg*. 2002;49:82–90.
159. Cederlund RI, Ramel E, Rosberg HE, et al. Outcome and clinical changes in patients 3, 6, 12 months after a severe or major hand injury – Can sense of coherence be an indicator for rehabilitation focus? *BMC Musculoskelet Disord*. 2010;11:286.
160. Campbell DA, Kay SP. What is cold intolerance? *J Hand Surg [Br]*. 1998;23:3–5.
161. Engkvist O, Wahren LK, Wallin G, et al. Effects of regional intravenous guanethidine block in posttraumatic cold intolerance in hand amputees. *J Hand Surg [Br]*. 1985;10:145–150.
162. Koman LA, Slone SA, Smith BP, et al. Significance of cold intolerance in upper extremity disorders. *J South Orthop Assoc*. 1998;7:192–197.
163. Backman C, Nystrom A, Bjerle P. Arterial spasticity and cold intolerance in relation to time after digital replantation. *J Hand Surg [Br]*. 1993;18:551–555.
164. Nancarrow JD, Rai SA, Sterne GD, et al. The natural history of cold intolerance of the hand. *Injury*. 1996;27:607–611.
165. Povlsen B, Nylander G, Nylander E. Cold-induced vasospasm after digital replantation does not improve with time. A 12-year prospective study. *J Hand Surg [Br]*. 1995;20:237–239.
166. Kay S. Venous occlusion plethysmography in patients with cold related symptoms after digital salvage procedures. *J Hand Surg [Br]*. 1985;10:151–154.
167. Koman LA, Nunley JA. Thermoregulatory control after upper extremity replantation. *J Hand Surg Am*. 1986;11:548–552.
168. Ruijs AC, Jaquet JB, van Riel WG, et al. Cold intolerance following median and ulnar nerve injuries: prognosis and predictors. *J Hand Surg Eur Vol*. 2007;32:434–439.
169. Craigen M, Kleinert JM, Crain GM, et al. Patient and injury characteristics in the development of cold sensitivity of the hand: a prospective cohort study. *J Hand Surg Am*. 1999;24:8–15.
170. Irwin MS, Gilbert SE, Terenghi G, et al. Cold intolerance following peripheral nerve injury. Natural history and factors predicting severity of symptoms. *J Hand Surg [Br]*. 1997;22:308–316.
171. Isogai N, Fukunishi K, Kamiishi H. Patterns of thermoregulation associated with cold intolerance after digital replantation. *Microsurgery*. 1995;16:556–565.
172. de Medinaceli L, Hurpeau J, Merle M, et al. Cold and post-traumatic pain: modeling of the peripheral nerve message. *Biosystems*. 1997;43:145–167.
173. Carlsson I, Cederlund R, Holmberg J, et al. Behavioural treatment of post-traumatic and vibration-induced digital cold sensitivity. *Scand J Plast Reconstr Surg Hand Surg*. 2003;3:371–378.
174. Gordh TE, Stubhaug A, Jensen TS, et al. Gabapentin in traumatic nerve injury pain: a randomized, double-blind, placebo-controlled, cross-over, multi-center study. *Pain*. 2008;138:255–266.
175. Vranken JH. Mechanisms and treatment of neuropathic pain. *Cent Nerv Syst Agents Med Chem*. 2009;9:71–78.
176. Dahlin L, Johansson F, Lindwall C, et al. Chapter 28: Future perspective in peripheral nerve reconstruction. *Int Rev Neurobiol*. 2009;87:507–530.

33

Nerve transfers

Kirsty Usher Boyd, Ida K. Fox, and Susan E. Mackinnon

 Access video lecture content for this chapter online at expertconsult.com

SYNOPSIS

- Nerve injuries are often devastating, with associated pain and impaired function.
- Motor nerve injuries must be managed expeditiously, because regenerating axons must reach target muscle prior to degeneration and fibrosis – “time is muscle”.
- Nerve transfers offer an advantageous method of reconstruction by delivering regenerating nerve fibers to the target end organ more quickly, thus converting a proximal injury to a more distal injury.
- Nerve transfers allow for dissection outside the original zone of injury, providing a safer and more technically straightforward procedure.
- Unlike tendon transfers, the muscle–tendon biomechanical structure is preserved, thus excursion, origin, insertion, and length–tension relationships are undisturbed.
- Nerve transfers require time for the nerve to regenerate and extensive physical therapy for retraining.
- Intraneural dissection is technically demanding, and nerve transfers require intimate knowledge of nerve topography.

Key points

- Nerve transfers are a relatively recent development in peripheral nerve surgery.
- Nerve transfers can be performed to restore sensory or motor deficits.
- Nerve transfers essentially convert a proximal injury to a distal injury, providing a source of regenerating axons in close proximity to the end target.
- Nerve transfers are associated with minimal to no downgrade in donor function.
- Nerve transfers preserve the original biomechanical muscle–tendon relationship.
- Nerve transfers may provide superior results to tendon transfer, with the ability to restore individual and separate muscle function.

- Nerve transfers are replacing other techniques as the gold standard for brachial plexus and other peripheral nerve injury in the authors’ practice.
- New applications of nerve transfers to pediatrics, lower extremity injury, partial injury (through supercharging or other end-to-side techniques), and central nervous system disorders (spinal cord injury and transverse myelitis) are exciting.

Introduction

While peripheral nerve reconstruction is an evolving field, nerve transfers have become a more broadly accepted reconstructive option.^{1–3} As our understanding of internal nerve topography improves, we are able to recognize redundant or non-essential potential donor nerves and fascicles. Recent contributions in basic science are broadening options for nerve transfer with new and improved techniques. Clinical research focusing on outcomes, applications to novel populations, and areas of debate continue to advance the field. This chapter will outline the history and principles of nerve transfers as they pertain to upper extremity nerve reconstruction. The recent literature as it relates to current techniques, debates, and advances in nerve transfers will be reviewed. Current commonly performed nerve transfers are detailed with focus on both motor and sensory nerve transfers, their indications, rehabilitation and postoperative protocols, and a basic overview of selected surgical techniques⁴ (see key points, above).



Access the Historical perspective section online at

<http://www.expertconsult.com>

Table 33.1 appears online only.

Historical perspective

The classification of nerve injury is perhaps the single most important factor when determining management (Table 33.1). The six degrees of nerve injury have been well described. First- and second-degree injuries recover spontaneously, as do third-degree, albeit recovery is variable and less than normal, depending on scar tissue. Fourth- and fifth-degree injuries are significant and recovery is not expected. These injuries should be managed with prompt surgical intervention to prevent degeneration and fibrosis of the motor end plates. Sixth-degree injuries encompass a variety of nerve injuries within a single nerve, and the need to operate is determined on an individual basis.

Table 33.1 Classification of nerve injury highlighting the six degrees of nerve injury and the anticipated rate and likelihood of recovery

Degree of injury		Tinel's sign present	Recovery	Rate of recovery	Surgical procedure
I	Neurapraxia	No	Complete	Up to 12 weeks	None
II	Axonotmesis	Yes	Complete	1* per month	None
III		Yes	Varies*	1* per month	None or neurolysis
IV	Neuroma-in-continuity	Yes, but no advancement	None	None	Nerve repair, graft, or transfer
V	Neurotmesis	Yes, but no advancement	None	None	Nerve repair, graft, or transfer
VI	Mixed injury (I–V)	Some fascicles (II, III)	Some fascicles (II, III)	Depends on degree of injury (I–V)	Neurolysis, nerve repair, graft, or transfer

*Recovery can vary from excellent to poor depending on the amount of scarring and the sensory versus motor axon misdirection to target receptors.

Once surgical intervention has been deemed necessary, there are a number of surgical options. Traditionally nerve repair or grafting was used with tendon transfers to augment poor recovery or delayed presentation. The difficulty with proximal nerve injuries is that the distance from the injury to the motor end plate is significant, and recovery is prolonged. In addition, delayed intervention may result in denervation and fibrosis prior to muscle reinnervation. Axonal regeneration has been shown to occur at the rate of approximately 1 inch (2.5 cm) per month and reinnervation of denervated muscle is not possible after 12–18 months; therefore nerve transfers offer a valuable means of providing regenerating axons in closer proximity to the motor end plate. Essentially, a nerve transfer converts a proximal nerve injury to a distal one, enabling faster recovery and quicker return to function.

$$\text{Function} \propto \frac{\text{Number of nerve fibers}}{\text{Time of denervation}}$$

Nerve transfers were described very early; however they were traditionally reserved for otherwise unsalvageable root avulsions and proximal pan-plexus injuries. Approximately 20 years ago, nerve transfers were revisited and applied to a significantly broader patient population, with applications in partial plexus injuries to recreate specific essential functions in the upper extremity.^{5–7} As our understanding of internal nerve topography has broadened, techniques and equipment for performing microsurgery have improved, and our diagnostic ability for brachial plexus and peripheral nerve injury has progressed, the field of nerve transfers has exploded. Nerve transfers have become the standard of care for treatment of peripheral nerve injuries in the authors' practice, and have largely replaced other modalities.

Basic science

There have been dramatic increases in our knowledge of nerve injury, healing, and regeneration. The majority will be touched on in Volume 1, Chapter 22, and Chapter 32 of this volume. The most relevant recent basic science advances pertaining to nerve transfers relate to end-to-side transfers (Fig. 33.1). End-to-side neurorrhaphy involves the coaptation of the distal end of an injured recipient nerve into the lateral aspect of an intact nerve, which serves as a proximal source of axons to regenerate into the injured nerve. Reports of end-to-side transfers occurred as early as the late 1800s and then made a resurgence in the 1990s. There has, however, been controversy regarding the success of these transfers, and sensory recovery has typically been more impressive than motor recovery. The sprouting of axons in an end-to-side coaptation, thus eliminating the need for a proximal nerve stump, makes nerve transfers an option for proximal nerve injuries and has been well demonstrated in the literature.^{8,9} While sensory nerves are able to sprout spontaneously (collateral sprouting), donor nerve axonotmetic injury is required for motor neuronal regeneration (regenerative sprouting) across the end-to-side repair (Fig. 33.2).⁸ An epineurotomy in the donor nerve is required, and partial axotomy will result in more significant regenerative sprouting into the recipient nerve, albeit at the potential expense of a measurable downgrade in donor nerve function.




Fig. 33.1 The various options for coaptation in nerve transfer. **(A)** End-to-end coaptation between the donor nerve (red) and the recipient nerve (blue). **(B)** End-to-side coaptation, where the distal end of the divided recipient nerve (blue) is transferred to the side of the intact donor nerve (red). In this transfer, fascicles from the donor will “sprout” into the distal donor nerve. The recipient nerve essentially “pulls” the donor fascicles into the distal nerve. **(C)** Reverse end-to-side coaptation. In this transfer, the donor nerve (red) has been divided and transferred to the side of the intact recipient nerve (blue). The donor essentially “pushes” regenerating fascicles into the distal donor nerve. (© Washington University in St. Louis.)

Reverse end-to-side nerve transfers involve the complete transection of the donor nerve, which is then coapted into the side of the intact recipient nerve. This maximizes the potential number of available motor axons from the donor nerve. This procedure does not interrupt any recovery in the injured recipient nerve because the nerve remains in continuity; however the additional axons recruited from the donor nerve improve distal target reinnervation, a concept




Fig. 33.2 The difference between regenerative and collateral sprouting. Traumatic regenerative sprouting occurs following injury to the proximal nerve. The damaged axons degenerate and then regenerate at the rate of 1 mm/day into the distal recipient nerve. Collateral sprouting occurs spontaneously, and does not require proximal nerve injury. Axons from the donor nerve simply sprout into the distal end of the recipient nerve. Only sensory nerves will undergo spontaneous collateral sprouting. Motor nerves require an axonotmetic injury to facilitate regenerative sprouting. (© Washington University in St. Louis.)




Fig. 33.3 A 62-year-old woman presented with ulnar nerve dysfunction. After an extended period of hand-intensive activity, she noted the onset of ulnar nerve distribution numbness and pain. She had subsequent weakness of extrinsic and absent intrinsic ulnar motor function. Electrodiagnostic testing revealed complete denervation without evidence of reinnervation at the intrinsic muscles. Nerve decompression and transposition at the elbow and decompression at the wrist was performed. Due to the significant distal abnormalities without evidence of recovery (at 3 months after onset of symptoms), side-to-side transfers were performed to restore and/or augment both motor and sensory function. This image depicts the intraoperative dissection of the distal median and ulnar nerves. The recipient ulnar nerve has been decompressed at Guyon's canal and is in continuity. The donor median nerve has been exposed at the upper aspect of the photo. Bridging acellularized allograft material is inlaid to provide side-to-side or "cross-grafting" reinnervation from the donor functional median nerve to the recipient non-functional sensory ulnar nerve branches. An additional coaptation of the pronator quadratus branch of the anterior interosseous nerve to the deep motor branch of the ulnar nerve in supercharge end-to-side fashion was also completed. This will provide an additional modicum of reinnervation as the ulnar nerve proper also, hopefully, recovers. (© 2015 nervesurgery.wustl.edu.)

known as "supercharging".¹⁰ In a proximal partial nerve injury, with a long distance required for reinnervation, this technique can protect target muscles from denervation atrophy and fibrosis.^{9,10} Clinically, the most relevant place to consider this strategy is for preservation of intrinsic hand function in proximal severe ulnar neuropathy with use of the end-to-side distal anterior interosseous (branch to pronator quadratus) to deep motor branch of ulnar nerve end-to-side coaptation.¹⁰

More recently, work on side-to-side, "cross-grafting" nerve transfers in animal models has also been completed and shows some role for preservation and protection of the denervated end organ (Fig. 33.3).¹¹ These strategies, however, remain under debate and deserve continued laboratory study and clinical evaluation.

Hints and tips

The end-to-side transfer can be considered as the recipient nerve "pulling" regenerating axons out of the intact donor, whereas the reverse end-to-side "supercharge" transfer can be considered as the donor nerve "pushing" regenerating axons out into the intact recipient.¹¹

Diagnosis and patient presentation

The value of a complete history and physical examination in the patient with a potential brachial plexus or proximal nerve injury of the upper extremity cannot be overstated. Patients should be evaluated promptly after injury, both to provide a baseline for future serial examinations and to facilitate timing of surgical intervention where necessary.

Patient history

On history, details of the mechanism and timing of injury are crucial. When seeing a patient in a delayed fashion, it is also useful to ascertain any interval recovery of function. The mechanism of injury will determine timing of intervention, with prompt exploration of penetrating sharp trauma, and more expectant management of closed injuries and gunshot wounds. Specific patient symptoms such as loss of function, both sensory and motor, and pain should be precisely elicited, as this will help focus the subsequent physical examination. The pain diagram and questionnaire are particularly useful for eliciting this information (Fig. 33.4). Other factors, such as patient age, handedness, occupation, and comorbidities, will factor into management decisions. Attention to patient goals and expectations allows for individually tailored and nuanced approaches that may or may not involve nerve transfer surgery techniques, which form "a part of the armamentarium"¹² when caring for patients with complex upper extremity injury. Further information on steadily improving quality of life and other gradual but continuing changes over time after nerve transfer in brachial plexus injury patients may further influence treatment choices and patient preference-specific choices.¹³

Physical examination

A complete physical examination of the upper extremity includes assessment of sensory and motor function, joint suppleness, range of motion, and a functional assessment with attention paid to adaptive strategies and use patterns. Particularly in patients with late presentation, the presence of fixed joint contractures may preclude functional recovery. Perfusion, bony pathology, presence of edema, scar, previous incisions, and other soft-tissue trauma are factors that influence treatment choices.

Function should be graded at each joint. Manual muscle testing and examination by direct palpation is imperative for assessing the presence of redundant function when checking for expendable donor muscles. Shoulder function should be assessed by examining deltoid, supraspinatus, infraspinatus, trapezius, latissimus dorsi, serratus anterior, and pectoralis major. The patient's ability to abduct/adduct, flex/extend, and internally/externally rotate must be assessed. The elbow should also be assessed for flexion and extension. Here it is important to differentiate between flexion secondary to biceps brachii and brachialis (musculocutaneous nerve) and brachioradialis (radial nerve). The forearm and wrist should be assessed for flexion/extension and pronation/supination. Palpation of the individual tendons with wrist flexion is essential to determine which nerves are involved, as well as

Text continued on p. 747

Pain Questionnaire

Name: _____

Date: _____

Age: _____ Sex: Male _____ Female _____ Dominant Hand: Right _____ Left _____ Diagnosis: _____

1. Pain is difficult to describe. Circle the words that best describe your symptoms:

Burning	Throbbing	Aching	Stabbing	Tingling	Twisting	Squeezing
Cramping	Cutting	Shooting	Numbing	Vague	Stinging	Indescribable
Pulling	Smarting	Pressure	Coldness	Dull	Other:	

Level of symptoms: place a mark through the line to indicate the level of your pain, if zero is no pain and the end of the line is the most severe pain you can imagine having.

2. Mark your average level of pain in the last month


No pain Most severe pain

3. Mark your worst level of pain in the last week

Right No pain Most severe pain

Left No pain Most severe pain

4. Where is your pain? (Draw on diagram)



Mark on this scale how your pain has affected your quality of life:

0% 100%

Very little A large amount

Mark on this scale how depressed you currently feel:

0% 100%

Not at all A large amount

A

Fig. 33.4 The pain questionnaire is a valuable tool for qualifying and quantifying patient pain and the impact their injury is having on their life. This has uses both in obtaining baseline information, and also in tracking progress as patients recover. This questionnaire is filled out by every nerve patient at each office visit.

Continued

5. Mark your average level of stress in the last month?

At home 0 10

At work 0 10

6. How well are you able to cope with that stress?

At home Very well Not at all

At work Very well Not at all

7. How did the pain that you are now experiencing occur?

- a. Sudden onset with accident or definable event
- b. Slow progressive onset
- c. Slow progressive onset with acute exacerbation without an accident or definable event
- d. A sudden onset without an accident or definable event

8. How many surgical procedures have you had in order to try to eliminate the cause of your pain?

- a. None or one
- b. Two surgical procedures
- c. Three or four surgical procedures
- d. Greater than four surgical procedures

9. Does movement have any effect on your pain?

- a. The pain is always worsened by use or movement
- b. The pain is usually worsened by use and movement
- c. The pain is not altered by use and movement

10. Does weather have any effect on your pain?

- a. The pain is usually worse with damp or cold weather
- b. The pain is occasionally worse with damp or cold weather
- c. Damp or cold weather have no effect on the pain

11. Do you ever have trouble falling asleep or awakening from sleep?

- a. No – Proceed to Question 12 b. Yes – Proceed to 11A & 11B

11A. How often do you have trouble falling asleep?

- a. Trouble falling asleep every night due to pain
b. Trouble falling asleep due to pain most nights of the week
c. Occasionally having difficulty falling asleep due to pain
d. No trouble falling asleep due to pain
e. Trouble falling asleep which is not related to pain

11B. How often do you awaken from sleep?

- a. Awakened by pain every night
b. Awakened from sleep by pain more than 3 times per week
c. Not usually awakened from sleep by pain
d. Restless sleep or early morning awakening with or without being able to return to sleep, both unrelated to pain

12. Has your pain affected your intimate personal relationships?

- a. No b. Yes

13. Are you involved in any legal action regarding your physical complaint?

- a. No b. Yes

14. Is this a Workers' Compensation case?

- a. No b. Yes

15. Are you receiving or have you ever received psychiatric/psychological treatment?

- a. No b. Presently receiving psychiatric treatment c. Previous psychiatric treatment

16. Have you ever thought of suicide?

- a. No b. Yes c. Previous suicide attempts

17. Have you been a victim of emotional abuse?

- a. No b. Yes c. No comment

18. Have you been a victim of physical abuse?

- a. No b. Yes c. No comment

19. Have you been a victim of sexual abuse?

- a. No b. Yes c. No comment

20. Are you presently a victim of abuse?

- a. No b. Yes c. No comment

21. If you are retired, a student or homemaker, proceed to Question 21B

21A. Are you still working?

- a. Work every day at the same pre-pain job
- b. Work every day but the job is not the same as the pre-pain job, with reduced responsibility or physical activity
- c. Work occasionally
- d. Not presently working

21B. Are you able to do your household chores?

- a. Do same level of household activities without discomfort
- b. Do same level of household chores with discomfort
- c. Do a reduced amount of household chores
- d. Most household chores are now performed by others

22. What medications have you used in the past month?

- a. No medications
- b. List medications: _____

23. If you had three wishes for anything in the world, what would you wish for?

- a. _____
- b. _____
- c. _____

the level and degree of injury and the availability of branches (flexor carpi ulnaris, flexor carpi palmaris, palmaris longus) for use as donor nerves. In the hand, a complete examination of extrinsic and intrinsic function again helps to delineate the level of injury.

Assessment of muscles and grouping the exam by peripheral nerve branch and/or by cervical root level pattern may be helpful, depending on the appropriate clinical scenario.

Sensation should be examined by both dermatome and peripheral nerve distribution, and can be helpful in distinguishing these injuries. The authors advocate the use of both two-point discrimination and the ten-test to evaluate sensory loss in the hand.¹⁴ A Tinel's sign, the tingling sensation elicited with percussion over a regenerating nerve, will help to localize the level of nerve injury, and may also be followed on serial clinical examination to check for signs of advancement, indicating spontaneous recovery. An advancing Tinel's sign distal to the site of injury quite often precedes clinical motor recovery.

For completeness, the presence of Horner's syndrome and dysfunction of nerve branches that come off the proximal brachial plexus (dorsal scapular nerve to rhomboids, long thoracic nerve to serratus anterior) indicate a very proximal level of injury.

One of the most important components of the physical examination is the simple determination of what is functioning, and what function has been lost. Not only does this help to determine the level of injury, it can guide future surgical planning. In the presence of an injury requiring surgical intervention, it is important to examine the patient for putative nerve donors, both intraplexal and extraplexal (spinal accessory, medial pectoral, and thoracodorsal).

Hints and tips

Remember to check not only for what muscles have lost function, but also for potential nerve transfer donors.

Imaging

Imaging is primarily useful for confirming level of injury in more complex closed-mechanism nerve injury patients. For example, imaging such as computed tomography myelogram and magnetic resonance imaging provides additional confirmation of a nerve root avulsion pattern. Additional X-rays, such as shoulder films that demonstrate scapular notch-level trauma, may provide information of localized trauma that would make proximal transfer to the suprascapular nerve ineffective due to the extensive zone of injury. Other plain films such as chest X-ray might be used to evaluate pathology such as rib fractures or diaphragm dysfunction that might make the use of intercostal and phrenic nerves as donor nerves less palatable, although the former is debatable.¹⁵

Electrodiagnostic testing

Electrodiagnostic testing, performed by an experienced person, can be a useful adjunct to physical examination for serial assessment of reinnervation in closed nerve injuries. Electromyography records the electrical activity of muscle fibers, tested both at rest and activity, by the insertion of needles into the muscle. Denervated muscles will

demonstrated fibrillations and positive sharp waves on needle insertion; however, the findings are not reliable until approximately 4 weeks after injury.¹⁶ Initial electrodiagnostic testing should be deferred until a minimum of 6–8 weeks post-injury to assess for signs of both axonal injury and root-level avulsion. Serial testing will reveal signs of reinnervation with nascent potential and motor unit potentials in the affected muscle groups, often prior to clinical evidence of recovery.

Detailed testing of both putative functioning donors and non-functioning recipient muscles is important to confirm physical exam findings. This is particularly important because subtle abnormalities in donor muscles correlate with subsequent clinical results. In fact, abnormalities seen in the putative donor muscles may dictate a change to a different donor, if available, or an understanding that results may be detrimentally affected.

Conduction velocity is used to measure the integrity of a peripheral nerve (sensory nerve action potentials [SNAP] or compound motor action potentials [CMAP]).¹⁶ A severed nerve will lose the ability to conduct a signal as Wallerian degeneration occurs; however, if measured too early, the distal aspect of the nerve will still conduct, leading to an inaccurate assessment. This is another reason for delaying initial electrodiagnostic studies. Preganglionic injuries will be associated with a loss of sensation but an intact SNAP and an absent CMAP.¹⁶ Thus the level of injury can be confirmed with electrodiagnostic studies.

In patients with no evidence of recovery 3 months after a closed nerve injury, the balance should tilt towards consideration of surgical intervention.

Hints and tips

Order baseline electrodiagnostic studies at 6–8 weeks and subsequent testing as indicated by the injury:

- Electromyography (EMG) showing fibrillations (fibs) and positive sharp waves (PSW) suggest denervation. Motor unit potentials (MUP) and nascent units suggest reinnervation.
- Do not be confused by automated EMG reporting errors – “normal” may appear in some reports by default. If a muscle has fibs and PSWs but the MUP column says “normal” this may be a machine printout error – consult with your electrodiagnostician as it more likely that there are *absent* MUPS (not “normal” MUPS).
- When assessing for recovery over time, ask to check proximal muscles first (example flexor carpi ulnaris not first dorsal interosseous, when evaluating ulnar nerve recovery).
- Remember, the EMG provides qualitative information only (not quantitative).
- Above all, careful communication with the electrodiagnostician and correlation to clinical exam findings are imperative when interpreting these test results.

Overall, the complete picture, including history, physical examination, and adjunct testing, should facilitate surgical decision-making. Appropriate treatment for open injuries with nerve dysfunction begs for timely management with surgery on an urgent or semi-urgent basis. For these injuries, direct exploration and repair have historically been the

treatment of choice, but in very proximal injuries, distal nerve transfer can allow for more timely and successful reinnervation. In closed nerve injuries or in gunshot wounds, appropriate management demands a more measured approach and surgery should be delayed to allow for spontaneous recovery, which is often superior to that seen in patients treated with hasty surgery. These patients in particular may benefit from “supercharging” with reverse end-to-side nerve transfer procedures, which can more quickly deliver regenerating axons to the appropriate end organ, while still allowing slower spontaneous recovery.¹⁰

Patient selection

Hints and tips

When considering nerve transfers, be aware of the various advantages, disadvantages, and limitations:

- Nerve transfers may allow for an unprecedented level of timely and biomechanically appropriate return of function.
- A single donor nerve (from one muscle) can provide individual and isolated muscle function to more than one recipient through motor re-education and cortical adaptation.
- It will take months to years for maximal function to be achieved after nerve transfer (time for regeneration, relearning and strengthening) but function can continue to improve over years post-surgery.
- A distal nerve transfer will not directly address pain from a proximal neuroma or neuroma-in-continuity.
- No transfer, no matter how close to the target, can restore function after terminal muscle denervation has occurred (that deadline occurs somewhere between 12–18 months after nerve injury).

Nerve transfers have become increasingly popular for a number of reasons, the most compelling of which is the “time is muscle” issue. The biggest challenge facing peripheral nerve surgeons is that with increasing time since injury, the ability to achieve good motor function becomes increasingly limited. In fact, for any nerve injury where there is complete discontinuity with the motor end organ, no reinnervation procedure will be able to restore muscle once denervation and fibrosis have occurred, a process which occurs as early as 1 year. Nerve transfers, by bringing the regenerating motor fibers closer to the target end organ more rapidly, essentially convert a more proximal-level injury to a more distal-level injury, thus increasing the chance of achieving meaningful muscle function.

Another advantage of nerve transfers is that they enable surgical reconstruction outside the zone of the original injury, avoiding complex dissections and limiting injury to critical neurovascular structures. In patients with brachial plexus trauma, the proximity of vital structures (great vessels, thoracic duct, lung) makes the occurrence of potentially life-threatening complications a real possibility. In other cases, such as concomitant vascular injury, previous blast injury, or soft-tissue deficits requiring flap reconstruction, the ability to

avoid doing a complex nerve exploration in the setting of dense fibrotic scar is particularly advantageous.

Nerve transfers allow for a very targeted intervention in cases of partial nerve injury such as in treatment of a sixth-degree or neuroma-in-continuity injury, where transfer can be done distal to the site of injury specifically to the non-functioning nerve branch. This allows for preservation of all intact function and restoration of only missing function. In addition, the ability to “supercharge” a recovering nerve is invaluable when it is unclear whether the nerve transfer or intrinsic recovery will be more beneficial.

Unlike tendon transfers, nerve transfers typically do not require immobilization, which is especially valuable in patients presenting with significant baseline stiffness. Nerve transfers also preserve the biomechanical properties of the musculotendinous unit, such as end organ origin, insertion, excursion, and length–tension relationships. Finally, nerve transfers can restore unique function such as pronation, which is incredibly difficult to restore by traditional surgical techniques.¹⁷

Thus nerve transfers are indicated in a number of situations (Table 33.2), for example, in proximal brachial plexus injury where grafting is not possible or the required distance for reinnervation will not allow motor axons to reach the target motor before denervation and fibrosis have occurred. In situations of extreme scarring, or major upper extremity trauma, a nerve transfer is preferable to risking damage to critical structures within the scarred region. Nerve transfers are also indicated in segmental nerve loss, and in partial nerve injury patterns with functional loss. Patients presenting in a delayed manner with inadequate time to reinnervate the distal targets are good candidates for distal nerve transfers. Also, patients with sensory nerve deficits in critical regions should be considered for nerve transfer to restore sensation.

The main reason a nerve transfer should not be performed is similar to the contraindication for any other traditional nerve repair/graft intervention, namely end organ unresponsiveness. An old peripheral nerve injury will not respond to the new “magic” of nerve transfers. Muscle that is in complete discontinuity with the nerve for greater than 1 year will not be reinnervated, no matter how elaborate the reinnervation strategy employed.

More relative contraindications for nerve transfer include issues such as the time required for regeneration, challenges of the surgery, the anatomic knowledge required, and problems of postoperative retraining and therapy, as these techniques are less familiar to hand therapists. There are some patients, such as the young manual laborer with a radial nerve

Table 33.2 Indications for nerve transfer

- Proximal brachial plexus injuries where grafting is not possible
- Proximal peripheral nerve injuries requiring long distance for reinnervation of distal targets
- Severely scarred areas with risk of damage to critical structures
- Segmental nerve loss
- Major upper extremity trauma
- Partial nerve injuries with functional loss
- Delayed presentation with inadequate time for reinnervation of distal targets with grafting
- Sensory nerve deficits in critical regions

injury, who may prefer the more rapid recovery associated with tendon transfer at the expense of the independent fine motor control that could be achieved through the use of nerve transfers. The surgery itself is challenging because of the detailed knowledge of internal nerve topography required. Most surgeons are not formally trained in the intraneural dissection techniques required to perform nerve transfers and the results are not apparent until months down the line. This requires a significant leap of faith for surgeons who are more used to immediate gratification and a clear result in weeks, not months or years!

Direct nerve repair and nerve grafting also remain valuable tools for the peripheral nerve surgeon and should continue to be the treatment of choice in a variety of scenarios. These include cases of multiple nerve injuries where there is a paucity of nerve donor material for nerve transfer. Also, in distal single-function nerve injuries, direct or graft repair is preferable to nerve transfer because one-to-one function is preserved, no retraining is necessary, no donor function is sacrificed, and the distance to the end target is short.

Patient general health, comorbidities, and associated injuries factor into the decision to perform nerve transfers. These procedures can be lengthy, and are not without significant risk from anesthesia in the fragile patient. In addition, patient compliance is an integral part of the recovery process, and patients require education preoperatively about the prolonged recovery and therapy times associated with nerve transfer.

Examples of nerve transfer procedures for specific injury patterns

Hints and tips

- Avoid paralytics, or use only short-term paralytics with anesthesia induction to allow for nerve stimulation.
- Minimize or avoid tourniquet time to avoid interference with nerve stimulation.
- Use plain epinephrine in proximal incisions to minimize blood loss without lidocaine paralysis.
- Obtain wide surgical exposure to identify nerves and appropriate branches.
- Choice of optimal nerve donor is based on quantity of motor axons, proximity to target muscles, synergy of muscle function, and donor expendability.
- Conduct neurolysis with your “eyes”, except at the site of actual transfer, to avoid prolonged dissection and increased trauma to nerve branches.
- Confirm no intraoperative stimulation in putative recipient before dividing donor.
- Divide donor nerve distally and recipient nerve proximally.
- Use 9-0 nylon and the operating microscope to perform tension-free epineurial repair.
- Use bupivacaine block at end of case for postoperative pain control.

Upper plexus injury

Specific patient exam findings

Patients with upper plexus injuries present with glenohumeral joint subluxation, loss of shoulder abduction and external rotation, and absent elbow flexion. When C7 is also involved, additional deficits in function may include loss of elbow extension and weakness of wrist and digit extension. Numbness over the corresponding dermatomes is noted.

Reconstruction techniques

Hints and tips

Priorities for upper plexus injuries include restoration of shoulder external rotation and abduction, as well as elbow flexion. Standard transfers include: (1) spinal accessory to suprascapular nerve; (2) medial triceps to axillary nerve; and (3) double fascicular nerve transfer.

Use of spinal accessory nerve (cranial nerve XI) to suprascapular nerve transfer (motor)

Restoration of shoulder stability and external rotation are facilitated by transferring the spinal accessory nerve (cranial nerve XI) to the suprascapular nerve. This transfer can be conducted by either an anterior or a posterior approach. In the posterior approach, the patient is positioned prone and surface landmarks are used to approximate the position of the nerves (Fig. 33.5A–D). The spinal accessory nerve runs parallel to the border of the trapezius and is localized 44% of the way along a line connecting the acromion to the dorsal midline at the level of the superior border of the scapula (Fig. 33.6). The suprascapular nerve is located midway between the medial border of the scapula and the acromion as it runs through the suprascapular notch.¹⁸ Dissection is carried through the trapezius in a muscle-splitting fashion and an end-to-end coaptation, sparing the upper trapezius nerve branches.

For the anterior approach, a supraclavicular incision is made; the lateral aspect of the trapezius is released off of the clavicle and the spinal accessory nerve is identified on its anterior surface (Fig. 33.7). The suprascapular nerve sits at the superolateral aspect of the upper trunk, which is identified between the anterior and middle scalene muscles. An end-to-side approach with a partial neurectomy of the donor accessory nerve is preferred as this preserves some donor function. A short interpositional graft from the recipient suprascapular nerve to the donor spinal accessory nerve is required to avoid tension. A proximal crush injury to the donor nerve encourages axonal sprouting such that regeneration into the recipient suprascapular nerve occurs without loss of significant donor nerve trapezius function.¹⁹

Use of triceps to axillary nerve transfer (motor component)

Additional abduction of the shoulder is provided by transferring a branch of the triceps, usually from the medial head, to




Fig. 33.5 The posterior approach for spinal accessory to suprascapular nerve transfers. **(A)** The nerves can be seen in their original orientation. **(B)** The end-to-end transfer has been completed. The transfer includes the functional spinal accessory nerve (donor) being transposed and coapted to the non-functional suprascapular nerve (recipient).

the axillary nerve (Fig. 33.8).^{18,20} Better results in upper plexus injury patients are achieved by reinnervating both the suprascapular and axillary nerves.²¹ A longitudinal incision is made on the posterior surface of the arm (Fig. 33.9). The axillary nerve is identified in the quadrangular space and dissected proximally to include the branch to teres minor, then divided proximally. The natural cleavage plane between the lateral and long heads of the triceps muscles is identified and blunt dissection is conducted to expose the donor radial nerve running along the humerus. The branch to the medial triceps sits superficially and medially on the surface of the radial nerve as a distinct branch. The donor triceps nerve is dissected as far distally as possible and then coapted to the axillary nerve (Fig. 33.10).

Use of the double fascicular (ulnar/median redundant branches to biceps brachii and brachialis branches of the musculocutaneous) nerve transfer (motor)

Restoration of elbow flexion is achieved with the double fascicular nerve transfer (Fig. 33.11). This transfer reinnervates both the biceps brachii and brachialis muscles using redundant fascicles from the ulnar and median nerves, if available.²² However, in cases of limited donor availability, reinnervation of biceps alone may provide adequate anti-gravity elbow flexion.²³ A medial arm incision allows exposure of the musculocutaneous, median, and ulnar nerves. Dissection at the underside of the biceps brachii muscle allows exposure of the proximal biceps and distal brachialis




Fig. 33.6 Surface markings for posterior approach to spinal accessory to suprascapular. The spinal accessory nerve is located 44% of the way along a line connecting the dorsal midline to the acromion. The suprascapular nerve is located at the halfway point between the medial border of the scapula and the acromion on an obliquely oriented line at the superior aspect of the scapular spine. It runs in the suprascapular notch.

nerve branches, (Fig. 33.12), which are divided and draped over to the median and ulnar nerves to determine best donor–recipient pairings. The ulnar and median nerves are then neurolyzed at the appropriate level, and expendable fascicles to the flexor carpi ulnaris (FCU) (ulnar), flexor carpi radialis (FCR), flexor digitorum superficialis (FDS), or palmaris longus (median) are divided distally and coapted end

to end. Reinnervation occurs at approximately 5–6 months postoperatively.

Other potential donors (medial pectoral nerve and thoracodorsal nerve)

Other potential donors that can be used to restore elbow flexion include the medial pectoral nerves and the thoracodorsal nerve. The medial pectoral nerves are identified by making an incision in the deltopectoral groove then dividing the pectoralis major tendon at the humeral head for exposure; the tendon can be reinserted using bone anchors or attaching to the remaining tendon insertion if the tendon is initially transected. While some advocate elevating the pectoralis minor to gain access to the nerves, we find that simple transection of the muscle belly affords the best exposure (Fig. 33.13). There are several branches to the pectoralis minor and these can be followed as distally as possible into the muscle to increase available donor nerve length.²⁴ Often a nerve graft will be required to reach the musculocutaneous recipient. The thoracodorsal nerve runs from the axilla along the lateral chest wall and can be exposed through an incision running along the free border of latissimus dorsi.

Lower plexus injury

Specific patient exam findings

Lower plexus injuries usually involve damage to C8 and T1 nerve roots. Patients have a resultant loss of the intrinsic hand function and variable loss of extrinsic hand and wrist function. Involvement of C7 can dramatically influence available options for nerve transfer.




Fig. 33.7 In the anterior approach to the spinal accessory to suprascapular nerve transfer, upper trapezius function is preserved by performing the nerve transfer in an end-to-side manner. **(A)** To inset this transfer with no tension, an interpositional lateral antebrachial cutaneous nerve (LABC) nerve graft is used. **(B)** To facilitate regenerative sprouting, injury to the donor nerve is required proximally. This is accomplished by “crushing” the nerve with a hemostat to cause a second-degree nerve injury. **(C)** Wallerian degeneration occurs distal to the site of compression. **(D)** Axons regenerate from the level of the crush injury, with some axons following the donor nerve and restoring function to the upper trapezius muscle, and some axons diverting into the distal recipient nerve via the LABC graft.




Fig. 33.8 The triceps to axillary nerve transfer via a posterior approach to the upper arm. **(A)** The axillary and radial nerves in their normal anatomical position. **(B)** The branch to the medial head of the triceps (donor) is transposed to meet the divided end of the axillary nerve (recipient). The branch to the medial head is coapted end to end to the axillary nerve.




Fig. 33.9 Set-up and incision for triceps to axillary. The patient is positioned in the prone position and draped with the entire extremity free and the medial border of the scapula exposed. A line connecting the olecranon and the acromion is drawn on the posterior aspect of the arm and then extended in a curvilinear fashion just above the posterior axillary fold. Positioning is facilitated by placing a “bump” beneath the anterior shoulder preventing internal rotation and anterior subluxation. The arm is draped free so that distal function can be assessed with intraoperative nerve stimulation.

Hints and tips

Priorities for lower plexus injuries include restoration of hand extrinsic function. Restoration of hand intrinsic function is virtually unobtainable except in the very young pediatric patient.

Reconstruction techniques

There are few good direct nerve transfer options for lower plexus injury reconstruction. Strategies include transfer of the nerve to brachialis (a branch of the musculocutaneous nerve) to the anterior interosseous nerve (AIN) to regain thumb and finger flexion. The details of this technique are described under the median nerve injury section below. The brachioradialis (if function is preserved) may also be used as a donor to the AIN.²⁵ Additional options include the use of the supinator to the posterior interosseous nerve to restore thumb and finger extension.²⁶




Fig. 33.10 A clinical example of the triceps to axillary nerve transfer. The patient is positioned with the head to the top right. The cross-hatchings of the posterior midline incision in the upper arm are visible and the quadrangular space is exposed. **(A)** The intact nerve *in situ* prior to division. A white vessel loop surrounds the entire nerve at that level. **(B)** The divided nerve transposed caudally with the proximal-most aspect held by the forceps. The branches are clearly visible with vessel loops around motor branches. The superior-most branch is the branch to teres minor. The sensory branch is the most inferior branch (no vessel loop) and can be visualized heading more superficially than the other branches. **(C)** The cut end of the recipient axillary nerve is visible on the most proximal blue background. The radial nerve is visualized at the base of the wound, with vessel loops around branches to the medial, long, and lateral heads of triceps. **(D)** The divided branch to the medial head (donor) is transposed proximally and coapted to the recipient axillary nerve.




Fig. 33.11 A schematic of the double fascicular nerve transfer. The divided recipient branches of the musculocutaneous nerve (biceps brachii laterally and brachialis medially) are transposed medially to the median and ulnar nerves. In this example, a redundant fascicle to flexor digitorum superficialis (median donor) is transferred to the biceps brachii branch and a redundant fascicle of the flexor carpi ulnaris (ulnar donor) is transferred to the brachialis branch.




Fig. 33.12 Operative photo of double fascicular nerve transfer. A clinical example of the double fascicular nerve transfer. The superior nerve is the musculocutaneous nerve with vessel loops around the branch to biceps brachii (proximal and lateral) and branch to brachialis (distal and medial). The ulnar nerve is also neurolyzed at the level appropriate for transfer. Redundant fascicles determined by intraoperative nerve stimulation that can serve as potential donors are marked with vessel loops.

Complete/near-complete plexus injury

Specific patient exam findings

Complete, or near-complete, brachial plexus injury often results from high-velocity, penetrating, or crush-type mechanisms and result in devastating loss of function. These patients will typically have an insensate, flail upper extremity with glenohumeral joint subluxation and a positive sulcus sign. Most will lack shoulder stability, abduction, rotation, flexion and extension, elbow flexion and extension, wrist flexion and extension, finger flexion, extension, and intrinsic function.




Fig. 33.13 Harvesting the medial pectoral nerve. Clinical photograph of a patient with medial pectoral nerve harvested as a donor. The divided pectoralis major muscle is flipped proximally and lying on the anterior chest wall. The medial pectoral nerves have been dissected from the deep surface of the pectoralis minor and divided distally. They have then been transposed towards the donor nerves in the arm and are lying on the most proximal blue background.

Reconstruction techniques

Hints and tips

Priorities for complete plexus injuries are to restore function in the following order of priority: (1) elbow flexion; (2) shoulder stability/external rotation; and (3) hand extrinsic function/grasp. Techniques include extraplexal to intraplexal nerve transfers. Most reconstructive approaches will require staged transfers due to the long distance to target, with banking of interposition grafts and subsequent free functional muscle reconstruction. Adjunctive fusion of selected joints (wrist, thumb) and other approaches may be completed. Contralateral C7 and phrenic nerve transfers are also described with varying and modest results.

Use of spinal accessory and intercostal nerves as donors (motor)

Reconstruction in this scenario has very different goals and outcomes from less traumatic injuries. Priorities include restoring elbow flexion, shoulder stability/external rotation, and hand extrinsic function/grasp. The extremity will often be a “helper” extremity at best. The severe damage to the brachial plexus means that options for nerve transfers are limited, and that extraplexal donors must be considered. Specifically, available extraplexal nerve donors may include the spinal accessory, medial pectoral, thoracodorsal, and intercostal nerves.

Donor nerves are isolated as follows: The spinal accessory nerve is harvested as described previously. Intercostal nerves are harvested through an L-shaped incision extending from the anterior axillary fold and curving anteriorly below the nipple–areolar complex. Rib periosteum is incised and peeled down to expose the neurovascular bundles running along the posterior inferior surface of each rib (Fig. 33.14). The motor




Fig. 33.14 Harvesting intercostal nerves. Clinical photograph of a female patient undergoing intercostal to musculocutaneous nerve transfer. The anterior subcutaneous flap has been turned over medially to expose the anterior chest wall. White vessel loops are around intercostal nerves at the inferior border of each rib. The recipient nerve is visualized in the upper arm on a blue background.

nerves are smaller and sit more superiorly than the sensory nerves. Often several are required. These are dissected as far medially as possible and then divided.

These extraplexal donor nerves can be transferred to a variety of potential recipients, depending on surgical goals. They can be used to establish shoulder stability and external rotation (suprascapular and axillary nerves), elbow flexion (musculocutaneous), or even to recreate elbow extension or finger flexion by neurotizing one or two free-functioning gracilis flaps.²⁷ This is often accomplished as a two-stage procedure.

Discussion of cross C7 transfer, phrenic nerve transfers (motor)

Contralateral C7 transfer has been described as a safe option in the literature^{28,29} and has been met with varying levels of success and controversy. Approaches include prespinal tunneling, and complete and partial root harvest. However, evidence suggests that the degree of function obtained does not justify the donor complications, even with hemi-contralateral C7 harvest.³⁰

The phrenic nerve has also been used, with some studies documenting no significant impact on respiration and others reporting decreased pulmonary capacity that goes on to improve. The senior author no longer uses either the phrenic nerve or the contralateral C7 as a potential nerve donor as results are, at best, Medical Research Council (MRC) grade 3 of 5 after several years for limited elbow flexion or poor finger flexion.

Median nerve injury

Specific patient exam findings

The median nerve proper supplies pronator teres (PT), FCR, palmaris longus, and FDS. The nerve then divides. The anterior interosseous nerve innervates flexor pollicis longus, flexor digitorum profundus (FDP) to the index finger and sometimes long finger, and pronator quadratus (PQ). The remainder of the nerve is largely sensory, with a small motor component contributing to the recurrent motor branch, which innervates the thenar muscles (abductor pollicis brevis, opponens pollicis and the superficial head of flexor pollicis brevis) and the two radial lumbricals.

Patients presenting with a median nerve injury will have numbness in the distribution of the median nerve. Depending on the level of injury, motor deficits will vary.

Hints and tips

Priorities with median nerve injury are to re-establish anterior interosseous nerve (AIN) function, thumb opposition, index and long finger flexion, and critical sensation to the first webspace. A combination of nerve and tendon transfers can be done. For reconstruction of proximal median nerve injuries, radial to median nerve transfers are used. For reconstruction of more distal median nerve or isolated AIN injuries, brachialis to AIN branch transfers can be done. This transfer is also useful for patients with lower plexus injuries.

Reconstruction techniques

Use of radial to median branch nerve transfers (motor)

Branches of the radial nerve may be used to restore median nerve function in a proximal median nerve injury.¹⁷ Transfer of the extensor carpi radialis brevis branch (ECRB) of the radial nerve is used to restore PT function. Transfer of the supinator branch is used to restore anterior interosseous nerve (AIN) function (Fig. 33.15). A volar forearm incision with step lengthening of the PT and release of the deep head will facilitate visualization. The median nerve is identified and dissected to reveal the PT and AIN recipient branches. The nerve to supinator is identified on the posterior aspect of the radial nerve and the ECRB nerve is also identified. There are two fascicles to the ECRB and use of one branch is sufficient to restore pronation. Recovery of pronation occurs approximately 3–4 months postoperatively. If AIN function is required, the authors recommend using the nerve to brachialis (described below).

Use of brachialis branch to AIN branch nerve transfer

The brachialis branch of the musculocutaneous nerve may be used to restore AIN function (or, as noted above, in the setting of a lower brachial plexus injury) (Fig. 33.16).³¹ A medial arm incision is made and the donor nerve to brachialis is then followed distally into the muscle as far as possible and divided. It is transposed over to the median nerve to identify the level for coaptation, and an internal neurolysis of the median nerve is performed (Fig. 33.17). Knowledge of the internal topography of the median nerve is crucial to performing this transfer. The lateral aspect of the median nerve is all sensory, and the medial aspect is motor. The AIN portion of the nerve is located at the posterior medial aspect of the nerve. Those performing this procedure for the first time may prefer to dissect the AIN out distally and then visually and, intermittently, physically neurolyze to confirm that the correct recipient fascicles have been identified. These recipient fascicles are neurotized and divided proximally. Of note, the nerve to the pronator can be included in this transfer to augment AIN function.

Sensory nerve transfer to restore critical sensation to the first webspace is also recommended (see below).

Use of adjunct tendon transfers to augment nerve transfers

Tendon transfers can be utilized to augment nerve transfers in median nerve injury. The most commonly performed tendon transfer would be to restore thumb opposition, as this is innervated by the most distal branches of the median nerve and will be slowest to recover. The authors' preference for restoration of thumb opposition is transfer of extensor indicis proprius tendon to abductor pollicis brevis. Another option is to use extensor digiti minimi.

Ulnar nerve injury

Specific patient exam findings

Patients presenting with an ulnar nerve injury will have numbness in the small and ulnar side of the ring finger.




Fig. 33.15 A schematic of radial to median nerve transfers. **(A)** The radial nerve is visualized superiorly as it branches into three branches, from lateral to medial: posterior interosseous nerve (PIN), extensor carpi radialis brevis (ECRB), and radial sensory. The donor ECRB nerve is green. The median nerve is visualized inferiorly, with the non-functioning anterior interosseous nerve (AIN) illustrated branching off the lateral aspect of the nerve (red). Note that the AIN is the only branch to exit radially. **(B)** The donor ECRB nerve has been coapted end to end with the distal recipient AIN nerve.

Depending on the level of injury, sensation to the dorsum of the hand and wrist may also be affected. The motor deficits associated with ulnar nerve injury are particularly devastating. The deep motor branch of the ulnar nerve innervates all of the intrinsic muscles of the hand, and injury results in the inability to pinch, abduct, and adduct the fingers, and impairs power grasp. More proximal injuries will also further impair grip, with added losses of the FDP to the small and ring fingers and FCU.

Hints and tips

Priorities for ulnar nerve injury are to re-establish intrinsic muscle function, especially pinch, ring, and small finger flexion, and critical sensation to the ulnar border of the hand. A combination of nerve and tendon transfers can be done. For reconstruction of proximal nerve injuries, a direct end-to-end anterior interosseous nerve (AIN) to deep motor branch of ulnar nerve transfer is useful. For incomplete, or partial, nerve injuries where level of recovery is uncertain, reverse end-to-side AIN to deep motor branch “supercharging” should be considered.




Fig. 33.16 A schematic of the nerve to brachialis to anterior interosseous nerve transfer. **(A)** The median nerve (pink) and musculocutaneous nerve (yellow) are shown in their normal anatomic position. Note that the branch to brachialis exits medially approximately 13 cm to the elbow crease. **(B)** The brachialis branch of the musculocutaneous nerve (donor) is coapted end to end with the divided distal end of the anterior interosseous nerve (recipient), which is located on the posterior medial aspect of the median nerve in the arm.

Reconstruction techniques

Use of median to ulnar branch nerve transfers (motor)

The median nerve may be used to restore ulnar nerve function, especially following very proximal injuries where time to regenerate to motor end plate becomes an issue. Both sensory and motor nerve transfers are utilized to restore

optimal function. The sensory nerve transfers are described later. For restoration of intrinsic muscle function, the distal AIN nerve is transferred to the deep motor branch of the ulnar nerve at the distal forearm level (Fig. 33.18).^{9,32} Release of the nerve through Guyon's canal, with particular attention to adequate release of the deep motor branch, is an essential component of this transfer.⁹ Use of a volar forearm incision





Fig. 33.17 Clinical photos of nerve to brachialis to anterior interosseous nerve. A clinical example of a nerve to brachialis to anterior interosseous nerve (AIN) transfer. **(A)** The median nerve is isolated with a vessel loop. Forceps are used to reveal the AIN nerve branching off the radial aspect of the median nerve. **(B)** A magnified view illustrating the branch to brachialis (marked with a vessel loop) divided and transposed over, to be coapted end to end with the recipient distal AIN.




Fig. 33.18 Anterior interosseous nerve (AIN) to deep motor branch of ulnar nerve. A schematic of the distal AIN to deep motor branch transfer. The donor AIN (green) is seen divided under the pronator quadratus muscle and transposed over to the recipient deep motor branch of the ulnar nerve. At this level, distal to the take off the dorsal cutaneous ulnar branch, the motor fascicles are ulnar and the main sensory component of the nerve is radial. The coaptation is performed in an end-to-end manner. FDS, Flexor digitorum superficialis; FDP, flexor digitorum profundus.

and retraction of the flexor tendons radially allow visualization of the donor AIN as it enters into the deep surface of the PQ. The AIN is dissected distally into the mid-substance of the muscle and divided. It is transposed over to the ulnar nerve to identify the point where it can be coapted with no tension (Fig. 33.19). At this point, the neurolysis of the ulnar nerve is performed. Within the proximal forearm, prior to the take off the dorsal cutaneous branch, the topography of the ulnar nerve is sensory-motor-sensory. The medial-most sensory portion goes on to become the dorsal cutaneous ulnar branch (DCU) approximately 9 cm proximal to the wrist crease. As the nerve continues, the lateral sensory portion of the ulnar nerve is significantly larger than the more medial motor portion. Microforceps are used to tap along the surface of the nerve until they plunge into the natural cleavage plane between the sensory and motor portions of the nerve.³² Visual

neurolysis from the deep motor branch decompression at the leading edge of the hypothenar muscles confirms this. Once this plane is identified, the recipient motor fascicular group is isolated proximally and divided to allow for the appropriate motor nerve transfer.

Sensory nerve transfer to the ulnar border of the hand is recommended (see below).

Use of adjunct tendon transfers to augment nerve transfers

Tendon transfers are frequently performed to augment median to ulnar nerve transfers. The intrinsic muscles are so distal and are so important for function that these tendon transfers are often performed at the same time as the nerve transfers, even though their use might be considered redundant. Tenodesis of the ulnar nerve-powered ring and small FDP tendons to the median nerve-powered index and long FDP tendons is performed. Thumb adduction is also augmented using



Fig. 33.19 Clinical photos of anterior interosseous nerve (AIN) to deep motor branch of ulnar nerve. Clinical example of an AIN to deep motor branch nerve transfer. (A) A vessel loop surrounds the distal AIN. The ulnar nerve is exposed on a blue background. The dorsal cutaneous ulnar branch is illustrated branching off ulnarly. (B) The donor AIN is divided distally and transposed over to the ulnar nerve. The dorsal cutaneous branch of the ulnar nerve is now located beneath the blue background, and a motor fascicle from the ulnar aspect of the main nerve is divided as the recipient and coapted end to end to the AIN nerve.

extensor indicis proprius to adductor pollicis tendon transfer. In patients with a prominent Wartenberg's sign, abductor digiti minimi is transferred to the extensor digitorum communis tendon of the small finger.³²

Radial nerve injury

Specific patient exam findings

The radial nerve is a mixed motor and sensory nerve that receives contribution from C5, C6, C7, C8, and T1. The radial nerve proper innervates the three heads of the triceps muscle, anconeus epitrochlearis, brachioradialis, and extensor carpi radialis longus (ECRL). The nerve then branches into the posterior interosseous nerve (PIN) and radial sensory nerve (RSN). The PIN then innervates the ECRB, supinator, extensor carpi ulnaris, extensor indicis proprius, extensor digitorum communis, extensor digiti minimi, abductor pollicis longus, extensor pollicis longus, and extensor pollicis brevis. Of note, the ECRB branch can occasionally come off the radial nerve proper or branch off along with the radial sensory nerve, meaning that wrist extension can be variably affected in injuries at this level depending on individual anatomy.

Patients presenting with radial nerve injuries will have sensory defects in the distribution of the radial nerve. Motor deficits will depend on the level of injury. Isolated radial nerve injuries are typically distal to the triceps, so elbow extension is often preserved.

Hints and tips

Priorities with radial nerve injury are to re-establish wrist, finger, and thumb extension. Unlike tendon transfers, use of median-to-radial nerve transfers allows for individual and separate finger extension in addition to wrist and thumb extension.

Reconstruction techniques

Use of median to radial branch nerve transfers

The most commonly performed transfers include using redundant fascicles to FDS or FCR as donors to provide innervation to PIN and ECRB (Fig. 33.20).³³ An incision is made at the volar forearm and step lengthening of the PT may be performed to improve visualization. Knowledge of the internal topography of the median nerve is essential for this transfer, as protection of the branches to PT and AIN is mandatory. The most proximal branches, of which there are usually two, are to PT. Then, a branch to FCR and PL departs from the ulnar side of the nerve. The next two branches will be to the FDS and also depart ulnarly. The AIN departs from the median nerve on the radial side, and is the only branch to exit radially. The remaining sensory and thenar branches continue distally.

The recipient radial nerve branches are identified by retracting the brachioradialis laterally. The first nerve encountered will be the radial sensory branch, followed by the smaller branch to ECRB and the larger PIN located just deep and radial to the sensory branch. These recipient nerves are dissected as proximally as possible and then transected. Mobilization is facilitated by excluding the branch to the supinator, which comes off posteriorly. The recipient nerves

are then transposed over to the median nerve to determine the level for neurolysis. The median nerve is dissected and redundant fascicles to FDS and FCR are divided and transferred. Motor reinnervation occurs at approximately 9–12 months postoperatively.

Use of adjunct tendon transfers to augment nerve transfers

The authors suggest augmenting median to radial nerve transfers with tendon transfer of PT to ECRB during the same procedure. This transfer provides earlier restoration of wrist extension, which is then enhanced once the nerve transfer becomes viable at 9–12 months.

Sensory nerve injury

Restoration of key sensory functions

Restoration of discriminatory sensation in critical areas can be accomplished using noncritical area donors. One of the newer developments in nerve transfer surgery is to maintain some donor territory protective sensation by use of adjunct end-to-side transfers. A number of studies have demonstrated that “collateral sprouting” occurs with an end-to-side sensory repair, and novel axonal regeneration from the donor nerve occurs into the recipient stump.⁸ Only sensory axons sprout *de novo* without injury, whereas motor nerves require a proximal nerve injury to do so.⁸ Making use of this principle, efforts are made to restore protective sensation to the donor region with end-to-side coaptation of the distal donor to an intact sensory nerve.

Use of ulnar to median branch nerve transfers (sensory)

A fourth webspace (ulnar) to first webspace (median) nerve transfer can be performed to restore critical first webspace sensation only. Alternatively, a triad of nerve transfers from the ulnar nerve can restore more extensive sensation and minimize donor deficits (Fig. 33.21). The DCU is transferred end to end to the radial portion of the median nerve to restore critical thumb and radial index sensation. The nerve to the third webspace is the most ulnar portion grouping of fascicles at this level (Fig. 33.22). It is coapted end to side to the main sensory component of the ulnar nerve for restoration of third webspace protective sensation. The distal end of the transected donor DCU is coapted end to side to the ulnar nerve to restore the donor deficit.³²

Use of median to ulnar branch nerve transfers (sensory)

A third webspace (median) to ulnar small-finger nerve transfer can be used to restore sensation to the ulnar border of the hand. Alternatively, restoration of ulnar nerve sensation can be provided by a triad of nerve transfers from the median nerve (Fig. 33.23). The third webspace fascicle of the median nerve is transferred end to end to the main sensory component of the ulnar nerve (Fig. 33.24). End-to-side coaptation of the dorsal cutaneous ulnar branch to the sensory component of the median nerve is performed more proximally. The distal third webspace (median) donor is then coapted end to side to the remainder of the intact sensory portion of the median nerve to restore protective sensation to the donor defect.




Fig. 33.20 Median to radial nerve transfers. A schematic diagram of median to radial nerve transfers. The redundant fascicles to flexor carpi radialis (FCR) and flexor digitorum superficialis (FDS) (donors) are transferred to the extensor carpi radialis brevis (ECRB) and posterior interosseous nerve (PIN) respectively.

Use of median and ulnar nerve transfers to restore first webspace sensation in C5–C6 root level brachial plexus injury (sensory)

In patients with an isolated upper trunk injury, sensation to the first and second webspaces will be absent. A combination of distal transfers at the level of the median and ulnar nerve proper can be used to reconstruct this deficit (Fig. 33.25). The third webspace nerve is transected and coapted end to end to the radial aspect of the median nerve to restore thumb and first webspace sensation. The distal end of the transected third webspace is coapted end to side to the ulnar nerve to restore protective sensation of the donor site. This effectively transfers intact sensation that originated from the

C7 and C8 roots to the C5 and C6 level at a close-to-target end organ level.

Use of lateral antebrachial cutaneous nerve to radial nerve transfers (sensory)

Patients with radial sensory nerve injury have numbness on the dorsal radial aspect of the hand and wrist. Unfortunately, this injury is also commonly associated with excruciating phantom pain due to this nerve's exquisite sensitivity to denervation. The lateral antebrachial cutaneous nerve runs superficial and medial to the brachioradialis and is in close proximity to the radial sensory nerve. It is also a close size match. Coaptation of the expendable lateral




Fig. 33.21 A schematic of the triad of transfers used to restore sensation in a median nerve deficit. **(A)** The non-functional median (red) and the functioning ulnar nerve (yellow). **(B)** The triad of nerve transfers from ulnar to median (inset) is a magnification of the transfers showing the dorsal cutaneous branch of the ulnar nerve (donor) coapted end to end to the radial side of the median (recipient) to restore first webspace sensation, the distal third webspace (recipient) end to side to the ulnar sensory (donor), and the distal dorsal cutaneous branch of the ulnar nerve end to side to restore sensation to the donor deficit. The third webspace fascicle is shown in blue.

antebrachial cutaneous nerve (LABC) to the denervated radial sensory nerve territory may not restore completely normal sensation, but can significantly interrupt the neuropathic pain cycle.

Use of radial to axillary nerve transfers (sensory)

Patients with axillary nerve injury have numbness on the lateral aspect of the shoulder. To treat this, the sensory portion of the axillary nerve can be transferred end to side to a

functioning intact nerve such as the radial. At this level, the internal topography of the radial nerve is such that the lateral aspect is sensory.

Postoperative care

Postoperative wound care

Patients are initially placed into a bulky soft dressing for comfort. Patients are encouraged to move their extremity early to promote nerve gliding, as all nerve transfers are performed under no tension.³⁴ Concomitant tendon transfers may also dictate splinting and therapy regimens and will supersede the minor restrictions required for post nerve transfer patients. If the insertion of the pectoralis major muscle was disinserted to allow access to the medial pectoral nerve, the tendon is reapproximated and the shoulder is immobilized for a full 4 weeks.³⁴

Complications

Complications specific to nerve surgery include temporary pain, paresthesias, or motor neurapraxia secondary to retraction or manipulation of nerves; neuroma; and inadequate functional recovery. The complication rate associated with nerve transfer should be significantly less than that seen with operating within a scarred and hostile zone of injury. Nerve transfers are performed remote from the time of injury, thus ensuring that patients have been stabilized, appropriately evaluated and educated, serially clinically examined, and perhaps most importantly, that surgery takes place during regular, scheduled hours with a staff familiar with the procedure, as opposed to exploratory repair in a trauma or after-hours situation.




Fig. 33.22 Identifying the fascicle to the third webspace. This clinical photograph demonstrates identifying the third webspace fascicle at the proximal wrist level. Microforceps were walked along the surface of the nerve until they plunged into the natural cleavage plane. The division is also marked with a prominent vessel on the surface of the nerve.




Fig. 33.23 Sensory nerve transfers to restore ulnar nerve deficit. A schematic of the triad of nerve transfers used to restore ulnar nerve sensation. **(A)** The functioning median nerve is shown in yellow and the non-functioning ulnar nerve is shown in red. **(B)** The triad of nerve transfers to restore sensation. (Inset) A magnified view of the nerve transfers illustrating the third webspace fascicle (donor) coapted end to end with the ulnar sensory (recipient), the distal dorsal cutaneous branch of the ulnar nerve (recipient) coapted end to side to the sensory side of the intact median nerve (donor), and the distal third webspace nerve coapted end to side to the median sensory to restore donor sensory loss.

Rehabilitation

All patients are introduced to our hand therapists prior to surgery and referrals for therapy are given at the first postoperative visit. Patients are instructed about wound and scar management, the need for protective splinting or sling use, and pain management. Wrist cock-up splints are used in




Fig. 33.24 Internal topography of the ulnar nerve in the distal forearm. A clinical photograph illustrating the internal topography of a neurolyzed ulnar nerve at the wrist. The tenotomy scissors are displacing the dorsal cutaneous branch of the ulnar nerve ulnarly, the microforceps are separating the deep motor branch fascicles ulnarly, and the remainder of the radial portion of the nerve is sensory. At this level, the topography of the ulnar nerve is sensory-motor-sensory in a radial to ulnar direction.

patients with radial nerve injuries until reinnervation occurs. Supportive braces for patients with painful humeral subluxation at the glenohumeral joint due to loss of deltoid function can also be used. Education about their nerve transfer is provided, and retraining is discussed in the early postoperative period, long before clinical recovery will have occurred, to keep the motor cortex prepared for reinnervation.^{34,35} The long-term focus of rehabilitation is on re-education, as the cortical command required to initiate target muscle function will differ from before. The patient will “relearn” motor control of the reinnervated target muscle by activating the nerve to the donor muscle, similar to the re-education required following tendon transfer. For restoration of sensation, as patients perceive input stimulus from the reinnervated territory, cortical remapping occurs. Patients are provided with written instructions about exercises as well as an anticipated timeline for recovery.

Prior to reinnervation, the focus is on maintaining full active and passive range of motion and on prevention of pain syndromes related to musculoskeletal imbalances associated with lost or impaired muscle strength. Therapists also work to optimize strength of uninvolved and donor muscles following transfer.

Once reinnervation has occurred, therapy is focused on strengthening. Maintaining full passive range of motion throughout is paramount. Patients may start by “strengthening the donor” and then advance to co-contraction activities as reinnervation proceeds. For example, this would include finger and wrist flexion with elbow flexion in double fascicular nerve transfer patients. Specific strategies involve repetitive motor co-contraction of the donor and recipient muscles, with and without passive assistance. The incorporation of resistance into the exercises is progressive as tolerated, starting with gravity completely eliminated and then against




Fig. 33.25 Sensory nerve transfers to restore C5/C6 deficit. A schematic of sensory nerve transfers used to restore sensation to the first webspace following C5/C6 root injuries of the brachial plexus. **(A)** The non-functional nerves are visualized in red and the functioning nerves are yellow. **(B)** The ulnar and median nerves are used to restore sensation to the first webspace and the radial border of the thumb. (Inset) A magnified view of the nerve transfers illustrating end-to-end coaptation of the third webspace nerve (donor) to the first webspace nerve (recipient). The distal third webspace nerve is then coapted end to side with the sensory portion of the ulnar nerve to restore sensation to the donor third webspace.




Fig. 33.26 (A–D) A 25-year-old right-handed female with a traumatic proximal ulnar nerve laceration. She underwent primary repair of the ulnar nerve transection at the time of initial injury by another surgeon. For timely restoration of intrinsic function, she underwent a distal nerve transfer procedure at 1 month post-injury. A distal anterior interosseous nerve (to pronator quadratus) to deep motor branch of ulnar nerve end-to-end coaptation was performed. At nearly 2 years post-injury, she has no significant clawing, improved strength (pinch of 18 on the right, 12 on the left; grip of 70 on the right, 60 on the left), and reasonable intrinsic function (intact abduction, adduction with simultaneous lumbrical plus positioning), residual Froment's sign and inability to cross the fingers. She has resumed all of her baseline work (desk job) and leisure (weightlifting) activities and is not interested in further surgery. (© 2015 nervesurgery.wustl.edu.)

gravity, and finally against resistance. Place-and-hold exercises facilitate strengthening. Resisted exercises are introduced much later, after good movement against gravity is obtained, to avoid overfatiguing the transfer and discouraging the patient.

In severe injuries, hand therapists can instruct patients in adaptive strategies for handedness retraining and performing activities of daily living with their impaired extremity. We have found that hand therapy is an integral part of the success of our nerve transfers.

Outcomes and prognosis

The evaluation of outcomes following brachial plexus and peripheral nerve reconstruction lacks standardization and objectivity, largely given the extent and variation of nerve injuries.³⁴ In addition, the expected outcomes vary with the initial injury, given that nerve transfer for a partial, distal nerve defect would be anticipated to have near-complete function following surgery compared to a pan-plexus type of injury presenting with a flail extremity, where expectations are significantly lower. Due to these difficulties, it is difficult to compare different surgical approaches with regard to patient outcome and prognosis; however, there have been numerous articles reporting favorable outcomes on an increasing number of nerve transfer options.

We feel shoulder function is best improved by reinnervation of both suprascapular and axillary nerves, confirmed in a large meta-analysis of 1088 nerve transfers.²¹ Variable levels of transfer and incomplete inclusion of all the branches of the axillary nerve (to teres minor and the anterior, middle, and posterior deltoid) may, in part, explain the continued debate in the literature about the variable conclusions regarding the superiority of transfer versus direct repair or interposition grafting.^{36–38} In a recent study by Garg *et al.*, the use of dual nerve transfers to restore shoulder and elbow function in C5/C6-level injuries was superior to the results of traditional nerve grafting.³⁹ In a clinical series of seven patients undergoing nerve transfer from triceps to axillary nerve, all patients recovered MRC 4/5 power. Five of the patients had excellent recoveries and 2 showed good results.⁴⁰

The double fascicular nerve transfer has been evaluated with long-term follow-up in more than one study, and all patients were noted to achieve at least MRC grade 4 of 5 function with no appreciable donor deficit. Innervation was noted at a mean of 5.5 months postoperatively.²²

In medial pectoral to musculocutaneous nerve transfers with an interpositional lateral antebrachial cutaneous nerve graft, three of four patients achieved MRC grade 4 of 5 elbow flexion, and the last, MRC grade 3 of 5. Reinnervation was first noted at 6–8 months postoperatively.⁵

Restoration of radial nerve function in the forearm using expendable branches of the median nerve has demonstrated predictable results, with MRC grade 4 of 5 wrist and finger extension by 1 year.⁴¹

In another series, eight patients undergoing transfer of the distal AIN to the deep motor branch of the ulnar nerve were evaluated. All patients had reinnervation of the ulnar intrinsic muscles facilitating grip and lateral pinch strength. No patient required ant Claw procedures. None of the patients had a deficit in pronation associated with AIN transfer (Fig.

33.26A–D). A single patient required a secondary tendon transfer to improve small-finger adduction.⁹

Inevitably, the literature contains much controversy regarding the outcomes following nerve transfers, and longer follow-up is required to assess the success of these novel procedures. This is particularly true because the continued effect of cortical remodeling as demonstrated with functional MRI studies as well as gradual strengthening and incorporation of the restored function has been shown to continue for as long as 5 years or more post-transfer surgery. It seems clear, however, that the exponential increase in publications related to nerve transfers demonstrates that nerve transfers can no longer be considered experimental, and are rivaling other procedures in the treatment of severe brachial plexus and many other peripheral nerve injuries.

Secondary procedures

Given the devastating nature of brachial plexus and proximal nerve injuries, it is inevitable that nerve transfers are not successful in every circumstance. Where concern exists regarding the likelihood of functional recovery, adjunct procedures are performed to augment the nerve transfer.

In the event of a failed nerve transfer and the necessity of further secondary procedures, there are several important considerations. When planning nerve transfers, one must consider the possible salvage procedures required should the transfer fail. Thus, when deciding on donor nerve, it is prudent to ensure that options are left for later (for example, avoiding the harvest of redundant fascicles to both flexor carpi radialis and FCU). A donor for tendon transfer requires MRC grade 5 of 5 strength because following transfer it will be downgraded by a minimum of one grade. This becomes especially challenging in patients with multiple nerve injuries, and illustrates the importance of an accurate and detailed physical examination at preoperative assessment.

Hints and tips

Avoid using a donor nerve that may be required for a secondary procedure such as a tendon transfer down the road. Prior to cutting a donor nerve, make sure the rest of the nerve performs all essential functions with fastidious intraoperative nerve stimulation.

Tendon transfers have the benefit of not being restricted by time, given that distal motor denervation and fibrosis do not affect the outcome. For this reason, there is no harm in attempting a nerve transfer as a primary procedure (as long as it is completed within the timeframe to achieve motor reinnervation, which is approximately within 12 months post-injury), and reserving the tendon transfer for a secondary procedure if the functional outcome is less than desired.

Nerve transfers should not be attempted if there are not suitable, redundant, available donors, as in the setting of a multineurve injury. In this setting, nerve grafting combined with tendon transfer, or even arthrodesis, may be warranted.

In our experience, secondary procedures are rarely required following nerve transfer. However, we are diligent about considering options when planning our initial procedure.

Future directions

Nerve transfer techniques have proved to be a powerful tool to restore meaning function. More recent work expands their application in a variety of directions.

In peripheral nerve and brachial plexus injury, novel combinations of sensory and motor transfers^{42–45} based on the principles of expendable donor, appropriate recipient and knowledge of internal topography continue to expand the literature. Early reports of adaptation to lower extremity nerve injury patterns,^{46–49} while more limited by the greater distances to target, are encouraging. Broadened applications to pediatrics^{50,51} and central nervous system disorders such as spinal cord injury^{52–59} and transverse myelitis⁶⁰ will require a cautious approach and ongoing study to avoid potential harms in these complicated and vulnerable patients.



Access the complete reference list online at

<http://www.expertconsult.com>

8. Hayashi A, Pannucci C, Moradzadeh A, et al. Axotomy or compression is required for axonal sprouting following end-to-side neurorrhaphy. *Exp Neurol*. 2008;211:539–550. *This study demonstrated that sensory nerves would collaterally sprout from a normal nerve into a distal end-to-side-positioned nerve spontaneously. By contrast it showed that a motor nerve needed an injury in order to sprout (traumatic sprouting). This is a significant paper in that it shows that if you want to get some sensory recovery, then the end-to-side will work, but if you want motor, you need to injure the motor nerve traumatically in order to get it to sprout in an end-to-side fashion.*
10. Kale SS, Glaus SW, Yee A, et al. Reverse end-to-side nerve transfer: from animal model to clinical use. *J Hand Surg Am*. 2011;36:1631–1639.e2.
16. Kozin SH. Injuries of the brachial plexus. In: Ianotti JP, ed. *Disorders of the Shoulder: Diagnosis and Management*. Philadelphia, PA: Lippincott Williams & Wilkins; 2007:1087–1130.
32. Brown JM, Yee A, Mackinnon SE. Distal median to ulnar nerve transfers to restore ulnar motor and sensory function within the hand: technical nuances. *Neurosurgery*. 2009;65:966–977, discussion 977–8. *This is an up-to-date description of the technical nuances of transfer from the distal anterior interosseous nerve to the motor component of the ulnar nerve. This anterior interosseous nerve to deep motor branch of ulnar nerve was first done by the authors in 1991 and is generally accepted as a procedure of choice for high ulnar nerve problems.*
33. Ray WZ, Mackinnon SE. Clinical outcomes following median to radial nerve transfers. *J Hand Surg Am*. 2011;36:201–208. *This manuscript describes the outcome of a number of patients undergoing median to radial nerve transfer and provides the technical nuances and the pearls and pitfalls of this nerve transfer.*
34. Tung TH, Mackinnon SE. Nerve transfers: indications, techniques, and outcomes. *J Hand Surg Am*. 2010;35:332–341.
35. Mackinnon SE, Novak CB (eds). Nerve Transfers issue. *Hand Clin*. 2008;24:319–488. *This Hand Clinics is a multiauthored text covering all aspects of nerve transfers from surgical techniques to physical therapy.*

References

- Boyd KU, Nimigan AS, Mackinnon SE. Nerve reconstruction in the hand and upper extremity. *Clin Plast Surg*. 2011;38:643–660.
- Lee SK, Wolfe SW. Nerve transfers for the upper extremity: new horizons in nerve reconstruction. *J Am Acad Orthop Surg*. 2012;20:506–517.
- Tung TH. Nerve transfers. *Clin Plast Surg*. 2014;41:551–559.
- Fox IK, Mackinnon SE, Yee A. <nerve surgery.wustl.edu>.
- Brandt KE, Mackinnon SE. A technique for maximizing biceps recovery in brachial plexus reconstruction. *J Hand Surg Am*. 1993;18:726–733.
- Mackinnon SE. New directions in peripheral nerve surgery. *Ann Plast Surg*. 1989;22:257–273.
- Oberlin C, Beal D, Leechavengvongs S, et al. Nerve transfer to biceps muscle using a part of ulnar nerve for C5–C6 avulsion of the brachial plexus: anatomical study and report of four cases. *J Hand Surg Am*. 1994;19:232–237.
- Hayashi A, Pannucci C, Moradzadeh A, et al. Axotomy or compression is required for axonal sprouting following end-to-side neurorrhaphy. *Exp Neurol*. 2008;211:539–550. *This study demonstrated that sensory nerves would collaterally sprout from a normal nerve into a distal end-to-side-positioned nerve spontaneously. By contrast it showed that a motor nerve needed an injury in order to sprout (traumatic sprouting). This is a significant paper in that it shows that if you want to get some sensory recovery, then the end-to-side will work, but if you want motor, you need to injure the motor nerve traumatically in order to get it to sprout in an end-to-side fashion.*
- Novak CB, Mackinnon SE. Distal anterior interosseous nerve transfer to the deep motor branch of the ulnar nerve for reconstruction of high ulnar nerve injuries. *J Reconstr Microsurg*. 2002;18:459–464.
- Kale SS, Glaus SW, Yee A, et al. Reverse end-to-side nerve transfer: from animal model to clinical use. *J Hand Surg Am*. 2011;36:1631–1639.e2.
- Farber SJ, Glaus SW, Moore AM, et al. Supercharge nerve transfer to enhance motor recovery: a laboratory study. *J Hand Surg Am*. 2013;38:466–477.
- Fox IK, Mackinnon SE. Adult peripheral nerve disorders: nerve entrapment, repair, transfer, and brachial plexus disorders. *Plast Reconstr Surg*. 2011;127:105e–118e.
- Dolan RT, Butler JS, Murphy SM, et al. Health-related quality of life and functional outcomes following nerve transfers for traumatic upper brachial plexus injuries. *J Hand Surg Eur Vol*. 2012;37:642–651.
- Strauch B, Lang A, Ferder M, et al. The ten test. *Plast Reconstr Surg*. 1997;99:1074–1078.
- Kovachevich R, Kircher MF, Wood CM, et al. Complications of intercostal nerve transfer for brachial plexus reconstruction. *J Hand Surg Am*. 2010;35:1995–2000.
- Kozin SH. Injuries of the brachial plexus. In: Ianotti JP, ed. *Disorders of the Shoulder: Diagnosis and Management*. Philadelphia, PA: Lippincott Williams & Wilkins; 2007:1087–1130.
- Hsiao EC, Fox IK, Tung TH, et al. Motor nerve transfers to restore extrinsic median nerve function: case report. *Hand (N Y)*. 2009;4:92–97.
- Colbert SH, Mackinnon S. Posterior approach for double nerve transfer for restoration of shoulder function in upper brachial plexus palsy. *Hand (N Y)*. 2006;1:71–77.
- Ray WZ, Kasukurthi R, Yee A, et al. Functional recovery following an end to side neurorrhaphy of the accessory nerve to the suprascapular nerve: case report. *Hand (N Y)*. 2010;5:313–317.
- Leechavengvongs S, Witoonchart K, Uerpaiojkit C, et al. Nerve transfer to deltoid muscle using the nerve to the long head of the triceps, part II: a report of 7 cases. *J Hand Surg Am*. 2003;28:633–638.
- Merrell GA, Barrie KA, Katz DL, et al. Results of nerve transfer techniques for restoration of shoulder and elbow function in the context of a meta-analysis of the English literature. *J Hand Surg Am*. 2001;26:303–314.
- Mackinnon SE, Novak CB, Myckatyn TM, et al. Results of reinnervation of the biceps and brachialis muscles with a double fascicular transfer for elbow flexion. *J Hand Surg Am*. 2005;30:978–985.
- Carlsen BT, Kircher MF, Spinner RJ, et al. Comparison of single versus double nerve transfers for elbow flexion after brachial plexus injury. *Plast Reconstr Surg*. 2011;127:269–276.
- Aszmann OC, Rab M, Kamolz L, et al. The anatomy of the pectoral nerves and their significance in brachial plexus reconstruction. *J Hand Surg Am*. 2000;25:942–947.
- Garcia-Lopez A, Sebastian P, Martinez F, et al. Transfer of the nerve to the brachioradialis muscle to the anterior interosseous nerve for treatment for lower brachial plexus lesions: case report. *J Hand Surg Am*. 2011;36:394–397.
- Bertelli JA, Ghizoni MF. Transfer of supinator motor branches to the posterior interosseous nerve in C7–T1 brachial plexus palsy. *J Neurosurg*. 2010;113:129–132.
- Doi K, Muramatsu K, Hottori Y, et al. Reconstruction of upper extremity function in brachial plexopathy using double free gracilis flaps. *Tech Hand Up Extrem Surg*. 2000;4:34–43.
- Terzis JK, Kokkalis ZT. Selective contralateral C7 transfer in posttraumatic brachial plexus injuries: a report of 56 cases. *Plast Reconstr Surg*. 2009;123:927–938.
- Wang L, Zhao X, Gao K, et al. Reinnervation of thenar muscle after repair of total brachial plexus avulsion injury with contralateral C7 root transfer: report of five cases. *Microsurgery*. 2011;31:323–326.
- Sammer DM, Kircher MF, Bishop AT, et al. Hemi-contralateral C7 transfer in traumatic brachial plexus injuries: outcomes and complications. *J Bone Joint Surg Am*. 2012;94:131–137.
- Zheng XY, Hou CL, Gu YD, et al. Repair of brachial plexus lower trunk injury by transferring brachialis muscle branch of musculocutaneous nerve: anatomic feasibility and clinical trials. *Chin Med J*. 2008;121:99–104.
- Brown JM, Yee A, Mackinnon SE. Distal median to ulnar nerve transfers to restore ulnar motor and sensory function within the hand: technical nuances. *Neurosurgery*. 2009;65:966–977, discussion 977–8. *This is an up-to-date description of the technical nuances of transfer from the distal anterior interosseous nerve to the motor component of the ulnar nerve. This anterior interosseous nerve to deep motor branch of ulnar nerve was first done by the authors in 1991 and is generally accepted as a procedure of choice for high ulnar nerve problems.*
- Ray WZ, Mackinnon SE. Clinical outcomes following median to radial nerve transfers. *J Hand Surg Am*. 2011;36:201–208. *This manuscript describes the outcome of a number of patients undergoing median to radial nerve transfer and provides the technical nuances and the pearls and pitfalls of this nerve transfer.*
- Tung TH, Mackinnon SE. Nerve transfers: indications, techniques, and outcomes. *J Hand Surg Am*. 2010;35:332–341.
- Mackinnon SE, Novak CB (eds). Nerve Transfers issue. *Hand Clin*. 2008;24:319–488. *This Hand Clinics is a multiauthored text covering all aspects of nerve transfers from surgical techniques to physical therapy.*
- Yang LJ, Chang KW, Chung KC. A systematic review of nerve transfer and nerve repair for the treatment of adult upper brachial plexus injury. *Neurosurgery*. 2012;71:417–429, discussion 29.
- Wolfe SW, Johnsen PH, Lee SK, et al. Long-nerve grafts and nerve transfers demonstrate comparable outcomes for axillary nerve injuries. *J Hand Surg Am*. 2014;39:1351–1357.
- Terzis JK, Barmptsioti A. Axillary nerve reconstruction in 176 posttraumatic plexopathy patients. *Plast Reconstr Surg*. 2010;125:233–247.
- Garg R, Merrell GA, Hillstrom HJ, et al. Comparison of nerve transfers and nerve grafting for traumatic upper plexus palsy: a systematic review and analysis. *J Bone Joint Surg Am*. 2011;93:819–829.
- Leechavengvongs S, Witoonchart K, Uerpaiojkit C. Thuvasethakul P. Nerve transfer to deltoid muscle using the nerve to the long head of the triceps, part II: a report of 7 cases. *J Hand Surg Am*. 2003;28(4):633–638.
- Ray WZ, Mackinnon SE. Clinical outcomes following median to radial nerve transfers. *J Hand Surg Am*. 2011;36:201–208.
- Phillips BZ, Franco MJ, Yee A, et al. Direct radial to ulnar nerve transfer to restore intrinsic muscle function in combined proximal

- median and ulnar nerve injury: case report and surgical technique. *J Hand Surg Am.* 2014;39:1358–1362.
43. Pet MA, Ray WZ, Yee A, et al. Nerve transfer to the triceps after brachial plexus injury: report of four cases. *J Hand Surg Am.* 2011;36:398–405.
 44. Malungpaishrope K, Leechavengvongs S, Witoonchart K, et al. Simultaneous intercostal nerve transfers to deltoid and triceps muscle through the posterior approach. *J Hand Surg Am.* 2012;37:677–682.
 45. Garcia-Lopez A, Perea D. Transfer of median and ulnar nerve fascicles for lesions of the posterior cord in infraclavicular brachial plexus injury: report of 2 cases. *J Hand Surg Am.* 2012;37:1986–1989.
 46. Tung TH, Chao A, Moore AM. Obturator nerve transfer for femoral nerve reconstruction: anatomic study and clinical application. *Plast Reconstr Surg.* 2012;130:1066–1074.
 47. Giuffre JL, Bishop AT, Spinner RJ, et al. Surgical technique of a partial tibial nerve transfer to the tibialis anterior motor branch for the treatment of peroneal nerve injury. *Ann Plast Surg.* 2012;69:48–53.
 48. Giuffre JL, Bishop AT, Spinner RJ, et al. Partial tibial nerve transfer to the tibialis anterior motor branch to treat peroneal nerve injury after knee trauma. *Clin Orthop Relat Res.* 2012;470:779–790.
 49. Flores LP, Martins RS, Siqueira MG. Clinical results of transferring a motor branch of the tibial nerve to the deep peroneal nerve for treatment of foot drop. *Neurosurgery.* 2013;73:609–615, discussion 15–6.
 50. Zuckerman SL, Eli IM, Shah MN, et al. Radial to axillary nerve neurotization for brachial plexus injury in children: a combined case series. *J Neurosurg Pediatr.* 2014;14:518–526.
 51. Chan KM, Olson JL, Morhart M, et al. Outcomes of nerve transfer versus nerve graft in ulnar nerve laceration. *Can J Neurol Sci.* 2012;39:242–244.
 52. Fox IK, Davidge KM, Novak CB, Hoben G, Kahn LC, Juknis N, Ruvinskaya R, Mackinnon SE. Nerve Transfers to Restore Upper Extremity Function in Cervical Spinal Cord Injury: Update and Preliminary Outcomes. *Plast Reconstr Surg.* 2015;136(4):780–792.
 53. Fox IK, Davidge KM, Novak CB, et al. Use of peripheral nerve transfers in tetraplegia: evaluation of feasibility and morbidity. *Hand (N Y).* 2015;10:60–67.
 54. van Zyl N, Hahn JB, Cooper CA, et al. Upper limb reinnervation in C6 tetraplegia using a triple nerve transfer: case report. *J Hand Surg Am.* 2014;39:1779–1783.
 55. Mackinnon SE, Yee A, Ray WZ. Nerve transfers for the restoration of hand function after spinal cord injury. *J Neurosurg.* 2012;117:176–185.
 56. Friden J, Gohritz A. Brachialis-to-extensor carpi radialis longus selective nerve transfer to restore wrist extension in tetraplegia: case report. *J Hand Surg Am.* 2012;37:1606–1608.
 57. Bertelli JA, Mendes Lehm VL, Tacca CP, et al. Transfer of the distal terminal motor branch of the extensor carpi radialis brevis to the nerve of the flexor pollicis longus: an anatomic study and clinical application in a tetraplegic patient. *Neurosurgery.* 2012;70:1011–1016.
 58. Bertelli JA, Ghizoni MF, Tacca CP. Transfer of the teres minor motor branch for triceps reinnervation in tetraplegia. *J Neurosurg.* 2011;114:1457–1460.
 59. Bertelli JA, Tacca CP, Ghizoni MF, et al. Transfer of supinator motor branches to the posterior interosseous nerve to reconstruct thumb and finger extension in tetraplegia: case report. *J Hand Surg Am.* 2010;35:1647–1651.
 60. Dorsi MJ, Belzberg AJ. Nerve transfers for restoration of upper extremity motor function in a child with upper extremity motor deficits due to transverse myelitis: case report. *Microsurgery.* 2012;32:64–67.

34

Tendon transfer for reconstruction of the wrist and hand

Neil F. Jones

SYNOPSIS

- Tendon transfers in the upper limb are indicated to restore function to paralyzed muscle and tendon following nerve injury, direct muscle or tendon injury, and to restore balance to hands affected by neurological disease.
- In selecting donor tissue, the surgeon has to consider expendability of the muscle–tendon unit, the native strength of donor and paralyzed muscle, and the direction of transfer and integrity of the muscle.
- The timing of tendon transfers can be classified as early, conventional, or late.
- Upper extremity neurological injury can be subdivided into radial nerve palsy, low and high median nerve palsy, low and high ulnar nerve palsy, and combined nerve injuries.

Introduction

Tendon transfers are reconstructive techniques that will restore motion or balance to the hand lost secondary to impaired or absent function of the extrinsic or intrinsic muscle–tendon units of the forearm and hand. In a typical tendon transfer, the tendon of insertion of a functioning muscle is detached, mobilized, and then reattached to another tendon or bone to substitute for the action of a non-functioning muscle–tendon unit. Very occasionally, both the tendon of origin and the tendon of insertion are detached and then reattached at different locations. Unlike a tendon graft, the transferred donor tendon remains attached to its parent muscle. A tendon transfer also differs from a microsurgical free muscle transfer in that the neurovascular pedicle to the muscle of the transferred tendon remains intact.

There are three general indications for tendon transfers in the upper extremity:

1. To restore function to a paralyzed muscle due to injuries of the peripheral nerves, the brachial plexus, or the spinal cord.
2. To restore function following closed tendon ruptures or open injuries to the tendons or muscles.
3. To restore balance to a deformed hand due to various neurological diseases.

Tendon transfers are best conceptualized as a means to restore a lost “function”, rather than a means of substituting for a specific muscle, i.e., restoring strong pinch as opposed to restoring function of the flexor pollicis longus. Tendon transfers are performed predominantly following peripheral nerve injuries and therefore will be discussed according to the three specific nerve palsies. However, the general principles described in this chapter apply to all transfers ([Table 34.1](#)).

General principles

Bone and soft-tissue healing

Steindler¹ first suggested that tendon transfers cannot glide through edematous or scarred soft tissues, nor can they flex or extend stiff metacarpophalangeal (MCP) and proximal interphalangeal (PIP) joints. He therefore advocated that tendon transfers be delayed until “tissue equilibrium” had been restored. Before a tendon transfer is performed, all fractures should be healed or rigidly fixed by internal fixation. Chronic scarred skin and subcutaneous tissues or skin grafts in the projected line of pull of a tendon transfer should be excised and the defect resurfaced with a flap that itself is allowed to heal and the new scars become mature. If secondary tendon transfers are likely to be necessary, initial split-thickness skin grafting of soft-tissue defects of the hand and forearm, simply to achieve a healed wound, should be avoided if possible. Instead, a pliable flap ideally of skin and subcutaneous tissues should be considered, either as a delayed primary coverage using pedicled flaps such as the groin flap and reverse radial forearm flap or free flaps such as the lateral arm flap, contralateral radial forearm flap, scapular flap, and latissimus dorsi flap. Occasionally, silicone rods can be placed

Table 34.1 Basic principles of tendon transfers

Soft-tissue “equilibrium”
Full passive range of motion of involved joints
Adequate amplitude of donor muscle
Direct line of pull
Single function for each transferred tendon
Synergy of transfer

at the time of flap coverage, either beneath or through the subcutaneous fat of a transferred flap to create a smooth tunnel through which a tendon transfer may be later passed. The span of the thumb–index finger webspace should be maintained by splinting, especially following median nerve injuries. If a secondary adduction contracture has developed, this should be released by a Z-plasty, skin grafting, or transposition flap, and release of the adductor pollicis if needed, prior to any opposition tendon transfer. Full passive range of motion of the MCP and PIP joints should be achieved by physical therapy and dynamic splinting prior to any tendon transfer. Preliminary capsulotomies of the MCP and PIP joints or tenolysis of adherent flexor or extensor tendons may occasionally be required if dynamic splinting fails to achieve adequate joint mobility.

Selection of donor muscle–tendon

Expendability

The muscle–tendon unit selected as a potential donor for transfer must be expendable. Its sacrifice must not create an important new deficit. For example, the ring finger flexor digitorum superficialis (FDS) tendon may be used to correct MCP hyperextension (claw deformity) in patients with a low ulnar nerve palsy, but it is not expendable in patients with a high ulnar nerve palsy who have no functioning flexor digitorum profundus (FDP) tendon to the ring finger. The selection of a muscle–tendon unit as a tendon transfer may also be influenced by the patient’s occupation. For example, the flexor carpi radialis (FCR) may be a more appropriate transfer to provide finger extension in a working man rather than the more conventional flexor carpi ulnaris (FCU) transfer, since the FCU provides the important function of flexion and ulnar deviation of the wrist needed in work activities such as hammering. More importantly, if multiple tendon transfers are required, a minimum of one wrist flexor, one wrist extensor, and one extrinsic flexor and extensor tendon to each digit should always be retained.

Clinical tips

- Full passive range of motion of the MCP and PIP joints should be achieved before considering any tendon transfers.
- The selected donor muscle–tendon unit must be expendable.
- One wrist flexor, one wrist extensor, one extrinsic flexor, and one extrinsic extensor tendon to each digit should always be retained.

- Potential amplitude of donor muscle–tendon units:
 - Finger flexors – 70 mm;
 - Finger extensors – 50 mm;
 - Wrist flexors and extensors – 33 mm.

Strength

In selecting the most appropriate donor muscle–tendon, the surgeon must consider not only the strength of the muscle to be transferred, but also the native strength of the now paralyzed muscle or muscles and the strength of the antagonist muscle.² Brand^{3,4} has emphasized that the maximum potential force of a muscle is directly proportional to its physiologic cross-sectional area. It has been calculated that a muscle can produce a force of 3.65 kg per square centimeter of its cross-sectional area. This potential force is maximal when the muscle is at its resting length which is defined as the position midway between the length when it is fully stretched passively and when it is fully contracted.

Amplitude

The potential amplitude or excursion of a donor muscle–tendon unit must also be sufficient to restore the specific lost function. The finger flexors have an amplitude of 70 mm, the finger extensors 50 mm and the wrist flexors and extensors 33 mm. The tenodesis effect of wrist flexion or extension may also increase the effective amplitude of a tendon transfer by 25 mm (Fig. 34.1). Excursion of a donor muscle may also be increased by extensive release of its surrounding fascia and is best exemplified by transfer of the brachioradialis (BR) muscle. The distal portion and tendon of the brachioradialis muscle are surrounded by dense fascia. Release of these fascial attachments will add an additional 2–3 cm of passive excursion.

Clinical tips

- The potential amplitude of a donor wrist extensor tendon may be increased by 20 mm to produce an effective amplitude by the tenodesis effect of wrist extension.
- The potential amplitude of a donor wrist flexor tendon can be increased by 20 mm to produce an effective amplitude by the tenodesis effect of wrist flexion.

Direction of transfer and integrity

A tendon transfer should pass in a direct line from the origin of the donor muscle to its new insertion. Unless early tendon transfers are being performed, when there is still a chance of reinnervation following nerve repair, the recipient tendons should be divided proximal to the site of the tendon juncture to create a more direct line of pull (end-to-end) rather than producing a Y-shaped end-to-side juncture. Tendon transfers should only act across one joint and only perform one single function. This maintains the “integrity” of the muscle. However, a transfer may be inserted into several recipient tendons as long as they each perform the same function in adjacent digits. Finally, the donor muscle selected should




Fig. 34.1 (A) The wrist tenodesis effect: Wrist flexion will increase the potential amplitude of a tendon transfer to restore finger extension by 20 mm. (B) Similarly, wrist extension will increase the potential amplitude of a tendon transfer to restore finger flexion by 20 mm.

preferably be synergistic with the function of the muscle to be restored or at least be potentially retrainable.

The surgeon has to determine the specific functions to be restored, select the appropriate donor muscle–tendon units, and decide on the timing of the tendon transfer. To make this selection, every muscle still functioning in the forearm and hand should be tested by manual muscle testing to document which ones are functioning and their strength graded. From this list of functioning muscles, only those that are expendable are available as donor transfers. The specific functions of the hand that need to be restored are then listed in order of priority. The final step is to match the available donor muscles with the functions that need to be restored, based on the force, amplitude, and direction of the various muscles available. Arthrodesis of a more proximal joint such as the wrist may occasionally need to be considered to release a wrist flexor or extensor tendon for transfer. Transfers that require postoperative immobilization with the wrist in flexion are usually performed at a first stage. Those transfers requiring postoperative immobilization with the wrist in extension are performed at a second stage.

Clinical tips

- Document which muscles are functioning and their individual strengths.
- Only the expendable muscles in this group of functioning muscles can be considered as potential donor transfers.
- List the specific hand functions that need to be restored, in order of priority.
- Match the available expendable donor muscles with the hand functions to be restored.

Timing of tendon transfers

Timing of tendon transfers may be classified as early, conventional, or late. A conventional tendon transfer is usually performed after reinnervation of the paralyzed muscle fails to occur by 3 months after the expected time of reinnervation based on the rate of nerve regeneration of 1 mm/day. Brand,³ Omer,⁵ and Burkhalter⁶ have advocated “early” tendon transfers in certain circumstances, in which a tendon transfer is performed simultaneously with the nerve repair or before the expected time of reinnervation of the muscle. This “early” tendon transfer therefore serves as a temporary substitute for the paralyzed muscle until reinnervation occurs, by acting as an “internal splint”. If reinnervation is suboptimal, the “early” tendon transfer acts as a helper to augment the power of the muscle and if reinnervation fails to occur it then acts as a permanent substitute.

Surgical techniques

The success of any tendon transfer depends entirely on preventing scarring or adhesions along the path of the transferred tendon. Incisions should be carefully planned prior to elevation of the tourniquet so that the final tendon junctures lie transversely beneath skin flaps rather than lying immediately beneath and paralleling the incisions. The donor muscle should be carefully mobilized to prevent damage to its neurovascular bundle which usually enters in the proximal third of the muscle. The transferred tendon should glide in a tunnel through the subcutaneous tissues and not cross bone devoid of uninjured periosteum nor pass through small fascial windows. Only the distal end of the tendon should be grasped with surgical instruments and care taken to prevent desiccation of the tendon or the surrounding tissues. Tendon junctures are performed using a Pulvertaft weave technique when possible. The donor and recipient tendons are sutured under normal tension and after one or two non-absorbable sutures have been inserted, the tension of the transfer is checked by observing the flexion and extension of the digit during tenodesis of the wrist. Postoperatively the hand is immobilized in the desired position for 3–4 weeks, at which time gentle active range of motion exercises are started, usually under the supervision of a therapist, but the hand is protected for a further 3 weeks in a lightweight protective splint.

Clinical tips

- Carefully design the incisions not only to allow dissection of the donor muscle–tendon unit, but also so that the tendon junctures lie beneath an elevated skin flap, rather than immediately beneath the incision, to prevent adhesions that will restrict gliding of the tendon transfer.
- The recipient tendon should be fully distracted to produce maximal function of the recipient tendon and the donor tendon transfer should be sutured at its resting length to the recipient tendon using a Pulvertaft weave technique.
- Correct tensioning of the tendon transfer is checked by observing flexion and extension of the digits or abduction and adduction of the thumb during tenodesis of the wrist.

Radial nerve palsy

Indications

The functional motor deficit in radial nerve palsy consists of inability to extend the wrist, inability to extend the fingers at the MCP joints, and inability to extend and radially abduct the thumb (Fig. 34.2). However, the most significant disability is that patients are unable to stabilize their wrist, so that transmission of flexor power to their fingers is impaired resulting in marked weakness of grip strength.

Tendon transfers are therefore required to provide wrist extension, extension of the fingers at the MCP joints, and extension and radial abduction of the thumb. Unlike the median and ulnar nerves, sensory loss following radial nerve injury is not functionally disabling unless the patient develops a painful neuroma.

Timing

Timing of tendon transfers for radial nerve palsy remains controversial. The two options are either to perform an “early” tendon transfer simultaneously with repair of the radial nerve to act as an “internal splint” to provide immediate restoration of power grip; or more conventionally, to delay any tendon transfers until reinnervation of the most proximal muscles, brachioradialis and extensor carpi radialis longus fails to occur within the calculated time limit. The more proximal the nerve injury, the less likely that functional muscle reinnervation will occur.^{3,6} If the nerve remains in continuity, most surgeons would suggest that 3 months of observation are indicated to await spontaneous recovery in peripheral nerve palsies.

Ring *et al.*⁷ reviewed 24 patients with a complete radial nerve palsy associated with a high-energy humeral fracture. Six of 11 open fractures had a transected radial nerve and none of the five patients who underwent primary repair of the radial nerve recovered any function. All eight nerves that were explored and found to be intact and 9 of 10 unexplored nerves recovered completely, with initial signs of recovery at an average of 7 weeks and full recovery at an average of 6 months. The authors concluded that primary repair of a transected radial nerve associated with a high-energy humerus




Fig. 34.2 (A) Typical appearance of a patient with radial nerve palsy with wrist drop. The fingers extend at the proximal interphalangeal joints through the tenodesis effect. (B) Even with the wrist supported in extension, the patient is unable to actively extend the fingers at the metacarpophalangeal joints or extend the thumb.

fracture was very poor, but the prognosis for full recovery of an intact radial nerve, whether the fracture is open or closed, was very good. Mayer and Mayfield⁸ reported 39 cases of posterior interosseous nerve (PIN) neurotomy with complete recovery in 28 and partial recovery in 11 patients. Young *et al.*⁹ studied 51 patients with PIN palsy and only 11 had resolved by 3 months. Of the remaining 40 patients, 20 of the 23 who underwent neurolysis and 10 of the 12 who underwent nerve grafting had excellent or good results. A conflicting study of radial nerve injuries demonstrated useful function in 65%, but only 38% of patients who underwent nerve grafting obtained useful motor function.¹⁰ These studies demonstrate that injury and repair of the radial and PIN nerves can provide significant return of function and should be considered. With extensive nerve gaps or associated soft-tissue injuries or in older patients, the chances of successful reinnervation are much less predictable and it may therefore be more appropriate for these patients to undergo the full set of tendon transfers early.¹¹ In a patient awaiting return of nerve function, it is important to maintain supple MCP joints capable of full extension and adequate radial abduction of the thumb with appropriate splinting and therapy.

Operations

Franke provided one of the earliest descriptions of tendon transfers for radial nerve palsy using the FCU to extensor digitorum communis (EDC) transfer through the interosseous membrane.¹² Capellen in 1899 described the FCR to extensor pollicis longus (EPL) transfer. The pronator teres (PT) to extensor carpi radialis longus (ECRL) and the extensor carpi radialis brevis (ECRB) transfer for wrist extension was first reported in 1906 by Sir Robert Jones. Zachary¹³ emphasized the importance of retaining at least one wrist flexor, preferably the FCR to facilitate wrist control. Other authors have suggested that FCU is not an expendable tendon and therefore prefer to use the FCR as the donor tendon to restore finger extension.¹⁴ The advantage of using FCR is that it preserves the important vector of wrist flexion and ulnar deviation which is so important for power grip in a working man. This is particularly true in the patient with a posterior interosseous nerve (PIN) palsy, in which ECRL function is preserved but extensor carpi ulnaris (ECU) activity is lost. This leads to radial deviation of the wrist with attempted wrist extension. Use of the FCU in this setting will therefore increase the radial deviation of the wrist, since only radially deviating wrist motors are preserved.

Several different tendon transfers have been reported for radial nerve palsy but three patterns of transfer have evolved.^{15,16} The use of pronator teres (PT) to provide wrist extension has become universally accepted, the only remaining controversy being whether to insert pronator teres into extensor carpi radialis brevis (ECRB) alone or into both extensor carpi radialis longus (ECRL) and extensor carpi radialis brevis. The three patterns of tendon transfer differ therefore only in the technique of restoring finger extension and thumb extension and radial abduction (Table 34.2).^{13,17–19}

Standard FCU transfer (Figs. 34.3–34.5)

In the patient with a radial nerve palsy, the FCU transfer is the author's preferred technique; in the patient with a PIN palsy, the FCR transfer is preferred. Through an inverted J-shaped incision over the ulnar–volar aspect of the distal forearm, the FCU tendon is transected at the wrist crease and released extensively from its fascial attachments up into the proximal third of the forearm, taking care not to damage the neurovascular pedicle, using a second incision in the proximal




Fig. 34.3 (A) The insertion of pronator teres is released from the radius, if necessary, extended by a strip of periosteum. (B) The pronator teres is passed around the radial border of the forearm superficial to brachioradialis and sutured to the transected tendon of extensor carpi radialis brevis.

Table 34.2 Tendon transfers for radial nerve palsy

Standard FCU transfer	FCR transfer	Boyce superficialis transfer
PT to ECRB	PT to ECRB	PT to ECRB
FCU to EDC	FCR to EDC	FDS of ring finger to EDC long, ring, and small fingers
PL to EPL	PL to EPL	FDS long finger to EIP and EPL (FCR to APL and EPB)

APL, Abductor pollicis longus; ECRB, extensor carpi radialis brevis; EDC, extensor digitorum communis; EIP, extensor indicis proprius; EPB, extensor pollicis brevis; EPL, extensor pollicis longus; FCR, flexor carpi radialis; FCU, flexor carpi ulnaris; FDS, flexor digitorum superficialis; PL, palmaris longus; PT, pronator teres.

forearm if necessary (see Figs. 34.4 & 34.6). Through the same distal incision, the palmaris longus (PL) tendon is transected at the wrist crease and the muscle mobilized into the middle third of the forearm (see Figs. 34.5 & 34.6). An S-shaped incision is then made beginning over the volar–radial aspect of the middle third of the forearm and passing dorsally and ulnarly over the radial border of the forearm. The tendon of pronator teres is elevated from the radius in continuity with a 2–3 cm strip of periosteum (see Fig. 34.3). The ECRB is transected at its musculotendinous junction if there is no chance of future reinnervation of the wrist extensors. The pronator teres is then re-routed around the radial border of the forearm superficial to the brachioradialis and extensor carpi radialis longus in a straight direction to its insertion into ECRB (see Fig. 34.3). The FCU tendon is passed through a subcutaneous tunnel made with a Kelly clamp from the




Fig. 34.4 (A) The flexor carpi ulnaris tendon is transected and passed around the ulnar border of the distal forearm and (B) woven into the combined extensor digitorum communis tendons proximal to the extensor retinaculum.




Fig. 34.5 (A) The extensor pollicis longus tendon is transected at its musculotendinous junction, (B) re-routed into the anterior aspect of the distal forearm and attached to the palmaris longus, if present, to provide both thumb extension and some radial abduction.




Fig. 34.6 (A) Through a volar incision in the distal third of the forearm, the flexor carpi ulnaris (FCU) tendon and its distal muscle and the palmaris longus tendon are isolated. (B) The pronator teres tendon is passed around the radial border of the forearm and sutured to extensor carpi radialis brevis. The FCU tendon is passed around the ulnar border of the distal forearm and sutured to the extensor digitorum communis tendons.

proximal incision used to mobilize FCU, around the ulnar border of the forearm into the dorsal incision, to lie obliquely across the EDC tendons proximal to the extensor retinaculum (see Fig. 34.6). Alternatively, the FCU tendon may be passed from the palmar incision to the dorsal incision through a window in the interosseous membrane.²⁰ If no return of EDC function is to be expected, the EDC tendons can be transected at their musculotendinous junctions so that a more direct line of pull can be achieved. Otherwise an end-to-side juncture is performed. The extensor pollicis longus (EPL) tendon is divided at its musculotendinous junction, removed from the third dorsal extensor tendon compartment, and passed through a subcutaneous tunnel from the base of the thumb metacarpal to the volar wrist incision (see Fig. 34.5). If the PL is absent, the EPL tendon is included with the EDC tendons and the FCU transfer provides both finger and thumb extension. To prevent a collapse flexion deformity at the carpometacarpal joint of the thumb, tenodesis of the abductor pollicis longus may be necessary. After transection of the APL tendon in the distal forearm, it is looped around the brachioradialis proximal to the radial styloid and sutured to itself with the thumb metacarpal held in extension with the wrist in 30° of extension.

The proper tension in radial nerve tendon transfers should be tight enough to provide full extension of the wrist and digits but without restricting full flexion of the digits when the wrist is fully extended. The pronator teres at its resting tension is woven through the ECRB tendon with the wrist in 45° of extension. The distal ends of the four EDC tendons to the index, long, ring and small fingers are sutured to the FCU tendon proximal to the extensor retinaculum. The extensor digiti minimi is usually not included unless there is still an extensor lag when proximal traction is applied to the EDC tendon to the small finger. With the wrist in neutral and FCU under maximal tension, each individual EDC tendon is sutured to provide full extension at the MCP joint, starting with the index finger and finishing with the small finger.

Appropriate tension is then evaluated by checking that all four digits extend synchronously when the wrist is palmar flexed and most importantly that all four digits can be passively flexed into a fist when the wrist is extended. Finally, palmaris longus and extensor pollicis longus are interwoven over the radiovolar aspect of the wrist with the thumb in maximal extension and the wrist in neutral with the PL tendon at its resting tension. The wrist is immobilized in 45° of extension in a volar splint with the MCP joints positioned in slight flexion and the thumb in full extension and abduction.

Active flexion and extension of the fingers and thumb are started at 3½ to 4 weeks and active exercises of the wrist begun at 5 weeks. Protective splinting is continued until 6 to 8 weeks postoperatively. Results have been uniformly good (Fig. 34.7).

FCR transfer (Fig. 34.8)

The skin incision begins from the radiovolar aspect of the mid-forearm and extends dorsally over the third and fourth extensor tendon compartments. The pronator teres is transferred to the extensor carpi radialis brevis and the palmaris longus is transferred to the extensor pollicis longus exactly as described in the standard FCU transfer. The FCR tendon is divided at the wrist crease and mobilized approximately to the level of the mid-forearm and re-routed around the radial border of the forearm. The four EDC tendons, and if necessary the EDM, may be woven through the donor FCR tendon proximal to the extensor retinaculum, but more usually the extensor tendons need to be re-routed superficial to the extensor retinaculum to obtain a straighter line of pull (see Fig. 34.8). To prevent a bulky tendon juncture, the small finger EDC and EDM may be sutured side-to-side to the ring finger EDC and the index finger EDC sutured side-to-side to the long finger EDC under appropriate tension. Then only the two EDC tendons to the long and ring fingers require weaving through the FCR tendon. As with the standard FCU transfer,




Fig. 34.7 (A) The patient 3 years following pronator teres to extensor carpi radialis brevis transfer showing wrist extension and satisfactory finger flexion; (B) full extension of the fingers at the metacarpophalangeal joints; and (C) excellent thumb extension and radial abduction.




Fig. 34.8 Flexor carpi radialis transfer to the combined tendons of extensor digitorum communis. The tendon junction may have to lie superficial to the extensor retinaculum. Tendon transfers of pronator teres to extensor carpi radialis brevis and palmaris longus to extensor pollicis longus are the same as in the flexor carpi ulnaris transfers.

these tendon junctions are performed with the wrist in neutral and the MCP joints in full extension with the FCR tendon under maximal traction. Postoperative management is similar to that for the FCU transfer. Chandraprakasam *et al.*²⁰ described a modification of the modified Jones transfer in which the pronator teres is transferred to ECRB; the FCR is transferred to the finger extensors and the palmaris longus transferred to EPL; all through a single incision along the radial aspect of the distal third of the forearm curving obliquely to end at Lister's tubercle.

Boyes flexor digitorum superficialis transfer (Fig. 34.9)

Boyes¹⁷ was the first to suggest that neither FCU nor FCR have sufficient amplitude (30 mm) to produce full excursion of the finger extensor tendons (50 mm) without the potential increase in amplitude obtained with the tenodesis effect of wrist flexion. He therefore advocated using the flexor digitorum superficialis (FDS) tendons to the long and ring fingers, which have an amplitude of 70 mm, to act as donor tendons to restore finger extension.^{17,18} The advantages of the Boyes transfer are that this transfer will potentially allow simultaneous wrist and finger extension; secondly, it may allow independent thumb and index finger extension; and finally, it does not weaken wrist flexion. However, the long and ring fingers are deprived of superficialis function and this may result in weak grip. Harvesting of the superficialis tendons may also lead to the subsequent development of either a "swan neck" deformity or a flexion contracture at the PIP joint.

The FDS tendons to the long and ring fingers are exposed between the A1 and A2 pulleys either through one transverse incision at the base of the fingers or two separate longitudinal incisions. The FDS tendons are divided just proximal to their decussation and then withdrawn proximally into a longitudinal incision over the volar aspect of the middle third of the forearm. The tendon of pronator teres can be transected and re-routed through this same incision as described previously. Blunt dissection on either side of the flexor digitorum profundus (FDP) muscles allows a window to be excised in the




Fig. 34.9 In the Boyes tendon transfer, the long and ring finger flexor digitorum superficialis tendons, FDS_L and FDS_R are transferred either through a window in the interosseous membrane (A) or around the radial and ulnar border of the forearm to restore extension of the extensor digitorum communis tendons to the long, ring, and small fingers and the extensor indicis proprius and extensor pollicis longus tendons (B).

interosseous membrane just proximal to the pronator quadratus (see Fig. 34.9). This window should be made as large as possible at least 4 cm long and as wide as the interosseous space, so that the muscle bellies of the two FDS tendons can be passed through this window to minimize the development of adhesions. It is important to pass the FDS tendons of the ring and long fingers to their respective sides of the median nerve to prevent scissoring over the nerve and compression.

Thomsen and Rasmussen²¹ prefer to transfer the two FDS tendons around the radial and ulnar borders of the forearm through subcutaneous tunnels. Through a J-shaped incision passing transversely across the dorsum of the wrist and then extending proximally along the dorsum of the ulna, the extensor tendons are isolated as well as extensor carpi radialis brevis. In Boyes' original description, pronator teres was sutured to both ECRL and ECRB,¹⁷ but in order to prevent excessive radial deviation, pronator teres should only be woven end-to-end into ECRB with the wrist in 30° of extension. The long finger FDS is then passed to the radial side of the FDP muscles and the ring finger FDS to the ulnar side through the interosseous window into the dorsal incision. After transection of the EPL and EIP tendons, they are woven end-to-end into the long finger FDS tendon. Similarly, the transected EDC tendons to the index, long, ring, and small fingers are woven end-to-end into the ring finger FDS tendon, although this arrangement can be reversed. The tendon junctions are performed proximal to the extensor retinaculum with resting tension in the donor FDS tendons and full extension at the MCP joints.

If necessary, abductor pollicis longus (APL) is transected at its musculotendinous junction and passed through a subcutaneous tunnel from the base of the thumb into the volar forearm incision. Either palmaris longus or flexor carpi radialis are transected at the wrist crease and woven end-to-end with the APL tendon to provide abduction of the thumb and prevent a collapse deformity of the thumb metacarpal. The tourniquet should be deflated prior to the closure of the incisions because of the likelihood of bleeding from the anterior or posterior interosseous arteries.

Outcomes

Tendon transfers for radial nerve palsy are generally predictable. Tsuge²² described the evolution of his technique in 69 patients over a 25 year period. Using the FCU transfer and insertion of pronator teres into both ECRL and ECRB in the initial 41 patients, he reported "fairly satisfactory" results, but felt that there were three problems: development of radial deviation of the wrist, restriction of wrist flexion, and marginal thumb abduction. Because of these concerns, pronator teres was transferred only to ECRB and the FCR was transferred through the interosseous membrane for finger extension, leaving the FCU intact leading to good results in 24 of 27 cases. A long-term functional study of the FCU transfer in six patients by Raskin and Wilgis²³ revealed adequate wrist motion and power to perform daily activities, and a work-simulation protocol showed patients were able to perform tasks without significant difficulty. Problems of inadequate ulnar deviation, grip strength, and wrist instability were not seen. A subjective outcome study by Riordan²⁴ also revealed satisfaction with the standard FCU transfer. Long-term evaluation of the FCU transfer for radial nerve palsy at a mean

follow up of 9.5 years revealed 11 excellent, two good, one fair, and one bad result, with the main problems being loss of power grip and development of a radial deviation deformity.²⁵ This resulted in an evolution in the author's technique to use pronator teres to restore wrist extension, FCR to restore finger extension, and palmaris longus to restore thumb extension with tenodesis of the abductor pollicis longus to brachioradialis to restore thumb abduction. Gousheh and Arasteh²⁶ transferred only the FCU to the finger extensors and EPL in 108 patients. At a mean follow-up of 4 years, wrist extension was less than the opposite side, but extension of the fingers was similar to the normal hand and most patients were able to return to their previous job. According to the authors, there was no obvious difference between the results using a single FCU tendon transfer compared to their previous results using the conventional three tendon transfers for reconstruction of radial nerve palsy. Altintas *et al.*²⁷ compared the long-term results after tendon transfers for radial nerve palsy, using the FCU in 58 patients and the FCR in 19 patients. Wrist extension averaged 73% of the opposite side, finger extension 32%, and thumb extension 80%. Grip strength was reduced to 49% and pinch strength to 28% of the opposite hand and the mean total DASH score was 16. Eighty-nine percent of patients remained employed after tendon transfers for radial nerve palsy.

Chuinard *et al.*¹⁸ studied 21 patients who had undergone the Boyes FDS transfers with excellent results in 10, good in six, and only a fair result in five patients. Subjectively, 13 patients felt that they had obtained an excellent result and eight a good result. Complications requiring a second procedure were reported in five patients and included adhesions, dehiscence of the transfer, MCP and wrist extension contractures, and problems with correct tensioning of the transfers. A report by Fujiwara²⁸ of 13 patients with radial nerve palsy and five patients with PIN palsy documented generally good results with the Boyes transfers. No patient in either of these studies developed postoperative median nerve compression despite the potential for this complication with this transfer. Krishnan and Schackert²⁹ evaluated the function of 29 patients who had undergone a Boyes transfer of the FDS tendons to the long and ring fingers through the interosseous membrane for radial nerve palsy. Near-normal wrist extension was achieved in 22 of 25 patients. Finger extension simultaneously with wrist extension was achieved in 12 patients, but in 17 patients full finger extension was only possible with the wrist in neutral. Selective extension of the index finger and thumb powered by the FDS tendon from the long finger was achieved in all patients.

All three techniques have been reported to yield good results, but there are few quantitative studies to substantiate the reported outcomes, and no prospective comparison of the three different techniques. The FCU transfer is perhaps the simplest technique and provides reproducibly good results in patients with radial nerve palsy.

Low median nerve palsy

Anatomical considerations

The functional deficit following injury to the median nerve distal to the innervation of the extrinsic forearm flexor muscles consists primarily of loss of opposition of the thumb and

absent sensation over the thumb, index, long, and radial half of the ring finger.

Opposition is a composite motion that occurs at all three joints to position the thumb pad opposite the distal phalanx of the partially flexed long finger. Abduction, pronation, and flexion occur at the carpometacarpal joint, abduction and flexion at the metacarpophalangeal joint, and either flexion or extension at the interphalangeal joint. Approximately 40° of abduction of the thumb metacarpal occurs at the carpometacarpal joint and 20° of abduction of the proximal phalanx occurs at the metacarpophalangeal joint. From a starting position of full extension and adduction, the thumb pronates approximately 90° during opposition to the long finger. Extension of the thumb interphalangeal joint is required for pulp-to-pulp pinch, whereas slight flexion of the interphalangeal joint allows tip-to-tip pinch. Of the three intrinsic thenar muscles, the flexor pollicis brevis (FPB) muscle typically, although not always, receives a dual innervation from both the median and ulnar nerves. Because the flexor pollicis brevis may remain innervated by the ulnar nerve in approximately 70% of median nerve injuries, patients may not notice any significant functional loss, but careful testing will reveal decreased strength of abduction and lack of pronation.

Prior to any opposition transfer, patients with median nerve injuries should be instructed to prevent the development of an adduction or supination contracture of the thumb by a program of passive abduction exercises. A static thumb-index finger webspace splint may be used at night, but this usually interferes with the already compromised function of the hand if used during the day. Care should be taken to insure that such splints abduct the thumb metacarpal rather than the proximal phalanx; otherwise the median nerve palsy will be compounded by attenuation of the ulnar collateral ligament of the metacarpophalangeal joint. If patients present with an established adduction or supination contracture of the thumb, release of the thumb-index finger webspace skin, fascia over the first dorsal interosseous muscle, or even the first dorsal interosseous and adductor muscles themselves may be required prior to any opposition tendon transfer.

Bunnell³⁰ first emphasized that the pull of an opposition tendon transfer should be in an oblique direction from the thumb metacarpophalangeal joint to the region of the pisiform, and secondly, that in order to produce pronation, the transfer should be inserted into the dorso-ulnar base of the proximal phalanx. Opposition transfers that are directed along the radial aspect of the palm will produce a greater component of palmar abduction, whereas transfers that pass from the pisiform will produce both abduction and pronation. The more distal the transfer passes across the palm, the greater the power of thumb flexion. Several methods of insertion of opposition transfers have been advocated including attachment to the dorso-ulnar base of the proximal phalanx (Bunnell³⁰, Royle-Thompson^{31,32}), insertion into the abductor pollicis brevis tendon (Littler³³), dual insertion into the abductor pollicis brevis and continuation distally into the MCP joint capsule and extensor pollicis longus tendon (Riordan²⁴), insertion into the abductor pollicis brevis, dorsal joint capsule and adductor pollicis (Edgerton and Brand³⁴), and finally utilization of a distal-based extensor pollicis brevis tendon (Phalen and Miller³⁵). However, a biomechanical study has shown that opposition tendon transfers inserted into the abductor pollicis brevis (APB) tendon alone will produce full abduction and

pronation.³⁶ Therefore the more complex dual insertions should probably be reserved for combined median and ulnar nerve palsies.

Timing

Several factors influence the likelihood of useful motor and sensory return following median nerve injury including patient age, level of injury, length of nerve defect and interposition nerve graft; and period of preoperative delay. The best results are realized in distal injuries in young patients requiring only primary repair. Associated injuries such as vascular injury, tendon injury, and concomitant ulnar nerve transection portend a worse prognosis. The chances of reinnervation of the thenar muscles following group fascicular repair of a distal median nerve laceration should be reasonably optimistic. Therefore, conventional timing of an opposition tendon transfer may only be required in those patients who fail to demonstrate signs of reinnervation within the usual calculated time interval. For older patients or those with poor prognostic comorbid factors, early tendon transfers should be considered.

Careful observation of thumb function following either a low or high median nerve palsy will reveal whether an “early” tendon transfer for thumb opposition is necessary. Flexor pollicis brevis remains innervated by the ulnar nerve in approximately 70% of median nerve injuries so that thumb function may not be significantly compromised. Consequently an “early” opposition transfer may not be necessary. Other patients, however, will adapt to their loss of opposition and abduction by substitution of the abductor pollicis longus to provide thumb abduction, but this can only be achieved with the hand positioned in pronation. This places the patient at an even greater disadvantage in that not only do they have absent sensation in the median nerve distribution, but with the forearm in pronation they cannot even see the palmar surface of their hand to compensate for their loss of sensation. Therefore, if the surgeon or therapist observes the patient attempting to grasp objects by radial abduction of the thumb with the forearm in pronation, an “early” opposition tendon transfer should be strongly considered. If, however, the patient is able to pick up an object with the forearm in neutral or grasp an object with the forearm in supination, it is likely that flexor pollicis brevis remains innervated by the ulnar nerve and consequently the decision for performing an “early” opposition tendon transfer can be delayed.

Operations

Burkhalter extensor indicis proprius transfer (Fig. 34.10)

The extensor indicis proprius (EIP) transfer³⁷ is the author's preferred technique, except in elderly patients with thenar atrophy secondary to severe carpal tunnel syndrome (see Fig. 34.10). The EIP tendon is transected through a small transverse incision just proximal to the MCP joint of the index finger. The distal stump of the EIP tendon is then repaired to the extensor digitorum communis tendon of the index finger to prevent extensor lag at the metacarpophalangeal joint. The EIP tendon is mobilized through two small transverse incisions one proximal and one distal to the extensor retinaculum and the




Fig. 34.10 (A,B) In the Burkhalter opposition tendon transfer, extensor indicis proprius (EIP) is transected at the level of the metacarpophalangeal (MCP) joint of the index finger and **(C)** mobilized through a dorsal-ulnar incision in the distal forearm. The EIP tendon is passed around the ulnar border of the distal forearm and **(D)** passed obliquely across the palm from the level of the pisiform to the radial aspect of the MCP joint of the thumb and sutured to the insertion of abductor pollicis brevis.

muscle belly mobilized through a longitudinal incision over the ulnar aspect of the dorsum of the mid-forearm (see Fig. 34.10C). A transverse incision is made just proximal to the pisiform bone and a subcutaneous tunnel developed to connect this incision to the dorsal forearm incision. The EIP tendon is then passed subcutaneously around the ulnar border of the distal forearm superficial to the extensor carpi ulnaris tendon into the pisiform incision. The abductor pollicis brevis tendon is identified through a small incision over the radial aspect of the MCP joint of the thumb and a subcutaneous tunnel made connecting this incision with the pisiform incision. The tendon transfer is passed obliquely across the palm (see Fig. 34.10D) and woven into the tendon of abductor pollicis brevis under maximum tension with the wrist in neutral position and the thumb in maximal palmar abduction. The tension of the transfer is then tested by the tenodesis effect of the wrist. Wrist flexion should allow the thumb to be passively adducted. If wrist extension produces excessive flexion or extension of the thumb at the metacarpophalangeal joint, this indicates that the transfer has been inserted either too far volarly or too far dorsally and should be adjusted accordingly. The thumb is immobilized in full abduction with the wrist in slight palmar flexion for 4 weeks, at which time active abduction and opposition movements are begun with protective splinting for a further 3–4 weeks. The only potential disadvantage with this tendon transfer is that the EIP tendon

is only just long enough to reach the abductor pollicis brevis tendon. The postoperative results have been very predictable (Fig. 34.11).

Bunnell ring finger flexor digitorum superficialis transfer (Fig. 34.12)

In the flexor digitorum superficialis transfer described originally by Bunnell,³⁰ the ring finger FDS tendon is isolated through a small transverse incision just distal to the distal palmar crease. The tendon is transected between the A1 and A2 pulleys and delivered into a proximal incision made over the volar aspect of the distal forearm (Fig. 34.13A). The flexor carpi ulnaris tendon is split longitudinally to create a distal-based strip of the radial half of the tendon. This is then passed through a slit in the flexor carpi ulnaris tendon just proximal to the pisiform and sutured to itself to create a pulley (see Fig. 34.13B,C). The distal end of the ring finger FDS tendon is passed through this pulley and through an oblique subcutaneous tunnel across the palm into an incision over the radial aspect of the MCP joint of the thumb. All the other incisions are then closed and the tension on the tendon transfer adjusted as described previously.

Simple looping of the ring finger FDS around the FCU tendon rather than using a fixed pulley rapidly becomes ineffective and the transfer becomes converted to a flexor of the




Fig. 34.11 (A) Postoperative opposition of the right thumb has been restored after a Burkhalter extensor indicis proprius transfer. (B) Thumb abduction is symmetrical with the normal thumb.

MCP joint rather than a true opposition transfer. Other pulleys for the ring finger FDS transfer include passing the tendon through Guyon's canal or through a window in the transverse carpal ligament (Snow–Fink).

Compared with the EIP transfer, the ring finger FDS is relatively stronger and has greater length. This is perhaps the strongest of the opposition transfers (Fig. 34.14C,D). However, the ring finger FDS is not available as a donor tendon in a high median nerve palsy or in low median nerve injuries in which there have been associated injuries to the flexor tendons. The ring finger FDS transfer should also not be selected in combined low median and high ulnar nerve palsies since the ring finger FDS is the only remaining flexor tendon in the ring finger. In low median–low ulnar nerve palsies, the ring finger FDS may be required for correction of clawing. In addition, harvesting of the FDS tendon may result in either a flexion contracture or a “swan neck” deformity of the PIP joint of the donor finger.

Camitz palmaris longus transfer (Fig. 34.15)

The palmaris longus (PL) donor tendon in the Camitz transfer^{38–41} will provide abduction of the thumb but little pronation or flexion and is particularly indicated in elderly patients with thenar atrophy due to long-standing carpal tunnel syndrome. A strip of palmar fascia is dissected in

continuity with the distal palmaris longus tendon through a standard carpal tunnel incision in the palm extending proximally into the distal forearm (Fig. 34.16A). A subcutaneous tunnel is developed from the radial aspect of the distal forearm incision along the thenar eminence into a mid-axial incision on the radial aspect of the MCP joint of the thumb (see Fig. 34.16B). The fascial extension of the palmaris longus tendon is passed through this subcutaneous tunnel and sutured to the abductor pollicis brevis tendon under maximal tension with the wrist in neutral position (see Fig. 34.16C).

Other opposition tendon transfers

Huber⁴² and Nicholaysen⁴³ described transfer of the abductor digiti minimi (ADM), which may occasionally be indicated in patients with a combined median and radial nerve palsy and also in children with congenital anomalies affecting the thumb. Since the muscle originates at the pisiform, this




Fig. 34.12 Bunnell transfer using the flexor digitorum superficialis of the ring finger passed through a pulley of the flexor carpi ulnaris tendon to restore opposition of the thumb.





Fig. 34.13 (A) Harvesting the flexor digitorum superficialis (FDS) tendon from the ring finger. (B,C) A sucker tip is used to create a pulley for the FDS from a distal-based slip of flexor carpi ulnaris just proximal to the pisiform.



Fig. 34.14 (A) Preoperative appearance of a patient with Charcot-Marie-Tooth disease with severe thenar atrophy and inability to oppose either thumb. (B) Postoperatively after a Bunnell transfer, the patient is able to oppose their right thumb to the tip of the small finger.




Fig. 34.15 Camitz opposition transfer using the palmaris longus tendon extended with a strip of palmar fascia and transferred to the insertion of abductor pollicis brevis.

transfer provides excellent flexion and pronation of the thumb but little palmar abduction. The insertion of the abductor digiti minimi tendon is transected from the ulnar lateral band through an ulnar midaxial incision along the proximal phalanx of the small finger. The incision is then extended proximally

along the radial aspect of the hypothenar eminence and the muscle elevated in a distal to proximal direction taking care to protect the neurovascular bundle which enters the muscle just beyond the pisiform. A wide subcutaneous tunnel is dissected between the hypothenar incision and the insertion of




Fig. 34.16 (A) In this patient with severe left carpal tunnel syndrome and thenar atrophy, the palmaris longus tendon is extended with a rolled-up sheet of palmar fascia and (B) transferred subcutaneously to the insertion of the abductor pollicis brevis tendon on the radial aspect of the metacarpophalangeal joint of the thumb. (C) One year postoperatively, the patient demonstrates excellent palmar abduction of the thumb; but because the vector of transfer is not from the region of the pisiform, the Camitz transfer does not provide pronation of the thumb.




Fig. 34.17 (A) In the Phalen and Miller opposition tendon transfer, the ECU is detached from the base of the small finger metacarpal and transferred around the ulnar border of the forearm and sutured to the distal-based EPB tendon **(B)**.

the abductor pollicis brevis muscle at the MCP joint of the thumb. Hemostasis is achieved after releasing the tourniquet and the entire abductor digiti minimi muscle rotated 180° through the subcutaneous tunnel in the palm and sutured into the abductor pollicis brevis tendon. This transfer has been compared to turning the page of a book.⁴² Cawrse and Sammut⁴⁴ described a modification of the Huber transfer in which the abductor digiti minimi is released both distally and proximally, so that the muscle is a complete island. This eliminates any compression of the ulnar nerve by the muscle transfer.

Phalen and Miller³⁵ advocate the use of the extensor pollicis brevis (EPB) tendon activated by extensor carpi ulnaris (ECU). The EPB is divided at its musculotendinous junction in the distal forearm and retrieved through an incision at the metacarpophalangeal joint of the thumb. This distally based tendon may then be passed through a subcutaneous tunnel obliquely across the palm to the area of the pisiform. The extensor carpi ulnaris tendon is transected at the base of the fifth metacarpal and routed subcutaneously around the ulnar border of the wrist to be interwoven with the extensor pollicis brevis tendon (Fig. 34.17).

Taylor described the use of the extensor digiti minimi (EDM) as an opposition tendon transfer.⁴⁵ This transfer, which was also described by Schneider, re-routes the EDM around the ulnar side of the hand to the thumb MCP joint.⁴⁶

High median nerve palsy

Indications

The functional deficit following injury to the median nerve proximal to its innervation of the extrinsic forearm flexor muscles consists of inability to flex the index finger at the PIP and distal interphalangeal (DIP) joints and the thumb at the interphalangeal joint in addition to loss of opposition (Fig. 34.18). This is due to paralysis of all four flexor digitorum



Fig. 34.18 Typical posture of high median nerve palsy with inability to flex the interphalangeal joint of the thumb and inability to flex the proximal interphalangeal and distal interphalangeal joints of the index finger.

superficialis muscles, the flexor digitorum profundus tendons to the index and long fingers, and the flexor pollicis longus muscle. Patients are often still able to flex the long finger due to interconnections between the FDP tendons to the long, ring, and small fingers in the distal forearm. Therefore, the two functions that need to be restored in patients with a high median nerve palsy are flexion at the interphalangeal joint of the thumb and flexion of the PIP and DIP joints of the index and long fingers, together with a conventional opposition tendon transfer.

Operations

Flexion of the interphalangeal joint of the thumb may be restored by transfer of brachioradialis (BR) to flexor pollicis longus (FPL) and flexion of the DIP joint of the index and long fingers by side-to-side tenorrhaphy of the FDPs of index and long fingers to the FDPs of the ring and small fingers¹⁶ (Fig. 34.19). The brachioradialis is divided at its insertion on the radial styloid and extensively mobilized from its investing fascia up into the proximal third of the forearm so that the freed muscle can develop approximately 30 mm of excursion. If reinnervation of the flexor pollicis longus muscle is not expected to occur following repair or grafting of the median nerve, the tendon can be divided at its musculotendinous junction and woven end-to-end into the brachioradialis tendon. However, if there is any possibility of reinnervation of FPL, the brachioradialis tendon should be woven

end-to-side into the flexor pollicis longus tendon, which remains in continuity. Through the same volar forearm incision, the FDP tendons to the index and long fingers can be sutured side-to-side to the ulnar innervated FDP tendons to the ring and small fingers. The results of these two transfers are also relatively predictable (Fig. 34.20).

If power flexion of the index and long fingers is required, then formal transfer of the extensor carpi radialis longus tendon to the index and long finger FDP tendons may be performed. The ECRL is transected through a small transverse incision at the base of the index finger metacarpal and passed subcutaneously around the radial border of the distal forearm into the volar incision. The FDP tendons to the index and long fingers are woven into the ECRL tendon so that with the wrist in 30–45° of extension, the tips of the index and long fingers almost touch the palm. Similarly, with the wrist in full palmar flexion, the fingers will almost assume a fully extended position. Adjusting tension on this transfer using the tenodesis effect of the wrist is absolutely critical, because the donor ECRL tendon has only 30 mm of amplitude whereas the FDP tendons normally have 70 mm of excursion. If this transfer is sutured under too much tension, it will result in flexion contractures of these two fingers.

The timing of tendon transfers in a high median nerve palsy remains controversial.⁶ If a good primary or delayed primary nerve repair can be performed, there is a reasonable chance of reinnervation of the extrinsic flexor muscles in a young patient. Consequently “early” brachioradialis to flexor




Fig. 34.19 (A) The flexor digitorum profundus (FDP) tendons of the index and long fingers are sutured to the FDP tendons of the ring and small fingers, which are still innervated by the ulnar nerve. (B) The flexor pollicis longus tendon is sutured to the brachioradialis tendon to restore flexion of the interphalangeal joint of the thumb.




Fig. 34.20 (A) Postoperatively after side-to-side tenorrhaphy of the flexor digitorum profundus tendons, the patient has regained satisfactory flexion at the proximal interphalangeal and distal interphalangeal joints of the index finger. (B) After the brachioradialis to flexor pollicis longus transfer, the patient has satisfactory flexion of the interphalangeal joint of the thumb. The patient also underwent a Burkharter opposition transfer using extensor indicis proprius and has excellent abduction of the thumb.

pollicis longus or side-to-side repair of the index and long finger FDP tendons to the ring and small finger FDP tendons is not necessary. However, if the patient is seen late and requires secondary nerve grafting of the median nerve, then tendon transfers for restoration of thumb flexion and index and long finger flexion should be performed simultaneously with the nerve graft.

Outcomes

There is no standard measurement of opposition in the literature. Some authors have developed functional scales to rate outcome, while others have reported subjective patient satisfaction.^{47,48} An anatomic and biomechanical study by Cooney *et al.*³⁶ showed that the FDS of the ring finger and the ECU were the best transfers for replacing thenar muscle strength, abduction, and pronation. They calculated that the ECU and FDS transfers restored 60% and 40% respectively of required thenar muscle strength. The Camitz transfer provided good abduction, but weak flexion and opposition.

Excellent or good results were obtained in approximately 88% after EIP transfer in patients with nerve deficits secondary to leprosy.⁴⁹ Similar results have been reported by other authors, but little data exists documenting thumb range of motion or rigorous functional outcomes. Schwartz and MacDonald⁵⁰ performed a retrospective review of 156 opposition tendon transfers primarily using FDS. Objective parameters

were rated as good or excellent in 89% and patient satisfaction was rated as good or fair in 93%. There are few publications containing objective data that discuss the long-term functional outcomes of the Bunnell FDS transfer. Brandsma *et al.*⁵¹ reported 32% excellent and 51% good results. Some of the other patients in this study underwent FDS transfers for intrinsic function. Of the 158 donor fingers, swan neck deformities were seen in 15%, DIP joint flexion contractures in 29%, and PIP joint flexion contractures in 18%. Groves and Goldner⁵² reported 75% success in 16 patients with high median nerve or brachial plexus lesions reconstructed with FDS opposition transfers.

While Phalen and Miller³⁵ reported good results with the ECU transfer, another study described the development of significant radial deviation in one-third of cases.⁵³ These authors cautioned that the FCU must have normal strength to maintain proper wrist balance after ECU transfer.

Braun⁴⁰ reported good results in 28 patients who underwent the Camitz transfer. Foucher *et al.*⁴¹ reported 91% good long-term results in 73 Camitz transfers performed at the same time as carpal tunnel release. Terrono *et al.*⁵⁴ retrospectively reviewed their experience with 33 Camitz transfers for severe median nerve compression in patients with a mean age of 65 years. Ninety-four percent of the patients felt that their thumb dexterity and speed were improved by the operation; only two patients were unhappy with the results. No objective biomechanical data are available for this transfer.

Table 34.3 catalogs some of the clinical studies of opposition tendon transfers. Success is defined differently in each study and thus a cohesive evaluation and enlightened recommendation is difficult to make. Data on high median nerve palsy reconstruction are even more scarce.

Low ulnar nerve palsy

Indications

Injury to the ulnar nerve distal to the innervation of the ring and small finger FDP and FCU muscles produces a functional deficit consisting of paralysis of all seven interossei, the ulnar two lumbricals, the hypothenar and the adductor pollicis (AP), and part of the flexor pollicis brevis (FPB) muscles. This results in an imbalance of the flexor and extensor forces at the MCP, PIP, and DIP joints of the fingers. Since the interossei are the main flexors of the MCP joints, extension of the proximal phalanges at the MCP joints by the extrinsic extensor tendons is unopposed and MCP joint hyperextension occurs to the extent allowed by the volar plates. Because the extrinsic extensor tendons concentrate their extension at the MCP joints and the interossei are unable to actively extend at the PIP and DIP joints, the increased tension in the flexor tendons that occurs as the MCP joints begin to hyperextend will be unopposed at the PIP and DIP joints. This therefore results in the typical claw hand with hyperextension at the MCP joints and reciprocal flexion at the PIP and DIP joints (Duchenne's sign) (Fig. 34.21).

Imbalance between the extrinsic extensor and flexor tendons leads to asynchronous flexion of the fingers and weak grip strength. The MCP joints do not flex until after the interphalangeal joints have become completely flexed, resulting in curling of the tips of the fingers into the palm with loss of ability to

Table 34.3 Opposition tendon transfers for low median nerve palsy

Technique	Etiology	Author	Success
Huber	Trauma, neurologic disease	Wissinger <i>et al.</i> , 1977 [*]	80%
Camitz	Nerve compression	Terrono <i>et al.</i> , 1993 ⁵⁴ Foucher <i>et al.</i> , 1991 ⁴¹	94% 91%
EIP	Trauma	Anderson <i>et al.</i> , 1991 ⁴⁹ Burkhalter <i>et al.</i> , 1973 ³⁷	88% 88%
Bunnell	Leprosy Leprosy Trauma Trauma	Brandsma <i>et al.</i> , 1992 ⁵¹ Palande 1975 [†] Kirklin and Thomas 1948 ⁴⁸ Groves and Goldner 1975 ⁵²	83% 94% 85% 75%
EDQ	Trauma	Schneider 1969 ⁴⁶	80%

^{*}Wissinger HA, Singen EG. Abductor digiti quinti opponensplasty. *J Bone Joint Surg Am.* 1977;2:22–23.

[†]Palande DD. Opponensplasty in intrinsic-muscle paralysis of the thumb in leprosy. *J Bone Joint Surg Am.* 1975;57:489–93.

grasp large objects. In a low ulnar nerve palsy, the clawing and loss of integrated MCP and interphalangeal joint flexion are confined to the ring and small fingers and to a lesser extent the long finger, since the lumbricals to the index and long fingers remain innervated by the median nerve. However, in a combined median and ulnar nerve palsy, all four fingers are affected (Fig. 34.22). Fowler⁵⁵ has shown that the PIP joints can be extended by the extrinsic extensor tendons provided that the MCP joints are stabilized against hyperextension. Both the claw deformity and the asynchronous flexion may therefore be improved either by static procedures to prevent hyperextension at the MCP joints or by dynamic tendon transfers to produce either MCP joint flexion alone or to provide both MCP joint flexion and interphalangeal joint extension.

The other significant impairment in patients with low ulnar nerve palsy is weak thumb–index finger pinch, which may be only 20–25% of normal due to paralysis of the adductor pollicis, one half of the FPB, and the first dorsal interosseous muscles. However, in 58% of ulnar nerve injuries, there is dual innervation of the flexor pollicis brevis muscle, which can to some extent provide thumb MP joint flexion and key pinch to the index finger. Loss of key pinch is usually manifest by compensatory activation of the flexor pollicis longus

producing excessive flexion at the interphalangeal joint (Froment's sign) (Fig. 34.23) and occasionally hyperextension at the MCP joint (Jeanne's sign) as the patient attempts forceful pinch. In such patients with weak pinch, tendon transfers will be required to restore adduction of the thumb and abduction of the index finger.

Patients may also develop an irritating ulnar deviation of the small finger in addition to clawing at the MCP joint of the small finger (Wartenberg's sign) caused by paralysis of the third palmar interosseous muscle and the unopposed action of the extensor digiti minimi tendon. Occasionally, a tendon transfer may be required to correct this ulnar deviation of the small finger.

Therefore, tendon transfers may be indicated in an ulnar nerve palsy^{15,16} (Table 34.4) to correct:

1. Clawing and asynchronous flexion of the fingers
2. Weak thumb–index finger pinch
3. Ulnar deviation deformity of the small finger
4. Weak FDP flexion at the DIP joints of the ring and small fingers.



Fig. 34.21 Typical posture of the ulnar claw hand characterized by hyperextension at the metacarpophalangeal joints, usually the ring and small fingers and reciprocal flexion at the proximal interphalangeal and distal interphalangeal joints.



Fig. 34.22 A patient with a combined low median–low ulnar nerve palsy demonstrating asynchronous flexion of the fingers, with flexion at the proximal interphalangeal and distal interphalangeal joints occurring before flexion at the metacarpophalangeal joints. Because of severe thenar atrophy, there is also loss of opposition of the thumb.



Fig. 34.23 With absence of the adductor pollicis muscle in a low ulnar nerve palsy, flexor pollicis longus primarily flexes the interphalangeal joint of the thumb, which results in hyperflexion of the interphalangeal joint when the patient attempts to produce key pinch (Froment's sign) and occasionally hyperextension at the metacarpophalangeal joint (Jeanne's sign).

Timing

Timing of tendon transfers for ulnar nerve palsy is primarily dependent on two factors: the probability of motor recovery and the severity of the functional deficit. Primary microsurgical repair of the ulnar nerve at the wrist can be expected to yield useful results in about 75% of patients. Secondary nerve grafting has been reported to provide some functional motor recovery in approximately 40% to 75% of cases, with a somewhat worse prognosis for sensory recovery. As in other peripheral nerve injuries, younger patients, those with shorter nerve defects, and those without other significant associated injuries have a better chance of obtaining useful results from ulnar nerve repair.

"Early" tendon transfers should be considered for those with a debilitating claw deformity. While clawing should be treated proactively using a lumbrical block splint, some patients may benefit from early static transfers to prevent MCP hyperextension and clawing. Trevett *et al.*⁵⁶ studied the functional results following both high and low ulnar nerve repairs to better define the indications for tendon transfers. They demonstrated continued improvement in intrinsic

muscle power, grip strength, and sensation for at least 2 years in high and 3 years in low ulnar nerve repairs. The significant conclusion from this study was that early tendon transfers should only be performed in manual laborers who complain of poor grip or key pinch.

Static procedures to correct clawing of the fingers

Static procedures to prevent hyperextension of the proximal phalanges at their MCP joints include A1 pulley release, fasciodesis at the MCP joint level, capsulodeses, and various tenodeses. Capsulodesis of the MCP joint, described by Zancolli,⁵⁷ is a very simple technique in which the A1 pulley is first released, the volar plate is incised longitudinally and detached from the metacarpal to create two distally based flaps, which are then advanced proximally and attached to the metacarpal neck to maintain the MCP joint in approximately 20° of flexion. Omer^{58,59} described creating a distal-based flap of the volar plate by making two parallel incisions on the medial and lateral aspects of the volar plate and excising Burow's triangles distally to allow proximal advancement of the volar plate (Fig. 34.24). The volar plate is anchored to the metacarpal neck with wire sutures through drill holes or by using a bone anchor. Recurrence of clawing has been demonstrated in long-term follow-up studies.⁶⁰

Parkes⁶¹ has described an effective tenodesis both to prevent hyperextension at the MCP joints and to provide extension at the interphalangeal joints by using tendon grafts sutured to the transverse carpal ligament and passed volar to the deep transverse intermetacarpal (intervolar plate) ligaments to insert into the radial lateral band of each finger. Omer⁵⁸ modified the Parkes tenodesis by attaching one tendon graft to the ulnar lateral band of the ring finger, passing around the deep transverse intermetacarpal ligament and suturing it to the radial lateral band of the small finger, with a second tendon graft from the ulnar lateral band of the index finger around the deep transverse intermetacarpal ligament to the radial lateral band of the long finger. Fowler attached tendon grafts to the extensor retinaculum, routed them dorsally through the intermetacarpal spaces and then volar to the deep transverse intermetacarpal ligaments and attached the grafts to the radial

Table 34.4 Tendon transfers for ulnar nerve palsy

Function to be restored	Preferred tendon transfer
Clawing of the ring and small fingers	Two slips of ring finger or long finger FDS to the radial lateral bands or proximal phalanges or A2 or A1 and A2 pulleys of the ring and small fingers
Clawing of all four fingers	EF4T or PL4T transfers to the radial lateral bands of the long, ring and small fingers and the ulnar lateral band of the index finger; or to the combined interosseous tendon insertion
Thumb adduction	ECRB + tendon graft to adductor pollicis
Index finger abduction	Accessory APL to first dorsal interosseous
Severe thumb MCP joint hyperextension	MCP joint arthrodesis
Fixed thumb IP joint contracture	IP joint arthrodesis
Weak DIP joint flexion ring and small fingers	Side-to-side tenorrhaphy of the ring and small finger FDP tendons to the long finger FDP tendon
DIP, Distal interphalangeal; ECRB, extensor carpi radialis brevis; EF4T, extensor tendon, flexor route, four-tailed graft; FDP, flexor digitorum profundus; FDS, flexor digitorum superficialis; IP, interphalangeal; MCP, metacarpophalangeal; PL4T, palmaris four-tailed graft.	




Fig. 34.24 Omer modification of the Zancolli capsulodesis: (A) The A1 pulley is released. (B) A distal-based flap of the volar plate is created and (C) advanced proximally and fixed to the metacarpal neck.

lateral bands of the fingers.⁵⁵ The Riordan tenodesis employs a similar dorsal route, utilizing two distally based strips of the ECRL and ECU tendons passed down the lumbrical canals, volar to the deep transverse intermetacarpal ligaments and attached to the radial lateral bands.²⁴

The various dynamic tendon transfers that have been described to correct clawing differ primarily as to whether they provide only MCP joint flexion or whether they provide both MCP joint flexion and interphalangeal joint extension. The surgeon can determine which general type of transfer is most appropriate by preoperative testing of PIP and DIP joint extension with the MCP joints held passively flexed – the Bouvier maneuver. With the MCP joints flexed, if the extrinsic extensor tendons can produce full extension at the PIP and

DIP joints (Fig. 34.25), the transfer may only need to produce strong MCP joint flexion by insertion of the transfer either into the A1 pulley (Zancolli⁶²); the A2 pulley (Brooks–Jones⁶³) (Fig. 34.26C); the A1 and proximal half of the A2 pulley Anderson⁶⁴; or through a drill hole in the proximal phalanx (Burkhalter⁶⁵) (see Fig. 34.26B). However, with longstanding flexion deformities of the PIP joints, the central slip of the extensor mechanism may become attenuated. Consequently, even with passive flexion of the MCP joints, the patient cannot actively extend the PIP joints using the extrinsic extensor tendons. In these circumstances, the transfer should be inserted into one of the lateral bands (see Fig. 34.26A); or into the dorsal base of the middle phalanx; or into the combined interosseous tendons (which Zancolli termed “direct interosseous




Fig. 34.25 The Bouvier maneuver: (A) Typical claw hand deformity of the small finger and to a lesser extent the ring finger with hyperextension at the metacarpophalangeal (MCP) joints and flexion at the proximal interphalangeal (PIP) and distal interphalangeal (DIP) joints. (B) In the Bouvier maneuver, the surgeon blocks hyperextension at the MCP joints and in this patient the extrinsic extensor tendons are able to produce full extension at the PIP and DIP joints.




Fig. 34.26 Alternative insertions for tendon transfers to prevent clawing: (A) Into the lateral band. (B) Burkhalter insertion through a drill hole or bone anchor in the proximal phalanx. (C) “Lasso” insertion into either the A1 pulley (Zancolli); the A2 pulley (Brooks-Jones); or the A1 and proximal half of the A2 pulley (Anderson).

activation^{62,66}), so that both MCP joint flexion and PIP joint extension can potentially be restored.

If one of the FDS tendons is used as a donor tendon to produce either MCP joint flexion alone or both MCP joint flexion and interphalangeal joint extension, it does not produce any increase in power grip; whereas adding an extra muscle-tendon unit from outside the hand to activate these transfers, such as a wrist flexor (FCR) or extensor tendon (ECRL, ECRB), will potentially lead to increased grip strength.

Tendon transfers to correct clawing

All of the following have been described as the donor muscle-tendon unit in tendon transfers to correct asynchronous finger flexion and clawing in ulnar nerve palsy⁶⁷ (see Table 34.4):

1. Flexor digitorum superficialis
2. Extensor carpi radialis brevis
3. Extensor indicis proprius and extensor digiti minimi
4. Flexor carpi radialis
5. Extensor carpi radialis longus
6. Palmaris longus.

Stiles and Forrester-Brown⁶⁸ originally described transfer of one slip of each FDS tendon into the extensor mechanism and this was subsequently modified by both Bunnell⁶⁹ and Littler.³³ The Littler modification is referred to as the modified Stiles-Bunnell technique and involves transfer of the FDS of the ring finger or long finger or both fingers, splitting the tendon longitudinally into two slips, passing each slip of the FDS tendon down the lumbrical canals, and attaching them to the radial lateral bands of the fingers (Fig. 34.27).

If the Bouvier maneuver confirms that the extrinsic extensor tendons can produce full extension at the PIP and DIP joints with the MCP joints flexed, alternative insertions of the modified Stiles-Bunnell transfer into either the pulleys or the proximal phalanx can be considered in an attempt to prevent the risk of developing a secondary hyperextension deformity at the PIP joint. Zancolli originally described dividing the FDS tendons to the ring and small fingers distal to the A1 pulley between the A1 and A2 pulleys through a distal palmar crease incision. Each tendon is withdrawn from the flexor sheath between the A1 and A2 pulleys, looped around the A1 pulley,

and sutured back to itself. This has been termed the “lasso” procedure.⁶² In patients with a high ulnar palsy, the ring and small finger superficialis tendons cannot be used and therefore the long finger FDS tendon is divided into two slips and each slip is passed under the A1 pulleys of the ring and small fingers and sutured to itself (see Fig. 34.27). The FDS tendon slips are sutured with the wrist in neutral, the MCP joints in 60° of flexion and the wrist is then immobilized in 10° of flexion and the MCP joint is 90° of flexion for 3 weeks, but allowing motion at the PIP and DIP joints. Omer and Brooks-Jones⁶³ described looping the FDS tendon around the A2 pulley (see Fig. 34.26C) rather than the A1 pulley, and Anderson⁶⁴ has described an extended pulley insertion (EPI) by looping the FDS tendon around both the A1 and the proximal half of the A2 pulleys. Burkhalter⁶⁵ recommended insertion of the FDS tendon slips of a modified Stiles-Bunnell transfer into a radial-ulnar drill hole in the proximal phalanx (see Fig. 34.26B).

In a combined high median-ulnar nerve palsy, all the FDS tendons are paralyzed and consequently an “indirect lasso” procedure is required. After passing the FDS tendons around the A1 pulleys, the proximal ends of the FDS tendons are activated either by extensor carpi radialis longus or flexor carpi radialis. Brooks and Jones⁶³ have described a variant of this transfer in which the extensor carpi radialis longus or flexor carpi radialis are elongated with plantaris or toe extensor tendon grafts passed through the carpal tunnel and inserted more distally into the A2 pulley. Burkhalter and Strait⁶⁵ have also used the same donor tendons, the ring finger FDS and extensor carpi radialis longus but with insertion through a transverse drill hole in the middle third of the proximal phalanx. The ring finger FDS is divided at the level of the PIP joint withdrawn into the palm and divided into two slips. Each slip is then passed down the lumbrical canal into a transverse drill hole on the radial aspect of the middle third of the proximal phalanx of the ring and small fingers.

Modified Stiles-Bunnell transfer (see Fig. 34.27)

In the modified Stiles-Bunnell transfer³³ for patients with an isolated low ulnar nerve palsy, the ring finger FDS tendon is




Fig. 34.27 (A) Modified Stiles-Bunnell transfer to prevent clawing. The flexor digitorum superficialis (FDS) tendon from the long finger is split into two slips and inserted into the radial lateral band (ring finger) or the A2 pulley (small finger). **(B)** Splitting of the FDS tendon from the long finger into two slips, which are passed down the lumbrical canals to the radial lateral bands of the ring and small fingers.

divided just proximal to the PIP joint, withdrawn through a transverse distal palmar crease incision, and split longitudinally into two slips. The radial lateral bands of the ring and small fingers are exposed through radial midaxial incisions and each slip of the FDS tendon is passed down the lumbrical canals of the ring and small fingers. With the wrist in neutral, each slip is sutured under adequate tension to the radial lateral bands with the MCP joints in 45–55° of flexion and the interphalangeal joints fully extended (see Fig. 34.27). Tension is assessed using the tenodesis effect of the wrist – with wrist extension, the fingers should assume the “intrinsic-plus” position. The hand is immobilized in a dorsal block splint with the wrist in slight flexion and the MCP joints flexed 70° for 3½ to 4 weeks. In a high ulnar nerve palsy, the ring finger FDS tendon is the only remaining extrinsic flexor tendon in the ring finger and therefore the long finger FDS tendon is used. Occasionally, the long or ring finger FDS tendon may be split into three slips, should the long, ring, and small fingers need correction. With a total intrinsic palsy, the FDS tendons to both the long and ring fingers are each divided into two slips and passed down the lumbrical canals to the radial lateral bands of the index, long, ring, and small fingers. Brand advocates insertion of the slip to the index finger into the ulnar lateral band to provide improved three-point pinch. However, this may result in scissoring of the index and long fingers. Zancolli⁶² has described insertion of the FDS donor tendon into the combined interosseous tendons rather than the radial lateral bands and termed this alternative technique of restoring MCP joint flexion and interphalangeal (IP) joint extension as “direct interosseous activation”.

One of the disadvantages of the modified Stiles-Bunnell transfer is that the ring finger superficialis is not expendable in a high ulnar nerve palsy or in a combined high median-high ulnar nerve palsy. Secondly, the transfer may result in progressive overcorrection of the claw deformity eventually resulting in a “swan neck” hyperextension deformity at the PIP joints. A “swan neck” hyperextension deformity can be prevented by utilizing one of the distal slips of FDS as a tenodesis across the PIP joint. Thirdly, the donor long or ring finger may develop a flexion contracture at the PIP joint or loss of extension at the DIP joint. North and Littler⁷⁰ recommended harvesting the FDS tendon through a Bruner incision between the A1 and A2 pulleys rather than a midaxial incision at the level of the PIP joint. The modified Stiles-Bunnell transfer should therefore only be used in patients with mild PIP joint flexion contractures or stable fingers without passive hyperextension at the PIP joints.

Brand EE4T transfer (Fig. 34.28)

Due to his extensive experience of tendon transfers in leprosy patients, Brand^{4,71} originally described transfer of the extensor carpi radialis brevis (ECRB), extended with four tendon grafts, passed from dorsal to palmar through the intermetacarpal spaces and then down the lumbrical canals to be attached to the radial lateral bands of the middle, ring, and small fingers, and to the ulnar lateral band of the index finger (EE4T: extensor tendon, extensor route, four-tailed graft). However, during wrist extension, the ECRB and tendon grafts relax, which is a relative disadvantage of this dorsal routing of the original Brand transfer. Burkhalter and Strait⁶⁵ modified the Brand EE4T transfer by using ECRL instead of ECRB and by only




Fig. 34.28 Brand EF4T (extensor tendon, extensor route, four-tailed graft) transfer: Extensor carpi radialis brevis is extended by three tendon grafts which are passed volar to the intermetacarpal ligaments and inserted into the radial lateral bands of the long, ring, and small fingers.

correcting the ring and small fingers. The ECRL is lengthened with two tendon slips which are passed through the third and fourth intermetacarpal spaces, down the lumbrical canals, volar to the deep transverse intermetacarpal ligaments and inserted into a drill hole on the radial aspect of the middle third of the proximal phalanges. The wrist is immobilized in 40° of extension and the MCP joints in 70° of flexion for 4 weeks. This transfer will only produce MCP joint flexion, but is an alternative transfer for a combined high median–high ulnar nerve palsy when the modified Stiles–Bunnell flexor digitorum superficialis transfer is not available. Riordan²⁴ described a similar transfer using flexor carpi radialis (FCR) transferred dorsally around the radial border of the forearm and elongated with tendon grafts passed dorsal-to-palmar through the intermetacarpal spaces volar to the deep transverse intermetacarpal ligaments and inserted into the radial lateral bands. This transfer is mutually beneficial if there is an associated flexion contracture of the wrist.

The dorsal route also forms the basis for the Fowler transfer using both the EIP and extensor digiti minimi (EDM) tendons. The two tendons are divided just beyond the MCP joints of the index and small fingers and each tendon is split longitudinally into two slips. The four slips are tunneled subcutaneously to the radial lateral bands of the fingers.⁵⁵ The EIP

tendon controls the index and long fingers and the EDM tendon controls the ring and small fingers. In a modification of this Fowler transfer, Riordan has described splitting only the EIP tendon into two slips and passing them from dorsal to palmar through the third and fourth intermetacarpal spaces to insert into the radial lateral bands to correct clawing of the ring and small fingers.⁷² A relative disadvantage of the Fowler and Riordan transfers is that the EIP and EDM tendons are only just long enough to reach the radial lateral bands and these transfers are rarely used.

Brand EF4T transfer (Fig. 34.29)

Brand⁷¹ modified his original dorsal transfer of ECRB by extending extensor carpi radialis longus (ECRL) with a four-tailed tendon graft or fascia lata graft through the carpal tunnel to the radial lateral bands of the long, ring, and small fingers and the ulnar lateral band of the ring finger (EF4T: extensor tendon, flexor route, four-tailed graft). In an isolated ulnar nerve palsy, this transfer is only attached to the radial




Fig. 34.29 Brand EF4T (extensor tendon, flexor route, four-tailed graft) transfer to correct clawing of all four fingers: Extensor carpi radialis longus is transferred around the radial border of the forearm, extended by four tendon grafts, which are passed through the carpal tunnel and inserted into the radial lateral bands of the long, ring, and small fingers and the ulnar lateral band of the index finger.





Fig. 34.30 Brand EF4T (extensor tendon, flexor route, four-tailed graft) transfer to correct clawing of the ring and small fingers in a low ulnar nerve palsy. **(A)** Extensor carpi radialis longus (ECRL) is detached from its insertion on the base of the index finger metacarpal. **(B)** A palmaris longus tendon graft has been sutured to ECRL and passed around the radial border of the forearm (or through the interosseous membrane). The palmaris longus tendon graft is passed through the carpal tunnel and split into two slips, which are passed down the lumbrical canals to be inserted into the radial lateral bands of the ring and small fingers. **(C)** Postoperative correction of the claw deformity of the ring and small fingers.

lateral bands of the ring and small fingers (Fig. 34.30). Two short transverse incisions are made, one over the second dorsal extensor tendon compartment to allow transection of the ECRL tendon, which is withdrawn into the second incision over the radial aspect of the mid-forearm. Either a folded fascia lata graft or a plantaris tendon graft is sutured to the distal end of the ECRL tendon projecting through the radial forearm incision. The elongated ECRL tendon is then passed around the radial border of the forearm into a transverse volar forearm incision just proximal to the wrist crease. Through a 3 cm-long incision on the ulnar side of the thenar crease, a tendon-tunneling forceps is introduced distal to the superficial palmar arch and passed along the floor of the carpal tunnel to exit on the radial side of the volar forearm incision and the tendon grafts or fascia lata graft are then pulled distally through the carpal tunnel into the palmar incision. The proximal tendon juncture therefore lies distal to the volar forearm incision, but proximal to the transverse carpal ligament. Each of the two plantaris slips are split longitudinally to produce four slips or the fascia lata graft is split into four slips. Through radial midaxial incisions over the proximal phalanges of the long, ring, and small fingers, the tunneling forceps is passed down each lumbrical canal volar to the deep transverse intermetacarpal ligaments into the palmar incision and the three tendon slips are brought out into each midaxial incision. The tendon slip to the index finger is tunneled to an ulnar midaxial incision and attached to the ulnar lateral band. This will produce supination of the index finger and may provide better three-point pinch. The hand is positioned on a frame with the wrist flexed 30°, the MCP joints flexed 70° and the interphalangeal joints fully extended. Proximal traction is applied to each lateral band to take up any slack in the extensor mechanism. After taking up the slack in all four plantaris tendon grafts, they are sutured to the lateral bands just

proximal to the PIP joints under equal tension. Tension is adjusted in the index finger first, then the small finger, and finally the long and ring fingers. The hand is immobilized with the wrist in neutral, the MCP joints flexed 90°, and the IP joints straight for 3 weeks.

Fritschi PF4T transfer

Fritschi⁷³ has described the palmaris longus as an alternative motor for the Brand EF4T transfer. In the Lennox–Fritschi PL4T (palmaris four-tail) transfer, the palmaris longus tendon is lengthened with a tendon graft or fascia lata graft, which are then passed through the carpal tunnel to the lateral bands in a similar route to the Brand EF4T procedure. However, the palmaris longus is obviously a much weaker donor muscle than the ECRL.

Two alternative insertions have been described for the Brand EF4T and Lennox–Fritschi PL4T transfers, either the common interosseous tendon insertion or the A2 pulley. Zancolli⁶² originally described looping the tendon graft or fascia lata grafts around the common interosseous tendon – a technique described as “direct interosseous activation”. In addition to restoring MCP joint flexion, this insertion may potentially provide abduction of the fingers. Palande⁶⁶ has also reported using both the ECRL and palmaris longus tendons extended with tendon grafts, inserting them around the common interosseous tendons. ECRL or palmaris longus are elongated with tendon grafts or fascia lata grafts which are then tunneled through the carpal tunnel to emerge distal to the superficial palmar arch through an incision just to the ulnar side of the thenar crease. The first dorsal interosseous tendon, the palmar and dorsal interosseous tendons in the second, third, and fourth webspaces and the muscle–tendon junction of the hypothenar muscles are all identified through

a transverse incision along the distal palmar crease. The plantaris tendon grafts or fascia lata grafts are split into four or five slips. One slip is looped around the muscle–tendon junction of the first dorsal interosseous; one slip around the combined first palmar interosseous and second dorsal interosseous tendons in the index–long finger webspace; one slip around the combined third dorsal interosseous and second palmar interosseous tendons in the long–ring finger webspace; one slip around the combined fourth dorsal interosseous and third palmar interosseous tendons in the ring–small finger webspace; and if necessary the final fifth slip can be looped around the muscle–tendon junction of the hypothenar muscles. The hand is positioned with the MCP joints flexed 60° and the interphalangeal joints straight. After slack has been taken up, each of the four or five slips are sutured back onto themselves, starting on the radial side with the index finger, then the slip between the ring and small fingers and finally the slips between the index and long fingers and between the long and ring fingers. The correct tension is confirmed by performing a wrist tenodesis maneuver. The hand is immobilized for 3 weeks with the wrist neutral, the MCP joints in 90° of flexion, and the interphalangeal joints extended.

Brooks and Jones⁶³ described amalgamating the Brand EF4T transfer with the Zancolli lasso procedure in which the ECRL or FCR tendons are elongated with plantaris or toe extensor tendon grafts and passed through the carpal tunnel and looped around the A2 pulleys of each finger. This variant of the EF4T transfer will only produce MCP joint flexion.

Tendon transfer to correct ulnar deviation of the small finger

A variant of the Fowler transfer has been advocated by Blacker *et al.*⁷⁴ to correct the ulnar deviation deformity of the small finger (Wartenberg's sign). The ulnar half of extensor digiti minimi is detached, passed volar to the deep transverse intermetacarpal ligament and sutured into the insertion of the radial collateral ligament of the MCP joint at the base of the proximal phalanx, or if there is associated clawing of the small finger, it is looped under the A2 pulley and sutured back to itself (Brooks' insertion). Chung *et al.*⁷⁵ described transferring EIP to the distal radial aspect of the extensor hood of the small finger to correct the persistent abduction deformity of the small finger in an ulnar nerve palsy.

Tendon transfers to provide adduction of the thumb

The most successful tendon transfers to restore adduction of the thumb have a transverse direction of pull across the palm deep to the flexor tendons to insert into the tendon of adductor pollicis. Littler³³ has advocated transfer of the ring finger FDS tendon deep to the flexor tendons of the index and long fingers, parallel and superficial to the transverse fibers of adductor pollicis and inserted into a drill hole just distal to the adductor insertion, and has been able to document an increase in pinch strength to 71% of the opposite hand. Smith⁷⁶ described using extensor carpi radialis brevis extended by a free tendon graft passed through the second intermetacarpal space and tunneled deep to the flexor tendons but superficial to the adductor pollicis to an insertion into the adductor




Fig. 34.31 Smith adduction transfer. A tendon graft is attached to the adductor tubercle on the ulnar base of the proximal phalanx of the thumb, passed through the second intermetacarpal space and sutured to extensor carpi radialis brevis.

tendon (Fig. 34.31). Other tendon transfers to restore adduction of the thumb have included either the brachioradialis⁷⁷ or extensor carpi radialis longus⁷⁸ elongated with a tendon graft and passed through the third intermetacarpal space to the thumb MCP joint, and the extensor indicis proprius passed through the second intermetacarpal space.⁷⁹ Combined transfers to provide both thumb adduction and index finger abduction have been described by splitting the extensor indicis proprius or extensor digiti minimi tendons.⁸⁰

If there is a severe collapse Z-deformity of the thumb with hyperextension at the MCP joint and flexion at the IP joint, or

an exaggerated Jeanne's sign when attempting to pinch, arthrodesis of the MCP joint may be necessary.^{33,81} The thumb MCP joint is positioned in 15–20° of flexion and 15° pronation and arthrodesis achieved using a dorsal plate, interosseous wiring, or tension band wiring. Arthrodesis of the MCP joint may be combined with an adductor transfer or the transfer may be performed secondarily. Occasionally, if there is a severe fixed flexion deformity of the IP joint, arthrodesis of the IP joint is indicated⁸² instead of the MCP joint, combined with an adductor transfer. IP joint arthrodesis is achieved with interosseous wiring, K-wires or a combination of each or headless compression screws.

For mild collapse deformities of the thumb without a fixed contracture, a split FPL to EPL transfer may be indicated.⁸³ Through a volar Bruner incision, the FPL is split longitudinally from its insertion proximally to the distal end of the A1 pulley. The radial half of FPL is transected at its insertion, retracted back proximal to the oblique pulley, and passed deep to the radial neurovascular bundle around the radial border of the proximal phalanx into a longitudinal incision on the dorsum of the proximal phalanx. The radial slip of FPL is sutured to the EPL tendon proximal to the IP joint with the MCP joint in 15° of flexion and the IP joint in full extension. The IP joint is fixed with a K-wire for 4 weeks.

Ring finger flexor digitorum superficialis adductor transfer

The ring finger FDS tendon is transected between the A1 and A2 pulleys through a short incision at the base of the ring finger.³³ The FDS tendon is then passed transversely across the palm deep to the index and long finger flexor tendons to the ulnar aspect of the thumb MCP joint, through a short incision just to the ulnar side of the thenar crease. The transfer is either sutured into the adductor pollicis tendon or passed through a drill hole in the proximal phalanx just distal to the adductor insertion and tied over a button. Tension is set with the wrist in neutral and the thumb adducted against the index finger with the FDS tendon at its resting length. Appropriate tension is confirmed by tenodesis of the wrist – with wrist flexion, the thumb should be able to be passively abducted. Edgerton and Brand³⁴ have described a variation of this transfer in which the ring finger FDS is brought through a window in the palmar fascia and then passed subcutaneously to the abductor insertion. The vertical septum of palmar fascia arising from the long finger metacarpal acts as a pulley. Obviously, the ring finger FDS cannot be used as an adductor transfer in patients with a high ulnar nerve palsy since this would deprive the ring finger of its only remaining flexor tendon.

Smith extensor carpi radialis brevis adductor transfer (see Fig. 34.31)

Extensor carpi radialis brevis is transected through a short transverse incision over the second dorsal extensor compartment just distal to the extensor retinaculum and withdrawn through a second transverse incision just proximal to the extensor retinaculum.⁷⁶ A small flap is then elevated over the ulnar aspect of the MCP joint of the thumb and a palmaris or plantaris tendon graft sutured to the adductor pollicis tendon. Through a short transverse incision overlying the proximal third of the second intermetacarpal space, a tendon passer is

used to tunnel the tendon graft deep to the flexor tendons but superficial to the adductor pollicis, withdrawing it dorsally through the second intermetacarpal space. After passing the tendon graft subcutaneously to the most proximal incision, it is woven into the extensor carpi radialis brevis tendon with the wrist in neutral and the thumb adducted (see Figs. 34.31 & 34.33). Tension is then checked by tenodesis of the wrist – with wrist flexion, the thumb should become strongly adducted, whereas wrist extension should allow easy passive abduction of the thumb. Postoperatively the thumb is immobilized for 3 weeks midway between full abduction and full adduction with the wrist in 20–30° of extension.

Tendon transfers to provide index finger abduction

Restoration of strong abduction of the index finger is the second component required for powerful pinch. Bunnell⁶⁹ described the transfer of extensor indicis proprius (EIP) extended with a short tendon graft and inserted into the first dorsal interosseous tendon. Bruner⁸⁴ divided the extensor pollicis brevis (EPB) tendon over the dorsum of the MCP joint of the thumb and tunneled it subcutaneously beneath the extensor pollicis longus tendon into the first dorsal interosseous tendon. Hirayama⁸⁵ lengthened the palmaris longus tendon with a strip of palmar fascia (similar to the Camitz transfer) and tunneled it subcutaneously around the radial border of the forearm over the dorsum of the wrist and hand to insert into the first dorsal interosseous tendon. Graham and Riordan⁸⁶ transferred the FDS of the ring finger in a similar route around the radial border of the wrist over the dorsum of the hand to either the first dorsal interosseous tendon or into a drill hole on the radial aspect of the index finger. However, one of the accessory tendons of abductor pollicis longus (APL) extended with a free tendon graft or attached to the re-routed EDC tendon of the index finger may be the best choice to restore abduction of the index finger.⁸⁷

Neviaser accessory abductor pollicis longus and free tendon graft (Fig. 34.32)

Neviaser *et al.*⁸⁷ described an accessory APL tendon elongated with a palmaris or plantaris tendon graft transferred to the insertion of the first dorsal interosseous tendon (see Figs. 34.32e and 34.33). A small flap is elevated over the radial aspect of the proximal phalanx of the index finger and a tendon graft sutured to the first dorsal interosseous tendon just distal to the MCP joint. The proximal end of the tendon graft is then passed subcutaneously to a transverse incision just distal to the first dorsal extensor compartment. After opening the compartment, one of the accessory APL tendons is transected and interwoven with the tendon graft with the wrist in neutral position and the index finger radially abducted.

High ulnar nerve palsy

Many surgeons fail to realize the significant functional deficit in a high ulnar nerve palsy associated with paralysis of the flexor carpi ulnaris and FDP tendons to the ring and small




Fig. 34.32 Neviasser transfer to restore abduction of the index finger. A palmaris tendon graft is sutured to the insertion of the first dorsal interosseous muscle on the radial base of the proximal phalanx of the index finger and sutured to one of the accessory tendons of abductor pollicis longus.

fingers. The only remaining tendons on the ulnar side of the hand are the FDS tendon to the ring finger and the usually diminutive FDS tendon to the small finger. However, paralysis of the FDP tendons to the ring and small fingers will often be masked by interconnections between these two tendons and the long finger FDP tendon at the wrist. If there is significant weakness of DIP joint flexion of the ring and small fingers (Pollock's sign), power grip can be restored by side-to-side tenorrhaphy of the ring and small finger FDP tendons to the median-innervated middle finger FDP tendon.⁵⁸ This should be performed before tendon transfers to correct clawing are performed, but patients should be warned that this will temporarily exaggerate their clawing and that they should use a lumbrical block splint. To restore independent flexion of the ring and small fingers, the FDS tendon of the long finger may be used as a donor tendon to activate the FDP tendons of the ring and small fingers. Patients requiring strong ulnar deviation and flexion of the wrist may occasionally need to be considered for transfer of the FCR tendon to FCU.⁵⁸

Outcomes

There are very few reports to substantiate the relative effectiveness of the various transfers to restore synchronous MP flexion and IP extension of the fingers and thumb-index finger pinch. Hastings and Davidson⁸⁸ compared four techniques: Zancolli "lasso", Stiles-Bunnell, Brand, and Riordan and Fowler transfers to correct the claw deformity in 12 patients with high, 14 patients with low, and three patients with mixed high and low ulnar nerve palsy. Successful outcomes were seen in the majority of cases. Most failures occurred in the small finger and transfers utilizing the superficialis tendons were found to further weaken the hand. Only transfers using wrist flexors or extensors have been shown to increase grip strength. A later report examining the effectiveness of the FDS "lasso" procedure showed similar results, with correction of clawing in 19 of 23 digits but no significant improvement in grip strength.⁸⁹ The extended pulley insertion for a modified Stiles-Bunnell transfer produced good to excellent correction of clawing in 92% of fingers.⁶⁴ Brandsma *et al.*⁵¹ reported good (57%) or excellent (21%) results using the FDS transfer to restore intrinsic function. The long or ring finger FDS transfer resulted in 95% good or excellent correction of clawing in leprosy patients at an average follow-up of 2 years.⁶⁴ The Brand EF4T transfer provided 79–86% good to excellent correction of clawing at a 10-year follow-up.⁶⁴ Eighty-five percent good to excellent results were obtained utilizing the common interosseous tendon insertion technique.⁶² PIP hyperextension occurred in 6.25% when the common interosseous tendon insertion was utilized in an EF4T transfer, compared with a 13.75% incidence when the EF4T transfer was inserted into the lateral bands.⁶⁴ Therefore there is less chance of over-correction producing a PIP joint hyperextension deformity by utilizing the common interosseous tendon insertion. An additional advantage of using ECRB as the motor is that the palmar arch is restored. Ozkan *et al.*⁹⁰ compared the results of three different tendon transfers to restore grip strength and correct the claw deformity in 44 patients with ulnar nerve palsy. Twenty-four patients were reconstructed with a modified Stiles-Bunnell four-tail procedure, 11 patients with the Brand EF4T transfer and nine patients with a Zancolli "lasso" procedure. With a recent paralysis, the Zancolli and Brand procedures were the most effective in restoring grip strength, but with long-standing paralysis, the Stiles-Bunnell four-tail procedure was the most successful in correcting the claw deformity.

Hastings and Davidson⁸⁸ showed an approximate doubling of pinch strength in hands treated with the ECRB adductorplasty transfer, although it is interesting to note that only 18 of the 34 patients in this study felt that pinch strength was compromised enough to warrant a tendon transfer. Robinson *et al.*⁸⁰ evaluated the combination of the ulnar slip of EDM to provide thumb adduction and EIP to restore index finger abduction in six patients and demonstrated an average improvement in pinch strength from 5% to 40–50% of the normal side. Fischer *et al.*⁹¹ evaluated the results of tendon transfers to restore thumb adduction (ECRL was transferred to adductor pollicis) and index finger abduction (APL was transferred to the first dorsal interosseous) at an average of 6 years postoperatively. Key pinch averaged 73%, pulp-to-pulp pinch averaged 72%, grip strength was 73%, the force of thumb adduction was 63%,




Fig. 34.33 (A) Smith transfer to restore adduction of the thumb and the Neviaser transfer to restore abduction of the index finger. (B) A tendon graft has been attached to the adductor pollicis insertion and passed deep to the flexor tendons and neurovascular bundles through the second intermetacarpal space from palmar to dorsal. A second tendon graft has been sutured to the tendon of insertion of the first dorsal interosseous muscle. (C) Traction on these two tendon grafts flexes and adducts the thumb and abducts the index finger at the metacarpophalangeal joint. (D) Postoperatively the patient has excellent abduction of the index finger for key pinch and (E) significant improvement in pinch strength.

and the force of index finger abduction was 58% of the normal hand.

Tendon transfers for combined nerve injuries

It is much more difficult to reconstruct the upper extremity affected by multiple nerve injuries. The majority of these patients require multiple reconstructive procedures and

tendon transfers. The choice of tendon transfers and the timing of the surgery should be well planned, designed, and individualized to address the patient's specific functional needs. It is unwise to adopt a "cookbook" approach for reconstruction of the patient with combined nerve injuries. Basic principles of tendon transfers such as soft-tissue equilibrium, full passive range of motion of involved joints, selection of the appropriate donor muscle, and direction of transfer as outlined earlier should be carefully considered in preoperative planning.

Before any operation is performed, the patient should be educated about the goals and risks of the procedure and the

fact that the injured extremity will never be normal. As a general rule, the results of tendon transfers for combined nerve injuries are inferior to those for a single nerve injury.^{92,93}

Adding to the complexity of these problems, the number of donor tendons is limited, more joints need to be mobilized, there is a more profound sensory loss, and the soft tissues may be more scarred in this patient population. Multiple nerve repairs or nerve grafting should be done as soon as clinically appropriate but return of motor function rarely extends beyond two major joints distal to the injury.⁹⁴ Reinnervated muscles, however, should not be used or only used with great caution as a donor for tendon transfers.

Dynamic tenodesis is an important concept in reconstruction of these combined nerve injuries. Wrist flexion or extension can be used to augment the excursion of any tendon transfer that crosses the wrist. For example, if a wrist flexor such as FCR is used to activate flexor digitorum profundus, flexion of the fingers will be enhanced if the patient extends their wrist using the ECRL or ECRB simultaneously with contraction of the FCR transfer. Therefore, if the excursion of a tendon transfer is less than optimal to produce a specific function, increased range of motion can be achieved through wrist tenodesis.⁹⁵

Tendon transfers for low median–low ulnar nerve palsy

A low median and low ulnar nerve palsy is the most common combined nerve injury in the upper extremity and is usually the result of a “spaghetti-wrist” laceration.⁹² This leads to complete loss of sensation on the palmar surface of the hand and a complete intrinsic motor paralysis that results in a claw hand deformity. A flat transverse metacarpal arch with hyperextension at the MCP joints and hyperflexion at the PIP joints (see Fig. 34.22) accompanied by an abducted small finger are the hallmark of this injury. It is especially important to prevent an adduction contracture of the thumb–index webspace.⁹⁵ The surgeon should repair or graft the median and ulnar nerves before any tendon transfers are performed in order to restore some protective sensibility to the hand. The goals of reconstruction in a low median–low ulnar nerve palsy are to restore thumb adduction, thumb abduction and opposition, abduction of the index finger, and improved extension of the PIP joints of the fingers.

Thumb adduction for key pinch can be restored by transfer of the extensor carpi radialis brevis extended by a tendon graft through the second intermetacarpal space and inserted into the adductor tubercle of the thumb metacarpal⁷⁶ or alternatively by transfer of the ring finger FDS tendon to the adductor insertion.³³ The best option for reconstruction of thumb opposition is the extensor indicis proprius transfer re-routed around the ulnar border of the hand and inserted into the abductor pollicis brevis tendon.^{37,96} This transfer can be combined with arthrodesis of the MCP joint of the thumb to allow for maximum stability.⁹⁷ Index finger abduction for strong pinch can be restored by transfer of one of the accessory slips of the abductor pollicis longus tendon extended by a tendon graft to the first dorsal interosseous insertion.⁸⁷ Finally, clawing of the fingers can be corrected by using ECRL or palmaris longus^{71,73} extended by four tendon grafts and inserted either into the radial lateral bands or the A2 pulleys as previously discussed. Alternatively, if the patient has

developed a flexion contracture of the wrist, by involuntarily trying to prevent clawing by flexing their wrist, the FCR tendon may be used to motor the four tendon grafts.²⁵

If the patient still has poor palmar sensibility despite nerve repair or nerve grafting, consideration should be given to transfer of a superficial radial nerve innervated flap to the thumb or nerve transfer of the superficial radial nerve to the distal median nerve.

Tendon transfers for high median–high ulnar nerve palsy

This is a very severe injury in which there is no active flexion of the fingers and thumb, and loss of thumb opposition and key pinch, in addition to the loss of palmar sensibility. Initially, the fingers may be fully extended even at the interphalangeal joints despite the intrinsic paralysis. However, once tendon transfers are completed to provide active finger flexion, the fingers gradually assume a claw posture. Tendon transfers for reconstruction of a high median–high ulnar nerve palsy have to be performed in two or three stages. The goals are to restore finger and thumb flexion, thumb–index finger pinch, abduction and opposition of the thumb, and correct the later development of clawing of the fingers.

Thumb adduction and key pinch can be achieved by transfer of extensor carpi radialis brevis with a free tendon graft through the second intermetacarpal space to the adductor pollicis insertion.^{76,98} Finger flexion can be restored by transfer of extensor carpi radialis longus to the four FDP tendons.⁵⁸ This can be combined with tenodesis of the DIP joints of the three ulnar fingers.⁹² Flexion of the thumb can be restored by transfer of the brachioradialis to flexor pollicis longus through the same palmar incision.⁵⁸ The brachioradialis muscle must be mobilized and elevated off the radius into the proximal third of the forearm. A Pulvertaft tendon weave is then performed between the brachioradialis and flexor pollicis longus in the distal third of the forearm.^{78,92} As in a low median–low ulnar nerve palsy, the most reliable procedure for thumb opposition is transfer of the extensor indicis proprius to the abductor pollicis brevis insertion.³⁷ If the IP joint of the thumb tends to assume a flexed position, the EIP transfer should be inserted both into the APB insertion and then into the EPL tendon just proximal to the IP joint.²⁵ If thumb pinch remains unstable with MP extension and IP joint flexion, arthrodesis of the MP joint should be considered. A useful procedure that avoids the need to fuse the IP joint of the thumb involves longitudinal splitting of the FPL tendon, detaching the radial half from its insertion into the distal phalanx and transfer of this tendon slip dorsally where it is attached into the EPL tendon proximal to the IP joint of the thumb.⁸³ This results in a dynamic stabilization of the IP joint when the transfer pulls through the FPL.

If after finger flexion has been restored the fingers begin to adopt a claw position, there are no expendable wrist extensors (ECRL and ECRB) remaining to provide integration of MP flexion and IP joint extension, static tenodesis techniques may be necessary. Free tendon grafts can be placed from the deep transverse metacarpal ligaments to the lateral bands⁶¹ or from the dorsal carpal ligament to the lateral bands.²⁵ Alternatively, hyperextension can be prevented by Zancolli capsulodeses or arthrodeses of the PIP joints. Finally, abduction of the index finger for pinch can be restored using an accessory abductor

pollicis longus tendon extended with a free tendon graft to the first dorsal interosseous⁸⁷ or alternatively by using extensor pollicis brevis.⁸⁴

The importance of restoring sensibility to the radial side of the hand in a high median–high ulnar nerve palsy cannot be overstated, either by secondary nerve repair or nerve grafting. A sensate hand is the prerequisite for performing the tendon transfers mentioned above. If sensation cannot be restored, Omer has advocated a fillet flap of the index finger to resurface the thumb–long finger webspace with dorsal skin innervated by the superficial radial nerve.⁹² Alternatively, a first dorsal metacarpal artery flap innervated by the superficial branch of the radial nerve can be transferred to the palmar surface of the thumb; or the superficial branch of the radial nerve itself can be transferred to the distal median nerve as a nerve transfer.

Tendon transfers for reconstruction after trauma

Tendon transfers are an excellent method of restoring active motion to the hand and wrist following traumatic injuries of the muscles and tendons of the forearm, wrist, and hand. If there has been segmental loss of tendon, a tendon graft is often used instead of a tendon transfer. With more severe trauma (industrial or motor vehicle accidents, blast, missile, and explosion injuries), associated damage to the soft tissues

will leave a scarred bed which is unsuitable for tendon grafts, since a tendon graft is more likely to become adherent to the scarred surrounding tissue than a tendon transfer. If a forearm muscle itself has been badly damaged, a tendon graft will be unable to restore active motion and a tendon transfer will be necessary.

Time is another important consideration in reconstruction of the post-traumatic upper extremity. Myostatic contracture and atrophy are the unavoidable fate of injured muscle if there has been a long delay between the traumatic event and the reconstructive procedure, again making a tendon transfer a more suitable option for reconstruction.

Tendon transfers to restore thumb extension

Rupture of the EPL tendon occurs in approximately 1 in 200 distal radius fractures, classically at Lister's tubercle, and may happen at any time from several weeks to several months after the fracture. Ischemia of the tendon due to swelling and edema of the tenosynovium and attrition over the roughened dorsal radial cortex have been postulated as the etiology for this tendon rupture.^{99–102} Patients present with weak or loss of extension at the interphalangeal joint (Fig. 34.34A) or paradoxically with incomplete extension at the MCP joint as well as inability to raise the thumb dorsal to the plane of the hand.

The optimal choice for restoration of thumb extension is the EIP to EPL transfer, which can be performed under local



Fig. 34.34 (A) This patient demonstrates inability to extend the interphalangeal joint of the thumb due to a rupture of the extensor pollicis longus (EPL) tendon caused by a minimally displaced Colles fracture of the distal radius. (B) The extensor indicis proprius tendon is transected at the metacarpophalangeal joint of the index finger and passed subcutaneously to be sutured to the ruptured end of the EPL tendon. (C) Postoperatively the patient demonstrates excellent extension and (D) flexion of the interphalangeal joint of the thumb.

anesthesia (see Fig. 34.34B). The EIP tendon is harvested through a short transverse incision just proximal to the index finger MCP joint and its distal stump is then sutured end-to-side to the EDC tendon of the index finger to prevent extensor lag of this finger. The EIP is retrieved through a second transverse incision just distal to the extensor retinaculum. A third incision is made over the distal third of the thumb metacarpal and the EIP is tunneled subcutaneously to this incision. The distal end of the EIP is sutured to the distal end of the EPL with the wrist held in neutral and the thumb fully extended and parallel or just volar to the plane of the palm.¹⁰³ The tension of the transfer can be checked by tenodesis of the wrist. With wrist flexion, the thumb should move dorsal to the plane of the palm and with wrist extension the thumb should be able to be placed in full passive abduction and opposition. The patient is even able to use the EIP transfer immediately and extend the thumb on the operating table if the surgery is performed under local anesthesia as “wide-awake” surgery.¹⁰⁴ Postoperatively, the wrist is immobilized in 40° of extension with the thumb in abduction and extension for 3–4 weeks. A removable splint is

used for an additional 3–4 weeks and there is usually no need for retraining (see Fig. 34.34C,D).

Tendon transfers to restore finger extension

Restoration of finger extension after trauma can be accomplished by tendon transfers similar to those used for radial nerve palsy. Those transfers were discussed in detail earlier in this chapter and include transfer of either of the wrist flexors FCU or FCR to the EDC or the Boyes transfer of the FDS of the long and ring fingers to the EDC.

Tendon transfers to restore thumb flexion

Acute lacerations or ruptures of the flexor pollicis longus tendon can be treated by primary or delayed primary repair or tendon grafting. However, with a missed diagnosis, the muscle fibers undergo significant shortening, atrophy, and fibrosis within 6 months to a year from injury. In these situations it is preferable to restore thumb flexion using a tendon




Fig. 34.35 (A) Loss of flexion at the interphalangeal joint of the thumb due to a missed laceration of the flexor pollicis longus (FPL) tendon. (B) The flexor digitorum superficialis of the ring finger is harvested and (C) transferred through the tendon sheath of FPL. (D) Postoperatively the patient demonstrates excellent flexion of the interphalangeal joint and (E) satisfactory extension.




Fig. 34.36 Tendon transfers to restore finger flexion. **(A)** The extensor carpi radialis longus (ECRL) tendon is transected from the base of the index finger metacarpal and transferred subcutaneously around the radial border of the distal forearm. **(B)** The ECRL tendon is sutured to the flexor digitorum profundus (FDP) tendons of the index, long, ring, and small fingers proximal to the carpal tunnel. Correct tensioning of this transfer is absolutely crucial, because ECRL only has 30 mm of amplitude whereas the FDP tendons require 70 mm of excursion for full finger flexion.

transfer, usually the FDS of the ring finger¹⁰⁵ (Fig. 34.35). The ring finger FDS is harvested through a transverse incision at the base of the proximal phalanx and retrieved through a second incision in the proximal palm. It is then passed through the flexor pollicis longus sheath to the base of the distal phalanx through an open incision or attached to a fine rubber catheter or feeding tube and withdrawn distally through the sheath. The ring finger FDS to FPL tendon transfer can be performed in one stage or in two stages if the bed is scarred with initial placement of a Silastic tendon rod.¹⁰⁵ If necessary, a pulley can be reconstructed using the old FPL tendon remnant or with a palmaris longus graft.⁹⁵ The tendon is sutured to the distal phalanx of the thumb using a pullout suture fixed over a button. The tension of the transfer can be checked by wrist tenodesis. With the wrist in full flexion, the thumb should extend completely and with wrist extension the thumb tip should overly the ring finger MCP joint.

Tendon transfers to restore finger flexion

Occasionally patients may present with severe crushing or avulsion injuries involving the forearm flexor muscles. The options for secondary reconstruction of finger flexion are either a tendon transfer of the ECRL to all four FDP tendons

(Fig. 34.36) or a functioning free gracilis muscle transfer. The ECRL is transected at the base of the index finger metacarpal and mobilized through a longitudinal incision on the dorsum of the forearm (Fig. 34.37). It is then tunneled subcutaneously around the radial border of the forearm to a palmar incision over the distal forearm. Great care has to be exercised in adjusting the tension when suturing the ECRL to all four FDP tendons, since the ECRL only has 30 mm amplitude and the FDP tendons require 70 mm of excursion for full finger flexion. Inserting the transfer too tightly will prevent full finger extension. The wrist tenodesis effect is vitally important in this transfer – wrist extension should cause the fingers to flex down to the palm, whereas wrist flexion should allow the fingers to come out to full extension. If the flexor pollicis longus is also non-functioning, thumb flexion can be restored by transferring brachioradialis to FPL through the same palmar incision (see Fig. 34.19B).

Summary

Tendon transfers, if carefully selected and performed meticulously, will provide a gratifying functional improvement to the hand affected by radial, median, ulnar or combined nerve



Fig. 34.37 (A) This boy sustained segmental loss of all the forearm flexor muscles as well as the median nerve and is unable to flex any of his fingers or thumb. (B) The extensor carpi radialis longus (ECRL) tendon is transected and mobilized more proximally. The extensor indicis proprius tendon has been harvested for a simultaneous opposition transfer for the thumb. Brachioradialis was also transferred to flexor pollicis longus to restore flexion of the thumb. (C) Postoperatively, satisfactory finger flexion has been restored by transfer of the ECRL to the flexor digitorum profundus tendons of all four fingers.

palsies, as well as severe trauma affecting the extrinsic flexor and extensor muscles and tendons. Quantitative outcome data is lacking for many of the tendon transfers described, but surgeons and patients can attest to the significant benefits derived from them.

Future directions

Comparative outcome studies must be designed in the future to document the effectiveness of the various tendon transfers

and their ultimate impact on hand function and return to work. It has also been suggested that nerve transfers will usurp the role of tendon transfers in the future and prospective outcome studies will need to be designed to compare the relative outcomes of nerve transfers and tendon transfers.¹⁰⁶



Access the complete reference list online at <http://www.expertconsult.com>

4. Brand PW. *Clinical Mechanics of the Hand*. St. Louis, MO: CV Mosby Co.; 1985. *This is the definitive reference book detailing the biomechanics of the hand.*
17. Boyes J. Tendon transfers for radial palsy. *Bull Hosp Joint Dis*. 1960;21:97–105. *The original description of the Boyes transfer for radial nerve palsy, using the flexor digitorum superficialis tendons from the middle and ring fingers transferred through the interosseous membrane to restore independent index finger and thumb extension.*
30. Bunnell S. Opposition of the thumb. *J Bone Joint Surg*. 1938;20:269–284.
37. Burkhalter W, Christensen RC, Brown P. Extensor indicis proprius opponensplasty. *J Bone Joint Surg Am*. 1973;55:725–732. *The original description of the Burkhalter transfer to restore thumb opposition in a low median nerve palsy using the extensor indicis proprius tendon.*
69. Bunnell S. Surgery of the intrinsic muscles of the hand other than those producing opposition of the thumb. *J Bone Joint Surg*. 1942;24:1–31.
71. Brand PW. Tendon grafting. *J Bone Joint Surg*. 1961;43:444–453. *This paper describes the dorsal route of the extensor carpi radialis brevis tendon extended with free tendon grafts and the palmar route of the extensor carpi radialis longus tendon extended with free tendon grafts to correct the clawing in ulnar nerve palsy due to leprosy.*
74. Blacker GJ, Lister GD, Kleinert HE. The abducted little finger in low ulnar nerve palsy. *J Hand Surg Am*. 1976;1:190–196.
76. Smith RJ. Extensor carpi radialis brevis tendon transfer for thumb adduction – a study of power pinch. *J Hand Surg Am*. 1983;8:4–15.
95. Brand PW. Tendon transfers for median and ulnar nerve paralysis. *Orthop Clin North Am*. 1970;1:447–454.
98. Smith RJ. *Tendon Transfers of the Hand and Forearm*. Boston, MA: Little Brown & Company; 1987. *This classic monograph, unfortunately out of print, is an excellent reference source describing tendon transfers for nerve injuries, trauma, rheumatoid arthritis, congenital anomalies, cerebral palsy, and spinal cord injuries.*

References

- Steindler A. Tendon transplantation in the upper extremity. *Am J Surg*. 1939;44:260.
- Peljovich A, Ratner JA, Marino J. Update of the physiology and biomechanics of tendon transfer surgery. *J Hand Surg Am*. 2010;35:1365–1369.
- Brand PW, Beach RB, Thompson DE. Relative tension and potential excursion of muscles in the forearm and hand. *J Hand Surg Am*. 1981;6:209–219.
- Brand PW. *Clinical Mechanics of the Hand*. St. Louis, MO: CV Mosby Co.; 1985. This is the definitive reference book detailing the biomechanics of the hand.
- Omer G. The technique and timing of tendon transfers. *Orthop Clin North Am*. 1974;5:243–252.
- Burkhalter WE. Early tendon transfer in upper extremity peripheral nerve injury. *Clin Orthop Relat Res*. 1974;104:68–79.
- Ring D, Chin K, Jupiter JB. Radial nerve palsy associated with high-energy humeral shaft fractures. *J Hand Surg Am*. 2004;29:144–147.
- Mayer JH Jr, Mayfield FH. Surgery of the posterior interosseous branch of the radial nerve; analysis of 58 cases. *Surg Gynecol Obstet*. 1947;84:979–982.
- Young C, Hudson A, Richards R. Operative treatment of palsy of the posterior interosseous nerve of the forearm. *J Bone Joint Surg Am*. 1990;72:1215–1219.
- Kallio PK, Vastamaki M, Solonen KA. The results of secondary microsurgical repair of radial nerve in 33 patients. *J Hand Surg [Br]*. 1993;18:320–322.
- Bevin AG. Early tendon transfer for radial nerve transection. *Hand*. 1976;8:134–136.
- Franke F. Sehnenerpflanzung. *Arch Klin Chir*. 1896;52:87.
- Zachary RB. Tendon transplantation for radial paralysis. *Br J Surg*. 1946;34:358–364.
- Starr C. Army experiences with tendon transference. *J Bone Joint Surg Am*. 1922;4:3–21.
- Ratner JA, Peljovich A, Kozin SH. Update on tendon transfers for peripheral nerve injuries. *J Hand Surg Am*. 2010;35:1371–1381.
- Jones NF, Machado GR. Tendon transfers for radial, median, and ulnar nerve injuries: current surgical techniques. *Clin Plast Surg*. 2011;38:621–642.
- Boyes J. Tendon transfers for radial palsy. *Bull Hosp Joint Dis*. 1960;21:97–105. The original description of the Boyes transfer for radial nerve palsy, using the flexor digitorum superficialis tendons from the middle and ring fingers transferred through the interosseous membrane to restore independent index finger and thumb extension.
- Chuinard RG, Boyes JH, Stark HH, et al. Tendon transfers for radial nerve palsy: use of superficialis tendons for digital extension. *J Hand Surg Am*. 1978;3:560–570.
- Tsuge K, Adachi N. Tendon transfer for extensor palsy of forearm. *Hiroshima J Med Sci*. 1969;18:219–232.
- Chandraprakasam T, Gavaskar AS, Prabhakaran T. Modified Jones transfer for radial nerve palsy using a single incision: surgical technique. *Tech Hand Up Extrem Surg*. 2009;13:16–18.
- Thomsen M, Rasmussen KB. Tendon transfers for defective long extensors of the wrist and fingers. *Scand J Plast Reconstr Surg*. 1969;3:71–78.
- Tsuge K. Tendon transfers for radial nerve palsy. *Aust N Z J Surg*. 1980;50:267–272.
- Raskin KB, Wilgis EF. Flexor carpi ulnaris transfer for radial nerve palsy: functional testing of long-term results. *J Hand Surg Am*. 1995;20:737–742.
- Riordan DC. Tendon transplantations in median-nerve and ulnar-nerve paralysis. *J Bone Joint Surg Am*. 1953;35:312–320.
- Ropars M, Dreano T, Siret P, et al. Long-term results of tendon transfers in radial and posterior interosseous nerve paralysis. *J Hand Surg [Br]*. 2006;31:502–506.
- Gousheh J, Arasteh E. Transfer of a single flexor carpi ulnaris tendon for treatment of radial nerve palsy. *J Hand Surg [Br]*. 2006;31:542–546.
- Altintas AA, Altintas MA, Gazyakan E, et al. Long-term results and the Disabilities of the Arm, Shoulder, and Hand score analysis after modified Brooks and D'Aubigne tendon transfer for radial nerve palsy. *J Hand Surg Am*. 2009;34:474–478.
- Fujiwara A, Ryo F, Kashiwagi D, et al. [Evaluation of the Boyes' method in the treatment of radial nerve paralysis]. *Seikei Geka*. 1970;21:954–956.
- Krishnan KG, Schackert G. An analysis of results after selective tendon transfers through the interosseous membrane to provide selective finger and thumb extension in chronic irreparable radial nerve lesions. *J Hand Surg Am*. 2008;33:223–231.
- Bunnell S. Opposition of the thumb. *J Bone Joint Surg*. 1938;20:269–284.
- Royle N. An operation for paralysis of the intrinsic muscles of the thumb. *JAMA*. 1938;111:612–613.
- Thompson TC. A modified operation for opponens paralysis. *J Bone Joint Surg*. 1942;24:632–640.
- Little JW. Tendon transfers and arthrodeses in combined median and ulnar nerve paralysis. *J Bone Joint Surg Am*. 1949;2:225–234.
- Edgerton MT, Brand PW. Restoration of abduction and adduction to the unstable thumb in median and ulnar paralysis. *Plast Reconstr Surg*. 1965;36:150–164.
- Phalen GS, Miller RC. The transfer of wrist extensor muscles to restore or reinforce flexion power of the fingers and opposition of the thumb. *J Bone Joint Surg Am*. 1947;29:993–997.
- Cooney WP, Linscheid RL, An KN. Opposition of the thumb: an anatomic and biomechanical study of tendon transfers. *J Hand Surg Am*. 1984;9:777–786.
- Burkhalter W, Christensen RC, Brown P. Extensor indicis proprius opponensplasty. *J Bone Joint Surg Am*. 1973;55:725–732. The original description of the Burkhalter transfer to restore thumb opposition in a low median nerve palsy using the extensor indicis proprius tendon.
- Camitz H. Über die behandlung der oppositionslähmung. *Acta Chir Scand*. 1929;65:77–81.
- Little JW, Li CS. Primary restoration of thumb opposition with median nerve decompression. *Plast Reconstr Surg*. 1967;39:74–75.
- Braun RM. Palmaris longus tendon transfer for augmentation of the thenar musculature in low median palsy. *J Hand Surg Am*. 1978;3:488–491.
- Foucher G, Malizos C, Sammut D, et al. Primary palmaris longus transfer as an opponensplasty in carpal tunnel release. A series of 73 cases. *J Hand Surg [Br]*. 1991;16:56–60.
- Huber E. Hilfsoperation bei medianus lähmung. *Dtsch Z Chir*. 1921;126:271.
- Nicolaysen J. Transplantation des m. abductor dig. v. bei fehlender oppositionsfähigkeit des daumens. *Dtsch Z Chir*. 1922;168:133–135.
- Cawrse NH, Sammut D. A modification in technique of abductor digiti minimi (Huber) opponensplasty. *J Hand Surg [Br]*. 2003;28:233–237.
- Taylor T. Reconstruction of the hand; a new technique in tenoplasty. *Surg Gynecol Obstet*. 1921;32:237–248.
- Schneider LH. Opponensplasty using the extensor digiti minimi. *J Bone Joint Surg Am*. 1969;51:1297–1302.
- Jensen EG. Restoration of opposition of the thumb. *Hand*. 1978;10:161–167.
- Kirklin JW, Thomas CG Jr. Opponents transplant; an analysis of the methods employed and results obtained in 75 cases. *Surg Gynecol Obstet*. 1948;86:213–223.
- Anderson GA, Lee V, Sundararaj GD. Extensor indicis proprius opponensplasty. *J Hand Surg [Br]*. 1991;16:334–338.
- Schwarz RJ, Macdonald M. Assessment of results of opponensplasty. *J Hand Surg [Br]*. 2003;28:593–596.
- Brandsma JW, Ottenhoff-De Jonge MW. Flexor digitorum superficialis tendon transfer for intrinsic replacement. Long-term results and the effect on donor fingers. *J Hand Surg [Br]*. 1992;17:625–628.

52. Groves R, Goldner J. Restoration of strong opposition after median-nerve or brachial plexus paralysis. *J Bone Joint Surg Am.* 1975;57:112–115.
53. Wood VE, Adams J. Complications of opponensplasty with transfer of extensor carpi ulnaris to extensor pollicis brevis. *J Hand Surg Am.* 1984;9:699–704.
54. Terrono AL, Rose JH, Mulroy J, et al. Camitz palmaris longus abductorplasty for severe thenar atrophy secondary to carpal tunnel syndrome. *J Hand Surg Am.* 1993;18:204–206.
55. Fowler S. Extensor apparatus of the digits. *J Bone Joint Surg.* 1949;31:477.
56. Trevett MC, Tuson C, de Jager LT, et al. The functional results of ulnar nerve repair. Defining the indications for tendon transfer. *J Hand Surg [Br].* 1995;20:444–446.
57. Zancolli EA. Claw-hand caused by paralysis of the intrinsic muscles: a simple surgical procedure for its correction. *J Bone Joint Surg Am.* 1957;1076–1080.
58. Omer GE Jr. Evaluation and reconstruction of the forearm and hand after acute traumatic peripheral nerve injuries. *J Bone Joint Surg Am.* 1968;50:1454–1478.
59. Brown PW. Zancolli capsulorrhaphy for ulnar claw hand. Appraisal of forty-four cases. *J Bone Joint Surg Am.* 1970;52:868–877.
60. Leddy JP, Stark HH, Ashworth CR, et al. Capsulodesis and pulley advancement for the correction of claw-finger deformity. *J Bone Joint Surg Am.* 1972;54:1465–1471.
61. Parkes A. Paralytic claw fingers – a graft tenodesis operation. *Hand.* 1973;5:192–199.
62. Zancolli E. Intrinsic paralysis of the ulnar nerve – physiopathology of the claw hand. In: *Structural and Dynamic Bases of Hand Surgery.* 2nd ed. Philadelphia, PA: JB Lippincott; 1979:159–206.
63. Brooks A, Jones D. A new intrinsic tendon transfer for the paralytic hand. *J Bone Joint Surg.* 1975;57A:730.
64. Anderson G. *Analysis of paralytic claw finger correction using flexor motors into different insertion sites.* MCh Orth Thesis, University of Liverpool; 1988.
65. Burkhalter WE, Strait JL. Metacarpophalangeal flexor replacement for intrinsic-muscle paralysis. *J Bone Joint Surg Am.* 1973;55:1667–1676.
66. Palande DD. Correction of intrinsic-minus hands associated with reversal of the transverse metacarpal arch. *J Bone Joint Surg Am.* 1983;65:514–521.
67. Sapienza A, Green S. Correction of the claw hand. *Hand Clin.* 2012;28:53–66.
68. Stiles HJ, Forrester-Brown MF. *Treatment of Injuries of the Peripheral Spinal Nerves.* London: H. Frowde, Hodder & Stoughton; 1922.
69. Bunnell S. Surgery of the intrinsic muscles of the hand other than those producing opposition of the thumb. *J Bone Joint Surg.* 1942;24:1–31.
70. North ER, Littler JW. Transferring the flexor superficialis tendon: technical considerations in the prevention of proximal interphalangeal joint disability. *J Hand Surg Am.* 1980;5:498–501.
71. Brand PW. Tendon grafting. *J Bone Joint Surg.* 1961;43:444–453. *This paper describes the dorsal route of the extensor carpi radialis brevis tendon extended with free tendon grafts and the palmar route of the extensor carpi radialis longus tendon extended with free tendon grafts to correct the clawing in ulnar nerve palsy due to leprosy.*
72. Enna CD, Riordan DC. The Fowler procedure for correction of the paralytic claw hand. *Plast Reconstr Surg.* 1973;52:352–360.
73. Fritsch E. Nerve involvement in leprosy; the examination of the hand; the restoration of finger function. In: *Reconstructive Surgery in Leprosy.* Bristol, UK: John Wright & Sons; 1971:11–27.
74. Blacker GJ, Lister GD, Kleinert HE. The abducted little finger in low ulnar nerve palsy. *J Hand Surg Am.* 1976;1:190–196.
75. Chung MS, Baek GH, Oh JH, et al. Extensor indicis proprius transfer for the abducted small finger. *J Hand Surg Am.* 2008;33:392–397.
76. Smith RJ. Extensor carpi radialis brevis tendon transfer for thumb adduction – a study of power pinch. *J Hand Surg Am.* 1983;8:4–15.
77. Bunnell S. *Surgery of the Hand.* Philadelphia, PA: JB Lippincott; 1964.
78. Omer GE Jr. Reconstruction of a balanced thumb through tendon transfers. *Clin Orthop Relat Res.* 1985;195:104–116.
79. Brown P. Reconstruction for pinch in ulnar intrinsic palsy. *Orthop Clin North Am.* 1974;5:323–342.
80. Robinson D, Aghasi MK, Halperin N. Restoration of pinch in ulnar nerve palsy by transfer of split extensor digiti minimi and extensor indicis. *J Hand Surg [Br].* 1992;17:622–624.
81. Mannerfelt L. Studies on the hand in ulnar nerve paralysis. A clinical-experimental investigation in normal and anomalous innervation. *Acta Orthop Scand.* 1966;37(suppl87):3–176.
82. Tubiana R. Palliative treatment of paralytic deformities of the thumb. *Orthop Clin North Am.* 1973;4:1141–1160.
83. Tsuge K, Hashizume C. Reconstruction of opposition in the paralyzed thumb. In: *Surgical Rehabilitation in Leprosy.* Baltimore, MD: Williams and Wilkins; 1974:185–199.
84. Bruner JM. Tendon transfer to restore abduction of the index finger using the extensor pollicis brevis. *Plast Reconstr Surg.* 1946;3:197–201.
85. Hirayama T, Atsuta Y, Takemitsu Y. Palmaris longus transfer for replacement of the first dorsal interosseous. *J Hand Surg [Br].* 1986;11:84–86.
86. Graham WC, Riordan D. Sublimis transplant to restore abduction of index finger. *Plast Reconstr Surg.* 1946;2:459–462.
87. Neviasser RJ, Wilson JN, Gardner MM. Abductor pollicis longus transfer for replacement of first dorsal interosseous. *J Hand Surg Am.* 1980;5:53–57.
88. Hastings H 2nd, Davidson S. Tendon transfers for ulnar nerve palsy. Evaluation of results and practical treatment considerations. *Hand Clin.* 1988;4:167–178.
89. Hastings H 2nd, McCollam SM. Flexor digitorum superficialis lasso tendon transfer in isolated ulnar nerve palsy: a functional evaluation. *J Hand Surg Am.* 1994;19:275–280.
90. Ozkan T, Ozer K, Gulgonen A. Three tendon transfer methods in reconstruction of ulnar nerve palsy. *J Hand Surg Am.* 2003;28:35–43.
91. Fischer T, Nagy L, Buechler U. Restoration of pinch grip in ulnar nerve paralysis: extensor carpi radialis longus to adductor pollicis and abductor pollicis longus to first dorsal interosseus tendon transfers. *J Hand Surg [Br].* 2003;28:28–32.
92. Omer GE Jr. Tendon transfers in combined nerve lesions. *Orthop Clin North Am.* 1974;5:377–387.
93. Omer GE Jr. Injuries to nerves of the upper extremity. *J Bone Joint Surg Am.* 1974;56:1615–1624.
94. Eversmann WW Jr. Tendon transfers for combined nerve injuries. *Hand Clin.* 1988;4:187–199.
95. Brand PW. Tendon transfers for median and ulnar nerve paralysis. *Orthop Clin North Am.* 1970;1:447–454.
96. Curtis RM. Opposition of the thumb. *Orthop Clin North Am.* 1974;5:305–321.
97. Williams HW. The leprosy thumb. *Br J Plast Surg.* 1966;19:136–139.
98. Smith RJ. *Tendon Transfers of the Hand and Forearm.* Boston, MA: Little Brown & Company; 1987. *This classic monograph, unfortunately out of print, is an excellent reference source describing tendon transfers for nerve injuries, trauma, rheumatoid arthritis, congenital anomalies, cerebral palsy, and spinal cord injuries.*
99. Christophe K. Rupture of the extensor pollicis longus tendon following Colles fracture. *J Bone Joint Surg Am.* 1953;1003–1005.
100. Duplay S. Rupture sous-cutanée du tendon du long extenseur du pouce de la main droite, au niveau de la tabatière anatomique. Flexion permanente du pouce. Rétablissement de la faculté d'extension par une opération (suture de l'extrémité de tendon rompu avec le premier radial externe). *Bull Mem Soc Chir.* 1876;2:788.
101. Schneider LH, Rosenstein RG. Restoration of extensor pollicis longus function by tendon transfer. *Plast Reconstr Surg.* 1983;71:533–537.

102. Strandell G. Post-traumatic rupture of the extensor pollicis longus tendon – pathogenesis and treatment; survey based on 208 cases, including 14 personal cases. *Acta Chir Scand.* 1955;109:81–96.
103. Low CK, Pereira BP, Chao VT. Optimum tensioning position for extensor indicis to extensor pollicis longus transfer. *Clin Orthop Relat Res.* 2001;388:225–232.
104. Lalonde DH. Wide-awake extensor indicis proprius to extensor pollicis longus tendon transfer. *J Hand Surg Am.* 2014;39:2297–2299.
105. Posner MA. Flexor superficialis tendon transfers to the thumb – an alternative to the free tendon graft for treatment of chronic injuries within the digital sheath. *J Hand Surg Am.* 1983;8:876–881.
106. Giuffre JL, Bishop AT, Spinner RJ, et al. The best of tendon and nerve transfers in the upper extremity. *Plast Reconstr Surg.* 2015;135:617e–630e.

35

Free-functioning muscle transfer in the upper extremity

Pundrique Sharma, Isaac Harvey, and Gregory H. Borschel

 Access video content for this chapter online at expertconsult.com

SYNOPSIS

- Free-functioning muscle transfer involves the transfer of a muscle from a distant location to replace a lost function.
- It is a complex procedure that requires a highly motivated patient.
- The procedure involves microvascular anastomoses and neural coaptation.
- Meticulous attention must be paid to proper positioning and tensioning of the transferred muscle.
- Postoperatively, a highly structured rehabilitation program is required for a prolonged period, often up to 2 years.
- In the appropriate patient, reliably good results can be achieved for patients with otherwise devastating injuries.

Introduction

Key points

- This is a complex procedure for use where no simpler alternative is available.
- Meticulous attention to microsurgical technique is required; thrombosis leads to muscle loss.
- Attention to muscle placement and tensioning is also critical.
- This technique is applicable to restoration of finger, thumb, and wrist flexion and extension, elbow flexion and extension, and shoulder flexion.

Free-functioning muscle transfer involves the microneurovascular transfer of a functioning muscle from its donor site to a recipient site in the upper limb. The aim of the procedure is to restore functionality that has been lost as a result of trauma or other acquired pathology such as sarcoma, or which was never present as in the case of congenital anomalies such as arthrogryposis.^{1,2} It is a complex procedure that was

developed for situations where no simpler alternative is available. Most muscles in the body have been assessed for their usefulness for tissue transfer, and many have been identified as expendable and suitable for microvascular transfer. Most of these muscles have a long pedicle of suitably large caliber. The viability of the muscle is maintained by microvascular anastomosis between the muscle's artery and vein and a suitable artery and vein in the recipient area. Neural coaptation of the transferred muscle's motor nerve to a suitable nerve in the recipient area provides the ability of the muscle to contract, giving functionality to the transfer. This functionality is dependent on viability of the muscle and neural regeneration as well as correct technical placement, positioning, and rehabilitative programs. The common indications for free functional muscle transfer include direct trauma with muscle loss, Volkmann's ischemic contracture, nerve injury such as brachial plexus injuries, and oncologic resection.

Free muscle transfers to the upper limb have been used to reconstruct functional deficits in finger flexion, finger extension, thumb abduction, elbow flexion and extension, and shoulder flexion. Key planning issues include: the choice of appropriate muscle for a given function, the choice of an appropriate local nerve to motor the transferred muscle, and/or creation of such a nerve via nerve grafts.

Although function may be restored, patients must be counseled to be realistic about their expectations of outcome from this type of surgery.



Access the Historical Perspective section online at

<http://www.expertconsult.com>

Basic science/disease process

The basic functional purpose of a muscle is to provide both static tension and functional shortening. To understand its functioning, one must understand the structure of a muscle

Historical perspective

After multiple attempts by numerous authors, Thompson³ was able to demonstrate that non-vascularized muscular transfer was possible. The first functioning muscle transfer was reported in 1970 by Tamai *et al.*,⁴ who transplanted the rectus femoris muscle in dogs. He was able to provide electrophysiological and biomechanical evidence of muscular contraction of the transferred muscle. Since this time, multiple authors have pursued functional muscle transfers throughout the body to replace lost function. Functional muscle transfers have been reported in both the upper and lower limb and also for facial reanimation. In 1973 at the Sixth People's Hospital in Shanghai, microsurgeons successfully transplanted the lateral portion of pectoralis major into the forearm of a patient with Volkmann's ischemic contracture.⁵ This was the first clinical application of free functional muscle transplantation in the upper limb. A good range of finger motion and substantial grip force were reported. In 1976, Ikuta *et al.*⁶ performed experimental work demonstrating the efficacy of free functional muscle transfer. They were also able to demonstrate almost normal histological condition of the transplanted muscle. In the same year, Harii *et al.*⁷ showed that it was possible to transfer muscle to the face for treatment of facial paralysis.




Fig. 35.1 Structure of striated muscle.

(Fig. 35.1). A skeletal muscle is composed of parallel muscle cells called myofibers. Each muscle cell is composed of smaller parallel myofibrils. These myofibrils are further subdivided into thin and thick filaments containing actin and myosin.⁸ Within each muscle cell the myofibrils are arranged within functional compartments known as sarcomeres. These sarcomeres are made up of interdigitating fibers of actin and

myosin that interact at a subcellular level (Fig. 35.2). When a muscle is stimulated to contract, the actin and myosin fibers move over one another by the flexing action of myosin cross-bridges.⁹

The amount of overlap of the actin and myosin fibers determines the number of side chains that are in contact and therefore able to contribute to force generation. When a muscle is overstretched there are fewer side chains in contact. When a muscle is overcontracted the myosin chains crumple and cannot contract further.¹⁰

This relationship leads to a length–tension relationship that provides for maximal force generation when the muscle is at its native physiological length (Fig. 35.3). The total force exerted by a muscle is the sum of the passive force provided by the elastic properties of the muscle fibers and surrounding tissues and the active force produced by the contraction of actin and myosin filaments.⁸ The relationship of length to contractile force generation is described by a bell curve with decreasing ability of force generation further from the physiological resting state corresponding with less overlap of the actin and myosin fibers. For this reason, determination of the resting length of the donor muscle is critical prior to transfer, such that this length can be reconstituted after transfer at inset of the muscle and maximal contractile force can be generated.¹⁰

There are many morphological types of muscle in the body. They can be divided into two major types, strap muscles and pennate muscles, or a combination of the two (Fig. 35.4). In a strap muscle, the muscle fibers are arranged in parallel to the long axis of the muscle. This is important from a functional




Fig. 35.2 Myosin cross-bridges in action. ADP, Adenosine diphosphate; ATP, adenosine triphosphate; P_i , inorganic phosphate.




Fig. 35.3 The length-tension relationship.




Fig. 35.5 In pennate muscle, the muscle fibers are arranged at an angle to a central tendon.




Fig. 35.4 Strap and pennate muscles.

standpoint, as the excursion of a strap muscle is directly proportional to its length. It has been demonstrated that at maximal contraction a strap muscle can contract up to 65% of its resting length.⁸ In a pennate muscle, the muscle fibers are arranged at an angle to a central tendon (Fig. 35.5). As a result, the individual fibers in a pennate muscle usually do not run the entire length of the muscle. The excursion achieved by a pennate muscle is proportional to the length of the muscle fibers, not the length of the entire muscle. As such, a pennate muscle will usually yield lesser excursion than a strap muscle.¹⁰

The pennation angle, or angle of pull of the muscle in relation to the tendon, affects both force generation and excursion. Muscles with a lesser pennation angle (a straighter angle between the fibers and the tendon) produce a greater excursion with contraction but less power than those with a greater pennation angle.

The force generated by a muscle is proportional to its total cross-sectional area. Whether this is due to a greater number of muscle fibers or hypertrophy of a smaller number of fibers, the maximal force generation has been calculated in mammals to be approximately 4 kg/cm².⁸ The cross-sectional area is calculated perpendicular to the direction of the muscle fibers. In a strap muscle this is perpendicular to the muscle as a whole and perpendicular to the tendon. In a pennate muscle this is perpendicular to the fibers and oblique to the tendon and muscle as a whole, resulting in a greater cross-sectional area and thus a greater potential for force generation.

The contraction of an individual muscle fiber is an all-or-none phenomenon: when a weak contraction is required, only a few fibers within the muscle are stimulated to contract.⁹ When a forceful contraction is required, a greater number of muscle fibers are stimulated to contract. Each muscle is innervated by a motor nerve. The motor nerve joins the muscle via its motor endplates at the neuromuscular junction. A given nerve fiber within the nerve will have a defined number of motor endplates, each of these innervating specific fibers within the muscle. A muscle is thus composed of functional motor units, multiple muscle fibers innervated by the same

Table 35.1 Principles of tendon transfer applicable to free-functioning muscle transfer

- An elective tendon/muscle transfer should never be performed in the presence of unhealed wounds
- Full passive joint motion must be restored before tendon/muscle transfer
- The transfer should not pass through areas of scar tissue or under skin grafts. Furthermore, surgical incisions should not be placed directly over the transfer
- Whenever possible, cutaneous sensibility should be restored before tendon/muscle transfer
- The normal function of the transferred muscle must be expendable
- Synergism between the muscle's original and new actions facilitates rehabilitation (in the case of free muscle transfer this principle could be applied to the function of the donor motor nerve)
- The transferred muscle must have sufficient amplitude and power to perform its new function; thus, reinnervated muscles should be used only in exceptional circumstances

(Adapted from Anastakis D, Manktelow R. Free functioning muscle transfers. In: *Green's Operative Hand Surgery*, 5th edn. Philadelphia, PA: Elsevier, 2005.)

nerve fiber. Depending on the muscle, this may be as few as five muscle fibers, such as in the extraocular muscles, or as many as several hundred, as is the case with most major skeletal muscles. This relationship is important in relation to reinnervation and the number of axons provided by a given donor motor nerve. A muscle with smaller muscle units may provide finer control but less power for a given number of axons, and *vice versa* – a muscle with larger motor units requires fewer axons for greater force generation.

Individual muscles considered for transfer have been assessed with regard to their internal architecture, vascular anatomy, motor innervation, and characteristics relevant to desired function. Ideally, the transferred muscle should have a single dominant vascular pedicle (Mathes and Nahai type 1)¹¹ of sufficient length to allow easy anastomosis after transfer without the need for vein grafts. The muscle should possess a single motor nerve of sufficient length and in the correct orientation to allow for primary coaptation of the nerve to the donor motor nerve. The muscle and the limb into which it is to be transferred should possess the appropriate characteristics to allow the muscle to perform its desired function (Table 35.1). These characteristics have been well described for tendon transfers in the upper limb, but apply equally to free functional muscle transfer.

Diagnosis/patient presentation

Free functional muscle transfer is applicable to patients who have sustained a major loss of skeletal muscle in the upper limb resulting in a significant functional disability. Free functional muscle transfer is indicated to replace lost function where no easier local option is available. This may be seen following direct trauma, in the setting of Volkmann's ischemic contracture (Fig. 35.6), following tumor ablation such as sarcoma resection, and in longstanding nerve injury such as brachial plexus lesions. Other rarer indications include



Fig. 35.6 Appearance of arm with Volkmann's ischemic contracture.

electrical burns and post gas gangrene and post-replant patients.¹² Each of these indications presents its own special set of considerations.

Of particular note, in the setting of brachial plexus reconstruction, local donor nerves to power the muscle transfer may be limited or completely unavailable. In this case, careful consideration must be given to the choice of donor motor nerve. In some cases, it is necessary to perform nerve grafts as a preliminary procedure to bring viable motor axons into the denervated limb.^{13,14} A similar picture can be found in the setting of Volkmann's ischemic contracture; however, here the anterior interosseous nerve of the forearm is often spared and can be available as a motor donor nerve.¹⁵ This will be discussed further later in the chapter in the section on choice of donor motor nerve.

Patient selection

Probably the most important decision to be made is whether to proceed with free muscle transfer at all. This is a highly involved surgical procedure that requires a motivated patient who is aware of the potential of the procedure and who is fully equipped and prepared to undertake the oftentimes intensive pre- and postoperative rehabilitation that is required for a successful outcome. The patient must understand that the maximal outcome of the procedure will not be realized inside 1–2 years.¹⁶ The importance of having a cooperative patient cannot be overemphasized. The ideal patient is stable, intelligent, and motivated to regain function and return to work, with no medical comorbidities. Inappropriate candidates are unfortunately common among patients with injuries who might otherwise benefit from this procedure. Head injuries may often accompany brachial plexus injuries in motor vehicle and motorcycle accidents.

Multiple physical factors must be taken into account prior to muscle transfer. The patient must have stable skeletal structure, including functional joints. He or she must have normal or near normal range of motion in the hand, wrist, and elbow. There must be adequate soft-tissue cover over the planned tendon-gliding site. If there is insufficient unscarred soft tissue to cover the planned site, soft-tissue reconstruction in the form of tissue expansion or local flaps may need to be performed prior to muscle transfer. Sensation in the hand should be normal to achieve optimal results, though this is not an absolute requirement.¹² There must be sufficient evidence that there are suitable recipient artery and veins in the arm to vascularize the transferred muscle. Preoperative Doppler ultrasound or angiography can be very helpful in this regard.¹⁰ Also, a suitable donor nerve must be available

Table 35.2 Requirements for free functional muscle transfer

- Available, undamaged motor nerve, artery, and vein at the site of muscle transplantation
- Adequate skin coverage for the distal half of the muscle
- Supple joints and gliding tendons
- Good hand sensibility and intrinsic function
- Adequate antagonist muscle function
- Good patient motivation
- No simpler solution for the patient's problem

(Adapted from Anastakis D, Manktelow R. Free functioning muscle transfers. In: *Green's Operative Hand Surgery*, 5th edn. Philadelphia, PA: Elsevier, 2005.)

to power the transferred muscle. There should be adequate antagonist function in the arm to allow the transfer to be of use, for example in performing a transfer to replace long finger flexor function and restore grip, there must be adequate finger extensor function to oppose the new action of the transferred muscle and to release the grip (Table 35.2).

Multiple muscles have been used for free transfer in the upper limb. The gracilis muscle (see Fig. 35.6) has been the most widely used as it fulfills many of the criteria for the “ideal” muscle transfer.^{17,18} Other transfers have included latissimus dorsi,^{19,20} rectus femoris,^{21,22} serratus anterior,^{23–34} gastrocnemius,²⁶ hemipectus,²⁷ flexor hallucis longus,²⁸ flexor carpi ulnaris,²⁹ pectoralis major,^{30,31} pectoralis minor,²⁴ and tensor fasciae latae.²⁵ As the reconstructive community's comfort with microsurgical transfer has increased over the years, more complex reconstructions have also been successfully attempted. Of particular note, the use of double-free flaps for dual functional reconstruction (such as elbow flexion and extension) has come into more common use. For example, Doi *et al.*³⁵ in 1995 described the use of a staged double free muscle transfer in children following brachial plexus palsy. Simultaneous transfer and neurotization of the adductor longus and gracilis on the same vascular axis has also been described.^{36,37}

The principles governing the choice of muscle for free functional transfer are similar to those that have been well described for tendon transfer. Additionally, the muscle ideally will have a singular dominant vascular pedicle and a single dominant motor nerve available for transfer.

Treatment/surgical technique

Selecting the appropriate muscle for transplantation is key to the success of the procedure. The ideal muscle to transfer will vary depending on which function it is intended to replace. Important considerations are the length, excursion, and power that are required for the given deficit, e.g., finger flexors normally have an excursion of ~7 cm and finger extensors ~5 cm. A transplanted muscle must be able to generate a sufficient force over the appropriate range of motion to be of functional value. The muscle must be expendable from its donor site with minimal functional deficit from its harvest. The muscle ideally should be easy to harvest, and should have a singular dominant vascular pedicle for ease and reliability of microvascular transfer. Ideally, the muscle should have a single easily identifiable motor nerve. Additionally a strong tendon allows for ease of inset with reduced chance of

dehiscence of the muscle insertion. Muscle fibers of uniform length make the procedure technically much easier.

Multiple muscles have been used as functional transfers in the upper limb. For most applications in the upper limb, the gracilis muscle comes closest to satisfying the above criteria.^{10,12} It is a fusiform muscle with longitudinally arranged fibers in the proximal portion. It has a single vascular pedicle easily accessible in the upper thigh with a single motor branch from the obturator nerve. Its functional range of motion can be up to 12–16 cm. The donor scar from the gracilis harvest on the inner thigh often widens but is placed in a relatively inconspicuous location for most patients. An additional advantage of the gracilis muscle is that the nerve is often arranged in 2–3 motor fascicles,^{10,12} which stimulate discrete portions of the muscle. As such, it is possible to use the muscle split into two components for dual functionality with separate motor innervations.^{32,33} A notable disadvantage of the gracilis muscle is the relatively short vascular and neural pedicles.

The gracilis muscle is a long slender strap-like muscle in the adductor compartment of the thigh (Fig. 35.7). It is the most superficial of the adductor muscles. It is thickest in its proximal portions and narrows to a tendon in its distal quarter. The gracilis originates from the body and inferior ramus of the pubis. Distally it narrows into a tendon, which passes behind the femoral condyle and inserts on the medial aspect of the tibia adjacent to the tibial tuberosity. McKee *et al.*³³ studied the muscle fiber anatomy of the gracilis in fresh and preserved cadavers. They described the muscle as fusiform with fibers of varying length. The shorter posterior fibers were found to insert more proximally into the gracilis tendon, whereas the longer more anterior fibers insert more distally. They also found that the fibers were parallel in the proximal three-fifths, whereas distally the fibers converge on to the tendon. The average fiber length within the gracilis muscle is 24 cm. The action of the gracilis is as a weak adductor of the leg and weak flexor of the knee joint. It also produces slight medial rotation of the tibia on the femur. Several authors have reported on harvest of the gracilis, finding that it does not result in a significant functional deficit.

The gracilis muscle may be harvested by a second team concurrent with preparation of the arm. The two-team approach significantly reduces operative time. For gracilis harvest, the markings are made along a line from the posterior aspect of the medial femoral condyle to the pubic tubercle. This line approximates the position of the adductor longus muscle. The gracilis muscle is found 2–4 cm posterior to the palpable margin of the adductor longus. An incision is planned in the upper thigh 2 cm behind the previously marked line. The patient is draped with the entire leg exposed and free-draped in the abducted and externally rotated position (Fig. 35.8). This allows movement of the limb intraoperatively.

An incision 8–10 cm long is made in the junction of the upper and middle third of the thigh. The gracilis muscle is identified beneath the deep fascia (Video 35.1). For the inexperienced operator, it can be useful to extend the knee to aid with identification of the gracilis muscle. The gracilis becomes taut on knee extension; the tension of the other adductors is unaffected. The fascia overlying the gracilis muscle is split longitudinally. This layer is preserved for later repair to prevent muscular herniation, a not uncommon problem if this layer is not repaired. The muscle is dissected proximally




Fig. 35.7 The gracilis muscle.

and distally. The vascular pedicle is found approximately 10–12 cm inferior to the pubis in adults and proportionately the same distance in children (approximately 25% of the length of the thigh), usually entering the muscle from the posterior medial surface. The pedicle courses deep to the adductor longus muscle, which can be retracted to expose the pedicle. Muscular branches are given off to each of the adductors, which need to be divided. The origin of the pedicle is usually from the profunda femoris artery and it can be traced to here with relative ease in most cases. This usually yields a pedicle length of 6–8 cm. The nerve supply to the gracilis is from a branch of the anterior division of the obturator nerve (L2–3). This can be located taking an oblique course in the plane between adductor longus and magnus and entering the posterior medial surface of the muscle 1–3 cm above the vascular pedicle. This is traced superiorly as far as required to obtain sufficient length for transfer. This may be as much as 10 cm.¹⁶ It is preferable to perform the nerve coaptation as close to the transferred muscle as possible, so a shorter nerve is preferable. A tension-free nerve coaptation is necessary; a single nerve coaptation is always preferable over a nerve

graft, so harvest of a longer motor nerve is performed where required. It is necessary to mark the length of the muscle with the leg in full abduction prior to release of either the origin or insertion. 5-0 silk sutures placed at 5-cm intervals will ensure that a correct muscle length–tension relationship is re-established (Fig. 35.9).

If required, it is possible to perform intraneural dissection to identify discrete motor fascicles within the motor nerve that innervate separate portions of the muscle. In 90% of cases it is possible to identify a single fascicle that innervates the anterior 20–50% of the muscle.^{10,31,34} Once these functional muscle subunits have been identified, it is possible to separate and inset them individually to the flexor pollicis longus and flexor digitorum profundus (FDP) tendons to recreate independent function of finger and thumb function.¹⁷

The gracilis is usually harvested as a muscle-only transfer. If it is to be used with a cutaneous paddle, care must be taken in orientation of the skin paddle over the proximal two-thirds of the muscle as the skin paddle becomes unreliable more distally. The operating surgeon must avoid injury to the musculocutaneous perforators, which are almost always



Fig. 35.8 Patient draped for simultaneous gracilis harvest and forearm dissection.



Fig. 35.9 Marking the length of the gracilis muscle with sutures placed 5 cm apart.

located directly over the dominant muscular pedicle. It is useful once the skin paddle has been incised to suture the skin edge to the gracilis fascia to prevent shearing of the musculocutaneous pedicle.

Preparation of the arm is an integral part of the procedure. Prior to embarking on a muscle transfer the surgeon should be satisfied that there is available a suitable vascular pedicle with which to vascularize the transferred muscle. Assessment of the vascularity of the limb should be performed clinically prior to any operation. In equivocal cases, imaging of the vascular system can be of assistance. A preoperative Doppler ultrasound examination or angiogram can be used.¹⁷ However, the final decision to proceed with muscle transfer should be made intraoperatively once a suitable vascular pedicle and donor motor nerve have been identified. The choice of motor nerve is discussed further in the section on choice of donor motor nerve, below.

Incisions should be planned such that they do not cross the path of gliding tendons (Fig. 35.10). Wound closure can often be a problem. In adding the bulk of a transferred muscle and with intraoperative swelling, it is often not possible to close the arm completely. In this case, skin grafts are required to cover the remaining skin defect (Fig. 35.11). This should be planned for with the incisions, so that any areas that require skin grafting are over the more proximal portions of the transferred muscle that undergo less excursion with contraction.

Choice of donor motor nerve

A nerve must be selected that provides motor axons for reinnervation of the transferred muscle. For replacement of long finger flexor musculature, the preferred motor nerves are the anterior interosseous nerve, branches of the median nerve that previously supplied the flexor digitorum superficialis, or



Fig. 35.11 Transferred muscle skin grafted where insufficient coverage is available from local tissue (graft ideally would not be required for distal portions of the muscle).

branches of the ulnar nerve previously supplying the FDP. For reconstruction of the finger and wrist extensors, branches of the radial nerve are used. For biceps reconstruction, branches of the musculocutaneous nerve are used; for the triceps, branches of the proximal radial nerve are used; and finally, for the deltoid, motor branches of the axillary nerve are selected.



Fig. 35.10 Incisions planned to avoid the gliding path of tendons.

Hints and tips

The anterior interosseous nerve may be found arising from the median nerve 3–6 cm distal to the elbow in adults. It courses through the pronator teres and then passes dorsally toward the interosseous membrane, lying next to the flexor digitorum profundus and flexor pollicis longus.

It is important to ensure that an undamaged motor nerve is available for use. This is usually apparent by clinical examination. When uncertainty exists, a preliminary exploration and biopsy of the nerve ends may be used. The biopsy specimen is sent for neurohistology to confirm the presence of motor axons in the resected nerve end. Once the presence of suitable motor nerve is confirmed, the surgeon may proceed with confidence. In the absence of a suitable motor nerve in the upper limb, e.g., in total brachial plexus avulsions, it is possible to perform nerve grafts as a preliminary procedure to introduce a donor source of motor axons into the upper limb. Once a sufficient period of time has elapsed to allow ingrowth of motor axons and there is evidence of regeneration along the nerve, such as a Tinel's sign at the distal end, the surgeon may then proceed with functional muscle transfer.

Muscle transfer to the flexor aspect of the forearm

Muscle transfers to replace long finger flexion are the most common indication for free muscle transfer in the upper limb. It is commonly required following trauma resulting in direct damage to the muscle or from ischemic necrosis following compartment syndrome. Where the extensor compartment remains undamaged, it may be more appropriate to perform a tendon transfer such as extensor carpi radialis longus (ECRL), as this is a less involved procedure with a faster recovery. However, evidence suggests that a free gracilis transfer is able to provide greater excursion and range of movement compared with an ECRL transfer.^{10,12,31}

The forearm must satisfy all the previously mentioned requirements for transfer. If these are satisfied and suitable vessels and nerve are available, transfer may proceed. The gracilis has proven the most useful muscle for this location. The known location of the neurovascular hilum in the donor muscle is matched to the available recipients in the forearm. The length and orientation of the muscle are planned. Incisions are planned to provide good exposure of neurovascular structures and to provide cover of the musculotendinous junction in the distal forearm. As such, it is important that primary skin coverage is provided for the distal half of the muscle transfer. It is possible to harvest the gracilis muscle with a cutaneous pedicle to provide extra skin coverage in the forearm. In the majority of patients, this cutaneous paddle is too thick, resulting in suboptimal cosmetic appearance. Many patients later request revision of this skin paddle. Alternatively, the muscle can be transferred as a muscle-only flap and the proximal half can be skin-grafted. This solves the problem of the bulky skin paddle. The skin graft in the proximal half does not interfere with gliding and excursion of the transfer. If it will not be possible to provide coverage of the distal muscle and musculotendinous junction, it will be necessary



Fig. 35.12 The dissected forearm.

to perform preliminary procedures to provide this. These procedures may include tissue expansion, or local and distant flaps such as groin or abdominal flaps. Once incisions are planned, dissection begins usually from proximal unscarred tissue to distal injured tissue. In dissecting the neurovascular structures, it is important that meticulous technique is used to avoid inadvertent damage to important structures (Fig. 35.12). The medial epicondyle is exposed in anticipation of suturing the proximal end of the transferred muscle. The FDP tendons are explored and checked for their gliding ability.

Hints and tips

Placing a small bean bag or gel roll under the ipsilateral hip permits greater exposure. A headlight is valuable for visualization. The incision must be carried quite proximally in order to visualize the neurovascular bundle adequately. There are usually two veins surrounding a single artery. A small set of perforating vessels may be seen entering the skin at the same level as the vascular pedicle deep to the muscle. A malleable retractor placed deep (posterior) to the pedicle assists in its dissection.

Once the forearm is dissected the muscle may be transferred. The neurovascular structures are aligned and the nerve positioned to allow nerve coaptation as close to the muscle as possible (Fig. 35.13). While the proximal portion is held to the medial condyle, the distal portion of the muscle is stretched to simulate finger flexion and extension. The neurovascular pedicle is observed during this movement to ensure that no tension will be placed on the repair during finger movement. Tacking sutures are then placed in the muscle to hold it to the forearm and prevent contraction during neurovascular repair. Microvascular repair is then performed under the operating microscope. Once vascular flow is re-established, the muscle is observed for bleeding from cut ends and the re-establishment of a "pink color". The

distal portions of the muscle will typically take some minutes to regain their color. Any area that fails to appear adequately revascularized can be excised. This does not present a problem as the tendon of the gracilis extends intramuscularly for some way and the cut ends of resected muscle fibers can be rejoined to the intramuscular portion of the tendon without affecting function. The neural repair is performed as a fascicular repair using 10-0 or 11-0 suture, as the nerve to gracilis contains approximately 60% fatty connective tissue. This ensures proper alignment of the fascicles.

When a single muscle is to be used to provide flexion to all of the fingers, they should be positioned such that they flex together, giving simultaneous contact with the object being gripped. A side-to-side tenodesis of the FDP tendons is performed distally in this position with each finger slightly more flexed than the previous. This provides a balanced mass flexion effect of all the fingers together (Fig. 35.14). Where FDP is to be included with a single muscle function, it should be positioned such that the thumb closes slightly later than the fingers. This results in a useful pinch grip for the patient. Alternatively, the muscle may be separated into its functional components to provide separate finger and thumb flexion.



Fig. 35.13 Neurovascular structures aligned.



Fig. 35.14 Flexor tendons sutured to provide mass flexion effect.

Hints and tips

Most side-to-side tenodeses between adjacent distal tendons can be readily performed with mattress 3-0 or 4-0 polyester sutures. A tendon weaver is not generally needed.

The muscle is inserted into the FDP tendons in such a way as to recreate its optimal functional length and excursion. Prior to transfer, the gracilis is placed on maximal physiological stretch by placing the thigh in maximal abduction. Sutures are then placed in the muscle every 5 cm. Once the muscle is transferred, the origin is fixed to the common flexor origin from the medial epicondyle. The wrist and fingers are then placed in maximal extension. The gracilis is then stretched distally to recreate the 5-cm distance between marking sutures ([Fig. 35.15](#)). The intersection of the FDP and gracilis muscle and tendons is then marked. The hand is then relaxed and a tendon weave is performed under no tension at the premarked site. This technique ensures that, once the procedure is completed, the transfer will allow a full range of finger and wrist extension and will allow finger flexion within the maximal force-generating range of the muscle. The

principles of this technique are applicable to muscle transfers in all locations.

The limb is rested with the wrist and fingers slightly flexed so as to relieve any tension on the musculotendinous junction. Postoperatively at the 3-week mark, a program of passive mobilization and stretching is instituted. This helps prevent any myoclonic contracture and promotes gliding at the musculotendinous junction. Once the muscle regains innervation it is very important to institute an active mobilization program. Once a functional range of motion is regained, a graduated weight-training program can be instituted to improve strength. This should be pursued for at least 1 year following regaining a useful range of motion. This should be incorporated into the patient's work and activities of daily living to maintain patient interest and participation.

In the correct patient, good flexion ([Fig. 35.16](#)) can be expected including, where planned, independent finger and thumb flexion ([Fig. 35.17](#)).

Muscle transfer for finger extension

Muscle transfer for finger extension follows the same basic pattern as for finger flexion, although a marginally lesser degree of excursion is required. The gracilis muscle has also been used most widely for this application. The choice of motor nerve for reinnervation is crucial. The posterior interosseous nerve has been used most commonly. The most appropriate site for identification and use of the nerve is as it emerges from supinator. At this point, it is possible to identify the branches innervating finger, thumb, and wrist extensors. The ideal branches to use are those to the finger extensors;

wrist extensor branches are less ideal. Identification of the nerve at this level is particularly useful if there are remnants of extensor motor function. In this case the nerve branches can be individually stimulated to select the appropriate branch or branches. The arterial anastomosis may be to any available artery. The posterior interosseous artery has been used, although this may be scarred or insufficient. In this case, the radial artery has been used in an end-to-side fashion, or the radial recurrent artery may be used. Similar attention as with the flexor reconstruction must be paid to achieving an appropriate physiological length. The distal extensors are joined together with a side-to-side tenodesis with the fingers in a



Fig. 35.15 Muscle *in situ* with recreation of original resting tension.

normal cascade. After proximal fixation of the muscle and establishment of vascularity, the wrist and fingers are maximally flexed. The muscle is stretched to recreate the 5-cm distance between marking sutures. The distal insertion is marked after attachment of the muscle has been performed. This allows fixation of the muscle at its maximal physiological length. Postoperatively, the wrist is splinted in neutral with the digits in the safe position. This relieves tension on the

muscle during the initial healing period. A mobilization program similar to that used with flexor reconstructions is initiated.

Muscle transfers for elbow flexion (biceps reconstruction)

The loss of elbow flexion can be a devastating injury. Fortunately both the biceps and brachialis can accomplish this function in the absence of the other. Loss of both these muscles is rare. Loss of innervation of these muscles is, however, much more common in the setting of brachial plexus injuries. Many authors have reported on the use of free functional muscle for reconstruction of elbow flexion in this setting.^{16,18} The principles are the same as for the previously described transfers. The acromion and bicipital aponeurosis are exposed for attachment of the transferred muscle. End-to-side vascular anastomosis to the brachial artery is performed and, if available, the musculocutaneous nerve is used for neural coaptation. The choice of nerve in brachial plexus cases may be more difficult and is based on preoperative examination and intraoperative findings. In this case, donor nerves can be intercostal nerves (ideally three nerves), motor fascicles of the ulnar or median nerves, or occasionally the spinal accessory or thoracodorsal nerve. Similar attention to length and tension of inset must be paid as previously described.

Transfers have been described for elbow extension, shoulder flexion, and thumb opposition, in which similar principles are applied.

Complications

Complications can be divided into early or late. As the procedure is long and complicated, care must be taken during the



Fig. 35.16 (A–C) Postoperative patient demonstrating good finger flexion.



Fig. 35.17 (A–D) Postoperative patient demonstrating independent finger and thumb flexion after separation of gracilis into independent functional units.

intraoperative period to protect the patient with particular attention to care of pressure areas and appropriate use of thromboprophylaxis. The most feared early complication is vascular insufficiency of the transferred muscle. After a period of 4–5 h sufficient ischemic damage is sustained by the muscle as to make salvage impossible. In this circumstance, a new free muscle transfer is required. Though not a common complication, this is unfortunately more common than detecting the vascular compromise in time to salvage the muscle. Vascular insufficiency may be due to thrombosis or technical problems with the anastomosis such as kinking or external pressure. Infection is also a risk, as the procedure is often performed through a heavily scarred bed and involves open wounds for a prolonged period. The routine use of pre- and intraoperative antibiotics is necessary. Delayed wound healing is a not uncommon complication but should not delay a rehabilitative program.

Late complications include inadequate power and adhesions. Insufficient power can be due to insufficient motor reinnervation either from an insufficient nerve or problems with the neural coaptation. In the setting of adhesions, a tenolysis may be required to allow improved function. If this is to be done, it is wise to wait for complete reinnervation of the muscle so that an aggressive postoperative mobilization program can be instituted. Wrist flexion contractures have been noted as a late complication after transfers for finger flexion. As the transferred muscle regains power, it may overpower the extensors, resulting in a flexion deformity. This can be overcome by early splinting programs but, even with appropriate treatment, further serial casting or surgical procedures may be required.

Secondary procedures

Unfortunately, some patients will not regain function following transfer. This can be due to technical problems, loss of the muscle due to ischemia, failure to reinnervate the muscle, tendinous adhesions, or co-contraction of antagonist muscles. In each case, a reason must be sought individually to explain the poor outcome. In the case of tendinous adhesions, a simple tenolysis may be sufficient. Inadequate or excessive tension on the muscle may result in a functioning muscle with incomplete or weak range of motion. In these cases, it may be possible to reposition the musculotendinous junction, or to perform repositioning of the muscular origin from the common flexor origin. These are both difficult procedures and are best addressed by attaining the correct tension at the primary procedure. In the case of muscle loss or failure of reinnervation, where a reason for the failure can be addressed, it is reasonable to perform a second free-functioning transfer with the expectation of a good functional result.

Future directions

Future developments in free muscle transfer are likely to involve techniques to improve neural regeneration, as it is known that the number of motor nerve units that grow across a nerve repair site affect the functional outcome.³⁸ Potentially exciting new avenues to improve neural regeneration include nerve cross-bridging,^{39,40} in which nerve grafts from a healthy nerve are coapted to a regenerating nerve and the use of a 1-h period of electrical stimulation at the time of neurography.⁴¹



Access the complete reference list online at

<http://www.expertconsult.com>

4. Tamai S, Komatsu S, Sakamoto A, et al. Free-muscle transplants in dogs with microsurgical neurovascular anastomoses. *Plast Reconstr Surg.* 1970;46:219–225. This paper represents the pioneering work on free functional muscle transplantation. Rectus femoris muscles were microvascularly transplanted and analyzed with light and electron microscopy and electromyography. The authors demonstrated viable muscles with normal thresholds for stimulation by 3 months postoperatively.

7. Harii K, Ohmori K, Torii S. Free gracilis muscle transplantation with microneurovascular anastomoses for the treatment of facial paralysis. *Plast Reconstr Surg.* 1976;57:133–143. This is the original description of gracilis transfer as applied to facial nerve palsy, and includes the authors' technique and two case reports.

17. Zuker RM, Manktelow RT. Functioning free muscle transfers. *Hand Clin.* 2007;23:57–72. This is an excellent review of the current status of

- functioning muscle transfer from a highly respected unit covering both their adult and pediatric experience.*
31. Manktelow RT, Zuker RM. Muscle transplantation by fascicular territory. *Plast Reconstr Surg.* 1984;73:751–755. *The authors describe the fascicular functional anatomy of the gracilis muscle and the ability to separate the functioning muscle into its component parts. A single case report is presented.*
 33. McKee NH, Fish JS, Manktelow RT, et al. Gracilis muscle anatomy as related to function of a free functioning muscle transplant. *Clin Anat.* 1990;30:87–92. *This is an excellent description of the anatomy of the gracilis muscle in relation to its use as a functional transplant.*

References

- Kay S, Pinder R, Wiper J, et al. Microvascular free functioning gracilis transfer with nerve transfer to establish elbow flexion. *J Plast Reconstr Aesthet Surg*. 2010;63:1142–1149.
- Doi K, Arakawa Y, Hattori Y, et al. Restoration of elbow flexion with functioning free muscle transfer in arthrogryposis: a report of two cases. *J Bone Joint Surg Am*. 2011;93:e105.
- Thompson N. Autogenous free grafts of skeletal muscle. A preliminary experimental and clinical study. *Plast Reconstr Surg*. 1971;48:11–27.
- Tamai S, Komatsu S, Sakamoto A, et al. Free-muscle transplants in dogs with microsurgical neurovascular anastomoses. *Plast Reconstr Surg*. 1970;46:219–225. *This paper represents the pioneering work on free functional muscle transplantation. Rectus femoris muscles were microvascularly transplanted and analyzed with light and electron microscopy and electromyography. The authors demonstrated viable muscles with normal thresholds for stimulation by 3 months postoperatively.*
- Sixth People's Hospital, Microvascular Service, Shanghai. Free muscle transplantation by microsurgical neurovascular anastomoses. *Clin Med J*. 1976;2:47.
- Ikuta Y, Kubo T, Tsuge K. Free muscle transplantation by microsurgical technique to treat severe Volkmann's contracture. *Plast Reconstr Surg*. 1976;58:407–411.
- Hariri K, Ohmori K, Torii S. Free gracilis muscle transplantation with microneurovascular anastomoses for the treatment of facial paralysis. *Plast Reconstr Surg*. 1976;57:133–143. *This is the original description of gracilis transfer as applied to facial nerve palsy, and includes the authors' technique and two case reports.*
- Carlson FD, Wilkie DR. *Muscle Physiology*. Englewood Cliffs, NJ: Prentice-Hall; 1974.
- Barrett KE, Barman SM, Boitano S, et al. *Brooks Ganong's Review of Medical Physiology*. 23rd ed. New York, NY: McGraw-Hill; 2009.
- Anastakis D, Manktelow R. Free functioning muscle transfers. In: *Green's Operative Hand Surgery*. 5th ed. Philadelphia, PA: Elsevier; 2005.
- Mathes SJ, Nahai F. Classification of the vascular anatomy of muscles: experiments and clinical correlation. *Plast Reconstr Surg*. 1981;67:177–187.
- Manktelow RT, Zuker RM, McKee NH. Functioning free muscle transplantation. *J Hand Surg Am*. 1984;9A:32–39.
- Doi K, Muramatsu K, Hattori Y, et al. Restoration of prehension with the double free muscle technique following complete avulsion of the brachial plexus. Indications and long-term results. *J Bone Joint Surg Am*. 2000;82:652–666.
- Baliarsing AS, Doi K, Hattori Y. Bilateral elbow flexion reconstruction with functioning free muscle transfer for obstetric brachial plexus palsy. *J Hand Surg [Br]*. 2002;27:484–486.
- Zuker RM. Volkmann's ischemic contracture. *Clin Plast Surg*. 1989;16:537–545.
- Kay S, Pinder R, Wiper J, et al. Microvascular free functioning gracilis transfer with nerve transfer to establish elbow flexion. *JPRAS*. 2010;63:1142–1149.
- Zuker RM, Manktelow RT. Functioning free muscle transfers. *Hand Clin*. 2007;23:57–72. *This is an excellent review of the current status of functioning muscle transfer from a highly respected unit covering both their adult and pediatric experience.*
- Barrie KA, Steinmann SP, Shin AY, et al. Gracilis free muscle transfer for restoration of function after complete brachial plexus avulsion. *Neurosurg Focus*. 2004;16:E8.
- Tobin GR, Shusterman M, Peterson GH, et al. The intra-muscular neurovascular anatomy of the latissimus dorsi muscle: the basis for splitting the flap. *Plast Reconstr Surg*. 1981;67:637–641.
- Favero KJ, Wood MB, Meland NB. Transfer of innervated latissimus dorsi free musculocutaneous flap for the restoration of finger flexion. *J Hand Surg Am*. 1993;18:535–540.
- Yang D, Morris S, Tang M, et al. A modified longitudinally split segmental rectus femoris muscle flap transfer for facial reanimation: anatomic basis and clinical applications. *JPRAS*. 2006;59:807–814.
- Yang D, Morris SF. Neurovascular anatomy of the rectus femoris muscle related to functioning muscle transfer. *Plast Reconstr Surg*. 1999;104:102–106.
- Whitney TM, Buncke HJ, Alpert BS, et al. The serratus anterior free muscle flap: experience with 100 consecutive cases. *Plast Reconstr Surg*. 1990;86:481–490.
- Terzis J, Manktelow R. Pectoralis minor: a new concept in facial reanimation. *Plast Surg Forum*. 1982;5:106.
- Kobayashi MR, Brenner KA, Gupta R, et al. Functional biceps brachii reconstruction using the free tensor fasciae latae. *Plast Reconstr Surg*. 2004;114:1208–1214.
- Liu XY, Ge BF, Win YM, et al. Free medial gastrocnemius myocutaneous flap transfer with neurovascular anastomosis to treat Volkmann's contracture of the forearm. *Br J Plast Surg*. 1992;45:6–8.
- Chuang D, Chen H, Wei FC, et al. Compound functioning free muscle flap transplantation (lateral half of soleus fibula and skin flap). *Plast Reconstr Surg*. 1992;89:335–339.
- Schoeller T, Wechselberger G, Meirer R, et al. Functional osteomuscular free-tissue transfer: the reinnervated fibula-flexor hallucis longus free flap. *Plast Reconstr Surg*. 2002;109:253–257.
- Lim A, Kumar V, Sebatin S, et al. Split flexor carpi ulnaris transfer: a new functioning free muscle transfer with independent dual function. *Plast Reconstr Surg*. 2006;117:1927–1932.
- Manktelow RT, McKee NH, Vettese T. An anatomical study of the pectoralis major muscle as related to functioning free muscle transplantation. *Plast Reconstr Surg*. 1980;65:610.
- Manktelow RT, Zuker RM. Muscle transplantation by fascicular territory. *Plast Reconstr Surg*. 1984;73:751–755. *The authors describe the fascicular functional anatomy of the gracilis muscle and the ability to separate the functioning muscle into its component parts. A single case report is presented.*
- Hariri K. Muscle transplantation by fascicular territory (discussion). *Plast Reconstr Surg*. 1984;73:756.
- McKee NH, Fish JS, Manktelow RT, et al. Gracilis muscle anatomy as related to function of a free functioning muscle transplant. *Clin Anat*. 1990;30:87–92. *This is an excellent description of the anatomy of the gracilis muscle in relation to its use as a functional transplant.*
- Lifchez SD, Sanger JR, Godat DM, et al. The serratus anterior subslip: anatomy and implications for facial and hand reanimation. *Plast Reconstr Surg*. 2004;114:1068.
- Doi K, Sakai K, Kuwata N, et al. Double free-muscle transfer to restore prehension following complete brachial plexus avulsion. *J Hand Surg Am*. 1995;20:408–414.
- Chuang DC, Strauch RJ, Wei FC. Technical considerations in two-stage functioning free muscle transplantation reconstruction of both flexor and extensor functions of the forearm. *Microsurgery*. 1994;15:338–343.
- Sananpanich K, Tu YK, Pookhang S, et al. Anatomic variance in common vascular pedicle of the gracilis and adductor longus muscles: feasibility of double functioning free muscle transplantation with single pedicle anastomosis. *J Reconstr Microsurg*. 2008;24:231–238.
- Snyder-Warwick AK, Fattah AY, Zive L, et al. The degree of facial movement following microvascular muscle transfer in pediatric facial reanimation depends on donor motor nerve axonal density. *Plast Reconstr Surg*. 2015;135:370e–381e.
- Gordon T, Hendry M, Lafontaine CA, et al. Nerve cross-bridging to enhance nerve regeneration in a rat model of delayed nerve repair. *PLoS ONE*. 2015;10:e0127397.
- Gordon T, Eva P, Borschel GH. Delayed peripheral nerve repair: methods, including surgical "cross-bridging" to promote nerve regeneration. *Neural Regen Res*. 2015;10:1540–1544.
- Willand MP, Nguyen MA, Borschel GH, et al. Electrical stimulation to promote peripheral nerve regeneration. *Neurorehabil Neural Repair*. 2016;30:490–496.

36

Brachial plexus injuries: Adult and pediatric

David Chwei-Chin Chuang

 Access video content for this chapter online at expertconsult.com

SYNOPSIS

- Complexity of brachial plexus injury (BPI): BPI is characterized by many complex problems and remains a dilemma to many reconstructive microsurgeons. These complexities include: (1) diverse injury patterns; (2) disrupted anatomy; (3) unpredictable nerve degeneration and regeneration; (4) difficult physical examination and diagnosis; (5) challenging nerve surgery; (6) long rehabilitation; (7) different palliative surgeries for sequelae deformity; (8) no consensus of outcome evaluation; and (9) difficult pain management. Many reconstructive microsurgeons show great interest but are greatly frustrated by this field.
- BPI can occur in adults and children. Although the anatomy is the same, there are many differences. Therefore, these two different entities will be discussed separately.

Introduction

Clinical tips

There are significant differences between adult brachial plexus injury and obstetric brachial plexus palsy (or neonatal brachial plexus palsy). The diagnosis and treatment of these different entities should be considered separately.

BPI can occur in adults and children. Although the anatomy is the same, there are many differences, including mechanism of injury, type and degree of injury, preoperative evaluation and diagnosis, surgical options, postoperative management and rehabilitation, palliative surgery for sequelae deformities, outcomes evaluation and pain management ([Table 36.1](#)).

Over 1900 adult and 500 pediatric brachial plexus palsy patients have been treated by the author since 1985. The following text will deal with the author's experience regarding adult and pediatric BPI.

Adult brachial plexus injury

Introduction

Clinical tips

For adult brachial plexus injury, there is debate between early (within 1 month) and delayed early (within 3–5 months after injury) nerve exploration. The latter is becoming more popular. Clinical evaluation is the most essential step for preoperative and postoperative judgment. Imaging studies can help the diagnosis, especially for level I (root) injury. Predicting the level of the lesion can help avoid unnecessarily long incision and dissection.

Adult brachial plexus injury (BPI) is characterized by many complex problems, and remains a dilemma to many reconstructive microsurgeons. These complexities include: (1) complexity of anatomy; (2) level of BPI; (3) diverse injury patterns; (3) unpredictable nerve degeneration and regeneration; (4) difficult physical examination and diagnosis; (5) challenging nerve surgery; (6) long rehabilitation and follow-up; (7) different palliative surgeries for sequelae deformity; (8) no consensus of outcome evaluation; and (9) difficult pain management. Many reconstructive microsurgeons show great interest but are greatly frustrated by this field.

Anatomy

Gross anatomy

The brachial plexus is a large plexus, which has the most complex structures in the peripheral nerve system. It is located superficially between two highly mobile structures, the neck and arm, causing its susceptibility to sustain injury, especially traction injury.

Table 36.1 Differences between adult and pediatric brachial plexus injury

Adult brachial plexus injury		Obstetric brachial plexus palsy
Popular terminology	BPI	Two types: (1) infantile OBPP (I-OBPP; also called neonatal brachial plexus palsy, NBPP) and (2) child OBPP with deformity
Etiology (mechanism)	Trauma, more closed injuries than open Majority caused by traction injury, mostly by motorcycle accident	All are closed and traction injuries following delivery
Demography	All ages	All are infants and children
Incidence	Increasing	Reducing (improvement in obstetric care)
Physical examination	Complex	Simple
Horner's syndrome	Reliable and persistent	Not reliable, not persistent
Spontaneous recovery	Less	Many
Classification of Injury	Four levels of injury: Level I: inside the bone Level II: inside the muscle Level III: pre- and retroclavicular Level IV: infraclavicular	All are level I–III injuries, very rare in level IV Five types of injury: Type 1: upper plexus palsy (Erb's palsy) Type 2: extended Erb's palsy Type 3: entire plexus without Horner's syndrome Type 4: entire plexus with Horner's syndrome Type 5: lower plexus palsy, Klumpke palsy
Intraoperative findings		
Patterns	More in root injury (level I)	Upper plexus tend to be rupture injury; lower plexus tends to be avulsion injury In operated cases, type 3 or 4 more common; in non-operated cases, type I or 2 more common
Dissection 3 months after injury	Difficult, more hazardous to dissect and expose the lower plexus	Highly possible to expose the whole spinal nerves
Vessel injury	Segmental occlusion of the subclavian artery in level I, and axillary artery in level IV are common	Rarely associated with vascular damage
Degree of nerve injury	In rupture injury, the gap is always more than 5 cm	The gap is short (2–4 cm); high incidence of aberrant reinnervation with co-contraction following nerve repair or spontaneous regeneration
Platysma muscle	Varies in thickness	Very thin or scarce
Surgical techniques		
Priority	Elbow flexion, shoulder abduction and rotation, hand sensation and finger flexion, then elbow and finger extension	Hand and shoulder function, elbow flexion
Nerve reconstruction	Nerve transfers more than nerve grafts	Nerve grafts more than nerve transfers
Phrenic nerve transfer	A strong neurotizer, often utilized	Rarely applied, risk for severe respiratory distress
Distal nerve transfers	Often	Less required
Contralateral C7 transfer	Often applied in total root avulsion	Rare
Postoperative		
Postoperative immobilization	3 weeks	4 weeks
Rehabilitation	Good and cooperative	Poor cooperation
Prognosis		
Recovery after repair	More expected, e.g., nerve grafts in level II rupture injury, time to achieve elbow flexion >M3, usually takes 1 year	Slow and unpredictable, e.g., nerve grafts in rupture injury, time to achieve elbow flexion usually takes 2 years
Intercostal nerve transfer	Fair result	Better result
C8 and T1 root injury	Recovery, all or none	Usually incomplete, (some T1 function is spared)
Intrinsic recovery following repair	Never	May happen
Backup (second) procedure to improve results	Less frequent (less than 10%)	More often (>50%)
Pain management	Big issue	Little problem

The brachial plexus is formed by the anterior primary rami of the lower cervical (C5–8) and the first thoracic (T1) spinal nerves, which give motor innervation to muscles of the shoulder, including all anterior and posterior chest muscles related to glenohumeral joint movement, muscles of the entire upper limb, and sensory innervation of the entire upper limb except the skin on some part of the medial aspect of the upper arm (T2 zone). Not infrequently, the C4 and T2 spinal nerve also contribute nerve fibers to it. Whenever the C4 contribution is large and the T1 contribution is small, the brachial plexus is called the “prefixed brachial plexus”. When the C5 contribution is small and T2 contribution is large, it is termed the “postfixed brachial plexus”. Clinically, the prefixed type is more common than the postfixed. But postfixed plexus in adult BPI has been rarely seen, probably because the injuries are either so extensive that further dissection of C8–T1 is hazardous and unnecessary, or the injuries are diagnosed not to involve C8–T1, so that further identification is also unnecessary. Each spinal nerve is formed by the joining of the ventral root (motor fibers) and the dorsal root (sensory fibers). Each root is formed by a number of rootlets, which exit from each spinal cord. These separate rootlets can be defined on magnetic resonance imaging (MRI) with three or four bands in the upper cervical roots (C5–7) and two bands of rootlets in the lower roots (C8–T1). The dorsal roots carry sensory information to the central nervous system, while the ventral roots convey motor fibers to the muscles. The cell bodies (neurons) of the motor fibers are located in the anterior horn of the spinal cord, while the cell bodies of the sensory fibers reside in the dorsal root ganglion located within the intervertebral foramen, immediately outside the dura mater of the spinal cord. The ventral and dorsal roots carry with them an extension of the arachnoid and dura, which forms the root sleeve, where the root sleeve attaches to the ventral root and ganglion to form the sheath of the spinal nerve so that the cerebrospinal fluid space does not extend beyond the intervertebral foramen.

The dorsal and ventral roots unite a few millimeters distal from the ganglion to form a spinal nerve, a mixed nerve, which goes through the interscalene space between the scalene anterior and middle muscles. Nerves arising from the anterior primary ramus include branch to scalene muscles (C5–8), branch to longus colli muscle (C5–8), the long thoracic nerve (C5–7), a portion of phrenic nerve (C5), and a portion of the dorsal scapular nerve (C5).

Just out of the scalene muscles, the five postganglionic spinal nerves make a first union to form the three trunks: upper (formed by C5 and C6), middle (C7 itself), and lower trunk (formed by C8 and T1 spinal nerves). Two branches are given off from the upper trunk: the nerve to the subclavius muscle and the suprascapular nerve. Each trunk divides into anterior and posterior divisions just proximal to or directly under the clavicle, i.e., retroclavicular. Lateral pectoral nerve is formed from anterior divisions of the upper and middle trunk to innervate the clavicular part of pectoralis major muscle; medial pectoral nerve is formed from the anterior division of the lower trunk to innervate the sternal part of the pectoralis major muscle.

Infraclavicularly, the nerves exchange fibers and form the second union, just distal to the clavicle, and are termed “cords”. The lateral cord is formed by the fusion of the two anterior divisions of the upper and middle trunks, containing

fibers derives from the C5 through C7. The posterior cord is a joining of all three posterior divisions, containing fibers derived from the C5 through C8. The medial cord is simply continuation of the anterior division of the lower trunk, containing fibers from the C8 and T1. Subclavian artery becomes axillary artery at lateral border of the first rib. Names for cord relationship are based on the axillary artery. Lateral and medial cords pass anterior, and the posterior cord passes posterior to the axillary artery. The cords run anterior to the subscapularis muscle, just distally behind the pectoralis minor muscle. Each cord has two or more terminal branches to the periphery. The medial and lateral cords, giving one or two terminal branches, join in a Y-shape to form the median nerve. Other main terminal branches of the cords contain the musculocutaneous nerve from the lateral cord, the ulnar nerve from the medial cord, the axillary and radial nerve from the posterior cord.

Numerous anatomical variations of the brachial plexus do exist^{1–3} and should be always kept in mind. For example, the musculocutaneous nerve may sometimes arise from the median nerve and not from the lateral cord. In some rare cases of C5–6 root avulsion, the musculocutaneous nerve is still found to be functional because part of the musculocutaneous nerve derives from the median nerve with its origins from C7.

Microanatomy


The microanatomy or internal topography of the brachial plexus has been extensively studied and described.^{2,3} The monofascicular pattern is usually found in regions of: (1) the spinal nerves; (2) anterior and posterior divisions of the upper trunk; and (3) the origin of the suprascapular and musculocutaneous nerve. Marked changes in fascicular topography occur every 10 mm. It is especially true at the level of the upper trunk where interfascicular crossovers are so extensive that direct repair or repair with short nerve grafts will frequently lead to co-contractions due to aberrant regeneration of a group of muscles. This aberrant regeneration is mainly found in obstetric brachial plexus palsy (OBPP) patients but rarely in adult BPI. In addition, plexus connective tissue is more abundant than neural tissue. All these factors are reasons why the results of brachial plexus nerve surgery are so unpredictable. Knowledge of the internal topography of the plexus can be helpful in connecting corresponding nerve fibers with bridging nerve grafts. However, localization within the spinal nerve to define specific axonal groups to supply specific muscles or specific branches is difficult and not practical.

Level of brachial plexus injury


Various classifications of the level of BPI have been proposed^{1, 4–12} (Table 36.2), e.g., two levels as supraclavicular and infraclavicular⁴; three levels as supra-, retro-, and infraclavicular;^{5,6} four levels as preganglionic root, postganglionic root, trunk and division, cord and terminal branches.^{7–8} These numerous classifications have made the understanding of the anatomy of the brachial plexus complex and confusing. The most confusing aspect is the so-called postganglionic root (Fig. 36.1). In fact, after the dorsal root ganglion, both ventral and dorsal roots continue for only a few millimeters (<5 mm) in distance and unite to become a mixed nerve where it is no longer a root. Sunderland¹³ has stated that “the term nerve

Table 36.2 Classifications for level of brachial plexus injury

Authors	Levels	Area of injury
Leffert ¹	2 levels	Supraclavicular injury (supraganglionic, infraganglionic, and sub- or retroclavicular) and infraclavicular injury
Krakauer and Wood ⁴	2 levels	Supraclavicular (roots, trunks and divisions), infraclavicular (cords and branches)
Terzis <i>et al.</i> ⁵	3 levels	Root, supraclavicular postganglionic, infraclavicular
Ferrante ⁶	3 levels	Supra-, retro-, and infraclavicular
Millesi ⁷	4 levels	Supraganglionic root, infraganglionic root, trunk, and cord
Alnot ⁸	4 levels	Preganglionic root, postganglionic root, supra- and retroclavicular, and infraclavicular
Chuang ⁹	4 levels	Preganglionic root, postganglionic spinal nerve, pre- and retroclavicular, and infraclavicular
Narakas ¹⁰	5 levels	Supraganglionic root, infraganglionic spinal nerve, infraganglionic trunk, retroclavicular and terminal branches
Mackinnon and Dellon ¹¹	6 levels	Root avulsion (preganglionic and postganglionic), trunk injury, lateral cord, posterior cord, medial cord, terminal cord branches injury
Boome ¹²	8 levels	C5–6; C5–6–7; C5–6–7 posterior divisions; C5; C6; lateral and medial cords; posterior cord



(A)




(B)

Fig. 36.1 (A) The illustration shows that the postganglionic root is part “a”; postganglionic spinal nerve is part “b” from the anatomical point of view; (B) an avulsion C7 (distal stump) during dissection.

root should be reserved for the paired anterior and posterior nerve roots in the spinal canal,” and that “the part of the plexus extending from the union of nerve roots to the formation of the trunks of the plexus should be referred to as a spinal nerve.” The author agrees with this statement. Therefore, the components of the brachial plexus are roots, spinal nerves, trunks, divisions, cords, and terminal branches.

To avoid anatomical confusion, we have described brachial plexus lesions with “numbers”, levels I–IV, instead of word descriptions¹⁴ (Fig. 36.2), e.g., two levels 4, three levels 5, 6; four levels 7–9; five levels 10; six levels 11 and even eight levels 12. A total of 819 cases of adult BPI were included (1986–2003) in this new classification and the incidence at different levels was determined:



Level I Preganglionic root injury

Level II Postganglionic spinal nerve injury

Level III Pre- and retroclavicular injury (trunks and divisions injury)

Level IV Infraclavicular injury (cords and terminal branches injury)

Fig. 36.2 Anatomy and numbered level of brachial plexus injury (see text).

- Level I injury: inside the (vertebral) bone; this is a preganglionic root injury including spinal cord, rootlet, and root injury; 70% of BPI patients are unfortunately injured at this level.
- Level II injury: inside the (scalene) muscle; this is a postganglionic spinal nerve injury, located at the interscalene space proximal to the suprascapular nerve; pure level II injuries account for around 8%.
- Level III injury: pre- and retroclavicular; this includes trunks and divisions; pure level III injuries account for about 5%.
- Level IV injury: infraclavicular; including cords and terminal branches injury proximal to the axillary fossa; the second largest population of BPI patients, at about 17%.

There are some relationships among the levels of injury:

1. An extended-level injury on the same nerve is frequently observed: for instance, C7 injury from the root level down to the interscalene space (level I and II injury).
2. A combined-level injury on different nerves is common: for instance, C5 and C6 spinal nerve rupture injury (level II) accompanied with C7–T1 root avulsion (level I).
3. A skip-level injury is rare: for instance, a longitudinal skip-level injury in which C5 and C7 are injured (avulsion or rupture) but C6 is intact; a horizontal skip-level injury in which level I and level III are injured, but level II is grossly intact.

4. Level IV injuries are usually isolated, and rarely show upward extension.

The term “supraclavicular BPI” will cover a large zone of injury, including level I, II, or III lesions.

Preoperative differential diagnosis of supra- (level I–III) and infraclavicular (level IV) injury is important to avoid large incisions, unnecessary dissection and tissue damage, prolonged operative time, increased postoperative morbidity and resulting scars. With help of imaging studies and preoperative clinical evaluation, it is not difficult to diagnose a level I lesion. However, when the injuries are incomplete, differential diagnosis becomes difficult¹⁵ (Table 36.3).

Patterns of brachial plexus injury

There are two types of characteristic lesions seen in BPI: avulsion and rupture. Both are traction injuries but with different characteristics. Avulsion refers to the nerve being torn from its attachment (proximal avulsion occurs at the spinal cord, distal avulsion at the muscle or bone edge). Rupture is a nerve injury involving a traction force on an incompletely divided nerve, causing a complete division with irregular proximal and distal ends. In avulsion injury, only one disrupted end with a coiled spring-like appearance can be seen in the operative field in the acute stage (Figs. 36.3A & 36.4A), or a fusiform pattern (glioma) in the chronic stage (see Figs. 36.3B & 36.4B). If a surgeon attempts to locate the other avulsed end, a second operative wound is usually required. However, in rupture injury the two nerve ends can be visualized in the same operative wound in the acute stage (see Fig. 36.3C), or within a big neuroma noted in the chronic stage.

Table 36.3 Differentiation diagnosis (DD) between supra- and infraclavicular BPI with incomplete paralysis of shoulder and elbow

Condition	Supraclavicular BPI	Infraclavicular BPI	Differential diagnosis
Isolated axillary nerve injury	Impossible	Yes	No need to DD
Isolated musculocutaneous nerve injury	Impossible	Yes	No need to DD
Shoulder dislocation		Yes	No need to DD
Infraclavicular Tinel's sign (+)	+ (due to nerve regeneration)	+	Need to DD
Muscle strength examination			
(A) When supraspinatus (M0), serratus anterior (M0)	Yes	Impossible	No need to DD
(B) When supraspinatus (M>3), serratus anterior (M>3)	Impossible	Yes	No need to DD
(C) When supraspinatus (M<2), serratus anterior (M<2)	?	?	Need to DD
(C-1) When C-PM (M>3), teres major (M>3), LD (M>3)	Impossible	Yes	No need to DD
(C-2) When C-PM (M<2), teres major (M>3), LD (M>3)	High possible level III		
(C-3) When C-PM(M<2), TM (M<2), LD (M<2)	High possible level II–III		
Condition			
Scapular fracture		Potential lesion	
Imaging studies	Important for level I	Not important	
EMG, NCV	Important	Important	
C-PM, Clavicular part of pectoralis major muscle; EMG, electromyography; LD, latissimus dorsi; NCV, nerve conduction velocity.			




Fig. 36.3 The drawing shows the mechanism of avulsion injury (A,B) vs. rupture injury (C).

Root avulsion is very common in BPI due to its weak supporting structures consisting of dura and dentate ligaments. A novel approach to performing spinal cord implantation with or without nerve graft^{16,17} showed unsatisfactory clinical results. This implies that in avulsion injury only one end (distal end) is available, while the other end (proximal) is absent or unsuitable for repair. "Root injury" is an obscure term that may mean avulsion from the cord (true avulsion) or rupture or stretch at rootlets or roots. Root avulsion in BPI is usually accompanied by dural tearing and a cerebrospinal fluid leak with cyst formation, called pseudomeningocele. However, in some cases, the root can be avulsed at its origin with an intact dura cone (called "avulsion *in situ*"). The nerve root may remain inside the spinal canal or at the dural orifice, giving a grossly normal appearance or loosening with curvature of the spinal nerve at the time of surgical intervention despite established paralysis. Most often, however, the entire

avulsed root, including ventral and dorsal roots, and ganglia, retracts and migrates downward to the interscalene or preclavicular region (see Fig. 36.2B).

Pathophysiology and degree of nerve injury

Timing of nerve exploration is dependent upon the degree of nerve injury. The degree of peripheral nerve injury can be classified into neuropraxia, axonotmesis, and neurotmesis (Seddon classification¹⁸) or grade 1–5 injury (Sunderland classification¹⁹). Seddon's axonotmesis or Sunderland's second-degree injury starts to have Wallerian degeneration at proximal and distal stumps. Seddon's neurotmesis or Sunderland's third- to fifth-degree injury has the potential for aberrant reinnervation after nerve regeneration. In Sunderland's fourth- or fifth-degree injuries, only nerve repair can succeed in restoring continuity, but in first-, second-, or third-degree




Fig. 36.4 (A) Coiled spring-like structure with irregularity of stumps of C5 and C6 avulsion (acute stage); (B) fusiform pattern neuroma (or glioma) of the distal C7 stump (chronic stage) during dissection.

injuries, spontaneous recovery, complete and incomplete, may occur.

Timing of brachial plexus exploration

There are five times for brachial plexus exploration and repair:

- Immediate repair or repair within days
- Early repair within a month
- Delayed early repair within 3–5 months
- Late repair at more than 6 months
- Chronic repair at more than 1 year.

There is rarely an argument against immediate exploration after penetrating injury by sharp objects for direct nerve repair. Some surgeons also advocate exploration of the BPI as early as possible^{20,21} for adult closed BPI for its advantages, including easy diagnosis of root avulsion and avoidance of difficult dissection through scarring. However, such early exploration is not recommended by most brachial plexus surgeons.^{7–9,22} In cases of closed BPI, the degree and extent of injury are difficult to judge soon after injury and are often underestimated. The benefits of waiting usually outweigh the advantages of early surgery.¹⁴

Clinical evaluation

Etiology of adult brachial plexus injury

BPI may be caused by trauma (open or closed type), compression, tumor, infection, inflammation, toxins, and other etiologies.

Patient history

Patient history should include mechanism of injury, level of consciousness at the time of trauma, associated injury (such as head injury, fracture, open wound, chest injury, vascular injury), kinds of previous surgical intervention (such as chest intubation, cervical spine surgery), and characteristics of pain. This information helps to determine the degree and extent of injury and the need for surgical intervention. Mechanism of injury (e.g., upward or downward traction and with or without rotation) is not easily detected due to the patient's loss of consciousness or amnesia for the accident. A history of shoulder dislocation or glenoid fracture may have a high incidence of level IV injury, whereas a history of cervical spine injury or fracture may cause a level I root injury. Artery rupture and repair imply the site of nerve injury. For instance, arm traction by rolling machine or conveyor belt often causes an open wound in the axilla, extensive ecchymosis around the shoulder and chest (due to rupture of axillary vessels), and level IV BPI. Segmental thrombosis of the subclavian artery is usually associated with C8–T1 root injury. History of rib fracture and chest intubation may preclude intercostal nerve transfer because of a higher failure rate.²³ Extreme causalgia with or without a phantom limb is often seen in cases of root avulsion in lower-root (C8–T1) avulsion as they contain the richest sympathetic fibers. The pain character, like electric shooting pains, continues for a short duration (seconds), followed by spontaneous relief and recurrence. Extreme causalgia is also a major factor for poor outcome due to poor rehabilitation. Sometimes a partial Brown–Sequard syndrome (hemitranssection of the spinal cord with ipsilateral upper

motor neuron lesion below the level of lesion, and contralateral abnormal sensation to pain and temperature, which may not be at the same level) is also noted in the level I injury.²⁴

Preoperative evaluation and diagnosis

Most adult BPIs are closed injuries. Accurate assessment of the extent and severity of the injury in closed BPI is difficult. Clinical evaluation is still essential and is the most important step in establishing the diagnosis of site and degree of injury, and determining the treatment and prognosis. A brachial plexus chart (left and right formats, [Fig. 36.5A,B](#)) outlining the possible injury should be completed before definitive brachial plexus surgery. This chart is filled at the initial examination, and usually performed at 2 months after injury. The chart is also useful for follow-up evaluations, allowing comparison of clinical pictures.

Motor examination

Muscle-by-muscle examination should be completed in a distal-to-proximal fashion and recorded using the British Medical Research Council (MRC) scale (M0–5).²⁵ We have modified the motor evaluation system, adding more detailed differentiation: M5, strength against four-finger (examiner) resistance; M4, against one finger, resistance for longer than 30 s; and M3, against gravity ([Table 36.4](#)). M4 is recognized as useful muscle strength. The action of each muscle should be examined separately in relation to the movement of a single joint. Although there is no single muscle innervated by a single spinal nerve, some muscle palsy can give specific information related to the level of the injury. For instance:

1. Diaphragm palsy implies C4 and very proximal C5 (level I) injury.
2. The levator scapulae muscle lies anterior to the trapezius muscle in the neck, and can be more easily detected than the rhomboid muscles, which are covered by the trapezius muscle. Both levator scapulae and rhomboid muscles are innervated by the same nerve (dorsal scapular nerve, or C4 and C5). Preservation of its function in upper plexus or total plexus injury may imply C5 is a rupture injury (level II) with an available proximal stump.
3. Serratus anterior muscle: The long thoracic nerve has two portions: the upper portion originating from C5 and C6, and the lower portion from C7. The upper portion is responsible for scapular protraction, and the lower portion is important for scapular stabilization.²⁶ Positive anterior traction of the scapula (shoulder protraction test) shows that at least C5 is ruptured after branching to the long thoracic nerve, so the proximal C5 is available for transfer. Scapular winging is observed only when the lower portion is denervated, but isolated C7 root avulsion is rarely seen in adult BPI. In pure C5–6 level I injury, the lower part of the muscle is still functional. The result of spinal accessory nerve transfer to the suprascapular nerve is much superior in the reconstruction of total root avulsion.
4. Clavicular and sternal portions of the pectoralis major muscle: The major pectoral muscle can be separated into two parts: clavicular and sternal parts. The clavicular

Table 36.4 British Medical Research Council (MRC) scale and Chuang modification

British MRC scale**Motor scale**

M0: No contraction
 M1: Flicker (trace of contraction)
 M2: Active movement with gravity eliminated
 M3: Active movement against gravity
 M4: Active movement against gravity and resistance
 M5: Normal (full) power

Sensory scale

S0: No sensation
 S1: Pain sensation
 S2: Pain and some touch sensation
 S3: Pain and touch with no overreaction
 S3+: Some two-point discrimination
 S4: Normal sensation

Chuang modification**Motor scale**

M4: Active movement against examiner's one-finger resistance ≥ 30 s
 M5: Active movement against examiner's four-finger resistance



Sensory scale

S2+: Pain and touch with overreaction

Right Brachial Plexus

Name _____ Chart # _____ Birth date _____ Date exam _____
 Address: _____
 Present illness _____ Date of injury _____
 Past history _____ X-Ray and _____ Horner's syndrome _____
 Date operation _____ MRI _____ Vascular lesion _____
 EMG _____ Mobility of diaphragm _____

Intolerable
 Disturbance
 Acceptable
 None



A

Fig. 36.5 Special charts for evaluation of brachial plexus injured patient, (A) for the right and (B) for the left upper limb.

Continued

Left Brachial Plexus

Name

Chart #

Birth date

Date exam

PAIN

Address:

Date of injury

Present illness

Past history

X-Ray and

Horner's syndrome

Date operation

MRI

Vascular lesion

EMG

Mobility of diaphragm

C5

C6

C7

C8

T1

TRAPEZ

Rhomb

Levator scap

SERRATUS ANT

II

III

IV

V

OPP

POL

APB

Post

Lat

DELT

ant

BICEPS

PRON

FCR

PL

TRICEPS

FLEX

POL

LONG

FL

POL

BR

FL

POL

BR

SUPRA

SPIN

INFRA

SPIN

BRACHIO-

RADIALIS

SUPINATOR

TERES MAJ

EXT DIG

COM+

PROPRII

APL EPB

EPL

FCU

FLEX

DIG

PROF

II

III

IV

V

POST

INTEROSS

ANT

INTEROSS

PECTORALIS MAJOR

CAVICULAR STERNAL

M0

M1

M2

M3

M4

M5

S0

S1

S2

S2+

S3

S3+

S4

C3

C4

C5

T2

T1

C6

C8

C7

Tinel

C3

C4

C5

T2

T1

C8

C6

C7

B

Fig. 36.5, cont'd

part is innervated by upper and middle trunks or its divisions (lateral pectoral nerve), while the sternal part is innervated by the lower trunk (medial pectoral nerve). An incomplete and complete paralysis of the clavicular part of the pectoralis major muscle may imply at least level III or more proximal lesion.¹⁵

Sensory examination

Sensory evaluation should include sensory tests and elicitation of a Tinel's sign. Sensibility tests include pain and temperature appreciation, static and moving two-point discrimination,

constant touch, and vibration. However, performing complete sensory tests in BPI is both unnecessary and illogical because we are examining the dermatomal distribution from spinal nerves, not the cutaneous distribution. Pinprick test from areas of normal to abnormal sensation to map out the area of sensory disturbance is sufficient for most brachial plexus-injured patients. Sensory grading is based on the British MRC scale (S0–4),²⁵ modified by adding a grade for sensory over-reaction (S2+) (see Table 36.4). Such sensory evaluations can give some clues about the level and degree of BPI.

The Hoffman–Tinel's sign is an important clinical sign to determine the location of a neuroma or to track the

regeneration of the injured nerves. Palpation or percussion at the neck, at the supraclavicular Erb's point (clavicular insertion of the sternocleidomastoid muscle), at the infraclavicular coracoid process of the scapula, or at the route of different nerves along their course may induce an electric current sensation (like pins and needles) running down to the shoulder or the hand (positive Tinel's sign). If the Tinel's sign remains at a fixed point, which means retardation of its progression, surgical exploration is warranted. If the Tinel's sign advances from supraclavicular to infraclavicular and distally to the arm or forearm at successive examinations, observation is recommended, as this may indicate a Sunderland third-degree lesion. A weak or absent Tinel's sign in the neck region usually indicates total root avulsion.

Horner's syndrome (miosis, ptosis, enophthalmos, and anhidrosis) is a sign of sympathetic nervous system disturbance. It indirectly implies avulsion of the T1 and C8 roots because the sympathetic fibers from the T1–2 sympathetic ganglia are quite close to the preganglionic fibers of T1 and C8. This syndrome may regress with time. It is a more reliable sign in adult BPI, but less accurate in obstetric traction injury.

Plain X-ray and imaging studies

Clinical tips

- Direct multiplanar imaging capabilities and superior soft-tissue contrast have turned MRI into the primary imaging tool for BPI evaluation.
- The MRI protocol for brachial plexus includes MRI myelogram (two-dimensional), FIESTA (three-dimensional), Cor (coronal) T1, Cor STIR, Sag (sagittal) T1, Sag STIR, Ax (Axial) T1 and Ax STIR, and DWI (diffusion-weighted imaging) techniques for determination of the BPI level.

Plain X-rays of the chest and cervical spine are required. The chest X-ray should include inspiration and expiration views to exclude diaphragmatic palsy. Cervical spine X-rays are evaluated for any fracture of the transverse process, spinous process, or vertebrae body.

Cervical myelography and computed tomography (CT) myelography can provide valuable information related to the level I injury of the brachial plexus.^{27,28} However, in recent years these studies have been gradually replaced by non-invasive MRI.^{29,30} The most useful MRI technique for the evaluation of a possible level I lesion is the three-dimensional (3D) fast imaging employing steady-state acquisition (FIESTA). These 3D source data are reconstructed along the planes of ventral and dorsal rootlets using a curve planar reformat technique to demonstrate the respective rootlets in a better perspective. Other MR techniques help in the imaging of the whole brachial plexus, notably of level II (Fig. 36.6A–F).

Electrodiagnostic studies

Clinical tips

- Electrodiagnostic studies (EDX) are useful for differential diagnosis between demyelinating conduction block

(Sunderland 1 injury) and axon loss lesions (Sunderland 2–5 lesions).

- Before Wallerian degeneration occurs, the distal stump remains capable of conduction of action potentials (within 2 weeks); the EDX during this period is useless.
- Most adult BPI are due to axon loss without accompanying focal demyelination; however, less frequently, concomitant demyelination is present (especially in shoulder dislocation reduced within 2 h).
- EDX essentially includes three components: sensory nerve conduction velocity (SNCV), motor nerve conduction velocity (MNCV), and needle electromyography (EMG).
- The amplitude of compound muscle action potentials (CMAP) (in MNCV) is the most useful component for quantifying the amount of axon loss. The amplitude in SNCV and fibrillation in EMG tend to overestimate, and the amplitude of MNCV (CMAP) tends to underestimate the severity of axon loss.

Electrodiagnostic studies, mainly consisting of nerve conduction studies (NCS) and needle EMG, are used to localize the lesion and to assess its severity. For the NCS, only amplitudes of the sensory nerve action potentials (SNAP) and CMAP are of value. Both SNAP and CMAP amplitudes provide a good indication of the degree of axon loss, or in contrast, the number of survival axons capable of conducting impulses.^{31,32} Sensory NCSs assess the function of the postganglionic portion of the sensory pathway. Therefore, abnormally low SNAP amplitudes indicate a ganglionic or postganglionic lesion. Conversely, the SNAP amplitude remains normal in a complete paralysis of limb implies pure level I lesion (root avulsion). A combination of unelicitable CMAPs with abnormal low or absent SNAP amplitudes suggests a combined preganglionic and postganglionic lesion. To assess the major elements of the brachial plexus, NCSs of multiple nerves are usually required. These include sensory NCS of the median, ulnar, radial, musculocutaneous, and axillary nerves, as well as motor NCS of the median, ulnar, radial, musculocutaneous, and axillary nerves. The presence of fibrillation potentials on needle EMG may suggest that the lesion is at least axonotmesis. The reduction of amplitude of compound muscle action potentials during motor NCS is more reliable than the presence of fibrillation potentials to indicate axonal loss rather than a neuropraxia lesion.

Needle EMG can detect a minimal amount of motor axon loss. For a comprehensive evaluation of the brachial plexus, adequate EMG sampling of muscles is critical. In addition to muscles innervated by major terminal nerves, examination of those supplied from or proximal to the brachial plexus can help to localize the lesion. These include the rhomboid major, serratus anterior, pectoralis major (both the clavicular and sternocostal parts), latissimus dorsi, teres major, and cervical paraspinal muscles. Needle EMG can also reveal evidence of early reinnervation and chronicity of the lesion. Presence of denervation potentials (i.e., fibrillation potentials and positive sharp waves) is the most sensitive indicator of motor axon loss. However, they require about 3 weeks to develop after axon injury.²⁷

Percutaneous somatosensory evoked potentials (SEPs) provide far less information than comprehensive NCSs and needle EMG studies in most patients with BPI. Thus SEPs are not routinely performed. Intraoperative SEPs may be useful to determine the continuity of individual segments of the brachial plexus and roots.

Vascular injury

Absence or weakness of pulsation of the radial artery at the wrist indicates a possible vascular injury of the axillary or subclavian artery. It may further indicate the extent and severity of the trauma. Subclavian artery occlusion may indicate a







Fig. 36.6 The patient with right C5-T1 total root avulsion: (A) coronal view of MR(magnetic resonance) FIESTA (fast imaging employing stead-state acquisition) neurogram, (B) oblique view of FIESTA neurogram, and (C) MR myelogram all show right C5-T1 avulsion cysts; The other patient with left C7 root avulsion: (D) using MRI curve planar reformat techniques, (E) axial view, and (F) Short-Tau Inversion Recovery (STIR) neurogram show the C7 avulsed cyst, and all other spinal nerves are still in continuity in Level II and III.





Fig. 36.6, cont'd



level I injury, while axillary artery occlusion may be associated with a level IV lesion. Vascular injury should be taken into account when considering the use of a vascularized ulnar nerve grafts for reconstruction because the ulnar artery is transferred with the ulnar nerve.

Surgical treatment and techniques

Clinical tips

- There are different incision lines for different purposes (Fig. 36.7).
- There are many important landmarks and key points for brachial plexus exploration for supraclavicular and infraclavicular brachial plexus exploration with safety and efficiency (Fig. 36.8).
- Surgical methods depend on the level of BPI. (Table 36.5).
- Debate between proximal nerve transfers and distal nerve transfers for incomplete BPI exists. The former is a traditional strategy; the latter is a new strategy and is becoming more popular (Table 36.6).
- Debate of reconstruction strategy between primary nerve reconstruction (multiple nerve transfers) and functioning muscle transplantation for total root avulsion of BPI exists. The former is proximal-to-distal, the latter is distal-to-proximal in reconstruction priority (Table 36.7).
- Postoperative management and follow-up should be longer: at least 2 years for upper plexus, and 4 years for lower plexus reconstruction.
- Induction exercise is an essential rehabilitation when any type of nerve transfer is utilized, including functioning free muscle transplantation.

Different incision lines for different approaches

Different incision lines for brachial plexus surgery are determined by preoperative diagnosis of level of BPI and management strategy (see Fig. 36.7). For the supraclavicular approach, a linear incision from the midpoint between the mastoid process of the temporal bone and the jugular notch, going along the posterior border of the sternocleidomastoid muscle, and curving laterally parallel to and above the clavicle (a C-curved incision) is a popular incision (see Fig. 36.7, mark 1). For the infraclavicular approach, the incision is just along



Fig. 36.7 Multiple incision lines for different purposes: 1, for supraclavicular brachial plexus exploration; 2, for infraclavicular brachial plexus exploration; 3, for Oberlin or Mackinnon method of nerve transfer; 4, for intercostals nerve dissection; 5, for contralateral C7 dissection; 6, for hypoglossal nerve dissection; and extended 1 incision for spinal accessory nerve dissection.

Table 36.5 Reconstructive strategies for different level of root avulsion

Condition	Nerve reconstruction	Late reconstruction
Five-root (C5–T1) level 1 injury	Ph→distal C5 for shoulder elevation IC→musculocutaneous nerve for elbow flexion contralateral C7→median nerve for hand	Wrist and thumb fusion, FFMT for EDC and elbow (XI)
Four-root injury (C5 level 2, C6–T1 level 1)	C5→median nerve for hand IC→musculocutaneous nerve for elbow flexion Ph→distal C5 for shoulder elevation	Wrist and thumb fusion, FFMT for EDC and elbow (XI)
Three-root injury		
1. C5, C6 level 2, C7–T1 level 1	C5→SS + PD of UT for shoulder C6→C8 or median nerve for hand IC→musculocutaneous nerve for elbow flexion	Variable
2. C5–7 level 1, C8–T1 intact	Ph + XI→distal C5 for shoulder elevation Part ulnar→biceps br Part median→brachialis br for elbow	Variable
Two-root injury		
1. C5–6 level 1, C7–T1 intact	Ph + XI→distal C5 for shoulder elevation Part ulnar→biceps br Part median→brachialis br for elbow	Variable
2. C6–7 level 1, C5 level 2, C8–T1 intact	Ph + XI→distal C5 for shoulder elevation C5→AD of UT for elbow	Variable
3. C8–T1 level 1, C5–7 level 2 injury	C5 nerve grafts for shoulder C6→median nerve for hand C7 nerve grafts to C7	Variable
4. C8–T1 level 1 injury, others intact	No nerve reconstruction	ECRL→EDC for finger extension FCR→FDP for finger flexion Br for opponensplasty Thumb IP fusion
Single-root injury		
1. C5 level 1 injury	Ph + XI + CMB→distal C5	
2. C6 level 1, usually C5 level 2 injury	C5→C6 or AD of UT for elbow Ph + XI + CMB→distal C5	
3. C7 level 1, C5–6 level 2 injury	C5, C6 nerve grafts itself	
Ph, Phrenic nerve; IC, intercostal; XI, spinal accessory nerve; CMB, cervical motor branches; FFMT, functioning free muscle transplantation; EDC, extensor digitorum communis; SS, suprascapular nerve; PD, AD, UT, posterior division, anterior division of the upper trunk; br, branch; ECRL, extensor carpi radialis longus; FCR, flexor carpi radialis; FDP, flexor digitorum profundus; IP, interphalangeal joint.		

Table 36.6 Proximal nerve transfer versus distal nerve transfer in adult BPI

	Proximal nerve transfer	Distal nerve transfer
Philosophy	Traditional and physiological	New strategy
Donor nerve	Supraclavicular, far from the target muscle	The nearby nerve close to the target muscle
Advantages	For diagnostic and treatment Proximal nerve(s), powerful Nerve cut stump often unhealthy, fewer functional deficits	A treatment procedure, but not diagnostic Direct repair; no need of nerve graft No scars, easy dissection, shorter operation time Nerve cut stump healthy Short rehabilitation, faster recovery
Disadvantages	More scars, difficult dissection Nerve cut stump unpredictable, often unhealthy All need nerve grafts, moreover long nerve grafts (>8 cm) Longer operation time Longer rehabilitation period	Nerve cut, risk of causing deficits Risk of iatrogenic injury May need multiple incisions
Indication	All kinds of avulsion/rupture injury of brachial plexus injury	Not global BPI Intrinsic palsy of the hand

Table 36.7 Comparison of multiple nerve transfers vs. functioning muscle transplantation for total root avulsion of BPI

	Multiple nerve transfers first	FFMT first
Authors prefer	Chuang ⁴⁰	Doj ³⁹
Philosophy	Traditional strategy Proximal-to-distal in reconstruction priority Shoulder, elbow first, then finger sensation and flexion, then finger extension	New strategy Distal-to-proximal in reconstruction priority Finger extension and flexion, then elbow flexion; then shoulder
Reconstructive strategy	Multiple nerve transfers are essential FFMT is an adjuvant procedure to backup the results	Two FFMTs are essential Nerve transfers are adjuvant
Brachial plexus exploration	Yes	Maybe not
Nerve reconstruction:		
For shoulder	Yes (by NT)	May or may not be needed
For elbow	Yes (by NT)	Need FFMT
For finger	Yes (by NT)	Need FFMT
Stage requirement for full reconstruction	Can be one stage	Always multiple stages
Rehabilitation period	At least 4 years	2 years
Patient selection	Should be a highly motivated and intelligent patient	Can be a less intelligent and impatient patient
Predict outcomes:		
Shoulder elevation	Better ($\geq 60^\circ$)	Shoulder fusion ($10\text{--}30^\circ$)
Elbow flexion	Usually better (M4)	M3–4
Finger flexion	M2–4	M2–4
Finger extension (EDC)	M0	M2–3

NT, Nerve transfer; FFMT, functioning free muscle transplantation; EDC, extensor digitorum communis.



Fig. 36.8 Chuang angle, and “white line” between clavicular and sternal part of pectoralis major muscle (see text). C-PM, Cervical part of pectoralis major; S-PM, sternal part of pectoralis major.

the deltopectoral groove and extends upward to meet the supraclavicular incision, or downward to the medial sulcus of the biceps (see Fig. 36.7, mark 2). Other additional incisions may be required: extended neck incision for accessing the spinal accessory nerve (upward extending incision of the mark 1 incision); chest semicircular incision for the intercostal nerve (see Fig. 36.7, mark 4); inframammary incision for the hypoglossal nerve (see Fig. 36.7, mark 6); medial arm incision for the biceps nerve and brachialis nerves (see Fig. 36.7, mark 3); and a contralateral neck C-curved incision for contralateral C7 spinal nerve dissection and transfer (see Fig. 36.7, mark 5). The different incision lines are used to avoid: a large incision wound, unnecessary dissection, prolonged operative time, increased postoperative morbidity (pain and numbness), and long ugly scars.

Landmarks and key points for supraclavicular dissection

1. A platysma musculocutaneous flap is elevated with the C-curved incision.
2. Dissection beneath the sternocleidomastoid muscle to the internal jugular vein is made but should never go beyond the internal jugular vein, the most medial landmark of the brachial plexus exploration. In addition, the suprascapular sensory nerves are the uppermost landmark, and one should never go above them.
3. The omohyoid muscle just behind the sternocleidomastoid muscle is identified and spared if

possible as it is an important landmark for possible secondary exploration.

4. Below the omohyoid muscle, there is an abundance of adipofascial tissue containing rich lymphatic ducts, lymph nodes, and the transverse cervical vessels. A similar C-shaped incision along the internal jugular vein medially and subclavian vein inferiorly is made and a superiorly based adipofascial flap is elevated. All the lymph tissues, including the ducts coming from the deep plane of the internal jugular vein, should be coagulated or ligated before division to avoid postoperative lymph leakage. The phrenic nerve and anterior scalene muscle are identified following adipofascial flap elevation.
5. The transverse cervical artery and vein in the inferior plane of the adipofascial tissue are preserved if possible as they are potentially required as the recipient vessels for a vascularized ulnar nerve graft. Sometimes the transverse cervical artery is abnormally beneath the brachial plexus. The subclavian artery just beneath the scalene anterior muscle is carefully protected.
6. The fibrotic scalene anterior muscle can be segmentally or totally excised depending on the necessity to expose the more proximal spinal nerve in level II injury for intraoperative diagnosis and nerve manipulation.
7. The vertebra C5 has a more prominent anterior tubercle of the transverse process than vertebra C6 or C4. While detaching the scalene anterior muscle and fascia, the nerve comes out above the tubercle is C5, and below is C6 spinal nerve.
8. Other anatomic landmarks are also helpful for localization:
 - a. The nerve beneath the transverse cervical artery is usually C5 or the upper trunk.
 - b. The nerve beneath the subclavian artery is C8 or the lower trunk.
 - c. The first branch from the upper trunk is the suprascapular nerve, exiting from the plexus and traveling backward. The division beside the suprascapular nerve is the posterior division of the upper trunk, which travels in a posterior plane, while the anterior division of the upper trunk travels in an anterior plane.
 - d. The spinal accessory (XI) nerve can be found through two ways: (1) dissection between the adipofascial tissue and platysma skin flap down to the trapezius muscle where the XI nerve lies in front of the trapezius muscle; or (2) extending the incision upward across the supraclavicular (sensory) nerves to locate the great auricular nerve, when the XI nerve will be seen within about one finger-breadth above the great auricular nerve, and beneath the sternocleidomastoid muscle. This can be confirmed by a nerve stimulator.

Landmarks and key points for infraclavicular dissection

1. Chuang's angle (Fig. 36.8A) is an angle shaped by the main branch of the cephalic vein on one side and

the clavicle on the other side. Some of the deltoid and the clavicular part of pectoralis major muscle attachments can be detached to increase the angle zone. Under the clavicle is the subclavius muscle, and under the subclavius muscle is a space where the posterior cord, lateral cord, and suprascapular nerve can be seen. From this, the suprascapular and infraclavicular fossa can be connected through this avascular plane which can be created by a finger dissection without fracturing the clavicle. The clavicle and the subclavius muscle are lifted together by a rolled gauze.

2. The "white line" (see Fig. 36.8B) is an intermuscular septal line between the clavicular and sternal parts of pectoralis major muscle. Opening the line, the underlying pectoralis minor muscle and infraclavicular brachial plexus can be visualized. Some anatomical landmarks are also helpful for anatomical localization infraclavicularly. The first cord encountered beneath the proximal pectoralis minor muscle is the lateral cord. Y-shaped limbs from lateral and medial cords will become the median nerve. The axillary artery (the artery beyond the first rib is axillary artery) can be easily found between the Y-shaped limbs. The posterior cord lying posterior to the subclavian artery has two terminal branches: the larger one is the radial nerve, and the smaller one is the axillary nerve.
3. In the upper arm, the musculocutaneous nerve can usually be found between the biceps and coracobrachialis muscles. The musculocutaneous nerve will penetrate the proximal coracobrachialis muscle. Sometimes it has anatomical variation and comes from the median nerve.
4. The axillary nerve in the axilla can be found at the humeral neck, above the tendinous portion of the teres major, accompanied by the lateral circumflex humeral artery.

Surgical techniques

Surgical methods include neurolysis, nerve grafts, nerve transfers and functioning free muscle, depending on preoperative diagnosis of level of injury and intraoperative findings. The following pages detail our experience with BPI treatment in terms of the level of injury (see Table 36.5).

Level I injury

The incidence of level I lesions is unfortunately very high, about 70%. Most are avulsion injuries. Nerves may be avulsed from the spinal cord (true avulsion), or ruptured at the preganglionic roots and rootlets. Partial Brown-Séquard syndrome is an example of true avulsion.²² One to all five roots may be avulsed. Root avulsion injuries lack central connection and are considered irreparable. Nerve transfer, pedicled or functioning free muscle transplantation (FFMT) provide the only possibilities for functional restoration.

Nerve transfer (Video 36.3 ▶)

Nerve transfer is a surgical option which intentionally divides a physiologically active nerve (with low donor morbidity)

and transfers it to a distal, more important but irreparable paralyzed nerve. The procedure is best done within a golden time period – within 5 months of the injury,^{9,33} in order to reactivate the paralyzed muscle(s) effectively (aiming for M4). Nerve transfer can be broadly classified into four categories: (1) extraplexus; (2) intraplexus; (3) close-target nerve transfer (or distal nerve transfer); and (4) end-to-side neurorrhaphy nerve transfer.

Extraplexus nerve transfer

Extraplexus nerve transfer involves the transfer of a brachial plexus neighboring nerve (from either the ipsilateral or contralateral neck) to the avulsed brachial plexus for neurotization of a paralyzed nerve. The commonly used donor nerves are mostly aimed at motor reinnervation.³³ These donor nerves include the phrenic (Ph) nerve, spinal accessory (XI) nerve (accessed by an anterior neck approach), deep motor branches of the cervical plexus (cervical motor branches, CMB), hypoglossal nerve (XII), and the contralateral C7 (CC7) spinal nerve. Extraplexus sensory nerve transfer such as supraclavicular sensory nerve to median nerve transfer is sometimes used to provide sensation to the paralyzed hand.

Intraplexus nerve transfer

Intraplexus nerve transfer is applicable in cases of non-global root avulsion, in which at least one of the spinal nerves is not ruptured and is still available for transfer – not to its original pathway, but to other more important nerves. For example, in a case of C5 rupture and C6 root avulsion, the C5 fibers are intentionally transferred to C6 (or the anterior division of the upper trunk) for elbow flexion, and the distal C5 (combining the posterior division of the upper trunk and suprascapular nerve) is then reinnervated by the phrenic and/or spinal accessory nerve (extraplexus) nerve transfer (Fig. 36.9). This strategy acknowledges that elbow flexion has priority over shoulder reconstruction. Intraplexus nerve transfer is individualized depending upon the intraoperative findings, the surgeon's philosophy, and the patient's condition and requirements. Extraplexus and intraplexus nerve transfers are both considered as proximal nerve neurotization (see Fig. 36.9).

Closed-target nerve transfer (or distal nerve transfer)

Closed-target nerve transfer is a procedure that provides a direct coaptation at a more distal site, closer to the neuromuscular junction, thus achieving faster recovery of motor outcomes. Closed-target nerve transfer is defined as a procedure outside the supra- and infraclavicular fossa. Examples include spinal accessory (XI) nerve transfer to the suprascapular nerve via a posterior approach; partial ulnar nerve transfer to the biceps nerve; partial median nerve transfer to the brachialis nerve; long head of triceps branch transfer to the anterior division of axillary nerve (Fig. 36.10); intercostal nerve transfer to the biceps nerve or the musculocutaneous nerve, or the nerve of the long head of triceps; anterior interosseus nerve transfer to the radial or posterior interosseus nerve; and branch of the anterior interosseus nerve transfer to the deep motor branch of the ulnar nerve in the forearm. Closed-target nerve transfer is considered as distal nerve transfer.³⁴ Selecting proximal or distal nerve transfer as a reconstructive strategy is now a subject of much debate (see Table 36.6).



Fig. 36.9 A case of left brachial plexus injury with drop shoulder and elbow. Exploration proved C5 rupture and C6 root avulsion. This patient received C5 nerve grafted (5 cm × 4) to C6 (intraplexus nerve transfer), and phrenic nerve plus spinal accessory nerve both transfer to the distal C5 (extraplexus nerve transfer). (A,B) Results after 3 years' rehabilitation showed good shoulder and good elbow recovery.

A cohort of 188 patients with different methods of musculocutaneous nerve neurotization for acute brachial plexus injuries were selected based on inclusive criteria in the author's series.³⁵ Musculocutaneous nerve neurotization from C5, medial cord, C8, contralateral C7, spinal accessory nerve, or phrenic nerve to obtain elbow flexion were all included into the group of proximal nerve transfer. Musculocutaneous neurotization from partial ulnar nerve and/or partial median nerve was classified into distal nerve transfer. Intercostal nerve transfer to the musculocutaneous nerve was categorized into a separate group. Results showed there were no significant differences in the success rate of recovery of elbow flexion ($M > 3$) between the use of proximal vs. distal nerve transfer ($P = 0.424$). Even though the speed of recovery was faster in



Fig. 36.10 A 17-year-old young male had right brachial plexus injury with C5 and C6 two-root avulsion. He received multiple nerve transfers: spinal accessory nerve transfer to the suprascapular nerve (extraplexus nerve transfer), and triceps branch (to long head of triceps) transfer to the anterior division of the axillary nerve, ulnar nerve fascicle to the biceps branch and median nerve fascicle to the brachialis branch (distal nerve transfer). (A–C) Results after 2½ years showed good shoulder and elbow recovery with good shape of supraspinatus, infraspinatus, deltoid, and elbow flexor muscles.

the distal group, 19 months vs. 23.9 months, the difference was also not significant. The only statistically significant difference was the speed of recovery between the use of partial ulnar nerve $\pm$ median nerve fascicle and the use of intercostals nerves ($P=0.046$). However, a selective number of patients had grip strength deficits resulted from distal nerve transfers for many years.

From the author's point of view, the new strategy of distal nerve transfer can provide an exciting alternative of the traditional proximal nerve graft and/or transfer. However, distal nerve transfer should not be applied in situations where proximal nerve graft/transfer is more indicated. Proximal nerve graft/transfer (extraplexus and intraplexus nerve transfer) is still the main reconstructive procedure based on the principle of "No diagnosis, no treatment" (Fig. 36.11). Proximal nerve graft/transfer is usually performed during brachial plexus exploration. It is quite common to find out the proximal ruptured spinal nerve for reconstruction, which is especially true for C5, even with a preoperative diagnosis of total root avulsion. In proximal nerve graft/transfer, if the transferred nerve comes from its original spinal nerve, it is usually more powerful with a huge number of axons. Proximal nerve graft/transfer can avoid iatrogenic injury where the lesion is still in continuity (more are Sunderland third-degree

injury) and neurolysis is maybe the only procedure without further cutting the nerve. Other donor nerves such as phrenic nerve, spinal accessory nerve, hypoglossal nerve, cervical motor branches can also be found without additional incisions. However, in proximal nerve graft/transfer, dense scars with difficult dissection will be encountered. Sometimes one needs to trim out the part of C5 transverse process to access the ruptured stump. Oozing and bleeding will occur very often and requires careful diathermy. Long operation time can be expected. The health of proximal ruptured stump is sometimes unpredictable, even accessed microscopically. Interposition of nerve grafts is always required, which can jeopardize functional recovery and longer rehabilitation time is necessary. Proximal nerve graft/transfer can be applied in either complete or incomplete avulsion brachial plexus injuries.

End-to-side neurorrhaphy nerve transfer

End-to-side neurorrhaphy (terminolateral neurorrhaphy) is a technique to transfer the distal end of a paralyzed and irreparable nerve to the side of an intact nerve with an epineurotomy window for both motor and sensory reconstruction.³⁶ The author has never used this technique for BPI.



Fig. 36.11 A case of right brachial plexus injury with drop shoulder and elbow for 5 months. **(A)** A healed scar over right neck was seen at the first clinic visit. Intraoperative findings 1 month later showed dense scars around C4, C5 and C6. Only external neurolysis with decompression was performed. **(B,C)** Results after 1-year rehabilitation showed good recovery. This case proved the principle of “No diagnosis, no treatment.”

Reconstructive strategies

Shoulder

Reconstruction for shoulder abduction in a level I lesion should take priority over shoulder adduction. If the supraspinatus, infraspinatus, and deltoid muscles are innervated simultaneously, results are predictably better. The Ph and XI are the main donor nerves for shoulder abduction. The XII nerve, CMB, part of C5 or C6, long thoracic nerve, branch to the long head of triceps, medial pectoral nerve, intercostal nerves, and CC7 have also been reported as the donor nerve for shoulder abduction. The recipient nerves for shoulder abduction in order of priority are the distal C5, suprascapular nerve, dorsal division of the upper trunk, then axillary nerve.³³ A study of a series of patients operated on between 2000 and 2003 demonstrated that triple nerve transfers produced the best and most consistently reliable results for shoulder elevation:

an average of 160° shoulder abduction was achieved following triple nerve transfers, but 85° following double nerve transfers and 65° following single nerve transfer.³⁷

Elbow

In level I injury, reconstruction for elbow flexion is always the first priority in adult BPI (in OBPP, reconstruction for hand function is the first priority). Reported donor nerves for elbow flexion include intercostal nerve, XI nerve with a nerve graft, Ph nerve with or without nerve graft, partial ulnar nerve, partial median nerve, pectoral nerve, thoracodorsal nerve, and CC7. The recipient nerve is the musculocutaneous nerve (mixed nerve), biceps nerve, or brachialis nerve. Elbow extension is usually a lower priority for reconstruction. Ph nerve transfer to the distal C5 or to the posterior division of the upper trunk, or to the radial nerve with a nerve graft, can




Fig. 36.12 (A,B) Example of results of one-stage surgery for C5 rupture, C6–T1 four-root avulsion 5 years after (1) phrenic nerve transfer to the posterior division of the upper trunk and spinal accessory transfer to the distal suprascapular nerve for shoulder elevation; (2) three intercostal nerves (T3–5) transfer to the musculocutaneous nerve for elbow flexion; and (3) proximal C5 transfer to the median nerve using vascularized ulnar nerve graft for finger flexion and sensation.

often yield elbow extension, usually in the third year of rehabilitation. Some authors describe transferring two or three intercostal nerves to the branch of the long head of triceps to achieve elbow extension.³⁸

Finger

In global C5–T1 injury (or total limb palsy) reconstructive priority for finger function depends on the procedure used: nerve transfer or FFMT.³⁹ Traditionally, reconstruction for finger flexion is preferable to finger extension which can sometimes be helped by a dynamic extension splint. In cases of C5 rupture with C6–T1 four-root avulsion, transfer of C5 to the median nerve (Fig. 36.12), or in cases of total root (C5–T1) avulsion, transfer of the CC7 to the median nerve (Fig. 36.13) can be performed to achieve finger and wrist flexion as well as finger sensation. Each procedure requires a vascularized ulnar nerve graft.

In total root avulsion, multiple nerve transfers first vs. FFMT reconstruction first is a subject of much debate (see Table 36.7). In the acute stage of BPI, using multiple nerve transfers to treat the total root avulsion, which is proposed by the author,⁴⁰ aiming to achieve a one-stage full reconstruction for shoulder, elbow, and hand functions, is a traditional strategy of proximal-to-distal reconstruction (Fig. 36.14). In these cases, FFMT is used as a secondary adjuvant reconstruction to enhance results at a later stage. Using FFMT to achieve hand function (finger extension and flexion) in the acute stage is a new strategy of distal-to-proximal reconstruction, proposed by Doi *et al.*,^{38,39} and is an alternative approach: A long FFMT (usually gracilis muscle) from the clavicle down to the extensor digitorum communis, innervated by the XI nerve, is performed in the first stage, followed by a second long FFMT

from the second rib to the flexor digitorum profundus, innervated by intercostal nerves in the second stage. In these cases, nerve reconstruction such as C5 transfer, contralateral C7 transfer, or intercostal transfer is an adjunctive procedure for shoulder function. The biggest remaining deficit in Doi's method is that the reconstructed patients had no or poor hand sensation. Comparison between multiple nerve transfers vs. FFMT to treat total root avulsion of BPI in the acute stage is illustrated in Table 36.7.

Pedicle muscle transfer (Video 36.2 ►)

Pedicle muscle transfer is indicated in non-global BPI such as C5–6 root avulsion with intact C7–T1. Local latissimus dorsi muscle transfer for elbow flexion or finger flexion, or even for shoulder abduction; local pectoralis major muscle transfer or local pectoralis minor transfer for elbow flexion; part deltoid transfer for elbow extension; and forearm muscle transfer for intrinsic palsy are examples of pedicle muscle transfer. Using a reinnervated muscle transfer as a pedicle muscle transfer is also an issue of debate. Preoperative muscle strength examination is very important. Before a reinnervated muscle can be used, it should be at least M4 muscle strength. Otherwise many of these transfers are useless and wasted. For example, using a local latissimus dorsi muscle transfer for elbow flexion in C5 and C6 (±C7) avulsion injury usually results in M3, but not M4 muscle strength, compared with latissimus dorsi transfer for the traumatic loss of biceps and brachialis, which always results in M4 muscle strength. The reason for this difference in outcome is the state of the thoracodorsal nerve, which originates from C6–8. In the former example, the thoracodorsal nerve is actually an injured




Fig. 36.13 Example of results of one-stage surgery for total root avulsion 5 years after (1) left contralateral C7 transfer to the median nerve using a vascularized ulnar nerve graft for finger flexion and sensation; (2) three intercostal nerves (T3–5) transfer to the musculocutaneous nerve for elbow flexion; and (3) phrenic nerve transfer to the suprascapular nerve for shoulder elevation. **(A)** Shows 90° shoulder elevation; **(B)** M4 elbow flexion; and **(C,D)** M3 finger flexion.



Fig. 36.14 A 17-year-old girl had left brachial plexus injury with total root avulsion. She received multiple nerve transfers simultaneously with right contralateral C7 transfer to the median nerve for finger flexion and sensation, three intercostal nerves (T3–5) transfer to the musculocutaneous nerve for elbow flexion, and spinal accessory nerve transfer to the suprascapular nerve and phrenic nerve transfer to the posterior division of the upper trunk for shoulder. **(A,B)** Results 5 years after showed good shoulder, good elbow, and acceptable hand function and sensation.

nerve, but in the latter example of traumatic muscle loss, the thoracodorsal nerve is an uninjured one. Local pedicled muscle transfer, although an alternative restorative option, is often not reliable due to the presence of a partial nerve injury.

Functioning free muscle transplantation (FFMT)

FFMT is the transfer of a muscle utilizing microvascular anastomoses for revascularization and microneural coaptation to the recipient motor nerve for reinnervation. The use of FFMT in brachial plexus reconstruction is one example of the application of nerve transfer (including extraplexus, intraplexus, and closed-target nerve transfer).^{39,41} It has been shown to be effective and has become increasingly popular. The gracilis myocutaneous FFMT is the most common and best choice of donor muscle in brachial plexus reconstruction. The commonly used donor nerves include the XI, the intercostal, the Ph nerve, the CC7 nerve, part of the ulnar nerve, part of the median nerve, or more proximally from the infra- or supraclavicular nerve, which requires nerve elongation (with a nerve graft in the first stage) and then FFMT in a two-stage procedure. The results from FFMT are more satisfactory than those achieved with a local muscle transfer. It is especially useful for elbow and hand function restoration in global plexopathy. Indications for FFMT in BPI include acute or chronic root avulsion, root injury with failed nerve transfer (muscle strength less than M3), or BPI with associated Volkmann's contracture of the forearm.

Level II injury

Level II injury is defined as an injury distal to the dorsal root ganglion (or outside the intervertebral foramen) but between the scalene muscles and proximal to the suprascapular nerve. If the suprascapular nerve is intact, the lesion will be in level III–IV and not in level II. The incidence of a pure level II injury is approximately 8%. Disruption of the spinal nerve with neuroma formation and dense scar tissue involving the scalene muscles (especially the middle scalene muscle) are the main findings in this type of injury. Nerve rupture may occur at one or multiple spinal nerves. The clinical differential diagnosis between preganglionic root (level I) and postganglionic spinal nerve (level II) injury is of great importance with regard to the surgical approach and prognosis. Reconstruction for this level of injury includes neurolysis, nerve repair, nerve grafts, and nerve transfer if associated with level I lesion in other spinal nerves, and palliative reconstruction.

Level III injury

Level III injury involves the trunks and divisions. In the author's series, only 5% of patients were injured purely in this zone. Nerve rupture with neuroma formation and dense scars were the most common findings. Bypass nerve grafting is required to re-establish the connection between the supra- and infraclavicular brachial plexus. A clavicle osteotomy is often required for wound exposure, especially for injuries involving the lower trunk, to allow grafting or direct neurolysis. Multiple nerve grafts are required and need to be harvested from different locations. A C-loop vascularized ulnar nerve graft is sometimes helpful to reduce the amount of nerve grafts, especially in cases of extensive injury.

Level IV injury

Level IV BPI involves the cords and their terminal branches. The incidence is high (17%), second after level I injury. Level IV injury is commonly limited to this zone only and rarely has proximal level involvement. Level IV injuries are mostly encountered with nerve ruptures and rarely with nerve avulsion. Any nerve avulsion here is distal avulsion at the bone margin (suprascapular nerve avulsion at the scapular notch, or axillary nerve at the humeral neck, or radial nerve at the spinal canal inlet), or at the muscle attachment (such as the musculocutaneous nerve from the biceps surface). In closed level IV injury, the nerve damage is variable, ranging from simple isolated nerve injuries (axillary, musculocutaneous, or radial nerve) to lesions of all cords or all terminal branches. Level IV injury has particular characteristics with specific challenges in surgical dissection and repair due to dense scarring. Nerve grafts are more frequently used with less aberrant reinnervation and better prognosis. There is a high incidence of vascular injury, rupture or segmental occlusion of the subclavian or axillary artery – about 30%. For ease of dissection, detachment of the insertion of the pectoralis major muscle by Z-lengthening incision is often required. For penetrating injuries, vascular and nerve repairs are usually performed simultaneously.

The golden time for primary direct repair of a divided nerve without nerve grafts in penetrating injury is within 2 weeks. Traction injuries in level IV are usually associated with fracture of the proximal humerus or the glenoid scapula. The nerve segments have been extensively damaged. Long nerve grafts are usually required to bridge the nerve gap, commonly more than 8 cm in length. Sometimes a C-loop vascularized ulnar nerve graft is harvested from the paralyzed forearm and utilized for median and radial nerve reconstruction. The results are usually good. In nerve avulsion from the muscle, nerve grafting of the proximal nerve stump and direct implantation into the muscle (nerve-to-muscle neurotization) yield fair results (around M3). As described previously, FFMT is another option of reconstruction for such cases.

Postoperative management and rehabilitation

Immediate postoperative splinting for 3 weeks is required after nerve grafts or nerve transfer. Thereafter, retraining and rehabilitation should start, including physiotherapy (to avoid joint stiffness), muscle stimulation (to delay muscle atrophy), brain cognition, biofeedback, and occupational therapy.

Patients should be followed periodically by the surgeon (every 3–4 months) and the physical therapist (twice a month). Patients are encouraged to have electric muscle stimulation at home (twice a day). In cases of intercostal nerve transfer, passive shoulder elevation remains restricted to less than 90° for 6 months. Regular follow-up in the rehabilitation center and outpatient clinic is tremendously important, and should be explained to patients before and emphasized again after surgery.

Induction or motivation exercise is an important muscle exercise for patients with nerve transfer and/or functioning free muscle. The original function of the donor nerve must be practiced to induce movement in the target muscles newly innervated by the transfer. For example, patients who have undergone intercostal nerve transfer must increase their

deep-breathing rate to induce movement in their target muscles. An induction exercise is commenced when movement of the innervated muscles is palpable (M1). The action is comparable to an internal electric stimulator. Various nerve transfers have different induction exercises.³³ Realizing the importance of these exercises is crucial. This explains why good results are commonly achieved by psychologically strong and ambitious patients who cooperate well in terms of their rehabilitation program, while poor results are often obtained by uncooperative patients. Permanent external orthosis to extend the interphalangeal joints of the fingers is always required for intrinsic palsy of the hand to improve the final result of surgical reconstruction and long rehabilitation programs.

Palliative reconstruction for sequelae deformities (Video 36.1 ▶)

Palliative reconstruction procedures include local muscle or tendon transfer, FFMT, tenodesis, and arthrodesis, or alternatively the use of orthotics and prosthetics. Palliative reconstruction can be considered when the injury involves C8 and T1 level (Klumpke's palsy in adults), or when deformities persist after maximum recovery either with or without nerve reconstruction.

Outcome evaluation (Videos 36.4, 36.5, 36.7 ▶)

Although the British MRC scale provides the possibility of homogeneity and consensus in motor evaluation, a considerable degree of heterogeneity exists in the evaluation of functional recovery of the shoulder, elbow, and digits. In the author's opinion, establishing an international consensus on motor evaluation of different movements is vital and imperative for the advancement of our understanding and mutual comparison. The British MRC scheme is used for individual muscle evaluation in plexus injuries, or for evaluation of the transferred muscle in FFMT. Both are evaluated by target joint movement.

Conclusion

Closed traction injuries of the brachial plexus are devastating injuries. For someone who has nothing, a little is a lot. Patients, especially those with total root avulsion, should be encouraged to recognize their disabilities and make use of the regained but not completely recovered limb. This may be shoulder elevation of 60°, M4 elbow flexion strength, and M2–3 strength of finger flexion following reconstruction. In a failed reconstruction, or if the patient perceives the injured limb as a useless dead weight, amputation may be considered as a last option.

Future directions

- Endoscopic-assisted and/or robot-assisted surgery for brachial plexus reconstruction.
- Unifying the level of brachial plexus injuries from level I–IV.
- Unifying outcomes evaluation in a simple, straightforward manner.
- Increasing the accuracy of MRI studies for diagnosis and evaluation.

Pediatric brachial plexus injury (obstetric brachial plexus palsy)

Key points

- OBPP has significant differences from adult BPI, including mechanism of injury, classification of injury, clinical evaluation, intraoperative findings, reconstructive strategy, postoperative rehabilitation and follow-up, result assessments, and pain character. It therefore presents as a separate entity (see Table 36.1).
- OBPP has two distinct phases: (1) infant OBPP (I-OBPP); and (2) sequelae OBPP (S-OBPP). Both have significant differences in management and prognosis, and will be discussed separately.
- I-OBPP includes risk factors, clinical presentation, preoperative evaluation, timing of nerve surgery, surgical exploration of the brachial plexus, reconstructive strategies for nerve surgery, postoperative management, and outcomes assessment.
- S-OBPP includes aberrant reinnervation, shoulder reconstruction, elbow reconstruction, and forearm and hand reconstruction.

Introduction

Clinical tips

- OBPP is an obstetric trauma; risk factors include overweight babies (>4000 g) in cephalic presentation, underweight babies (<2500 g) in breech presentation, or fetal distress (such as septicemia) with loss of protective muscular tone during Caesarean section.
- Infant OBPP focuses on nerve surgery, timing of surgery, and results from nerve surgery.
- Sequelae OBPP focuses on palliative reconstruction for shoulder, elbow, and hand deformities.

There are different but similar terms being used to describe pediatric brachial plexus injury in the literature, such as obstetric (or obstetrical) brachial plexus palsy (OBPP),⁴² neonatal brachial plexus palsy (NBPP),⁴³ or brachial plexus birth palsy (BPBP).⁴⁴ In this chapter, pediatric brachial plexus injury is termed OBPP for obstetric brachial plexus palsy.

OBPP almost always results from traumatic delivery, although some other possible causes have been mentioned.⁴⁵ Overweight babies (>4000 g) in cephalic presentation, underweight babies (<2500 g) in breech presentation, and fetal distress (such as septicemia) with loss of protective muscular tone during Caesarean section are all susceptible to brachial plexus injury following delivery. It is caused by traction force during delivery, which widens the angle between neck and shoulder and induces the plexus nerves damage. The term “palsy”, not “injury” as in adult BPI, has been used to describe pediatric BPI from a very early point in the literature, in 1872, by Duchenne.⁴⁵

There are many differences between OBPP and adult BPI (see Table 36.1). The incidence of stretch (neurapraxia or axonotmesis) and incomplete rupture are more common in OBPP than in adult BPI in which complete rupture or avulsion is often seen. Often there is paresis (incomplete paralysis) rather than flaccid paralysis (complete paralysis) in OBPP. Even when there is complete rupture, the gaps are short and spontaneous regeneration is still possible; while in adult brachial plexus injury the gaps are long and the scars are dense which make spontaneous regeneration impossible. In OBPP, most are Erb's palsy (upper plexus injury), and the lesion is always supraclavicular. Mixed complex neuroma of the upper and middle trunk is frequently seen, and motor recovery with misdirection (or aberrant reinnervation) often occurs in OBPP, particularly in the muscles innervated by the upper and middle trunks. Aberrant reinnervation causes abnormal co-contraction of multiple muscles, especially in the shoulder and elbow. Aberrant reinnervation diminishes function significantly, even in those patients considered to have had complete spontaneous recovery. This is why consequent deformities develop in OBPP and many require reconstruction. In adult BPI, the location of injury varies. Aberrant reinnervation occurs only in cases of penetrating injury of the upper trunk where trunk to trunk repair is performed directly or indirectly with short nerve grafts. Recovery after nerve reconstruction is generally slow in OBPP. Improvement continues for at least 3 years. Poor cooperation and rehabilitation may be a factor. The most improved period after nerve reconstruction is at 3 years of age. This is why second reconstruction is always performed after the age of 4 years. Regarding sensation recovery, it usually greatly exceeds that of muscle and sympathetic function. Central plasticity may be a factor. OBPP patients always show remarkable absence of neuropathic pain.

For the purpose of treatment, OBPP can be subdivided into two distinct phases: (1) I-OBPP, and (2) S-OBPP (or late OBPP with deformity).⁴⁶ These patients may present at any time and have a wide variation in clinical presentation. All stages have different management and prognosis. I-OBPP refers to the infant's brachial plexus that has been paralyzed following delivery. Some require early nerve surgery and some do not. Reconstruction is focused on primary nerve surgery, in which timing of intervention and results of nerve surgery are a concern. S-OBPP refers to the sequelae deformities resulting from I-OBPP with or without previous nerve surgery. Many S-OBPP patients request surgical correction for the shoulder, elbow, forearm, and hand.⁴⁷⁻⁴⁹ Reconstruction in sequelae OBPP is focused on palliative surgeries on bone or joint, tendon or muscle, and no longer on nerve surgery of the brachial plexus.

Infant obstetric brachial plexus palsy

Although the evolution of microsurgical nerve repair has significantly allowed surgeons to perform early intervention for I-OBPP, many rehabilitation therapists⁵⁰⁻⁵¹ and even some surgeons⁵²⁻⁵³ continue to argue against early nerve surgery. Arguments against early surgery include high rates of spontaneous recovery (70-92% in the literature), high risks of surgery and postoperative care at an early age, and lack of significant functional improvement. Nevertheless, following developments in operative magnification (loupe and

microscope), refinements in nerve grafting and nerve transfer, understanding of the brachial plexus anatomy, and pathophysiology of nerve degeneration and regeneration, more microsurgeons⁵⁴⁻⁵⁸ have begun to choose early nerve surgery as the treatment of choice for I-OBPP. This group found that the rate of spontaneous recovery was actually low (7-50%), and early nerve surgery may potentially decrease or eliminate the late sequelae. The results from the author's series⁵⁸ prove that early nerve surgery, when indicated, is still the treatment of choice for I-OBPP patients. In addition, the reconstructions performed in the late group were found to be difficult, and required complex procedures to achieve reasonable results.⁴⁷⁻⁴⁹

Risk factors for I-OBPP during cephalic delivery include high birth body weight (>4000 g), shoulder dystocia, cephalopelvic disproportion, forceps or vacuum suction delivery, or poor technique of delivery. I-OBPP may also occur during difficult breech presentation or in fetal distress (such as septicemia) during Caesarean section. Associated injuries with birth palsy can be seen, including fracture (ipsilateral or contralateral clavicle, humerus, femur, or ribs), respiratory insufficiency (asphyxia) due to diaphragm palsy, ecchymosis (neck, chest, face, or upper back), and wry neck (torticollis). Although the cause of I-OBPP is still a subject to debate (some believe it can be of intrauterine origin), the author believes that it is caused by obstetric trauma and not due to intrauterine compression neuropathy. All of the author's intraoperative findings in I-OBPP have been similar to adult brachial plexus traction injury (avulsion, rupture with neuroma and mixed with muscles), not like pictures of compression neuropathy that presents with pseudoneuroma and are rarely mixed with muscle fibers.

Clinical presentation

Determining the relationship between I-OBPP and S-OBPP and predicting the progressive changes in I-OBPP with age is a great challenge.⁴⁶ Different surgeons have different opinions about the clinical presentation of I-OBPP. In general, there are five types of clinical presentation in I-OBPP: type 1 (or Erb's) palsy, which involves deficits of C5 and C6, resulting in a posture of shoulder abduction or internal rotation, elbow extension, and forearm pronation (Fig. 36.15A,B); type 2 (or extended Erb's) palsy, which extends further deficits to C7 or C8, resulting in a posture of type 1 with wrist flexion (waiter tip deformity); type 3 and 4 palsies involving the entire plexus (global palsy), resulting in a flail arm without or with a Horner's syndrome, respectively; and type 5 (or Klumpke) palsy, which involves an isolated lower plexus, resulting in only a paralyzed hand (Fig. 36.16A,B). In unoperated cases, type 1 or 2 is much more common than type 3 or 4. But in operated cases, it is reversed: global palsy is more common than Erb's. Type 5 palsy is rarely seen, only in about 1%. In about 1% of I-OBPP cases, the injury is bilateral but predominantly on one side, and it is frequently seen in breech delivery or Caesarean section with fetal distress.

Clinical examination

Newborns are difficult to examine thoroughly. A precise muscle or sensory examination of an infant is impossible. The evaluation chart used for adult BPI (see Fig. 36.5) is not



Fig. 36.15 (A) A 2-month-old infant showed improving shoulder abduction of his right upper limb; (B) A 3-month-old infant showed improving elbow flexion of her right upper limb. Both were type 1 OBPP with no need for primary nerve surgery.

practical. Evaluation should include parents' observation at home, especially during bathing or dressing, and the examiner's observation in clinic. The infant is placed in the lateral decubitus position with the normal side down. The examiner then tickles the baby (tickling test, Fig. 36.17A), or covers the infant's face with a towel (towel test, see Fig. 36.17B) and uses this to evaluate dynamic movements of the infant's shoulder, elbow, and hand. An M2 (movement with weight eliminated) muscle strength score in a newborn infant is sufficient to predict a good result when the infant grows. In I-OBPP, there is no need to see M4 or M5 muscle strength as in adult BPI. Horner's syndrome with signs of ptosis or miosis may disappear with time, indicating that the T1 has a stretch but not an avulsion injury, or that T1 has a good connection with T2 (postfixed brachial plexus). An ipsilateral clavicle fracture is

usually a good prognostic sign due to traction force divergence. However, a contralateral clavicle fracture is usually a bad prognostic sign as this indicates a high energy traction force. Ideally the infant should be followed up after birth and then at 1-month intervals until the decision to operate or not is made.

Neurophysiologic studies are not performed routinely. EMG in I-OBPP is usually positive and too optimistic, and may not be accurate enough to predict useful function. Even intraoperative EMG can be misleading. Improving techniques of MRI are now useful to evaluate level I and II lesions as in adult BPI, and are becoming the author's routine investigation for preoperative imaging (Fig. 36.18A–D). CT myelogram can also be useful.

Timing of surgery

Gilbert⁵⁹ recommends surgical intervention for infants without evidence of elbow flexion by 3 months. Terzis and Papakonstantinou⁶⁰ emphasize that the presence of total palsy with Horner's syndrome warrants earlier surgical intervention at



Fig. 36.16 (A,B) A 4-year-old girl shows isolated type 5 (Klumpke) palsy of her right upper limb.



Fig. 36.17 (A) The tickling test; and (B) the towel test to examine the I-OBPP.

2 months of age. Clarke and Curtis⁶¹ advocate that failure to perform a “cookie test”, to place a cookie in the mouth by 9 months of age is an indication for exploration. Our results⁵⁸ indicate that shoulder and elbow recovery were not different when surgery was performed at 2 months or at 11 months of age. Even patients who received primary nerve surgery beyond 1 year of age also showed significant improvement in shoulder and elbow function, but no improvement at all in hand function. In addition, our previous results showed similar improvement of shoulder function in late palliative reconstructions for late OBPP patients compared to those who underwent primary early nerve surgery for I-OBPP.⁴⁷ However, recovery of hand function with secondary reconstructive methods was far inferior to those who had early nerve surgery for hand function.⁴⁹ The ideal opportunity for improving hand function is by performing nerve surgery early. Our results demonstrate that Gilbert’s “rule of 3 months” overestimates the poor results of shoulder and elbow function. However, Clarke and Curtis’s “rule of 9 months” underestimates the poor results of forearm and hand function. The presence of poor shoulder and elbow function in I-OBPP is not an urgent indication for surgery. However, hand palsy is an urgent condition, indicating early surgical intervention. Therefore, our recommended timing of surgery falls between that of Gilbert and Clarke. A global palsy with absence of

biceps function and little or no hand function is an indication for early exploration within 3 months. However, in the presence of wrist extension and finger flexion, an additional 3 months of observation is recommended. If by 6 months of age there continues to be no improvement in elbow flexion, then exploration is indicated. If poor shoulder or elbow function persists by 1 year of age, surgery is indicated too. However, poor hand function at this late age is not an indication for exploration as it is too late. The observation of M2 wrist extension or interphalangeal extension on clinical examination may imply that C7 may be injured (more often with avulsion), but C8 and T1 are intact, warranting an additional 3-month period of observation until the child reaches 6 months.

Preoperative preparation

Treating an OBPP patient is treating the whole family. A thorough explanation of the risks and benefits of surgery to the patient’s family is very important, including preoperative diagnosis, surgical risks, postoperative care and rehabilitation, long-term follow-up, possible outcomes, and possible subsequent operations. After intubation, central venous pressure and arterial lines with long catheters should be secured in the femoral vessels. Those two vessel lines are crucial during the operation and for the first 3 days of postoperative care.

Surgical technique

Incision lines, dissection, and brachial plexus exploration are all similar to adult BPI, except:

1. The platysma in infants is very thin and sparse, resulting in an incision directly superficial to the surface of the sternocleidomastoid muscle.
2. The phrenic nerve should be isolated and well protected. Care should be taken during the operation to avoid excessive traction as this may prolong the extubation time due to transient palsy of the diaphragm.
3. All spinal nerves, C5–T1, should be identified and examined.
4. The scalenus anterior muscle is usually segmentally excised, permitting exposure of the level II spinal nerves and release of compression of the subclavian artery.
5. Lesion-in-continuity of the upper and middle trunks is commonly seen, requiring microneurolysis to evaluate the severity of scarring and judge the degree of nerve injury. If the scar is dense and the axis of the nerve (proximal and distal segments) are badly distorted, resection of the neuroma and nerve grafts are required.
6. When the lesions are more distal involving the divisions (level III injury), the incision is then extended to the deltopectoral groove, exposing Chuang’s angle (see Fig. 36.8). The supra- and infraclavicular fossa are connected by opening the space under the subclavius muscle. The clavicle can be elevated easily without clavicle osteotomy.
7. Nerve grafts are commonly harvested from the both sural and saphenous nerves. If necessary, medial cutaneous nerve of the arm, superficial radial nerve, and lateral antebrachii cutaneous nerve from the injured limb are other sources.




Fig. 36.18 A 3-month-old with I-OBPP: (A) T2 MRI, coronal view to locate the level of cervical spine; (B) MRI 3D, coronal view, T2 normal on right side; MRI 3D FIESTA and CPR techniques (C) ventral roots and (D) dorsal root showing left C7–C8–T1 root avulsion.

Reconstructive strategies

Two groups of spinal nerve injury are classified based on intraoperative findings: (1) pure rupture injury (40%, 47/118); and (2) rupture injury associated with root avulsion (60%, 71/118) (Table 36.8). C5 and C6 tend to be ruptured, but C8–T1 tend to be avulsed (Table 36.9). If C8 is avulsed alone, T1 tends to be avulsed too, but partially. Once C8–T1 two root avulsion occurs, a ruptured C7 tends to have more proximal avulsion injury too. In global palsy, incidence of three-trunk rupture is

about 5% (6/118). Preoperative MRI can be very helpful as a diagnostic tool to see level I or II injury.

Pure rupture injury

Except six patients who had rupture of all three trunks, the majority of patients (41/47, 87%) had rupture injury involving the upper and/or middle trunk. The reconstructive procedures consisted of microneurolysis and nerve grafts. Reconstructive strategies in these pure rupture injury groups varied

Table 36.8 Intraoperative findings of obstetric brachial plexus palsy (1992–2004, Chang Gung Memorial Hospital)

Findings	Number of patients (percent of total)
Ruptured injury alone	47 (40%)
Rupture of UT	17
Rupture of UT and MT	24
Rupture of UT, MT, and LT	6
Rupture and avulsion injury	72 (60%)
One-root avulsion	18
Two-root avulsion	28
Three-root avulsion	17
Four-root avulsion	9
Total	119
UT, Upper trunk; MT, middle trunk; LT, lower trunk.	

based on intraoperative findings and judgment. The majority of patients received C5 nerve grafting to the suprascapular nerve and posterior division of the upper trunk for shoulder, and C6 nerve grafting to the anterior division of the upper trunk for elbow function instead of proximal upper trunk nerve grafting to the distal upper trunk (Table 36.10). Four to six cable nerve grafts (2–3 cm in length) are usually required for coaptation. A ruptured C7 has a high incidence of accompanying avulsion. The proximal stump of C7 was therefore routinely repaired to the distal stump of C7 via nerve grafts. There were few patients who received longer nerve grafting (4–6 cm in length) from supraclavicular spinal nerves to the infraclavicular selected target nerves (posterior and lateral cord). Table 36.10 shows our reconstructive strategies for pure rupture injury.

Rupture injury associated with root avulsion

A total of 72 patients (60%) were included in this series. Once avulsion occurs, it tends to involve at least two roots (75%). This type of reconstruction depends on the number of root avulsions, and the remaining proximal neural resources. In global palsy, restoration of hand function becomes the first priority, followed by elbow flexion and then shoulder function (Table 36.11). In I-OBPP, C5 is usually ruptured, not avulsed (see Table 36.9). The proximal C5 stump can be a source for selective neurotization to the C8 or lower trunk

Table 36.9 Incidence of type of injury on different spinal nerves (1992–2004, Chang Gung Memorial Hospital)

	Rupture	Avulsion
C5	117	12
C6	95	42
C7	49	79
C8	9	71
T1	8	39

Table 36.10 Reconstructive strategies for isolated rupture injury

Trunk rupture	Nerve reconstructive strategy
Upper trunk	C5-ng-SS and PD C6-ng-AD
Upper and middle	C5-ng-SS and PD C6-ng-AD C7-ng-C7
Upper and middle and lower	C5-ng-SS and PD C6-ng-AD C7-ng-C7 LT-ng-LT
UT, Upper trunk; ng, nerve graft; SS, suprascapular nerve; PD, posterior division; AD, anterior division of the upper trunk; LT, lower trunk.	

(intraplexus neurotization). The frequency of nerve transfers increases if associated root avulsion increases, including intercostal nerve transfer for elbow or finger flexion, XI nerve transfer for the shoulder, or intraplexus transfer from C5 or C6 to the C8 or median nerve for hand function in three- or four-root avulsion. Intercostal nerve transfer, either to the musculocutaneous nerve for elbow, or to the median nerve for hand function, is an effective procedure in infant patients (much better than in adults). Few patients need contralateral C7 transfer,⁴⁰ branch of ulnar nerve transfer (Oberlin method⁶²) or combined branch of median nerve transfer (Mackinnon method⁶³). Table 36.11 shows our reconstructive strategies for rupture injury associated with root avulsion.

In this series of patients, 10 cases of I-OBPP were operated on late, at 1 year of age or older (range, 1 year to 2 years 6 months). Most of these patients showed poor spontaneous recovery of shoulder and/or elbow function prior to surgery. Primary nerve surgery for these late operative cases showed encouraging results in shoulder and elbow function recovery, but few gained recovery of hand function.

Postoperative management

A rigid premade neck splint is placed on every patient immediately postoperatively (Fig. 36.19). Total operative time is on average 8 h, with a range of 6–10 h. Postoperatively the patient is transferred to the intensive care unit after extubation. The patient is cared for in the head-up position to avoid dyspnea due to any temporary palsy of the diaphragm. The patient is kept in the intensive care unit for 3–5 days, and then transferred to the general ward for an additional 2 days. Total hospitalization is approximately 1 week.

The neck splint is kept in place for 4 weeks. Follow-up at regular intervals (the first month postoperatively and then every 4 months afterwards) is performed for a minimum of 4 years. Home electrical muscle stimulation (twice daily for 15–20 min each time) is started 4 weeks after surgery and performed for approximately 1 year or until muscle function reaches M2 level.

There are two important exercises for prevention of shoulder adduction contracture: pull-up bar exercise (stretching exercise), and swimming (dynamic exercise), where both upper limbs are exercised simultaneously.

Table 36.11 Nerve reconstructive strategy for rupture injury associated with root avulsion

Root avulsion		Nerve reconstructive strategy		
		For shoulder	For elbow	For hand
One	C5	XI-SS	C6-ng- (major) AD and (minor) PD	
	C7	C5-ng-SS and PD	C6-ng- AD	C5, C6 (minor)-C7
	C8	C5-ng-SS and PD	T3–5 ICN-MCN	C6-ng-C8 (C7-ng-C7)
	T1	C5-ng-SS and PD	C6-ng-AD	C7-ng-C7; C8-ng-C8
Two	C5 and C6	XI-SS	T3–5ICN-MCN	C8-ng-C8
	C6 and C7	XI-SS	C5-ng-C6	C6-ng-C8
	C7 and C8	XI-SS	T3–5ICN-MCN	C6-ng-C8 (or median)
	C8 and T1(8)	XI-SS	T3–5ICN-MCN	(C7-ng-C7)
Three	C5–7	XI-SS	T3–5ICN-MCN	
	C6–8	XI-SS	T3–5ICN-MCN	C5-ng-median
	C7, C8, and T1	C6-ng-SS and PD	T3–5ICN-MCN	C5-ng-median
Four	C6–T1	C5-ng-SS and PD	T3–4 ICN- MCN	T5–7ICN-median
		C5-ng-SS and PD	T3–5ICN-MCN	CC7T-ng-C8

XI, Spinal accessory nerve; ng, nerve graft; SS, suprascapular nerve; ICN, intercostal nerve; MCN, musculocutaneous nerve; PD, posterior division; AD, anterior division of the upper trunk.

Outcome assessment

There is a lack of consensus with regard to the optimal method of assessing results. This is partly due to the complexity of the lesions (i.e., aberrant reinnervation), complexity of the repair (i.e., different surgical strategies), complexity of limb involvement (shoulder, elbow, forearm and hand), and finally the young age of the patients, which makes cooperation difficult. The reported methods of functional assessment include MRC muscle grading system, Gilbert and Tassin muscle grading system, Clark and Curtis active movement scale, Narakas' grading system, and others.^{42–45} All patients should be followed for a minimum of 4 years. The results are categorized as “good”, “fair”, or “poor” based on the degree of shoulder abduction, external rotation, elbow flexion and extension, and finger flexion (Table 36.12).

Results

Our overall results in C5 nerve grafting, especially to the suprascapular nerve and posterior division of the upper trunk for shoulder, and C6 nerve grafting to the anterior division of

the upper trunk for elbow function were consistently good (Fig. 36.20A–D); shoulder abduction averaged 132° (90–180°), shoulder external rotation averaged 67° (50–90°) and elbow flexion was mostly M3. More than half of the patients (71/118, 60%) had rupture injury associated with at least one nerve root avulsion. Seventy-five percent had at least two-root avulsion. Intraplexus nerve transfer from C5, or C6 to the C8 or to the median nerve resulted in improvement of hand function. Extraplexus nerve transfer by intercostal nerve transfer to the musculocutaneous nerve or median nerve, and spinal accessory nerve transfer to the suprascapular nerve have proved useful for restoring shoulder abduction, elbow and finger flexion (Fig. 36.21A–E).

The sequelae of obstetric brachial plexus palsy

Aberrant regeneration (due to misdirection of regenerated axons), muscular imbalance, and growth are the three main causes of shoulder and elbow deformity in I-OBPP with or without nerve surgery. Flaccid paralysis of the shoulder and

Table 36.12 Postoperative functional assessment of obstetric brachial plexus palsy

	Good	Fair	Poor
Shoulder			
Shoulder abduction	>120°	90–120°	<90°
Shoulder external rotation	>90°	60–90°	<60°
(Hand to occiput movement)	(Occipital line)	(Ear line)	(Preface or prechest)
Elbow			
Hand to mouth movement	Easy (M=3)	Difficult (M=2)	Impossible (M<2)
Elbow extension	Easy (M=3)	Difficult (M=2)	Impossible (M<2)
Finger			
Finger flexion	Easy (M=3)	Difficult (M=2)	Impossible (M<2)



Fig. 36.19 (A,B) Postoperative neck splint.

elbow is rare, but flaccid paralysis is commonly seen in the hand due to root avulsion of C7–T1 without aberrant regeneration. Aberrant reinnervation more frequently occurs in the shoulder and elbow and less in the hand. Therefore contractures (or hypertrophy) of the teres major, pectoralis major, brachialis and biceps muscles are frequently seen and cause the deformity of the shoulder and elbow. In addition, growth is another factor in shoulder and elbow deformities, often found in the form of concomitant skeletal deformity.

There are four main types of co-contractions resulting from aberrant reinnervation causing different types of deformities of the shoulder and elbow:

1. Co-contraction can occur between shoulder abductors (supraspinatus, infraspinatus and deltoid) and adductors (mainly, teres major and pectoralis major). This will result in limitation of shoulder elevation. Shoulder adduction contracture (or internal rotation) will develop when growing.
2. Co-contraction between elbow flexors (biceps and brachialis) and elbow extensors (triceps) can also develop. In the mild type, patients are unable to perform elbow flexion normally, such as pulling up trousers, hand-to-flank or hand-to-spine movement. In the severe type, patients cannot even perform hand-to-mouth movement. Flexion contracture of the elbow eventually develops.
3. Co-contraction between elbow flexors (mainly brachialis) and shoulder abductors (mainly deltoid) is a third possible occurrence. When asked to perform hand-to-mouth movement, the shoulder will be involuntarily elevated, similar to blowing a trumpet (trumpet sign). With this deformity, if the arm-to-body angle is less than 40° , mild cross-innervation is present; if the angle is more than 80° , severe cross-innervation is predicted.
4. Co-contraction among shoulder abductors, elbow flexors, and forearm flexors is the last possibility. When asked to perform shoulder elevation, the elbow and fingers flex involuntarily.

A special chart for S-OBPP examination (Table 36.13) should be completed before planning the reconstructive strategy for the sequelae deformities of shoulder, elbow, and hand. For motor recovery with aberrant reinnervation, release of contracted muscles and augmentation of paretic muscles form the basis of surgical intervention.^{46,47}

Shoulder deformity reconstruction

Before 1968, palliative reconstruction for S-OBPP with shoulder deformity was focused on the anatomical deformity (subluxation or posterior dislocation of the shoulder). Osteotomy of the humerus, or release of the contracted internal rotator muscles (concept of muscle fibrosis due to delivery trauma), such as the subscapularis, pectoralis major, or long head of biceps^{64–66} was preferred, but the results were disappointing. These techniques improved only the patient's cosmetic appearance but not the function. Some authors performed local muscle transfer such as trapezius and levator scapulae muscle transfers to restore some shoulder abduction⁵⁶ using the concept of dynamic reconstruction for muscular imbalance. However, the concept of aberrant reinnervation has now been well accepted by the author as the main cause of shoulder deformity in S-OBPP.⁴⁷ All reconstructive methods should be aimed at minimizing the influence of aberrant reinnervation. If perioperative physical examination demonstrates the existence of muscle recovery by aberrant regeneration, the author's studies demonstrate the following procedures are good for shoulder abduction: (1) release of antagonistic muscles (pectoralis major and teres major muscles); (2) augmentation of paretic muscles (transferring teres major to the infraspinatus muscle, re-routing both ends of the clavicular part of the pectoralis major muscle laterally). In addition, latissimus dorsi transfer to the teres minor insertion (or lateral humerus) is good for shoulder external rotation. The ideal age for the reconstruction is between 4 and 10 years. The average shoulder abduction following the muscle transposition was 151° (i.e., average gain 77°), and that of external rotation was 72° (average gain 48°). Comparing with the S-OBPP patients who had no surgery and with early




Fig. 36.20 Example of rupture of upper and middle trunks. A 3-month-old infant had right brachial plexus injury (A), receiving nerve grafts from C5 to the suprascapular nerve and posterior division of the upper trunk for the shoulder, C6 to the anterior division of the upper trunk for the elbow, and C7 to C7 due to rupture injury of the upper and middle trunks without C8–T1 avulsion. Six years later she showed good shoulder abduction (B), good shoulder external rotation (C), and M4 elbow flexion (D) following one-stage early nerve surgery. There is no aberrant reinnervation between shoulder and elbow.

nerve surgery for the infant OBPP, the results of our reconstructive strategy for the shoulder appear to be significantly improved.⁴⁷

Elbow deformity reconstruction

The common deformities of the elbow in S-OBPP include: (1) aberrant reinnervation between elbow flexors and extensors, which causes weak elbow extension and weak elbow flexion; (2) aberrant reinnervation between shoulder abductors and elbow flexors, resulting in a severe “trumpet sign” with angle greater than 80° between the medial arm and trunk on hand-to-mouth movement; and (3) no motor recovery with muscle paralysis or paresis of biceps and brachialis muscles.⁴⁸ Traditionally, elbow flexion has always been top priority and triceps-to-biceps transfer is a commonly used method for

achieving elbow flexion. However, this results in loss of elbow extension, a significant functional problem for a growing child and one that is especially frustrating when shoulder elevation has been restored after shoulder correction. In addition, the loss of muscular imbalance at the elbow frequently leads to progressive flexion contracture (40°, range 30–70°) and/or dislocation at the elbow. Restoration of elbow extension following triceps-to-biceps transfer has been disappointing, whether performed by regional muscle transfer (such as latissimus dorsi transfer), or by free muscle transplantation. Because of these drawbacks, we have discontinued the use of the triceps-to-biceps transfer. For motor recovery with aberrant reinnervation between elbow flexors and extensors, reconstruction of elbow extension should precede that of elbow flexion. This is achieved either by biceps-to-triceps transfer with preservation of an intact brachialis muscle, or by



Fig. 36.21 Example of C5 rupture and C6–T1 root avulsion (**A**). A 3-month-old infant had right brachial plexus injury, receiving primary nerve surgery with nerve grafts from C5 to the surascapular nerve and posterior division of the upper trunk, nerve transfers from T3–4 two intercostal nerves to the musculocutaneous nerve for elbow, and T5–8 four to the median nerve. Seven years later he showed: (**B**) acceptable shoulder elevation, (**C**) M4 elbow flexion, and (**D,E**) M3 finger flexion.



brachialis-to-triceps transfer with preservation of an intact biceps when elbow shows flexion contracture.⁴⁸ Half of our patients can achieve acceptable elbow flexion and extension in a single-stage procedure. The other half require a second stage procedure, either by FFMT or by Steindler flexorplasty. Existence of brachioradialis muscle power is a determining factor. A powerful brachioradialis can decrease the need for the second procedure.

In patients with a paralyzed biceps due to C5–7 root avulsion, Steindler flexorplasty or FFMT⁶⁷ is the option for restoration of elbow function. When shoulder–elbow co-contraction is a major issue, the anterior half of the deltoid is transferred to the distal biceps tendon with a fascial lata graft for biceps augmentation to decrease the “trumpet angle”. However, patients with intrinsic deformities of the elbow joint (i.e., dislocation of the radial and/or ulnar head) are not good candidates for the above-mentioned regional elbow muscle transfer. Altered joint anatomy and abnormal joint biomechanics may create instability of the elbow joint, which contributes to untoward results in these patients. In patients with deformities of shoulder and elbow due to motor recovery by

aberrant regeneration, simultaneous reconstruction of the shoulder and elbow can be safely performed.

Forearm and hand deformity reconstruction

S-OBPP in the forearm and hand includes weakness or absence of wrist or metacarpophalangeal or interphalangeal joint extension; weakness or absence of finger flexion; forearm supination or less commonly pronation contracture; ulnar deviation of the wrist; dislocation of the radius or ulna; thumb instability; or sensory disturbance of the hand.⁴⁹ Palliative reconstruction of these forearm and hand manifestations is more difficult than for the shoulder or elbow because of the lack of powerful regional muscles for transfer. The phenomenon of aberrant reinnervation is less significant. Continuous physical therapy with a rehabilitation program to optimize the residual muscle strength in the forearm and hand is vital for later management. Surgical treatment is highly individualized. The optimal age for forearm and hand reconstruction is therefore usually later (school age, 6–13 years old) than for shoulder and elbow reconstruction (preschool years, 4–6 years old).

Table 36.13 Special chart for S-OBPP examination			
Name:		Chart no:	
Age:			
Address:			
Date of exam		History:	
Site of injury:		R	L
Shoulder function			
Shoulder abduction (deltoid, SS): _____ degree; M _____ (muscle strength)			
Cross-innervation: PM, TM (+ LD); biceps, triceps; forearm (flexors, extensors)			
Shoulder external rotation (IS, T minor): _____ (without support) _____ degree			
_____ (with support) _____ degree			
Shoulder internal rotation (PM, TM, subscapul): M _____			
Elbow function			
Elbow flexion (biceps, brachialis): M _____ ; degree _____			
Cross-innervation: deltoid, triceps, forearm flexors			
Brachioradials: M _____ ; triceps function M _____			
Forearm supination: _____ degree; forearm pronation _____ degree			
Hand to occipital (forearm pronation, elbow flexion, shoulder abduction and external rotation): pre-chest; pre-face; pre-ear; ear; postauricular			
Hand to mouth (forearm supination, elbow flexion, shoulder abduction and external rotation): Chest; chin; mouth			
Trumpet sign: marked (>80°); partial (40–80°); mild (<40°)			
Hand to abdomen (forearm neutral, elbow flexion, shoulder internal rotation):			
not possible	difficult	easy	
Hand to spine (forearm pronation, elbow flexion, shoulder post flexion and abduction):			
not possible	difficult	easy	
Hand to flank:			
not possible	difficult	easy	
Hand to object (forearm pronation, elbow extension, shoulder ant. flexion):			
not possible	difficult	easy	
Hand function			
Wrist extension: (ECRL, ECRB, ECU)			
Flexion: (FCR, PL, FCU, finger flexors)			
Finger extension (EDC): mass, individual; 2nd, 3rd, 4th, 5th			
Finger extension (intrinsic mm): 2nd, 3rd, 4th, 5th			
Finger flexion (FDS, FDP): active, passive; mass, individual; 2nd, 3rd, 4th, 5th			
Thumb: FPL			
EPL			
APL			
Lateral pinch (when pronated forearm) (ulnar)			
Opposition (median): partial, full			
Sensation disturbance ☐ No			
☐ Yes _____			
Others: Dislocation of shoulder, proximal radial head, proximal ulnar head, distal radials, distal ulna			
Contracture _____			
		Lesioned	Intact
Length:	Acromion–lateral epicondyle	_____	_____
	Lateral epicondyle–radial styloid	_____	_____
	Radial styloid long fingertip	_____	_____
Circumference:	Deltoid prominence	_____	_____
	Midarm	_____	_____
	Upper forearm prominence	_____	_____
	Midpalm	_____	_____
Planning:			

Multiple procedures for forearm and hand function are often performed. Sometimes they are done simultaneously with reconstructive procedures to improve shoulder and/or elbow function. Traditional tendon transfer techniques do not provide satisfactory reconstruction for these deformities. Many of the author's patients required more complex techniques such as FFMT^{67,68} to augment traditional techniques of tendon and/or bone management.

For wrist and metacarpophalangeal extension, powerful wrist or finger flexors and/or pronator teres can be useful donor muscles for flexor-to-extensor transfers. Sometimes two wrist flexors, flexor carpi radialis and palmaris longus, are woven together, becoming a more powerful unit, and are transferred to the extensor digitorum communis to achieve both wrist and finger extension. For forearm supination contracture, re-routing the biceps muscle, as described by Zancolli,⁶⁹ is effective for mild cases. For weakness or absence of finger flexion, wrist extensors are usually too weak to be transferred. FFMT for flexor digitorum profundus replacement using intercostal nerves as the donor nerve is required. Sensory disturbance of the forearm and hand in late obstetric brachial plexus palsy seems a minor problem and further sensory reconstruction is unnecessary.

Conclusions

In I-OBPP, early primary nerve surgery provides therapeutic advantages. Surgery within 3 months is strongly indicated in patients with total palsy, but only relatively indicated for

patients without elbow flexion but good hand function. Better results can be achieved when numerous short nerve grafts are used for rupture injuries. Cases associated with multiple root avulsions benefit from intraplexus nerve transfer for hand function and extraplexus nerve transfer for shoulder and/or elbow function. This approach affords patients a one-stage functional reconstruction of the upper limb. In S-OBPP, secondary reconstruction for shoulder and elbow deformities can achieve acceptable function. For forearm and hand, surgical treatment and result are highly individualized, and multiple procedures are often required.

Future directions

- A change in the reconstruction priority may become evident. Since the use of FFMT for biceps replacement is much easier and more effective than for triceps replacement^{41,67} in the later reconstruction, the reconstruction priority for I-OBPP may be changed. Restoration of hand function should become the first priority, followed by shoulder function and then elbow flexion. This is different from adult BPI in which elbow flexion is always the first priority for restoration.
- The classification of I-OBPP will need consensus.
- Endoscopic or robot-assisted diagnosis of I-OBPP injury at very early stage may triage treatment.
- Early nerve surgery on more selective patients may be recommended.



Access the complete reference list online at

<http://www.expertconsult.com>

2. Slingluff CL, Terzis JK, Edgerton MT. The quantitative microanatomy of the brachial plexus in man. Reconstructive relevance. In: Terzis JK, ed. *Microreconstruction of Nerve Injuries*. Philadelphia, PA: WB Saunders; 1987:285. *This is an important article because quantitative microanatomy of the brachial plexus is described. Many questions related to brachial plexus anatomy are answered.*
6. Ferrante MA. Electrodiagnostic assessment of the brachial plexus. *Neurol Clin*. 2012;30:551–580. *This article presents important and useful concepts of electrodiagnosis for BPI.*
8. Alnot JY. Traumatic paralysis of the brachial plexus: preoperative problems and therapeutic indications. In: Terzis JK, ed. *Microreconstruction of Nerve Injuries*. Philadelphia, PA: WB Saunders; 1987:331. *The author describes brachial plexus injury in detail, including anatomy, diagnosis, and treatment. For a young surgeon who is interested in brachial plexus treatment, this is an excellent article to read and understand.*
9. Chuang DCC. Adult brachial plexus injuries. In: Mathes SJ, Hentz VR, eds. *Plastic Surgery*. Philadelphia, PA: Saunders Elsevier; 2006:515. *The author describes brachial plexus injury in great detail including anatomy, diagnosis, treatment, and conclusion. There are multiple useful surgical tips. For a beginner who is interested in brachial plexus treatment, this is a good article to read in order to gain confidence.*
14. Chuang DCC. Adult brachial plexus reconstruction with the level of injury: review and personal experience. *Plast Reconstr Surg*. 2009;124(suppl):e359–e369. *This article presents a simple classification system in terms of numbered levels. This easy system may become a universal classification of brachial plexus injury.*

References

- Leffert RD. Brachial plexus. In: Green D, ed. *Operative Hand Surgery*. 3rd ed. New York, NY: Churchill Livingstone; 1993:1483.
- Slingluff CL, Terzis JK, Edgerton MT. The quantitative microanatomy of the brachial plexus in man. Reconstructive relevance. In: Terzis JK, ed. *Microreconstruction of Nerve Injuries*. Philadelphia, PA: WB Saunders; 1987:285. *This is an important article because quantitative microanatomy of the brachial plexus is described. Many questions related to brachial plexus anatomy are answered.*
- Narakas A. Surgical treatment of traction injuries of the brachial plexus. *Clin Orthop*. 1978;133:71–90.
- Krakauer JD, Wood MB. Adult injuries and salvage. In: Peimer CA, ed. *Surgery of the Hand and Upper Extremity*. New York, NY: McGraw-Hill; 1996:1411.
- Terzis JK, Verkris MD, Soucacos P. Outcomes of brachial plexus reconstruction in 204 patients with devastating paralysis. *Plast Reconstr Surg*. 1999;104:1221–1240.
- Ferrante MA. Electrodiagnostic assessment of the brachial plexus. *Neurol Clin*. 2012;30:551–580. *This article presents important and useful concepts of electrodiagnosis for BPI.*
- Millesi H. Brachial plexus lesions: classification and operative technique. In: Tubiana R, ed. *The Hand*. Philadelphia, PA: WB Saunders; 1988:645.
- Alnot JY. Traumatic paralysis of the brachial plexus: preoperative problems and therapeutic indications. In: Terzis JK, ed. *Microreconstruction of Nerve Injuries*. Philadelphia, PA: WB Saunders; 1987:331. *The author describes brachial plexus injury in detail, including anatomy, diagnosis, and treatment. For a young surgeon who is interested in brachial plexus treatment, this is an excellent article to read and understand.*
- Chuang DCC. Adult brachial plexus injuries. In: Mathes SJ, Hentz VR, eds. *Plastic Surgery*. Philadelphia, PA: Saunders Elsevier; 2006:515. *The author describes brachial plexus injury in great detail including anatomy, diagnosis, treatment, and conclusion. There are multiple useful surgical tips. For a beginner who is interested in brachial plexus treatment, this is a good article to read in order to gain confidence.*
- Narakas AO. Lesions found when operating traction injuries of the brachial plexus. *Clin Neurol Neurosurg*. 1993;95(suppl):S56–S64.
- Mackinnon SE, Dellon AL. *Surgery of the Peripheral Nerve*. New York, NY: Thieme; 1988:427.
- Boome RS. Practical anatomy, clinical assessment, and surgical exposure. *Hand Upper Extremity*. 1997;14:9.
- Sunderland S. Brachial plexus injuries. *Clin Neurol Neurosurg*. 1993;95(suppl):S1–S2.
- Chuang DCC. Adult brachial plexus reconstruction with the level of injury: review and personal experience. *Plast Reconstr Surg*. 2009;124(suppl):e359–e369. *This article presents a simple classification system in terms of numbered levels. This easy system may become a universal classification of brachial plexus injury.*
- Qiu SS, Chuang DCC. Reliability of various predictors for preoperative diagnosis of infraclavicular brachial plexus lesions with combined shoulder and elbow paresis. (submitted).
- Carlstedt T, Grane P, Hallin RG, et al. Return of function after spinal cord implantation of avulsed spinal nerve root. *Lancet*. 1995;346:1323–1325.
- Fournier HD, Mercier P, Menei P. Repair of avulsed ventral nerve roots by direct ventral intraspinal implantation after brachial plexus injury. *Hand Clin*. 2005;21:109–118.
- Seddon HJ. Three types of nerve injury. *Brain*. 1943;66:237–283.
- Sunderland S. A classification of peripheral nerve injuries producing loss of function. *Brain*. 1951;74:491–516.
- Birch R. Timing of surgical reconstruction for closed traumatic injury to the supraclavicular brachial plexus. *J Hand Surg Eur Vol*. 2015;40:562–567.
- Birch R. Infraclavicular lesions. In: Boome RS, ed. *The Brachial Plexus*. New York, NY: Churchill Livingstone; 1997:79.
- Hems TEJ. Timing of surgical reconstruction for closed traumatic injury to the supraclavicular brachial plexus. *J Hand Surg Eur Vol*. 2015;40:568–572.
- Chuang DCC, Yeh MC, Wei FC. Intercostal nerve transfer of the musculocutaneous nerve in avulsed brachial plexus injuries – evaluation of 66 patients. *J Hand Surg Am*. 1992;17:822–828.
- Chen CC, Wang YC, Yang DY, et al. Brown-Séquard syndrome associated with Horner's syndrome in cervical epidural haematoma. *Spine*. 1995;20:244–247.
- Lister G. *The Hand*. 3rd ed. Edinburgh: Churchill Livingstone; 1993:233.
- Bertelli JA, Ghizoni F. Long thoracic nerve: anatomy and functional assessment. *J Bone Joint Surg Am*. 2005;87:993–998.
- Doi K, Otsuka K, Okamoto Y, et al. Cervical nerve root avulsion in brachial plexus injuries: magnetic resonance imaging classification and comparison with myelography and computerized tomography myelography. *J Neurosurg*. 2002;96(3 suppl):277–284.
- Yoshikawa T, Hayashi N, Yamamoto S, et al. Brachial plexus injury: clinical manifestation, conventional imaging findings, and the latest imaging techniques. *Radiographics*. 2006;26(suppl 1):S133–S143.
- Lutz AM, Gold G, Beaulieu C. MR imaging of the brachial plexus. *Neuroimaging Clin N Am*. 2014;24:91–108.
- Vargas MI, Viallon M, Nguyen D, et al. New approaches in imaging of the brachial plexus. *Eur J Radiol*. 2010;74:403–410.
- Wilbourn AJ. Brachial plexopathies. In: Brown WF, Bolton CF, Aminoff MJ, eds. *Neuromuscular Function and Disease. Basic, Clinical, and Electrodiagnostic Aspects*. Philadelphia, PA: W.B. Saunders; 2002:831.
- Ferrante MA. Electrodiagnostic assessment of the brachial plexus. *Neurol Clin*. 2012;30:551–580.
- Chuang DCC. Nerve transfers in adult brachial plexus injuries: my methods. *Hand Clin*. 2005;21:71–82.
- Machinnon SE, Novak CB. Nerve transfers. *Hand Clin*. 1999;15:643–666, ix.
- Chuang DCC. Restoration of elbow flexion by nerve transfer – comparison between proximal vs. distal nerve transfer in 188 acute brachial plexus injuries. (Submitted).
- Viterbo F, Trindade JC, Hoshino K, et al. End-to-side neurorrhaphy with removal of the epineurial sheath: an experimental study in rats. *Plast Reconstr Surg*. 1994;94:1038–1047.
- Cardenas-Mejia A, O'Boyle CP, Chen KT, et al. Evaluation of single, double, and triple-nerve transfers for shoulder abduction in 90 patients with supraclavicular brachial plexus injury. *Plast Reconstr Surg*. 2008;122:1470–1478.
- Hentz VR, Doi K. Traumatic brachial plexus injury. In: Green DP, Hotchikiss RN, Pederson WC, et al., eds. *Green's Operative Hand Surgery*. 5th ed. Philadelphia, PA: Elsevier/Churchill Livingstone; 2005:1351.
- Doi K. Management of total paralysis of the brachial plexus by the double free-muscle transfer technique. *J Hand Surg*. 2008;33E:240–251.
- Chuang DCC, Hernon C. Minimum 4-year follow-up on contralateral C7 nerve transfers for brachial plexus injuries. *J Hand Surg Am*. 2012;37:270–276.
- Chuang DCC. Nerve transfer with functioning free muscle transplantation. *Hand Clin*. 2008;24:377–388, vi.
- Pondaag W, Malessy MA. The evidence for nerve repair in obstetric brachial plexus palsy revisited. *Biomed Res Int*. 2014;2014:434619.
- Tse R, Kozin SH, Malessy MJ, et al. International Federation of Societies for Surgery of the Hand Committee Report: The role of nerve transfers in the treatment of neonatal brachial plexus palsy. *J Hand Surg Am*. 2015;40:1246–1259.
- Kozin SH. The evaluation and treatment of children with brachial plexus birth palsy. *J Hand Surg Am*. 2011;36:1360–1369.
- Al-Qattan MM. Obstetric brachial plexus injuries. *J Hand Surg Am*. 2003;3:41–54.
- Chuang DCC, Ma HS, Wei FC. A new evaluation system to predict the sequelae of late obstetric brachial plexus palsy. *Plast Reconstr Surg*. 1998;101:673–685.

47. Chuang DCC, Ma HS, Wei FC. A new strategy of muscle transposition for treatment of shoulder deformity caused by obstetric brachial plexus palsy. *Plast Reconstr Surg*. 1998;101:686–694.
48. Chunag DCC, Hattori Y, Ma HS, et al. The reconstructive strategy for improving elbow function in late obstetric brachial plexus palsy. *Plast Reconstr Surg*. 2002;109:116–126.
49. Chuang DCC, Ma HS, Borud LJ, et al. Surgical strategy for improving forearm and hand function in late obstetric brachial plexus palsy. *Plast Reconstr Surg*. 2002;109:1934–1946.
50. Hardy AE. Birth Injuries of the brachial plexus: incidence and prognosis. *J Bone Joint Surg Br*. 1981;63:98–101.
51. Greenwald AG, Schute PC, Shiveley JL. Brachial plexus birth palsy, a 10-year report on the incidence and prognosis. *J Pediatr Orthop*. 1984;4:689–692.
52. Kline DG, Hudson CG. *Nerve Injuries*. Philadelphia, PA: W.B. Saunders; 1995:461.
53. Boome RS, Kaye JC. Obstetric traction injuries of the brachial plexus: natural history, indication for surgical repair and results. *J Bone Joint Surg Br*. 1988;70:571–576.
54. Gilbert A. Long-term evaluation of brachial plexus surgery in obstetrical palsy. *Hand Clin*. 1995;11:583–594, discussion 594–595.
55. Terzis JK, Kokkalis ZT. Outcomes of hand reconstruction in obstetric brachial plexus palsy. *Plast Reconstr Surg*. 2008;122:516–526.
56. Hentz VR. Obstetric brachial plexus palsy. In: Mathes SJ, Hentz VR, eds. *Plastic Surgery*. 2nd ed. Philadelphia, PA: Saunders/Elsevier; 2006:539.
57. Clarke HM, Curtis CG. An approach to obstetrical brachial plexus injuries. *Hand Clin*. 1995;11:563–580.
58. Chuang DCC, Mardini S, Ma HS. Surgical strategy for infant obstetrical brachial plexus palsy: experiences at Chang Gung Memorial Hospital. *Plast Reconstr Surg*. 2005;116:132–142.
59. Gilbert A. Indications and strategy. In: Gilbert A, ed. *Brachial Plexus Injuries*. Martin Dunitz Ltd; 2001:205.
60. Terzis JK, Papakonstantinou K. Surgical treatment of obstetrical brachial plexus paralysis: the Norfolk experience. *Semin Plast Surg*. 2004;18:359–375.
61. Clarke HM, Curtis CG. Examination and prognosis. In: Gilbert A, ed. *Brachial Plexus Injuries*. Martin Dunitz Ltd; 2001:159.
62. Oberlin C, Béal D, Leechavengvongs S, et al. Nerve transfer to biceps muscle using a part of ulnar nerve for C5–6 avulsion of the brachial plexus – anatomical studies and report of four cases. *J Hand Surg Am*. 1994;19:232–237.
63. Mackinnon SE, Novak CB, Myckatyn TM, et al. Results of reinnervation of the biceps and brachialis muscles with a double fascicular transfer for elbow flexion. *J Hand Surg Am*. 2005;30:978–985.
64. Muhlig RS, Blaauw G, Slooff ACJ, et al. Conservative treatment of obstetrical brachial plexus palsy (OBPP) and rehabilitation. In: Gilbert A, ed. *Brachial Plexus Injuries*. Martin Dunitz Ltd; 2001:173.
65. Price AE, Grossman JAI. A management approach for secondary shoulder and forearm deformities following obstetric brachial plexus injuries. *Hand Clin*. 1995;11:607–617.
66. Egloff DV, Raffoul W, Bonnard C, et al. Palliative surgical procedures to restore shoulder function in obstetric brachial palsy – critical analysis of Narakas' series. *Hand Clin*. 1995;11:597–606.
67. Chuang DCC, Cheng MH, Ma HS. Clinical application of functioning free muscle transplantation (FFMT) in the late obstetric brachial plexus palsy (OBPP). *J Plast Surg Associ ROC*. 2006;15:211.
68. Doi K. Obstetric and traumatic pediatric palsy. In: Peimer CA, ed. *Surgery of the Hand and Upper Extremity*. New York, NY: McGraw-Hill; 1996:1443.
69. Zancolli EA, Zancolli ER. Palliative surgical procedures in sequelae of obstetrical palsy. *Hand Clin*. 1988;4:643–669.

37

Restoration of upper extremity function in tetraplegia

Carina Reinholdt and Catherine Curtin

Access video and video lecture content for this chapter online at expertconsult.com 

SYNOPSIS

- Suffering a spinal cord injury causes a huge life transition, where simple everyday tasks become a challenge. When patients with tetraplegia were asked which function they would most like to regain, they ranked hand and arm control as the most important.¹ For people with tetraplegia, restoration of independence is the primary goal.
- There is no treatment to cure spinal cord injuries, but highly specialized care can rehabilitate and partially reconstruct some of the lost functions.
- Restoration of function requires a team approach combining physical and occupational therapy, assistive devices, and surgery including tendon transfer, nerve transfer, tenodesis, and arthrodesis.
- Patients with tetraplegia due to spinal cord injury often greatly benefit from grip and elbow extension reconstruction. These procedures have been shown to improve functional independence.^{2,3}
- Early active mobilization improves outcomes after surgical reconstruction.
- A resolution was established in Philadelphia in 2007 (at the International Congress of Tetraplegia Hand Surgery and Rehabilitation) that patients who have sustained spinal cord injuries with tetraplegia should be examined, assessed, and informed about possible reconstruction of motor function in their upper extremities.⁴
- These reconstructive procedures are currently underutilized.⁵
- Strengthening connections between spinal cord injury specialists and upper limb surgeons represents an opportunity to improve access to this care.

Introduction

Surgery on the upper limb of people with tetraplegia requires special consideration because the hand represents a critical residual resource.⁶ After cervical spinal cord injury, upper limbs take on new unique functions different from any other patient in that they must “walk on their hands”. Given the importance of the upper limb, surgery requires a multidisciplinary team approach as part of a comprehensive

rehabilitation plan. The patient must realistic expectations and understand that surgical intervention will not result in a “normal arm” but as Dr. Sterling Bunnell said, “for those who have nothing, a little is a lot”.⁷

Basic science/disease process

Today, the most common mechanisms of cervical spine injury (SCI) are motor vehicle accidents, falls, especially in the elderly, and sports injuries. The most common level of injury C5/C6.⁶ The anatomic level and completeness of injury determine the functional deficits. Modern acute care of these injuries allows most patients to survive their injury and thus face a lifetime in a greatly altered state of existence. Every patient with tetraplegia suffers some loss of upper limb function. Their upper limbs represent a critical residual functional asset.

Although upper limb surgeons often do not participate in the initial management of the SCI patient, the acute rehabilitation focuses on the upper limbs. Special care is taken to prevent contractures of fingers, wrist, or elbow. Even a relatively mild elbow contracture can inhibit independent transfers.⁸ Fortunately, well-educated therapists are aware of the need for protective splinting right after injury. The shoulder must also be protected as the patient learns to adjust to their injury. Pulling patients, poor posture, or falls during rehabilitation can result in shoulder injuries that ultimately limit independence. Indeed the majority of people with tetraplegia have shoulder pain at the end of their acute rehabilitation.⁹ Early attention to the upper limb provides the best long-term function.

Classification of the tetraplegic upper extremity

Cervical spinal cord injury has been classified in many ways, including by the skeletal level of injury or according to the most distal functioning cervical root. However, this

Table 37.1 International classification for surgery of the hand in tetraplegia

ICHST group	Motor characteristics	Description/function
0	No muscles below elbow suitable for transfer	Flexion/supination of elbow
1	BR	
2	ECRL	Extension of wrist (weak or strong)
3	ECRB	Extension of wrist
4	PT	Extension and pronation of wrist
5	FCR	Flexion of wrist
6	Finger extensors	Extrinsic extension of fingers, partial or complete
7	Thumb extension	Extrinsic extension of the thumb
8	Partial digital flexors	Extrinsic flexion of the fingers, weak
9	Lacks only intrinsics	Extrinsic flexion of the fingers
X	Exceptions	
Caution: it is not possible to determine ECRB strength without surgical exposure. Each patients is also checked for sensibility and placed in ocular or Cutaneous groups. O, Ocular; Cu, cutaneous; BR, brachioradialis; ECRL, extensor carpi radialis longus; ECRB, extensor carpi radialis brevis; PT, pronator teres; FCR, flexor carpi radialis.		

classification system is too general for hand surgeons because no two patients are exactly alike. Injury pattern can differ between those with the same skeletal level of injury and each patient often has different function between the right and left arm. In order to develop useful algorithms for treatment of the upper limb, it was necessary to develop a more precise classification method of these patients upper limb issues. From this need arose the International Classification (IC), which is based on the limb's remaining useful motor and sensory resources (Table 37.1). The motor function identifies the number of strong muscles under volitional control below the elbow. To be counted, the muscle must have grade 4 or 5 Medical Research Council (MRC) strength. The grade 4 level was chosen because a grade 4 muscle can be transferred with the expectation that it will be able to perform useful work. A grade 3 muscle loses so much of its power in transfer and is not reliable as a donor for transfer.

Moberg^{10,11} encouraged also accounting for remaining sensory resources. If sufficient proprioception remains in any part of the hand (typically the thumb and index fingers), the patient can control his/her hand without having to keep it in view. If the hand lacks proprioception, the patient needs his/her eyes to direct the hand. Lack of proprioception limits the ability to perform bi-manual activities, but it is not a contraindication to reconstructive hand surgery. Patients benefit from grip reconstruction even though they lack sensation. A

hand without a sensibility is more useful with a grip than without a grip.¹² Today, static two-point discrimination of less than 12–15 mm is acknowledged as indicating the presence of proprioception. The IC accounts for the presence or absence of proprioception by including codes to indicate whether afferent control resides in the hands, termed “cutaneous”, or “Cu”, or only in the eyes of the patient, termed “ocular”, and abbreviated as “O”.

Later, the IC scheme was extended to include a determination of the presence or absence of active elbow extension. The IC system is used by essentially all surgeons involved in the care of the upper extremities of these patients.

Patient presentation and patient selection

Forming a team

Moberg stressed the need to develop a “critical mass” of likeminded professionals into a team that should include physiatrists involved in the rehabilitation and long-term care of people with tetraplegia. Critical to the success of an upper limb team are well-trained therapists, either physical therapists or occupational therapists (preferably both). The hand and upper extremity surgeon provides the technical expertise. Others including social workers and psychologists may offer additional support to the team. The patient's support group including family or attendant is the key to success. The central member of the team is the patient.^{14–16}

The roles of the professionals in this team are relatively clear. The physiatrists assist in determining the appropriateness of the patient for surgery as well as when to time surgery relative to overall rehabilitation goals and schedules. The therapist frequently serves as the patient's advocate. He or she knows the patient better than anyone else and, most importantly, the patient's expectations, voiced or not.

For the patient, upper extremity surgery can have a large emotional impact. Some patients are concerned about altering their anatomy because they are waiting for the cure for SCI. While the goal of surgical reconstruction for the upper extremity is greater function, the patient must be willing to lose temporarily some of their hard-won independence during the postoperative rehabilitation. For family and attendants, this greater period of dependence translates into more inconvenience and effort. All the team members must play a role in the decision-making process and must share in the frustrations as well as the rewards.

The hand and upper extremity team should become part of the routine evaluation of newly injured patients. The cervical cord injured patient arrives at a rehabilitation facility or spinal cord injury unit usually with fairly supple upper limbs, although with no or only minimal volitional movement. The upper limb assessment becomes clearer. Once the patient's vertebral injury is stabilized and the patient can sit in a wheelchair, an assessment by the upper extremity team takes on new meaning, and the rehabilitation of the hands starts. By the fourth month following injury, the eventual functional level is usually clearly established for the majority of patients.¹⁷ At this time, the training of the patient's upper limb function has mainly proceeded into training of managing daily life, by



Fig. 37.1 A patient pushing her wheelchair after grip reconstruction.

coordination training of perceived functions, adaptive grasping patterns, technical aids, and assistive devices.^{18–20} The aim is optimal use of the hands to maximize independence, despite lack of active grasp function.

Timing

Hand or upper extremity surgery is rarely indicated during the initial months of rehabilitation following injury. The patient needs time to experience neurologic, psychologic, and social stability. From a practical standpoint, there are simply too many more important rehabilitation activities going on. On the other hand, a dogmatic philosophy such as “never operate on a patient before 12 months” has no basis in science. Some patients are clearly candidates for surgery prior to this calendar date. For example, early surgical intervention to relieve the pathologic effects of a fixed elbow flexion contracture may allow a patient to participate more vigorously in necessary rehabilitation activities.⁸ Early release of a fixed elbow flexion contracture can be done with a simultaneous transfer of the contracted biceps muscle to the triceps. This removes a pathologic or deforming force and reinforces or restores some power to the antagonist. Botox is another important tool in the early rehabilitation armamentarium. It is especially helpful for patients with concomitant brain injury who may not comply with splinting or therapy and have increased tone.

Once the patient has achieved neurological and psychological stability, a formal evaluation to establish the appropriateness of upper extremity surgery can be accomplished by the team. The evaluation should focus on both tangible evidence of recovery by assessing remaining motor and sensory resources and the important intangibles such as motivation and intelligence. There is increasing recognition of the co-occurrence of traumatic brain injury with spinal cord injury and the impact of brain injury on rehabilitation.²¹ Cognitive deficits need to be understood before embarking on upper extremity reconstruction given the intensive post-surgical therapy. The initial patient assessment should include an evaluation on how the patient uses the hand to accomplish tasks of daily living (Figs. 37.1 & 37.2A,B). Tendon transfers




Fig. 37.2 Postoperative results after single-stage grip release reconstruction. (A) Writing before reconstruction; (B) writing after reconstruction.

may alter the position of the hand and fingers. After reconstruction, the hand or arm must be protected in a splint. This protection entails difficulties to perform critical daily activities such as wheelchair propulsion and bed transfers (Fig. 37.3). It is best for patients to plan for temporary greater dependence and learn safe transfer techniques before surgery.



Fig. 37.3 Splint to allow for as active rehabilitation as possible, e.g., propulsion of wheelchair, use of computer or cell phone (with the little peg).

The timing of surgery is important and it is critical that the patient has the right expectations and is motivated for not only the surgery but also the rehabilitation. Some patients, especially women, seem to wait longer before making a decision for surgery, probably due to family matters.²² Tendon transfers can be performed a long time after the injury; our record is 38 years post-injury with good outcomes. One caveat to this is the emerging use of nerve transfers, which may have a tighter time window than tendon transfers. Though the best timing of nerve transfers for these patients remains unknown, we believe it is somewhere around 18 months.

Patient evaluation/selection

The upper limb examination includes assessment of motor strength and a sensory evaluation. The exam also identifies pathologic conditions such as contracted, painful, or unstable joints that may impact surgical results. There is also a sensory evaluation, which includes measuring two-point discrimination in the digits to assess proprioception. The currently used grip patterns are assessed. Occasionally, spinal cord injured patients will have focal areas of severe neuropathic pain that will make the exam painful and potentially limit surgical results.

The patient's global functional status in daily living is assessed, including mobility, personal care, domestic life, type of wheelchair, and other adaptive devices. Is s/he dependent or independent in bed mobility? How are transfers performed? Does s/he use a manual or electric wheelchair? What adaptive devices are used for dressing, grooming, feeding? If surgery is to be performed, is there sufficient support to get the patient through a period of greater functional dependence or will the extra burden of care result in the patient's attendant quitting? For some patients, upper extremity surgery means restriction to an electric-driven chair. Can this be made available? Does the home situation permit the use of an electric wheelchair? Are the controls of the chair mounted on the non-operated side? The patient's primary caregiver can help answer these questions. Most patients can use their manual wheelchair provided that they use protective orthoses during the postoperative rehabilitation time. Preparation before surgery will prevent complications such as pressure sores and social consequences such as divorce and make the patient able to focus on the important postoperative rehabilitation.

Finally, the patient's goals for surgery are reviewed. We prefer using the Canadian Occupational Performance Measure (COPM).²³ It enables specific tasks to be identified, e.g., "I want to eat the triple decker sandwich at Joe's by myself." This instrument helps the surgeon and therapist understand if the patient has reasonable expectations and can help tailor the procedures. It also serves as an important evaluation tool.

Treatment/surgical technique

General guidelines for reconstruction

Five surgical procedures are applicable for improving upper limb function in tetraplegia:

1. Arthrodesis: permits stabilization of joints lacking muscle stabilization.
2. Tenodesis: performed to stabilize a joint or so that a proximal movement, e.g., wrist extension, will result in

the tightening of the tenodesis and movement of a more distally located joint, e.g., thumb flexion.

3. Tendon transfer: the transfer of the power of an expendable muscle–tendon unit under good volitional control to compensate for the absence or ineffectiveness of function of another muscle–tendon unit.
4. Nerve transfers: the transfer of functional nerve branches from active muscles to paralyzed muscles to provide muscle function.
5. Spasticity-reducing surgery: tendon lengthening or muscle releases to reduce spasticity by making the tendon–muscle unit longer. This allows for better volitional control.

Tendon transfers are the workhorse procedures for reconstruction of the upper extremity in tetraplegia. These techniques have been refined over the last 80 years and several basic principles have evolved: (1) First is *correction of any joint contracture*. Tendon transfers are often biomechanically disadvantaged and will not be able to overcome a contracted joint. (2) The *donor muscle must have adequate strength*. Transferred muscles will generally lose a grade of strength after transfer. Therefore it must be strong preoperatively to be able to perform functional tasks postoperatively and should have a MRC > 4. (3) The *donor muscle must be expendable*. (4) For the best biomechanical advantage, the most *effective routing of muscle insertion is a straight line*. (5) The *soft tissue bed must be stable*. These surgeries must be performed in a supple bed with adequate skin coverage. Scarred beds will prevent tendon gliding and will impair the result. (6) The *donor muscle should have adequate excursion* to perform the desired function.

For patients with tetraplegia, spasticity must also be considered. The donor muscle must have volitional control and not have too much tone. Overall level of spasticity can be improved with physical therapy and medications. A small amount of spasticity and tone is acceptable and sometimes beneficial to reconstructive procedures. The surgeon should assess the level of spasticity and make sure it is optimized before intervention. Spasticity should always be treated before tendon transfers are considered. Most patients with incomplete tetraplegia have spasticity and can be treated with tendon lengthening and muscle releases when conservative treatment is not sufficient.⁴

The surgical procedures can be grouped using the IC system (Table 37.2). For these procedures, it is critical that each patient, and indeed each upper extremity, be evaluated and then each treatment plan individualized.²⁴

For high cervical spinal cord injuries, there are no expendable muscles available for transfer in the arm. For patients with lower injuries, such as a C7 injury, many potentially expendable, and thus transferable, muscles of grade 4 or 5 power exist. The choice of procedure depends primarily on the residual resources and, secondly, on the many intangibles such as patient desires, motivation, and support. The surgical techniques used in tetraplegia are the same procedures as reconstructions after peripheral nerve injuries, but the difference between these procedures is the preoperative preparation and matching the patient to the correct procedure. A cautious approach while one gains experience pays great dividends in terms of obtaining the acceptance of team members and patients that surgery can promote greater independence. A

Table 37.2 Algorithm for surgical treatment in tetraplegia

ICSHT group O/Cu	Available muscles below elbow	Suggested or possible procedure
0	No muscles	Nerve transfer, triceps reconstruction
1	BR	BR–ECRB, passive key pinch, triceps reconstruction, nerve transfer
2-3	ECRL, ECRB	BR–FPL or FDP and passive key pinch, triceps reconstruction, House procedure, nerve transfers
4-5	PT, FCR	Single-stage grip release procedure, triceps reconstruction, nerve transfer
6-8	EDC, thumb extension, partial finger flexors	Single-stage grip release procedure with options: EDM–APB, active IO
9	Lack only intrinsic	Active interossei – FDS IV to IO
x	Mixed pattern	Combinations
Spasticity	Mixed pattern	Tendon lengthening, muscle release, ECU–tenodesis, distal ulna intrinsic release

ICSHT, international classification for surgery of the hand in tetraplegia; O, Ocular; Cu, cutaneous; BR, brachioradialis; ECRL, extensor carpi radialis longus; ECRB, extensor carpi radialis brevis; PT, pronator teres; FCR, flexor carpi radialis; EDC, extensor digitorum communis; FPL, flexor pollicis longus; FDP, flexor digitorum profundus; EDM, extensor digiti minimi; APB, abductor pollicis brevis; IO, interosseus; FDS, flexor digitorum superficialis; ECU, extensor carpi ulnaris.

poor outcome early in the team's experience creates a tremendous hurdle.

Surgical reconstruction

Elbow extension

Erik Moberg highlighted the importance of active elbow extension for the spinal cord injured patient. A wheelchair user depends upon good shoulder and elbow power to push a manual wheelchair, transfer from bed to chair, and to perform pressure releases to prevent pressure sores. Without active elbow extension, a patient cannot stabilize the arm in space such that the hands fall into his face when lying supine, which makes eating and daily hygiene challenging (Fig. 37.4). Restoring elbow extension can increase the reachable space by an additional 12 inches resulting in 800% more functional space and can assist with simple tasks such as turning on a light switch. There are two surgical procedures advocated for restoring active elbow extension – biceps-to-triceps and deltoid-to-triceps transfer.

Biceps-to-triceps transfer

This procedure is a common and straightforward technique.²⁵⁻²⁸ It is the procedure of choice when there is a pre-existing flexion contracture of the elbow greater than 45° because transferring the biceps also addresses the deforming flexion force. The advantages of biceps-to-triceps transfer include no need for an interposition graft and one tendon repair site. Disadvantages include a more challenging rehabilitation program and the potential for loss of elbow flexion strength.

Surgical technique

The biceps tendon is detached from its insertion on the greater tuberosity of the radius, the muscle–tendon unit routed either medially²⁹ or laterally,^{30,31} and the tendon attached to the triceps aponeurosis or directly into the olecranon.

The incisions that are employed depend in large measure on whether a wide exposure to the anterior aspect of the elbow joint is needed to allow adequate release of contracture. The distal extent of the incision should allow complete dissection of the tendon of the biceps allowing detachment at the level of insertion on the bicipital tuberosity of the radius (Fig. 37.5A).

The incision is carried through the subcutaneous tissue, protecting the large tributaries of the basilic and cephalic veins. The soft tissues overlying the lacertus fibrosis are elevated and the lacertus is either divided off the primary tendon or dissected distally as far as possible to provide another point of fixation to the triceps (see Fig. 37.5B).

The primary tendon of the biceps is dissected to its point of insertion on the radius. Flexing the elbow and supinating the forearm assists in this exposure. The tendon is sectioned as far distally as possible. The biceps muscle is dissected proximally from within its dense investing fascia, the dissection proceeding proximally until the cutaneous portion of the musculocutaneous nerve is identified as it courses between the overlying biceps and the deeper brachialis muscle. This



Fig. 37.4 Postoperative elbow extension allowing for stabilization of the arm to assist with combing the hair.




Fig. 37.5 Biceps-to-triceps transfer by the medial route (A–D). (Redrawn from Hentz V, Leclercq C. *Surgical Rehabilitation of the Upper Limb in Tetraplegia*. London: Harcourt Health Sciences; 2002, with permission.)

nerve is protected while dissection of the biceps proceeds proximally until the most distal motor branches coming from the musculocutaneous nerve are visualized.

Both medial and lateral routing of the transfer have been described. Since the ulnar nerve is typically non-functional in this population, we have preferred to route the biceps medially. It is necessary to dissect widely the arcade of Struthers and all other fascial communications about the medial intermuscular septum. One must be concerned about compression of the radial nerve when the lateral route is chosen.

A second incision located posteromedially is made in order to expose the medial aspect of the triceps insertion. Through this incision, the medial border of the triceps is elevated and dissected to its insertion on the olecranon. The biceps muscle and tendon are then passed from the anterior to the posterior incision through the widely dissected subcutaneous tunnel (see Fig. 37.5C). The anterior incision may be closed at this point.

The biceps tendon typically just reaches the tip of the olecranon but there is often not enough tendon length to permit a strong attachment into the olecranon. Instead, the tendon of the biceps is woven into the medial border of the triceps tendon and anchored in multiple locations with stout

sutures (see Fig. 37.5D). We have judged that the proper tension is achieved when the biceps is pulled distally enough to permit the end of the tendon to touch the olecranon with the elbow in about 20° of flexion. Once the tendon-to-tendon junctures are made, the elbow is fully extended to relax the site of approximation.

Postoperative rehabilitation

Regardless of what elbow extension reconstruction technique chosen, the elbow is immobilized in full extension using a light plaster or fiberglass cylinder cast for 3½ weeks. An overhead, chair-mounted sling is fitted to the patient's wheelchair and is used whenever the patient is in the wheelchair and until the cast is removed.

The initial cast is left undisturbed for 3½ weeks if preoperatively the elbow had normal passive extension. If the elbow had a preoperative flexion contracture between 15° and 30°, the elbow is extended as much as possible at the time of surgery and casted in that position. This cast is then removed between 10 and 14 days postoperatively. Great care must be taken to keep the elbow extended during this maneuver. Typically, the elbow can then be further extended at this time by




Fig. 37.6 Hinged orthosis to protect the repair across the elbow. The degree of flexion is gradually flexed over time.

slow stretch and the arm is recasted, now typically in near full extension. After removal of the cast, the elbow is slowly allowed progressive elbow flexion in a specially designed flexion-stop brace (Fig. 37.6). Although the biceps seems to be an antagonist to elbow extension, by teaching the patient to conjointly supinate the forearm and extend the elbow, the patient can be re-educated to use the supinator function of the biceps to extend the elbow. Electrical stimulation and biofeedback therapy has been used on occasion with improved results. Six months of cautious use are necessary to prevent overstretching of the transfer and maximal strength is obtained after many months.

Deltoid-to-triceps transfer³²

Surgical technique (Fig. 37.7)

Hints and tips

1. Detach the deltoid from the humerus with as much fascia and fibrous insertion as possible, including some of the fascial origin of the brachialis muscle.
2. Ensure the triceps fascia is intact to protect the radial nerve.
3. Attach the deltoid to the triceps at maximum tension with the shoulder abducted 90° and the elbow as straight as possible and the forearm pronated. When the elbow is flexed 10–15°, the tendon transfer should be maximally tight. Make sure the elbow is not flexed more during the procedure. Let the assistant keep the elbow extended.
4. Cast elbow in full extension and keep the arm abducted at the shoulder during healing.

The surgical landmarks at the shoulder include the tip of the acromion superiorly, the interval between the posterior margin of the deltoid and the triceps muscle posteriorly, and the estimated point of insertion of the deltoid on the humerus. The landmark at the elbow is the tip of the olecranon. The surgeon should keep in mind the neurovascular anatomy of

the region including the course of the axillary nerve and the circumflex humeral artery and the radial nerve and its relationship to the insertion of the deltoid.

The upper incision is centered half way between the midaxial line of the humerus and the posterior margin of the deltoid. The skin incision is carried to the level of the muscle fascia and the skin and subcutaneous tissues are elevated anteriorly to just past the midaxial line of the humerus. Posteriorly, the skin flap is elevated to the confluence of deltoid and the long head of the triceps. The plane between these two muscles is developed by sharp or finger dissection. As the finger strikes the humerus, the fingertip tip can be insinuated upward through the fibers of the deltoid, separating the muscle into relatively equal anterior and posterior halves. At least a third of the posterior deltoid is needed for the transfer.

Detaching the insertion of the posterior half of the muscle from its point of insertion onto the humerus is done by sharply incising a rectangle of periosteum at the point of attachment and elevating the periosteum and the fibers of attachment off the humerus. We include as much fascia and fibrous insertion as possible, including some of the fascial origin of the brachialis muscle. The radial nerve will be emerging from behind the humerus several centimeters distal to this point. Injury to this nerve has been reported as a rare but devastating complication of this procedure.

A suture is placed in the fibrous origin of the posterior half of the deltoid muscle and the dissection is carried superiorly until the branches of the axillary nerve are visualized. The superior dissection should stop at this point.

Several methods have been proposed to attach the posterior deltoid to the triceps or olecranon including:

- Autogenous tissue such as fascia lata, toe extensors,³³ tibialis anterior tendon,¹¹ or extensor carpi ulnaris (ECU)³⁴
- A turned up strip of the central part of the triceps tendon with synthetic reinforcement³⁵
- Bone to bone attachments³⁶
- Various synthetic materials.³⁷

We prefer autologous tibialis anterior tendon because its thickness and proximal fan shape, which matches the deltoid aponeurosis well.

The tibialis anterior tendon is harvested through two incisions, at the insertion site and a longitudinal incision lateral to the tibia. The tendon is detached from the muscle, and sutured with side-to-side sutures to the deltoid aponeurosis and to the triceps tendon. The tibialis tendon graft does not need to be tunneled through olecranon.

In walking patients with incomplete tetraplegia, the fascia lata is preferable. The fascia is harvested through several transverse incisions placed over the iliotibial band. The ideal width is about 2.5 cm. The fascia lata is encircled about the fibrous insertion of the deltoid using mattress sutures of non-absorbable braided suture, tubed over its remaining length and tunneled subcutaneously to the olecranon.

The olecranon is exposed just distal to the triceps insertion. The triceps tendon is split longitudinally to further expose the tip of the olecranon and a 5-mm drill bit is used to create an oblique tunnel through the olecranon. A Bunnell tendon stripper is a useful instrument to “polish” this channel so that the tubed fascia lata can be passed smoothly in a proximal to distal direction.³⁸ The fascia lata is passed into the distal




Fig. 37.7 (A–H) Deltoid-to-triceps transfer with fascia lata. (Redrawn from Hentz V, Leclercq C. *Surgical Rehabilitation of the Upper Limb in Tetraplegia*. London: Harcourt Health Sciences; 2002, with permission.)




Fig. 37.7, cont'd

exposure, separated into two tails and the tails are passed through the bone channel.

The shoulder is abducted about 90° and the elbow is extended as much as possible. The two fascia lata tails are then pulled to *maximally* tense the transfer and these tails are turned proximally and woven into the fascia lata tube and anchored with non-absorbable sutures. Once suturing is complete, the fascial tube should be under moderate but definite tension. The wounds are closed and a cylinder cast is placed as is described in the biceps-to-triceps transfer with the elbow fully extended.

Postoperative rehabilitation

Postoperative care is quite similar to the biceps-to-triceps transfer. However, for deltoid to triceps transfer, shoulder position is more of a concern. The shoulder is kept somewhat abducted and the patient and other caregivers are cautioned to not allow the shoulder to accidentally flop across the chest. The wheelchair frame is critical because it holds the arm approximately 30° elevated and helps to keep the arm approximately 30° abducted from the body. This position relaxes the deltoid, prevents distal edema, and maintains seating stability.

After 3 weeks, the patient gets a dynamic elbow orthosis and start flexing the elbow 15° per week, starting at 30–45° of flexion depending on where the first resistance appears. Full load is allowed 8–10 weeks postoperatively. Complications are rare provided the patient follows the exercise protocol and does not overstretch the transfer by too rapidly regaining full elbow flexion. Even though the rehabilitation can be relatively

lengthy, the functional gain is substantial, predictable, and easily appreciated by the patient.³⁹

IC groups 0, 1, and 2

For the IC group 0 patient with no muscles functioning at the grade 4 or greater level distal to the elbow, few reconstructive possibilities exist. These patients benefit from a triceps reconstruction. A new procedure using nerve transfers to reconstruct wrist extension has been introduced.⁴⁰ When active wrist extension is regained, a passive key grip can be added.

Improving wrist extension: the IC group 1 and 2 patient

In the IC group 1 patient, the brachioradialis (BR) is typically the only muscle with grade 4 strength distal to the elbow. However, grade 2+ to grade 3+ radial wrist extensor function is typically present as well. The patient may be able to extend the wrist against gravity but cannot generate useful force between digits and thumb through any existing natural tenodesis effect or cannot utilize a wrist-driven flexor hand splint unless it is equipped with a ratchet mechanism. For this patient, wrist extensor strength can be augmented by transferring the power of the BR into the more central of the radial wrist extensors, the extensor carpi radialis brevis (ECRB) tendon.^{41–43} From several biomechanical studies^{44,45} it has been determined that the BR becomes a more effective wrist extensor following transfer if the patient can stabilize the elbow in space. If no active elbow extension is present, the BR may waste some of its excursion and power by flexing the elbow

rather than in extending the wrist. For this reason, we prefer first to reconstruct active elbow extension and after that transfer the BR to the ECRB for wrist extension, which will work as a motor for a passive key grip. Further balancing of the thumb can often be useful and additional procedures such as arthrodesis of the first carpometacarpal (CMC) joint and a split tenodesis of the flexor pollicis longus (FPL) to extensor pollicis longus (EPL) can be considered. We will describe these techniques later.

A wide dissection of the distal BR muscle and tendon from its insertion at the radial styloid up to the very proximal forearm level is necessary to obtain the most effective excursion of the muscle. Fridén has shown that the BR tendon needs to be released 12–15 cm to get an excursion of 4 cm of the BR tendon.⁴⁶ The tension on the BR should be adjusted to re-establish the normal resting length of the muscle with care taken not to overstretch this muscle. In adjusting the tension, it is important to place the elbow in some flexion. Moberg¹¹ recommended that the elbow be set at about 40° of flexion and we have followed this guideline.

Postoperative rehabilitation

All patients start early active mobilization the first postoperative day. (A prerequisite for early active training is side-to-side suture technique: see next paragraph.) During the first 3–4 weeks, patients perform unloaded functional training to allow for movement of the tendon transfers, tenodeses, or tendon lengthening. This is important to avoid swelling, edema, and adhesions. A resting splint protects the hand between training sessions. The patients perform a self-directed training protocol at home. After 3–4 weeks the patients return for task-oriented training under supervision of a trained therapist. Night splints and weight-bearing restrictions are kept until 10 weeks postoperatively. The elbow is not splinted since data has shown secure safety margins for tension of the BR.⁴⁷

Side-to-side sutures

Side to side sutures are used in tendon transfers and in tendon lengthening. The tendons are sutured side-to-side with cross-stitches running along both sides overlapping 5 cm of donor and recipient tendons (Fig. 37.8). *In vitro* studies have shown that failure to load is more than 20 kg on this attachment,⁴⁸ which is twice as strong as the Pulvertaft weave.⁴⁹ In our unit we have used side-to-side sutures for several years now for all tendon transfers without any ruptures.

Restoring key pinch: the IC group 1 and 2 patient

Hints and tips

1. Do not release the A1 pulley of the thumb if the metacarpophalangeal (MP) joint flexes beyond 45°.
2. Routinely perform the split FPL-to-EPL transfer or the extensor pollicis longus shortening procedure.
3. If the thumb collapses into supination as the wrist is extended, perform the Brand modification of Moberg's procedure.
4. Always put a test suture to test the right tension in a tenodesis or transfer.




Fig. 37.8 Side-to-side suture technique.

Patients at the IC group 1 or 2 level are candidates for active wrist extension, BR-to-ECRB transfer, and creation of a lateral or key pinch as described by Moberg.³² Conceptually, this is a very simple operative procedure and, importantly, it represents an automatic pinch in that the tendon of the thumb flexor, the FPL, is anchored to the palmar surface of the radius under such tension that with wrist extension the thumb tip is pulled against the side of the index finger. The other fingers are usually left supple and the patient frequently must learn to roll these digits into some flexion in order to provide a platform against which the thumb can act. Gravity is needed to flex the wrist, releasing tension on the tenodesed FPL and allowing opening of the grip.

Provided that wrist extension power is adequate, the key steps of the procedure have evolved to currently include:

- Stabilization of the interphalangeal joint of the thumb
- Fixation of the tendon of the flexor pollicis longus to the radius at the correct tension




Fig. 37.9 A very effective method to stabilize the interphalangeal joint of the thumb without making it rigid. This procedure, attributed to Rothwell and Sinclair⁵⁰ has become universally accepted. (Redrawn after Hentz V, Leclercq C. *Surgical Rehabilitation of the Upper Limb in Tetraplegia*. London: Harcourt Health Sciences; 2002, with permission.)

- Usually stabilization of the thumb's carpometacarpal joint against excessive flexion.

The first step is stabilization of the interphalangeal joint of the thumb. The split flexor pollicis longus transfer as described by Mohammed *et al.*⁵⁰ or the ELK-tenodesis described by Fridén *et al.*⁵¹ These techniques eliminate the need for long-term hardware and preserve some active and even greater passive interphalangeal joint movement.

Split FPL-to-EPL interphalangeal stabilization

For an optimum result, the critical pulleys, including the oblique pulley of the flexor sheath of the thumb, must be preserved. The procedure may be carried out using the incisions outlined in Fig. 37.9A, or using just one incision along the radial midaxis of the thumb.

The zig-zag incision is made and the neurovascular bundle on the radial side of the digit is dissected. The neurovascular bundle is included within the skin flap to protect it. Frequently, there is a small annular ligament or pulley located at the level of the interphalangeal joint. This can be incised to visualize the flexor pollicis longus tendon (see Fig. 37.9B,C).

A blunt probe is used to find the naturally occurring midline split in the tendon's structure. This split is lengthened both distally and proximally. When the distal dissection reaches the insertion of the tendon, the radial half of the split flexor pollicis longus tendon is divided at its bony insertion. The tendon end is delivered into the wound. The proximal split is extended to the level of the MP joint. Finally, a small window into the flexor sheath is created just proximal to the oblique pulley and the detached radial half of the tendon is brought through this window.

If a second incision is used, it is located on the mid-dorsum of the thumb, over the course of the extensor pollicis longus. The radial half of the flexor pollicis longus is tunneled under

the intervening skin, *deep* to the radial digital nerve and brought out the dorsal incision.

The tendon slip is passed under the tendon of the extensor pollicis longus and then brought back over onto itself (see Fig. 37.9D). The thumb interphalangeal joint is temporarily stabilized in about 20° of flexion with a 0.045 Kirschner wire placed across the joint. The transferred slip of tendon is pulled distally until a noticeable slackening of the remaining tendon half is noted and then relaxed slightly so that there is equal tension on the slip of transferred tendon and on the original remaining half of the tendon (see Fig. 37.9E). Pinning the interphalangeal joint before final adjustment of tension makes this step much more easily accomplished. The transferred half of the tendon is sutured to itself and to the extensor pollicis longus with absorbable 4-0 sutures.

ELK-tenodesis

The interphalangeal joint of the thumb may also be stabilized by a shortening the EPL tendon on the dorsum of the thumb⁵¹ (Fig. 37.10). The joint is supposed to hyperextended after the procedure and will return to a more flexed position with the addition of a BR motor to the FPL.

Flexor pollicis longus tenodesis (passive key pinch)

The proximal tendon of the FPL is anchored to the distal radius augmenting the natural tenodesis of the thumb pinch with wrist extension.

The incision is made and in the interval between the flexor carpi radialis (FCR) and the palmaris longus (PL). The FPL muscle-tendon junction is just deep to this interval. The tendon is identified and the muscle-tendon junction divided as far proximal as possible. Next the FPL tendon is anchored to the



Fig. 37.10 Extensor pollicis longus-loop-knot (ELK)-tenodesis. The extensor pollicis longus is duplicated and sutured to itself, bringing the interphalangeal joint into hyperextension. The brachioradialis to flexor pollicis longus transfer will correct it into slight flexion.

radius at the proper tension. A 3- or 4-mm drill point is used to drill a hole from volar to dorsal through the radius, avoiding the radial wrist extensor tendons. A dorsal incision is designed at the site where the drill point exits the dorsal aspect of the radius. A loop of 30-gauge (3-0) monofilament wire is passed through the drill hole in a dorsal to palmar direction and the FPL tendon is placed in the loop and drawn through the radius. By pulling on the tendon, the tension can be adjusted so that the pulp of the thumb just contacts the radial side of the flexed index finger when the wrist is in the neutral position. When the wrist is flexed, the tension of the FPL is relaxed and the thumb ray will extend in response to the dorsal tenodesis/viscoelastic forces. After satisfactory tensioning of the FPL tendon, the FPL is anchored to the radius.

Postoperative rehabilitation

On the first postoperative day the patient starts early active mobilization of the new functions as described above. We have found the results of this technique predictable. We can measure the gain in pinch strength and it is typically proportional to the strength of the wrist extensor power but somewhat depends on the stability of the thumb and finger joints. Pinch strengths of 1–5 kg have been uniformly achieved.

IC group 2 and some IC group 3

Restoring active key pinch by brachioradialis (BR)-to-FPL transfer

Hints and tips

- Assess if arthrodesis of the thumb CMC joint will provide a more functional position ([Fig. 37.11](#)).
- Avoid CMC fusion if there is a stiff MP joint.
- Take care setting the BR tension.
- Always stabilize the interphalangeal joint of the thumb (as described earlier).




Fig. 37.11 Thumb carpometacarpal joint arthrodesis. Note the position of the thumb ray.

Patients in IC group 2–3 have by definition a functional BR and active wrist extension. Below are steps for reconstruction of the IC 2–3 ([Fig. 37.12](#)):

1. The CMC is evaluated and, if there is excess laxity, a CMC arthrodesis is performed to pre-position the thumb tip to contact the index finger middle phalanx.
2. The EPL tendon is anchored to the fibrous tissue in the third compartment on the dorsum of the wrist.
3. The brachioradialis is transferred to the tendon of the FPL.
4. The split FPL-to-EPL transfer or the EPL shortening is performed.
5. Interosseus stabilization (described below) for fingers to meet thumb in lateral key pinch.

Operative procedure

The operative steps are carried out via one longer and three or four smaller incisions as illustrated in [Fig. 37.12A](#). An FPL-to-EPL interphalangeal joint stabilization procedure is completed as illustrated in [Fig. 37.12B](#). If needed, the CMC joint is then exposed through an incision made along the juncture of the glabrous and hair-bearing skin over the palmar–radial aspect of the thumb's thenar eminence. The thenar muscles are reflected off the capsule of the CMC joint and the capsule opened. The adjacent joint surfaces are prepared for arthrodesis by sharp excision of all cartilage and by perforating the




Fig. 37.12 A procedure to restore active key pinch. The carpometacarpal joint of the thumb is stabilized by fusion, the thumb interphalangeal joint by split flexor pollicis longus (FPL) to extensor pollicis longus (EPL) tenodesis, the EPL is tenodeses to the radius so that the thumb extends with wrist flexion and the brachioradialis is transferred to the FPL to provide potential voluntary pinch irrespective of wrist position. (Redrawn after Hentz V, Leclercq C. *Surgical Rehabilitation of the Upper Limb in Tetraplegia*. London: Harcourt Health Sciences; 2002, with permission.)

dense subchondral bone in several areas on the metacarpal base and the face of the trapezium. Bone is removed with a small osteotome, curette, or powered burr equally from both sides of the joint. This maintains the relative contours of metacarpal base and trapezium and good bone-to-bone contact between the two surfaces.

Correct positioning of the CMC fusion is a critical step. Both palmar and radial abduction are considered and final position is determined by the preoperative flexor tenodesis pattern and the passive range of motion at the thumb's MP joint. The ideal position goal is to have the pulp of the thumb contact the radial side of the index finger middle phalanx with wrist extension. Opening of the grip depends upon wrist flexion and occurs almost exclusively at the MP joint. The ideal candidate has a well-preserved tenodesis pattern and passive MP flexion exceeds the range of CMC extension. For such a patient, the thumb ray should be positioned in only about 20° of palmar abduction, and almost maximum radial abduction. A thumb ray fused in too much palmar abduction will interfere with transfers and pressure-relief efforts. If the patient has poor finger flexion as the wrist is extended, the CMC joint should be arthrodesed in a slightly less palmarly abducted posture. If MP flexion is limited, the CMC joint should be fused in less than maximal radial abduction. If too radially abducted, the patient with a poorly flexible MP joint will not achieve firm contact between pulp of thumb and index finger.

The CMC joint is temporarily pinned with a 2-mm Kirschner wire to test positioning. If the position seems ideal, the joint is further stabilized. A small four-corner plate or a locking-plate has provided sufficiently rigid bone-to-bone contact. Locking-plates provide more stable fixation and are associated with fewer non-unions than conservative fixation methods.⁵²

The third step involves creating a firm tenodesis of the EPL. Since the CMC joint is now fused, no particular EPL re-routing is needed. Through a transverse incision made just proximal to Lister's tubercle, the tendon of the EPL is located and divided at its muscle-tendon junction, withdrawn at the level of the MP joint, passed proximally and under the tendons of the first dorsal compartment, and then toward the third compartment. This provides an extensor-abductor vector when the wrist is flexed. The EPL is anchored to the dense fibrous tissue between the third and fourth extensor compartment using with several non-absorbable sutures. The thumb should reach maximum extension as the wrist reaches 45° of flexion but the pulp of the thumb should contact the radial side of the index finger as the wrist reaches the neutral position.

The last procedure involves BR-to-FPL transfer.⁵³ The FPL is identified in the volar forearm, either through the same incision used to dissect the BR or through a separate volar incision. The FPL is divided at its muscle-tendon junction and the two tendons are directed in as straight a line as possible toward one another. The end of the BR tendon is passed through the FPL tendon and a side-to-side suture is performed. The ideal tension for the transfer is established as described for BR-to-ECRB transfer. The juncture is created with the elbow in 40° of flexion, the wrist in a neutral position, and the index finger held flexed at MP and proximal interphalangeal joints. The BR is pulled distally to a point midway between maximum passive stretch and fully relaxed (zero-tension)

tension and the FPL tendon is pulled proximally so that the pulp of the thumb just touches the radial side of the index finger. The assistant maintains this posture of both tendons while the surgeon joins together the two tendons with a test suture. The tension of the FPL transfer and the EPL tenodesis is tested by gently moving the wrist between 45° of flexion and 45° of extension. It is important that the thumb still fully extends at the MP joint with wrist flexion after BR transfer. The wounds are closed and the limb solidly immobilized in a below-elbow cast that maintains the wrist in a neutral position and the thumb MP joint in some flexion. We typically place the thumb in contact with the flexed index finger.

Other options

The BR can be transferred to the deep flexors (flexor digitorum profundus [FDP] index-ring) for active grip and the thumb may get a passive key pinch driven by an active wrist extension. We have done a few patients with this combination with promising outcomes.

Postoperative rehabilitation

On the first postoperative day the patient starts early active mobilization of the new functions as described above. At the beginning of the third or fourth postoperative week, the patient starts task-oriented training under supervision of a trained therapist. The therapist constructs a small hand-based splint to protect the CMC joint fusion. The use of night splints and weight-bearing transfers on the hand are restricted until about 10 weeks postoperatively.

IC groups 3, 4 and 5

Restoring active key pinch, grasp, and release in one operative stage

Historically these patients were treated using a two-stage technique first establishing hand opening and then a second procedure for closing/grasp. However, the higher-volume centers have found that this can be completed in a single stage. Both techniques utilize two expendable muscles for transfer, the ECRL and the BR may be performed.⁵⁴ Outcomes have shown stronger grip strength and better opening after the single-stage procedure.⁵⁵ Prerequisites for these procedures include near-normal passive wrist movement and reasonably flexible fingers. These patients may possess useful triceps function. If not, this function should be restored.

The single-stage grip and release procedure⁵⁴ (Video 37.1)

Hints and tips

- It is critical to be certain of the true strength of the ECRB before transferring the ECRL.
- Before detaching ECRL from its insertion the ECRB insertion should be visualized to avoid mistakes.
- While tensioning the tendon slips in the House procedure the position of joints are important: 60° flexion of metacarpal joints (MCP) and fully extended interphalangeal joints (IP).

Surgical order of procedures:

- Split FPL-to-EPL transfer or EPL shortening⁵¹
- Thumb CMC joint arthrodesis
- Intrinsic substitution procedure (House⁵⁶ procedure)
- BR transfer to the FPL
- ECRL transfer to the FDP II–IV
- Re-routed passive tenodesis of the thumb (EPL)
- ECU-tenodesis to correct for radial wrist deviation deformity.⁵⁷

The very strong IC group 3 patient will have at least one of the two radial wrist extensors at MRC grade 5. The other will probably be MRC grade 4. The surgeon must proceed with care as it is a grave error to transfer the ECRL and lose strong wrist extension. This is a real risk since it is impossible to perfectly isolate and assess ECRB strength in preoperative testing. However, these patients commonly have some function of the pronator teres (PT). If the PT is intact one can assume both wrist extensors are functional.⁵⁸ Another method to assess if both wrist extensors are functional (grade 4 or more) is that a groove occurs between the bellies of the ECRL and ECRB, known as “Bean’s sign”.⁵⁰ If there is any question of the ECRB strength, it can be tested intraoperative. The ECRB tendon is exposed just distal to the extensor retinaculum under local anesthesia, a probe is slipped under the tendon and the patient is asked to forcefully extend the wrist. If the muscle is MRC grade 4 or 4+, the tendon cannot be displaced by the surgeon’s probe. This can be done at the start of the surgery and if the ECRB is judged to be sufficiently strong and direct the next steps of the procedure.

The ECRL and BR tendon transfers start with a long dorsal incision (as described for BR transfer). The ECRL and BR tendons are mobilized and then passed volarly. The BR is sutured to the FPL (side-to-side). The tendons of the FDP are synchronized. Some advocate setting the finger cascade with slightly more opening of the ulnar sided digits: a “reverse cascade”. The theory is that this allows easier ability to get hand around object. The tendon of the ECRL is passed obliquely through the synchronized FDPs and attached with side-to-side sutures. The FDP of the little finger is left out of the transfer, but will be passively flexed by connections between the muscles of the little and the ring finger. Tension of this transfer is adjusted so that a relatively natural posture of the fingers is achieved with wrist flexion and extension. A bandage roll (4 cm in diameter) placed in the palm facilitates the tensioning of the fingers and the creation of a normal finger cascade. It is preferable to tension this transfer after intrinsic stabilization is performed (see below.) The BR-to-FPL transfer is tensioned so that with the wrist in neutral, the thumb pulp just touches the side of the flexed index finger. Early active mobilization is very important when performing several simultaneous procedures.

Intrinsic stabilization

The intrinsic muscles are critical to hand function. Without intrinsics, grip strength is considerably weakened and finger abduction at the metacarpophalangeal joint is lost. Even though the long flexors of the fingers can flex all the intervening joints, without the synchronizing effects of the intrinsic muscles, in flexion the fingertips touch only to the bases of the fingers rather than the center of the palm. This rolling up

of the fingertip seen when intrinsics are lacking tends to push large objects out of the grasp.

The second major biomechanical function of the intrinsic muscles is assisting the extrinsic extensors to extend the interphalangeal joints. Without intrinsic muscle activity, the extrinsic muscle action at the metacarpophalangeal joint is unopposed, hyperextending the MP joint. Furthermore, this MP hyperextension increases the viscoelastic tone of the long flexors, inducing flexion at the interphalangeal joints. This imbalance gives rise to the “claw hand” characterized by metacarpophalangeal hyperextension and interphalangeal joint flexion.

For most people with tetraplegia, the absence of intrinsic muscle function may also result in an imbalance between the paralyzed extrinsic flexors and extensors. The preoperative hand of patients in IC groups 1–5 possesses only residual passive tenodesis grasp and release. For these patients, the tendency for the finger to claw as the wrist is flexed may represent only a cosmetic annoyance. However, reconstructive procedures to improve digital flexion and extension may accentuate the clawed posture by adding tone to both extrinsic extensors and flexors. In this circumstance, the claw deformity frequently becomes a functional liability.

House and Walsh⁵⁹ found that some type of intrinsic substitution improves the grasp in the tetraplegic patient who undergoes candidate for a grasp-release procedure. Since most people with tetraplegia do not possess sufficient transferable muscles to allow intrinsic substitution by standard tendon transfer procedures, static procedures are utilized. Two procedures have been described: the first attributed to Zancolli⁶⁰ and termed the “lasso” procedure, and the other described by House *et al.*⁵⁷

Zancolli “lasso” procedure

In IC groups 3, 4 and 5, the flexor digitorum superficialis (FDS) muscles are paralyzed, typically at the upper motor neuron level. As such, they retain some stretch reflexes through the intact spinal reflex arc and relatively normal viscoelastic properties. Zancolli⁶⁰ proposed using these paralyzed muscles as an elastic tenodesis to reduce metacarpophalangeal joint hyperextension and lessen the clawed posture of the tetraplegic hand (Fig. 37.13A–F). In this technique, superficialis tendon of a clawed finger is released distally and inserted into the flexor sheath at the distal margin of the A1 pulley or the proximal part of the A2 pulley. The tendon is placed under slight tension. The superficialis tendon now becomes a flexor of the MCP joint.

The mechanical basis for this dynamic tenodesis procedure is debated. Zancolli believes that the transfer must be fixed under significant tension in order to still provide MCP flexor tone even with the wrist near-maximally flexed. If this transfer is performed as part of the flexor phase, it is preferable to first perform the “lasso” procedure before adjusting the tension of the finger flexor transfer.

House intrinsic tenodesis

This procedure, described by House *et al.*,⁵⁵ is a modification of Riordan’s tenodesis procedure.⁶¹ In the patient with tetraplegia, the procedure (Fig. 37.14) is usually performed on all four fingers. However, it is sometimes performed for only the index and middle finger, since these fingers are the most




Fig. 37.13 The Zancolli "lasso" procedure (A–F). Either several longitudinal incisions or one longer transverse incision can be made. The flexor digitorum superficialis is divided distal to the A1 pulley, looped about the pulley, and sutured to itself proximal to the pulley under strong tension. If the metacarpophalangeal joints remain nearly fully flexed with the wrist in neutral, proper tension has been achieved. (Redrawn after Hentz V, Leclercq C. *Surgical Rehabilitation of the Upper Limb in Tetraplegia*. London: Harcourt Health Sciences; 2002, with permission.)




Fig. 37.14 The House intrinsic substitution procedure. The tendon loops have to go volar to the intermetacarpal ligaments.

critical in grasp and release functions. A tendon graft is needed: PL or FDS ring is harvested and split into two slips. Mediolateral or oblique incisions are made on the proximal phalanx of each finger and two small incisions on the dorsum of the hand. With the MCP in 60° of flexion and extended IP joints, the first slip is tunneled from the radial side of the phalanx of the index finger under the insertion of the first dorsal interosseous, and then under tendons of the extensor communis of the index and the extensor indicis proprius. After that the tendon slip is tunneled through the lumbrical canal, volar to the intermetacarpal ligaments, and sutured onto the lateral and central band. The other tendon slip is tunneled through lumbrical canals of the fourth and fifth digits.

ECU-tenodesis

The ECU-tenodesis is a passive tenodesis.⁶ Patients with tetraplegia typically present with a radial deformity of the wrist, which impairs grip strength.⁵⁷ The correction starts with a curved incision made over the ulnar head and the sixth extensor compartment is opened. The dorsal sensory branch of the ulnar nerve is protected. The wrist is ulnarly deviated and the ECU is lifted with a tendon elevator, the tendon is then shortened until the radial deviation deformity is gone. The excess tendon is secured onto the ulnar head with a couple of mattress sutures (Fig. 37.15). This is usually the last procedure in the single-stage grip release reconstruction.

Finally before closing the wounds the tenodeses and the passive interosseous function should be tested to allow for adjustments.

Postoperative rehabilitation

On the first postoperative day the patient starts early active mobilization. After the intrinsic stabilization procedure, the patient is restricted from full finger flexion for 4 weeks. The protocol allows for flexion up to a digit–palm distance of 3 cm. After 4 weeks, the patient is allowed to gradually flex all the way. Full load is allowed after 8 weeks. Despite the full finger flexion restriction, the task-specific training starts at 3 weeks postoperatively including active wheelchair maneuvering and all types of daily activities. Complications are rare, provided that the patient follows the rehabilitation protocol and the gains are highly appreciated by the patients.^{62,63}

Other procedures

In IC group 4, the PT is strong and available for transfer. In IC group 5, the flexor carpi radialis (FCR) is strong, but experience has shown that it should not be used as a transfer. Therefore, the surgical options are similar for both IC groups 4 and 5.

The PT is the only functioning pronator muscle in these IC group 4 and 5 patients. However after transfer, the PT will retain most of its pronator function if the transfer pull is the same direction as the original tendon's pull. The PT can be safely transferred to the FPL though an interposition tendon graft may be needed. The BR is then available for another functions, such as transfer to extensor digitorum communis (EDC) and EPL for finger and thumb extension. This is done if other techniques failed to provide adequate hand opening and there is enough volar stabilization of the wrist (FCR with MRC strength 3 or above). If BR-to-EDC/




Fig. 37.15 Extensor carpi ulnaris tenodesis to correct for wrist radial deviation deformity.

EPL is chosen, tension is set with the elbow in 40° flexion, the wrist in a neutral position, and the MP joint in about 20° of flexion. Tension should be such that, during passive flexion of the wrist, the MP joints start extending when the wrist reaches neutral from an extended position. The tension on the EPL tendon should be adjusted last and its tension is typically set slightly looser than that of the EDC. The fingers should exhibit full passive flexion when the wrist is fully extended.

Alternative procedures for IC groups 4 and 5 include various combinations of procedures already described. Since patients differ, it is important to be able to plan for variations in patient presentation and individual functional objectives. The greatest variation in hand use has been a consequence of the management of the thumb's CMC joint. A fused CMC joint, while predictably pre-positioning the thumb, does limit the size of objects easily grasped within the first webspace. If the CMC joint is left mobile, the postoperative position of the thumb ray is less predictable, sometimes significantly so, but larger objects can be pushed into the first webspace and held.

IC groups 6, 7, 8 and 9

Patients classified at the IC 6 level possess active digital extension but lack thumb extension, interosseous function, and grip strength. They require the multiple tendon transfers to achieve balanced thumb pinch and strong finger grasp as described earlier as well as adding an extensor force for the thumb. Transfer of extensor digiti minimi (EDM) to abductor pollicis brevis (APB) is a good option for better thumb movement.⁶⁴ Volar abduction of the thumb is useful for fine motor skills

and usually much appreciated by the patients. We have used EDM with grade 3 muscle strength with satisfactory results; as volar abduction does not require much strength.

Patients with an even greater number of remaining resources, such as patients in IC groups 7–9, can be reconstructed similarly to patients with a lower peripheral nerve injury. The surgical procedures performed for these patients are directed at reconstructing some aspects of hand intrinsic muscle function and balance. The interosseus function can be made active by using an active superficial flexor digitorum (FDS) tendon of the ring finger, splitting it into four slips if the tendon size allows it. Alternatively, FDS long and ring can be split into two slips each. This Stiles–Bunnell transfer⁷ may be considered in cases with incomplete tetraplegia or in group 8. There are relatively few patients with tetraplegia in these categories compared to the IC 2–5 categories.

Group X and spasticity

Group X has a mixed pattern and many patients with incomplete tetraplegia belong to this group.

Up to 78% of patients with traumatic spinal cord injury develop spasticity and this is primarily treated with conservative treatment methods such as physiotherapy, splints, baclofen, and botulinum toxin A injections. Before surgery is considered, conservative treatment must be thoroughly explored. Surgical treatment reduces spasticity by lengthening of tendons, releasing muscles, and sometimes correcting deformities.⁶⁵ Short-term (1 year follow-up) outcomes are encouraging. The patients open their hands well and also gain grip strength even though the tendons are lengthened. We have ongoing studies to evaluate the durability.




Fig. 37.16 A multichannel functional electrical stimulation. (Redrawn after Kilgore KL, Hoen HA, Bryden AM, et al. An implanted upper extremity neuroprosthesis utilizing myoelectric control. *J Hand Surg Am.* 2008;33:539–550.)

Future directions

Nerve transfers

Nerve transfers have long been a treatment of choice for patients with brachial plexus injuries, but have recently been explored for the tetraplegic population. Bertelli described using a brachialis nerve branch to triceps to restore elbow extension in 2012.⁶⁶ Fridén used a brachialis nerve branch to restore wrist extension for a patient in IC group 0.⁴⁰ Mackinnon presented cases in 2013 using peripheral nerve transfers for tetraplegia⁶⁷ and Van Zyl described a triple nerve transfer⁶⁸: teres minor nerve branch to long head of triceps, brachialis nerve branch to anterior interosseous, and supinator nerve branch to posterior interosseous. These transfers successfully restored elbow extension, grasp, release, and key pinch.

In our center we have performed supinator nerve branch to posterior interosseous nerve transfer. This procedure requires minimal postoperative restrictions: a plaster splint for 2 weeks to protect the nerve coaptation. Preoperative testing of muscle function and electromyography assesses whether the target muscle can be stimulated. There is debate as to what is the appropriate timing of nerve transfers in this population. Early evidence suggests that timing of nerve transfers for patients with tetraplegia is similar to peripheral nerve injury (earlier reconstruction is better). However, recruiting these complex patients so soon after their injuries is challenging.

Another challenge for nerve transfers is the long wait before functional gains are seen. After tendon transfer surgery, the patient can see the new movement the day after surgery whereas a year may pass before the patient sees results from a nerve transfer. We believe an approach using all the available tools: nerve transfers combined with tendon transfers will provide the best results.⁶⁹ An active finger extension for release combined with tendon transfers for a strong grip and key pinch seems as an attractive combination.

Functional neuromuscular stimulation

Functional electrical stimulation (FES) is an exciting adjuvant for improving arm function in these patients. The initial commercially available system was an eight epimysial electro-channel device called the Freehand System. This system allowed patients with very high spinal injury to activate and control a pre-programmed sequence of muscle contractions and achieve a useful grasp for one hand.^{69–72} Research continues on this system and current models have the ability to stimulate 12 muscles.⁷³ These systems of electrodes are often the only option to restore useful function in limbs heretofore deemed unreconstructable by standard surgical techniques. We hope that as further research proceeds, these devices may again become commercially available (Fig. 37.16).

Outcomes and complications

These procedures have evolved over time and can provide predictable improvement in function. The surgery also provides a great impact on activity and participation aspects in the patient's life.^{74,63,39} Both practical issues in daily life and psychological aspects have shown to improve.⁶³ A systematic review provided data on the average outcomes for the most common of these procedures – posterior deltoid-to-triceps transfer and procedures to restore pinch. For the deltoid to triceps, the average postoperative strength was 3.3 MRC. This would certainly allow stabilization of the arm in space. Complications were not infrequent at 25%, with the most frequent being rupture or stretching of the repair. Since we implemented side-to-side sutures we have not seen any ruptures or elongations of attachments. Pinch-reconstruction procedures were divided into those with active motors, such as a BR, or those that were simply a FPL tenodesis or Moberg procedure. The mean postoperative strength after both types of pinch surgery was 1.9 kg. The mean postoperative strength after FPL tenodesis was 1.17 kg, and for those using an active motor, postoperative strength was 2.32 kg. There was a 40% rate of complications

in this review. The most common complications were flexion contracture of the elbow or of the thumb, stretching or rupture of repair, and loosening of pins across the thumb IP joint. Two of these complications, flexion contracture of the thumb and loosening of pins, are no longer applicable as the procedures have evolved to address these complications (we no longer fuse the IP joint and do not release the A1 pulley).

These procedures are also very durable.^{22,75} Hentz *et al.* examined 45 patients who had been operated at least 10 years prior to evaluation. A total of 21 of these patients had undergone elbow extensor reconstruction; 15 patients had posterior deltoid to triceps transfer; and 10 had bilateral transfers. Fifteen required a motorized wheelchair as their primary means of movement before surgery. At 10 years after surgery, nine now used a pushchair as their standard chair and four others used a pushchair at least some of the time. There were three patients who had undergone bilateral posterior deltoid-to-triceps transfer who were able to self-transfer in the early postoperative period. All three continued to be able to perform this monumental, for a tetraplegic, task. In the six patients that had biceps-to-triceps transfer (all needing contracture release), two could use a pushchair, but not exclusively so. None had developed a recurrence of elbow contracture.

The second goal was the restoration of some hand function. IC group 2 patients typically had key grip fashioned by tenodesis of the FPL to the radius. Seven were evaluated for more than 10 years. Five had maintained pinch strength essentially equivalent to that demonstrated 6–12 months following surgery. The IC group 3 patients typically had transfer of BR to FPL to restore dynamic voluntary key pinch. Six were evaluated and all had maintained useful power, which averaged 20 N.

Historically, groups 3, 4 and 5 were treated in two stages: the flexor and the extensor phase. For 10 years a Swedish group has performed the single-stage grip and release procedure as

described above (Video 37.2 ). A traditional (staged) group of 18 hands were compared with the single-stage procedure (16 hands). All patients had early active mobilization. The single-stage group had a significantly stronger grip strength postoperatively, 6.5 kg, compared to the historical group, 1.6 kg, and significantly better opening of the hand: 5.5 cm vs. 3.0 cm. The key pinch was about the same: 2.8 kg vs. 2.0 kg.⁵⁵ Several surgeons found, as did House and Walsh,⁵⁹ that those patients who had had some type of intrinsic stabilization, either by Zancolli lasso⁶⁰ or by House *et al.*'s intrinsic reconstruction procedure,⁵⁶ had, on average, more powerful grasp. This may be a product of pre-selection as the stronger patients may have been chosen for intrinsic substitution. The last years have brought several case reports of different nerve transfers. This is an exciting new field to be further researched as it is still too early to assess the outcomes.

Conclusions

Carefully planned upper limb reconstructive procedures in tetraplegia are both effective and durable. Systematic post-injury evaluation of their upper limbs should become a standard part of care of the person with tetraplegia. Aside from their brain, the upper limbs remain the most important residual resource for people with tetraplegia. The value of greater independence is difficult to quantify, but many of our patients express relief for being able to feed themselves and perform their daily activities. Patients have said "Everything goes faster now"; "I don't need to bring my personal assistant on dates anymore"; "I can send my own texts"; "I've started to work again"; "I can visit restaurants again and eat by myself, even cutting beef." These surgeries can be the pinnacle of hand surgery restoring function to those in great need.



Access the complete reference list online at <http://www.expertconsult.com>

6. Hentz VR, Leclercq C. *Surgical Rehabilitation of the Upper Limb in Tetraplegia*. London: Harcourt Health Sciences; 2002. *This is the most up-to-date monograph devoted to the field of upper extremity reconstruction for tetraplegia. It delves into all of the nuances of these procedures.*
7. Bunnell S. *Surgery of the Hand*. Philadelphia, PA: JB Lippincott; 1944.
28. Kozin SH, D'Addesi L, Chafetz RS, et al. Biceps-to-triceps transfer for elbow extension in persons with tetraplegia. *J Hand Surg Am*. 2010;35:968–975. *This article presents the key technical details for biceps to triceps transfer. The illustrations simplify the procedure. The postoperative regimen is clearly described.*
32. Moberg E. Surgical treatment for absent single-hand grip and elbow extension in quadriplegia. *J Bone Joint Surg Am*. 1975;57:196–206. *This is the classic article that must be read by anyone contemplating operating on a tetraplegic patient. It describes two key procedures, the Moberg key pinch and deltoid to triceps transfer.*
42. Freehafer AA. Gaining independence in tetraplegia. Cleveland technique. *Clin Orthop*. 1998;355:282–289. *This article represents a summary of techniques and pearls.*
47. Fridén J, Shillito MC, Chebab EF, et al. Mechanical feasibility of immediate mobilization of the brachioradialis muscle after tendon transfer. *J Hand Surg Am*. 2010;35:1473–1478.
48. Brown SH, Hentzen ER, Kwan A, et al. Mechanical strength of the side-to-side versus Pulvertaft weave tendon repair. *J Hand Surg Am*. 2010;35:540–545.
50. Mohammed KD, Rothwell AG, Sinclair SW, et al. Upper-limb surgery for tetraplegia. *J Bone Joint Surg Br*. 1992;74:873–879.
54. Fridén J, Reinholdt C, Turcsanyii I, et al. A single-stage operation for reconstruction of hand flexion, extension, and intrinsic function in tetraplegia: the alphabet procedure. *Tech Hand Up Extrem Surg*. 2011;15:230–235.
59. House J, Walsh T. Two stage reconstruction of the tetraplegic hand. Master techniques in orthopaedic surgery. In: Strickland JW, ed. *The Hand*. Philadelphia, PA: Lippincott; 1998:60.

References

- Anderson KD. Targeting recovery: priorities of the spinal cord-injured population. *J Neurotrauma*. 2004;21:1371–1383.
- Cizmar I, Zalesak B, Pilny J, et al. Possible restorations of the upper extremity motion in tetraplegic patients – 5-year clinical experience. *Biomed Pap Med Fac Univ Palacky Olomouc Czech Repub*. 2006;150:313–319.
- Meiners T, Abel R, Lindel K, et al. Improvements in activities of daily living following functional hand surgery for treatment of lesions to the cervical spinal cord: self-assessment by patients. *Spinal Cord*. 2002;40:574–580.
- Fridén J, Reinholdt C. Current concepts in reconstruction of hand function in tetraplegia. *Scand J Surg*. 2008;97:341–346.
- Curtin CM, Gater DR, Chung KC. Upper extremity reconstruction in the tetraplegic population, a national epidemiologic study. *J Hand Surg Am*. 2006;30:94–99.
- Hentz VR, Leclercq C. *Surgical Rehabilitation of the Upper Limb in Tetraplegia*. London: Harcourt Health Sciences; 2002. *This is the most up-to-date monograph devoted to the field of upper extremity reconstruction for tetraplegia. It delves into all of the nuances of these procedures.*
- Bunnell S. *Surgery of the Hand*. Philadelphia, PA: JB Lippincott; 1944.
- Grover J, Gellman H, Waters RL. The effect of a flexion contracture of the elbow on the ability to transfer in patients who have quadriplegia at the sixth cervical level. *J Bone Joint Surg Am*. 1996;78:1397–1400.
- Salisbury SK, Choy NL, Nitz J. Shoulder pain, range of motion, and functional motor skills after acute tetraplegia. *Arch Phys Med Rehabil*. 2003;84:1480–1485.
- Moberg E. Hand surgery and the development of hand prostheses. *Scand J Plast Reconstr Surg*. 1975;9:227–230.
- Moberg E. *The Upper Limb in Tetraplegia. A New Approach to Surgical Rehabilitation*. Stuttgart: George Thieme; 1978.
- Wangdell J, Fridén J. Performance of prioritized activities is not correlated with functional factors after grip reconstruction in tetraplegia. *J Rehabil Med*. 2011;43:626–630.
- McDowell CL, Moberg EA, Smith AG. International conference on surgical rehabilitation of the upper limb in tetraplegia. *J Hand Surg Am*. 1979;4:387–390.
- Hentz VR, Keoshian L. Changing perspectives in surgical hand rehabilitation in quadriplegic patients. *Plast Reconstr Surg*. 1979;64:509–515.
- Hentz VR. Historical background and changing perspectives in surgical reconstruction of the upper limb in quadriplegia. *J Am Paraplegia Soc*. 1984;2:36–38.
- Hentz VR, Hamlin C, Keoshian LA. Surgical reconstruction in tetraplegia. *Hand Clin*. 1988;4:601–607.
- Ditunno JF, Stover SL, Freed MM, et al. Motor recovery of the upper extremities in traumatic quadriplegia: a multicenter study. *Arch Phys Med Rehabil*. 1992;73:431–436.
- Curtin M. Development of a tetraplegia specific assessment and splinting protocol. *Paraplegia*. 1994;32:159–169.
- DiPasquale-Lehnerz P. Orthotic intervention for development of hand function with C6 quadriplegia. *Am J Occup Ther*. 1994;48:138–144.
- Krajnik SR, Bridle M. Hand splinting in quadriplegia: current practice. *Am J Occup Ther*. 1992;46:149–156.
- Bradbury CL, Wodchis WP, Mikulis DJ, et al. Traumatic brain injury in patients with traumatic spinal cord injury: clinical and economic consequences. *Arch Phys Med Rehabil*. 2008;89(12 suppl):S77–S84.
- Dunn JA, Rothwell AG, Mohammed KD, et al. The effects of aging on upper limb tendon transfers in patients with tetraplegia. *J Hand Surg Am*. 2014;39:317–323.
- Law M, Baptiste S, McColl M, et al. The Canadian occupational performance measure: an outcome measure for occupational therapy. *Can J Occup Ther*. 1990;57(2):82–87.
- Fridén J, Reinholdt C, Wangdell J, et al. Upper extremity reconstruction in non-traumatic spinal cord injuries: an under-recognized opportunity. *J Rehabil Med*. 2014;46:33–38.
- Zancolli E. *Structural and Dynamic Basis of Hand Surgery*. Philadelphia, PA: JB Lippincott; 1968.
- Zancolli E. Surgery for the quadriplegic hand with active, strong wrist extension preserved. *Clin Orthop Relat Res*. 1975;112:101–113.
- Zancolli E. *Structural and Dynamic Bases of Hand Surgery*. 2nd ed. Philadelphia, PA: JB Lippincott; 1979.
- Kozin SH, D'Addesi L, Chafetz RS, et al. Biceps-to-triceps transfer for elbow extension in persons with tetraplegia. *J Hand Surg Am*. 2010;35:968–975. *This article presents the key technical details for biceps to triceps transfer. The illustrations simplify the procedure. The postoperative regimen is clearly described.*
- Kuz JE, Van Heest AE, House JH. Biceps-to-triceps transfer in tetraplegic patients: report of the medial routing technique and follow-up of three cases. *J Hand Surg Am*. 1999;24:161–172.
- Friedenberg Z. Transposition of the biceps brachii for triceps weakness. *J Bone Joint Surg Am*. 1954;36:656–658.
- Gellman H, Kan D, Waters RL, et al. Rerouting of the biceps brachii for paralytic supination contracture of the forearm in tetraplegia due to trauma. *J Bone Joint Surg Am*. 1994;76:398–402.
- Moberg E. Surgical treatment for absent single-hand grip and elbow extension in quadriplegia. *J Bone Joint Surg Am*. 1975;57:196–206. *This is the classic article that must be read by anyone contemplating operating on a tetraplegic patient. It describes two key procedures, the Moberg key pinch and deltoid to triceps transfer.*
- Moberg E. Reconstructive hand surgery in tetraplegia, stroke, and cerebral palsy: some basic concepts in physiology and neurology. *J Hand Surg Am*. 1975;1:29–34.
- Lamb DW. Upper limb surgery in tetraplegia. *J Hand Surg [Br]*. 1989;14:143–144.
- Allieu Y, Benichou M, Teissier J, et al. La réanimation du membre supérieur du tétraplégique par transferts tendineux. *Chirurgie*. 1986;112:736–743.
- Mennen U, Boonzaier A. An improved technique of posterior deltoid to triceps transfer in tetraplegia. *J Hand Surg [Br]*. 1991;16:197–201.
- Allieu Y. *Le Membre Supérieur du Tetraplégique*. Conférences d'enseignement du GEM. Paris: L'expansion Scientifique; 1994.
- Bunnell S. *Tendon Transfers in the Hand and Forearm*. American Academy of Orthopedic Surgery – Instructional Course Lectures 6. St Louis: Mosby; 1949:106–112.
- Wangdell J, Fridén J. Activity gains after reconstructions of elbow extension in patients with tetraplegia. *J Hand Surg Am*. 2012;37:1003–1010.
- Fridén J, Gohritz A. Brachialis-to-extensor carpi radialis longus selective nerve transfer to restore wrist extension in tetraplegia: case report. *J Hand Surg Am*. 2012;37:1606–1608.
- Freehafer A, Mast W. Transfer of the brachioradialis to improve wrist extension in high spinal cord injury. *J Bone Joint Surg Am*. 1967;49:648–652.
- Freehafer AA. Gaining independence in tetraplegia. Cleveland technique. *Clin Orthop*. 1998;355:282–289. *This article represents a summary of techniques and pearls.*
- Johnson DL, Gellman H, Waters RL, et al. Brachioradialis transfer for wrist extension in tetraplegic patients who have fifth-cervical-level neurological function. *J Bone Joint Surg Am*. 1996;78:1063–1067.
- Brys D, Waters R. Effect of triceps function on the brachioradialis transfer in quadriplegia. *J Hand Surg Am*. 1987;12:237–239.
- Waters RL, Stark LZ, Gubernick I, et al. Electromyographic analysis of brachioradialis to flexor pollicis longus tendon transfer in quadriplegia. *J Hand Surg Am*. 1990;15:335–339.
- Fridén J, Albrecht D, Lieber RL. Biomechanical analysis of the brachioradialis as a donor in tendon transfer. *Clin Orthop*. 2001;383:152–161.
- Fridén J, Shillito MC, Chebab EF, et al. Mechanical feasibility of immediate mobilization of the brachioradialis muscle after tendon transfer. *J Hand Surg Am*. 2010;35:1473–1478.
- Brown SH, Hentzen ER, Kwan A, et al. Mechanical strength of the side-to-side versus Pulvertaft weave tendon repair. *J Hand Surg Am*. 2010;35:540–545.

49. Pulvertaft G. Repair of tendon injuries in the hand. *Ann Royal Coll Surg.* 1948;3:14.
50. Mohammed KD, Rothwell AG, Sinclair SW, et al. Upper-limb surgery for tetraplegia. *J Bone Joint Surg Br.* 1992;74:873–879.
51. Fridén J, Reinholdt C, Gohritz A. The extensor pollicis longus-loop-knot (ELK) procedure for dynamic balance of the paralyzed thumb interphalangeal joint. *Tech Hand Up Extrem Surg.* 2013;17:184–186.
52. Ruchelsman DE, Mudgal CS, Jupiter JB. The role of locking technology in the hand. *Hand Clin.* 2010;26:307–319.
53. Johanson ME, Hentz VR, Smaby N, et al. Activation of brachioradialis muscles transferred to restore lateral pinch in tetraplegia. *J Hand Surg Am.* 2006;31:747–753.
54. Fridén J, Reinholdt C, Turcsanyii I, et al. A single-stage operation for reconstruction of hand flexion, extension, and intrinsic function in tetraplegia: the alphabet procedure. *Tech Hand Up Extrem Surg.* 2011;15:230–235.
55. Reinholdt C, Fridén J. Outcomes of single-stage grip-release reconstruction in tetraplegia. *J Hand Surg Am.* 2013;38:1137–1144.
56. House JH, Gwathmey FW, Lundsgaard DK. Restoration of strong grasp and lateral pinch in tetraplegia due to cervical spinal cord injury. *J Hand Surg Am.* 1976;1:152–159.
57. Reinholdt C, Fridén J. Rebalancing the tetraplegic wrist using extensor carpi ulnaris-tenodesis. *J Hand Surg Eur Vol.* 2013;38:22–28.
58. Allieu Y. *Rehabilitation Chirurgicale du Membre Superior du Tetraplegique.* Cahiers: SOFCOT; 1988;233–255.
59. House J, Walsh T. Two stage reconstruction of the tetraplegic hand. Master techniques in orthopaedic surgery. In: Strickland JW, ed. *The Hand.* Philadelphia, PA: Lippincott; 1998:60.
60. Zancolli E. Correccion de la “garra” digital por paralisis intrinseca. La operacion del lazo. *Acta Ortop Latinoam.* 1974;1:65–71.
61. Riordan D. Tendon transplantation in median-nerve and ulnar nerve paralysis. *J Bone Joint Surg Am.* 1953;35:312–320.
62. Wangdell J, Fridén J. Satisfaction and performance in patient selected goals after grip reconstruction in tetraplegia. *J Hand Surg Eur Vol.* 2010;35:563–568.
63. Wangdell J, Carlsson G, Fridén J. Enhanced independence: experiences after regaining grip function in people with tetraplegia. *Disabil Rehabil.* 2013;35:1968–1974.
64. Fridén J, Gohritz A, Turcsanyii I, et al. Restoration of active palmar abduction of the thumb in tetraplegia by tendon transfer of the extensor digiti minimi to abductor pollicis brevis. *J Hand Surg Eur Vol.* 2012;37:665–672.
65. Allieu Y. Surgical management of the adult spastic hand. *Chir Main.* 2011;30:159–175.
66. Bertelli JA, Ghizoni MF. Transfer of nerve branch to the brachialis to reconstruct elbow extension in incomplete tetraplegia: case report. *J Hand Surg Am.* 2012;37:1990–1993.
67. Davidge KM, Yee A, Kahn LC, et al. Median to radial nerve transfers for restoration of wrist, finger, and thumb extension. *J Hand Surg Am.* 2013;38:1812–1827.
68. Van Zyl N, Hahn JB, Cooper CA, et al. Upper limb reinnervation in C6 tetraplegia using a triple nerve transfer: case report. *J Hand Surg Am.* 2014;39:1779–1783.
69. Fridén J, Gohritz A. Muscle and nerve transfer in tetraplegia. *J Neurosurg.* 2013;118:706–707.
70. Mulcahey MJ, Smith BT, Betz RR, et al. Functional neuromuscular stimulation: outcome in young people with tetraplegia. *J Am Paraplegia Soc.* 1994;17:20–35.
71. Smith BT, Mulcahey MJ, Betz RR. Quantitative comparison of grasp and release abilities with and without functional neuromuscular stimulation in adolescents with tetraplegia. *Paraplegia.* 1996;34:16–23.
72. Triolo RJ, Betz RR, Mulcahey MJ, et al. Application of functional neuromuscular stimulation to children with spinal cord injuries. Candidate selection for upper and lower extremity research. *Paraplegia.* 1994;32:824–843.
73. Wuolle KS, Van Doren CL, Thrope GB, et al. Development of a quantitative hand grasp and release test for patients with tetraplegia using a hand neuroprosthesis. *J Hand Surg Am.* 1994;19:209–218.
74. Kilgore KL, Hoyen HA, Bryden AM, et al. An implanted upper-extremity neuroprosthesis using myoelectric control. *J Hand Surg Am.* 2008;33:539–550.
75. Hamou C, Shah NR, DiPonio L, et al. Pinch and elbow extension restoration in people with tetraplegia: a systematic review of the literature. *J Hand Surg Am.* 2009;34:692–699.

38

Upper extremity vascularized composite allotransplantation

Jaimie T. Shores, Joseph Lopez, Gerald Brandacher, and W. P. Andrew Lee

Access video content for this chapter online at expertconsult.com 

SYNOPSIS

- Vascularized composite allografts are composed of multiple tissue components of variable immunogenicity such as skin, lymph nodes, bone marrow, nerves, vessels, muscles, and bone.
- After non-salvageable upper extremity loss, transplantation can restore upper extremity appearance, anatomy, and function by replacing and restoring missing tissue without compromising donor site morbidity or requiring multiple reconstructions.
- Vascularized composite allotransplantation (VCA) is not a life-saving procedure but it can significantly enhance a patient's quality of life. Unlike solid organ transplantation, recipients are otherwise healthy without significant comorbidities. The risk–benefit consideration for patients must include the potential side effects of long-term immunosuppression – treatment that is necessary for graft survival.
- The conventional immunosuppression protocols used in upper extremity VCA are similar to those used in solid organ transplantation and have prevented early graft loss but not acute rejection.
- Acute rejection in vascularized composite allografts can be monitored visually, which allows for timely intervention. Acute rejection events, when properly managed, do not appear to impact long-term allograft function or survival.
- During the past two decades, over 100 upper extremity transplants have been performed around the world in over 70 patients with encouraging intermediate to long-term functional and graft survival outcomes.
- In order to broaden the application of this life-changing reconstructive modality, future research should focus on investigating novel immunomodulatory approaches that aim to enable long-term allograft survival while minimizing the need for life-long immunosuppression.

Introduction

Millions of individuals each year sustain major upper extremity trauma, undergo resection of upper extremity tumors, or are born with major congenital defects that require multiple, complex reconstructive surgeries to repair large upper extremity defects. Conventional management of these tissue deficiencies includes prosthetic rehabilitation or surgical reconstruction (with autologous tissues), but these modalities are often hampered by highly variable outcomes.⁶⁴ There are several factors that negatively impact surgical outcomes with traditional approaches including the prolonged process and cost of rehabilitation, multiple surgeries, limited autologous tissue for reconstruction, and secondary morbidity from extensive autologous donor-site surgery. For such complex injuries not amenable to conventional reconstruction, vascularized composite allotransplantation (VCA) can achieve near-perfect primary restoration of tissue defects with improved functional and aesthetic outcomes. VCA is a newly developed focus area in transplantation medicine and combines the time-tested techniques of reconstructive microsurgery with the immunologic principles of transplantation. The overall goal of VCA is to improve the quality of life of patients with significant composite tissue defects, and use the plastic surgery principle of replacing “like with like” with the goal of maximizing not only upper extremity functional outcomes but also aesthetic results.

In the United States alone, approximately 1285000 upper extremity amputations are performed per year.⁶⁵ In 2005, there were approximately 1.6 million individuals living in the US with upper or lower extremity limb loss.⁶⁶ Of these 1.6 million patients, nearly 540000 individuals have had upper extremity amputations. Even if only 1% of these patients were deemed candidates for upper extremity allotransplantation, this would mean that over 300 patients could potentially benefit from this life-changing treatment. Thus far, only over 70 patients have undergone upper extremity allotransplantation in the last two decades. However, despite the



Access the Historical Perspective section online at

<http://www.expertconsult.com>

Fig. 38.1 appears online only.

Historical development and milestones

The earliest accounts of organ transplantation date to the Chinese physician Pien Chi'ao, who in 500 BCE performed a dual-heart transplant on warriors Gong Hu and Qi Ying.¹ In addition, in the *Suśruta Samhita*, a surgical report written by the Indian surgeon Suśruta who lived around 480 BCE, Suśruta describes in detail the techniques of rhinoplasty and pedicled autografts from the forehead, neck, and cheek to restore mutilating injuries of the nose and ear.²⁻⁴ About 870 years later, the patron saints Cosmas and Damian are credited with performing the first limb allotransplantation.⁵⁻⁹ Legend has it that around the year 348, they successfully transplanted the right leg of a dead Moor onto the Roman deacon, Justinian, after amputating his cancerous/gangrenous leg (Fig. 38.1). The first description of skin allografting was done by the 16th century Italian surgeon, Gaspare Tagliacozzi, from Bologna, who in his book *De Curtorum Chirurigia per Insitionem* ("On the Surgery of Mutilation by Grafting"), described a novel method of nasal and aural allo-reconstruction, where he used skin from the inner aspect of the arm from a slave to reconstruct the nose of a wealthy patient who injured it during a sword fight.¹⁰⁻¹² In this book, Tagliacozzi goes on to describe one of the first description of tissue rejection, when he



Fig. 38.1 St. Cosmas and Damian perform the first human extremity allotransplantation. Per mythology, Christian Roman deacon Justinian had a malignant growth on his leg and fell asleep while praying for a cure in the Church of Cosmas and Damian in Rome. In his dreams, the saints amputated the diseased limb and transplanted the leg of a Moor, brought to the church for burial. The patient awoke and gratefully observed a now healthy leg, though black in color. (Reproduction with permission from Württembergisches Landesmuseum, Stuttgart.)

discusses the practical difficulty of binding two different individuals (referring to tissue rejection) to one another for a sufficient length of time.

It took another 300 years before these "practical difficulties" in transplantation began to be elucidated. During this time, advancements in antisepsis, anesthesia, hemostasis, organ preservation and, most importantly, microvascular surgery led to the rapid progress of reconstructive microsurgery. Alexis Carrell in 1902 described the surgical technique of vascular anastomosis, thus laying the foundation for conventional vascular and microsurgery.¹³ Carrell successfully obtained the revascularization of experimental organ allografts,^{14,15} but failed to achieve permanent graft acceptance. Carrell attributed this "organ failure" to vascular complications because he had no knowledge of the process of rejection. In 1932 and 1937, the first attempts at skin grafting were performed between identical twins.^{16,17} Again, no mention was made of rejection. In 1944, Hall published the first detailed theoretical account of cadaveric donor upper extremity transplantation (at the mid-humeral level).¹⁸ In his protocol, Hall described that an experienced surgical team within a well-equipped hospital was needed to perform the procedure. Additionally, his protocol included important and innovative descriptions of organ preservation, osteosynthesis, and vascular anastomoses. Lastly, potential complications related to thrombosis and infections were discussed, but, again, no reference was made to the occurrence of rejection. Strikingly, Hall was not aware that Sir Peter Brian Medawar, a young zoologist in Britain, and Thomas Gibson, a plastic surgeon, had made the historic discovery of the immunologic phenomenon of skin allograft rejection that very same year (1944).¹⁹ The challenge of skin transplantation led to the exploration of new frontiers in organ transplantation. In 1954, a plastic surgeon, Joseph E. Murray, with his team members – John P. Merrill and J. Hartwell Harrison – in Boston, performed the first successful human kidney transplantation between identical twins.^{20,21} This was followed, in 1957, by the first clinical attempt at allotransplantation of an *en bloc* composite digital flexor tendon mechanism by a plastic surgeon, Erle E. Peacock, Jr.^{22,23} Indeed, it was Peacock who coined the term "composite tissue allograft" to differentiate these transplants that were composed of multiple tissues unlike solid organs.²⁴

Our understanding of the immunologic behavior of allografts lagged behind technical developments in surgery. It was only the knowledge gained from landmark discoveries in the past century²⁵⁻³³ that facilitated the manipulation or suppression of the immune response, allowing successful prolongation of graft survival. After Medawar's demonstration that rejection was an immunologic event, the next logical question was: Why not prevent this phenomenon by suppressing the immune system? In the 1950s, corticosteroids and irradiation were used for immunosuppression.^{34,35} In the 1960s, the antimetabolites 6-mercaptopurine and its derivative azathioprine were introduced, along with agents such as antilymphocyte globulin. These drugs were used either alone^{36,37} or in combination with corticosteroids.³⁸⁻⁴⁰ Graft survival improved, but surgical outcomes were dismal because these drugs acted indiscriminately and were associated with severe organ-specific and systemic adverse effects.

In 1964, the first hand transplantation was performed using pharmacologic immunosuppression.⁴¹⁻⁴³ Dr. Gilbert

in Guayaquil, Ecuador, transplanted the right forearm of a 28-year-old sailor who had lost his limb at the wrist level caused by a hand-grenade explosion the previous day. The donor was a laborer who had died of hematemesis (with gastric bleeding) a few hours earlier. The recipient was given heparin, dextran, and a broad-spectrum antibiotic after the surgery and was maintained on a combination regimen of prednisone and 6-mercaptopurine (6-mercaptopurine was replaced 24 h later by azathioprine). These drugs are considered primitive according to present day standards, and unfortunately, signs of acute allograft rejection occurred after 2½ weeks. The patient was then moved to Peter Bent Brigham Hospital in Boston, where, at 3 weeks, aggressive rejection set in, and the forearm had to be re-amputated at 4 cm above the wrist level. Unfortunately, the advanced state of necrosis prevented any histopathologic evaluation of the graft. This bold and pioneering attempt at hand transplantation laid the foundation to the successful attempts yet to come.

In 1976, another major breakthrough in transplantation came with the discovery of the immunosuppressive properties of the calcineurin inhibitor cyclosporine A.^{44,45} In 1978,

cyclosporine was first used clinically in organ⁴⁶ as well as bone marrow transplantation with remarkable results. The US Food and Drug Administration (FDA) approved cyclosporine A in 1983. Cyclosporine A, along with agents like anti-CD3 antibody (OKT3, introduced in 1981),⁴⁷ effectively reduced the reliance on high-dose steroids for the prevention of rejection. The calcineurin inhibitor tacrolimus (FK 506) was discovered in 1987,⁴⁸ clinical trials were conducted in 1989,⁴⁹ and FDA approval came in 1994. Tacrolimus led to dramatic improvements in solid organ transplantation,^{50–53} allowing highly immunogenic grafts such as the small bowel to be transplanted.^{54–56} The success of the calcineurin inhibitors cyclosporine A and tacrolimus made them the cornerstone drugs of the modern era of transplantation.⁵⁷ The 1990s saw the introduction of novel drugs such as the antimetabolite mycophenolate mofetil⁵⁸ (MMF, approved by FDA in 1995) and rapamycin⁵⁹ (sirolimus, discovered in 1976 but FDA approved only in 1999). Combining these drugs with a calcineurin inhibitor^{60–63} were found to significantly reduce rejection and improve solid organ graft survival with a reduction in adverse effects.

fact that surgical, immunological, and functional results are highly encouraging, the need for long-term and high-dose immunosuppression to enable graft survival and to treat/reverse acute skin rejection episodes remains a rate-limiting obstacle towards widespread application.^{67,68} The risks of immunosuppression are not benign. These include infection, cancer, and metabolic derangements. All these risks greatly affect the recipient's quality of life, alter the risk profile, and jeopardize the potential benefits of upper extremity transplantation. Furthermore, unlike in solid organs, clinical success is dictated not only by graft acceptance and survival but also by nerve regeneration, which determines ultimate functional outcomes. Novel strategies such as cellular and biologic therapies that integrate the concepts of immune regulation with those of nerve regeneration have shown promising results in small and large animal models. Clinical translation of these insights to upper extremity reconstructive transplantation could further minimize the need of immunosuppression and optimize functional outcomes, enabling greater feasibility and wider application of these procedures as an option for upper extremity amputees.

Evolution of upper extremity vascularized composite allotransplantation

Immunology of vascularized composite allotransplantation

Research findings in small and large animal models have vastly improved our knowledge of the immunologic aspects of vascularized composite allografts. These studies have demonstrated that the allograft is composed of different tissues, each with its own degree of antigenicity as a result of differing antigen expression and presentation mechanisms.⁶⁹ Each component in a vascularized composite allograft expresses different amounts of major histocompatibility complex (MHC) and tissue-specific antigens – important factors that elicit a recipient's cellular-mediated immune response.⁷⁰ Antigen recognition and targeting by the recipient's immune system also differs among the allograft tissue elements due to differential vascular and lymphatic supply. Altogether, these factors help explain the pattern of rejection that is observed in whole limb transplanted allografts. For instance, transplanted muscle evokes mainly a cell-mediated immune response, whereas skin induces both cellular and humoral responses.⁷¹ Furthermore, skin and bone marrow appear to reject earlier and more aggressively than muscle, bone, cartilage, or tendon. Having an appreciation and understanding of the relative antigenicity of vascularized composite tissue components can facilitate the development of strategies aimed at decreasing the antigenicity of these specific components. In addition, understanding the relative antigenicity of specific allograft components enables the tailoring of immunosuppression, thus limiting the amount of immunosuppression needed when treating rejection.⁷² Over the last few decades, our understanding of relative antigenicity and humeral/cellular immunity has allowed the testing of several tailored immunosuppressive regimens in small animal (rat)

and large animal (porcine, canine, and non-human primate) VCA models.

Experimental background and scientific basis for upper extremity transplantation

In early rodent limb transplantation studies, recipients treated with various combinations of immunosuppressive doses of 6-mercaptopurine, or its derivative azathioprine, and prednisone all died from drug-induced side effects before the onset of macroscopic signs of rejection.⁷³ Even after the introduction of cyclosporine A, the use of high doses of cyclosporine A demonstrated no improvement in limb or animal survival.^{74–78} In fact, cyclosporine A monotherapy was found to be uniformly unsuccessful in prolonging vascularized composite allograft survival in both small animal and non-human primate models.⁷⁹ Further studies in non-human primate models demonstrated that acute rejection could only be prevented with cyclosporine A when trough levels were 3–4 times the level achieved in human solid organ transplantation – levels that are associated with significant peri-transplant infections and malignancies.^{80–83}

In 1996, Benhaim and colleagues demonstrated that a combination of cyclosporine A with an antimetabolite (such as mycophenolate mofetil) could successfully prolong rat hindlimb allograft survival.⁸⁴ Benhaim and his team were the first to show that predictable, long-term, functional limb allograft survival could be achieved. Using a similar regimen, others went on to demonstrate, using a swine model, that long-term survival of fully mismatched composite allografts was technically feasible.^{85,86} Since swine and humans share immunological similarities including the structure of MHC and the expression of MHC class II antigens (on endothelial cells, epithelial cells, and dendritic cells),⁸⁷ these findings provided sufficient sound evidence, in both small (rodent)^{88,89} and large animal VCA models,^{85,86} that human upper extremity allotransplantation was feasible.⁹⁰

Our extensive experience with organ transplantation has provided valuable information about the immunologic consequences of organ transplantation and the efficacy and toxicity of immunosuppressive drugs. The field of transplantation evolved from transplanted kidneys⁹¹ and hearts^{92,93} to livers,⁹⁴ lungs,⁹⁵ pancreas,⁹⁶ small bowel,⁹⁷ multiple abdominal viscera,⁹⁸ bone marrow,⁹⁹ and, most recently, vascularized composite allografts.^{100,101} As expected, the initial results of allograft and patient survival after organ transplantation in the 1960s were poor. Editorials in major clinical journals,¹⁰² including the *New England Journal of Medicine*,^{103–105} questioned the feasibility and ethical basis of organ transplantation. There was great concern for the adverse effects of chronic immunosuppression, especially the risk of opportunistic infections and malignancies. During the next four decades, due to improvements in immunosuppression and in the management of post-transplant complications, this pessimism abated. Similarly, attempts at upper extremity transplantation,^{106,107} after three decades of quiescence since the first attempt in Ecuador,^{46,47} has also been met with vigorous skepticism. Interestingly, most of the criticism has come from hand surgeons.^{108–114} Most argue that the risks of immunosuppressive therapy are justifiable in potentially life-saving organ transplantation, but not in upper extremity allotransplantation. Furthermore, many hand surgeons argue that the

immunological, ethical,^{115,116} and psychological¹¹⁷ issues associated with hand transplantation still need to be addressed.¹¹⁸

The rationale for proceeding with clinical trials of upper extremity transplantation using modern immunosuppression have been based on scientific progress on: (1) the availability of novel immunosuppressive drugs that have improved the efficacy and lower risk profile of immunosuppression; (2) the availability of highly efficacious treatments for opportunistic fungal or viral infections (such as *Pneumocystis carinii* and *Cytomegalovirus*); (3) the development of novel therapeutics for post-transplant malignancies (such as rituximab for post-transplant lymphoproliferative disorder, PTLD); (4) research on immunosuppressive drug regimens based on years of experience with solid organ transplantation; and (5) the success of human transplantation of all individual component tissues of the hand, including skin, muscle, tendons, vessels, nerve, bone and joint.¹¹⁹

Chronology of clinical upper extremity allotransplantation

In September 1991, the first conference on VCA was held in Washington, DC to “determine the clinical feasibility of transplanting limbs in patients with limb loss” and the “direction in which clinically oriented limb transplantation research should head.”¹²⁰ In November 1997, the first International Symposium on VCA was convened in Louisville, Kentucky, to discuss the “scientific, clinical and ethical barriers standing in the way of performing the first human hand transplant.” International experts at the meeting predicted that limb transplantation was not far from “becoming a clinical reality”.¹²¹ Within the next 22 months, 34 years after the first hand transplantation was performed,^{46,47} surgeons in Lyon, France, performed the world’s second unilateral hand transplant in September 1998.^{106,107,122,123} In January 1999, the first unilateral hand transplant in the United States was performed in Louisville, Kentucky.^{124,125}

Following these attempts, numerous centers in Europe, Asia, and the US have performed over 70 upper extremity transplantations. Most of these transplantations were wrist to mid-forearm amputations, except for two partial hand grafts in China, one partial hand graft in the US, and two cases of above-elbow transplantation.^{126,127}

Clinical experience with upper extremity allotransplantation

Program, patient, procedural and protocol-related considerations

Program establishment and implementation

Starting a hand transplant program poses numerous challenges.^{128,129} Solid organ transplantation and hand replantation are time-tested procedures and are now the standard of care. Hand transplantation is the amalgamation of the scientific principles of reconstructive surgery and the concepts of organ transplantation. Therefore, the success of any hand transplant program lies on its ability to foster collaboration between a multidisciplinary team comprised of a core group of hand

(plastic or orthopedic) and transplant surgeons, psychiatrists, physical therapists, social workers, and transplantation nursing staff to name a few. Although the transplant clinical process is well established, it is also bound by tight regulation; this may come as a surprise to reconstructive plastic/hand surgeons who wish to start a hand program. Therefore, the experience of the solid organ transplantation members is essential when negotiating through the regulatory process. Such a joint effort can overcome the challenges that are inherent in a complex therapeutic option that integrates multiple specialties during the planning, procedural, and post-transplant phases.

Donor and recipient selection

The overall success of VCA relies on many factors. However, our own experience with upper extremity allotransplantation has taught us that proper evaluation, selection, and management of donors and potential recipients is probably the most important determinant of outcomes. Recipient screening and selection is a multistage process, which takes a multidisciplinary look into the patient’s past medical history and pre-transplant life.¹³⁰ Data on psychological and social factors must be collected and evaluated prior to determining patient eligibility. While these psychological and social aspects of screening are critical, they are also the most difficult to assess. The worldwide experience with upper extremity allotransplantation has shown that only patients who are physically and mentally healthy, with adequate psychological and social support, and are highly motivated to undergo long-term (>6 months) intensive rehabilitation and therapy, are “good” candidates for upper extremity transplantation.

Decades of experience with solid organ transplantation has provided the field of transplantation medicine with well-established criteria for donor and recipient selection. Given that the field of upper extremity allotransplantation is still in its infancy, parameters for inclusion and exclusion of donors and recipients have yet to be fully established.^{131,132} Tables 38.1 and

Table 38.1 Donor considerations in upper extremity allotransplantation

Demographic and phenotypic characteristics
Skin color, tone, and texture match
Limb size and dimension (bone length and diameter match)
Age, sex, race and ethnicity match if possible
Donors must be deceased (brain death declared)
Donor limb dissection and procurement must not interfere with organ recovery
Limb usually prepped first, perfused under isolated tourniquet, dissected after cross clamp and retrieved in sequence with heart and lung recovery. This minimizes overall ischemia time
History of malignancy (recent or remote) may be an exclusion
Paralysis of ischemia or traumatic origin, inherited peripheral neuropathy, infectious, post-infectious or inflammatory neuropathy, toxic neuropathy (i.e., heavy metal poisoning, drug toxicity, industrial agent exposure) or mixed connective tissue disease, severe deforming rheumatoid, or osteoarthritis in the limb may be exclusions

38.2 highlight the general selection criteria that has been used in upper extremity allotransplantation. Patients below the age of 18 years are generally excluded due to issues of informed consent of an experimental procedure. Furthermore, from experience in solid organ transplantation, it is known that pediatric patients are more likely to develop immunosuppression-related complications like PTLD than adults.¹³³ Patients over the age of 65 are also generally excluded because of increased immunosuppression-related complications, limited years of potential gain from the transplant, and decreased nerve regeneration potential. Medical screening of recipients includes a complete medical history and physical examination; routine laboratory studies; blood typing and cross-matching; human leucocyte antigen (HLA) typing; testing for panel-reactive antibodies; and serology for Epstein–Barr virus, cytomegalovirus, HIV, and viral hepatitis. Other tests include radiography (to plan for osteosynthesis), angiography (to exclude abnormal vascular patterns), electromyography, nerve conduction velocity, and functional magnetic resonance imaging (fMRI).

Procedural aspects

Donor limb procurement

Once an immunologically appropriate donor has been identified by the Organ Procurement Organization (OPO), further “matching” is necessary to ensure adequate skin color, gender, age, and length/circumference.¹³⁴ The level of procurement depends on the specific deficit on the recipient. Each recipient should receive a “custom” operation tailored to its respective anatomical deficits. For distal forearm and mid-forearm transplants, an elbow disarticulation provides enough soft tissue, vessel length, nerve length, and extra



Fig. 38.2 Donor graft after isolated perfusion and disarticulation.


skin/bone for transplantation. For proximal trans-humeral transplants, a proximal humeral procurement at the most proximal level possible that can still maintain tourniquet control is usually adequate.¹³⁵ Proximal arm procurements may often require intra-thoracic cannulation and control of the subclavian vessels by the thoracic procurement team. The limb is perfused with cold histidine–tryptophan–ketoglutarate (HTK, Custodiol) or University of Wisconsin (UW) solution based on the individual center preference. Depending on the stability of the donor, level of procurement, and operating room space, upper extremity procurement may occur concurrently, before, or after standard organ procurement. We recommend procurement of the upper extremity before visceral organ procurement to minimize ischemia time as much as possible. Upon completion of hand retrieval (Fig. 38.2), the donor stump is closed, and the body can be fitted with a cosmetic prosthesis, allowing the family the option of an open-casket funeral. Following retrieval, the limb (wrapped in moist sterile gauze and placed in a polyurethane bag) is transported in a sterile container (provided by the OPO) with iced water at 4–6°C. Donor spleen and lymph nodes are collected and cell suspensions cryopreserved for future immune assays.

Recipient surgery

The recipient operation is carefully planned prior to procurement and involves close communication between donor and recipient teams. After confirming donor match, the recipient undergoes placement of regional blocks, preparation for general anesthesia and induction therapy (most commonly with basiliximab, Simulect; anti-thymocyte globulin (ATG); or alemtuzumab, Campath-1H). Hand transplantation does not differ greatly from replantation. Instrumentation and technique are similar. A two-team approach is used. The donor team prepares the donor limb once received on the back table, tailoring the graft to the needs of the recipient and tagging the structures (Fig. 38.3). The two main hand transplant surgeons and assistant hand transplant surgeons (dissecting the donor limb) are assisted by one scrub nurse per extremity, two circulators per room, and at least one anesthesiologist. Based on the preoperative assessment of the recipient, tissue requirements from the donor will be known. The team dissecting the recipient must know exactly what measurements are necessary for the donor team to proceed. The recipient team will need to clearly identify the amount

Table 38.2 Recipient considerations in upper extremity allotransplantation

Subjects can be of any race, color, ethnicity in good health
Age range for eligibility is variable but usually over 18 years and under 65 years
Subjects with congenital defects (e.g., transverse arrest) are currently excluded
The impact of the lack of pre-existing cortical recognition is unknown
Blindness is an exclusion in some programs
Eyesight necessary to follow the rigorous rehabilitation process. Additionally, visual feedback is critical for functional recovery
Rigorous psychosocial assessment is mandatory
Used to determine the motivation for transplantation, emotional and cognitive preparedness for the procedure, body image adaptation, level of realistic expectations regarding post-transplant outcomes, anticipated comfort with the transplant, personality organization/risk of regression, history of medication compliance/substance abuse, potential for compliance, and social support system/family structure
Use or attempted use of prostheses prior to transplant is a suggested requirement



Our experience over the past two decades has elucidated specific principles that are important for the recipient operation. In general, nerve approximation should be performed as distally as possible. Over-dissection of donor arteries should be avoided to prevent postoperative bleeding and to minimize the risk of a persistent inflammatory reaction. The limb should be kept on sterile ice at all times with an interface between the ice and tissue to prevent thermal injury. Lastly, the authors typically use an implantable venous Doppler on the anastomosed veins and use pulse-oximetry probes on the transplanted hand for oxygenation monitoring.

Distal forearm allotransplantation often relies on the recipient's native extrinsic musculature, but this requires the careful approximation of median and ulnar motor fascicles for recovery of intrinsic function. Recipient incisions should create volar and dorsal skin flaps, while donor incisions should create radial and ulnar skin flaps for interdigitation. Tendon approximation can be performed using the Pulvertaft weave technique, facilitating immediate postoperative active/passive range of motion. The osteosynthesis can be performed with standard distal radius and ulna fixation techniques. The authors typically perform osteosynthesis first, taking great care to create a stable distal radioulnar joint (DRUJ), followed by arterial and venous anastomoses, followed by reconstruction of the extensors, then flexors, then nerves.

Proximal forearm allotransplantation requires the transplantation of donor flexor/extensor muscle groups in order to obtain meaningful digital excursion and strength in the hand. Volar and dorsal skin flaps are created on the recipient limb to protect the antecubital fossa and olecranon while donor limb skin flaps are elevated radially and ulnarly. The new flexor/pronator origins are fixed with bone anchors and sutures on top of the native flexor/pronator muscle mass at the medial epicondyle (Fig. 38.6A–D). Similarly, the extensor origin is fixated with bone anchors into the lateral epicondyle. Additionally, the annular ligament and radiocapitellar joint capsule of the donor are sutured to the extensor origin of the recipient. The radial nerve can be usually dissected to individual muscle groups such as the extensor carpi radialis branch, posterior interosseus branch, and extensor carpi radialis longus branch. We use an end-to-side brachial-to-brachial artery anastomosis to preserve maximum blood flow to the proximal ulna, radius, and native flexor/extensor motor groups. Veins are anastomosed in end-to-end fashion.




Fig. 38.5 (A,B) Mid-forearm allotransplantation.




Fig. 38.6 Proximal forearm and trans-humeral transplantation: (A) left forearm proximal transplantation –preop; (B) possible donor forearm incisions indicated; (C) post-fixation X-rays; (D) inset of skin flaps; (E) right upper arm transplantation – preop; (F) donor arm procured and demonstrating skin flap incisions; (G) post-fixation X-rays; (H) inset of skin flaps.

Clinical tips

Trans-humerus allotransplantation

Trans-humeral transplants can be categorized as distal, middle, and proximal. Distal humerus allotransplantation is performed with primary repair of the donor brachialis fascia and biceps/triceps tendon to the recipient brachialis fascia and biceps/triceps tendons (see Fig. 38.6E–H). End-to-end brachial artery/vein anastomoses (in addition to several superficial vein anastomoses) are performed. Fixation is achieved by utilizing single-plate osteosynthesis with the authors preferring a tapered 4.5/3.5 mm stainless steel locking compression plate. Skin flaps are elevated while maintaining skin integrity at the antecubital fossa and olecranon. In mid-humerus transplantation, one must decide whether the remnant flexor/extensor muscle groups will be adequate for active elbow motion. If one decides to maintain the native biceps and triceps to power the elbow, then muscle-to-muscle approximation is performed with as much tendon/fascia substance as possible. The use of fascial/tendon graft or allograft may be beneficial for strengthening the repair. The brachialis, due to its extensive origin on the humerus, can be transferred with the donor limb and be expected to function if the musculocutaneous nerve is adequately coapted. The same osteosynthesis, nerve repair, and vascular reconstructions are performed as described for the proximal humerus procedure. If one decides to transplant the donor flexor and extensor masses, then the steps for the proximal humerus allotransplantation are followed.

For proximal humerus allotransplantation, one may be required to transplant the entire flexor/extensor muscle compartments of the antebrachium (Fig. 38.7). Both the biceps short head and the biceps long head tendons are dissected off their origins on the donor limb. Both of these muscles can be sutured or woven into the recipient short head and long head/conjoint tendons, respectively. This level of transplantation also requires the division of the recipient pectoralis tendon with tagging for future repair. Osteosynthesis is performed utilizing a 4.5 mm locking compression plate, which is placed anterolaterally. Once osteosynthesis is complete, the most posterior compartment structures are reconstructed with the recipient and donor triceps muscle/tendons sutured to one another with some tension with the elbow in extension. Next, the radial, ulnar, and median nerves are coapted. Attention is then directed to the arterial and venous anastomoses. The brachial artery on the recipient is anastomosed to axillary artery of the donor limb and the brachial and cephalic veins are anastomosed proximally as well. Lastly, after reperfusion is complete, the biceps long and short head proximal tendons are woven and/or sutured with the elbow in flexion and under some tension, followed by musculocutaneous nerve coaptation. Once this is complete, the pectoralis tendon may be repaired or reinserted with bone anchors if necessary.




Fig. 38.7 (A,B) Use of the high non-pneumatic tourniquet for proximal trans-humeral procurement.

Protocol-related considerations

Maintenance immunosuppression

The current immunosuppression protocols applied to upper extremity allotransplantation are extrapolated from regimens used in solid organ transplantation. The overall amount of immunosuppression required to ensure graft survival is comparable with that used in renal transplantation. Such conventional immunosuppression has resulted in >95% patient and graft survival at 1 year after upper extremity transplantation.¹²⁶ The majority of hand transplant patients received either polyclonal (ATGs) or monoclonal (alemtuzumab, basiliximab) antibody preparations as induction therapy followed by a high-dose triple-drug combination for maintenance therapy including tacrolimus, mycophenolate mofetil (MMF), and steroids, although the dose and trough levels of each drug differs by center. Such regimens have proven sufficient to prevent early immunologic graft loss but have yet to prevent acute rejection episodes. Some programs follow steroid-avoidance regimens, while others rely on monotherapy immunosuppression. Successful reversal of acute rejection episodes (see Fig. 38.8) has been achieved using topical clobetasol or tacrolimus ointment with or without short-term bolus steroid doses.^{136,137}




Fig. 38.8 (A–C) Clinical manifestations of acute skin rejection. These can range from discrete or diffuse maculopapular rash with or without edema and palmar involvement.

Rehabilitation and functional assessment after upper extremity allotransplantation

Rehabilitation and functional assessment are integral components of successful upper extremity allotransplantation.¹³⁸ A fully-trained hand therapist should be involved in the entire process from initial screening of prospective patients through final discharge. The goal is functional integration of the transplanted hand into the patient's daily activities. Successful rehabilitation of upper extremity transplant patients follows guidelines similar to replant protocols. There are several significant differences, however, such as the screening process for an ideal candidate and the monitoring for signs of rejection.

The preoperative evaluation process involves patient acceptance of the amputation, attempted prosthetic use, and the establishment of realistic goals for surgery and outcomes. This includes a full history and physical exam to document the range of motion (ROM) of the available joints; manual muscle testing (MMT) of available muscles; response of the residual forearm musculature to electrical muscle stimulation; documentation of pain and sensitivity complaints; scar quality; level of amputation; sensation; edema; skin and soft tissue integrity; and circumference of the forearms at varying levels, as well as length of the forearms. Different tests, questionnaires or instruments can be used to evaluate preoperative functional level and the status of residual muscles that will power the transplanted hand. As appropriate, electrical muscle stimulation, as well as isometric exercise, can help in preoperative strengthening of these muscles.

The goals of postoperative therapy, bracing, and splinting are similar to the goals in replantation surgery. Knowledge of the exact level of nerve repair, type of osteosyntheses, and details of tendon repairs are essential in planning of splinting and therapy. Uniquely, the hand therapist can help monitor for signs of rejection as the patient spends considerable time

in rehabilitation after surgery. At our institution, a rigorous rehabilitation regimen has been implemented in all patients with 3–6 h of supervised therapy, 5 days a week during the first 3–6 months postoperatively, depending on the nature and upper extremity level of the transplant. Therapy must consist of passive and active ROM exercises with appropriate static and dynamic splinting to allow for gentle active flexion/extension, limit adhesions, and promote healing. Hand-based splints such as dynamic extension outrigger splints (Fig. 38.9) and anti-claw splints should be used in all patients. The outrigger allows for an intrinsic-plus position, protects flexors and extensors, and enables constant tension throughout the range of controlled motion. Compression gloves are useful in patients with lymphedema. Qualitative and quantitative tests for hand and upper extremity function such as the Carroll score,¹³⁹ the DASH¹⁴⁰ score, and the Hand Transplantation Score System¹⁴¹ may be utilized, along with standard tests that evaluate motor and sensory recovery (Tinell's, Semmes-Weinstein monofilaments, 2PD, dynamometry, peg board tests, etc.). After discharge at 3–6 months postoperatively, communication and coordination with a certified local therapist is critical to ensure follow-up continuity of an intensive regimen and a home therapy exercise routine that is paramount to achieving functionality.

Assessment for rejection (host-versus-graft reaction)

Acute rejection (AR) is a T-cell- and/or antibody-mediated attack of the transplant by the recipient's immune system resulting in damage and ultimately loss of the graft. The skin has been demonstrated to be the prime target of rejection and monitoring of the skin by inspection is therefore considered most important for monitoring. Protocol graft-skin biopsies must be routinely performed until the first year plus whenever clinically indicated (visible signs of rejection such as a maculopapular rash). Biopsy samples may be analyzed by means



Fig. 38.9 Dynamic extension (crane) outrigger splint.

of histology and immunohistochemistry (staining for CD3, CD4, CD8, CD20, and CD68) for quantification and characterization of cellular infiltrates. Scoring for severity of acute rejection is accomplished using established standard grading criteria such as the Banff classification (Fig. 38.10 & Table 38.3).^{142,143} Important clinical characteristics of AR include edema, erythema, escharification, and necrosis. Atypical rejection in the form of scaling, leuconychia or nail dystrophy can also occur (Fig. 38.11).¹³⁷ Biopsies must also be examined for evidence of chronic rejection (CR), including intimal hyperplasia and sub-intimal foamy histiocytes in the vessels of the skin, or muscle and tissue fibrosis (Fig. 38.12).

Immunomonitoring

Recipient and donor cells must be typed before transplantation for human leukocyte antigens (HLA).^{144,145} Additionally, DNA samples from recipient/donor must be stored for future typing for MICA (MHC class I chain A-related) genes in those patients in whom anti-MICA antibody is detected. All sera should be screened by antihuman globulin-enhanced complement-dependent cytotoxicity assays (AHG-CDC), by enzyme-linked immunosorbent assay (to identify immunoglobulin G anti-HLA class I- and class II-specific antibodies independently) and by Luminex (allows for the identification of anti-MICA antibodies, as well as ascertainment of their donor specificity). The MICA and MICB antigens are expressed on surface of endothelial cells and epithelial cells and elicit a strong antibody response in recipients of solid organ transplants. Cell-mediated immunity may be measured by the ImmuKnow (Cylex) assay that detects adenosine

triphosphate (ATP) synthesis in CD4 cells. Immune responses are reported in ng/mL of ATP and categorized as strong (>525) moderate (226–524) or low (<225). The desirable target zone for all transplant recipients is 280 ng/mL ATP, with a 96% negative predictive value for rejection or infection.

World experience and surgical outcomes

The International Registry of Hand and Composite Tissue Transplantation (IRHCTT) (www.handregistry.com) tracks upper extremity allotransplants around the world. The 2008 and 2010 reports¹⁴⁶ indicated that the average age of recipients is 32 years (range 19–54 years), usually male, with time from injury to transplant ranging between 2 months and 34 years. Follow-up ranged from 1 month to 11 years. Patient survival following hand transplantation stands at 100% in the United States. Long-term graft survival among patients in Europe and the United States is approximately >80%, with only a few graft losses. The first French patient who received an upper extremity transplant underwent amputation following irreversible graft rejection secondary to medication non-compliance. Two American patients lost the upper extremity allograft due to medication non-compliance as well, while another lost bilateral upper extremity allografts immediately postoperative due to sepsis.¹⁴⁷ Lastly, another American patient lost the upper extremity allograft due to ischemia secondary to vascular intimal hyperplasia.¹⁴⁸

Highly compliant (with respect to immunosuppressive medication and rehabilitation) hand transplant recipients show highly encouraging early and intermediate functional outcomes (Video 38.1). However, these excellent results are dependent on intensive and continuous rehabilitation. Protective sensation has been achieved in all patients within 12 months. Furthermore, the transplanted upper extremity limbs show restored abilities not otherwise afforded by prostheses.¹⁴⁹ These include grasping small objects, pouring water from pitchers, tying shoe laces, playing chess, throwing a ball, and using hands in activities of daily living. Recipients have also demonstrated rapid progression of their Tinel's sign and

Table 38.3 Banff grading scale

Grade	Histopathology of skin
Grade 0	None. Rare inflammatory infiltrates
Grade I	Mild. Mild perivascular lymphocytic and eosinophilic infiltration. No involvement of the overlying epidermis
Grade II	Moderate. Moderate-to-severe perivascular inflammation with or without mild epidermal and/or adnexal involvement (limited to spongiosis and exocytosis)
Grade III	Dense inflammation and epidermal involvement with epithelial apoptosis, dyskeratosis, and/or keratinolysis
Grade IV	Necrotizing acute rejection. Necrosis of single keratinocytes and focal dermal-epidermal separation

(Reproduced with permission from Cendales LC, Kanitakis J, Schneeberger S, et al. The Banff 2007 working classification of skin-containing composite tissue allograft pathology. *Am J Transplant*. 2008;8:1396–1400.)




Fig. 38.10 The Banff histopathology grading system for acute rejection in skin: grades IVa and IVb are variants in severity of rejection (Banff grade IV).




Fig. 38.11 Atypical manifestations of acute rejection: (A) palmar scaling, (B) nail dystrophy, and (C) pitting and leuconychia.




Fig. 38.12 Intimal hyperplasia of the ulnar artery following hand transplantation. (Courtesy of Dr. Warren Breidenbach, Christine M. Kleinert Institute.)

early return (at 1 year) of temperature and pressure sensation, touch localization, and pain sensation in the hand and fingers. Return of motor power and grip strength has also been observed. Electrophysiologic testing has confirmed clinical evidence of motor function return in the transplanted intrinsic muscles of the hand, and, in a few cases, true recovery of partial intrinsic function. Early objective testing using the Carroll test has also demonstrated return of function in upper extremity transplant recipients similarly to what is achieved after replantation and superior to what is achieved with prostheses.^{149,150}

Immunosuppression protocols currently used in solid organ transplantation have proved to be sufficient to prevent allograft loss. However, the use of these immunosuppression regimens have been associated with adverse effects including opportunistic infections (i.e., cytomegalovirus, *Clostridium*, herpes, cutaneous mycosis) and *Staphylococcus aureus*-mediated ulnar osteitis; and metabolic complications such as hyperglycemia, hyperlipidemia, impaired renal function, arterial hypertension, and aseptic hip necrosis requiring bilateral hip replacement. Of note, no life-threatening complications or malignancies have been observed thus far.¹⁴⁶

Unique aspects of vascularized composite allotransplantation

Unlike solid organ transplantation, upper extremity transplantation allows the continuous visual monitoring of the allograft for rejection. This facilitates early diagnosis by directed biopsy, unbiased pathologic confirmation of the earliest stages of acute rejection, and timely intervention with precise and individualized tailoring of immunosuppressive medications. When treated adequately and effectively, acute rejection does not seem to impair graft function or long-term survival. Studies from our own group have shown that whole limb allografts elicit a less intense alloimmune response than its individual components.⁶⁹ In addition, vascularized composite allografts contain immunocompetent elements such as bone marrow and lymph nodes, which some argue may hasten the rejection processes or, conversely, result in graft-versus-host disease (GvHD). Unlocking the special immune reactivity of these allogeneic tissues, unlike solid organ

transplantation, provides a unique opportunity for potential immunomodulation and tolerance induction.^{151,152}

Unlike solid organ transplants that are immediately functional after revascularization, a vascularized composite allograft is dependent on peripheral nerve regeneration for functional recovery. Following transplantation, the recipient's nerves/axons have to regrow and reinnervate allograft muscles and other sensory end organs. This process allows the recipient to establish motor control and receive sensory input from the allograft. As a result, neuroregeneration represents a unique challenge in VCA. Interestingly, the use of immunosuppressive drugs like tacrolimus has been shown to not only prolong the survival of limb allografts but also to augment nerve regeneration in animal models.^{153–155} However, at this time there are no available agents applicable in upper extremity allotransplantation that may augment the peripheral nerve regeneration process. Although our current clinical experience has been promising, future studies that seek to improve nerve generation in VCA could ultimately translate into improved function in transplant recipients, making the risk and costs associated with upper extremity allotransplantation more acceptable.

Emerging insights in vascularized composite allotransplantation

Cortical plasticity and neuro-integration

A unique phenomenon observed after upper extremity transplantation is the reassignment of portions of the recipient's brain to control the limb. This is known as brain "reorganization" or "plasticity". Previous studies have demonstrated that changes in cortical organization occur after amputation. However, the impact of limb transplantation on spatial reorganization of the motor cortex is just now being revealed.¹⁵⁶

After an upper extremity amputation, the area of the brain that was once receiving signals from the hand is gradually lost and is "molded" for use in other functions. However, after an upper extremity transplant, the area of the brain that once controlled upper extremity function can re-establish its original function.¹⁵⁷ Such neural integration of the transplant into the pre-motor cortex has been demonstrated using fMRI studies and high-definition fiber tracking with diffusion tractography.

Chronic rejection

In solid organ transplantation, CR is defined as low-grade injury to the vascular endothelium of the allograft leading to irreversible allograft damage (see Fig. 38.12).¹⁴⁸ The hallmark of CR shared by all solid organs is concentric generalized sclerosis and low-grade perivasculitis of graft arteries leading to obliterative arteriopathy. These histologic changes are the result of both immunologic and non-immunologic factors.

According to the latest report of the IRHCTT (www.handregistry.com), over a dozen patients have undergone upper extremity transplantation and have been followed for 5–10 years post-transplantation without any objective measurable vascular changes suggestive of myointimal hyperproliferation (or other indirect signs of CR). However, experimental animal studies have demonstrated that, although

less likely to occur than solid organ transplantation, chronic rejection can be induced in VCA animal models. Unadkat *et al.* using a rat hindlimb transplant model, reported histological changes consistent with chronic rejection after repeated episodes of acute rejection.¹⁵⁸ Similarly, using a non-human primate facial allotransplantation model, Munding *et al.* demonstrated that multiple acute rejection episodes can result in chronic rejection.¹⁵⁹ Furthermore, more recent reports by Kaufman and colleagues provide clinical evidence for chronic rejection in six hand transplant recipients who show signs of arterial vasculopathy.¹⁶⁰ Aggressive and severe intima hyperproliferation was observed in the early postoperative period in two of the six recipients in their patient series. Morelon *et al.* reported clinicopathological findings and the first clinically documented evidence of chronic rejection in one of their face transplant recipients.¹⁶¹ This case demonstrated that chronic rejection is a complex multifactorial process in VCA. Chronic rejection of the skin seems to be driven by the recipient's cellular immune effectors, which can lead to the development of scleroderma-like features, resembling chronic GvHD. In contrast, graft vasculopathy is probably more dependent on the humoral arm of the alloimmune response, as evidenced also in solid organ transplantation. Additional mechanistic studies in reliable small and large animal settings are needed to explore these complex rejection processes. With prolonged survival of upper extremity transplants, we will inevitably see over the next 1–2 decades more allografts develop signs of chronic rejection. We will then be able to better define, diagnose, and grade this condition. Meanwhile, we are limited to minimizing the known risk factors (from the solid organ experience) that may contribute to a postulated increase of chronic rejection in upper extremity allotransplantation (Table 38.4).

Tolerance approaches and immunomodulatory strategies

VCA is different to solid organ transplantation in that it is a life-enhancing, not a life-saving, procedure. Therefore, the

development of tolerance is of utmost importance in order to reduce the toxicities associated with chronic immunosuppression. Although tolerance has been difficult to define, an “operational” definition is “the long-term functional survival of an allograft in a patient without the need for maintenance immunosuppression”.¹⁶² Such a tolerant state is characterized by hyporesponsiveness to donor tissue with the preservation of the recipient's immune responses to microorganisms (bacteria, viruses) and tumor antigens. The strategies for induction of allograft tolerance can be broadly divided into two approaches: (1) central deletional mechanisms or (2) peripheral regulatory strategies.¹⁶³

When considering development of novel therapeutic strategies for minimization or avoidance of maintenance immunosuppression after upper extremity allotransplantation, cell-based protocols, including mixed chimerism induction using donor bone marrow cells, mesenchymal stem cells (from various sources such as bone marrow or fat), regulatory T and B cells, or tolerogenic dendritic cells (TolDCs) have all demonstrated potential for inducing tolerance in preclinical animal models.¹⁶⁴ For example, in the case of bone marrow-derived stem cell therapy, stem cells are transplanted into the recipient, and the newly developing recipient T cells begin to see these donor cells as “self”. Therefore, the recipient perceives an organ from the same marrow donor as “self” and accepts it without immunosuppression. The mixed chimerism model involves induction of allograft tolerance by establishing long-term mixed chimerism, a state in which both donor and recipient hematopoietic cells coexist.¹⁶⁵ This strategy requires engraftment of donor stem cells. Some vascularized composite allografts, in particular limb transplants, bring with them vascularized bone marrow in its microenvironment enabling a sustainable, renewable source of donor bone marrow cells that could potentially promote immunoregulation without the need for engraftment.^{166,167} In solid organ transplantation, infusion of donor-derived bone marrow cells has been shown to reduce/avoid maintenance immunosuppression required for graft survival.¹⁶⁸ Bone marrow is critical for the establishment of macrochimerism, microchimerism, or mixed

Table 38.4 Recommendations to reduce risk of acute and chronic rejection in hand transplantation

Immunologic factors		
1.	Prevention of AR	Use selective, specific and safer immunosuppressive drugs. Potent and targeted induction agents like Campath-1H (alemtuzumab) could maximize AR prevention, allowing monotherapy maintenance and steroid avoidance
2.	Treat steroid-resistant or CD20-positive AR	Campath-1H (anti-CD52) or rituximab (anti-CD20)
3.	Monitor and curb medication non-compliance	Suggested methods include electronic measurements of pill container opening, regular monitoring of blood drug levels, frequent clinical examinations, repeated biopsies or immune monitoring
4.	Reduce risk factors	Exclude patients with high PRA, avoid sex/racial mismatch between donor/recipient and exclude hand allografts from CMV+ donors.
Non-immunologic factors		
1.	Choose younger donors and exclude donors with systemic atherosclerosis	
2.	Avoid prolonged cold ischemia	
3.	Treat recipient risk factors aggressively (antidiabetic, antihypertensive, or lipid lowering drugs with dietary or lifestyle changes if necessary).	
AR, Acute rejection; PRA, panel reactive antibody; CMV, cytomegalovirus.		

chimerism after organ transplantation, and is a known prerequisite for donor-antigen-specific tolerance induction.^{169,170}

Allograft rejection is caused by activated T cells and cannot occur in their absence. Campath-1H (alemtuzumab) is an antibody that binds to the CD52 receptor, critical for T-cell function in humans.¹⁷¹ Campath-1H leads to peri-transplant depletion of T cells, B cells, and monocytes, but spares bone marrow stem cells. Renal transplant trials with Campath-1H have demonstrated that allograft survival could be prolonged but with low doses of maintenance immunosuppression.^{172,173} Such a state of tolerance is called “prope-tolerance” or “tolerance-lite”. Campath 1H has been used as an induction agent in several upper extremity transplant programs toward the goal of minimizing maintenance immunosuppression; however, its efficacy is still unknown.

Over the past five decades, more than 50 different methods of tolerance induction have succeeded in small or large animal models. Yet tolerance protocols have not widely replaced immunosuppression in clinical transplantation. The transition of experimental tolerance protocols to the clinical transplant arena is fraught with questions: Can experimental tolerance protocols meet the stringent fail-safe clinical standards of reliability and efficacy? How durable or persistent is the tolerant state? How immunocompetent will the recipient be? What is the universally accepted test or “assay” for tolerance? What are the long-term adverse effects of tolerance induction? However, the few tolerance strategies that have been translated to the clinic hold great promise for becoming more widespread and clinically routine in the near future. Until this

is achieved, conventional immunosuppression, as used in solid organ transplantation, will remain the “gold standard” in VCA.

Future directions of upper extremity reconstructive transplantation

VCA has emerged as a viable option to treat patients with severe defects not amenable to traditional autogenous reconstruction. Although surgical outcomes over the last two decades show great promise, the long-term results with this innovative procedure are still emerging. The main obstacles that limit the success of upper extremity VCA are the current immunotherapy requirements as well as current limits to peripheral nerve regeneration, thus limiting functional outcomes with very proximal defects. However, with current advances in cell-based therapy and the increasing immunological understanding of vascularized composite allografts, research in reconstructive transplantation is uniquely poised to make significant breakthroughs in transplant immunology, with the potential to make the application of this innovative reconstructive treatment modality widely available.



Bonus image for this chapter can be found online at

<http://www.expertconsult.com>

Fig. 38.1 St. Cosmas and Damian perform the first human extremity allotransplantation.



Access the complete reference list online at <http://www.expertconsult.com>

15. Carrel A. Results of the transplantation of blood vessels, organs and limbs. *JAMA*. 1908;51:1662.
21. Merrill JP, Murray JE, Harrison JH, et al. Successful homotransplantation of the human kidney between identical twins. *JAMA*. 1956;160:277.
26. Gibson T, Medawar PB. The fate of skin homografts in man. *J Anat*. 1943;77:299. *This is a classic landmark paper by Thomas Gibson and Sir Peter Medawar that provides the first insights into the immune behavior of skin transplants and laid the foundations for tissue transplantation.*
41. Anonymous. Historic cadaver-to-man hand transplant. *Med World News*. 1964;5(6):60.
69. Lee WP, Yaremchuk MJ, Pan YC, et al. Relative antigenicity of components of a vascularized limb allograft. *Plast Reconstr Surg*. 1991;87:401–411. *This is a highly cited study that addresses the differential antigenicity of limb transplants, establishing that whole-limb allografts elicit lesser immune response than their individual components (skin, subcutaneous tissue, muscle, bone, and blood vessels) in terms of cell-mediated and humoral immune responses as well as the timing and intensity of rejection.*
90. Breidenbach WC, Tobin GR, Gorantla VS, et al. A position statement in support of hand transplantation. *J Hand Surg Am*. 2002;27:760–770. *This is a comprehensive review of emerging outcomes in upper extremity transplantation with emphasis on the early developments in the field, experimental, scientific, and clinical considerations and the ethical debate surrounding initial human trials.*
126. Petruzzo P, Lanzetta M, Dubernard JM, et al. The International Registry on Hand and Composite Tissue Transplantation. *Transplantation*. 2010;90:1590–1594.
128. Amirlak B, Gonzalez R, Gorantla V, et al. Creating a hand transplant program. *Clin Plast Surg*. 2007;34:279–289. *This is essential reading to understand the basic requirements to establish an upper extremity composite tissue transplant program. The planning, preapproval, personnel, protocol and public relations related aspects and the program, procedural, and patient considerations are discussed.*
142. Cendales LC, Kanitakis J, Schneeberger S, et al. The Banff 2007 working classification of skin-containing composite tissue allograft pathology. *Am J Transplant*. 2008;8:1396–1400.
162. Starzl TE. Immunosuppressive therapy and tolerance of organ allografts. *N Engl J Med*. 2008;358:407–411. *Authored by one of the pioneers in organ transplantation, this paper discusses the concepts and clinical applications of immunosuppression, immunomodulation and tolerance, highlighting the paradigm shifts in the field.*

References

- Bergan A. Ancient myth, modern reality: a brief history of transplantation. *J Biocommun.* 1997;24:2-9.
- Bhishagratna KC. *An English Translation of the Sushruta Samhita, Based on Original Sanskrit Text.* Calcutta: 1907.
- Hoernlé AFR. *Studies in the Medicine of Ancient India.* Oxford: Clarendon; 1907.
- Hoernlé AFR. *Archaeological Survey of India.* Calcutta: The Bower Manuscripts; 1893:22.
- Da Varagine J. *Leggenda Aurea.* Florence: Libreria Editrice Fiorentina; 1952:648.
- Kahan BD. Cosmas and Damian revisited. *Transplant Proc.* 1983;15(4 suppl 1-2):2211.
- Danilevicius Z. Cosmas and Damian: the patron saints of medicine in art. *JAMA.* 1967;201:1021.
- Rinaldi E. The first homoplastic limb transplant according to the legend of Saint Cosmas and Saint Damian. *Italian J Orthop Traumatol.* 1987;13(3):393-406.
- Converse JM, Casson PR. The historical background of transplantation. In: Rapaport FT, Dausset J, eds. *Human Transplantation.* New York, NY: Grune & Stratton; 1968.
- Tagliacozzi G. *De Curtorum Chirurgia per Insitionem.* Venice: University of Milan; 1597.
- Tagliacozzi G. *De curtorum chirurgia.* Lib. In: Reiner G, ed. xxx. Berloni: 1831 Chs 12,18 (and passim).
- Teach M, Gnudi JP. The sympathetic slave. In: *The Life and Times of Gaspare Tagliacozzi.* Los Angeles: Zeitlin and Ver Brugge; 1976:285-286.
- Carrel A. La technique opératoire des anastomoses vasculaires et la transplantation des viscères. *Lyon Med.* 1902;99:859.
- Carrel A. The surgery of blood vessels, etc. *Bull Johns Hopkins Hosp.* 1907;18:18.
- Carrel A. Results of the transplantation of blood vessels, organs and limbs. *JAMA.* 1908;51:1662.
- Padgett EC. The full-thickness skin graft in the correction of soft tissue deformities. *JAMA.* 1932;98:18.
- Brown JB. Homografting of skin: with report of success in identical twins. *Surgery.* 1937;1:558.
- Hall RH. Whole upper extremity transplant for human being: general plans of procedure and operative technique. *Ann Surg.* 1944;120:12.
- Medawar PB. The behavior and fate of skin autografts and skin homografts in rabbits. *J Anat.* 1944;78:176.
- Murray JE, Merrill JP, Harrison JH. Renal homotransplantation in identical twins. *Surg Forum.* 1955;6:432.
- Merrill JP, Murray JE, Harrison JH, et al. Successful homotransplantation of the human kidney between identical twins. *JAMA.* 1956;160:277.
- Peacock EE Jr. Some problems in flexor tendon healing. *Surgery.* 1959;45:415.
- Peacock EE Jr. Restoration of finger flexion with homologous composite tissue tendon grafts of the digital flexor mechanism in human beings. *Trans Bull.* 1960;7:418.
- Tobin GR, Breidenbach WC 3rd, Ildstad ST, et al. The history of human composite tissue allotransplantation. *Transplant Proc.* 2009;41:466-471.
- Landsteiner K. Über: Agglutinationserscheinungen normalen menschlichen blutes. *Wien Klin Wochenschr.* 1901; 14:1132.
- Gibson T, Medawar PB. The fate of skin homografts in man. *J Anat.* 1943;77:299. This is a classic landmark paper by Thomas Gibson and Sir Peter Medawar that provides the first insights into the immune behavior of skin transplants and laid the foundations for tissue transplantation.
- Owen RD. Immunogenetic consequences of vascular anastomoses between bovine twins. *Science.* 1945;102:400.
- Anderson D, Billingham RE, Lampkin GH, et al. The use of skin grafting to distinguish between monozygotic and dizygotic twins in cattle. *Heredity.* 1951;5:379.
- Simonsen M. The impact on the developing embryo and newborn animal of adult homologous cells. *Acta Pathol Microbiol Scan.* 1957;40:480.
- Dausset J. Iso-leuco-anticorps. *Acta Haematol.* 1958;20:157.
- Terasaki PI, McClelland JD. Microdroplet assay of human serum cytotoxins. *Nature.* 1964;204:998.
- Dausset J, Ivanyi P, Ivanyi D. Tissue alloantigens in humans: identification of a complex system (HU-1). In: Balner H, Cleton FJ, Eernisse JG, eds. *Histocompatibility Testing.* Copenhagen: Munksgaard; 1965:51-62.
- Dausset J, Rapaport FT, Legrand L, et al. Skin allograft survival in 238 human subjects: rule of specific relationship at the four sites of the first and the second HLA loci. In: *Histocompatibility Testing.* Copenhagen: Munksgaard; 1970:381-397.
- Hamburger J, Vaysse J, Crosnier J, et al. Transplantation of a kidney between non-monozygotic twins after irradiation of the receiver: good function at the fourth month. *Press Med.* 1959;67:1771.
- Hamburger J, Vaysse J, Crosnier J, et al. Renal homotransplantations in man after radiation of the recipient. *Am J Med.* 1962;32:854.
- Murray JE, Merrill JP, Dammin GJ, et al. Kidney transplantation in modified recipients. *Ann Surg.* 1962;156:337.
- Murray JE, Merrill JP, Harrison JH, et al. Prolonged survival of human-kidney homografts by immunosuppressive drug therapy. *N Engl J Med.* 1963;268:1315.
- Küss R, Legrain M, Mathe G, et al. Homologous human kidney transplantation: experience with six patients. *Postgrad Med J.* 1962;38:528.
- Starzl TE, Marchioro TL, Weddell WR. The reversal of rejection in human renal homografts with subsequent development of homograft tolerance. *Surg Gynecol Obstet.* 1963;117:385.
- Starzl TE. *Experience in renal transplantation.* Philadelphia, PA: Saunders; 1964:1-383.
- Anonymous. Historic cadaver-to-man hand transplant. *Med World News.* 1964;5(6):60.
- Anonymous. Helping hand. *Time.* 1964;83(10):42.
- Najarian JS, Simmons RL, eds. *Clinical transplantation: Bone and cartilage: transplantation.* Philadelphia, PA: Lea and Febiger; 1972:685-686.
- Dreyfuss M, Harri E, Hofmann H, et al. Cyclosporin A and C; new metabolites from *Trichoderma polysporum* Rifai. *Eur J Appl Microbiol.* 1976;3:125-133.
- Borel JF, Feurer C, Gubler HU, et al. Biological effects of cyclosporine A; a new antilymphocyte agent. *Agents Actions.* 1976;6:468-475.
- Calne RY, White DJG, Thiru S, et al. Cyclosporine A in patients receiving renal allografts from cadaver donors. *Lancet.* 1978;2:1323-1327.
- Cosimi AB, Colvin RB, Barton RC, et al. Use of monoclonal antibodies to T-cell subsets for immunological monitoring and treatment in recipients of renal allografts. *N Engl J Med.* 1981;305:308-314.
- Goto T, Kino T, Hatanaka H, et al. Discovery of FK-506, a novel immunosuppressant isolated from *Streptomyces tsukubaensis*. *Transplant Proc.* 1987;19(5 suppl 6):4-8.
- Starzl TE, Todo S, Fung JJ, et al. FK 506 for human liver, kidney and pancreas transplantation. *Lancet.* 1989;2:1000-1004.
- Fung JJ, Todo S, Jain A, et al. Conversion of liver allograft recipients with cyclosporine related complications from cyclosporine to FK 506. *Transplant Proc.* 1990;22:6-12.
- Armitage JM, Kormos RL, Griffith BP, et al. The clinical trial of FK 506 as primary and rescue immunosuppression in cardiac transplantation. *Transplant Proc.* 1991;23:1149-1152.
- Todo S, Fung JJ, Starzl TE, et al. Liver, kidney and thoracic organ transplantation under FK 506. *Ann Surg.* 1990;212:295-305.

53. Starzl TE, Fung JJ, Jordan M, et al. Kidney transplantation under FK 506. *JAMA*. 1990;264:63–67.
54. Starzl TE, Abu Elmagd K, Tzakis A, et al. Selected topics on FK 506: with special reference to rescue extrahepatic whole organ grafts, transplantation of “forbidden organs,” side effects, mechanisms, and practical pharmacokinetics. *Transplant Proc*. 1991;23:914–919.
55. Todo S, Tzakis AG, Abou Elmagd K, et al. Intestinal transplantation in composite visceral grafts or alone. *Ann Surg*. 1992;216:223–233.
56. Todo S, Tzakis AG, Abou Elmagd K, et al. Cadaveric small bowel and small bowel-liver transplantation in humans. *Transplantation*. 1992;53:369–376.
57. Gorantla VS, Barker JH, Jones JW Jr, et al. Immunosuppressive agents in transplantation: mechanisms of action and current anti-rejection strategies. *Microsurgery*. 2000;20:420–429.
58. Allison AC, Eugui EM. Immunosuppressive and other effects of mycophenolic acid and an ester prodrug, mycophenolate mofetil. *Immunol Rev*. 1993;136:5–28.
59. Vézina C, Kudelski A, Sehgal SN. Rapamycin (AY-22989), a new anti-fungal antibiotic: Taxonomy of the producing streptomycete and isolation of the active principle. *J Antibiot (Tokyo)*. 1975;28:721–726.
60. Halloran P, Mathew T, Tomlanovich S, et al. Mycophenolate mofetil in renal allograft recipients: a pooled efficacy analysis of three randomized, double blind clinical studies in prevention of rejection. The International Mycophenolate Mofetil Renal Transplant Study Groups. *Transplantation*. 1997;63:3–47.
61. McAlister VC, Gao Z, Peltekian K, et al. Sirolimus-tacrolimus combination immunosuppression. *Lancet*. 2000;355:376–377.
62. Kahan BD, Podbielski J, Napoli KL, et al. Immunosuppressive effects and safety of sirolimus/cyclosporine combination regimen for renal transplantation. *Transplantation*. 1998;66:1040–1046.
63. Shapiro JAM, Lakey JRT, Ryan EA, et al. Islet transplantation in seven patients with type-1 diabetes mellitus using a glucocorticoid free immunosuppressive regimen. *N Engl J Med*. 2000;343:230–238.
64. Shores JT, Brandacher G, Schneeberger S, et al. Composite tissue allotransplantation: hand transplantation and beyond. *J Am Acad Orthop Surg*. 2010;18:127–131.
65. National Center for Health Statistics. *Vital and Health Statistic Reports*. 1996. https://www.cdc.gov/nchs/data/series/sr_10/sr10_200.pdf.
66. Ziegler-Graham K, MacKenzie EJ, Ephraim PL, et al. Estimating the prevalence of limb loss in the United States: 2005 to 2050. *Arch Phys Med Rehabil*. 2008;89:422–429.
67. Pollard MS. Hand transplantation: risks of immunosuppression. *J Hand Surg [Br]*. 2001;26:517.
68. Brenner MJ, Tung TH, Jensen JN, et al. The spectrum of complications of immunosuppression: is the time right for hand transplantation? *J Bone Joint Surg Am*. 2002;84:1861–1870.
69. Lee WP, Yaremchuk MJ, Pan YC, et al. Relative antigenicity of components of a vascularized limb allograft. *Plast Reconstr Surg*. 1991;87:401–411. *This is a highly cited study that addresses the differential antigenicity of limb transplants, establishing that whole-limb allografts elicit lesser immune response than their individual components (skin, subcutaneous tissue, muscle, bone, and blood vessels) in terms of cell-mediated and humoral immune responses as well as the timing and intensity of rejection.*
70. Zeevi A. Immunomonitoring after human limb allotransplantation. *Transplant Proc*. 1998;30:2711–2715.
71. Duquesnoy RJ. Is histocompatibility testing needed for composite tissue transplantation? *Transplant Proc*. 1998;30:2724–2728.
72. Schneeberger S, Gorantla VS, Hautz T, et al. Immunosuppression and rejection in human hand transplantation. *Transplant Proc*. 2009;41:472–475.
73. Doi K. Homotransplantation of limbs in rats. *Plast Reconstr Surg*. 1979;64:613–621.
74. Press BH, Sibley RK, Shons AR. Modification of experimental limb allograft rejection with cyclosporine and prednisone: a preliminary report. *Transplant Proc*. 1983;15(suppl 1):3057.
75. Black KS, Hewitt CW, Hwang JS, et al. Dose response of cyclosporine-treated composite tissue allografts in a strong histocompatible rat model. *Transplant Proc*. 1988;20:266–268.
76. Kim SK, Aziz S, Oyer P, et al. Use of cyclosporine A in allotransplantation of rat limbs. *Ann Plast Surg*. 1984;12:249–255.
77. Fritz WD, Swartz WM, Rose S, et al. Limb allografts in rats immunosuppressed with cyclosporine A. *Ann Surg*. 1984;199:211–215.
78. Min Z, Jones NF. Limb transplantation in rats: immunosuppression with FK-506. *J Hand Surg Am*. 1995;20:77–87.
79. Jensen JN, Mackinnon SE. Composite tissue allotransplantation: A comprehensive review of the literature: part III. *J Reconstr Microsurg*. 2000;16:235–251.
80. Daniel RK, Egerszegi EP, Samulack DD, et al. Tissue transplants in primates for upper extremity reconstruction: a preliminary report. *J Hand Surg Am*. 1986;11:1–8.
81. Stark GB, Swartz WM, Narayanan K, et al. Hand transplantation in baboons. *Transplant Proc*. 1987;19:3968–3971.
82. Hovius SE, Stevens HP, van Nierop PW, et al. Allogeneic transplantation of the radial side of the hand in the rhesus monkey: I. Technical aspects. *Plast Reconstr Surg*. 1992;89:700–709.
83. Egerszegi EP, Samulack DD, Daniel RK. Experimental models in primates for reconstructive surgery utilizing tissue transplants. *Ann Plast Surg*. 1984;13:423–430.
84. Benhaim P, Anthony JP, Ferreira L, et al. Use of combination of low-dose cyclosporine and RS-61443 in a rat hindlimb model of composite tissue allotransplantation. *Transplantation*. 1996;61:527–532.
85. Üstüner ET, Zdichavsky M, Ren X, et al. Long-term composite tissue allograft survival in a porcine model with cyclosporine/mycophenolate mofetil therapy. *Transplantation*. 1998;66:1581–1587.
86. Jones JW Jr, Üstüner ET, Zdichavsky M, et al. Long-term survival of an extremity composite tissue allograft with FK506-mycophenolate mofetil therapy. *Surgery*. 1999;126:384–388.
87. Hall T, Tumbleson M, eds. *Swine in Biomedical Research*. New York, NY: Plenum Press; 1985:373.
88. Lanzetta M, Ayrout C, Gal A, et al. Experimental limb transplantation in rodents. Excellent functional recovery and indefinite survival without immunosuppression. In: Dubernard JM, ed. *Composite Tissue Allografts*. Paris: John Libbey Eurotext; 2001:3.
89. Perez-Abadia G, Laurentin-Perez L, Gorantla VS, et al. Low dose immunosuppression in a rat hind-limb transplantation model. *Transpl Int*. 2003;16:835–842.
90. Breidenbach WC, Tobin GR, Gorantla VS, et al. A position statement in support of hand transplantation. *J Hand Surg Am*. 2002;27:760–770. *This is a comprehensive review of emerging outcomes in upper extremity transplantation with emphasis on the early developments in the field, experimental, scientific, and clinical considerations and the ethical debate surrounding initial human trials.*
91. Merrill JP, Murray JE, Harrison JH, et al. Successful homotransplantation of the kidney between non-identical twins. *N Engl J Med*. 1960;262:1251–1260.
92. Barnard CN. What we have learned about heart transplants. *J Thorac Cardiovasc Surg*. 1968;56:457–468.
93. Dong E, as told by Shumway NE, Lower RR. In: Terasaki PI, ed. *History of Transplantation: Thirty-Five Recollections*. Los Angeles, CA: UCLA Tissue Typing Laboratory; 1991:435.
94. Starzl TE, Groth CG, Bretschneider L, et al. Orthotopic homotransplantation of the human liver. *Ann Surg*. 1968;168:392–415.
95. Derom F, Barbier F, Ringoir S, et al. Ten-month survival after lung homotransplantation in man. *J Thorac Cardiovasc Surg*. 1971;61:835–846.
96. Lillehei RC, Simmons RL, Najarian JS, et al. Pancreaticoduodenal allotransplantation: Experimental and clinical observations. *Ann Surg*. 1970;172:405–436.
97. Goulet O, Revillon Y, Brousse N, et al. Successful small bowel transplantation in an infant. *Transplantation*. 1992;53:940–943.

98. Starzl TE, Rowe M, Todo S, et al. Transplantation of multiple abdominal viscera. *JAMA*. 1989;261:1449–1457.
99. Thomas ED, Lochte HL Jr, Lu WC, et al. Intravenous infusion of bone marrow in patients receiving irradiation and chemotherapy. *N Engl J Med*. 1957;257:491–496.
100. Wu S, Xu H, Ravindra K, et al. Composite tissue allotransplantation: past, present and future—the history and expanding applications of CTA as a new frontier in transplantation. *Transplant Proc*. 2009;41:463–465.
101. Swearingen B, Ravindra K, Xu H, et al. Science of composite tissue allotransplantation. *Transplantation*. 2008;86:627–635.
102. Burnet FM. The new approach to immunology. *N Engl J Med*. 1961;264:24–34.
103. Page IH. Editorial: Prolongation of life in affluent society. *Mod Med*. 1963;14:89–91.
104. Page IH. Editorial: Unwise publicity. *Mod Med*. 1964;20:139.
105. Elkinton JR. Moral problems in the use of borrowed organs, artificial and transplanted. *Ann Intern Med*. 1964;60:309–313.
106. Dubernard JM, Owen E, Herzberg G, et al. Human hand allograft: report on first 6 months. *Lancet*. 1999;353:1315–1320.
107. Dubernard JM, Owen E, Lefrancois N, et al. First human hand transplantation. Case report. *Transpl Int*. 2000;13:S521–S524.
108. Strickland JW. Hand transplant: technology over good sense. *The Indiana Hand Center Newsletter*. 1999;3:2–4.
109. Herndon JH. Composite tissue transplantation: a new frontier. *N Engl J Med*. 2000;343:503–505.
110. Foucher G. Prospects for hand transplantation. *Lancet*. 1999;353:1286–1287.
111. Hettiaratchy S, Butler PE, Lee WPA. Lessons from hand transplantations. *Lancet*. 2001;357:494–495.
112. Lee WP. Composite tissue transplantation: more science and patience needed. *Plast Reconstr Surg*. 2001;107:1066–1070.
113. Pollard S. Hand transplantation – risk of immunosuppression. *J Hand Surg [Br]*. 2001;26:517.
114. Cooney WP, Hentz VR. Hand transplantation—primum non nocere. *J Hand Surg Am*. 2002;27:165–168.
115. Siegler M. Ethical issues in innovative surgery: should we attempt a cadaveric hand transplantation in a human subject? *Transplant Proc*. 1998;30:2779–2782.
116. Simmons PD. Ethical considerations in composite tissue allotransplantation. *Microsurgery*. 2000;20:458–465.
117. Klapheke M, Marcell C, Taliaferro G, et al. Psychiatric assessment of candidates for hand transplantation. *Microsurgery*. 2000;20:453–457.
118. Jones NF. Concerns about human hand transplantation in the 21st century. *J Hand Surg Am*. 2002;27:771–787.
119. Gorantla VS, Maldonado C, Frank J, et al. Composite tissue allotransplantation (CTA): current status and future insights. *Eur J Trauma*. 2001;27:267–274.
120. Black KS, Hewitt CW. Report: composite tissue transplantation workshop. Washington DC: Department of Veterans Affairs, Rehabilitation Research and Development Service; 1991.
121. Barker JH, Jones JW, Breidenbach WC. Closing remarks. Proceedings of the International Symposium on Composite Tissue Allotransplantation, Louisville, Kentucky. *Transplant Proc*. 1998;30(Special Issue):2787.
122. Petruzzo P, Dubernard JM. Hand transplantation: Lyon experience. In: Dubernard JM, ed. *Composite Tissue Allografts*. Paris: John Libbey Eurotext; 2001:63.
123. Petruzzo P, Kanitakis J, Badet L, et al. Long-term follow-up in composite tissue allotransplantation: in-depth study of five (hand and face) recipients. *Am J Transplant*. 2011;11:808–816.
124. Jones JW, Gruber SA, Barker JH, et al. Successful hand transplantation. One-year follow-up. Louisville Hand Transplant Team. *N Engl J Med*. 2000;343:468–473.
125. Breidenbach WC, Gonzales NR, Kaufman CL, et al. Outcomes of the first 2 American hand transplants at 8 and 6 years posttransplant. *J Hand Surg Am*. 2008;33:1039–1047.
126. Petruzzo P, Lanzetta M, Dubernard JM, et al. The International Registry on Hand and Composite Tissue Transplantation. *Transplantation*. 2010;90:1590–1594.
127. Brandacher G, Gorantla VS, Lee WP. Hand allotransplantation. *Semin Plast Surg*. 2010;24:11–17.
128. Amirlak B, Gonzalez R, Gorantla V, et al. Creating a hand transplant program. *Clin Plast Surg*. 2007;34:279–289. *This is essential reading to understand the basic requirements to establish an upper extremity composite tissue transplant program. The planning, preapproval, personnel, protocol and public relations related aspects and the program, procedural, and patient considerations are discussed.*
129. Gordon CR, Siemionow M. Requirements for the development of a hand transplantation program. *Ann Plast Surg*. 2009;63:262–273.
130. Shores JT. Recipient screening and selection: who is the right candidate for hand transplantation. *Hand Clin*. 2011;27:539–543.
131. Hollenbeck ST, Erdmann D, Levin LS. Current indications for hand and face allotransplantation. *Transplant Proc*. 2009;41:495–498.
132. Kvernmo HD, Gorantla VS, Gonzalez RN, et al. Hand transplantation. A future clinical option? *Acta Orthop*. 2005;76:14–27.
133. Younes BS, McDiarmid SV, Martin MG, et al. The effect of immunosuppression on posttransplant lymphoproliferative disease in pediatric liver transplant patients. *Transplantation*. 2000;70:94–99.
134. McDiarmid SV, Azari KK. Donor-related issues in hand transplantation. *Hand Clin*. 2011;27:545–552.
135. Shores JT, Higgins JP, Lee WP. Above-elbow (supracondylar) arm transplantation: clinical considerations and surgical technique. *Tech Hand Up Extrem Surg*. 2013;1:221–227.
136. Kanitakis J, Jullien D, Petruzzo P, et al. Immunohistologic studies of the skin of human hand allografts: Our experience with two patients. *Transplant Proc*. 2001;33:1722.
137. Schneeberger S, Gorantla VS, van Riet RP, et al. Atypical acute rejection after hand transplantation. *Am J Transplant*. 2008;8:688–696.
138. Hodges A, Chesher S, Feranda S. Hand transplantation: rehabilitation: case report. *Microsurgery*. 2000;20:389–392.
139. Carroll D. A quantitative test of upper extremity function. *J Chronic Dis*. 1965;18:479–491.
140. Hudak PL, Amadio PC, Bombardier C. Development of an upper extremity outcome measure: the DASH (disabilities of the arm, shoulder and hand) [corrected]. The Upper Extremity Collaborative Group (UECG). *Am J Ind Med*. 1996;29:602–608.
141. Lanzetta M, Petruzzo P, Dubernard JM, et al. Second report (1998–2006) of the International Registry of Hand and Composite Tissue Transplantation. *Transpl Immunol*. 2007;18:1–6.
142. Cendales LC, Kanitakis J, Schneeberger S, et al. The Banff 2007 working classification of skin-containing composite tissue allograft pathology. *Am J Transplant*. 2008;8:1396–1400.
143. Cendales LC, Kirk AD, Moresi JM, et al. Composite tissue allotransplantation: classification of clinical acute skin rejection. *Transplantation*. 2006;81:418–422. Erratum: *Transplantation*. 2006;81:422.
144. Zeevi A. Immunomonitoring after human limb allotransplantation. *Transplant Proc*. 1998;30:2711–2715.
145. Ting A, Terasaki PI. Lymphocyte-dependent antibody cross-matching for transplant patients. *Lancet*. 1975;1:304–306.
146. Petruzzo P, Lanzetta M, Dubernard JM, et al. The International Registry on Hand and Composite Tissue Transplantation. *Transplantation*. 2008;86:487–492.
147. Pomahac B, Bueno EM, Sisk GC, et al. Current principles of facial allotransplantation: the Brigham and Women's Hospital Experience. *Plast Reconstr Surg*. 2013;131:1069–1076.
148. Joosten SA, van Kooten C, Paul LC. Pathogenesis of chronic allograft rejection. *Transpl Int*. 2003;16:137–145.
149. Graham B, Adkins P, Tsai TM, et al. Major replantation versus revision amputation and prosthetic fitting in the upper extremity: a late functional outcomes study. *J Hand Surg Am*. 1998;23:783–791.

150. Russell RC, O'Brien BM, Morrison WA, et al. The late functional results of upper limb revascularization and replantation. *J Hand Surg Am.* 1984;9:623–633.
151. Mathes DW, Randolph MA, Solari MG, et al. Split tolerance to a composite tissue allograft in a swine model. *Transplantation.* 2003;75:25–31.
152. Brouha PC, Perez-Abadia G, Francois CG, et al. Lymphadenectomy prior to rat hind limb allotransplantation prevents graft-versus-host disease in chimeric hosts. *Transpl Int.* 2004;17:341–350.
153. Gold BG, Katoh K, Storm-Dickerson T. The immunosuppressant FK506 increases the rate of axonal regeneration in rat sciatic nerve. *J Neurosci.* 1995;15:7509–7516.
154. Doolabh VB, Mackinnon SE. FK 506 accelerates functional recovery following nerve grafting in a rat model. *Plast Reconstr Surg.* 1999;103:1928–1936.
155. Tanaka K, Fujita N, Higashi Y, et al. Neuroprotective and antioxidant properties of FKBP-binding immunophilin ligands are independent on the FKBP12 pathway in human cells. *Neurosci Lett.* 2002;330:147–150.
156. Giraux P, Sirigu A, Schneider F, et al. Cortical reorganization in motor cortex after graft of both hands. *Nat Neurosci.* 2001;4:691–692.
157. Frey SH, Bogdanov S, Smith JC, et al. Chronically deafferented sensory cortex recovers a grossly typical organization after allogeneic hand transplantation. *Curr Biol.* 2008;18:1530–1534.
158. Unadkat JV, Schneeberger S, Horibe EH, et al. Composite tissue vasculopathy and degeneration following multiple episodes of acute rejection in reconstructive transplantation. *Am J Transplant.* 2010;10:251–261.
159. Munding GS, Munivenkatappa R, Drachenberg CB, et al. Histopathology of chronic rejection in a nonhuman primate model of vascularized composite allotransplantation. *Transplantation.* 2013;95:1204–1210.
160. Kaufman CL, Ouseph R, Blair B, et al. Graft vasculopathy in clinical hand transplantation. *Am J Transplant.* 2012;12:1004–1016.
161. Petruzzo P, Kaniakis J, Testelin S, et al. Clinicopathological findings of chronic rejection in a face grafted patient. *Transplantation.* 2015;99:2644–2650.
162. Starzl TE. Immunosuppressive therapy and tolerance of organ allografts. *N Engl J Med.* 2008;358:407–411. *Authored by one of the pioneers in organ transplantation, this paper discusses the concepts and clinical applications of immunosuppression, immunomodulation and tolerance, highlighting the paradigm shifts in the field.*
163. Gorantla VS, Brandacher G, Schneeberger S, et al. Favoring the risk-benefit balance for upper extremity transplantation: the Pittsburgh Protocol. *Hand Clin.* 2011;27:511–520.
164. Madariaga ML, Shanmugarajah K, Michel SG, et al. Immunomodulatory strategies directed toward tolerance of vascularized composite allografts. *Transplantation.* 2015;99:1590–1597.
165. Prabhune KA, Gorantla VS, Maldonado C, et al. Mixed allogeneic chimerism and tolerance to composite tissue allografts. *Microsurgery.* 2000;20:441–447.
166. Ravindra KV, Wu S, Bozulic L, et al. Composite tissue transplantation: a rapidly advancing field. *Transplant Proc.* 2008;40:1237–1248.
167. Taieb A, Clavijo-Alvarez JA, Hamad GG, et al. Immunologic approaches to composite tissue allograft. *J Hand Surg Am.* 2007;32:1072–1085.
168. Kawai T, Cosimi AB, Spitzer TR, et al. HLA-mismatched renal transplantation without maintenance immunosuppression. *N Engl J Med.* 2008;358:353–361.
169. Starzl TE, Demetris AJ, Trucco M, et al. Cell migration and chimerism after whole-organ transplantation: the basis of graft acceptance. *Hepatology.* 1993;17:1127–1152.
170. Wekerle T, Sykes M. Mixed chimerism and transplantation tolerance. *Annu Rev Med.* 2001;52:353–370.
171. Schneeberger S, Landin L, Kaufmann C, et al. Alemtuzumab – the key for minimization of maintenance immunosuppression in reconstructive transplantation? *Transplant Proc.* 2009;41:499–502.
172. Calne RY. Prope tolerance: a step in the search for tolerance in the clinic. *World J Surg.* 2000;24:793–796.
173. Calne RY, Moffatt SD, Friend PJ, et al. Campath 1H allows low-dose cyclosporine monotherapy in 31 cadaveric renal allograft recipients. *Transplantation.* 1999;68:1613–1616.

39

Hand therapy

Christine B. Novak and Rebecca L. Neiduski

 Access video content for this chapter online at expertconsult.com

SYNOPSIS

- In optimal situations, hand therapists work closely with hand surgeons to maximize non-operative and postoperative outcomes for patients with upper extremity conditions.
- Assessment in the area of impairment and body structures includes edema, wound, vascularity, pain, range of motion, strength, and sensibility.
- Following nerve injury and with chronic nerve compression, rehabilitation strategies should be directed not only to the distal recovery but also to re-establishing normal movement patterns and cortical remapping.
- Active motion regimens following flexor tendon repair are becoming more prevalent in both research and practice. The inclusion of a controlled arc of motion with the wrist positioned in extension creates an optimal force/excursion ratio.
- Hand fractures are challenging and require careful attention to bony integrity and maintenance of the flexor and extensor tendon-gliding systems.

In optimal situations, hand therapists work closely with hand surgeons to maximize non-operative and postoperative outcomes for patients with upper extremity conditions. The purpose of this chapter is to provide the plastic surgeon with an overview of the evaluative and rehabilitative approaches for patients with nerve, tendon, skeletal, and soft-tissue conditions as afforded by collaboration with a hand therapist.

Evaluative guidelines

A comprehensive evaluation provides valuable diagnostic and prognostic information to the plastic surgeon and hand therapist prior to intervention, and serves to inform clinical decision-making for management (non-operative and postoperative) of patients with upper extremity conditions. In concert with the International Classification of Functioning, Disability and Health,¹ hand therapists are well versed in the clinical assessment of patients in areas of impairment, activity, and participation.

Introduction

Tenets of hand therapy

According to the Hand Therapy Certification Committee (www.htcc.org/about/index.cfm), the specialty of hand therapy is defined in the following manner:

Hand therapy is the art and science of rehabilitation of the upper limb, which includes the hand, wrist, elbow, and shoulder girdle. It is a merging of occupational therapy and physical therapy theory and practice that combines comprehensive knowledge of the structure of the upper limb with function and activity. Using specialized skills in assessment, planning and treatment, hand therapists provide therapeutic interventions to prevent dysfunction, restore function and/or reverse the progression of pathology of the upper limb in order to enhance an individual's ability to execute tasks and to participate fully in life situations.

Clinical tips

Assessment

- Comprehensive evaluation can provide diagnostic and prognostic information and inform clinical decision making for non-operative and postoperative management.
- Self report questionnaires provide important information to assess impact of injury, activity and participation
- Pain experiences should be documented with subjective report of intensity, quality and impact on function.
- Physical impairments can be assessed related to muscle weakness with manual muscle testing or dynamometers and sensory dysfunction with measures of threshold and discrimination

Assessment in the area of impairment and body structures includes edema, wound, vascularity, pain, range of motion, strength, and sensibility. Edema is most commonly assessed with circumferential measurement. However, it is more accurately assessed using volumetric displacement with a reported test-retest reliability within ± 3 mL.² Wound assessment is characterized by both descriptive and objective components, including a detailed patient history and observation of wound size, color, drainage, odor, and temperature. Vascularity can be assessed both proximally and distally in the upper extremity using provocative maneuvers. In addition to the Allen's test for circulation via the radial and ulnar arteries at the wrist, vascularity may be assessed more proximally using Adson's maneuver at the subclavian artery; the costoclavicular maneuver and hyperabduction test assessed via the radial pulse; and the elevated arm stress test, as described by Roos.³⁻⁵ Pain is a subjective and multifaceted construct, and should be assessed before, during, and after therapeutic interventions. Numeric, verbal, and visual analog scales are commonly used to rate pain intensity and have been identified as having good construct validity.⁶ Simple measures and scales that assess only pain intensity may be inadequate to capture and measure the multidimensional aspects of the pain. The McGill Pain Questionnaire and the Short-Form McGill Pain Questionnaire (SF-MPQ) are the most widely used pain questionnaires to assess the multidimensional qualities of the pain experience and overall have been shown to possess good to excellent psychometric properties.⁷⁻¹⁰ The SF-MPQ consists of a pain intensity visual analog scale, the present pain intensity index, and 15 pain adjectives (11 sensory, four affective) to calculate the pain-rating index.

Goniometric measurement (Video 39.1 ) is used to assess passive and active range of motion. While electrogoniometers and costly systems are available for clinical use, standard manual goniometers are easily portable and inexpensive. In a study assessing wrist motion, high intra-rater reliability was reported using multiple techniques to assess wrist range of motion, with a dorsal volar approach demonstrating the highest inter-rater reliability.¹¹ Ellis and Bruton found composite finger flexion measurements to be as reliable as manual goniometry between raters, with manual goniometry demonstrating increased intra-rater reliability for measurement of the proximal interphalangeal joint.¹² Manual muscle testing is employed to isolate strength of individual muscles and often graded using the Medical Research Council (MRC) grade 0-5 classification.¹³ In a review, Cuthbert and Goodheart reported good evidence to support the use of manual muscle testing for patients with neuromusculoskeletal dysfunction.¹⁴ Sensory impairment is most often assessed using monofilaments for threshold testing (Video 39.2 ) and/or two-point discrimination for innervation density.¹⁵⁻¹⁹ Using standardized techniques, good validity and reliability have been shown using these types of assessment tools.^{15,17,20-23} The Ten Test was introduced as a quick assessment of light touch sensation and has been shown to be a valid measure as compared to monofilament testing.²⁴

Clinical evaluation may also include assessment of grip and pinch strength.²⁵⁻²⁸ A calibrated, hand-held dynamometer is used to measure grip strength in a standard position of glenohumeral adduction, elbow flexion, and neutral forearm rotation.²⁶ One trial has been identified as equally reliable to the best or average of three trials and elicits less patient

discomfort.²⁵ The influences of hand size and span have also been identified as factors to consider when selecting the grip handle position.²⁹⁻³¹ Calibrated gauges are also used to measure both lateral and tip pinch.

A paradigm shift towards increased incorporation of qualitative and patient-reported data into outcomes assessment is strongly encouraged as a means of assessing participation.³² Clinical evaluation tools that assess physical impairments, such as range of motion, have demonstrated limited responsiveness and weak association to patient self-report measures, which may indicate that these types of assessments evaluate different constructs.³³⁻³⁶ Research has also shown a weak relationship between patient perception of health-related quality of life and ratings from healthcare providers.³⁷ Patient perception of ability has been suggested as more valuable than functional evaluations.³⁸ In addition, patient assessment of the importance of change in health status is preferable to that interpreted by the healthcare professional.³⁹ Despite numerous tools and support in the literature, the incorporation of self-report outcome measures is inconsistent in clinical practice.⁴⁰

The Disabilities of the Arm, Shoulder, and Hand (DASH), one of the most recognized self-report outcome measures for the upper extremity, was published as a joint effort of the American Academy of Orthopedic Surgery and the Institute for Work and Health.⁴¹ The DASH was created as a tool to assess upper extremity disability that would allow comparison of conditions throughout the upper extremity while considering it a single, functional unit.^{41,42} Careful development of this tool, including an extensive literature review and consideration of questions and attribution, has made it a popular tool in upper extremity research and clinical practice. However, uniform application in different pathologies and timing of assessments is necessary for valid comparisons of upper extremity disability scores.⁴³ Other studies that investigated the DASH questionnaire as a single construct using factor analysis found a three-factor structure was the best model fit.⁴⁴

Rehabilitation following nerve injury/surgery

Following nerve injury and with chronic nerve compression, neural changes occur in the peripheral and central nervous system. The primary focus has been on the alterations that occur to the nerve and the distal sensory receptors and muscle fibers. The proximal changes that occur in the central nervous system have been less emphasized. Cortical remapping and cell body changes have been documented with nerve injury and nerve compression. Therefore to optimize outcome, rehabilitation strategies should be directed not only to the distal recovery but also to re-establishing normal movement patterns and cortical remapping. This section will review postoperative management following surgery for carpal and cubital tunnel syndrome, nerve repair, and nerve transfers.

Compression neuropathies

Postoperative care following surgery for compression neuropathies is a balance between protecting the surgical repair site and maintaining neural mobility. To minimize adhesions

and scarring, early motion is advocated. However, the definition of “early motion” following release of an entrapment site is variable and is determined by the surgical procedure performed and surgeon preference.^{45,46} Compared to the historical reports in the literature, the tendency has been to decrease the length of time of immobilization and to use less restrictive postoperative dressings.^{47,48} Range-of-motion exercises are instituted and restoration of muscle balance is also a goal of postoperative care.

In the acute postoperative stage, consideration is given to edema control and pain management, and the patient is instructed in strategies to minimize edema and pain. Even in the early stages following surgery, nerve-gliding exercises are instituted with range-of-motion exercises to the distal and proximal joints that are not included in the bulky dressing. These types of exercise will provide some longitudinal movement of the nerve to minimize adhesions.

Carpal tunnel syndrome

Postoperative care

Historically, following release of the carpal tunnel, immobilization was used to protect the wound and to prevent bow-stringing of the flexor tendons by restricting motion at the wrist. With recognition of the importance of early motion, the duration and type of immobilization following carpal tunnel release have substantially decreased. In our practice, a bulky dressing is used for restriction of wrist movement and for patient comfort in the immediate postoperative period. Following surgery, the patient is instructed in range-of-motion exercises for the fingers, elbow, and shoulder. Two days following surgery, the bulky dressing is removed and the patient is instructed in range-of-motion exercises for the fingers, wrist, elbow, and shoulder. For patient comfort, an orthosis in a wrist neutral position may be used at night. The sutures are removed 12–14 days following surgery. Return to work is dependent upon the type of job and specific patient factors. However, at 4 weeks after surgery, patients should have full range of motion and may lift up to 2 lb (0.9 kg) and, by 2 months following surgery, full activity without restrictions is expected.⁴⁷ Depending on the severity of nerve compression, the duration of time required to achieve full sensory and motor recovery may vary.

Cubital tunnel syndrome

With failure of non-operative treatment, there are numerous surgical procedures performed for the operative treatment of cubital tunnel syndrome, ranging from simple decompression, medial epicondylectomy, to various types of anterior transposition of the ulnar nerve.⁴⁷ With each procedure, there are numerous protocols for the postoperative management and many vary depending upon surgeon preference. In general, early motion is recommended to minimize adhesions and scarring of the ulnar nerve and surrounding soft tissue.

Postoperative care

There is wide variability in the duration of immobilization following surgery for cubital tunnel syndrome and this depends upon the operative procedure performed and surgeon preference. The period of immobilization is increased for those procedures that involve more complex release of the

soft tissue surrounding the ulnar nerve (i.e., least immobilization for simple decompression). In most cases, the postoperative dressing may be removed 2–3 days after surgery and then a postoperative method of immobilization may be used if required. For patient comfort, a sling may be used at night to restrict upper extremity motion while the patient is sleeping. The postoperative care following an intramuscular or submuscular transposition will be described.⁴⁷ In our experience, patients may begin range-of-motion exercises (fingers, wrist, forearm, elbow, and shoulder) when the dressing is removed at postoperative day 2 or 3. Patients are cautioned to perform these exercises slowly and initially to avoid full forearm supination combined with full elbow extension because this motion will place the most stress on the soft-tissue repair. Initially elbow extension is performed with the forearm in pronation and then, as a separate exercise, forearm supination is performed with the elbow flexed at 90°. When the patient is able to move comfortably into full supination, forearm supination is combined with elbow extension. A sling is used at night for patient comfort to avoid rapid elbow extension and may be discontinued when the patient has achieved full elbow extension with full forearm supination. The emphasis in the early postoperative period is to regain full range of motion and it is anticipated that this is achieved within the first 2–3 weeks following surgery. If the patient appears to be progressing slowly and lacking improvements in range of motion, more structured hand therapy is recommended. Strengthening exercises are instituted 1 month following surgery and full activity is permitted at 8 weeks.

Concomitant soft-tissue muscle imbalances and other sites of nerve compression in the upper extremity may require rehabilitation therapy to achieve full recovery. Some patients may also have restricted neural excursion, cervicospinal discomfort, and/or rotator cuff tendinitis associated with muscle imbalances in this region. Specific exercises to address these more proximal soft-tissue and neural structures will help to ameliorate these types of symptoms in patients with more diffuse upper extremity discomfort, paresthesia, and/or numbness.^{49–54}

Nerve repair

Changes in the peripheral and central nervous system begin shortly after nerve injury and continue through recovery. The ultimate functional outcome depends upon reinnervation of the sensory receptors and motor end plates and the appropriate remapping of the motor and sensory cortex. Based upon these proximal changes, rehabilitation is maximized by including strategies directed towards these cortical alterations.

Early postoperative care

In the immediate postoperative period, the primary goal is to protect the nerve repair site. Initially, a bulky dressing is used and, if required by the operative procedure, more rigid support can be utilized. The patient is instructed in edema control and range-of-motion exercises for the joints that are not immobilized by the bulky operative dressing. The initial dressing is removed within a few days following surgery. Immobilization is continued with the use of a custom-made or prefabricated orthosis or, in some cases, a sling or shoulder

immobilizer may provide sufficient support to restrict forces on the repair site. Nerve repairs compared to nerve grafts or nerve transfers are typically immobilized for longer periods of time – in some cases up to 3 weeks. The timing of immobilization will depend upon the location of the nerve repaired and the amount of nerve mobility and stress on the nerve coaptation site. In some cases, such as with digital nerve injuries, some surgeons have advocated no immobilization after the initial operative dressing has been removed.⁵⁵ With a nerve graft or transfer, there is excessive nerve length at the repair site and lack of tension with these reconstructions and, as such, these types of reconstruction require less rigid immobilization and may be mobilized earlier (7–14 days) compared to nerve repairs. However, other soft tissues (tendons, muscles, or ligaments) that may have been released or repaired in the operative procedure may prolong the period of immobilization. For example, repair of the pectoralis major with exploration of the brachial plexus may require 4 weeks of immobilization in internal shoulder rotation using a shoulder immobilizer to avoid tension on the soft-tissue repair or, with acute injuries that may involve a tendon repair, a tendon rehabilitation protocol would be followed.

Early postoperative pain resulting from the operative procedure may be controlled with analgesics, edema control, early motion, and hand therapy. However, ongoing severe neuropathic pain may negatively impact outcome and therefore early pain management intervention is recommended.^{56,57} Neuropathic pain following trauma may require a comprehensive multidisciplinary approach and, as such, referral to a pain management team may be warranted.

The use of electrical muscle stimulation is often advocated following nerve injury to prevent muscle degeneration and to protect the muscle fiber until regeneration occurs. However, the literature does not present strong evidence for the use of this modality following nerve injury.^{58,59} Historically, the rationale for electrical stimulation of denervated muscles has been to retain integrity of the muscle fibers while waiting for muscle reinnervation. Studies using animal models with denervated muscles and electrodes implanted directly into the muscle have shown preservation of some normal muscle properties.^{60,61} However, no efficacy trials have provided evidence of these benefits in humans. Evidence presented in the literature suggests that longer durations of axotomy and Schwann cell denervation are predictive of poor functional outcome.^{62,63} Low-frequency stimulation of the nerve following nerve transection and repair in animal models has shown an increase in axonal regeneration into the appropriate neural pathway.^{63,64} In patients after carpal tunnel release, 1 h of low-frequency nerve stimulation resulted in significantly faster motor reinnervation.⁶⁵ This evidence provides the impetus for future investigation into the benefits of direct nerve stimulation to improve recovery following a motor nerve injury. However, the use of direct current stimulation for denervated muscles has not been shown to be efficacious in humans and, as such, is not advocated by the authors.

Late rehabilitation

In the later phases of rehabilitation, sensory re-education has been recognized as an integral component of therapy following nerve injury; however, the importance of motor re-education following nerve injury has been less emphasized.

The integration of function between the sensory and motor cortex is essential for restoration of sensorimotor control and to optimize outcome. The concept of cortical plasticity and its importance to recovery following nerve injury have gained increased attention in the past decade.

Sensory re-education

Following sensory nerve reconstruction, sensory re-education is commonly included in the rehabilitation program to improve hand sensibility and function. These strategies have been used to maximize sensory recovery, to decrease pain and for desensitization related to allodynia and/or hyperalgesia.^{66–70} Desensitization exercises using different textures and vibration techniques may be used to decrease allodynia and/or hyperalgesia. The concept of vibration for desensitization relates to the gate control theory of pain and stimulation of large A-beta fibers with vibration.⁷¹ The use of small-amplitude vibration for desensitization is best tolerated by patients and may be achieved by using an electric shaver with the cap on it. This will provide an easy technique for the patient to continue this exercise in a home program. With decreasing sensitivity, the area of allodynia may be challenged with different types of texture to promote sensory re-education and appropriate cortical mapping.

With evidence of reinnervation of the sensory receptors, sensory re-education is advocated.⁶⁶ This typically includes a structured program with an emphasis on textures, localization, and discriminatory tasks.⁶⁶ The exercises are progressed to challenge the sensory system as the patient's sensation improves, beginning with varying textures, localization exercises, and then discriminatory tasks. However, strategies to enhance and promote cortical remapping have been also advocated in the earlier phases following surgery. Rosen and Lundborg have described re-education programs using mirror imagery, visuotactile training, and audiotactile interaction to enhance the functional reorganization of the sensory cortex in the early phases of recovery before there is evidence of sensory receptor reinnervation.^{72,73}

Mirror visual feedback has been extensively used for treatment in patients following stroke and with amputation injuries and has been more recently reported for use in patients with pain syndromes or nerve injury.^{74,75} The concept of mirror visual feedback is that patients observe their reflected image in the mirror, which would appear as the contralateral limb (Fig. 39.1) and thus activate the brain. Patients may perform specific exercises or movements with the unaffected hand or extremity and in the mirror it would appear as normal movement to the affected hand or extremity. With improvement in sensory function or decreased pain, more complex activities may be introduced and also combined with motor re-education.

Motor re-education

The goals of treatment for motor function are directed towards re-establishment of normal movement patterns and muscle balance. Following nerve injury, motor re-education is not as frequently advocated compared to sensory re-education. Alterations in cortical mapping and motor patterns occur following injury to a motor nerve.^{76,77} With reinnervation of the denervated muscles, muscle imbalances will remain due to weakness of the reinnervated muscles compared to the




Fig. 39.1 Re-education can be optimized with the use of mirror imagery. This allows the patient to visualize the uninjured hand as the contralateral hand and perform the task. (Courtesy of Christine B. Novak, PT, PhD.)

uninjured muscles and also compensatory movement patterns that have been performed since the injury. Particularly in patients with brachial plexus injuries, the duration of time from injury until muscle reinnervation occurs may be prolonged (12–18 months) and abnormal movement patterns are established. Therefore motor re-education will provide the opportunity to focus on appropriate muscle recruitment and muscle balance. Even in patients with only sensory loss following median nerve injury, there will be alteration of the motor pattern due to compensation in movements as a result of numbness to the sensory distribution of the median nerve. Therefore, the emphasis should be on restoration of the integration of motor and sensory re-education following nerve injury. Sensorimotor control to perform upper extremity tasks requires the coordination of both the sensory and motor systems.⁷⁸ Alteration in either motor or sensory function as a result of nerve injury will impact sensorimotor control in the upper extremity. Improvement in hand function may occur with increased use of the hand, but progress may be enhanced with the use of activity-based sensorimotor retraining, emphasis on control, and appropriate feedback learning. As with any new task learning, repetition and feedback are essential and therefore patient education and an effective home program should be emphasized.

Nerve transfers

Historically, motor nerve transfers were used as a salvage procedure when nerve repair or graft was not possible, such as in the case of an avulsion of the proximal nerve source, and there was limited potential for excellent outcome. However, the utilization of nerve transfers has increased, particularly with proximal peripheral nerve injuries, where recovery is limited due to the lengthy distance from the injury to target muscle fibers and prolonged time for reinnervation.^{79,80} Because a nerve transfer utilizes an innervation source closer to the target muscle, the distance and time for reinnervation are shorter and the results following these types of transfer have been very encouraging.^{81–88} However, optimal results

depend not only on the number of regenerating motor axons and reinnervation of muscle fibers but also on cortical plasticity, remapping, and functional integration. Previously established motor patterns and cortical maps are no longer relevant because a new proximal nerve source is used with a nerve transfer. Studies have evaluated cortical mapping following nerve transfers, muscle transfers, and toe-to-thumb transfers.^{76,77,89–91} Collectively, these studies have illustrated shifts in the motor cortex following transfers and the importance of effective relearning to optimize outcome. Therefore, rehabilitation programs after nerve transfer should include not only range-of-motion and strengthening exercises to regain muscle balance, but also motor re-education to promote normal movement patterns and appropriate cortical mapping.^{92,93}

Clinical tips

Retraining after motor nerve transfer

- Following nerve injury, rehabilitation should be directed not only to the distal motor and sensory recovery but also to cortical remapping and normal movement patterns.
- Immobilization for 7–10 days after nerve transfer.
- Initially contract muscle from the “donor” muscle to contract reinnervated recipient muscle.
- Utilize synergistic movement patterns and sensorimotor re-education.
- Be aware of antagonistic muscle co-contraction.
- Restore muscle balance.

With nerve transfers, there is alteration of the proximal nerve source, therefore muscle contraction is initially recruited with “contraction” of the muscle from the donor nerve because of the established motor pattern. The new recruitment pattern from the new proximal nerve source from the donor nerve has yet to be recognized. Even with evidence of muscle reinnervation, the newly innervated muscle may not contract with initiation of the intended action, but rather requires “contraction” of the muscle from the donor nerve. To facilitate relearning, contraction of the muscles on the uninjured contralateral side will provide cortical input of a normal movement. The relearning associated with nerve transfers is similar to relearning following tendon transfers. In general, relearning is more straightforward following a transfer (nerve, muscle, or tendon) when the donor is from a muscle with a synergistic action. While it is possible to relearn an action that is from a muscle with an antagonistic action (such as triceps-to-biceps muscle transfer), the relearning is more difficult compared to a synergistic muscle action.

In patients with brachial plexus avulsion injuries, an intercostal-to-musculocutaneous nerve transfer is often performed to restore elbow flexion.⁹⁴ Postoperative education often includes deep-breathing exercises to provide a stimulus to the intercostal nerves for contraction of the biceps and brachialis muscles, which are innervated via the musculocutaneous nerve. While deep breathing does initiate contraction of the newly innervated elbow flexors, it is difficult to provide a prolonged contraction for re-education and strengthening. The abdominal muscles and intercostal muscles are activated with core abdominal exercises. Therefore core-strengthening exercises will also provide contraction of the biceps and

brachialis muscles in patients who have had an intercostal-to-musculocutaneous nerve transfer. The muscle activity in the elbow flexors associated with trunk flexion has been shown by Chalidapong and colleagues.⁹⁵ Core exercises which use the abdominal and intercostal muscles may begin early in the rehabilitation stages (Fig. 39.2) and with early reinnervation will recruit the muscle fibers in the brachialis and biceps.

More recent descriptions of nerve transfers to restore elbow flexion have included donor pectoral nerves and fascicles from the median and ulnar nerves.^{83,88} To assist with the retraining following these types of nerve transfer, re-education may begin preoperatively with education on the unaffected extremity and contraction of the muscles from the donor nerve and recipient muscle. In this way, the patient may practice co-contraction of these muscle groups to understand better the re-education that will be required with reinnervation of the denervated muscles. For a medial pectoral-to-musculocutaneous nerve transfer, the patient will simultaneously contract the pectoral and the biceps (and brachialis if included) muscles (Fig. 39.3). This is initially done bilaterally and then only to the injured side. Using place-and-hold positioning in 90° of elbow flexion, an isometric contraction is performed. Once the patient is able to hold this contraction against gravity, the degree of flexion may be altered and progressed through a full range of motion. A double fascicular transfer from the median and ulnar nerves to restore elbow flexion will require contraction of the wrist flexors to initiate contraction of the biceps and brachialis muscles (Fig. 39.4).

To restore innervation to the ulnar nerve intrinsic muscles, an anterior interosseous nerve (AIN) to deep motor branch of the ulnar nerve transfer may be performed.⁸⁴ With an AIN to deep motor branch of the ulnar nerve transfer, attempts by the patient to pinch must be initially combined with forearm pronation to recruit the newly innervated intrinsic muscles from the AIN proximal source (Fig. 39.5). With evidence of ulnar innervated actions, fine dexterity exercises and tasks can be incorporated into the rehabilitation program and the



Fig. 39.2 Following an intercostal-to-musculocutaneous nerve transfer, the patient is performing an abdominal crunch to initiate contraction of the intercostal muscles and thus initiate contraction of the biceps and brachialis muscles. (Courtesy of Susan E. Mackinnon, MD.)




Fig. 39.3 To facilitate understanding and relearning following a motor nerve transfer, re-education begins with a muscle contraction on the unaffected side.

(A) With a medial pectoral-to-musculocutaneous nerve transfer, the patient begins on the unaffected side with contraction of the pectoralis major muscle and (B) then contraction of both the pectoralis major and the biceps muscle. (C) This is followed by simultaneous contraction of the pectoralis major muscle on the affected side, (D) followed by bilateral contraction of these muscles. (E) The contraction is then isolated to the affected side and (F) finally dissociation of the donor muscle from the target muscle.

patient will be able to complete the ulnar motor nerve actions independent of the action of forearm pronation. A comprehensive motor retraining program combined with cortical remapping, and relearned motor patterns will provide the opportunity for optimal outcomes after nerve transfer.

As outlined previously in this chapter, the evidence in the literature does not support the efficacy of direct current electrical stimulation with denervated muscles. With evidence of muscle reinnervation, some have advocated the use of electrical muscle stimulation using an alternating current to increase the force of the muscle contraction and thereby increase muscle strength. Theoretically, with an innervated muscle, it is possible to use an alternating current to elicit a muscle contraction. However, with a reinnervated muscle, there may be scarcity of reinnervated fibers to produce the intended muscle contraction via electrical stimulation. Passive muscle contraction will not assist in the relearning of motor patterns. Therefore, it is our recommendation that these types of modalities should not be considered as the primary treatment but may be used as an adjunct to therapy as a “sensory stimulus” for relearning if necessary.

Functional relearning may be facilitated with visual or auditory feedback, which can provide immediate response to the patient regarding the muscle contraction. Simple biofeedback units with external surface electrodes may be used to facilitate muscle contraction or to minimize aberrant co-contraction of an antagonistic muscle action. Using a two-channel or four-channel biofeedback unit, the electrodes may




Fig. 39.4 The relearning associated with a partial ulnar and median nerve transfer from the forearm to the elbow flexors is illustrated. Initially, simple grip-strengthening exercises and/or gentle wrist flexion will initiate contraction of the biceps and brachialis muscles. **(A)** The patient begins on the unaffected side with a contraction of the forearm flexors and **(B)** then simultaneously contracts biceps/brachialis muscles and the forearm flexors. **(C,D)** The next step is bilateral contraction of these muscles and **(E)** then the exercise is isolated to the affected side. **(F)** The final exercise is to dissociate contraction of the donor muscle from the target muscle.

be placed on the appropriate muscles to increase or decrease muscle contraction. To facilitate relearning, the action should be performed on the unaffected side first to allow the patient to understand the strategies necessary to enhance or minimize the intended action. It is also useful to perform these actions simultaneously with the affected and unaffected extremity. This will provide immediate feedback on the “normal” contraction and motor pattern and provide the opportunity for

the patient to reproduce the action in the newly reinnervated muscles. With adequate muscle reinnervation, the patient will receive feedback by observing and “feeling” the muscle contraction. Specific exercises to promote muscle contraction without a specific biofeedback unit will allow the patient to perform the exercises more frequently as a home program.

Muscle physiology and biomechanics should be considered when structuring rehabilitation programs following nerve repair or transfer. Because of the weakness and associated fatigue in newly reinnervated muscle, exercise sessions should be of short duration. A slow-onset contraction with a longer duration hold of 10–15 s is recommended to increase muscle endurance and strength. To minimize the muscle forces required initially, muscle contraction in mid-range is suggested. Place-and-hold exercises or gravity-eliminated positions may be used and then progressed to different degrees of motion as the patient is able to sustain a muscle contraction. With MRC grade 3 strength, progressive resistance exercises can be implemented. The focus of strengthening is to regain muscle balance. Because of the relative weakness between the uninjured and reinnervated muscles, it is important to regain good motor control of the reinnervated muscles before resistance exercises are instituted, otherwise learned compensatory motor patterns will be maintained.

Upper extremity movement requires composite motor patterns involving the glenohumeral and scapular muscles.^{51,54} While distal nerve injuries may not include the shoulder complex, strength of uninjured upper extremity muscles may be weakened from disuse or from compensatory movement patterns. Similarly, brachial plexus nerve injuries may not include direct injury to the scapular muscles; however, these muscles (such as the middle and lower trapezius and serratus anterior muscles) may be weak from disuse and thus compromise upper extremity function. Assessment of muscle strength and length in the cervicospinal region should be performed, and then a rehabilitation program to address these muscle imbalances implemented to optimize outcome.

Rehabilitation programs following nerve injury and nerve compression surgery must include sensorimotor re-education and the inclusion of normal movement patterns for appropriate cortical remapping. Bimanual tasks will encourage use of the injured extremity and input normal movement patterns and purposeful movements involving self-care, recreation, and work will facilitate the resumption of normal activities. In some cases, vocational rehabilitation will be necessary to assist in future planning and employment opportunities. Patient education and an effective home program are necessary to optimize learning of new motor/sensory tasks and to optimize outcome.

Rehabilitation following tendon injury/surgery

Flexor tendon injuries

Surgical and rehabilitative approaches following flexor tendon injury can be described as one of the most researched, controversial, and clinically complex aspects of hand therapy. While originally eschewed as excessively progressive or risky by many surgeons, active motion regimens are becoming more



Fig. 39.5 With an anterior interosseus nerve to deep motor branch of the ulnar nerve transfer, forearm pronation is combined with pinching to recruit the innervated intrinsic muscles and facilitate relearning. (Courtesy of Christine B. Novak, PT, PhD.)

common in both research and clinical practice. Three primary factors have emerged as crucial in informing postoperative decision-making: (1) early initiation of rehabilitation; (2) the impact of wrist position on excursion and force; and (3) the use of controlled active motion to create safe and effective tendon glide.

Clinical tips

Rehabilitation after flexor tendon injury and repair

- Specificity and timing of exercise following flexor tendon repair can be optimally arranged to facilitate high-excision/low-force rehabilitation.
- Communication of the operative details between the therapist and plastic surgeon is essential to guide initiation and progression of exercise following flexor tendon repair.
- Early controlled motion should be initiated on the fourth or fifth postoperative day when work of flexion is likely decreased.
- Edema should be considered an objective means by which to inform therapeutic progression including range, frequency, and speed of exercise.
- Place-and-hold measurement is a safe and effective way to monitor tendon glide, progress treatment, and measure outcomes.
- Synergistic motion facilitates excursion while decreasing force.
- Tendon excursion occurs in both proximal and distal directions, and can be influenced both by type of exercise and antagonistic musculature.

The timing of rehabilitation following flexor tendon repair can readily be identified as a topic of historical and continued controversy. The study of tendon healing over time has demonstrated that early controlled motion is beneficial to tendon healing and preferable to immobilization.⁹⁶⁻⁹⁸ The timing of early motion following flexor tendon repair continues to be researched; however, some consistency is evident. Postoperative day 4–5 is suggested as a time during which work of flexion is decreased and preferable for the initiation of rehabilitation.⁹⁹⁻¹⁰¹

Edema is a postoperative symptom that often impedes the initiation of rehabilitation. Current research specific to edema and the flexor tendon system has identified numerous factors that can be effectively modulated by therapists in order to begin rehabilitation.^{100,102,103} In a series of studies by Cao and colleagues, their results indicated that the area and severity of edema following flexor tendon repair increased both gliding resistance and work of flexion.^{100,102,103} However, slow and gentle motion decreased the work of flexion. Decreasing both the arc of motion and frequency of exercise were methods to safely begin motion in the presence of edema. Conversely, recent literature has identified an intervention that should not be utilized when faced with edema after flexor tendon repair. While many therapists use self-adherent wrap as a postoperative dressing and for edema management, leaving this wrap in place during active motion significantly increases the work of flexion.¹⁰⁴ In summary, gentle and controlled motion at a lower frequency is suggested for patients with edema with




Fig. 39.6 Synergistic motion can be safely and effectively initiated with a hinged, dorsal blocking splint that allows the patient to create wrist extension prior to flexing the digits.

the caveat that any compressive dressings should be removed prior to exercise.

The position of the wrist in the postoperative orthosis can also create a potential limitation for therapeutic intervention. The impact of wrist positioning has been comprehensively studied as it pertains to force and excursion of the flexor tendon system.¹⁰⁵⁻¹⁰⁸ The position of metacarpophalangeal (MP) flexion coupled with wrist extension has been suggested to produce the least passive tension in the extensor tendons, thereby decreasing the minimal active tension of the flexor tendons.¹⁰⁷ Synergistic motion has also been observed to create the greatest amount of flexor digitorum superficialis, flexor digitorum profundus, and differential excursion,¹⁰⁵ serve as an effective pulling force to create proximal glide,¹⁰⁸ and result in low force with high excursion.^{109,110} Synergistic motion can be safely and effectively initiated with a hinged, dorsal blocking splint that allows the patient to create wrist extension prior to flexing the digits (Fig. 39.6). The literature indicates that asking patients to perform digit flexion when the wrist is flexed actually demands more force than the same motion performed with the wrist extended.

Prior to 2005, the most commonly used postoperative protocols maintained the wrist in a flexed position both during and between exercise for the first 6 weeks following repair.¹¹¹⁻¹¹³ More recent flexor tendon rehabilitation regimens have been built with consideration of the wrist and have progressed to varying levels of active motion. The Mass Protocol¹¹⁴ includes immediate postoperative positioning of the wrist in 20° of extension paired with active digital flexion through the “available range”. Comparatively, the Nantong Protocol¹¹⁵ reverts back to a conservative wrist-flexed position for the first 2½ weeks while the patient focuses on full extension to the dorsal block. Despite the inherent risks, this protocol does suggest completion of active motion through the first two-thirds of full range. The Saint John Protocol¹¹⁶ affords a similar approach, modifying the wrist to an extended position and the active motion to mid-range.

The most current and progressive approach to postoperative immobilization is the Manchester Short Splint.¹¹⁷ This protocol includes a hand-based, dorsal blocking orthosis that allows wrist extension up to 45° (Fig. 39.7A,B). On the fourth or fifth postoperative day, active motion of the digits within the first third of the range is paired with active wrist extension; the patient is instructed to focus on initiation of distal




Fig. 39.7 (A,B) A hand-based, dorsal blocking orthosis allows wrist extension up to 45°.

interphalangeal (DIP) joint motion to maximize differential tendon glide. In an comparative outcome study, patients ($n = 40$) who completed rehabilitation with the Manchester Short Splint demonstrated significantly less flexion contractures at the proximal interphalangeal (PIP) joint at 6 and 12 weeks, had significantly greater arcs of flexion at the DIP joint, and had a greater proportion of excellent and good results compared to patients ($n = 62$) treated with forearm-based orthoses.¹¹⁷ As all of the protocols presented here have been published within the past 10 years, it will be interesting to observe their integration into clinical practice.

Once the initial rehabilitative choices have been made, the progression of therapeutic exercise requires careful consideration as it pertains to the force exerted and consequential excursion of the tendon relative to adjacent structures. Studies have suggested that postoperative exercise should create the least possible force to achieve tendon excursion that will deter peri-tendinous adhesions.^{99–101} From a rehabilitative perspective, it is important to recognize that tendon excursion occurs in both proximal and distal directions, and can be influenced by both types of exercise and antagonistic musculature.^{110,118,119} A working knowledge of the force and excursion produced by specific exercises facilitates clinical progression following tendon repair (Table 39.1).^{120,121}

The use of straight fist, hook fist, composite fist, and isolated joint exercises is suggested as a sequential regimen for controlled force once synergistic motion has been initiated (Fig. 39.8). Consistent communication between the therapist and plastic surgeon is essential to both initiation and progression of exercise for the patient following flexor tendon repair, beginning with a detailed operative report outlining the number of strands crossing the repair site and perceived integrity of the repair.

Extensor tendon injuries

Care of the patient following an extensor tendon injury is a far less complicated pursuit compared to flexor tendon injury. Use

of standard protocols based on the anatomy and biomechanics of the extensor apparatus has led to consistent and favorable results throughout all zones of the extensor musculature.

Clinical tips

Rehabilitation after extensor tendon injury

- For a mallet finger, non-operative treatment includes continuous immobilization of the DIP joint in full extension for 6 weeks.
- For a boutonnière deformity, non-operative management includes PIP joint at 0° extension for 6–8 weeks and following surgical management, a short arc motion protocol may be initiated within 48 h.
- With zone VI–VII injuries, attention to anatomic specificity is very important and isolation of specific musculature to produce joint extension. Edema must be managed immediately to avoid tendon adhesions. A passively mobile joint with an active extensor lag is best managed via active tendon gliding in both proximal and distal directions.

Table 39.1 Analysis of tendon excursion and force

Exercise	Excursion	Force
Passive protected extension	3–8 mm Distal Duran and Houser ¹¹¹	200–300 g Urbaniak <i>et al.</i> ¹¹⁹
Place-and-hold digital flexion during wrist extension	FDS 26 mm FDP 33 mm Proximal Wehbe and Hunter ¹²⁰	900 g Lieber <i>et al.</i> ¹¹⁰
Active straight fist	Wrist neutral FDS 28 mm FDP 27 mm Maximum FDS Proximal Wehbe and Hunter ¹²⁰	1100 g Greenwald <i>et al.</i> ¹²¹
Active hook fist	Wrist neutral FDS 13 mm FDP 24 mm Maximum differential Proximal Wehbe and Hunter ¹²⁰	1300 g Greenwald <i>et al.</i> ¹²¹
Active composite fist	Wrist neutral–extension FDS 24–26 mm FDP 32–33 mm Maximum FDP Proximal Wehbe and Hunter ¹²⁰	400–4000 g Schuind <i>et al.</i> ¹¹⁸
Active, isolated PIP flexion	~13 mm (calculated) FDP Proximal	900 g Schuind <i>et al.</i> ¹¹⁸
Active, isolated DIP flexion	~6.5 mm (calculated) FDP Proximal	1900 g Schuind <i>et al.</i> ¹¹⁸

FDS, Flexor digitorum superficialis; FDP, flexor digitorum profundus; PIP, proximal interphalangeal; DIP, distal interphalangeal.




Fig. 39.8 The sequential use of (A) straight fist, (B) hook fist, (C) composite fist, and (D,E) isolated joint exercises are suggested as a means of consciously progressing forces on the healing flexor tendon.

A zone I injury is commonly referred to as “mallet finger”. Upon clinical examination, patients demonstrate an inability to actively extend the DIP joint due to detachment of the terminal extensor tendon from the distal phalanx. A mallet finger is characterized by varying degrees of flexion at the DIP joint. Non-operative treatment for a mallet finger includes continuous immobilization of the DIP joint in full extension for 6 weeks (Fig. 39.9). The PIP joint is mobilized during this timeframe as a means of maintaining proper alignment of the lateral bands and balance of the flexor and extensor tendons. Fabrication or issuance of two orthoses is suggested to minimize maceration of tissues and facilitate skin integrity during daily hygiene activities. After 6 weeks, the therapist initiates a gradual orthosis-weaning process and the patient begins gentle, composite flexion exercises. The patient is also



Fig. 39.9 An injury to the extensor tendon in zone I, commonly termed mallet finger, is most often treated conservatively with distal interphalangeal extension immobilization at all times for 6 weeks. (Courtesy of Rebecca Neiduski, PhD, OTR/L, CHT.)

educated on the avoidance of isolated joint motion that can unnecessarily stress the terminal tendon. Lateral tracing of the digit for daily comparison serves as an effective visual aid to monitor for development of an extensor lag during the orthosis-weaning process. If an extensor lag develops at any time during this process, support in extension is resumed and flexion exercises are decreased or discontinued.

Loss of integrity of the central slip in zone III is termed a boutonnière deformity. As the lateral bands sublux volarly, flexion of the PIP joint is unopposed. Flexion contractures are common sequelae of this condition and avoidance of this difficult complication must be pursued early in the treatment process. In addition, extensor forces are transmitted to the DIP joint, resulting in hyperextension of the DIP joint. Differential diagnosis of a pseudoboutonnière from a true boutonnière is an important component of the evaluative process. In the former, the DIP joint remains passively flexible, whereas in the latter, the DIP joint cannot be passively flexed. Non-operative management of the boutonnière deformity includes continual use of an orthosis or cast that positions the PIP joint at 0° extension for 6–8 weeks. The DIP and MP joints do not need to be included in the orthosis or cast, if the therapist is successfully able to maintain the PIP joint at 0° extension, which is often difficult. The orthosis is continued between exercises until the tenth week following injury.

A short arc motion protocol may be initiated within 48 h of surgical correction of a boutonnière deformity, as suggested by Evans.¹²² A template is fabricated that allows 30° of PIP and 20° of DIP joint flexion. The patient is instructed to produce finger flexion to the template and active extension to 0°. This exercise is completed 10–20 times every 1–2 h with the wrist held in 30° flexion and the MP joints between 0° extension and slight flexion. The template is adjusted to 40° of flexion after the second week if there is no active extensor lag. It is then progressed to 50° by the third postoperative week and up to 70–80° by the end of the fourth week. The finger is immobilized in full extension between exercises and an exercise orthosis to facilitate isolated DIP flexion is also fabricated.

Injuries in zones V–VII may occur with open (such as lacerations) or closed (such as blunt trauma) mechanisms of injury. Disturbance of the sagittal bands often leads to long extensor tendon subluxation with resultant MP extensor lag. Following surgical repair, multiple protocols are considered effective for treating extensor tendon injuries in these zones.

The most conservative protocol includes immobilizing the wrist in 40–45° extension and the MP joints in 0–20° flexion. A volar interphalangeal extension orthosis is fabricated to support the joints in full extension between exercises and at night as a means of preventing both flexion contractures and an extensor lag. Treatment of edema and scar is critical in this zone as adhesions are likely and will limit both proximal and distal glide of the extensor tendons. Exercises begin at 3–4 weeks postoperatively and include a wrist tenodesis exercise with active MP flexion and extension as well as continued interphalangeal active motion.

In zone VI–VII injuries, Evans and Burkhalter suggested a dorsal dynamic extension assist orthosis to allow 30° active MP flexion and returns the digits to 0° extension via dynamic traction.¹²³ The early distal glide allowed by this orthosis makes it an excellent choice for patients who can manage a more intricate orthosis design. Individual PIP extension gutters are added for those patients who demonstrate




Fig. 39.10 The immediate controlled active motion protocol, as described by Howell *et al.*,¹²⁴ includes a wrist cock-up orthosis and a yoke orthosis, which effectively creates hyperextension of the affected digit relative to the other digits. (Courtesy of Rebecca Neiduski, PhD, OTR/L, CHT.)

extensor lags. Howell *et al.* suggest immediate controlled active motion (ICAM) for patients with repairs in these zones.¹²⁴ This protocol includes three phases, the first of which can be initiated between 0 and 21 days after surgery. The wrist is immobilized in 20–25° extension, while the MP joint of the affected digit is positioned with a “yoke” orthosis in 15–20° of hyperextension relative to the other digits (Fig. 39.10). Both orthoses are to be worn at all times and the patient must achieve full active motion within the ICAM orthosis before progressing to the next phase. Phase 2 begins 22–35 days after repair, during which the yoke orthosis is worn at all times and both the yoke and wrist orthoses are only worn for medium to heavy activities. The patient is instructed to relax the digits during wrist exercise. Phase 3 is initiated 36–49 days after repair and includes discontinuation of the wrist orthosis with the yoke orthosis or buddy taping continued during activities. The yoke orthosis is removed for active motion during the final phase.

Despite the seeming simplicity of extensor tendon as compared to flexor tendon rehabilitation, attention to anatomic specificity is very important as it pertains to final outcomes. Edema collects easily in the dorsal hand and must be managed immediately to avoid tendon adhesions. Attention to both active and passive motion at all joints provides valuable information for the choice and progression of interventions. A passively mobile joint with an active extensor lag is best managed via active tendon gliding in both proximal and distal directions. Resistive exercises are an excellent method of restoring tendon glide after the eighth week. Perhaps the most important approach is the isolation of specific musculature to produce joint extension including the extensor digitorum communis for MP extension and the intrinsic musculature for interphalangeal extension.

Tenolysis

Following flexor and extensor tendon repairs, the likelihood of scar adhesions that limit active excursion is unfortunately high. While early motion coupled with continual evaluation and progression can modulate scar formation, confounding factors including overall health, medical comorbidities, pain, and compliance may negatively impact postoperative results. If progress has plateaued at the 3-month interval, patients are often evaluated as candidates for tenolysis.

Proper assessment of tendon gliding includes comprehensive measurement and comparison of active and passive range of motion at all joints of the affected digit(s). The optimal candidate for tenolysis is the patient who demonstrates full passive motion of the digit and is deemed compliant by the therapist and surgeon. As the postoperative treatment of tenolysis is both painful and time-intensive, thorough education of patient and family is vital to success. A therapy schedule for daily treatment during the first 7 days post-tenolysis, including weekend days, should be established preoperatively.

Direct communication between the surgeon and the hand therapist regarding the integrity of the tendon and active motion as accomplished during surgery should be a priority and postoperative treatment should begin on the same day as surgery. It is advisable to allow the patient multiple hours of recovery time, including a full meal and initiation of pain medication if possible to decrease the likelihood of adverse reactions (i.e., fainting) if treatment is promptly initiated. Use of a sterile field and gloves is important to minimize the likelihood of infection as the therapist initiates hourly active exercises to facilitate tendon glide. Edema management and wound care are also carefully addressed as the therapist attempts to find a balance between adequate dressings for drainage absorption that provide minimal physical blockage to active motion. Consistent measurement of active and passive motion is pursued during the first 7 consecutive days of treatment.

Therapy intensity can decrease after the first week for patients who demonstrate compliance with hourly exercise and the ability to complete wound care independently. The outcomes of tenolysis are quickly recognized and difficult to remediate after the first 3–4 weeks of treatment. For this reason, communication between the surgeon and hand therapist and careful selection of patients for this procedure are perhaps the most influential factors influencing final outcome.

Tendon transfers

Rehabilitation following tendon transfers requires careful communication between the plastic surgeon and hand therapist and attention to detail. This detail not only includes surgical specificity but the unique needs and expectations of the patient coupled with a neuromuscular intervention plan. For the purposes of brevity, the example of a pronator teres (PT) to extensor carpi radialis brevis (ECRB) tendon transfer, as performed in cases of radial nerve injury, will be used throughout this section as a case example.

Patient education should include the purpose of the surgical procedure, expected timeline for rehabilitation, possible complications, and expected outcomes.¹²⁵ The patient needs to be informed that functional use will be altered following surgery and that a tendon transfer procedure will not correct for losses in sensation.¹²⁶ Prior to surgery, efforts are instituted to strengthen the donor muscle selected for the procedure.¹²⁵ If the patient has difficulty isolating the donor muscle, bio-feedback and exercise orthosis may be useful.¹²⁵

Immediately following surgery, the transfer and all involved joints are immobilized in a position to minimize tension on the newly transferred tendon. An immobilization period of 3–4 weeks is commonly implemented to allow adequate healing and reduce the risk of tendon rupture upon



Fig. 39.11 The patient with a pronator teres to extensor carpi radialis brevis tendon transfer is immobilized in 45° of wrist extension for 3–4 weeks following surgery. (Courtesy of Rebecca Neiduski, PhD, OTR/L, CHT.)

mobilization of the transfer.¹²⁶ During this period, the postoperative dressing is removed and the patient is immobilized in a thermoplastic orthosis. In the case of a PT-to-ECRB transfer, the patient is immobilized in a wrist cock-up orthosis at 45° extension (Fig. 39.11). For those cases in which coaptation of the muscles are considered tenuous, an orthosis that limits forearm rotation while positioning the wrist in extension can be fabricated. During this period, the therapist's focus is centered on the evaluation and treatment of edema, pain, and infection.

In the absence of complications during the immobilization phase, initiation of active motion typically occurs 3–4 weeks postoperatively.^{125,126} The therapist initiates neuromuscular re-education exercises, including isolation and activation of the transfer to produce a desired motion. Central to this process is the concept of cortical plasticity, or the capacity of a cortical circuit to reorganize its structure or response subsequent to an experience.¹²⁷ As suggested by Sanes and Donoghue, the primary motor cortex exhibits such plasticity as a result of repetition of simple movements.¹²⁷ Combination exercises are frequently incorporated to facilitate re-education of a donor muscle, and include training the patient to produce the primary movement of a denervated muscle utilizing a new musculotendinous unit. A PT-to-ECRB tendon transfer is performed to restore wrist extension, the patient is instructed to pronate the forearm while simultaneously extending the wrist. Proprioceptive feedback is preferable to visual as it facilitates cortical reorganization and auditory feedback can also be helpful.

The length of time it takes to isolate a transfer effectively is highly variable, depending on the type of transfer and specific patient factors. Isometric activation can be carefully initiated with those patients who find combination exercises difficult. In the case of a PT-to-ECRB transfer, gentle resistance is provided to the wrist while the patient is producing pronation with wrist extension. As the patient progresses, the goal is isolated activation of the donor muscle in production of the newly desired motion, in this case, wrist extension against gravity without simultaneous pronation.

At 6–7 weeks post-surgery, the tendon has healed and is able to tolerate functional activities and light resistance. Passive range-of-motion exercises may also be initiated to mitigate any residual tightness incurred during surgery or the immobilization period.¹²⁵ At 8 weeks post-surgery, progressive resistance exercises may be incorporated into the exercise regimen.¹²⁵

Rehabilitation following skeletal injury/surgery

Proximal phalanx fractures are challenging and require careful attention to bony integrity and maintenance of the flexor and extensor tendon-gliding systems. Therapeutic interventions as outlined in this section are based on the assumption that a patient presents with one of the following: a potentially unstable, yet non-displaced, extra-articular fracture; an inherently stable fracture; or hardware fixation facilitating stability such as an open-reduction internal fixation or closed-reduction external fixation.

According to Feehan, structural strength following a proximal phalanx fracture is influenced by location, pattern and displacement, type of reduction, hardware, concomitant soft-tissue injuries, stage of healing, and the functional demands of the patient.¹²⁸ Initiation of early controlled mobilization is based on the surgeon's perception of structural strength and can be altered by choosing the number of joints to be mobilized, active and/or passive motion, a safe arc of motion, and the duration or repetitions of motion.¹²⁸ Isolating short arc motion at one or more joints when possible provides tendon glide and lengthening of connective tissue structures that will positively facilitate final outcomes for patients following proximal phalanx fracture. As the flexor digitorum profundus lies in close proximity to the proximal phalanx, isolated DIP motion should be initiated as soon as possible. Moving the joint actively through flexion and extension will also afford some proximal and distal excursion of the extensor mechanism.

Following a proximal phalanx fracture, MP joint positioning and PIP joint mobilization have been studied as a means of avoiding complications. MP joint flexion is the close-packed position of the joint, or the position at which the joint space is minimized, and the joint surfaces of the head of the metacarpal and the base of the proximal phalanx are maximally congruent. In addition, MP joint flexion moves the extensor hood distally, translates the force of the extensor digitorum to the PIP joint, and creates circumferential compression on the fracture.¹²⁹ From a volar perspective, flexion also decreases the proximity of the flexor tendons to the fracture site. PIP joint range of motion has been suggested to maintain the length of the joint capsule and increase soft-tissue gliding as well as creating a dynamic tension band effect in conjunction with the extensor digitorum to facilitate fracture reduction.^{130,131} According to Feehan, the functional and physiologic stresses associated with early controlled mobilization increase the quality and rate of bone healing.¹²⁸

Complications following proximal phalanx fractures are often sequelae of scar tissue that limits all structures in the zone of injury. Typical issues include extensor mechanism adherence and fracture deformity with resultant PIP joint extensor lags.^{129,132} In a study by Kurzen *et al.*, 52% of patients demonstrated less than 180° of total active motion following plate fixation of a proximal phalanx fracture.¹³³ To avoid such outcomes, LaStayo *et al.* recommend a progressive program be initiated in the following order: protection or external support, edema management, protected and controlled mobilization of proximal and distal joints, tendon gliding, passive range of motion, and strengthening.¹³¹ The external support,

typically a custom-fabricated orthosis, can either be hand- or forearm-based and dorsally blocks the MP joints in flexion^{129,134} (Fig. 39.12).

Metacarpal fractures

Metacarpal fractures are commonly seen primarily in the fourth and fifth metacarpal and often in adolescent males. From an anatomic perspective, consideration of both the metacarpals and their adjacent tendinous and connective tissue structures directs clinical decision-making. The second through fifth metacarpals are aligned as parallel long bones and serve both mobility and stability functions for the digits. The proximal bases of the second and third metacarpal are firmly affixed to the distal carpal row, more specifically, the trapezoid and capitate. More mobile carpometacarpal (CMC) joints at the thumb and small finger surround this stable center, while the fourth metacarpal demonstrates limited mobility on the hamate. Distally, the deep transverse metacarpal ligament connects the heads of the second through fifth metacarpals. The alignment of the distal carpal row, reinforced by this ligament, creates the transverse arches of the hand that contribute to grasp and function.

According to McNemar *et al.*, metacarpal head fractures are immobilized in the position of safety, with the wrist extended, MP joints fully flexed, and PIP and DIP joints extended, in either a cast or a custom-fabricated orthosis¹³⁵ (Fig. 39.13). This close-packed positioning maintains the length of the collateral ligaments, counteracts the tendency towards a claw deformity, and draws the extensor mechanism distally to support the fracture.¹³⁵ For those cases requiring open reduction and internal fixation through an incision of the extensor mechanism, early motion becomes a necessity to avoid tendon adherence.

The more typical metacarpal neck fracture often occurs in the fourth or fifth metacarpal and is typically seen in young males who have been involved in an altercation. A more conservative approach to this injury includes immobilization of the wrist in extension and the MP joints in flexion, with early mobilization of the PIP and DIP.¹³⁵ For those fractures that are minimally displaced with reasonable stability, a less



Fig. 39.12 Following a proximal phalanx fracture, immobilization of the metacarpophalangeal joint in flexion facilitates close-packed positioning, creates circumferential pressure via the extensor mechanism, and decreases the proximity of the flexor tendons to the fracture site. Allowance of proximal interphalangeal joint motion increases the opportunity for differential tendon gliding along the fracture site. (Courtesy of Rebecca Neiduski, PhD, OTR/L, CHT.)



Fig. 39.13 Fractures to the metacarpal head are immobilized with an orthosis or cast in wrist extension, metacarpophalangeal joint flexion, and interphalangeal joint extension. (Courtesy of Rebecca Neiduski, PhD, OTR/L, CHT.)

restrictive regimen of immobilization and exercise can be initiated. A cuff orthosis that creates circumferential pressure around the hand and approximates the metacarpals towards anatomical alignment is fabricated to allow unrestricted motion of the wrist and MP joints (Fig. 39.14). For additional distal alignment, the proximal phalanx of the affected metacarpal can be taped or strapped to the adjacent digit with which it is optimally aligned lengthwise. Using this approach, the patient is encouraged to perform active exercise while avoiding sustained or forceful grasp during the healing phase.

Complications after metacarpal fractures include rotational deformities, loss of length, and dense adhesions restricting tendon glide of the extrinsic extensor tendons. Rotational deformities lead to scissoring of the digits during active



Fig. 39.14 Metacarpal neck and shaft fractures that are minimally displaced can be immobilized using a simple cuff which approximates the metacarpals and creates circumferential pressure. (Courtesy of Rebecca Neiduski, PhD, OTR/L, CHT.)

flexion, while metacarpal shortening can lead to active insufficiency of the extrinsic digit extensors and the possibility of decreased grip strength.¹³⁵ Extensor adherence can be avoided with early motion protocols emphasizing isolated glide of the long extensors. Composite extension of the digit will not achieve this goal; rather, the patient is instructed in transition from a full fist to a hook fist, which creates maximal, isolated glide of the extensor digitorum communis. These exercises are of increased importance following open reduction and internal fixation of metacarpal head, neck, and shaft fractures.

Thumb carpometacarpal osteoarthritis

Osteoarthritis of the first CMC joint is an extremely common diagnosis addressed by the plastic surgeon and hand therapist, most often observed in women of middle age. This diagnosis is the subject of much debate, ranging from anatomy to interventions.

The typical presentation of a patient with CMC osteoarthritis includes marked adduction of the first CMC joint with hyperextension of the MP joint. This positioning is influenced by numerous musculoskeletal imbalances that are presumed to have both causative and resultant roles. Prolonged adduction of the joint leads to shortening of the adductor pollicis, active insufficiency of the abductor pollicis brevis and extensor pollicis brevis, and decreased stabilization by the first dorsal interossei. The extensor pollicis longus, having the greatest moment arm for MP extension, subsequently creates compensatory MP hyperextension to increase the first web-space for grasp and function. Offsetting this compensatory pattern via positioning of the MP joint in flexion has been noted to unload the palmar surfaces of the CMC joint, suggesting that the more distal MP joint may play a role in the progression of arthritis at the proximal CMC joint.¹³⁶

A recent systematic review of conservative interventions for osteoarthritis of the hand provides evidence for numerous interventions based on specific patient goals.¹³⁷ Moderate evidence was found to support heat, exercise, education on joint protection, and issuance of adaptive equipment as adjunctive methods for pain reduction and increased function. The use of orthoses to decrease pain and increase function was supported with high to moderate evidence. Numerous orthoses are available for conservative management of CMC osteoarthritis, both custom and prefabricated. Evidence to support the superiority of one orthosis design from a diagnostic perspective is lacking; however, studies have shown patient preferences towards prefabricated, hand-based orthoses¹³⁷ (Fig. 39.15). The work by Moulton *et al.* supports the inclusion of the MP joint in the orthosis, positioned in flexion as a means of unloading the volar surface of the CMC joint and decreasing forces on the anterior oblique ligament.¹³⁶

For patients with advanced stages of CMC osteoarthritis, or those who have failed non-operative management, surgical intervention is often recommended. Despite the numerous surgical methods for treatment of thumb CMC arthritis ranging from simple partial or complete trapeziectomy with or without ligament reconstruction tendon interposition, postoperative care is relatively straightforward. Emphasis during the rehabilitative phase is placed on the maintenance of stability of the newly reconstructed joint as a means of facilitating pain-free thumb function. The surgical procedure performed, patient factors, and surgeon preference will guide



Fig. 39.15 Patients with carpometacarpal osteoarthritis are often immobilized in a hand-based thumb spica orthosis to relieve pain and provide support and positioning to facilitate functional use. (Courtesy of Rebecca Neiduski, PhD, OTR/L, CHT.)

the postsurgical management and immobilization. Following trapeziectomy with ligament reconstruction tendon interposition, the patient is typically immobilized in a forearm-based thumb spica cast or orthosis for 4 weeks following surgery. The interphalangeal joint is left free to facilitate tendon gliding of the extensor pollicis longus and flexor pollicis longus across the surgical site. This early motion can also contribute to decreasing edema and hypersensitivity, two common sequelae of this procedure.

After 4 weeks, a program of active circumduction range of motion, scar management, and desensitization is initiated. Active range of motion of the CMC joint is pursued gently, mindful of the influence of proximal stability on distal mobility and overall function of the thumb. Close attention to the balance of musculature about the thumb is also important, especially as it pertains to the length of the adductor pollicis and activation of the extensor pollicis brevis and abductor pollicis longus. MP hyperextension should be carefully monitored; blocking the interphalangeal joint of the thumb in slight flexion during active exercise is often effective in controlling the mechanical advantage of the extensor pollicis longus. Scar adhesions and hypersensitivity are common complaints following this procedure and should be addressed with early and progressive massage and desensitization.

While gentle passive motion can be initiated at 6 weeks, continued use of the orthosis between exercise sessions and

at night is often continued until the eighth postoperative week. Strengthening should be avoided until pain is no longer a primary complaint, and pursued only within the realm of the function required on an individual basis.

Future directions

Advancements in the understanding of response to injury, wound healing, and other innovations in hand surgery have guided the advancements in hand therapy. Recognition of cortical changes and neural plasticity has advanced our treatment following nerve injury, repair, and nerve transfers. Emphasis on sensorimotor control and methods to exploit the neural plasticity potential have led to improved outcomes following nerve reconstruction and nerve and tendon transfers. The concept of soft-tissue mobility and methods to improve mobility and minimize adherent scarring has changed our practice after soft-tissue and bony injuries to the hand. Many of the active motion protocols presented in this chapter have been published within the past 10 years. As these protocols become integrated into clinical practice and future studies report the long-term outcomes, we will be better able to build on these successes.

Conclusion

Key points

1. Optimal outcomes necessitate a collaborative relationship and open communication between the patient, surgeon, and hand therapist.
2. A comprehensive evaluation is necessary to provide diagnostic and prognostic information and to inform clinical decision-making for non-operative and postoperative management.
3. Following nerve injury, rehabilitation should be directed not only to the distal motor and sensory recovery but also to cortical remapping and normal movement patterns.
4. Specificity and timing of exercise following flexor tendon repair can be optimally arranged to facilitate high excursion/low force rehabilitation.
5. Early controlled mobilization can increase healing, tendon glide, and joint mobility in patients with extra-articular hand fractures.

Comprehensive evaluation and multidisciplinary treatment approaches are advocated for patients following hand surgery and optimal outcomes necessitate a collaborative relationship and open communication between the patient, surgeon, and hand therapist.



Access the complete reference list online at

<http://www.expertconsult.com>

32. Amadio PC. Outcome assessment in hand surgery and hand therapy: an update. *J Hand Ther.* 2001;14:63–68.
75. Ramachandran VS, Altschuler EL. The use of visual feedback, in particular mirror visual feedback, in restoring brain function. *Brain.* 2009;132:1693–1710.

92. Novak CB. Rehabilitation following motor nerve transfers. *Hand Clin.* 2008;24:417–423.
99. Amadio PC. Friction of the gliding surface: implications for tendon surgery and rehabilitation. *J Hand Ther.* 2005;18:112–119.

105. Cooney WP, Lin GT, An KN. Improved tendon excursion following flexor tendon repair. *J Hand Ther.* 1989;2:102–106. *In this cadaveric study, postoperative rehabilitation protocols were compared, including Kleinert, the Brooke Army Hospital modification, and synergistic motion. Synergistic motion yielded the greatest flexor digitorum profundus, flexor digitorum superficialis, and differential excursion.*
110. Lieber RL, Silva MJ, Amiel D, et al. Wrist and digital joint motion produce unique flexor tendon force and excursion in the canine forelimb. *J Biomech.* 1999;32:175–181. *This study using a canine model suggested that forces exerted on the healing flexor tendon are highly dependent on wrist position. Synergistic motion was noted to result in low passive forces on the flexor tendon with high excursion.*
124. Howell JW, Merritt WH, Robinson SJ. Immediate controlled active motion following zone 4–7 extensor tendon repair. *J Hand Ther.* 2005;18:182–190. *The protocol described for extensor tendon injuries includes a wrist orthosis paired with a yoke orthosis which positions the metacarpophalangeal joint of the affected digit in hyperextension relative to the other digits. Full active motion within the immediate controlled active motion orthosis is expected prior to progression to the next phase of the protocol.*
128. Feehan LM. Early controlled mobilization of potentially unstable extra-articular hand fractures. *J Hand Ther.* 2003;16:161–169. *This article suggests that functional and physiologic stresses associated with active range of motion increase the quality and rate of healing in potentially unstable extra-articular hand fractures. Control of clinical factors is recommended as a means of incorporating early motion into fracture management.*
136. Moulton MJ, Parentis MA, Kelly MJ, et al. Influence of metacarpal joint position on the basal joint loading in the thumb. *J Bone Joint Surg Am.* 2001;83:709–716. *In this cadaveric study, immobilization of the metacarpophalangeal joint was studied as it pertained to forces on the trapezial surface during lateral pinch. Metacarpophalangeal flexion was noted to unload the most palmar aspect of the carpometacarpal joint effectively, decreasing strain on the palmar oblique ligament.*

References

- World Health Organization. *ICF: International Classification of Functioning, Disability and Health*. Geneva: World Health Organization; 2001.
- Dodds RL, Nielson KA, Shirley AG, et al. Test-retest reliability of the commercial volumeter. *Work*. 2004;22:107-110.
- Adson AW. Surgical treatment for symptoms produced by cervical ribs and the scalenus anticus muscle. *Surg Gynecol Obstet*. 1947;85:687-700.
- Kelley MJ. Clinical evaluation of the shoulder. In: Mackin EJ, Callahan AD, Skirven TM, et al., eds. *Rehabilitation of the Hand and Upper Extremity*. St Louis, MO: Mosby; 2002:1311-1350.
- Roos DB. New concepts of thoracic outlet syndrome that explain etiology, symptoms, diagnosis and treatment. *Vasc Surg*. 1979;13:313-321.
- Jensen MP, Karoly P, Braver S. The measurement of clinical pain intensity. *Pain*. 1986;27:117-126.
- Grafton KV, Foster NE, Wright CC. Test-retest reliability of the short-form McGill Pain Questionnaire. *Clin J Pain*. 2005;21:73-82.
- Melzack R. The McGill Pain Questionnaire: major properties and scoring methods. *Pain*. 1975;1:277-299.
- Melzack R. The short-form McGill Pain Questionnaire. *Pain*. 1987;30:191-197.
- Melzack R, Katz J. Assessment of pain in adult patients. In: McMahon SB, Koltzenburg M, eds. *Wall & Melzack's Textbook of Pain*. New York, NY: Churchill Livingstone; 2006:291-304.
- Carter TI, Pansy B, Wolff AL, et al. Accuracy and reliability of three different techniques for manual goniometry of wrist motion: a cadaveric study. *J Hand Surg Am*. 2009;34:1422-1428.
- Ellis B, Bruton A. A study to compare the reliability of composite finger flexion with goniometry for measurement of range of motion in the hand. *Clin Rehabil*. 2002;16:562-570.
- Medical Research Council of the UK. *Aids to the Examination of the Peripheral Nervous System*. Palo Alto, CA: Pentagon House; 1976.
- Cuthbert SC, Goodheart GJ. On the reliability and validity of manual muscle testing: a literature review. *Chiropr Osteopat*. 2007;15:4-11.
- Bell-Krotoski JA. Light touch-deep pressure testing using Semmes-Weinstein monofilaments. In: Hunter JM, Schneider LH, Mackin EJ, et al., eds. *Rehabilitation of the Hand: Surgery & Therapy*. St. Louis, MO: The C.V. Mosby Company; 1990.
- Dellon AL. The moving two-point discrimination test: clinical evaluation of the quickly adapting fiber receptor system. *J Hand Surg Am*. 1978;3:474-481.
- Mackinnon SE, Dellon AL. Two-point discrimination tester. *J Hand Surg Am*. 1985;10:906-907.
- Moberg E. Objective methods of determining functional value of sensibility in the hand. *J Bone Joint Surg Br*. 1958;40:454-476.
- Novak CB, Mackinnon SE, Kelly L. Correlation of two-point discrimination and hand function following median nerve injury. *Ann Plast Surg*. 1993;31:495-498.
- Bell-Krotoski JA. Sensibility testing: current concepts. In: Hunter JM, Mackin EJ, Callahan AD, eds. *Rehabilitation of the Hand: Surgery & Therapy*. St. Louis, MO: C.V. Mosby Company; 1995:109-128.
- Novak CB, Mackinnon SE, Williams JJ, et al. Establishment of reliability in the evaluation of hand sensibility. *Plast Reconstr Surg*. 1993;92:311-322.
- Novak CB, Mackinnon SE. Evaluation of nerve injury and nerve compression in the upper quadrant. *J Hand Ther*. 2005;18:230-240.
- van Vliet D, Novak CB, Mackinnon SE. Duration of contact time alters cutaneous pressure threshold measurements. *Ann Plast Surg*. 1993;31:335-339.
- Strauch B, Lang A, Ferder M, et al. The ten test. *Plast Reconstr Surg*. 1997;99:1074-1078.
- Coldham F, Lewis J, Lee H. The reliability of one vs. three grip trials in symptomatic and asymptomatic subjects. *J Hand Ther*. 2006;19:318-326.
- Massy-Westropp N, Rankin W, Ahern M, et al. Measuring grip strength in normal adults: reference ranges and comparison of electronic and hydraulic instruments. *J Hand Surg Am*. 2004;29:514-519.
- Mathiowetz V, Weber K, Volland G, et al. Reliability and validity of grip and pinch strength evaluations. *J Hand Surg Am*. 1984;9:222-226.
- Mathiowetz V. Comparison of Rolyan and Jamar dynamometers for measuring grip strength. *Occup Ther Int*. 2002;9:201-209.
- Ruiz-Ruiz J, Mesa JLM, Gutierrez A, et al. Hand size influences optimal grip span in women but not in men. *J Hand Surg Am*. 2002;27:897-901.
- Ruiz JR, Espana-Romero V, Ortega FB, et al. Hand span influences optimal grip span in male and female teenagers. *J Hand Surg Am*. 2006;31:1367-1372.
- Watanabe T, Owashi K, Kanauchi Y, et al. The short-term reliability of grip strength measurement and the effects of posture and grip span. *J Hand Surg Am*. 2005;30:603-609.
- Amadio PC. Outcome assessment in hand surgery and hand therapy: an update. *J Hand Ther*. 2001;14:63-68.
- Amadio PC, Silverstein MD, Ilstrup DM, et al. Outcome assessment for carpal tunnel surgery: the relative responsiveness of generic, arthritis-specific, disease-specific and physical examination measures. *J Hand Surg Am*. 1996;21:338-346.
- Atroshi I, Gummesson C, Johnsson R, et al. Symptoms of disability and quality of life in patients with carpal tunnel syndrome. *J Hand Surg Am*. 1999;24:398-404.
- Katz JN, Gelberman RH, Wright EA, et al. Responsiveness of self-reported and objective measures of disease severity in carpal tunnel syndrome. *Med Care*. 1994;32:1127-1133.
- Koran LM. The reliability of clinical methods, data and judgments. *N Engl J Med*. 1975;293:642-646.
- Sprangers MAG, Aaronson NK. The role of health care providers and significant others in evaluating the quality of life of patients with chronic disease: a review. *J Clin Epidemiol*. 1992;45:743-760.
- Ripat J, Etcheverry E, Cooper J, et al. A comparison of the Canadian occupational performance measure and the health assessment questionnaire. *Can J Occup Ther*. 2001;68:247-253.
- Bellamy N, Campbell J, Haraoui B, et al. Dimensionality and clinical importance of pain and disability in hand osteoarthritis: development of the Australian/Canadian (AUSCAN) osteoarthritis hand index. *Osteoarthritis Cartil*. 2002;10:855-862.
- MacDermid JC. Outcome evaluation in patients with elbow pathology: issues in instrument development and evaluation. *J Hand Ther*. 2001;14:105-114.
- Hudak PL, Amadio PC, Bombardier C. Development of an upper extremity outcome measure: the DASH (disabilities of the arm, shoulder and hand). *Am J Ind Med*. 1996;29:602-608.
- Davis AM, Beaton DE, Hudak PL, et al. Measuring disability of the upper extremity: a rationale supporting the use of a regional outcome measure. *J Hand Ther*. 1999;12:269-274.
- Baltzer H, Novak CB, McCabe SJ. A scoping review of DASH scores for hand and wrist conditions. *J Hand Surg Am*. 2014;39:2472-2480.
- Franchignoni F, Giordana A, Sartorio F, et al. Suggestions for refinement of the Disabilities of the Arm, Shoulder and Hand outcome measure (DASH): a factor analysis and Rasch validation study. *Arch Phys Med Rehabil*. 2010;91:1370-1377.
- Huemer GM, Koller M, Pachinger T, et al. Postoperative splinting after open carpal tunnel release does not improve functional and neurological outcome. *Muscle Nerve*. 2007;36:528-531.
- Levis CM, Tung TH, Mackinnon SE. Variations in incisions and postoperative management in carpal tunnel surgery. *Can J Plast Surg*. 2002;10:63-67.
- Mackinnon SE, Novak CB. Compressive neuropathies. In: Wolfe SW, Hotchkiss RN, Pederson WC, et al., eds. *Green's Operative Hand Surgery*. Philadelphia, PA: Elsevier Churchill Livingstone; 2011:977-1014.

48. Shin EK, Bachoura A, Jacoby SM, et al. Treatment of carpal tunnel syndrome by members of the American Association for Hand Surgery. *Hand*. 2012;7:351–356.
49. Coppiters MW, Hough AD, Dilley A. Different nerve-gliding exercises induce different magnitudes of median nerve longitudinal excursion: an in vivo study using dynamic ultrasound imaging. *J Orthop Sports Phys Ther*. 2009;39:164–171.
50. Janda V. Muscles and motor control in cervicogenic disorders: assessment and management. In: Grant R, ed. *Clinics in Physical Therapy: Physical Therapy of the Cervical and Thoracic Spine*. New York, NY: Churchill Livingstone; 1995:153–166.
51. Kendall FP, McCreary EK, Provance PG. *Muscles: Testing and Function*. Baltimore, MD: Williams & Wilkins; 1993.
52. Novak CB. Conservative management of thoracic outlet syndrome. *Chest Surg Clin N Am*. 1999;9:747–760.
53. Novak CB. Work-related musculoskeletal disorders. *J Orthop Sports Phys Ther*. 2004;34:628–637.
54. Sahrmann SA. *Diagnosis and Treatment of Movement Impairment Syndromes*. St. Louis, MO: Mosby; 2002.
55. Clare TD, De Haviland Mee S, Belcher HJCR. Rehabilitation of digital nerve repair: is splinting necessary? *J Hand Surg [Br]*. 2004;29:552–556.
56. Novak CB, Katz J. Neuropathic pain in patients with upper extremity nerve injury. *Physiother Can*. 2010;62:190–201.
57. Novak CB, Anastakis DJ, Beaton DE, et al. Biomedical and psychosocial factors associated with disability after peripheral nerve injury. *J Hand Surg Am*. 2010;35:49–50.
58. Eberstein A, Eberstein S. Electrical stimulation of denervated muscle: is it worthwhile? *Med Sci Sports Exerc*. 1996;28:1463–1469.
59. Michlovitz SL. Is there a role for ultrasound and electrical stimulation following injury to tendon and nerve? *J Hand Ther*. 2005;18:292–296.
60. Williams HB. The value of continuous electrical muscle stimulation using a completely implantable system in the preservation of muscle function following motor nerve injury and repair: an experimental study. *Microsurgery*. 1996;17:589–596.
61. Williams HB. A clinical pilot study to assess functional return following continuous muscle stimulation after nerve injury and repair in the upper extremity using a completely implantable electrical system. *Microsurgery*. 1996;17:597–605.
62. Fu SY, Gordon T. Contributing factors to poor functional recovery after delayed nerve repair: prolonged denervation. *J Neurosci*. 1995;15:3886–3895.
63. Gordon T, Sulaiman OAR, Ladak A. Electrical stimulation for improving nerve regeneration: where do we stand? *Int Rev Neurobiol*. 2009;87:433–444.
64. Gordon T, Brushart TM, Amirjani N, et al. The potential of electrical stimulation to promote functional recovery after peripheral nerve injury – comparisons between rats and humans. *Acta Neurochir Suppl*. 2007;100:3–11.
65. Gordon T, Amirjani N, Edwards DC, et al. Brief post-surgical electrical stimulation accelerates axon regeneration and muscle reinnervation without affecting the functional measures in carpal tunnel syndrome patients. *Exp Neurol*. 2010;223:192–202.
66. Dellon AL. *Somatosensory Testing and Rehabilitation*. Baltimore, MD: Institute for Peripheral Nerve; 2000.
67. Imai H, Tajima T, Natsumi Y. Successful reeducation of functional sensibility after median nerve repair at the wrist. *J Hand Surg Am*. 1991;16:60–65.
68. Novak CB, Kelly L, Mackinnon SE. Sensory recovery after median nerve grafting. *J Hand Surg Am*. 1992;17:59–68.
69. Spicher CJ, Kohut G. Rapid relief of a painful, long-standing posttraumatic digital neuroma treated by transcutaneous vibratory stimulation (TVS). *J Hand Ther*. 1996;9:47–51.
70. Spicher CJ, Mathis F, Degrange B, et al. Static mechanical allodynia (SMA) is a paradoxical painful hypo-aesthesia: observations derived from neuropathic pain patients treated with somatosensory rehabilitation. *Somatosens Mot Res*. 2008;25:77–92.
71. Melzack R, Wall PD. Pain mechanisms: a new theory. *Science*. 1965;150:971–979.
72. Rosen B, Lundborg G. Sensory re-education following nerve repair. In: Slutsky DJ, ed. *Upper Extremity Nerve Repair – Tips and Techniques: A Master Skills Publication*. Rosemont, IL: American Society for Surgery of the Hand; 2008:159–178.
73. Rosen B, Vikstrom P, Turner S, et al. Enhanced early sensory outcome after nerve repair as a result of immediate post-operative re-learning: a randomized controlled trial. *J Hand Surg Eur Vol*. 2015;40:598–606.
74. Moseley GL, Wiech K. The effect of tactile discrimination training is enhanced when patients watch the reflected image of their unaffected limb during training. *Pain*. 2009;144:314–319.
75. Ramachandran VS, Altschuler EL. The use of visual feedback, in particular mirror visual feedback, in restoring brain function. *Brain*. 2009;132:1693–1710.
76. Anastakis DJ, Chen R, Davis KD, et al. Cortical plasticity following upper extremity injury and reconstruction. *Clin Plast Surg*. 2005;32:617–634.
77. Malesy MJ, Bakker D, Dekker AJ, et al. Functional magnetic resonance imaging and control over the biceps muscle after intercostal – musculocutaneous nerve transfer. *J Neurosurg*. 2003;98:261–268.
78. Duff SV. Impact of peripheral nerve injury on sensorimotor control. *J Hand Ther*. 2005;18:277–291.
79. Colbert SH, Mackinnon SE. Nerve transfers for brachial plexus reconstruction. *Hand Clin*. 2008;24:341–362.
80. Kozin SH. Nerve transfers in brachial plexus birth palsies: indications, techniques and outcomes. *Hand Clin*. 2008;24:363–376.
81. Leechavengvongs S, Witoonchart K, Uerpaiojkit C, et al. Nerve transfer to biceps muscle using a part of the ulnar nerve in brachial plexus injury (upper arm type): a report of 32 cases. *J Hand Surg Am*. 1998;23:711–716.
82. Leechavengvongs S, Witoonchart K, Uerpaiojkit C, et al. Nerve transfer to deltoid muscle using the nerve to the long head of the triceps, part II: a report of 7 cases. *J Hand Surg Am*. 2003;28:633–638.
83. Mackinnon SE, Novak CB, Myckatyn TM, et al. Results of reinnervation of the biceps and brachialis muscles with a double fascicular transfer. *J Hand Surg Am*. 2005;30:978–985.
84. Novak CB, Mackinnon SE. A distal anterior interosseous nerve transfer to the deep motor branch of the ulnar nerve for reconstruction of high ulnar nerve injuries. *J Reconstr Microsurg*. 2002;18:459–463.
85. Novak CB, Tung TH, Mackinnon SE. Patient outcome following a thoracodorsal to musculocutaneous nerve transfer for reconstruction of elbow flexion. *Br J Plast Surg*. 2003;55:416–419.
86. Oberlin C, Beal D, Leechavengvongs S, et al. Nerve transfer to biceps muscle using a part of ulnar nerve for C5–C6 avulsion of the brachial plexus: anatomical study and report of four cases. *J Hand Surg Am*. 1994;19:232–237.
87. Tung TH, Mackinnon SE. Flexor digitorum superficialis nerve transfer to restore pronation: two case reports and anatomic study. *J Hand Surg Am*. 2001;26:1065–1072.
88. Tung TH, Novak CB, Mackinnon SE. Nerve transfers to the biceps and brachialis branches to improve elbow flexion strength after brachial plexus injuries. *J Neurosurg*. 2003;98:313–318.
89. Chen R, Anastakis DJ, Haywood CT, et al. Plasticity of the human motor system following muscle reconstruction: a magnetic stimulation and functional magnetic resonance imaging study. *Clin Neurophysiol*. 2003;114:2434–2446.
90. Merzenich MM, Jenkins WM. Reorganization of cortical representations of the hand following alterations of skin inputs induced by nerve injury, skin island transfers and experience. *J Hand Ther*. 1993;6:89–104.
91. Taylor KS, Anastakis DJ, Davis KD. Cutting your nerve changes your brain. *Brain*. 2009;132:3122–3133.
92. Novak CB. Rehabilitation following motor nerve transfers. *Hand Clin*. 2008;24:417–423.
93. Novak CB. Rehabilitation following nerve transfer. In: Slutsky DJ, ed. *Upper Extremity Nerve Repair – Tips and Techniques: A Master Skills Publication*. Rosemont, IL: American Society for Surgery of the Hand; 2008:261–266.

94. Chuang DC-C, Yeh M-C, Wei F-C. Intercostal nerve transfer of the musculocutaneous nerve in avulsed brachial plexus injuries: evaluation of 66 patients. *J Hand Surg Am.* 1992;17:822–828.
95. Chalidapong P, Sananpanick K, Klapahajone J. Electromyographic comparison of various exercises to improve elbow flexion following intercostal nerve transfer. *J Bone Joint Surg Br.* 2006;88:620–622.
96. Gelberman RH, Woo SL. The physiological basis for application of controlled stress in the rehabilitation after flexor digitorum profundus tendon repair in a canine model. *J Hand Ther.* 1989;2:66–70.
97. Hitchcock TF, Light TR, Bunch WH. The effect of immediate constrained digital motion on the strength of flexor tendon repairs in chickens. *J Hand Surg Am.* 1987;12:590–595.
98. Lundborg G, Rank F. Experimental studies on cellular mechanisms involved in healing of animal and human flexor tendon in synovial environment. *Hand.* 1980;12:3–11.
99. Amadio PC. Friction of the gliding surface: implications for tendon surgery and rehabilitation. *J Hand Ther.* 2005;18:112–119.
100. Cao Y, Chen CH, Wu YF, et al. Digital oedema, adhesion formation and resistance to digital motion after primary flexor tendon repair. *J Hand Surg Eur Vol.* 2008;33:745–752.
101. Zhao C, Amadio PC, Tanaka T, et al. Short-term assessment of optimal timing for postoperative rehabilitation after flexor digitorum profundus tendon repair in a canine model. *J Hand Ther.* 2005;18:322–328.
102. Cao Y, Tang JB. Investigation of resistance of digital subcutaneous edema to gliding of the flexor tendon: an in vitro study. *J Hand Surg Am.* 2005;30:1248–1254.
103. Cao Y, Tang JB. Resistance to motion of flexor tendons and digital edema: an in vivo study in a chicken model. *J Hand Surg Am.* 2008;31:1645–1651.
104. Buonocore S, Sawh-Martinez R, Emerson JW, et al. The effects of edema and self-adherent wrap on the work of flexion in a cadaveric hand. *J Hand Surg Am.* 2012;37:1349–1355.
105. Cooney WP, Lin GT, An KN. Improved tendon excursion following flexor tendon repair. *J Hand Ther.* 1989;2:102–106. *In this cadaveric study, postoperative rehabilitation protocols were compared, including Kleinert, the Brooke Army Hospital modification, and synergistic motion. Synergistic motion yielded the greatest flexor digitorum profundus, flexor digitorum superficialis, and differential excursion.*
106. Evans RB, Thompson DE. The application of force to the healing tendon. *J Hand Ther.* 1993;6:266–284.
107. Savage R. The influence of wrist position on the minimum force required for active movement of the interphalangeal joints. *J Hand Surg [Br].* 1988;13:262–268.
108. Zhao C, Amadio PC, Zobitz ME, et al. Effect of synergistic motion on flexor digitorum profundus tendon excursion. *Clin Orthop Relat Res.* 2002;396:223–230.
109. Lieber RL, Kaufman KR, Whitney J, et al. Relationship between joint motion and flexor tendon force in the canine forelimb. *J Hand Surg Am.* 1996;21:957–962.
110. Lieber RL, Silva MJ, Amiel D, et al. Wrist and digital joint motion produce unique flexor tendon force and excursion in the canine forelimb. *J Biomech.* 1999;32:175–181. *This study using a canine model suggested that forces exerted on the healing flexor tendon are highly dependent on wrist position. Synergistic motion was noted to result in low passive forces on the flexor tendon with high excursion.*
111. Duran RE, Houser RG. *Controlled passive motion following flexor tendon repair in zones two and three.* American Academy of Orthopaedic Surgeons: Symposium on Tendon Surgery in the Hand 1975;105–114.
112. Groth GN. Current practice patterns of flexor tendon rehabilitation. *J Hand Ther.* 2005;18:169–174.
113. Kleinert HE, Kutz JE, Cohen MJ. *Primary repair of zone 2 flexor tendon lacerations.* American Academy of Orthopaedic Surgeons: Symposium on Tendon Surgery in the Hand 1975;91–104.
114. Coats RW, Echevarria-Ore JC, Mass DP. Acute flexor tendon repairs in zone II. *Hand Clin.* 2005;21:173–179.
115. Tang JB. Indications, methods, postoperative motion, and outcome evaluation of primary flexor tendon repairs in zone 2. *J Hand Surg Eur Vol.* 2007;32:118–129.
116. Lalonde D. How the wide awake approach is changing hand surgery and hand therapy: inaugural AAHS sponsored lecture at the ASHT meeting, San Diego, 2012. *J Hand Ther.* 2013;26:175–178.
117. Peck FH, Roe AE, Ng CY, et al. The Manchester short splint: a change to splinting practice in the rehabilitation of zone II flexor tendon repairs. *Hand Ther.* 2014;19:47–53.
118. Schuind F, Garcia-Elias M, Cooney WP, et al. Flexor tendon forces: in vivo measurements. *J Hand Surg Am.* 1992;17:291–298.
119. American Academy of Orthopedic Surgeons. *Tendon Suturing Methods: Analysis of Tensile Strengths.* St. Louis, MO: C.V. Mosby; 1975.
120. Wehbe MA, Hunter JM. Flexor tendon gliding in the hand. Part II. *J Hand Surg Am.* 1985;10:575–579.
121. Greenwald D, Shumway S, Allen C, et al. Dynamic analysis of profundus tendon function. *J Hand Surg Am.* 1994;19:626–635.
122. Evans RB. Immediate short arc motion for the repaired central slip. *J Hand Surg Am.* 1994;19:991–997.
123. Evans RB, Burkhalter WE. A study of the dynamic anatomy of extensor tendons and implications for treatment. *J Hand Surg Am.* 1986;11:774–779.
124. Howell JW, Merritt WH, Robinson SJ. Immediate controlled active motion following zone 4–7 extensor tendon repair. *J Hand Ther.* 2005;18:182–190. *The protocol described for extensor tendon injuries includes a wrist orthosis paired with a yoke orthosis which positions the metacarpophalangeal joint of the affected digit in hyperextension relative to the other digits. Full active motion within the immediate controlled active motion orthosis is expected prior to progression to the next phase of the protocol.*
125. Toth S. Therapist's management of tendon transfers. *Hand Clin.* 1986;2:239–246.
126. Richards RR. Tendon transfers for failed nerve reconstruction. *Clin Plast Surg.* 2003;30:223–245.
127. Sanes JN, Donoghue JP. Plasticity and primary motor cortex. *Annu Rev Neurosci.* 2000;23:393–415.
128. Feehan LM. Early controlled mobilization of potentially unstable extra-articular hand fractures. *J Hand Ther.* 2003;16:161–169. *This article suggests that functional and physiologic stresses associated with active range of motion increase the quality and rate of healing in potentially unstable extra-articular hand fractures. Control of clinical factors is recommended as a means of incorporating early motion into fracture management.*
129. Freeland AE, Hardy MA. Rehabilitation for proximal phalangeal fractures. *J Hand Ther.* 2003;16:129–142.
130. Henry MH. Fractures of the proximal phalanx and metacarpals in the hand: preferred methods of stabilization. *J Am Acad Orthop Surg.* 2008;16:586–595.
131. LaStayo PC, Winters KM, Hardy MA. Fracture healing: bone healing, fracture management and current concepts related to the hand. *J Hand Ther.* 2003;16:81–93.
132. Page S, Stern P. Complications and range of motion following plate fixation of metacarpal and phalangeal fractures. *J Hand Surg Am.* 1998;27:827–832.
133. Kurzen P, Fusetti C, Bonaccio M, et al. Complications after plate fixation of phalangeal fractures. *J Trauma.* 2006;60:841–843.
134. Ebinger T, Erhard N, Kinzl L, et al. Dynamic treatment of displaced proximal phalangeal fractures. *J Hand Surg Am.* 1999;24:1254–1262.
135. McNemar TB, Howell JW, Chang E. Management of metacarpal fractures. *J Hand Ther.* 2003;16:143–151.
136. Moulton MJ, Parentis MA, Kelly MJ, et al. Influence of metacarpal joint position on the basal joint loading in the thumb. *J Bone Joint Surg Am.* 2001;83:709–716. *In this cadaveric study, immobilization of the metacarpophalangeal joint was studied as it pertained to forces on the trapezial surface during lateral pinch. Metacarpophalangeal flexion was noted to unload the most palmar aspect of the carpometacarpal joint effectively, decreasing strain on the palmar oblique ligament.*
137. Valdes K, von der Heyde RL. An exercise program for carpometacarpal osteoarthritis based on biomechanical principles. *J Hand Ther.* 2012;25:251–262.

40

Treatment of the upper extremity amputee

Gregory A. Dumanian, Jason M. Souza, and Todd Kuiken

SYNOPSIS

- Upper extremity amputees are different from lower extremity amputees: patients are younger and their amputations are primarily due to trauma and tumors rather than dysvascular conditions. The patients live longer with their residual limbs.
- Prosthetic concerns for the two groups of patients dramatically differ.
- Upper extremity prostheses require more control, more movement, and more precision than that for a leg. Fortunately, upper extremity prostheses have less load bearing requirements, since they do not need to support the weight of the body.

Introduction

Upper extremity amputees are different from lower extremity amputees in many aspects. The patients are younger and their amputations are primarily due to trauma and tumors rather than dysvascular conditions. The patients live longer with their residual limbs. Prosthetic concerns for the two groups of patients dramatically differ. Upper extremity prostheses require more control, more movement, and more precision than that for a leg. Fortunately, upper extremity prostheses have less load bearing requirements, since they do not need to support the weight of the body. The purpose of this chapter is to familiarize the reader with necessary concepts to care for the upper extremity amputee. Handling of soft tissues, bones, and nerves are reviewed for each of the levels of amputation. Prosthetics and prosthetic control will be a necessary accompaniment of this chapter. Recent advancements in the field including targeted reinnervation will be introduced.

Aesthetic prostheses

Aesthetic prostheses refer to devices that are used to camouflage a limb deformity, while functional prostheses refer to devices that are operational.⁵ Aesthetic prostheses assist patients in issues of body image and self-esteem, with possible functional gains due to a newfound social openness and ability to expose the limb. Patients can appear fairly normal in public with aesthetic prostheses (Figs. 40.1 & 40.2). Most of these prostheses are custom made and require a high level of expertise on the part of the prosthetist. Because intact skin is used to secure the prosthetics in place, some amount of sensory feedback of the residual limb will be lost, and this is one drawback to these devices. Osseointegration of aesthetic prostheses into bone has been studied at length, because of the potential for improved tolerance of the soft tissues to the prosthesis, the limit on the amount of soft tissues covered, and ability to use stiffer materials in the devices for possible secondary functional gains. The bone–soft tissue–implant interface for osseointegration of upper limb prosthetics remains problematic.⁶

Control of upper extremity prosthetic devices

A prosthesis is only as good as the control signals that it receives from the user. The goal of any prosthesis is to be moved and positioned in space smoothly, quickly, intuitively, and with minimal exertion and mental fatigue to accomplish this task.⁷ Multifunctional prostheses offer the potential for greater functionality, but come at the cost of increased complexity with regard to control strategies. Prostheses with both a terminal “hand” device and a prosthetic elbow require differentiation between signals intended for hand control and those intended for elbow function. This differentiation becomes even more critical when these functions are attempted simultaneously.



Access the Historical perspective section online at

<http://www.expertconsult.com>

Historical perspective

Putti documented the history of upper extremity prostheses in the 1930s, and this work has been subsequently translated into English.¹ The field of prosthetics began soon after advancements in battlefield surgery allowed patients to survive limb amputations. Prior to cautery, surgeons were forced to allow tissue to mummify, and then to slowly separate living tissue from dead. Residual limbs developed in this manner had poor soft-tissue coverage of bone, and therefore were poorly able to tolerate the weight of a prosthesis. Advances in metalworking permitted the creation of metallic prostheses beginning in the early 1500s. A famous knight, Gottfried von Berlichingen (c.1480–1562) was known as Gotz of the Iron Hand for his below elbow amputation. The prosthesis he wore was strapped to the forearm with leather bands, and had moveable fingers and thumb that could be revolved and tightened around the hilt of a sword. Ambroise Pare documented the ingenious Petit Lorrain artificial hand that had fingers that moved into extension with springs, and could be held in flexion by sprockets that caught metal levers.² The Alt-Ruppin prosthesis, fished out of a canal in the town of the same name, was constructed in the 1500s and similarly had moveable fingers and thumb. These prostheses inspired the imagination of onlookers, and demonstrated the ingenuity of armor makers of the day.

The Ballif arm of 1812 was an improvement over the metallic arms for its softer materials and for the active control of the prosthetic hand. Rather than locking prosthetic fingers into place for a static grip, the Ballif arm utilized cables attached to the shoulder and arm to allow opening and closing of the prosthetic hand. The Civil War created a huge number of amputees in the United States, leading to companies such as the A. A. Marks Company (1853) of New York and the J. E. Hanger Company (1861, still in existence today). These firms and others provided body-powered prostheses to the masses by mail order. World War II led to further refinements in body-powered prostheses due to the large numbers of upper extremity amputees coupled with significant advances in technology developed for the aviation industry.³ With minor adjustments for materials and socket designs, body-powered upper extremity prostheses have remained relatively unchanged since the 1950s. Body-powered prostheses are operated by using shoulder motion to pull on a housed cable (like a bicycle brake cable) and thus transfer power to the prosthetic joints. Generally only one joint can be operated at

a time. Thus when using a prosthesis with multiple joints, the user unlocks only the joint he wishes to operate using a variety of different types of switches.

The development of externally powered prostheses powered by electricity or pressurized gas began in Germany soon after World War I. The myoelectric hand, controlled using Electromyogram (EMG) signals from the residual limb, was first created by Mr. Reinhold Reiter for the Bavarian Red Cross in 1943 during World War II and published in 1948. Parallel efforts to create a myoelectric prosthesis began in England, the Soviet Union, and the United States. The United States effort was led by the Committee on Prosthetics Research and Development of the National Research Council, with the initial meeting held at Northwestern University. Technical advancements were greatly aided by the miniaturization of electric components. The first device to use transistors was the so-called “Russian Hand” of 1959. Along with the Vaduz and Bottomley Hands, these single-function (open and close) devices received much publicity, but were rather slow and clumsy to operate. Multifunction myoelectric devices with wrist flexion/extension and pronation/supination were introduced in the mid-1960s as a means to further improve on these devices.⁴ Despite research efforts that spanned the globe, these multifunction prostheses were limited by the difficulty for the amputee to control the movements of the prosthesis.

Proponents of body-powered prostheses have been arguing with the proponents of externally powered system for the last half-century. However, both types of devices are useful and often complementary. Body-powered prostheses are generally lighter and more robust than external systems with batteries and motors. Externally powered systems require more daily maintenance for battery changes and are more fragile than the simpler and sturdier harnesses and hooks. Functionally, body-powered prostheses tend to give the wearer a bit more feedback during use. A significant advantage for transradial and more distal myoelectric prostheses is that they can be anatomically suspended using the humeral condyles or using suction sleeves; this eliminates the need for cumbersome shoulder harnessing. Furthermore, as unilateral upper limb amputees tend to use the prosthetic limb only as a helper hand, the improved cosmetics of myoelectric devices can make up for their many drawbacks and are often preferred.³ Hybrid systems also exist that try to combine the best features of both body-powered and external-powered prostheses. One example is to have a body-powered prosthetic elbow coupled with a myoelectric hand.



Fig. 40.1 Patient with multiple finger amputations due to sepsis and hypotension.

The cable systems used by body-powered devices provide a reliable method for control, but lack fluidity and do not offer simultaneous control of multiple functions. Body-powered prostheses, as previously described, utilize shoulder motions to operate the prosthesis. This is problematic, because muscles that are designed for strong movements – such as the latissimus dorsi and the serratus anterior – are required to move accurately and sensitively to control cables and switches. Body-powered devices use non-intuitive shoulder muscles to control a prosthetic elbow or hand.

Myoelectric control, derived from surface EMG recording of residual limb muscles, provides prosthetic control without the need for accessory shoulder movement. From the standpoint of aesthetics and comfort, the lack of cables and pulleys is advantageous, but is often offset by the bulk of the socket and the increased weight of the motorized device. Myoelectric control represented a promising technological advance, but the prosthetic function provided by the earlier devices remained relatively slow and disjointed, thus limiting applicability. The residual limb musculature being recorded was not usually cortically linked to the prosthetic function being controlled (i.e., biceps brachii used to control finger flexion). Also, as with body-powered devices, only one joint could be operated at a time. Multifunctional devices required an

additional switch or signal to enable the device to change between functions.

The potential offered by myoelectric control was realized in 1995, when Kuiken, Childress and Rymer demonstrated a new myoelectric control strategy now called “targeted muscle reinnervation” (TMR). TMR utilizes nerve transfers between the transected brachial nerves and the residual limb muscles to reclaim the neural control information that is lost as a result of upper extremity amputation.⁸ As a result, prosthetic function can be directly coupled with EMG signals corresponding to the nerves responsible for the identical function in the previously intact limb. Clinically, this technique yields intuitive and relatively seamless device control. In addition, the increased number of EMG control sites provided by TMR enables simultaneous control of multiple functions. Kuiken and Dumanian first reported this procedure in shoulder disarticulation patients in 2004,⁹ and in transhumeral amputees in 2008.¹⁰

While the functional capabilities of prosthetic devices once outpaced the amount of information available to control them, the pendulum has now swung the other way. When it was introduced, the number of nerve transfers performed as part of the TMR procedure largely dictated the number of prosthetic functions capable of being controlled. This control strategy, labeled “direct control”, meant that a single reinnervated muscle segment could be used to control only one function via a single EMG electrode (i.e., reinnervation of short head of biceps by median nerve for hand closure). Recently, “direct control” has been supplanted by “pattern recognition”, whereby advanced algorithms are used to correlate the pattern of muscular contractions recorded from many more electrodes. This approach provides greater flexibility for rehabilitation and has served to markedly improve the functional capacity of the amputee.

Other strategies for prosthetic control are still in the investigative phase, but show promise. Implantable myoelectric sensor systems that transmit EMG signals out to a detecting device could improve the EMG signal quality and consistency, as well as provide control signals from small muscle bodies such as the individual finger extensors of the forearm.¹¹ Direct signal acquisition from the amputated nerves using a variety of implanted electrodes or small muscle grafts to amplify the nerve signals have been investigated.^{12,13} Prosthetic control using fine wire electrodes was recently demonstrated in an acute experiment in humans.¹⁴ Direct recording and stimulation of the cerebral cortex has been performed in monkeys in order to effect peripheral movement. This brain-machine interface, if successful, could have wide applicability, not only for amputees, but also for patients with spinal cord injuries.¹⁵



Fig. 40.2 Multiple-digit prostheses for improvement of cosmetic appearance.

Prosthetic implications of upper limb amputation surgery

The surgical treatment of patients with unreconstructable upper extremity disorders must take into account issues unique to the amputee. The amputation must have durable soft tissues to allow for prosthetic fitting. In all instances, an evaluation is performed as to how to preserve intact nerves and how to manage unavoidable end-neuromas. The means

by which the prosthesis will be controlled must be considered. With these concepts in mind, a level-by-level analysis of common upper extremity amputations is presented.

Finger amputation

Patients undergoing reconstructive upper extremity surgery do best when the surgeon “Think(s) Nerve” first.¹⁶ Patients can easily tolerate a painless stiff digit, while they are greatly troubled by a mobile painful digit with a symptomatic neuroma. Patients with wounds of the fingers should be evaluated as to which nerves are irreparably cut, and which digital nerves are intact. If a major portion of one of the two digital nerves is intact, then a flap should be performed for wound closure, rather than a shortening amputation with division of both digital nerves. The digital nerves to the finger pulp trifurcate approximately 2 mm distal to the volar distal interphalangeal joint skin crease. One branch travels to the nail fold, a second branch travels to the volar tip, and the third branch innervates the volar pad. Amputations at or proximal to the trifurcation have two cut digital nerves, and therefore a revision amputation will not cut a new nerve to achieve wound closure. In the figure shown, the ulnar digital nerve to the ring finger is intact, while the radial digital nerve is cut (Figs. 40.3 & 40.4). The cross finger flap is performed to achieve wound closure, but more importantly to avoid the necessity of dividing an intact digital nerve as part of a revision amputation.

Much has been written about more proximal finger amputations. For these patients, a traction neurectomy is performed to keep the nerve from trying to reinnervate the skin laceration area. The surgeon should attempt to achieve a smooth and tapered end to the digit, rather than having a bulbous tip. This requires removal of the condyles for joint disarticulations, and longer skin incisions down the midaxial lines of the digits for removal of 1 “dog ears”.

Partial hand

Again “Thinking Nerve”, loss of the ulnar, radial, or dorsal aspect of the hand with preservation of the volar nerves warrants flap reconstruction to obviate the need to divide nerves



Fig. 40.4 Same patient as in Fig. 40.3: 2 weeks later, with the cross-finger flap sewn in place.

that remain in continuity. Typically, this will be either a free flap, or a pedicled groin flap as a second choice. If the majority of the digital nerves are divided, then the next decision is whether there is a functional and stable wrist joint. Maintenance of the wrist will allow the residual limb to be an excellent helper hand, even without a prosthesis (Figs. 40.5–40.7). In some avulsive injuries, the dorsal wrist extensors have been removed by the injury, and it is worthwhile to reinsert extensor tendons to the residual carpal bones with bone anchors and a flap for coverage. Thicker muscle flaps are preferable to skin flaps, as the associated atrophy will facilitate the placement of passive finger prostheses that can assist in grasp.¹⁷

Body-powered and externally powered prostheses exist for partial hand amputations, but have significant size constraints to provide moveable components that will not



Fig. 40.3 Young adult with injury to half of the pulp of his ring finger. Completion amputation was recommended at an outside institution.



Fig. 40.5 Amputated specimen in young male.



Fig. 40.6 Radiograph showing preserved radiocarpal joint.

cause the device to be longer than the opposite hand. Suspension of these devices is also difficult due to the need to not impede wrist motion. Rather than prosthetics, improvements in hand function for patients with thumb, multiple digit, or partial hand amputations can be achieved with toe-to-hand transfers.

Wrist disarticulation and transradial amputation

Injuries that divide the digital nerves and strip the soft tissues off of the carpal bones are better served by a wrist disarticulation or a transradial amputation than by efforts to salvage a scarred and immobile hand for the sake of “preserving length” (Fig. 40.8). These patients have already suffered a complete



Fig. 40.8 A young worker had skin grafts applied to a proximal hand stripped of almost all soft tissues in an attempt to “save length”. He underwent a transradial amputation for treatment of his painful immobile scarred hand.

division of the median, radial, and ulnar nerves from their injury, and so a more formal amputation with manipulation and re-division of the nerves where the soft tissues are more supple is appropriate.

In the operating room, plans are made for soft-tissue coverage of the residual limb with development of palmar and dorsal skin flaps. A dorsal approach to the wrist identifies the proximal carpal row, and these bones are excised much like a proximal row carpectomy. The ulnar and radial arteries are doubly ligated. The radial and ulnar styloids are trimmed to allow for easier prosthetic fitting without pressure points, but the triangular fibrocartilage complex is maintained to preserve pronation and supination. When possible, more durable volar skin is used for coverage as opposed to thinner dorsal skin.

Handling of the nerves to prevent a symptomatic mixed major nerve neuroma from developing is important, as a painful neuroma will complicate prosthetic wear. Standard treatment is traction neurectomy, where the nerves are placed on stretch, divided, and allowed to retract away from the incision line. A general concept is that the better “padded” is a neuroma, the less symptomatic. Other treatments supported both by experimental animal surgery and clinical experience include placing the cut nerve ending within immobile muscle as opposed to simply allowing them to retract.^{18,19}

Clinical work with TMR has revealed that major mixed nerves do not form symptomatic neuromas when nerve transfers are performed. Nerve transfers are now often performed at the time of a wrist disarticulation. This is not for obtaining new control signals (although this may occur), but rather for prevention of symptomatic end-neuromas. Through a proximal incision between the flexor carpi ulnaris (FCU) and flexor digitorum superficialis (FDS), the median nerve is transferred to a motor nerve of the FDS, the ulnar nerve is transferred to a motor nerve innervating the FCU, and the radial nerve is transferred to the motor nerve innervating the pronator quadratus. This strategy has been successful for neuroma control, and there is no morbidity associated with sacrifice of the recipient motor nerves due to the distal amputation. Also, as demonstrated clinically with every muscle flap harvest, cut motor nerves in humans do not form symptomatic neuroma.

If the patient is unlikely to wear a prosthesis, a wrist disarticulation with good soft coverage will give the patient a longer and more functional residual limb. Wrist disarticulation prostheses do well in capturing the distal bony structures for wrist rotation; however, room is limited for prosthetic components and the devices tend to look bulky. A long transradial amputation generally facilitates better prosthetic



Fig. 40.7 Mobile wrist joint acts as a helper hand. The patient's extensor tendons were reinserted into the carpal bones with bone anchors.




Fig. 40.9 Patient with previous transradial amputation plagued by poor soft-tissue coverage of residual limb.

fitting by allowing room for prosthetic components and providing better cosmetic appearance.

A lack of soft tissue may require a transradial amputation as opposed to a wrist disarticulation. In these instances, the shorter lever arm will place more stresses on the residual soft tissues for movement of the prostheses. Pronation and supination will not be as easily translated into prosthetic movement and positioning. Patients undergoing transradial amputations will have similar treatments of the arteries and nerves of the forearm. The radial nerve will be divided and allowed to retract underneath the brachioradialis. A myoplasty of the extensor and flexor muscles over the cut ends of the radius and ulna will stabilize the muscle masses, and facilitate later prosthetic fitting. Drill holes through the bones for passage of suture are useful to prevent muscle movement over the end of the residual limb. At least 5 cm of ulna is necessary to retain elbow movement, but in these instances of very short residual limbs, the insertion of the biceps tendon may need to be transferred to the ulna. Preservation of length of bone may require a soft tissue flap taken from the flank.²⁰ This pedicled flap is divided after 3 weeks, but provides thick soft tissue and a smoother soft-tissue envelope for prosthetic fitting (Figs. 40.9 & 40.10). The function of a transradial amputation is much greater than a transhumeral amputation, thus aggressive treatment to save the elbow and reasonable forearm length is warranted.

Elbow disarticulation and long transhumeral amputation

Non-reconstructable and non-replantable injuries at the elbow level require removal of the ulna and radius. The level of amputation depends on the plan for prosthetic rehabilitation. If no prosthetic is planned, then the elbow disarticulation is a more functional level than a higher amputation, because the limb is long enough to reach a table in sitting and thus is easier to use for moving and stabilizing objects. While the condyles

in an elbow disarticulation can be useful in suspension of the prosthesis and for humeral rotation, the appearance of the arm with its prosthetic appears too long. Very long transhumeral amputees can be treated with an angulation osteotomy (with or without shortening) of the distal humerus. It can provide a lever arm for suspension and for rotational control of the prosthesis.²¹ Finally, if a powered elbow is planned, a transhumeral amputation 5–6 cm above the olecranon allows room for the motor and the elbow “joint” seems to be in the correct place. A transhumeral amputation at this level still allows for TMR of the median, ulnar, and radial nerves.

In the operating room, anterior and posterior skin flaps are elevated. The level of the bone division is decided, and either the elbow capsule and ligaments are divided sharply, or else the humerus is cut just proximal to the epicondyles. A myodesis of the triceps and biceps to the distal bone is performed utilizing drill holes for several reasons. Good quality soft-tissue coverage of the distal bone is a necessity. The end of the residual limb should not have too much redundancy and mobility to facilitate application of a socket and donning the prosthesis. Finally, prevention of proximal migration of the muscle mass during contraction is important for later signal detection for a myoelectric prosthesis. For performance of an angulation osteotomy, the amputation is done in the prone position for proper plate placement.

Handling of the neurovascular structures is another important decision branch point. Treatment of the median, ulnar, and radial nerves is quite important at this stage. The standard traction neurectomy is *no longer* the optimal treatment for these large mixed nerves. The question is whether targeted reinnervation should be performed at the time of the amputation or at a later date. Immediate targeted reinnervation has the advantage of avoiding a second surgery, and the nerve transfers would be performed when the nerves are at their longest length, without neuromas to resect and with a full axon complement. Benefits of immediate targeted reinnervation include a shorter time between amputation and the possibility to have additional control signals for improved prosthetic function. As has been mentioned, nerve transfers are a method to prevent the development of symptomatic



Fig. 40.10 Pedicled periumbilical perforator flap is transferred to the end of the limb after excision of skin-grafted area, and divided 3½ weeks later.

painful neuroma. The effect of targeted reinnervation on phantom limb sensation is under investigation. Amputation followed by a later TMR has the advantage of improved patient education and consent, the avoidance of new proximal incisions in a swollen traumatized limb, and the ability to advantageously thin the subcutaneous fat to improve EMG acquisition. If the prospect of delayed TMR exists, then the major mixed nerves should be left long and without additional dissection.

Transhumeral amputations through the middle third of the humerus still allow for a mobile shoulder joint and successful prosthetic fitting. Often TMR can be still be performed. Pedicled latissimus flaps can be extremely useful to achieve wound closure and maintain length when needed, but make delayed TMR a bit more challenging. Short transhumeral amputations can undergo Ilizarov lengthening or even free fibula transfer to achieve a longer lever arm for the prosthesis.

With severe brachial plexopathies resulting in flail limbs, amputation is often considered. Amputation will not relieve neuropathic plexopathy pain, but can relieve traction pain at the shoulder and it clearly removes the inconveniences of having a paralyzed arm. We recommend a transhumeral amputation at 25–30% of humeral length in these instances. This removes the weight of the limb, relieving traction pain, and preserves a nice shoulder and upper arm contour for clothing. Fusion of the shoulder to enhance prosthetic fitting is not recommended. Prosthetic fittings with flail residual limbs have extremely poor outcomes and a humerus fused in abduction and flexion interferes with some activities, especially positioning in bed.

Proximal transhumeral and shoulder disarticulation

Loss of the biceps and triceps due to electrical injury or avulsive injuries are best treated with a proximal transhumeral amputation or a shoulder disarticulation. Maintenance of the humeral head in its glenohumeral fossa has cosmetic implications in shirt fitting, and depends on the local soft tissues. Again, traction neurectomies should be avoided to preserve nerve length. Preservation of a small humeral remnant under deltoid motor control can be extremely useful to activate switches via miniature touch pads. The deltoid muscle is typically spared in electrical injuries due to the increased cross-sectional area of the body. In avulsive injuries, the deltoid is spared due to its broad origin on the scapula. The deltoid is pulled inferiorly with sutures, and the chest skin can be mobilized superiorly for closure of the glenohumeral fossa.

Surgery of the residual limb

Soft-tissue improvement

Patients with traumatic amputations often have soft tissues that are suboptimal for prolonged prosthetic wear. Contour irregularities due to scars, skin grafts, and skin redundancy compromise the fit of prosthetic sockets and liners. Skin breakdown is common, resulting in discomfort and recurrent infections that serve to further limit prosthetic wear. Because physiatrists or prosthetists manage most elements




Fig. 40.11 Transhumeral amputee with scarred soft tissues of her residual limb.

of prosthetic use, even straightforward surgical solutions are often delayed in favor of socket or behavioral modifications. Thus, the importance of close collaboration between reconstructive surgeons and rehabilitation providers cannot be overstated. Surgical techniques remain the most effective ways to achieve a wound-free residual limb without painful neuromas or poorly covered bone. The specific techniques employed will vary based on the mechanism of amputation and degree of injury, but largely include advancement flaps, excision of skin grafts, Z-plasties for scar contractures, and lipectomy either through direct excision or circumferential liposuction (Figs. 40.11 & 40.12). The patient must be aware that even after primary skin healing, swelling will take many weeks to resolve, and therefore may require multiple re-fittings and an extended period during which the patient will be without use of the prosthetic.

Skin breakdown can occur from poor prosthetic fit, but it also can occur when skin grafts have been used to preserve length in the absence of adequate soft tissue. Revision amputations can be considered when the prosthetist and physiatrist agree that a shorter residual limb with improved soft tissues



Fig. 40.12 Same patient as Fig. 40.11 after excision of previously placed skin graft and closure with advanced skin flap, analogous to a brachioplasty.

will be preferable to a longer amputation covered with skin grafts. When limb shortening is not a viable option, both pedicle and free flaps are useful for improving padding and durability. The goal is a smooth contour that better distributes pressure.

In addition to addressing contour abnormalities and skin breakdown, the function of myoelectric prosthetic control can also be improved with soft-tissue revision. The removal of subcutaneous fat decreases the resistance between the underlying muscle and skin. This can markedly increase the amplitude of the EMG signals and decrease interference (cross-talk) from neighboring muscles.²²

Neuroma management

Neuromas are significant problems after upper extremity amputations. Large series from areas of conflict document neuromas and stump pain in over one-quarter of upper extremity amputees.^{23–25} Clinically, large mixed neuromas can be very symptomatic, as can superficial sensory nerve neuromas. “Pure” motor nerves are less than 50% motor fibers by staining, yet clinically they do not create symptomatic end-neuromas when cut. Neuroma pain is described as a localized area of tenderness when pressure is applied, typically with a radiation of discomfort in the area that the nerve had previously innervated. This is in contradistinction to phantom sensations, which are defined as the feeling that a deafferented body part is still present following amputation.

Numerous strategies have been reported to be successful in the management of painful stump neuromas. The simplest method of neuroma excision and traction neurectomy has a documented 70% improvement rate.²⁶ Neuroma excision with burying the nerve end in muscle,²⁷ neuroma translocation away from areas of pressure,²⁸ and the centro-centralization technique of Gorkisch²⁹ have all been documented to have high levels of patient satisfaction and low recurrence rates. These studies are all limited by being observational studies. Experimental neuroma work is hampered by the fact that all peripheral nerves form neuromas in the absence of a distal target, but not all neuromas are symptomatic, making it difficult to differentiate a quiet neuroma from a symptomatic one in a preclinical setting.

There is now growing evidence to suggest that reconstitution of the nervous system through nerve repair, grafting, or transfer serves to limit neuroma pain by inhibiting the disorganized regeneration that underlies neuroma formation. In a recent clinical report by Moran *et al.*, nerve repair was shown to be superior to neuroma excision and muscle/bone implantation for treatment of symptomatic neuromas in the intact upper extremity.³⁰ The nerve transfers utilized in TMR provide the transected brachial nerves a vascularized scaffold for coordinated axon regeneration, necessary neurotrophic factors, and a target volume of denervated muscle to reinnervate. TMR offers the potential to restore continuity to the peripheral nervous system despite the absence of the native distal nerve segments. A multicenter retrospective review demonstrated no neuroma pain involving a transferred nerve following 82 TMR nerve transfers in 26 patients over a 10-year period.³¹ More recently, TMR has been used for management of existing neuroma pain at all amputation levels proximal to the wrist with good clinical results.

Targeted muscle reinnervation

As noted above, TMR is a technique involving transfer of the median, radial, ulnar and/or musculocutaneous nerves in an amputated arm to redundant residual limb muscles. These reinnervated target muscles then serve as biological amplifiers for the nerve signals, providing surface EMG control signals for improved operation of motorized prostheses. The TMR surgical procedure was recently reviewed,⁸ and demonstrates improved outcomes in comparison to standard prostheses documented.⁸ The following is a brief review of the surgical techniques.

Transhumeral level

The indications to perform TMR at the transhumeral level include poor prosthetic function using standard body-powered, myoelectric, or hybrid systems despite adequate training. Good candidates are young patients with cortical control of biceps and triceps contraction without plexopathy, supple soft tissues, and without other cardiopulmonary risk factors. Bilateral amputations and long residual limbs also favor the procedure. Patients who have suffered avulsions of the limb at the time of injury or patients with brachialplexopathies are poor candidates for surgery.

On examination, Tinel’s signs signifying the ends of the median, ulnar, and radial nerve are marked. Tinel’s signs located at the mid-humeral level or distal have long enough nerves to perform nerve transfers. The raphe between heads of the biceps and triceps are palpated and marked preoperatively, as the absence of normal distal landmarks makes it easy to lose orientation of the arm once the patient is positioned on the operating room table. The anterior incision provides access to the median, ulnar, and musculocutaneous nerves. The median nerve is transferred to the motor nerve of the short head of the biceps, while preserving the musculocutaneous nerve innervation to the lateral head of the biceps (Fig. 40.13). This transfer provides a “hand closing” signal for the prosthesis, while preserving the native “elbow flexion” signal. In the operating room, after raising thin skin flaps, an adipofascial flap is elevated and based proximally. The neuromatous end of the median nerve is identified, cut back to healthy fascicles, and is mobilized into the space adjacent to the motor




Fig. 40.13 Cadaveric dissection splitting the medial and lateral heads of the biceps to expose the motor points of the musculocutaneous nerve.




Fig. 40.14 Schematic of targeted muscle reinnervation nerve transfer.

entry point of the musculocutaneous nerve on the short head of the biceps. The nerve transfer is completed by transecting the motor nerve to this muscle segment and coapting the median nerve directly to this 1–1.5 mm motor nerve (Fig. 40.14). The coaptation site should be as near to the muscle belly as possible to decrease innervation times and to facilitate placement of a supportive epimysial suture. In the case of long transhumeral amputations, where the brachialis has been preserved, the ulnar nerve can be transferred to the motor entry point of the musculocutaneous nerve into the brachialis. This follows an identical thought process and procedure as that performed for the median nerve. At closure, the adipofascial flap is placed back between the biceps heads to spatially separate the two biceps signals. Posteriorly, the distal radial nerve is transferred to the motor nerve innervating the lateral head of the triceps, while the native innervation of the long head of the triceps is maintained. This creates a “hand opening” signal, while preserving an intact “elbow extension” signal from the proximal radial nerve. After the elevation of a proximally based adipofascial flap, the triceps is split between the long and lateral heads to reveal the motor nerve to the lateral head of the triceps and the distal radial nerve. The distal radial nerve is coapted to the newly divided motor nerve of the lateral head of the triceps. Drains and a mildly compressing dressing are applied. Therapy can begin several weeks after the nerve transfer procedure.³²

Shoulder disarticulation level

TMR at the shoulder level should be performed only by surgical teams possessing a significant knowledge of upper chest and axillary anatomy.^{33,34} Patient evaluation begins with a thorough history and physical examination. Patients with brachial plexus injuries are not candidates for the procedure, as the median, radial, and ulnar nerves must elicit action potentials under direct cortical control. Though it may seem obvious, patients cannot undergo TMR unless they have had an amputation, as there is no region of the body to accept the prosthetic arm. The indication for performing surgery is to improve prosthetic function. Painful neuromas and uncomfortable areas of heterotopic ossification have been other relative indications for the procedure. A Tinel’s sign over the major three nerves is elicited, as is confirmation that the pectoralis, serratus, and latissimus muscles are under active cortical control. These will be potential recipient targets for the nerve transfers.

An infraclavicular approach to the plexus and proximal nerve branches is performed incising the skin two finger-breadths below the clavicle and carefully opening the interspace between the sternal and clavicular heads of the pectoralis major (Figs. 40.15–40.19). During the approach, thin skin flaps are raised and the thick chest adiposity is thinned for improved signal detection in a region 10 cm in superior-to-inferior dimension, and from the medial chest to the anterior axillary line. The motor nerves to the clavicular head of the pectoralis off of the lateral cord are located at the midpoint of the clavicle and are tagged. Motor nerves to the sternal head pectoralis are identified next and come in three clusters: a motor nerve that is near the motor nerve to the clavicular head, a motor nerve that travels through the pectoralis minor or is just medial to the pectoralis minor, and a motor nerve that is on the lateral aspect of the pectoralis. The origin of these motor nerves does not matter – as only the size and location of these motor point nerves as they reach the muscle (where the transfers will be performed) is important. What major mixed nerve can reach which motor nerve? Next, either medial or lateral to the pectoralis minor tendon, the brachial plexus and the musculocutaneous, median, ulnar, and radial nerves emanating from it are identified. The radial nerve is stimulated to make sure there is no triceps remnant to leave in continuity. The identity of the nerves is made by their branching pattern off of the brachial plexus. The axillary nerve is not seen typically at this level. Deep to the plexus, the proximal thoracodorsal nerve is identified as a potential target.

Typically, there are four nerves to transfer and there must be four recipients (Table 40.1). The most common transfers are the musculocutaneous nerve to the clavicular head of the pectoralis, the median nerve to the largest motor nerve innervating the sternal head of the pectoralis, and the radial nerve to the thoracodorsal nerve. The recipient for the ulnar nerve is generally the motor nerve innervating the lateral aspect of the pectoralis major. Alternatives for the ulnar nerve include the long thoracic nerve, or the nerve innervating the pectoralis minor. If the pectoralis minor is used, it will need to be mobilized laterally, and the insertion of the pectoralis divided (if present) so that it is moved laterally for better signal detection. When the pectoralis receives more than one innervation, it can be divided along its fibers based on its vascular anatomy and motor nerve anatomy. Segments should be at least 4–5 cm in diameter for adequate signal detection. The target muscle should be completely denervated during these transfers so that the previous pectoral EMG signal is eliminated. Nerve coaptations are performed as close to the entry point of the motor nerve into the muscle as possible to decrease the time

Table 40.1 Targeted muscle reinnervation for shoulder disarticulations

Nerve	Possible recipient
Musculocutaneous	Clavicular head of pectoralis major
Median	Largest motor nerve innervating sternal head of pectoralis major
Radial	Thoracodorsal or long thoracic
Ulnar	Lateral motor nerve innervating sternal head of pectoralis major or minor




Fig. 40.15 Schematic nerve coaptations for shoulder targeted muscle reinnervation.



Fig. 40.16 Patient with small humeral remnant undergoing shoulder-level targeted muscle reinnervation. The clavicle is dotted, and the incision is drawn.




Fig. 40.17 Adipofascial flap is raised, exposing the interspace between the clavicular and sternal heads of the pectoralis major.




Fig. 40.18 The radial, median, and ulnar nerves are dissected free with hemostats holding them laterally. The musculocutaneous nerve is visible just inferior to the army-navy retractor.

of reinnervation. The adipofascial flap is placed between the pectoral heads to reduce aberrant reinnervation and to separate the muscle bellies from each other thereby improving EMG signal detection. The skin is closed over drains after placement of quilting sutures to decrease seromas. The patient may resume wearing his/her original prosthesis when there is adequate wound healing. Prosthetic fitting for new control sites will occur in 3–6 months. The latissimus muscle, being farthest away from the coaptation site, will take the longest to come under cortical control.




Fig. 40.19 Radial to thoracodorsal nerve coaptation.

Targeted sensory reinnervation is also possible; the afferent fibers of the transferred nerves will reinnervate any denervated skin overlying the target muscle. When this reinnervated skin is touched, the patient feels that their missing hand is being touched, providing cortical feedback to the “hand” aspect of the brain. All modalities of cutaneous sensation are restored including pressure, vibration and thermal. Special devices termed “tactors” may provide feedback from the prosthesis to the brain in the correct part of the brain for position or pressure applied by the terminal device. In doing so, targeted motor and sensory reinnervation will “close the loop” for prosthetic function. Sensory nerves, including the supraclavicular nerve and the lateral intercostal nerve, have been coapted end-to-side to medial and ulnar nerves to provide targeted sensory reinnervation. A recent review article provides a useful summary of the state of the art with regard to prosthetic sensory feedback and associated technologies for neural signaling.³⁵

Transradial level

TMR has been performed for patients with transradial amputations, but for neuroma control rather than improved prosthetic function. These transfers are described above in the “Wrist disarticulation and transradial amputation” section. Several of these transradial TMR patients are currently enrolled in a study comparing TMR-based control to myoelectric control in subjects with conventional transradial amputations. It is hoped that in combination with computer-decoding algorithms, the intrinsic hand muscle EMG information derived from transradial TMR will help to better control multifunction prosthetic hands.³⁶

Comparison of prosthetics with composite tissue allotransplantation

Clinically, there have not been any direct comparisons between the functional outcomes obtained with TMR-controlled prosthetics and those resulting from composite tissue allotransplantation (CTA). While a comparison of the two techniques is useful for highlighting and defining the capabilities and limitations of the individual technique, there is a role for each in the comprehensive approach to patients with upper extremity amputations.

The best patient for TMR is an above elbow amputee, because conventional myoelectric prosthetic function is poor, and CTA has provided unpredictable results. In the absence of TMR, the amputee lacks the capability for simultaneous and intuitive hand and elbow function. This amputation level also provides ample space for advanced prosthetic components. This contrasts with the transradial level, whereby space for prosthetic components is inherently limited, resulting in advanced myoelectric devices that are excessively bulky. CTA, on the other hand, is ideal in the distal forearm, where there is little muscle mass in the transplanted piece, and nerve topographic anatomy is defined. The total transplant load is relatively low, and salvage of the patient from a failed transplant would be facilitated by its distal location. Direct comparisons between transradial patients rehabilitated with either TMR/advanced prosthetics or CTA will require significant cooperation between academic centers.

Future directions

Future advancements for the prosthetic rehabilitation of the amputee are achievable in the near term. Osseointegration of the prosthetic into the humerus radius, femur, or tibia will dramatically improve the control and strength of the terminal device, as well as make the prosthetic more comfortable to wear. The absence of a prosthetic liner will render more facile the recording of EMG signals on the residual limb. Improvements in TMR will be obtained by further subdividing the nerve into smaller fascicles and the use of regenerative peripheral nerve interfaces for direct recording of nerve depolarizations. Alternatively, implantable myoelectric sensors (IMES) will be able to beam the muscle signal out to a detector without a surface electrode. Finally, improved prosthetic processing of the complex EMG signal termed “pattern recognition” has been shown to permit independent finger movements, even in the most proximal amputations.

Clinical tips

1. Targeted muscle reinnervation (TMR) requires an amputated limb with the nerve normally connected to the brain and spinal cord. Patients with brachial plexus injuries are not candidates for TMR.
2. Physical examination suffices for location of end-neuromas and muscles under cortical control. There is no need for magnetic resonance imaging, ultrasound, and electromyography so long as there is no history of a brachial plexus injury in addition to the amputation.
3. Soft-tissue revision of the amputated limb can and should be performed when indicated at the time of TMR.
4. TMR procedures can be performed in a straightforward manner with loop magnification and a simple nerve stimulator to identify motor nerves of adjacent muscles.
5. Free muscle flaps can be used advantageously as a recipient for the nerve transfer when there are no available local motor nerves.



Access the complete reference list online at

<http://www.expertconsult.com>

8. Gart MS, Souza JM, Dumanian GA. Targeted muscle reinnervation in the upper extremity amputee: a technical roadmap. *J Hand Surg Am.* 2015;40:1877–1888. *Current technique with cadaver dissections for TMR in upper extremity amputees. The surgical technique is well illustrated in this review.*
9. Kuiken TA, Dumanian GA, Lipschutz RD, et al. The use of targeted muscle reinnervation for improved myoelectric prosthesis control in a bilateral shoulder disarticulation amputee. *Prosthet Orthot Int.* 2004;28:245–253. *This is the initial report of TMR in a shoulder disarticulation patient. Objective testing before and after the nerve transfer procedure is presented.*
31. Souza JM, Cheesborough JE, Ko JH, et al. Targeted muscle reinnervation: a novel approach to postamputation neuroma pain. *Clin Orthop Relat Res.* 2014;472:2984–2990. *The effect of TMR on painful neuromas is reviewed.*
34. Kuiken TA, Miller LA, Lipschutz RD, et al. Targeted reinnervation for enhanced prosthetic arm function in a woman with a proximal amputation: a case study. *Lancet.* 2007;369:371–380. *Illustrated case of TMR in a shoulder disarticulation patient, with additional diagrams of targeted sensory reinnervation.*

References

- Putti V. Historical prostheses. (First published La chirurgia degli organi di movimento, 1925, vol IX, nos. 4–5.). *J Hand Surg [Br]*. 2005;30:310–325.
- Thurston AJ. Pare and prosthetics: the early history of artificial limbs. *ANZ J Surg*. 2007;77:1114–1119.
- Muilenburg AL, LeBlanc MA. Body-powered upper-limb components. In: Atkins DJ, Meier RH, eds. *Comprehensive Management of the Upper-Limb Amputee*. New York, NY: Springer-Verlag; 1989:28–38.
- Childress DS. Historical aspects of powered limb prostheses. *Clin Prosthet Orthot*. 1985;9:2–13.
- Pillet J, Didierjean-Pillet A. Aesthetic hand prosthesis: gadget or therapy? Presentation of a new classification. *J Hand Surg [Br]*. 2001;26:523–528.
- Doppen P, Solomons M, Krizinger S. Osseointegrated finger prostheses. *J Hand Surg Eur Vol*. 2009;34:29–34.
- Childress DS, Weir R. Control of limb prostheses. In: Smith DS, Michael JW, Bowker JH, eds. *Atlas of Amputations and Limb Deficiencies*. 3rd ed. Rosemont, IL: American Academy of Orthopedic Surgeons; 2004:173–195.
- Gart MS, Souza JM, Dumanian GA. Targeted muscle reinnervation in the upper extremity amputee: a technical roadmap. *J Hand Surg Am*. 2015;40:1877–1888. *Current technique with cadaver dissections for TMR in upper extremity amputees. The surgical technique is well illustrated in this review.*
- Kuiken TA, Dumanian GA, Lipschutz RD, et al. The use of targeted muscle reinnervation for improved myoelectric prosthesis control in a bilateral shoulder disarticulation amputee. *Prosthet Orthot Int*. 2004;28:245–253. *This is the initial report of TMR in a shoulder disarticulation patient. Objective testing before and after the nerve transfer procedure is presented.*
- O'Shaughnessy KD, Dumanian GA, Lipschutz R, et al. Targeted reinnervation: a surgical technique to improve prosthesis control in transhumeral amputees. *J Bone Joint Surg*. 2008;90:393–400.
- Weir RF, Troyk PR, Demichele GA, et al. Implantable myoelectric sensors (IMES) for intramuscular electromyogram recording. *IEEE Trans Biomed Eng*. 2009;56:159–171.
- Dhillon GS, Lawrence SM, Hutchinson DT, et al. Residual function in peripheral nerve stumps of amputees: implications for neural control of artificial limbs. *J Hand Surg Am*. 2004;29:605–615.
- Langhals NB, Woo SL, Moon JD, et al. Electrically stimulated signals from a long-term Regenerative Peripheral Nerve Interface. *Conf Proc IEEE End Med Biol Soc*. 2014;2014:1989–1992.
- Rossini PM, Micera S, Benvenuto A, et al. Double nerve intraneural interface implant on a human amputee for robotic hand control. *Clin Neurophysiol*. 2010;121:777–783.
- London BM, Jordan LR, Jackson CR, et al. Electrical stimulation of the proprioceptive cortex (area 3a) used to instruct a behaving monkey. *IEEE Trans Neural Syst Rehabil Eng*. 2008;16:32–36.
- Dellon AL. Think nerve" in upper extremity reconstruction. *Clin Plast Surg*. 1989;16:617–627.
- Lake C. Partial hand amputation: prosthetic management. In: Smith DS, Michael JW, Bowker JH, eds. *Atlas of Amputations and Limb Deficiencies*. 3rd ed. Rosemont, IL: American Academy of Orthopedic Surgeons; 2004:209–217.
- Mackinnon SE, Dellon AL, Hudson AR, et al. Alteration of neuroma formation by manipulation of its microenvironment. *Plast Reconstr Surg*. 1985;76:345–352.
- Dellon AL, Mackinnon SE, Pestronk A. Implantation of sensory nerve into muscle: preliminary clinical and experimental observations on neuroma formation. *Ann Plast Surg*. 1984;12:30–40.
- O'Shaughnessy KD, Rawlani V, Hijawi J, et al. Oblique pedicled PIP (paraumbilical perforator) based flap for reconstruction of complex proximal forearm defects. *J Hand Surg*. 2010;35A:1105–1110.
- Marquardt E, Neff G. The angulation osteotomy of above-elbow stumps. *Clin Orthop*. 1974;104:232–238.
- Kuiken TA, Lowery MM, Stoykov NS. The effect of subcutaneous fat on myoelectric signal amplitude and cross-talk. *Prosthet Orthot Int*. 2003;27:48–54.
- Soroush M, Modirian E, Soroush M, et al. Neuroma in bilateral upper limb amputation. *Orthopedics*. 2008;31.
- Lacoux PA, Crombie IK, Macrae WA. Pain in traumatic upper limb amputees in Sierra Leone. *Pain*. 2002;99:309–312.
- Ducic I, Mesbahi AN, Attinger CE, et al. The role of peripheral nerve surgery in the treatment of chronic pain associated with amputation stumps. *Plast Reconstr Surg*. 2008;121:908–914.
- Tupper JW, Booth DM. Treatment of painful neuromas of sensory nerves in the hand: a comparison of traditional and newer methods. *J Hand Surg Am*. 1976;1:144–151.
- Dellon AL, Mackinnon SE. Treatment of painful neuroma by neuroma resection and muscle implantation. *Plast Reconstr Surg*. 1984;73:427–438.
- Atherton DD, Leong JC, Anand P, et al. Relocation of painful end neuromas and scarred nerves from the zone II territory of the hand. *J Hand Surg [Br]*. 2007;32:38–44.
- Gorkisch K, Boese-Landgraf J, Vaubel E. Treatment and prevention of amputation neuromas in hand surgery. *Plast Reconstr Surg*. 1986;77:293–299.
- Guse DM, Moran SL. Outcomes of the surgical treatment of peripheral neuromas of the hand and forearm: a 25-year comparative outcome study. *Ann Plast Surg*. 2013;71:654–658.
- Souza JM, Cheesborough JE, Ko JH, et al. Targeted muscle reinnervation: a novel approach to postamputation neuroma pain. *Clin Orthop Relat Res*. 2014;472:2984–2990. *The effect of TMR on painful neuromas is reviewed.*
- Stubblefield KA, Miller LA, Lipschutz RD, et al. Occupational therapy protocol for amputees with targeted muscle reinnervation. *J Rehabil Res Dev*. 2009;46:481–488.
- Hijawi J, Kuiken TA, Lipschutz RD, et al. An improved brain-machine interface accomplished using multiple nerve transfers. *Plast Reconstr Surg*. 2006;118:1573–1578.
- Kuiken TA, Miller LA, Lipschutz RD, et al. Targeted reinnervation for enhanced prosthetic arm function in a woman with a proximal amputation: a case study. *Lancet*. 2007;369:371–380. *Illustrated case of TMR in a shoulder disarticulation patient, with additional diagrams of targeted sensory reinnervation.*
- Ngiem BT, Sando IC, Gillespie RB, et al. Providing a sense of touch to prosthetic hands. *Plast Reconstr Surg*. 2015;135:1652–1663.
- Li G, Kuiken TA. EMG pattern recognition control of multifunctional prostheses by transradial amputees. *Conf Proc IEEE End Med Biol Soc*. 2009;2009:6914–6917.